

231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Facility Assessment Report**

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About\_CPS/Policies\_and\_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1930	4	397,258	\$18,554,144
SITE				\$691,651
Campus Total			397,258	\$19,245,794

#### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments				
Entranc	trance										
	Entrance Control - Audio and Video	#1 Main	2	EA	6	\$1,403					
	Exterior Doors - Exterior AMP Door	#1 Main	3	EA	6	\$2,022					
	Exterior Doors - Exterior AMP Door	#1.1 W Court Yard	1	EA	6	\$674					
	Exterior Doors - Exterior AMP Door	#1.2 W Court Yard	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#10 S	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#11 S	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#12 S	4	EA	6	\$2,696					
	Exterior Doors - Exterior AMP Door	#13 SW	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#14 W	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#5 NE	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#6 E	6	EA	6	\$4,044					
	Exterior Doors - Exterior AMP Door	#7 E Court Yard	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#7.5 E Court Yard	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#8 SE	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	#9 S	4	EA	6	\$2,696					
	Exterior Doors - Exterior AMP Door	15 NW	10	EA	6	\$6,741					
	Exterior Doors - Exterior AMP Door	16 NW	4	EA	6	\$2,696					
	Exterior Doors - Exterior AMP Door	17 N	2	EA	6	\$1,348					
	Exterior Doors - Exterior AMP Door	18 N	4	EA	6	\$2,696					
	Exterior Doors - Exterior AMP Door	2 NW	2	EA	6	\$1,348					
	Exterior Doors - Exterior FRP Door	3 N	2	EA	6	\$1,263					



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entranc	e						
	Exterior Doors - Exterior FRP Door	3.1 Chiller Room	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	3.2 Boiler Room	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	4.1 N	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	Roof	3	EA	6	\$1,894	
	Exterior Doors - Exterior Stainless Steel Door	4 N	2	EA	6	\$1,092	
	Exterior Doors - Exterior Stainless Steel Door	Roof	1	EA	6	\$546	
	Exterior Doors - Overhead Rolling/ Garage Door	#4.2 to Room 129	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	#4.3 N Yard Storage	1	EA	6	\$1,433	
	Exterior Doors - Transom Lite	#11 S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#6 E	6	EA	6	\$1,880	
	Exterior Doors - Transom Lite	15 NW	10	EA	6	\$3,133	
	Exterior Doors - Transom Lite	18 N	4	EA	6	\$1,253	
	Exterior Stairs - Concrete	#1 Main	4	LF	5	\$438	cracks
	Exterior Stairs - Concrete	#1.2 W Court Yard	18	LF	6	\$1,472	
	Exterior Stairs - Concrete	#12 S	96	LF	6	\$7,850	
	Exterior Stairs - Concrete	#13 SW	40	LF	5	\$4,383	Cracks
	Exterior Stairs - Concrete	#14 W	40	LF	5	\$4,383	Cracks
	Exterior Stairs - Concrete	#5 NE	88	LF	5	\$9,643	Spalling
	Exterior Stairs - Concrete	#6 E	240	LF	6	\$19,624	
	Exterior Stairs - Concrete	#7.5 E Court Yard	24	LF	6	\$1,962	
	Exterior Stairs - Concrete	#8 SE	70	LF	6	\$5,724	
	Exterior Stairs - Concrete	#9 S	140	LF	6	\$11,447	
	Exterior Stairs - Concrete	16 NW	48	LF	6	\$3,925	
	Exterior Stairs - Concrete	17 N	84	LF	6	\$6,868	
	Exterior Stairs - Concrete	18 N	96	LF	6	\$7,850	
	Exterior Stairs - Concrete	2 NW	36	LF	5	\$3,945	Cracks
	Exterior Stairs - Concrete	3.2 Boiler Room	10	LF	6	\$818	
	Exterior Stairs - Concrete	4 N	6	LF	6	\$491	
	Exterior Stairs - Concrete	4.1 N	20	LF	6	\$1,635	
	Exterior Stairs - Stone	#1.1 W Court Yard	18	LF	6	\$2,034	
	Exterior Stairs - Stone	#10 S	80	LF	6	\$9,039	
	Exterior Stairs - Stone	#11 S	64	LF	6	\$7,231	
	Exterior Stairs - Stone	#7 E Court Yard	24	LF	6	\$2,712	
	Exterior Stairs - Stone	15 NW	135	LF	5	\$36,608	Open joints
	Exterior Stairs - Stone	3 N	12	LF	6	\$1,356	
	Exterior Stairs - Stone	4 N	6	LF	6	\$678	
	Power Door Operator and Controls	#1 Main	1	EA	6	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entran	ce						
	Power Door Operator and Controls	#8 SE	1	EA	6	\$0	
	Ramp Handrail - Steel_Ramp Handrail	#1 Main	70	LF	6	\$607	
	Ramp Handrail - Steel_Ramp Handrail	#7.5 E Court Yard	60	LF	6	\$520	
	Ramp Handrail - Steel_Ramp Handrail	#8 SE	110	LF	6	\$953	
	Ramp Handrail - Wood_Ramp Handrail	4.1 N	17	LF	6	\$147	
	Ramps - Concrete	#1 Main	35	LF	5	\$18,607	Spalling, cracks
	Ramps - Concrete	#7.5 E Court Yard	27	LF	6	\$4,056	
	Ramps - Concrete	#8 SE	50	LF	6	\$7,512	
	Ramps - Wood Ramp	4.1 N	17	LF	5	\$5,773	gap at deck excessive
	Stair Handrail	#14 W	15	LF	6	\$0	
	Stair Handrail - Steel_Stair Handrail	#1 Main	12	LF	6	\$104	
	Stair Handrail - Steel_Stair Handrail	#1.1 W Court Yard	10	LF	6	\$87	
	Stair Handrail - Steel_Stair Handrail	#1.2 W Court Yard	12	LF	6	\$104	
	Stair Handrail - Steel_Stair Handrail	#10 S	30	LF	6	\$260	
	Stair Handrail - Steel_Stair Handrail	#12 S	40	LF	6	\$347	
	Stair Handrail - Steel_Stair Handrail	#13 SW	24	LF	6	\$208	
	Stair Handrail - Steel_Stair Handrail	#5 NE	10	LF	4	\$1,502	Rusted out
	Stair Handrail - Steel_Stair Handrail	#6 E	60	LF	6	\$520	Grafitti
	Stair Handrail - Steel_Stair Handrail	#7 E Court Yard	10	LF	6	\$87	
	Stair Handrail - Steel_Stair Handrail	#7.5 E Court Yard	15	LF	7	\$0	
	Stair Handrail - Steel_Stair Handrail	#8 SE	25	LF	6	\$217	
	Stair Handrail - Steel_Stair Handrail	#9 S	56	LF	6	\$485	
	Stair Handrail - Steel_Stair Handrail	15 NW	50	LF	6	\$433	
	Stair Handrail - Steel_Stair Handrail	16 NW	24	LF	6	\$208	
	Stair Handrail - Steel_Stair Handrail	17 N	28	LF	6	\$243	
	Stair Handrail - Steel_Stair Handrail	18 N	40	LF	6	\$347	
	Stair Handrail - Steel_Stair Handrail	2 NW	12	LF	6	\$104	
	Stair Handrail - Steel_Stair Handrail	3 N	8	LF	6	\$69	
	Stair Handrail - Steel_Stair Handrail	4.1 N	8	LF	6	\$69	
Founda	ation						
	Foundation - Concrete	Entire Building	2,555	LF	7	\$0	Some seepage
	Superstructure - Concrete	Entire Building	397,258	SF	7	\$0	-
Lightin	g						
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	18	EA	6	\$9,658	
	Exterior Lighting - Wall Mounted	Entire Building	35	EA	6	\$10,106	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof S	/stem						
	Chimney - Brick Chimney- Stainless Steel Liner	Roof #2	54	LF	6	\$51,553	
	Chimney - Brick Chimney- Stainless Steel Liner	Roof #2	36	LF	5	\$94,160	efflorescence, cracks - has straps
	Chimney - Metal Flue	Roof #12	70	LF	6	\$11,070	
	Coping - Metal	Roof #10	40	LF	6	\$1,285	
	Coping - Terra Cotta	Roof #1	1,870	LF	6	\$60,060	some open joints
	Coping - Terra Cotta	Roof #11	83	LF	6	\$2,666	
	Coping - Terra Cotta	Roof #12	356	LF	6	\$11,434	some open joints
	Coping - Terra Cotta	Roof #13	81	LF	6	\$2,602	
	Coping - Terra Cotta	Roof #2	315	LF	6	\$10,117	some open joints
	Coping - Terra Cotta	Roof #3	347	LF	6	\$11,145	some open joints
	Coping - Terra Cotta	Roof #4	270	LF	6	\$8,672	some open joints
	Coping - Terra Cotta	Roof #5	76	LF	6	\$2,441	some open joints
	Coping - Terra Cotta	Roof #6	81	LF	6	\$2,602	
	Coping - Terra Cotta	Roof #7	81	LF	6	\$2,602	
	Coping - Terra Cotta	Roof #8	318	LF	6	\$10,213	some open joints
	Coping - Terra Cotta	Roof #9	329	LF	6	\$10,567	some open joints
	Downspouts - Exterior Downspouts	Roof #10	10	LF	6	\$332	
	Downspouts - Exterior Downspouts	Roof #12	20	LF	6	\$665	
	Downspouts - Exterior Downspouts	Roof #13	8	LF	6	\$266	
	Downspouts - Exterior Downspouts	Roof #5	3	LF	6	\$100	
	Downspouts - Exterior Downspouts	Roof #6	8	LF	6	\$266	
	Downspouts - Exterior Downspouts	Roof #7	8	LF	6	\$266	
	Downspouts - Interior Downspouts	Roof #1	1,190	LF	6	\$39,548	
	Downspouts - Interior Downspouts	Roof #11	30	LF	6	\$997	
	Downspouts - Interior Downspouts	Roof #12	176	LF	6	\$5,849	
	Downspouts - Interior Downspouts	Roof #2	216	LF	6	\$7,178	
	Downspouts - Interior Downspouts	Roof #3	216	LF	6	\$7,178	
	Downspouts - Interior Downspouts	Roof #4	75	LF	6	\$2,492	
	Downspouts - Interior Downspouts	Roof #8	108	LF	6	\$3,589	
	Downspouts - Interior Downspouts	Roof #9	216	LF	6	\$7,178	
	Parapet - 16" - 30" Height	Roof #1	1,538	LF	6	\$61,450	
	Parapet - 16" - 30" Height	Roof #11	83	LF	6	\$3,316	
	Parapet - 16" - 30" Height	Roof #13	81	LF	6	\$3,236	
	Parapet - 16" - 30" Height	Roof #6	81	LF	6	\$3,236	
	Parapet - 16" - 30" Height	Roof #7	81	LF	6	\$3,236	
	Parapet - Parapet < 16" Height	Roof #10	40	LF	6	\$852	
	Parapet - Parapet < 16" Height	Roof #12	306	LF	6	\$6,520	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
of Sy	stem						
	Parapet - Parapet < 16" Height	Roof #1 / West	152	LF	6	\$3,239	
	Parapet - Parapet < 16" Height	Roof #5	76	LF	6	\$1,619	
	Parapet - Parapet < 16" Height	Roof #8	60	LF	6	\$1,278	
	Parapet - Parapet > 30"	Roof #1	180	LF	6	\$11,506	
	Parapet - Parapet > 30"	Roof #12	50	LF	6	\$3,196	
	Parapet - Parapet > 30"	Roof #2	315	LF	6	\$20,135	
	Parapet - Parapet > 30"	Roof #3	347	LF	6	\$22,181	
	Parapet - Parapet > 30"	Roof #4	270	LF	6	\$17,259	
	Parapet - Parapet > 30"	Roof #8	258	LF	6	\$16,492	
	Parapet - Parapet > 30"	Roof #9	329	LF	6	\$21,030	some open joints
	Roof Structure - Concrete	Roof #10	178	SF	7	\$0	
	Roof Structure - Concrete	Roof #12	3,658	SF	7	\$0	at pitched metal roof
	Roof Structure - Steel with Clay Tile Arch	Roof #1	47,575	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #11	879	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #12	7,993	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #13	409	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #2	9,047	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #3	17,975	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #4	3,029	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #5	693	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #6	409	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #7	409	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #8	11,682	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #9	17,337	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Roof #1	47,575	SF	6	\$483,709	
	Roof - Asphalt Gravel Ballast	Roof #11	879	SF	6	\$8,937	
	Roof - Asphalt Gravel Ballast	Roof #12	7,993	SF	6	\$81,267	
	Roof - Asphalt Gravel Ballast	Roof #13	409	SF	6	\$4,158	not accessible
	Roof - Asphalt Gravel Ballast	Roof #2	9,047	SF	6	\$91,984	
	Roof - Asphalt Gravel Ballast	Roof #3	17,975	SF	6	\$182,757	
	Roof - Asphalt Gravel Ballast	Roof #4	2,716	SF	6	\$27,614	
	Roof - Asphalt Gravel Ballast	Roof #8	11,682	SF	6	\$118,774	
	Roof - Asphalt Gravel Ballast	Roof #9	17,337	SF	6	\$176,270	
	Roof - Metal	Roof #12	4,320	SF	6	\$57,884	
	Roof - Metal	Roof #4	406	SF	6	\$5,440	not accessible
	Roof - Modified Bitumen	Roof #10	178	SF	5	\$3,744	poor seams
	Roof - Modified Bitumen	Roof #5	693	SF	5	\$14,577	•



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Building: Main**

#### **Category: Building Exterior**

	tem - Type	Location	Quantity	Unit	Rank	Cost	Comments
ys	tem						
F	Roof - Modified Bitumen	Roof #6	409	SF	5	\$8,603	poor seams - not accessible
F	Roof - Modified Bitumen	Roof #7	409	SF	5	\$8,603	poor seams - not accessible
(	Canopy - Fabric	Entire Building	24	SF	6	\$369	
(	Cheek-Wall - Concrete	Entire Building	8	SF	5	\$189	spalling
(	Cheek-Wall - Concrete	Entire Building	60	SF	5	\$1,415	spalling
(	Cheek-Wall - Concrete	Entire Building	60	SF	5	\$1,415	spalling
(	Cheek-Wall - Concrete	Entire Building	310	SF	6	\$3,178	
(	Cheek-Wall - Stone	Entire Building	40	SF	6	\$410	
(	Cornice - Terra Cotta	Entire Building	145	LF	6	\$5,028	
E	Exterior Walls - Brick	Entire Building	10	SF	5	\$238	vertical cracks
E	Exterior Walls - Brick	Entire Building	20	SF	5	\$476	vertical cracks
E	Exterior Walls - Brick	Entire Building	15	SF	5	\$357	vertical cracks
E	Exterior Walls - Brick	Entire Building	50	SF	5	\$1,190	vertical cracks, efflorescence
E	Exterior Walls - Brick	Entire Building	15	SF	4	\$2,470	vertical and step cracks
E	Exterior Walls - Brick	Entire Building	5	SF	4	\$823	vertical cracks
E	Exterior Walls - Brick	Entire Building	50	SF	4	\$8,233	vertical cracks
E	Exterior Walls - Brick	Entire Building	146,386	SF	7	\$0	
E	Exterior Walls - Brick	Entire Building	20,000	SF	6	\$156,442	vines at NW elevation
E	Exterior Walls - Terra Cotta	Entire Building	2	SF	5	\$31	vegetative growth
E	Exterior Walls - Terra Cotta	Entire Building	3,328	SF	6	\$22,367	
ows							
(	Guard - Guards perforated	Entire Building	7,644	SF	6	\$97,613	
L	intels - Steel	Entire Building	4,465	LF	6	\$129,614	
L	intels - Terra Cotta	Entire Building	196	LF	6	\$0	
1	Vindows - Casement Steel	Entire Building	308	SF	5	\$25,189	poor glazing
	Vindows - Sash Aluminum Double-pane	Entire Building	40,322	SF	6	\$300,988	

#### **Building: Main**

Category: Electrical System

· · · · · · · · · · · · · · · · ·					
Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Emergency System					
Automatic Transfer Switch	Electrical Room	1	EA	6	\$408
Emergency A/C Power - Auditoium and Aisle Lighting	Entire Building / 1st Floor	22,412	SF	6	\$11,858



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Category: Electrical System

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	ency System						
	Emergency A/C Power - Corridors and Stairs	Entire Building	56,849	SF	6	\$17,072	
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	21,832	SF	6	\$8,117	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	10,079	SF	6	\$3,747	
	Emergency A/C Power - Multipurpose Room	Entire Building / 1st Floor	3,070	SF	6	\$1,141	
	Emergency A/C Power - Pool	Entire Building / 1st Floor	5,459	SF	6	\$2,030	
	Emergency A/C Power - Students Toilets	Entire Building	3,759	SF	6	\$1,398	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	12	EA	6	\$2,430	
	Emergency Generator- Outdoor- Natural Gas - 101 - 150 KW	Site West	1	EA	6	\$13,513	
	Exit Signs - Auditoium	Entire Building / 1st Floor	22	EA	6	\$3,294	
	Exit Signs - Corridors and Stairs	Entire Building	80	EA	6	\$11,980	
	Exit Signs - Gym	Entire Building	22	EA	6	\$3,463	
	Exit Signs - Lunchroom	Entire Building	9	EA	6	\$1,348	
	Security System - CCTV	Entire Building	397,258	SF	6	\$119,297	
	Security System - Intrusion Detection	Entire Building	397,258	SF	6	\$102,254	
Main S	ervice						
	Independent Electrical Service for emergency power	Entire Building	1	EA	6	\$2,921	
	Main Electrical Service - 1600 A 120/208/3PH	Boiler Room	1	EA	6	\$5,641	
	Main Electrical Service - Greater than 3000 A 120/208/3PH	Boiler Room	1	EA	6	\$16,381	Older but stable
	PA System	Entire Building / 1st Floor	397,258	SF	4	\$1,732,641	Poor condition. does not communicate to all rooms
Power	Distribution						
	Lighting and Power Panels - 100 A	Entire Building	1	EA	4	\$4,849	
	Lighting and Power Panels - 100 A	Entire Building	1	EA	6	\$299	Pool
	Lighting and Power Panels - 100 A	Entire Building	1	EA	6	\$299	Kitchen
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building / 3rd Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	6	\$497	Machine Shop
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	6	\$497	MDF
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	



### **Building: Main**

Category: Electrical System

231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Distribution						
Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	4	\$6,578	
Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	3	EA	6	\$1,491	
Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / 4th Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / 4th Floor	3	EA	4	\$19,733	
Lighting and Power Panels - Above 100 A	Entire Building / 4th Floor	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building / Basement	1	EA	4	\$6,578	Live front
Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	4	\$6,578	Panel L-ISE
Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	6	\$497	
Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
Main Distribution Panels - 400 - 600 amp	Entire Building / Basement	1	EA	6	\$528	
Main Distribution Panels - 400 - 600 amp	Entire Building / Basement	1	EA	6	\$528	
Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	
Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	
Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	
Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	6	\$3,021	
ical System Subtotal:				\$2	2,124,836	

## **Category: Safty System**

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm						
Fire Alarm Panel	Mechanical Room	1	EA	4	\$49,477	obsolete
Fire Alarm Strobe Lights	Mechanical Room / Entire Building	397,258	SF	5	\$306,763	
Fire Alarm_System	Mechanical Room / Entire Building	397,258	SF	5	\$443,102	
					<u> </u>	
Safty System Subtotal:					\$799,341	

#### Safty System Subtotal:

### **Building: Main Category: Mechanical System**



231 N Pine Ave Chicago, IL 60644

_	_						TIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE H
	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Cond	litioning						
	Chemical Pot Feeder	Mechanical Room	1	EA	6	\$725	
	Chiller-Water Cooled- Cetrifugal - 201-300 tons	Mechanical Room	1	EA	6	\$9,403	Active oil leak
	Cooling Tower - Closed Cell	Mechanical Room / Roof	2	EA	5	\$102,352	
	Glycol Feed	Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Steel	Mechanical Room / Entire Building	250	LF	6	\$472	
	Pipes - Dual Temperature Pipe- Steel	Mechanical Room	400	LF	6	\$755	
	Pressure Fill System	Mechanical Room	1	EA	6	\$1,405	
Air Hand	lling Systems						
	Air Handling Unit- Built Up- Single Zone- Daul Temperature Coils - 15001 - 25000 cfm	Basement	1	EA	6	\$5,788	
	Air Handling Unit- Built Up- Single Zone- Daul Temperature Coils - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Air Handling Unit- Built Up- Single Zone- Steam Coils - 25001 - 35000 cfm	Basement	1	EA	5	\$55,649	
	Air Handling Unit- Built Up- Single Zone- Steam Coils - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Air Handling Unit- Built Up- Single Zone- Steam Coils - Greater than 35000 cfm	Basement	1	EA	4	\$141,258	Corroded cabinet, squirel cage
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Daul Temperature Coils - 25001 - 35000 cfm	Basement	3	EA	5	\$166,946	
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Air Handling Unit- Package Single Zone- Outdoor Roof Mounted- Daul Temperature Coils Greater than 30,000 cfm	Roof	4	EA	6	\$13,400	
	Air Intake	Roof	4	EA	6	\$23,059	
	Air Intake	Basement	3	EA	6	\$17,294	
	Air Intake	Basement / Roof	1	EA	6	\$5,765	
	Air Intake	Basement / Roof	1	EA	6	\$5,765	
	Air Intake	Basement / Roof	1	EA	6	\$5,765	
	Air Intake	Basement / Roof	1	EA	4	\$17,616	corroded
	Air Intake	Basement / Roof	1	EA	6	\$5,765	
	Air Intake	Basement / Roof	1	EA	6	\$5,765	
	Auxiliaries - 15001 - 25000 cfm	Basement	1	EA	6	\$5,788	
	Auxiliaries - 25001 - 35000 cfm	Basement	3	EA	6	\$19,533	
	Auxiliaries - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Auxiliaries - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Auxiliaries - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Auxiliaries - 25001 - 35000 cfm	Basement	1	EA	6	\$6,511	
	Auxiliaries - Greater than 35000 cfm	Basement	1	EA	4	\$45,482	Corodded
	Dehumidification Unit- Indoor- Steam Heating- DX Cooling with Self Contained Compressor - Greater than 8000 cfm	Basement	1	EA	5	\$45,463	
	Reheat Boxes - Reheat Boxes with Steam Coil	Basement	20	EA	6	\$21,022	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

**Category: Mechanical System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	dling Systems						
	Reheat Boxes - Reheat Boxes with Steam Coil	Basement / Plenum	10	EA	6	\$10,511	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement	300	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	4	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	7	\$0	
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 5 - 10 tons	Roof	1	EA	5	\$10,623	
	Zone Dampers	Basement	73	EA	6	\$60,811	
	Zone Dampers	Basement / Plenum	32	EA	6	\$26,657	
Boiler f	Systems						
Doner	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - Greater than 300 HP	Boiler Room	2	EA	6	\$1,996	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	
	Combustion Dampers	Boiler Room	2	EA	6	\$818	
	Condensate Pump	Boiler Room / Basement	1	EA	4	\$44,329	
	Condensate Pump	Boiler Room / Entire Building	11	EA	6	\$22,232	
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - Greater than 300 HP	Boiler Room	2	EA	6	\$1,996	
	Steam Traps	Boiler Room / Entire Building	150	EA	5	\$197,235	
Heat Ex	changers						
	Heat Exchanger - Steam to Hot Water Shell Type	Boiler Room	1	EA	6	\$0	
Heatinç	Devices						
	Fin Tube - Steam	Entire Building / 4th Floor	3	LF	6	\$28	
	Fin Tube - Steam	Entire Building	45	LF	5	\$3,664	
	Radiators - Steam	Entire Building	152	EA	5	\$254,648	
	Radiators - Steam	Entire Building	8	EA	4	\$29,257	
	Unit Heater - Electric	Entire Building / 2nd Floor	12	EA	6	\$3,334	
	Unit Heater - Steam	Entire Building	6	EA	4	\$10,533	
	Wall Heater - Electric	Entire Building	18	EA	5	\$9,659	
	Wall Heater - Electric	Entire Building	5	EA	4	\$5,413	
Mechar	nical Plumbing						
	Chilled Water Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Building: Main**

#### **Category: Mechanical System**

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
chan	ical Plumbing						
	Chilled Water Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
	Condensate-Steel or Galvanized	Entire Building	1,200	LF	4	\$391,299	
	Daul Temperature Pump - 21 - 50 HP	Boiler Room	2	EA	6	\$2,485	
	Hydronic Supply and Return	Entire Building	2,500	LF	6	\$0	
npera	ature Control						
	DDC System	Entire Building	397,258	SF	6	\$227,232	needs calibration
	Electric Controls	Entire Building	12	SF	6	\$0	
	Thermostats - DDC	Entire Building	115	EA	6	\$0	
ntilati	ion						
	Exhaust Fans- Indoor - 1501 - 8000 CFM	Entire Building / 1st Floor	2	EA	6	\$1,185	
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / Attic	4	EA	6	\$2,370	
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building	4	EA	6	\$2,370	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	6	\$592	
	Lab Exhaust Hood	Entire Building	1	EA	6	\$1,248	
	Roof Mounted Duct Work	Entire Building	75	LF	6	\$28,427	
	Roof Mounted Duct Work	Entire Building	10	LF	4	\$16,695	
	Type I Exhaust Hood- Culinary Arts	Entire Building / 1st Floor	1	EA	6	\$1,248	
	Type I Exhaust Hood- Kitchen	Entire Building / 2nd Floor	3	EA	6	\$3,743	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 2nd Floor	1	EA	6	\$920	
cha	inical System Subtotal:				\$2	2,157,557	

#### Building: Main

### Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments			
Hot Wat	t Water									
	Gas Heater - Greater than 600000 BTU/HR	Boiler Room	2	EA	6	\$620				
Piping	ing									
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	18,629	SF	6	\$3,730				
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	18,629	SF	6	\$3,730				
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	18,629	SF	6	\$4,529				
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	18,629	SF	6	\$4,529				
	Domestic Piping-Cold Water Risers	Entire Building	18,629	SF	6	\$3,463				



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Building: Main**

#### **Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comme
iping							
	Domestic Piping-Cold Water Risers	Entire Building	18,629	SF	6	\$3,463	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	18,629	SF	6	\$2,930	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	18,629	SF	6	\$2,930	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	18,629	SF	6	\$3,463	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	18,629	SF	6	\$3,463	
	Domestic Piping-Hot Water Return Lines	Entire Building	18,629	SF	6	\$2,664	
	Domestic Piping-Hot Water Return Lines	Entire Building	18,629	SF	6	\$2,664	
	Domestic Piping-Hot Water Return Risers	Entire Building	18,629	SF	6	\$2,664	
	Domestic Piping-Hot Water Return Risers	Entire Building	18,629	SF	6	\$2,664	
	Sanitary Piping	Entire Building	397,258	SF	4	\$1,380,432	
	Storm Piping	Entire Building	397,258	SF	4	\$1,374,751	
	Vent Piping	Entire Building	397,258	SF	4	\$971,415	
ool Sy	vstems						
	Pool Drain Piping	Basement	75	LF	6	\$2,147	
	Pool Filtration System including Pump	Basement	1	EA	6	\$12,330	
	Pool Hot Water Heater - Gas Fired	Basement / Boiler Room	1	EA	6	\$310	
	Pool Supply and Return Piping	Basement	150	LF	6	\$7,207	
mps							
	Pumps - Domestic Booster Pump-Duplex	Basement and Boiler Room / Basement	1	EA	6	\$1,977	
	Pumps - Ejector-Duplex	Basement and Boiler Room / Boiler Room	1	EA	5	\$7,535	
	Pumps - Sump-Duplex	Basement and Boiler Room / Basement	1	EA	5	\$7,535	
	Pumps - Sump-Duplex	Basement and Boiler Room / Basement	4	EA	6	\$5,548	
	ing Quetem Quintotal						

Plumbing System Subtotal:

\$3,818,692

#### **Building: Main**

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comment
Classroom #124 (Special Education)					
Casework	1st Floor	8	LF	6	\$202
Ceiling - Lay-in	1st Floor	718	SF	6	\$2,156
Chalk Board	1st Floor	12	LF	4	\$1,102
Doors - Transom Window	1st Floor	8	SF	6	\$135
Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301
Floor - Wood	1st Floor	718	SF	6	\$5,062



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

ID	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	om #124 (Special Education)	Location	Quantity	Unit	Kullk	0031	Common to
5100	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0 \$0	
	Walls - Plaster/Drywall	1st Floor	1,442	SF	6	\$3,980	
	Walls - Plaster/Drywall	1st Floor	2	SF	5		hole in wall
	Work Sink	1st Floor	- 1	EA	4		missing- pipes capped off
					·	<i><b>Q</b></i> <b>QQQQQQQQQQQQQ</b>	
5100	om #128 (Multi Purpose Room) Casework	1st Floor	13	LF	6	\$328	
		1st Floor		SF	6	\$328 \$4,063	
	Ceiling - Lay-in	1st Floor	1,353	SF			water steins
	Ceiling - Lay-in Chalk Board	1st Floor	2	LF	5 4	\$1,653	water stains
	Doors - Transom Window	1st Floor	18	SF		\$1,653 \$271	
	Doors - Transom Window Doors - Wood Doors inclu hw	1st Floor	16 2	EA	6 6	\$271 \$602	
		1st Floor					
	Floor - Tile	1st Floor 1st Floor	1,355 38	SF	6	\$2,965 \$0	
	Lighting - Lay-in	1st Floor 1st Floor	38 1	EA EA	7		anon alaak bay
	Lighting - Wall Mounted Marker Board	1st Floor		LF	6 7	\$124 \$0	open clock box
	Storage/ Closet	1st Floor	4 246	SF	6		2 rooms (1 marked dark room, but teache
	Storage/ Cluser	IST FIOOI	240	эг	U	φι,/64	confirmed it is just for storage)
	Walls - Plaster/Drywall	1st Floor	17	SF	5	\$87	peeling & water damaged
	Walls - Plaster/Drywall	1st Floor	1,732	SF	6	\$4,780	
sro	om #129 (Laboratory/Shop)						
	Ceiling - Lay-in	1st Floor	1,092	SF	6	\$3,279	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6		double door
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Floor - Concrete Epoxy/ Painted	1st Floor	1,092	SF	6	\$578	
	Lighting - Pendent/Surface	1st Floor	19	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Storage/ Closet	1st Floor	106	SF	6		2 storage rooms
	Walls - Concrete Block	1st Floor	2,020	SF	6	\$5,922	-
	Work Sink	1st Floor	1	EA	6	\$379	
sro	om #131 (Laboratory/Shop)						
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Lay-in	1st Floor	1,091	SF	6	\$3,276	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	1,091	SF	6	\$7,691	
	Lighting - Lay-in	1st Floor	27	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classre	oom #131 (Laboratory/Shop)						
	Marker Board	1st Floor	15	LF	7	\$0	
	Storage/ Closet	1st Floor	32	SF	6	\$232	
	Walls - Concrete Block	1st Floor	1,392	SF	6	\$4,081	
Classr	oom #135 (Regular Classroom)						
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Lay-in	1st Floor	720	SF	6	\$2,162	1 ceiling tile falling out
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Wood	1st Floor	720	SF	6	\$5,076	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	986	SF	6	\$2,721	
Classr	oom #136 (Regular Classroom)						
	Casework	1st Floor	16	LF	6	\$404	
	Ceiling - Lay-in	1st Floor	718	SF	6	\$2,156	1 ceiling tile falling out
	Chalk Board	1st Floor	22	LF	4	\$2,020	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Wood	1st Floor	698	SF	6	\$4,921	
	Floor - Wood	1st Floor	20	SF	5	\$394	floor buckling at entry door
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	998	SF	6	\$2,754	
Classr	oom #137 (Regular Classroom)						
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Lay-in	1st Floor	728	SF	6	\$2,186	1 ceiling tile falling out
	Chalk Board	1st Floor	13	LF	4	\$1,193	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	728	SF	6	\$1,593	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,000	SF	6	\$2,760	
Classr	oom #138 (Office)						
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Lay-in	1st Floor	724	SF	6	\$2,174	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

			<b>•</b>		- ·	•	<b>a</b>
-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #138 (Office)						
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	724	SF	6	\$1,584	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,090	SF	6	\$3,008	
Classro	oom #200 (Computer Lab)						
	Casework	2nd Floor	44	LF	6	\$1,111	
	Ceiling - Lay-in	2nd Floor	1,484	SF	6	\$4,456	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Tile	2nd Floor	40	SF	5	\$231	
	Floor - Tile	2nd Floor	1,444	SF	6	\$3,159	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Walls	2nd Floor	1		5	\$0	Open junction box
	Walls - Plaster/Drywall	2nd Floor	1,569	SF	6	\$4,330	
	Walls - Plaster/Drywall	2nd Floor	8	SF	5	\$41	
Classro	oom #201 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	745	SF	6	\$2,237	
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	745	SF	6	\$1,587	
	Lighting - Lay-in	2nd Floor	17	EA	7	\$0	
	Marker Board	2nd Floor	18	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,056	SF	6	\$2,914	
Classro	oom #202 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	745	SF	6	\$2,237	
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	745	SF	6	\$1,587	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

b Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
room #202 (Regular Classroom)						
Lighting - Lay-in	2nd Floor	17	EA	7	\$0	
Marker Board	2nd Floor	18	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	1	SF	5	\$5	Exposed wires at thermostat
Walls - Plaster/Drywall	2nd Floor	1,055	SF	6	\$2,912	
room #211 (Science)						
Casework	2nd Floor	54	LF	6	\$1,364	
Ceiling - Lay-in	2nd Floor	1,212	SF	6	\$3,640	
Doors - Transom Window	2nd Floor	12	SF	6	\$203	
Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
Floor - Tile	2nd Floor	1,212	SF	6	\$2,652	
Fume Hood	2nd Floor	1	EA	6	\$816	
Gas Line	2nd Floor	2	EA	6	\$1,018	
Lighting - Lay-in	2nd Floor	36	EA	7	\$0	
Science Lab Elements	2nd Floor	42	SF	6	\$285	
Walls	2nd Floor	1		5	\$0	Exposed junction box
Walls - Plaster/Drywall	2nd Floor	1,350	SF	6	\$3,726	
Work Sink	2nd Floor	3	EA	6	\$1,137	
room #212 (Regular Classroom)						
Casework		10	LF	6	\$253	
Ceiling - Lay-in		8	SF	5	\$64	
Ceiling - Lay-in		747	SF	6	\$2,243	
Chalk Board		36	LF	4	\$3,305	
Doors - Wood Doors inclu hw		2	EA	6	\$602	
Floor - Wood		745	SF	6	\$5,252	
Lighting - Lay-in		14	EA	7	\$0	
				0	¢0.050	
Walls - Plaster/Drywall		1,036	SF	6	\$2,859	
		1,036	SF	6	\$2,609	
Walls - Plaster/Drywall	2nd Floor	1,036	SF	6	\$884	
Walls - Plaster/Drywall room #215 (Vacant)	2nd Floor 2nd Floor					
Walls - Plaster/Drywall room #215 (Vacant) Casework		35	LF	6	\$884	
Walls - Plaster/Drywall room #215 (Vacant) Casework Ceiling - Lay-in	2nd Floor	35 1,027	LF SF	6	\$884 \$3,084	
Walls - Plaster/Drywall room #215 (Vacant) Casework Ceiling - Lay-in Doors - Transom Window	2nd Floor 2nd Floor	35 1,027 18	LF SF SF	6 6 6	\$884 \$3,084 \$305	
Walls - Plaster/Drywall room #215 (Vacant) Casework Ceiling - Lay-in Doors - Transom Window Doors - Wood Doors inclu hw	2nd Floor 2nd Floor 2nd Floor	35 1,027 18 2	LF SF SF EA	6 6 6	\$884 \$3,084 \$305 \$602	
Walls - Plaster/Drywall room #215 (Vacant) Casework Ceiling - Lay-in Doors - Transom Window Doors - Wood Doors inclu hw Eye Wash Station	2nd Floor 2nd Floor 2nd Floor 2nd Floor	35 1,027 18 2 1	LF SF SF EA EA	6 6 6 6 6	\$884 \$3,084 \$305 \$602 \$336	
Walls - Plaster/Drywall room #215 (Vacant) Casework Ceiling - Lay-in Doors - Transom Window Doors - Wood Doors inclu hw Eye Wash Station Floor - Tile/Sheet	2nd Floor 2nd Floor 2nd Floor 2nd Floor 2nd Floor	35 1,027 18 2 1 1,027	LF SF EA EA SF	6 6 6 6 6	\$884 \$3,084 \$305 \$602 \$336 \$1,028	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #215 (Vacant)						
	Work Sink	2nd Floor	3	EA	6	\$1,137	sinks in base cabinet
Classro	oom #216 (Regular Classroom)						
	Casework	2nd Floor	42	LF	6	\$1,061	
	Ceiling - Exposed	2nd Floor	1,224	SF	6	\$1,820	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	1,224	SF	6	\$8,629	
	Lighting - Lay-in	2nd Floor	36	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,317	SF	6	\$3,635	
	Work Sink	2nd Floor	1	EA	5	\$1,508	
Classro	oom #219 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	637	SF	6	\$1,913	1 ceiling tile stained
	Ceiling - Plaster/Drywall	2nd Floor	73	SF	6	\$253	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	3	SF	5	\$17	crack in tiles at entry door
	Floor - Tile	2nd Floor	707	SF	6	\$1,547	
	Lighting - Lay-in	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	987	SF	6	\$2,724	
Classro	oom #220 (Vacant)						
	AC Units	2nd Floor	3	EA	6	\$1,487	
	Casework	2nd Floor	21	LF	6	\$530	
	Ceiling - Lay-in	2nd Floor	1,341	SF	6	\$4,027	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,341	SF	6	\$2,934	
	Lighting - Lay-in	2nd Floor	40	EA	7	\$0	
	Storage/ Closet	2nd Floor	67	SF	6	\$486	Room 220A
	Walls - Plaster/Drywall	2nd Floor	1,277	SF	6	\$3,524	
	Work Sink	2nd Floor	5	EA	6	\$1,895	
Classro	oom #227 (Computer Lab)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	1,262	SF	6		1 ceiling tile cracked
	Chalk Board	2nd Floor	10	LF	4	\$918	<b>.</b>



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

•	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #227 (Computer Lab)						
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	1,262	SF	6	\$8,897	
	Lighting - Lay-in	2nd Floor	30	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,391	SF	6	\$3,839	
	Work Sink	2nd Floor	1	EA	6	\$379	pedestal sink
Classro	oom #229 (Computer Lab)						
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	1,326	SF	6	\$3,982	
	Chalk Board	2nd Floor	7	LF	4	\$643	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,326	SF	6	\$2,901	
	Lighting - Pendent/Surface	2nd Floor	26	EA	7	\$0	
	Storage/ Closet	2nd Floor	157	SF	6	\$1,138	Storage 229A inside classroom 229
	Walls - Plaster/Drywall	2nd Floor	1,199	SF	6	\$3,309	
	Wireless System	2nd Floor	1	EA	6	\$372	
Classro	oom #232 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	735	SF	6	\$2,207	1 ceiling tile falling out
	Chalk Board	2nd Floor	15	LF	4	\$1,377	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	735	SF	6	\$5,182	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,100	SF	6	\$3,036	
Classro	oom #233 (Computer Lab)						
	AC Units	2nd Floor	3	EA	6	\$1,487	
	Casework	2nd Floor	11	LF	6	\$278	
	Ceiling - Lay-in	2nd Floor	1,090	SF	6	\$3,273	1 ceiling tile falling out
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	1,090	SF	6	\$7,684	
	Lighting - Lay-in	2nd Floor	30	EA	7	\$0	1 outlet box taped to strip



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

-		Leveller	0	11	Devil	0	0
-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	bom #233 (Computer Lab)						
	Marker Board	2nd Floor	32	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,344	SF	6	\$3,709	
	Wireless System	2nd Floor	1	EA	6	\$372	
	Work Sink	2nd Floor	1	EA	6	\$379	pedestal sink
Classro	oom #234 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	726	SF	6	\$2,180	
	Chalk Board	2nd Floor	15	LF	4	\$1,377	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	726	SF	6	\$5,118	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	15	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,075	SF	6	\$2,967	
Classro	oom #236 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	722	SF	6	\$2,168	
	Chalk Board	2nd Floor	28	LF	4	\$2,571	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	722	SF	6	\$5,090	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	1 outlet blown out
	Marker Board	2nd Floor	6	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,005	SF	6	\$2,774	
Classro	oom #237 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	728	SF	6	\$2,186	
	Chalk Board	2nd Floor	28	LF	4	\$2,571	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	728	SF	6	\$5,132	
	Lighting - Lay-in	2nd Floor	14	EA	6	\$1,666	
	Walls - Plaster/Drywall	2nd Floor	1,084	SF	6	\$2,992	
Classro	oom #238 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	724	SF	5	\$4,307	2 ceiling tiles falling out



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	bom #238 (Regular Classroom)	20041011	Quantity	onne	- Carine	0001	
0140010	Chalk Board	2nd Floor	28	LF	4	\$2,571	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	724	SF	6	\$5,104	
	Lighting - Lay-in	2nd Floor	14	EA	6	\$1,666	
	Walls - Plaster/Drywall	2nd Floor	1,090	SF	6	\$3,008	
Classro	pom #239 (Science Lab Level 1)		,	-		¥ - )	
0100010	Casework	2nd Floor	95	LF	6	\$2,399	
	Ceiling - Lay-in	2nd Floor	1,194	SF	6	\$3,586	
	Doors - Wood Doors inclu hw	2nd Floor	1,101	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,194	SF	6	\$1,195	
	Fume Hood	2nd Floor	1,101	EA	6	\$816	
	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Lay-in	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	2nd Floor	1,171	SF	6	\$3,232	
	Work Sink	2nd Floor	, 10	EA	6		in base cabinets
Classro	oom #240 (Regular Classroom)						
	Casework	2nd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	2nd Floor	728	SF	6	\$2,186	
	Chalk Board	2nd Floor	27	LF	4	\$2,479	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	728	SF	6	\$5,132	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,017	SF	6	\$2,807	
Classro	oom #242 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	726	SF	6	\$2,180	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	726	SF	6	\$5,118	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lassro	om #242 (Regular Classroom)						
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,065	SF	6	\$2,939	
	Walls - Plaster/Drywall	2nd Floor	10	SF	6	\$39	holes in walls
lassro	oom #300A (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	775	SF	6	\$2,327	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Carpet	3rd Floor	775	SF	6	\$1,651	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Walls	3rd Floor	1		5	\$0	Open wires at junction box
	Walls - Plaster/Drywall	3rd Floor	1,200	SF	6	\$3,312	
lassro	om #300B (Regular Classroom)						
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	
	Doors - Transom Window	3rd Floor	1	SF	6	\$17	
	Floor - Carpet	3rd Floor	750	SF	6	\$1,598	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	6	\$214	
	Walls - Plaster/Drywall	3rd Floor	1,060	SF	6	\$2,925	
	Walls - Plaster/Drywall	3rd Floor	10	SF	5	\$51	Damage at window
assro	om #301 (Regular Classroom)						
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	3rd Floor	750	SF	6	\$3,925	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	22	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,036	SF	6	\$2,859	
lassro	om #302B (Regular Classroom)						
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	360	SF	6	\$1,081	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	360	SF	6	\$2,538	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-		Eocation	Quantity	Unit	Rdiik	COSI	Comments
assro	om #302B (Regular Classroom) Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor			7	\$0 \$0	
	Walls - Plaster/Drywall	3rd Floor	16 10	SF	5		Crack
	Walls - Plaster/Drywall	3rd Floor	788	SF	5 6	<sub>401</sub> \$2,175	CTACK
		310 F1001	100	SF	0	φ <b>Ζ</b> , 175	
assro	om #303 (Regular Classroom)						
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	750	SF	6	\$5,287	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Walls	3rd Floor	1		5	\$0	Open junction box
	Walls - Plaster/Drywall	3rd Floor	1,036	SF	6	\$2,859	
assro	oom #304 (Regular Classroom)						
	AC Units	3rd Floor	2	EA	6	\$991	
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	
	Chalk Board	3rd Floor	10	LF	4	\$918	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	750	SF	6	\$5,287	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	36	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,070	SF	6	\$2,953	
ssro	om #305 (Regular Classroom)						
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	3rd Floor	750	SF	6	\$3,925	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	22	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,036	SF	6	\$2,859	
assro	oom #307 (Regular Classroom)						
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #307 (Regular Classroom)						
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	3rd Floor	750	SF	6	\$3,925	
	Lighting - Lay-in	3rd Floor	14	EA	6	\$1,666	
	Marker Board	3rd Floor	18	LF	6	\$386	
	Walls - Plaster/Drywall	3rd Floor	1,016	SF	6	\$2,804	
	Walls - Plaster/Drywall	3rd Floor	20	SF	5	\$102	Water damaged at window
Classro	oom #308 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	920	SF	6	\$2,763	
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	3rd Floor	920	SF	6	\$4,815	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	15	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,118	SF	6	\$3,086	
Classro	oom #310 (Art Room)						
	Casework	3rd Floor	31	LF	6	\$783	
	Ceiling - Lay-in	3rd Floor	1,027	SF	6	\$3,084	
	Doors - Transom Window	3rd Floor	2	SF	6	\$34	
	Floor - Wood	3rd Floor	1,027	SF	6	\$7,240	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,237	SF	6	\$3,414	
Classro	oom #312 (Regular Classroom)						
	Casework	3rd Floor	33	LF	6	\$833	
	Ceiling - Lay-in	3rd Floor	909	SF	6	\$2,730	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	909	SF	6	\$6,408	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	17	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,124	SF	6	\$3,102	
lassro	oom #313 (Science)						
	Casework	3rd Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	3rd Floor	1,425	SF	6	\$4,279	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classre	bom #313 (Science)						
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,425	SF	6	\$1,426	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	42	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Elements	3rd Floor	42	SF	6	\$285	
	Storage/ Closet	3rd Floor	81	SF	6	\$587	
	Walls - Plaster/Drywall	3rd Floor	1,035	SF	6	\$2,856	
	Work Sink	3rd Floor	7	EA	6	\$2,653	
Classro	oom #319 (Science)						
	Casework	3rd Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	3rd Floor	1,333	SF	6	\$4,003	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Transom Window	3rd Floor	2	SF	6	\$34	
	Floor - Tile/Sheet	3rd Floor	1,333	SF	6	\$1,334	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	2	EA	6	\$1,018	
	Lighting - Lay-in	3rd Floor	39	EA	7	\$0	
	Marker Board	3rd Floor	40	LF	7	\$0	
	Science Lab Elements	3rd Floor	45	SF	6	\$305	
	Walls - Plaster/Drywall	3rd Floor	1,282	SF	6	\$3,538	
	Work Sink	3rd Floor	3	EA	5	\$4,523	Dripping
Classro	oom #321 (Science Classroom)						
	Casework	3rd Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	3rd Floor	1,401	SF	6	\$4,207	2 ceiling tile falling out
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	1,401	SF	6	\$9,877	
	Lighting - Lay-in	3rd Floor	28	EA	7	\$0	exposed electrical wires at front desk
	Marker Board	3rd Floor	26	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,048	SF	6	\$2,892	
	Work Sink	3rd Floor	4	EA	6	\$1,516	3 sinks in base cabinets, 1 eye wash station



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

-						-	
-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #322 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	733	SF	6	\$2,201	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	733	SF	6	\$5,168	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	27	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,111	SF	6	\$3,066	
Classro	oom #323 (Music Room)						
	Ceiling - Lay-in	3rd Floor	1,675	SF	6	\$5,030	
	Chalk Board	3rd Floor	10	LF	4	\$918	
	Doors - Steel Doors incl hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	1,675	SF	6	\$11,809	
	Lighting - Pendent/Surface	3rd Floor	1	EA	7	\$0	at Vestibule
	Lighting - Pendent/Surface	3rd Floor	36	EA	7	\$0	
	Sound System	3rd Floor	1	EA	6	\$1,442	
	Walls - Plaster/Drywall	3rd Floor	1,820	SF	6	\$5,023	
Classro	oom #324 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	1 cabinet door missing
	Ceiling - Lay-in	3rd Floor	729	SF	6	\$2,189	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	729	SF	6	\$5,139	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	29	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,119	SF	6	\$3,088	
Classro	oom #325 (Music Room)						
	Ceiling - Lay-in	3rd Floor	1,578	SF	6	\$4,739	
	Ceiling - Plaster/Drywall	3rd Floor	82	SF	4	\$1,235	ceiling at vestibule peeling / some ares stained
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Steel Doors incl hw	3rd Floor	2	EA	6	\$602	2 - sets of double doors
	Floor - Wood	3rd Floor	1,660	SF	6	\$11,703	
	Lighting - Lay-in	3rd Floor	36	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	1	EA	7	\$0	at vestibule



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ssro	om #325 (Music Room)						
	Walls - Plaster/Drywall	3rd Floor	7	SF	5	\$36	wall peeling / stained in some areas / hole in wa with exposed elect. wires
	Walls - Plaster/Drywall	3rd Floor	1,825	SF	6	\$5,037	
ssro	om #326 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	722	SF	6	\$2,168	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	722	SF	6	\$5,090	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	29	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	554	SF	6	\$1,529	
ssro	om #328 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	724	SF	6	\$2,174	1 ceiling tile falling out
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	724	SF	6	\$5,104	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,124	SF	6	\$3,102	
ssro	om #330 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	728	SF	6	\$2,186	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	728	SF	6	\$5,132	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,030	SF	6	\$2,843	
ssro	om #331 (Computer Lab)						
	Casework	3rd Floor	116	LF	6	\$2,929	
	Ceiling - Lay-in	3rd Floor	1,264	SF	6	\$3,796	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	boom #331 (Computer Lab)	Location	Guantity	onit	Nann	0031	
0103310	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	1,264	SF	6	\$8,911	
	Lighting - Lay-in	3rd Floor	15	EA	7	¢0,011 \$0	1 bad outlet box
	Marker Board	3rd Floor	8	LF	7	\$0	
	Storage/ Closet	3rd Floor	116	SF	6	\$841	Storage 331A - stained ceiling tile
	Walls - Plaster/Drywall	3rd Floor	1,446	SF	6	\$3,991	
	Wireless System	3rd Floor	.,	EA	6	\$372	
	-					<b>+-</b> ·-	
Classro	oom #332 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	727	SF	6	\$2,183	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	727	SF	6	\$5,125	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	26	LF	6	\$557	
	Walls - Plaster/Drywall	3rd Floor	1,122	SF	6	\$3,097	
Classro	oom #335 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	1,472	SF	6	\$4,420	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,472	SF	6	\$3,221	
	Lighting - Lay-in	3rd Floor	28	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1	SF	5	\$5	hole in wall with exposed elect. wiring
	Walls - Plaster/Drywall	3rd Floor	1,315	SF	6	\$3,629	
Classro	oom #337 (Computer Lab)						
	Casework	3rd Floor	121	LF	6	\$3,056	
	Ceiling - Lay-in	3rd Floor	1,469	SF	6	\$4,411	
	Charging Station	3rd Floor	1	EA	6	\$485	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	1,469	SF	6	\$10,356	
	Lighting - Lay-in	3rd Floor	26	EA	7	\$0	
	Marker Board	3rd Floor	22	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,688	SF	6	\$4,659	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
assro	om #337 (Computer Lab)						
	Wireless System	3rd Floor	1	EA	6	\$372	
assro	om #341 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	745	SF	6	\$2,237	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	745	SF	6	\$5,252	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	30	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,116	SF	6	\$3,080	
assro	om #343 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	726	SF	6	\$2,180	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	726	SF	6	\$5,118	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	10 of 24 floor outlets broke, tapped up
	Marker Board	3rd Floor	30	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	10	SF	6	\$39	several holes / patches in walls
	Walls - Plaster/Drywall	3rd Floor	1,106	SF	6	\$3,052	
assro	om #345 (Regular Classroom)						
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	726	SF	6	\$2,180	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	726	SF	6	\$5,118	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,043	SF	6	\$2,879	
assro	om #400 (Regular Classroom)						
	AC Units	4th Floor	1	EA	6	\$496	
	Ceiling - Lay-in	4th Floor	940	SF	6	\$2,823	
	Chalk Board	4th Floor	18	LF	4	\$1,653	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

-	ltem - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classre	oom #400 (Regular Classroom)						
	Floor - Wood	4th Floor	940	SF	6	\$6,627	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	36	LF	7	\$0	
	Walls	4th Floor	1		5	\$0	Exposed wiring at intercom
	Walls - Plaster/Drywall	4th Floor	1,195	SF	6	\$3,298	
Classro	oom #401 (Regular Classroom)						
	AC Units	4th Floor	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	4th Floor	730	SF	6	\$2,526	
	Chalk Board	4th Floor	10	LF	4	\$918	
	Doors - Transom Window	4th Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Wood	4th Floor	730	SF	6	\$5,146	
	Lighting - Pendent/Surface	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	36	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,015	SF	6	\$2,801	
Classro	oom #402 (Faculty Lounge)						
	AC Units	4th Floor	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	4th Floor	307	SF	6	\$1,062	
	Chalk Board	4th Floor	10	LF	4	\$918	
	Doors - Store Front	4th Floor	1	EA	6	\$1,208	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	730	SF	6	\$5,146	
	Lighting - Pendent/Surface	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,015	SF	6	\$2,801	
Classro	oom #402A (Regular Classroom)						
	AC Units		1	EA	6	\$496	
	Ceiling - Plaster/Drywall		730	SF	6	\$2,526	
	Doors - Transom Window		6	SF	6	\$102	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		730	SF	6	\$5,146	
	Lighting - Pendent/Surface		14	EA	7	\$0	
	Marker Board		16	LF	7	\$0	
	Walls - Plaster/Drywall		1,015	SF	6	\$2,801	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	oom #404 (Regular Classroom)						
	AC Units	4th Floor	1	EA	6	\$496	
	Ceiling - Lay-in	4th Floor	975	SF	6	\$2,928	
	Chalk Board	4th Floor	16	LF	4	\$1,469	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	975	SF	6	\$6,874	
	Lighting - Lay-in	4th Floor	18	EA	7	\$0	
	Marker Board	4th Floor	36	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,190	SF	6	\$3,284	
	Work Sink	4th Floor	1	EA	6	\$379	
Classro	oom #405 (Regular Classroom)						
	AC Units	4th Floor	1	EA	6	\$496	
	Ceiling - Lay-in	4th Floor	730	SF	6	\$2,192	
	Chalk Board	4th Floor	10	LF	4	\$918	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	730	SF	6	\$5,146	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	36	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,015	SF	6	\$2,801	
Classro	oom #406 (Regular Classroom)						
	AC Units	4th Floor	1	EA	6	\$496	
	Casework	4th Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	4th Floor	750	SF	6	\$2,595	
	Chalk Board	4th Floor	10	LF	4	\$918	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	750	SF	6	\$5,287	
	Lighting - Pendent/Surface	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	36	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	6	SF	5	\$31	Crack at door
	Walls - Plaster/Drywall	4th Floor	1,030	SF	6	\$2,843	
Classro	oom #407 (Regular Classroom)						
	Ceiling - Lay-in	4th Floor	730	SF	6	\$2,192	
	Doors - Transom Window	4th Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	om #407 (Regular Classroom)		•				
	Doors - Wood Doors inclu hw	4th Floor	1	EA	5	\$1,174	Out of alignment
	Floor - Wood	4th Floor	730	SF	6	\$5,146	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	36	LF	7	\$0	
,	Walls - Plaster/Drywall	4th Floor	20	SF	5	\$152	
lassroo	om #408 (Regular Classroom)						
	Casework	4th Floor	37	LF	6	\$934	
	Ceiling - Plaster/Drywall	4th Floor	985	SF	6	\$3,409	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	985	SF	6	\$6,944	
	Lighting - Pendent/Surface	4th Floor	18	EA	7	\$0	
	Marker Board	4th Floor	18	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,183	SF	6	\$3,265	
	Work Sink	4th Floor	1	EA	6	\$379	
assroo	om #410 (Regular Classroom)						
	Casework	4th Floor	12	LF	6	\$303	
	Ceiling - Lay-in	4th Floor	745	SF	6	\$2,237	
	Doors - Transom Window	4th Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Wood	4th Floor	745	SF	6	\$5,252	
	Lighting - Pendent/Surface	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	18	LF	6	\$386	
,	Walls - Plaster/Drywall	4th Floor	169	SF	5	\$747	Peeling paint and damage at door
,	Walls - Plaster/Drywall	4th Floor	863	SF	6	\$2,382	
,	Work Sink	4th Floor	1	EA	5	\$1,508	Replace levers
assroo	om #411 (Science Lab Level 1)						
	Casework	4th Floor	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	4th Floor	1,325	SF	6	\$4,585	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Eye Wash Station	4th Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	4th Floor	1,325	SF	6	\$1,326	
	Fume Hood	4th Floor	1	EA	6	\$816	
	Gas Line	4th Floor	1	EA	6	\$509	
	Lighting - Pendent/Surface	4th Floor	39	EA	7	\$0	
	Marker Board	4th Floor	36	LF	6	\$771	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	om #411 (Science Lab Level 1)						
	Science Lab Elements	4th Floor	45	SF	6	\$305	
	Walls - Plaster/Drywall	4th Floor	1,391	SF	6	\$3,839	
	Work Sink	4th Floor	3	EA	6	\$1,137	
Classro	om #412 (Computer Lab)						
	AC Units	4th Floor	1	EA	6	\$496	
	Casework	4th Floor	27	LF	6	\$682	
	Ceiling - Lay-in	4th Floor	938	SF	6	\$2,817	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	4th Floor	18	EA	7	\$0	
	Marker Board	4th Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,146	SF	6	\$3,163	
	Work Sink	4th Floor	1	EA	6	\$379	old pedestal sink
Classro	om #415 (Science Lab Level 1)						
	Casework	4th Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	4th Floor	1,325	SF	6	\$3,979	
	Chalk Board	4th Floor	30	LF	4	\$2,754	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Eye Wash Station	4th Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	4th Floor	1,325	SF	6	\$1,326	
	Fume Hood	4th Floor	1	EA	6	\$816	
	Gas Line	4th Floor	1	EA	6	\$509	
	Lighting - Lay-in	4th Floor	39	EA	7	\$0	
	Marker Board	4th Floor	8	LF	7	\$0	
	Science Lab Elements	4th Floor	36	SF	6	\$244	
	Walls - Plaster/Drywall	4th Floor	1,391	SF	6	\$3,839	
	Work Sink	4th Floor	8	EA	6	\$3,032	
Classro	om #416 (Computer Lab)						
	Casework	4th Floor	9	LF	6	\$227	
	Ceiling - Lay-in	4th Floor	730	SF	6	\$2,192	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	730	SF	6	\$5,146	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lassroo	om #416 (Computer Lab)						
	Marker Board	4th Floor	28	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,097	SF	6	\$3,028	
	Wireless System	4th Floor	1	EA	6	\$372	
lassroo	om #418 (Regular Classroom)						
	Casework	4th Floor	11	LF	6	\$278	
	Ceiling - Lay-in	4th Floor	733	SF	6	\$2,201	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	722	SF	6	\$5,090	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	29	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,090	SF	6	\$3,008	
assroo	om #419 (Science Classroom)						
	AC Units	4th Floor	2	EA	6	\$991	
	Casework	4th Floor	45	LF	6	\$1,136	
	Ceiling - Lay-in	4th Floor	1,300	SF	6	\$3,904	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Eye Wash Station	4th Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	4th Floor	12	SF	5	\$69	areas of floor coming (bubbling) up
	Floor - Tile/Sheet	4th Floor	1,288	SF	6	\$1,289	
	Lighting - Lay-in	4th Floor	36	EA	7	\$0	
	Marker Board	4th Floor	17	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,496	SF	6	\$4,129	
	Work Sink	4th Floor	3	EA	6	\$1,137	sinks in base cabinets
assroo	om #420 (Regular Classroom)						
	Casework	4th Floor	8	LF	6	\$202	
	Ceiling - Lay-in	4th Floor	722	SF	6	\$2,168	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Wood	4th Floor	722	SF	6	\$5,090	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	51	LF	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,028	SF	6	\$2,837	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments		
	Classroom #422 (Regular Classroom)								
	Casework	4th Floor	11	LF	6	\$278			
	Ceiling - Lay-in	4th Floor	969	SF	6	\$2,910			
	Doors - Transom Window	4th Floor	18	SF	6	\$305			
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602			
	Floor - Wood	4th Floor	969	SF	6	\$6,831			
	Lighting - Lay-in	4th Floor	18	EA	7	\$0			
	Marker Board	4th Floor	29	LF	7	\$0			
	Walls - Plaster/Drywall	4th Floor	2	SF	6	\$8	holes in wall		
	Walls - Plaster/Drywall	4th Floor	1,260	SF	6	\$3,477			
	Work Sink	4th Floor	1	EA	6	\$379	old sink		
Classro	om #424 (Regular Classroom)								
	Casework	4th Floor	7	LF	6	\$177			
	Ceiling - Lay-in	4th Floor	728	SF	6	\$2,186			
	Doors - Transom Window	4th Floor	18	SF	6	\$305			
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602			
	Floor - Wood	4th Floor	728	SF	6	\$5,132			
	Lighting - Lay-in	4th Floor	14	EA	7	\$0			
	Marker Board	4th Floor	17	LF	7	\$0			
	Walls - Plaster/Drywall	4th Floor	1,023	SF	6	\$2,823			
Classro	om #425 (Regular Classroom)								
	Casework	4th Floor	9	LF	6	\$227			
	Ceiling - Lay-in	4th Floor	728	SF	6	\$2,186	2 ceiling tiles falling out		
	Doors - Transom Window	4th Floor	18	SF	6	\$305			
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602			
	Floor - Tile	4th Floor	728	SF	6	\$1,593			
	Lighting - Lay-in	4th Floor	14	EA	7	\$0			
	Marker Board	4th Floor	27	LF	7	\$0			
	Walls - Plaster/Drywall	4th Floor	1,084	SF	6	\$2,992			
	Walls - Plaster/Drywall	4th Floor	1	SF	5	\$5	holes in walls with exposed elect. wires		
Classro	om #427 (Regular Classroom)								
	Casework	4th Floor	9	LF	6	\$227			
	Ceiling - Lay-in	4th Floor	725	SF	6	\$2,177	1 tile falling out		
	Doors - Transom Window	4th Floor	18	SF	6	\$305			
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602			
	Floor - Wood	4th Floor	725	SF	6	\$5,111			
	Lighting - Lay-in	4th Floor	14	EA	7	\$0			



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

roup Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
lassroom #427 (Regu	ular Classroom)						
Marker Board		4th Floor	29	LF	7	\$0	
Walls - Plaster	r/Drywall	4th Floor	750	SF	6	\$2,070	
lassroom #429 (Regu	ular Classroom)						
Casework		4th Floor	9	LF	6	\$227	
Ceiling - Lay-i	n	4th Floor	724	SF	6	\$2,174	
Doors - Transo	om Window	4th Floor	18	SF	6	\$305	
Doors - Wood	Doors inclu hw	4th Floor	2	EA	6	\$602	
Floor - Wood		4th Floor	724	SF	6	\$5,104	
Lighting - Lay-	-in	4th Floor	14	EA	7	\$0	
Marker Board		4th Floor	28	LF	7	\$0	
Walls - Plaster	r/Drywall	4th Floor	1,021	SF	6	\$2,818	
lassroom #431 (Regu	ular Classroom)						
Casework		4th Floor	11	LF	6	\$278	
Ceiling - Lay-i	n	4th Floor	967	SF	6	\$2,904	
Doors - Transo	om Window	4th Floor	18	SF	6	\$305	
Doors - Wood	Doors inclu hw	4th Floor	2	EA	6	\$602	
Floor - Tile		4th Floor	967	SF	6	\$2,116	
Lighting - Lay-	-in	4th Floor	16	EA	7	\$0	
Marker Board		4th Floor	27	LF	7	\$0	
Walls - Plaster	r/Drywall	4th Floor	270	SF	6	\$884	Splined wall areas
Walls - Plaster		4th Floor	971	SF	6	\$2,680	
lassroom #433 (Regu	ular Classroom)						
Casework		4th Floor	8	LF	6	\$202	
Ceiling - Lay-i	n	4th Floor	702	SF	6	\$2,108	
Doors - Wood	Doors inclu hw	4th Floor	2	EA	6	\$602	
Floor - Tile		4th Floor	702	SF	6	\$1,536	
Lighting - Lay-	-in	4th Floor	12	EA	7	\$0	
Marker Board		4th Floor	21	LF	7	\$0	
Walls - Plaster	r/Drywall	4th Floor	1,008	SF	6	\$2,782	
	otal:				¢4	,081,882	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Building: Main**

#### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Ceiling - Plaster/Drywall	1st - 123 Teachers lounge	535	SF	6	\$1,851	
	Doors - Wood Doors inclu hw	1st - 123 Teachers lounge	1	EA	6	\$301	
	Floor - Tile	1st - 123 Teachers lounge	535	SF	6	\$1,171	
	Lighting - Pendent/Surface	1st - 123 Teachers lounge	4	EA	7	\$0	
	Power Distribution	1st - 123 Teachers lounge	4	EA	6	\$8,500	
	Walls - Concrete Block	1st - 123 Teachers lounge	338	SF	6	\$991	
	Walls - Plaster/Drywall	1st - 123 Teachers lounge	612	SF	6	\$1,689	
	Walls - Tile Ceramic/ Porcelain	1st - 123 Teachers lounge	252	SF	6	\$569	
	AC Unit	1st - 123A Teacher's Lounge	2	EA	6	\$991	
	Ceiling - Lay-in	1st - 123A Teacher's Lounge	1,336	SF	6	\$4,012	
	Doors - Transom Window	1st - 123A Teacher's Lounge	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st - 123A Teacher's Lounge	2	EA	6	\$602	
	Floor - Tile	1st - 123A Teacher's Lounge	1,336	SF	6	\$2,923	
	Lighting - Lay-in	1st - 123A Teacher's Lounge	26	EA	7	\$0	
	Power Distribution	1st - 123A Teacher's Lounge	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	1st - 123A Teacher's Lounge	1,324	SF	6	\$3,654	
	Work SInk	1st - 123A Teacher's Lounge	1	EA	6	\$508	sink in base cabinet
	Ceiling - Lay-in	1st - 133 P.A.T.H / Clinic	742	SF	6	\$2,228	
	Doors - Side-lite	1st - 133 P.A.T.H / Clinic	8	SF	6	\$134	
	Doors - Transom Window	1st - 133 P.A.T.H / Clinic	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st - 133 P.A.T.H / Clinic	3	EA	6	\$903	
	Floor - Tile/Sheet	1st - 133 P.A.T.H / Clinic	742	SF	6	\$743	
	Lighting - Lay-in	1st - 133 P.A.T.H / Clinic	17	EA	6	\$2,023	
	Power Distribution	1st - 133 P.A.T.H / Clinic	12	EA	7	\$0	
	Storage/ Closet	1st - 133 P.A.T.H / Clinic	25	SF	6	\$181	
	Storage/ Closet	1st - 133 P.A.T.H / Clinic	45	SF	6	\$326	
	Storage/ Closet	1st - 133 P.A.T.H / Clinic	78	SF	6	\$566	
	Storage/ Closet	1st - 133 P.A.T.H / Clinic	112	SF	6	\$812	door hard to open, sticks on floor
	Walls - Plaster/Drywall	1st - 133 P.A.T.H / Clinic	1,965	SF	6	\$5,423	
	Walls - Structural Glazed Tile	1st - 133 P.A.T.H / Clinic	232	SF	6	\$730	
	Work Sink	1st - 133 P.A.T.H / Clinic	1	EA	6	\$508	in lunch room area
	Ceiling - Lay-in	1st - 134 Dean of Students (doors labeled 134A / 134)	529	SF	6	\$1,589	
	Doors - Transom Window	1st - 134 Dean of Students (doors labeled 134A / 134)	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st - 134 Dean of Students (doors labeled 134A / 134)	2	EA	6	\$602	
	Floor - Tile	1st - 134 Dean of Students (doors labeled 134A / 134)	529	SF	6	\$1,157	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
minis	strative Suites/Offices						
	Lighting - Lay-in	1st - 134 Dean of Students (doors labeled 134A / 134)	14	EA	7	\$0	1 outlet junction box pull away from wall
	Power Distribution	1st - 134 Dean of Students (doors labeled 134A / 134)	10	EA	7	\$0	
	Walls - Plaster/Drywall	1st - 134 Dean of Students (doors labeled 134A / 134)	911	SF	6	\$2,514	
	AC Unit	1st - 134A Office - inside 134	1	EA	6	\$496	
	Ceiling - Lay-in	1st - 134A Office - inside 134	180	SF	6	\$541	
	Doors - Wood Doors inclu hw	1st - 134A Office - inside 134	1	EA	6	\$301	
	Floor - Tile	1st - 134A Office - inside 134	180	SF	6	\$394	
	Lighting - Lay-in	1st - 134A Office - inside 134	6	EA	7	\$0	
	Power Distribution	1st - 134A Office - inside 134	4	EA	7	\$0	
	Walls - Plaster/Drywall	1st - 134A Office - inside 134	624	SF	6	\$1,722	
	AC Unit	1st - 134B Office used by Chicago Police Department	1	EA	6	\$496	
	Ceiling - Lay-in	1st - 134B Office used by Chicago Police Department	224	SF	6	\$673	
	Doors - Wood Doors inclu hw	1st - 134B Office used by Chicago Police Department	1	EA	6	\$301	
	Floor - Tile	1st - 134B Office used by Chicago Police Department	224	SF	6	\$490	
	Lighting - Lay-in	1st - 134B Office used by Chicago Police Department	6	EA	7	\$0	
	Power Distribution	1st - 134B Office used by Chicago Police Department	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	1st - 134B Office used by Chicago Police Department	689	SF	6	\$1,902	
	AC Unit	1st - 134C (doors labeled as 134 / 134 B)	) 1	EA	6	\$496	
	Ceiling - Lay-in	1st - 134C (doors labeled as 134 / 134 B)	) 371	SF	6	\$1,114	
	Doors - Transom Window	1st - 134C (doors labeled as 134 / 134 B)	) 18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st - 134C (doors labeled as 134 / 134 B)	) 3	EA	6	\$903	2 - entry doors / 1 door from hallway entering 13 marked door
	Floor - Tile	1st - 134C (doors labeled as 134 / 134 B)	) 371	SF	6	\$812	
	Lighting - Lay-in	1st - 134C (doors labeled as 134 / 134 B)	) 10	EA	7	\$0	
	Power Distribution	1st - 134C (doors labeled as 134 / 134 B)	) 6	EA	7	\$0	
	Storage/ Closet	1st - 134C (doors labeled as 134 / 134 B)	) 10	SF	6	\$73	in hallway
	Walls - Plaster/Drywall	1st - 134C (doors labeled as 134 / 134 B)	) 909	SF	6	\$2,509	
	Ceiling - Lay-in	1st - 140 Attendance	714	SF	6	\$2,144	1 ceiling tile falling out
	Doors - Transom Window	1st - 140 Attendance	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st - 140 Attendance	2	EA	6	\$602	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	istrative Suites/Offices						
	Floor - Wood	1st - 140 Attendance	472	SF	6	\$3,328	
	Lighting - Lay-in	1st - 140 Attendance	14	EA	7	\$0	Lights from 140A Attendance is included since interior partitions don't extend to ceiling
	Power Distribution	1st - 140 Attendance	27	EA	7	\$0	
	Walls - Metal Panel	1st - 140 Attendance	220	SF	6	\$1,642	interior partitions - don't extend to ceiling
	Walls - Plaster/Drywall	1st - 140 Attendance	860	SF	6	\$2,374	
	Doors - Wood Doors inclu hw	1st - 140A Attendance inside 140	1	EA	6	\$301	
	Floor - Wood	1st - 140A Attendance inside 140	242	SF	6	\$1,706	
	Power Distribution	1st - 140A Attendance inside 140	14	EA	7	\$0	
	Walls - Metal Panel	1st - 140A Attendance inside 140	220	SF	6	\$1,642	
	Walls - Plaster/Drywall	1st - 140A Attendance inside 140	353	SF	6	\$974	
	AC Unit	1st- 100 Main Office	2	EA	6	\$991	
	Ceiling - Lay-in	1st- 100 Main Office	739	SF	6	\$2,219	
	Doors - Side-lite	1st- 100 Main Office	40	SF	6	\$669	
	Doors - Transom Window	1st- 100 Main Office	48	SF	6	\$813	
	Doors - Wood Doors inclu hw	1st- 100 Main Office	2	EA	6	\$602	
	Floor - Carpet	1st- 100 Main Office	378	SF	6	\$805	
	Floor - Tile	1st- 100 Main Office	361	SF	6	\$790	
	Lighting - Lay-in	1st- 100 Main Office	18	EA	7	\$0	
	Power Distribution	1st- 100 Main Office	18	EA	6	\$38,248	
	Walls - Plaster/Drywall	1st- 100 Main Office	1,232	SF	6	\$3,400	
	AC Unit	1st- 100A Principal	1	EA	6	\$496	
	Ceiling - Lay-in	1st- 100A Principal	365	SF	6	\$1,096	
	Doors - Transom Window	1st- 100A Principal	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st- 100A Principal	2	EA	6	\$602	
	Floor - Carpet	1st- 100A Principal	365	SF	6	\$778	
	Lighting - Lay-in	1st- 100A Principal	12	EA	7	\$0	
	Lighting - Wall Mounted	1st- 100A Principal	1	EA	6	\$124	Open clock box, exposed wiring
	Power Distribution	1st- 100A Principal	12	EA	6	\$25,499	
	Storage/ Closet	1st- 100A Principal	13	SF	6	\$94	
	Walls - Plaster/Drywall	1st- 100A Principal	883	SF	6	\$2,437	
	Ceiling - Lay-in	1st- 100D Rm inside Main office	194	SF	6	\$583	
	Doors - Wood Doors inclu hw	1st- 100D Rm inside Main office	2	EA	6	\$602	
	Floor - Carpet	1st- 100D Rm inside Main office	194	SF	6	\$413	
	Lighting - Lay-in	1st- 100D Rm inside Main office	3	EA	7	\$0	
	Power Distribution	1st- 100D Rm inside Main office	4	EA	6	\$8,500	
	Storage/ Closet	1st- 100D Rm inside Main office	9	SF	6	\$65	
	Walls - Plaster/Drywall	1st- 100D Rm inside Main office	889	SF	6	\$2,454	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
dmini	strative Suites/Offices						
	Ceiling - Lay-in	1st- 101 Attendance Office	668	SF	6	\$2,006	
	Doors - Side-lite	1st- 101 Attendance Office	102	SF	6	\$1,705	
	Doors - Steel Doors incl hw	1st- 101 Attendance Office	2	EA	6	\$602	
	Doors - Transom Window	1st- 101 Attendance Office	32	SF	6	\$542	
	Doors - Wood Doors inclu hw	1st- 101 Attendance Office	1	EA	6	\$301	
	Floor - Tile	1st- 101 Attendance Office	668	SF	6	\$1,462	
	Lighting - Lay-in	1st- 101 Attendance Office	18	EA	7	\$0	
	Power Distribution	1st- 101 Attendance Office	28	EA	6	\$59,497	
	Walls - Metal Panel	1st- 101 Attendance Office	106	SF	6	\$791	partition walls
	Walls - Plaster/Drywall	1st- 101 Attendance Office	1,035	SF	6	\$2,856	
	Ceiling - Lay-in	1st 102 Counselor Office	545	SF	6	\$1,637	
	Doors - Side-lite	1st 102 Counselor Office	30	SF	6	\$502	
	Doors - Steel Doors incl hw	1st 102 Counselor Office	2	EA	6	\$602	
	Doors - Transom Window	1st 102 Counselor Office	32	SF	6	\$542	
	Doors - Wood Doors inclu hw	1st 102 Counselor Office	1	EA	6	\$301	
	Floor - Tile	1st 102 Counselor Office	545	SF	6	\$1,192	
	Lighting - Lay-in	1st 102 Counselor Office	10	EA	7	\$0	
	Power Distribution	1st 102 Counselor Office	24	EA	6	\$50,997	
	Storage/ Closet	1st 102 Counselor Office	3	SF	6	\$22	
	Walls - Metal Panel	1st 102 Counselor Office	106	SF	6	\$791	partition walls
	Walls - Plaster/Drywall	1st 102 Counselor Office	1,215	SF	6	\$3,353	
	AC Unit	1st- 103A- Scheduler	1	EA	6	\$496	
	Ceiling - Lay-in	1st- 103A- Scheduler	158	SF	6	\$474	
	Doors - Side-lite	1st- 103A- Scheduler	20	SF	6	\$334	
	Doors - Transom Window	1st- 103A- Scheduler	24	SF	6	\$406	
	Doors - Wood Doors inclu hw	1st- 103A- Scheduler	1	EA	6	\$301	
	Floor - Carpet	1st- 103A- Scheduler	158	SF	6	\$337	
	Lighting - Lay-in	1st- 103A- Scheduler	2	EA	7	\$0	
	Lighting - Lay-in	1st- 103A- Scheduler	1	EA	6	\$119	cover missing
	Power Distribution	1st- 103A- Scheduler	6	EA	6	\$12,749	
	Storage/ Closet	1st- 103A- Scheduler	10	SF	6	\$73	
	Walls - Plaster/Drywall	1st- 103A- Scheduler	635	SF	6	\$1,753	
	AC Unit	1st- 103B- Social Work	1	EA	6	\$496	
	Ceiling - Lay-in	1st- 103B- Social Work	196	SF	6	\$589	
	Doors - Transom Window	1st- 103B- Social Work	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st- 103B- Social Work	1	EA	6	\$301	
	Floor - Carpet	1st- 103B- Social Work	196	SF	6	\$418	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	Lighting - Lay-in	1st- 103B- Social Work	6	EA	7	\$0	
	Power Distribution	1st- 103B- Social Work	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st- 103B- Social Work	636	SF	6	\$1,755	
	AC Unit	1st- 106 Principal Office (off of 112)	1	EA	6	\$496	
	Ceiling - Lay-in	1st- 106 Principal Office (off of 112)	348	SF	6	\$1,045	
	Ceiling - Lay-in	1st- 106 Principal Office (off of 112)	13	SF	5	\$104	water damaged
	Doors - Side-lite	1st- 106 Principal Office (off of 112)	38	SF	6	\$635	
	Doors - Transom Window	1st- 106 Principal Office (off of 112)	52	SF	6	\$880	
	Doors - Wood Doors inclu hw	1st- 106 Principal Office (off of 112)	3	EA	6	\$903	
	Floor - Carpet	1st- 106 Principal Office (off of 112)	361	SF	6	\$769	
	Lighting - Metal Halide/ High Pressure Sodium	1st- 106 Principal Office (off of 112)	9	EA	7	\$0	
	Lighting - Wall Mounted	1st- 106 Principal Office (off of 112)	1	EA	6	\$124	open clock box, exposed wiring
	Power Distribution	1st- 106 Principal Office (off of 112)	14	EA	6	\$29,748	
	Walls - Plaster/Drywall	1st- 106 Principal Office (off of 112)	1,423	SF	6	\$3,927	
	Ceiling - Lay-in	1st- 108A Vacant Room (former toilet in 108)	231	SF	6	\$694	
	Doors - Wood Doors inclu hw	1st- 108A Vacant Room (former toilet in 108)	1	EA	6	\$301	
	Floor - Tile	1st- 108A Vacant Room (former toilet in 108)	231	SF	6	\$505	
	Lighting - Lay-in	1st- 108A Vacant Room (former toilet in 108)	6	EA	7	\$0	
	Power Distribution	1st- 108A Vacant Room (former toilet in 108)	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	1st- 108A Vacant Room (former toilet in 108)	610	SF	6	\$1,684	
	Ceiling - Lay-in	1st- 108B (inside Rm 108)	104	SF	6	\$312	
	Doors - Transom Window	1st- 108B (inside Rm 108)	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st- 108B (inside Rm 108)	2	EA	6	\$602	
	Floor - Tile	1st- 108B (inside Rm 108)	104	SF	6	\$228	
	Lighting - Lay-in	1st- 108B (inside Rm 108)	2	EA	7	\$0	
	Power Distribution	1st- 108B (inside Rm 108)	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	1st- 108B (inside Rm 108)	450	SF	6	\$1,242	
	AC Unit	1st- 112 Principal Suite	1	EA	6	\$496	
	Ceiling - Lay-in	1st- 112 Principal Suite	824	SF	6	\$2,474	
	Doors - Transom Window	1st- 112 Principal Suite	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	1st- 112 Principal Suite	2	EA	6	\$602	
	Floor - Carpet	1st- 112 Principal Suite	824	SF	6	\$1,756	
	Lighting - Lay-in	1st- 112 Principal Suite	25	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admir	istrative Suites/Offices						
	Power Distribution	1st- 112 Principal Suite	15	EA	6	\$31,873	
	Storage/ Closet	1st- 112 Principal Suite	16	SF	5	\$258	cracking & peeling paint
	Walls - Plaster/Drywall	1st- 112 Principal Suite	3,201	SF	6	\$8,834	
	AC Unit	1st- 114 Principals Office (off of 112)	1	EA	6	\$496	
	Ceiling - Lay-in	1st- 114 Principals Office (off of 112)	4	SF	5	\$32	water damaged
	Ceiling - Lay-in	1st- 114 Principals Office (off of 112)	296	SF	6	\$889	
	Ceiling - Plaster/Drywall	1st- 114 Principals Office (off of 112)	9	SF	6	\$31	
	Ceiling - Plaster/Drywall	1st- 114 Principals Office (off of 112)	6	SF	5	\$65	water damaged
	Doors - Transom Window	1st- 114 Principals Office (off of 112)	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st- 114 Principals Office (off of 112)	1	EA	6	\$301	
	Floor - Carpet	1st- 114 Principals Office (off of 112)	315	SF	6	\$671	
	Lighting - Lay-in	1st- 114 Principals Office (off of 112)	15	EA	7	\$0	
	Power Distribution	1st- 114 Principals Office (off of 112)	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	1st- 114 Principals Office (off of 112)	1,318	SF	6	\$3,638	
	AC Unit	1st- 124A Security Office	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st- 124A Security Office	301	SF	5	\$2,759	leaking ceiling, water damage & dripping all over wall &security equiptment
	Doors - Steel Doors incl hw	1st- 124A Security Office	1	EA	6	\$301	
	Floor - Terrazzo	1st- 124A Security Office	12	SF	6	\$26	
	Floor - Tile Ceramic/ Porcelain	1st- 124A Security Office	289	SF	6	\$612	
	Lighting - Pendent/Surface	1st- 124A Security Office	6	EA	7	\$0	
	Power Distribution	1st- 124A Security Office	2	EA	5	\$7,703	outlet box lying on floor with exposed wiring
	Power Distribution	1st- 124A Security Office	10	EA	6	\$21,249	
	Walls - Masonry	1st- 124A Security Office	90	SF	6	\$283	stone slabs
	Walls - Plaster/Drywall	1st- 124A Security Office	50	SF	5	\$255	water damaged from leaking ceiling
	Walls - Plaster/Drywall	1st- 124A Security Office	830	SF	6	\$2,291	
	Ceiling - Lay-in	1st- 125 Asst. Eng. Office	159	SF	6	\$477	
	Doors - Wood Doors inclu hw	1st- 125 Asst. Eng. Office	1	EA	5	\$1,174	door de-laminating & door stop is loose
	Floor - Lay-in	1st- 125 Asst. Eng. Office	159	SF	6	\$0	
	Lighting - Lay-in	1st- 125 Asst. Eng. Office	2	EA	7	\$0	
	Power Distribution	1st- 125 Asst. Eng. Office	8	EA	7	\$0	
	Storage/ Closet	1st- 125 Asst. Eng. Office	37	SF	6	\$268	
	Walls - Plaster/Drywall	1st- 125 Asst. Eng. Office	644	SF	6	\$1,777	
	AC Unit	1st- File room inside 100 Main office	1	EA	6	\$496	
	Ceiling - Lay-in	1st- File room inside 100 Main office	188	SF	6	\$565	
	Doors - Wood Doors inclu hw	1st- File room inside 100 Main office	2	EA	6	\$602	
	Floor - Carpet	1st- File room inside 100 Main office	188	SF	6	\$401	
	Lighting - Lay-in	1st- File room inside 100 Main office	6	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	Power Distribution	1st- File room inside 100 Main office	4	EA	6	\$8,500	
	Storage/ Closet	1st- File room inside 100 Main office	20	SF	6	\$145	
	Walls - Plaster/Drywall	1st- File room inside 100 Main office	613	SF	6	\$1,692	
	AC Unit	1st- Kitchen Office	1	EA	6	\$496	
	Ceiling - Lay-in	1st- Kitchen Office	125	SF	6	\$375	
	Doors - Transom Window	1st- Kitchen Office	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st- Kitchen Office	1	EA	6	\$301	
	Floor - Terrazzo	1st- Kitchen Office	125	SF	6	\$273	
	Lighting - Lay-in	1st- Kitchen Office	3	EA	7	\$0	
	Power Distribution	1st- Kitchen Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	1st- Kitchen Office	194	SF	6	\$535	
	Walls - Structural Glazed Tile	1st- Kitchen Office	291	SF	6	\$915	
	Ceiling - Plaster/Drywall	1st- Ticket Booth 1 in Auditorium foyer	62	SF	5	\$568	bowing down from a water leak,
	Doors - Wood Doors inclu hw	1st- Ticket Booth 1 in Auditorium foyer	1	EA	6	\$301	
	Floor - Concrete	1st- Ticket Booth 1 in Auditorium foyer	62	SF	6	\$33	
	Lighting - Wall Mounted	1st- Ticket Booth 1 in Auditorium foyer	1	EA	7	\$0	
	Power Distribution	1st- Ticket Booth 1 in Auditorium foyer	1	EA	6	\$2,125	light switch not mounted to box & missing cover. exposed wiring
	Walls - Plaster/Drywall	1st- Ticket Booth 1 in Auditorium foyer	16	SF	5	\$82	water damage/efflorecense
	Walls - Plaster/Drywall	1st- Ticket Booth 1 in Auditorium foyer	410	SF	6	\$1,132	
	Ceiling - Plaster/Drywall	1st- Ticket Booth 2 in Auditorium foyer	62	SF	6	\$215	
	Doors - Wood Doors inclu hw	1st- Ticket Booth 2 in Auditorium foyer	1	EA	5	\$1,174	delaminating
	Floor - Concrete	1st- Ticket Booth 2 in Auditorium foyer	62	SF	6	\$33	
	Lighting - Wall Mounted	1st- Ticket Booth 2 in Auditorium foyer	1	EA	7	\$0	
	Walls - Plaster/Drywall	1st- Ticket Booth 2 in Auditorium foyer	426	SF	6	\$1,176	
	Ceiling - Plaster/Drywall	203B	116	SF	6	\$401	
	Doors - Wood Doors inclu hw	203B	1	EA	6	\$301	
	Floor - Tile	203B	116	SF	6	\$254	
	Lighting - Pendent/Surface	203B	2	EA	6	\$248	
	Power Distribution	203B	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	203B	581	SF	6	\$1,604	
	Work SInk	203B	1	EA	6	\$508	
	Ceiling - Plaster/Drywall	208	213	SF	6	\$737	
	Doors - Wood Doors inclu hw	208	1	EA	6	\$301	
	Floor - Tile	208	213	SF	6	\$466	
	Lighting - Pendent/Surface	208	3	EA	7	\$0	
	Power Distribution	208	4	EA	7	\$0	
	Walls - Plaster/Drywall	208	788	SF	6	\$2,175	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
istrative Suites/Offices						
Ceiling - Lay-in	228 - PE Office	338	SF	6	\$1,015	
Doors - Wood Doors inclu hw	228 - PE Office	1	EA	6	\$301	
Floor - Tile	228 - PE Office	338	SF	6	\$740	
Lighting - Lay-in	228 - PE Office	4	EA	7	\$0	
Power Distribution	228 - PE Office	6	EA	6	\$12,749	
Walls - Plaster/Drywall	228 - PE Office	848	SF	6	\$2,340	
Work SInk	228 - PE Office	1	EA	6	\$508	pedestal sink
Ceiling - Lay-in	2nd - 220B Office	298	SF	6	\$895	stains in 2 ceiling tiles
Doors - Transom Window	2nd - 220B Office	9	SF	6	\$152	
Doors - Wood Doors inclu hw	2nd - 220B Office	1	EA	6	\$301	
Floor - Carpet	2nd - 220B Office	298	SF	6	\$635	
Lighting - Lay-in	2nd - 220B Office	4	EA	7	\$0	
Power Distribution	2nd - 220B Office	6	EA	7	\$0	
Walls - Plaster/Drywall	2nd - 220B Office	793	SF	6	\$2,189	
AC Unit	2nd - 231 Work Room	1	EA	6	\$496	
Ceiling - Lay-in	2nd - 231 Work Room	363	SF	6	\$1,090	
Doors - Transom Window	2nd - 231 Work Room	9	SF	6	\$152	
Doors - Wood Doors inclu hw	2nd - 231 Work Room	1	EA	6	\$301	
Floor - Carpet	2nd - 231 Work Room	363	SF	6	\$773	
Lighting - Lay-in	2nd - 231 Work Room	5	EA	7	\$0	
Power Distribution	2nd - 231 Work Room	8	EA	7	\$0	
Walls - Plaster/Drywall	2nd - 231 Work Room	906	SF	6	\$2,500	
Ceiling - Lay-in	2nd - 243 Engineer Office	235	SF	6	\$706	
Doors - Transom Window	2nd - 243 Engineer Office	9	SF	6	\$152	
Doors - Wood Doors inclu hw	2nd - 243 Engineer Office	1	EA	6	\$301	
Floor - Carpet	2nd - 243 Engineer Office	200	SF	6	\$426	
Floor - Tile/Sheet	2nd - 243 Engineer Office	35	SF	6	\$35	
Lighting - Lay-in	2nd - 243 Engineer Office	4	EA	7	\$0	
Power Distribution	2nd - 243 Engineer Office	14	EA	7	\$0	
Walls - Plaster/Drywall	2nd - 243 Engineer Office	739	SF	6	\$2,040	
Ceiling - Lay-in	302A	360	SF	6	\$1,081	
Doors - Wood Doors inclu hw	302A	1	EA	6	\$301	
Floor - Wood	302A	360	SF	6	\$2,538	
Lighting - Lay-in	302A	6	EA	7	\$0	
Power Distribution	302A	8	EA	7	\$0	
Walls - Plaster/Drywall	302A	795	SF	6	\$2,194	
Ceiling - Plaster/Drywall	313B	94	SF	6	\$325	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

p l'	tem - Type	Location	Quantity	Unit	Rank	Cost	Comments
inistr	ative Suites/Offices						
Γ	Doors - Wood Doors inclu hw	313B	1	EA	6	\$301	
F	Floor - Tile Quarry	313B	94	SF	6	\$199	
L	ighting - Pendent/Surface	313B	1	EA	6	\$124	
F	Power Distribution	313B	6	EA	7	\$0	
V	Valls - Plaster/Drywall	313B	522	SF	6	\$1,441	
(	Ceiling - Lay-in	3rd - 314 Office	702	SF	6	\$2,108	
Γ	Doors - Transom Window	3rd - 314 Office	9	SF	6	\$152	
Γ	Doors - Wood Doors inclu hw	3rd - 314 Office	1	EA	6	\$301	
F	Floor - Carpet	3rd - 314 Office	702	SF	6	\$1,496	
L	ighting - Lay-in	3rd - 314 Office	11	EA	7	\$0	
F	Power Distribution	3rd - 314 Office	6	EA	7	\$0	
ξ	Storage/ Closet	3rd - 314 Office	12	SF	5	\$194	hole in wall with exposed elect. wires
1	Valls - Plaster/Drywall	3rd - 314 Office	1,189	SF	6	\$3,282	
1	Vork SInk	3rd - 314 Office	1	EA	6	\$508	
(	Ceiling - Lay-in	3rd - 316 Office	284	SF	6	\$853	
[	Doors - Wood Doors inclu hw	3rd - 316 Office	1	EA	6	\$301	
F	Floor - Carpet	3rd - 316 Office	284	SF	6	\$605	
L	ighting - Lay-in	3rd - 316 Office	4	EA	7	\$0	
F	Power Distribution	3rd - 316 Office	6	EA	7	\$0	
١	Valls - Plaster/Drywall	3rd - 316 Office	761	SF	6	\$2,100	
(	Ceiling - Lay-in	3rd - 318 Room	341	SF	6	\$1,024	
E	Doors - Transom Window	3rd - 318 Room	9	SF	6	\$152	
Γ	Doors - Wood Doors inclu hw	3rd - 318 Room	1	EA	6	\$301	
F	Floor - Carpet	3rd - 318 Room	341	SF	6	\$727	
L	.ighting - Lay-in	3rd - 318 Room	5	EA	7	\$0	
F	Power Distribution	3rd - 318 Room	2	EA	7	\$0	
١	Valls - Plaster/Drywall	3rd - 318 Room	5	SF	6	\$19	cracking / peeling
١	Valls - Plaster/Drywall	3rd - 318 Room	909	SF	6	\$2,509	
١	Vork SInk	3rd - 318 Room	1	EA	5	\$1,508	no in good condition
(	Ceiling - Lay-in	3rd - 320 Room	243	SF	6	\$730	
Γ	Doors - Transom Window	3rd - 320 Room	9	SF	6	\$152	
Γ	Doors - Wood Doors inclu hw	3rd - 320 Room	1	EA	6	\$301	
F	Floor - Tile	3rd - 320 Room	243	SF	6	\$532	
l	.ighting - Lay-in	3rd - 320 Room	5	EA	7	\$0	
	Power Distribution	3rd - 320 Room	6	EA	7	\$0	
١	Valls - Plaster/Drywall	3rd - 320 Room	789	SF	6	\$2,178	
	Ceiling - Lay-in	3rd - 320A Office	298	SF	6	\$895	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

up Iter	т - Туре	Location	Quantity	Unit	Rank	Cost	Comments
inistrat	ive Suites/Offices						
Do	ors - Transom Window	3rd - 320A Office	9	SF	6	\$152	
Do	ors - Wood Doors inclu hw	3rd - 320A Office	1	EA	6	\$301	
Flo	bor - Carpet	3rd - 320A Office	298	SF	6	\$635	
Lig	hting - Lay-in	3rd - 320A Office	4	EA	7	\$0	
Po	wer Distribution	3rd - 320A Office	2	EA	7	\$0	
Wa	alls - Plaster/Drywall	3rd - 320A Office	821	SF	6	\$2,266	
Cei	iling - Lay-in	3rd - 327 Prep Room	434	SF	6	\$1,303	
Do	ors - Transom Window	3rd - 327 Prep Room	9	SF	6	\$152	
Do	ors - Wood Doors inclu hw	3rd - 327 Prep Room	1	EA	6	\$301	
Flo	oor - Tile/Sheet	3rd - 327 Prep Room	434	SF	6	\$434	
Lig	hting - Lay-in	3rd - 327 Prep Room	11	EA	7	\$0	
Pov	wer Distribution	3rd - 327 Prep Room	6	EA	7	\$0	
Wa	alls - Concrete Block	3rd - 327 Prep Room	219	SF	6	\$642	
Wa	alls - Plaster/Drywall	3rd - 327 Prep Room	678	SF	6	\$1,871	
Wo	ork Sink	3rd - 327 Prep Room	1	EA	6	\$508	sink in base
AC	; Unit	3rd - 351 Engineer Office	1	EA	6	\$496	
Cei	iling - Lay-in	3rd - 351 Engineer Office	234	SF	6	\$703	
Do	ors - Transom Window	3rd - 351 Engineer Office	9	SF	6	\$152	
Do	ors - Wood Doors inclu hw	3rd - 351 Engineer Office	1	EA	6	\$301	
Flo	bor - Carpet	3rd - 351 Engineer Office	234	SF	6	\$499	
Lig	hting - Lay-in	3rd - 351 Engineer Office	4	EA	7	\$0	
Pov	wer Distribution	3rd - 351 Engineer Office	6	EA	7	\$0	
Wa	alls - Plaster/Drywall	3rd - 351 Engineer Office	715	SF	6	\$1,973	
Cei	iling - Plaster/Drywall	3rd - Office inside Classroom 325	223	SF	6	\$772	
Do	ors - Side-lite	3rd - Office inside Classroom 325	7	SF	6	\$117	
Do	ors - Transom Window	3rd - Office inside Classroom 325	14	SF	6	\$237	
Do	ors - Wood Doors inclu hw	3rd - Office inside Classroom 325	1	EA	6	\$301	
Flo	por - Wood	3rd - Office inside Classroom 325	223	SF	6	\$1,572	
Lig	hting - Pendent/Surface	3rd - Office inside Classroom 325	3	EA	7	\$0	
Pov	wer Distribution	3rd - Office inside Classroom 325	6	EA	7	\$0	
Wa	alls - Plaster/Drywall	3rd - Office inside Classroom 325	779	SF	6	\$2,150	
Cei	iling - Lay-in	3rd - Social Worker Office next to 341	153	SF	6	\$459	
Do	ors - Wood Doors inclu hw	3rd - Social Worker Office next to 341	1	EA	6	\$301	
Flo	por - Tile	3rd - Social Worker Office next to 341	153	SF	6	\$335	
Lig	hting - Lay-in	3rd - Social Worker Office next to 341	3	EA	7	\$0	
-	wer Distribution	3rd - Social Worker Office next to 341	2	EA	7	\$0	
Wa	alls - Plaster/Drywall	3rd - Social Worker Office next to 341	502	SF	6	\$1,385	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	AC Unit	401A	1	EA	6	\$496	
	Ceiling - Lay-in	401A	243	SF	6	\$730	
	Doors - Wood Doors inclu hw	401A	1	EA	6	\$301	
	Floor - Tile	401A	243	SF	6	\$532	
	Lighting - Lay-in	401A	6	EA	7	\$0	
	Power Distribution	401A	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	401A	614	SF	6	\$1,695	
	Ceiling - Lay-in	403	394	SF	6	\$1,183	
	Doors - Wood Doors inclu hw	403	1	EA	6	\$301	
	Floor - Tile	403	394	SF	6	\$862	
	Lighting - Lay-in	403	8	EA	7	\$0	
	Power Distribution	403	12	EA	6	\$25,499	
	Walls - Plaster/Drywall	403	943	SF	6	\$2,603	
	AC Unit	409	1	EA	6	\$496	
	Ceiling - Lay-in	409	547	SF	6	\$1,643	
	Doors - Transom Window	409	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	409	1	EA	6	\$301	
	Floor - Tile	409	547	SF	6	\$1,197	
	Lighting - Lay-in	409	10	EA	7	\$0	
	Power Distribution	409	36	EA	7	\$0	
	Walls - Plaster/Drywall	409	1,041	SF	6	\$2,873	
	Ceiling - Plaster/Drywall	410 A	250	SF	6	\$865	
	Doors - Transom Window	410 A	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	410 A	1	EA	6	\$301	
	Floor - Wood	410 A	250	SF	6	\$1,762	
	Lighting - Pendent/Surface	410 A	5	EA	7	\$0	
	Power Distribution	410 A	10	EA	7	\$0	
	Walls - Plaster/Drywall	410 A	800	SF	6	\$2,208	
	Ceiling - Lay-in	4th - 414 Office	242	SF	6	\$727	
	Doors - Transom Window	4th - 414 Office	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th - 414 Office	1	EA	6	\$301	
	Floor - Wood	4th - 414 Office	242	SF	6	\$1,706	
	Lighting - Lay-in	4th - 414 Office	5	EA	7	\$0	
	Power Distribution	4th - 414 Office	14	EA	7	\$0	
	Walls - Plaster/Drywall	4th - 414 Office	795	SF	6	\$2,194	
	Ceiling - Plaster/Drywall	4th - 414B Office	290	SF	6	\$1,004	
	Ceiling - Plaster/Drywall	4th - 414B Office	7	SF	6	\$34	crack in ceiling



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	Doors - Transom Window	4th - 414B Office	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th - 414B Office	1	EA	6	\$301	
	Floor - Carpet	4th - 414B Office	297	SF	6	\$633	
	Lighting - Pendent/Surface	4th - 414B Office	2	EA	7	\$0	
	Power Distribution	4th - 414B Office	14	EA	7	\$0	
	Walls - Plaster/Drywall	4th - 414B Office	946	SF	6	\$2,611	
	Ceiling - Lay-in	4th - 421 Prep Room	443	SF	6	\$1,330	
	Doors - Transom Window	4th - 421 Prep Room	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th - 421 Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	4th - 421 Prep Room	443	SF	6	\$443	
	Lighting - Lay-in	4th - 421 Prep Room	11	EA	7	\$0	
	Power Distribution	4th - 421 Prep Room	6	EA	7	\$0	
	Walls - Concrete Block	4th - 421 Prep Room	180	SF	6	\$528	
	Walls - Plaster/Drywall	4th - 421 Prep Room	624	SF	6	\$1,722	
	Work SInk	4th - 421 Prep Room	1	EA	6	\$508	1 sink in base cabinet
	Ceiling - Lay-in	4th - 428 Office used as shared storage	238	SF	6	\$715	
	Doors - Transom Window	4th - 428 Office used as shared storage	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th - 428 Office used as shared storage	1	EA	6	\$301	
	Floor - Wood	4th - 428 Office used as shared storage	238	SF	6	\$1,678	
	Lighting - Lay-in	4th - 428 Office used as shared storage	5	EA	7	\$0	
	Power Distribution	4th - 428 Office used as shared storage	5	EA	7	\$0	
	Walls - Plaster/Drywall	4th - 428 Office used as shared storage	790	SF	6	\$2,180	
Auditor	ium & Theater						
	AC Unit	1st- 105 Assembly Hall	2	EA	6	\$991	
	Ceiling - Plaster/Drywall	1st- 105 Assembly Hall	2,454	SF	6	\$20,459	
	Ceiling - Plaster/Drywall	1st- 105 Assembly Hall	60	SF	5	\$1,890	water damaged
	Doors - Transom Window	1st- 105 Assembly Hall	48	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st- 105 Assembly Hall	7	EA	6	\$2,107	
	Floor - Wood	1st- 105 Assembly Hall	10	SF	5	\$197	broken floor boards
	Floor - Wood	1st- 105 Assembly Hall	2,504	SF	6	\$17,653	
	Lighting - Pendent/Surface	1st- 105 Assembly Hall	24	EA	7	\$0	
	Lighting - Wall Mounted	1st- 105 Assembly Hall	5	EA	7	\$0	
	Main Floor Seating	1st- 105 Assembly Hall	246	EA	7	\$0	
	Stage	1st- 105 Assembly Hall	515	SF	6	\$2,975	
	Stage Curtain	1st- 105 Assembly Hall	2	EA	6	\$0	
	Stage Lift	1st- 105 Assembly Hall	1	EA	6	\$6,510	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
uditor	ium & Theater						
	Stage-Stairs - Wood	1st- 105 Assembly Hall	10	LF	6	\$117	
	Walls - Plaster/Drywall	1st- 105 Assembly Hall	2,819	SF	6	\$13,424	
	Balcony Seating	1st Floor	789	EA	6	\$137,220	
	Ceiling - Exposed	1st Floor	3,395	SF	6	\$5,049	over stage
	Ceiling - Plaster/Drywall	1st Floor	40	SF	5	\$1,260	25sf water damaged in main auditorium/15sf in hallway near stage/
	Ceiling - Plaster/Drywall	1st Floor	18,799	SF	6	\$156,725	includes: main auditorium, balcony, lobbies & vestibules
	Doors - Wood Doors inclu hw	1st Floor	32	EA	6	\$9,632	
	Floor - Concrete	1st Floor	867	SF	6	\$459	balcony
	Floor - Terrazzo	1st Floor	234	SF	6	\$780	stair landings
	Floor - Terrazzo	1st Floor	5,645	SF	6	\$12,351	includes: lobbies & vestibules
	Floor - Tile	1st Floor	50	SF	5	\$288	50sf damaged tile by stage/6sf damaged in hall near stage/
	Floor - Tile	1st Floor	12,221	SF	6	\$26,738	main auditorium floor & vestibules
	Lighting - Chandelier, Incandescent	1st Floor	12	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	2	EA	6	\$248	missing cover
	Lighting - Pendent/Surface	1st Floor	32	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	38	EA	7	\$0	
	Main Floor Seating	1st Floor	1,948	EA	6	\$338,790	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	3,395	SF	6	\$19,614	Wood
	Stage Curtain	1st Floor	8	EA	7	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor	3	LF	5	\$160	stair nosing broken
	Stage-Stairs - Wood	1st Floor	10	LF	6	\$117	
	Stairs - Terrazzo	1st Floor	46	LF	6	\$352	
	Storage/ Closet	1st Floor	455	SF	6	\$3,299	
	Walls - Masonry	1st Floor	9,945	SF	6	\$31,287	stage walls
	Walls - Plaster/Drywall	1st Floor	35	SF	5	\$395	damaged: outside Women's RR/by stairs/& balcony
	Walls - Plaster/Drywall	1st Floor	22,335	SF	6	\$106,357	includes: main auditorium, balcony, lobbies & vestibules
	Walls - Tile Ceramic/ Porcelain	1st Floor	2,182	SF	6	\$4,930	Stone walls- main auditorium
linic							
	Ceiling - Lay-in	1st - admin office in clinic	125	SF	6	\$375	
	Floor - Tile/Sheet	1st - admin office in clinic	125	SF	6	\$125	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Clinic							
	Lighting - Lay-in	1st - admin office in clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - admin office in clinic	404	SF	6	\$1,115	
	Ceiling - Lay-in	1st - exam room 1 inside Clinic	88	SF	6	\$264	
	Doors - Wood Doors inclu hw	1st - exam room 1 inside Clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - exam room 1 inside Clinic	88	SF	6	\$88	
	Lighting - Lay-in	1st - exam room 1 inside Clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - exam room 1 inside Clinic	243	SF	6	\$671	
	Walls - Structural Glazed Tile	1st - exam room 1 inside Clinic	50	SF	6	\$157	
	Ceiling - Lay-in	1st - exam room 2 inside clinic	88	SF	6	\$264	
	Doors - Wood Doors inclu hw	1st - exam room 2 inside clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - exam room 2 inside clinic	88	SF	6	\$88	
	Lighting - Lay-in	1st - exam room 2 inside clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - exam room 2 inside clinic	243	SF	6	\$671	
	Walls - Structural Glazed Tile	1st - exam room 2 inside clinic	50	SF	6	\$157	
	Ceiling - Lay-in	1st - exam room 3 inside clinic	88	SF	6	\$264	
	Doors - Wood Doors inclu hw	1st - exam room 3 inside clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - exam room 3 inside clinic	88	SF	6	\$88	
	Lighting - Lay-in	1st - exam room 3 inside clinic	2	EA	6	\$238	
	Walls - Plaster/Drywall	1st - exam room 3 inside clinic	171	SF	6	\$472	
	Walls - Structural Glazed Tile	1st - exam room 3 inside clinic	171	SF	6	\$538	1 tile cracked
	Ceiling - Lay-in	1st - lab inside clinic	79	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st - lab inside clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - lab inside clinic	79	SF	6	\$79	
	Lighting - Lay-in	1st - lab inside clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - lab inside clinic	324	SF	6	\$894	
	Ceiling - Lay-in	1st - Office 1 inside clinic	75	SF	6	\$225	
	Doors - Wood Doors inclu hw	1st - Office 1 inside clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - Office 1 inside clinic	75	SF	6	\$75	
	Lighting - Lay-in	1st - Office 1 inside clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - Office 1 inside clinic	244	SF	6	\$673	
	Walls - Structural Glazed Tile	1st - Office 1 inside clinic	70	SF	6	\$220	
	Ceiling - Lay-in	1st - office 2 in clinic	75	SF	6	\$225	
	Doors - Wood Doors inclu hw	1st - office 2 in clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - office 2 in clinic	75	SF	6	\$75	
	Lighting - Lay-in	1st - office 2 in clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - office 2 in clinic	244	SF	6	\$673	
	Walls - Structural Glazed Tile	1st - office 2 in clinic	70	SF	6	\$220	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Clinic							
	Ceiling - Lay-in	1st - office 3 in clinic	94	SF	6	\$282	
	Doors - Wood Doors inclu hw	1st - office 3 in clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - office 3 in clinic	94	SF	6	\$94	
	Lighting - Lay-in	1st - office 3 in clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - office 3 in clinic	356	SF	6	\$983	
	Ceiling - Lay-in	1st - office 4 inside clinic	124	SF	6	\$372	stains on ceiling
	Doors - Wood Doors inclu hw	1st - office 4 inside clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - office 4 inside clinic	124	SF	6	\$124	
	Lighting - Lay-in	1st - office 4 inside clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - office 4 inside clinic	402	SF	6	\$1,109	
	Ceiling - Lay-in	1st - office 5 in clinic	113	SF	6	\$339	stains on ceiling
	Doors - Wood Doors inclu hw	1st - office 5 in clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - office 5 in clinic	113	SF	6	\$113	
	Lighting - Lay-in	1st - office 5 in clinic	2	EA	7	\$0	
	Walls - Structural Glazed Tile	1st - office 5 in clinic	386	SF	6	\$1,214	
Green House							
	Finishes	213A	520	SF	5	\$6,231	Floor cracks, seepage at perimeter wall
	Glazing	213A	965	SF	6	\$24,025	
	Plumbing	213A	180	SF	6	\$103	
	Glazing	Courtyard	556	SF	5	\$47,347	
Gymna	asia						
	Bleacher Seating	204	419	EA	6	\$12,127	
	Ceiling - Splined	204	25	SF	5	\$242	Damaged or missing
	Ceiling - Splined	204	10,731	SF	6	\$8,747	
	Doors - Wood Doors inclu hw	204	10	EA	6	\$3,010	
	Floor - Concrete	204	3,144	SF	6	\$1,663	
	Floor - Wood	204	7,612	SF	6	\$53,664	
	Lighting - Pendent/Surface	204	48	EA	7	\$0	
	Scoreboards	204	1	EA	6	\$2,244	
	Sound System	204	1	EA	6	\$41,654	
	Storage/ Closet	204	1,747	SF	6	\$12,666	Missing light
	Walls - Structural Glazed Tile	204	10	SF	5	\$508	Cracking
	Ceiling - Plaster/Drywall	210	2,017	SF	6	\$11,133	
	Ceiling - Plaster/Drywall	210	124	SF	5	\$2,484	
	Doors - Wood Doors inclu hw	210	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	210	2,141	SF	6	\$11,206	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymna	sia						
	Lighting - Pendent/Surface	210	3	EA	6	\$372	
	Storage/ Closet	210	182	SF	5	\$2,936	Hole in ceiling
	Walls	210	1		5	\$0	Open junction box
	Walls - Plaster/Drywall	210	262	SF	5	\$1,338	
	Walls - Plaster/Drywall	210	3,705	SF	6	\$10,225	
	Ceiling - Plaster/Drywall	214	3,980	SF	6	\$21,969	
	Doors - Wood Doors inclu hw	214	6	EA	6	\$1,806	
	Floor - Wood	214	3,980	SF	6	\$28,059	
	Lighting - Metal Halide/Sodium Vapor	214	15	EA	6	\$2,006	
	Sound System	214	1	EA	6	\$41,654	
	Walls - Plaster/Drywall	214	6,622	SF	6	\$18,276	
	Ceiling - Plaster/Drywall	2nd - 222 Gymnasium	300	SF	5	\$5,109	stained / cracked / peeling
	Ceiling - Plaster/Drywall	2nd - 222 Gymnasium	687	SF	6	\$3,792	
	Doors - Transom Window	2nd - 222 Gymnasium	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	2nd - 222 Gymnasium	2	EA	6	\$602	1 - double door
	Floor - Wood	2nd - 222 Gymnasium	387	SF	6	\$2,728	
	Lighting - Pendent/Surface	2nd - 222 Gymnasium	2	EA	7	\$0	
	Storage/ Closet	2nd - 222 Gymnasium	52	SF	6	\$377	
	Walls - Plaster/Drywall	2nd - 222 Gymnasium	3,016	SF	6	\$8,324	
	Bleacher Seating	2nd - 230 Gymnasium	42	EA	5	\$2,136	almost all damaged
	Ceiling - Plaster/Drywall	2nd - 230 Gymnasium	4,548	SF	6	\$25,104	
	Ceiling - Plaster/Drywall	2nd - 230 Gymnasium	20	SF	6	\$155	plaster peeling / stained
	Doors - Steel Doors incl hw	2nd - 230 Gymnasium	2	EA	6	\$602	2 - sets of double doors, 1 single door at bleacher seating area
	Doors - Transom Window	2nd - 230 Gymnasium	43	SF	6	\$728	
	Doors - Wood Doors inclu hw	2nd - 230 Gymnasium	1	EA	6	\$301	1 - double door
	Floor - Wood	2nd - 230 Gymnasium	4,568	SF	6	\$32,204	
	Lighting - Pendent/Surface	2nd - 230 Gymnasium	18	EA	7	\$0	
	Sound System	2nd - 230 Gymnasium	1	EA	6	\$41,654	
	Storage/ Closet	2nd - 230 Gymnasium	309	SF	6	\$2,240	230A
	Walls - Structural Glazed Tile	2nd - 230 Gymnasium	7,506	SF	6	\$23,614	
Kitcher							
	Ceiling - Lay-in	1st Floor	2,589	SF	6	\$7,775	
	Doors - Transom Window	1st Floor	90	SF	6	\$1,524	
	Doors - Wood Doors inclu hw	1st Floor	10	EA	6	\$3,010	
	Floor - Terrazzo	1st Floor	2,589	SF	6	\$5,664	
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Kitchen							
	Lighting - Pendent/Surface	1st Floor	6	EA	7	\$0	
	Storage/ Closet	1st Floor	398	SF	6	\$2,886	
	Walls - Plaster/Drywall	1st Floor	1,218	SF	6	\$3,362	
	Walls - Structural Glazed Tile	1st Floor	3,900	SF	6	\$12,269	
	Ceiling - Lay-in	1st- Serving Rm 121	1,537	SF	6	\$4,616	
	Ceiling - Plaster/Drywall	1st- Serving Rm 121	210	SF	6	\$727	
	Doors - Transom Window	1st- Serving Rm 121	72	SF	6	\$1,219	
	Doors - Wood Doors inclu hw	1st- Serving Rm 121	8	EA	6	\$2,408	
	Floor - Terrazzo	1st- Serving Rm 121	1,747	SF	6	\$3,822	
	Lighting - Pendent/Surface	1st- Serving Rm 121	30	EA	7	\$0	
	Serving Line	1st- Serving Rm 121	160	LF	6	\$9,523	
	Walls - Plaster/Drywall	1st- Serving Rm 121	563	SF	6	\$1,554	
	Walls - Structural Glazed Tile	1st- Serving Rm 121	1,127	SF	6	\$3,546	
Library							
	Casework	203 E D	11	LF	6	\$278	
	Ceiling - Lay-in	203 E D	136	SF	6	\$408	
	Doors - Store Front	203 E D	6	EA	6	\$7,249	
	Doors - Wood Doors inclu hw	203 E D	1	EA	6	\$301	
	Floor - Tile	203 E D	136	SF	6	\$298	
	Lighting - Lay-in	203 E D	3	EA	7	\$0	
	Storage/ Closet	203 E D	61	SF	5	\$984	
	Walls - Plaster/Drywall	203 E D	684	SF	6	\$1,888	
	Casework	203	198	LF	6	\$5,000	
	Ceiling - Plaster/Drywall	203	1,841	SF	6	\$6,371	
	Doors - Transom Window	203	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	203	2	EA	6	\$602	
	Floor - Tile	203	1,841	SF	6	\$4,028	
	Lighting - Pendent/Surface	203	36	EA	7	\$0	
Locker/	Shower Room						
	Ceiling - Plaster/ Drywall	1st- 116 Vacant Rm (former shower room)	30	SF	5	\$392	peeling
	Ceiling - Plaster/ Drywall	1st- 116 Vacant Rm (former shower room)	311	SF	6	\$1,076	
	Doors - Transom Window	1st- 116 Vacant Rm (former shower room)	16	SF	5	\$677	broken glass panes
	Doors - Wood Doors inclu hw	1st- 116 Vacant Rm (former shower room)	2	EA	6	\$602	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
r/Shower Room						
Floor Drain	1st- 116 Vacant Rm (former shower room)	3	EA	6	\$3,177	
Floor - Tile Ceramic/ Porcelain	1st- 116 Vacant Rm (former shower room)	12	SF	5	\$251	cracked & damaged shower curb
Floor - Tile Ceramic/ Porcelain	1st- 116 Vacant Rm (former shower room)	329	SF	6	\$696	
Lighting - Pendent/Surface	1st- 116 Vacant Rm (former shower room)	3	EA	7	\$0	
Partitions	1st- 116 Vacant Rm (former shower room)	3	EA	6	\$891	
Showers	1st- 116 Vacant Rm (former shower room)	5	EA	5	\$13,572	not working
Student Lockers - One Tier	1st- 116 Vacant Rm (former shower room)	5	EA	6	\$464	
Walls - Plaster/Drywall	1st- 116 Vacant Rm (former shower room)	10	SF	5	\$51	peeling
Walls - Plaster/Drywall	1st- 116 Vacant Rm (former shower room)	170	SF	6	\$469	
Walls - Structural Glazed Tile	1st- 116 Vacant Rm (former shower room)	827	SF	6	\$2,602	
Accessories	1st Floor	73	SF	6	\$286	
Accessories	1st Floor	87	SF	6	\$341	
Benches, ped mounted	1st Floor	240	LF	6	\$26,131	
Benches, ped mounted	1st Floor	200	LF	6	\$21,776	
Ceiling - Plaster/ Drywall	1st Floor	30	SF	5	\$392	peeling
Ceiling - Plaster/ Drywall	1st Floor	7,287	SF	6	\$25,217	
Ceiling - Plaster/ Drywall	1st Floor	4,673	SF	6	\$16,171	
Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	stainless steel
Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
Doors - Transom Window	1st Floor	32	SF	6	\$542	solid panel
Doors - Transom Window	1st Floor	16	SF	6	\$271	
Floor Drain	1st Floor	4	EA	6	\$4,237	
Floor Drain	1st Floor	19	EA	6	\$20,124	
Floor - Terrazzo	1st Floor	1,580	SF	6	\$3,457	
Floor - Tile Ceramic/ Porcelain	1st Floor	4,683	SF	6	\$9,911	
Floor - Tile Ceramic/ Porcelain	1st Floor	20	SF	5		cracked
Floor - Tile Ceramic/ Porcelain	1st Floor	5,708	SF	6	\$12,080	
Hand Dryer	1st Floor	2	EA	6	\$460	
Lavatory	1st Floor	2	EA	6	\$639	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/	Shower Room						
	Lavatory	1st Floor	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Floor	134	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	90	EA	7	\$0	
	Partitions	1st Floor	3	EA	6	\$891	
	Partitions	1st Floor	5	EA	6	\$1,485	
	Partitions	1st Floor	1	EA	5	\$751	ADA stall door is missing
	Showers	1st Floor	11	EA	6	\$3,426	
	Showers	1st Floor	1	EA	5	\$2,714	Constantly running, needs to be shut off or fixed.
	Showers	1st Floor	14	EA	6	\$4,360	
	Student Lockers - One Tier	1st Floor	497	EA	6	\$46,139	
	Student Lockers - One Tier	1st Floor	682	EA	6	\$63,314	
	Urinals	1st Floor	4	EA	6	\$1,344	
	Walls - Plaster/Drywall	1st Floor	432	SF	6	\$1,192	
	Walls - Structural Glazed Tile	1st Floor	7,493	SF	6	\$23,573	
	Walls - Structural Glazed Tile	1st Floor	6,331	SF	6	\$19,917	
	Water Closet	1st Floor	2	EA	6	\$672	
	Water Closet	1st Floor	5	EA	6	\$1,680	
	Ceiling - Lay-In	2nd - 224 Locker Room	201	SF	6	\$604	
	Doors - Wood Doors inclu hw	2nd - 224 Locker Room	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd - 224 Locker Room	201	SF	6	\$201	
	Lighting - Lay-in	2nd - 224 Locker Room	3	EA	7	\$0	
	Student Lockers - One Tier	2nd - 224 Locker Room	13	EA	6	\$1,207	
	Walls - Plaster/Drywall	2nd - 224 Locker Room	489	SF	6	\$1,350	
	Walls - Tile Ceramic/ Porcelain	2nd - 224 Locker Room	117	SF	6	\$264	
	Ceiling - Lay-In	2nd - 226 ADA Locker Room	200	SF	6	\$601	
	Doors - Wood Doors inclu hw	2nd - 226 ADA Locker Room	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd - 226 ADA Locker Room	200	SF	6	\$200	
	Lighting - Lay-in	2nd - 226 ADA Locker Room	6	EA	6	\$714	
	Storage/ Closet	2nd - 226 ADA Locker Room	37	SF	6	\$268	
	Student Lockers - One Tier	2nd - 226 ADA Locker Room	18	EA	6	\$1,671	
	Walls - Plaster/Drywall	2nd - 226 ADA Locker Room	524	SF	6	\$1,446	
	Walls - Tile Ceramic/ Porcelain	2nd - 226 ADA Locker Room	109	SF	6	\$246	
Lunch {	& Multipurpose Room						
	Ceiling - Lay-in	1st - lunchroom inside clinic	71	SF	6	\$213	
	Doors - Wood Doors inclu hw	1st - lunchroom inside clinic	1	EA	6	\$301	
	Floor - Tile/Sheet	1st - lunchroom inside clinic	71	SF	6	\$71	
	Lighting - Lay-in	1st - lunchroom inside clinic	1	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch a	& Multipurpose Room						
	Walls - Plaster/Drywall	1st - lunchroom inside clinic	238	SF	6	\$657	
	Walls - Structural Glazed Tile	1st - lunchroom inside clinic	93	SF	6	\$293	
	AC Unit	1st- 107 Meeting Room	2	EA	6	\$991	
	Ceiling - Lay-in	1st- 107 Meeting Room	1,163	SF	6	\$3,492	
	Doors - Transom Window	1st- 107 Meeting Room	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	1st- 107 Meeting Room	2	EA	6	\$602	
	Floor - Tile	1st- 107 Meeting Room	1,163	SF	6	\$2,545	
	Lighting - Lay-in	1st- 107 Meeting Room	22	EA	7	\$0	
	Market Board	1st- 107 Meeting Room	12	LF	6	\$257	
	Storage/ Closet	1st- 107 Meeting Room	28	SF	6	\$203	
	Walls - Plaster/Drywall	1st- 107 Meeting Room	1,820	SF	6	\$5,023	
	Ceiling - Lay-in	1st- 108 Multi-Purpose Room	1,907	SF	6	\$5,727	
	Chalk Board	1st- 108 Multi-Purpose Room	16	LF	4	\$1,469	
	Doors - Transom Window	1st- 108 Multi-Purpose Room	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st- 108 Multi-Purpose Room	2	EA	6	\$602	
	Floor - Tile	1st- 108 Multi-Purpose Room	1,907	SF	6	\$4,172	
	Lighting - Lay-in	1st- 108 Multi-Purpose Room	31	EA	7	\$0	
	Market Board	1st- 108 Multi-Purpose Room	6	LF	7	\$0	
	Walls - Plaster/Drywall	1st- 108 Multi-Purpose Room	4,674	SF	6	\$12,900	
	Ceiling - Lay-in	1st Floor	6	SF	5	\$48	stained tiles
	Ceiling - Lay-in	1st Floor	6,019	SF	6	\$18,075	
	Ceiling - Plaster/Drywall	1st Floor	12	SF	5	\$110	peeling
	Ceiling - Splined	1st Floor	3,392	SF	6	\$2,765	
	Doors - Transom Window	1st Floor	128	SF	6	\$2,167	
	Doors - Wood Doors inclu hw	1st Floor	16	EA	6	\$4,816	
	Floor - Terrazzo	1st Floor	10,079	SF	6	\$22,052	
	Lighting - Lay-in	1st Floor	96	EA	7	\$0	
	Serving Line	1st Floor	19	LF	6	\$1,131	
	Walls - Plaster/Drywall	1st Floor	3,027	SF	6	\$8,354	
	Walls - Structural Glazed Tile	1st Floor	3,027	SF	6	\$9,523	
MDF_ID	DF						
	Doors - Wood Doors inclu hw	1st - MDF Closet across from Classroom 135	1	EA	6	\$301	double door
	Finishes	1st - MDF Closet across from Classroom 135	105	SF	6	\$749	14 sq.ft. terrazzo floor, 91 sq.ft. drywall walls / ceiling
	AC Unit	2nd - 249 MDF Room	2	EA	6	\$991	
	Doors - Steel Doors incl hw	2nd - 249 MDF Room	1	EA	6	\$301	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
MDF_I	)F						
	Finishes	2nd - 249 MDF Room	886	SF	6	\$6,322	616 sq.ft. plaster / 270 sq.ft. cmu
	Ventilation and Cooling	2nd - 249 MDF Room	3	EA	6	\$5,565	2 a/c units and a fan / cool in room
Mechar	nical/ Service Rooms						
	Janitor's Closet	1st Floor	159	SF	6	\$1,139	
	Janitor's Closet	1st Floor	262	SF	5	\$4,226	128C- door only opens 1/2 way, walls cracked & peeling
	Storage Room	1st Floor	161	SF	6	\$1,153	inside unisex corridor
	Storage Room	1st Floor	211	SF	6	\$1,512	across from clinic 133 - areas of walls cracked / peeling
	Storage Room	1st Floor	591	SF	6	\$4,234	155A Janitor Storage
	Storage Room	1st Floor	502	SF	6	\$3,596	110
	Storage Room	1st Floor	105	SF	6	\$752	127 (door sign says Rec Room)
	Storage Room	1st Floor	482	SF	5	\$7,775	130B- 1/3 of floor tile missing & some Structural Glazed Tile is defaced.
	Vaults	1st Floor	131	SF	6	\$939	Inside Rm 112- Principal Suite
	Vaults	1st Floor	231	SF	6	\$1,655	ROTC Vault inside of Rm 108
	Janitor's Closet	2nd Floor	34	SF	5	\$548	Location: 201C peeling paint
	Janitor's Closet	2nd Floor	342	SF	6	\$2,450	
	Storage Room	2nd Floor	1,529	SF	6	\$10,954	
	Janitor's Closet	3rd Floor	442	SF	6	\$3,167	
	Janitor's Closet	3rd Floor	40	SF	5	\$645	Location: Near Room 303 Water damage at wall.
	Mechanical/ Service Rooms	3rd Floor	100	SF	5	\$1,613	No fire stop at pipe chase
	Storage Room	3rd Floor	501	SF	6	\$3,589	
	Janitor's Closet	4th Floor	150	SF	5	\$2,420	Near room 402 No fire stop at conduit
	Air Intake Plenums	Basement	504	SF	6	\$3,121	
	Air Tunnel	Basement	9,036	SF	6	\$55,950	Pipe leak Air Tunnel #4
	Auditorium Plenums	Basement	12,064	SF	6	\$74,699	
	Boiler Room	Basement	3,264	SF	6	\$23,384	
	Coal Room	Basement	1,395	SF	6	\$9,994	
	Crawl Space - Unfinished	Basement	7,908	SF	6	\$48,966	
	Interior Stairs	Basement	34	LF	6	\$307	
	Mechanical/ Service Rooms	Basement	18,820	SF	6	\$134,832	
	Mechanical/ Service Rooms	Basement	2,000	SF	5	\$32,261	Water seepage. Pool filtration, NW Wall, Rifle Range, S-9, S-4, Fan #9
	Storage Room	Basement	2,652	SF	6	\$19,000	
	Vaults	Basement	510	SF	6	\$3,654	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
latatorium						
Bleachers Seating/Plank Seating	1st Floor	42	EA	6	\$1,216	
Ceiling - Plaster/ Drywall	1st Floor	5,459	SF	6	\$30,133	
Doors - Steel Doors incl hw	1st Floor	18	EA	6	\$5,418	stainless steel
Doors - Transom Window	1st Floor	64	SF	6	\$1,084	stainless steel
Floor - Concrete	1st Floor	1,186	SF	6	\$628	
Floor - Tile Ceramic/ Porcelain	1st Floor	4,273	SF	6	\$9,043	
Lighting - Pendent/Surface	1st Floor	26	EA	7	\$0	
Pool Basin	1st Floor	1,571	SF	6	\$53,153	
Pool Deck	1st Floor	2,702	SF	6	\$25,656	
Pool Deck Drains	1st Floor	7	EA	6	\$2,954	
Walls - Structural Glazed Tile	1st Floor	2,305	SF	6	\$7,252	
om						
Ceiling - Plaster/Drywall	1st- Dishwashing Rm 121B	444	SF	6	\$1,537	
Doors - Transom Window	1st- Dishwashing Rm 121B	18	SF	6	\$305	
Doors - Wood Doors inclu hw	1st- Dishwashing Rm 121B	2	EA	6	\$602	
Floor - Terrazzo	1st- Dishwashing Rm 121B	444	SF	6	\$971	
Lighting - Pendent/Surface	1st- Dishwashing Rm 121B	4	EA	7	\$0	
Walls - Structural Glazed Tile	1st- Dishwashing Rm 121B	1,124	SF	6	\$3,536	
Casework	1st- Inside 107	6	LF	6	\$152	
Ceiling - Plaster/Drywall	1st- Inside 107	110	SF	6	\$381	
Doors - Wood Doors inclu hw	1st- Inside 107	1	EA	6	\$301	
Floor - Tile	1st- Inside 107	110	SF	6	\$241	
Lighting - Pendent/Surface	1st- Inside 107	2	EA	7	\$0	
Walls - Plaster/Drywall	1st- Inside 107	10	SF	5	\$51	cracked
Walls - Plaster/Drywall	1st- Inside 107	530	SF	6	\$1,463	
Work Sink	1st- Inside 107	1	EA	6	\$379	
Casework	213	25	LF	6	\$631	
Ceiling - Lay-in	213	456	SF	6	\$1,369	
Doors - Steel Doors incl hw	213	2	EA	6	\$602	
Doors - Transom Window	213	40	SF	6	\$677	
Doors - Wood Doors inclu hw	213	1	EA	6	\$301	
Floor - Tile/Sheet	213	456	SF	6	\$456	
Lighting - Lay-in	213	14	EA	7	\$0	
Walls - Plaster/Drywall	213	8	SF	5	\$61	Water damage at exterior wall
Work Sink	213	1	EA	6	\$379	
Casework	2nd - 217 Dark Room used as storage	11	LF	6	\$278	
Ceiling - Plaster/Drywall	2nd - 217 Dark Room used as storage	198	SF	6	\$685	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Prep Ro	oom						
	Doors - Wood Doors inclu hw	2nd - 217 Dark Room used as storage	1	EA	6	\$301	
	Floor - Concrete	2nd - 217 Dark Room used as storage	198	SF	6	\$105	
	Lighting - Pendent/Surface	2nd - 217 Dark Room used as storage	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd - 217 Dark Room used as storage	3	SF	5	\$15	hole in wall
	Walls - Plaster/Drywall	2nd - 217 Dark Room used as storage	759	SF	6	\$2,095	
	Work Sink	2nd - 217 Dark Room used as storage	2	EA	6	\$758	
	Casework	2nd - 239A Prep Room inside classroom 239	12	LF	6	\$303	
	Ceiling - Lay-in	2nd - 239A Prep Room inside classroom 239	225	SF	6	\$676	
	Doors - Wood Doors inclu hw	2nd - 239A Prep Room inside classroom 239	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd - 239A Prep Room inside classroom 239	225	SF	6	\$225	
	Lighting - Lay-in	2nd - 239A Prep Room inside classroom 239	3	EA	7	\$0	1 lay-in light missing cover
	Walls - Plaster/Drywall	2nd - 239A Prep Room inside classroom 239	552	SF	6	\$1,523	
	Work Sink	2nd - 239A Prep Room inside classroom 239	1	EA	6	\$379	sink in base cabinet
	Ceiling - Plaster/Drywall	2nd- Dressing room for auditorium	296	SF	5	\$2,713	peeling
	Doors - Wood Doors inclu hw	2nd- Dressing room for auditorium	1	EA	6	\$301	
	Floor - Wood	2nd- Dressing room for auditorium	296	SF	6	\$2,087	
	Lighting - Pendent/Surface	2nd- Dressing room for auditorium	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd- Dressing room for auditorium	908	SF	6	\$2,506	
	Work Sink	2nd- Dressing room for auditorium	1	EA	6	\$379	
	Ceiling - Plaster/Drywall	2nd- Makeup/Dressing room for auditorium	83	SF	6	\$287	
	Doors - Wood Doors inclu hw	2nd- Makeup/Dressing room for auditorium	1	EA	6	\$301	
	Floor - Wood	2nd- Makeup/Dressing room for auditorium	83	SF	6	\$585	
	Lighting - Pendent/Surface	2nd- Makeup/Dressing room for auditorium	1	EA	7	\$0	
	Lighting - Wall Mounted	2nd- Makeup/Dressing room for auditorium	6	EA	7	\$0	
	Walls - Plaster/Drywall	2nd- Makeup/Dressing room for auditorium	547	SF	6	\$1,510	
	Work Sink	2nd- Makeup/Dressing room for auditorium	1	EA	6	\$379	Cold water lever missing
	Casework	313A	26	LF	6	\$657	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

р	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Ro	bom						
	Ceiling - Lay-in	313A	360	SF	6	\$1,081	
	Doors - Wood Doors inclu hw	313A	2	EA	6	\$602	
	Floor - Tile/Sheet	313A	360	SF	6	\$360	
	Lighting - Lay-in	313A	12	EA	7	\$0	
	Walls - Plaster/Drywall	313A	912	SF	6	\$2,517	
	Work Sink	313A	1	EA	5	\$1,508	
	Ceiling - Plaster/Drywall	3rd- Dressing room for auditorium	296	SF	6	\$1,024	
	Doors - Wood Doors inclu hw	3rd- Dressing room for auditorium	1	EA	6	\$301	
	Floor - Wood	3rd- Dressing room for auditorium	296	SF	6	\$2,087	
	Lighting - Pendent/Surface	3rd- Dressing room for auditorium	1	EA	7	\$0	
	Walls - Plaster/Drywall	3rd- Dressing room for auditorium	908	SF	6	\$2,506	
	Work Sink	3rd- Dressing room for auditorium	1	EA	6	\$379	
	Casework	415	45	LF	6	\$1,136	
	Ceiling - Lay-in	415	250	SF	6	\$751	
	Doors - Transom Window	415	24	SF	6	\$406	
	Doors - Wood Doors inclu hw	415	2	EA	6	\$602	
	Floor - Tile/Sheet	415	250	SF	6	\$250	
	Lighting - Lay-in	415	10	EA	7	\$0	
	Walls - Plaster/Drywall	415	751	SF	6	\$2,073	
00							
00	Accessories	1ma	244	SF	6	\$2,251	
		1ma 1ma	244 244	SF	6	م 844\$	
	Ceiling - Plaster/Drywall Floor Drain	1ma 1ma	244	EA	6	<del>۵</del> 044 \$1,059	
	Floor - Sport Flooring	1ma 1ma	244	SF	6	\$1,059 \$527	
			244	EA		\$527 \$230	
	Hand Dryer	1ma 1ma	2	EA	6 6	\$230 \$639	
	Lavatory Lighting - Pendent/Surface		2	EA	6 7	\$639 \$0	
	Partitions	1ma	5	EA	6	\$0 \$594	
	Urinals	1ma 1ma	2	EA	6	\$594 \$672	
	Walls - Plaster/Drywall		2 255	SF	6	\$072 \$704	
	Walls - Tile Ceramic/ Porcelain	1ma		SF			
	Waiis - The Ceramic/ Porcelain Water Closet	1ma	480	SF EA	6	\$1,085 \$672	
		1ma 1SM	2	EA SF	6		
	Accessories		168		6	\$1,550	
	Ceiling - Lay-in	1SM	168	SF	6	\$505	
	Doors - Wood Doors inclu hw	1SM	2	EA	6	\$602	
	Floor Drain	1SM	1	EA	6	\$1,059	
	Floor - Terrazzo	1SM	80	SF	6	\$175	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

RestroomFloor - Tile1SM88SF6\$193Lavatory1SM1EA6\$320Lighting - Lay-in1SM4EA7\$0Partitions1SM1EA6\$297Urinals1SM2EA6\$672Walls - Plaster/Drywall1SM422SF6\$1,165Walls - Tile Ceramic/ Porcelain1SM321SF6\$725Water Closet1SM1EA6\$336	
Lavatory1SM1EA6\$320Lighting - Lay-in1SM4EA7\$0Partitions1SM1EA6\$297Urinals1SM2EA6\$672Walls - Plaster/Drywall1SM422SF6\$1,165Walls - Tile Ceramic/ Porcelain1SM321SF6\$725	
Lighting - Lay-in1SM4EA7\$0Partitions1SM1EA6\$297Urinals1SM2EA6\$672Walls - Plaster/Drywall1SM422SF6\$1,165Walls - Tile Ceramic/ Porcelain1SM321SF6\$725	
Partitions1SM1 EA6\$297Urinals1SM2EA6\$672Walls - Plaster/Drywall1SM422SF6\$1,165Walls - Tile Ceramic/ Porcelain1SM321SF6\$725	
Urinals 1SM 2 EA 6 \$672   Walls - Plaster/Drywall 1SM 422 SF 6 \$1,165   Walls - Tile Ceramic/ Porcelain 1SM 321 SF 6 \$725	
Walls - Plaster/Drywall 1SM 422 SF 6 \$1,165   Walls - Tile Ceramic/ Porcelain 1SM 321 SF 6 \$725	
Walls - Tile Ceramic/ Porcelain1SM321SF6\$725	
Water Closet 1SM 1 EA 6 \$226	
Accessories 1st - Boy's Bath 367 SF 6 \$3,385	
Ceiling - Plaster/Drywall 1st - Boy's Bath 367 SF 6 \$1,270	
Floor Drain   1st - Boy's Bath   2   EA   6   \$2,118	
Floor - Terrazzo 1st - Boy's Bath 367 SF 6 \$803	
Hand Dryer 1st - Boy's Bath 1 EA 6 \$230	
Lavatory 1st - Boy's Bath 3 EA 6 \$959	
Lighting - Pendent/Surface 1st - Boy's Bath 7 EA 7 \$0	
Partitions 1st - Boy's Bath 2 EA 6 \$594	
Urinals 1st - Boy's Bath 5 EA 6 \$1,680	
Walls - Plaster/Drywall1st - Boy's Bath329SF6\$908	
Walls - Structural Glazed Tile1st - Boy's Bath820SF6\$2,580	
Water Closet 1st - Boy's Bath 4 EA 6 \$1,344	
Accessories 1st - Girl's Bath 371 SF 6 \$3,422	
Ceiling - Plaster/Drywall 1st - Girl's Bath 371 SF 6 \$1,284	
Floor Drain 1st - Girl's Bath 1 EA 6 \$1,059	
Floor - Terrazzo 1st - Girl's Bath 371 SF 6 \$812	
Hand Dryer 1st - Girl's Bath 1 EA 6 \$230	
Lavatory 1st - Girl's Bath 3 EA 6 \$959	
Lighting - Pendent/Surface 1st - Girl's Bath 9 EA 7 \$0	
Partitions 1st - Girl's Bath 6 EA 6 \$1,782	
Walls - Plaster/Drywall1st - Girl's Bath244SF6\$673	
Walls - Structural Glazed Tile1st - Girl's Bath670SF6\$2,108	
Water Closet   1st - Girl's Bath   7   EA   6   \$2,352	
Accessories 1st - inside 133 clinic 70 SF 6 \$646	
Ceiling - Lay-in 1st - inside 133 clinic 4 SF 5 \$32 stained / cracked	
Ceiling - Lay-in 1st - inside 133 clinic 66 SF 6 \$198	
Doors - Wood Doors inclu hw 1st - inside 133 clinic 1 EA 6 \$301	
Floor Drain 1 EA 5 \$2,094 hole in floor cause cap not	t installed properly
Floor - Tile Ceramic/ Porcelain1st - inside 133 clinic70SF6\$148metal threshold not flush to	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroo	om						
	Lavatory	1st - inside 133 clinic	1	EA	6	\$320	
	Lighting - Lay-in	1st - inside 133 clinic	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st - inside 133 clinic	70	SF	6	\$193	
	Walls - Structural Glazed Tile	1st - inside 133 clinic	82	SF	6	\$258	
	Walls - Tile Ceramic/ Porcelain	1st - inside 133 clinic	153	SF	6	\$346	
	Water Closet	1st - inside 133 clinic	1	EA	6	\$336	
	Accessories	1st - Staff bath in hallway next to 134C	31	SF	6	\$286	
	Ceiling - Plaster/Drywall	1st - Staff bath in hallway next to 134C	31	SF	6	\$107	
	Doors - Wood Doors inclu hw	1st - Staff bath in hallway next to 134C	1	EA	6	\$301	
	Floor - Tile	1st - Staff bath in hallway next to 134C	31	SF	6	\$68	
	Lavatory	1st - Staff bath in hallway next to 134C	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st - Staff bath in hallway next to 134C	1	EA	6	\$124	old incandescent with no cover
	Walls - Plaster/Drywall	1st - Staff bath in hallway next to 134C	181	SF	6	\$500	
	Water Closet	1st - Staff bath in hallway next to 134C	1	EA	6	\$336	
	Accessories	1st - Unisex Bath	57	SF	6	\$526	
	Ceiling - Plaster/Drywall	1st - Unisex Bath	57	SF	6	\$197	
	Doors - Wood Doors inclu hw	1st - Unisex Bath	1	EA	6	\$301	
	Floor Drain	1st - Unisex Bath	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st - Unisex Bath	57	SF	6	\$121	
	Hand Dryer	1st - Unisex Bath	1	EA	6	\$230	
	Lavatory	1st - Unisex Bath	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st - Unisex Bath	1	EA	7	\$0	
	Walls - Plaster/Drywall	1st - Unisex Bath	39	SF	6	\$108	
	Walls - Structural Glazed Tile	1st - Unisex Bath	243	SF	6	\$764	
	Water Closet	1st - Unisex Bath	1	EA	6	\$336	
	Accessories	1st- 108C Men's Staff RR	201	SF	6	\$1,854	
	Ceiling - Lay-in	1st- 108C Men's Staff RR	201	SF	6	\$604	
	Doors - Wood Doors inclu hw	1st- 108C Men's Staff RR	2	EA	6	\$602	
	Floor Drain	1st- 108C Men's Staff RR	1	EA	6	\$1,059	
	Floor - Terrazzo	1st- 108C Men's Staff RR	82	SF	6	\$179	
	Floor - Tile	1st- 108C Men's Staff RR	119	SF	6	\$260	
	Hand Dryer	1st- 108C Men's Staff RR	1	EA	6	\$230	
	Lavatory	1st- 108C Men's Staff RR	1	EA	6	\$320	
	Lighting - Lay-in	1st- 108C Men's Staff RR	2	EA	7	\$0	
	Partitions	1st- 108C Men's Staff RR	1	EA	6	\$297	
	Urinals	1st- 108C Men's Staff RR	2	EA	6	\$672	
	Walls - Plaster/Drywall	1st- 108C Men's Staff RR	411	SF	6	\$1,134	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroo	om						
	Walls - Structural Glazed Tile	1st- 108C Men's Staff RR	333	SF	6	\$1,048	
	Water Closet	1st- 108C Men's Staff RR	1	EA	6	\$336	
	Accessories	1st- 108D Boy's RR	224	SF	6	\$2,066	
	Ceiling - Plaster/Drywall	1st- 108D Boy's RR	224	SF	6	\$775	
	Floor Drain	1st- 108D Boy's RR	1	EA	6	\$1,059	
	Floor - Terrazzo	1st- 108D Boy's RR	224	SF	6	\$490	
	Hand Dryer	1st- 108D Boy's RR	1	EA	6	\$230	
	Lavatory	1st- 108D Boy's RR	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st- 108D Boy's RR	4	EA	7	\$0	
	Partitions	1st- 108D Boy's RR	1	EA	6	\$297	
	Urinals	1st- 108D Boy's RR	4	EA	6	\$1,344	
	Walls - Plaster/Drywall	1st- 108D Boy's RR	414	SF	6	\$1,143	
	Walls - Structural Glazed Tile	1st- 108D Boy's RR	234	SF	6	\$736	
	Water Closet	1st- 108D Boy's RR	1	EA	6	\$336	
	Accessories	1st Floor	133	SF	6	\$1,227	
	Accessories	1st Floor	212	SF	6	\$1,955	
	Accessories	1st Floor	236	SF	6	\$2,177	
	Ceiling - Lay-in	1st Floor	133	SF	6	\$399	
	Ceiling - Lay-in	1st Floor	212	SF	6	\$637	
	Ceiling - Plaster/Drywall	1st Floor	226	SF	6	\$782	
	Ceiling - Plaster/Drywall	1st Floor	10	SF	4	\$218	Damaged
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor - Sport Flooring	1st Floor	236	SF	6	\$510	
	Floor - Terrazzo	1st Floor	138	SF	6	\$302	
	Floor - Terrazzo	1st Floor	133	SF	6	\$291	
	Floor - Tile	1st Floor	107	SF	6	\$234	
	Floor - Tile	1st Floor	74	SF	6	\$162	
	Hand Dryer	1st Floor	1	EA	6	\$230	
	Hand Dryer	1st Floor	1	EA	6	\$230	
	Lavatory	1st Floor	1	EA	6	\$320	
	Lavatory	1st Floor	2	EA	6	\$639	
	Lavatory	1st Floor	2	EA	6	\$639	
	Lighting - Lay-in	1st Floor	5	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

m   state   state <thtate< th="">   state   state</thtate<>	Type Location	Quantity	ity offic	italik	COSI	Comments
Lighting - Pendent/Surface 1st Floor 5 EA 7 \$0   Partitions 1st Floor 3 EA 6 \$891   Partitions 1st Floor 3 EA 6 \$891   Partitions 1st Floor 3 EA 6 \$891   Valls - Plaster/Drywall 1st Floor 3 EA 6 \$802   Walls - Plaster/Drywall 1st Floor 16 S 6 \$820   Walls - Plaster/Drywall 1st Floor 16 S 6 \$820   Walls - Tile Ceramic/ Porcelain 1st Floor 37 EA 6 \$1,223   Walls - Tile Ceramic/ Porcelain 1st Floor 3 EA 6 \$1,028   Water Closet 1st Floor 3 EA 6 \$1,028   Water Closet 1st Floor 3 EA 6 \$1,028   Vater Closet 1st Inside 125 Asst Eng Office 28 SF 6 \$2,029   Loward Marce 1st Inside 125 Asst Eng Office 1 EA 6 \$3,0108   Lighting						
Partitions   1st Floor   3   EA   6   \$891     Partitions   1st Floor   3   EA   6   \$891     Valls - Plaster/Drywall   1st Floor   3   EA   6   \$890     Walls - Plaster/Drywall   1st Floor   293   SF   6   \$800     Walls - Plaster/Drywall   1st Floor   293   SF   6   \$8120     Walls - Plaster/Drywall   1st Floor   297   SF   6   \$820     Walls - Tile Ceramic/ Porcelain   1st Floor   33   SF   6   \$8100     Waler Closet   1st Floor   3   EA   6   \$1000     Water Closet   1st Floor   3   EA   6   \$1000     Water Closet   1st Floor   3   EA   6   \$200     Ceiting - Plaster/Drywall   1st Hoide 125 Asst Eng Office   28   SF   6   \$200     Ceiting - Plaster/Drywall   1st Hoide 125 Asst Eng Office   1   EA   6   \$301     Elow - Tile Ce	g - Lay-in 1st Floor	5	5 EA	6	\$595	
Partitions 1st Floor 3 EA 6 \$891   Partitions 1st Floor 3 EA 6 \$891   Walls - Plaster/Drywall 1st Floor 293 SF 6 \$820   Walls - Plaster/Drywall 1st Floor 465 SF 6 \$820   Walls - Plaster/Drywall 1st Floor 267 SF 6 \$820   Walls - Plaster/Drywall 1st Floor 36 SF 6 \$820   Walls - Tile Ceramic/ Porcelain 1st Floor 35 K 6 \$1,222   Water Closet 1st Floor 3 EA 6 \$1,008   Vater Closet 1st Floor 3 EA 6 \$1,008   Ceiling - Plaster/Drywall 1st Inside 125 Asst Eng Offrice 28 F 6 \$320   Layatory 1st In	g - Pendent/Surface 1st Floor	5	5 EA	7	\$0	
Partitions 1st Floor 3 EA 6 \$891   Walls - Plaster/Dywall 1st Floor 293 SF 6 \$8009   Walls - Plaster/Dywall 1st Floor 116 SF 6 \$523   Walls - Plaster/Dywall 1st Floor 66 \$512 \$523   Walls - Plaster/Dyrophil 1st Floor 36 SF 6 \$5100   Walls - Tile Ceramic/ Porcelain 1st Floor 36 SF 6 \$51,008   Water Closet 1st Floor 3 EA 6 \$51,008   Water Closet 1st Floor 3 EA 6 \$51,008   Accessories 1st Floor 3 EA 6 \$51,008   Accessories 1st Inside 125 Asst Eng Office 28 F 6 \$253   Colign - Plaster/Dryvall 1st Inside 125 Asst Eng Office 18 F 6 \$320   Lighting - Pendent/Surface 1st Inside 125 Asst Eng Office 1 EA 6 \$333   Lighting - Plaster/Dryvall 1st Inside 125 Asst Eng Office 1 EA 7	ns 1st Floor	3	3 EA	6	\$891	
Walls - Plaster/Drywall 1st Floor 116 SF 6 \$320   Walls - Plaster/Drywall 1st Floor 166 SF 6 \$320   Walls - Plaster/Drywall 1st Floor 297 SF 6 \$650   Walls - Tile Ceramic/ Porcelain 1st Floor 363 SF 6 \$8120   Walts - Tile Ceramic/ Porcelain 1st Floor 36 SF 6 \$8120   Water Closet 1st Floor 3 EA 6 \$1,008   Water Closet 1st Floor 3 EA 6 \$1,008   Accessories 1st Inside 125 Asst Eng Office 28 SF 6 \$258   Ceiling - Plaster/Drywall 1st Inside 125 Asst Eng Office 1 EA 7 \$50   Lavatory 1st Inside 125 Asst Eng Office 1 EA 7 \$50   Lavatory 1st- Inside 125 Asst Eng Office 1 EA 7 \$50   Lavatory 1st- Inside 125 Asst Eng Office 1 EA 7 \$50   Valer Closet 1st- Inside 125 Asst Eng Office 1 EA <td>ns 1st Floor</td> <td>3</td> <td>3 EA</td> <td>6</td> <td>\$891</td> <td></td>	ns 1st Floor	3	3 EA	6	\$891	
Walls - Plaster/Drywall 1st Floor 116 SF 6 \$320   Walls - Plaster/Drywall 1st Floor 267 SF 6 \$1,283   Walls - Tile Caramic/ Porcelain 1st Floor 267 SF 6 \$820   Walls - Tile Caramic/ Porcelain 1st Floor 363 SF 6 \$820   Walls - Tile Caramic/ Porcelain 1st Floor 3 EA 6 \$1,022   Water Closet 1st Floor 3 EA 6 \$1,008   Water Closet 1st Floor 3 EA 6 \$1,008   Water Closet 1st Inside 125 Asst Eng Office 28 SF 6 \$258   Ceiling - Plaster/Drywall 1st Inside 125 Asst Eng Office 28 SF 6 \$320   Lavatory 1st Inside 125 Asst Eng Office 1 EA 6 \$320   Lighting - Pendent/Surface 1st Inside 125 Asst Eng Office 1 EA 7 \$00   Walls - Relater/Drywall 1st Inside 125 Asst Eng Office 1 EA 6 \$320   Lighting - Pendent/Surface 1st Inside	ns 1st Floor	3	3 EA	6	\$891	
Walls - Plaster/Dywall   1st Floor   465   SF   6   \$1,283     Walls - Tile   1st Floor   297   SF   6   \$650     Walls - Tile Ceramic/ Porcelain   1st Floor   36   SF   6   \$1,223     Walls - Tile Ceramic/ Porcelain   1st Floor   3   EA   6   \$1,028     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Accessories   1st Inside 125 Asst Eng Offrice   28   SF   6   \$301     Coors - Wood Doors inclu hw   1st Inside 125 Asst Eng Offrice   1   EA   6   \$301     Floor - Tile Ceramic/ Porcelain   1st Inside 125 Asst Eng Offrice   1   EA   6   \$301     Lighting - Pendent/Surface   1st Inside 125 Asst Eng Offrice   1   EA   7   \$0     Walls - Plaster/Drywall   1st Inside 125 Asst Eng Offrice   1   EA   7   \$0     Walls - Plaster/Drywall   1st Inside 125 Asst Eng Offrice	Plaster/Drywall 1st Floor	293	93 SF	6	\$809	
Walls - Tile   1st Floor   297   SF   6   \$650     Walls - Tile Ceramic/ Porcelain   1st Floor   363   SF   6   \$820     Walls - Tile Ceramic/ Porcelain   1st Floor   363   SF   6   \$820     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Inside 125 Asst Eng Office   28   SF   6   \$258     Ceiling - Plaster/Drywall   1st Inside 125 Asst Eng Office   1   EA   \$6   \$301     Floor - Tile Ceramic/ Porcelain   1st Inside 125 Asst Eng Office   1   EA   \$6   \$320     Lighting - Pendent/Surface   1st Inside 125 Asst Eng Office   1   EA   \$6   \$320     Walls - Plaster/Drywall   1st Inside 125 Asst Eng Office   1   EA   \$6   \$330     Valls - Plaster/Drywall   1st Inside 125 Asst Eng Office   1	Plaster/Drywall 1st Floor	116	16 SF	6	\$320	
Walls - Tile Ceramic/ Porcelain   1st Floor   363   SF   6   \$820     Walls - Tile Ceramic/ Porcelain   1st Floor   541   SF   6   \$1,222     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Accessories   1st Inside 125 Asst Eng Office   28   SF   6   \$301     Colling - Plaster/Drywall   1st Inside 125 Asst Eng Office   1   EA   6   \$301     Floor - Tile Ceramic/ Porcelain   1st Inside 125 Asst Eng Office   1   EA   6   \$301     Lighting - Pendent/Surface   1st Inside 125 Asst Eng Office   1   EA   6   \$330     Lighting - Pendent/Surface   1st- Inside 125 Asst Eng Office   1   EA   6   \$330     Valls - Plaster/Drywall   1st- Inside 125 Asst Eng Office   1   EA   6   \$333     Valls - Plaster/Drywall   1st- Inside Pool	Plaster/Drywall 1st Floor	465	65 SF	6	\$1,283	
Walls - Tile Ceramic/ Porcelain1st Floor541SF6\$1,222Water Closet1st Floor3EA6\$1,008Water Closet1st Floor3EA6\$1,008Water Closet1st Floor3EA6\$1,008Water Closet1st Floor28SF6\$258Ceiling - Plaster/Drywall1st Inside 125 Asst Eng Office28SF6\$301Doors - Wood Doors inclu hw1st-Inside 125 Asst Eng Office28SF6\$301Floor - Tile Ceramic/ Porcelain1st-Inside 125 Asst Eng Office28SF6\$59Lavatory1st-Inside 125 Asst Eng Office28SF6\$59Lighting - Pendent/Surface1st-Inside 125 Asst Eng Office1EA7\$0Lighting - Pendent/Surface1st-Inside 125 Asst Eng Office1EA7\$0Walls - Plaster/Drywall1st-Inside 125 Asst Eng Office1EA5\$30water damageWalls - Plaster/Drywall1st-Inside 125 Asst Eng Office1EA5\$30water damageWalls - Plaster/Drywall1st-Inside 125 Asst Eng Office1EA6\$3304Ceiling - Plaster/Drywall1st-Inside Pool Rm137SF6\$1,264Coors - Steel Doors incl hw1st-Inside Pool Rm137SF6\$133stainless steelFloor - Tile Ceramic/ Porcelain1st-Inside Pool Rm1EA6\$130stainless	Tile 1st Floor	297	97 SF	6	\$650	
Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Accessories   1st-Inside 125 Asst Eng Office   28   SF   6   \$301     Celing - Plaster/Dywall   1st-Inside 125 Asst Eng Office   1   EA   6   \$301     Floor - Tile Ceramic/ Porcelain   1st-Inside 125 Asst Eng Office   1   EA   6   \$320     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   6   \$330     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   6   \$330     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   6   \$316     Accessories   1st-Inside Pool Rm   137	Tile Ceramic/ Porcelain 1st Floor	363	863 SF	6	\$820	
Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Accessories   1st-Inside 125 Asst Eng Office   28   SF   6   \$258     Ceiling - Plaster/Drywall   1st-Inside 125 Asst Eng Office   28   SF   6   \$301     Doors - Wood Doors inclu hw   1st-Inside 125 Asst Eng Office   28   SF   6   \$301     Floor - Tile Ceramic / Porcelain   1st-Inside 125 Asst Eng Office   18   EA   6   \$300     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside Pool Rm   137   SF   6   \$1,264     Ceiling - Plaster/Drywall   1st-	Tile Ceramic/ Porcelain 1st Floor	541	541 SF	6	\$1,222	
Water Closet   1st Floor   3   EA   6   \$1,008     Water Closet   1st Floor   3   EA   6   \$1,008     Accessories   1st-Inside 125 Asst Eng Office   28   SF   6   \$258     Celling - Plaster/Drywall   1st-Inside 125 Asst Eng Office   28   SF   6   \$301     Doors - Wood Doors inclu hw   1st-Inside 125 Asst Eng Office   28   SF   6   \$3301     Floor - Tile Ceramic/ Porcelain   1st-Inside 125 Asst Eng Office   18   EA   6   \$3301     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   6   \$3302     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside Pool Rm   137   SF   6   \$1301   \$151     Vater Closet	Closet 1st Floor	3	3 EA	6	\$1,008	
Water Closet   1st Floor   3   EA   6   \$1,008     Accessories   1st-Inside 125 Asst Eng Office   28   SF   6   \$258     Ceiling - Plaster/Drywall   1st-Inside 125 Asst Eng Office   28   SF   6   \$2301     Doors - Wood Doors inclu hw   1st-Inside 125 Asst Eng Office   1   EA   6   \$3301     Floor - Tile Ceramic/ Porcelain   1st-Inside 125 Asst Eng Office   1   EA   6   \$3201     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Lighting - Pendent/Surface   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Uighting - Wall Mounted   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   7   \$00     Water Closet   1st-Inside 125 Asst Eng Office   1   EA   6   \$130     Accessories   1st-Inside Pool Rm   137   SF   6   \$1426     Ceiling - Plaster/D	Closet 1st Floor	3	3 EA	6		
Accessories 1st- Inside 125 Asst Eng Office 28 SF 6 \$258   Ceiling - Plaster/Drywall 1st- Inside 125 Asst Eng Office 28 SF 6 \$977   Doors - Wood Doors inclu hw 1st- Inside 125 Asst Eng Office 1 EA 6 \$301   Floor - Tile Ceramic/ Porcelain 1st- Inside 125 Asst Eng Office 28 SF 6 \$320   Lavatory 1st- Inside 125 Asst Eng Office 1 EA 6 \$320   Lighting - Pendent/Surface 1st- Inside 125 Asst Eng Office 1 EA 7 \$00   Lighting - Wall Mounted 1st- Inside 125 Asst Eng Office 1 EA 7 \$00   Walls - Plaster/Drywall 1st- Inside 125 Asst Eng Office 1 EA 7 \$00   Walls - Plaster/Drywall 1st- Inside 125 Asst Eng Office 1 EA 6 \$330 water damage   Walls - Plaster/Drywall 1st- Inside Pool Rm 137 SF 6 \$133   Accessories 1st- Inside Pool Rm 137 SF 6 \$135   Doors - Transom Window 1st- Inside Pool Rm 1	Closet 1st Floor	3	3 EA	6		
Ceiling - Plaster/Drywall1st- Inside 125 Asst Eng Office28SF6\$97Doors - Wood Doors inclu hw1st- Inside 125 Asst Eng Office1EA6\$301Floor - Tile Ceramic/ Porcelain1st- Inside 125 Asst Eng Office28SF6\$59Lavatory1st- Inside 125 Asst Eng Office1EA6\$320Lighting - Pendent/Surface1st- Inside 125 Asst Eng Office1EA7\$0Lighting - Wall Mounted1st- Inside 125 Asst Eng Office1EA7\$0Walls - Plaster/Drywall1st- Inside 125 Asst Eng Office1EA6\$330water damageWater Closet1Ist- Inside 125 Asst Eng Office1EA6\$336Accessories1st- Inside Pool Rm137SF6\$474Doors - Steel Doors incl hw1st- Inside Pool Rm18SF6\$135stainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$135stainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$135stainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$29	sories 1st- Inside 125 Asst Eng (	fice 28	28 SF	6		
Doors - Wood Doors inclu hw1st- Inside 125 Asst Eng Office1EA6\$301Floor - Tile Ceramic/ Porcelain1st- Inside 125 Asst Eng Office28SF6\$59Lavatory1st- Inside 125 Asst Eng Office1EA6\$320Lighting - Pendent/Surface1st- Inside 125 Asst Eng Office1EA7\$0Lighting - Wall Mounted1st- Inside 125 Asst Eng Office1EA7\$0Walls - Plaster/Drywall1st- Inside 125 Asst Eng Office1EA7\$0Water Closet1st- Inside 125 Asst Eng Office1EA6\$336Accessories1st- Inside 125 Asst Eng Office1EA6\$336Ceiling - Plaster/Drywall1st- Inside 125 Asst Eng Office1EA6\$336Doors - Steel Doors incl hw1st- Inside Pool Rm137SF6\$474Doors - Transom Window1st- Inside Pool Rm1EA6\$135stainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm1EA6\$230Istainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm1EA6\$290Istainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm137SF6\$290Lighting - Pendent/Surface1st- Inside Pool Rm137SF6\$290Lighting - Pendent/Surface1st- Insi	-		28 SF	6	\$97	
Lavatory1stInside 125 AsstEng Office1EA6\$320Lighting - Pendent/Surface1stInside 125 AsstEng Office1EA7\$0Lighting - Wall Mounted1stInside 125 AsstEng Office1EA7\$0Walls - Plaster/Drywall1stInside 125 AsstEng Office1EA7\$30water damageWater Closet1stInside 125 AsstEng Office1EA6\$336*********************************	- Wood Doors inclu hw 1st- Inside 125 Asst Eng C	fice 1	1 EA	6	\$301	
Lighting - Pendent/Surface1st - Inside 125 Asst Eng Office1EA7\$0Lighting - Wall Mounted1st - Inside 125 Asst Eng Office1EA7\$0Walls - Plaster/Drywall1st - Inside 125 Asst Eng Office4SF5\$30water damageWater Closet1st - Inside 125 Asst Eng Office1EA6\$336Accessories1st - Inside Pool Rm137SF6\$1,264Ceiling - Plaster/Drywall1st - Inside Pool Rm137SF6\$4774Doors - Steel Doors incl hw1st - Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st - Inside Pool Rm1EA6\$11,55stainless steelFloor Drain1st - Inside Pool Rm1EA6\$10,59\$11,55\$11,55Floor - Tile Ceramic/ Porcelain1st - Inside Pool Rm137SF6\$2200\$200Lighting - Pendent/Surface1st - Inside Pool Rm1EA6\$320	Tile Ceramic/ Porcelain 1st- Inside 125 Asst Eng C	fice 28	28 SF	6	\$59	
Lighting - Wall Mounted1st- Inside 125 Asst Eng Office1EA7\$0Walls - Plaster/Drywall1st- Inside 125 Asst Eng Office4SF5\$30water damageWater Closet1st- Inside 125 Asst Eng Office1EA6\$336Accessories1st- Inside Pool Rm137SF6\$1,264Ceiling - Plaster/Drywall1st- Inside Pool Rm137SF6\$474Doors - Steel Doors incl hw1st- Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st- Inside Pool Rm1EA6\$1,264\$11Floor Drain1st- Inside Pool Rm1EA6\$301stainless steelFloor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$1,059Lavatory1st- Inside Pool Rm137SF6\$290Lighting - Pendent/Surface1st- Inside Pool Rm1EA6\$320	ry 1st- Inside 125 Asst Eng C	fice 1	1 EA	6	\$320	
Walls - Plaster/Drywall1st- Inside 125 Asst Eng Office4SF5\$30water damageWater Closet1st- Inside 125 Asst Eng Office1EA6\$336Accessories1st- Inside Pool Rm137SF6\$1,264Ceiling - Plaster/Drywall1st- Inside Pool Rm137SF6\$474Doors - Steel Doors incl hw1st- Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st- Inside Pool Rm1EA6\$135stainless steelFloor Drain1st- Inside Pool Rm1EA6\$1,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	g - Pendent/Surface 1st- Inside 125 Asst Eng C	fice 1	1 EA	7	\$0	
Walls - Plaster/Drywall1st- Inside 125 Asst Eng Office4SF5\$30water damageWater Closet1st- Inside 125 Asst Eng Office1EA6\$336Accessories1st- Inside Pool Rm137SF6\$1,264Ceiling - Plaster/Drywall1st- Inside Pool Rm137SF6\$474Doors - Steel Doors incl hw1st- Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st- Inside Pool Rm1EA6\$135stainless steelFloor Drain1st- Inside Pool Rm1EA6\$1,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	g - Wall Mounted 1st- Inside 125 Asst Eng C	fice 1	1 EA	7	\$0	
Accessories1st- Inside Pool Rm137SF6\$1,264Ceiling - Plaster/Drywall1st- Inside Pool Rm137SF6\$474Doors - Steel Doors incl hw1st- Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st- Inside Pool Rm1EA6\$11,059Floor Drain1st- Inside Pool Rm1EA6\$10,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	-		4 SF	5	\$30	water damage
Ceiling - Plaster/Drywall1st- Inside Pool Rm137SF6\$474Doors - Steel Doors incl hw1st- Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st- Inside Pool Rm8SF6\$135stainless steelFloor Drain1st- Inside Pool Rm1EA6\$1,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	Closet 1st- Inside 125 Asst Eng C	fice 1	1 EA	6	\$336	-
Doors - Steel Doors incl hw1st- Inside Pool Rm1EA6\$301stainless steelDoors - Transom Window1st- Inside Pool Rm8SF6\$135stainless steelFloor Drain1st- Inside Pool Rm1EA6\$1,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	sories 1st- Inside Pool Rm	137	37 SF	6	\$1,264	
Doors - Transom Window1st- Inside Pool Rm8SF6\$135stainless steelFloor Drain1st- Inside Pool Rm1EA6\$1,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	- Plaster/Drywall 1st- Inside Pool Rm	137	37 SF	6	\$474	
Floor Drain1st- Inside Pool Rm1EA6\$1,059Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	- Steel Doors incl hw 1st- Inside Pool Rm	1	1 EA	6	\$301	stainless steel
Floor - Tile Ceramic/ Porcelain1st- Inside Pool Rm137SF6\$290Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	- Transom Window 1st- Inside Pool Rm	8	8 SF	6	\$135	stainless steel
Lavatory1st- Inside Pool Rm1EA6\$320Lighting - Pendent/Surface1st- Inside Pool Rm2EA7\$0	Prain 1st- Inside Pool Rm	1	1 EA	6	\$1,059	
Lighting - Pendent/Surface 1st- Inside Pool Rm 2 EA 7 \$0	Tile Ceramic/ Porcelain 1st- Inside Pool Rm	137	37 SF	6	\$290	
	ry 1st- Inside Pool Rm	1	1 EA	6	\$320	
	g - Pendent/Surface 1st- Inside Pool Rm	2	2 EA	7	\$0	
Showers   1st- Inside Pool Rm   1 EA   6   \$311	rs 1st- Inside Pool Rm	1	1 EA	6	\$311	
Student Lockers - One Tier 1st- Inside Pool Rm 3 EA 6 \$279	It Lockers - One Tier 1st- Inside Pool Rm	3	3 EA	6	\$279	
Walls - Plaster/Drywall1st- Inside Pool Rm79SF6\$218	Plaster/Drywall 1st- Inside Pool Rm	79	79 SF	6	\$218	
Walls - Structural Glazed Tile 1st- Inside Pool Rm 532 SF 6 \$1,674		532	532 SF	6	\$1,674	
Water Closet1st- Inside Pool Rm1EA6\$336	Closet 1st- Inside Pool Rm	1	1 EA	6		
Accessories 1st- Men's in Auditorium Foyer 145 SF 6 \$1,337	sories 1st- Men's in Auditorium F	/er 145	45 SF	6		



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	om						
	Ceiling - Plaster/Drywall	1st- Men's in Auditorium Foyer	145	SF	6	\$502	
	Doors - Wood Doors inclu hw	1st- Men's in Auditorium Foyer	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Men's in Auditorium Foyer	145	SF	6	\$307	
	Hand Dryer	1st- Men's in Auditorium Foyer	1	EA	6	\$230	
	Lavatory	1st- Men's in Auditorium Foyer	1	EA	6	\$320	
	Lavatory	1st- Men's in Auditorium Foyer	1	EA	5	\$1,590	leaking faucet
	Lighting - Pendent/Surface	1st- Men's in Auditorium Foyer	2	EA	7	\$0	
	Partitions	1st- Men's in Auditorium Foyer	2	EA	6	\$594	
	Urinals	1st- Men's in Auditorium Foyer	1	EA	6	\$336	
	Walls - Plaster/Drywall	1st- Men's in Auditorium Foyer	303	SF	6	\$836	
	Walls - Tile Ceramic/ Porcelain	1st- Men's in Auditorium Foyer	243	SF	6	\$549	Stone
	Water Closet	1st- Men's in Auditorium Foyer	2	EA	6	\$672	
	Accessories	1st- Unisex RR Backstage in auditorium	83	SF	6	\$766	
	Ceiling - Plaster/Drywall	1st- Unisex RR Backstage in auditorium	83	SF	6	\$287	
	Doors - Wood Doors inclu hw	1st- Unisex RR Backstage in auditorium	1	EA	5	\$1,174	laying on ground, broken off at hinges
	Floor - Tile Ceramic/ Porcelain	1st- Unisex RR Backstage in auditorium	83	SF	6	\$176	
	Lavatory	1st- Unisex RR Backstage in auditorium	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st- Unisex RR Backstage in auditorium	1	EA	7	\$0	
	Partitions	1st- Unisex RR Backstage in auditorium	1	EA	6	\$297	
	Walls - Plaster/Drywall	1st- Unisex RR Backstage in auditorium	908	SF	6	\$2,506	
	Water Closet	1st- Unisex RR Backstage in auditorium	1	EA	6	\$336	
	Accessories	1st- Women's in Auditorium Foyer	149	SF	6	\$1,374	
	Ceiling - Plaster/Drywall	1st- Women's in Auditorium Foyer	60	SF	5	\$645	water damage
	Ceiling - Plaster/Drywall	1st- Women's in Auditorium Foyer	89	SF	6	\$308	
	Doors - Wood Doors inclu hw	1st- Women's in Auditorium Foyer	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Women's in Auditorium Foyer	149	SF	6	\$315	
	Hand Dryer	1st- Women's in Auditorium Foyer	1	EA	6	\$230	
	Lavatory	1st- Women's in Auditorium Foyer	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st- Women's in Auditorium Foyer	2	EA	7	\$0	
	Partitions	1st- Women's in Auditorium Foyer	1	EA	6	\$297	
	Partitions	1st- Women's in Auditorium Foyer	1	EA	5	\$751	door delaminating
	Walls - Plaster/Drywall	1st- Women's in Auditorium Foyer	303	SF	6	\$836	
	Walls - Plaster/Drywall	1st- Women's in Auditorium Foyer	50	SF	5	\$221	water damage
	Walls - Tile Ceramic/ Porcelain	1st- Women's in Auditorium Foyer	235	SF	6	\$531	stone
	Water Closet	1st- Women's in Auditorium Foyer	2	EA	6	\$672	
	Accessories	2nd - Boy's Bath	367	SF	6	\$3,385	
	Ceiling - Plaster/Drywall	2nd - Boy's Bath	367	SF	6	\$1,270	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	om						
	Floor Drain	2nd - Boy's Bath	2	EA	6	\$2,118	
	Floor - Terrazzo	2nd - Boy's Bath	367	SF	6	\$803	
	Hand Dryer	2nd - Boy's Bath	1	EA	6	\$230	
	Lavatory	2nd - Boy's Bath	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd - Boy's Bath	7	EA	7	\$0	
	Partitions	2nd - Boy's Bath	2	EA	6	\$594	
	Urinals	2nd - Boy's Bath	5	EA	6	\$1,680	
	Walls - Plaster/Drywall	2nd - Boy's Bath	329	SF	6	\$908	
	Walls - Structural Glazed Tile	2nd - Boy's Bath	820	SF	6	\$2,580	
	Water Closet	2nd - Boy's Bath	4	EA	6	\$1,344	
	Accessories	2nd - Girls's Bath	371	SF	6	\$3,422	
	Ceiling - Plaster/Drywall	2nd - Girls's Bath	371	SF	6	\$1,284	
	Floor Drain	2nd - Girls's Bath	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd - Girls's Bath	371	SF	6	\$812	
	Hand Dryer	2nd - Girls's Bath	1	EA	6	\$230	
	Lavatory	2nd - Girls's Bath	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd - Girls's Bath	9	EA	7	\$0	
	Partitions	2nd - Girls's Bath	6	EA	6	\$1,782	
	Walls - Plaster/Drywall	2nd - Girls's Bath	244	SF	6	\$673	
	Walls - Structural Glazed Tile	2nd - Girls's Bath	670	SF	6	\$2,108	
	Water Closet	2nd - Girls's Bath	7	EA	6	\$2,352	
	Accessories	2nd - inside 243 Engineer Office	154	SF	6	\$1,420	
	Ceiling - Plaster/Drywall	2nd - inside 243 Engineer Office	154	SF	6	\$533	
	Doors - Wood Doors inclu hw	2nd - inside 243 Engineer Office	1	EA	6	\$301	folding door
	Floor - Tile Ceramic/ Porcelain	2nd - inside 243 Engineer Office	154	SF	6	\$326	
	Lavatory	2nd - inside 243 Engineer Office	1	EA	6	\$320	pedestal sink
	Lighting - Pendent/Surface	2nd - inside 243 Engineer Office	1	EA	7	\$0	
	Partitions	2nd - inside 243 Engineer Office	1	EA	6	\$297	
	Showers	2nd - inside 243 Engineer Office	1	EA	6	\$311	
	Walls - Plaster/Drywall	2nd - inside 243 Engineer Office	543	SF	6	\$1,499	
	Walls - Tile Ceramic/ Porcelain	2nd - inside 243 Engineer Office	128	SF	6	\$289	granite partitions / wainscot
	Water Closet	2nd - inside 243 Engineer Office	1	EA	6	\$336	
	Accessories	2nd - Unisex Bath	57	SF	6	\$526	
	Ceiling - Plaster/Drywall	2nd - Unisex Bath	57	SF	6	\$197	
	Doors - Wood Doors inclu hw	2nd - Unisex Bath	1	EA	6	\$301	
	Floor Drain	2nd - Unisex Bath	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Unisex Bath	57	SF	6	\$121	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

р	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
rooi	m						
	Hand Dryer	2nd - Unisex Bath	1	EA	6	\$230	
	Lavatory	2nd - Unisex Bath	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd - Unisex Bath	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd - Unisex Bath	39	SF	6	\$108	
	Walls - Structural Glazed Tile	2nd - Unisex Bath	243	SF	6	\$764	
	Water Closet	2nd - Unisex Bath	1	EA	6	\$336	
	Accessories	2nd Floor	168	SF	6	\$1,550	
	Accessories	2nd Floor	244	SF	6	\$2,251	
	Accessories	2nd Floor	233	SF	6	\$2,149	
	Ceiling - Lay-in	2nd Floor	233	SF	6	\$700	
	Ceiling - Lay-in	2nd Floor	168	SF	6	\$505	
	Ceiling - Plaster/Drywall	2nd Floor	244	SF	6	\$844	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd Floor	244	SF	6	\$534	
	Floor - Terrazzo	2nd Floor	138	SF	6	\$302	
	Floor - Terrazzo	2nd Floor	80	SF	6	\$175	
	Floor - Tile	2nd Floor	88	SF	6	\$193	
	Floor - Tile	2nd Floor	95	SF	6	\$208	
	Hand Dryer	2nd Floor	1	EA	6	\$230	
	Hand Dryer	2nd Floor	1	EA	6	\$230	
	Lavatory	2nd Floor	1	EA	6	\$320	
	Lavatory	2nd Floor	2	EA	6	\$639	
	Lavatory	2nd Floor	1	EA	6	\$320	
	Lighting - Lay-in	2nd Floor	4	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	5	EA	6	\$595	
	Lighting - Pendent/Surface	2nd Floor	5	EA	6	\$619	
	Partitions	2nd Floor	1	EA	6	\$297	
	Partitions	2nd Floor	3	EA	6	\$891	
	Partitions	2nd Floor	3	EA	6	\$891	
	Urinals	2nd Floor	2	EA	6	\$672	
	Walls - Plaster/Drywall	2nd Floor	115	SF	6	\$317	
	Walls - Plaster/Drywall	2nd Floor	255	SF	6	\$704	
	Walls - Plaster/Drywall	2nd Floor	115	SF	6	\$317	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	om						
	Walls - Tile Ceramic/ Porcelain	2nd Floor	307	SF	6	\$694	
	Walls - Tile Ceramic/ Porcelain	2nd Floor	307	SF	6	\$694	
	Walls - Tile Ceramic/ Porcelain	2nd Floor	480	SF	6	\$1,085	
	Water Closet	2nd Floor	3	EA	6	\$1,008	
	Water Closet	2nd Floor	3	EA	6	\$1,008	
	Water Closet	2nd Floor	1	EA	6	\$336	
	Accessories	2nd- Women's on Auditorium Balcony Foyer	114	SF	6	\$1,051	
	Ceiling - Plaster/Drywall	2nd- Women's on Auditorium Balcony Foyer	114	SF	6	\$395	
	Doors - Wood Doors inclu hw	2nd- Women's on Auditorium Balcony Foyer	1	EA	5	\$1,174	delaminating
	Floor - Tile Ceramic/ Porcelain	2nd- Women's on Auditorium Balcony Foyer	114	SF	6	\$241	
	Lavatory	2nd- Women's on Auditorium Balcony Foyer	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd- Women's on Auditorium Balcony Foyer	1	EA	7	\$0	
	Partitions	2nd- Women's on Auditorium Balcony Foyer	2	EA	6	\$594	
	Walls - Plaster/Drywall	2nd- Women's on Auditorium Balcony Foyer	194	SF	6	\$535	
	Walls - Tile Ceramic/ Porcelain	2nd- Women's on Auditorium Balcony Foyer	194	SF	6	\$438	stone
	Water Closet	2nd- Women's on Auditorium Balcony Foyer	2	EA	6	\$672	
	Accessories	3rd - bath inside Office 314	19	SF	6	\$175	
	Ceiling - Plaster/Drywall	3rd - bath inside Office 314	19	SF	6	\$66	skylight
	Doors - Wood Doors inclu hw	3rd - bath inside Office 314	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd - bath inside Office 314	19	SF	6	\$40	
	Lighting - Wall Mounted	3rd - bath inside Office 314	1	EA	6	\$124	no cover
	Walls - Plaster/Drywall	3rd - bath inside Office 314	194	SF	6	\$535	
	Water Closet	3rd - bath inside Office 314	1	EA	6	\$336	
	Accessories	3rd - Boy's Bath	367	SF	6	\$3,385	
	Ceiling - Plaster/Drywall	3rd - Boy's Bath	367	SF	6	\$1,270	
	Floor Drain	3rd - Boy's Bath	2	EA	6	\$2,118	
	Floor - Terrazzo	3rd - Boy's Bath	367	SF	6	\$803	
	Hand Dryer	3rd - Boy's Bath	1	EA	6	\$230	
	Lavatory	3rd - Boy's Bath	3	EA	6	\$959	
	Lighting - Pendent/Surface	3rd - Boy's Bath	7	EA	7	\$0	



231 N Pine Ave Chicago, IL 60644

#### Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

## **Building: Main**

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
estroo	m						
	Partitions	3rd - Boy's Bath	2	EA	6	\$594	
	Urinals	3rd - Boy's Bath	5	EA	6	\$1,680	
	Walls - Plaster/Drywall	3rd - Boy's Bath	329	SF	6	\$908	
	Walls - Structural Glazed Tile	3rd - Boy's Bath	820	SF	6	\$2,580	
	Water Closet	3rd - Boy's Bath	4	EA	6	\$1,344	
	Accessories	3rd - Girl's Bath	371	SF	6	\$3,422	
	Ceiling - Plaster/Drywall	3rd - Girl's Bath	371	SF	6	\$1,284	
	Floor Drain	3rd - Girl's Bath	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd - Girl's Bath	371	SF	6	\$812	
	Hand Dryer	3rd - Girl's Bath	1	EA	6	\$230	
	Lavatory	3rd - Girl's Bath	2	EA	6	\$639	1 - missing / being replaced per engineer
	Lighting - Pendent/Surface	3rd - Girl's Bath	9	EA	7	\$0	
	Partitions	3rd - Girl's Bath	6	EA	6	\$1,782	
	Walls - Plaster/Drywall	3rd - Girl's Bath	244	SF	6	\$673	
	Walls - Structural Glazed Tile	3rd - Girl's Bath	670	SF	6	\$2,108	
	Water Closet	3rd - Girl's Bath	7	EA	6	\$2,352	
	Accessories	3rd - inside 341 Engineer Office	154	SF	6	\$1,420	
	Ceiling - Lay-in	3rd - inside 341 Engineer Office	154	SF	6	\$462	
	Doors - Wood Doors inclu hw	3rd - inside 341 Engineer Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd - inside 341 Engineer Office	154	SF	6	\$326	
	Lavatory	3rd - inside 341 Engineer Office	1	EA	6	\$320	laundry sink
	Lighting - Lay-in	3rd - inside 341 Engineer Office	2	EA	7	\$0	
	Partitions	3rd - inside 341 Engineer Office	1	EA	6	\$297	
	Student Lockers - One Tier	3rd - inside 341 Engineer Office	2	EA	6	\$186	
	Walls - Plaster/Drywall	3rd - inside 341 Engineer Office	563	SF	6	\$1,554	
	Walls - Tile Ceramic/ Porcelain	3rd - inside 341 Engineer Office	44	SF	6	\$99	granite slab partitions
	Water Closet	3rd - inside 341 Engineer Office	1	EA	6	\$336	
	Accessories	3rd - Unisex Bath	57	SF	6	\$526	
	Ceiling - Plaster/Drywall	3rd - Unisex Bath	57	SF	6	\$197	
	Doors - Wood Doors inclu hw	3rd - Unisex Bath	1	EA	6	\$301	
	Floor Drain	3rd - Unisex Bath	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd - Unisex Bath	57	SF	6	\$121	
	Hand Dryer	3rd - Unisex Bath	1	EA	6	\$230	
	Lavatory	3rd - Unisex Bath	1	EA	6	\$320	
	Lighting - Pendent/Surface	3rd - Unisex Bath	1	EA	7	\$0	
	Walls - Plaster/Drywall	3rd - Unisex Bath	39	SF	6	\$108	
	Walls - Structural Glazed Tile	3rd - Unisex Bath	243	SF	6	\$764	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Water Closet	3rd - Unisex Bath	1	EA	6	\$336	
	Accessories	3rd Floor	236	SF	6	\$2,177	
	Accessories	3rd Floor	158	SF	6	\$1,457	
	Ceiling - Lay-in	3rd Floor	158	SF	6	\$474	
	Ceiling - Plaster/Drywall	3rd Floor	236	SF	6	\$817	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor Drain	3rd Floor	1	EA	6	\$1,059	
	Floor Drain	3rd Floor	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd Floor	158	SF	6	\$346	
	Floor - Terrazzo	3rd Floor	236	SF	6	\$516	
	Hand Dryer	3rd Floor	1	EA	6	\$230	
	Lavatory	3rd Floor	2	EA	6	\$639	
	Lavatory	3rd Floor	2	EA	6	\$639	
	Lighting - Lay-in	3rd Floor	4	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	5	EA	7	\$0	
	Partitions	3rd Floor	3	EA	6	\$891	
	Partitions	3rd Floor	2	EA	6	\$594	
	Urinals	3rd Floor	2	EA	6	\$672	
	Walls - Plaster/Drywall	3rd Floor	254	SF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	293	SF	6	\$809	
	Walls - Tile Ceramic/ Porcelain	3rd Floor	541	SF	6	\$1,222	
	Walls - Tile Ceramic/ Porcelain	3rd Floor	254	SF	6	\$574	
	Water Closet	3rd Floor	2	EA	6	\$672	
	Water Closet	3rd Floor	3	EA	6	\$1,008	
	Accessories	4th - Boy's Bath	367	SF	6	\$3,385	
	Ceiling - Plaster/Drywall	4th - Boy's Bath	367	SF	6	\$1,270	
	Floor Drain	4th - Boy's Bath	2	EA	6	\$2,118	
	Floor - Terrazzo	4th - Boy's Bath	367	SF	6	\$803	
	Hand Dryer	4th - Boy's Bath	1	EA	6	\$230	
	Lavatory	4th - Boy's Bath	3	EA	6	\$959	
	Lighting - Pendent/Surface	4th - Boy's Bath	7	EA	7	\$0	
	Partitions	4th - Boy's Bath	2	EA	6	\$594	
	Urinals	4th - Boy's Bath	5	EA	6	\$1,680	
	Walls - Plaster/Drywall	4th - Boy's Bath	329	SF	6	\$908	
	Walls - Structural Glazed Tile	4th - Boy's Bath	820	SF	6	\$2,580	
	Water Closet	4th - Boy's Bath	4	EA	6	\$1,344	
	Accessories	4th - Girl's Bath	371	SF	6	\$3,422	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

### Category: Rooms (Other Than Classrooms)

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom						
Ceiling - Plaster/Drywall	4th - Girl's Bath	371	SF	6	\$1,284	
Floor Drain	4th - Girl's Bath	1	EA	6	\$1,059	
Floor - Terrazzo	4th - Girl's Bath	371	SF	6	\$812	
Hand Dryer	4th - Girl's Bath	1	EA	6	\$230	
Lavatory	4th - Girl's Bath	3	EA	6	\$959	
Lighting - Pendent/Surface	4th - Girl's Bath	9	EA	7	\$0	
Partitions	4th - Girl's Bath	6	EA	6	\$1,782	
Walls - Plaster/Drywall	4th - Girl's Bath	244	SF	6	\$673	
Walls - Structural Glazed Tile	4th - Girl's Bath	670	SF	6	\$2,108	
Water Closet	4th - Girl's Bath	7	EA	6	\$2,352	
Accessories	4th - Unisex Bath	57	SF	6	\$526	
Ceiling - Lay-in	4th - Unisex Bath	57	SF	6	\$171	
Doors - Wood Doors inclu hw	4th - Unisex Bath	1	EA	6	\$301	
Floor Drain	4th - Unisex Bath	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	4th - Unisex Bath	57	SF	6	\$121	
Hand Dryer	4th - Unisex Bath	1	EA	6	\$230	
Lavatory	4th - Unisex Bath	1	EA	6	\$320	
Lighting - Lay-in	4th - Unisex Bath	1	EA	7	\$0	
Walls - Plaster/Drywall	4th - Unisex Bath	39	SF	6	\$108	
Walls - Structural Glazed Tile	4th - Unisex Bath	243	SF	6	\$764	
Water Closet	4th - Unisex Bath	1	EA	6	\$336	
Accessories	4th Floor	233	SF	6	\$2,149	
Ceiling - Lay-in	4th Floor	233	SF	6	\$700	
Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
Floor Drain	4th Floor	1	EA	6	\$1,059	
Floor - Terrazzo	4th Floor	138	SF	6	\$302	
Floor - Tile	4th Floor	95	SF	6	\$208	
Hand Dryer	4th Floor	1	EA	6	\$230	
Lavatory	4th Floor	1	EA	6	\$320	
Lighting - Lay-in	4th Floor	5	EA	7	\$0	
Partitions	4th Floor	3	EA	6	\$891	
Walls - Plaster/Drywall	4th Floor	115	SF	6	\$317	
Walls - Tile Ceramic/ Porcelain	4th Floor	307	SF	6	\$694	
Water Closet	4th Floor	3	EA	6	\$1,008	
Pooms (Other Than Classrooms) Subtotal:				¢.	2 773 326	

Rooms (Other Than Classrooms) Subtotal:

\$3,773,326



# Building: Main

# **Category: Building Interior**

231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

up	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
rido	r						
	Ceiling - Plaster/Drywall	1st Floor, E Corridor	3,237	SF	6	\$20,043	
	Doors - Steel Doors incl hw	1st Floor, E Corridor	4	EA	6	\$1,204	
	Doors - Transom Window	1st Floor, E Corridor	180	EA	6	\$3,048	
	Doors - Wood Doors include hw	1st Floor, E Corridor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	1st Floor, E Corridor	2	EA	6	\$672	
	Floor - Terrazzo	1st Floor, E Corridor	1,618	SF	6	\$13,582	
	Floor - Tile/Sheet	1st Floor, E Corridor	1,618	SF	6	\$879	
	Lighting - Pendent/Surface	1st Floor, E Corridor	30	EA	6	\$3,717	
	Student Lockers - One Tier	1st Floor, E Corridor	143	EA	6	\$13,275	
	Walls - Plaster/Drywall	1st Floor, E Corridor	1,893	SF	6	\$8,392	
	Walls - Structural Glazed Tile	1st Floor, E Corridor	2,104	SF	6	\$6,619	
	Walls - Tile Ceramic/ Porcelain	1st Floor, E Corridor	210	SF	6	\$661	
	Ceiling - Plaster/Drywall	1st Floor, N Corridor	3,991	SF	6	\$24,712	
	Doors - Steel Doors incl hw	1st Floor, N Corridor	10	EA	6	\$3,010	
	Doors - Transom Window	1st Floor, N Corridor	108	EA	6	\$1,829	
	Doors - Wood Doors include hw	1st Floor, N Corridor	2	EA	6	\$602	
	Drinking Fountains - Double Fountain	1st Floor, N Corridor	2	EA	6	\$672	
	Floor - Terrazzo	1st Floor, N Corridor	399	SF	6	\$3,349	
	Floor - Tile/Sheet	1st Floor, N Corridor	3,592	SF	6	\$1,952	
	Lighting - Pendent/Surface	1st Floor, N Corridor	37	EA	6	\$4,584	
	Lighting - Wall Mounted	1st Floor, N Corridor	2	EA	6	\$248	
	Student Lockers - One Tier	1st Floor, N Corridor	90	EA	6	\$8,355	
	Walls - Plaster/Drywall	1st Floor, N Corridor	2,594	SF	6	\$11,499	
	Walls - Structural Glazed Tile	1st Floor, N Corridor	2,334	SF	6	\$7,343	
	Walls - Tile Ceramic/ Porcelain	1st Floor, N Corridor	259	SF	6	\$815	base board runner
	Ceiling - Plaster/Drywall	1st Floor, S Corridor	3,895	SF	6	\$24,117	
	Doors - Steel Doors incl hw	1st Floor, S Corridor	4	EA	6	\$1,204	
	Doors - Transom Window	1st Floor, S Corridor	36	EA	6	\$610	
	Drinking Fountains - Double Fountain	1st Floor, S Corridor	2	EA	6	\$672	
	Floor - Terrazzo	1st Floor, S Corridor	389	SF	6	\$3,265	
	Floor - Tile/Sheet	1st Floor, S Corridor	3,506	SF	6	\$1,905	
	Lighting - Pendent/Surface	1st Floor, S Corridor	34	EA	6	\$4,212	
	Student Lockers - One Tier	1st Floor, S Corridor	197	EA	6	\$18,289	
	Walls - Plaster/Drywall	1st Floor, S Corridor	2,278	SF	6	\$10,098	
	Walls - Structural Glazed Tile	1st Floor, S Corridor	2,531	SF	6	\$7,963	
	Walls - Tile Ceramic/ Porcelain	1st Floor, S Corridor	253	SF	6	\$796	base board runner
	Ceiling - Plaster/Drywall	1st Floor, W Corridor	3,261	SF	6	\$20,192	



# Building: Main

## **Category: Building Interior**

231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
orrido	r						
	Doors - Steel Doors incl hw	1st Floor, W Corridor	6	EA	6	\$1,806	
	Doors - Transom Window	1st Floor, W Corridor	36	EA	6	\$610	
	Drinking Fountains - Double Fountain	1st Floor, W Corridor	2	EA	6	\$672	
	Floor - Terrazzo	1st Floor, W Corridor	1,631	SF	6	\$13,691	
	Floor - Tile/Sheet	1st Floor, W Corridor	1,631	SF	6	\$886	
	Lighting - Pendent/Surface	1st Floor, W Corridor	30	EA	6	\$3,717	
	Walls - Plaster/Drywall	1st Floor, W Corridor	1,907	SF	6	\$8,454	
	Walls - Structural Glazed Tile	1st Floor, W Corridor	2,119	SF	6	\$6,666	
	Walls - Tile Ceramic/ Porcelain	1st Floor, W Corridor	211	SF	6	\$664	base board runner
	Ceiling - Plaster/Drywall	2nd Floor, E Corridor	3,237	SF	6	\$20,043	
	Doors - Steel Doors incl hw	2nd Floor, E Corridor	4	EA	6	\$1,204	
	Doors - Transom Window	2nd Floor, E Corridor	180	EA	6	\$3,048	
	Doors - Wood Doors include hw	2nd Floor, E Corridor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	2nd Floor, E Corridor	2	EA	6	\$672	
	Floor - Terrazzo	2nd Floor, E Corridor	324	SF	6	\$2,720	
	Floor - Tile/Sheet	2nd Floor, E Corridor	2,913	SF	6	\$1,583	
	Lighting - Pendent/Surface	2nd Floor, E Corridor	30	EA	6	\$3,717	
	Student Lockers - One Tier	2nd Floor, E Corridor	143	EA	6	\$13,275	
	Walls - Plaster/Drywall	2nd Floor, E Corridor	1,893	SF	6	\$8,392	
	Walls - Structural Glazed Tile	2nd Floor, E Corridor	2,104	SF	6	\$6,619	
	Walls - Tile Ceramic/ Porcelain	2nd Floor, E Corridor	210	SF	6	\$661	
	Ceiling - Plaster/Drywall	2nd Floor, N Corridor	3,991	SF	6	\$24,712	
	Doors - Steel Doors incl hw	2nd Floor, N Corridor	10	EA	6	\$3,010	
	Doors - Transom Window	2nd Floor, N Corridor	108	EA	6	\$1,829	
	Doors - Wood Doors include hw	2nd Floor, N Corridor	2	EA	6	\$602	
	Drinking Fountains - Double Fountain	2nd Floor, N Corridor	2	EA	6	\$672	
	Floor - Terrazzo	2nd Floor, N Corridor	399	SF	6	\$3,349	
	Floor - Tile/Sheet	2nd Floor, N Corridor	3,592	SF	6	\$1,952	
	Lighting - Pendent/Surface	2nd Floor, N Corridor	37	EA	6	\$4,584	
	Lighting - Wall Mounted	2nd Floor, N Corridor	2	EA	6	\$248	
	Student Lockers - One Tier	2nd Floor, N Corridor	90	EA	6	\$8,355	
	Walls - Plaster/Drywall	2nd Floor, N Corridor	2,334	SF	6	\$10,347	
	Walls - Structural Glazed Tile	2nd Floor, N Corridor	2,495	SF	6	\$7,849	
	Walls - Tile Ceramic/ Porcelain	2nd Floor, N Corridor	259	SF	6	\$815	
	Ceiling - Plaster/Drywall	2nd Floor, S1 Corridor	641	SF	6	\$3,969	
	Floor - Terrazzo	2nd Floor, S1 Corridor	64	SF	6	\$537	
	Floor - Tile/Sheet	2nd Floor, S1 Corridor	577	SF	6	\$314	



#### **Category: Building Interior**

231 N Pine Ave Chicago, IL 60644

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Commen
orrido	pr						
	Lighting - Pendent/Surface	2nd Floor, S1 Corridor	4	EA	6	\$496	
	Walls - Plaster/Drywall	2nd Floor, S1 Corridor	3,750	SF	6	\$16,624	
	Walls - Structural Glazed Tile	2nd Floor, S1 Corridor	4,167	SF	6	\$13,109	
	Walls - Tile Ceramic/ Porcelain	2nd Floor, S1 Corridor	416	SF	6	\$1,309	
	Ceiling - Plaster/Drywall	2nd Floor, S2 Corridor	2,679	SF	6	\$16,588	
	Doors - Transom Window	2nd Floor, S2 Corridor	72	EA	6	\$1,219	
	Doors - Wood Doors include hw	2nd Floor, S2 Corridor	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	2nd Floor, S2 Corridor	2	EA	6	\$672	
	Floor - Terrazzo	2nd Floor, S2 Corridor	268	SF	6	\$2,250	
	Floor - Tile/Sheet	2nd Floor, S2 Corridor	2,411	SF	6	\$1,310	
	Lighting - Pendent/Surface	2nd Floor, S2 Corridor	26	EA	6	\$3,221	
	Student Lockers - One Tier	2nd Floor, S2 Corridor	200	EA	6	\$18,567	
	Walls - Plaster/Drywall	2nd Floor, S2 Corridor	1,567	SF	6	\$6,947	
	Walls - Structural Glazed Tile	2nd Floor, S2 Corridor	1,741	SF	6	\$5,477	
	Walls - Tile Ceramic/ Porcelain	2nd Floor, S2 Corridor	174	SF	6	\$547	
	Ceiling - Plaster/Drywall	2nd Floor, W1 Corridor	2,340	SF	6	\$14,489	
	Drinking Fountains - Double Fountain	2nd Floor, W1 Corridor	1	EA	6	\$336	
	Drinking Fountains - Single Fountain	2nd Floor, W1 Corridor	1	EA	6	\$276	
	Floor - Terrazzo	2nd Floor, W1 Corridor	234	SF	6	\$1,964	
	Floor - Tile/Sheet	2nd Floor, W1 Corridor	2,106	SF	6	\$1,144	
	Lighting - Pendent/Surface	2nd Floor, W1 Corridor	22	EA	6	\$2,726	
	Student Lockers - One Tier	2nd Floor, W1 Corridor	156	EA	6	\$14,482	
	Walls - Plaster/Drywall	2nd Floor, W1 Corridor	1,368	SF	6	\$6,064	
	Walls - Structural Glazed Tile	2nd Floor, W1 Corridor	1,521	SF	6	\$4,785	
	Walls - Tile Ceramic/ Porcelain	2nd Floor, W1 Corridor	152	SF	6	\$478	
	Ceiling - Plaster/Drywall	2nd Floor, W2 Corridor	1,140	SF	6	\$7,059	
	Floor - Terrazzo	2nd Floor, W2 Corridor	114	SF	6	\$957	
	Floor - Tile/Sheet	2nd Floor, W2 Corridor	1,026	SF	6	\$558	
	Lighting - Pendent/Surface	2nd Floor, W2 Corridor	10	EA	6	\$1,239	
	Walls - Plaster/Drywall	2nd Floor, W2 Corridor	6,669	SF	6	\$29,564	
	Walls - Structural Glazed Tile	2nd Floor, W2 Corridor	7,410	SF	6	\$23,312	
	Walls - Tile Ceramic/ Porcelain	2nd Floor, W2 Corridor	741	SF	6	\$2,331	
	Ceiling - Plaster/Drywall	3rd Floor, E Corridor	3,237	SF	6	\$20,043	
	Doors - Steel Doors incl hw	3rd Floor, E Corridor	4	EA	6	\$1,204	
	Doors - Transom Window	3rd Floor, E Corridor	180	EA	6	\$3,048	
	Doors - Wood Doors include hw	3rd Floor, E Corridor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	3rd Floor, E Corridor	2	EA	6	\$672	



#### **Category: Building Interior**

231 N Pine Ave Chicago, IL 60644

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
rido	r						
	Floor - Terrazzo	3rd Floor, E Corridor	324	SF	6	\$2,720	
	Floor - Tile/Sheet	3rd Floor, E Corridor	2,913	SF	6	\$1,583	
	Lighting - Pendent/Surface	3rd Floor, E Corridor	30	EA	6	\$3,717	
	Student Lockers - One Tier	3rd Floor, E Corridor	143	EA	6	\$13,275	
	Walls - Plaster/Drywall	3rd Floor, E Corridor	1,893	SF	6	\$8,392	
	Walls - Structural Glazed Tile	3rd Floor, E Corridor	2,104	SF	6	\$6,619	
	Walls - Tile Ceramic/ Porcelain	3rd Floor, E Corridor	210	SF	6	\$661	
	Ceiling - Plaster/Drywall	3rd Floor, N Corridor	3,991	SF	6	\$24,712	
	Doors - Steel Doors incl hw	3rd Floor, N Corridor	10	EA	6	\$3,010	
	Doors - Transom Window	3rd Floor, N Corridor	108	EA	6	\$1,829	
	Doors - Wood Doors include hw	3rd Floor, N Corridor	2	EA	6	\$602	
	Drinking Fountains - Double Fountain	3rd Floor, N Corridor	2	EA	6	\$672	
	Floor - Terrazzo	3rd Floor, N Corridor	399	SF	6	\$3,349	
	Floor - Tile/Sheet	3rd Floor, N Corridor	3,592	SF	6	\$1,952	
	Lighting - Pendent/Surface	3rd Floor, N Corridor	37	EA	6	\$4,584	
	Lighting - Wall Mounted	3rd Floor, N Corridor	2	EA	6	\$248	
	Student Lockers - One Tier	3rd Floor, N Corridor	90	EA	6	\$8,355	
	Walls - Plaster/Drywall	3rd Floor, N Corridor	2,334	SF	6	\$10,347	
	Walls - Structural Glazed Tile	3rd Floor, N Corridor	2,594	SF	6	\$8,161	
	Walls - Tile Ceramic/ Porcelain	3rd Floor, N Corridor	259	SF	6	\$815	
	Ceiling - Plaster/Drywall	3rd Floor, S1 Corridor	641	SF	6	\$3,969	
	Floor - Terrazzo	3rd Floor, S1 Corridor	64	SF	6	\$537	
	Floor - Tile/Sheet	3rd Floor, S1 Corridor	577	SF	6	\$314	
	Lighting - Pendent/Surface	3rd Floor, S1 Corridor	26	EA	6	\$3,221	
	Walls - Plaster/Drywall	3rd Floor, S1 Corridor	3,750	SF	6	\$16,624	
	Walls - Structural Glazed Tile	3rd Floor, S1 Corridor	4,167	SF	6	\$13,109	
	Walls - Tile Ceramic/ Porcelain	3rd Floor, S1 Corridor	416	SF	6	\$1,309	
	Ceiling - Plaster/Drywall	3rd Floor, S2 Corridor	2,679	SF	6	\$16,588	
	Doors - Transom Window	3rd Floor, S2 Corridor	72	EA	6	\$1,219	
	Doors - Wood Doors include hw	3rd Floor, S2 Corridor	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	3rd Floor, S2 Corridor	2	EA	6	\$672	
	Floor - Terrazzo	3rd Floor, S2 Corridor	268	SF	6	\$2,250	
	Floor - Tile/Sheet	3rd Floor, S2 Corridor	2,411	SF	6	\$1,310	
	Lighting - Pendent/Surface	3rd Floor, S2 Corridor	26	EA	6	\$3,221	
	Student Lockers - One Tier	3rd Floor, S2 Corridor	200	EA	6	\$18,567	
	Walls - Plaster/Drywall	3rd Floor, S2 Corridor	15,672	SF	6	\$69,474	
	Walls - Structural Glazed Tile	3rd Floor, S2 Corridor	17,414	SF	6	\$54,784	



#### Category: Building Interior

231 N Pine Ave Chicago, IL 60644

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
rido	)r						
	Walls - Tile Ceramic/ Porcelain	3rd Floor, S2 Corridor	1,741	SF	6	\$5,477	
	Ceiling - Plaster/Drywall	3rd Floor, W1 Corridor	2,340	SF	6	\$14,489	
	Drinking Fountains - Double Fountain	3rd Floor, W1 Corridor	1	EA	6	\$336	
	Drinking Fountains - Single Fountain	3rd Floor, W1 Corridor	1	EA	6	\$276	
	Floor - Terrazzo	3rd Floor, W1 Corridor	234	SF	6	\$1,964	
	Floor - Tile/Sheet	3rd Floor, W1 Corridor	2,106	SF	6	\$1,144	
	Lighting - Pendent/Surface	3rd Floor, W1 Corridor	22	EA	6	\$2,726	
	Student Lockers - One Tier	3rd Floor, W1 Corridor	156	EA	6	\$14,482	
	Walls - Plaster/Drywall	3rd Floor, W1 Corridor	1,368	SF	6	\$6,064	
	Walls - Structural Glazed Tile	3rd Floor, W1 Corridor	1,521	SF	6	\$4,785	
	Walls - Tile Ceramic/ Porcelain	3rd Floor, W1 Corridor	152	SF	6	\$478	
	Ceiling - Plaster/Drywall	3rd Floor, W2 Corridor	1,140	SF	6	\$7,059	
	Floor - Terrazzo	3rd Floor, W2 Corridor	114	SF	6	\$957	
	Floor - Tile/Sheet	3rd Floor, W2 Corridor	1,026	SF	6	\$558	
	Lighting - Pendent/Surface	3rd Floor, W2 Corridor	10	EA	6	\$1,239	
	Walls - Plaster/Drywall	3rd Floor, W2 Corridor	6,669	SF	6	\$29,564	
	Walls - Structural Glazed Tile	3rd Floor, W2 Corridor	7,410	SF	6	\$23,312	
	Walls - Tile Ceramic/ Porcelain	3rd Floor, W2 Corridor	741	SF	6	\$2,331	
	Ceiling - Plaster/Drywall	4th Floor, E Corridor	3,237	SF	6	\$20,043	
	Doors - Steel Doors incl hw	4th Floor, E Corridor	6	EA	6	\$1,806	
	Doors - Steel Doors incl hw	4th Floor, E Corridor	4	EA	6	\$1,204	
	Doors - Transom Window	4th Floor, E Corridor	180	EA	6	\$3,048	
	Drinking Fountains - Double Fountain	4th Floor, E Corridor	2	EA	6	\$672	
	Floor - Terrazzo	4th Floor, E Corridor	324	SF	6	\$2,720	
	Floor - Tile/Sheet	4th Floor, E Corridor	2,913	SF	6	\$1,583	
	Lighting - Pendent/Surface	4th Floor, E Corridor	30	EA	6	\$3,717	
	Student Lockers - One Tier	4th Floor, E Corridor	143	EA	6	\$13,275	
	Walls - Plaster/Drywall	4th Floor, E Corridor	1,893	SF	6	\$8,392	
	Walls - Structural Glazed Tile	4th Floor, E Corridor	2,104	SF	6	\$6,619	
	Walls - Tile Ceramic/ Porcelain	4th Floor, E Corridor	210	SF	6	\$661	
	Ceiling - Plaster/Drywall	4th Floor, N Corridor	3,991	SF	6	\$24,712	
	Doors - Steel Doors incl hw	4th Floor, N Corridor	10	EA	6	\$3,010	
	Doors - Transom Window	4th Floor, N Corridor	108	EA	6	\$1,829	
	Doors - Wood Doors include hw	4th Floor, N Corridor	2	EA	6	\$602	
	Drinking Fountains - Double Fountain	4th Floor, N Corridor	2	EA	6	\$672	
	Floor - Terrazzo	4th Floor, N Corridor	399	SF	6	\$3,349	
	Floor - Tile/Sheet	4th Floor, N Corridor	3,592	SF	6	\$1,952	



#### **Category: Building Interior**

231 N Pine Ave Chicago, IL 60644

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	r						
	Lighting - Pendent/Surface	4th Floor, N Corridor	37	EA	6	\$4,584	
	Lighting - Wall Mounted	4th Floor, N Corridor	2	EA	6	\$248	
	Student Lockers - One Tier	4th Floor, N Corridor	90	EA	6	\$8,355	
	Walls - Plaster/Drywall	4th Floor, N Corridor	2,334	SF	6	\$10,347	
	Walls - Structural Glazed Tile	4th Floor, N Corridor	2,594	SF	6	\$8,161	
	Walls - Tile Ceramic/ Porcelain	4th Floor, N Corridor	259	SF	6	\$815	
	Ceiling - Plaster/Drywall	4th Floor, S1 Corridor	641	SF	6	\$3,969	
	Floor - Terrazzo	4th Floor, S1 Corridor	64	SF	6	\$537	
	Floor - Tile/Sheet	4th Floor, S1 Corridor	577	SF	6	\$314	
	Lighting - Pendent/Surface	4th Floor, S1 Corridor	4	EA	6	\$496	
	Walls - Plaster/Drywall	4th Floor, S1 Corridor	3,750	SF	6	\$16,624	
	Walls - Structural Glazed Tile	4th Floor, S1 Corridor	4,167	SF	6	\$13,109	
	Walls - Tile Ceramic/ Porcelain	4th Floor, S1 Corridor	416	SF	6	\$1,309	
	Ceiling - Plaster/Drywall	4th Floor, S2 Corridor	2,679	SF	6	\$16,588	
	Doors - Transom Window	4th Floor, S2 Corridor	72	EA	6	\$1,219	
	Doors - Wood Doors include hw	4th Floor, S2 Corridor	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	4th Floor, S2 Corridor	2	EA	6	\$672	
	Floor - Terrazzo	4th Floor, S2 Corridor	268	SF	6	\$2,250	
	Floor - Tile/Sheet	4th Floor, S2 Corridor	2,411	SF	6	\$1,310	
	Lighting - Pendent/Surface	4th Floor, S2 Corridor	26	EA	6	\$3,221	
	Student Lockers - One Tier	4th Floor, S2 Corridor	200	EA	6	\$18,567	
	Walls - Plaster/Drywall	4th Floor, S2 Corridor	1,567	SF	6	\$6,947	
	Walls - Structural Glazed Tile	4th Floor, S2 Corridor	1,741	SF	6	\$5,477	
	Walls - Tile Ceramic/ Porcelain	4th Floor, S2 Corridor	174	SF	6	\$547	
	Ceiling - Plaster/Drywall	4th Floor, W1 Corridor	2,340	SF	6	\$14,489	
	Drinking Fountains - Double Fountain	4th Floor, W1 Corridor	1	EA	6	\$336	
	Drinking Fountains - Single Fountain	4th Floor, W1 Corridor	1	EA	6	\$276	
	Floor - Terrazzo	4th Floor, W1 Corridor	234	SF	6	\$1,964	
	Floor - Tile/Sheet	4th Floor, W1 Corridor	2,106	SF	6	\$1,144	
	Lighting - Pendent/Surface	4th Floor, W1 Corridor	22	EA	6	\$2,726	
	Student Lockers - One Tier	4th Floor, W1 Corridor	156	EA	6	\$14,482	
	Walls - Plaster/Drywall	4th Floor, W1 Corridor	1,368	SF	6	\$6,064	
	Walls - Structural Glazed Tile	4th Floor, W1 Corridor	1,521	SF	6	\$4,785	
	Walls - Tile Ceramic/ Porcelain	4th Floor, W1 Corridor	152	SF	6	\$478	
	Ceiling - Plaster/Drywall	4th Floor, W2 Corridor	1,140	SF	6	\$7,059	
	Floor - Terrazzo	4th Floor, W2 Corridor	495	SF	6	\$4,155	
	Floor - Tile/Sheet	4th Floor, W2 Corridor	1,026	SF	6	\$558	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

## **Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	r						
	Lighting - Pendent/Surface	4th Floor, W2 Corridor	10	EA	6	\$1,239	
	Walls - Plaster/Drywall	4th Floor, W2 Corridor	6,669	SF	6	\$29,564	
	Walls - Structural Glazed Tile	4th Floor, W2 Corridor	7,410	SF	6	\$23,312	
	Walls - Tile Ceramic/ Porcelain	4th Floor, W2 Corridor	741	SF	6	\$2,331	
Safety							
	Camera Viewing Station	Entire building	8	EA	6	\$5,461	
	Metal Dedector	Entire building	3	EA	6	\$2,642	
	Security Cameras	Entire building	45	EA	6	\$8,732	
	Security Cameras	Entire building	13	EA	6	\$2,522	
Stairs							
	Ceiling - Plaster/Drywall	Stair 10	1,534	SF	6	\$11,231	
	Floor - Terrazzo	Stair 10	1,507	SF	6	\$12,650	
	Handrails	Stair 10	165	LF	6	\$1,430	
	Lighting - Chandelier, Incandescent	Stair 10	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 10	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 10	81	LF	6	\$752	
	Walls - Plaster/Drywall	Stair 10	4,092	SF	6	\$11,294	
	Walls - Structural Glazed Tile	Stair 10	4,092	SF	6	\$12,873	
	Ceiling - Plaster/Drywall	Stair 1 / 4th Floor	109	SF	5	\$2,230	Water damaged
	Ceiling - Plaster/Drywall	Stair 1	1,599	SF	6	\$11,707	
	Floor - Terrazzo	Stair 1	1,534	SF	6	\$12,877	
	Handrails	Stair 1	262	LF	6	\$2,270	
	Lighting - Chandelier, Incandescent	Stair 1	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 1	7	EA	6	\$867	
	Lighting - Wall Mounted	Stair 1	1	EA	6	\$124	
	Stairs - Terrazzo	Stair 1	119	LF	6	\$1,104	
	Walls - Plaster/Drywall	Stair 1	849	SF	5	\$4,541	Water damaged, cracking, peeling
	Walls - Plaster/Drywall	Stair 1	3,896	SF	6	\$10,753	
	Walls - Structural Glazed Tile	Stair 1	3,980	SF	6	\$12,521	
	Ceiling - Plaster/Drywall	Stair 2.1	1,574	SF	6	\$11,524	
	Floor - Terrazzo	Stair 2.1	1,507	SF	6	\$12,650	
	Handrails	Stair 2.1	165	LF	6	\$1,430	
	Lighting - Chandelier, Incandescent	Stair 2.1	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 2.1	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 2.1	81	LF	6	\$752	
	Walls - Plaster/Drywall	Stair 2.1	4,092	SF	6	\$11,294	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Building: Main**

#### **Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Walls - Structural Glazed Tile	Stair 2.1	4,092	SF	6	\$12,873	
	Ceiling - Plaster/Drywall	Stair 2	1,574	SF	6	\$11,524	
	Floor - Terrazzo	Stair 2	1,507	SF	6	\$12,650	
	Handrails	Stair 2	165	LF	6	\$1,430	
	Lighting - Chandelier, Incandescent	Stair 2	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 2	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 2	81	LF	6	\$752	
	Walls - Plaster/Drywall	Stair 2	4,092	SF	6	\$11,294	
	Walls - Structural Glazed Tile	Stair 2	4,092	SF	6	\$12,873	
	Ceiling - Plaster/Drywall	Stair 3	988	SF	6	\$7,234	
	Floor - Terrazzo	Stair 3	839	SF	6	\$7,043	
	Handrails	Stair 3	112	LF	6	\$971	
	Lighting - Chandelier, Incandescent	Stair 3	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 3	4	EA	6	\$496	
	Stairs - Terrazzo	Stair 3	56	LF	6	\$520	
	Walls - Plaster/Drywall	Stair 3	1,877	SF	6	\$5,180	
	Walls - Structural Glazed Tile	Stair 3	1,877	SF	6	\$5,905	
	Ceiling - Plaster/Drywall	Stair 4	5	SF	5	\$102	Cracking, peeling
	Ceiling - Plaster/Drywall	Stair 4	2,099	SF	6	\$15,368	
	Floor - Terrazzo	Stair 4	5	SF	5	\$262	Cracking
	Floor - Terrazzo	Stair 4	2,196	SF	6	\$18,433	
	Handrails	Stair 4	107	LF	6	\$927	
	Lighting - Chandelier, Incandescent	Stair 4	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 4	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 4	50	LF	6	\$464	
	Walls - Plaster/Drywall	Stair 4	4,704	SF	6	\$12,983	
	Walls - Structural Glazed Tile	Stair 4	4,704	SF	6	\$14,799	
	Ceiling - Plaster/Drywall	Stair 5	1,574	SF	6	\$11,524	
	Floor - Terrazzo	Stair 5	1,490	SF	6	\$12,507	
	Floor - Terrazzo	Stair 5	17	SF	5	\$890	Cracking
	Handrails	Stair 5	165	LF	6	\$1,430	
	Lighting - Chandelier, Incandescent	Stair 5	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 5	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 5	81	LF	6	\$752	
	Walls - Plaster/Drywall	Stair 5	4,089	SF	6	\$11,285	
	Walls - Plaster/Drywall	Stair 5	25	SF	4	\$368	Cracking, peeling
	Walls - Structural Glazed Tile	Stair 5	4,092	SF	6	\$12,873	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Building: Main**

#### **Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Walls - Plaster/Drywall	Stair 7 / 4th Floor	242	SF	5	\$1,294	Water damaged
	Ceiling - Plaster/Drywall	Stair 7	988	SF	6	\$7,234	
	Floor - Terrazzo	Stair 7	839	SF	6	\$7,043	
	Handrails	Stair 7	112	LF	6	\$971	
	Lighting - Chandelier, Incandescent	Stair 7	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 7	4	EA	6	\$496	
	Stairs - Terrazzo	Stair 7	56	LF	6	\$520	
	Walls - Plaster/Drywall	Stair 7	1,848	SF	6	\$5,100	
	Walls - Structural Glazed Tile	Stair 7	1,877	SF	6	\$5,905	
	Ceiling - Plaster/Drywall	Stair 8	1,574	SF	6	\$11,524	
	Floor - Terrazzo	Stair 8	1,507	SF	6	\$12,650	
	Handrails	Stair 8	165	LF	6	\$1,430	
	Lighting - Chandelier, Incandescent	Stair 8	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 8	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 8	81	LF	6	\$752	
	Walls - Plaster/Drywall	Stair 8	4,092	SF	6	\$11,294	
	Walls - Structural Glazed Tile	Stair 8	4,092	SF	6	\$12,873	
	Ceiling - Plaster/Drywall	Stair 9	1,574	SF	6	\$11,524	
	Floor - Terrazzo	Stair 9	1,507	SF	6	\$12,650	
	Handrails	Stair 9	165	LF	6	\$1,430	
	Lighting - Chandelier, Incandescent	Stair 9	1	EA	6	\$478	
	Lighting - Pendent/Surface	Stair 9	7	EA	6	\$867	
	Stairs - Terrazzo	Stair 9	81	LF	6	\$752	
	Walls - Plaster/Drywall	Stair 9	4,092	SF	6	\$11,294	
	Walls - Structural Glazed Tile	Stair 9	4,092	SF	6	\$12,873	
Buildi	ng Interior Subtotal:				\$1	,923,617	

#### **Building Interior Subtotal:**

#### **Total Building Cost**

#### SITE

#### Category: Site

oup Item - Type	Location	Quantity Unit	Rank	Cost Comments
hletic				
Lighting	East	6 EA	6	\$21,626
Surface - Natural	East	54,353 SF	6	\$45,080

\$18,554,144



231 N Pine Ave Chicago, IL 60644 Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### SITE

Category: Site
----------------

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Athletic							
	Surface - Natural	East	59,583	SF	6	\$49,418	
Civil/Dr	ainage						
	Civil/ Drainage - Catch Basin	Entire Site	18	EA	7	\$0	
	Civil/ Drainage - Site Manhole	Entire Site	25	EA	7	\$0	
Fencing	3						
	Fencing - Chain Link	Entire Site / Site - East	695	LF	6	\$13,049	includes baseball backstops
	Fencing - New Standard Ornamental	Entire Site	1,731	LF	6	\$55,225	
	Fencing - Old Standard Ornamental	Entire Site	733	LF	6	\$37,944	rust
Landsc	ape						
	Benches	Entire Site / Site - East	10	EA	6	\$4,300	at baseball fields for players
	Landscape - Grass	Entire Site	10,985	SF	6	\$9,111	
	Parkway trees	Entire Site	64	EA	7	\$0	
	Planting Beds/ Area	Entire Site	9,076	SF	6	\$14,925	includes fine gravel at courtyards
	Retaining Wall - Concrete	Entire Site	1,840	SF	6	\$43,125	Location: basement wells
	Retaining Wall - Concrete	Entire Site	100	SF	6	\$3,245	Location: SE parking lot
	Retaining Wall - Concrete	Entire Site / Site North	40	SF	6	\$1,298	
	Retaining Wall - Concrete	Entire Site / Site North	20	SF	5	\$1,470	spalling
	Trash Receptacles	Entire Site / Site West	1	EA	6	\$312	
	Walking Path - Crushed Stone	Entire Site / Courtyard	6,865	SF	6	\$14,529	
Parking	Lot						
	Concrete Curbs	NE parking lot	448	LF	6	\$5,753	
	Concrete Curbs	Parking Lot- North	262	LF	6	\$3,364	
	Concrete Curbs	SE parking lot	1,161	LF	6	\$14,909	
	Interior Plantings	NE parking lot	105	LF	6	\$4,467	
	Interior Plantings	Parking Lot- North	75	LF	6	\$3,191	
	Interior Plantings	SE parking lot	280	LF	6	\$11,912	
	Lighting	NE parking lot	6		6	\$0	
	Lighting	Parking Lot- North	2		6	\$0	
	Lighting - Pole Mounted	SE parking lot	8	EA	6	\$11,620	
	Surface - Asphalt	NE parking lot	17,748	SF	6	\$42,892	
	Surface - Asphalt	Parking Lot- North	9,967	SF	6	\$24,087	
	Surface - Asphalt	SE parking lot	28,512	SF	6	\$68,905	
	Surface - Concrete	SE parking lot	1,274	SF	6		at driveways
		Parking Lot- North	., 1	EA	6	\$0	·····
	Trash Compactor	Parking Lot- North		EA		20	



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

\$19,245,794

#### SITE

oup Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
rking Lot		Location	quantity	0			
Vehicular Screening		NE parking lot	265	LF	6	\$20,865	
Vehicular Screening		SE parking lot	342	LF	6	\$26,928	
dewalks							
Sidewalks - Internal Walks		Entire Site	639	LF	6	\$7,676	
Sidewalks - Perimeter Side	walks	Entire Site	35,349	SF	6	\$70,263	
Sidewalks - Perimeter Side	walks	Entire Site / Site North	1,400	SF	5	\$13,373	pitting, cracking
Sidewalks - Perimeter Side	walks	Entire Site / Site South	200	SF	5	\$1,910	cracks
Sidewalks - Perimeter Side	walks	Entire Site / Site West	200	SF	5	\$1,910	cracks
gnage							
Flag Pole - Building Mount	ed Flag Pole	Entire Site / West Façade	1	EA	6	\$828	
Marquee - Free Standing E	ack lighted w/ LED	Entire Site / Site West	1	EA	6	\$0	
Monument - Building Mou	nted Cut Letter Sign	Entire Site	5	EA	6	\$0	Location: doors: 1, 2, 8, 9 & 12
te Subtotal:					:	\$691,651	
otal Site Cost						\$691,651	

Campus Total <sup>2 3</sup>

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

#### Definitions

- Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated.
- Unit means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").



231 N Pine Ave Chicago, IL 60644

- Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.
- Campus Total also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

### **Classroom Summary**

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main		ł	-											4
Art Room	Art Room	3rd Floor	310	310	1,027	1	2	32	273	21	40	Y	N	Y
Computer Lab	Library	2nd Floor	200	200	1,484	0	0	19	390	42	40	Y	Y	Ν
Computer Lab	Computer Lab	2nd Floor	227	227	1,262	1	2	43	252	18	40	Y	Y	Ν
Computer Lab	Computer Lab	2nd Floor	229	229	1,326	1	2	13	697	53	40	Y	Y	Ν
Computer Lab	Special Program	2nd Floor	233	233	1,090	3	31	97	252	18	40	Y	Y	Ν
Computer Lab	Computer Lab	3rd Floor	331	331	1,264	2	32	87	252	18	40	Y	Y	Y
Computer Lab	Computer Lab	3rd Floor	337	337	1,469	0	43	97	336	24	40	Y	N	Ν
Computer Lab	Computer Lab	4th Floor	412	412	938	2	32	89	312	24	40	Y	Y	Ν
Computer Lab	Regular Classroom	4th Floor	416	416	730	2	3	60	168	16	40	Y	Y	Y
Faculty Lounge	Regular Classroom	4th Floor	402	402	730	1	1	13	162	18	40	Y	N	Ν
Laboratory/Shop	Laboratory/Shop	1st Floor	129	129	1,092	0	0	18	168	12	40	Y	N	Ν
Laboratory/Shop	Laboratory/Shop	1st Floor	131	131	1,091	2	2	20	336	24	40	Y	Y	Ν
Multi Purpose Room	Regular Classroom	1st Floor	128	128	1,355	5	2	16	407	33	40	Y	N	Ν
Music Room	Regular Classroom	3rd Floor	323	323	1,675	1	2	18	162	18	40	Y	Y	Y
Music Room	Regular Classroom	3rd Floor	325	325	1,660	2	3	12	168	12	40	Y	N	Ν
Office	Regular Classroom	1st Floor	138	138	724	3	3	17	168	12	40	Y	N	Ν
Regular Classroom	Regular Classroom	1st Floor	135	135	720	2	2	13	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	1st Floor	136	136	718	2	2	16	234	18	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	137	137	728	2	3	11	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	2nd Floor	201	202	745	1	2	38	164	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	2nd Floor	202	201	745	1	2	25	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom		212	212	745	1	2	14	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	2nd Floor	216	216	1,224	1	2	14	390	30	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	219	219	710	0	1	4	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	2nd Floor	232	232	735	2	2	16	168	12	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	234	234	726	2	2	16	168	12	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	236	236	722	2	2	17	234	18	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	237	237	728	2	3	17	168	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	238	238	724	2	3	17	168	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	240	240	728	2	2	14	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	2nd Floor	242	242	726	2	2	15	168	12	40	Y	Y	Ν
Regular Classroom	Regular Classroom	3rd Floor	300A	300A	775	1	2	18	112	8	40	Y	N	Ν
Regular Classroom	Regular Classroom	3rd Floor	300B	300B	750	1	2	8	234	18	40	Y	N	Ν
Regular Classroom	Regular Classroom	3rd Floor	301	301	750	1	3	57	234	18	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	302B	302B	360	2	3	32	117	9	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	303	303	750	0	0	19	234	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	304	304	750	1	2	48	234	18	40	Y	N	Y



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Current Usage** Intended Usage Room Room Floor Plan Area (SF) Voice Data Elect. Glazed Operable Noise Window Power Smart-Location Number Room Outlets Outlets Outlets Window Window Level Stop Strip Board Number Area Area Main Regular Classroom Regular Classroom 3rd Floor 305 305 750 3 234 40 17 18 γ Ν Y 1 Y Υ 307 307 750 0 0 7 234 18 40 Ν Regular Classroom Regular Classroom 3rd Floor 3rd Floor 3 2 37 40 Y Regular Classroom Regular Classroom 308 308 920 312 24 Ν Ν 3rd Floor 2 3 24 Y Ν Ν Regular Classroom Regular Classroom 312 312 909 46 312 40 Regular Classroom Regular Classroom 3rd Floor 322 322 733 2 2 39 168 16 40 Y Ν Y 324 324 2 2 40 40 Υ Ν Υ Regular Classroom Regular Classroom 3rd Floor 729 168 16 Regular Classroom Regular Classroom 3rd Floor 326 326 722 2 3 43 40 Υ Ν Υ 168 16 2 Υ Regular Classroom Regular Classroom 3rd Floor 328 328 724 2 38 168 16 40 Υ Υ Regular Classroom Regular Classroom 3rd Floor 330 330 728 1 2 37 234 18 40 Υ Ν Υ Regular Classroom Regular Classroom 3rd Floor 332 332 727 2 3 39 168 16 40 Υ Ν Ν Υ Υ Regular Classroom Regular Classroom 3rd Floor 335 335 1.472 0 18 616 44 40 Ν 1 Regular Classroom Regular Classroom 3rd Floor 341 341 745 1 2 62 162 18 40 Υ Ν Ν 2 Υ Regular Classroom Regular Classroom 3rd Floor 343 726 2 16 40 Ν Υ 343 39 168 Regular Classroom Regular Classroom 3rd Floor 345 345 726 2 3 16 234 18 40 Υ Ν Ν Regular Classroom Regular Classroom 4th Floor 400 400 940 1 2 28 234 18 40 Υ Υ Υ Regular Classroom Regular Classroom 4th Floor 401 401 730 18 3 27 162 18 40 Υ Ν Ν Regular Classroom Regular Classroom 402A 402A 2 234 Υ Υ 730 1 19 18 40 Ν Regular Classroom Regular Classroom 4th Floor 404 404 975 5 2 28 312 24 40 Υ Υ Υ Y Υ Y Regular Classroom Regular Classroom 4th Floor 405 405 730 9 2 28 234 18 40 Regular Classroom Regular Classroom 4th Floor 406 750 12 24 234 18 40 Υ Ν Y 406 1 Y Y Regular Classroom Regular Classroom 4th Floor 6 3 234 18 Ν 407 407 730 30 40 Regular Classroom Regular Classroom 4th Floor 408 408 985 1 2 32 312 24 40 Υ Ν Ν Regular Classroom Regular Classroom 4th Floor 410 745 1 2 11 234 18 40 Υ Ν Ν 410 Regular Classroom Regular Classroom 4th Floor 418 418 722 2 2 22 168 12 40 Υ Ν Ν Regular Classroom Regular Classroom 4th Floor 420 420 722 2 3 22 234 18 40 Υ Υ Ν Regular Classroom Regular Classroom 4th Floor 422 422 969 1 3 13 224 16 40 Υ Ν Υ Υ Regular Classroom 4th Floor 424 424 728 2 2 16 234 18 40 Ν Υ Regular Classroom Regular Classroom Regular Classroom 4th Floor 425 425 728 2 3 17 168 16 40 Υ Υ Υ 2 2 Υ Regular Classroom Regular Classroom 4th Floor 427 427 725 20 168 16 40 Υ Υ 724 2 3 234 18 40 Υ Υ Regular Classroom Regular Classroom 4th Floor 429 429 18 Ν 967 3 40 Υ Υ Regular Classroom Regular Classroom 4th Floor 431 431 1 15 224 16 Ν Regular Classroom 433 433 702 2 2 26 234 40 Υ Ν Υ Regular Classroom 4th Floor 18 Υ Science Science 2nd Floor 211 211 1.212 0 3 16 351 27 40 Ν Ν Science Science 3rd Floor 313 313 1.425 1 3 38 390 24 40 Υ Υ Y Science Science 3rd Floor 319 1.333 2 3 24 429 33 40 Υ Υ Υ 319 2 3 28 36 Y Υ Ν Science Classroom Regular Classroom 3rd Floor 321 321 1.401 468 40 Y Science Lab Level 1 1.300 0 22 24 40 Ν Science Classroom 4th Floor 419 419 1 312 Ν

#### **Classroom Summary**



231 N Pine Ave Chicago, IL 60644

Co-locating on this campus are AUSTIN POLY HS, AUSTIN BUS & ENTRP HS and VOISE HS

#### **Classroom Summary**

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main														
Science Lab Level 1	Science Lab Level 1	2nd Floor	239	239	1,194	18	1	64	252	18	40	Y	Ν	N
Science Lab Level 1	Science Lab Level 1	4th Floor	411	411	1,325	4	4	28	429	33	0	Y	Ν	N
Science Lab Level 1	Science Lab Level 1	4th Floor	415	415	1,325	3	3	36	429	33	0	Y	Ν	N
Special Education	Regular Classroom	1st Floor	124	124	718	1	2	14	162	18	40	Y	Ν	N
Vacant	Science Lab Level 1	2nd Floor	215	215	1,027	0	2	24	312	24	40	Y	Ν	Ν
Vacant	Laboratory/Shop	2nd Floor	220	220	1,341	0	1	24	468	36	40	Y	Ν	N