

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

| Campus Summary      |                  |                  |                       |                     |
|---------------------|------------------|------------------|-----------------------|---------------------|
| Building Name       | Year Constructed | Number of Floors | Building Area (Sq Ft) | Assessed Need       |
| Main                | 1926             | 3                | 217,770               | \$19,696,406        |
| SITE                |                  |                  |                       | \$286,205           |
| <b>Campus Total</b> |                  |                  | <b>217,770</b>        | <b>\$19,982,611</b> |

### Building: Main

#### Category: Building Exterior

| Group           | Item - Type                          | Location         | Quantity | Unit | Rank | Cost    | Comments |
|-----------------|--------------------------------------|------------------|----------|------|------|---------|----------|
| <b>Entrance</b> |                                      |                  |          |      |      |         |          |
|                 | Entrance Control - Audio and Video   | 1                | 1        | EA   | 6    | \$702   |          |
|                 | Exterior Doors - Exterior Steel Door | 10               | 1        | EA   | 6    | \$481   |          |
|                 | Exterior Doors - Exterior Steel Door | 13               | 1        | EA   | 7    | \$0     |          |
|                 | Exterior Doors - Exterior Steel Door | 15               | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Steel Door | 16               | 4        | EA   | 6    | \$1,922 |          |
|                 | Exterior Doors - Exterior Steel Door | 17               | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Steel Door | 2                | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Steel Door | 3                | 6        | EA   | 5    | \$8,048 |          |
|                 | Exterior Doors - Exterior Steel Door | 4                | 2        | EA   | 7    | \$0     |          |
|                 | Exterior Doors - Exterior Steel Door | 5                | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Steel Door | 6                | 1        | EA   | 6    | \$481   |          |
|                 | Exterior Doors - Exterior Steel Door | 8                | 2        | EA   | 7    | \$0     |          |
|                 | Exterior Doors - Exterior Steel Door | 9                | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Steel Door | Garage Door West | 1        | EA   | 6    | \$481   |          |
|                 | Exterior Doors - Exterior Wood Door  | 1                | 2        | EA   | 5    | \$2,683 |          |
|                 | Exterior Doors - Exterior Wood Door  | 11               | 3        | EA   | 5    | \$4,024 |          |
|                 | Exterior Doors - Exterior Wood Door  | 12               | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Wood Door  | 14               | 1        | EA   | 5    | \$1,341 |          |
|                 | Exterior Doors - Exterior Wood Door  | 18               | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Wood Door  | 19               | 2        | EA   | 6    | \$961   |          |
|                 | Exterior Doors - Exterior Wood Door  | 7                | 3        | EA   | 6    | \$1,442 |          |

**Building: Main**

**Category: Building Exterior**

| Group           | Item - Type                         | Location | Quantity | Unit | Rank | Cost     | Comments |
|-----------------|-------------------------------------|----------|----------|------|------|----------|----------|
| <b>Entrance</b> |                                     |          |          |      |      |          |          |
|                 | Exterior Doors - Side lite          | 8        | 1        | EA   | 7    | \$0      |          |
|                 | Exterior Doors - Transom Lite       | 1        | 1        | EA   | 5    | \$822    |          |
|                 | Exterior Doors - Transom Lite       | 12       | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 13       | 1        | EA   | 7    | \$0      |          |
|                 | Exterior Doors - Transom Lite       | 14       | 1        | EA   | 6    | \$313    |          |
|                 | Exterior Doors - Transom Lite       | 15       | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 16       | 4        | EA   | 5    | \$3,287  |          |
|                 | Exterior Doors - Transom Lite       | 17       | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 18       | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 19       | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 2        | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 3        | 6        | EA   | 6    | \$1,880  |          |
|                 | Exterior Doors - Transom Lite       | 4        | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 5        | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Doors - Transom Lite       | 7        | 3        | EA   | 6    | \$940    |          |
|                 | Exterior Doors - Transom Lite       | 9        | 2        | EA   | 6    | \$627    |          |
|                 | Exterior Stairs - Concrete          | 1        | 60       | LF   | 6    | \$4,906  |          |
|                 | Exterior Stairs - Concrete          | 12       | 60       | LF   | 7    | \$0      |          |
|                 | Exterior Stairs - Concrete          | 15       | 10       | LF   | 6    | \$818    |          |
|                 | Exterior Stairs - Concrete          | 18       | 40       | LF   | 6    | \$3,271  |          |
|                 | Exterior Stairs - Concrete          | 2        | 15       | LF   | 7    | \$0      |          |
|                 | Exterior Stairs - Concrete          | 3        | 70       | LF   | 6    | \$5,724  |          |
|                 | Exterior Stairs - Concrete          | 5        | 60       | LF   | 6    | \$4,906  |          |
|                 | Exterior Stairs - Concrete          | 6        | 70       | LF   | 6    | \$5,724  |          |
|                 | Exterior Stairs - Concrete          | 7        | 45       | LF   | 6    | \$3,680  |          |
|                 | Exterior Stairs - Steel or Aluminum | 10       | 60       | LF   | 6    | \$231    |          |
|                 | Exterior Stairs - Stone             | 1        | 25       | LF   | 6    | \$2,825  |          |
|                 | Exterior Stairs - Stone             | 11       | 30       | LF   | 6    | \$3,390  |          |
|                 | Exterior Stairs - Stone             | 13       | 3        | LF   | 6    | \$339    |          |
|                 | Exterior Stairs - Stone             | 15       | 50       | LF   | 6    | \$5,649  |          |
|                 | Exterior Stairs - Stone             | 16       | 12       | LF   | 6    | \$1,356  |          |
|                 | Exterior Stairs - Stone             | 17       | 35       | LF   | 6    | \$3,954  |          |
|                 | Exterior Stairs - Stone             | 18       | 15       | LF   | 6    | \$1,695  |          |
|                 | Exterior Stairs - Stone             | 19       | 75       | LF   | 5    | \$20,338 |          |
|                 | Exterior Stairs - Stone             | 2        | 60       | LF   | 6    | \$6,779  |          |
|                 | Exterior Stairs - Stone             | 3        | 93       | LF   | 6    | \$10,508 |          |
|                 | Exterior Stairs - Stone             | 5        | 10       | LF   | 6    | \$1,130  |          |

**Building: Main**

**Category: Building Exterior**

| Group              | Item - Type                                     | Location        | Quantity | Unit | Rank | Cost      | Comments   |
|--------------------|---|-----------------|----------|------|------|-----------|--|
| <b>Entrance</b>    |   |                 |          |      |      |           |  |
|                    | Exterior Stairs - Stone                         | 7               | 40       | LF   | 6    | \$4,519   |  |
|                    | Exterior Stairs - Stone                         | 8               | 30       | LF   | 6    | \$3,390   |  |
|                    | Exterior Stairs - Stone                         | 9               | 85       | LF   | 6    | \$9,604   |  |
|                    | Ramp Handrail - Steel_Ramp Handrail             | 4               | 32       | LF   | 6    | \$277     |  |
|                    | Ramps - Concrete                                | 2               | 8        | LF   | 7    | \$0       |  |
|                    | Ramps - Concrete                                | 4               | 15       | LF   | 6    | \$2,254   |  |
|                    | Stair Handrail - Steel_Stair Handrail           | 12              | 10       | LF   | 6    | \$87      |  |
| <b>Foundation</b>  |   |                 |          |      |      |           |  |
|                    | Foundation - Concrete                           | Entire Building | 2,492    | LF   | 7    | \$0       |  |
|                    | Foundation - Concrete                           | Entire Building | 500      | LF   | 7    | \$0       | seepage throughout   |
|                    | Superstructure - Concrete                       | Entire Building | 211,156  | SF   | 7    | \$0       |  |
|                    | Superstructure - Concrete                       | Entire Building | 10       | SF   | 7    | \$0       | corroded rebar, spalled concrete                                   |
| <b>Lighting</b>    |   |                 |          |      |      |           |  |
|                    | Exterior Lighting - Wall Mounted                | Entire Site     | 58       | EA   | 6    | \$16,747  |  |
| <b>Roof System</b> |   |                 |          |      |      |           |  |
|                    | Chimney - Brick Chimney- Concrete/ Mortar Liner | A               | 29       | LF   | 5    | \$82,695  | no liner   |
|                    | Chimney - Brick Chimney- Concrete/ Mortar Liner | A               | 50       | LF   | 4    | \$281,598 | no liner; stepcracking, cap displaced, cracking along metal ladder |
|                    | Coping - Metal                                  | C               | 113      | LF   | 5    | \$4,777   |  |
|                    | Coping - Metal                                  | E               | 130      | LF   | 5    | \$5,495   |  |
|                    | Coping - Metal                                  | F               | 274      | LF   | 5    | \$11,582  |  |
|                    | Coping - Terra Cotta                            | A               | 461      | LF   | 5    | \$77,380  | cracking throughout  |
|                    | Coping - Terra Cotta                            | B               | 515      | LF   | 5    | \$86,445  |  |
|                    | Coping - Terra Cotta                            | C               | 276      | LF   | 5    | \$46,328  |  |
|                    | Coping - Terra Cotta                            | D               | 781      | LF   | 5    | \$131,094 |  |
|                    | Coping - Terra Cotta                            | E               | 375      | LF   | 5    | \$62,945  |  |
|                    | Coping - Terra Cotta                            | F               | 317      | LF   | 5    | \$53,210  |  |
|                    | Coping - Terra Cotta                            | G               | 328      | LF   | 5    | \$55,056  |  |
|                    | Coping - Terra Cotta                            | H               | 94       | LF   | 5    | \$15,778  |  |
|                    | Downspouts - Exterior Downspouts                | B               | 54       | LF   | 5    | \$4,361   |  |
|                    | Downspouts - Interior Downspouts                | A               | 87       | LF   | 5    | \$19,254  | all roof drains clogged  |
|                    | Downspouts - Interior Downspouts                | B               | 564      | LF   | 5    | \$124,817 | clogged  |
|                    | Downspouts - Interior Downspouts                | C               | 115      | LF   | 5    | \$25,450  | clogged  |
|                    | Downspouts - Interior Downspouts                | D               | 472      | LF   | 5    | \$104,457 | clogged  |
|                    | Downspouts - Interior Downspouts                | E               | 115      | LF   | 5    | \$25,450  | clogged  |
|                    | Downspouts - Interior Downspouts                | F               | 188      | LF   | 5    | \$41,606  | clogged  |

**Building: Main**

**Category: Building Exterior**

| Group              | Item - Type                      | Location            | Quantity | Unit | Rank | Cost      | Comments  |
|--------------------|----------------------------------|---------------------|----------|------|------|-----------|---|
| <b>Roof System</b> |                                  |                     |          |      |      |           |   |
|                    | Downspouts - Interior Downspouts | G                   | 130      | LF   | 5    | \$28,770  | clogged   |
|                    | Downspouts - Interior Downspouts | H                   | 22       | LF   | 5    | \$4,869   | clogged   |
|                    | Parapet - 16" - 30" Height       | A / Entire Building | 222      | LF   | 4    | \$125,905 | mod bit has been applied over areas of coping throughout. step cracking, open joints, bulging |
|                    | Parapet - 16" - 30" Height       | C                   | 113      | LF   | 4    | \$64,087  | step cracking, open joints, bulging   |
|                    | Parapet - 16" - 30" Height       | D                   | 158      | LF   | 4    | \$89,608  | step cracking, open joints, bulging   |
|                    | Parapet - 16" - 30" Height       | E                   | 176      | LF   | 4    | \$99,816  | step cracking, open joints, bulging   |
|                    | Parapet - 16" - 30" Height       | G                   | 328      | LF   | 4    | \$186,021 | step cracking, open joints, bulging   |
|                    | Parapet - 16" - 30" Height       | H                   | 94       | LF   | 4    | \$53,311  | step cracking, open joints, bulging   |
|                    | Parapet - Parapet < 16" Height   | A / Entire Building | 239      | LF   | 5    | \$22,109  | mod bit has been applied over areas of coping throughout                                      |
|                    | Parapet - Parapet < 16" Height   | B                   | 515      | LF   | 4    | \$252,227 | step cracking, open joints, bulging   |
|                    | Parapet - Parapet < 16" Height   | C                   | 113      | LF   | 4    | \$55,343  | step cracking, open joints, bulging   |
|                    | Parapet - Parapet < 16" Height   | E                   | 113      | LF   | 4    | \$55,343  | step cracking, open joints, bulging   |
|                    | Parapet - Parapet < 16" Height   | F                   | 317      | LF   | 4    | \$155,254 | step cracking, open joints, bulging   |
|                    | Parapet - Parapet > 30"          | C                   | 50       | LF   | 4    | \$44,680  | parapets require repointing throughout, bulging, stepcracking, open joints                    |
|                    | Parapet - Parapet > 30"          | D                   | 623      | LF   | 4    | \$556,708 | step cracking, open joints, bulging   |
|                    | Parapet - Parapet > 30"          | E                   | 86       | LF   | 4    | \$76,849  | step cracking, open joints, bulging   |
|                    | Roof Structure - Concrete        | A                   | 10,556   | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | B                   | 13,455   | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | C                   | 9,316    | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | D                   | 16,724   | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | E                   | 9,959    | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | F                   | 5,980    | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | G                   | 8,040    | SF   | 7    | \$0       |   |
|                    | Roof Structure - Concrete        | H                   | 1,309    | SF   | 7    | \$0       |   |
|                    | Roof - Asphalt Shingle           | B                   | 3,573    | SF   | 6    | \$16,401  |   |
|                    | Roof - Asphalt Shingle           | C                   | 678      | SF   | 6    | \$3,112   |   |
|                    | Roof - Asphalt Shingle           | E                   | 678      | SF   | 6    | \$3,112   |   |
|                    | Roof - Asphalt Shingle           | F                   | 1,794    | SF   | 6    | \$8,235   |   |
|                    | Roof - Modified Bitumen          | A                   | 10,556   | SF   | 5    | \$222,049 | all roof drains clogged with debris, vegetal growth   |
|                    | Roof - Modified Bitumen          | B                   | 9,882    | SF   | 5    | \$207,871 |   |
|                    | Roof - Modified Bitumen          | C                   | 8,638    | SF   | 5    | \$181,703 |   |
|                    | Roof - Modified Bitumen          | D                   | 16,724   | SF   | 5    | \$351,794 |   |
|                    | Roof - Modified Bitumen          | E                   | 9,281    | SF   | 5    | \$195,229 |   |
|                    | Roof - Modified Bitumen          | F                   | 4,186    | SF   | 5    | \$88,054  |   |
|                    | Roof - Modified Bitumen          | G                   | 8,040    | SF   | 5    | \$169,124 |   |

## Building: Main

### Category: Building Exterior

| Group              | Item - Type                  | Location                      | Quantity | Unit | Rank | Cost        | Comments  |
|--------------------|------------------------------|-------------------------------|----------|------|------|-------------|---|
| <b>Roof System</b> |                              |                               |          |      |      |             |   |
|                    | Roof - Modified Bitumen      | H                             | 400      | SF   | 4    | \$10,965    | ponding   |
|                    | Roof - Modified Bitumen      | H                             | 909      | SF   | 5    | \$19,121    |   |
| <b>Walls</b>       |                              |                               |          |      |      |             |   |
|                    | Cheek-Wall - Stone           | Entire Building               | 162      | SF   | 6    | \$1,661     |   |
|                    | Cheek-Wall - Stone           | Entire Building               | 102      | SF   | 5    | \$2,427     | bulging, cracks, spalled                            |
|                    | Exterior Walls - Brick       | Entire Building               | 55,044   | SF   | 5    | \$978,402   |   |
|                    | Exterior Walls - Brick       | Entire Building               | 620      | SF   | 4    | \$102,083   | stepcracking  |
|                    | Exterior Walls - Brick       | Entire Building               | 745      | SF   | 4    | \$122,664   | bulging below parapets, at corners and lintels      |
|                    | Exterior Walls - Brick       | Entire Building               | 100      | SF   | 3    | \$16,465    | bricks displaced 1" or more                         |
|                    | Exterior Walls - Brick       | Entire Building               | 100      | SF   | 3    | \$16,465    | bulging   |
|                    | Exterior Walls - Brick       | Entire Building               | 1,000    | SF   | 4    | \$164,650   | require repointing                                  |
|                    | Exterior Walls - Stone-Cut   | Entire Building               | 7,476    | SF   | 5    | \$100,492   |   |
|                    | Exterior Walls - Stone-Cut   | Entire Building / East Façade | 8        | SF   | 4    | \$1,703     | spalled stone                                       |
|                    | Exterior Walls - Terra Cotta | Entire Building               | 5,000    | SF   | 4    | \$2,963,175 | straps around terra cotta                           |
|                    | Exterior Walls - Terra Cotta | Entire Building               | 100      | SF   | 5    | \$1,559     | cracking  |
|                    | Exterior Walls - Terra Cotta | Entire Building               | 4        | SF   | 4    | \$2,595     | terra cotta missing                                 |
|                    | Exterior Walls - Terra Cotta | Entire Building               | 9,968    | SF   | 5    | \$118,595   |   |
| <b>Windows</b>     |                              |                               |          |      |      |             |   |
|                    | Guard - Guards wire guard    | Entire Building / 1st Floor   | 654      | SF   | 5    | \$10,026    |   |
|                    | Lintels - Concrete           | Entire Building               | 16       | LF   | 5    | \$3,610     |   |
|                    | Lintels - Steel              | Entire Building               | 902      | LF   | 4    | \$408,395   | bulging throughout                                  |
|                    | Lintels - Terra Cotta        | Entire Building               | 598      | LF   | 4    | \$201,095   | cracking, netting throughout                        |
|                    | Windows - Insulated Panel    | Entire Building               | 4,268    | SF   | 5    | \$134,515   | condition similar to that of windows                |
|                    | Windows - Sash Lexan         | Entire Building               | 10,477   | SF   | 5    | \$307,583   | weather strip deteriorated, panes damaged, graffiti |

### Building Exterior Subtotal:

**\$10,431,875**

## Building: Main

### Category: Electrical System

| Group                   | Item - Type   | Location                    | Quantity | Unit | Rank | Cost     | Comments |
|-------------------------|---|-----------------------------|----------|------|------|----------|----------|
| <b>Emergency System</b> |   |                             |          |      |      |          |          |
|                         | Automatic Transfer Switch                           | Electrical Room             | 2        | EA   | 6    | \$816    |          |
|                         | Emergency A/C Power - Auditorium and Aisle Lighting | Entire Building             | 7,220    | SF   | 2    | \$32,006 |          |
|                         | Emergency A/C Power - Corridors and Stairs          | Entire Building             | 43,270   | SF   | 6    | \$12,994 |          |
|                         | Emergency A/C Power - Gym                           | Entire Building / 2nd Floor | 11,238   | SF   | 6    | \$4,178  |          |
|                         | Emergency A/C Power - Lunchrooms                    | Entire Building / 1st Floor | 4,901    | SF   | 6    | \$1,822  |          |

**Building: Main**

**Category: Electrical System**

| Group                              | Item - Type  | Location                          | Quantity | Unit | Rank | Cost             | Comments  |
|------------------------------------|--|-----------------------------------|----------|------|------|------------------|---|
| <b>Emergency System</b>            |  |                                   |          |      |      |                  |   |
|                                    | Emergency A/C Power - Students Toilets               | Entire Building                   | 1,949    | SF   | 6    | \$725            |   |
|                                    | Emergency Generator- Outdoor- Diesel - 151 - 200 KW  | Central Courtyard                 | 1        | EA   | 6    | \$12,534         |   |
|                                    | Exit Signs - Auditorium                              | Entire Building                   | 9        | EA   | 6    | \$1,348          |   |
|                                    | Exit Signs - Corridors and Stairs                    | Entire Building                   | 55       | EA   | 6    | \$8,236          |   |
|                                    | Exit Signs - Gym                                     | Entire Building / 2nd Floor       | 5        | EA   | 6    | \$787            |   |
|                                    | Exit Signs - Lunchroom                               | Entire Building / 1st Floor       | 2        | EA   | 6    | \$299            |   |
|                                    | Exit Signs - Pool                                    | Entire Building / 1st Floor       | 2        | EA   | 6    | \$310            |   |
|                                    | Security System - CCTV                               | Entire Building                   | 211,156  | SF   | 6    | \$63,410         | Engineer said cameras are scheduled to be installed soon. |
|                                    | Security System - Intrusion Detection                | Entire Building                   | 211,156  | SF   | 6    | \$54,352         |   |
| <b>Main Service</b>                |  |                                   |          |      |      |                  |   |
|                                    | Main Electrical Service - 1200 A 120/208/3PH         | Electrical Room / Basement        | 1        | EA   | 6    | \$5,078          |   |
|                                    | Main Electrical Service - 2000 A 120/208/3PH         | Electrical Room / Basement        | 1        | EA   | 6    | \$8,232          |   |
|                                    | Main Electrical Service - 2001 to 3000 A 120/208/3PH | Electrical Room / Basement        | 1        | EA   | 6    | \$10,867         |   |
|                                    | PA System  | Entire Building                   | 211,156  | SF   | 6    | \$69,449         |   |
| <b>Power Distribution</b>          |  |                                   |          |      |      |                  |   |
|                                    | Lighting and Power Panels - 100 A                    | Entire Building / 3rd Floor       | 1        | EA   | 5    | \$0              | There are no labels on panel                              |
|                                    | Lighting and Power Panels - 100 A                    | Entire Building                   | 37       | EA   | 6    | \$11,067         |   |
|                                    | Main Distribution Panels - 400 - 600 amp             | Entire Building / Electrical Room | 3        | EA   | 6    | \$1,583          | 400 A   |
|                                    | Main Distribution Panels - Less than 400 amp         | Entire Building                   | 9        | EA   | 6    | \$4,528          |   |
|                                    | Transformers - 120/240 - 120/208                     | Entire Building / Electrical Room | 1        | EA   | 6    | \$3,021          | 150 Kva   |
| <b>Electrical System Subtotal:</b> |  |                                   |          |      |      | <b>\$307,644</b> |   |

**Building: Main**

**Category: Safty System**

| Group                         | Item - Type              | Location                    | Quantity | Unit | Rank | Cost             | Comments   |
|-------------------------------|--------------------------|-----------------------------|----------|------|------|------------------|--|
| <b>Fire Alarm</b>             |                          |                             |          |      |      |                  |  |
|                               | Fire Alarm Panel         | Entire Building / 1st Floor | 1        | EA   | 6    | \$6,406          | Gamewell system (2006); No other information available |
|                               | Fire Alarm Strobe Lights | Entire Building             | 211,156  | SF   | 6    | \$75,488         |  |
|                               | Fire Alarm_System        | Entire Building             | 211,156  | SF   | 6    | \$102,664        |  |
| <b>Safty System Subtotal:</b> |                          |                             |          |      |      | <b>\$184,558</b> |  |

**Building: Main**

## Category: Mechanical System

| Group                       | Item - Type  | Location                   | Quantity | Unit | Rank | Cost      | Comments   |
|-----------------------------|--|----------------------------|----------|------|------|-----------|--|
| <b>Air Handling Systems</b> |  |                            |          |      |      |           |  |
|                             | Air Handling Unit- Built Up- Single Zone- Steam Coils - 15001 - 25000 cfm                      | Basement                   | 1        | EA   | 5    | \$44,262  | New York Blower Company, 22000 CFM   |
|                             | Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 25001 - 35000 cfm        | Basement                   | 3        | EA   | 5    | \$166,946 | The fan is old, the housing wall is deteriorating, and the pneumatic control system is old and not functioning well.   |
|                             | Air Handling Unit- Built Up-Multi Zone- Steam Coils - 25001 - 35000                            | Basement                   | 1        | EA   | 5    | \$78,608  | Approx 22,476 CFM. The fan is old, dampers do not work well, and some bypass dampers are held open with objects.       |
|                             | Air Handling Unit- Built Up-Multi Zone- Steam Coils - Less than 8000 cfm                       | Basement                   | 1        | EA   | 5    | \$36,019  | Approx 6566 CFM. The fan is old, dampers do not work well, and some bypass dampers are held open with objects.         |
|                             | Air Handling Unit- Built Up-Multi Zone- Steam Coils - Less than 8000 cfm                       | Basement                   | 1        | EA   | 5    | \$36,019  | Approx 4,800 CFM. The fan is old, dampers do not work well, and some bypass dampers are held open with objects.        |
|                             | Air Intake   | Basement / Roof            | 3        | EA   | 6    | \$17,294  | All three units  |
|                             | Air Intake   | Basement / Roof            | 1        | EA   | 6    | \$5,765   |  |
|                             | Air Intake   | Basement / Roof            | 3        | EA   | 5    | \$22,412  |  |
|                             | Auxiliaries - 15001 - 25000 cfm  | Basement                   | 1        | EA   | 4    | \$36,420  | Steam valves are old and corroded, housing was is deteriorated   |
|                             | Auxiliaries - 25001 - 35000 cfm  | Basement                   | 1        | EA   | 4    | \$39,696  | The housing walls are deteriorating, many of the steam pipes are rusted, and the paint on the fans is chipping off.    |
|                             | Auxiliaries - 25001 - 35000 cfm  | Basement                   | 3        | EA   | 4    | \$119,089 | The housing wall is deteriorated and old, some of the steam valves are old and corroding, dampers need to be repaired. |
|                             | Auxiliaries - Less than 8000 cfm   | Basement                   | 1        | EA   | 4    | \$25,511  | The housing walls are deteriorating, many of the steam pipes are rusted, and the paint on the fans is chipping off.    |
|                             | Auxiliaries - Less than 8000 cfm   | Basement                   | 1        | EA   | 4    | \$25,511  | The housing walls are deteriorating, many of the steam pipes are rusted, and the paint on the fans is chipping off.    |
|                             | Reheat Boxes - Reheat Boxes with Steam Coil  | Basement                   | 25       | EA   | 5    | \$107,207 | Housing wall on reheat boxes is deteriorated and controls on many of the dampers are not working properly.             |
|                             | Return Duct Work - Masonry and Ducts- Missing or Existing Shaft                                | Basement / Balcony         | 100      | LF   | 5    | \$131,341 | No return duct work.   |
|                             | Return Duct Work - Masonry and Ducts- Missing or Existing Shaft                                | Basement                   | 300      | LF   | 5    | \$394,024 | There is no return duct work for any of the 3 units.   |
|                             | Return Duct Work - Masonry and Ducts- Missing or Existing Shaft                                | Basement / Entire Building | 300      | LF   | 5    | \$394,024 | No return duct work for any of the 3 units.  |
|                             | Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - Greater than 45 tons | Roof                       | 1        | EA   | 5    | \$37,963  | RTU package is heated the adjacent hw boiler.  |
|                             | Zone Dampers   | Basement                   | 30       | EA   | 5    | \$57,406  | All three units  |
|                             | Zone Dampers   | Basement                   | 71       | EA   | 5    | \$150,957 | Dampers are old, controls do not work properly   |
| <b>Boiler Systems</b>       |  |                            |          |      |      |           |  |
|                             | Boiler Auxiliary- Non Condensing Hot Water - 500 - 1000 MBH                                    | Roof                       | 1        | EA   | 5    | \$26,293  | Serves RTU   |

## Building: Main

### Category: Mechanical System

| Group                      | Item - Type  | Location                      | Quantity | Unit | Rank | Cost        | Comments  |
|----------------------------|--|-------------------------------|----------|------|------|-------------|---|
| <b>Boiler Systems</b>      |  |                               |          |      |      |             |   |
|                            | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 76 - 100 HP                   | Boiler Room                   | 1        | EA   | 5    | \$9,533     |   |
|                            | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - Greater than 300 HP           | Boiler Room                   | 2        | EA   | 5    | \$51,050    |   |
|                            | Chemical Feeder  | Boiler Room                   | 2        | EA   | 6    | \$2,156     |   |
|                            | Combustion Dampers   | Boiler Room / Basement        | 2        | EA   | 6    | \$818       |   |
|                            | Combustion Dampers   | Boiler Room                   | 1        | EA   | 6    | \$409       |   |
|                            | Condensate Pump  | Boiler Room / Basement        | 4        | EA   | 6    | \$8,084     | Pumps located all throughout basement   |
|                            | Feed Water Pumps and Tank  | Boiler Room                   | 1        | EA   | 5    | \$36,450    | 4 pumps   |
|                            | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 76 - 100 HP         | Boiler Room                   | 1        | EA   | 5    | \$9,533     |   |
|                            | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - Greater than 300 HP | Boiler Room                   | 2        | EA   | 5    | \$51,050    |   |
|                            | Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - 500 - 1000 MBH  | Roof                          | 1        | EA   | 5    | \$35,549    |   |
|                            | Piping - Condensate Pipe- Steel  | Boiler Room / Entire Building | 1,000    | LF   | 5    | \$13,099    | Piping for entire system  |
|                            | Piping - Steam Pipe- Steel   | Boiler Room / Entire Building | 1,000    | LF   | 5    | \$14,986    | Piping for entire system  |
|                            | Steam Traps  | Boiler Room / Entire Building | 1        | EA   | 4    | \$2,510     | Engineer stated he has issues with steam traps during heating                                 |
| <b>Heat Exchangers</b>     |  |                               |          |      |      |             |   |
|                            | Heat Exchanger - Steam to Hot Water Shell Type   | Boiler Room                   | 1        | EA   | 6    | \$0         |   |
| <b>Heating Devices</b>     |  |                               |          |      |      |             |   |
|                            | Fin Tube - Steam   | Entire Building               | 90       | LF   | 6    | \$849       |   |
|                            | Radiators - Steam  | Entire Building               | 95       | EA   | 5    | \$159,155   | Radiators are very old  |
|                            | Unit Heater - Electric   | 1st Floor                     | 1        | EA   | 4    | \$2,001     | Unit is very old and in poor condition  |
|                            | Unit Heater - Gas  | Boiler Room                   | 1        | EA   | 5    | \$1,527     | Unit is very old  |
|                            | Unit Heater - Steam  | Boiler Room / Basement        | 1        | EA   | 5    | \$909       | Unit is very old  |
|                            | Unit Heater - Steam  | Boiler Room                   | 1        | EA   | 5    | \$909       |   |
|                            | Wall Heater - Electric   | Entire Building               | 14       | EA   | 5    | \$7,512     |   |
|                            | Wall Heater - Electric   | Entire Building               | 8        | EA   | 6    | \$1,111     |   |
| <b>Mechanical Plumbing</b> |  |                               |          |      |      |             |   |
|                            | Hydronic Supply and Return - Galvanized  | Roof                          | 40       | LF   | 6    | \$3,093     | Piping supplies the RTU   |
| <b>Temperature Control</b> |  |                               |          |      |      |             |   |
|                            | Pneumatic System   | Entire Building               | 211,156  | SF   | 4    | \$1,099,109 | Controls are very old, many dampers are operated manually, and not all sensors are responding |
|                            | Thermostats - Pneumatic  | Entire Building               | 103      | EA   | 4    | \$75,935    | Engineer said that most thermostats do not work.  |



**Building: Main**

**Category: Mechanical System**

| Group              | Item - Type                                  | Location                    | Quantity | Unit | Rank | Cost     | Comments   |
|--------------------|--|-----------------------------|----------|------|------|----------|--|
| <b>Ventilation</b> |  |                             |          |      |      |          |  |
|                    | Exhaust Fans- Indoor - 500 - 1500 CFM        | Entire Building / Basement  | 3        | EA   | 4    | \$12,734 | Exhaust fan is more than 15 years of age and is not working. |
|                    | Exhaust Fans- Indoor - 500 - 1500 CFM        | Entire Building             | 3        | EA   | 6    | \$1,777  |  |
|                    | Exhaust Fans- Roof Mounted - 1501 - 8000 CFM | Entire Building / Roof      | 2        | EA   | 6    | \$1,185  |  |
|                    | Exhaust Fans- Roof Mounted - 500 - 1500 CFM  | Entire Building / Roof      | 1        | EA   | 6    | \$592    |  |
|                    | Lab Exhaust Hood                             | Entire Building / 3rd Floor | 1        | EA   | 6    | \$1,248  |  |
|                    | Type I Exhaust Hood- Kitchen                 | Entire Building / 1st Floor | 1        | EA   | 5    | \$4,647  |  |
|                    | Type II Exhaust Hood- Warming Kitchen        | Entire Building / 1st Floor | 1        | EA   | 6    | \$920    |  |

**Mechanical System Subtotal: \$3,563,209**

**Building: Main**

**Category: Plumbing System**

| Group               | Item - Type  | Location        | Quantity | Unit | Rank | Cost      | Comments                         |
|---------------------|--|-----------------|----------|------|------|-----------|----------------------------------|
| <b>Hot Water</b>    |  |                 |          |      |      |           |                                  |
|                     | Electric Heater - Greater than 50 KW               | Basement        | 1        | EA   | 6    | \$682     |                                  |
|                     | Steam Storage Tank - 501 - 1000 Gallons            | Boiler Room     | 1        | EA   | 5    | \$2,249   |                                  |
| <b>Piping</b>       |  |                 |          |      |      |           |                                  |
|                     | Domestic Piping-Cold Water from Risers to Fixtures | Entire Building | 211,156  | SF   | 6    | \$42,273  |                                  |
|                     | Domestic Piping-Cold Water Horizontal Lines        | Entire Building | 211,156  | SF   | 6    | \$51,332  |                                  |
|                     | Domestic Piping-Cold Water Risers                  | Entire Building | 211,156  | SF   | 6    | \$39,254  |                                  |
|                     | Domestic Piping-Hot Water from Risers to Fixtures  | Entire Building | 211,156  | SF   | 6    | \$33,215  |                                  |
|                     | Domestic Piping-Hot Water Horizontal Lines         | Entire Building | 211,156  | SF   | 6    | \$39,254  |                                  |
|                     | Domestic Piping-Hot Water Return Lines             | Entire Building | 211,156  | SF   | 6    | \$30,195  |                                  |
|                     | Domestic Piping-Hot Water Return Risers            | Entire Building | 211,156  | SF   | 6    | \$30,195  |                                  |
|                     | Sanitary Piping                                    | Entire Building | 211,156  | SF   | 6    | \$193,250 |                                  |
|                     | Storm Piping                                       | Entire Building | 211,156  | SF   | 6    | \$184,191 |                                  |
|                     | Vent Piping  | Entire Building | 211,156  | SF   | 6    | \$141,918 |                                  |
| <b>Pool Systems</b> |  |                 |          |      |      |           |                                  |
|                     | Pool Drain Piping                                  | Basement        | 60       | LF   | 6    | \$1,718   |                                  |
|                     | Pool Filtration System including Pump              | Basement        | 1        | EA   | 6    | \$12,330  |                                  |
|                     | Pool Hot Water Heater - Steam Heat Exchanger       | Basement        | 1        | EA   | 6    | \$0       |                                  |
|                     | Pool Supply and Return Piping                      | Basement        | 120      | LF   | 6    | \$5,766   |                                  |
| <b>Pumps</b>        |  |                 |          |      |      |           |                                  |
|                     | Pumps - Domestic Booster Pump-Simplex              | Basement        | 1        | EA   | 6    | \$1,446   | No information available on pump |

**Building: Main**

**Category: Plumbing System**

| Group        | Item - Type            | Location | Quantity | Unit | Rank | Cost    | Comments |
|--------------|------------------------|----------|----------|------|------|---------|----------|
| <b>Pumps</b> |                        |          |          |      |      |         |          |
|              | Pumps - Ejector-Duplex | Basement | 2        | EA   | 6    | \$2,774 |          |
|              | Pumps - Sump-Duplex    | Basement | 2        | EA   | 6    | \$2,774 |          |
|              | Pumps - Sump-Simplex   | Basement | 1        | EA   | 6    | \$745   |          |

**Plumbing System Subtotal:**

**\$815,562**

**Building: Main**

**Category: Classrooms**

| Group                                      | Item - Type                 | Location | Quantity | Unit | Rank | Cost    | Comments                 |
|--|-----------------------------|----------|----------|------|------|---------|--------------------------|
| <b>Classroom #018 - Weight Rm (Weight)</b> |                             |          |          |      |      |         |                          |
|  | Ceiling - Exposed           | Basement | 1,118    | SF   | 4    | \$5,100 | damaged and deteriorated |
|  | Doors - Wood Doors inclu hw | Basement | 1        | EA   | 4    | \$3,413 | end of serviceable life. |
|  | Floor - Concrete            | Basement | 1,118    | SF   | 5    | \$1,918 |                          |
|  | Lighting - Pendent/Surface  | Basement | 1        | EA   | 6    | \$124   |                          |
|  | Lighting - Pendent/Surface  | Basement | 6        | EA   | 5    | \$1,095 |                          |
|  | Storage/ Closet             | Basement | 80       | SF   | 6    | \$580   |                          |
|  | Walls - Concrete Block      | Basement | 1,450    | SF   | 6    | \$4,251 |                          |

**Classroom #021 (Unsafe/Unusable Condition)**

|  |                             |          |       |    |   |          |   |
|--|-----------------------------|----------|-------|----|---|----------|---|
|  | Ceiling - Exposed           | Basement | 1,132 | SF | 5 | \$3,108  | peeling paint                               |
|  | Doors - Wood Doors inclu hw | Basement | 2     | EA | 6 | \$602    |   |
|  | Floor - Carpet              | Basement | 1,132 | SF | 3 | \$10,409 | standing water in nw corner. Mildew odor.   |
|  | Lighting - Pendent/Surface  | Basement | 12    | EA | 6 | \$1,487  |   |
|  | Walls - Concrete Block      | Basement | 1,438 | SF | 4 | \$51,552 | peeling paint + signs of water infiltration |

**Classroom #106 (Computer Lab)**

|  |                             |           |       |    |   |         |  |
|--|-----------------------------|-----------|-------|----|---|---------|--|
|  | AC Units                    | 1st Floor | 2     | EA | 6 | \$991   |  |
|  | Casework                    | 1st Floor | 15    | LF | 6 | \$379   |  |
|  | Ceiling - Lay-in            | 1st Floor | 1,165 | SF | 6 | \$3,498 |  |
|  | Charging Station            | 1st Floor | 2     | EA | 7 | \$0     |  |
|  | Doors - Wood Doors inclu hw | 1st Floor | 1     | EA | 5 | \$1,174 |  |
|  | Floor - Carpet              | 1st Floor | 1,165 | SF | 7 | \$0     |  |
|  | Lighting - Lay-in           | 1st Floor | 33    | EA | 7 | \$0     |  |
|  | Storage/ Closet             | 1st Floor | 8     | SF | 6 | \$58    |  |
|  | Walls - Plaster/Drywall     | 1st Floor | 1,167 | SF | 7 | \$0     |  |

**Classroom #110 (Regular Classroom)**

|  |          |           |   |    |   |       |  |
|--|----------|-----------|---|----|---|-------|--|
|  | AC Units | 2nd Floor | 1 | EA | 6 | \$496 |  |
|--|----------|-----------|---|----|---|-------|--|

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                    | Location  | Quantity | Unit | Rank | Cost     | Comments  |
|---|--------------------------------|-----------|----------|------|------|----------|---|
| <b>Classroom #110 (Regular Classroom)</b> |                                |           |          |      |      |          |   |
|   | Casework                       | 2nd Floor | 8        | LF   | 6    | \$202    |   |
|   | Ceiling - Lay-in               | 2nd Floor | 662      | SF   | 6    | \$1,988  |   |
|   | Chalk Board                    | 2nd Floor | 55       | LF   | 4    | \$5,049  | Obsolete Material.  |
|   | Doors - Transom Window         | 2nd Floor | 9        | SF   | 6    | \$152    |   |
|   | Doors - Wood Doors inclu hw    | 2nd Floor | 1        | EA   | 6    | \$301    |   |
|   | Floor - Tile                   | 2nd Floor | 662      | SF   | 6    | \$1,448  |   |
|   | Lighting - Lay-in              | 2nd Floor | 18       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall        | 2nd Floor | 30       | SF   | 4    | \$441    | Cracking and peeling paint at door frame.                                   |
|   | Walls - Plaster/Drywall        | 2nd Floor | 900      | SF   | 6    | \$2,484  |   |
| <b>Classroom #119 (Special Program)</b>   |                                |           |          |      |      |          |   |
|   | AC Units                       | 1st Floor | 2        | EA   | 6    | \$991    |   |
|   | Casework                       | 1st Floor | 19       | LF   | 5    | \$3,973  |   |
|   | Ceiling - Exposed              | 1st Floor | 1,010    | SF   | 6    | \$1,502  |   |
|   | Chalk Board                    | 1st Floor | 8        | LF   | 4    | \$734    | Obsolete Material.  |
|   | Doors - Transom Window         | 1st Floor | 9        | SF   | 6    | \$152    |   |
|   | Doors - Wood Doors inclu hw    | 1st Floor | 1        | EA   | 6    | \$301    |   |
|   | Floor - Wood                   | 1st Floor | 1,010    | SF   | 6    | \$7,120  |   |
|   | Lighting - Pendent/Surface     | 1st Floor | 20       | EA   | 7    | \$0      |   |
|   | Marker Board                   | 1st Floor | 6        | LF   | 6    | \$129    |   |
|   | Storage/ Closet                | 1st Floor | 105      | SF   | 5    | \$1,694  |   |
|   | Walls - Plaster/Drywall        | 1st Floor | 1,032    | SF   | 6    | \$2,848  |   |
|   | Walls - Structural Glazed Tile | 1st Floor | 280      | SF   | 6    | \$881    |   |
|   | Work Sink                      | 1st Floor | 1        | EA   | 6    | \$379    | One triple sink.  |
| <b>Classroom #122 (Regular Classroom)</b> |                                |           |          |      |      |          |   |
|   | AC Units                       | 1st Floor | 2        | EA   | 7    | \$0      |   |
|   | Casework                       | 1st Floor | 14       | LF   | 5    | \$2,927  |   |
|   | Ceiling - Lay-in               | 1st Floor | 1,450    | SF   | 4    | \$14,743 | water damage throughout, warped tiles, ceiling framing needs to be painted. |
|   | Chalk Board                    | 1st Floor | 27       | LF   | 4    | \$2,479  | Obsolete Material.  |
|   | Doors - Transom Window         | 1st Floor | 9        | SF   | 6    | \$152    |   |
|   | Doors - Wood Doors inclu hw    | 1st Floor | 1        | EA   | 5    | \$1,174  |   |
|   | Floor - Tile                   | 1st Floor | 50       | SF   | 4    | \$649    | under drinking fountain- warped and deteriorated                            |
|   | Floor - Tile                   | 1st Floor | 1,400    | SF   | 6    | \$3,063  |   |
|   | Lighting - Lay-in              | 1st Floor | 33       | EA   | 7    | \$0      |   |
|   | Storage/ Closet                | 1st Floor | 115      | SF   | 6    | \$834    |   |
|   | Walls - Plaster/Drywall        | 1st Floor | 765      | SF   | 6    | \$2,111  |   |
|   | Walls - Structural Glazed Tile | 1st Floor | 725      | SF   | 6    | \$2,281  |   |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                    | Location  | Quantity | Unit | Rank | Cost    | Comments  |
|---|--------------------------------|-----------|----------|------|------|---------|---|
| <b>Classroom #122 (Regular Classroom)</b> |                                |           |          |      |      |         |   |
| <b>Classroom #124 (Regular Classroom)</b> |                                |           |          |      |      |         |   |
|   | AC Units                       | 2nd Floor | 2        | EA   | 7    | \$0     |   |
|   | AC Units                       |           | 2        | EA   | 7    | \$0     |   |
|   | Casework                       | 2nd Floor | 14       | LF   | 6    | \$354   |   |
|   | Casework                       |           | 14       | LF   | 6    | \$354   |   |
|   | Ceiling - Lay-in               | 2nd Floor | 570      | SF   | 6    | \$1,712 |   |
|   | Ceiling - Lay-in               | 2nd Floor | 100      | SF   | 4    | \$1,133 | damaged/ displaced ceiling tiles                  |
|   | Ceiling - Lay-in               |           | 100      | SF   | 4    | \$1,133 | damaged/ displaced ceiling tiles                  |
|   | Ceiling - Lay-in               |           | 570      | SF   | 6    | \$1,712 |   |
|   | Chalk Board                    | 2nd Floor | 23       | LF   | 4    | \$2,112 |   |
|   | Chalk Board                    |           | 23       | LF   | 4    | \$2,112 |   |
|   | Doors - Side-lite              | 2nd Floor | 220      | SF   | 7    | \$0     | storefront  |
|   | Doors - Side-lite              |           | 220      | SF   | 7    | \$0     | storefront  |
|   | Doors - Wood Doors inclu hw    | 2nd Floor | 2        | EA   | 5    | \$2,348 |   |
|   | Doors - Wood Doors inclu hw    |           | 2        | EA   | 5    | \$2,348 |   |
|   | Floor - Tile                   | 2nd Floor | 670      | SF   | 5    | \$3,008 |   |
|   | Floor - Tile                   |           | 670      | SF   | 5    | \$3,008 |   |
|   | Lighting - Lay-in              | 2nd Floor | 18       | EA   | 7    | \$0     |   |
|   | Lighting - Lay-in              |           | 18       | EA   | 7    | \$0     |   |
|   | Walls - Plaster/Drywall        | 2nd Floor | 375      | SF   | 6    | \$1,035 |   |
|   | Walls - Plaster/Drywall        |           | 375      | SF   | 6    | \$1,035 |   |
|   | Walls - Structural Glazed Tile | 2nd Floor | 95       | SF   | 6    | \$299   | glazed brick                                      |
|   | Walls - Structural Glazed Tile |           | 95       | SF   | 6    | \$299   | glazed bricks                                     |
| <b>Classroom #125 (Store Room)</b>        |                                |           |          |      |      |         |   |
|   | AC Units                       | 1st Floor | 1        | EA   | 7    | \$0     |   |
|   | Casework                       | 1st Floor | 10       | LF   | 6    | \$253   |   |
|   | Ceiling - Lay-in               | 1st Floor | 660      | SF   | 6    | \$1,982 |   |
|   | Chalk Board                    | 1st Floor | 14       | LF   | 4    | \$1,285 |   |
|   | Doors - Wood Doors inclu hw    | 1st Floor | 3        | EA   | 6    | \$903   |   |
|   | Floor - Tile                   | 1st Floor | 660      | SF   | 6    | \$1,444 |   |
|   | Lighting - Lay-in              | 1st Floor | 15       | EA   | 7    | \$0     |   |
|   | Walls - Plaster/Drywall        | 1st Floor | 620      | SF   | 6    | \$1,711 |   |
|   | Walls - Structural Glazed Tile | 1st Floor | 185      | SF   | 6    | \$582   | glazed brick                                      |
| <b>Classroom #126 (Regular Classroom)</b> |                                |           |          |      |      |         |   |
|   | AC Units                       | 1st Floor | 1        | EA   | 3    | \$6,086 | unit is not supported properly per CPS standards. |
|   | AC Units                       |           | 1        | EA   | 5    | \$1,826 |   |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                    | Location  | Quantity | Unit | Rank | Cost    | Comments                                   |
|---|--------------------------------|-----------|----------|------|------|---------|--|
| <b>Classroom #126 (Regular Classroom)</b> |                                |           |          |      |      |         |  |
|   | Casework                       | 1st Floor | 12       | LF   | 5    | \$2,509 |  |
|   | Casework                       |           | 12       | LF   | 5    | \$2,509 |  |
|   | Ceiling - Lay-in               | 1st Floor | 970      | SF   | 6    | \$2,913 |  |
|   | Ceiling - Lay-in               |           | 970      | SF   | 6    | \$2,913 |  |
|   | Chalk Board                    | 1st Floor | 8        | LF   | 4    | \$734   | Obsolete Material.                         |
|   | Chalk Board                    |           | 8        | LF   | 4    | \$734   |  |
|   | Doors - Transom Window         | 1st Floor | 9        | SF   | 6    | \$152   |  |
|   | Doors - Transom Window         |           | 9        | SF   | 6    | \$152   |  |
|   | Doors - Wood Doors inclu hw    | 1st Floor | 1        | EA   | 6    | \$301   |  |
|   | Doors - Wood Doors inclu hw    |           | 1        | EA   | 6    | \$301   |  |
|   | Floor - Tile                   | 1st Floor | 970      | SF   | 5    | \$4,355 |  |
|   | Floor - Tile                   |           | 970      | SF   | 5    | \$4,355 |  |
|   | Lighting - Lay-in              | 1st Floor | 21       | EA   | 6    | \$2,498 |  |
|   | Lighting - Lay-in              |           | 21       | EA   | 6    | \$2,498 |  |
|   | Walls - Plaster/Drywall        | 1st Floor | 10       | SF   | 4    | \$147   | evidence of previous leak; moisture damage |
|   | Walls - Plaster/Drywall        | 1st Floor | 575      | SF   | 6    | \$1,587 |  |
|   | Walls - Plaster/Drywall        |           | 575      | SF   | 6    | \$1,587 |  |
|   | Walls - Plaster/Drywall        |           | 10       | SF   | 4    | \$147   | evidence of previous leak; moisture damage |
|   | Walls - Structural Glazed Tile | 1st Floor | 560      | SF   | 6    | \$1,762 |  |
|   | Walls - Structural Glazed Tile |           | 560      | SF   | 6    | \$1,762 |  |
|   | Work Sink                      | 1st Floor | 1        | EA   | 6    | \$379   | one triple sink.                           |
|   | Work Sink                      |           | 1        | EA   | 6    | \$379   |  |
| <b>Classroom #132 (Store Room)</b>        |                                |           |          |      |      |         |  |
|   | Casework                       | 1st Floor | 8        | LF   | 5    | \$1,673 |  |
|   | Ceiling - Lay-in               | 1st Floor | 700      | SF   | 6    | \$2,102 |  |
|   | Chalk Board                    | 1st Floor | 48       | LF   | 4    | \$4,407 | Obsolete Material.                         |
|   | Doors - Transom Window         | 1st Floor | 9        | SF   | 6    | \$152   |  |
|   | Doors - Wood Doors inclu hw    | 1st Floor | 1        | EA   | 5    | \$1,174 |  |
|   | Floor - Tile                   | 1st Floor | 700      | SF   | 6    | \$1,532 |  |
|   | Lighting - Lay-in              | 1st Floor | 18       | EA   | 6    | \$2,142 |  |
|   | Walls - Plaster/Drywall        | 1st Floor | 900      | SF   | 5    | \$6,821 |  |
| <b>Classroom #135 (Faculty Lounge)</b>    |                                |           |          |      |      |         |  |
|   | Casework                       | 1st Floor | 8        | LF   | 5    | \$1,673 |  |
|   | Ceiling - Lay-in               | 1st Floor | 690      | SF   | 7    | \$0     |  |
|   | Chalk Board                    | 1st Floor | 42       | LF   | 4    | \$3,856 | Partially covered; obsolete material.      |
|   | Doors - Wood Doors inclu hw    | 1st Floor | 2        | EA   | 6    | \$602   |  |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments                                      |
|---|-----------------------------|-----------|----------|------|------|----------|---|
| <b>Classroom #135 (Faculty Lounge)</b>    |                             |           |          |      |      |          |   |
|   | Floor - Tile                | 1st Floor | 690      | SF   | 6    | \$1,510  |   |
|   | Lighting - Lay-in           | 1st Floor | 18       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall     | 1st Floor | 10       | SF   | 4    | \$147    | cracking around doorframe                     |
|   | Walls - Plaster/Drywall     | 1st Floor | 865      | SF   | 6    | \$2,387  |   |
| <b>Classroom #137 (Regular Classroom)</b> |                             |           |          |      |      |          |   |
|   | Casework                    | 1st Floor | 8        | LF   | 5    | \$1,673  |   |
|   | Ceiling - Lay-in            | 1st Floor | 680      | SF   | 7    | \$0      |   |
|   | Chalk Board                 | 1st Floor | 48       | LF   | 4    | \$4,407  |   |
|   | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 5    | \$1,174  |   |
|   | Floor - Tile                | 1st Floor | 680      | SF   | 6    | \$1,488  |   |
|   | Lighting - Lay-in           | 1st Floor | 18       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall     | 1st Floor | 815      | SF   | 6    | \$2,249  |   |
| <b>Classroom #139 (Music Room)</b>        |                             |           |          |      |      |          |   |
|   | AC Units                    | 1st Floor | 1        | EA   | 7    | \$0      |   |
|   | Casework                    | 1st Floor | 55       | LF   | 5    | \$11,499 | Chipped wood doors, missing casework drawers. |
|   | Ceiling - Lay-in            | 1st Floor | 1,015    | SF   | 7    | \$0      |   |
|   | Chalk Board                 | 1st Floor | 12       | LF   | 4    | \$1,102  | Obsolete Material.                            |
|   | Doors - Transom Window      | 1st Floor | 9        | SF   | 6    | \$152    |   |
|   | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301    |   |
|   | Floor - Tile                | 1st Floor | 1,015    | SF   | 6    | \$2,221  |   |
|   | Lighting - Lay-in           | 1st Floor | 29       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall     | 1st Floor | 920      | SF   | 6    | \$2,539  |   |
|   | Walls - Plaster/Drywall     | 1st Floor | 250      | SF   | 5    | \$1,105  |   |
| <b>Classroom #141 (Music Room)</b>        |                             |           |          |      |      |          |   |
|   | AC Units                    | 1st Floor | 1        | EA   | 7    | \$0      |   |
|   | Casework                    | 1st Floor | 18       | LF   | 5    | \$3,763  |   |
|   | Ceiling - Lay-in            | 1st Floor | 1,175    | SF   | 6    | \$3,529  |   |
|   | Ceiling - Lay-in            | 1st Floor | 20       | SF   | 4    | \$281    | water damage.                                 |
|   | Chalk Board                 | 1st Floor | 24       | LF   | 4    | \$2,203  | Obsolete Material.                            |
|   | Doors - Transom Window      | 1st Floor | 1        | SF   | 6    | \$17     |   |
|   | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301    |   |
|   | Floor - Tile                | 1st Floor | 1,195    | SF   | 5    | \$5,366  |   |
|   | Lighting - Lay-in           | 1st Floor | 35       | EA   | 7    | \$0      |   |
|   | Storage/ Closet             | 1st Floor | 70       | SF   | 6    | \$508    |   |
|   | Walls - Plaster/Drywall     | 1st Floor | 1,080    | SF   | 6    | \$2,981  |   |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments   |
|---|-----------------------------|-----------|----------|------|------|---------|------------|
| <b>Classroom #205 (Regular Classroom)</b> |                             |           |          |      |      |         |            |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |            |
|   | Ceiling - Lay-in            | 2nd Floor | 552      | SF   | 7    | \$0     |            |
|   | Chalk Board                 | 2nd Floor | 20       | LF   | 4    | \$1,836 |            |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |            |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |            |
|   | Floor - Tile/Sheet          | 2nd Floor | 552      | SF   | 5    | \$2,479 |            |
|   | Lighting - Lay-in           | 2nd Floor | 15       | EA   | 7    | \$0     |            |
|   | Walls - Metal Panel         | 2nd Floor | 258      | SF   | 7    | \$0     | Glass Wall |
|   | Walls - Plaster/Drywall     | 2nd Floor | 590      | SF   | 6    | \$1,628 |            |
| <b>Classroom #206 (Regular Classroom)</b> |                             |           |          |      |      |         |            |
|   | Casework                    | 2nd Floor | 18       | LF   | 6    | \$455   |            |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |            |
|   | Chalk Board                 | 2nd Floor | 20       | LF   | 4    | \$1,836 |            |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |            |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |            |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 7    | \$0     |            |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |            |
|   | Work Sink                   | 2nd Floor | 1        | EA   | 6    | \$379   |            |
| <b>Classroom #207 (Regular Classroom)</b> |                             |           |          |      |      |         |            |
|   | Ceiling - Lay-in            | 2nd Floor | 552      | SF   | 7    | \$0     |            |
|   | Chalk Board                 | 2nd Floor | 26       | LF   | 4    | \$2,387 |            |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |            |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |            |
|   | Floor - Tile/Sheet          | 2nd Floor | 552      | SF   | 5    | \$2,479 |            |
|   | Lighting - Lay-in           | 2nd Floor | 15       | EA   | 7    | \$0     |            |
|   | Walls - Metal Panel         | 2nd Floor | 258      | SF   | 7    | \$0     | Glass Wall |
|   | Walls - Plaster/Drywall     | 2nd Floor | 590      | SF   | 7    | \$0     |            |
| <b>Classroom #208 (Regular Classroom)</b> |                             |           |          |      |      |         |            |
|   | AC Units                    |           | 1        | EA   | 6    | \$496   |            |
|   | Casework                    |           | 12       | LF   | 6    | \$303   |            |
|   | Ceiling - Lay-in            |           | 684      | SF   | 7    | \$0     |            |
|   | Chalk Board                 |           | 28       | LF   | 4    | \$2,571 |            |
|   | Doors - Wood Doors inclu hw |           | 2        | EA   | 5    | \$2,348 |            |
|   | Floor - Tile/Sheet          |           | 684      | SF   | 6    | \$685   |            |
|   | Lighting - Lay-in           |           | 21       | EA   | 7    | \$0     |            |
|   | Walls - Plaster/Drywall     |           | 967      | SF   | 6    | \$2,669 |            |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #208 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
| <b>Classroom #209 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |          |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 7    | \$0     |          |
|   | Chalk Board                 | 2nd Floor | 26       | LF   | 4    | \$2,387 |          |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |          |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |          |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |          |
| <b>Classroom #210 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |          |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |          |
|   | Chalk Board                 | 2nd Floor | 34       | LF   | 4    | \$3,121 |          |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |          |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 7    | \$0     |          |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |          |
|   | Work Sink                   | 2nd Floor | 1        | EA   | 6    | \$379   |          |
| <b>Classroom #211 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | AC Units                    | 2nd Floor | 1        | EA   | 6    | \$496   |          |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |          |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 7    | \$0     |          |
|   | Chalk Board                 | 2nd Floor | 49       | LF   | 4    | \$4,498 |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |          |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |          |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |          |
| <b>Classroom #213 (Computer Lab)</b>      |                             |           |          |      |      |         |          |
|   | AC Units                    | 2nd Floor | 1        | EA   | 6    | \$496   |          |
|   | Casework                    | 2nd Floor | 42       | LF   | 5    | \$8,781 |          |
|   | Ceiling - Lay-in            | 2nd Floor | 782      | SF   | 6    | \$2,348 |          |
|   | Chalk Board                 | 2nd Floor | 15       | LF   | 4    | \$1,377 |          |
|   | Doors - Transom Window      | 2nd Floor | 16       | SF   | 5    | \$677   |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |          |



**Building: Main**

**Category: Classrooms**

| Group                                       | Item - Type                     | Location  | Quantity | Unit | Rank | Cost     | Comments  |
|---|---------------------------------|-----------|----------|------|------|----------|---|
| <b>Classroom #213 (Computer Lab)</b>        |                                 |           |          |      |      |          |   |
|   | Floor - Tile/Sheet              | 2nd Floor | 782      | SF   | 6    | \$783    |   |
|   | Lighting - Lay-in               | 2nd Floor | 21       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall         | 2nd Floor | 962      | SF   | 6    | \$2,655  |   |
| <b>Classroom #217 (Computer Lab)</b>        |                                 |           |          |      |      |          |   |
|   | AC Units                        | 2nd Floor | 1        | EA   | 6    | \$496    |   |
|   | AC Units                        | 2nd Floor | 1        | EA   | 4    | \$6,086  | in state of disrepair, does not appear cost effective to repair |
|   | Casework                        | 2nd Floor | 42       | LF   | 5    | \$8,781  |   |
|   | Ceiling - Lay-in                | 2nd Floor | 782      | SF   | 6    | \$2,348  |   |
|   | Chalk Board                     | 2nd Floor | 15       | LF   | 4    | \$1,377  |   |
|   | Charging Station                | 2nd Floor | 3        | EA   | 7    | \$0      |   |
|   | Doors - Transom Window          | 2nd Floor | 16       | SF   | 5    | \$677    |   |
|   | Doors - Wood Doors inclu hw     | 2nd Floor | 2        | EA   | 5    | \$2,348  |   |
|   | Floor - Tile/Sheet              | 2nd Floor | 782      | SF   | 6    | \$783    |   |
|   | Lighting - Lay-in               | 2nd Floor | 21       | EA   | 6    | \$2,498  |   |
|   | Walls - Plaster/Drywall         | 2nd Floor | 962      | SF   | 6    | \$2,655  |   |
|   | Wireless System                 | 2nd Floor | 1        | EA   | 7    | \$0      | WAP   |
|   | Work Sink                       | 2nd Floor | 2        | EA   | 6    | \$758    |   |
| <b>Classroom #222 (Science Lab Level 3)</b> |                                 |           |          |      |      |          |   |
|   | AC Units                        | 2nd Floor | 1        | EA   | 6    | \$496    |   |
|   | Casework                        | 2nd Floor | 68       | LF   | 5    | \$14,217 |   |
|   | Ceiling - Lay-in                | 2nd Floor | 912      | SF   | 6    | \$2,739  |   |
|   | Chalk Board                     | 2nd Floor | 12       | LF   | 4    | \$1,102  |   |
|   | Doors - Steel Doors incl hw     | 2nd Floor | 1        | EA   | 6    | \$301    |   |
|   | Doors - Transom Window          | 2nd Floor | 20       | SF   | 7    | \$0      |   |
|   | Doors - Wood Doors inclu hw     | 2nd Floor | 2        | EA   | 5    | \$2,348  |   |
|   | Eye Wash Station                | 2nd Floor | 1        | EA   | 4    | \$3,018  | Most parts missing  |
|   | Floor - Concrete Epoxy/ Painted | 2nd Floor | 912      | SF   | 7    | \$0      |   |
|   | Gas Line                        | 2nd Floor | 1        | EA   | 6    | \$509    |   |
|   | Lighting - Lay-in               | 2nd Floor | 27       | EA   | 7    | \$0      |   |
|   | Storage/ Closet                 | 2nd Floor | 15       | SF   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall         | 2nd Floor | 1,140    | SF   | 6    | \$3,146  |   |
|   | Work Sink                       | 2nd Floor | 3        | EA   | 5    | \$4,523  | Controls need replacing   |
| <b>Classroom #223 (Office)</b>              |                                 |           |          |      |      |          |   |
|   | AC Units                        |           | 1        | EA   | 7    | \$0      |   |
|   | Ceiling - Lay-in                |           | 912      | SF   | 7    | \$0      |   |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments                                  |
|---|-----------------------------|-----------|----------|------|------|----------|---|
| <b>Classroom #223 (Office)</b>            |                             |           |          |      |      |          |   |
|   | Doors - Wood Doors inclu hw |           | 2        | EA   | 5    | \$2,348  | corridor doors covered with metal plating |
|   | Doors - Wood Doors inclu hw |           | 2        | EA   | 7    | \$0      |   |
|   | Floor - Tile/Sheet          |           | 912      | SF   | 5    | \$4,095  |   |
|   | Lighting - Lay-in           |           | 24       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall     |           | 1,170    | SF   | 7    | \$0      |   |
| <b>Classroom #225 (Art Room)</b>          |                             |           |          |      |      |          |   |
|   | AC Units                    | 2nd Floor | 1        | EA   | 7    | \$0      |   |
|   | Casework                    | 2nd Floor | 73       | LF   | 6    | \$1,844  |   |
|   | Ceiling - Lay-in            | 2nd Floor | 912      | SF   | 7    | \$0      |   |
|   | Chalk Board                 | 2nd Floor | 15       | LF   | 4    | \$1,377  |   |
|   | Doors - Transom Window      | 2nd Floor | 20       | SF   | 7    | \$0      |   |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348  |   |
|   | Eye Wash Station            | 2nd Floor | 1        | EA   | 6    | \$336    |   |
|   | Floor - Tile/Sheet          | 2nd Floor | 912      | SF   | 6    | \$913    |   |
|   | Gas Line                    | 2nd Floor | 1        | EA   | 6    | \$509    |   |
|   | Lighting - Lay-in           | 2nd Floor | 27       | EA   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,140    | SF   | 5    | \$8,640  |   |
|   | Work Sink                   | 2nd Floor | 2        | EA   | 5    | \$3,016  | Contrlrs need replacing                   |
| <b>Classroom #226 (Science Classroom)</b> |                             |           |          |      |      |          |   |
|   | AC Units                    | 2nd Floor | 1        | EA   | 6    | \$496    |   |
|   | Casework                    | 2nd Floor | 68       | LF   | 5    | \$14,217 |   |
|   | Ceiling - Lay-in            | 2nd Floor | 912      | SF   | 6    | \$2,739  |   |
|   | Chalk Board                 | 2nd Floor | 12       | LF   | 4    | \$1,102  |   |
|   | Doors - Transom Window      | 2nd Floor | 20       | SF   | 7    | \$0      |   |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602    |   |
|   | Eye Wash Station            | 2nd Floor | 1        | EA   | 5    | \$844    |   |
|   | Floor - Tile/Sheet          | 2nd Floor | 912      | SF   | 5    | \$4,095  |   |
|   | Lighting - Lay-in           | 2nd Floor | 27       | EA   | 7    | \$0      |   |
|   | Storage/ Closet             | 2nd Floor | 15       | SF   | 7    | \$0      |   |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,140    | SF   | 6    | \$3,146  | 10 sf of wall needs patching              |
|   | Work Sink                   | 2nd Floor | 3        | EA   | 5    | \$4,523  | Controls needed for sinks                 |
| <b>Classroom #227 (Regular Classroom)</b> |                             |           |          |      |      |          |   |
|   | Casework                    | 2nd Floor | 23       | LF   | 5    | \$4,809  |   |
|   | Ceiling - Lay-in            | 2nd Floor | 747      | SF   | 6    | \$2,243  |   |
|   | Chalk Board                 | 2nd Floor | 36       | LF   | 4    | \$3,305  |   |
|   | Doors - Transom Window      | 2nd Floor | 5        | SF   | 7    | \$0      |   |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                  |
|---|-----------------------------|-----------|----------|------|------|---------|---------------------------|
| <b>Classroom #227 (Regular Classroom)</b> |                             |           |          |      |      |         |                           |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |                           |
|   | Floor - Tile/Sheet          | 2nd Floor | 747      | SF   | 6    | \$748   |                           |
|   | Lighting - Lay-in           | 2nd Floor | 22       | EA   | 7    | \$0     |                           |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,012    | SF   | 6    | \$2,793 |                           |
| <b>Classroom #229 (Regular Classroom)</b> |                             |           |          |      |      |         |                           |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |                           |
|   | Ceiling - Lay-in            | 2nd Floor | 708      | SF   | 7    | \$0     |                           |
|   | Chalk Board                 | 2nd Floor | 52       | LF   | 4    | \$4,774 |                           |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |                           |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |                           |
|   | Floor - Tile/Sheet          | 2nd Floor | 708      | SF   | 6    | \$709   |                           |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 6    | \$2,142 | Two lights missing lenses |
|   | Walls - Plaster/Drywall     | 2nd Floor | 930      | SF   | 6    | \$2,567 |                           |
| <b>Classroom #230 (Regular Classroom)</b> |                             |           |          |      |      |         |                           |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                           |
|   | Ceiling - Lay-in            | 2nd Floor | 708      | SF   | 7    | \$0     |                           |
|   | Chalk Board                 | 2nd Floor | 35       | LF   | 4    | \$3,213 |                           |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |                           |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |                           |
|   | Floor - Tile/Sheet          | 2nd Floor | 708      | SF   | 5    | \$3,179 |                           |
|   | Lighting - Lay-in           | 2nd Floor | 16       | EA   | 7    | \$0     |                           |
|   | Walls - Plaster/Drywall     | 2nd Floor | 903      | SF   | 6    | \$2,492 |                           |
| <b>Classroom #231 (Vacant)</b>            |                             |           |          |      |      |         |                           |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                           |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 7    | \$0     |                           |
|   | Chalk Board                 | 2nd Floor | 48       | LF   | 4    | \$4,407 |                           |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |                           |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |                           |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 5    | \$3,071 |                           |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |                           |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |                           |
| <b>Classroom #232 (Regular Classroom)</b> |                             |           |          |      |      |         |                           |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                           |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |                           |
|   | Chalk Board                 | 2nd Floor | 46       | LF   | 4    | \$4,223 |                           |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                    |
|---|-----------------------------|-----------|----------|------|------|---------|-----------------------------|
| <b>Classroom #232 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |                             |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |                             |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |                             |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |                             |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |                             |
| <b>Classroom #233 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                             |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |                             |
|   | Chalk Board                 | 2nd Floor | 43       | LF   | 4    | \$3,948 |                             |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |                             |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |                             |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |                             |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |                             |
| <b>Classroom #234 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                             |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |                             |
|   | Chalk Board                 | 2nd Floor | 42       | LF   | 4    | \$3,856 |                             |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |                             |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |                             |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 5    | \$3,071 |                             |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 6    | \$2,142 | 1 bank of lay-in lights out |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 7    | \$0     |                             |
| <b>Classroom #235 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                             |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |                             |
|   | Chalk Board                 | 2nd Floor | 43       | LF   | 4    | \$3,948 |                             |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |                             |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |                             |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |                             |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |                             |
| <b>Classroom #236 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                             |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 6    | \$2,054 |                             |
|   | Chalk Board                 | 2nd Floor | 20       | LF   | 4    | \$1,836 |                             |
|   | Doors - Transom Window      | 2nd Floor | 10       | SF   | 7    | \$0     |                             |

**Building: Main**

**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments         |
|---|-----------------------------|-----------|----------|------|------|---------|------------------|
| <b>Classroom #236 (Regular Classroom)</b> |                             |           |          |      |      |         |                  |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 5    | \$2,348 |                  |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 5    | \$3,071 |                  |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |                  |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |                  |
| <b>Classroom #237 (Regular Classroom)</b> |                             |           |          |      |      |         |                  |
|   | AC Units                    | 2nd Floor | 2        | EA   | 7    | \$0     |                  |
|   | Casework                    | 2nd Floor | 8        | LF   | 5    | \$1,673 |                  |
|   | Ceiling - Lay-in            | 2nd Floor | 684      | SF   | 7    | \$0     |                  |
|   | Chalk Board                 | 2nd Floor | 15       | LF   | 4    | \$1,377 |                  |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 5    | \$1,174 |                  |
|   | Floor - Tile/Sheet          | 2nd Floor | 684      | SF   | 6    | \$685   |                  |
|   | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 7    | \$0     |                  |
|   | Walls - Plaster/Drywall     | 2nd Floor | 967      | SF   | 6    | \$2,669 |                  |
| <b>Classroom #313 (Regular Classroom)</b> |                             |           |          |      |      |         |                  |
|   | AC Units                    | 3rd Floor | 1        | EA   | 7    | \$0     |                  |
|   | Casework                    | 3rd Floor | 47       | LF   | 5    | \$9,827 |                  |
|   | Ceiling - Lay-in            | 3rd Floor | 916      | SF   | 6    | \$2,751 |                  |
|   | Chalk Board                 | 3rd Floor | 8        | LF   | 4    | \$734   |                  |
|   | Doors - Transom Window      | 3rd Floor | 20       | SF   | 7    | \$0     |                  |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 5    | \$2,348 |                  |
|   | Floor - Tile/Sheet          | 3rd Floor | 916      | SF   | 6    | \$917   |                  |
|   | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 7    | \$0     |                  |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,157    | SF   | 6    | \$3,193 |                  |
|   | Work Sink                   | 3rd Floor | 2        | EA   | 5    | \$3,016 | Sinks don't work |
| <b>Classroom #315 (Store Room)</b>        |                             |           |          |      |      |         |                  |
|   | AC Units                    | 3rd Floor | 1        | EA   | 6    | \$496   |                  |
|   | Casework                    | 3rd Floor | 39       | LF   | 6    | \$985   |                  |
|   | Ceiling - Lay-in            | 3rd Floor | 435      | SF   | 6    | \$1,306 |                  |
|   | Chalk Board                 | 3rd Floor | 21       | LF   | 4    | \$1,928 |                  |
|   | Doors - Side-lite           | 3rd Floor | 50       | SF   | 7    | \$0     |                  |
|   | Doors - Transom Window      | 3rd Floor | 50       | SF   | 7    | \$0     |                  |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                  |
|   | Floor - Tile/Sheet          | 3rd Floor | 435      | SF   | 6    | \$435   |                  |
|   | Lighting - Lay-in           | 3rd Floor | 9        | EA   | 7    | \$0     |                  |
|   | Walls - Plaster/Drywall     | 3rd Floor | 765      | SF   | 6    | \$2,111 |                  |

**Building: Main**

**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                              |
|---|-----------------------------|-----------|----------|------|------|---------|---------------------------------------|
| <b>Classroom #317 (Regular Classroom)</b>   |                             |           |          |      |      |         |                                       |
|   | AC Units                    | 3rd Floor | 1        | EA   | 7    | \$0     |                                       |
|   | Casework                    | 3rd Floor | 47       | LF   | 5    | \$9,827 |                                       |
|   | Ceiling - Lay-in            | 3rd Floor | 96       | SF   | 6    | \$288   |                                       |
|   | Chalk Board                 | 3rd Floor | 8        | LF   | 4    | \$734   |                                       |
|   | Doors - Transom Window      | 3rd Floor | 20       | SF   | 7    | \$0     |                                       |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 5    | \$2,348 |                                       |
|   | Floor - Wood                | 3rd Floor | 916      | SF   | 6    | \$6,458 |                                       |
|   | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 7    | \$0     |                                       |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,157    | SF   | 5    | \$8,769 |                                       |
|   | Work Sink                   | 3rd Floor | 2        | EA   | 5    | \$3,016 | Sinks don't work                      |
| <b>Classroom #321 (Science Lab Level 1)</b> |                             |           |          |      |      |         |                                       |
|   | AC Units                    | 3rd Floor | 2        | EA   | 6    | \$991   |                                       |
|   | Casework                    | 3rd Floor | 93       | LF   | 6    | \$2,349 |                                       |
|   | Ceiling - Lay-in            | 3rd Floor | 1,032    | SF   | 6    | \$3,099 |                                       |
|   | Doors - Transom Window      | 3rd Floor | 20       | SF   | 7    | \$0     |                                       |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 5    | \$2,348 |                                       |
|   | Eye Wash Station            | 3rd Floor | 1        | EA   | 5    | \$844   | Not working                           |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,032    | SF   | 6    | \$1,033 |                                       |
|   | Fume Hood                   | 3rd Floor | 1        | EA   | 6    | \$816   |                                       |
|   | Gas Line                    | 3rd Floor | 15       | EA   | 6    | \$7,637 |                                       |
|   | Lighting - Lay-in           | 3rd Floor | 18       | EA   | 7    | \$0     |                                       |
|   | Marker Board                | 3rd Floor | 9        | LF   | 7    | \$0     |                                       |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,278    | SF   | 6    | \$3,527 |                                       |
|   | Work Sink                   | 3rd Floor | 10       | EA   | 6    | \$3,790 |                                       |
| <b>Classroom #322 (Science Lab Level 1)</b> |                             |           |          |      |      |         |                                       |
|   | Casework                    | 3rd Floor | 73       | LF   | 6    | \$1,844 |                                       |
|   | Ceiling - Lay-in            | 3rd Floor | 1,031    | SF   | 6    | \$3,096 |                                       |
|   | Chalk Board                 | 3rd Floor | 10       | LF   | 4    | \$918   |                                       |
|   | Doors - Steel Doors incl hw | 3rd Floor | 1        | EA   | 7    | \$0     |                                       |
|   | Doors - Transom Window      | 3rd Floor | 20       | SF   | 7    | \$0     |                                       |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 5    | \$2,348 |                                       |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,031    | SF   | 6    | \$1,032 |                                       |
|   | Fume Hood                   | 3rd Floor | 1        | EA   | 5    | \$3,773 |                                       |
|   | Gas Line                    | 3rd Floor | 1        | EA   | 6    | \$509   |                                       |
|   | Lighting - Lay-in           | 3rd Floor | 28       | EA   | 7    | \$0     |                                       |
|   | Science Lab Shower          | 3rd Floor | 1        | EA   | 4    | \$3,326 | Does not work; eye wash parts missing |

**Building: Main**

**Category: Classrooms**

| Group   | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments                |
|---|-----------------------------|-----------|----------|------|------|----------|-------------------------|
| <b>Classroom #322 (Science Lab Level 1)</b>     |                             |           |          |      |      |          |                         |
|   | Storage/ Closet             | 3rd Floor | 98       | SF   | 7    | \$0      |                         |
|   | Walls - Plaster/Drywall     | 3rd Floor | 914      | SF   | 6    | \$2,523  |                         |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 5    | \$4,523  | Controls need replacing |
| <b>Classroom #325 (Regular Classroom)</b>       |                             |           |          |      |      |          |                         |
|   | AC Units                    | 3rd Floor | 2        | EA   | 6    | \$991    |                         |
|   | Casework                    | 3rd Floor | 57       | LF   | 7    | \$0      |                         |
|   | Ceiling - Lay-in            | 3rd Floor | 1,080    | SF   | 7    | \$0      |                         |
|   | Chalk Board                 | 3rd Floor | 4        | LF   | 4    | \$367    |                         |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602    |                         |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,080    | SF   | 7    | \$0      |                         |
|   | Lighting - Lay-in           | 3rd Floor | 30       | EA   | 7    | \$0      |                         |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,295    | SF   | 6    | \$3,574  |                         |
|   | Work Sink                   | 3rd Floor | 1        | EA   | 6    | \$379    | Sink does not work      |
| <b>Classroom #326 (Science Lab Level 3)</b>     |                             |           |          |      |      |          |                         |
|   | Casework                    | 3rd Floor | 177      | LF   | 5    | \$37,007 |                         |
|   | Ceiling - Lay-in            | 3rd Floor | 906      | SF   | 6    | \$2,721  |                         |
|   | Chalk Board                 | 3rd Floor | 15       | LF   | 4    | \$1,377  |                         |
|   | Doors - Steel Doors incl hw | 3rd Floor | 1        | EA   | 7    | \$0      |                         |
|   | Doors - Transom Window      | 3rd Floor | 20       | SF   | 7    | \$0      |                         |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 5    | \$2,348  |                         |
|   | Eye Wash Station            | 3rd Floor | 1        | EA   | 4    | \$3,018  | Does not work           |
|   | Floor - Tile/Sheet          | 3rd Floor | 906      | SF   | 6    | \$907    |                         |
|   | Gas Line                    | 3rd Floor | 1        | EA   | 6    | \$509    |                         |
|   | Lighting - Lay-in           | 3rd Floor | 27       | EA   | 7    | \$0      |                         |
|   | Storage/ Closet             | 3rd Floor | 115      | SF   | 6    | \$834    |                         |
|   | Walls - Plaster/Drywall     | 3rd Floor | 920      | SF   | 6    | \$2,539  |                         |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 5    | \$4,523  | Controls need replacing |
| <b>Classroom #327 (Other Instructional Use)</b> |                             |           |          |      |      |          |                         |
|   | Casework                    | 3rd Floor | 40       | LF   | 7    | \$0      |                         |
|   | Ceiling - Lay-in            | 3rd Floor | 1,189    | SF   | 7    | \$0      |                         |
|   | Chalk Board                 | 3rd Floor | 8        | LF   | 4    | \$734    |                         |
|   | Doors - Transom Window      | 3rd Floor | 10       | SF   | 7    | \$0      |                         |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 5    | \$1,174  |                         |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,189    | SF   | 5    | \$5,339  |                         |
|   | Lighting - Lay-in           | 3rd Floor | 27       | EA   | 7    | \$0      |                         |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,262    | SF   | 6    | \$3,483  |                         |

**Building: Main**

**Category: Classrooms**

| Group   | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                |
|---|-----------------------------|-----------|----------|------|------|---------|-------------------------|
| <b>Classroom #327 (Other Instructional Use)</b> |                             |           |          |      |      |         |                         |
|   | Work Sink                   | 3rd Floor | 1        | EA   | 6    | \$379   |                         |
| <b>Classroom #328 (Science Classroom)</b>       |                             |           |          |      |      |         |                         |
|   | Casework                    | 3rd Floor | 146      | LF   | 6    | \$3,687 |                         |
|   | Ceiling - Lay-in            | 3rd Floor | 937      | SF   | 6    | \$2,814 |                         |
|   | Chalk Board                 | 3rd Floor | 15       | LF   | 4    | \$1,377 |                         |
|   | Doors - Side-lite           | 3rd Floor | 20       | SF   | 7    | \$0     |                         |
|   | Doors - Steel Doors incl hw | 3rd Floor | 1        | EA   | 7    | \$0     |                         |
|   | Doors - Transom Window      | 3rd Floor | 20       | SF   | 7    | \$0     |                         |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 3        | EA   | 5    | \$3,522 |                         |
|   | Eye Wash Station            | 3rd Floor | 1        | EA   | 4    | \$3,018 | Most parts missing      |
|   | Floor - Tile/Sheet          | 3rd Floor | 937      | SF   | 5    | \$4,207 |                         |
|   | Lighting - Lay-in           | 3rd Floor | 23       | EA   | 7    | \$0     |                         |
|   | Storage/ Closet             | 3rd Floor | 65       | SF   | 5    | \$1,048 | Room 328A               |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,343    | SF   | 6    | \$3,707 |                         |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 5    | \$4,523 | Controls need replacing |

**Classrooms Subtotal:**

**\$847,477**

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location              | Quantity | Unit | Rank | Cost    | Comments |
|--------------------------------------|-----------------------------|-----------------------|----------|------|------|---------|----------|
| <b>Administrative Suites/Offices</b> |                             |                       |          |      |      |         |          |
|                                      | AC Unit                     | 105 Library Office    | 1        | EA   | 6    | \$496   |          |
|                                      | Ceiling - Lay-in            | 105 Library Office    | 320      | SF   | 6    | \$961   |          |
|                                      | Doors - Transom Window      | 105 Library Office    | 9        | SF   | 6    | \$152   |          |
|                                      | Doors - Wood Doors inclu hw | 105 Library Office    | 1        | EA   | 5    | \$1,174 |          |
|                                      | Floor - Tile                | 105 Library Office    | 320      | SF   | 6    | \$700   |          |
|                                      | Lighting - Lay-in           | 105 Library Office    | 6        | EA   | 7    | \$0     |          |
|                                      | Power Distribution          | 105 Library Office    | 4        | EA   | 6    | \$8,500 |          |
|                                      | Walls - Plaster/Drywall     | 105 Library Office    | 690      | SF   | 6    | \$1,904 |          |
|                                      | AC Unit                     | 107 Library Work Room | 1        | EA   | 6    | \$496   |          |
|                                      | Ceiling - Lay-in            | 107 Library Work Room | 245      | SF   | 7    | \$0     |          |
|                                      | Doors - Wood Doors inclu hw | 107 Library Work Room | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Tile                | 107 Library Work Room | 245      | SF   | 6    | \$536   |          |
|                                      | Power Distribution          | 107 Library Work Room | 6        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 107 Library Work Room | 490      | SF   | 6    | \$1,352 |          |



**Building: Main**

**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location              | Quantity | Unit | Rank | Cost    | Comments |
|--------------------------------------|-----------------------------|-----------------------|----------|------|------|---------|----------|
| <b>Administrative Suites/Offices</b> |                             |                       |          |      |      |         |          |
|                                      | Work Slnk                   | 107 Library Work Room | 1        | EA   | 7    | \$0     |          |
|                                      | AC Unit                     | 113 Main Office       | 2        | EA   | 7    | \$0     |          |
|                                      | Ceiling - Lay-in            | 113 Main Office       | 815      | SF   | 6    | \$2,447 |          |
|                                      | Doors - Transom Window      | 113 Main Office       | 9        | SF   | 5    | \$381   |          |
|                                      | Doors - Wood Doors inclu hw | 113 Main Office       | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Tile                | 113 Main Office       | 815      | SF   | 6    | \$1,783 |          |
|                                      | Lighting - Lay-in           | 113 Main Office       | 17       | EA   | 7    | \$0     |          |
|                                      | Power Distribution          | 113 Main Office       | 12       | EA   | 7    | \$0     |          |
|                                      | Storage/ Closet             | 113 Main Office       | 10       | SF   | 6    | \$73    |          |
|                                      | Walls - Plaster/Drywall     | 113 Main Office       | 1,090    | SF   | 6    | \$3,008 |          |
|                                      | AC Unit                     | 113A                  | 1        | EA   | 7    | \$0     |          |
|                                      | Ceiling - Lay-in            | 113A                  | 155      | SF   | 7    | \$0     |          |
|                                      | Doors - Wood Doors inclu hw | 113A                  | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Tile                | 113A                  | 155      | SF   | 6    | \$339   |          |
|                                      | Lighting - Lay-in           | 113A                  | 4        | EA   | 7    | \$0     |          |
|                                      | Power Distribution          | 113A                  | 6        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 113A                  | 450      | SF   | 6    | \$1,242 |          |
|                                      | AC Unit                     | 113B                  | 1        | EA   | 7    | \$0     |          |
|                                      | Ceiling - Lay-in            | 113B                  | 155      | SF   | 7    | \$0     |          |
|                                      | Doors - Wood Doors inclu hw | 113B                  | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Tile                | 113B                  | 155      | SF   | 6    | \$339   |          |
|                                      | Lighting - Lay-in           | 113B                  | 4        | EA   | 7    | \$0     |          |
|                                      | Power Distribution          | 113B                  | 6        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 113B                  | 450      | SF   | 6    | \$1,242 |          |
|                                      | AC Unit                     | 113C Principal        | 1        | EA   | 7    | \$0     |          |
|                                      | Ceiling - Lay-in            | 113C Principal        | 350      | SF   | 6    | \$1,051 |          |
|                                      | Doors - Wood Doors inclu hw | 113C Principal        | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Carpet              | 113C Principal        | 350      | SF   | 6    | \$746   |          |
|                                      | Lighting - Lay-in           | 113C Principal        | 4        | EA   | 7    | \$0     |          |
|                                      | Power Distribution          | 113C Principal        | 8        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 113C Principal        | 690      | SF   | 6    | \$1,904 |          |
|                                      | Ceiling - Exposed           | 121 Attendance Office | 530      | SF   | 7    | \$0     |          |
|                                      | Doors - Steel Doors incl hw | 121 Attendance Office | 1        | EA   | 7    | \$0     |          |
|                                      | Doors - Wood Doors inclu hw | 121 Attendance Office | 2        | EA   | 6    | \$602   |          |
|                                      | Doors - Wood Doors inclu hw | 121 Attendance Office | 1        | EA   | 7    | \$0     |          |
|                                      | Floor - Wood                | 121 Attendance Office | 530      | SF   | 5    | \$7,753 |          |
|                                      | Lighting - Pendant/Surface  | 121 Attendance Office | 12       | EA   | 7    | \$0     |          |

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                    | Location              | Quantity | Unit | Rank | Cost     | Comments     |
|--------------------------------------|--------------------------------|-----------------------|----------|------|------|----------|--------------|
| <b>Administrative Suites/Offices</b> |                                |                       |          |      |      |          |              |
|                                      | Power Distribution             | 121 Attendance Office | 14       | EA   | 7    | \$0      |              |
|                                      | Walls - Plaster/Drywall        | 121 Attendance Office | 755      | SF   | 6    | \$2,084  |              |
|                                      | Walls - Structural Glazed Tile | 121 Attendance Office | 240      | SF   | 6    | \$755    | glazed brick |
|                                      | AC Unit                        | 123 Program Office    | 1        | EA   | 6    | \$496    |              |
|                                      | Ceiling - Lay-in               | 123 Program Office    | 595      | SF   | 6    | \$1,787  |              |
|                                      | Doors - Transom Window         | 123 Program Office    | 9        | SF   | 6    | \$152    |              |
|                                      | Doors - Wood Doors inclu hw    | 123 Program Office    | 2        | EA   | 6    | \$602    |              |
|                                      | Floor - Tile                   | 123 Program Office    | 595      | SF   | 5    | \$2,672  |              |
|                                      | Lighting - Lay-in              | 123 Program Office    | 15       | EA   | 7    | \$0      |              |
|                                      | Power Distribution             | 123 Program Office    | 12       | EA   | 7    | \$0      |              |
|                                      | Storage/ Closet                | 123 Program Office    | 6        | SF   | 6    | \$44     |              |
|                                      | Walls - Plaster/Drywall        | 123 Program Office    | 420      | SF   | 6    | \$1,159  |              |
|                                      | Walls - Structural Glazed Tile | 123 Program Office    | 270      | SF   | 6    | \$849    |              |
|                                      | Ceiling - Lay-in               | 124A Office           | 275      | SF   | 6    | \$826    |              |
|                                      | Doors - Wood Doors inclu hw    | 124A Office           | 1        | EA   | 6    | \$301    |              |
|                                      | Floor - Tile                   | 124A Office           | 275      | SF   | 5    | \$1,235  |              |
|                                      | Lighting - Lay-in              | 124A Office           | 6        | EA   | 7    | \$0      |              |
|                                      | Power Distribution             | 124A Office           | 12       | EA   | 7    | \$0      |              |
|                                      | Walls - Plaster/Drywall        | 124A Office           | 140      | SF   | 6    | \$386    |              |
|                                      | Walls - Structural Glazed Tile | 124A Office           | 185      | SF   | 6    | \$582    | glazed brick |
|                                      | AC Unit                        | 128 Counselor         | 4        | EA   | 6    | \$1,982  |              |
|                                      | Ceiling - Lay-in               | 128 Counselor         | 1,065    | SF   | 6    | \$3,198  |              |
|                                      | Doors - Transom Window         | 128 Counselor         | 18       | SF   | 6    | \$305    |              |
|                                      | Doors - Wood Doors inclu hw    | 128 Counselor         | 2        | EA   | 6    | \$602    |              |
|                                      | Floor - Tile                   | 128 Counselor         | 1,065    | SF   | 6    | \$2,330  |              |
|                                      | Lighting - Lay-in              | 128 Counselor         | 30       | EA   | 7    | \$0      |              |
|                                      | Power Distribution             | 128 Counselor         | 20       | EA   | 7    | \$0      |              |
|                                      | Walls - Metal Panel            | 128 Counselor         | 620      | SF   | 6    | \$4,628  |              |
|                                      | Walls - Plaster/Drywall        | 128 Counselor         | 1,178    | SF   | 6    | \$3,251  |              |
|                                      | AC Unit                        | 129 Counselor         | 1        | EA   | 6    | \$496    |              |
|                                      | Ceiling - Lay-in               | 129 Counselor         | 210      | SF   | 6    | \$631    |              |
|                                      | Doors - Steel Doors incl hw    | 129 Counselor         | 1        | EA   | 6    | \$301    |              |
|                                      | Floor - Tile                   | 129 Counselor         | 210      | SF   | 5    | \$943    |              |
|                                      | Lighting - Lay-in              | 129 Counselor         | 6        | EA   | 6    | \$714    |              |
|                                      | Power Distribution             | 129 Counselor         | 10       | EA   | 6    | \$21,249 |              |
|                                      | Walls - Plaster/Drywall        | 129 Counselor         | 375      | SF   | 6    | \$1,035  |              |
|                                      | Walls - Structural Glazed Tile | 129 Counselor         | 170      | SF   | 6    | \$535    | glazed brick |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                                | Item - Type                    | Location                 | Quantity | Unit | Rank | Cost    | Comments                     |
|--------------------------------------|--------------------------------|--------------------------|----------|------|------|---------|------------------------------|
| <b>Administrative Suites/Offices</b> |                                |                          |          |      |      |         |                              |
|                                      | AC Unit                        | 130 Nurse                | 1        | EA   | 7    | \$0     |                              |
|                                      | Ceiling - Lay-in               | 130 Nurse                | 325      | SF   | 6    | \$976   |                              |
|                                      | Doors - Wood Doors inclu hw    | 130 Nurse                | 1        | EA   | 5    | \$1,174 |                              |
|                                      | Floor - Tile                   | 130 Nurse                | 325      | SF   | 5    | \$1,459 |                              |
|                                      | Lighting - Lay-in              | 130 Nurse                | 9        | EA   | 7    | \$0     |                              |
|                                      | Power Distribution             | 130 Nurse                | 4        | EA   | 6    | \$8,500 |                              |
|                                      | Walls - Plaster/Drywall        | 130 Nurse                | 655      | SF   | 6    | \$1,808 |                              |
|                                      | AC Unit                        | 131 Community Room       | 3        | EA   | 6    | \$1,487 |                              |
|                                      | Ceiling - Lay-in               | 131 Community Room       | 1,030    | SF   | 5    | \$6,127 |                              |
|                                      | Doors - Transom Window         | 131 Community Room       | 9        | SF   | 6    | \$152   |                              |
|                                      | Doors - Wood Doors inclu hw    | 131 Community Room       | 1        | EA   | 5    | \$1,174 |                              |
|                                      | Floor - Carpet                 | 131 Community Room       | 1,030    | SF   | 6    | \$2,195 |                              |
|                                      | Lighting - Lay-in              | 131 Community Room       | 20       | EA   | 7    | \$0     | recessed                     |
|                                      | Lighting - Lay-in              | 131 Community Room       | 21       | EA   | 7    | \$0     |                              |
|                                      | Power Distribution             | 131 Community Room       | 12       | EA   | 7    | \$0     |                              |
|                                      | Walls - Plaster/Drywall        | 131 Community Room       | 1,060    | SF   | 6    | \$2,925 |                              |
|                                      | Ceiling - Lay-in               | 133 Kitchenette          | 110      | SF   | 6    | \$330   |                              |
|                                      | Doors - Transom Window         | 133 Kitchenette          | 18       | SF   | 6    | \$305   |                              |
|                                      | Doors - Wood Doors inclu hw    | 133 Kitchenette          | 1        | EA   | 5    | \$1,174 |                              |
|                                      | Floor - Tile                   | 133 Kitchenette          | 110      | SF   | 5    | \$494   |                              |
|                                      | Lighting - Lay-in              | 133 Kitchenette          | 3        | EA   | 7    | \$0     |                              |
|                                      | Power Distribution             | 133 Kitchenette          | 2        | EA   | 6    | \$4,250 |                              |
|                                      | Storage/ Closet                | 133 Kitchenette          | 120      | SF   | 6    | \$870   | locked                       |
|                                      | Walls - Plaster/Drywall        | 133 Kitchenette          | 335      | SF   | 6    | \$925   |                              |
|                                      | Work Slnk                      | 133 Kitchenette          | 1        | EA   | 7    | \$0     |                              |
|                                      | Ceiling - Exposed              | 136 Music Office         | 185      | SF   | 7    | \$0     |                              |
|                                      | Doors - Wood Doors inclu hw    | 136 Music Office         | 1        | EA   | 6    | \$301   |                              |
|                                      | Floor - Terrazzo               | 136 Music Office         | 185      | SF   | 6    | \$405   |                              |
|                                      | Lighting - Pendent/Surface     | 136 Music Office         | 3        | EA   | 7    | \$0     |                              |
|                                      | Power Distribution             | 136 Music Office         | 12       | EA   | 7    | \$0     |                              |
|                                      | Storage/ Closet                | 136 Music Office         | 115      | SF   | 6    | \$834   |                              |
|                                      | Walls - Concrete Block         | 136 Music Office         | 85       | SF   | 7    | \$0     |                              |
|                                      | Walls - Structural Glazed Tile | 136 Music Office         | 745      | SF   | 6    | \$2,344 | glazed brick                 |
|                                      | Ceiling - Exposed              | 138 - Transcripts Office | 371      | SF   | 4    | \$1,692 | water damage, peeling paint. |
|                                      | Doors - Wood Doors inclu hw    | 138 - Transcripts Office | 2        | EA   | 6    | \$602   |                              |
|                                      | Floor - Terrazzo               | 138 - Transcripts Office | 371      | SF   | 6    | \$812   |                              |
|                                      | Lighting - Pendent/Surface     | 138 - Transcripts Office | 7        | EA   | 6    | \$867   |                              |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                                | Item - Type                     | Location                 | Quantity | Unit | Rank | Cost     | Comments  |
|--------------------------------------|---------------------------------|--------------------------|----------|------|------|----------|---|
| <b>Administrative Suites/Offices</b> |                                 |                          |          |      |      |          |   |
|                                      | Storage/ Closet                 | 138 - Transcripts Office | 94       | SF   | 5    | \$1,516  |   |
|                                      | Walls - Structural Glazed Tile  | 138 - Transcripts Office | 1,110    | SF   | 6    | \$3,492  |   |
|                                      | Ceiling - Plaster/Drywall       | 142A - PE Office         | 189      | SF   | 6    | \$654    |   |
|                                      | Doors - Wood Doors inclu hw     | 142A - PE Office         | 1        | EA   | 6    | \$301    |   |
|                                      | Floor - Concrete                | 142A - PE Office         | 189      | SF   | 6    | \$100    |   |
|                                      | Lighting - Pendent/Surface      | 142A - PE Office         | 3        | EA   | 6    | \$372    |   |
|                                      | Walls - Plaster/Drywall         | 142A - PE Office         | 643      | SF   | 6    | \$1,775  |   |
|                                      | Ceiling - Exposed               | 145 - Teachers' Lounge   | 2,164    | SF   | 4    | \$9,872  | peeling paint at ductwork.                                |
|                                      | Doors - Transom Window          | 145 - Teachers' Lounge   | 9        | SF   | 4    | \$688    | Broken glass.   |
|                                      | Doors - Transom Window          | 145 - Teachers' Lounge   | 9        | SF   | 6    | \$152    |   |
|                                      | Doors - Wood Doors inclu hw     | 145 - Teachers' Lounge   | 2        | EA   | 5    | \$2,348  |   |
|                                      | Floor - Terrazzo                | 145 - Teachers' Lounge   | 1,449    | SF   | 4    | \$88,270 | patches throughout from conversion from boys' locker room |
|                                      | Floor - Tile Ceramic/ Porcelain | 145 - Teachers' Lounge   | 715      | SF   | 4    | \$19,999 | patched from boys' locker room conversion                 |
|                                      | Lighting - Pendent/Surface      | 145 - Teachers' Lounge   | 35       | EA   | 6    | \$4,336  |   |
|                                      | Walls - Structural Glazed Tile  | 145 - Teachers' Lounge   | 3,801    | SF   | 6    | \$11,958 |   |
|                                      | Ceiling - Exposed               | 149 - Custodial Office   | 210      | SF   | 7    | \$0      |   |
|                                      | Doors - Transom Window          | 149 - Custodial Office   | 12       | SF   | 6    | \$203    |   |
|                                      | Doors - Wood Doors inclu hw     | 149 - Custodial Office   | 2        | EA   | 5    | \$2,348  |   |
|                                      | Floor - Terrazzo                | 149 - Custodial Office   | 210      | SF   | 6    | \$459    |   |
|                                      | Lighting - Pendent/Surface      | 149 - Custodial Office   | 3        | EA   | 6    | \$372    |   |
|                                      | Walls - Plaster/Drywall         | 149 - Custodial Office   | 1,183    | SF   | 6    | \$3,265  |   |
|                                      | Ceiling - Exposed               | 151 - Custodial Office   | 129      | SF   | 7    | \$0      |   |
|                                      | Doors - Wood Doors inclu hw     | 151 - Custodial Office   | 2        | EA   | 5    | \$2,348  |   |
|                                      | Floor - Terrazzo                | 151 - Custodial Office   | 129      | SF   | 6    | \$282    |   |
|                                      | Lighting - Pendent/Surface      | 151 - Custodial Office   | 2        | EA   | 7    | \$0      |   |
|                                      | Power Distribution              | 151 - Custodial Office   | 4        | EA   | 6    | \$8,500  |   |
|                                      | Walls - Plaster/Drywall         | 151 - Custodial Office   | 556      | SF   | 6    | \$1,535  |   |
|                                      | Work Slnk                       | 151 - Custodial Office   | 1        | EA   | 6    | \$508    |   |
|                                      | Ceiling - Plaster/Drywall       | 153 - Engineer Office    | 89       | SF   | 6    | \$308    |   |
|                                      | Doors - Transom Window          | 153 - Engineer Office    | 12       | SF   | 6    | \$203    |   |
|                                      | Doors - Wood Doors inclu hw     | 153 - Engineer Office    | 1        | EA   | 6    | \$301    |   |
|                                      | Floor - Tile                    | 153 - Engineer Office    | 89       | SF   | 6    | \$195    |   |
|                                      | Lighting - Pendent/Surface      | 153 - Engineer Office    | 1        | EA   | 7    | \$0      |   |
|                                      | Storage/ Closet                 | 153 - Engineer Office    | 12       | SF   | 6    | \$87     |   |
|                                      | Walls - Plaster/Drywall         | 153 - Engineer Office    | 434      | SF   | 6    | \$1,198  |   |
|                                      | Ceiling - Plaster/Drywall       | 157 B - Pool Office      | 33       | SF   | 7    | \$0      |   |
|                                      | Doors - Side-lite               | 157 B - Pool Office      | 12       | SF   | 7    | \$0      |   |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                                | Item - Type                     | Location                  | Quantity | Unit | Rank | Cost     | Comments        |
|--------------------------------------|---------------------------------|---------------------------|----------|------|------|----------|-----------------|
| <b>Administrative Suites/Offices</b> |                                 |                           |          |      |      |          |                 |
|                                      | Doors - Steel Doors incl hw     | 157 B - Pool Office       | 1        | EA   | 7    | \$0      |                 |
|                                      | Floor - Tile Ceramic/ Porcelain | 157 B - Pool Office       | 33       | SF   | 6    | \$70     |                 |
|                                      | Lighting - Pendent/Surface      | 157 B - Pool Office       | 1        | EA   | 7    | \$0      |                 |
|                                      | Power Distribution              | 157 B - Pool Office       | 2        | EA   | 7    | \$0      |                 |
|                                      | Walls - Structural Glazed Tile  | 157 B - Pool Office       | 215      | SF   | 7    | \$0      |                 |
|                                      | Ceiling - Plaster/Drywall       | 162 Engineer Office       | 113      | SF   | 6    | \$391    |                 |
|                                      | Doors - Wood Doors inclu hw     | 162 Engineer Office       | 1        | EA   | 5    | \$1,174  |                 |
|                                      | Floor - Terrazzo                | 162 Engineer Office       | 113      | SF   | 6    | \$247    |                 |
|                                      | Lighting - Pendent/Surface      | 162 Engineer Office       | 3        | EA   | 6    | \$372    |                 |
|                                      | Power Distribution              | 162 Engineer Office       | 4        | EA   | 6    | \$8,500  |                 |
|                                      | Walls - Plaster/Drywall         | 162 Engineer Office       | 408      | SF   | 5    | \$3,092  |                 |
|                                      | AC Unit                         | 173 Cafeteria Manager     | 1        | EA   | 6    | \$496    |                 |
|                                      | Ceiling - Lay-in                | 173 Cafeteria Manager     | 125      | SF   | 6    | \$375    |                 |
|                                      | Doors - Wood Doors inclu hw     | 173 Cafeteria Manager     | 1        | EA   | 6    | \$301    |                 |
|                                      | Floor - Tile                    | 173 Cafeteria Manager     | 125      | SF   | 6    | \$273    |                 |
|                                      | Lighting - Pendent/Surface      | 173 Cafeteria Manager     | 3        | EA   | 7    | \$0      |                 |
|                                      | Power Distribution              | 173 Cafeteria Manager     | 8        | EA   | 7    | \$0      |                 |
|                                      | Storage/ Closet                 | 173 Cafeteria Manager     | 2        | SF   | 6    | \$15     |                 |
|                                      | Walls - Plaster/Drywall         | 173 Cafeteria Manager     | 280      | SF   | 6    | \$773    |                 |
|                                      | Walls - Structural Glazed Tile  | 173 Cafeteria Manager     | 395      | SF   | 6    | \$1,243  |                 |
|                                      | Ceiling - Lay-in                | 205A Office/Storage       | 225      | SF   | 7    | \$0      |                 |
|                                      | Doors - Wood Doors inclu hw     | 205A Office/Storage       | 2        | EA   | 6    | \$602    |                 |
|                                      | Floor - Tile/Sheet              | 205A Office/Storage       | 225      | SF   | 6    | \$225    |                 |
|                                      | Lighting - Lay-in               | 205A Office/Storage       | 5        | EA   | 7    | \$0      |                 |
|                                      | Power Distribution              | 205A Office/Storage       | 8        | EA   | 7    | \$0      |                 |
|                                      | Walls - Metal Panel             | 205A Office/Storage       | 462      | SF   | 7    | \$0      | Walls are glass |
|                                      | Walls - Plaster/Drywall         | 205A Office/Storage       | 225      | SF   | 6    | \$621    |                 |
|                                      | AC Unit                         | 215 Student Dean's Office | 2        | EA   | 6    | \$991    |                 |
|                                      | Ceiling - Lay-in                | 215 Student Dean's Office | 428      | SF   | 7    | \$0      |                 |
|                                      | Doors - Side-lite               | 215 Student Dean's Office | 70       | SF   | 6    | \$1,170  |                 |
|                                      | Doors - Transom Window          | 215 Student Dean's Office | 8        | SF   | 6    | \$135    |                 |
|                                      | Doors - Wood Doors inclu hw     | 215 Student Dean's Office | 1        | EA   | 6    | \$301    |                 |
|                                      | Floor - Tile/Sheet              | 215 Student Dean's Office | 428      | SF   | 5    | \$1,922  |                 |
|                                      | Lighting - Lay-in               | 215 Student Dean's Office | 9        | EA   | 7    | \$0      |                 |
|                                      | Lighting - Wall Mounted         | 215 Student Dean's Office | 1        | EA   | 7    | \$0      |                 |
|                                      | Power Distribution              | 215 Student Dean's Office | 16       | EA   | 6    | \$33,998 |                 |
|                                      | Walls - Plaster/Drywall         | 215 Student Dean's Office | 812      | SF   | 6    | \$2,241  |                 |

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                     | Location                   | Quantity | Unit | Rank | Cost     | Comments                           |
|--------------------------------------|---------------------------------|----------------------------|----------|------|------|----------|------------------------------------|
| <b>Administrative Suites/Offices</b> |                                 |                            |          |      |      |          |                                    |
|                                      | AC Unit                         | 221-Social Worker          | 1        | EA   | 7    | \$0      |                                    |
|                                      | Ceiling - Lay-in                | 221-Social Worker          | 206      | SF   | 5    | \$1,225  | peeling paint                      |
|                                      | Doors - Wood Doors inclu hw     | 221-Social Worker          | 2        | EA   | 6    | \$602    |                                    |
|                                      | Floor - Carpet                  | 221-Social Worker          | 206      | SF   | 6    | \$439    |                                    |
|                                      | Lighting - Pendent/Surface      | 221-Social Worker          | 2        | EA   | 7    | \$0      |                                    |
|                                      | Power Distribution              | 221-Social Worker          | 8        | EA   | 7    | \$0      |                                    |
|                                      | Storage/ Closet                 | 221-Social Worker          | 5        | SF   | 6    | \$36     |                                    |
|                                      | Walls - Plaster/Drywall         | 221-Social Worker          | 732      | SF   | 6    | \$2,020  |                                    |
|                                      | Ceiling - Plaster/Drywall       | 243- East Gym Office       | 113      | SF   | 6    | \$391    |                                    |
|                                      | Doors - Transom Window          | 243- East Gym Office       | 8        | SF   | 6    | \$135    |                                    |
|                                      | Doors - Wood Doors inclu hw     | 243- East Gym Office       | 1        | EA   | 6    | \$301    |                                    |
|                                      | Floor - Tile/Sheet              | 243- East Gym Office       | 113      | SF   | 6    | \$113    | 4 wood treads 6'-0" wide in office |
|                                      | Lighting - Pendent/Surface      | 243- East Gym Office       | 3        | EA   | 6    | \$372    |                                    |
|                                      | Power Distribution              | 243- East Gym Office       | 2        | EA   | 6    | \$4,250  |                                    |
|                                      | Storage/ Closet                 | 243- East Gym Office       | 61       | SF   | 6    | \$442    |                                    |
|                                      | Walls - Plaster/Drywall         | 243- East Gym Office       | 500      | SF   | 6    | \$1,380  |                                    |
|                                      | Ceiling - Plaster/Drywall       | 245- West Gym Office       | 113      | SF   | 6    | \$391    |                                    |
|                                      | Doors - Transom Window          | 245- West Gym Office       | 8        | SF   | 6    | \$135    |                                    |
|                                      | Doors - Wood Doors inclu hw     | 245- West Gym Office       | 2        | EA   | 6    | \$602    |                                    |
|                                      | Floor - Tile/Sheet              | 245- West Gym Office       | 113      | SF   | 6    | \$113    | 4 wood treads in office 6' wide    |
|                                      | Lighting - Pendent/Surface      | 245- West Gym Office       | 3        | EA   | 6    | \$372    |                                    |
|                                      | Power Distribution              | 245- West Gym Office       | 2        | EA   | 6    | \$4,250  |                                    |
|                                      | Storage/ Closet                 | 245- West Gym Office       | 61       | SF   | 6    | \$442    |                                    |
|                                      | Walls - Plaster/Drywall         | 245- West Gym Office       | 500      | SF   | 6    | \$1,380  |                                    |
|                                      | AC Unit                         | Bsmt Chief Engineer Office | 1        | EA   | 6    | \$496    |                                    |
|                                      | Ceiling - Exposed               | Bsmt Chief Engineer Office | 310      | SF   | 5    | \$851    | peeling paint                      |
|                                      | Doors - Wood Doors inclu hw     | Bsmt Chief Engineer Office | 2        | EA   | 6    | \$602    |                                    |
|                                      | Floor - Concrete Epoxy/ Painted | Bsmt Chief Engineer Office | 310      | SF   | 6    | \$164    |                                    |
|                                      | Lighting - Pendent/Surface      | Bsmt Chief Engineer Office | 3        | EA   | 7    | \$0      |                                    |
|                                      | Power Distribution              | Bsmt Chief Engineer Office | 16       | EA   | 7    | \$0      |                                    |
|                                      | Walls - Plaster/Drywall         | Bsmt Chief Engineer Office | 700      | SF   | 5    | \$5,305  | peeling paint                      |
| <b>Auditorium &amp; Theater</b>      |                                 |                            |          |      |      |          |                                    |
|                                      | Balcony Seating                 | 1st Floor                  | 30       | EA   | 4    | \$22,424 | Broken seating.                    |
|                                      | Balcony Seating                 | 1st Floor                  | 252      | EA   | 5    | \$95,895 |                                    |
|                                      | Ceiling - Plaster/Drywall       | 1st Floor                  | 6,820    | SF   | 6    | \$56,858 |                                    |
|                                      | Ceiling - Plaster/Drywall       | 1st Floor                  | 400      | SF   | 5    | \$12,601 |                                    |
|                                      | Doors - Steel Doors incl hw     | 1st Floor                  | 3        | EA   | 6    | \$903    |                                    |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                           | Item - Type                                   | Location             | Quantity | Unit | Rank | Cost      | Comments  |
|---------------------------------|---|----------------------|----------|------|------|-----------|---|
| <b>Auditorium &amp; Theater</b> |   |                      |          |      |      |           |   |
|                                 | Doors - Steel Doors incl hw                   | 1st Floor            | 1        | EA   | 5    | \$1,174   |   |
|                                 | Doors - Wood Doors inclu hw                   | 1st Floor            | 9        | EA   | 5    | \$10,567  |   |
|                                 | Floor - Concrete Epoxy/ Painted               | 1st Floor            | 5,870    | SF   | 6    | \$3,106   |   |
|                                 | Floor - Wood                                  | 1st Floor            | 950      | SF   | 6    | \$6,697   | Stage Flooring.   |
|                                 | Lighting - Pendent/Surface                    | 1st Floor            | 61       | EA   | 6    | \$7,558   |   |
|                                 | Lighting - Wall Mounted                       | 1st Floor            | 16       | EA   | 5    | \$2,712   | Dim light/no light, needs replacement.                                |
|                                 | Main Floor Seating                            | 1st Floor            | 492      | EA   | 5    | \$187,224 |   |
|                                 | Sound System                                  | 1st Floor            | 1        | EA   | 6    | \$10,721  | per engineer: not in use  |
|                                 | Stage   | 1st Floor            | 950      | SF   | 6    | \$5,488   |   |
|                                 | Stage Curtain                                 | 1st Floor            | 3        | EA   | 5    | \$36,861  |   |
|                                 | Stage Lighting System                         | 1st Floor            | 1        | EA   | 6    | \$8,077   |   |
|                                 | Stage-Stairs - Wood                           | 1st Floor            | 24       | LF   | 6    | \$282     |   |
|                                 | Stairs - Terrazzo                             | 1st Floor            | 216      | LF   | 6    | \$1,653   |   |
|                                 | Walls - Plaster/Drywall                       | 1st Floor            | 500      | SF   | 5    | \$5,641   |   |
|                                 | Walls - Plaster/Drywall                       | 1st Floor            | 8,310    | SF   | 6    | \$39,571  |   |
| <b>Gymnasia</b>                 |   |                      |          |      |      |           |   |
|                                 | Ceiling - Plaster/Drywall                     | East Gym - 2nd Floor | 4,967    | SF   | 5    | \$71,525  |   |
|                                 | Doors - Transom Window                        | East Gym - 2nd Floor | 36       | SF   | 5    | \$1,524   |   |
|                                 | Doors - Wood Doors inclu hw                   | East Gym - 2nd Floor | 6        | EA   | 5    | \$7,044   | Note: 2 doors which access exit stairway are chained + padlocked.     |
|                                 | Floor - Wood                                  | East Gym - 2nd Floor | 167      | SF   | 4    | \$6,971   | Floor has water damage and major buckling in two locations            |
|                                 | Floor - Wood                                  | East Gym - 2nd Floor | 4,800    | SF   | 6    | \$33,840  |   |
|                                 | Lighting - Metal Halide/ High Pressure Sodium | East Gym - 2nd Floor | 36       | EA   | 6    | \$4,814   |   |
|                                 | Lighting - Pendent/Surface                    | East Gym - 2nd Floor | 6        | EA   | 6    | \$743     |   |
|                                 | Scoreboards                                   | East Gym - 2nd Floor | 1        | EA   | 4    | \$19,113  | Non-operational   |
|                                 | Sound System                                  | East Gym - 2nd Floor | 1        | EA   | 4    | \$189,224 | Non-operational   |
|                                 | Storage/ Closet                               | East Gym - 2nd Floor | 385      | SF   | 6    | \$2,791   |   |
|                                 | Walls - Masonry                               | East Gym - 2nd Floor | 1,998    | SF   | 6    | \$6,286   | Glazed Brick - some stepped cracking in SE corner.                    |
|                                 | Walls - Plaster/Drywall                       | East Gym - 2nd Floor | 2,000    | SF   | 6    | \$5,520   |   |
|                                 | Walls - Plaster/Drywall                       | East Gym - 2nd Floor | 300      | SF   | 4    | \$5,444   | water damage - exterior assessment crew was made aware of this issue. |
|                                 | Bleacher Seating                              | West Gym - 2nd Floor | 157      | EA   | 7    | \$0       | Newer Aluminum seating  |
|                                 | Bleacher Seating                              | West Gym - 2nd Floor | 112      | EA   | 4    | \$26,452  | Old Wood Bleachers  |
|                                 | Ceiling - Plaster/Drywall                     | West Gym - 2nd Floor | 6,271    | SF   | 6    | \$34,615  |   |
|                                 | Doors - Steel Doors incl hw                   | West Gym - 2nd Floor | 2        | EA   | 6    | \$602     |   |
|                                 | Doors - Transom Window                        | West Gym - 2nd Floor | 62       | SF   | 6    | \$1,050   |   |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                     | Item - Type                                   | Location             | Quantity | Unit | Rank | Cost      | Comments   |
|---------------------------|---|----------------------|----------|------|------|-----------|--|
| <b>Gymnasia</b>           |   |                      |          |      |      |           |  |
|                           | Doors - Wood Doors inclu hw                   | West Gym - 2nd Floor | 7        | EA   | 4    | \$23,891  | Note: 2 doors which access exit stair were chained + padlocked while class was in session. |
|                           | Floor - Wood                                  | West Gym - 2nd Floor | 6,271    | SF   | 6    | \$44,210  |  |
|                           | Lighting - Metal Halide/ High Pressure Sodium | West Gym - 2nd Floor | 45       | EA   | 7    | \$0       |  |
|                           | Lighting - Pendent/Surface                    | West Gym - 2nd Floor | 8        | EA   | 6    | \$991     |  |
|                           | Scoreboards                                   | West Gym - 2nd Floor | 1        | EA   | 6    | \$2,244   |  |
|                           | Sound System                                  | West Gym - 2nd Floor | 1        | EA   | 5    | \$104,564 | Non-Operational  |
|                           | Storage/ Closet                               | West Gym - 2nd Floor | 380      | SF   | 6    | \$2,755   |  |
|                           | Walls - Plaster/Drywall                       | West Gym - 2nd Floor | 2,586    | SF   | 6    | \$7,137   |  |
|                           | Walls - Structural Glazed Tile                | West Gym - 2nd Floor | 2,107    | SF   | 6    | \$6,629   | Glazed Brick Facing  |
| <b>Kitchen</b>            |   |                      |          |      |      |           |  |
|                           | Ceiling - Splined                             | 1st Floor            | 830      | SF   | 6    | \$677     |  |
|                           | Floor - Terrazzo                              | 1st Floor            | 830      | SF   | 6    | \$1,816   |  |
|                           | Lighting - Pendent/Surface                    | 1st Floor            | 15       | EA   | 6    | \$1,858   |  |
|                           | Walls - Structural Glazed Tile                | 1st Floor            | 1,170    | SF   | 6    | \$3,681   | glazed brick   |
| <b>Library</b>            |   |                      |          |      |      |           |  |
|                           | AC Unit                                       | 109 Library          | 5        | EA   | 7    | \$0       |  |
|                           | Casework                                      | 109 Library          | 192      | LF   | 7    | \$0       |  |
|                           | Ceiling - Plaster/Drywall                     | 109 Library          | 2,021    | SF   | 7    | \$0       |  |
|                           | Doors - Steel Doors incl hw                   | 109 Library          | 1        | EA   | 7    | \$0       |  |
|                           | Doors - Transom Window                        | 109 Library          | 20       | SF   | 7    | \$0       |  |
|                           | Doors - Wood Doors inclu hw                   | 109 Library          | 2        | EA   | 7    | \$0       |  |
|                           | Floor - Carpet                                | 109 Library          | 2,021    | SF   | 7    | \$0       |  |
|                           | Lighting - Pendent/Surface                    | 109 Library          | 50       | EA   | 6    | \$6,195   | Two lights missing lenses  |
|                           | Storage/ Closet                               | 109 Library          | 50       | SF   | 7    | \$0       | Room 109A on the plan  |
|                           | Walls - Plaster/Drywall                       | 109 Library          | 1,348    | SF   | 6    | \$3,720   | Walls covered w/spline ceiling tiles   |
| <b>Locker/Shower Room</b> |   |                      |          |      |      |           |  |
|                           | Accessories                                   | 143                  | 863      | SF   | 6    | \$3,381   |  |
|                           | Benches, ped mounted                          | 143                  | 104      | LF   | 5    | \$28,574  |  |
|                           | Ceiling - Exposed                             | 143                  | 3,034    | SF   | 4    | \$13,840  | water leaks and peeling paint.   |
|                           | Doors - Transom Window                        | 143                  | 9        | SF   | 6    | \$152     |  |
|                           | Doors - Wood Doors inclu hw                   | 143                  | 1        | EA   | 5    | \$1,174   |  |
|                           | Floor Drain                                   | 143                  | 18       | EA   | 5    | \$37,691  | Broken floor drains.   |
|                           | Floor - Terrazzo                              | 143                  | 863      | SF   | 6    | \$1,888   |  |
|                           | Floor - Tile Ceramic/ Porcelain               | 143                  | 2,171    | SF   | 6    | \$4,595   |  |
|                           | Lavatory                                      | 143                  | 2        | EA   | 6    | \$639     |  |



## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                     | Item - Type                     | Location                        | Quantity | Unit | Rank | Cost      | Comments  |
|---------------------------|---------------------------------|---------------------------------|----------|------|------|-----------|---|
| <b>Locker/Shower Room</b> |                                 |                                 |          |      |      |           |   |
|                           | Lighting - Pendent/Surface      | 143                             | 52       | EA   | 6    | \$6,443   |   |
|                           | Partitions                      | 143                             | 108      | EA   | 5    | \$81,093  |   |
|                           | Showers                         | 143                             | 37       | EA   | 5    | \$100,436 |   |
|                           | Student Lockers - Two Tier      | 143                             | 814      | EA   | 5    | \$76,302  | Rusted lockers, missing hardware and doors, vandalized.                     |
|                           | Walls - Plaster/Drywall         | 143                             | 1,581    | SF   | 6    | \$4,363   |   |
|                           | Walls - Structural Glazed Tile  | 143                             | 2,937    | SF   | 6    | \$9,240   |   |
|                           | Water Closet                    | 143                             | 4        | EA   | 5    | \$15,576  |   |
|                           | Accessories                     | 159 - Men's Locker Room at Pool | 785      | SF   | 5    | \$6,859   | paper towel disp is broken; missing pt dispenser. Soap dispenser available. |
|                           | Ceiling - Plaster/ Drywall      | 159 - Men's Locker Room at Pool | 785      | SF   | 7    | \$0       |   |
|                           | Doors - Steel Doors incl hw     | 159 - Men's Locker Room at Pool | 1        | EA   | 7    | \$0       |   |
|                           | Doors - Wood Doors inclu hw     | 159 - Men's Locker Room at Pool | 3        | EA   | 4    | \$10,239  | split at corners and edges - due for replacement                            |
|                           | Floor Drain                     | 159 - Men's Locker Room at Pool | 5        | EA   | 5    | \$10,470  |   |
|                           | Floor - Terrazzo                | 159 - Men's Locker Room at Pool | 393      | SF   | 6    | \$860     |   |
|                           | Floor - Tile Ceramic/ Porcelain | 159 - Men's Locker Room at Pool | 393      | SF   | 6    | \$832     |   |
|                           | Lavatory                        | 159 - Men's Locker Room at Pool | 1        | EA   | 6    | \$320     |   |
|                           | Lighting - Pendent/Surface      | 159 - Men's Locker Room at Pool | 9        | EA   | 6    | \$1,115   |   |
|                           | Partitions                      | 159 - Men's Locker Room at Pool | 2        | EA   | 5    | \$1,502   |   |
|                           | Showers                         | 159 - Men's Locker Room at Pool | 6        | EA   | 6    | \$1,868   |   |
|                           | Student Lockers - One Tier      | 159 - Men's Locker Room at Pool | 49       | EA   | 6    | \$4,549   |   |
|                           | Urinals                         | 159 - Men's Locker Room at Pool | 2        | EA   | 7    | \$0       |   |
|                           | Walls - Structural Glazed Tile  | 159 - Men's Locker Room at Pool | 1,170    | SF   | 6    | \$3,681   |   |
|                           | Water Closet                    | 159 - Men's Locker Room at Pool | 2        | EA   | 6    | \$672     |   |
|                           | Accessories                     | 249 Womens Locker Room          | 1,768    | SF   | 4    | \$26,445  | existing accessories are old and deteriorating and are due for replacement  |
|                           | Benches, ped mounted            | 249 Womens Locker Room          | 112      | LF   | 4    | \$55,811  | stained and splintering   |
|                           | Ceiling - Plaster/ Drywall      | 249 Womens Locker Room          | 1,768    | SF   | 4    | \$26,622  | Water Infiltration, peeling paint, damaged substrates                       |
|                           | Doors - Transom Window          | 249 Womens Locker Room          | 36       | SF   | 5    | \$1,524   |   |
|                           | Doors - Wood Doors inclu hw     | 249 Womens Locker Room          | 3        | EA   | 5    | \$3,522   |   |
|                           | Floor Drain                     | 249 Womens Locker Room          | 12       | EA   | 5    | \$25,128  |   |
|                           | Floor - Tile Ceramic/ Porcelain | 249 Womens Locker Room          | 1,768    | SF   | 6    | \$3,742   |   |
|                           | Hand Dryer                      | 249 Womens Locker Room          | 11       | EA   | 5    | \$6,495   |   |
|                           | Lavatory                        | 249 Womens Locker Room          | 4        | EA   | 6    | \$1,278   |   |
|                           | Lighting - Pendent/Surface      | 249 Womens Locker Room          | 35       | EA   | 7    | \$0       |   |
|                           | Partitions                      | 249 Womens Locker Room          | 35       | EA   | 4    | \$69,524  | damaged, cracked, missing doors - due for replaement                        |
|                           | Showers                         | 249 Womens Locker Room          | 14       | EA   | 4    | \$66,086  | deteriorating materials - due for replacement                               |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                                | Item - Type                    | Location               | Quantity | Unit | Rank | Cost     | Comments   |
|--------------------------------------|--------------------------------|------------------------|----------|------|------|----------|--|
| <b>Locker/Shower Room</b>            |                                |                        |          |      |      |          |  |
|                                      | Student Lockers - One Tier     | 249 Womens Locker Room | 56       | EA   | 4    | \$30,753 | rusting and dented - due for replacement                                 |
|                                      | Walls - Plaster/Drywall        | 249 Womens Locker Room | 377      | SF   | 5    | \$2,857  | water damage   |
|                                      | Walls - Structural Glazed Tile | 249 Womens Locker Room | 1,131    | SF   | 5    | \$57,464 | some wall cracks   |
|                                      | Water Closet                   | 249 Womens Locker Room | 7        | EA   | 4    | \$53,685 | stained and do not meet current plumbing standards - due for replacement |
| <b>Lunch &amp; Multipurpose Room</b> |                                |                        |          |      |      |          |  |
|                                      | Ceiling - Lay-in               | 102 Servery            | 1,450    | SF   | 6    | \$4,354  | yellowed frame.  |
|                                      | Doors - Wood Doors inclu hw    | 102 Servery            | 8        | EA   | 5    | \$9,393  |  |
|                                      | Doors - Wood Doors inclu hw    | 102 Servery            | 4        | EA   | 4    | \$13,652 | Chipped wood frame and door, missing hardware.                           |
|                                      | Doors - Wood Doors inclu hw    | 102 Servery            | 2        | EA   | 6    | \$602    |  |
|                                      | Floor - Terrazzo               | 102 Servery            | 1,450    | SF   | 6    | \$3,172  |  |
|                                      | Lighting - Lay-in              | 102 Servery            | 28       | EA   | 6    | \$3,331  |  |
|                                      | Serving Line                   | 102 Servery            | 105      | LF   | 7    | \$0      |  |
|                                      | Walls - Structural Glazed Tile | 102 Servery            | 1,260    | SF   | 6    | \$3,964  | glazed brick   |
|                                      | Ceiling - Lay-in               | 1st Floor              | 4,901    | SF   | 6    | \$14,718 |  |
|                                      | Doors - Wood Doors inclu hw    | 1st Floor              | 7        | EA   | 5    | \$8,219  |  |
|                                      | Floor - Terrazzo               | 1st Floor              | 4,901    | SF   | 7    | \$0      |  |
|                                      | Lighting - Pendent/Surface     | 1st Floor              | 48       | EA   | 7    | \$0      |  |
|                                      | Storage/ Closet                | 1st Floor              | 265      | SF   | 6    | \$1,921  |  |
|                                      | Walls - Plaster/Drywall        | 1st Floor              | 3,455    | SF   | 6    | \$9,535  |  |
|                                      | Walls - Structural Glazed Tile | 1st Floor              | 961      | SF   | 5    | \$55,450 | glazed brick- step cracking  |
|                                      | Walls - Structural Glazed Tile | 1st Floor              | 961      | SF   | 6    | \$4,191  | glazed brick   |
| <b>MDF_IDF</b>                       |                                |                        |          |      |      |          |  |
|                                      | AC Unit                        | 220 on plan            | 1        | EA   | 7    | \$0      |  |
|                                      | Doors - Steel Doors incl hw    | 220 on plan            | 1        | EA   | 6    | \$301    |  |
|                                      | Doors - Transom Window         | 220 on plan            | 8        | SF   | 6    | \$135    |  |
|                                      | Finishes                       | 220 on plan            | 205      | SF   | 7    | \$0      |  |
|                                      | Ventilation and Cooling        | 220 on plan            | 1        | EA   | 7    | \$0      |  |
| <b>Mechanical/ Service Rooms</b>     |                                |                        |          |      |      |          |  |
|                                      | Janitor's Closet               | 1st Floor              | 17       | SF   | 6    | \$122    |  |
|                                      | Janitor's Closet               | 1st Floor              | 17       | SF   | 5    | \$274    | 147J   |
|                                      | Mechanical/ Service Rooms      | 1st Floor              | 216      | SF   | 6    | \$1,547  | 161 Laundry Room   |
|                                      | Storage Room                   | 1st Floor              | 157      | SF   | 5    | \$2,532  | 153S Janitor's Storage   |
|                                      | Storage Room                   | 1st Floor              | 405      | SF   | 5    | \$6,533  | moisture damage/water damage.  |
|                                      | Storage Room                   | 247 Storage            | 77       | SF   | 6    | \$552    |  |
|                                      | Janitor's Closet               | 2nd flr Center Wing    | 15       | SF   | 6    | \$107    |  |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                            | Item - Type                     | Location            | Quantity | Unit | Rank | Cost     | Comments   |
|----------------------------------|---------------------------------|---------------------|----------|------|------|----------|--|
| <b>Mechanical/ Service Rooms</b> |                                 |                     |          |      |      |          |  |
|                                  | Storage Room                    | 2nd flr Center Wing | 490      | SF   | 6    | \$3,511  | 2 rooms  |
|                                  | Janitor's Closet                | 3rd flr Center Wing | 15       | SF   | 6    | \$107    |  |
|                                  | Storage Room                    | 3rd flr Center Wing | 326      | SF   | 6    | \$2,336  | 3 rooms  |
|                                  | Air Tunnel                      | Basement            | 6,500    | SF   | 6    | \$40,247 | Peeling ceiling/wall paint. Signs of water infiltration and some standing water.                         |
|                                  | Boiler Room                     | Basement            | 3,000    | SF   | 6    | \$21,493 | in North Wing - Signs of water infiltration and some standing water. Peeling paint on exposed structure. |
|                                  | Interior Stairs                 | Basement            | 128      | LF   | 6    | \$1,155  | 004S1 + 004S2 - painted steel in Boiler Room   |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 003S   |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 004S   |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 022S   |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 018S   |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 008S1  |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 008S2  |
|                                  | Interior Stairs                 | Basement            | 72       | LF   | 6    | \$650    | 001S   |
|                                  | Mechanical/ Service Rooms       | Basement            | 3,000    | SF   | 6    | \$21,493 | Center Wing - peeling ceiling/wall paint. Signs of water infiltration and some standing water.           |
|                                  | Mechanical/ Service Rooms       | Basement            | 6,000    | SF   | 6    | \$42,986 | South Wing - peeling ceiling/wall paint. Signs of water infiltration and some standing water.            |
|                                  | Mechanical/ Service Rooms       | Basement            | 11,500   | SF   | 6    | \$82,389 | North Wing. peeling ceiling/wall paint. Signs of water infiltration and some standing water.             |
|                                  | Mechanical/ Service Rooms       | Basement            | 2,000    | SF   | 6    | \$14,329 | Center NS Corridor Area  |
|                                  | Storage Room                    | Basement            | 2,500    | SF   | 4    | \$69,677 | Basement - Former Rooms 020, 021, 022, 023 are unsafe and completely vacant.                             |
|                                  | Storage Room                    | Basement            | 900      | SF   | 6    | \$6,448  | South Wing - peeling ceiling/wall paint. Signs of water infiltration and some standing water.            |
|                                  | Storage Room                    | Basement            | 2,800    | SF   | 6    | \$20,060 | North Wing - peeling ceiling/wall paint. Signs of water infiltration and some standing water.            |
|                                  | Vaults                          | Basement            | 300      | SF   | 6    | \$2,149  | South Wing Switchgear - signs of water infiltration. Peeling wall + ceiling paint.                       |
|                                  | Vaults                          | Basement            | 300      | SF   | 6    | \$2,149  | North Wing Switchgear - peeling ceiling/wall paint.  |
| <b>Pool &amp; Natatorium</b>     |                                 |                     |          |      |      |          |  |
|                                  | Bleachers Seating/Plank Seating | 157 - Pool          | 5        | EA   | 6    | \$145    |  |
|                                  | Ceiling - Exposed               | 157 - Pool          | 2,841    | SF   | 6    | \$4,225  |  |
|                                  | Doors - Steel Doors incl hw     | 157 - Pool          | 2        | EA   | 7    | \$0      |  |
|                                  | Floor - Tile Ceramic/ Porcelain | 157 - Pool          | 2,841    | SF   | 6    | \$6,013  |  |
|                                  | Lighting - Pendant/Surface      | 157 - Pool          | 10       | EA   | 6    | \$1,239  |  |
|                                  | Pool Basin                      | 157 - Pool          | 615      | SF   | 6    | \$20,808 |  |
|                                  | Pool Deck                       | 157 - Pool          | 2,155    | SF   | 6    | \$20,462 |  |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group                        | Item - Type                     | Location               | Quantity | Unit | Rank | Cost    | Comments   |
|------------------------------|---------------------------------|------------------------|----------|------|------|---------|--|
| <b>Pool &amp; Natatorium</b> |                                 |                        |          |      |      |         |  |
|                              | Pool Deck Drains                | 157 - Pool             | 6        | EA   | 6    | \$2,532 |  |
|                              | Storage/ Closet                 | 157 - Pool             | 71       | SF   | 6    | \$515   |  |
|                              | Walls - Structural Glazed Tile  | 157 - Pool             | 6,021    | SF   | 7    | \$0     |  |
|                              | Bleachers Seating/Plank Seating | 157A Pool Stands       | 99       | EA   | 6    | \$2,865 |  |
|                              | Ceiling - Exposed               | 157A Pool Stands       | 442      | SF   | 6    | \$657   |  |
|                              | Floor - Concrete Epoxy/ Painted | 157A Pool Stands       | 442      | SF   | 6    | \$234   |  |
|                              | Lighting - Wall Mounted         | 157A Pool Stands       | 12       | EA   | 7    | \$0     |  |
|                              | Walls - Structural Glazed Tile  | 157A Pool Stands       | 815      | SF   | 7    | \$0     |  |
| <b>Prep Room</b>             |                                 |                        |          |      |      |         |  |
|                              | Casework                        | 222 Office/224 on plan | 46       | LF   | 5    | \$9,618 | Two sinks do not operate or need controls replaced |
|                              | Ceiling - Lay-in                | 222 Office/224 on plan | 278      | SF   | 7    | \$0     |  |
|                              | Doors - Side-lite               | 222 Office/224 on plan | 50       | SF   | 7    | \$0     |  |
|                              | Doors - Wood Doors inclu hw     | 222 Office/224 on plan | 2        | EA   | 6    | \$602   |  |
|                              | Floor - Tile/Sheet              | 222 Office/224 on plan | 246      | SF   | 6    | \$246   |  |
|                              | Lighting - Lay-in               | 222 Office/224 on plan | 6        | EA   | 7    | \$0     |  |
|                              | Walls - Plaster/Drywall         | 222 Office/224 on plan | 604      | SF   | 6    | \$1,667 |  |
|                              | Casework                        | 321A                   | 30       | LF   | 6    | \$758   |  |
|                              | Ceiling - Lay-in                | 321A                   | 306      | SF   | 6    | \$919   |  |
|                              | Doors - Wood Doors inclu hw     | 321A                   | 1        | EA   | 6    | \$301   |  |
|                              | Floor - Tile/Sheet              | 321A                   | 306      | SF   | 6    | \$306   |  |
|                              | Lighting - Lay-in               | 321A                   | 3        | EA   | 7    | \$0     |  |
|                              | Walls - Plaster/Drywall         | 321A                   | 515      | SF   | 6    | \$1,421 |  |
|                              | Casework                        | 322A                   | 25       | LF   | 6    | \$631   |  |
|                              | Ceiling - Lay-in                | 322A                   | 135      | SF   | 7    | \$0     |  |
|                              | Doors - Wood Doors inclu hw     | 322A                   | 1        | EA   | 6    | \$301   |  |
|                              | Floor - Tile/Sheet              | 322A                   | 135      | SF   | 7    | \$0     |  |
|                              | Lighting - Lay-in               | 322A                   | 2        | EA   | 7    | \$0     |  |
|                              | Walls - Plaster/Drywall         | 322A                   | 449      | SF   | 6    | \$1,239 |  |
|                              | Casework                        | 326A                   | 19       | LF   | 6    | \$480   | Worksink needs new controls                        |
|                              | Ceiling - Lay-in                | 326A                   | 160      | SF   | 6    | \$480   |  |
|                              | Doors - Side-lite               | 326A                   | 25       | SF   | 7    | \$0     |  |
|                              | Doors - Wood Doors inclu hw     | 326A                   | 1        | EA   | 6    | \$301   |  |
|                              | Floor - Concrete                | 326A                   | 110      | SF   | 7    | \$0     |  |
|                              | Lighting - Lay-in               | 326A                   | 3        | EA   | 7    | \$0     |  |
|                              | Walls - Plaster/Drywall         | 326A                   | 435      | SF   | 6    | \$1,201 |  |
|                              | Casework                        | 328B                   | 25       | LF   | 6    | \$631   |  |
|                              | Ceiling - Lay-in                | 328B                   | 135      | SF   | 6    | \$405   |  |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group            | Item - Type                     | Location                  | Quantity | Unit | Rank | Cost    | Comments                              |
|------------------|---------------------------------|---------------------------|----------|------|------|---------|---------------------------------------|
| <b>Prep Room</b> |                                 |                           |          |      |      |         |                                       |
|                  | Doors - Wood Doors inclu hw     | 328B                      | 1        | EA   | 6    | \$301   |                                       |
|                  | Floor - Tile/Sheet              | 328B                      | 135      | SF   | 6    | \$135   |                                       |
|                  | Lighting - Lay-in               | 328B                      | 2        | EA   | 7    | \$0     |                                       |
|                  | Walls - Plaster/Drywall         | 328B                      | 449      | SF   | 6    | \$1,239 |                                       |
| <b>Restroom</b>  |                                 |                           |          |      |      |         |                                       |
|                  | Accessories                     | 107A Library Work Room    | 30       | SF   | 6    | \$277   |                                       |
|                  | Ceiling - Plaster/Drywall       | 107A Library Work Room    | 30       | SF   | 6    | \$104   |                                       |
|                  | Doors - Transom Window          | 107A Library Work Room    | 9        | SF   | 6    | \$152   |                                       |
|                  | Doors - Wood Doors inclu hw     | 107A Library Work Room    | 1        | EA   | 6    | \$301   |                                       |
|                  | Floor - Tile Ceramic/ Porcelain | 107A Library Work Room    | 30       | SF   | 7    | \$0     |                                       |
|                  | Lavatory                        | 107A Library Work Room    | 1        | EA   | 7    | \$0     |                                       |
|                  | Lighting - Pendent/Surface      | 107A Library Work Room    | 1        | EA   | 6    | \$124   |                                       |
|                  | Partitions                      | 107A Library Work Room    | 1        | EA   | 6    | \$297   |                                       |
|                  | Walls - Masonry                 | 107A Library Work Room    | 60       | SF   | 7    | \$0     | Actual wall material is marble.       |
|                  | Walls - Plaster/Drywall         | 107A Library Work Room    | 70       | SF   | 4    | \$851   | multiple continuous cracks            |
|                  | Walls - Plaster/Drywall         | 107A Library Work Room    | 70       | SF   | 6    | \$229   |                                       |
|                  | Water Closet                    | 107A Library Work Room    | 1        | EA   | 6    | \$336   |                                       |
|                  | Ceiling - Plaster/Drywall       | 113D                      | 30       | SF   | 6    | \$104   |                                       |
|                  | Doors - Wood Doors inclu hw     | 113D                      | 1        | EA   | 6    | \$301   |                                       |
|                  | Floor - Tile Ceramic/ Porcelain | 113D                      | 30       | SF   | 6    | \$63    |                                       |
|                  | Lavatory                        | 113D                      | 1        | EA   | 6    | \$320   |                                       |
|                  | Lighting - Pendent/Surface      | 113D                      | 1        | EA   | 7    | \$0     |                                       |
|                  | Walls - Concrete Block          | 113D                      | 122      | SF   | 7    | \$0     | marble                                |
|                  | Walls - Plaster/Drywall         | 113D                      | 135      | SF   | 6    | \$373   |                                       |
|                  | Water Closet                    | 113D                      | 1        | EA   | 7    | \$0     |                                       |
|                  | Accessories                     | 153A                      | 21       | SF   | 6    | \$194   | Soap dispenser and mirror.            |
|                  | Ceiling - Exposed               | 153A                      | 21       | SF   | 6    | \$31    |                                       |
|                  | Doors - Wood Doors inclu hw     | 153A                      | 1        | EA   | 5    | \$1,174 |                                       |
|                  | Floor - Tile Ceramic/ Porcelain | 153A                      | 21       | SF   | 6    | \$44    |                                       |
|                  | Lavatory                        | 153A                      | 1        | EA   | 6    | \$320   |                                       |
|                  | Lighting - Pendent/Surface      | 153A                      | 1        | EA   | 6    | \$124   |                                       |
|                  | Walls - Plaster/Drywall         | 153A                      | 351      | SF   | 5    | \$2,660 | Wall cracks, crumbling paint.         |
|                  | Water Closet                    | 153A                      | 1        | EA   | 6    | \$336   |                                       |
|                  | Accessories                     | 178A Auditorium Vestibule | 130      | SF   | 6    | \$1,199 | Soap dispenser.                       |
|                  | Ceiling - Plaster/Drywall       | 178A Auditorium Vestibule | 130      | SF   | 6    | \$450   | evidence of moisture damage at window |
|                  | Floor - Tile Ceramic/ Porcelain | 178A Auditorium Vestibule | 130      | SF   | 5    | \$2,077 |                                       |
|                  | Lavatory                        | 178A Auditorium Vestibule | 2        | EA   | 6    | \$639   |                                       |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group           | Item - Type                     | Location                  | Quantity | Unit | Rank | Cost    | Comments                        |
|-----------------|---------------------------------|---------------------------|----------|------|------|---------|---------------------------------|
| <b>Restroom</b> |                                 |                           |          |      |      |         |                                 |
|                 | Lighting - Pendant/Surface      | 178A Auditorium Vestibule | 1        | EA   | 6    | \$124   |                                 |
|                 | Partitions                      | 178A Auditorium Vestibule | 2        | EA   | 6    | \$594   |                                 |
|                 | Urinals                         | 178A Auditorium Vestibule | 2        | EA   | 6    | \$672   |                                 |
|                 | Walls - Masonry                 | 178A Auditorium Vestibule | 150      | SF   | 7    | \$0     | marble                          |
|                 | Walls - Plaster/Drywall         | 178A Auditorium Vestibule | 8        | SF   | 5    | \$41    | damage at window                |
|                 | Walls - Plaster/Drywall         | 178A Auditorium Vestibule | 75       | SF   | 6    | \$207   |                                 |
|                 | Water Closet                    | 178A Auditorium Vestibule | 2        | EA   | 6    | \$672   |                                 |
|                 | Accessories                     | 178B Auditorium Vestibule | 130      | SF   | 6    | \$1,199 | Mirror.                         |
|                 | Ceiling - Plaster/Drywall       | 178B Auditorium Vestibule | 130      | SF   | 6    | \$450   |                                 |
|                 | Floor - Tile Ceramic/ Porcelain | 178B Auditorium Vestibule | 130      | SF   | 5    | \$2,077 |                                 |
|                 | Lavatory                        | 178B Auditorium Vestibule | 2        | EA   | 7    | \$0     |                                 |
|                 | Lighting - Pendant/Surface      | 178B Auditorium Vestibule | 1        | EA   | 6    | \$124   |                                 |
|                 | Partitions                      | 178B Auditorium Vestibule | 2        | EA   | 5    | \$1,502 |                                 |
|                 | Walls - Masonry                 | 178B Auditorium Vestibule | 155      | SF   | 6    | \$488   | Actual wall material is marble. |
|                 | Walls - Plaster/Drywall         | 178B Auditorium Vestibule | 80       | SF   | 6    | \$221   |                                 |
|                 | Walls - Plaster/Drywall         | 178B Auditorium Vestibule | 3        | SF   | 5    | \$15    | cracking, missing plaster       |
|                 | Water Closet                    | 178B Auditorium Vestibule | 2        | EA   | 6    | \$672   |                                 |
|                 | Accessories                     | 1st Floor                 | 410      | SF   | 6    | \$3,782 |                                 |
|                 | Ceiling - Plaster/Drywall       | 1st Floor                 | 410      | SF   | 6    | \$1,419 |                                 |
|                 | Floor Drain                     | 1st Floor                 | 1        | EA   | 6    | \$1,059 |                                 |
|                 | Floor - Tile Ceramic/ Porcelain | 1st Floor                 | 410      | SF   | 6    | \$868   |                                 |
|                 | Hand Dryer                      | 1st Floor                 | 1        | EA   | 7    | \$0     |                                 |
|                 | Lavatory                        | 1st Floor                 | 2        | EA   | 6    | \$639   |                                 |
|                 | Lighting - Pendant/Surface      | 1st Floor                 | 6        | EA   | 7    | \$0     |                                 |
|                 | Partitions                      | 1st Floor                 | 3        | EA   | 6    | \$891   |                                 |
|                 | Partitions                      | 1st Floor                 | 11       | EA   | 5    | \$8,260 |                                 |
|                 | Walls - Plaster/Drywall         | 1st Floor                 | 955      | SF   | 6    | \$2,636 |                                 |
|                 | Water Closet                    | 1st Floor                 | 14       | EA   | 6    | \$4,704 |                                 |
|                 | Accessories                     | 218 Men's Washroom        | 380      | SF   | 6    | \$3,505 |                                 |
|                 | Ceiling - Plaster/Drywall       | 218 Men's Washroom        | 380      | SF   | 6    | \$1,315 |                                 |
|                 | Doors - Transom Window          | 218 Men's Washroom        | 16       | SF   | 6    | \$271   | no doors                        |
|                 | Floor Drain                     | 218 Men's Washroom        | 1        | EA   | 6    | \$1,059 |                                 |
|                 | Floor - Tile Ceramic/ Porcelain | 218 Men's Washroom        | 50       | SF   | 4    | \$1,604 | damaged and deteriorated        |
|                 | Floor - Tile Ceramic/ Porcelain | 218 Men's Washroom        | 330      | SF   | 6    | \$698   |                                 |
|                 | Hand Dryer                      | 218 Men's Washroom        | 1        | EA   | 6    | \$230   |                                 |
|                 | Lavatory                        | 218 Men's Washroom        | 2        | EA   | 6    | \$639   |                                 |
|                 | Lighting - Pendant/Surface      | 218 Men's Washroom        | 6        | EA   | 6    | \$743   |                                 |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group           | Item - Type                     | Location                        | Quantity | Unit | Rank | Cost    | Comments   |
|-----------------|---------------------------------|---------------------------------|----------|------|------|---------|--|
| <b>Restroom</b> |                                 |                                 |          |      |      |         |  |
|                 | Partitions                      | 218 Men's Washroom              | 6        | EA   | 5    | \$4,505 | stone partitions have been painted and should be replaced. |
|                 | Partitions                      | 218 Men's Washroom              | 2        | EA   | 5    | \$1,502 | metal modesty partitions at door                           |
|                 | Urinals                         | 218 Men's Washroom              | 9        | EA   | 7    | \$0     |  |
|                 | Walls - Plaster/Drywall         | 218 Men's Washroom              | 320      | SF   | 5    | \$1,414 | painted stone panels                                       |
|                 | Walls - Plaster/Drywall         | 218 Men's Washroom              | 370      | SF   | 6    | \$1,021 |  |
|                 | Walls - Structural Glazed Tile  | 218 Men's Washroom              | 225      | SF   | 7    | \$0     | urinal wall.   |
|                 | Water Closet                    | 218 Men's Washroom              | 6        | EA   | 6    | \$2,016 |  |
|                 | Accessories                     | 220 Women                       | 136      | SF   | 7    | \$0     |  |
|                 | Ceiling - Plaster/Drywall       | 220 Women                       | 136      | SF   | 6    | \$471   |  |
|                 | Doors - Transom Window          | 220 Women                       | 10       | SF   | 7    | \$0     |  |
|                 | Doors - Wood Doors inclu hw     | 220 Women                       | 2        | EA   | 6    | \$602   |  |
|                 | Floor - Tile Ceramic/ Porcelain | 220 Women                       | 136      | SF   | 7    | \$0     |  |
|                 | Hand Dryer                      | 220 Women                       | 1        | EA   | 7    | \$0     |  |
|                 | Lavatory                        | 220 Women                       | 2        | EA   | 7    | \$0     |  |
|                 | Lighting - Pendant/Surface      | 220 Women                       | 3        | EA   | 7    | \$0     |  |
|                 | Partitions                      | 220 Women                       | 2        | EA   | 7    | \$0     |  |
|                 | Walls - Masonry                 | 220 Women                       | 325      | SF   | 7    | \$0     | Masonry is stone paneling                                  |
|                 | Walls - Plaster/Drywall         | 220 Women                       | 325      | SF   | 7    | \$0     |  |
|                 | Water Closet                    | 220 Women                       | 2        | EA   | 7    | \$0     |  |
|                 | Accessories                     | 221A - Social Worker's Bathroom | 51       | SF   | 6    | \$470   |  |
|                 | Ceiling - Plaster/Drywall       | 221A - Social Worker's Bathroom | 51       | SF   | 7    | \$0     |  |
|                 | Doors - Wood Doors inclu hw     | 221A - Social Worker's Bathroom | 1        | EA   | 6    | \$301   |  |
|                 | Floor - Tile Ceramic/ Porcelain | 221A - Social Worker's Bathroom | 51       | SF   | 6    | \$108   | Crack  |
|                 | Lavatory                        | 221A - Social Worker's Bathroom | 1        | EA   | 6    | \$320   |  |
|                 | Lighting - Pendant/Surface      | 221A - Social Worker's Bathroom | 1        | EA   | 4    | \$541   | t-12   |
|                 | Walls - Plaster/Drywall         | 221A - Social Worker's Bathroom | 345      | SF   | 6    | \$952   |  |
|                 | Water Closet                    | 221A - Social Worker's Bathroom | 1        | EA   | 6    | \$336   |  |
|                 | Accessories                     | 226                             | 242      | SF   | 6    | \$2,232 |  |
|                 | Ceiling - Plaster/Drywall       | 226                             | 242      | SF   | 6    | \$837   |  |
|                 | Doors - Transom Window          | 226                             | 20       | SF   | 7    | \$0     |  |
|                 | Doors - Wood Doors inclu hw     | 226                             | 2        | EA   | 5    | \$2,348 |  |
|                 | Floor Drain                     | 226                             | 1        | EA   | 7    | \$0     |  |
|                 | Floor - Tile Ceramic/ Porcelain | 226                             | 242      | SF   | 6    | \$512   |  |
|                 | Hand Dryer                      | 226                             | 1        | EA   | 7    | \$0     |  |
|                 | Lavatory                        | 226                             | 2        | EA   | 7    | \$0     |  |
|                 | Lighting - Pendant/Surface      | 226                             | 5        | EA   | 7    | \$0     |  |
|                 | Partitions                      | 226                             | 4        | EA   | 5    | \$3,003 | Partitions missing doors                                   |

## Building: Main

### Category: Rooms (Other Than Classrooms)

| Group           | Item - Type                     | Location                | Quantity | Unit | Rank | Cost    | Comments                                 |
|-----------------|---------------------------------|-------------------------|----------|------|------|---------|--|
| <b>Restroom</b> |                                 |                         |          |      |      |         |  |
|                 | Urinals                         | 226                     | 9        | EA   | 7    | \$0     |  |
|                 | Walls - Masonry                 | 226                     | 355      | SF   | 7    | \$0     | Masonry is stone paneling                |
|                 | Walls - Masonry                 | 226                     | 118      | SF   | 7    | \$0     | Masonry is glazed brick                  |
|                 | Walls - Plaster/Drywall         | 226                     | 475      | SF   | 5    | \$3,600 |  |
|                 | Water Closet                    | 226                     | 4        | EA   | 6    | \$1,344 |  |
|                 | Accessories                     | 227 Women (219 on plan) | 247      | SF   | 7    | \$0     | Room is currently being used for Storage |
|                 | Ceiling - Plaster/Drywall       | 227 Women (219 on plan) | 247      | SF   | 6    | \$855   |  |
|                 | Doors - Transom Window          | 227 Women (219 on plan) | 20       | SF   | 7    | \$0     |  |
|                 | Doors - Wood Doors inclu hw     | 227 Women (219 on plan) | 2        | EA   | 5    | \$2,348 |  |
|                 | Floor Drain                     | 227 Women (219 on plan) | 1        | EA   | 6    | \$1,059 |  |
|                 | Floor - Tile Ceramic/ Porcelain | 227 Women (219 on plan) | 247      | SF   | 6    | \$523   |  |
|                 | Hand Dryer                      | 227 Women (219 on plan) | 1        | EA   | 7    | \$0     |  |
|                 | Lavatory                        | 227 Women (219 on plan) | 2        | EA   | 6    | \$639   |  |
|                 | Lighting - Pendent/Surface      | 227 Women (219 on plan) | 6        | EA   | 7    | \$0     |  |
|                 | Partitions                      | 227 Women (219 on plan) | 7        | EA   | 7    | \$0     |  |
|                 | Walls - Masonry                 | 227 Women (219 on plan) | 475      | SF   | 7    | \$0     | Masonry is stone paneling                |
|                 | Walls - Plaster/Drywall         | 227 Women (219 on plan) | 475      | SF   | 5    | \$3,600 |  |
|                 | Water Closet                    | 227 Women (219 on plan) | 7        | EA   | 6    | \$2,352 |  |
|                 | Accessories                     | 238E Men Washroom       | 186      | SF   | 6    | \$1,716 |  |
|                 | Ceiling - Plaster/Drywall       | 238E Men Washroom       | 186      | SF   | 7    | \$0     |  |
|                 | Doors - Transom Window          | 238E Men Washroom       | 8        | SF   | 6    | \$135   |  |
|                 | Doors - Wood Doors inclu hw     | 238E Men Washroom       | 1        | EA   | 6    | \$301   |  |
|                 | Floor Drain                     | 238E Men Washroom       | 1        | EA   | 6    | \$1,059 |  |
|                 | Floor - Terrazzo                | 238E Men Washroom       | 174      | SF   | 6    | \$381   |  |
|                 | Floor - Tile Ceramic/ Porcelain | 238E Men Washroom       | 12       | SF   | 6    | \$25    | at urinals                               |
|                 | Lavatory                        | 238E Men Washroom       | 1        | EA   | 6    | \$320   |  |
|                 | Lighting - Pendent/Surface      | 238E Men Washroom       | 2        | EA   | 6    | \$248   |  |
|                 | Partitions                      | 238E Men Washroom       | 1        | EA   | 6    | \$297   | stone w/wood door                        |
|                 | Urinals                         | 238E Men Washroom       | 2        | EA   | 7    | \$0     |  |
|                 | Walls - Plaster/Drywall         | 238E Men Washroom       | 730      | SF   | 6    | \$2,015 |  |
|                 | Walls - Structural Glazed Tile  | 238E Men Washroom       | 72       | SF   | 7    | \$0     | at urinals                               |
|                 | Water Closet                    | 238E Men Washroom       | 1        | EA   | 6    | \$336   |  |
|                 | Accessories                     | 2nd Floor               | 410      | SF   | 6    | \$3,782 |  |
|                 | Ceiling - Plaster/Drywall       | 2nd Floor               | 410      | SF   | 6    | \$1,419 |  |
|                 | Floor Drain                     | 2nd Floor               | 1        | EA   | 6    | \$1,059 |  |
|                 | Floor - Tile Ceramic/ Porcelain | 2nd Floor               | 410      | SF   | 6    | \$868   |  |
|                 | Hand Dryer                      | 2nd Floor               | 1        | EA   | 7    | \$0     |  |



**Building: Main**

**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                      | Quantity | Unit | Rank | Cost    | Comments                          |
|-----------------|---------------------------------|-------------------------------|----------|------|------|---------|-----------------------------------|
| <b>Restroom</b> |                                 |                               |          |      |      |         |                                   |
|                 | Lavatory                        | 2nd Floor                     | 2        | EA   | 6    | \$639   |                                   |
|                 | Lighting - Pendent/Surface      | 2nd Floor                     | 6        | EA   | 7    | \$0     |                                   |
|                 | Partitions                      | 2nd Floor                     | 11       | EA   | 5    | \$8,260 |                                   |
|                 | Partitions                      | 2nd Floor                     | 3        | EA   | 6    | \$891   |                                   |
|                 | Walls - Plaster/Drywall         | 2nd Floor                     | 955      | SF   | 6    | \$2,636 |                                   |
|                 | Water Closet                    | 2nd Floor                     | 14       | EA   | 6    | \$4,704 |                                   |
|                 | Accessories                     | 329G Teachers Lounge/Restroom | 66       | SF   | 7    | \$0     | Most of the room used for storage |
|                 | Ceiling - Plaster/Drywall       | 329G Teachers Lounge/Restroom | 310      | SF   | 5    | \$2,842 |                                   |
|                 | Doors - Steel Doors incl hw     | 329G Teachers Lounge/Restroom | 3        | EA   | 6    | \$903   |                                   |
|                 | Floor Drain                     | 329G Teachers Lounge/Restroom | 2        | EA   | 7    | \$0     |                                   |
|                 | Floor - Tile Ceramic/ Porcelain | 329G Teachers Lounge/Restroom | 310      | SF   | 6    | \$656   |                                   |
|                 | Lavatory                        | 329G Teachers Lounge/Restroom | 1        | EA   | 7    | \$0     |                                   |
|                 | Lighting - Pendent/Surface      | 329G Teachers Lounge/Restroom | 6        | EA   | 4    | \$3,244 | T12                               |
|                 | Partitions                      | 329G Teachers Lounge/Restroom | 2        | EA   | 5    | \$1,502 |                                   |
|                 | Walls - Plaster/Drywall         | 329G Teachers Lounge/Restroom | 819      | SF   | 5    | \$6,207 |                                   |
|                 | Water Closet                    | 329G Teachers Lounge/Restroom | 1        | EA   | 7    | \$0     | 2nd stall missing the watercloset |
|                 | Accessories                     | Boiler Room                   | 60       | SF   | 6    | \$553   |                                   |
|                 | Ceiling - Plaster/Drywall       | Boiler Room                   | 60       | SF   | 6    | \$208   |                                   |
|                 | Doors - Wood Doors inclu hw     | Boiler Room                   | 1        | EA   | 6    | \$301   |                                   |
|                 | Floor - Concrete                | Boiler Room                   | 60       | SF   | 5    | \$103   |                                   |
|                 | Lavatory                        | Boiler Room                   | 1        | EA   | 6    | \$320   |                                   |
|                 | Lighting - Pendent/Surface      | Boiler Room                   | 1        | EA   | 6    | \$124   |                                   |
|                 | Partitions                      | Boiler Room                   | 1        | EA   | 5    | \$751   | Stone partition with no door      |
|                 | Showers                         | Boiler Room                   | 1        | EA   | 5    | \$1,172 | shower base is cracked.           |
|                 | Walls - Plaster/Drywall         | Boiler Room                   | 250      | SF   | 5    | \$1,895 | Cracks and peeling paint.         |
|                 | Water Closet                    | Boiler Room                   | 1        | EA   | 6    | \$336   |                                   |

**Rooms (Other Than Classrooms) Subtotal:**

**\$3,109,543**

**Building: Main**

**Category: Building Interior**

| Group           | Item - Type                          | Location                  | Quantity | Unit | Rank | Cost    | Comments      |
|-----------------|--------------------------------------|---------------------------|----------|------|------|---------|---------------|
| <b>Corridor</b> |                                      |                           |          |      |      |         |               |
|                 | Ceiling - Plaster/Drywall            | 108C Auditorium Vestibule | 535      | SF   | 6    | \$3,313 |               |
|                 | Doors - Wood Doors include hw        | 108C Auditorium Vestibule | 2        | EA   | 5    | \$2,348 |               |
|                 | Drinking Fountains - Single Fountain | 108C Auditorium Vestibule | 2        | EA   | 6    | \$551   | in auditorium |
|                 | Floor - Terrazzo                     | 108C Auditorium Vestibule | 535      | SF   | 7    | \$0     |               |

## Building: Main

### Category: Building Interior

| Group           | Item - Type                    | Location  | Quantity | Unit | Rank | Cost    | Comments                                    |
|-----------------|--------------------------------|---|----------|------|------|---------|---|
| <b>Corridor</b> |                                |   |          |      |      |         |   |
|                 | Lighting - Pendent/Surface     | 108C Auditorium Vestibule                               | 3        | EA   | 6    | \$372   |   |
|                 | Walls - Plaster/Drywall        | 108C Auditorium Vestibule                               | 665      | SF   | 6    | \$2,948 |   |
|                 | Walls - Plaster/Drywall        | 108C Auditorium Vestibule                               | 15       | SF   | 4    | \$221   | deterioration, holes at boys restroom entry |
|                 | Ceiling - Plaster/Drywall      | 155C Vestibule / 1st Floor                              | 89       | SF   | 7    | \$0     |   |
|                 | Doors - Wood Doors include hw  | 155C Vestibule / 1st Floor                              | 2        | EA   | 6    | \$602   |   |
|                 | Floor - Terrazzo               | 155C Vestibule / 1st Floor                              | 89       | SF   | 6    | \$747   |   |
|                 | Lighting - Pendent/Surface     | 155C Vestibule / 1st Floor                              | 1        | EA   | 6    | \$124   |   |
|                 | Walls - Plaster/Drywall        | 155C Vestibule / 1st Floor                              | 75       | SF   | 6    | \$332   |   |
|                 | Walls - Structural Glazed Tile | 155C Vestibule / 1st Floor                              | 162      | SF   | 6    | \$510   |   |
|                 | Ceiling - Plaster/Drywall      | 163C - 1st Floor Vestibule                              | 66       | SF   | 7    | \$0     |   |
|                 | Doors - Steel Doors incl hw    | 163C - 1st Floor Vestibule                              | 2        | EA   | 5    | \$2,758 |   |
|                 | Doors - Transom Window         | 163C - 1st Floor Vestibule                              | 10       | EA   | 6    | \$169   |   |
|                 | Floor - Terrazzo               | 163C - 1st Floor Vestibule                              | 66       | SF   | 6    | \$554   |   |
|                 | Lighting - Pendent/Surface     | 163C - 1st Floor Vestibule                              | 1        | EA   | 6    | \$124   |   |
|                 | Walls - Plaster/Drywall        | 163C - 1st Floor Vestibule                              | 97       | SF   | 6    | \$430   |   |
|                 | Walls - Structural Glazed Tile | 163C - 1st Floor Vestibule                              | 175      | SF   | 6    | \$551   |   |
|                 | Ceiling - Plaster/Drywall      | 172C Cafeteria Vestibule                                | 130      | SF   | 7    | \$0     |   |
|                 | Doors - Wood Doors include hw  | 172C Cafeteria Vestibule                                | 3        | EA   | 5    | \$3,522 |   |
|                 | Floor - Terrazzo               | 172C Cafeteria Vestibule                                | 130      | SF   | 7    | \$0     |   |
|                 | Lighting - Pendent/Surface     | 172C Cafeteria Vestibule                                | 2        | EA   | 7    | \$0     |   |
|                 | Walls - Plaster/Drywall        | 172C Cafeteria Vestibule                                | 205      | SF   | 6    | \$909   |   |
|                 | Walls - Structural Glazed Tile | 172C Cafeteria Vestibule                                | 195      | SF   | 6    | \$613   | glazed brick                                |
|                 | Ceiling - Lay-in               | 1st Floor Corr. North Wing at Rm. 145, Teachers' Lounge | 627      | SF   | 6    | \$1,883 |   |
|                 | Doors - Wood Doors include hw  | 1st Floor Corr. North Wing at Rm. 145, Teachers' Lounge | 2        | EA   | 5    | \$2,348 |   |
|                 | Floor - Terrazzo               | 1st Floor Corr. North Wing at Rm. 145, Teachers' Lounge | 627      | SF   | 6    | \$5,263 |   |
|                 | Lighting - Lay-in              | 1st Floor Corr. North Wing at Rm. 145, Teachers' Lounge | 15       | EA   | 6    | \$1,785 |   |
|                 | Walls - Plaster/Drywall        | 1st Floor Corr. North Wing at Rm. 145, Teachers' Lounge | 798      | SF   | 6    | \$3,538 |   |
|                 | Walls - Structural Glazed Tile | 1st Floor Corr. North Wing at Rm. 145, Teachers' Lounge | 1,707    | SF   | 6    | \$5,370 |   |
|                 | Ceiling - Lay-in               | 1st Floor Lunchroom                                     | 528      | SF   | 6    | \$1,586 |   |
|                 | Floor - Terrazzo               | 1st Floor Lunchroom                                     | 528      | SF   | 7    | \$0     |   |
|                 | Lighting - Pendent/Surface     | 1st Floor Lunchroom                                     | 6        | EA   | 7    | \$0     |   |
|                 | Walls - Plaster/Drywall        | 1st Floor Lunchroom                                     | 80       | SF   | 6    | \$355   |   |
|                 | Walls - Structural Glazed Tile | 1st Floor Lunchroom                                     | 410      | SF   | 6    | \$1,290 | glazed brick                                |

**Building: Main**

**Category: Building Interior**

| Group           | Item - Type                          | Location   | Quantity | Unit | Rank | Cost     | Comments |
|-----------------|--------------------------------------|--|----------|------|------|----------|----------|
| <b>Corridor</b> |                                      |  |          |      |      |          |          |
|                 | Ceiling - Lay-in                     | 1st Floor North Wing, West Side Corridor / 1st Floor         | 1,006    | SF   | 6    | \$3,021  |          |
|                 | Doors - Transom Window               | 1st Floor North Wing, West Side Corridor / 1st Floor         | 84       | EA   | 6    | \$1,422  |          |
|                 | Doors - Wood Doors include hw        | 1st Floor North Wing, West Side Corridor / 1st Floor         | 4        | EA   | 6    | \$1,204  |          |
|                 | Floor - Terrazzo                     | 1st Floor North Wing, West Side Corridor / 1st Floor         | 1,006    | SF   | 6    | \$8,444  |          |
|                 | Lighting - Lay-in                    | 1st Floor North Wing, West Side Corridor / 1st Floor         | 16       | EA   | 6    | \$1,904  |          |
|                 | Walls - Structural Glazed Tile       | 1st Floor North Wing, West Side Corridor / 1st Floor         | 2,343    | SF   | 6    | \$7,371  |          |
|                 | Ceiling - Lay-in                     | 1st Floor  | 10,709   | SF   | 6    | \$32,159 |          |
|                 | Ceiling - Plaster/Drywall            | 1st Floor  | 208      | SF   | 7    | \$0      |          |
|                 | Doors - Transom Window               | 1st Floor  | 18       | EA   | 6    | \$305    |          |
|                 | Doors - Wood Doors include hw        | 1st Floor  | 6        | EA   | 6    | \$1,806  |          |
|                 | Drinking Fountains - Single Fountain | 1st Floor  | 6        | EA   | 7    | \$0      |          |
|                 | Floor - Terrazzo                     | 1st Floor  | 2,255    | SF   | 6    | \$18,929 |          |
|                 | Floor - Tile/Sheet                   | 1st Floor  | 8,599    | SF   | 6    | \$4,673  |          |
|                 | Lighting - Lay-in                    | 1st Floor  | 15       | EA   | 7    | \$0      |          |
|                 | Lighting - Pendent/Surface           | 1st Floor  | 120      | EA   | 7    | \$0      |          |
|                 | Lighting - Wall Mounted              | 1st Floor  | 2        | EA   | 7    | \$0      |          |
|                 | Student Lockers - One Tier           | 1st Floor  | 343      | EA   | 7    | \$0      |          |
|                 | Walls - Masonry                      | 1st Floor  | 5,510    | SF   | 7    | \$0      |          |
|                 | Walls - Plaster/Drywall              | 1st Floor  | 7,945    | SF   | 7    | \$0      |          |
|                 | Walls - Plaster/Drywall              | 1st Floor  | 586      | SF   | 6    | \$3,645  |          |
|                 | Ceiling - Lay-in                     | 1st Flr at North Wing outside of engineer office / 1st Floor | 627      | SF   | 6    | \$1,883  |          |
|                 | Doors - Wood Doors include hw        | 1st Flr at North Wing outside of engineer office / 1st Floor | 2        | EA   | 6    | \$602    |          |
|                 | Floor - Terrazzo                     | 1st Flr at North Wing outside of engineer office / 1st Floor | 627      | SF   | 6    | \$5,263  |          |
|                 | Lighting - Lay-in                    | 1st Flr at North Wing outside of engineer office / 1st Floor | 15       | EA   | 7    | \$0      |          |
|                 | Walls - Structural Glazed Tile       | 1st Flr at North Wing outside of engineer office / 1st Floor | 1,707    | SF   | 6    | \$5,370  |          |
|                 | Walls - Tile Ceramic/ Porcelain      | 1st Flr at North Wing outside of engineer office / 1st Floor | 786      | SF   | 6    | \$2,473  |          |
|                 | Ceiling - Lay-in                     | 1st North West Corridor at North Wing                        | 318      | SF   | 6    | \$955    |          |
|                 | Doors - Transom Window               | 1st North West Corridor at North Wing                        | 15       | EA   | 6    | \$254    |          |
|                 | Doors - Wood Doors include hw        | 1st North West Corridor at North Wing                        | 2        | EA   | 6    | \$602    |          |

**Building: Main**

**Category: Building Interior**

| Group           | Item - Type                          | Location                                | Quantity | Unit | Rank | Cost     | Comments                                      |
|-----------------|--------------------------------------|---|----------|------|------|----------|---|
| <b>Corridor</b> |                                      |   |          |      |      |          |   |
|                 | Floor - Terrazzo                     | 1st North West Corridor at North Wing   | 318      | SF   | 6    | \$2,669  |   |
|                 | Lighting - Lay-in                    | 1st North West Corridor at North Wing   | 8        | EA   | 7    | \$0      |   |
|                 | Walls - Plaster/Drywall              | 1st North West Corridor at North Wing   | 1,484    | SF   | 6    | \$6,579  |   |
|                 | Walls - Structural Glazed Tile       | 1st North West Corridor at North Wing   | 1,484    | SF   | 6    | \$4,669  |   |
|                 | Ceiling - Lay-in                     | 2nd Floor                               | 10,064   | SF   | 6    | \$30,222 |   |
|                 | Ceiling - Plaster/Drywall            | 2nd Floor                               | 371      | SF   | 7    | \$0      |   |
|                 | Drinking Fountains - Single Fountain | 2nd Floor                               | 5        | EA   | 7    | \$0      |   |
|                 | Floor - Terrazzo                     | 2nd Floor                               | 1,350    | SF   | 6    | \$11,332 |   |
|                 | Floor - Tile/Sheet                   | 2nd Floor                               | 9,183    | SF   | 7    | \$0      |   |
|                 | Lighting - Pendent/Surface           | 2nd Floor                               | 119      | EA   | 7    | \$0      |   |
|                 | Student Lockers - One Tier           | 2nd Floor                               | 307      | EA   | 7    | \$0      |   |
|                 | Walls - Masonry                      | 2nd Floor                               | 390      | SF   | 7    | \$0      |   |
|                 | Walls - Masonry                      | 2nd Floor                               | 5,939    | SF   | 7    | \$0      |   |
|                 | Walls - Plaster/Drywall              | 2nd Floor                               | 5,893    | SF   | 6    | \$26,124 |   |
|                 | Drinking Fountains - Single Fountain | 2nd Floor                               | 1        | EA   | 4    | \$3,908  |   |
|                 | Ceiling - Lay-in                     | 3rd Floor                               | 3,728    | SF   | 6    | \$11,195 |   |
|                 | Ceiling - Plaster/Drywall            | 3rd Floor                               | 174      | SF   | 7    | \$0      |   |
|                 | Drinking Fountains - Single Fountain | 3rd Floor                               | 2        | EA   | 7    | \$0      |   |
|                 | Floor - Terrazzo                     | 3rd Floor                               | 1,195    | SF   | 7    | \$0      |   |
|                 | Floor - Tile/Sheet                   | 3rd Floor                               | 2,707    | SF   | 7    | \$0      |   |
|                 | Lighting - Pendent/Surface           | 3rd Floor                               | 43       | EA   | 7    | \$0      |   |
|                 | Student Lockers - One Tier           | 3rd Floor                               | 91       | EA   | 7    | \$0      |   |
|                 | Walls - Masonry                      | 3rd Floor                               | 550      | SF   | 7    | \$0      |   |
|                 | Walls - Plaster/Drywall              | 3rd Floor                               | 3,147    | SF   | 6    | \$13,951 |   |
|                 | Ceiling - Exposed                    | Basement - Main Center Corridor runs NS | 9,500    | SF   | 6    | \$14,128 |   |
|                 | Doors - Steel Doors incl hw          | Basement - Main Center Corridor runs NS | 4        | EA   | 6    | \$1,204  |   |
|                 | Doors - Steel Doors incl hw          | Basement - Main Center Corridor runs NS | 1        | EA   | 7    | \$0      |   |
|                 | Doors - Wood Doors include hw        | Basement - Main Center Corridor runs NS | 6        | EA   | 6    | \$1,806  |   |
|                 | Doors - Wood Doors include hw        | Basement - Main Center Corridor runs NS | 28       | EA   | 6    | \$8,428  |   |
|                 | Floor - Concrete Epoxy/ Painted      | Basement - Main Center Corridor runs NS | 9,500    | SF   | 6    | \$4,619  |   |
|                 | Lighting - Pendent/Surface           | Basement - Main Center Corridor runs NS | 12       | EA   | 7    | \$0      |   |
|                 | Walls - Concrete Block               | Basement - Main Center Corridor runs NS | 8,800    | SF   | 6    | \$25,797 | signs of water infiltration and peeling paint |

**Building: Main**

**Category: Building Interior**

| Group           | Item - Type                    | Location  | Quantity | Unit | Rank | Cost    | Comments         |
|-----------------|--------------------------------|---|----------|------|------|---------|------------------|
| <b>Corridor</b> |                                |   |          |      |      |         |                  |
|                 | Ceiling - Plaster/Drywall      | North East from Gym 240                             | 364      | SF   | 5    | \$4,586 | Water Filtration |
|                 | Floor - Terrazzo               | North East from Gym 240                             | 364      | SF   | 6    | \$3,055 |                  |
|                 | Lighting - Pendent/Surface     | North East from Gym 240                             | 5        | EA   | 6    | \$619   |                  |
|                 | Walls - Plaster/Drywall        | North East from Gym 240                             | 429      | SF   | 6    | \$1,902 |                  |
|                 | Walls - Structural Glazed Tile | North East from Gym 240                             | 531      | SF   | 6    | \$1,671 |                  |
|                 | Doors - Wood Doors include hw  | North Stair between Gyms - 143S                     | 4        | EA   | 6    | \$1,204 |                  |
|                 | Ceiling - Plaster/Drywall      | North Vestibule Adjacent to Main Office / 1st Floor | 104      | SF   | 7    | \$0     |                  |
|                 | Doors - Wood Doors include hw  | North Vestibule Adjacent to Main Office / 1st Floor | 2        | EA   | 6    | \$602   |                  |
|                 | Floor - Terrazzo               | North Vestibule Adjacent to Main Office / 1st Floor | 104      | SF   | 6    | \$873   |                  |
|                 | Lighting - Pendent/Surface     | North Vestibule Adjacent to Main Office / 1st Floor | 2        | EA   | 6    | \$248   |                  |
|                 | Walls - Masonry                | North Vestibule Adjacent to Main Office / 1st Floor | 182      | SF   | 6    | \$573   |                  |
|                 | Walls - Plaster/Drywall        | North Vestibule Adjacent to Main Office / 1st Floor | 182      | SF   | 6    | \$807   |                  |
|                 | Ceiling - Plaster/Drywall      | Northern Vestibule off of Main Corridor / 1st Floor | 84       | SF   | 6    | \$520   |                  |
|                 | Doors - Wood Doors include hw  | Northern Vestibule off of Main Corridor / 1st Floor | 2        | EA   | 6    | \$602   |                  |
|                 | Floor - Terrazzo               | Northern Vestibule off of Main Corridor / 1st Floor | 90       | SF   | 6    | \$755   |                  |
|                 | Lighting - Pendent/Surface     | Northern Vestibule off of Main Corridor / 1st Floor | 2        | EA   | 6    | \$248   |                  |
|                 | Walls - Masonry                | Northern Vestibule off of Main Corridor / 1st Floor | 185      | SF   | 6    | \$582   |                  |
|                 | Walls - Plaster/Drywall        | Northern Vestibule off of Main Corridor / 1st Floor | 185      | SF   | 6    | \$820   |                  |
|                 | Ceiling - Plaster/Drywall      | South Vestibule Adjacent to Main Office / 1st Floor | 104      | SF   | 6    | \$644   |                  |
|                 | Doors - Wood Doors include hw  | South Vestibule Adjacent to Main Office / 1st Floor | 2        | EA   | 6    | \$602   |                  |
|                 | Floor - Terrazzo               | South Vestibule Adjacent to Main Office / 1st Floor | 104      | SF   | 6    | \$873   |                  |
|                 | Lighting - Pendent/Surface     | South Vestibule Adjacent to Main Office / 1st Floor | 2        | EA   | 6    | \$248   |                  |
|                 | Walls - Masonry                | South Vestibule Adjacent to Main Office / 1st Floor | 182      | SF   | 6    | \$573   |                  |
|                 | Walls - Plaster/Drywall        | South Vestibule Adjacent to Main Office / 1st Floor | 182      | SF   | 6    | \$807   |                  |

**Building: Main**

**Category: Building Interior**

| Group         | Item - Type                    | Location  | Quantity | Unit | Rank | Cost     | Comments  |
|---------------|--------------------------------|---|----------|------|------|----------|---|
| <b>Safety</b> | Security Cameras               |   | 24       | EA   | 5    | \$16,505 | Cameras viewed over internet; Bldg Eng. indicated about 20% are off-line but a camera upgrade project is scheduled for this school. |
| <b>Stairs</b> | Ceiling - Exposed              | 241   | 109      | SF   | 4    | \$497    | severely peeling paint; mold may be present   |
|               | Floor - Terrazzo               | 241   | 15       | SF   | 6    | \$126    |   |
|               | Handrails                      | 241   | 58       | LF   | 6    | \$503    |   |
|               | Lighting - Pendent/Surface     | 241   | 1        | EA   | 6    | \$124    |   |
|               | Lighting - Wall Mounted        | 241   | 1        | EA   | 6    | \$124    |   |
|               | Stairs - Terrazzo              | 241   | 94       | LF   | 6    | \$872    |   |
|               | Walls - Plaster/Drywall        | 241   | 136      | SF   | 6    | \$375    |   |
|               | Walls - Structural Glazed Tile | 241   | 407      | SF   | 6    | \$1,280  |   |
|               | Ceiling - Plaster/Drywall      | 112S & 128S Stairs/Vestibules Center Wing North & South | 844      | SF   | 7    | \$0      |   |
|               | Floor - Terrazzo               | 112S & 128S Stairs/Vestibules Center Wing North & South | 554      | SF   | 7    | \$0      |   |
|               | Floor - Tile/Sheet             | 112S & 128S Stairs/Vestibules Center Wing North & South | 172      | SF   | 7    | \$0      |   |
|               | Handrails                      | 112S & 128S Stairs/Vestibules Center Wing North & South | 136      | LF   | 7    | \$0      |   |
|               | Lighting - Pendent/Surface     | 112S & 128S Stairs/Vestibules Center Wing North & South | 12       | EA   | 7    | \$0      |   |
|               | Lighting - Wall Mounted        | 112S & 128S Stairs/Vestibules Center Wing North & South | 4        | EA   | 7    | \$0      |   |
|               | Stairs - Terrazzo              | 112S & 128S Stairs/Vestibules Center Wing North & South | 638      | LF   | 7    | \$0      |   |
|               | Walls - Masonry                | 112S & 128S Stairs/Vestibules Center Wing North & South | 1,094    | SF   | 7    | \$0      | Masonry is glazed brick   |
|               | Walls - Plaster/Drywall        | 112S & 128S Stairs/Vestibules Center Wing North & South | 1,094    | SF   | 7    | \$0      |   |
|               | Ceiling - Lay-in               | 126S Stair/Vestibule Center Wing West                   | 240      | SF   | 6    | \$721    |   |
|               | Ceiling - Plaster/Drywall      | 126S Stair/Vestibule Center Wing West                   | 90       | SF   | 7    | \$0      |   |
|               | Floor - Terrazzo               | 126S Stair/Vestibule Center Wing West                   | 353      | SF   | 7    | \$0      |   |
|               | Handrails                      | 126S Stair/Vestibule Center Wing West                   | 72       | LF   | 6    | \$624    |   |
|               | Lighting - Pendent/Surface     | 126S Stair/Vestibule Center Wing West                   | 5        | EA   | 7    | \$0      |   |
|               | Stairs - Terrazzo              | 126S Stair/Vestibule Center Wing West                   | 319      | LF   | 7    | \$0      |   |
|               | Walls - Masonry                | 126S Stair/Vestibule Center Wing West                   | 1,005    | SF   | 7    | \$0      | Masonry is glazed brick   |
|               | Walls - Plaster/Drywall        | 126S Stair/Vestibule Center Wing West                   | 1,005    | SF   | 7    | \$0      |   |
|               | Ceiling - Exposed              | 143S Stair/Vestibule North Wing between Gymnasiums      | 168      | SF   | 7    | \$0      |   |

**Building: Main**

**Category: Building Interior**

| Group         | Item - Type                    | Location   | Quantity | Unit | Rank | Cost    | Comments |
|---------------|--------------------------------|--|----------|------|------|---------|----------|
| <b>Stairs</b> |                                |  |          |      |      |         |          |
|               | Ceiling - Plaster/Drywall      | 143S Stair/Vestibule North Wing between Gymnasiums | 750      | SF   | 6    | \$5,491 |          |
|               | Floor - Terrazzo               | 143S Stair/Vestibule North Wing between Gymnasiums | 900      | SF   | 6    | \$7,555 |          |
|               | Handrails                      | 143S Stair/Vestibule North Wing between Gymnasiums | 112      | LF   | 6    | \$971   |          |
|               | Lighting - Pendent/Surface     | 143S Stair/Vestibule North Wing between Gymnasiums | 18       | EA   | 6    | \$2,230 |          |
|               | Stairs - Terrazzo              | 143S Stair/Vestibule North Wing between Gymnasiums | 385      | LF   | 6    | \$3,573 |          |
|               | Walls - Masonry                | 143S Stair/Vestibule North Wing between Gymnasiums | 1,200    | SF   | 6    | \$3,775 |          |
|               | Walls - Plaster/Drywall        | 143S Stair/Vestibule North Wing between Gymnasiums | 660      | SF   | 6    | \$1,822 |          |
|               | Ceiling - Exposed              | 177S Stair/Vestibule South Wing by Kitchen         | 30       | SF   | 7    | \$0     |          |
|               | Ceiling - Lay-in               | 177S Stair/Vestibule South Wing by Kitchen         | 368      | SF   | 6    | \$1,105 |          |
|               | Ceiling - Plaster/Drywall      | 177S Stair/Vestibule South Wing by Kitchen         | 180      | SF   | 7    | \$0     |          |
|               | Floor - Terrazzo               | 177S Stair/Vestibule South Wing by Kitchen         | 450      | SF   | 6    | \$3,777 |          |
|               | Handrails                      | 177S Stair/Vestibule South Wing by Kitchen         | 58       | LF   | 6    | \$503   |          |
|               | Lighting - Lay-in              | 177S Stair/Vestibule South Wing by Kitchen         | 4        | EA   | 7    | \$0     |          |
|               | Lighting - Pendent/Surface     | 177S Stair/Vestibule South Wing by Kitchen         | 1        | EA   | 7    | \$0     |          |
|               | Stairs - Terrazzo              | 177S Stair/Vestibule South Wing by Kitchen         | 131      | LF   | 6    | \$1,216 |          |
|               | Walls - Plaster/Drywall        | 177S Stair/Vestibule South Wing by Kitchen         | 300      | SF   | 7    | \$0     |          |
|               | Walls - Structural Glazed Tile | 177S Stair/Vestibule South Wing by Kitchen         | 546      | SF   | 7    | \$0     |          |
|               | Ceiling - Exposed              | 178S Stair/Vestibule SE Main Corridor              | 30       | SF   | 7    | \$0     |          |
|               | Ceiling - Lay-in               | 178S Stair/Vestibule SE Main Corridor              | 580      | SF   | 6    | \$1,742 |          |
|               | Ceiling - Plaster/Drywall      | 178S Stair/Vestibule SE Main Corridor              | 240      | SF   | 6    | \$1,757 |          |
|               | Floor - Terrazzo               | 178S Stair/Vestibule SE Main Corridor              | 700      | SF   | 6    | \$5,876 |          |
|               | Handrails                      | 178S Stair/Vestibule SE Main Corridor              | 81       | LF   | 6    | \$702   |          |
|               | Lighting - Lay-in              | 178S Stair/Vestibule SE Main Corridor              | 8        | EA   | 6    | \$952   |          |
|               | Lighting - Pendent/Surface     | 178S Stair/Vestibule SE Main Corridor              | 4        | EA   | 7    | \$0     |          |
|               | Stairs - Terrazzo              | 178S Stair/Vestibule SE Main Corridor              | 162      | LF   | 6    | \$1,503 |          |

**Building: Main**

**Category: Building Interior**

| Group         | Item - Type                    | Location                              | Quantity | Unit | Rank | Cost    | Comments     |
|---------------|--------------------------------|---------------------------------------|----------|------|------|---------|--------------|
| <b>Stairs</b> |                                |                                       |          |      |      |         |              |
|               | Walls - Masonry                | 178S Stair/Vestibule SE Main Corridor | 923      | SF   | 7    | \$0     |              |
|               | Walls - Plaster/Drywall        | 178S Stair/Vestibule SE Main Corridor | 500      | SF   | 7    | \$0     |              |
|               | Ceiling - Exposed              | 191S Stair/Vestibule NE Main Corridor | 70       | SF   | 7    | \$0     |              |
|               | Ceiling - Lay-in               | 191S Stair/Vestibule NE Main Corridor | 388      | SF   | 6    | \$1,165 |              |
|               | Ceiling - Plaster/Drywall      | 191S Stair/Vestibule NE Main Corridor | 240      | SF   | 7    | \$0     |              |
|               | Floor - Terrazzo               | 191S Stair/Vestibule NE Main Corridor | 567      | SF   | 6    | \$4,759 |              |
|               | Handrails                      | 191S Stair/Vestibule NE Main Corridor | 70       | LF   | 6    | \$607   |              |
|               | Lighting - Lay-in              | 191S Stair/Vestibule NE Main Corridor | 6        | EA   | 7    | \$0     |              |
|               | Lighting - Pendent/Surface     | 191S Stair/Vestibule NE Main Corridor | 3        | EA   | 7    | \$0     |              |
|               | Stairs - Terrazzo              | 191S Stair/Vestibule NE Main Corridor | 162      | LF   | 6    | \$1,503 |              |
|               | Walls - Masonry                | 191S Stair/Vestibule NE Main Corridor | 800      | SF   | 7    | \$0     |              |
|               | Walls - Masonry                | 191S Stair/Vestibule NE Main Corridor | 40       | SF   | 4    | \$3,996 |              |
|               | Walls - Plaster/Drywall        | 191S Stair/Vestibule NE Main Corridor | 462      | SF   | 7    | \$0     |              |
|               | Ceiling - Plaster/Drywall      | 240S                                  | 216      | SF   | 5    | \$3,175 | Water damage |
|               | Floor - Terrazzo               | 240S                                  | 101      | SF   | 6    | \$848   |              |
|               | Handrails                      | 240S                                  | 64       | LF   | 6    | \$555   |              |
|               | Lighting - Lay-in              | 240S                                  | 6        | EA   | 6    | \$714   |              |
|               | Lighting - Pendent/Surface     | 240S                                  | 2        | EA   | 6    | \$248   |              |
|               | Stairs - Terrazzo              | 240S                                  | 72       | LF   | 6    | \$668   |              |
|               | Walls - Plaster/Drywall        | 240S                                  | 346      | SF   | 5    | \$1,578 | water damage |
|               | Walls - Structural Glazed Tile | 240S                                  | 692      | SF   | 6    | \$2,177 |              |
|               | Ceiling - Plaster/Drywall      | 247                                   | 113      | SF   | 7    | \$0     |              |
|               | Floor - Terrazzo               | 247                                   | 113      | SF   | 6    | \$949   |              |
|               | Handrails                      | 247                                   | 52       | LF   | 6    | \$451   |              |
|               | Lighting - Pendent/Surface     | 247                                   | 3        | EA   | 6    | \$372   |              |
|               | Stairs - Concrete              | 247                                   | 21       | LF   | 6    | \$174   |              |
|               | Walls - Plaster/Drywall        | 247                                   | 285      | SF   | 6    | \$787   |              |
|               | Walls - Structural Glazed Tile | 247                                   | 854      | SF   | 6    | \$2,687 |              |
|               | Ceiling - Plaster/Drywall      | 249                                   | 84       | SF   | 4    | \$1,994 | Water damage |
|               | Floor - Terrazzo               | 249                                   | 33       | SF   | 6    | \$277   |              |
|               | Handrails                      | 249                                   | 22       | LF   | 6    | \$191   |              |
|               | Lighting - Pendent/Surface     | 249                                   | 2        | EA   | 6    | \$248   |              |
|               | Stairs - Terrazzo              | 249                                   | 71       | LF   | 6    | \$659   |              |
|               | Walls - Plaster/Drywall        | 249                                   | 184      | SF   | 5    | \$839   | water damage |
|               | Walls - Structural Glazed Tile | 249                                   | 374      | SF   | 6    | \$1,177 |              |



**Building: Main**

**Category: Building Interior**

| Group                              | Item - Type | Location | Quantity | Unit | Rank | Cost             | Comments |
|------------------------------------|-------------|----------|----------|------|------|------------------|----------|
| <b>Building Interior Subtotal:</b> |             |          |          |      |      | <b>\$436,538</b> |          |

**Total Building Cost**

**\$19,696,406**

**SITE**

**Category: Site**

| Group                 | Item - Type                            | Location                     | Quantity | Unit | Rank | Cost     | Comments  |
|-----------------------|--|------------------------------|----------|------|------|----------|---|
| <b>Civil/Drainage</b> |  |                              |          |      |      |          |   |
|                       | Civil/ Drainage - Catch Basin          | Entire Site                  | 5        | EA   | 7    | \$0      |   |
|                       | Civil/ Drainage - Site Manhole         | Entire Site                  | 28       | EA   | 7    | \$0      |   |
| <b>Fencing</b>        |  |                              |          |      |      |          |   |
|                       | Fencing - Chain Link                   | Entire Site / Site West      | 350      | LF   | 6    | \$6,572  |   |
|                       | Fencing - New Standard Ornamental      | Entire Site / Site South     | 26       | LF   | 7    | \$0      |   |
| <b>Landscape</b>      |  |                              |          |      |      |          |   |
|                       | Landscape - Grass                      | Entire Site                  | 58,120   | SF   | 6    | \$48,205 |   |
|                       | Landscape - Hardscape- Concrete        | Entire Site                  | 16,236   | SF   | 6    | \$83,815 |   |
|                       | Landscape - Hardscape- Concrete        | Entire Site / Site North     | 100      | SF   | 5    | \$1,276  | cracking  |
|                       | Landscape - Hardscape- Concrete        | Entire Site / West Courtyard | 150      | SF   | 5    | \$1,913  | ponding at retaining wall                       |
|                       | Parkway trees                          | Entire Site                  | 34       | EA   | 7    | \$0      |   |
|                       | Planting Beds/ Area                    | Entire Site                  | 788      | SF   | 5    | \$2,389  | mainly on east side                             |
|                       | Retaining Wall - Concrete              | Entire Site                  | 1,836    | SF   | 6    | \$43,032 | south door 6                                    |
|                       | Retaining Wall - Concrete              | Entire Site / North          | 100      | SF   | 4    | \$13,831 | crack   |
| <b>Parking Lot</b>    |  |                              |          |      |      |          |   |
|                       | Surface - Asphalt                      | North                        | 22,203   | SF   | 6    | \$53,658 |   |
|                       | Surface - Asphalt                      | North                        | 500      | SF   | 5    | \$2,953  | cracking at perimeter and manholes/catch basins |
| <b>Sidewalks</b>      |  |                              |          |      |      |          |   |
|                       | Sidewalks - Perimeter Sidewalks        | Entire Site                  | 12,351   | SF   | 6    | \$24,550 |   |
|                       | Sidewalks - Perimeter Sidewalks        | Entire Site / Site - East    | 420      | SF   | 5    | \$4,012  |   |
| <b>Signage</b>        |  |                              |          |      |      |          |   |
|                       | Flag Pole - Building Mounted Flag Pole | Entire Site                  | 1        | EA   | 7    | \$0      |   |
|                       | Marquee - Free Standing Back Lighted   | Entire Site                  | 1        | EA   | 7    | \$0      |   |

**Site Subtotal:**

**\$286,205**

---

**Total Site Cost****\$286,205****Campus Total <sup>2 3</sup>****\$19,982,611**

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

---

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

## Classroom Summary

| Current Usage           | Intended Usage      | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|-------------------------|---------------------|---------------|-------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| <b>Main</b>             |                     |               |             |                        |           |               |              |                |                    |                      |             |             |             |             |
| Art Room                | Science Lab Level 3 | 2nd Floor     | 225         | 225                    | 912       | 1             | 11           | 76             | 162                | 50                   | 40          | N           | Y           | N           |
| Computer Lab            | Computer Lab        | 1st Floor     | 106         | 106                    | 1,173     | 2             | 38           | 80             | 133                | 17                   | 40          | Y           | N           | N           |
| Computer Lab            | Computer Lab        | 2nd Floor     | 213         | 213                    | 782       | 1             | 32           | 70             | 151                | 8                    | 40          | N           | Y           | N           |
| Computer Lab            | Computer Lab        | 2nd Floor     | 217         | 217                    | 782       | 1             | 33           | 94             | 151                | 8                    | 40          | N           | N           | N           |
| Faculty Lounge          | Regular Classroom   | 1st Floor     | 135         | 135                    | 690       | 1             | 9            | 20             | 81                 | 12                   | 40          | Y           | Y           | N           |
| Music Room              | Music Room          | 1st Floor     | 139         | 139                    | 1,015     | 2             | 9            | 22             | 58                 | 11                   | 40          | Y           | N           | N           |
| Music Room              | Music Room          | 1st Floor     | 141         | 141                    | 1,265     | 1             | 7            | 22             | 125                | 20                   | 40          | Y           | Y           | N           |
| Office                  | Regular Classroom   |               | 223         | 223                    | 912       | 1             | 9            | 50             | 162                | 50                   | 40          | N           | Y           | N           |
| Other Instructional Use | Science Classroom   | 3rd Floor     | 327         | 327                    | 1,189     | 1             | 8            | 18             | 243                | 90                   | 40          | N           | N           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 110         | 110                    | 662       | 2             | 10           | 18             | 77                 | 10                   | 40          | Y           | N           | N           |
| Regular Classroom       | Regular Classroom   | 1st Floor     | 122         | 122                    | 1,565     | 0             | 6            | 16             | 144                | 24                   | 40          | Y           | N           | N           |
| Regular Classroom       | Regular Classroom   |               | 124         | 124                    | 670       | 1             | 6            | 16             | 45                 | 6                    | 40          | Y           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 124         | 124                    | 670       | 1             | 6            | 16             | 45                 | 6                    | 40          | Y           | Y           | N           |
| Regular Classroom       | Regular Classroom   |               | 126         | 126                    | 970       | 1             | 8            | 34             | 0                  | 0                    | 40          | N           | N           | N           |
| Regular Classroom       | Regular Classroom   | 1st Floor     | 126         | 126                    | 970       | 1             | 8            | 34             | 0                  | 0                    | 40          | N           | N           | N           |
| Regular Classroom       | Regular Classroom   | 1st Floor     | 137         | 137                    | 680       | 1             | 9            | 22             | 81                 | 12                   | 40          | Y           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 205         | 205                    | 552       | 1             | 8            | 24             | 162                | 60                   | 40          | N           | N           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 206         | 206                    | 684       | 1             | 8            | 32             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 207         | 207                    | 552       | 1             | 8            | 20             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   |               | 208         | 208                    | 684       | 1             | 6            | 20             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 209         | 209                    | 684       | 1             | 7            | 18             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 210         | 210                    | 684       | 1             | 8            | 32             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 211         | 211                    | 684       | 1             | 8            | 24             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 227         | 227                    | 747       | 1             | 7            | 18             | 108                | 40                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 229         | 229                    | 708       | 1             | 8            | 42             | 135                | 50                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 230         | 230                    | 708       | 1             | 8            | 16             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 232         | 232                    | 684       | 1             | 9            | 28             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 233         | 233                    | 684       | 1             | 9            | 18             | 79                 | 38                   | 40          | Y           | N           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 234         | 234                    | 684       | 1             | 9            | 22             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 235         | 235                    | 684       | 1             | 10           | 18             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 236         | 236                    | 684       | 1             | 9            | 18             | 162                | 60                   | 40          | N           | Y           | N           |
| Regular Classroom       | Regular Classroom   | 2nd Floor     | 237         | 237                    | 684       | 1             | 9            | 60             | 162                | 40                   | 40          | N           | Y           | N           |
| Regular Classroom       | Art Room            | 3rd Floor     | 313         | 313                    | 916       | 0             | 8            | 27             | 117                | 20                   | 40          | N           | Y           | N           |
| Regular Classroom       | Art Room            | 3rd Floor     | 317         | 317                    | 916       | 0             | 8            | 16             | 117                | 20                   | 40          | N           | Y           | N           |
| Regular Classroom       | Laboratory/Shop     | 3rd Floor     | 325         | 325                    | 1,080     | 1             | 1            | 8              | 189                | 50                   | 40          | N           | Y           | N           |
| Science Classroom       | Science Lab Level 3 | 2nd Floor     | 226         | 226                    | 927       | 1             | 8            | 26             | 162                | 50                   | 40          | N           | Y           | N           |
| Science Classroom       | Science Lab Level 3 | 3rd Floor     | 328         | 328                    | 1,002     | 1             | 8            | 24             | 162                | 60                   | 40          | N           | Y           | N           |

## Classroom Summary

| Current Usage            | Intended Usage      | Room Location | Room Number     | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|--------------------------|---------------------|---------------|-----------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| <b>Main</b>              |                     |               |                 |                        |           |               |              |                |                    |                      |             |             |             |             |
| Science Lab Level 1      | Science Lab Level 1 | 3rd Floor     | 321             | 321                    | 1,032     | 0             | 13           | 34             | 162                | 40                   | 40          | N           | Y           | N           |
| Science Lab Level 1      | Science Lab Level 1 | 3rd Floor     | 322             | 322                    | 1,129     | 1             | 6            | 22             | 216                | 80                   | 40          | N           | Y           | N           |
| Science Lab Level 3      | Science Lab Level 3 | 2nd Floor     | 222             | 222                    | 927       |               | 8            | 24             | 162                | 50                   | 40          | N           | Y           | N           |
| Science Lab Level 3      | Science Lab Level 3 | 3rd Floor     | 326             | 326                    | 1,021     | 1             | 8            | 82             | 162                | 60                   | 40          | N           | Y           | N           |
| Special Program          | Regular Classroom   | 1st Floor     | 119             | 119                    | 1,115     | 0             | 6            | 16             | 120                | 60                   | 40          | Y           | Y           | N           |
| Store Room               | Regular Classroom   | 1st Floor     | 125             | 125                    | 660       | 0             | 10           | 18             | 77                 | 22                   | 40          | N           | N           | N           |
| Store Room               | Regular Classroom   | 1st Floor     | 132             | 132                    | 700       | 1             | 9            | 22             | 81                 | 12                   | 40          | Y           | N           | N           |
| Store Room               | Special Education   | 3rd Floor     | 315             | 315                    | 435       | 0             | 12           | 32             | 81                 | 20                   | 40          | N           | N           | N           |
| Unsafe/Unusable Conditio | Regular Classroom   | Basement      | 021             | 024                    | 1,132     | 0             | 0            | 8              | 0                  | 0                    | 40          | N           | N           | N           |
| Vacant                   | Regular Classroom   | 2nd Floor     | 231             | 231                    | 684       | 1             | 6            | 20             | 162                | 60                   | 40          | N           | N           | N           |
| Weight                   | Weight              | Basement      | 018 - Weight Rn | 018                    | 1,198     | 0             | 0            | 0              | 0                  | 0                    | 40          | N           | N           | N           |