

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1911	4	252,761	\$9,524,814
Addition 1	1937	3	23,690	\$1,181,724
Addition 2	1970	3	22,050	\$1,000,750
Addition 3	1937	3	26,460	\$1,296,514
SITE				\$865,790
Campus Total			324,961	\$13,869,592

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	#1 E Main Entrance	1	EA	6	\$702	
	Exterior Doors - Exterior Wood Door	#2 N	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	#3 N	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	#4 W	4	EA	6	\$1,922	
	Exterior Doors - Store Front	#1 E Main Entrance	10	EA	6	\$5,461	
	Exterior Doors - Transom Lite	#1 E Main Entrance	30	EA	6	\$9,399	
	Exterior Doors - Transom Lite	#2 N	12	EA	6	\$3,760	
	Exterior Doors - Transom Lite	#3 N	12	EA	6	\$3,760	
	Exterior Doors - Transom Lite	#4 W	2	EA	6	\$627	
	Exterior Stairs - Concrete	#2 N	20	LF	5	\$2,192	Cracks
	Exterior Stairs - Concrete	#3 N	30	LF	6	\$2,453	
	Exterior Stairs - Concrete	#4 W	100	LF	5	\$10,958	Cracks
	Power Door Operator and Controls	#1 E Main Entrance	1	EA	6	\$0	
Foundation							
	Foundation - Concrete	Entire Building	1,215	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	252,761	SF	7	\$0	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	1	EA	6	\$537	
	Exterior Lighting - Wall Mounted	Entire Building	25	EA	6	\$7,219	
Roof System							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Main Roof	45	LF	6	\$42,961	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Main Roof	45	LF	5	\$128,320	Need cleaning and tuck pointing
	Coping - Metal	Main Roof	1,397	LF	6	\$44,869	
	Coping - Metal	Penthouse Roof	556	LF	6	\$17,857	
	Coping - Stone	Main Roof	698	LF	5	\$76,438	Need caulking
	Downspouts - Interior Downspouts	Main Roof	1,260	LF	6	\$41,874	need cleaning
	Downspouts - Interior Downspouts	Penthouse Roof	90	LF	6	\$2,991	
	Parapet - 16" - 30" Height	Main Roof	2,096	LF	6	\$83,744	
	Parapet - 16" - 30" Height	Penthouse Roof	556	LF	6	\$22,215	
	Roof Structure - Steel with Clay Tile Arch	Main Roof	75,762	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Penthouse Roof	11,418	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Main Roof	52,310	SF	5	\$1,235,002	Leaks, bubbles and worn
	Roof - Asphalt Shingle	Penthouse Roof	14,273	SF	6	\$65,517	
	Roof - Modified Bitumen	Main Roof	4,700	SF	5	\$98,866	Ponding and open seams
	Roof - Modified Bitumen	Main Roof	18,752	SF	6	\$176,445	
Walls							
	Cheek-Wall - Concrete	Entire Building	50	SF	5	\$1,179	Need tuck pointing
	Cornice - Masonry Projecting Limestone	Entire Building	946	LF	6	\$32,805	
	Cornice - Metal Projecting	Entire Building / 4th Floor	25	LF	4	\$30,152	Damaged
	Cornice - Metal Projecting	Entire Building / Roof	1,753	LF	5	\$263,739	Rust
	Exterior Walls - Brick	Entire Building	15,100	SF	5	\$319,145	Need tuck pointing and cleaning
	Exterior Walls - Brick	Entire Building	51,072	SF	6	\$343,255	
	Exterior Walls - Stone-Cast	Entire Building	2,520	SF	5	\$40,216	Need tuck pointing
	Exterior Walls - Stone-Cast	Entire Building	6,220	SF	6	\$41,805	
Windows							
	Guard - Guards perforated	Entire Building / 1st Floor	5,856	SF	6	\$74,781	
	Lintels - Steel	Entire Building	1,359	LF	6	\$39,450	
	Skylite - Lexan	Entire Building	280	SF	6	\$6,691	
	Windows - Decorative	Entire Building	1,172	SF	6	\$8,749	
	Windows - Sash Aluminum Double-pane	Entire Building	9,072	SF	6	\$67,719	
	Windows - Sash Aluminum Double-pane	Entire Building	9,072	SF	5	\$488,691	Balance issues

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Building Exterior Subtotal:						\$3,846,385	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Emergency System

	Automatic Transfer Switch	Electrical Room / Entire Building	1	EA	6	\$408	Building has emergency AC service and the required ATS.
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	5,251	SF	6	\$2,778	
	Emergency A/C Power - Corridors and Stairs	Entire Building	64,662	SF	6	\$19,418	
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	13,400	SF	6	\$4,982	
	Emergency A/C Power - Pool	Entire Building / 1st Floor	3,875	SF	6	\$1,441	
	Emergency A/C Power - Students Toilets	Entire Building	3,176	SF	6	\$1,181	
	Emergency Battery Packs - Auditorium and Aisle Lighting	Entire Building / 1st Floor	8	EA	6	\$1,620	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	2	EA	6	\$405	
	Emergency Battery Packs - Pool	Entire Building / 1st Floor	2	EA	6	\$405	
	Exit Signs - Auditorium	Entire Building / 1st Floor	8	EA	7	\$0	Building has AC generator.
	Exit Signs - Corridors and Stairs	Entire Building	40	EA	7	\$0	Building has AC generator.
	Exit Signs - Pool	Entire Building / 1st Floor	6	EA	7	\$0	Building has AC generator.
	Security System - CCTV	Entire Building	252,761	SF	6	\$75,904	
	Security System - Intrusion Detection	Entire Building	252,761	SF	6	\$65,061	
	UPS - Less than 30 KW	MDF Room	1	EA	6	\$7,886	Serves MDF room.

Main Service

	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Secondary feed from ComEd.
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	1	EA	6	\$8,232	Panels removed exposing wires.
	PA System	Entire Building	252,761	SF	6	\$83,133	Serves main and all additions. Control console located in main.

Power Distribution

	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	6	\$497	Westinghouse, needs cover to be installed
	Lighting and Power Panels - Above 100 A	Entire Building	12	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	8	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Entire Building	4	EA	7	\$0	

Electrical System Subtotal:

\$273,351

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	250,000	SF	6	\$89,375	
	Fire Alarm Strobe Lights	Entire Building	2,761	SF	4	\$3,751	A few classrooms do not have strobes.
	Fire Alarm_System	Entire Building	252,761	SF	6	\$122,892	Fire alarm panel in Addition 2.

Safty System Subtotal:

\$216,018

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	Serves computer room.
Air Handling Systems							
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves southwest corner.
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves southeast corner of main building.
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves northeast corner.
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	5	\$70,185	Serves northwest corner.
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 6000-10000 cfm	4th Floor	1	EA	6	\$3,350	Serves 4th floor penthouse classrooms.
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - Less than 6000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves 3 music rooms.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	1st Floor	1	EA	6	\$3,350	Serves south Auditorium.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves stage of Auditorium.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves Studio.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves north side of Auditorium.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	2nd Floor	1	EA	6	\$3,350	Serves Lecture Room 210.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	Mechanical Room / 2nd Floor	1	EA	5	\$21,708	Serves Lecture Room 231.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - 4000-8000 cfm	Pool / 1st Floor	1	EA	6	\$3,350	Serves pool area.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - Less than 4000 cfm	Boiler Room	1	EA	6	\$3,350	serves mechanical room

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	1st Floor / Roof	1	EA	6	\$5,765	
	Air Intake	2nd Floor / Roof	1	EA	6	\$5,765	
	Air Intake	4th Floor / Roof	1	EA	6	\$5,765	
	Air Intake	Boiler Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Pool / Roof	1	EA	7	\$0	
	Dehumidification Unit-Outdoor- Gas Heating- DX Cooling with Self Contained Compressor - 4001 - 8000 cfm	Roof	1	EA	6	\$9,570	Serves the pool. Evaporator in pool area
	Zone Dampers	4th Floor / Entire Building	5	EA	5	\$9,568	
	Zone Dampers	Mechanical Room / Entire Building	15	EA	6	\$12,495	
	Zone Dampers	Mechanical Room / Entire Building	15	EA	6	\$12,495	
	Zone Dampers	Mechanical Room / Entire Building	3	EA	6	\$2,499	
	Zone Dampers	Mechanical Room / Entire Building	15	EA	6	\$12,495	
	Zone Dampers	Mechanical Room / Entire Building	15	EA	6	\$12,495	
Boiler Systems							
	Boiler Auxiliary- Non Condensing Hot Water - 1001 - 2000 MBH	Boiler Room	1	EA	6	\$2,046	
	Boiler Auxiliary- Non Condensing Hot Water - Greater than 4000 MBH	Boiler Room	2	EA	6	\$4,093	
	Chemical Pot Feeder	Boiler Room	1	EA	6	\$725	
	Combustion Dampers	Boiler Room	3	EA	6	\$1,227	
	Glycol Feed System	Boiler Room	1	EA	6	\$539	
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - 1001 - 2000 MBH	Boiler Room	1	EA	6	\$998	also serves addition
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - Greater than 4000 MBH	Boiler Room	2	EA	6	\$1,996	also serves addition
	Water Fill System	Boiler Room	1	EA	6	\$1,168	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building / Entire Site	3	EA	6	\$1,063	
	Fin Tube - Hot Water	Entire Building	2,000	LF	6	\$18,876	
	Unit Heater - Electric	Loading Dock	1	EA	6	\$278	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical Plumbing							
	Chilled Water Pump - 10 - 20 HP	Entire Building / Mechanical Room	2	EA	6	\$2,485	
	Chilled Water Pump - 10 - 20 HP	Entire Building / Mechanical Room	4	EA	6	\$4,969	
	Chilled Water Pump - Less than 10	Entire Building	6	EA	6	\$6,667	Near AHUs and ASUs.
	Hot Water Pump - 10 - 20 HP	Entire Building / Mechanical Room	3	EA	6	\$3,727	
	Hot Water Pump - Less than 10	Entire Building	6	EA	6	\$6,667	Near AHUs and ASUs. Coil circulation pumps.
	Hydronic Supply and Return - Galvanized	Entire Building	1,200	LF	6	\$92,784	for fin tubes and AHUs and ASUs
Temperature Control							
	DDC System	Entire Building	252,761	SF	6	\$144,579	
	Electric Thermostat	Entire Building	2	EA	6	\$0	For unit heater.
	Thermostats - DDC	Entire Building	66	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	4	EA	6	\$2,370	
	Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Entire Building / Roof	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	6	\$592	
	Lab Exhaust Hood	Entire Building / 3rd Floor	2	EA	6	\$2,495	
	Roof Mounted Duct Work	Entire Building / Roof	60	LF	6	\$22,741	For dehumidifier and kitchen exhaust fan.

Mechanical System Subtotal:

\$562,508

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - Greater than 600000 BTU/HR	Boiler Room	1	EA	5	\$2,249	
	Hot Water Storage Tank_Gas - 501 - 1000 Gallons	Boiler Room	1	EA	6	\$678	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	252,761	SF	6	\$50,603	1911 construction, leaks frequently repaired.
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	252,761	SF	6	\$61,446	1911 construction, leaks frequently repaired.
	Domestic Piping-Cold Water Risers	Entire Building	252,761	SF	6	\$46,988	1911 construction, leaks frequently repaired.
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	252,761	SF	6	\$39,759	1911 construction, leaks frequently repaired.
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	252,761	SF	6	\$46,988	1911 construction, leaks frequently repaired.
	Domestic Piping-Hot Water Return Lines	Entire Building	252,761	SF	6	\$36,145	1911 construction, leaks frequently repaired.
	Domestic Piping-Hot Water Return Risers	Entire Building	252,761	SF	6	\$36,145	1911 construction, leaks frequently repaired.
	Sanitary Piping	Entire Building	252,761	SF	6	\$231,327	
	Storm Piping	Entire Building	252,761	SF	6	\$220,483	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Vent Piping	Entire Building	252,761	SF	6	\$169,881	
Pool Systems							
	Pool Drain Piping	Pool Area / Mechanical Room	60	LF	6	\$1,718	
	Pool Filtration System including Pump	Pool Area / Mechanical Room	1	EA	6	\$12,330	
	Pool Hot Water Heater - Electric	Pool Area / Mechanical Room	2	EA	6	\$1,814	
	Pool Supply and Return Piping	Pool Area / Basement	100	LF	6	\$4,805	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Basement	1	EA	6	\$1,977	Pump Room.
	Pumps - Ejector-Duplex	Basement	1	EA	6	\$1,387	Near pool area.
	Pumps - Sump-Simplex	Basement	1	EA	6	\$745	Elevator sump pump.
	Pumps - Sump-Simplex	Basement / Boiler Room	1	EA	6	\$745	

Plumbing System Subtotal:

\$968,214

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #117 (Computer Lab)							
	Ceiling - Exposed	1st Floor	1,549	SF	6	\$2,304	
	Doors - Side-lite	1st Floor	22	SF	6	\$368	
	Doors - Side-lite	1st Floor	12	SF	6	\$201	Wood panel
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,549	SF	6	\$1,551	
	Lighting - Lay-in	1st Floor	34	EA	6	\$4,045	
	Storage/ Closet	1st Floor	195	SF	6	\$1,414	
	Walls - Plaster/Drywall	1st Floor	1,716	SF	6	\$4,736	
Classroom #119 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	887	SF	6	\$2,664	
	Chalk Board	1st Floor	18	LF	6	\$402	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Side-lite	1st Floor	3	SF	6	\$50	Wood panel
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	887	SF	6	\$888	
	Lighting - Lay-in	1st Floor	18	EA	6	\$2,142	
	Storage/ Closet	1st Floor	92	SF	6	\$667	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #119 (Regular Classroom)							
	Walls - Plaster/Drywall	1st Floor	1	SF	5	\$5	Bubbling and peeling paint
	Walls - Plaster/Drywall	1st Floor	1,310	SF	5	\$9,928	
Classroom #121 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	945	SF	6	\$2,838	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	3	SF	6	\$50	Wood panel
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	5	SF	5	\$29	Damaged tiles
	Floor - Tile/Sheet	1st Floor	950	SF	6	\$951	
	Lighting - Lay-in	1st Floor	24	EA	6	\$2,855	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	56	SF	6	\$406	
	Walls - Plaster/Drywall	1st Floor	1,489	SF	6	\$4,109	
Classroom #123 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	950	SF	6	\$2,853	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	Wood panel
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	950	SF	6	\$951	
	Lighting - Lay-in	1st Floor	24	EA	6	\$2,855	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	28	SF	6	\$203	
	Walls - Plaster/Drywall	1st Floor	1,489	SF	6	\$4,109	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #125 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	950	SF	6	\$2,853	
	Ceiling - Plaster/Drywall	1st Floor	3	SF	5	\$27	Peeling paint
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	Wood panel
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	5	SF	5	\$29	Damaged tiles
	Floor - Tile/Sheet	1st Floor	945	SF	6	\$946	
	Lighting - Lay-in	1st Floor	24	EA	6	\$2,855	
	Marker Board	1st Floor	12	LF	5	\$608	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #125 (Regular Classroom)							
	Storage/ Closet	1st Floor	28	SF	6	\$203	
	Walls - Plaster/Drywall	1st Floor	1,489	SF	6	\$4,109	
Classroom #126 (Office)							
	Casework	1st Floor	30	LF	5	\$6,272	
	Ceiling - Lay-in	1st Floor	4	SF	5	\$32	water damaged
	Ceiling - Lay-in	1st Floor	971	SF	6	\$2,916	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	11	SF	5	\$63	damaged
	Floor - Tile	1st Floor	964	SF	6	\$2,109	
	Lighting - Lay-in	1st Floor	15	EA	7	\$0	
	Storage/ Closet	1st Floor	207	SF	6	\$1,501	126A
	Walls - Plaster/Drywall	1st Floor	3	SF	5	\$15	peeling
	Walls - Plaster/Drywall	1st Floor	1,197	SF	6	\$3,304	
	Work Sink	1st Floor	1	EA	5	\$1,508	missing a knob & the spout
Classroom #128 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	778	SF	6	\$2,336	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	778	SF	6	\$779	
	Lighting - Lay-in	1st Floor	1	EA	5	\$162	cover missing
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	970	SF	6	\$2,677	
Classroom #129 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	485	SF	6	\$1,456	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	485	SF	6	\$485	
	Lighting - Lay-in	1st Floor	2	EA	6	\$238	missing covers
	Lighting - Lay-in	1st Floor	7	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	840	SF	5	\$6,366	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #130 (Vacant)							
	Ceiling - Lay-in	1st Floor	778	SF	6	\$2,336	
	Chalk Board	1st Floor	21	LF	4	\$1,928	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	25	SF	5	\$128	wall damaged
	Walls - Plaster/Drywall	1st Floor	945	SF	6	\$2,608	
Classroom #131 (Other Instructional Use)							
	Ceiling - Plaster/Drywall	1st Floor	117	SF	6	\$405	
	Ceiling - Splined	1st Floor	562	SF	6	\$458	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	961	SF	6	\$962	
	Lighting - Lay-in	1st Floor	10	EA	6	\$1,190	
	Lighting - Pendent/Surface	1st Floor	15	EA	6	\$1,858	
	Walls - Concrete Block	1st Floor	762	SF	6	\$2,234	
	Walls - Plaster/Drywall	1st Floor	2,411	SF	6	\$6,654	
Classroom #132 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	778	SF	6	\$2,336	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	5	SF	5	\$29	damaged
	Floor - Tile	1st Floor	773	SF	6	\$1,691	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	970	SF	6	\$2,677	
Classroom #133 (Music Room)							
	Ceiling - Lay-in	1st Floor	378	SF	6	\$1,135	
	Ceiling - Plaster/Drywall	1st Floor	880	SF	6	\$3,045	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	5	\$2,348	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	50	SF	5	\$288	damaged
	Floor - Tile	1st Floor	1,208	SF	6	\$2,643	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #133 (Music Room)							
	Lighting - Lay-in	1st Floor	3	EA	6	\$357	covers missing
	Lighting - Lay-in	1st Floor	15	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Storage/ Closet	1st Floor	423	SF	6	\$3,067	133A/B/C/D & 2 hall storages
	Storage/ Closet	1st Floor	46	SF	6	\$334	
	Student Lockers - One Tier	1st Floor	4	EA	6	\$371	instrument storage
	Student Lockers - Three Tiers	1st Floor	16	EA	6	\$495	instrument storage- 4 high
	Student Lockers - Three Tiers	1st Floor	60	EA	6	\$1,857	instrument storage- 5 high
	Student Lockers - Three Tiers	1st Floor	12	EA	6	\$371	instrument storage
	Walls - Plaster/Drywall	1st Floor	1,785	SF	6	\$4,926	
Classroom #134 (Music Room)							
	Ceiling - Lay-in	1st Floor	378	SF	6	\$1,135	
	Ceiling - Plaster/Drywall	1st Floor	878	SF	6	\$3,038	
	Ceiling - Plaster/Drywall	1st Floor	2	SF	5	\$25	damaged
	Doors - Wood Doors inclu hw	1st Floor	3	EA	6	\$903	
	Floor - Tile	1st Floor	21	SF	5	\$121	damaged
	Floor - Tile	1st Floor	1,237	SF	6	\$2,706	
	Lighting - Lay-in	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Storage/ Closet	1st Floor	46	SF	6	\$334	
	Walls - Plaster/Drywall	1st Floor	1,781	SF	6	\$4,915	
	Walls - Plaster/Drywall	1st Floor	4	SF	5	\$20	damaged
Classroom #135 (Music Room)							
	Ceiling - Lay-in	1st Floor	1,258	SF	6	\$3,778	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,258	SF	6	\$2,752	
	Lighting - Lay-in	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	24	LF	6	\$514	
	Storage/ Closet	1st Floor	157	SF	5	\$2,532	some peeling & water damage in each closet
	Walls - Plaster/Drywall	1st Floor	1,785	SF	6	\$4,926	
Classroom #136 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	975	SF	6	\$2,928	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	8	SF	5	\$46	damaged
	Floor - Tile	1st Floor	967	SF	6	\$2,116	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #136 (Regular Classroom)							
	Lighting - Lay-in	1st Floor	1	EA	6	\$119	cover missing
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	6	SF	5	\$31	crack
	Walls - Plaster/Drywall	1st Floor	1,104	SF	6	\$3,047	
Classroom #137 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	20	SF	5	\$160	water damaged
	Ceiling - Lay-in	1st Floor	1,238	SF	6	\$3,718	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	15	SF	5	\$86	tiles & subfloor are damaged
	Floor - Tile	1st Floor	1,243	SF	6	\$2,720	
	Lighting - Lay-in	1st Floor	5	EA	6	\$595	covers missing
	Lighting - Lay-in	1st Floor	13	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Storage/ Closet	1st Floor	423	SF	5	\$6,823	137A/B/C/D & 2 hall storages - all rooms need some floor fixed
	Storage/ Closet	1st Floor	231	SF	6	\$1,675	
	Walls - Plaster/Drywall	1st Floor	15	SF	5	\$77	peeling & damaged
	Walls - Plaster/Drywall	1st Floor	1,770	SF	6	\$4,885	
Classroom #138 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	778	SF	6	\$2,336	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	970	SF	6	\$2,677	
Classroom #140 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	778	SF	6	\$2,336	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #140 (Regular Classroom)							
	Storage/ Closet	1st Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	1st Floor	1,030	SF	6	\$2,843	
Classroom #200 (Science Lab Level 3)							
	Casework	2nd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	2nd Floor	1,000	SF	6	\$3,003	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,000	SF	6	\$1,001	
	Lighting - Lay-in	2nd Floor	18	EA	6	\$2,142	
	Science Lab Elements	2nd Floor	1,000	SF	6	\$6,778	
	Walls - Plaster/Drywall	2nd Floor	1,200	SF	6	\$3,312	
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classroom #202 (Regular Classroom)							
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Splined	2nd Floor	605	SF	6	\$493	
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Side-lite	2nd Floor	3	SF	6	\$50	wood panel
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	605	SF	6	\$606	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Walls - Plaster/Drywall	2nd Floor	910	SF	6	\$2,512	
Classroom #204 (Science Lab Level 3)							
	Casework	2nd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	2nd Floor	1,000	SF	6	\$3,003	
	Chalk Board	2nd Floor	24	LF	6	\$535	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,000	SF	6	\$1,001	
	Gas Line	2nd Floor	16	EA	6	\$8,146	
	Lighting - Lay-in	2nd Floor	18	EA	6	\$2,142	Missing lens
	Science Lab Elements	2nd Floor	1,000	SF	6	\$6,778	
	Walls - Plaster/Drywall	2nd Floor	1,137	SF	6	\$3,138	
	Walls - Plaster/Drywall	2nd Floor	1	SF	5	\$5	Peeling paint
	Work Sink	2nd Floor	4	EA	6	\$1,516	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #204 (Science Lab Level 3)							
Classroom #208 (Other Instructional Use)							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	2,158	SF	6	\$6,480	
	Ceiling - Lay-in	2nd Floor	2	SF	5	\$16	Missing and damaged tile
	Doors - Side-lite	2nd Floor	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	2,160	SF	6	\$2,162	
	Lighting - Lay-in	2nd Floor	42	EA	6	\$4,997	
	Walls - Plaster/Drywall	2nd Floor	2,380	SF	6	\$6,569	
Classroom #210 (Other Instructional Use)							
	Ceiling - Lay-in	2nd Floor	484	SF	6	\$1,453	
	Ceiling - Plaster/Drywall	2nd Floor	2	SF	5	\$25	Bubbling paint
	Ceiling - Plaster/Drywall	2nd Floor	1,642	SF	6	\$5,682	
	Chalk Board	2nd Floor	24	LF	6	\$535	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Tile/Sheet	2nd Floor	4	SF	5	\$23	Missing tiles
	Floor - Tile/Sheet	2nd Floor	2,096	SF	6	\$2,098	
	Lighting - Lay-in	2nd Floor	27	EA	6	\$3,212	
	Storage/ Closet	2nd Floor	230	SF	6	\$1,668	#210,1 & 210.3
	Walls - Plaster/Drywall	2nd Floor	1	SF	5	\$5	Peeling paint
	Walls - Plaster/Drywall	2nd Floor	2,430	SF	6	\$6,707	
Classroom #212 (Science Lab Level 3)							
	Casework	2nd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	2nd Floor	1,000	SF	6	\$3,003	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,000	SF	6	\$1,001	
	Gas Line	2nd Floor	10	EA	6	\$5,091	
	Lighting - Lay-in	2nd Floor	18	EA	6	\$2,142	
	Science Lab Elements	2nd Floor	1,000	SF	6	\$6,778	
	Walls - Plaster/Drywall	2nd Floor	1,200	SF	6	\$3,312	
	Work Sink	2nd Floor	2	EA	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #214 (Computer Lab)							
	Casework	2nd Floor	35	LF	6	\$884	
	Ceiling - Lay-in	2nd Floor	673	SF	6	\$2,021	
	Chalk Board	2nd Floor	35	LF	4	\$3,213	
	Doors - Side-lite	2nd Floor	3	SF	6	\$50	Wood panel
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	673	SF	6	\$674	
	Lighting - Lay-in	2nd Floor	8	EA	6	\$952	
	Walls - Plaster/Drywall	2nd Floor	972	SF	6	\$2,683	
Classroom #216 (Science Lab Level 3)							
	Casework	2nd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	2nd Floor	1,000	SF	6	\$3,003	
	Chalk Board	2nd Floor	8	LF	6	\$178	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,000	SF	6	\$1,001	
	Gas Line	2nd Floor	2	EA	6	\$1,018	
	Lighting - Lay-in	2nd Floor	18	EA	6	\$2,142	
	Science Lab Elements	2nd Floor	1,000	SF	6	\$6,778	
	Walls - Plaster/Drywall	2nd Floor	1,219	SF	6	\$3,364	
	Walls - Plaster/Drywall	2nd Floor	1	SF	5	\$5	Peeling paint
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classroom #226 (Regular Classroom)							
	Casework	2nd Floor	5	LF	6	\$126	
	Ceiling - Lay-in	2nd Floor	1,473	SF	6	\$4,423	dirt on one tile
	Chalk Board	2nd Floor	32	LF	4	\$2,938	
	Doors - Side-lite	2nd Floor	3	SF	6	\$50	Wood panel
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,473	SF	6	\$1,474	
	Lighting - Lay-in	2nd Floor	24	EA	6	\$2,855	
	Storage/ Closet	2nd Floor	264	SF	6	\$1,914	#226A (Locked)
	Walls - Plaster/Drywall	2nd Floor	1,520	SF	6	\$4,195	
Classroom #228 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #228 (Regular Classroom)							
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	4	LF	6	\$86	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	
Classroom #229 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	Broken tile
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	4	LF	6	\$86	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	
Classroom #230 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	6	SF	6	\$44	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	
Classroom #231 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	484	SF	6	\$1,453	
	Ceiling - Plaster/Drywall	2nd Floor	1,644	SF	5	\$15,069	Peeling paint
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #231 (Computer Lab)							
	Floor - Tile/Sheet	2nd Floor	2,128	SF	6	\$2,130	
	Lighting - Lay-in	2nd Floor	27	EA	6	\$3,212	
	Storage/ Closet	2nd Floor	1,150	SF	6	\$8,338	#231-3 and #231-1
	Walls - Plaster/Drywall	2nd Floor	2,431	SF	6	\$6,709	
Classroom #232 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	
	Doors - Steel Doors incl hw	2nd Floor	9	EA	6	\$2,709	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	14	LF	6	\$300	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	
Classroom #234 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	Missing tile
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	6	SF	6	\$44	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	
Classroom #236 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	one tile broken and loose
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #238 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	Missing tile
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	14	LF	6	\$300	
	Storage/ Closet	2nd Floor	6	SF	6	\$44	
	Walls - Plaster/Drywall	2nd Floor	1,076	SF	6	\$2,970	
Classroom #240 (Regular Classroom)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	
	Chalk Board	2nd Floor	4	LF	4	\$367	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	778	SF	6	\$779	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	1,123	SF	6	\$3,099	
Classroom #241 (Dance Room)							
	Ceiling - Splined	2nd Floor	1,171	SF	6	\$954	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	1,171	SF	6	\$8,255	
	Lighting - Pendent/Surface	2nd Floor	15	EA	6	\$1,858	
	Storage/ Closet	2nd Floor	280	SF	6	\$2,030	#241B
	Wall Mirrors	2nd Floor	384	EA	6	\$0	
	Walls - Plaster/Drywall	2nd Floor	2,142	SF	6	\$5,912	
Classroom #242 (Physical Education Room)							
	Ceiling - Splined	2nd Floor	864	SF	6	\$704	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	864	SF	6	\$865	
	Lighting - Pendent/Surface	2nd Floor	17	EA	6	\$2,106	
	Walls - Plaster/Drywall	2nd Floor	340	SF	6	\$1,113	Folding Partition
	Walls - Plaster/Drywall	2nd Floor	2,050	SF	6	\$5,658	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #242 (Physical Education Room)							
Classroom #244 (Weight)							
	Ceiling - Plaster/Drywall	2nd Floor	2,564	SF	6	\$8,873	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Wood Doors inclu hw	2nd Floor	6	EA	6	\$1,806	
	Floor - Weight/ Fitness Room Floor Matting	2nd Floor	2,564	SF	6	\$13,419	
	Lighting - Pendent/Surface	2nd Floor	29	EA	6	\$3,593	
	Walls - Plaster/Drywall	2nd Floor	3,954	SF	6	\$10,913	
Classroom #300 (Science Lab Level 3)							
	Casework	3rd Floor	8	LF	5	\$1,673	damaged
	Ceiling - Lay-in	3rd Floor	964	SF	6	\$2,895	
	Ceiling - Lay-in	3rd Floor	15	SF	5	\$120	water damaged
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	979	SF	6	\$2,142	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Science Lab Elements	3rd Floor	6	SF	6	\$41	
	Walls - Plaster/Drywall	3rd Floor	1,210	SF	6	\$3,339	
	Walls - Plaster/Drywall	3rd Floor	20	SF	5	\$102	water damaged
	Work Sink	3rd Floor	1	EA	5	\$1,508	not working
Classroom #301 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	770	SF	6	\$628	
	Ceiling - Splined	3rd Floor	10	SF	5	\$97	damaged
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	780	SF	6	\$1,707	
	Lighting - Pendent/Surface	3rd Floor	8	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	1	EA	4	\$541	missing fixture
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,198	SF	6	\$3,306	
	Walls - Plaster/Drywall	3rd Floor	36	SF	5	\$184	crack & water damage
Classroom #302 (Regular Classroom)							
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	604	SF	6	\$1,814	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #302 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	1	SF	5	\$8	water damaged
	Chalk Board	3rd Floor	4	LF	4	\$367	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	605	SF	6	\$1,324	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	2	EA	6	\$238	covers missing
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	910	SF	6	\$2,512	
Classroom #303 (Office)							
	Ceiling - Splined	3rd Floor	695	SF	6	\$566	
	Ceiling - Splined	3rd Floor	5	SF	5	\$48	damaged
	Chalk Board	3rd Floor	42	LF	4	\$3,856	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	692	SF	6	\$1,514	
	Floor - Tile	3rd Floor	8	SF	5	\$46	damaged
	Lighting - Pendent/Surface	3rd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,138	SF	6	\$3,141	
	Walls - Plaster/Drywall	3rd Floor	25	SF	5	\$128	cracks
Classroom #304 (Science Lab Level 3)							
	Ceiling - Lay-in	3rd Floor	1,110	SF	6	\$3,333	
	Ceiling - Lay-in	3rd Floor	10	SF	5	\$80	water damaged
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,120	SF	6	\$2,450	
	Gas Line	3rd Floor	5	EA	6	\$2,546	
	Lighting - Lay-in	3rd Floor	11	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	7	EA	6	\$833	no covers
	Science Lab Elements	3rd Floor	1,120	SF	6	\$7,592	
	Walls - Plaster/Drywall	3rd Floor	1,175	SF	6	\$3,243	
	Walls - Plaster/Drywall	3rd Floor	25	SF	5	\$128	damaged
	Work Sink	3rd Floor	2	EA	6	\$758	2 have missing faucets
	Work Sink	3rd Floor	2	EA	6	\$758	
Classroom #305 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	700	SF	6	\$571	
	Chalk Board	3rd Floor	42	LF	4	\$3,856	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #305 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	692	SF	6	\$1,514	
	Floor - Tile	3rd Floor	8	SF	5	\$46	damaged
	Lighting - Pendent/Surface	3rd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,158	SF	6	\$3,196	
	Walls - Plaster/Drywall	3rd Floor	10	SF	5	\$51	cracked
Classroom #307 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	700	SF	6	\$571	
	Chalk Board	3rd Floor	42	LF	4	\$3,856	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	695	SF	6	\$1,521	
	Floor - Tile	3rd Floor	20	SF	5	\$115	damaged
	Lighting - Pendent/Surface	3rd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,158	SF	6	\$3,196	
	Walls - Plaster/Drywall	3rd Floor	10	SF	5	\$51	cracked
Classroom #308 (Regular Classroom)							
	Casework	3rd Floor	26	LF	5	\$5,436	old & damaged
	Ceiling - Lay-in	3rd Floor	1,100	SF	6	\$3,303	
	Ceiling - Lay-in	3rd Floor	85	SF	3	\$1,195	water damaged
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,185	SF	6	\$2,593	
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	3	EA	6	\$357	missing covers
	Walls - Plaster/Drywall	3rd Floor	748	SF	6	\$2,064	
	Walls - Plaster/Drywall	3rd Floor	700	SF	5	\$3,093	Water damaged-- ROOM HAS BAD MOLD SMELL
Classroom #309 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	760	SF	6	\$619	
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	750	SF	6	\$1,641	
	Floor - Tile	3rd Floor	10	SF	5	\$58	damaged
	Lighting - Pendent/Surface	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #309 (Regular Classroom)							
	Walls - Plaster/Drywall	3rd Floor	1,221	SF	6	\$3,370	
Classroom #311 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	755	SF	6	\$615	
	Ceiling - Splined	3rd Floor	5	SF	5	\$48	damaged
	Chalk Board	3rd Floor	32	LF	4	\$2,938	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	760	SF	5	\$3,413	cracks throughout
	Lighting - Pendent/Surface	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,221	SF	6	\$3,370	
Classroom #312 (Store Room)							
	Casework	3rd Floor	25	LF	6	\$631	
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	1,130	SF	6	\$3,393	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,130	SF	6	\$1,131	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	9	EA	6	\$4,582	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	7	\$0	
	Science Lab Elements	3rd Floor	54	SF	6	\$366	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,230	SF	6	\$3,395	
	Work Sink	3rd Floor	9	EA	6	\$3,411	
Classroom #314 (Computer Lab)							
	Ceiling - Lay-in	3rd Floor	673	SF	6	\$2,021	
	Doors - Side-lite	3rd Floor	1	SF	6	\$17	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	673	SF	6	\$1,472	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	972	SF	6	\$2,683	
	Wireless System	3rd Floor	1	EA	6	\$372	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #315 (Regular Classroom)							
	Casework	3rd Floor	25	LF	6	\$631	
	Ceiling - Splined	3rd Floor	863	SF	6	\$703	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	863	SF	6	\$1,888	
	Floor - Tile	3rd Floor	5	SF	5	\$29	damaged
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	3	EA	6	\$357	missing covers
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	70	SF	6	\$508	vault
	Walls - Plaster/Drywall	3rd Floor	1,260	SF	6	\$3,477	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #316 (Store Room)							
	Casework	3rd Floor	35	LF	6	\$884	
	Ceiling - Lay-in	3rd Floor	1,130	SF	6	\$3,393	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,130	SF	6	\$1,131	
	Gas Line	3rd Floor	10	EA	6	\$5,091	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	7	\$0	
	Science Lab Elements	3rd Floor	48	SF	6	\$325	
	Storage/ Closet	3rd Floor	19	SF	6	\$138	
	Walls - Plaster/Drywall	3rd Floor	1,230	SF	6	\$3,395	
	Work Sink	3rd Floor	8	EA	6	\$3,032	
Classroom #323 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	653	SF	6	\$532	
	Chalk Board	3rd Floor	16	LF	4	\$1,469	
	Doors - Side-lite	3rd Floor	23	SF	6	\$384	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Carpet	3rd Floor	653	SF	6	\$1,391	
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,128	SF	6	\$3,113	
Classroom #326 (Special Program)							
	Ceiling - Lay-in	3rd Floor	768	SF	6	\$2,306	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #326 (Special Program)							
	Ceiling - Lay-in	3rd Floor	10	SF	5	\$80	water damaged
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	7	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	4	EA	6	\$476	covers missing
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,066	SF	6	\$2,942	
	Walls - Plaster/Drywall	3rd Floor	10	SF	5	\$51	peeling
Classroom #327 (Regular Classroom)							
	Casework	3rd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Terrazzo	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,068	SF	6	\$2,948	
	Walls - Plaster/Drywall	3rd Floor	8	SF	5	\$41	water damaged
Classroom #328 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	6	EA	6	\$714	covers missing
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,061	SF	6	\$2,928	
	Walls - Plaster/Drywall	3rd Floor	15	SF	5	\$77	water damaged
Classroom #329 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Chalk Board	3rd Floor	6	LF	4	\$551	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	778	SF	6	\$779	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #329 (Regular Classroom)							
	Lighting - Lay-in	3rd Floor	9	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	3	EA	6	\$357	covers missing
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,070	SF	6	\$2,953	
	Walls - Plaster/Drywall	3rd Floor	6	SF	5	\$31	water damaged
Classroom #330 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,075	SF	6	\$2,967	
	Walls - Plaster/Drywall	3rd Floor	1	SF	5	\$5	water damaged
Classroom #331A (Store Room)							
	Ceiling - Splined	3rd Floor	598	SF	6	\$487	
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	598	SF	5	\$2,685	
	Lighting - Pendent/Surface	3rd Floor	10	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,074	SF	6	\$2,964	1 wall has FRP on it
	Walls - Plaster/Drywall	3rd Floor	15	SF	5	\$77	water damaged
Classroom #332 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,056	SF	6	\$2,914	
	Walls - Plaster/Drywall	3rd Floor	10	SF	5	\$51	water damaged

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #333 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	835	SF	6	\$681	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	835	SF	6	\$1,827	
	Lighting - Pendent/Surface	3rd Floor	13	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	1	EA	6	\$124	cover cracked
	Marker Board	3rd Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	3rd Floor	240	SF	6	\$786	FRP panels
	Walls - Plaster/Drywall	3rd Floor	1,049	SF	6	\$2,895	
Classroom #334 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,076	SF	6	\$2,970	
Classroom #335 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	926	SF	6	\$2,781	
	Chalk Board	3rd Floor	10	LF	4	\$918	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	5	\$1,174	
	Floor - Tile	3rd Floor	926	SF	6	\$2,026	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,372	SF	6	\$3,787	
Classroom #336 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	32	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,072	SF	6	\$2,959	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #336 (Regular Classroom)							
	Walls - Plaster/Drywall	3rd Floor	4	SF	5	\$20	damaged
Classroom #337 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	926	SF	6	\$2,781	
	Chalk Board	3rd Floor	2	LF	4	\$184	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	923	SF	6	\$2,019	
	Floor - Tile	3rd Floor	3	SF	5	\$17	damaged
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Metal Panel	3rd Floor	1,372	SF	6	\$10,241	
Classroom #338 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	778	SF	6	\$1,702	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,071	SF	6	\$2,956	
	Walls - Plaster/Drywall	3rd Floor	5	SF	5	\$26	water damaged
Classroom #339 (Office)							
	Ceiling - Lay-in	3rd Floor	926	SF	6	\$2,781	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	921	SF	6	\$2,015	
	Floor - Tile	3rd Floor	5	SF	5	\$29	damaged
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	30	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,366	SF	6	\$3,770	
	Walls - Plaster/Drywall	3rd Floor	6	SF	5	\$31	damaged
Classroom #340 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	778	SF	6	\$2,336	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #340 (Regular Classroom)							
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	778	SF	6	\$779	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Storage/ Closet	3rd Floor	7	SF	6	\$51	
	Walls - Plaster/Drywall	3rd Floor	1,074	SF	6	\$2,964	
	Walls - Plaster/Drywall	3rd Floor	2	SF	5	\$10	water damaged
Classroom #401 (Store Room)							
	Casework	4th Floor	75	LF	6	\$1,894	
	Ceiling - Lay-in	4th Floor	20	SF	5	\$160	water damaged
	Ceiling - Lay-in	4th Floor	1,054	SF	6	\$3,165	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	5	\$1,174	glazing is missing
	Floor - Concrete Epoxy/ Painted	4th Floor	1,074	SF	5	\$1,843	needs refinishing
	Instructional Surface	4th Floor	8	LF	6	\$269	
	Lighting - Lay-in	4th Floor	24	EA	7	\$0	
	Storage/ Closet	4th Floor	20	SF	5	\$323	water damage & a T12 fixture
	Storage/ Closet	4th Floor	321	SF	6	\$2,327	401A/B/C
	Walls - Plaster/Drywall	4th Floor	3	SF	5	\$15	peeling
	Walls - Plaster/Drywall	4th Floor	1,456	SF	6	\$4,018	
	Work Sink	4th Floor	2	EA	6	\$758	
Classroom #402 (Art Room)							
	Casework	4th Floor	75	LF	6	\$1,894	
	Ceiling - Lay-in	4th Floor	1,069	SF	6	\$3,210	
	Ceiling - Lay-in	4th Floor	5	SF	5	\$40	water damaged
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	4th Floor	1,074	SF	5	\$1,843	needs refinishing
	Instructional Surface	4th Floor	8	LF	6	\$269	
	Lighting - Lay-in	4th Floor	26	EA	7	\$0	
	Storage/ Closet	4th Floor	96	SF	6	\$696	Includes Rm 402A- which has a T12 in it
	Walls - Plaster/Drywall	4th Floor	1,439	SF	6	\$3,971	
	Walls - Plaster/Drywall	4th Floor	20	SF	5	\$102	water damaged
	Work Sink	4th Floor	1	EA	6	\$379	
Classroom #403 (Vacant)							
	Casework	4th Floor	8	LF	6	\$202	
	Ceiling - Lay-in	4th Floor	863	SF	6	\$2,592	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #403 (Vacant)							
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	863	SF	6	\$1,888	
	Lighting - Pendent/Surface	4th Floor	7	EA	7	\$0	
	Storage/ Closet	4th Floor	10	SF	6	\$73	
	Walls - Plaster/Drywall	4th Floor	1,674	SF	6	\$4,620	
Classroom #405 (Vacant)							
	Casework	4th Floor	20	LF	6	\$505	
	Ceiling - Lay-in	4th Floor	776	SF	6	\$2,330	
	Ceiling - Lay-in	4th Floor	6	SF	5	\$48	water damaged
	Floor - Tile	4th Floor	782	SF	6	\$1,711	
	Lighting - Pendent/Surface	4th Floor	16	EA	7	\$0	
	Walls - Plaster/Drywall	4th Floor	1,305	SF	6	\$3,602	
	Walls - Plaster/Drywall	4th Floor	100	SF	5	\$511	water damaged walls in one of the film rooms
	Work Sink	4th Floor	1	EA	6	\$379	
Classroom #406 (Art Room)							
	Casework	4th Floor	100	LF	6	\$2,525	
	Ceiling - Lay-in	4th Floor	1,343	SF	6	\$4,033	
	Ceiling - Lay-in	4th Floor	7	SF	5	\$56	water damaged
	Chalk Board	4th Floor	14	LF	4	\$1,285	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Epoxy/ Painted	4th Floor	1,350	SF	5	\$2,317	needs to be refinished
	Instructional Surface	4th Floor	8	LF	6	\$269	
	Lighting - Lay-in	4th Floor	36	EA	7	\$0	
	Storage/ Closet	4th Floor	8	SF	6	\$58	
	Storage/ Closet	4th Floor	190	SF	4	\$5,295	Rm 406A- water damage on ceiling & walls
	Walls - Plaster/Drywall	4th Floor	1,954	SF	6	\$5,393	
	Walls - Plaster/Drywall	4th Floor	6	SF	5	\$31	water damaged
	Work Sink	4th Floor	3	EA	6	\$1,137	
Classroom #407 (Art Room)							
	Casework	4th Floor	100	LF	6	\$2,525	
	Ceiling - Lay-in	4th Floor	1,135	SF	6	\$3,408	
	Ceiling - Lay-in	4th Floor	15	SF	5	\$120	water damaged
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	4th Floor	1,150	SF	6	\$608	
	Instructional Surface	4th Floor	8	LF	6	\$269	
	Lighting - Lay-in	4th Floor	31	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #407 (Art Room)							
	Storage/ Closet	4th Floor	8	SF	6	\$58	
	Storage/ Closet	4th Floor	170	SF	5	\$2,742	Rm 407A & 407B- water damage on walls &
	Walls - Plaster/Drywall	4th Floor	1,960	SF	6	\$5,409	
	Work Sink	4th Floor	2	EA	6	\$758	

Classrooms Subtotal:

\$986,778

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Plaster/Drywall	109 Ticket check/Security room	298	SF	6	\$1,031	
	Doors - Wood Doors inclu hw	109 Ticket check/Security room	1	EA	6	\$301	
	Floor - Tile/Sheet	109 Ticket check/Security room	2	SF	5	\$12	Missing tiles
	Floor - Tile/Sheet	109 Ticket check/Security room	296	SF	6	\$296	
	Lighting - Lay-in	109 Ticket check/Security room	3	EA	7	\$0	
	Power Distribution	109 Ticket check/Security room	6	EA	7	\$0	
	Walls - Concrete Block	109 Ticket check/Security room	915	SF	6	\$2,682	
	Walls - Plaster/Drywall	109 Ticket check/Security room	184	SF	6	\$508	
	Ceiling - Plaster/Drywall	109A Storage/Audio for Auditorium	173	SF	6	\$599	
	Doors - Wood Doors inclu hw	109A Storage/Audio for Auditorium	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	109A Storage/Audio for Auditorium	173	SF	6	\$92	
	Lighting - Pendant/Surface	109A Storage/Audio for Auditorium	3	EA	7	\$0	
	Power Distribution	109A Storage/Audio for Auditorium	4	EA	7	\$0	
	Walls - Concrete Block	109A Storage/Audio for Auditorium	420	SF	6	\$1,231	
	Ceiling - Lay-in	112B Attendance Office	480	SF	6	\$1,441	
	Doors - Wood Doors inclu hw	112B Attendance Office	1	EA	6	\$301	
	Floor - Carpet	112B Attendance Office	480	SF	6	\$1,023	
	Lighting - Lay-in	112B Attendance Office	5	EA	7	\$0	
	Power Distribution	112B Attendance Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	112B Attendance Office	1	SF	5	\$5	Peeling paint
	Walls - Plaster/Drywall	112B Attendance Office	1,284	SF	6	\$3,544	
	Ceiling - Lay-in	116 Program Office	363	SF	6	\$1,090	
	Doors - Transom Window	116 Program Office	12	SF	6	\$203	Wood panel
	Doors - Wood Doors inclu hw	116 Program Office	1	EA	6	\$301	
	Floor - Tile/Sheet	116 Program Office	363	SF	6	\$363	Stains on tiles
	Lighting - Lay-in	116 Program Office	7	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	116 Program Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	116 Program Office	5	SF	5	\$26	Peeling paint
	Walls - Plaster/Drywall	116 Program Office	1,126	SF	6	\$3,108	
	Ceiling - Lay-in	116B Office	226	SF	6	\$679	
	Doors - Wood Doors inclu hw	116B Office	1	EA	6	\$301	
	Floor - Carpet	116B Office	226	SF	6	\$482	
	Lighting - Lay-in	116B Office	5	EA	7	\$0	
	Power Distribution	116B Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	116B Office	700	SF	6	\$1,932	
	Ceiling - Plaster/Drywall	118A Office	1	SF	5	\$12	Black dirt
	Ceiling - Plaster/Drywall	118A Office	134	SF	6	\$464	
	Doors - Wood Doors inclu hw	118A Office	1	EA	6	\$301	
	Floor - Tile/Sheet	118A Office	135	SF	6	\$135	
	Lighting - Lay-in	118A Office	2	EA	7	\$0	
	Power Distribution	118A Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	118A Office	493	SF	6	\$1,361	
	Walls - Plaster/Drywall	118A Office	1	SF	5	\$5	Peeling paint
	Ceiling - Plaster/Drywall	200B Office	92	SF	6	\$318	
	Doors - Wood Doors inclu hw	200B Office	1	EA	6	\$301	
	Floor - Tile/Sheet	200B Office	92	SF	6	\$92	
	Lighting - Pendent/Surface	200B Office	2	EA	7	\$0	
	Power Distribution	200B Office	2	EA	7	\$0	
	Walls - Metal Panel	200B Office	110	SF	6	\$821	Glass
	Walls - Plaster/Drywall	200B Office	126	SF	6	\$348	
	Ceiling - Plaster/Drywall	212B Office (Use as Storage)	91	SF	6	\$315	
	Ceiling - Plaster/Drywall	212B Office (Use as Storage)	1	SF	5	\$12	Peeling paint
	Doors - Wood Doors inclu hw	212B Office (Use as Storage)	1	EA	6	\$301	
	Floor - Tile/Sheet	212B Office (Use as Storage)	92	SF	6	\$92	
	Lighting - Pendent/Surface	212B Office (Use as Storage)	2	EA	7	\$0	
	Power Distribution	212B Office (Use as Storage)	2	EA	7	\$0	
	Walls - Metal Panel	212B Office (Use as Storage)	89	SF	6	\$664	Glass
	Walls - Plaster/Drywall	212B Office (Use as Storage)	146	SF	6	\$403	
	Walls - Plaster/Drywall	212B Office (Use as Storage)	1	SF	5	\$5	Peeling paint
	Ceiling - Plaster/Drywall	216B Office	92	SF	6	\$318	
	Doors - Wood Doors inclu hw	216B Office	1	EA	6	\$301	
	Floor - Tile/Sheet	216B Office	92	SF	6	\$92	
	Lighting - Pendent/Surface	216B Office	2	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	216B Office	2	EA	7	\$0	
	Walls - Metal Panel	216B Office	89	SF	6	\$664	Glass
	Walls - Plaster/Drywall	216B Office	137	SF	6	\$378	
	Work Slnk	216B Office	1	EA	6	\$508	
	Ceiling - Splined	217 Library Stor use as Comp Lab for Teachers	2	SF	5	\$19	Damaged and missing tiles
	Ceiling - Splined	217 Library Stor use as Comp Lab for Teachers	723	SF	6	\$589	
	Doors - Wood Doors inclu hw	217 Library Stor use as Comp Lab for Teachers	1	EA	6	\$301	
	Floor - Carpet	217 Library Stor use as Comp Lab for Teachers	725	SF	6	\$1,545	
	Lighting - Lay-in	217 Library Stor use as Comp Lab for Teachers	9	EA	7	\$0	
	Power Distribution	217 Library Stor use as Comp Lab for Teachers	14	EA	7	\$0	
	Walls - Plaster/Drywall	217 Library Stor use as Comp Lab for Teachers	1,120	SF	6	\$3,091	
	Ceiling - Plaster/Drywall	219, 220, 221, 222 Library Area	1,095	SF	6	\$3,789	
	Ceiling - Splined	219, 220, 221, 222 Library Area	67,600	SF	6	\$55,101	
	Doors - Wood Doors inclu hw	219, 220, 221, 222 Library Area	4	EA	6	\$1,204	
	Floor - Carpet	219, 220, 221, 222 Library Area	7,613	SF	6	\$16,221	
	Lighting - Lay-in	219, 220, 221, 222 Library Area	325	EA	7	\$0	
	Power Distribution	219, 220, 221, 222 Library Area	12	EA	7	\$0	
	Storage/ Closet	219, 220, 221, 222 Library Area	142	SF	6	\$1,030	#222A, 222B
	Walls - Plaster/Drywall	219, 220, 221, 222 Library Area	3,645	SF	6	\$10,060	
	Ceiling - Splined	220A Librarian Office (Use as Storage)	432	SF	6	\$352	
	Doors - Side-lite	220A Librarian Office (Use as Storage)	180	SF	6	\$3,009	
	Doors - Transom Window	220A Librarian Office (Use as Storage)	20	SF	6	\$339	Wood panel
	Doors - Wood Doors inclu hw	220A Librarian Office (Use as Storage)	2	EA	6	\$602	
	Floor - Carpet	220A Librarian Office (Use as Storage)	432	SF	6	\$920	
	Lighting - Lay-in	220A Librarian Office (Use as Storage)	6	EA	6	\$714	
	Power Distribution	220A Librarian Office (Use as Storage)	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	220A Librarian Office (Use as Storage)	855	SF	6	\$2,360	
	Ceiling - Splined	220B Office in Library (Use as Storage)	216	SF	6	\$176	
	Doors - Side-lite	220B Office in Library (Use as Storage)	40	SF	6	\$669	
	Doors - Transom Window	220B Office in Library (Use as Storage)	10	SF	6	\$169	Wood panel
	Doors - Wood Doors inclu hw	220B Office in Library (Use as Storage)	1	EA	6	\$301	
	Floor - Carpet	220B Office in Library (Use as Storage)	216	SF	6	\$460	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	220B Office in Library (Use as Storage)	4	EA	7	\$0	
	Power Distribution	220B Office in Library (Use as Storage)	4	EA	7	\$0	
	Walls - Plaster/Drywall	220B Office in Library (Use as Storage)	561	SF	6	\$1,548	
	Ceiling - Splined	220C Conference Room	1,122	SF	6	\$915	
	Ceiling - Splined	220C Conference Room	3	SF	5	\$29	Dirt/water stains and damaged tiles
	Doors - Side-lite	220C Conference Room	3	SF	6	\$50	Wood panel
	Doors - Side-lite	220C Conference Room	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	220C Conference Room	1	EA	6	\$301	
	Floor - Tile/Sheet	220C Conference Room	1,125	SF	6	\$1,126	
	Lighting - Pendent/Surface	220C Conference Room	16	EA	6	\$1,982	Missing lenses
	Power Distribution	220C Conference Room	6	EA	7	\$0	
	Walls - Plaster/Drywall	220C Conference Room	1,854	SF	6	\$5,117	
	Work Slnk	220C Conference Room	1	EA	6	\$508	
	Ceiling - Splined	222F Office in Library	594	SF	6	\$484	
	Doors - Wood Doors inclu hw	222F Office in Library	1	EA	6	\$301	
	Floor - Carpet	222F Office in Library	594	SF	6	\$1,266	
	Lighting - Lay-in	222F Office in Library	10	EA	6	\$1,190	
	Power Distribution	222F Office in Library	6	EA	6	\$12,749	
	Walls - Metal Panel	222F Office in Library	346	SF	6	\$2,583	Glass (SF)
	Walls - Plaster/Drywall	222F Office in Library	1,010	SF	6	\$2,787	
	Ceiling - Splined	225A, Office in Library	454	SF	6	\$370	
	Doors - Side-lite	225A, Office in Library	45	SF	6	\$752	
	Doors - Transom Window	225A, Office in Library	10	SF	6	\$169	Wood panel
	Doors - Wood Doors inclu hw	225A, Office in Library	1	EA	6	\$301	
	Floor - Carpet	225A, Office in Library	454	SF	6	\$967	
	Lighting - Lay-in	225A, Office in Library	15	EA	7	\$0	
	Power Distribution	225A, Office in Library	8	EA	7	\$0	
	Walls - Plaster/Drywall	225A, Office in Library	825	SF	6	\$2,277	
	Ceiling - Splined	225A, Office	454	SF	6	\$370	
	Doors - Side-lite	225A, Office	45	SF	6	\$752	
	Doors - Transom Window	225A, Office	10	SF	6	\$169	Wood panel
	Doors - Wood Doors inclu hw	225A, Office	1	EA	6	\$301	
	Floor - Carpet	225A, Office	454	SF	6	\$967	
	Lighting - Lay-in	225A, Office	15	EA	7	\$0	
	Power Distribution	225A, Office	8	EA	7	\$0	
	Walls - Plaster/Drywall	225A, Office	825	SF	6	\$2,277	
	Ceiling - Splined	Conference room near English 322	375	SF	6	\$306	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Side-lite	Conference room near English 322	150	SF	6	\$2,508	
	Doors - Wood Doors inclu hw	Conference room near English 322	1	EA	6	\$301	
	Floor - Carpet	Conference room near English 322	375	SF	4	\$3,448	Carpet, damage and stained
	Lighting - Pendent/Surface	Conference room near English 322	6	EA	7	\$0	
	Power Distribution	Conference room near English 322	18	EA	7	\$0	
	Walls - Plaster/Drywall	Conference room near English 322	1,400	SF	6	\$3,864	
	Ceiling - Plaster/Drywall	Copy room next to 109A	138	SF	6	\$478	
	Doors - Wood Doors inclu hw	Copy room next to 109A	1	EA	6	\$301	
	Floor - Tile/Sheet	Copy room next to 109A	6	SF	5	\$35	Missing tiles
	Floor - Tile/Sheet	Copy room next to 109A	132	SF	6	\$132	
	Lighting - Lay-in	Copy room next to 109A	2	EA	7	\$0	
	Power Distribution	Copy room next to 109A	4	EA	7	\$0	
	Walls - Concrete Block	Copy room next to 109A	46	SF	6	\$135	
	Walls - Plaster/Drywall	Copy room next to 109A	70	SF	6	\$193	
	Ceiling - Lay-in	ID Office NE of main Entrance	144	SF	6	\$432	
	Doors - Wood Doors inclu hw	ID Office NE of main Entrance	1	EA	6	\$301	
	Floor - Carpet	ID Office NE of main Entrance	114	SF	6	\$243	
	Lighting - Lay-in	ID Office NE of main Entrance	2	EA	7	\$0	
	Power Distribution	ID Office NE of main Entrance	6	EA	7	\$0	
	Storage/ Closet	ID Office NE of main Entrance	8	SF	6	\$58	
	Walls - Plaster/Drywall	ID Office NE of main Entrance	458	SF	6	\$1,264	
	Ceiling - Splined	Office D & C in Library	210	SF	6	\$171	
	Doors - Wood Doors inclu hw	Office D & C in Library	2	EA	6	\$602	
	Floor - Carpet	Office D & C in Library	210	SF	6	\$447	
	Lighting - Lay-in	Office D & C in Library	2	EA	7	\$0	
	Power Distribution	Office D & C in Library	6	EA	7	\$0	
	Walls - Plaster/Drywall	Office D & C in Library	637	SF	6	\$1,758	
	Ceiling - Plaster/Drywall	Office in Boy's locker room	70	SF	6	\$242	
	Doors - Side-lite	Office in Boy's locker room	30	SF	6	\$502	
	Doors - Steel Doors incl hw	Office in Boy's locker room	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Office in Boy's locker room	70	SF	6	\$148	Stain on floor
	Lighting - Pendent/Surface	Office in Boy's locker room	2	EA	7	\$0	
	Power Distribution	Office in Boy's locker room	2	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	Office in Boy's locker room	204	SF	6	\$461	
	Ceiling - Plaster/Drywall	Office in Girl's locker room	70	SF	6	\$242	
	Doors - Side-lite	Office in Girl's locker room	30	SF	6	\$502	
	Doors - Steel Doors incl hw	Office in Girl's locker room	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Tile Ceramic/ Porcelain	Office in Girl's locker room	70	SF	6	\$148	
	Lighting - Pendent/Surface	Office in Girl's locker room	2	EA	6	\$248	
	Power Distribution	Office in Girl's locker room	2	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	Office in Girl's locker room	204	SF	6	\$461	
	Ceiling - Lay-in	Office in room 117	167	SF	6	\$502	
	Doors - Wood Doors inclu hw	Office in room 117	1	EA	6	\$301	
	Floor - Tile/Sheet	Office in room 117	167	SF	6	\$167	
	Lighting - Lay-in	Office in room 117	3	EA	7	\$0	
	Power Distribution	Office in room 117	4	EA	7	\$0	
	Walls - Plaster/Drywall	Office in room 117	1	SF	5	\$8	Bubbling paint
	Walls - Structural Glazed Tile	Office in room 117	586	SF	6	\$1,844	
	Ceiling - Lay-in	Police Security Located in 210	248	SF	6	\$745	
	Doors - Transom Window	Police Security Located in 210	2	SF	6	\$34	
	Floor - Tile/Sheet	Police Security Located in 210	248	SF	6	\$248	
	Lighting - Lay-in	Police Security Located in 210	4	EA	7	\$0	
	Power Distribution	Police Security Located in 210	4	EA	7	\$0	
	Walls - Concrete Block	Police Security Located in 210	264	SF	6	\$774	
	Walls - Plaster/Drywall	Police Security Located in 210	432	SF	6	\$1,192	
	Ceiling - Lay-in	Principal's office, room 100	223	SF	6	\$670	
	Doors - Wood Doors inclu hw	Principal's office, room 100	1	EA	6	\$301	
	Floor - Carpet	Principal's office, room 100	223	SF	6	\$475	
	Lighting - Lay-in	Principal's office, room 100	4	EA	7	\$0	
	Power Distribution	Principal's office, room 100	2	EA	7	\$0	
	Walls - Plaster/Drywall	Principal's office, room 100	350	SF	6	\$966	
	Ceiling - Lay-in	Rm 101- Engineer's office	345	SF	6	\$1,036	
	Doors - Wood Doors inclu hw	Rm 101- Engineer's office	1	EA	6	\$301	
	Floor - Tile	Rm 101- Engineer's office	345	SF	6	\$755	
	Lighting - Lay-in	Rm 101- Engineer's office	6	EA	7	\$0	
	Power Distribution	Rm 101- Engineer's office	10	EA	7	\$0	
	Storage/ Closet	Rm 101- Engineer's office	24	SF	6	\$174	
	Walls - Plaster/Drywall	Rm 101- Engineer's office	829	SF	6	\$2,288	
	AC Unit	Rm 106- Main office (Public/Gen. Office)	2	EA	4	\$12,173	not working
	Ceiling - Lay-in	Rm 106- Main office (Public/Gen. Office)	1,117	SF	6	\$3,354	
	Doors - Side-lite	Rm 106- Main office (Public/Gen. Office)	11	SF	6	\$184	
	Doors - Wood Doors inclu hw	Rm 106- Main office (Public/Gen. Office)	2	EA	6	\$602	
	Floor - Tile	Rm 106- Main office (Public/Gen. Office)	1,117	SF	6	\$2,444	
	Lighting - Lay-in	Rm 106- Main office (Public/Gen. Office)	22	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	Rm 106- Main office (Public/Gen. Office)	10	EA	7	\$0	
	Storage/ Closet	Rm 106- Main office (Public/Gen. Office)	150	SF	6	\$1,088	storage room
	Walls - Plaster/Drywall	Rm 106- Main office (Public/Gen. Office)	2,335	SF	6	\$6,444	
	Ceiling - Plaster/Drywall	Rm 106C, Treasurer's Office	115	SF	6	\$398	
	Doors - Wood Doors inclu hw	Rm 106C, Treasurer's Office	1	EA	6	\$301	
	Floor - Carpet	Rm 106C, Treasurer's Office	115	SF	6	\$245	
	Lighting - Lay-in	Rm 106C, Treasurer's Office	4	EA	7	\$0	
	Power Distribution	Rm 106C, Treasurer's Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106C, Treasurer's Office	400	SF	6	\$1,104	
	Ceiling - Lay-in	Rm 106D- Clerk's Office	115	SF	6	\$345	
	Doors - Wood Doors inclu hw	Rm 106D- Clerk's Office	1	EA	6	\$301	
	Floor - Carpet	Rm 106D- Clerk's Office	115	SF	6	\$245	
	Lighting - Lay-in	Rm 106D- Clerk's Office	4	EA	7	\$0	
	Power Distribution	Rm 106D- Clerk's Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106D- Clerk's Office	400	SF	6	\$1,104	
	AC Unit	Rm 106H- Principal Office	1	EA	6	\$496	
	Ceiling - Lay-in	Rm 106H- Principal Office	230	SF	6	\$691	
	Doors - Wood Doors inclu hw	Rm 106H- Principal Office	1	EA	6	\$301	
	Floor - Carpet	Rm 106H- Principal Office	230	SF	6	\$490	
	Lighting - Lay-in	Rm 106H- Principal Office	4	EA	7	\$0	
	Power Distribution	Rm 106H- Principal Office	8	EA	7	\$0	
	Storage/ Closet	Rm 106H- Principal Office	8	SF	6	\$58	
	Walls - Plaster/Drywall	Rm 106H- Principal Office	500	SF	6	\$1,380	
	Ceiling - Lay-in	Rm 106I- Work Rm	266	SF	6	\$799	
	Doors - Wood Doors inclu hw	Rm 106I- Work Rm	1	EA	6	\$301	
	Floor - Tile	Rm 106I- Work Rm	266	SF	6	\$582	
	Lighting - Lay-in	Rm 106I- Work Rm	5	EA	7	\$0	
	Power Distribution	Rm 106I- Work Rm	8	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106I- Work Rm	500	SF	6	\$1,380	
	AC Unit	Rm 106J- Conference Rm	1	EA	4	\$6,086	not working
	Ceiling - Lay-in	Rm 106J- Conference Rm	230	SF	6	\$691	
	Doors - Wood Doors inclu hw	Rm 106J- Conference Rm	1	EA	6	\$301	
	Floor - Tile	Rm 106J- Conference Rm	230	SF	6	\$503	
	Lighting - Lay-in	Rm 106J- Conference Rm	4	EA	7	\$0	
	Power Distribution	Rm 106J- Conference Rm	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106J- Conference Rm	500	SF	6	\$1,380	
	AC Unit	Rm 106K, Asst Principal	1	EA	6	\$496	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	Rm 106K, Asst Principal	105	SF	6	\$315	
	Doors - Wood Doors inclu hw	Rm 106K, Asst Principal	1	EA	6	\$301	
	Floor - Tile	Rm 106K, Asst Principal	105	SF	6	\$230	
	Lighting - Lay-in	Rm 106K, Asst Principal	2	EA	7	\$0	
	Power Distribution	Rm 106K, Asst Principal	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106K, Asst Principal	386	SF	6	\$1,065	
	AC Unit	Rm 106L- Break Room	1	EA	4	\$6,086	not working
	Ceiling - Lay-in	Rm 106L- Break Room	98	SF	6	\$294	
	Doors - Wood Doors inclu hw	Rm 106L- Break Room	1	EA	6	\$301	
	Floor - Carpet	Rm 106L- Break Room	98	SF	6	\$209	
	Lighting - Lay-in	Rm 106L- Break Room	2	EA	7	\$0	
	Power Distribution	Rm 106L- Break Room	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106L- Break Room	375	SF	6	\$1,035	
	Walls - Plaster/Drywall	Rm 106L- Break Room	1	SF	5	\$5	damaged
	AC Unit	Rm 106M- Asst.Principal	1	EA	4	\$6,086	not working
	Ceiling - Lay-in	Rm 106M- Asst.Principal	130	SF	6	\$390	
	Doors - Wood Doors inclu hw	Rm 106M- Asst.Principal	1	EA	6	\$301	
	Floor - Tile	Rm 106M- Asst.Principal	130	SF	6	\$284	
	Lighting - Pendent/Surface	Rm 106M- Asst.Principal	4	EA	7	\$0	
	Power Distribution	Rm 106M- Asst.Principal	10	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106M- Asst.Principal	425	SF	6	\$1,173	
	Ceiling - Lay-in	Rm 106O, Uniform Storage/Office	115	SF	6	\$345	
	Doors - Wood Doors inclu hw	Rm 106O, Uniform Storage/Office	1	EA	6	\$301	
	Floor - Carpet	Rm 106O, Uniform Storage/Office	115	SF	6	\$245	
	Lighting - Lay-in	Rm 106O, Uniform Storage/Office	4	EA	7	\$0	
	Power Distribution	Rm 106O, Uniform Storage/Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 106O, Uniform Storage/Office	400	SF	6	\$1,104	
	Ceiling - Lay-in	Rm 127- BAM Office	218	SF	6	\$655	
	Doors - Wood Doors inclu hw	Rm 127- BAM Office	1	EA	6	\$301	
	Floor - Tile	Rm 127- BAM Office	218	SF	6	\$477	
	Lighting - Lay-in	Rm 127- BAM Office	6	EA	7	\$0	
	Power Distribution	Rm 127- BAM Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 127- BAM Office	440	SF	6	\$1,214	
	Ceiling - Lay-in	Rm 310- Teacher's Office	975	SF	6	\$2,928	
	Ceiling - Lay-in	Rm 310- Teacher's Office	20	SF	5	\$160	water damaged
	Doors - Side-lite	Rm 310- Teacher's Office	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	Rm 310- Teacher's Office	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Tile	Rm 310- Teacher's Office	995	SF	6	\$2,177	
	Lighting - Lay-in	Rm 310- Teacher's Office	11	EA	7	\$0	
	Power Distribution	Rm 310- Teacher's Office	20	EA	7	\$0	
	Storage/ Closet	Rm 310- Teacher's Office	44	SF	5	\$710	water damaged
	Storage/ Closet	Rm 310- Teacher's Office	161	SF	6	\$1,167	
	Walls - Plaster/Drywall	Rm 310- Teacher's Office	30	SF	5	\$153	water damaged-- ROOM HAS A MUSTY SMELL
	Walls - Plaster/Drywall	Rm 310- Teacher's Office	1,308	SF	6	\$3,610	
	Ceiling - Splined	Rm 315A- Book & Copy Rm	379	SF	6	\$309	
	Ceiling - Splined	Rm 315A- Book & Copy Rm	5	SF	5	\$48	water damaged
	Doors - Side-lite	Rm 315A- Book & Copy Rm	107	SF	6	\$1,789	
	Doors - Wood Doors inclu hw	Rm 315A- Book & Copy Rm	1	EA	6	\$301	
	Floor - Carpet	Rm 315A- Book & Copy Rm	384	SF	4	\$3,531	Old worn and stained
	Lighting - Lay-in	Rm 315A- Book & Copy Rm	6	EA	7	\$0	
	Power Distribution	Rm 315A- Book & Copy Rm	12	EA	7	\$0	
	Storage/ Closet	Rm 315A- Book & Copy Rm	77	SF	6	\$558	
	Walls - Plaster/Drywall	Rm 315A- Book & Copy Rm	1,171	SF	6	\$3,232	
	Walls - Plaster/Drywall	Rm 315A- Book & Copy Rm	20	SF	5	\$102	water damaged
	Ceiling - Splined	Rm 317A, Vacant Office	97	SF	6	\$79	
	Doors - Wood Doors inclu hw	Rm 317A, Vacant Office	1	EA	6	\$301	
	Floor - Carpet	Rm 317A, Vacant Office	97	SF	4	\$892	old, worn, stained
	Lighting - Lay-in	Rm 317A, Vacant Office	1	EA	7	\$0	
	Power Distribution	Rm 317A, Vacant Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 317A, Vacant Office	365	SF	6	\$1,007	
	Walls - Plaster/Drywall	Rm 317A, Vacant Office	50	SF	5	\$221	water damaged
	Ceiling - Splined	Rm 317A1, Social Studies Office	466	SF	6	\$380	
	Doors - Wood Doors inclu hw	Rm 317A1, Social Studies Office	1	EA	6	\$301	
	Floor - Carpet	Rm 317A1, Social Studies Office	466	SF	4	\$4,285	old, worn & stained
	Lighting - Lay-in	Rm 317A1, Social Studies Office	12	EA	7	\$0	4 are cans
	Power Distribution	Rm 317A1, Social Studies Office	16	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 317A1, Social Studies Office	8	SF	5	\$41	water damaged
	Walls - Plaster/Drywall	Rm 317A1, Social Studies Office	1,419	SF	6	\$3,916	
	Ceiling - Splined	Rm 317B, Office	97	SF	6	\$79	
	Doors - Side-lite	Rm 317B, Office	59	SF	6	\$986	
	Doors - Wood Doors inclu hw	Rm 317B, Office	1	EA	6	\$301	
	Floor - Carpet	Rm 317B, Office	97	SF	4	\$892	old, worn, stained
	Lighting - Lay-in	Rm 317B, Office	1	EA	7	\$0	
	Power Distribution	Rm 317B, Office	4	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Plaster/Drywall	Rm 317B, Office	415	SF	6	\$1,145	
	Ceiling - Splined	Rm 317C, Office	2	SF	5	\$19	water damaged
	Ceiling - Splined	Rm 317C, Office	95	SF	6	\$77	
	Doors - Side-lite	Rm 317C, Office	59	SF	6	\$986	
	Doors - Wood Doors inclu hw	Rm 317C, Office	1	EA	5	\$1,174	split at lock
	Floor - Carpet	Rm 317C, Office	97	SF	4	\$892	old, worn, stained
	Lighting - Lay-in	Rm 317C, Office	1	EA	7	\$0	
	Power Distribution	Rm 317C, Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 317C, Office	415	SF	6	\$1,145	
	Ceiling - Splined	Rm 317F, Office	97	SF	6	\$79	
	Doors - Side-lite	Rm 317F, Office	59	SF	6	\$986	
	Doors - Wood Doors inclu hw	Rm 317F, Office	1	EA	6	\$301	
	Floor - Carpet	Rm 317F, Office	97	SF	4	\$892	old, worn, stained
	Lighting - Lay-in	Rm 317F, Office	1	EA	7	\$0	
	Power Distribution	Rm 317F, Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 317F, Office	415	SF	6	\$1,145	
	Ceiling - Splined	Rm 317G, Vacant Office	113	SF	6	\$92	
	Doors - Side-lite	Rm 317G, Vacant Office	59	SF	6	\$986	
	Doors - Wood Doors inclu hw	Rm 317G, Vacant Office	1	EA	6	\$301	
	Floor - Carpet	Rm 317G, Vacant Office	113	SF	4	\$1,039	old, worn, stained
	Lighting - Lay-in	Rm 317G, Vacant Office	1	EA	7	\$0	
	Power Distribution	Rm 317G, Vacant Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 317G, Vacant Office	465	SF	6	\$1,283	
	Ceiling - Plaster/Drywall	Rm 319-322- Reading room	10	SF	5	\$125	water damaged
	Ceiling - Plaster/Drywall	Rm 319-322- Reading room	1,095	SF	6	\$3,789	
	Ceiling - Splined	Rm 319-322- Reading room	6,740	SF	6	\$5,494	
	Ceiling - Splined	Rm 319-322- Reading room	20	SF	5	\$193	water stains
	Doors - Steel Doors incl hw	Rm 319-322- Reading room	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	Rm 319-322- Reading room	2	EA	6	\$602	
	Floor - Carpet	Rm 319-322- Reading room	7,613	SF	6	\$16,221	
	Lighting - Lay-in	Rm 319-322- Reading room	252	EA	7	\$0	
	Lighting - Pendent/Surface	Rm 319-322- Reading room	11	EA	7	\$0	
	Power Distribution	Rm 319-322- Reading room	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 319-322- Reading room	3,645	SF	6	\$10,060	
	Walls - Plaster/Drywall	Rm 319-322- Reading room	6	SF	5	\$31	water damaged
	Ceiling - Splined	Rm 320A -Math dept office	147	SF	6	\$120	
	Doors - Wood Doors inclu hw	Rm 320A -Math dept office	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Carpet	Rm 320A -Math dept office	147	SF	5	\$755	
	Lighting - Lay-in	Rm 320A -Math dept office	2	EA	7	\$0	
	Power Distribution	Rm 320A -Math dept office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 320A -Math dept office	365	SF	6	\$1,007	
	Ceiling - Splined	Rm 320B -Math dept office	147	SF	6	\$120	
	Doors - Wood Doors inclu hw	Rm 320B -Math dept office	1	EA	6	\$301	
	Floor - Carpet	Rm 320B -Math dept office	147	SF	4	\$1,352	Old worn and stained
	Lighting - Lay-in	Rm 320B -Math dept office	2	EA	7	\$0	
	Power Distribution	Rm 320B -Math dept office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 320B -Math dept office	365	SF	6	\$1,007	
	Ceiling - Plaster/Drywall	Rm 323A -Lobby of English dept	103	SF	6	\$356	
	Doors - Side-lite	Rm 323A -Lobby of English dept	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	Rm 323A -Lobby of English dept	1	EA	6	\$301	
	Floor - Carpet	Rm 323A -Lobby of English dept	103	SF	4	\$947	old, worn and stained
	Lighting - Pendant/Surface	Rm 323A -Lobby of English dept	2	EA	7	\$0	
	Power Distribution	Rm 323A -Lobby of English dept	2	EA	7	\$0	
	Storage/ Closet	Rm 323A -Lobby of English dept	86	SF	6	\$624	
	Walls - Plaster/Drywall	Rm 323A -Lobby of English dept	320	SF	6	\$883	
	Ceiling - Splined	Rm 323A, Special Ed Office	115	SF	6	\$94	
	Doors - Side-lite	Rm 323A, Special Ed Office	118	SF	6	\$1,973	
	Doors - Wood Doors inclu hw	Rm 323A, Special Ed Office	1	EA	6	\$301	
	Floor - Carpet	Rm 323A, Special Ed Office	115	SF	4	\$1,057	old, worn, stained
	Lighting - Lay-in	Rm 323A, Special Ed Office	2	EA	7	\$0	
	Power Distribution	Rm 323A, Special Ed Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 323A, Special Ed Office	445	SF	6	\$1,228	
	Ceiling - Lay-in	Rm 323B -English dept office	147	SF	6	\$441	
	Doors - Wood Doors inclu hw	Rm 323B -English dept office	1	EA	6	\$301	
	Floor - Carpet	Rm 323B -English dept office	147	SF	4	\$1,352	Old worn and stained
	Lighting - Lay-in	Rm 323B -English dept office	2	EA	7	\$0	
	Power Distribution	Rm 323B -English dept office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 323B -English dept office	365	SF	6	\$1,007	
	Ceiling - Splined	Rm 323C -English dept office	146	SF	6	\$119	
	Ceiling - Splined	Rm 323C -English dept office	1	SF	5	\$10	damaged
	Doors - Wood Doors inclu hw	Rm 323C -English dept office	1	EA	6	\$301	
	Floor - Carpet	Rm 323C -English dept office	147	SF	4	\$1,352	old worn and stained
	Lighting - Lay-in	Rm 323C -English dept office	2	EA	7	\$0	
	Power Distribution	Rm 323C -English dept office	6	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Plaster/Drywall	Rm 323C -English dept office	365	SF	6	\$1,007	
	Ceiling - Splined	Rm 324- Student Center	656	SF	6	\$535	
	Doors - Wood Doors inclu hw	Rm 324- Student Center	1	EA	6	\$301	
	Floor - Carpet	Rm 324- Student Center	656	SF	4	\$6,032	Old worn and stained
	Lighting - Lay-in	Rm 324- Student Center	12	EA	7	\$0	
	Power Distribution	Rm 324- Student Center	24	EA	7	\$0	
	Storage/ Closet	Rm 324- Student Center	59	SF	6	\$428	
	Walls - Metal Panel	Rm 324- Student Center	180	SF	6	\$1,344	Partition
	Walls - Plaster/Drywall	Rm 324- Student Center	891	SF	6	\$2,459	
	Work Slnk	Rm 324- Student Center	1	EA	6	\$508	
	Ceiling - Splined	Rm 325- Career Academy Suite	4	SF	5	\$39	water damaged
	Ceiling - Splined	Rm 325- Career Academy Suite	652	SF	6	\$531	
	Doors - Side-lite	Rm 325- Career Academy Suite	50	SF	6	\$836	
	Doors - Wood Doors inclu hw	Rm 325- Career Academy Suite	1	EA	6	\$301	
	Floor - Carpet	Rm 325- Career Academy Suite	656	SF	6	\$1,398	
	Lighting - Lay-in	Rm 325- Career Academy Suite	9	EA	7	\$0	
	Power Distribution	Rm 325- Career Academy Suite	10	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 325- Career Academy Suite	1,471	SF	6	\$4,060	
	Work Slnk	Rm 325- Career Academy Suite	1	EA	6	\$508	
	Ceiling - Splined	Rm 325B, Psychologist Office	115	SF	6	\$94	
	Doors - Side-lite	Rm 325B, Psychologist Office	118	SF	6	\$1,973	
	Doors - Wood Doors inclu hw	Rm 325B, Psychologist Office	1	EA	6	\$301	
	Floor - Carpet	Rm 325B, Psychologist Office	115	SF	4	\$1,057	old, worn, stained
	Lighting - Lay-in	Rm 325B, Psychologist Office	2	EA	7	\$0	
	Power Distribution	Rm 325B, Psychologist Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 325B, Psychologist Office	445	SF	6	\$1,228	
	Ceiling - Exposed	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	1,100	SF	6	\$1,636	
	Doors - Side-lite	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	18	SF	6	\$301	
	Doors - Side-lite	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	10	SF	6	\$167	Wood panel
	Doors - Wood Doors inclu hw	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	1	EA	6	\$301	
	Floor - Carpet	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	1,100	SF	6	\$2,344	
	Lighting - Lay-in	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	22	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	36	EA	7	\$0	
	Storage/ Closet	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	64	SF	6	\$464	
	Walls - Plaster/Drywall	Room 114 (Office 1-9, 112 Nurse & Rec. Office)	4,400	SF	6	\$12,144	
	Ceiling - Splined	Room 317, Conference room	883	SF	6	\$720	
	Doors - Wood Doors inclu hw	Room 317, Conference room	1	EA	6	\$301	
	Floor - Carpet	Room 317, Conference room	883	SF	5	\$4,533	
	Lighting - Lay-in	Room 317, Conference room	8	EA	7	\$0	
	Power Distribution	Room 317, Conference room	36	EA	7	\$0	
	Walls - Plaster/Drywall	Room 317, Conference room	1,427	SF	6	\$3,938	
Auditorium & Theater							
	Ceiling - Plaster/Drywall	1st Floor	5,251	SF	6	\$43,777	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	1st Floor	6	EA	6	\$1,806	
	Floor - Concrete Epoxy/ Painted	1st Floor	2,465	SF	6	\$1,304	
	Floor - Tile/Sheet	1st Floor	2,786	SF	6	\$2,789	
	Lighting - Lay-in	1st Floor	80	EA	6	\$9,518	
	Main Floor Seating	1st Floor	658	EA	6	\$114,437	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	1,649	SF	6	\$9,527	Wood floor
	Stage Curtain	1st Floor	8	EA	6	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor	10	LF	6	\$117	Carpet
	Storage/ Closet	1st Floor	174	SF	6	\$1,262	
	Walls - Concrete Block	1st Floor	3,645	SF	6	\$10,685	
	Walls - Plaster/Drywall	1st Floor	3,645	SF	6	\$17,357	
Gymnasia							
	Bleacher Seating	243 Main Gymnasium	1,200	EA	6	\$34,732	
	Ceiling - Exposed	243 Main Gymnasium	13,400	SF	6	\$19,928	
	Doors - Wood Doors inclu hw	243 Main Gymnasium	4	EA	6	\$1,204	
	Floor - Wood	243 Main Gymnasium	13,400	SF	6	\$94,469	
	Lighting - Pendent/Surface	243 Main Gymnasium	51	EA	7	\$0	
	Scoreboards	243 Main Gymnasium	2	EA	6	\$4,489	
	Sound System	243 Main Gymnasium	1	EA	6	\$41,654	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymnasia							
	Storage/ Closet	243 Main Gymnasium	10	SF	4	\$279	Holes and water damaged in ceiling
	Storage/ Closet	243 Main Gymnasium	618	SF	6	\$4,481	
	Walls - Concrete Block	243 Main Gymnasium	14,353	SF	6	\$42,076	
Library							
	Ceiling - Lay-in	217 Computer Lab	454	SF	6	\$1,363	
	Doors - Side-lite	217 Computer Lab	25	SF	6	\$418	
	Doors - Side-lite	217 Computer Lab	10	SF	6	\$167	Metal panel
	Doors - Transom Window	217 Computer Lab	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	217 Computer Lab	1	EA	6	\$301	
	Floor - Tile/Sheet	217 Computer Lab	454	SF	6	\$454	
	Lighting - Lay-in	217 Computer Lab	12	EA	7	\$0	
	Walls - Plaster/Drywall	217 Computer Lab	825	SF	6	\$2,277	
	Doors - Side-lite	219, 220, 221, 222 Library Area	160	SF	6	\$2,675	
	Doors - Transom Window	219, 220, 221, 222 Library Area	40	SF	6	\$677	Wood panel
Locker/Shower Room							
	Accessories	Boys Locker next to Pool & Natatorium	2,045	SF	6	\$8,013	
	Benches, ped mounted	Boys Locker next to Pool & Natatorium	14	LF	6	\$1,524	
	Ceiling - Plaster/ Drywall	Boys Locker next to Pool & Natatorium	2,045	SF	6	\$7,077	
	Doors - Wood Doors inclu hw	Boys Locker next to Pool & Natatorium	1	EA	6	\$301	
	Floor Drain	Boys Locker next to Pool & Natatorium	5	EA	6	\$5,296	
	Floor - Concrete Epoxy/ Painted	Boys Locker next to Pool & Natatorium	2,045	SF	6	\$1,082	
	Hand Dryer	Boys Locker next to Pool & Natatorium	1	EA	6	\$230	
	Lavatory	Boys Locker next to Pool & Natatorium	2	EA	6	\$639	
	Lighting - Pendant/Surface	Boys Locker next to Pool & Natatorium	15	EA	6	\$1,858	
	Partitions	Boys Locker next to Pool & Natatorium	3	EA	6	\$891	
	Showers	Boys Locker next to Pool & Natatorium	7	EA	6	\$2,180	
	Storage/ Closet	Boys Locker next to Pool & Natatorium	98	SF	6	\$711	Towel area
	Student Lockers - One Tier	Boys Locker next to Pool & Natatorium	8	EA	6	\$743	
	Student Lockers - Two Tier	Boys Locker next to Pool & Natatorium	52	EA	6	\$2,414	
	Walls - Tile Ceramic/ Porcelain	Boys Locker next to Pool & Natatorium	5,317	SF	6	\$12,013	
	Water Closet	Boys Locker next to Pool & Natatorium	3	EA	6	\$1,008	
	Accessories	Girls Locker next to Pool & Natatorium	2,045	SF	6	\$8,013	
	Benches, ped mounted	Girls Locker next to Pool & Natatorium	16	LF	6	\$1,742	
	Ceiling - Plaster/ Drywall	Girls Locker next to Pool & Natatorium	2,045	SF	6	\$7,077	
	Doors - Wood Doors inclu hw	Girls Locker next to Pool & Natatorium	1	EA	6	\$301	
	Floor Drain	Girls Locker next to Pool & Natatorium	5	EA	6	\$5,296	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Floor - Concrete Epoxy/ Painted	Girls Locker next to Pool & Natatorium	2,045	SF	6	\$1,082	
	Hand Dryer	Girls Locker next to Pool & Natatorium	1	EA	6	\$230	
	Lavatory	Girls Locker next to Pool & Natatorium	2	EA	6	\$639	
	Lighting - Pendent/Surface	Girls Locker next to Pool & Natatorium	19	EA	6	\$2,354	
	Partitions	Girls Locker next to Pool & Natatorium	3	EA	6	\$891	
	Showers	Girls Locker next to Pool & Natatorium	15	EA	6	\$4,671	
	Storage/ Closet	Girls Locker next to Pool & Natatorium	132	SF	6	\$957	Towel area
	Student Lockers - One Tier	Girls Locker next to Pool & Natatorium	9	EA	6	\$836	
	Student Lockers - Two Tier	Girls Locker next to Pool & Natatorium	62	EA	6	\$2,878	
	Walls - Tile Ceramic/ Porcelain	Girls Locker next to Pool & Natatorium	5,317	SF	6	\$12,013	
	Water Closet	Girls Locker next to Pool & Natatorium	4	EA	6	\$1,344	
	Accessories	Men's staff locker room- next to engineer's office	84	SF	6	\$329	
	Ceiling - Plaster/ Drywall	Men's staff locker room- next to engineer's office	84	SF	6	\$291	
	Doors - Wood Doors inclu hw	Men's staff locker room- next to engineer's office	1	EA	6	\$301	
	Floor Drain	Men's staff locker room- next to engineer's office	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	Men's staff locker room- next to engineer's office	151	SF	6	\$320	
	Floor - Tile Ceramic/ Porcelain	Men's staff locker room- next to engineer's office	10	SF	5	\$209	missing tiles
	Floor - Tile/Sheet	Men's staff locker room- next to engineer's office	363	SF	5	\$1,630	
	Lavatory	Men's staff locker room- next to engineer's office	2	EA	6	\$639	
	Lighting - Pendent/Surface	Men's staff locker room- next to engineer's office	7	EA	7	\$0	
	Lighting - Pendent/Surface	Men's staff locker room- next to engineer's office	1	EA	4	\$541	T12 in shower
	Lighting - Pendent/Surface	Men's staff locker room- next to engineer's office	2	EA	5	\$365	rusting & missing cover in toilet area
	Lighting - Wall Mounted	Men's staff locker room- next to engineer's office	1	EA	4	\$393	T12 on wall in toilet area
	Partitions	Men's staff locker room- next to engineer's office	1	EA	6	\$297	
	Showers	Men's staff locker room- next to engineer's office	1	EA	6	\$311	
	Storage/ Closet	Men's staff locker room- next to engineer's office	214	SF	6	\$1,552	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Student Lockers - One Tier	Men's staff locker room- next to engineer's office	15	EA	5	\$2,102	old & rusting
	Urinals	Men's staff locker room- next to engineer's office	2	EA	6	\$672	
	Walls - Plaster/Drywall	Men's staff locker room- next to engineer's office	935	SF	5	\$7,086	needs painting. area above lockers is a paneling of some kind
	Walls - Tile Ceramic/ Porcelain	Men's staff locker room- next to engineer's office	50	SF	5	\$1,050	wall in bowing in from water damage
	Walls - Tile Ceramic/ Porcelain	Men's staff locker room- next to engineer's office	583	SF	6	\$1,317	
	Water Closet	Men's staff locker room- next to engineer's office	1	EA	6	\$336	
MDF_IDF							
	Doors - Wood Doors inclu hw	Located in room 231	2	EA	6	\$602	
	Finishes	Located in room 231	264	SF	6	\$1,884	Painted conc. wall
	Finishes	Located in room 231	434	SF	6	\$3,097	Painted drywall
Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	1st Floor	110	SF	6	\$788	Machine room located in 131 video production
	Mechanical/ Service Rooms	1st Floor	998	SF	6	\$7,150	#148
	Mechanical/ Service Rooms	1st Floor	1,004	SF	6	\$7,193	Fan Rooms, Elev Machine Room & Mech. room
	Storage Room	1st Floor	810	SF	6	\$5,803	Pool Storage & equipment area
	Storage Room	1st Floor	316	SF	6	\$2,264	Book Storage/Storage
	Vaults	1st Floor	45	SF	6	\$322	Room 106B
	Interior Stairs	2nd Floor	56	LF	6	\$505	
	Janitor's Closet	2nd Floor	75	SF	6	\$537	#231A
	Mechanical/ Service Rooms	2nd Floor	3,576	SF	6	\$25,620	ASU #14,15,16,17
	Storage Room	2nd Floor	115	SF	6	\$824	241A Storage/Electrical in gym
	Storage Room	2nd Floor	253	SF	6	\$1,813	220E Book stor. in Library
	Janitor's Closet	3rd Floor	56	SF	5	\$903	water damaged walls & ceiling (near 315)
	Storage Room	3rd Floor	133	SF	5	\$2,145	324D & 331A - water damage
	Storage Room	3rd Floor	761	SF	6	\$5,452	317E (6' of wall is damaged), 324C, 322,
Pool & Natatorium							
	Accessories	1st Floor	3,875	SF	6	\$2,660	
	Bleachers Seating/Plank Seating	1st Floor	96	EA	6	\$2,779	
	Ceiling - Plaster/ Drywall	1st Floor	2,434	SF	6	\$13,435	
	Ceiling - Splined (Moister Resistance)	1st Floor	1,440	SF	6	\$1,503	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pool & Natatorium							
	Floor - Concrete Epoxy/ Painted	1st Floor	866	SF	6	\$458	
	Floor - Tile Ceramic/ Porcelain	1st Floor	1,324	SF	6	\$2,802	
	Lighting - Lay-in	1st Floor	24	EA	6	\$2,855	
	Lighting - Pendent/Surface	1st Floor	18	EA	6	\$2,230	
	Pool Basin	1st Floor	1,568	SF	6	\$53,051	
	Pool Deck	1st Floor	1,324	SF	6	\$12,572	
	Pool Deck Drains	1st Floor	14	EA	6	\$5,909	
	Walls - Plaster/Drywall	1st Floor	4,998	SF	6	\$15,509	
Prep Room							
	Casework	200A Prep Room	20	LF	6	\$505	
	Ceiling - Plaster/Drywall	200A Prep Room	45	SF	6	\$156	
	Doors - Wood Doors inclu hw	200A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	200A Prep Room	45	SF	6	\$45	
	Lighting - Pendent/Surface	200A Prep Room	1	EA	6	\$124	
	Walls - Plaster/Drywall	200A Prep Room	280	SF	6	\$773	
	Work Sink	200A Prep Room	1	EA	6	\$379	
	Casework	204A Prep Room	20	LF	6	\$505	
	Ceiling - Plaster/Drywall	204A Prep Room	45	SF	6	\$156	
	Doors - Wood Doors inclu hw	204A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	204A Prep Room	45	SF	6	\$45	
	Lighting - Pendent/Surface	204A Prep Room	1	EA	6	\$124	
	Walls - Plaster/Drywall	204A Prep Room	1	SF	5	\$5	Peeling paint
	Walls - Plaster/Drywall	204A Prep Room	279	SF	6	\$770	
	Work Sink	204A Prep Room	1	EA	6	\$379	
	Casework	212A Prep Room	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	212A Prep Room	54	SF	6	\$187	
	Doors - Wood Doors inclu hw	212A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	212A Prep Room	54	SF	6	\$54	
	Lighting - Pendent/Surface	212A Prep Room	1	EA	6	\$124	
	Walls - Plaster/Drywall	212A Prep Room	314	SF	6	\$867	
	Work Sink	212A Prep Room	1	EA	6	\$379	
	Casework	216A Prep Room	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	216A Prep Room	54	SF	6	\$187	
	Doors - Wood Doors inclu hw	216A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	216A Prep Room	54	SF	6	\$54	
	Lighting - Pendent/Surface	216A Prep Room	1	EA	6	\$124	
	Walls - Plaster/Drywall	216A Prep Room	314	SF	6	\$867	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Prep Room							
	Work Sink	216A Prep Room	1	EA	6	\$379	
	Casework	302A Prep Room	20	LF	6	\$505	
	Ceiling - Lay-in	302A Prep Room	55	SF	6	\$165	
	Doors - Wood Doors inclu hw	302A Prep Room	1	EA	6	\$301	
	Floor - Tile	302A Prep Room	55	SF	6	\$120	
	Lighting - Lay-in	302A Prep Room	2	EA	6	\$238	
	Walls - Plaster/Drywall	302A Prep Room	280	SF	6	\$773	
	Work Sink	302A Prep Room	1	EA	6	\$379	missing faucet
	Casework	304A Prep Room	9	LF	6	\$227	
	Ceiling - Lay-in	304A Prep Room	55	SF	6	\$165	
	Doors - Wood Doors inclu hw	304A Prep Room	1	EA	6	\$301	
	Floor - Tile	304A Prep Room	55	SF	6	\$120	
	Lighting - Lay-in	304A Prep Room	1	EA	6	\$119	
	Walls - Plaster/Drywall	304A Prep Room	280	SF	6	\$773	
	Work Sink	304A Prep Room	1	EA	6	\$379	
	Casework	312A Prep Room	40	LF	6	\$1,010	
	Ceiling - Lay-in	312A Prep Room	249	SF	6	\$748	
	Doors - Wood Doors inclu hw	312A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	312A Prep Room	249	SF	6	\$249	
	Lighting - Lay-in	312A Prep Room	4	EA	6	\$476	
	Walls - Plaster/Drywall	312A Prep Room	685	SF	6	\$1,891	
	Work Sink	312A Prep Room	1	EA	6	\$379	
	Casework	316A Prep Room	30	LF	6	\$758	
	Ceiling - Lay-in	316A Prep Room	219	SF	6	\$658	
	Doors - Wood Doors inclu hw	316A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	316A Prep Room	219	SF	6	\$219	
	Lighting - Lay-in	316A Prep Room	3	EA	6	\$357	
	Walls - Plaster/Drywall	316A Prep Room	625	SF	6	\$1,725	
	Work Sink	316A Prep Room	1	EA	6	\$379	
	Ceiling - Lay-in	Rm 403A- Photo Studio Control Rm	225	SF	6	\$676	
	Doors - Side-lite	Rm 403A- Photo Studio Control Rm	93	SF	6	\$1,555	
	Doors - Wood Doors inclu hw	Rm 403A- Photo Studio Control Rm	1	EA	6	\$301	
	Floor - Tile	Rm 403A- Photo Studio Control Rm	225	SF	6	\$492	
	Lighting - Lay-in	Rm 403A- Photo Studio Control Rm	2	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 403A- Photo Studio Control Rm	100	SF	5	\$442	water damaged
	Walls - Plaster/Drywall	Rm 403A- Photo Studio Control Rm	505	SF	6	\$1,394	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Accessories	1st floor Men's north across from 130	264	SF	6	\$2,435	
	Ceiling - Plaster/Drywall	1st floor Men's north across from 130	3	SF	5	\$37	Bubbling paint
	Ceiling - Plaster/Drywall	1st floor Men's north across from 130	261	SF	6	\$903	
	Floor Drain	1st floor Men's north across from 130	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor Men's north across from 130	264	SF	6	\$559	
	Hand Dryer	1st floor Men's north across from 130	1	EA	6	\$230	
	Lavatory	1st floor Men's north across from 130	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	1st floor Men's north across from 130	5	EA	6	\$619	
	Partitions	1st floor Men's north across from 130	2	EA	6	\$594	
	Urinals	1st floor Men's north across from 130	6	EA	6	\$2,016	
	Walls - Tile Ceramic/ Porcelain	1st floor Men's north across from 130	3	SF	5	\$63	Missing tiles
	Walls - Tile Ceramic/ Porcelain	1st floor Men's north across from 130	891	SF	6	\$2,013	
	Water Closet	1st floor Men's north across from 130	3	EA	6	\$1,008	
	Accessories	1st floor Women's south across from	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	1st floor Women's south across from	265	SF	6	\$917	
	Floor Drain	1st floor Women's south across from	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor Women's south across from	265	SF	6	\$561	
	Hand Dryer	1st floor Women's south across from	1	EA	6	\$230	
	Lavatory	1st floor Women's south across from	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	1st floor Women's south across from	5	EA	6	\$619	
	Partitions	1st floor Women's south across from	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	1st floor Women's south across from	894	SF	6	\$2,813	
	Water Closet	1st floor Women's south across from	7	EA	6	\$2,352	
	Accessories	1st Flr Men's- Next to 132	208	SF	6	\$1,918	
	Ceiling - Plaster/Drywall	1st Flr Men's- Next to 132	208	SF	6	\$720	
	Doors - Wood Doors inclu hw	1st Flr Men's- Next to 132	1	EA	6	\$301	
	Floor Drain	1st Flr Men's- Next to 132	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Flr Men's- Next to 132	208	SF	6	\$440	
	Lavatory	1st Flr Men's- Next to 132	2	EA	6	\$639	
	Lighting - Pendant/Surface	1st Flr Men's- Next to 132	5	EA	7	\$0	
	Partitions	1st Flr Men's- Next to 132	2	EA	6	\$594	
	Walls - Tile Ceramic/ Porcelain	1st Flr Men's- Next to 132	698	SF	6	\$1,577	
	Water Closet	1st Flr Men's- Next to 132	2	EA	6	\$672	
	Accessories	1st Flr Women's- Near 132	208	SF	6	\$1,918	
	Ceiling - Plaster/Drywall	1st Flr Women's- Near 132	208	SF	6	\$720	
	Doors - Wood Doors inclu hw	1st Flr Women's- Near 132	1	EA	6	\$301	
	Floor Drain	1st Flr Women's- Near 132	1	EA	6	\$1,059	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor - Tile Ceramic/ Porcelain	1st Flr Women's- Near 132	208	SF	6	\$440	
	Lavatory	1st Flr Women's- Near 132	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Flr Women's- Near 132	5	EA	7	\$0	
	Partitions	1st Flr Women's- Near 132	3	EA	6	\$891	
	Walls - Tile Ceramic/ Porcelain	1st Flr Women's- Near 132	15	SF	5	\$315	cracked wall tile
	Walls - Tile Ceramic/ Porcelain	1st Flr Women's- Near 132	683	SF	6	\$1,543	
	Water Closet	1st Flr Women's- Near 132	3	EA	6	\$1,008	
	Accessories	2nd floor Men's room south across from 204	264	SF	6	\$2,435	
	Ceiling - Plaster/Drywall	2nd floor Men's room south across from 204	264	SF	6	\$914	
	Floor Drain	2nd floor Men's room south across from 204	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor Men's room south across from 204	264	SF	6	\$559	
	Hand Dryer	2nd floor Men's room south across from 204	2	EA	6	\$460	
	Lavatory	2nd floor Men's room south across from 204	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	2nd floor Men's room south across from 204	5	EA	6	\$619	
	Partitions	2nd floor Men's room south across from 204	2	EA	6	\$594	
	Urinals	2nd floor Men's room south across from 204	6	EA	6	\$2,016	
	Walls - Structural Glazed Tile	2nd floor Men's room south across from 204	894	SF	6	\$2,813	
	Water Closet	2nd floor Men's room south across from 204	3	EA	6	\$1,008	
	Accessories	2nd floor women's room north across from 204	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	2nd floor women's room north across from 204	265	SF	6	\$917	
	Floor Drain	2nd floor women's room north across from 204	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor women's room north across from 204	265	SF	6	\$561	
	Hand Dryer	2nd floor women's room north across from 204	1	EA	6	\$230	
	Lavatory	2nd floor women's room north across from 204	4	EA	6	\$1,278	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Pendent/Surface	2nd floor women's room north across from 204	5	EA	6	\$619	
	Partitions	2nd floor women's room north across from 204	5	EA	6	\$1,485	
	Walls - Tile Ceramic/ Porcelain	2nd floor women's room north across from 204	894	SF	6	\$2,020	
	Water Closet	2nd floor women's room north across from 204	6	EA	6	\$2,016	
	Accessories	2nd floor Women's room south	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	2nd floor Women's room south	262	SF	6	\$907	
	Ceiling - Plaster/Drywall	2nd floor Women's room south	3	SF	5	\$37	Bubbling and peeling paint
	Doors - Wood Doors inclu hw	2nd floor Women's room south	1	EA	6	\$301	
	Floor Drain	2nd floor Women's room south	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor Women's room south	265	SF	6	\$561	
	Hand Dryer	2nd floor Women's room south	1	EA	6	\$230	
	Lavatory	2nd floor Women's room south	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	2nd floor Women's room south	5	EA	6	\$619	
	Partitions	2nd floor Women's room south	5	EA	6	\$1,485	
	Walls - Structural Glazed Tile	2nd floor Women's room south	894	SF	6	\$2,813	
	Water Closet	2nd floor Women's room south	6	EA	6	\$2,016	
	Accessories	3rd flr- Men's Across from 304	264	SF	6	\$2,435	
	Ceiling - Plaster/Drywall	3rd flr- Men's Across from 304	264	SF	6	\$914	
	Floor Drain	3rd flr- Men's Across from 304	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd flr- Men's Across from 304	264	SF	6	\$559	
	Hand Dryer	3rd flr- Men's Across from 304	1	EA	6	\$230	
	Lavatory	3rd flr- Men's Across from 304	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	3rd flr- Men's Across from 304	5	EA	7	\$0	
	Partitions	3rd flr- Men's Across from 304	2	EA	6	\$594	
	Urinals	3rd flr- Men's Across from 304	5	EA	6	\$1,680	
	Urinals	3rd flr- Men's Across from 304	1	EA	5	\$1,344	not working
	Walls - Structural Glazed Tile	3rd flr- Men's Across from 304	894	SF	6	\$2,813	
	Water Closet	3rd flr- Men's Across from 304	2	EA	6	\$672	
	Accessories	3rd flr- Men's Next to 333	264	SF	6	\$2,435	
	Ceiling - Plaster/Drywall	3rd flr- Men's Next to 333	264	SF	6	\$914	
	Floor Drain	3rd flr- Men's Next to 333	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd flr- Men's Next to 333	264	SF	6	\$559	
	Hand Dryer	3rd flr- Men's Next to 333	1	EA	6	\$230	
	Lavatory	3rd flr- Men's Next to 333	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	3rd flr- Men's Next to 333	3	EA	6	\$372	covers missing

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Pendant/Surface	3rd flr- Men's Next to 333	2	EA	7	\$0	
	Partitions	3rd flr- Men's Next to 333	2	EA	6	\$594	
	Urinals	3rd flr- Men's Next to 333	6	EA	6	\$2,016	
	Walls - Tile Ceramic/ Porcelain	3rd flr- Men's Next to 333	894	SF	6	\$2,020	
	Water Closet	3rd flr- Men's Next to 333	3	EA	6	\$1,008	
	Accessories	3rd Flr Unisex- Across from 314	70	SF	6	\$646	
	Ceiling - Plaster/Drywall	3rd Flr Unisex- Across from 314	70	SF	6	\$242	
	Doors - Wood Doors inclu hw	3rd Flr Unisex- Across from 314	1	EA	6	\$301	
	Floor Drain	3rd Flr Unisex- Across from 314	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Flr Unisex- Across from 314	70	SF	6	\$148	
	Hand Dryer	3rd Flr Unisex- Across from 314	1	EA	6	\$230	
	Lavatory	3rd Flr Unisex- Across from 314	1	EA	6	\$320	
	Lighting - Lay-in	3rd Flr Unisex- Across from 314	2	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	3rd Flr Unisex- Across from 314	268	SF	6	\$606	
	Water Closet	3rd Flr Unisex- Across from 314	1	EA	6	\$336	
	Accessories	3rd flr- Women's Across from 304	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	3rd flr- Women's Across from 304	265	SF	6	\$917	
	Floor Drain	3rd flr- Women's Across from 304	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd flr- Women's Across from 304	265	SF	6	\$561	
	Hand Dryer	3rd flr- Women's Across from 304	1	EA	6	\$230	
	Lavatory	3rd flr- Women's Across from 304	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	3rd flr- Women's Across from 304	5	EA	7	\$0	
	Partitions	3rd flr- Women's Across from 304	5	EA	6	\$1,485	
	Walls - Structural Glazed Tile	3rd flr- Women's Across from 304	894	SF	6	\$2,813	
	Water Closet	3rd flr- Women's Across from 304	6	EA	6	\$2,016	
	Accessories	3rd flr- Women's Next to 335	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	3rd flr- Women's Next to 335	265	SF	6	\$917	
	Floor Drain	3rd flr- Women's Next to 335	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd flr- Women's Next to 335	265	SF	6	\$561	
	Hand Dryer	3rd flr- Women's Next to 335	1	EA	6	\$230	
	Lavatory	3rd flr- Women's Next to 335	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	3rd flr- Women's Next to 335	5	EA	7	\$0	
	Partitions	3rd flr- Women's Next to 335	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	3rd flr- Women's Next to 335	894	SF	6	\$2,813	
	Water Closet	3rd flr- Women's Next to 335	7	EA	6	\$2,352	
	Accessories	In engineer's office	46	SF	6	\$424	
	Ceiling - Plaster/Drywall	In engineer's office	46	SF	6	\$159	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	In engineer's office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	In engineer's office	46	SF	6	\$97	
	Lavatory	In engineer's office	1	EA	6	\$320	
	Lighting - Pendent/Surface	In engineer's office	1	EA	7	\$0	
	Partitions	In engineer's office	1	EA	6	\$297	
	Walls - Tile Ceramic/ Porcelain	In engineer's office	225	SF	6	\$508	
	Water Closet	In engineer's office	1	EA	6	\$336	
	Accessories	Men's faculty restroom next to #116B	56	SF	6	\$517	
	Ceiling - Plaster/Drywall	Men's faculty restroom next to #116B	56	SF	6	\$194	
	Doors - Wood Doors inclu hw	Men's faculty restroom next to #116B	1	EA	6	\$301	
	Floor Drain	Men's faculty restroom next to #116B	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's faculty restroom next to #116B	56	SF	6	\$119	
	Lavatory	Men's faculty restroom next to #116B	1	EA	6	\$320	
	Lighting - Lay-in	Men's faculty restroom next to #116B	1	EA	6	\$119	
	Partitions	Men's faculty restroom next to #116B	1	EA	6	\$297	
	Urinals	Men's faculty restroom next to #116B	1	EA	6	\$336	
	Walls - Tile Ceramic/ Porcelain	Men's faculty restroom next to #116B	240	SF	6	\$542	
	Water Closet	Men's faculty restroom next to #116B	1	EA	6	\$336	
	Accessories	Men's in Main Office	61	SF	6	\$563	
	Ceiling - Plaster/Drywall	Men's in Main Office	61	SF	6	\$211	
	Doors - Wood Doors inclu hw	Men's in Main Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Men's in Main Office	61	SF	6	\$129	
	Lavatory	Men's in Main Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	Men's in Main Office	1	EA	7	\$0	
	Partitions	Men's in Main Office	1	EA	6	\$297	
	Walls - Tile Ceramic/ Porcelain	Men's in Main Office	310	SF	6	\$700	
	Water Closet	Men's in Main Office	1	EA	6	\$336	
	Accessories	Men's restroom north across from 228	114	SF	6	\$1,051	
	Ceiling - Plaster/Drywall	Men's restroom north across from 228	1	SF	5	\$12	Cracks
	Ceiling - Plaster/Drywall	Men's restroom north across from 228	113	SF	6	\$391	
	Doors - Wood Doors inclu hw	Men's restroom north across from 228	1	EA	6	\$301	
	Floor Drain	Men's restroom north across from 228	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's restroom north across from 228	114	SF	6	\$241	
	Lavatory	Men's restroom north across from 228	2	EA	6	\$639	
	Lighting - Lay-in	Men's restroom north across from 228	2	EA	6	\$238	
	Partitions	Men's restroom north across from 228	1	EA	6	\$297	
	Urinals	Men's restroom north across from 228	1	EA	5	\$1,344	Does not work

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Urinals	Men's restroom north across from 228	1	EA	6	\$336	
	Walls - Structural Glazed Tile	Men's restroom north across from 228	425	SF	6	\$1,337	
	Water Closet	Men's restroom north across from 228	1	EA	6	\$336	
	Accessories	Men's south next to 107 Auditorium	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	Men's south next to 107 Auditorium	265	SF	6	\$917	
	Floor Drain	Men's south next to 107 Auditorium	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's south next to 107 Auditorium	265	SF	6	\$561	
	Hand Dryer	Men's south next to 107 Auditorium	2	EA	6	\$460	
	Lavatory	Men's south next to 107 Auditorium	4	EA	6	\$1,278	faucet knob missing on ADA lavatory
	Lighting - Pendant/Surface	Men's south next to 107 Auditorium	5	EA	6	\$619	
	Partitions	Men's south next to 107 Auditorium	2	EA	5	\$1,502	Delaminated
	Urinals	Men's south next to 107 Auditorium	6	EA	6	\$2,016	
	Walls - Structural Glazed Tile	Men's south next to 107 Auditorium	894	SF	6	\$2,813	
	Water Closet	Men's south next to 107 Auditorium	2	EA	6	\$672	
	Accessories	Next to engineer's office	35	SF	6	\$323	
	Ceiling - Plaster/Drywall	Next to engineer's office	35	SF	6	\$121	
	Doors - Wood Doors inclu hw	Next to engineer's office	2	EA	6	\$602	
	Floor - Tile Ceramic/ Porcelain	Next to engineer's office	46	SF	6	\$97	
	Lavatory	Next to engineer's office	1	EA	6	\$320	
	Lighting - Wall Mounted	Next to engineer's office	1	EA	7	\$0	
	Partitions	Next to engineer's office	1	EA	6	\$297	
	Walls - Tile Ceramic/ Porcelain	Next to engineer's office	225	SF	6	\$508	
	Water Closet	Next to engineer's office	1	EA	6	\$336	
	Accessories	Principal's rest room	47	SF	6	\$434	
	Ceiling - Plaster/Drywall	Principal's rest room	47	SF	6	\$163	
	Doors - Wood Doors inclu hw	Principal's rest room	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Principal's rest room	47	SF	6	\$99	
	Lavatory	Principal's rest room	1	EA	6	\$320	
	Lighting - Lay-in	Principal's rest room	1	EA	7	\$0	
	Partitions	Principal's rest room	1	EA	6	\$297	
	Walls - Tile Ceramic/ Porcelain	Principal's rest room	275	SF	6	\$621	
	Water Closet	Principal's rest room	1	EA	6	\$336	
	Accessories	Room 112 Nurse area	25	SF	6	\$231	
	Ceiling - Plaster/Drywall	Room 112 Nurse area	25	SF	6	\$87	
	Doors - Wood Doors inclu hw	Room 112 Nurse area	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Room 112 Nurse area	25	SF	6	\$53	
	Lavatory	Room 112 Nurse area	1	EA	6	\$320	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Lay-in	Room 112 Nurse area	1	EA	6	\$119	
	Walls - Tile Ceramic/ Porcelain	Room 112 Nurse area	150	SF	6	\$339	
	Water Closet	Room 112 Nurse area	1	EA	6	\$336	
	Accessories	Toilet in ID Office	25	SF	6	\$231	
	Ceiling - Plaster/Drywall	Toilet in ID Office	25	SF	6	\$87	
	Doors - Wood Doors inclu hw	Toilet in ID Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Toilet in ID Office	25	SF	6	\$53	
	Lavatory	Toilet in ID Office	1	EA	6	\$320	
	Lighting - Lay-in	Toilet in ID Office	1	EA	6	\$119	
	Walls - Tile Ceramic/ Porcelain	Toilet in ID Office	150	SF	6	\$339	
	Water Closet	Toilet in ID Office	1	EA	6	\$336	
	Accessories	Unisex Staff toilet in Pool area	120	SF	6	\$1,107	
	Benches	Unisex Staff toilet in Pool area	4	LF	6	\$58	
	Ceiling - Plaster/Drywall	Unisex Staff toilet in Pool area	120	SF	6	\$415	
	Doors - Steel Doors incl hw	Unisex Staff toilet in Pool area	1	EA	6	\$301	
	Floor Drain	Unisex Staff toilet in Pool area	3	EA	6	\$3,177	
	Floor - Tile Ceramic/ Porcelain	Unisex Staff toilet in Pool area	120	SF	6	\$254	
	Hand Dryer	Unisex Staff toilet in Pool area	1	EA	6	\$230	
	Lavatory	Unisex Staff toilet in Pool area	1	EA	6	\$320	
	Lighting - Pendant/Surface	Unisex Staff toilet in Pool area	3	EA	7	\$0	
	Showers	Unisex Staff toilet in Pool area	1	EA	6	\$311	
	Walls - Tile Ceramic/ Porcelain	Unisex Staff toilet in Pool area	448	SF	6	\$1,012	
	Water Closet	Unisex Staff toilet in Pool area	1	EA	6	\$336	
	Accessories	Women's faculty restroom next to 116B	56	SF	6	\$517	
	Ceiling - Plaster/Drywall	Women's faculty restroom next to 116B	56	SF	6	\$194	
	Doors - Wood Doors inclu hw	Women's faculty restroom next to 116B	1	EA	6	\$301	
	Floor Drain	Women's faculty restroom next to 116B	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's faculty restroom next to 116B	56	SF	6	\$119	
	Lavatory	Women's faculty restroom next to 116B	1	EA	6	\$320	
	Lighting - Lay-in	Women's faculty restroom next to 116B	1	EA	7	\$0	
	Partitions	Women's faculty restroom next to 116B	1	EA	6	\$297	
	Walls - Tile Ceramic/ Porcelain	Women's faculty restroom next to 116B	240	SF	6	\$542	
	Water Closet	Women's faculty restroom next to 116B	2	EA	6	\$672	
	Accessories	Women's in Main Office	61	SF	6	\$563	
	Ceiling - Plaster/Drywall	Women's in Main Office	61	SF	6	\$211	
	Doors - Wood Doors inclu hw	Women's in Main Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Women's in Main Office	61	SF	6	\$129	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	Women's in Main Office	1	EA	6	\$320	
	Lighting - Pendant/Surface	Women's in Main Office	1	EA	7	\$0	
	Partitions	Women's in Main Office	1	EA	6	\$297	
	Walls - Tile Ceramic/ Porcelain	Women's in Main Office	306	SF	6	\$691	
	Walls - Tile Ceramic/ Porcelain	Women's in Main Office	4	SF	5	\$84	damaged
	Water Closet	Women's in Main Office	1	EA	6	\$336	
	Accessories	Women's north next to 107 Auditorium	265	SF	6	\$2,444	
	Ceiling - Plaster/Drywall	Women's north next to 107 Auditorium	265	SF	6	\$917	
	Floor Drain	Women's north next to 107 Auditorium	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's north next to 107 Auditorium	265	SF	6	\$561	
	Hand Dryer	Women's north next to 107 Auditorium	2	EA	6	\$460	
	Lavatory	Women's north next to 107 Auditorium	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	Women's north next to 107 Auditorium	5	EA	6	\$619	
	Partitions	Women's north next to 107 Auditorium	5	EA	5	\$3,754	Delaminated
	Walls - Structural Glazed Tile	Women's north next to 107 Auditorium	894	SF	6	\$2,813	
	Water Closet	Women's north next to 107 Auditorium	6	EA	6	\$2,016	
	Accessories	Women's restroom 2nd flr across from 214	114	SF	6	\$1,051	
	Ceiling - Plaster/Drywall	Women's restroom 2nd flr across from 214	114	SF	6	\$395	
	Doors - Wood Doors inclu hw	Women's restroom 2nd flr across from 214	1	EA	6	\$301	
	Floor Drain	Women's restroom 2nd flr across from 214	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's restroom 2nd flr across from 214	114	SF	6	\$241	
	Lavatory	Women's restroom 2nd flr across from 214	2	EA	6	\$639	
	Lighting - Lay-in	Women's restroom 2nd flr across from 214	2	EA	6	\$238	
	Partitions	Women's restroom 2nd flr across from 214	2	EA	6	\$594	
	Walls - Structural Glazed Tile	Women's restroom 2nd flr across from 214	425	SF	6	\$1,337	
	Water Closet	Women's restroom 2nd flr across from 214	2	EA	6	\$672	

Rooms (Other Than Classrooms) Subtotal: \$1,478,701

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	19,468	SF	6	\$58,462	
	Ceiling - Plaster/Drywall	1st Floor	2,563	SF	6	\$15,870	
	Drinking Fountains - Double Water Cooler	1st Floor	3	EA	6	\$1,131	
	Floor - Terrazzo	1st Floor	6,054	SF	6	\$50,818	
	Floor - Tile/Sheet	1st Floor	4	SF	5	\$23	damage tiles
	Floor - Tile/Sheet	1st Floor	19,468	SF	6	\$10,579	
	Lighting - Lay-in	1st Floor	112	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	10	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	4	EA	6	\$496	
	Student Lockers - One Tier	1st Floor	618	EA	6	\$57,372	
	Walls - Plaster/Drywall	1st Floor	39,088	SF	6	\$173,277	
	Ceiling - Lay-in	2nd Floor	18,468	SF	6	\$55,459	
	Drinking Fountains - Double Water Cooler	2nd Floor	4	EA	6	\$1,508	
	Floor - Tile/Sheet	2nd Floor	18,468	SF	6	\$10,036	
	Lighting - Lay-in	2nd Floor	79	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	720	EA	6	\$66,842	
	Walls - Plaster/Drywall	2nd Floor	33,089	SF	6	\$146,684	
	Walls - Tile Ceramic/ Porcelain	2nd Floor	220	SF	6	\$692	
	Ceiling - Lay-in	3rd Floor	18,468	SF	6	\$55,459	
	Drinking Fountains - Double Water Cooler	3rd Floor	4	EA	6	\$1,508	
	Floor - Tile/Sheet	3rd Floor	18,468	SF	6	\$10,036	
	Lighting - Lay-in	3rd Floor	79	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	740	EA	6	\$68,698	
	Walls - Plaster/Drywall	3rd Floor	33,089	SF	6	\$146,684	
	Walls - Tile Ceramic/ Porcelain	3rd Floor	220	SF	6	\$692	
Safety							
	Camera Viewing Station	1st Floor	3	EA	6	\$2,048	Security desk in main lobby, Principal Office & Engineers Office
	Metal Dedector	1st Floor	3	EA	6	\$2,642	
	Security Cameras	1st Floor / Entire Building	45	EA	6	\$8,732	
	Security Cameras	1st Floor / Entire Building	4	EA	6	\$776	
Stairs							
	Ceiling - Plaster/Drywall	#1	1,580	SF	6	\$11,568	
	Floor - Concrete	#1	680	SF	6	\$360	
	Handrails	#1	288	LF	6	\$2,496	
	Lighting - Pendent/Surface	#1	9	EA	7	\$0	
	Stairs - Concrete	#1	90	LF	6	\$746	
	Walls - Plaster/Drywall	#1	6,890	SF	6	\$19,016	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Ceiling - Plaster/Drywall	#2	890	SF	6	\$6,516	
	Floor - Concrete	#2	170	SF	6	\$90	
	Handrails	#2	196	LF	6	\$1,698	
	Lighting - Pendent/Surface	#2	3	EA	7	\$0	
	Stairs - Concrete	#2	72	LF	6	\$597	
	Walls - Plaster/Drywall	#2	2,410	SF	6	\$6,651	
	Ceiling - Plaster/Drywall	#3	890	SF	6	\$6,516	
	Floor - Concrete	#3	170	SF	6	\$90	
	Handrails	#3	196	LF	6	\$1,698	
	Lighting - Pendent/Surface	#3	3	EA	7	\$0	
	Stairs - Concrete	#3	72	LF	6	\$597	
	Walls - Plaster/Drywall	#3	2,410	SF	6	\$6,651	
	Ceiling - Plaster/Drywall	#4	1,290	SF	6	\$9,445	
	Floor - Concrete	#4	500	SF	6	\$265	
	Handrails	#4	196	LF	6	\$1,698	
	Lighting - Pendent/Surface	#4	9	EA	7	\$0	
	Stairs - Concrete	#4	120	LF	6	\$995	
	Walls - Plaster/Drywall	#4	3,260	SF	6	\$8,997	
	Ceiling - Plaster/Drywall	#8	1,580	SF	6	\$11,568	
	Floor - Concrete	#8	680	SF	6	\$360	
	Handrails	#8	288	LF	6	\$2,496	
	Lighting - Pendent/Surface	#8	8	EA	7	\$0	
	Stairs - Concrete	#8	90	LF	6	\$746	
	Walls - Plaster/Drywall	#8	6,890	SF	6	\$19,016	
Vertical Conveyance							
	Elevator - Hydraulic Elevator	1st Floor	1	EA	5	\$86,984	Stop occasional
	Elevator - Hydraulic Elevator	1st Floor	2	EA	6	\$38,476	NE corner of Auditorium, in the main lobby

Building Interior Subtotal: \$1,192,860

Total Building Cost \$9,524,814

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Wood Door	#5 W	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	#5.1 S	2	EA	6	\$961	
	Exterior Doors - Side lite	#5.1 S	4	EA	6	\$1,253	
	Exterior Doors - Transom Lite	#5.1 S	4	EA	6	\$1,253	
	Exterior Stairs - Concrete	#5 W	60	LF	5	\$6,575	Cracks
Foundation							
	Foundation - Concrete	Entire Building	466	LF	7	\$0	
	Superstructure - Concrete	Entire Building	23,690	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	5	EA	6	\$1,444	
Roof System							
	Coping - Stone	Main Roof	400	LF	5	\$43,804	Needs caulking
	Coping - Stone	South Low Roof	148	LF	5	\$16,207	Need caulking
	Downspouts - Interior Downspouts	Main Roof	140	LF	6	\$4,653	
	Downspouts - Interior Downspouts	South Low Roof	36	LF	6	\$1,196	
	Parapet - 16" - 30" Height	Main Roof	400	LF	6	\$15,982	
	Parapet - 16" - 30" Height	South Low Roof	148	LF	6	\$5,913	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main Roof	9,725	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	South Low Roof	2,321	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Main Roof	9,725	SF	5	\$229,600	Leaks, bubbles and worn
	Roof - Asphalt Gravel Ballast	South Low Roof	2,321	SF	5	\$54,797	Leaks, bubbles and worn
Walls							
	Cornice - Masonry Projecting Limestone	Entire Building / Roof	138	LF	6	\$4,785	
	Exterior Walls - Brick	Entire Building	2,550	SF	5	\$53,895	Need tuck pointing
	Exterior Walls - Brick	Entire Building	7,400	SF	6	\$49,735	
	Exterior Walls - Stone-Cast	Entire Building	500	SF	6	\$3,361	
	Exterior Walls - Stone-Cast	Entire Building	180	SF	5	\$2,873	Need tuck pointing
Windows							
	Guard - Guards perforated	Entire Building / 1st Floor	960	SF	6	\$12,259	
	Guard - Guards wire guard	Entire Building / 1st Floor	338	SF	6	\$4,316	
	Lintels - Steel	Entire Building	204	LF	6	\$5,922	
	Windows - Sash Aluminum Double-pane	Entire Building	860	SF	5	\$46,327	Balance issues
	Windows - Sash Aluminum Double-pane	Entire Building	860	SF	6	\$6,420	

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Building Exterior Subtotal:						\$574,493	

Building: Addition 1

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Corridors and Stairs	Entire Building	4,393	SF	6	\$1,319	
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	7,497	SF	6	\$2,787	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	5,101	SF	6	\$1,897	
	Emergency Battery Packs - Lunchrooms	1st Floor	2	EA	6	\$405	
	Exit Signs - Corridors and Stairs	Entire Building	12	EA	7	\$0	Building has AC generator.
	Exit Signs - Gym	Entire Building / 2nd Floor	5	EA	7	\$0	Building has AC generator.
	Exit Signs - Lunchroom	Entire Building / 1st Floor	6	EA	7	\$0	Building has AC generator.
	Security System - CCTV	Entire Building	23,690	SF	6	\$7,114	
	Security System - Intrusion Detection	Entire Building	23,690	SF	6	\$6,098	
Main Service							
	PA System	Entire Building	23,690	SF	6	\$7,792	Serves main and all additions. Control console located in main.
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Served from switchgear in addition 2.
Electrical System Subtotal:						\$27,412	

Building: Addition 1

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	23,690	SF	6	\$8,469	
	Fire Alarm_System	Entire Building	23,690	SF	6	\$11,518	
Safty System Subtotal:						\$19,987	

Building: Addition 1

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 15001-20000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves southwest addition.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	2nd Floor	1	EA	6	\$3,350	Serves gym - west, one of multiple gym ASUs.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	2nd Floor	1	EA	6	\$3,350	Serves gym - east, one of multiple gym AHUs.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves dance room.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves weight room.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - 4000-8000 cfm	2nd Floor	1	EA	6	\$3,350	Serves girl's gym.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves gym lockerr room , heating only.
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	2nd Floor / Roof	1	EA	7	\$0	
	Air Intake	2nd Floor / Roof	1	EA	7	\$0	
	Air Intake	2nd Floor / Roof	1	EA	7	\$0	
	Air Intake	2nd Floor / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	Mechanical Room	3	EA	6	\$5,571	
	Zone Dampers	Mechanical Room / Entire Building	12	EA	6	\$9,996	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building	4	EA	6	\$1,417	
	Fin Tube - Hot Water	Entire Building	400	LF	6	\$3,775	
	Unit Heater - Electric	Entire Building	2	EA	6	\$556	
Mechanical Plumbing							
	Hydronic Supply and Return - Copper	Entire Building	500	LF	6	\$26,233	
	Hydronic Supply and Return - Galvanized	Entire Building	500	LF	6	\$38,660	
Temperature Control							
	DDC System	Entire Building	23,690	SF	6	\$13,551	
	Electric Thermostat	Entire Building	2	EA	6	\$0	For unit heaters.
	Thermostats - DDC	Entire Building	12	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	4	EA	6	\$2,370	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	3	EA	6	\$1,777	
	Lab Exhaust Hood	Entire Building / 3rd Floor	2	EA	6	\$2,495	

Building: Addition 1

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Ventilation							
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	2	EA	6	\$2,495	Serving line, with sprinklers.
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	6	\$1,248	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	6	\$920	Dish washer room.

Mechanical System Subtotal:

\$134,515

Building: Addition 1

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Electric Heater - 20 - 50 KW	1st Floor	2	EA	6	\$1,364	Kitchen water heater boosters.
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	23,690	SF	6	\$4,743	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	23,690	SF	6	\$5,759	
	Domestic Piping-Cold Water Risers	Entire Building	23,690	SF	6	\$4,404	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	23,690	SF	6	\$3,726	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	23,690	SF	6	\$4,404	
	Domestic Piping-Hot Water Return Lines	Entire Building	23,690	SF	6	\$3,388	
	Domestic Piping-Hot Water Return Risers	Entire Building	23,690	SF	6	\$3,388	
	Sanitary Piping	Entire Building	23,690	SF	6	\$21,681	
	Storm Piping	Entire Building	23,690	SF	6	\$20,665	
	Vent Piping	Entire Building	23,690	SF	6	\$15,922	
Pumps							
	Pumps - Sump-Simplex	Basement	2	EA	6	\$1,490	

Plumbing System Subtotal:

\$90,934

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	141A Facility Dinning	528	SF	6	\$1,586	
	Ceiling - Lay-in	141A Facility Dinning	4	SF	5	\$32	Missing tile
	Doors - Wood Doors inclu hw	141A Facility Dinning	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	141A Facility Dinning	528	SF	6	\$1,117	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	141A Facility Dinning	12	EA	7	\$0	
	Power Distribution	141A Facility Dinning	8	EA	7	\$0	
	Walls - Plaster/Drywall	141A Facility Dinning	669	SF	6	\$1,846	
	Ceiling - Plaster/Drywall	141L Kitchen manager's office	79	SF	6	\$273	
	Doors - Wood Doors inclu hw	141L Kitchen manager's office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	141L Kitchen manager's office	79	SF	6	\$167	
	Lighting - Lay-in	141L Kitchen manager's office	2	EA	7	\$0	
	Power Distribution	141L Kitchen manager's office	4	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	141L Kitchen manager's office	215	SF	6	\$486	
Gymnasia							
	Bleacher Seating	250 Girls Practice Gymnasium	72	EA	6	\$2,084	
	Ceiling - Splined	250 Girls Practice Gymnasium	7,492	SF	6	\$6,107	
	Ceiling - Splined	250 Girls Practice Gymnasium	5	SF	5	\$48	Missing tiles
	Doors - Wood Doors inclu hw	250 Girls Practice Gymnasium	4	EA	6	\$1,204	
	Floor - Wood	250 Girls Practice Gymnasium	7,497	SF	6	\$52,853	
	Lighting - Pendent/Surface	250 Girls Practice Gymnasium	42	EA	6	\$5,204	
	Scoreboards	250 Girls Practice Gymnasium	1	EA	6	\$2,244	
	Walls - Plaster/Drywall	250 Girls Practice Gymnasium	7,940	SF	6	\$21,914	
Kitchen							
	Ceiling - Plaster/Drywall	141B Dish Wash	384	SF	6	\$1,329	
	Doors - Wood Doors inclu hw	141B Dish Wash	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	141B Dish Wash	384	SF	6	\$813	
	Lighting - Lay-in	141B Dish Wash	8	EA	6	\$952	
	Walls - Tile Ceramic/ Porcelain	141B Dish Wash	850	SF	6	\$1,920	
	Ceiling - Splined	141C Serving area & 141H Kitchen	3,181	SF	6	\$2,593	
	Doors - Wood Doors inclu hw	141C Serving area & 141H Kitchen	4	EA	6	\$1,204	
	Floor - Tile Quarry	141C Serving area & 141H Kitchen	3,181	SF	6	\$6,732	
	Lighting - Lay-in	141C Serving area & 141H Kitchen	43	EA	6	\$5,116	
	Serving Line	141C Serving area & 141H Kitchen	130	LF	6	\$7,737	
	Storage/ Closet	141C Serving area & 141H Kitchen	506	SF	6	\$3,669	141K Food Storage Room
	Walls - Plaster/Drywall	141C Serving area & 141H Kitchen	3,444	SF	6	\$9,505	
	Walls - Tile Ceramic/ Porcelain	141C Serving area & 141H Kitchen	1,519	SF	6	\$3,432	
Lunch & Multipurpose Room							
	Ceiling - Lay-in	141 Lunch Room	4,950	SF	6	\$14,865	
	Doors - Wood Doors inclu hw	141 Lunch Room	2	EA	6	\$602	
	Floor - Tile Ceramic/ Porcelain	141 Lunch Room	4,950	SF	6	\$10,476	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Lighting - Lay-in	141 Lunch Room	294	EA	6	\$34,979	
	Serving Line	141 Lunch Room	114	LF	6	\$6,785	
	Walls - Plaster/Drywall	141 Lunch Room	6,745	SF	6	\$18,616	
	Walls - Plaster/Drywall	141 Lunch Room	10	SF	5	\$51	peeling paint
	Ceiling - Plaster/Drywall	141D Snack bar/canteen	151	SF	6	\$523	
	Doors - Wood Doors inclu hw	141D Snack bar/canteen	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	141D Snack bar/canteen	151	SF	6	\$320	
	Lighting - Lay-in	141D Snack bar/canteen	2	EA	6	\$238	
	Walls - Tile Ceramic/ Porcelain	141D Snack bar/canteen	456	SF	6	\$1,030	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	78	SF	6	\$559	#141N
	Janitor's Closet	2nd Floor	67	SF	6	\$480	250A Janitor Closet
	Storage Room	3rd Floor	68	SF	6	\$487	Roof Truss Room
	Mechanical/ Service Rooms	Basement	1,494	SF	6	\$10,703	
	Storage Room	Basement	152	SF	6	\$1,089	
Restroom							
	Accessories	Men's Room off Kitchen	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	Men's Room off Kitchen	38	SF	6	\$132	
	Doors - Wood Doors inclu hw	Men's Room off Kitchen	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Men's Room off Kitchen	38	SF	6	\$80	
	Lavatory	Men's Room off Kitchen	1	EA	6	\$320	
	Lighting - Pendent/Surface	Men's Room off Kitchen	1	EA	6	\$124	
	Walls - Structural Glazed Tile	Men's Room off Kitchen	235	SF	6	\$739	
	Water Closet	Men's Room off Kitchen	1	EA	6	\$336	
	Accessories	Women's Locker Room off kitchen	239	SF	6	\$2,204	
	Ceiling - Lay-in	Women's Locker Room off kitchen	239	SF	6	\$718	
	Doors - Wood Doors inclu hw	Women's Locker Room off kitchen	1	EA	6	\$301	
	Floor Drain	Women's Locker Room off kitchen	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Locker Room off kitchen	239	SF	6	\$506	
	Lavatory	Women's Locker Room off kitchen	1	EA	6	\$320	
	Lighting - Lay-in	Women's Locker Room off kitchen	4	EA	6	\$476	
	Student Lockers - One Tier	Women's Locker Room off kitchen	23	EA	6	\$2,135	
	Walls - Tile Ceramic/ Porcelain	Women's Locker Room off kitchen	622	SF	6	\$1,405	
	Water Closet	Women's Locker Room off kitchen	1	EA	6	\$336	
	Accessories	Women's Room off Kitchen	239	SF	6	\$2,204	
	Ceiling - Lay-in	Women's Room off Kitchen	239	SF	6	\$718	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	Women's Room off Kitchen	1	EA	6	\$301	
	Floor Drain	Women's Room off Kitchen	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Room off Kitchen	239	SF	6	\$506	
	Lavatory	Women's Room off Kitchen	1	EA	6	\$320	
	Lighting - Lay-in	Women's Room off Kitchen	4	EA	6	\$476	
	Student Lockers - One Tier	Women's Room off Kitchen	23	EA	6	\$2,135	
	Walls - Structural Glazed Tile	Women's Room off Kitchen	622	SF	6	\$1,957	
	Water Closet	Women's Room off Kitchen	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$267,027

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	1,989	SF	6	\$5,973	Water stains
	Drinking Fountains - Double Water Cooler	1st Floor	1	EA	6	\$377	
	Floor - Tile/Sheet	1st Floor	1,989	SF	6	\$1,081	
	Lighting - Lay-in	1st Floor	10	EA	5	\$1,622	Missing lens
	Walls - Plaster/Drywall	1st Floor	2,358	SF	6	\$10,453	
	Ceiling - Lay-in	2nd Floor	942	SF	6	\$2,829	Loose and crack tiles
	Ceiling - Plaster/Drywall	2nd Floor	175	SF	6	\$1,084	
	Floor - Tile Quarry	2nd Floor	1,115	SF	6	\$3,109	
	Floor - Tile/Sheet	2nd Floor	2	SF	5	\$9	Missing tiles
	Lighting - Lay-in	2nd Floor	5	EA	6	\$595	
	Lighting - Pendent/Surface	2nd Floor	1	EA	6	\$124	Missing lens
	Walls - Plaster/Drywall	2nd Floor	1,676	SF	6	\$7,430	
	Ceiling - Plaster/Drywall	3rd Floor	1,117	SF	6	\$6,916	
	Floor - Tile/Sheet	3rd Floor	1,115	SF	6	\$606	
	Floor - Tile/Sheet	3rd Floor	2	SF	5	\$12	Missing/Damaged tiles
	Lighting - Pendent/Surface	3rd Floor	8	EA	6	\$991	Missing lens
	Walls - Plaster/Drywall	3rd Floor	1,676	SF	6	\$7,430	
Safety							
	Security Cameras	Entire Building	5	EA	6	\$970	
	Security Cameras	Entire Building	1	EA	6	\$194	

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Ceiling - Plaster/Drywall	#5	890	SF	6	\$6,516	
	Floor - Concrete	#5	170	SF	6	\$90	
	Handrails	#5	196	LF	6	\$1,698	
	Lighting - Pendent/Surface	#5	3	EA	7	\$0	
	Stairs - Concrete	#5	72	LF	6	\$597	
	Walls - Plaster/Drywall	#5	2,410	SF	6	\$6,651	

Building Interior Subtotal:

\$67,357

Total Building Cost

\$1,181,724

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Steel Door	#5.2 S	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#5.3 S	2	EA	6	\$961	
	Exterior Doors - Overhead Rolling/ Garage Door	#5.2 S	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	#5.3 S	1	EA	6	\$1,433	
Foundation							
	Foundation - Concrete	Entire Building	368	LF	7	\$0	
	Superstructure - Steel	Entire Building	22,050	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	South Façade	2	EA	6	\$577	
Roof System							
	Coping - Stone	Main Roof	75	LF	5	\$8,213	Need caulking
	Downspouts - Interior Downspouts	Main Roof	130	LF	5	\$28,770	
	Parapet - 16" - 30" Height	Main Roof	75	LF	6	\$2,997	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main Roof	8,050	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Main Roof	8,050	SF	4	\$225,625	Bubble, leaks and worn
Walls							
	Exterior Walls - Brick	Entire Building / South Façade	3,023	SF	6	\$20,318	
	Exterior Walls - Brick	Entire Building / South Façade	750	SF	5	\$15,852	Need tuck pointing

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Windows							
	Lintels - Steel	Entire Building / South Façade	30	LF	6	\$871	

Building Exterior Subtotal:

\$307,531

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	3	EA	6	\$1,224	Also serves other buildings.
	Emergency A/C Power - Corridors and Stairs	Entire Building	3,616	SF	6	\$1,086	
	Emergency A/C Power - Students Toilets	Entire Building	149	SF	6	\$55	
	Emergency Generator- Outdoor- Diesel - 101 - 150 KW	Site South	1	EA	7	\$0	Serves all 4 buildings.
	Exit Signs - Corridors and Stairs	Entire Building	5	EA	7	\$0	Building is served by AC generator.
	Security System - CCTV	Entire Building	22,050	SF	6	\$6,622	
	Security System - Intrusion Detection	Entire Building	22,050	SF	6	\$5,676	

Main Service

	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Secondary feed from ComEd.
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	1	EA	6	\$8,662	
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	1	EA	6	\$10,867	
	PA System	Entire Building	22,050	SF	6	\$7,252	Serves main and all additions. Control console located in the main building.

Power Distribution

	Lighting and Power Panels - 100 A	Entire Building	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building	1	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	Serve other buildings.
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	Serve other buildings.
	Main Distribution Panels - Less than 400 amp	Entire Building / Electrical Room	2	EA	7	\$0	

Electrical System Subtotal:

\$41,444

Building: Addition 2

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Mechanical Room	1	EA	6	\$6,406	Serves main and other two additions as well.
	Fire Alarm Strobe Lights	Mechanical Room / Entire Building	22,050	SF	4	\$29,955	no strobes, horn only
	Fire Alarm_System	Mechanical Room / Entire Building	22,050	SF	6	\$10,721	

Safty System Subtotal: \$47,081

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Chemical Pot Feeder	Mechanical Room	1	EA	6	\$725	
	Chiller-Water Cooled- Cetrifugal - 301-400 tons	Mechanical Room	2	EA	6	\$19,330	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	2	EA	6	\$6,667	2 serve evaporator units in room 142
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	2	EA	6	\$6,667	2 serve evaporator units in room 345
	Cooling Tower - Closed Cell	Mechanical Room / Roof	1	EA	6	\$4,969	Two-cell tower.
	Glycol Feed	Mechanical Room	1	EA	6	\$490	
	Pressure Fill System	Mechanical Room	1	EA	6	\$1,405	
Air Handling Systems							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	3rd Floor	1	EA	6	\$3,350	Serves lecture room for ROTC.
	Air Intake	3rd Floor / Roof	1	EA	7	\$0	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building	2	EA	6	\$709	
	Duct Heater - Hot Water	3rd Floor	2		6	\$965	Near ROTC room ducts. Reheat coils.
	Fin Tube - Hot Water	Entire Building	60	LF	6	\$566	
	Unit Heater - Hot Water	Basement	2	EA	6	\$558	
	Wall Heater - Electric	Entire Building	2	EA	6	\$278	
Mechanical Plumbing							
	Chilled Water Pump - Less than 10	2nd Floor	2	EA	6	\$2,222	Near air handlers.
	Condenser Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - Less than 10	2nd Floor	2	EA	6	\$2,222	Near air handlers.
	Hydronic Supply and Return	Entire Building	500	LF	6	\$0	
	Hydronic Supply and Return - Galvanized	Entire Building	600	LF	6	\$46,392	
Temperature Control							
	DDC System	Entire Building	22,050	SF	6	\$12,613	
	Electric Thermostat	Entire Building / 1st Floor	2	EA	6	\$0	Serve the unit heaters.
	Thermostats - DDC	Entire Building	5	EA	6	\$0	

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Ventilation							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / Electrical Room	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	2	EA	6	\$1,185	

Mechanical System Subtotal: \$114,392

Building: Addition 2

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	22,050	SF	6	\$4,414	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	22,050	SF	6	\$5,360	
	Domestic Piping-Cold Water Risers	Entire Building	22,050	SF	6	\$4,099	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	22,050	SF	6	\$3,468	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	22,050	SF	6	\$4,099	
	Domestic Piping-Hot Water Return Lines	Entire Building	22,050	SF	6	\$3,153	
	Domestic Piping-Hot Water Return Risers	Entire Building	22,050	SF	6	\$3,153	
	Sanitary Piping	Entire Building	22,050	SF	6	\$20,180	
	Storm Piping	Entire Building	22,050	SF	6	\$19,234	
	Vent Piping	Entire Building	22,050	SF	6	\$14,820	

Plumbing System Subtotal: \$81,982

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #341 (Other Instructional Use)							
	Ceiling - Lay-in	3rd Floor	5	SF	5	\$40	Damaged and missing tiles
	Ceiling - Lay-in	3rd Floor	3,160	SF	6	\$9,489	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	3,165	SF	6	\$3,168	
	Lighting - Lay-in	3rd Floor	24	EA	6	\$2,855	
	Storage/ Closet	3rd Floor	357	SF	6	\$2,588	341A Storage
	Walls - Concrete Block	3rd Floor	1,322	SF	6	\$3,875	
	Walls - Plaster/Drywall	3rd Floor	1,322	SF	6	\$3,649	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #342 (Other Instructional Use)							
	Ceiling - Splined	3rd Floor	2	SF	5	\$19	Missing and damaged tiles
	Ceiling - Splined	3rd Floor	1,434	SF	6	\$1,169	
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	3rd Floor	1,436	SF	5	\$2,464	Damaged
	Lighting - Pendent/Surface	3rd Floor	34	EA	6	\$4,212	Missing bulbs and lenses
	Storage/ Closet	3rd Floor	128	SF	6	\$928	Vault no combination
	Walls - Plaster/Drywall	3rd Floor	1,755	SF	6	\$4,844	

Classrooms Subtotal:

\$44,611

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Plaster/Drywall	248A P.E. office	389	SF	6	\$1,346	
	Doors - Side-lite	248A P.E. office	16	SF	6	\$267	
	Doors - Transom Window	248A P.E. office	1	SF	6	\$17	
	Floor - Tile/Sheet	248A P.E. office	389	SF	6	\$389	
	Lighting - Lay-in	248A P.E. office	4	EA	7	\$0	
	Power Distribution	248A P.E. office	6	EA	7	\$0	
	Storage/ Closet	248A P.E. office	49	SF	6	\$355	
	Walls - Plaster/Drywall	248A P.E. office	902	SF	6	\$2,489	
	Ceiling - Plaster/Drywall	249A P.E. office	389	SF	6	\$1,346	
	Doors - Side-lite	249A P.E. office	16	SF	6	\$267	
	Doors - Wood Doors inclu hw	249A P.E. office	1	EA	6	\$301	
	Floor - Tile/Sheet	249A P.E. office	389	SF	6	\$389	
	Lighting - Lay-in	249A P.E. office	4	EA	7	\$0	
	Power Distribution	249A P.E. office	6	EA	7	\$0	
	Storage/ Closet	249A P.E. office	46	SF	6	\$334	
	Walls - Plaster/Drywall	249A P.E. office	902	SF	6	\$2,489	
	Ceiling - Lay-in	JROTC Office in room 342	217	SF	6	\$652	Loose tiles
	Doors - Side-lite	JROTC Office in room 342	16	SF	6	\$267	
	Doors - Wood Doors inclu hw	JROTC Office in room 342	1	EA	6	\$301	
	Floor - Tile/Sheet	JROTC Office in room 342	217	SF	6	\$217	
	Lighting - Lay-in	JROTC Office in room 342	6	EA	7	\$0	
	Power Distribution	JROTC Office in room 342	6	EA	7	\$0	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Concrete Block	JROTC Office in room 342	505	SF	6	\$1,480	
Locker/Shower Room							
	Accessories	Men's locker room, 2nd floor	2,627	SF	6	\$10,293	
	Benches, ped mounted	Men's locker room, 2nd floor	160	LF	6	\$17,421	
	Ceiling - Plaster/ Drywall	Men's locker room, 2nd floor	2,627	SF	6	\$9,091	
	Doors - Wood Doors inclu hw	Men's locker room, 2nd floor	1	EA	6	\$301	
	Floor Drain	Men's locker room, 2nd floor	10	EA	6	\$10,592	
	Floor - Tile Ceramic/ Porcelain	Men's locker room, 2nd floor	2,627	SF	6	\$5,560	
	Lavatory	Men's locker room, 2nd floor	2	EA	6	\$639	
	Lighting - Pendent/Surface	Men's locker room, 2nd floor	65	EA	6	\$8,053	
	Showers	Men's locker room, 2nd floor	20	EA	6	\$6,228	
	Student Lockers - Two Tier	Men's locker room, 2nd floor	178	EA	6	\$8,262	
	Urinals	Men's locker room, 2nd floor	2	EA	6	\$672	
	Walls - Plaster/Drywall	Men's locker room, 2nd floor	2,956	SF	6	\$8,158	
	Walls - Tile Ceramic/ Porcelain	Men's locker room, 2nd floor	1,399	SF	6	\$3,161	
	Water Closet	Men's locker room, 2nd floor	1	EA	6	\$336	
	Accessories	Women's locker room 2nd floor	1,944	SF	6	\$7,617	
	Benches, ped mounted	Women's locker room 2nd floor	12	LF	6	\$1,307	
	Ceiling - Plaster/ Drywall	Women's locker room 2nd floor	2	SF	5	\$26	Water strains and damaged plaster
	Ceiling - Plaster/ Drywall	Women's locker room 2nd floor	1,942	SF	6	\$6,720	
	Doors - Wood Doors inclu hw	Women's locker room 2nd floor	1	EA	6	\$301	
	Floor Drain	Women's locker room 2nd floor	12	EA	6	\$12,710	
	Floor - Tile Ceramic/ Porcelain	Women's locker room 2nd floor	1,934	SF	6	\$4,093	
	Floor - Tile/Sheet	Women's locker room 2nd floor	10	SF	5	\$45	Missing and damaged tiles
	Hand Dryer	Women's locker room 2nd floor	5	EA	6	\$1,150	
	Lavatory	Women's locker room 2nd floor	3	EA	6	\$959	
	Lighting - Pendent/Surface	Women's locker room 2nd floor	80	EA	6	\$9,912	Missing lenses
	Partitions	Women's locker room 2nd floor	2	EA	6	\$594	
	Showers	Women's locker room 2nd floor	20	EA	6	\$6,228	
	Storage/ Closet	Women's locker room 2nd floor	45	SF	6	\$326	
	Walls - Concrete Block	Women's locker room 2nd floor	1,958	SF	6	\$5,740	
	Walls - Plaster/Drywall	Women's locker room 2nd floor	604	SF	6	\$1,667	
	Walls - Tile Ceramic/ Porcelain	Women's locker room 2nd floor	1,399	SF	6	\$3,161	
	Water Closet	Women's locker room 2nd floor	3	EA	6	\$1,008	
Mechanical/ Service Rooms							
	Boiler Room	1st Floor	2,531	SF	6	\$18,133	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	37	SF	6	\$265	
	Loading Docks	1st Floor	1,763	SF	6	\$12,631	Loading Docks
	Mechanical/ Service Rooms	1st Floor	13,634	SF	6	\$97,678	Electrical vault, Elec. clos, Chiller room, Incinator
	Storage Room	1st Floor	671	SF	6	\$4,807	
	Mechanical/ Service Rooms	Basement	720	SF	6	\$5,158	151 Abortion Room
Restroom							
	Benches	2nd Flr ADA unisex shower room next to Women	4	LF	5	\$137	
	Ceiling - Plaster/Drywall	2nd Flr ADA unisex shower room next to Women	149	SF	6	\$516	
	Doors - Wood Doors inclu hw	2nd Flr ADA unisex shower room next to Women	1	EA	6	\$301	
	Floor Drain	2nd Flr ADA unisex shower room next to Women	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Flr ADA unisex shower room next to Women	149	SF	6	\$315	
	Hand Dryer	2nd Flr ADA unisex shower room next to Women	1	EA	6	\$230	
	Lavatory	2nd Flr ADA unisex shower room next to Women	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd Flr ADA unisex shower room next to Women	3	EA	7	\$0	
	Showers	2nd Flr ADA unisex shower room next to Women	1	EA	6	\$311	
	Student Lockers - One Tier	2nd Flr ADA unisex shower room next to Women	4	EA	6	\$371	
	Walls - Tile Ceramic/ Porcelain	2nd Flr ADA unisex shower room next to Women	487	SF	6	\$1,100	
	Water Closet	2nd Flr ADA unisex shower room next to Women	1	EA	6	\$336	
	Accessories	Toilet in room 342	62	SF	6	\$572	
	Ceiling - Plaster/Drywall	Toilet in room 342	10	SF	5	\$92	Damaged
	Ceiling - Splined	Toilet in room 342	52	SF	6	\$42	
	Doors - Wood Doors inclu hw	Toilet in room 342	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Toilet in room 342	62	SF	6	\$131	
	Lavatory	Toilet in room 342	1	EA	6	\$320	
	Lighting - Lay-in	Toilet in room 342	1	EA	6	\$119	
	Partitions	Toilet in room 342	1	EA	6	\$297	
	Walls - Concrete Block	Toilet in room 342	234	SF	6	\$686	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Rooms (Other Than Classrooms) Subtotal:						\$311,469	

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	1,272	SF	6	\$3,820	water stains
	Floor - Concrete Epoxy/ Painted	1st Floor	175	SF	6	\$85	
	Floor - Tile/Sheet	1st Floor	1,270	SF	6	\$690	
	Floor - Tile/Sheet	1st Floor	2	SF	5	\$12	Damaged tiles
	Lighting - Lay-in	1st Floor	10	EA	6	\$1,190	
	Lighting - Pendent/Surface	1st Floor	3	EA	6	\$372	
	Walls - Masonry	1st Floor	641	SF	6	\$2,017	
	Walls - Plaster/Drywall	1st Floor	2,745	SF	6	\$12,169	
	Walls - Plaster/Drywall	1st Floor	5	SF	5	\$50	Damaged plaster
	Ceiling - Lay-in	2nd Floor	552	SF	6	\$1,658	
	Ceiling - Plaster/Drywall	2nd Floor	520	SF	6	\$3,220	
	Floor - Tile/Sheet	2nd Floor	1,070	SF	6	\$581	
	Lighting - Lay-in	2nd Floor	6	EA	6	\$714	
	Walls - Plaster/Drywall	2nd Floor	2,124	SF	6	\$9,416	
	Ceiling - Lay-in	3rd Floor	552	SF	6	\$1,658	dirt and loose tiles
	Ceiling - Plaster/Drywall	3rd Floor	520	SF	6	\$3,220	
	Floor - Tile/Sheet	3rd Floor	2	SF	5	\$12	Missing tiles
	Floor - Tile/Sheet	3rd Floor	1,070	SF	6	\$581	
	Lighting - Lay-in	3rd Floor	6	EA	6	\$714	
	Stairs - Concrete Stairs	3rd Floor	8	LF	6	\$66	
	Walls - Plaster/Drywall	3rd Floor	2,124	SF	6	\$9,416	
Safety							
	Security Cameras	Entire Building	1	EA	6	\$194	
	Security Cameras	Entire Building	2	EA	6	\$388	
Building Interior Subtotal:						\$52,240	

Total Building Cost

\$1,000,750

Building: Addition 3

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	#6 S	1	EA	6	\$702	
	Exterior Doors - Exterior Wood Door	#6 S	2	EA	5	\$2,683	
	Exterior Doors - Exterior Wood Door	#7 E	2	EA	6	\$961	
	Exterior Doors - Transom Lite	#7 E	6	EA	6	\$1,880	
	Power Door Operator and Controls	#6 S	1	EA	6	\$0	
	Ramp Handrail - Steel_Ramp Handrail	#6 S	36	LF	6	\$312	
	Ramps - Concrete	#6 S	18	LF	6	\$2,704	
Foundation							
	Foundation - Concrete	Entire Building	388	LF	7	\$0	
	Superstructure - Concrete	Entire Building	26,460	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	3	EA	6	\$1,610	
	Exterior Lighting - Wall Mounted	Entire Building	4	EA	6	\$1,155	
Roof System							
	Coping - Stone	Main Roof	355	LF	5	\$38,876	Need tuck pointing
	Downspouts - Interior Downspouts	Main Roof	140	LF	5	\$30,983	
	Parapet - 16" - 30" Height	Main Roof	355	LF	6	\$14,184	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main Roof	7,436	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Main Roof	7,436	SF	5	\$175,559	bubbles
Walls							
	Cornice - Masonry Projecting Limestone	Entire Building	136	LF	6	\$4,716	
	Exterior Walls - Brick	Entire Building	7,450	SF	6	\$50,071	
	Exterior Walls - Brick	Entire Building	2,500	SF	5	\$52,839	Need tuck pointing
	Exterior Walls - Stone-Cast	Entire Building	180	SF	5	\$2,873	Need tuck pointing
	Exterior Walls - Stone-Cast	Entire Building	500	SF	6	\$3,361	
Windows							
	Guard - Guards perforated	Entire Building	960	SF	6	\$12,259	
	Guard - Guards wire guard	Entire Building	338	SF	6	\$4,316	
	Lintels - Steel	Entire Building	204	LF	6	\$5,922	
	Windows - Sash Aluminum Double-pane	Entire Building	860	SF	5	\$46,327	Balance issues
	Windows - Sash Aluminum Double-pane	Entire Building	860	SF	6	\$6,420	

Building Exterior Subtotal:

\$460,710

Building: Addition 3

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Corridors and Stairs	Entire Building	4,212	SF	6	\$1,265	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	4	EA	6	\$810	
	Exit Signs - Corridors and Stairs	Entire Building	4	EA	7	\$0	Building is served by AC generator.
	Security System - CCTV	Entire Building	26,460	SF	6	\$7,946	
	Security System - Intrusion Detection	Entire Building	26,460	SF	6	\$6,811	
Main Service							
	PA System	Entire Building	26,460	SF	6	\$8,703	Serves the main and all additions. Control console located in the main building.
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	Fed from switchgear in Addition 2.
Electrical System Subtotal:						\$25,534	

Building: Addition 3

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	26,460	SF	4	\$35,946	no strobes, horns only
	Fire Alarm_System	Entire Building	26,460	SF	5	\$29,513	Fire alarm panel located in Addition 2.
Safty System Subtotal:						\$65,459	

Building: Addition 3

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 15001-20000 cfm	3rd Floor	1	EA	6	\$3,350	Serves Addition 3.
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water Coils - 6000-10000 cfm	Entire Building	1	EA	6	\$3,350	Serves southeast corner, 3rd floor, and ROTC lecture rooms.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - Less than 4000 cfm	1st Floor	1	EA	6	\$3,350	Serves wood shop.
	Air Intake	1st Floor / Roof	1	EA	7	\$0	
	Air Intake	3rd Floor / Roof	1	EA	7	\$0	
	Air Intake	Entire Building / Roof	1	EA	7	\$0	

Building: Addition 3

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	Entire Building / Mechanical Room	2	EA	6	\$3,714	
	Zone Dampers	3rd Floor / Entire Building	8	EA	6	\$6,664	
	Zone Dampers	Entire Building	4	EA	6	\$3,332	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	1st Floor	2	EA	6	\$709	
	Fin Tube - Hot Water	Entire Building	200	LF	6	\$1,888	
	Unit Heater - Hot Water	Entire Building	2	EA	6	\$558	
Mechanical Plumbing							
	Chilled Water Pump - 10 - 20 HP	2nd Floor	1	EA	6	\$1,242	Serves AHU-6.
	Hot Water Pump - Less than 10	2nd Floor / 3rd Floor	1	EA	6	\$1,111	Serves AHU-6.
	Hydronic Supply and Return - Copper	Entire Building	600	LF	6	\$31,480	
	Hydronic Supply and Return - Galvanized	Entire Building	500	LF	6	\$38,660	
Temperature Control							
	DDC System	Mechanical Room / Entire Building	26,460	SF	6	\$15,135	
	Electric Thermostat	Mechanical Room / Entire Building	2	EA	6	\$0	Serve the unit heaters.
	Thermostats - DDC	Mechanical Room / Entire Building	13	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	
	Lab Exhaust Hood	Entire Building / 3rd Floor	2	EA	6	\$2,495	
	Type I Exhaust Hood- Culinary Arts	Entire Building / 3rd Floor	1	EA	6	\$1,248	Presently not used.
Mechanical System Subtotal:						\$120,657	

Building: Addition 3

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	26,460	SF	6	\$5,297	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	26,460	SF	6	\$6,432	
	Domestic Piping-Cold Water Risers	Entire Building	26,460	SF	6	\$4,919	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	26,460	SF	6	\$4,162	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	26,460	SF	6	\$4,919	
	Domestic Piping-Hot Water Return Lines	Entire Building	26,460	SF	6	\$3,784	
	Domestic Piping-Hot Water Return Risers	Entire Building	26,460	SF	6	\$3,784	

Building: Addition 3

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Sanitary Piping	Entire Building	26,460	SF	6	\$24,216	
	Storm Piping	Entire Building	26,460	SF	6	\$23,081	
	Vent Piping	Entire Building	26,460	SF	6	\$17,784	
Pumps							
	Pumps - Sump-Simplex	Basement	2	EA	6	\$1,490	

Plumbing System Subtotal: \$99,868

Building: Addition 3

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #142 (Other Instructional Use)							
	Ceiling - Lay-in	1st Floor	1,064	SF	6	\$3,195	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,064	SF	6	\$2,328	
	Lighting - Lay-in	1st Floor	20	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Storage/ Closet	1st Floor	121	SF	6	\$877	
	Walls - Plaster/Drywall	1st Floor	1,487	SF	6	\$4,104	
Classroom #144 (Special Program)							
	Ceiling - Lay-in	1st Floor	2	SF	5	\$16	water damaged
	Ceiling - Lay-in	1st Floor	1,949	SF	6	\$5,853	
	Chalk Board	1st Floor	60	LF	4	\$5,508	
	Doors - Side-lite	1st Floor	9	SF	6	\$150	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	5	SF	5	\$29	damaged
	Floor - Tile	1st Floor	1,898	SF	6	\$4,153	
	Floor - Tile Ceramic/ Porcelain	1st Floor	48	SF	6	\$102	
	Lighting - Lay-in	1st Floor	37	EA	7	\$0	
	Lighting - Lay-in	1st Floor	6	EA	6	\$714	missing covers
	Marker Board	1st Floor	24	LF	7	\$0	
	Storage/ Closet	1st Floor	296	SF	6	\$2,146	
	Storage/ Closet	1st Floor	305	SF	5	\$4,920	water damaged ceiling (old dark room, according to floor plan)
	Walls - Plaster/Drywall	1st Floor	2,244	SF	6	\$6,193	

Building: Addition 3

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #144 (Special Program)							
	Walls - Tile Ceramic/ Porcelain	1st Floor	2	SF	5	\$42	damaged
	Walls - Tile Ceramic/ Porcelain	1st Floor	76	SF	6	\$172	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #145 (Store Room)							
	Casework	1st Floor	4	LF	6	\$101	
	Ceiling - Lay-in	1st Floor	1,839	SF	6	\$5,523	
	Ceiling - Lay-in	1st Floor	1	SF	5	\$8	water damaged
	Chalk Board	1st Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,840	SF	6	\$4,026	
	Lighting - Lay-in	1st Floor	52	EA	7	\$0	
	Storage/ Closet	1st Floor	48	SF	6	\$348	
	Walls - Plaster/Drywall	1st Floor	2,162	SF	6	\$5,967	
	Walls - Plaster/Drywall	1st Floor	30	SF	5	\$153	water damaged
	Work Sink	1st Floor	1	EA	6	\$379	Unsure of condition, sink was buried by stuff
Classroom #146 (Office)							
	Ceiling - Lay-in	1st Floor	1,409	SF	6	\$4,231	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,409	SF	6	\$3,083	
	Floor - Tile Ceramic/ Porcelain	1st Floor	48	SF	6	\$102	
	Lighting - Lay-in	1st Floor	34	EA	7	\$0	
	Marker Board	1st Floor	18	LF	7	\$0	
	Storage/ Closet	1st Floor	58	SF	6	\$421	
	Walls - Plaster/Drywall	1st Floor	1,497	SF	6	\$4,132	
	Walls - Tile Ceramic/ Porcelain	1st Floor	78	SF	6	\$176	
Classroom #245 (Science Lab Level 1)							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	1,016	SF	6	\$3,051	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,016	SF	6	\$1,017	
	Gas Line	2nd Floor	3	EA	6	\$1,527	
	Lighting - Lay-in	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	6	LF	7	\$0	

Building: Addition 3

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #245 (Science Lab Level 1)							
	Science Lab Elements	2nd Floor	12	SF	6	\$81	
	Walls - Plaster/Drywall	2nd Floor	1,408	SF	6	\$3,886	
	Work Sink	2nd Floor	4	EA	6	\$1,516	
Classroom #246 (Science Lab Level 1)							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	917	SF	6	\$2,754	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile	2nd Floor	917	SF	6	\$2,006	
	Fume Hood	2nd Floor	1	EA	6	\$816	
	Gas Line	2nd Floor	9	EA	6	\$4,582	
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	1	EA	6	\$119	missing cover
	Science Lab Elements	2nd Floor	66	SF	6	\$447	
	Walls - Plaster/Drywall	2nd Floor	1,320	SF	6	\$3,643	
	Work Sink	2nd Floor	8	EA	5	\$12,062	not in use- missing faucets
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classroom #343 (Science Lab Level 3)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	6	SF	5	\$48	water damaged
	Ceiling - Lay-in	3rd Floor	1,289	SF	6	\$3,871	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,295	SF	6	\$1,296	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	16	EA	6	\$8,146	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Science Lab Elements	3rd Floor	27	SF	6	\$183	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,559	SF	6	\$4,303	
	Work Sink	3rd Floor	9	EA	6	\$3,411	
Classroom #344 (Computer Lab)							
	Casework	3rd Floor	3	LF	6	\$76	

Building: Addition 3

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #344 (Computer Lab)							
	Ceiling - Lay-in	3rd Floor	1,046	SF	6	\$3,141	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	1,046	SF	6	\$2,289	
	Lighting - Lay-in	3rd Floor	20	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,412	SF	6	\$3,897	
	Wireless System	3rd Floor	1	EA	6	\$372	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #345 (Computer Lab)							
	AC Units	3rd Floor	2	EA	6	\$991	in wall
	Ceiling - Lay-in	3rd Floor	1,160	SF	6	\$3,483	
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	1,160	SF	7	\$0	
	Lighting - Lay-in	3rd Floor	20	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Storage/ Closet	3rd Floor	191	SF	6	\$1,385	storage/work room 345A
	Walls - Plaster/Drywall	3rd Floor	1,449	SF	6	\$3,999	
	Wireless System	3rd Floor	1	EA	6	\$372	
Classroom #346 (Vacant)							
	Casework	3rd Floor	13	LF	6	\$328	
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	water damaged
	Ceiling - Lay-in	3rd Floor	1,276	SF	6	\$3,832	
	Culinary Kitchen Equipment	3rd Floor	5	EA	5	\$145,056	Some equipment is missing
	Doors - Side-lite	3rd Floor	9	SF	6	\$150	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,284	SF	5	\$5,765	
	Lighting - Lay-in	3rd Floor	30	EA	6	\$3,569	no covers
	Storage/ Closet	3rd Floor	873	SF	6	\$6,329	Rm 346A & 346B
	Walls - Plaster/Drywall	3rd Floor	5	SF	5	\$26	water damaged
	Walls - Plaster/Drywall	3rd Floor	1,512	SF	6	\$4,173	some applied FRP
	Work Sink	3rd Floor	1	EA	6	\$379	

Classrooms Subtotal:

\$335,136

Building: Addition 3

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	Rm 142B- TV Broadcast Instructor Office	65	SF	6	\$195	
	Doors - Side-lite	Rm 142B- TV Broadcast Instructor Office	91	SF	6	\$1,521	
	Doors - Wood Doors inclu hw	Rm 142B- TV Broadcast Instructor Office	1	EA	6	\$301	
	Floor - Tile	Rm 142B- TV Broadcast Instructor Office	65	SF	6	\$142	
	Lighting - Lay-in	Rm 142B- TV Broadcast Instructor Office	1	EA	7	\$0	
	Power Distribution	Rm 142B- TV Broadcast Instructor Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 142B- TV Broadcast Instructor Office	209	SF	6	\$577	
	Ceiling - Lay-in	Rm 245B- Science Office	246	SF	6	\$739	
	Ceiling - Lay-in	Rm 245B- Science Office	4	SF	5	\$32	water damaged
	Doors - Side-lite	Rm 245B- Science Office	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	Rm 245B- Science Office	1	EA	6	\$301	
	Floor - Tile	Rm 245B- Science Office	250	SF	6	\$547	
	Lighting - Lay-in	Rm 245B- Science Office	4	EA	7	\$0	
	Power Distribution	Rm 245B- Science Office	10	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 245B- Science Office	15	SF	5	\$77	water damage
	Walls - Plaster/Drywall	Rm 245B- Science Office	647	SF	6	\$1,786	
	Ceiling - Lay-in	Rm 246C- Science Office	250	SF	6	\$751	
	Doors - Side-lite	Rm 246C- Science Office	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	Rm 246C- Science Office	1	EA	6	\$301	
	Floor - Tile	Rm 246C- Science Office	250	SF	6	\$547	
	Lighting - Lay-in	Rm 246C- Science Office	4	EA	7	\$0	
	Power Distribution	Rm 246C- Science Office	22	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 246C- Science Office	662	SF	6	\$1,827	
Locker/Shower Room							
	Accessories	Visiting Team Locker Rm 247	473	SF	6	\$1,853	
	Ceiling - Plaster/ Drywall	Visiting Team Locker Rm 247	473	SF	6	\$1,637	
	Doors - Wood Doors inclu hw	Visiting Team Locker Rm 247	1	EA	6	\$301	
	Floor Drain	Visiting Team Locker Rm 247	3	EA	6	\$3,177	
	Floor - Tile Ceramic/ Porcelain	Visiting Team Locker Rm 247	169	SF	6	\$358	
	Floor - Tile/Sheet	Visiting Team Locker Rm 247	304	SF	6	\$304	
	Lavatory	Visiting Team Locker Rm 247	1	EA	6	\$320	
	Lighting - Lay-in	Visiting Team Locker Rm 247	15	EA	7	\$0	

Building: Addition 3

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Partitions	Visiting Team Locker Rm 247	1	EA	6	\$297	
	Showers	Visiting Team Locker Rm 247	6	EA	6	\$1,868	
	Storage/ Closet	Visiting Team Locker Rm 247	225	SF	6	\$1,631	Equipment & Drying Rm
	Student Lockers - One Tier	Visiting Team Locker Rm 247	31	EA	6	\$2,878	
	Urinals	Visiting Team Locker Rm 247	1	EA	5	\$3,894	not working
	Walls - Plaster/Drywall	Visiting Team Locker Rm 247	803	SF	6	\$2,216	
	Walls - Tile Ceramic/ Porcelain	Visiting Team Locker Rm 247	672	SF	6	\$1,518	
	Water Closet	Visiting Team Locker Rm 247	1	EA	6	\$336	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	29	SF	6	\$208	
	Mechanical/ Service Rooms	1st Floor	28	SF	6	\$201	
	Janitor's Closet	2nd Floor	29	SF	6	\$208	
	Mechanical/ Service Rooms	2nd Floor	28	SF	6	\$201	Inside Team Locker Rm247
	Janitor's Closet	3rd Floor	29	SF	6	\$208	
	Mechanical/ Service Rooms	3rd Floor	28	SF	6	\$201	
	Interior Stairs	Basement	11	LF	6	\$99	Leading down to pipe chase
	Mechanical/ Service Rooms	Basement	1,140	SF	6	\$8,167	Pipe chase
	Storage Room	Basement	1,265	SF	6	\$9,063	
Prep Room							
	Ceiling - Lay-in	Rm 142A- TV Broadcast Rm	130	SF	6	\$390	
	Doors - Side-lite	Rm 142A- TV Broadcast Rm	61	SF	6	\$1,020	
	Doors - Wood Doors inclu hw	Rm 142A- TV Broadcast Rm	1	EA	6	\$301	
	Floor - Tile	Rm 142A- TV Broadcast Rm	130	SF	6	\$284	
	Lighting - Lay-in	Rm 142A- TV Broadcast Rm	2	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 142A- TV Broadcast Rm	297	SF	6	\$820	
	Casework	Rm 245A	25	LF	6	\$631	
	Ceiling - Lay-in	Rm 245A	446	SF	6	\$1,339	
	Doors - Side-lite	Rm 245A	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	Rm 245A	1	EA	6	\$301	
	Floor - Tile	Rm 245A	446	SF	6	\$976	
	Lighting - Lay-in	Rm 245A	6	EA	6	\$714	missing covers
	Walls - Plaster/Drywall	Rm 245A	924	SF	6	\$2,550	
	Walls - Plaster/Drywall	Rm 245A	5	SF	5	\$26	water damage
	Work Sink	Rm 245A	1	EA	6	\$379	
	Casework	Rm 246A	15	LF	6	\$379	
	Ceiling - Lay-in	Rm 246A	96	SF	6	\$288	

Building: Addition 3

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Prep Room							
	Doors - Wood Doors inclu hw	Rm 246A	1	EA	6	\$301	
	Floor - Tile	Rm 246A	96	SF	6	\$210	
	Lighting - Lay-in	Rm 246A	2	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 246A	409	SF	6	\$1,129	
	Work Sink	Rm 246A	1	EA	6	\$379	
	Casework	Rm 246B	20	LF	6	\$505	
	Ceiling - Lay-in	Rm 246B	159	SF	6	\$477	
	Doors - Wood Doors inclu hw	Rm 246B	1	EA	6	\$301	
	Floor - Tile	Rm 246B	159	SF	6	\$348	
	Lighting - Lay-in	Rm 246B	2	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 246B	535	SF	6	\$1,477	
	Work Sink	Rm 246B	1	EA	6	\$379	
	Casework	Rm 246D	25	LF	6	\$631	
	Ceiling - Lay-in	Rm 246D	446	SF	6	\$1,339	
	Doors - Side-lite	Rm 246D	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	Rm 246D	1	EA	6	\$301	
	Floor - Tile	Rm 246D	446	SF	6	\$976	
	Lighting - Lay-in	Rm 246D	6	EA	7	\$0	
	Walls - Plaster/Drywall	Rm 246D	30	SF	5	\$153	peeling & water damage
	Walls - Plaster/Drywall	Rm 246D	907	SF	6	\$2,503	
	Work Sink	Rm 246D	1	EA	6	\$379	
	Ceiling - Plaster/Drywall	Rm 247A- Team Training Rm (inside Locker Rm)	188	SF	6	\$651	
	Doors - Side-lite	Rm 247A- Team Training Rm (inside Locker Rm)	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	Rm 247A- Team Training Rm (inside Locker Rm)	1	EA	6	\$301	
	Floor - Tile	Rm 247A- Team Training Rm (inside Locker Rm)	188	SF	5	\$844	
	Lighting - Lay-in	Rm 247A- Team Training Rm (inside Locker Rm)	4	EA	7	\$0	
	Walls - Concrete Block	Rm 247A- Team Training Rm (inside Locker Rm)	294	SF	5	\$3,019	
	Walls - Plaster/Drywall	Rm 247A- Team Training Rm (inside Locker Rm)	294	SF	6	\$811	
Restroom							
	Accessories	2nd Flr Men's- Across from 245	121	SF	6	\$1,116	
	Ceiling - Plaster/Drywall	2nd Flr Men's- Across from 245	121	SF	6	\$419	
	Doors - Wood Doors inclu hw	2nd Flr Men's- Across from 245	2	EA	6	\$602	

Building: Addition 3

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	2nd Flr Men's- Across from 245	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Flr Men's- Across from 245	121	SF	6	\$256	
	Lavatory	2nd Flr Men's- Across from 245	2	EA	6	\$639	
	Lighting - Pendant/Surface	2nd Flr Men's- Across from 245	3	EA	7	\$0	
	Lighting - Wall Mounted	2nd Flr Men's- Across from 245	1	EA	7	\$0	
	Partitions	2nd Flr Men's- Across from 245	2	EA	6	\$594	
	Urinals	2nd Flr Men's- Across from 245	2	EA	6	\$672	
	Walls - Tile Ceramic/ Porcelain	2nd Flr Men's- Across from 245	210	SF	6	\$474	
	Water Closet	2nd Flr Men's- Across from 245	2	EA	6	\$672	
	Accessories	2nd Flr Women's- Across from 245	121	SF	6	\$1,116	
	Ceiling - Plaster/Drywall	2nd Flr Women's- Across from 245	121	SF	6	\$419	
	Doors - Wood Doors inclu hw	2nd Flr Women's- Across from 245	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd Flr Women's- Across from 245	121	SF	6	\$256	
	Lavatory	2nd Flr Women's- Across from 245	2	EA	6	\$639	
	Lighting - Pendant/Surface	2nd Flr Women's- Across from 245	3	EA	7	\$0	
	Lighting - Wall Mounted	2nd Flr Women's- Across from 245	1	EA	7	\$0	
	Partitions	2nd Flr Women's- Across from 245	3	EA	6	\$891	
	Walls - Tile Ceramic/ Porcelain	2nd Flr Women's- Across from 245	210	SF	6	\$474	
	Walls - Tile Ceramic/ Porcelain	2nd Flr Women's- Across from 245	10	SF	5	\$210	damaged
	Water Closet	2nd Flr Women's- Across from 245	3	EA	6	\$1,008	

Rooms (Other Than Classrooms) Subtotal:

\$92,223

Building: Addition 3

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	1,424	SF	5	\$9,387	water stains
	Doors	1st Floor	2	EA	6	\$0	
	Drinking Fountains - Double Water Cooler	1st Floor	1	EA	6	\$377	
	Floor - Tile/Sheet	1st Floor	4	SF	5	\$23	Damaged tiles
	Floor - Tile/Sheet	1st Floor	1,420	SF	6	\$772	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	2,936	SF	6	\$13,015	
	Ceiling - Lay-in	2nd Floor	1,224	SF	5	\$8,069	water stain and missing tile
	Drinking Fountains - Double Water Cooler	2nd Floor	1	EA	6	\$377	
	Floor - Tile/Sheet	2nd Floor	1,224	SF	6	\$665	

Building: Addition 3

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Lighting - Lay-in	2nd Floor	10	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	28	EA	6	\$2,599	
	Walls - Plaster/Drywall	2nd Floor	2,606	SF	6	\$11,552	
	Ceiling - Lay-in	3rd Floor	1,224	SF	6	\$3,676	Loose tiles
	Drinking Fountains - Double Water Cooler	3rd Floor	1	EA	6	\$377	
	Floor - Tile/Sheet	3rd Floor	1,224	SF	6	\$665	
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	24	EA	6	\$2,228	
	Walls - Plaster/Drywall	3rd Floor	2,606	SF	6	\$11,552	
Safety							
	Security Cameras	Entire Building	3	EA	6	\$582	
	Security Cameras	Entire Building	2	EA	6	\$388	
Stairs							
	Ceiling - Plaster/Drywall	#6	890	SF	6	\$6,516	
	Floor - Concrete	#6	170	SF	6	\$90	
	Handrails	#6	140	LF	6	\$1,213	
	Lighting - Pendent/Surface	#6	1	EA	7	\$0	
	Stairs - Concrete	#6	72	LF	6	\$597	
	Walls - Plaster/Drywall	#6	2,410	SF	6	\$6,651	
	Ceiling - Plaster/Drywall	#7	890	SF	6	\$6,516	
	Floor - Concrete	#7	170	SF	6	\$90	
	Handrails	#7	196	LF	6	\$1,698	
	Lighting - Pendent/Surface	#7	3	EA	7	\$0	
	Stairs - Concrete	#7	72	LF	6	\$597	
	Walls - Plaster/Drywall	#7	2,410	SF	6	\$6,651	
Building Interior Subtotal:						\$96,927	

Total Building Cost

\$1,296,514

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	5	EA	6	\$5,469	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Site Manhole	Entire Site	5	EA	6	\$7,464	
Fencing							
	Fencing - New Standard Ornamental	Entire Site	1,813	LF	6	\$57,841	
Landscape							
	Benches	Entire Site / Site South	13	EA	6	\$5,591	
	Landscape - Grass	Entire Site	16,176	SF	6	\$13,416	
	Landscape - Hardscape- Concrete	Entire Site / Main Entrance	1,829	SF	6	\$9,442	
	Parkway trees	Entire Site	151	EA	6	\$99,667	
	Planting Beds/ Area	Entire Site	3,480	SF	6	\$7,664	Planters next to building
	Planting Beds/ Area	Entire Site / South Courtyard	34,275	SF	6	\$56,365	
	Retaining Wall - Concrete	Entire Site	3,120	SF	6	\$73,126	
	Trash Receptacles	Entire Site	4	EA	6	\$1,249	
Parking Lot							
	Concrete Curbs	South Courtyard	492	LF	6	\$6,318	
	Interior Plantings	South Courtyard	300	LF	6	\$12,763	
	Surface - Asphalt	South Courtyard	53,950	SF	4	\$425,860	Pot holes and cracking
	Trash Compactor	South Courtyard	1	EA	6	\$0	
	Trash Enclosure - Chain Links	South Courtyard	368	SF	6	\$6,457	
	Vehicular Screening	South Courtyard	170	LF	6	\$13,385	
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	198	LF	6	\$2,378	
	Sidewalks - Perimeter Sidewalks	Entire Site	30,858	SF	6	\$61,336	
Signage							
	Flag Pole - Flag Pole	East Courtyard / Main Entrance	1	EA	7	\$0	
	Marquee - Free Standing Back Lighted	East Courtyard / East	1	EA	6	\$0	
	Marquee - Free Standing Back lighted w/ LED	East Courtyard / South East	1	EA	6	\$0	
Site Subtotal:						\$865,790	
Total Site Cost						\$865,790	
Campus Total ^{2 3}						\$13,869,592	

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
 - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Art Room	4th Floor	402	402	1,074	1	2	16	112	28	40	N	N	N
Art Room	Art Room	4th Floor	406	406	1,350	0	0	16	141	36	40	N	N	N
Art Room	Art Room	4th Floor	407	407	1,150	0	0	16	141	36	40	N	N	N
Computer Lab	Regular Classroom	1st Floor	117	117	1,549	1	36	50	140	28	50	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	214	214	673	1	15	34	140	60	40	N	N	N
Computer Lab	Other Instructional Use	2nd Floor	231	231	2,128	1	50	58	0	0	50	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	314	314	673	1	34	78	140	60	40	N	N	N
Dance Room	Dance Room	2nd Floor	241	241	1,171	0	0	2	0	0	40	N	N	N
Music Room	Music Room	1st Floor	133	Band Room	1,258	1	10	54	0	0	0	N	Y	N
Music Room	Music Room	1st Floor	134	Orchestra Rm	1,258	1	4	32	0	0	40	N	N	N
Music Room	Music Room	1st Floor	135	Choral Room W	1,258	1	10	54	0	0	0	N	Y	N
Office	Regular Classroom	1st Floor	126	126	975	1	9	24	150	60	40	N	Y	N
Office	Regular Classroom	3rd Floor	303	303	700	1	12	26	0	0	40	N	N	N
Office	Regular Classroom	3rd Floor	339	339	926	926	1	6	26	0	40	N	Y	N
Other Instructional Use	Other Instructional Use	1st Floor	131	131	961	2	2	20	0	0	40	N	Y	N
Other Instructional Use	Other Instructional Use	2nd Floor	208	208	2,160	0	0	16	216	15	40	N	Y	N
Other Instructional Use	Other Instructional Use	2nd Floor	210	210	2,100	1	4	14	0	0	50	N	Y	N
Physical Education Room	Physical Education Roo	2nd Floor	242	242	864	0	0	2	0	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	119	119	887	1	13	34	175	35	50	N	N	N
Regular Classroom	Regular Classroom	1st Floor	121	121	950	1	8	26	175	35	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	123	123	950	1	8	26	175	35	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	125	125	950	1	8	26	175	35	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	128	128	778	1	9	24	180	72	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	129	129	485	1	2	24	90	36	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	132	132	778	0	0	8	180	72	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	136	136	975	1	18	34	240	96	40	N	Y	N
Regular Classroom	Music Room	1st Floor	137	Choral Room E	1,258	1	14	30	0	0	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	138	138	778	1	18	34	180	72	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	140	140	778	1	9	24	120	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	605	0	0	8	140	60	40	N	Y	N
Regular Classroom	Other Instructional Use	2nd Floor	226	226	1,473	1	9	24	280	120	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	228	228	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	229	229	778	1	18	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	230	230	778	1	18	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	232	232	778	1	18	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	234	234	778	1	18	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	236	236	778	1	18	34	141	36	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	2nd Floor	238	238	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	240	240	778	1	9	24	188	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	780	1	11	36	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	302	302	605	1	9	24	140	60	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	305	305	700	1	12	26	84	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	307	307	700	1	12	26	112	48	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	308	308	1,185	1	2	10	100	20	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	309	309	760	1	10	28	168	72	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	311	311	760	1	10	28	168	72	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	315	315	863	1	15	34	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	323	323	653	1	14	34	0	0	50	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	327	327	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	328	328	778	1	17	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	329	329	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	330	330	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	332	332	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	333	333	835	1	2	6	196	84	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	334	334	778	1	9	24	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	335	335	926	926	15	30	26	0	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	336	336	778	1	15	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	337	337	926	926	12	24	26	0	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	338	338	778	1	15	34	141	36	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	340	340	778	1	15	34	94	24	40	N	N	N
Science Lab Level 3	Science Lab Level 3	2nd Floor	200	200	1,000	1	2	16	112	48	40	N	Y	N
Science Lab Level 3	Science Lab Level 3	2nd Floor	204	204	1,000	1	2	16	224	96	40	N	Y	N
Science Lab Level 3	Science Lab Level 3	2nd Floor	212	212	1,000	1	2	16	224	96	40	N	Y	N
Science Lab Level 3	Science Lab Level 3	2nd Floor	216	216	1,000	1	2	16	140	60	40	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	300	300	979	1	9	24	140	60	40	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	304	304	1,120	1	9	24	224	96	40	N	N	N
Special Program	Regular Classroom	3rd Floor	326	326	778	1	9	24	94	24	40	N	N	N
Store Room	Science Lab Level 1	3rd Floor	312	312	1,130	1	40	80	186	84	40	N	N	N
Store Room	Science Lab Level 1	3rd Floor	316	316	1,130	1	9	24	186	84	40	N	N	N
Store Room	Regular Classroom	3rd Floor	331A	331	598	1	6	20	196	84	40	N	N	N
Store Room	Art Room	4th Floor	401	401	1,074	1	2	28	112	28	40	N	N	N
Vacant	Regular Classroom	1st Floor	130	130	778	1	9	24	180	72	40	N	Y	N
Vacant	Laboratory/Shop	4th Floor	403	403	863	1	1	10	0	0	40	N	N	N
Vacant	Laboratory/Shop	4th Floor	405	405	782	1	2	16	0	0	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Weight	Weight	2nd Floor	244	244	2,564	0	0	4	0	0	40	N	N	N
Addition 2														
Other Instructional Use	Regular Classroom	3rd Floor	341	341	3,165	1	5	20	0	0	50	N	Y	N
Other Instructional Use	Regular Classroom	3rd Floor	342	342	1,436	1	3	6	0	0	40	N	Y	N
Addition 3														
Computer Lab	Computer Lab	3rd Floor	344	344	1,046	1	8	16	18	9	40	N	N	N
Computer Lab	Computer Lab	3rd Floor	345	345	1,160	1	50	100	120	60	40	N	N	N
Office	Other Instructional Use	1st Floor	146	146	1,409	1	8	22	180	72	40	N	N	N
Other Instructional Use	Other Instructional Use	1st Floor	142	142	1,064	1	48	78	0	0	40	N	N	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	245	245	1,016	1	2	20	0	0	40	N	N	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	246	246	917	1	2	20	0	0	40	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	343	343	1,295	1	8	42	27	0	40	N	N	N
Special Program	Other Instructional Use	1st Floor	144	Graphics St Rm	1,951	1	2	26	0	0	40	N	N	N
Store Room	Laboratory/Shop	1st Floor	145	145	1,840	1	2	24	210	84	40	N	N	N
Vacant	Culinary	3rd Floor	346	346	1,284	1	2	20	280	120	40	N	N	N