

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

| Campus Summary      |                  |                  |                       |                     |
|---------------------|------------------|------------------|-----------------------|---------------------|
| Building Name       | Year Constructed | Number of Floors | Building Area (Sq Ft) | Assessed Need       |
| Main                | 1928             | 3                | 224,663               | \$9,716,899         |
| Addition            | 2001             | 3                | 73,769                | \$2,106,102         |
| SITE                |                  |                  |                       | \$642,760           |
| <b>Campus Total</b> |                  |                  | <b>298,432</b>        | <b>\$12,465,760</b> |

### Building: Main

#### Category: Building Exterior

| Group           | Item - Type                                    | Location                      | Quantity | Unit | Rank | Cost    | Comments  |
|-----------------|--|-------------------------------|----------|------|------|---------|---|
| <b>Entrance</b> |  |                               |          |      |      |         |   |
|                 | Entrance Control - Audio and Video             | Entrance 7-West               | 1        | EA   | 6    | \$702   |   |
|                 | Exterior Doors - Exterior FRP Door             | 2-NE - Assembly Hall          | 4        | EA   | 6    | \$2,526 |   |
|                 | Exterior Doors - Exterior FRP Door             | Entrance 3-NE                 | 2        | EA   | 6    | \$1,263 |   |
|                 | Exterior Doors - Exterior FRP Door             | Entrance 4-East Main          | 2        | EA   | 6    | \$1,263 |   |
|                 | Exterior Doors - Exterior FRP Door             | Entrance 5-SE                 | 2        | EA   | 6    | \$1,263 |   |
|                 | Exterior Doors - Exterior FRP Door             | Entrance 7-West               | 4        | EA   | 6    | \$2,526 |   |
|                 | Exterior Doors - Exterior FRP Door             | Entrance 8-NW                 | 2        | EA   | 6    | \$1,263 |   |
|                 | Exterior Doors - Exterior FRP Door             | Exit 1B-North - Assembly Hall | 2        | EA   | 6    | \$1,263 |   |
|                 | Exterior Doors - Exterior FRP Door             | Exit 6-SW                     | 2        | EA   | 6    | \$1,263 |   |
|                 | Exterior Doors - Exterior Steel Door           | Entrance 9-NW - Boiler Room   | 1        | EA   | 6    | \$481   |   |
|                 | Exterior Doors - Exterior Steel Door           | Exit 6A-SW                    | 2        | EA   | 4    | \$7,645 | Majority of door cracked, peeling, not working properly |
|                 | Exterior Doors - Overhead Rolling/ Garage Door | Entrance 9A-NW                | 1        | EA   | 6    | \$1,433 |   |
|                 | Exterior Doors - Overhead Rolling/ Garage Door | Entrance 9B-NW                | 1        | EA   | 6    | \$1,433 |   |
|                 | Exterior Doors - Overhead Rolling/ Garage Door | Entrance 9C-NW                | 1        | EA   | 6    | \$1,433 |   |
|                 | Exterior Doors - Transom Lite                  | 2-NE - Assembly Hall          | 2        | EA   | 6    | \$627   |   |
|                 | Exterior Doors - Transom Lite                  | Entrance 3-NE                 | 1        | EA   | 6    | \$313   |   |
|                 | Exterior Doors - Transom Lite                  | Entrance 4-East Main          | 2        | EA   | 6    | \$627   |   |
|                 | Exterior Doors - Transom Lite                  | Entrance 5-SE                 | 1        | EA   | 6    | \$313   |   |
|                 | Exterior Doors - Transom Lite                  | Entrance 7-West               | 4        | EA   | 6    | \$1,253 |   |

**Building: Main**
**Category: Building Exterior**

| Group             | Item - Type                                 | Location                      | Quantity | Unit | Rank | Cost     | Comments   |
|-------------------|---|-------------------------------|----------|------|------|----------|--|
| <b>Entrance</b>   |   |                               |          |      |      |          |  |
|                   | Exterior Doors - Transom Lite               | Entrance 8-NW                 | 2        | EA   | 6    | \$627    |  |
|                   | Exterior Doors - Transom Lite               | Entrance 9-NW - Boiler Room   | 1        | EA   | 6    | \$313    |  |
|                   | Exterior Stairs - Concrete                  | 2-NE - Assembly Hall          | 168      | LF   | 6    | \$13,737 |  |
|                   | Exterior Stairs - Concrete                  | 2-NE - Assembly Hall          | 12       | LF   | 6    | \$981    | Step at door uneven, spalling with divots throughout |
|                   | Exterior Stairs - Concrete                  | Entrance 3-NE                 | 170      | LF   | 6    | \$13,900 |  |
|                   | Exterior Stairs - Concrete                  | Entrance 4-East Main          | 135      | LF   | 6    | \$11,039 |  |
|                   | Exterior Stairs - Concrete                  | Entrance 4-East Main          | 10       | LF   | 5    | \$1,096  | spalling   |
|                   | Exterior Stairs - Concrete                  | Entrance 5-SE                 | 180      | LF   | 6    | \$14,718 |  |
|                   | Exterior Stairs - Concrete                  | Entrance 7-West               | 155      | LF   | 6    | \$12,674 |  |
|                   | Exterior Stairs - Concrete                  | Entrance 8-NW                 | 77       | LF   | 6    | \$6,296  |  |
|                   | Exterior Stairs - Concrete                  | Entrance 8-NW                 | 3        | LF   | 5    | \$329    | Area cracked, uneven with holes                      |
|                   | Exterior Stairs - Concrete                  | Exit 1B-North - Assembly Hall | 5        | LF   | 5    | \$548    | Area cracked, uneven surface at old patch            |
|                   | Exterior Stairs - Concrete                  | Exit 1B-North - Assembly Hall | 10       | LF   | 6    | \$818    |  |
|                   | Exterior Stairs - Concrete                  | Exit 6A-SW                    | 6        | LF   | 6    | \$491    |  |
|                   | Exterior Stairs - Concrete                  | Exit 6-SW                     | 190      | LF   | 6    | \$15,536 |  |
|                   | Exterior Stairs - Concrete                  | Exit 6-SW                     | 10       | LF   | 5    | \$1,096  | Cracked with gaps throughout                         |
|                   | Power Door Operator and Controls            | Entrance 5-SE                 | 1        | EA   | 6    | \$0      |  |
|                   | Power Door Operator and Controls            | Entrance 7-West               | 1        | EA   | 6    | \$0      |  |
|                   | Ramp Handrail - Steel_Ramp Handrail         | Entrance 5-SE                 | 135      | LF   | 6    | \$1,170  |  |
|                   | Ramp Handrail - Steel_Ramp Handrail         | Entrance 7-West               | 145      | LF   | 6    | \$1,257  |  |
|                   | Ramps - Concrete                            | Entrance 5-SE                 | 60       | LF   | 6    | \$9,014  |  |
|                   | Ramps - Concrete                            | Entrance 5-SE                 | 10       | LF   | 5    | \$5,316  | Area spalling  |
|                   | Ramps - Concrete                            | Entrance 7-West               | 75       | LF   | 6    | \$11,268 |  |
|                   | Stair Handrail - Steel_Stair Handrail       | 2-NE - Assembly Hall          | 12       | LF   | 6    | \$104    | Rusted, peeling throughout                           |
|                   | Stair Handrail - Steel_Stair Handrail       | Entrance 4-East Main          | 26       | LF   | 5    | \$299    | Rusted and peeling throughout                        |
|                   | Stair Handrail - Steel_Stair Handrail       | Entrance 5-SE                 | 50       | LF   | 6    | \$433    |  |
|                   | Stair Handrail - Steel_Stair Handrail       | Entrance 7-West               | 40       | LF   | 6    | \$347    |  |
| <b>Foundation</b> |   |                               |          |      |      |          |  |
|                   | Foundation - Masonry                        | Entire Building               | 1,630    | LF   | 7    | \$0      |  |
|                   | Foundation - Masonry                        | Entire Building               | 10       | LF   | 5    | \$3,335  | Seepage, cracking                                    |
|                   | Superstructure - Concrete                   | Entire Building               | 224,665  | SF   | 7    | \$0      |  |
| <b>Lighting</b>   |   |                               |          |      |      |          |  |
|                   | Exterior Lighting - Parapet or Roof Mounted | Entire Building               | 1        | EA   | 5    | \$2,180  | Not working properly, cover cracked                  |
|                   | Exterior Lighting - Parapet or Roof Mounted | Entire Building               | 26       | EA   | 6    | \$13,950 |  |
|                   | Exterior Lighting - Wall Mounted            | Entire Building               | 13       | EA   | 6    | \$3,754  |  |

**Building: Main**
**Category: Building Exterior**

| Group              | Item - Type                                     | Location                    | Quantity | Unit | Rank | Cost      | Comments  |
|--------------------|---|-----------------------------|----------|------|------|-----------|---|
| <b>Roof System</b> |   |                             |          |      |      |           |   |
|                    | Chimney - Brick Chimney- Concrete/ Mortar Liner | Roof 1                      | 122      | LF   | 6    | \$116,471 |   |
|                    | Chimney - Brick Chimney- Concrete/ Mortar Liner | Roof 1                      | 5        | LF   | 5    | \$14,258  | Several areas at steel ladder penetrations cracked with loose and missing mortar joints   |
|                    | Coping - Stone                                  | Roof 1                      | 1,740    | LF   | 6    | \$55,885  |   |
|                    | Coping - Terra Cotta                            | Roof 1                      | 80       | LF   | 6    | \$2,569   |   |
|                    | Downspouts - Exterior Downspouts                | Roof 1                      | 30       | LF   | 6    | \$997     |   |
|                    | Downspouts - Interior Downspouts                | Roof 1                      | 980      | LF   | 6    | \$32,569  |   |
|                    | Parapet - 16" - 30" Height                      | Roof 1                      | 240      | LF   | 6    | \$9,589   |   |
|                    | Parapet - Parapet < 16" Height                  | Roof 1                      | 1,400    | LF   | 6    | \$29,830  |   |
|                    | Parapet - Parapet > 30"                         | Roof 1                      | 170      | LF   | 6    | \$10,867  |   |
|                    | Parapet - Parapet > 30"                         | Roof 1                      | 10       | LF   | 5    | \$3,797   | Several areas with loose and missing mortar joints  |
|                    | Roof Structure - Steel with Clay Tile Arch      | Roof 1                      | 60,314   | SF   | 7    | \$0       |   |
|                    | Roof - Metal                                    | Roof 1                      | 390      | SF   | 5    | \$10,747  | Worn out, area damage around roof drain   |
|                    | Roof - Modified Bitumen                         | Roof 1                      | 57,924   | SF   | 6    | \$545,030 |   |
|                    | Roof - Modified Bitumen                         | Roof 1                      | 2,000    | SF   | 4    | \$102,874 | Several areas bubbling, blistering, cracking with open seams throughout   |
| <b>Walls</b>       |   |                             |          |      |      |           |   |
|                    | Cheek-Wall - Concrete                           | Entire Building             | 660      | SF   | 6    | \$6,767   |   |
|                    | Cheek-Wall - Concrete                           | Entire Building             | 40       | SF   | 5    | \$943     | Entrance 8 - Cracked with loose and missing mortar joints adjacent to stairs / Exit 6 - Loose and missing mortar joints adjacent to stairs / Entrances 2, 3 - Areas cracked, chipped with loose and missing mortar joints |
|                    | Cheek-Wall - Stone                              | Entire Building             | 65       | SF   | 6    | \$666     | Entrance 7 - Vertical crack in between ramp and steps with loose and missing mortar joints, efflorescence present throughout / Entrance 4 - Loose and missing bricks and mortar joints adjacent to steps                  |
|                    | Cheek-Wall - Stone                              | Entire Building             | 680      | SF   | 6    | \$6,972   | At entrance 5, 7 ramps / Entrance 4 steps   |
|                    | Cornice - Terra Cotta                           | Entire Building             | 340      | LF   | 6    | \$11,790  |   |
|                    | Exterior Walls - Brick                          | Entire Building             | 52,530   | SF   | 6    | \$353,054 |   |
|                    | Exterior Walls - Stone-Cast                     | Entire Building             | 5        | SF   | 6    | \$34      |   |
|                    | Exterior Walls - Terra Cotta                    | Entire Building             | 5,935    | SF   | 6    | \$39,889  |   |
| <b>Windows</b>     |   |                             |          |      |      |           |   |
|                    | Clerestory - Glass Double-Pane                  | Entire Building             | 3,315    | SF   | 6    | \$31,050  |   |
|                    | Guard - Guards perforated                       | Entire Building / 1st Floor | 8,950    | SF   | 7    | \$0       |   |
|                    | Guard - Guards wire guard                       | Entire Building             | 1,600    | SF   | 6    | \$20,432  | Inside of windows   |
|                    | Lintels - Steel                                 | Entire Building             | 2,295    | LF   | 7    | \$0       |   |
|                    | Lintels - Terra Cotta                           | Entire Building             | 275      | LF   | 6    | \$0       |   |

**Building: Main**
**Category: Building Exterior**

| Group          | Item - Type                             | Location        | Quantity | Unit | Rank | Cost        | Comments  |
|----------------|---|-----------------|----------|------|------|-------------|---|
| <b>Windows</b> |   |                 |          |      |      |             |   |
|                | Windows - Decorative                    | Entire Building | 120      | SF   | 6    | \$896       |   |
|                | Windows - Louver                        | Entire Building | 330      | SF   | 6    | \$2,463     |   |
|                | Windows - Sash Aluminum Double-pane     | Entire Building | 9,815    | SF   | 4    | \$1,288,314 | Too heavy, inoperable due to balance failures or racking, several screwed shut at bathrooms |
|                | Windows - Sash Lexan/ Glass Double-pane | Entire Building | 9,815    | SF   | 6    | \$73,265    |   |

**Building Exterior Subtotal:**
**\$2,947,530**
**Building: Main**
**Category: Electrical System**

| Group                   | Item - Type   | Location   | Quantity | Unit | Rank | Cost     | Comments  |
|-------------------------|---|--|----------|------|------|----------|---|
| <b>Emergency System</b> |   |  |          |      |      |          |   |
|                         | Automatic Transfer Switch                               | Electrical Room  | 1        | EA   | 6    | \$408    |   |
|                         | Emergency A/C Power - Auditorium and Aisle Lighting     | 1st, 2nd, 3rd floor, Entire Building / 1st Floor       | 6,277    | SF   | 6    | \$3,321  |   |
|                         | Emergency A/C Power - Corridors and Stairs              | 1st, 2nd, 3rd floor, Entire Building / Entire Building | 36,385   | SF   | 6    | \$10,926 |   |
|                         | Emergency A/C Power - Gym                               | 1st, 2nd, 3rd floor, Entire Building / 2nd Floor       | 5,983    | SF   | 4    | \$10,780 | Boy's Gym Not on                                  |
|                         | Emergency A/C Power - Gym                               | 1st, 2nd, 3rd floor, Entire Building / 2nd Floor       | 5,972    | SF   | 6    | \$2,220  | Girl's Gym  |
|                         | Emergency A/C Power - Lunchrooms                        | 1st, 2nd, 3rd floor, Entire Building / 3rd Floor       | 5,615    | SF   | 6    | \$2,088  |   |
|                         | Emergency A/C Power - Multipurpose Room                 | 1st, 2nd, 3rd floor, Entire Building / 3rd Floor       | 1,456    | SF   | 6    | \$541    |   |
|                         | Emergency A/C Power - Pool                              | 1st, 2nd, 3rd floor, Entire Building / 1st Floor       | 3,561    | SF   | 6    | \$1,324  |   |
|                         | Emergency A/C Power - Students Toilets                  | 1st, 2nd, 3rd floor, Entire Building / Entire Building | 3,170    | SF   | 6    | \$1,179  |   |
|                         | Emergency Battery Packs - Auditorium and Aisle Lighting | Entire Building / 1st Floor                            | 6        | EA   | 6    | \$1,215  |   |
|                         | Emergency Battery Packs - Gym                           | Entire Building / 2nd Floor                            | 4        | EA   | 6    | \$810    |   |
|                         | Emergency Battery Packs - Students Toilets              | Entire Building  | 16       | EA   | 6    | \$3,240  |   |
|                         | Emergency Generator- Outdoor- Natural Gas - 60 - 100 KW | Site West / West Courtyard                             | 1        | EA   | 7    | \$0      | Also serves the Addition                          |
|                         | Exit Signs - Auditorium                                 | Entire Building / 1st Floor                            | 15       | EA   | 6    | \$2,246  | Served by Generator, Some lights are out          |
|                         | Exit Signs - Corridors and Stairs                       | Entire Building  | 41       | EA   | 6    | \$6,140  | Served by Generator, Some lights are out          |
|                         | Exit Signs - Gym  | Entire Building / 2nd Floor                            | 3        | EA   | 6    | \$472    | Served by Generator, Some lights are out          |
|                         | Exit Signs - Lunchroom                                  | Entire Building / 3rd Floor                            | 2        | EA   | 6    | \$299    | Served by Generator, Some lights are out          |
|                         | Exit Signs - Pool                                       | Entire Building / 1st Floor                            | 3        | EA   | 6    | \$465    | Served by Generator, Some lights are out          |
|                         | Security System - CCTV                                  | Entire Building  | 224,663  | SF   | 6    | \$67,466 | viewing stations and controls also serve addition |

**Building: Main**
**Category: Electrical System**

| Group                     | Item - Type  | Location        | Quantity | Unit | Rank | Cost     | Comments  |
|---------------------------|--|-----------------|----------|------|------|----------|---|
| <b>Emergency System</b>   |  |                 |          |      |      |          |   |
|                           | Security System - Intrusion Detection              | Entire Building | 224,663  | SF   | 6    | \$57,828 |   |
| <b>Main Service</b>       |  |                 |          |      |      |          |   |
|                           | Independent Electrical Service for emergency power | Electrical Room | 1        | EA   | 7    | \$0      | Emergency Feed from ComEd   |
|                           | Main Electrical Service - 1200 A 120/208/3PH       | Electrical Room | 4        | EA   | 7    | \$0      |   |
|                           | PA System  | Entire Building | 224,663  | SF   | 6    | \$73,892 | Speakers and controls in some rooms are broken, no volume control in some rooms, also serves addition |
| <b>Power Distribution</b> |  |                 |          |      |      |          |   |
|                           | Lighting and Power Panels - 100 A                  | Electrical Room | 2        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - 100 A                  | Electrical Room | 12       | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 5        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 5        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 1        | EA   | 7    | \$0      | Emergency fuse type   |
|                           | Main Distribution Panels - 400 - 600 amp           | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Main Distribution Panels - 400 - 600 amp           | Electrical Room | 1        | EA   | 4    | \$13,694 | Live Front, hazardous access to Buss bars   |
|                           | Main Distribution Panels - 400 - 600 amp           | Electrical Room | 1        | EA   | 4    | \$13,694 | Live Front, hazardous access to Buss bars   |

**Electrical System Subtotal:**
**\$274,250**
**Building: Main**
**Category: Safty System**

| Group             | Item - Type              | Location                          | Quantity | Unit | Rank | Cost      | Comments |
|-------------------|--------------------------|-----------------------------------|----------|------|------|-----------|----------|
| <b>Fire Alarm</b> |                          |                                   |          |      |      |           |          |
|                   | Fire Alarm Panel         | Mechanical Room                   | 2        | EA   | 6    | \$12,812  |          |
|                   | Fire Alarm Strobe Lights | Mechanical Room / Entire Building | 224,663  | SF   | 6    | \$80,317  |          |
|                   | Fire Alarm_System        | Mechanical Room / Entire Building | 224,663  | SF   | 6    | \$109,231 |          |

**Safty System Subtotal:**
**\$202,360**
**Building: Main**
**Category: Mechanical System**

| Group                   | Item - Type                                      | Location | Quantity | Unit | Rank | Cost     | Comments                    |
|-------------------------|--|----------|----------|------|------|----------|-----------------------------|
| <b>Air Conditioning</b> |  |          |          |      |      |          |                             |
|                         | Condensing Unit- Roof Mounted - Less than 5 tons | Roof     | 6        | EA   | 6    | \$20,002 | Not in use but operational. |

## Building: Main

### Category: Mechanical System

| Group                       | Item - Type   | Location                          | Quantity | Unit | Rank | Cost     | Comments  |
|-----------------------------|---|-----------------------------------|----------|------|------|----------|---|
| <b>Air Conditioning</b>     |   |                                   |          |      |      |          |   |
|                             | Condensing Unit- Roof Mounted - Less than 5 tons  | Roof                              | 1        | EA   | 6    | \$3,334  | Serves MAU1, Lab Room 204   |
|                             | Condensing Unit- Roof Mounted - Less than 5 tons  | Roof                              | 1        | EA   | 6    | \$3,334  | Serves Office   |
| <b>Air Handling Systems</b> |   |                                   |          |      |      |          |   |
|                             | Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - Greater than 35000 cfm          | Mechanical Room                   | 1        | EA   | 6    | \$8,716  | Serves 1,2,3, South central floors                                  |
|                             | Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - Greater than 35000 cfm          | Mechanical Room                   | 1        | EA   | 6    | \$8,716  | Serves 1,2,3, North central floors                                  |
|                             | Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - Greater than 35000 cfm          | Mechanical Room                   | 1        | EA   | 6    | \$8,716  | Serves South Wing floors  |
|                             | Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000                                   | Mechanical Room                   | 1        | EA   | 6    | \$5,788  | Serves G.Gym/Locker room  |
|                             | Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000                                   | Mechanical Room                   | 1        | EA   | 5    | \$66,438 | Serves B.Gym/Locker room, Pool                                      |
|                             | Air Handling Unit- Package Multi Zone- Indoor- Steam Coil and Chilled Water Coils - 15001-20000 cfm   | Mechanical Room                   | 1        | EA   | 6    | \$3,350  | Serves Lunch, Serving area  |
|                             | Air Handling Unit- Package Single Zone- Indoor- Steam Coils and Chilled Water Coils - 12001-20000 cfm | Mechanical Room                   | 1        | EA   | 7    | \$0      | Serves Assembly Hall, Installed 2012                                |
|                             | Air Intake  | Mechanical Room / Roof            | 1        | EA   | 7    | \$0      |   |
|                             | Air Intake  | Mechanical Room / Roof            | 1        | EA   | 7    | \$0      |   |
|                             | Air Intake  | Mechanical Room / Roof            | 3        | EA   | 7    | \$0      |   |
|                             | Air Intake  | Mechanical Room / Roof            | 1        | EA   | 7    | \$0      |   |
|                             | Air Intake  | Mechanical Room / Roof            | 2        | EA   | 7    | \$0      |   |
|                             | Auxiliaries - 15001 - 25000 cfm   | Mechanical Room                   | 1        | EA   | 5    | \$14,899 |   |
|                             | Auxiliaries - 15001 - 25000 cfm   | Mechanical Room                   | 1        | EA   | 6    | \$5,788  |   |
|                             | Auxiliaries - Greater than 35000 cfm  | Mechanical Room                   | 1        | EA   | 6    | \$8,716  |   |
|                             | Auxiliaries - Greater than 35000 cfm  | Mechanical Room                   | 1        | EA   | 6    | \$8,716  |   |
|                             | Auxiliaries - Greater than 35000 cfm  | Mechanical Room                   | 1        | EA   | 6    | \$8,716  |   |
|                             | Make Up Air Unit- Roof Mounted- Gas Heating and DX Cooling Coil - Less than 6000 cfm                  | Roof                              | 1        | EA   | 6    | \$3,350  | Serves Lab 204  |
|                             | Reheat Boxes - Reheat Boxes with Steam Coil   | Mechanical Room / Plenum          | 7        | EA   | 6    | \$7,358  | AHU3  |
|                             | Reheat Boxes - Reheat Boxes with Steam Coil   | Mechanical Room / Plenum          | 6        | EA   | 6    | \$6,307  | AHU5  |
|                             | Reheat Boxes - Reheat Boxes with Steam Coil   | Mechanical Room / Plenum          | 6        | EA   | 6    | \$6,307  | AHU4  |
|                             | Return Duct Work - Indoor- Vertical Shaft and Ducts   | Mechanical Room / Entire Building | 100      | LF   | 7    | \$0      |   |
|                             | Return Duct Work - Indoor- Vertical Shaft and Ducts   | Mechanical Room / Entire Building | 100      | LF   | 7    | \$0      |   |
|                             | Return Duct Work - Masonry and Ducts- Missing or Existing Shaft                                       | Mechanical Room / Entire Building | 700      | LF   | 7    | \$0      |   |
|                             | Zone Dampers  | Mechanical Room                   | 18       | EA   | 6    | \$14,995 | AH7, Pneumatic's do not work. Manual operation with wood or string. |
|                             | Zone Dampers  | Mechanical Room                   | 8        | EA   | 6    | \$6,664  |   |
|                             | Zone Dampers  | Mechanical Room                   | 8        | EA   | 5    | \$15,308 | AH6, Pneumatic's do not work. Manual operation with wood or string. |
|                             | Zone Dampers  | Mechanical Room                   | 19       | EA   | 6    | \$15,828 | AH5   |

**Building: Main**
**Category: Mechanical System**

| Group                       | Item - Type   | Location                      | Quantity | Unit | Rank | Cost        | Comments  |
|-----------------------------|---|-------------------------------|----------|------|------|-------------|---|
| <b>Air Handling Systems</b> |   |                               |          |      |      |             |   |
|                             | Zone Dampers  | Mechanical Room               | 25       | EA   | 6    | \$20,826    | AH4   |
|                             | Zone Dampers  | Mechanical Room               | 27       | EA   | 6    | \$22,492    | AH3   |
| <b>Boiler Systems</b>       |   |                               |          |      |      |             |   |
|                             | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 201 - 300 HP           | Boiler Room                   | 1        | EA   | 6    | \$998       |   |
|                             | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 201 - 300 HP           | Boiler Room                   | 1        | EA   | 6    | \$998       |   |
|                             | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 50 - 75 HP             | Boiler Room                   | 1        | EA   | 7    | \$0         |   |
|                             | Chemical Feed System  | Boiler Room / Mechanical Room | 1        | EA   | 7    | \$0         |   |
|                             | Chemical Feeder   | Boiler Room / Mechanical Room | 1        | EA   | 6    | \$1,078     |   |
|                             | Combustion Dampers  | Boiler Room                   | 3        | EA   | 6    | \$1,227     |   |
|                             | Condensate Pump   | Boiler Room / Mechanical Room | 7        | EA   | 6    | \$14,148    |   |
|                             | Feed Water Pumps and Tank   | Boiler Room                   | 1        | EA   | 6    | \$2,545     |   |
|                             | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 201 - 300 HP | Boiler Room                   | 1        | EA   | 5    | \$27,797    |   |
|                             | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 201 - 300 HP | Boiler Room                   | 1        | EA   | 5    | \$27,797    |   |
|                             | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 50 - 75 HP   | Boiler Room                   | 1        | EA   | 7    | \$0         | Installed 5/2015  |
|                             | Piping - Condensate Pipe- Steel   | Boiler Room / Entire Building | 1,500    | LF   | 6    | \$2,831     |   |
|                             | Piping - Steam Pipe- Steel  | Boiler Room / Entire Building | 1,500    | LF   | 6    | \$2,831     |   |
|                             | Steam Traps   | Boiler Room / Mechanical Room | 38       | EA   | 5    | \$49,966    |   |
|                             | Vacuum Pump   | Boiler Room / Mechanical Room | 1        | EA   | 6    | \$2,471     |   |
| <b>Heating Devices</b>      |   |                               |          |      |      |             |   |
|                             | Radiators - Steam   | Entire Building               | 80       | EA   | 5    | \$134,025   |   |
| <b>Mechanical Plumbing</b>  |   |                               |          |      |      |             |   |
|                             | Hydronic Supply and Return - Steel  | Entire Building               | 400      | LF   | 6    | \$30,711    |   |
| <b>Temperature Control</b>  |   |                               |          |      |      |             |   |
|                             | Pneumatic System  | Entire Building               | 224,663  | SF   | 4    | \$1,169,416 | Leaks in system older then 20 years old, manual temperature control |
|                             | Thermostats - Pneumatic   | Entire Building               | 20       | EA   | 4    | \$14,745    | Broken stats, manual temperature control                            |
|                             | Thermostats - Pneumatic   | Entire Building               | 48       | EA   | 4    | \$35,387    | Not in operation  |
| <b>Ventilation</b>          |   |                               |          |      |      |             |   |
|                             | Exhaust Fans- Roof Mounted - 1501 - 8000 CFM  | Roof, 3rd floor / Roof        | 8        | EA   | 6    | \$4,739     |   |
|                             | Exhaust Fans- Roof Mounted - 500 - 1500 CFM   | Roof, 3rd floor / Roof        | 3        | EA   | 6    | \$1,777     |   |
|                             | Exhaust Fans- Roof Mounted - Less than 500 CFM                                      | Roof, 3rd floor / Roof        | 1        | EA   | 6    | \$296       |   |

**Building: Main**
**Category: Mechanical System**

| Group              | Item - Type                           | Location                    | Quantity | Unit | Rank | Cost    | Comments   |
|--------------------|---------------------------------------|-----------------------------|----------|------|------|---------|--|
| <b>Ventilation</b> |                                       |                             |          |      |      |         |  |
|                    | Lab Exhaust Hood                      | Roof, 3rd floor / Roof      | 1        | EA   | 6    | \$1,248 |  |
|                    | Roof Mounted Duct Work                | Roof, 3rd floor / Roof      | 20       | LF   | 7    | \$0     | Stainless  |
|                    | Type I Exhaust Hood- Culinary Arts    | Roof, 3rd floor / 3rd Floor | 1        | EA   | 6    | \$1,248 | Due for maintenance and cleaning.                  |
|                    | Type I Exhaust Hood- Kitchen          | Roof, 3rd floor / 3rd Floor | 1        | EA   | 6    | \$1,248 | Warming Kitchen, Due for maintenance and cleaning. |
|                    | Type I Exhaust Hood- Kitchen          | Roof, 3rd floor / 3rd Floor | 1        | EA   | 6    | \$1,248 | Serves Dishwashing Area                            |
|                    | Type II Exhaust Hood- Warming Kitchen | Roof, 3rd floor / 3rd Floor | 1        | EA   | 6    | \$920   | Due for service and testing.                       |

**Mechanical System Subtotal:**
**\$1,826,354**
**Building: Main**
**Category: Plumbing System**

| Group            | Item - Type                            | Location        | Quantity | Unit | Rank | Cost     | Comments   |
|------------------|--|-----------------|----------|------|------|----------|--|
| <b>Hot Water</b> |  |                 |          |      |      |          |  |
|                  | Electric Heater - Less than 20 KW      | Mechanical Room | 1        | EA   | 6    | \$682    | Serves Kitchen   |
|                  | Steam Storage Tank - 201 - 500 Gallons | Boiler Room     | 1        | EA   | 4    | \$13,270 | twin tank has ruptured and not in service any longer. End of life    |
|                  | Steam Storage Tank - 201 - 500 Gallons | Boiler Room     | 1        | EA   | 3    | \$13,270 | Valved off not operational inner/outer walls compromised and leaking |

**Piping**

|  |  |                 |         |    |   |           |                               |
|--|--|-----------------|---------|----|---|-----------|-------------------------------|
|  | Domestic Piping-Cold Water from Risers to Fixtures | Entire Building | 224,663 | SF | 7 | \$0       | Replaced with fixtures / 2010 |
|  | Domestic Piping-Cold Water Horizontal Lines        | Entire Building | 224,663 | SF | 7 | \$0       | Replaced with fixtures / 2010 |
|  | Domestic Piping-Cold Water Risers                  | Entire Building | 224,663 | SF | 6 | \$41,765  |                               |
|  | Domestic Piping-Hot Water from Risers to Fixtures  | Entire Building | 224,663 | SF | 7 | \$0       | Replaced with fixtures / 2010 |
|  | Domestic Piping-Hot Water Horizontal Lines         | Entire Building | 224,663 | SF | 7 | \$0       | Replaced with fixtures / 2010 |
|  | Domestic Piping-Hot Water Return Lines             | Entire Building | 224,663 | SF | 6 | \$32,127  |                               |
|  | Domestic Piping-Hot Water Return Risers            | Entire Building | 224,663 | SF | 6 | \$32,127  |                               |
|  | Sanitary Piping                                    | Entire Building | 224,663 | SF | 6 | \$205,612 |                               |
|  | Storm Piping                                       | Entire Building | 224,663 | SF | 6 | \$195,974 |                               |
|  | Vent Piping  | Entire Building | 224,663 | SF | 6 | \$150,996 |                               |

**Pool Systems**

|  |  |                 |     |    |   |          |               |
|--|--|-----------------|-----|----|---|----------|---------------|
|  | Pool Drain Piping                            | Mechanical Room | 100 | LF | 6 | \$2,863  | Has Leaks     |
|  | Pool Filtration System including Pump        | Mechanical Room | 2   | EA | 6 | \$24,661 | Salt/Chlorine |
|  | Pool Hot Water Heater - Steam Heat Exchanger | Mechanical Room | 1   | EA | 6 | \$0      |               |
|  | Pool Supply and Return Piping                | Mechanical Room | 200 | LF | 6 | \$9,610  | Has Leaks     |



**Building: Main**
**Category: Plumbing System**

| Group        | Item - Type                           | Location        | Quantity | Unit | Rank | Cost    | Comments            |
|--------------|---------------------------------------|-----------------|----------|------|------|---------|---------------------|
| <b>Pumps</b> |                                       |                 |          |      |      |         |                     |
|              | Pumps - Domestic Booster Pump-Simplex | Mechanical Room | 1        | EA   | 6    | \$1,446 |                     |
|              | Pumps - Sump-Duplex                   | Mechanical Room | 2        | EA   | 6    | \$2,774 |                     |
|              | Pumps - Sump-Simplex                  | Mechanical Room | 1        | EA   | 6    | \$745   | Serves Elevator pit |

**Plumbing System Subtotal:**
**\$727,920**
**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|--|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #103 (Regular Classroom)</b>  |                             |           |          |      |      |         |          |
|  | AC Units                    | 1st Floor | 1        | EA   | 6    | \$496   |          |
|  | Casework                    | 1st Floor | 8        | LF   | 6    | \$202   |          |
|  | Ceiling - Lay-in            | 1st Floor | 765      | SF   | 6    | \$2,297 |          |
|  | Doors - Transom Window      | 1st Floor | 16       | SF   | 6    | \$271   |          |
|  | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Tile/Sheet          | 1st Floor | 765      | SF   | 6    | \$766   |          |
|  | Lighting - Lay-in           | 1st Floor | 21       | EA   | 6    | \$2,498 |          |
|  | Marker Board                | 1st Floor | 24       | LF   | 6    | \$514   |          |
|  | Walls - Plaster/Drywall     | 1st Floor | 973      | SF   | 6    | \$2,685 |          |
| <b>Classroom #104 (Computer Lab)</b>       |                             |           |          |      |      |         |          |
|  | AC Units                    | 1st Floor | 2        | EA   | 6    | \$991   |          |
|  | Casework                    | 1st Floor | 12       | LF   | 6    | \$303   |          |
|  | Ceiling - Lay-in            | 1st Floor | 765      | SF   | 6    | \$2,297 |          |
|  | Chalk Board                 | 1st Floor | 36       | LF   | 4    | \$3,305 |          |
|  | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Tile/Sheet          | 1st Floor | 765      | SF   | 6    | \$766   |          |
|  | Lighting - Lay-in           | 1st Floor | 21       | EA   | 6    | \$2,498 |          |
|  | Storage/ Closet             | 1st Floor | 6        | SF   | 6    | \$44    |          |
|  | Walls - Plaster/Drywall     | 1st Floor | 973      | SF   | 6    | \$2,685 |          |
| <b>Classroom #107A (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Ceiling - Lay-in            | 1st Floor | 360      | SF   | 6    | \$1,081 |          |
|  | Doors - Transom Window      | 1st Floor | 8        | SF   | 6    | \$135   |          |
|  | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Wood                | 1st Floor | 360      | SF   | 6    | \$2,538 |          |
|  | Lighting - Lay-in           | 1st Floor | 10       | EA   | 6    | \$1,190 |          |
|  | Marker Board                | 1st Floor | 16       | LF   | 6    | \$343   |          |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments       |
|--|-----------------------------|-----------|----------|------|------|---------|----------------|
| <b>Classroom #107A (Regular Classroom)</b> |                             |           |          |      |      |         |                |
|  | Walls - Plaster/Drywall     | 1st Floor | 788      | SF   | 6    | \$2,175 |                |
| <b>Classroom #107B (Regular Classroom)</b> |                             |           |          |      |      |         |                |
|  | Casework                    | 1st Floor | 6        | LF   | 6    | \$152   |                |
|  | Ceiling - Lay-in            | 1st Floor | 360      | SF   | 6    | \$1,081 |                |
|  | Doors - Transom Window      | 1st Floor | 8        | SF   | 6    | \$135   |                |
|  | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301   |                |
|  | Floor - Wood                | 1st Floor | 360      | SF   | 6    | \$2,538 |                |
|  | Lighting - Lay-in           | 1st Floor | 10       | EA   | 6    | \$1,190 |                |
|  | Marker Board                | 1st Floor | 12       | LF   | 6    | \$257   |                |
|  | Walls - Plaster/Drywall     | 1st Floor | 790      | SF   | 6    | \$2,180 |                |
| <b>Classroom #108 (Office)</b>             |                             |           |          |      |      |         |                |
|  | AC Units                    | 1st Floor | 3        | EA   | 6    | \$1,487 |                |
|  | Casework                    | 1st Floor | 12       | LF   | 6    | \$303   |                |
|  | Ceiling - Lay-in            | 1st Floor | 765      | SF   | 6    | \$2,297 |                |
|  | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |                |
|  | Floor - Wood                | 1st Floor | 765      | SF   | 6    | \$5,393 |                |
|  | Lighting - Lay-in           | 1st Floor | 21       | EA   | 6    | \$2,498 |                |
|  | Walls - Plaster/Drywall     | 1st Floor | 973      | SF   | 6    | \$2,685 |                |
| <b>Classroom #111A (Regular Classroom)</b> |                             |           |          |      |      |         |                |
|  | AC Units                    | 1st Floor | 1        | EA   | 6    | \$496   |                |
|  | Casework                    | 1st Floor | 20       | LF   | 6    | \$505   |                |
|  | Ceiling - Plaster/Drywall   | 1st Floor | 850      | SF   | 6    | \$2,942 |                |
|  | Ceiling - Plaster/Drywall   | 1st Floor | 600      | SF   | 5    | \$6,452 | Peering paint. |
|  | Doors - Transom Window      | 1st Floor | 8        | SF   | 6    | \$135   |                |
|  | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301   |                |
|  | Floor - Tile/Sheet          | 1st Floor | 850      | SF   | 6    | \$851   |                |
|  | Lighting - Pendent/Surface  | 1st Floor | 24       | EA   | 6    | \$2,973 |                |
|  | Marker Board                | 1st Floor | 16       | LF   | 6    | \$343   |                |
|  | Storage/ Closet             | 1st Floor | 6        | SF   | 6    | \$44    |                |
|  | Walls - Plaster/Drywall     | 1st Floor | 1,534    | SF   | 6    | \$4,234 |                |
| <b>Classroom #111B (Regular Classroom)</b> |                             |           |          |      |      |         |                |
|  | Ceiling - Plaster/Drywall   | 1st Floor | 317      | SF   | 6    | \$1,097 |                |
|  | Doors - Transom Window      | 1st Floor | 8        | SF   | 6    | \$135   |                |
|  | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301   |                |
|  | Floor - Tile/Sheet          | 1st Floor | 317      | SF   | 6    | \$317   |                |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                         | Location  | Quantity | Unit | Rank | Cost    | Comments |
|--|-------------------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #111B (Regular Classroom)</b> |                                     |           |          |      |      |         |          |
|  | Lighting - Pendant/Surface          | 1st Floor | 6        | EA   | 6    | \$743   |          |
|  | Marker Board                        | 1st Floor | 16       | LF   | 6    | \$343   |          |
|  | Walls - Plaster/Drywall             | 1st Floor | 962      | SF   | 6    | \$2,655 |          |
| <b>Classroom #112A (Regular Classroom)</b> |                                     |           |          |      |      |         |          |
|  | AC Units                            | 1st Floor | 1        | EA   | 6    | \$496   |          |
|  | Casework                            | 1st Floor | 10       | LF   | 6    | \$253   |          |
|  | Ceiling - Exposed                   | 1st Floor | 490      | SF   | 6    | \$729   |          |
|  | Doors - Transom Window              | 1st Floor | 8        | SF   | 6    | \$135   |          |
|  | Doors - Wood Doors inclu hw         | 1st Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Wood                        | 1st Floor | 490      | SF   | 6    | \$3,454 |          |
|  | Lighting - Pendant/Surface          | 1st Floor | 6        | EA   | 6    | \$743   |          |
|  | Marker Board                        | 1st Floor | 24       | LF   | 6    | \$514   |          |
|  | Walls - Plaster/Drywall             | 1st Floor | 873      | SF   | 6    | \$2,409 |          |
| <b>Classroom #112B (Office)</b>            |                                     |           |          |      |      |         |          |
|  | AC Units                            | 1st Floor | 1        | EA   | 6    | \$496   |          |
|  | Ceiling - Lay-in                    | 1st Floor | 228      | SF   | 6    | \$685   |          |
|  | Doors - Transom Window              | 1st Floor | 8        | SF   | 6    | \$135   |          |
|  | Doors - Wood Doors inclu hw         | 1st Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Wood                        | 1st Floor | 228      | SF   | 6    | \$1,607 |          |
|  | Lighting - Lay-in                   | 1st Floor | 4        | EA   | 6    | \$476   |          |
|  | Marker Board                        | 1st Floor | 12       | LF   | 6    | \$257   |          |
|  | Walls - Plaster/Drywall             | 1st Floor | 542      | SF   | 6    | \$1,496 |          |
| <b>Classroom #113 (Office)</b>             |                                     |           |          |      |      |         |          |
|  | AC Units                            | 1st Floor | 2        | EA   | 6    | \$991   |          |
|  | Ceiling - Lay-in                    | 1st Floor | 730      | SF   | 6    | \$2,192 |          |
|  | Doors - Transom Window              | 1st Floor | 16       | SF   | 6    | \$271   |          |
|  | Doors - Wood Doors inclu hw         | 1st Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Wood                        | 1st Floor | 730      | SF   | 6    | \$5,146 |          |
|  | Lighting - Chandelier, Incandescent | 1st Floor | 19       | EA   | 6    | \$9,074 |          |
|  | Lighting - Lay-in                   | 1st Floor | 20       | EA   | 6    | \$2,380 |          |
|  | Marker Board                        | 1st Floor | 4        | LF   | 6    | \$86    |          |
|  | Storage/ Closet                     | 1st Floor | 10       | SF   | 6    | \$73    |          |
|  | Walls - Plaster/Drywall             | 1st Floor | 1,005    | SF   | 6    | \$2,774 |          |
| <b>Classroom #114 (Office)</b>             |                                     |           |          |      |      |         |          |
|  | AC Units                            | 1st Floor | 2        | EA   | 6    | \$991   |          |

**Building: Main**
**Category: Classrooms**

| Group                                | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|--------------------------------------|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #114 (Office)</b>       |                             |           |          |      |      |         |          |
|                                      | Casework                    | 1st Floor | 20       | LF   | 6    | \$505   |          |
|                                      | Ceiling - Lay-in            | 1st Floor | 732      | SF   | 6    | \$2,198 |          |
|                                      | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|                                      | Floor - Tile/Sheet          | 1st Floor | 732      | SF   | 6    | \$733   |          |
|                                      | Lighting - Lay-in           | 1st Floor | 21       | EA   | 6    | \$2,498 |          |
|                                      | Storage/ Closet             | 1st Floor | 8        | SF   | 6    | \$58    |          |
|                                      | Walls - Plaster/Drywall     | 1st Floor | 1,830    | SF   | 6    | \$5,051 |          |
| <b>Classroom #116 (Office)</b>       |                             |           |          |      |      |         |          |
|                                      | AC Units                    | 1st Floor | 1        | EA   | 6    | \$496   |          |
|                                      | Ceiling - Lay-in            | 1st Floor | 357      | SF   | 6    | \$1,072 |          |
|                                      | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Tile/Sheet          | 1st Floor | 357      | SF   | 6    | \$357   |          |
|                                      | Lighting - Lay-in           | 1st Floor | 9        | EA   | 6    | \$1,071 |          |
|                                      | Walls - Plaster/Drywall     | 1st Floor | 595      | SF   | 6    | \$1,642 |          |
| <b>Classroom #117 (Computer Lab)</b> |                             |           |          |      |      |         |          |
|                                      | AC Units                    | 1st Floor | 2        | EA   | 6    | \$991   |          |
|                                      | Ceiling - Plaster/Drywall   | 1st Floor | 960      | SF   | 6    | \$3,322 |          |
|                                      | Doors - Transom Window      | 1st Floor | 16       | SF   | 6    | \$271   |          |
|                                      | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|                                      | Floor - Wood                | 1st Floor | 960      | SF   | 6    | \$6,768 |          |
|                                      | Lighting - Pendent/Surface  | 1st Floor | 30       | EA   | 6    | \$3,717 |          |
|                                      | Marker Board                | 1st Floor | 10       | LF   | 6    | \$214   |          |
|                                      | Storage/ Closet             | 1st Floor | 6        | SF   | 6    | \$44    |          |
|                                      | Walls - Plaster/Drywall     | 1st Floor | 1,135    | SF   | 6    | \$3,132 |          |
|                                      | Work Sink                   | 1st Floor | 1        | EA   | 6    | \$379   |          |
| <b>Classroom #121 (Computer Lab)</b> |                             |           |          |      |      |         |          |
|                                      | AC Units                    | 1st Floor | 2        | EA   | 6    | \$991   |          |
|                                      | Ceiling - Lay-in            | 1st Floor | 960      | SF   | 6    | \$2,883 |          |
|                                      | Doors - Transom Window      | 1st Floor | 16       | SF   | 6    | \$271   |          |
|                                      | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|                                      | Floor - Wood                | 1st Floor | 960      | SF   | 6    | \$6,768 |          |
|                                      | Lighting - Lay-in           | 1st Floor | 30       | EA   | 6    | \$3,569 |          |
|                                      | Marker Board                | 1st Floor | 10       | LF   | 6    | \$214   |          |
|                                      | Walls - Plaster/Drywall     | 1st Floor | 1,135    | SF   | 6    | \$3,132 |          |
|                                      | Work Sink                   | 1st Floor | 1        | EA   | 6    | \$379   |          |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|--|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #125 (Office)</b>             |                             |           |          |      |      |         |          |
|  | Ceiling - Lay-in            | 1st Floor | 1,230    | SF   | 6    | \$3,694 |          |
|  | Doors - Transom Window      | 1st Floor | 16       | SF   | 6    | \$271   |          |
|  | Doors - Wood Doors inclu hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Wood                | 1st Floor | 1,230    | SF   | 6    | \$8,671 |          |
|  | Lighting - Pendent/Surface  | 1st Floor | 36       | EA   | 6    | \$4,460 |          |
|  | Walls - Plaster/Drywall     | 1st Floor | 1,510    | SF   | 6    | \$4,167 |          |
|  | Work Sink                   | 1st Floor | 2        | EA   | 6    | \$758   |          |
| <b>Classroom #201 (Computer Lab)</b>       |                             |           |          |      |      |         |          |
|  | AC Units                    | 2nd Floor | 2        | EA   | 6    | \$991   |          |
|  | Casework                    | 2nd Floor | 40       | LF   | 6    | \$1,010 |          |
|  | Ceiling - Lay-in            | 2nd Floor | 1,180    | SF   | 6    | \$3,544 |          |
|  | Chalk Board                 | 2nd Floor | 15       | LF   | 6    | \$335   |          |
|  | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Tile/Sheet          | 2nd Floor | 1,180    | SF   | 6    | \$1,181 |          |
|  | Lighting - Lay-in           | 2nd Floor | 30       | EA   | 6    | \$3,569 |          |
|  | Marker Board                | 2nd Floor | 4        | LF   | 7    | \$0     |          |
|  | Storage/ Closet             | 2nd Floor | 50       | SF   | 6    | \$363   |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 1,300    | SF   | 6    | \$3,588 |          |
|  | Wireless System             | 2nd Floor | 1        | EA   | 6    | \$372   |          |
|  | Work Sink                   | 2nd Floor | 1        | EA   | 6    | \$379   |          |
| <b>Classroom #202A (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 15       | LF   | 6    | \$379   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 646      | SF   | 6    | \$1,940 |          |
|  | Chalk Board                 | 2nd Floor | 6        | LF   | 4    | \$551   |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Tile/Sheet          | 2nd Floor | 646      | SF   | 6    | \$647   |          |
|  | Lighting - Lay-in           | 2nd Floor | 18       | EA   | 6    | \$2,142 |          |
|  | Marker Board                | 2nd Floor | 6        | LF   | 6    | \$129   |          |
|  | Storage/ Closet             | 2nd Floor | 50       | SF   | 6    | \$363   |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 930      | SF   | 6    | \$2,567 |          |
| <b>Classroom #202B (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Ceiling - Lay-in            | 2nd Floor | 465      | SF   | 6    | \$1,396 |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 6        | EA   | 6    | \$1,806 |          |

**Building: Main**
**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments        |
|---|-----------------------------|-----------|----------|------|------|----------|-----------------|
| <b>Classroom #202B (Regular Classroom)</b>  |                             |           |          |      |      |          |                 |
|   | Floor - Tile/Sheet          | 2nd Floor | 465      | SF   | 6    | \$465    |                 |
|   | Lighting - Lay-in           | 2nd Floor | 12       | EA   | 6    | \$1,428  |                 |
|   | Marker Board                | 2nd Floor | 10       | LF   | 7    | \$0      |                 |
|   | Walls - Plaster/Drywall     | 2nd Floor | 867      | SF   | 6    | \$2,393  |                 |
| <b>Classroom #203 (Science Lab Level 1)</b> |                             |           |          |      |      |          |                 |
|   | Casework                    | 2nd Floor | 160      | LF   | 6    | \$4,041  |                 |
|   | Ceiling - Lay-in            | 2nd Floor | 1,494    | SF   | 6    | \$4,486  |                 |
|   | Chalk Board                 | 2nd Floor | 30       | LF   | 4    | \$2,754  |                 |
|   | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203    |                 |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602    |                 |
|   | Eye Wash Station            | 2nd Floor | 4        | EA   | 5    | \$3,376  | Not working     |
|   | Floor - Tile/Sheet          | 2nd Floor | 1,494    | SF   | 6    | \$1,495  |                 |
|   | Fume Hood                   | 2nd Floor | 1        | EA   | 6    | \$816    | In 203A prep rm |
|   | Gas Line                    | 2nd Floor | 28       | EA   | 6    | \$14,255 |                 |
|   | Lighting - Lay-in           | 2nd Floor | 45       | EA   | 6    | \$5,354  |                 |
|   | Science Lab Elements        | 2nd Floor | 1,494    | SF   | 6    | \$10,127 |                 |
|   | Science Lab Shower          | 2nd Floor | 1        | EA   | 6    | \$379    |                 |
|   | Storage/ Closet             | 2nd Floor | 125      | SF   | 6    | \$906    |                 |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,674    | SF   | 6    | \$4,620  |                 |
|   | Work Sink                   | 2nd Floor | 16       | EA   | 5    | \$24,124 | Not working     |
|   | Work Sink                   | 2nd Floor | 1        | EA   | 6    | \$379    |                 |
| <b>Classroom #204 (Science Lab Level 3)</b> |                             |           |          |      |      |          |                 |
|   | Casework                    | 2nd Floor | 100      | LF   | 6    | \$2,525  |                 |
|   | Ceiling - Lay-in            | 2nd Floor | 1,092    | SF   | 6    | \$3,279  |                 |
|   | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203    |                 |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602    |                 |
|   | Eye Wash Station            | 2nd Floor | 1        | EA   | 6    | \$336    |                 |
|   | Floor - Tile/Sheet          | 2nd Floor | 1,092    | SF   | 6    | \$1,093  |                 |
|   | Fume Hood                   | 2nd Floor | 1        | EA   | 6    | \$816    |                 |
|   | Gas Line                    | 2nd Floor | 8        | EA   | 6    | \$4,073  |                 |
|   | Lighting - Lay-in           | 2nd Floor | 15       | EA   | 6    | \$1,785  |                 |
|   | Marker Board                | 2nd Floor | 40       | LF   | 7    | \$0      |                 |
|   | Science Lab Elements        | 2nd Floor | 1,092    | SF   | 6    | \$7,402  |                 |
|   | Science Lab Shower          | 2nd Floor | 1        | EA   | 6    | \$379    |                 |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,370    | SF   | 6    | \$3,781  |                 |
|   | Work Sink                   | 2nd Floor | 10       | EA   | 6    | \$3,790  |                 |

**Building: Main**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments         |
|---|-----------------------------|-----------|----------|------|------|---------|------------------|
| <b>Classroom #205 (Computer Lab)</b>      |                             |           |          |      |      |         |                  |
|   | AC Units                    | 2nd Floor | 2        | EA   | 6    | \$991   |                  |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |                  |
|   | Ceiling - Lay-in            | 2nd Floor | 744      | SF   | 6    | \$2,234 |                  |
|   | Chalk Board                 | 2nd Floor | 20       | LF   | 4    | \$1,836 |                  |
|   | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |                  |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |                  |
|   | Floor - Wood                | 2nd Floor | 744      | SF   | 6    | \$5,245 |                  |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498 |                  |
|   | Marker Board                | 2nd Floor | 20       | LF   | 7    | \$0     |                  |
|   | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |                  |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,040    | SF   | 6    | \$2,870 |                  |
|   | Walls - Plaster/Drywall     | 2nd Floor | 10       | SF   | 5    | \$51    | Cracking plaster |
|   | Wireless System             | 2nd Floor | 1        | EA   | 6    | \$372   |                  |
| <b>Classroom #206 (Regular Classroom)</b> |                             |           |          |      |      |         |                  |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |                  |
|   | Ceiling - Lay-in            | 2nd Floor | 730      | SF   | 6    | \$2,192 |                  |
|   | Chalk Board                 | 2nd Floor | 6        | LF   | 4    | \$551   |                  |
|   | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |                  |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |                  |
|   | Floor - Wood                | 2nd Floor | 730      | SF   | 6    | \$5,146 |                  |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498 |                  |
|   | Marker Board                | 2nd Floor | 32       | LF   | 7    | \$0     |                  |
|   | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |                  |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,005    | SF   | 6    | \$2,774 |                  |
| <b>Classroom #207 (Science Classroom)</b> |                             |           |          |      |      |         |                  |
|   | Casework                    | 2nd Floor | 120      | LF   | 6    | \$3,030 |                  |
|   | Ceiling - Lay-in            | 2nd Floor | 1,014    | SF   | 6    | \$3,045 |                  |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |                  |
|   | Floor - Tile/Sheet          | 2nd Floor | 1,014    | SF   | 6    | \$1,015 |                  |
|   | Lighting - Lay-in           | 2nd Floor | 28       | EA   | 6    | \$3,331 |                  |
|   | Lighting - Pendent/Surface  | 2nd Floor | 2        | EA   | 6    | \$248   |                  |
|   | Marker Board                | 2nd Floor | 30       | LF   | 6    | \$643   |                  |
|   | Storage/ Closet             | 2nd Floor | 20       | SF   | 6    | \$145   |                  |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,322    | SF   | 6    | \$3,649 |                  |
|   | Work Sink                   | 2nd Floor | 2        | EA   | 6    | \$758   |                  |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|--|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #208 (Regular Classroom)</b>  |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 735      | SF   | 6    | \$2,207 |          |
|  | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Wood                | 2nd Floor | 735      | SF   | 6    | \$5,182 |          |
|  | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498 |          |
|  | Marker Board                | 2nd Floor | 30       | LF   | 7    | \$0     |          |
|  | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 1,094    | SF   | 6    | \$3,019 |          |
| <b>Classroom #209A (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 330      | SF   | 6    | \$991   |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Wood                | 2nd Floor | 330      | SF   | 6    | \$2,326 |          |
|  | Lighting - Lay-in           | 2nd Floor | 9        | EA   | 6    | \$1,071 |          |
|  | Marker Board                | 2nd Floor | 20       | LF   | 7    | \$0     |          |
|  | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 765      | SF   | 6    | \$2,111 |          |
| <b>Classroom #209B (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 6        | LF   | 6    | \$152   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 403      | SF   | 6    | \$1,210 |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Wood                | 2nd Floor | 403      | SF   | 6    | \$2,841 |          |
|  | Lighting - Lay-in           | 2nd Floor | 12       | EA   | 6    | \$1,428 |          |
|  | Marker Board                | 2nd Floor | 12       | LF   | 7    | \$0     |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 896      | SF   | 6    | \$2,473 |          |
| <b>Classroom #210 (Regular Classroom)</b>  |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 730      | SF   | 6    | \$2,192 |          |
|  | Chalk Board                 | 2nd Floor | 40       | LF   | 4    | \$3,672 |          |
|  | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Wood                | 2nd Floor | 730      | SF   | 6    | \$5,146 |          |
|  | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498 |          |



**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                |
|--|-----------------------------|-----------|----------|------|------|---------|-------------------------|
| <b>Classroom #210 (Regular Classroom)</b>  |                             |           |          |      |      |         |                         |
|  | Marker Board                | 2nd Floor | 10       | LF   | 7    | \$0     |                         |
|  | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |                         |
|  | Walls - Plaster/Drywall     | 2nd Floor | 1,042    | SF   | 6    | \$2,876 |                         |
| <b>Classroom #212 (Regular Classroom)</b>  |                             |           |          |      |      |         |                         |
|  | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |                         |
|  | Ceiling - Lay-in            | 2nd Floor | 735      | SF   | 6    | \$2,207 |                         |
|  | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |                         |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |                         |
|  | Floor - Wood                | 2nd Floor | 735      | SF   | 6    | \$5,182 |                         |
|  | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498 |                         |
|  | Marker Board                | 2nd Floor | 40       | LF   | 7    | \$0     |                         |
|  | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |                         |
|  | Walls - Plaster/Drywall     | 2nd Floor | 1,094    | SF   | 6    | \$3,019 |                         |
| <b>Classroom #213A (Regular Classroom)</b> |                             |           |          |      |      |         |                         |
|  | Casework                    |           | 5        | LF   | 6    | \$126   |                         |
|  | Ceiling - Lay-in            |           | 403      | SF   | 6    | \$1,210 |                         |
|  | Doors - Transom Window      |           | 6        | SF   | 6    | \$102   |                         |
|  | Doors - Wood Doors inclu hw |           | 1        | EA   | 6    | \$301   |                         |
|  | Floor - Wood                |           | 403      | SF   | 6    | \$2,841 |                         |
|  | Lighting - Lay-in           |           | 12       | EA   | 7    | \$0     |                         |
|  | Marker Board                |           | 12       | LF   | 7    | \$0     |                         |
|  | Storage/ Closet             |           | 4        | SF   | 6    | \$29    |                         |
|  | Walls - Plaster/Drywall     |           | 790      | SF   | 6    | \$2,180 |                         |
| <b>Classroom #213B (Regular Classroom)</b> |                             |           |          |      |      |         |                         |
|  | Casework                    | 2nd Floor | 3        | LF   | 6    | \$76    |                         |
|  | Ceiling - Lay-in            | 2nd Floor | 330      | SF   | 5    | \$1,963 | water stains throughout |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |                         |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |                         |
|  | Floor - Wood                | 2nd Floor | 330      | SF   | 6    | \$2,326 |                         |
|  | Lighting - Lay-in           | 2nd Floor | 9        | EA   | 6    | \$1,071 |                         |
|  | Marker Board                | 2nd Floor | 24       | LF   | 7    | \$0     |                         |
|  | Walls - Plaster/Drywall     | 2nd Floor | 765      | SF   | 6    | \$2,111 |                         |
| <b>Classroom #214A (Regular Classroom)</b> |                             |           |          |      |      |         |                         |
|  | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202   |                         |
|  | Ceiling - Lay-in            | 2nd Floor | 506      | SF   | 6    | \$1,520 |                         |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|--|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #214A (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Chalk Board                 | 2nd Floor | 20       | LF   | 4    | \$1,836 |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Wood                | 2nd Floor | 506      | SF   | 6    | \$3,567 |          |
|  | Lighting - Lay-in           | 2nd Floor | 16       | EA   | 6    | \$1,904 |          |
|  | Marker Board                | 2nd Floor | 10       | LF   | 6    | \$214   |          |
|  | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 860      | SF   | 6    | \$2,374 |          |
| <b>Classroom #217A (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 4        | LF   | 6    | \$101   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 485      | SF   | 6    | \$1,456 |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Tile/Sheet          | 2nd Floor | 485      | SF   | 6    | \$485   |          |
|  | Lighting - Lay-in           | 2nd Floor | 15       | EA   | 6    | \$1,785 |          |
|  | Marker Board                | 2nd Floor | 12       | LF   | 7    | \$0     |          |
|  | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29    |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 840      | SF   | 6    | \$2,318 |          |
| <b>Classroom #217B (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|  | Casework                    | 2nd Floor | 4        | LF   | 6    | \$101   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 468      | SF   | 6    | \$1,405 |          |
|  | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|  | Floor - Tile/Sheet          | 2nd Floor | 468      | SF   | 6    | \$468   |          |
|  | Lighting - Lay-in           | 2nd Floor | 6        | EA   | 6    | \$714   |          |
|  | Marker Board                | 2nd Floor | 36       | LF   | 7    | \$0     |          |
|  | Walls - Plaster/Drywall     | 2nd Floor | 820      | SF   | 6    | \$2,263 |          |
| <b>Classroom #221 (Computer Lab)</b>       |                             |           |          |      |      |         |          |
|  | AC Units                    | 2nd Floor | 2        | EA   | 6    | \$991   |          |
|  | Casework                    | 2nd Floor | 12       | LF   | 6    | \$303   |          |
|  | Ceiling - Lay-in            | 2nd Floor | 824      | SF   | 6    | \$2,474 |          |
|  | Doors - Transom Window      | 2nd Floor | 12       | SF   | 6    | \$203   |          |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |          |
|  | Floor - Wood                | 2nd Floor | 824      | SF   | 6    | \$5,809 |          |
|  | Lighting - Lay-in           | 2nd Floor | 27       | EA   | 6    | \$3,212 |          |
|  | Marker Board                | 2nd Floor | 10       | LF   | 7    | \$0     |          |

**Building: Main**
**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments      |
|---|-----------------------------|-----------|----------|------|------|----------|---------------|
| <b>Classroom #221 (Computer Lab)</b>        |                             |           |          |      |      |          |               |
|   | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29     |               |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,040    | SF   | 6    | \$2,870  |               |
|   | Wireless System             | 2nd Floor | 1        | EA   | 6    | \$372    | Missing cover |
|   | Work Sink                   | 2nd Floor | 1        | EA   | 6    | \$379    |               |
| <b>Classroom #225 (Computer Lab)</b>        |                             |           |          |      |      |          |               |
|   | AC Units                    | 2nd Floor | 2        | EA   | 6    | \$991    |               |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202    |               |
|   | Ceiling - Lay-in            | 2nd Floor | 755      | SF   | 6    | \$2,267  |               |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602    |               |
|   | Floor - Wood                | 2nd Floor | 755      | SF   | 6    | \$5,323  |               |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498  |               |
|   | Marker Board                | 2nd Floor | 20       | LF   | 7    | \$0      |               |
|   | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29     |               |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,055    | SF   | 6    | \$2,912  |               |
| <b>Classroom #227 (Regular Classroom)</b>   |                             |           |          |      |      |          |               |
|   | Casework                    | 2nd Floor | 8        | LF   | 6    | \$202    |               |
|   | Ceiling - Lay-in            | 2nd Floor | 816      | SF   | 6    | \$2,450  |               |
|   | Doors - Transom Window      | 2nd Floor | 6        | SF   | 6    | \$102    |               |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301    |               |
|   | Floor - Wood                | 2nd Floor | 816      | SF   | 6    | \$5,753  |               |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 6    | \$2,498  |               |
|   | Marker Board                | 2nd Floor | 20       | LF   | 7    | \$0      |               |
|   | Storage/ Closet             | 2nd Floor | 4        | SF   | 6    | \$29     |               |
|   | Walls - Plaster/Drywall     | 2nd Floor | 1,035    | SF   | 6    | \$2,856  |               |
| <b>Classroom #301 (Science Lab Level 3)</b> |                             |           |          |      |      |          |               |
|   | Casework                    | 3rd Floor | 65       | LF   | 6    | \$1,641  |               |
|   | Ceiling - Lay-in            | 3rd Floor | 950      | SF   | 6    | \$2,853  |               |
|   | Chalk Board                 | 3rd Floor | 30       | LF   | 4    | \$2,754  |               |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203    |               |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602    |               |
|   | Floor - Tile/Sheet          | 3rd Floor | 950      | SF   | 6    | \$951    |               |
|   | Gas Line                    | 3rd Floor | 5        | EA   | 5    | \$17,907 | Not working   |
|   | Lighting - Lay-in           | 3rd Floor | 43       | EA   | 6    | \$5,116  |               |
|   | Science Lab Elements        | 3rd Floor | 950      | SF   | 6    | \$6,439  |               |
|   | Storage/ Closet             | 3rd Floor | 12       | SF   | 6    | \$87     |               |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,205    | SF   | 6    | \$3,326  |               |

**Building: Main**
**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments       |
|---|-----------------------------|-----------|----------|------|------|----------|----------------|
| <b>Classroom #301 (Science Lab Level 3)</b> |                             |           |          |      |      |          |                |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 6    | \$1,137  |                |
| <b>Classroom #302 (Science Lab Level 3)</b> |                             |           |          |      |      |          |                |
|   | Casework                    | 3rd Floor | 65       | LF   | 6    | \$1,641  |                |
|   | Ceiling - Lay-in            | 3rd Floor | 1,097    | SF   | 6    | \$3,294  |                |
|   | Chalk Board                 | 3rd Floor | 30       | LF   | 4    | \$2,754  |                |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203    |                |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602    |                |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,097    | SF   | 6    | \$1,098  |                |
|   | Lighting - Lay-in           | 3rd Floor | 33       | EA   | 6    | \$3,926  |                |
|   | Science Lab Elements        | 3rd Floor | 1,097    | SF   | 6    | \$7,436  |                |
|   | Storage/ Closet             | 3rd Floor | 65       | SF   | 6    | \$471    |                |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,365    | SF   | 6    | \$3,767  |                |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 6    | \$1,137  |                |
| <b>Classroom #303 (Science Lab Level 3)</b> |                             |           |          |      |      |          |                |
|   | Casework                    | 3rd Floor | 65       | LF   | 6    | \$1,641  |                |
|   | Ceiling - Lay-in            | 3rd Floor | 969      | SF   | 6    | \$2,910  |                |
|   | Chalk Board                 | 3rd Floor | 36       | LF   | 4    | \$3,305  |                |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203    |                |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602    |                |
|   | Floor - Tile/Sheet          | 3rd Floor | 969      | SF   | 6    | \$970    |                |
|   | Gas Line                    | 3rd Floor | 5        | EA   | 5    | \$17,907 | Not working    |
|   | Lighting - Lay-in           | 3rd Floor | 27       | EA   | 6    | \$3,212  |                |
|   | Science Lab Elements        | 3rd Floor | 969      | SF   | 6    | \$6,568  |                |
|   | Storage/ Closet             | 3rd Floor | 12       | SF   | 6    | \$87     |                |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,105    | SF   | 6    | \$3,050  |                |
| <b>Classroom #304 (Science Lab Level 2)</b> |                             |           |          |      |      |          |                |
|   | Casework                    | 3rd Floor | 65       | LF   | 6    | \$1,641  |                |
|   | Ceiling - Lay-in            | 3rd Floor | 1,063    | SF   | 6    | \$3,192  |                |
|   | Chalk Board                 | 3rd Floor | 24       | LF   | 6    | \$535    |                |
|   | Doors - Transom Window      | 3rd Floor | 6        | SF   | 6    | \$102    |                |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602    |                |
|   | Eye Wash Station            | 3rd Floor | 1        | EA   | 6    | \$336    |                |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,063    | SF   | 6    | \$1,064  |                |
|   | Fume Hood                   | 3rd Floor | 1        | EA   | 5    | \$3,773  | Not hooked up. |
|   | Gas Line                    | 3rd Floor | 20       | EA   | 6    | \$10,182 |                |
|   | Lighting - Lay-in           | 3rd Floor | 30       | EA   | 6    | \$3,569  |                |

**Building: Main**
**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #304 (Science Lab Level 2)</b> |                             |           |          |      |      |         |          |
|   | Science Lab Elements        | 3rd Floor | 1,063    | SF   | 6    | \$7,205 |          |
|   | Storage/ Closet             | 3rd Floor | 12       | SF   | 6    | \$87    |          |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,224    | SF   | 6    | \$3,378 |          |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 6    | \$1,137 |          |
| <b>Classroom #305 (Regular Classroom)</b>   |                             |           |          |      |      |         |          |
|   | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |          |
|   | Ceiling - Lay-in            | 3rd Floor | 730      | SF   | 6    | \$2,192 |          |
|   | Chalk Board                 | 3rd Floor | 40       | LF   | 4    | \$3,672 |          |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Wood                | 3rd Floor | 730      | SF   | 6    | \$5,146 |          |
|   | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |          |
|   | Marker Board                | 3rd Floor | 16       | LF   | 7    | \$0     |          |
|   | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |          |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,056    | SF   | 6    | \$2,914 |          |
| <b>Classroom #306 (Regular Classroom)</b>   |                             |           |          |      |      |         |          |
|   | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |          |
|   | Ceiling - Lay-in            | 3rd Floor | 730      | SF   | 6    | \$2,192 |          |
|   | Chalk Board                 | 3rd Floor | 6        | LF   | 4    | \$551   |          |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Wood                | 3rd Floor | 730      | SF   | 6    | \$5,146 |          |
|   | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |          |
|   | Marker Board                | 3rd Floor | 40       | LF   | 7    | \$0     |          |
|   | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |          |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,040    | SF   | 6    | \$2,870 |          |
| <b>Classroom #307 (Regular Classroom)</b>   |                             |           |          |      |      |         |          |
|   | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |          |
|   | Ceiling - Lay-in            | 3rd Floor | 745      | SF   | 6    | \$2,237 |          |
|   | Chalk Board                 | 3rd Floor | 50       | LF   | 4    | \$4,590 |          |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Wood                | 3rd Floor | 745      | SF   | 6    | \$5,252 |          |
|   | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |          |
|   | Marker Board                | 3rd Floor | 15       | LF   | 7    | \$0     |          |
|   | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |          |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments  |
|--|-----------------------------|-----------|----------|------|------|---------|-----------|
| <b>Classroom #307 (Regular Classroom)</b>  |                             |           |          |      |      |         |           |
|  | Walls - Plaster/Drywall     | 3rd Floor | 1,047    | SF   | 6    | \$2,890 |           |
| <b>Classroom #308 (Regular Classroom)</b>  |                             |           |          |      |      |         |           |
|  | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |           |
|  | Ceiling - Lay-in            | 3rd Floor | 735      | SF   | 6    | \$2,207 |           |
|  | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |           |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |           |
|  | Floor - Wood                | 3rd Floor | 735      | SF   | 6    | \$5,182 |           |
|  | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |           |
|  | Marker Board                | 3rd Floor | 46       | LF   | 7    | \$0     |           |
|  | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |           |
|  | Walls - Plaster/Drywall     | 3rd Floor | 1,012    | SF   | 6    | \$2,793 |           |
| <b>Classroom #309A (Regular Classroom)</b> |                             |           |          |      |      |         |           |
|  | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |           |
|  | Ceiling - Lay-in            | 3rd Floor | 622      | SF   | 6    | \$1,868 |           |
|  | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |           |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 3        | EA   | 6    | \$903   |           |
|  | Floor - Wood                | 3rd Floor | 622      | SF   | 6    | \$4,385 |           |
|  | Lighting - Lay-in           | 3rd Floor | 15       | EA   | 6    | \$1,785 |           |
|  | Marker Board                | 3rd Floor | 16       | LF   | 6    | \$343   |           |
|  | Storage/ Closet             | 3rd Floor | 95       | SF   | 6    | \$689   | Room 309B |
|  | Walls - Plaster/Drywall     | 3rd Floor | 953      | SF   | 6    | \$2,630 |           |
| <b>Classroom #310 (Regular Classroom)</b>  |                             |           |          |      |      |         |           |
|  | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |           |
|  | Ceiling - Lay-in            | 3rd Floor | 745      | SF   | 6    | \$2,237 |           |
|  | Chalk Board                 | 3rd Floor | 26       | LF   | 4    | \$2,387 |           |
|  | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |           |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |           |
|  | Floor - Wood                | 3rd Floor | 745      | SF   | 6    | \$5,252 |           |
|  | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |           |
|  | Marker Board                | 3rd Floor | 20       | LF   | 7    | \$0     |           |
|  | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |           |
|  | Walls - Plaster/Drywall     | 3rd Floor | 1,047    | SF   | 6    | \$2,890 |           |
| <b>Classroom #311 (Regular Classroom)</b>  |                             |           |          |      |      |         |           |
|  | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |           |
|  | Ceiling - Lay-in            | 3rd Floor | 725      | SF   | 6    | \$2,177 |           |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                       |
|--|-----------------------------|-----------|----------|------|------|---------|--------------------------------|
| <b>Classroom #311 (Regular Classroom)</b>  |                             |           |          |      |      |         |                                |
|  | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |                                |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |                                |
|  | Floor - Wood                | 3rd Floor | 725      | SF   | 6    | \$5,111 |                                |
|  | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |                                |
|  | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |                                |
|  | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |                                |
|  | Walls - Plaster/Drywall     | 3rd Floor | 980      | SF   | 6    | \$2,705 |                                |
|  | Walls - Plaster/Drywall     | 3rd Floor | 10       | SF   | 5    | \$51    | Peeling cracking paint/plaster |
| <b>Classroom #312 (Regular Classroom)</b>  |                             |           |          |      |      |         |                                |
|  | Casework                    | 3rd Floor | 8        | LF   | 6    | \$202   |                                |
|  | Ceiling - Lay-in            | 3rd Floor | 735      | SF   | 6    | \$2,207 |                                |
|  | Chalk Board                 | 3rd Floor | 20       | LF   | 4    | \$1,836 |                                |
|  | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |                                |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 7    | \$0     |                                |
|  | Floor - Wood                | 3rd Floor | 735      | SF   | 6    | \$5,182 |                                |
|  | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498 |                                |
|  | Marker Board                | 3rd Floor | 24       | LF   | 7    | \$0     |                                |
|  | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |                                |
|  | Walls - Plaster/Drywall     | 3rd Floor | 1,004    | SF   | 6    | \$2,771 |                                |
| <b>Classroom #313A (Regular Classroom)</b> |                             |           |          |      |      |         |                                |
|  | Casework                    | 3rd Floor | 5        | LF   | 6    | \$126   |                                |
|  | Ceiling - Lay-in            | 3rd Floor | 383      | SF   | 6    | \$1,150 |                                |
|  | Ceiling - Lay-in            | 3rd Floor | 20       | SF   | 5    | \$160   | Water damaged tiles,falling.   |
|  | Doors - Transom Window      | 3rd Floor | 6        | SF   | 7    | \$0     |                                |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                                |
|  | Floor - Wood                | 3rd Floor | 403      | SF   | 6    | \$2,841 |                                |
|  | Lighting - Lay-in           | 3rd Floor | 12       | EA   | 6    | \$1,428 |                                |
|  | Marker Board                | 3rd Floor | 30       | LF   | 7    | \$0     |                                |
|  | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |                                |
|  | Walls - Plaster/Drywall     | 3rd Floor | 790      | SF   | 6    | \$2,180 |                                |
| <b>Classroom #313B (Regular Classroom)</b> |                             |           |          |      |      |         |                                |
|  | Casework                    | 3rd Floor | 4        | LF   | 6    | \$101   |                                |
|  | Ceiling - Lay-in            | 3rd Floor | 320      | SF   | 6    | \$961   |                                |
|  | Chalk Board                 | 3rd Floor | 6        | LF   | 4    | \$551   |                                |
|  | Doors - Transom Window      | 3rd Floor | 6        | SF   | 6    | \$102   |                                |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                                |

**Building: Main**
**Category: Classrooms**

| Group                                      | Item - Type                    | Location  | Quantity | Unit | Rank | Cost     | Comments      |
|--|--------------------------------|-----------|----------|------|------|----------|---------------|
| <b>Classroom #313B (Regular Classroom)</b> |                                |           |          |      |      |          |               |
|  | Floor - Wood                   | 3rd Floor | 320      | SF   | 6    | \$2,256  |               |
|  | Lighting - Lay-in              | 3rd Floor | 9        | EA   | 6    | \$1,071  |               |
|  | Marker Board                   | 3rd Floor | 8        | LF   | 6    | \$171    |               |
|  | Walls - Plaster/Drywall        | 3rd Floor | 760      | SF   | 6    | \$2,098  |               |
| <b>Classroom #314A (Regular Classroom)</b> |                                |           |          |      |      |          |               |
|  | Casework                       | 3rd Floor | 8        | LF   | 6    | \$202    |               |
|  | Ceiling - Lay-in               | 3rd Floor | 506      | SF   | 6    | \$1,520  |               |
|  | Chalk Board                    | 3rd Floor | 6        | LF   | 4    | \$551    |               |
|  | Doors - Transom Window         | 3rd Floor | 6        | SF   | 6    | \$102    |               |
|  | Doors - Wood Doors inclu hw    | 3rd Floor | 1        | EA   | 6    | \$301    |               |
|  | Floor - Wood                   | 3rd Floor | 506      | SF   | 6    | \$3,567  |               |
|  | Lighting - Lay-in              | 3rd Floor | 16       | EA   | 6    | \$1,904  |               |
|  | Marker Board                   | 3rd Floor | 18       | LF   | 7    | \$0      |               |
|  | Storage/ Closet                | 3rd Floor | 4        | SF   | 6    | \$29     |               |
|  | Walls - Plaster/Drywall        | 3rd Floor | 860      | SF   | 6    | \$2,374  |               |
| <b>Classroom #315 (Regular Classroom)</b>  |                                |           |          |      |      |          |               |
|  | Ceiling - Plaster/Drywall      | 3rd Floor | 1,450    | SF   | 5    | \$13,291 | Peeling paint |
|  | Chalk Board                    | 3rd Floor | 5        | LF   | 4    | \$459    |               |
|  | Doors - Transom Window         | 3rd Floor | 12       | SF   | 6    | \$203    |               |
|  | Doors - Wood Doors inclu hw    | 3rd Floor | 1        | EA   | 6    | \$301    |               |
|  | Floor - Wood                   | 3rd Floor | 1,450    | SF   | 6    | \$10,222 |               |
|  | Lighting - Pendent/Surface     | 3rd Floor | 12       | EA   | 6    | \$1,487  |               |
|  | Marker Board                   | 3rd Floor | 12       | LF   | 6    | \$257    |               |
|  | Walls - Plaster/Drywall        | 3rd Floor | 992      | SF   | 6    | \$2,738  |               |
|  | Walls - Structural Glazed Tile | 3rd Floor | 1,024    | SF   | 6    | \$3,222  |               |
| <b>Classroom #317 (Regular Classroom)</b>  |                                |           |          |      |      |          |               |
|  | Casework                       | 3rd Floor | 30       | LF   | 6    | \$758    |               |
|  | Ceiling - Lay-in               | 3rd Floor | 790      | SF   | 6    | \$2,372  |               |
|  | Doors - Transom Window         | 3rd Floor | 12       | SF   | 6    | \$203    |               |
|  | Doors - Wood Doors inclu hw    | 3rd Floor | 2        | EA   | 6    | \$602    |               |
|  | Floor - Wood                   | 3rd Floor | 790      | SF   | 6    | \$5,569  |               |
|  | Lighting - Lay-in              | 3rd Floor | 28       | EA   | 6    | \$3,331  |               |
|  | Marker Board                   | 3rd Floor | 10       | LF   | 7    | \$0      |               |
|  | Storage/ Closet                | 3rd Floor | 4        | SF   | 6    | \$29     |               |
|  | Walls - Plaster/Drywall        | 3rd Floor | 1,040    | SF   | 6    | \$2,870  |               |
|  | Work Sink                      | 3rd Floor | 1        | EA   | 6    | \$379    |               |



**Building: Main**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #317 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
| <b>Classroom #318 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | AC Units                    | 3rd Floor | 3        | EA   | 6    | \$1,487 |          |
|   | Casework                    | 3rd Floor | 12       | LF   | 6    | \$303   |          |
|   | Ceiling - Lay-in            | 3rd Floor | 1,552    | SF   | 6    | \$4,661 |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,552    | SF   | 6    | \$1,554 |          |
|   | Lighting - Lay-in           | 3rd Floor | 40       | EA   | 6    | \$4,759 |          |
|   | Marker Board                | 3rd Floor | 18       | LF   | 7    | \$0     |          |
|   | Risers                      | 3rd Floor | 14       | LF   | 6    | \$315   |          |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,664    | SF   | 6    | \$4,592 |          |
| <b>Classroom #320 (Faculty Lounge)</b>    |                             |           |          |      |      |         |          |
|   | AC Units                    | 3rd Floor | 3        | EA   | 6    | \$1,487 |          |
|   | Casework                    | 3rd Floor | 65       | LF   | 6    | \$1,641 |          |
|   | Ceiling - Lay-in            | 3rd Floor | 1,552    | SF   | 6    | \$4,661 |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,552    | SF   | 6    | \$1,554 |          |
|   | Lighting - Lay-in           | 3rd Floor | 40       | EA   | 6    | \$4,759 |          |
|   | Storage/ Closet             | 3rd Floor | 43       | SF   | 6    | \$312   |          |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,664    | SF   | 6    | \$4,592 |          |
| <b>Classroom #321 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | Casework                    | 3rd Floor | 30       | LF   | 6    | \$758   |          |
|   | Ceiling - Lay-in            | 3rd Floor | 790      | SF   | 6    | \$2,372 |          |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Wood                | 3rd Floor | 790      | SF   | 6    | \$5,569 |          |
|   | Lighting - Lay-in           | 3rd Floor | 24       | EA   | 6    | \$2,855 |          |
|   | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |          |
|   | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29    |          |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,040    | SF   | 6    | \$2,870 |          |
|   | Work Sink                   | 3rd Floor | 1        | EA   | 6    | \$379   |          |
| <b>Classroom #325 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | Casework                    | 3rd Floor | 30       | LF   | 6    | \$758   |          |
|   | Ceiling - Lay-in            | 3rd Floor | 790      | SF   | 6    | \$2,372 |          |
|   | Doors - Transom Window      | 3rd Floor | 12       | SF   | 6    | \$203   |          |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |          |

**Building: Main**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost             | Comments                       |
|---|-----------------------------|-----------|----------|------|------|------------------|--------------------------------|
| <b>Classroom #325 (Regular Classroom)</b> |                             |           |          |      |      |                  |                                |
|   | Floor - Wood                | 3rd Floor | 790      | SF   | 6    | \$5,569          |                                |
|   | Lighting - Lay-in           | 3rd Floor | 21       | EA   | 6    | \$2,498          |                                |
|   | Marker Board                | 3rd Floor | 18       | LF   | 7    | \$0              |                                |
|   | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29             |                                |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,040    | SF   | 6    | \$2,870          |                                |
| <b>Classroom #327 (Regular Classroom)</b> |                             |           |          |      |      |                  |                                |
|   | Casework                    | 3rd Floor | 30       | LF   | 6    | \$758            |                                |
|   | Ceiling - Lay-in            | 3rd Floor | 782      | SF   | 6    | \$2,348          |                                |
|   | Ceiling - Lay-in            | 3rd Floor | 8        | SF   | 5    | \$64             | Peeling cracking paint/plaster |
|   | Doors - Transom Window      | 3rd Floor | 6        | SF   | 6    | \$102            |                                |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301            |                                |
|   | Floor - Wood                | 3rd Floor | 790      | SF   | 6    | \$5,569          |                                |
|   | Lighting - Lay-in           | 3rd Floor | 24       | EA   | 6    | \$2,855          |                                |
|   | Marker Board                | 3rd Floor | 12       | LF   | 7    | \$0              |                                |
|   | Storage/ Closet             | 3rd Floor | 4        | SF   | 6    | \$29             |                                |
|   | Walls - Plaster/Drywall     | 3rd Floor | 1,040    | SF   | 6    | \$2,870          |                                |
|   | Work Sink                   | 3rd Floor | 1        | EA   | 6    | \$379            |                                |
| <b>Classrooms Subtotal:</b>               |                             |           |          |      |      | <b>\$957,392</b> |                                |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                     | Location              | Quantity | Unit | Rank | Cost    | Comments                       |
|--------------------------------------|---------------------------------|-----------------------|----------|------|------|---------|--------------------------------|
| <b>Administrative Suites/Offices</b> |                                 |                       |          |      |      |         |                                |
|                                      | AC Unit                         | 102 Main Office       | 1        | EA   | 6    | \$496   |                                |
|                                      | Ceiling - Lay-in                | 102 Main Office       | 468      | SF   | 6    | \$1,405 |                                |
|                                      | Doors - Side-lite               | 102 Main Office       | 6        | SF   | 6    | \$100   | on either side of double doors |
|                                      | Doors - Transom Window          | 102 Main Office       | 8        | SF   | 6    | \$135   |                                |
|                                      | Doors - Wood Doors inclu hw     | 102 Main Office       | 2        | EA   | 6    | \$602   |                                |
|                                      | Floor - Wood                    | 102 Main Office       | 282      | SF   | 6    | \$1,988 |                                |
|                                      | Lighting - Lay-in               | 102 Main Office       | 31       | EA   | 6    | \$3,688 |                                |
|                                      | Power Distribution              | 102 Main Office       | 12       | EA   | 7    | \$0     |                                |
|                                      | Walls - Plaster/Drywall         | 102 Main Office       | 152      | SF   | 6    | \$420   |                                |
|                                      | Walls - Tile Ceramic/ Porcelain | 102 Main Office       | 194      | SF   | 6    | \$438   |                                |
|                                      | AC Unit                         | 102A Principal Office | 1        | EA   | 6    | \$496   |                                |
|                                      | Ceiling - Lay-in                | 102A Principal Office | 194      | SF   | 6    | \$583   |                                |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location              | Quantity | Unit | Rank | Cost    | Comments |
|--------------------------------------|-----------------------------|-----------------------|----------|------|------|---------|----------|
| <b>Administrative Suites/Offices</b> |                             |                       |          |      |      |         |          |
|                                      | Doors - Wood Doors inclu hw | 102A Principal Office | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Wood                | 102A Principal Office | 194      | SF   | 6    | \$1,368 |          |
|                                      | Lighting - Lay-in           | 102A Principal Office | 6        | EA   | 6    | \$714   |          |
|                                      | Power Distribution          | 102A Principal Office | 8        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 102A Principal Office | 485      | SF   | 6    | \$1,339 |          |
|                                      | AC Unit                     | 102B Office           | 1        | EA   | 6    | \$496   |          |
|                                      | Ceiling - Lay-in            | 102B Office           | 140      | SF   | 6    | \$420   |          |
|                                      | Doors - Wood Doors inclu hw | 102B Office           | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Wood                | 102B Office           | 140      | SF   | 6    | \$987   |          |
|                                      | Lighting - Lay-in           | 102B Office           | 6        | EA   | 6    | \$714   |          |
|                                      | Power Distribution          | 102B Office           | 8        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 102B Office           | 516      | SF   | 6    | \$1,424 |          |
|                                      | AC Unit                     | 102C Office           | 1        | EA   | 6    | \$496   |          |
|                                      | Ceiling - Lay-in            | 102C Office           | 140      | SF   | 6    | \$420   |          |
|                                      | Doors - Wood Doors inclu hw | 102C Office           | 1        | EA   | 6    | \$301   |          |
|                                      | Floor - Wood                | 102C Office           | 140      | SF   | 6    | \$987   |          |
|                                      | Lighting - Lay-in           | 102C Office           | 6        | EA   | 6    | \$714   |          |
|                                      | Power Distribution          | 102C Office           | 8        | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 102C Office           | 516      | SF   | 6    | \$1,424 |          |
|                                      | AC Unit                     | 106 Counselor Office  | 2        | EA   | 6    | \$991   |          |
|                                      | Ceiling - Lay-in            | 106 Counselor Office  | 730      | SF   | 6    | \$2,192 |          |
|                                      | Doors - Wood Doors inclu hw | 106 Counselor Office  | 2        | EA   | 6    | \$602   |          |
|                                      | Floor - Tile/Sheet          | 106 Counselor Office  | 730      | SF   | 6    | \$731   |          |
|                                      | Lighting - Lay-in           | 106 Counselor Office  | 21       | EA   | 6    | \$2,498 |          |
|                                      | Power Distribution          | 106 Counselor Office  | 12       | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 106 Counselor Office  | 1,005    | SF   | 6    | \$2,774 |          |
|                                      | AC Unit                     | 110 Counselor Office  | 2        | EA   | 6    | \$991   |          |
|                                      | Ceiling - Lay-in            | 110 Counselor Office  | 730      | SF   | 6    | \$2,192 |          |
|                                      | Doors - Wood Doors inclu hw | 110 Counselor Office  | 2        | EA   | 6    | \$602   |          |
|                                      | Floor - Tile/Sheet          | 110 Counselor Office  | 730      | SF   | 6    | \$731   |          |
|                                      | Lighting - Lay-in           | 110 Counselor Office  | 21       | EA   | 6    | \$2,498 |          |
|                                      | Power Distribution          | 110 Counselor Office  | 14       | EA   | 7    | \$0     |          |
|                                      | Walls - Plaster/Drywall     | 110 Counselor Office  | 1,005    | SF   | 6    | \$2,774 |          |
|                                      | Ceiling - Lay-in            | 110A Counselor Office | 400      | SF   | 6    | \$1,201 |          |
|                                      | Doors - Side-lite           | 110A Counselor Office | 12       | SF   | 6    | \$201   |          |
|                                      | Doors - Transom Window      | 110A Counselor Office | 16       | SF   | 6    | \$271   |          |
|                                      | Doors - Wood Doors inclu hw | 110A Counselor Office | 1        | EA   | 6    | \$301   |          |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location               | Quantity | Unit | Rank | Cost    | Comments     |
|--------------------------------------|-----------------------------|------------------------|----------|------|------|---------|--------------|
| <b>Administrative Suites/Offices</b> |                             |                        |          |      |      |         |              |
|                                      | Floor - Tile/Sheet          | 110A Counselor Office  | 400      | SF   | 6    | \$400   |              |
|                                      | Lighting - Lay-in           | 110A Counselor Office  | 5        | EA   | 6    | \$595   |              |
|                                      | Power Distribution          | 110A Counselor Office  | 8        | EA   | 7    | \$0     |              |
|                                      | Walls - Plaster/Drywall     | 110A Counselor Office  | 1,005    | SF   | 6    | \$2,774 |              |
|                                      | AC Unit                     | 113A Nurse Office      | 1        | EA   | 6    | \$496   |              |
|                                      | Ceiling - Lay-in            | 113A Nurse Office      | 210      | SF   | 6    | \$631   |              |
|                                      | Doors - Wood Doors inclu hw | 113A Nurse Office      | 1        | EA   | 6    | \$301   |              |
|                                      | Floor - Tile/Sheet          | 113A Nurse Office      | 210      | SF   | 6    | \$210   |              |
|                                      | Lighting - Lay-in           | 113A Nurse Office      | 5        | EA   | 6    | \$595   |              |
|                                      | Power Distribution          | 113A Nurse Office      | 8        | EA   | 7    | \$0     |              |
|                                      | Walls - Plaster/Drywall     | 113A Nurse Office      | 390      | SF   | 6    | \$1,076 |              |
|                                      | Work Slnk                   | 113A Nurse Office      | 1        | EA   | 6    | \$508   |              |
|                                      | AC Unit                     | 114 Attendance Office  | 2        | EA   | 6    | \$991   |              |
|                                      | Ceiling - Lay-in            | 114 Attendance Office  | 730      | SF   | 6    | \$2,192 |              |
|                                      | Doors - Transom Window      | 114 Attendance Office  | 16       | SF   | 6    | \$271   |              |
|                                      | Doors - Wood Doors inclu hw | 114 Attendance Office  | 2        | EA   | 6    | \$602   |              |
|                                      | Floor - Tile/Sheet          | 114 Attendance Office  | 730      | SF   | 6    | \$731   |              |
|                                      | Lighting - Lay-in           | 114 Attendance Office  | 21       | EA   | 6    | \$2,498 |              |
|                                      | Power Distribution          | 114 Attendance Office  | 14       | EA   | 7    | \$0     |              |
|                                      | Walls - Plaster/Drywall     | 114 Attendance Office  | 1,005    | SF   | 6    | \$2,774 |              |
|                                      | AC Unit                     | 114A Attendance Office | 1        | EA   | 6    | \$496   |              |
|                                      | Ceiling - Lay-in            | 114A Attendance Office | 133      | SF   | 6    | \$399   |              |
|                                      | Doors - Wood Doors inclu hw | 114A Attendance Office | 1        | EA   | 6    | \$301   |              |
|                                      | Floor - Tile/Sheet          | 114A Attendance Office | 133      | SF   | 6    | \$133   |              |
|                                      | Lighting - Lay-in           | 114A Attendance Office | 3        | EA   | 6    | \$357   |              |
|                                      | Power Distribution          | 114A Attendance Office | 6        | EA   | 7    | \$0     |              |
|                                      | Walls - Plaster/Drywall     | 114A Attendance Office | 252      | SF   | 6    | \$695   | Plywood wall |
|                                      | Walls - Plaster/Drywall     | 114A Attendance Office | 120      | SF   | 6    | \$393   |              |
|                                      | AC Unit                     | 114B Attendance Office | 1        | EA   | 6    | \$496   |              |
|                                      | Ceiling - Lay-in            | 114B Attendance Office | 133      | SF   | 6    | \$399   |              |
|                                      | Doors - Wood Doors inclu hw | 114B Attendance Office | 1        | EA   | 6    | \$301   |              |
|                                      | Floor - Tile/Sheet          | 114B Attendance Office | 133      | SF   | 6    | \$133   |              |
|                                      | Lighting - Lay-in           | 114B Attendance Office | 2        | EA   | 6    | \$238   |              |
|                                      | Power Distribution          | 114B Attendance Office | 6        | EA   | 7    | \$0     |              |
|                                      | Walls - Plaster/Drywall     | 114B Attendance Office | 252      | SF   | 6    | \$695   | Plywood wall |
|                                      | Walls - Plaster/Drywall     | 114B Attendance Office | 120      | SF   | 6    | \$393   |              |
|                                      | AC Unit                     | 114C Attendance Office | 1        | EA   | 6    | \$496   |              |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location                | Quantity | Unit | Rank | Cost    | Comments                            |
|--------------------------------------|-----------------------------|-------------------------|----------|------|------|---------|-------------------------------------|
| <b>Administrative Suites/Offices</b> |                             |                         |          |      |      |         |                                     |
|                                      | Ceiling - Lay-in            | 114C Attendance Office  | 133      | SF   | 6    | \$399   |                                     |
|                                      | Doors - Wood Doors inclu hw | 114C Attendance Office  | 1        | EA   | 6    | \$301   |                                     |
|                                      | Floor - Tile/Sheet          | 114C Attendance Office  | 133      | SF   | 6    | \$133   |                                     |
|                                      | Lighting - Lay-in           | 114C Attendance Office  | 2        | EA   | 6    | \$238   |                                     |
|                                      | Power Distribution          | 114C Attendance Office  | 6        | EA   | 7    | \$0     |                                     |
|                                      | Walls - Plaster/Drywall     | 114C Attendance Office  | 252      | SF   | 6    | \$695   | Plywood wall                        |
|                                      | Walls - Plaster/Drywall     | 114C Attendance Office  | 120      | SF   | 6    | \$393   |                                     |
|                                      | Ceiling - Plaster/Drywall   | 118 Office              | 122      | SF   | 6    | \$422   |                                     |
|                                      | Doors - Wood Doors inclu hw | 118 Office              | 1        | EA   | 6    | \$301   |                                     |
|                                      | Floor - Tile/Sheet          | 118 Office              | 122      | SF   | 6    | \$122   |                                     |
|                                      | Lighting - Pendent/Surface  | 118 Office              | 2        | EA   | 6    | \$248   |                                     |
|                                      | Power Distribution          | 118 Office              | 4        | EA   | 7    | \$0     |                                     |
|                                      | Walls - Concrete Block      | 118 Office              | 571      | SF   | 6    | \$1,674 |                                     |
|                                      | Ceiling - Plaster/Drywall   | 137 (Engineer's Office) | 150      | SF   | 6    | \$519   |                                     |
|                                      | Floor - Concrete            | 137 (Engineer's Office) | 150      | SF   | 6    | \$79    |                                     |
|                                      | Lighting - Pendent/Surface  | 137 (Engineer's Office) | 1        | EA   | 6    | \$124   |                                     |
|                                      | Power Distribution          | 137 (Engineer's Office) | 4        | EA   | 7    | \$0     |                                     |
|                                      | Walls - Plaster/Drywall     | 137 (Engineer's Office) | 720      | SF   | 6    | \$1,987 |                                     |
|                                      | AC Unit                     | 215B Boys gym office    | 1        | EA   | 6    | \$496   |                                     |
|                                      | Ceiling - Lay-in            | 215B Boys gym office    | 256      | SF   | 6    | \$769   |                                     |
|                                      | Doors - Wood Doors inclu hw | 215B Boys gym office    | 2        | EA   | 6    | \$602   |                                     |
|                                      | Floor - Wood                | 215B Boys gym office    | 256      | SF   | 6    | \$1,805 |                                     |
|                                      | Lighting - Lay-in           | 215B Boys gym office    | 4        | EA   | 7    | \$0     |                                     |
|                                      | Power Distribution          | 215B Boys gym office    | 24       | EA   | 7    | \$0     |                                     |
|                                      | Walls - Plaster/Drywall     | 215B Boys gym office    | 655      | SF   | 6    | \$1,808 |                                     |
|                                      | Work Slnk                   | 215B Boys gym office    | 1        | EA   | 6    | \$508   |                                     |
|                                      | AC Unit                     | 223B girls gym office   | 1        | EA   | 6    | \$496   |                                     |
|                                      | Ceiling - Plaster/Drywall   | 223B girls gym office   | 258      | SF   | 6    | \$893   |                                     |
|                                      | Doors - Wood Doors inclu hw | 223B girls gym office   | 2        | EA   | 6    | \$602   |                                     |
|                                      | Floor - Wood                | 223B girls gym office   | 258      | SF   | 6    | \$1,819 |                                     |
|                                      | Lighting - Lay-in           | 223B girls gym office   | 4        | EA   | 7    | \$0     |                                     |
|                                      | Power Distribution          | 223B girls gym office   | 21       | EA   | 7    | \$0     |                                     |
|                                      | Walls - Plaster/Drywall     | 223B girls gym office   | 661      | SF   | 6    | \$1,824 |                                     |
|                                      | Work Slnk                   | 223B girls gym office   | 1        | EA   | 6    | \$508   |                                     |
|                                      | AC Unit                     | 314B                    | 1        | EA   | 6    | \$496   | Free standing                       |
|                                      | Ceiling - Lay-in            | 314B                    | 160      | SF   | 6    | \$480   |                                     |
|                                      | Ceiling - Lay-in            | 314B                    | 10       | SF   | 4    | \$141   | Water stained/damaged ceiling tiles |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                     | Location                            | Quantity | Unit | Rank | Cost    | Comments               |
|--------------------------------------|---------------------------------|-------------------------------------|----------|------|------|---------|------------------------|
| <b>Administrative Suites/Offices</b> |                                 |                                     |          |      |      |         |                        |
|                                      | Doors - Steel Doors incl hw     | 314B                                | 1        | EA   | 6    | \$301   |                        |
|                                      | Doors - Transom Window          | 314B                                | 6        | SF   | 6    | \$102   |                        |
|                                      | Doors - Wood Doors inclu hw     | 314B                                | 1        | EA   | 6    | \$301   |                        |
|                                      | Floor - Wood                    | 314B                                | 170      | SF   | 6    | \$1,198 |                        |
|                                      | Lighting - Lay-in               | 314B                                | 5        | EA   | 6    | \$595   |                        |
|                                      | Power Distribution              | 314B                                | 8        | EA   | 7    | \$0     |                        |
|                                      | Walls - Plaster/Drywall         | 314B                                | 490      | SF   | 6    | \$1,352 |                        |
|                                      | Walls - Plaster/Drywall         | 314B                                | 10       | SF   | 5    | \$51    | Water damage at window |
|                                      | Ceiling - Plaster/Drywall       | ID Room                             | 311      | SF   | 6    | \$1,076 |                        |
|                                      | Doors - Wood Doors inclu hw     | ID Room                             | 1        | EA   | 6    | \$301   |                        |
|                                      | Floor - Tile Ceramic/ Porcelain | ID Room                             | 311      | SF   | 6    | \$658   |                        |
|                                      | Lighting - Pendent/Surface      | ID Room                             | 5        | EA   | 6    | \$619   |                        |
|                                      | Power Distribution              | ID Room                             | 6        | EA   | 7    | \$0     |                        |
|                                      | Walls - Structural Glazed Tile  | ID Room                             | 750      | SF   | 6    | \$2,360 |                        |
|                                      | Ceiling - Exposed               | In Basement Former ROTC Rifle Range | 822      | SF   | 6    | \$1,222 |                        |
|                                      | Doors - Wood Doors inclu hw     | In Basement Former ROTC Rifle Range | 1        | EA   | 6    | \$301   |                        |
|                                      | Floor - Concrete                | In Basement Former ROTC Rifle Range | 822      | SF   | 6    | \$435   |                        |
|                                      | Lighting - Pendent/Surface      | In Basement Former ROTC Rifle Range | 16       | EA   | 6    | \$1,982 |                        |
|                                      | Power Distribution              | In Basement Former ROTC Rifle Range | 12       | EA   | 7    | \$0     |                        |
|                                      | Walls - Concrete Block          | In Basement Former ROTC Rifle Range | 800      | SF   | 6    | \$2,345 |                        |
|                                      | Walls - Plaster/Drywall         | In Basement Former ROTC Rifle Range | 1,200    | SF   | 6    | \$3,312 |                        |
|                                      | AC Unit                         | Library Workroom                    | 1        | EA   | 6    | \$496   |                        |
|                                      | Ceiling - Lay-in                | Library Workroom                    | 210      | SF   | 6    | \$631   |                        |
|                                      | Doors - Wood Doors inclu hw     | Library Workroom                    | 1        | EA   | 6    | \$301   |                        |
|                                      | Floor - Tile/Sheet              | Library Workroom                    | 210      | SF   | 6    | \$210   |                        |
|                                      | Lighting - Lay-in               | Library Workroom                    | 5        | EA   | 6    | \$595   |                        |
|                                      | Power Distribution              | Library Workroom                    | 6        | EA   | 7    | \$0     |                        |
|                                      | Walls - Plaster/Drywall         | Library Workroom                    | 390      | SF   | 6    | \$1,076 |                        |
|                                      | Ceiling - Lay-in                | Lunchroom Manager's Office          | 77       | SF   | 6    | \$231   |                        |
|                                      | Doors - Wood Doors inclu hw     | Lunchroom Manager's Office          | 1        | EA   | 6    | \$301   |                        |
|                                      | Floor - Tile/Sheet              | Lunchroom Manager's Office          | 77       | SF   | 6    | \$77    |                        |
|                                      | Lighting - Lay-in               | Lunchroom Manager's Office          | 1        | EA   | 7    | \$0     |                        |
|                                      | Power Distribution              | Lunchroom Manager's Office          | 12       | EA   | 7    | \$0     |                        |
|                                      | Walls - Concrete Block          | Lunchroom Manager's Office          | 142      | SF   | 6    | \$416   |                        |
|                                      | Walls - Structural Glazed Tile  | Lunchroom Manager's Office          | 142      | SF   | 6    | \$447   |                        |
|                                      | Ceiling - Plaster/Drywall       | Next to Room 214                    | 185      | SF   | 6    | \$640   |                        |
|                                      | Doors - Transom Window          | Next to Room 214                    | 6        | SF   | 6    | \$102   |                        |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                     | Location         | Quantity | Unit | Rank | Cost    | Comments             |
|--------------------------------------|---------------------------------|------------------|----------|------|------|---------|----------------------|
| <b>Administrative Suites/Offices</b> |                                 |                  |          |      |      |         |                      |
|                                      | Doors - Wood Doors inclu hw     | Next to Room 214 | 2        | EA   | 6    | \$602   |                      |
|                                      | Floor - Wood                    | Next to Room 214 | 185      | SF   | 6    | \$1,304 |                      |
|                                      | Lighting - Pendent/Surface      | Next to Room 214 | 5        | EA   | 7    | \$0     |                      |
|                                      | Power Distribution              | Next to Room 214 | 8        | EA   | 7    | \$0     |                      |
|                                      | Walls - Plaster/Drywall         | Next to Room 214 | 583      | SF   | 6    | \$1,609 |                      |
|                                      | Ceiling - Plaster/Drywall       | Pool Office      | 61       | SF   | 6    | \$211   |                      |
|                                      | Doors - Steel Doors incl hw     | Pool Office      | 1        | EA   | 6    | \$301   |                      |
|                                      | Floor - Tile Ceramic/ Porcelain | Pool Office      | 61       | SF   | 6    | \$129   |                      |
|                                      | Lighting - Pendent/Surface      | Pool Office      | 1        | EA   | 6    | \$124   |                      |
|                                      | Power Distribution              | Pool Office      | 4        | EA   | 7    | \$0     |                      |
|                                      | Walls - Structural Glazed Tile  | Pool Office      | 246      | SF   | 6    | \$774   |                      |
|                                      | Ceiling - Plaster/Drywall       | Rm 319           | 122      | SF   | 6    | \$422   |                      |
|                                      | Doors - Transom Window          | Rm 319           | 6        | SF   | 6    | \$102   |                      |
|                                      | Doors - Wood Doors inclu hw     | Rm 319           | 1        | EA   | 6    | \$301   |                      |
|                                      | Floor - Tile                    | Rm 319           | 122      | SF   | 6    | \$267   |                      |
|                                      | Lighting - Pendent/Surface      | Rm 319           | 2        | EA   | 4    | \$1,081 | T12                  |
|                                      | Power Distribution              | Rm 319           | 3        | EA   | 7    | \$0     |                      |
|                                      | Storage/ Closet                 | Rm 319           | 45       | SF   | 6    | \$326   |                      |
|                                      | Walls - Plaster/Drywall         | Rm 319           | 340      | SF   | 6    | \$938   |                      |
|                                      | Ceiling - Plaster/Drywall       | Rm218 office     | 120      | SF   | 6    | \$415   |                      |
|                                      | Doors - Transom Window          | Rm218 office     | 6        | SF   | 6    | \$102   |                      |
|                                      | Doors - Wood Doors inclu hw     | Rm218 office     | 1        | EA   | 6    | \$301   |                      |
|                                      | Floor - Tile                    | Rm218 office     | 114      | SF   | 6    | \$249   |                      |
|                                      | Floor - Tile                    | Rm218 office     | 6        | SF   | 5    | \$35    | Missing/broken tiles |
|                                      | Lighting - Pendent/Surface      | Rm218 office     | 2        | EA   | 4    | \$1,081 | T12                  |
|                                      | Power Distribution              | Rm218 office     | 4        | EA   | 7    | \$0     |                      |
|                                      | Walls - Plaster/Drywall         | Rm218 office     | 567      | SF   | 6    | \$1,565 |                      |
|                                      | Ceiling - Plaster/Drywall       | Room 222A        | 150      | SF   | 6    | \$519   |                      |
|                                      | Doors - Transom Window          | Room 222A        | 6        | SF   | 6    | \$102   |                      |
|                                      | Doors - Wood Doors inclu hw     | Room 222A        | 1        | EA   | 6    | \$301   |                      |
|                                      | Floor - Tile                    | Room 222A        | 150      | SF   | 6    | \$328   |                      |
|                                      | Lighting - Pendent/Surface      | Room 222A        | 2        | EA   | 7    | \$0     |                      |
|                                      | Power Distribution              | Room 222A        | 7        | EA   | 7    | \$0     |                      |
|                                      | Storage/ Closet                 | Room 222A        | 12       | SF   | 6    | \$87    |                      |
|                                      | Walls - Plaster/Drywall         | Room 222A        | 720      | SF   | 6    | \$1,987 |                      |
|                                      | Ceiling - Plaster/Drywall       | Room 222B        | 115      | SF   | 6    | \$398   |                      |
|                                      | Doors - Wood Doors inclu hw     | Room 222B        | 1        | EA   | 6    | \$301   |                      |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                          | Location                | Quantity | Unit | Rank | Cost     | Comments                        |
|--------------------------------------|--------------------------------------|-------------------------|----------|------|------|----------|---------------------------------|
| <b>Administrative Suites/Offices</b> |                                      |                         |          |      |      |          |                                 |
|                                      | Floor - Carpet                       | Room 222B               | 115      | SF   | 5    | \$590    | Stained/odor                    |
|                                      | Lighting - Pendent/Surface           | Room 222B               | 1        | EA   | 4    | \$541    | T12                             |
|                                      | Power Distribution                   | Room 222B               | 3        | EA   | 7    | \$0      |                                 |
|                                      | Storage/ Closet                      | Room 222B               | 9        | SF   | 6    | \$65     |                                 |
|                                      | Walls - Plaster/Drywall              | Room 222B               | 670      | SF   | 6    | \$1,849  |                                 |
|                                      | Walls - Plaster/Drywall              | Room 222B               | 10       | SF   | 5    | \$51     | Peeling paint                   |
|                                      | AC Unit                              | Room 222C               | 1        | EA   | 6    | \$496    |                                 |
|                                      | Ceiling - Plaster/Drywall            | Room 222C               | 150      | SF   | 6    | \$519    |                                 |
|                                      | Doors - Transom Window               | Room 222C               | 6        | SF   | 6    | \$102    |                                 |
|                                      | Doors - Wood Doors inclu hw          | Room 222C               | 1        | EA   | 6    | \$301    |                                 |
|                                      | Floor - Concrete                     | Room 222C               | 150      | SF   | 6    | \$79     |                                 |
|                                      | Lighting - Pendent/Surface           | Room 222C               | 1        | EA   | 4    | \$541    | T12                             |
|                                      | Power Distribution                   | Room 222C               | 7        | EA   | 7    | \$0      |                                 |
|                                      | Storage/ Closet                      | Room 222C               | 9        | SF   | 6    | \$65     |                                 |
|                                      | Walls - Plaster/Drywall              | Room 222C               | 720      | SF   | 6    | \$1,987  |                                 |
| <b>Auditorium &amp; Theater</b>      |                                      |                         |          |      |      |          |                                 |
|                                      | Balcony Seating                      | 1st Floor               | 240      | EA   | 6    | \$41,740 |                                 |
|                                      | Ceiling - Plaster/Drywall            | 1st Floor               | 6,277    | SF   | 6    | \$52,331 |                                 |
|                                      | Doors - Wood Doors inclu hw          | 1st Floor               | 2        | EA   | 6    | \$602    |                                 |
|                                      | Floor - Concrete                     | 1st Floor               | 6,277    | SF   | 6    | \$3,321  |                                 |
|                                      | Lighting - Pendent/Surface           | 1st Floor               | 55       | EA   | 6    | \$6,814  |                                 |
|                                      | Main Floor Seating                   | 1st Floor               | 465      | EA   | 6    | \$80,871 |                                 |
|                                      | Sound System                         | 1st Floor               | 1        | EA   | 6    | \$10,721 |                                 |
|                                      | Stage                                | 1st Floor               | 955      | SF   | 6    | \$5,517  |                                 |
|                                      | Stage Curtain                        | 1st Floor               | 8        | EA   | 6    | \$0      |                                 |
|                                      | Stage Lighting System                | 1st Floor               | 1        | EA   | 6    | \$8,077  |                                 |
|                                      | Stage-Stairs - Wood                  | 1st Floor               | 2        | LF   | 6    | \$23     |                                 |
|                                      | Stairs - Terrazzo                    | 1st Floor               | 2        | LF   | 7    | \$0      |                                 |
|                                      | Walls - Plaster/Drywall              | 1st Floor               | 10,272   | SF   | 6    | \$48,914 |                                 |
| <b>Gymnasia</b>                      |                                      |                         |          |      |      |          |                                 |
|                                      | Bleacher Seating                     | 219 Boys Gym, 2nd Floor | 60       | EA   | 6    | \$1,737  |                                 |
|                                      | Ceiling - Plaster/Drywall            | 219 Boys Gym, 2nd Floor | 5,983    | SF   | 5    | \$86,156 | Peeling/cracking, paint/plaster |
|                                      | Doors - Transom Window               | 219 Boys Gym, 2nd Floor | 24       | SF   | 6    | \$406    | Solid wood panels               |
|                                      | Doors - Wood Doors inclu hw          | 219 Boys Gym, 2nd Floor | 4        | EA   | 6    | \$1,204  |                                 |
|                                      | Floor - Wood                         | 219 Boys Gym, 2nd Floor | 5,983    | SF   | 6    | \$42,180 |                                 |
|                                      | Lighting - Metal Halide/Sodium Vapor | 219 Boys Gym, 2nd Floor | 18       | EA   | 6    | \$2,407  |                                 |



**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                          | Location                       | Quantity | Unit | Rank | Cost     | Comments   |
|-----------------|--------------------------------------|--------------------------------|----------|------|------|----------|--|
| <b>Gymnasia</b> |                                      |                                |          |      |      |          |  |
|                 | Scoreboards                          | 219 Boys Gym, 2nd Floor        | 1        | EA   | 6    | \$2,244  |  |
|                 | Sound System                         | 219 Boys Gym, 2nd Floor        | 1        | EA   | 6    | \$41,654 |  |
|                 | Storage/ Closet                      | 219 Boys Gym, 2nd Floor        | 90       | SF   | 6    | \$653    |  |
|                 | Walls - Plaster/Drywall              | 219 Boys Gym, 2nd Floor        | 700      | SF   | 6    | \$1,932  |  |
|                 | Walls - Plaster/Drywall              | 219 Boys Gym, 2nd Floor        | 100      | SF   | 3    | \$1,815  | Major water damage, broken falling plaster.              |
|                 | Walls - Structural Glazed Tile       | 219 Boys Gym, 2nd Floor        | 8,640    | SF   | 6    | \$27,181 | South East corner vertical cracking in structural brick. |
|                 | Ceiling - Plaster/Drywall            | Girls Gym, 2nd Floor           | 5,972    | SF   | 5    | \$85,997 | Peeling/cracking, paint/plaster                          |
|                 | Doors - Transom Window               | Girls Gym, 2nd Floor           | 24       | SF   | 6    | \$406    | Solid wood panel   |
|                 | Doors - Wood Doors inclu hw          | Girls Gym, 2nd Floor           | 4        | EA   | 6    | \$1,204  |  |
|                 | Floor - Wood                         | Girls Gym, 2nd Floor           | 5,972    | SF   | 6    | \$42,102 |  |
|                 | Lighting - Metal Halide/Sodium Vapor | Girls Gym, 2nd Floor           | 18       | EA   | 6    | \$2,407  |  |
|                 | Sound System                         | Girls Gym, 2nd Floor           | 1        | EA   | 6    | \$41,654 |  |
|                 | Storage/ Closet                      | Girls Gym, 2nd Floor           | 110      | SF   | 6    | \$798    |  |
|                 | Walls - Plaster/Drywall              | Girls Gym, 2nd Floor           | 777      | SF   | 6    | \$2,144  |  |
|                 | Walls - Structural Glazed Tile       | Girls Gym, 2nd Floor           | 8,629    | SF   | 6    | \$27,147 |  |
| <b>Kitchen</b>  |                                      |                                |          |      |      |          |  |
|                 | Ceiling - Lay-in                     | 316B Kitchen                   | 520      | SF   | 6    | \$1,562  |  |
|                 | Doors - Transom Window               | 316B Kitchen                   | 12       | SF   | 6    | \$203    |  |
|                 | Doors - Wood Doors inclu hw          | 316B Kitchen                   | 2        | EA   | 6    | \$602    |  |
|                 | Floor - Tile/Sheet                   | 316B Kitchen                   | 520      | SF   | 6    | \$521    |  |
|                 | Lighting - Lay-in                    | 316B Kitchen                   | 16       | EA   | 7    | \$0      |  |
|                 | Walls - Structural Glazed Tile       | 316B Kitchen                   | 723      | SF   | 6    | \$2,275  |  |
|                 | Ceiling - Plaster/Drywall            | Warming kitchen next to rm 318 | 213      | SF   | 5    | \$1,952  | Peeling cracking paint/plaster                           |
|                 | Doors - Transom Window               | Warming kitchen next to rm 318 | 213      | SF   | 6    | \$3,606  |  |
|                 | Doors - Wood Doors inclu hw          | Warming kitchen next to rm 318 | 1        | EA   | 6    | \$301    |  |
|                 | Floor - Terrazzo                     | Warming kitchen next to rm 318 | 213      | SF   | 6    | \$466    |  |
|                 | Lighting - Pendent/Surface           | Warming kitchen next to rm 318 | 5        | EA   | 4    | \$2,703  | T12  |
|                 | Walls - Structural Glazed Tile       | Warming kitchen next to rm 318 | 780      | SF   | 6    | \$2,454  |  |
| <b>Library</b>  |                                      |                                |          |      |      |          |  |
|                 | AC Unit                              | 101 Library                    | 3        | EA   | 6    | \$1,487  |  |
|                 | Casework                             | 101 Library                    | 150      | LF   | 6    | \$3,788  |  |
|                 | Ceiling - Plaster/Drywall            | 101 Library                    | 2,043    | SF   | 6    | \$7,070  |  |
|                 | Doors - Transom Window               | 101 Library                    | 24       | SF   | 6    | \$406    |  |
|                 | Doors - Wood Doors inclu hw          | 101 Library                    | 3        | EA   | 6    | \$903    |  |
|                 | Floor - Tile/Sheet                   | 101 Library                    | 2,043    | SF   | 6    | \$2,045  |  |
|                 | Lighting - Pendent/Surface           | 101 Library                    | 72       | EA   | 6    | \$8,920  |  |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                     | Item - Type                     | Location                                   | Quantity | Unit | Rank | Cost     | Comments |
|---------------------------|---------------------------------|--|----------|------|------|----------|----------|
| <b>Library</b>            | Walls - Plaster/Drywall         | 101 Library                                | 2,600    | SF   | 6    | \$7,176  |          |
| <b>Locker/Shower Room</b> | Accessories                     | Boys Locker Room, 1st Floor                | 3,270    | SF   | 6    | \$12,813 |          |
|                           | Benches, ped mounted            | Boys Locker Room, 1st Floor                | 66       | LF   | 6    | \$7,186  |          |
|                           | Ceiling - Plaster/ Drywall      | Boys Locker Room, 1st Floor                | 3,270    | SF   | 6    | \$11,316 |          |
|                           | Doors - Steel Doors incl hw     | Boys Locker Room, 1st Floor                | 2        | EA   | 6    | \$602    |          |
|                           | Floor Drain                     | Boys Locker Room, 1st Floor                | 6        | EA   | 6    | \$6,355  |          |
|                           | Floor - Tile Ceramic/ Porcelain | Boys Locker Room, 1st Floor                | 3,270    | SF   | 6    | \$6,921  |          |
|                           | Hand Dryer                      | Boys Locker Room, 1st Floor                | 8        | EA   | 6    | \$1,840  |          |
|                           | Lavatory                        | Boys Locker Room, 1st Floor                | 1        | EA   | 6    | \$320    |          |
|                           | Lighting - Pendent/Surface      | Boys Locker Room, 1st Floor                | 93       | EA   | 6    | \$11,522 |          |
|                           | Partitions                      | Boys Locker Room, 1st Floor                | 10       | EA   | 6    | \$2,969  |          |
|                           | Showers                         | Boys Locker Room, 1st Floor                | 14       | EA   | 6    | \$4,360  |          |
|                           | Student Lockers - Two Tier      | Boys Locker Room, 1st Floor                | 1,000    | EA   | 6    | \$46,418 |          |
|                           | Urinals                         | Boys Locker Room, 1st Floor                | 4        | EA   | 6    | \$1,344  |          |
|                           | Walls - Structural Glazed Tile  | Boys Locker Room, 1st Floor                | 5,160    | SF   | 6    | \$16,233 |          |
|                           | Water Closet                    | Boys Locker Room, 1st Floor                | 3        | EA   | 6    | \$1,008  |          |
|                           | Accessories                     | Girl's Locker Room, 1st Floor              | 5,694    | SF   | 6    | \$22,310 |          |
|                           | Benches, ped mounted            | Girl's Locker Room, 1st Floor              | 114      | LF   | 6    | \$12,412 |          |
|                           | Ceiling - Plaster/ Drywall      | Girl's Locker Room, 1st Floor              | 5,694    | SF   | 6    | \$19,705 |          |
|                           | Floor Drain                     | Girl's Locker Room, 1st Floor              | 10       | EA   | 6    | \$10,592 |          |
|                           | Floor - Tile Ceramic/ Porcelain | Girl's Locker Room, 1st Floor              | 5,694    | SF   | 6    | \$12,051 |          |
|                           | Hand Dryer                      | Girl's Locker Room, 1st Floor              | 20       | EA   | 6    | \$4,601  |          |
|                           | Lavatory                        | Girl's Locker Room, 1st Floor              | 1        | EA   | 6    | \$320    |          |
|                           | Lighting - Pendent/Surface      | Girl's Locker Room, 1st Floor              | 85       | EA   | 6    | \$10,531 |          |
|                           | Partitions                      | Girl's Locker Room, 1st Floor              | 15       | EA   | 6    | \$4,454  |          |
|                           | Showers                         | Girl's Locker Room, 1st Floor              | 52       | EA   | 6    | \$16,193 |          |
|                           | Student Lockers - Two Tier      | Girl's Locker Room, 1st Floor              | 900      | EA   | 6    | \$41,776 |          |
|                           | Walls - Structural Glazed Tile  | Girl's Locker Room, 1st Floor              | 8,559    | SF   | 6    | \$26,927 |          |
|                           | Water Closet                    | Girl's Locker Room, 1st Floor              | 5        | EA   | 6    | \$1,680  |          |
|                           | Accessories                     | Next to girls restroom across from lunchrm | 120      | SF   | 6    | \$470    |          |
|                           | Ceiling - Plaster/ Drywall      | Next to girls restroom across from lunchrm | 215      | SF   | 6    | \$744    |          |
|                           | Doors - Transom Window          | Next to girls restroom across from lunchrm | 12       | SF   | 6    | \$203    |          |
|                           | Doors - Wood Doors inclu hw     | Next to girls restroom across from lunchrm | 2        | EA   | 6    | \$602    |          |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                     | Location                                   | Quantity | Unit | Rank | Cost     | Comments                    |
|--------------------------------------|---------------------------------|--|----------|------|------|----------|-----------------------------|
| <b>Locker/Shower Room</b>            |                                 |  |          |      |      |          |                             |
|                                      | Floor - Tile Ceramic/ Porcelain | Next to girls restroom across from lunchrm | 95       | SF   | 6    | \$201    |                             |
|                                      | Floor - Tile/Sheet              | Next to girls restroom across from lunchrm | 120      | SF   | 6    | \$120    |                             |
|                                      | Hand Dryer                      | Next to girls restroom across from lunchrm | 1        | EA   | 6    | \$230    |                             |
|                                      | Lavatory                        | Next to girls restroom across from lunchrm | 1        | EA   | 6    | \$320    |                             |
|                                      | Lighting - Lay-in               | Next to girls restroom across from lunchrm | 2        | EA   | 7    | \$0      |                             |
|                                      | Lighting - Pendent/Surface      | Next to girls restroom across from lunchrm | 2        | EA   | 4    | \$1,081  | T12                         |
|                                      | Partitions                      | Next to girls restroom across from lunchrm | 2        | EA   | 6    | \$594    |                             |
|                                      | Student Lockers - One Tier      | Next to girls restroom across from lunchrm | 16       | EA   | 6    | \$1,485  |                             |
|                                      | Walls - Masonry                 | Next to girls restroom across from lunchrm | 138      | SF   | 6    | \$434    | Toilet stalls               |
|                                      | Walls - Plaster/Drywall         | Next to girls restroom across from lunchrm | 917      | SF   | 6    | \$2,531  |                             |
|                                      | Water Closet                    | Next to girls restroom across from lunchrm | 2        | EA   | 6    | \$672    |                             |
| <b>Lunch &amp; Multipurpose Room</b> |                                 |  |          |      |      |          |                             |
|                                      | Ceiling - Lay-in                | 316 Lunch room/ Cafeteria                  | 4,505    | SF   | 6    | \$13,529 |                             |
|                                      | Ceiling - Lay-in                | 316 Lunch room/ Cafeteria                  | 50       | SF   | 3    | \$703    | water damage, missing tiles |
|                                      | Doors - Transom Window          | 316 Lunch room/ Cafeteria                  | 24       | SF   | 6    | \$406    |                             |
|                                      | Doors - Wood Doors inclu hw     | 316 Lunch room/ Cafeteria                  | 4        | EA   | 6    | \$1,204  |                             |
|                                      | Floor - Tile/Sheet              | 316 Lunch room/ Cafeteria                  | 4,555    | SF   | 6    | \$4,560  |                             |
|                                      | Lighting - Lay-in               | 316 Lunch room/ Cafeteria                  | 78       | EA   | 6    | \$9,280  |                             |
|                                      | Serving Line                    | 316 Lunch room/ Cafeteria                  | 16       | LF   | 6    | \$952    |                             |
|                                      | Walls - Plaster/Drywall         | 316 Lunch room/ Cafeteria                  | 2,761    | SF   | 6    | \$7,620  |                             |
|                                      | Walls - Structural Glazed Tile  | 316 Lunch room/ Cafeteria                  | 2,761    | SF   | 6    | \$8,686  |                             |
|                                      | Ceiling - Lay-in                | 316 servery                                | 1,060    | SF   | 6    | \$3,183  |                             |
|                                      | Doors - Transom Window          | 316 servery                                | 9        | SF   | 6    | \$152    | Only at one entrance door   |
|                                      | Doors - Wood Doors inclu hw     | 316 servery                                | 5        | EA   | 6    | \$1,505  |                             |
|                                      | Floor - Tile/Sheet              | 316 servery                                | 1,031    | SF   | 6    | \$1,032  |                             |
|                                      | Lighting - Lay-in               | 316 servery                                | 24       | EA   | 6    | \$2,855  |                             |
|                                      | Serving Line                    | 316 servery                                | 63       | LF   | 6    | \$3,750  |                             |
|                                      | Storage/ Closet                 | 316 servery                                | 330      | SF   | 6    | \$2,393  |                             |
|                                      | Walls - Plaster/Drywall         | 316 servery                                | 593      | SF   | 6    | \$1,637  |                             |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                    | Location            | Quantity | Unit | Rank | Cost      | Comments   |
|--------------------------------------|--------------------------------|---------------------|----------|------|------|-----------|--|
| <b>Lunch &amp; Multipurpose Room</b> |                                |                     |          |      |      |           |  |
|                                      | Walls - Structural Glazed Tile | 316 servery         | 593      | SF   | 6    | \$1,866   |  |
| <b>MDF_IDF</b>                       |                                |                     |          |      |      |           |  |
|                                      | Doors - Wood Doors inclu hw    | Across from rm 209B | 1        | EA   | 6    | \$301     |  |
|                                      | Finishes                       | Across from rm 209B | 80       | SF   | 6    | \$571     |  |
|                                      | Ventilation and Cooling        | Across from rm 209B | 1        | EA   | 6    | \$1,855   |  |
|                                      | Doors - Wood Doors inclu hw    | Across from rm 218  | 1        | EA   | 6    | \$301     |  |
|                                      | Finishes                       | Across from rm 218  | 80       | SF   | 6    | \$571     |  |
|                                      | Ventilation and Cooling        | Across from rm 218  | 1        | EA   | 6    | \$1,855   |  |
| <b>Mechanical/ Service Rooms</b>     |                                |                     |          |      |      |           |  |
|                                      | Boiler Room                    | 1st Floor           | 6,036    | SF   | 6    | \$43,244  |  |
|                                      | Janitor's Closet               | 1st Floor           | 230      | SF   | 6    | \$1,648   |  |
|                                      | Loading Docks                  | 1st Floor           | 340      | SF   | 6    | \$2,436   |  |
|                                      | Mechanical/ Service Rooms      | 1st Floor           | 1,520    | SF   | 6    | \$10,890  |  |
|                                      | Storage Room                   | 1st Floor           | 508      | SF   | 6    | \$3,639   | 1A Storage room  |
|                                      | Storage Room                   | 1st Floor           | 380      | SF   | 6    | \$2,722   | Outside yard storage - inside loading dock               |
|                                      | Interior Stairs                | 2nd Floor           | 5        | LF   | 6    | \$45      | In auditorium light rm. (Steel)                          |
|                                      | Janitor's Closet               | 2nd Floor           | 20       | SF   | 6    | \$143     | In boys restroom   |
|                                      | Janitor's Closet               | 2nd Floor           | 20       | SF   | 6    | \$143     | Boys restroom 213B                                       |
|                                      | Mechanical/ Service Rooms      | 2nd Floor           | 140      | SF   | 5    | \$2,258   | Auditorium lighting control room, Water damaged ceiling. |
|                                      | Storage Room                   | 2nd Floor           | 9        | SF   | 6    | \$64      | Across from rm 201                                       |
|                                      | Storage Room                   | 2nd Floor           | 9        | SF   | 6    | \$64      | Across from rm 205                                       |
|                                      | Storage Room                   | 2nd Floor           | 9        | SF   | 6    | \$64      | Across from rm 213B                                      |
|                                      | Storage Room                   | 2nd Floor           | 268      | SF   | 6    | \$1,920   | 2A storage next to freight elevator                      |
|                                      | Storage Room                   | 2nd Floor           | 98       | SF   | 6    | \$702     | Outside coaches offices                                  |
|                                      | Janitor's Closet               | 3rd Floor           | 25       | SF   | 6    | \$179     | In boys restroom next to rm 311                          |
|                                      | Janitor's Closet               | 3rd Floor           | 25       | SF   | 6    | \$179     | In boys restroom next to rm 312                          |
|                                      | Storage Room                   | 3rd Floor           | 25       | SF   | 6    | \$179     | Across from servery                                      |
|                                      | Storage Room                   | 3rd Floor           | 85       | SF   | 6    | \$609     | Next to boys rm next to 312. Roof access                 |
|                                      | Storage Room                   | 3rd Floor           | 268      | SF   | 6    | \$1,920   | 3A storage w/cooler                                      |
|                                      | Storage Room                   | 3rd Floor           | 85       | SF   | 6    | \$609     | Next to boys rm 311                                      |
|                                      | Air Intake Plenums             | Basement            | 1,530    | SF   | 6    | \$9,474   |  |
|                                      | Air Tunnel                     | Basement            | 4,106    | SF   | 6    | \$25,424  |  |
|                                      | Auditorium Plenums             | Basement            | 6,277    | SF   | 6    | \$38,867  |  |
|                                      | Janitor's Closet               | Basement            | 1,201    | SF   | 6    | \$8,604   | All Janitor are adding together                          |
|                                      | Mechanical/ Service Rooms      | Basement            | 29,520   | SF   | 6    | \$211,490 | All mechanical are adding together                       |
|                                      | Storage Room                   | Basement            | 9,035    | SF   | 6    | \$64,729  | All storage room adding together                         |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group                            | Item - Type                     | Location                    | Quantity | Unit | Rank | Cost     | Comments          |
|----------------------------------|---------------------------------|-----------------------------|----------|------|------|----------|-------------------|
| <b>Mechanical/ Service Rooms</b> |                                 |                             |          |      |      |          |                   |
| <b>Pool &amp; Natatorium</b>     |                                 |                             |          |      |      |          |                   |
|                                  | Accessories                     | 1st Floor                   | 3,561    | SF   | 6    | \$2,444  |                   |
|                                  | Bleachers Seating/Plank Seating | 1st Floor                   | 1        | EA   | 6    | \$29     |                   |
|                                  | Ceiling - Exposed               | 1st Floor                   | 3,561    | SF   | 6    | \$5,296  | Painted           |
|                                  | Doors - Steel Doors incl hw     | 1st Floor                   | 2        | EA   | 6    | \$602    |                   |
|                                  | Doors - Transom Window          | 1st Floor                   | 12       | SF   | 6    | \$203    | wire glass        |
|                                  | Floor - Terrazzo                | 1st Floor                   | 120      | SF   | 7    | \$0      |                   |
|                                  | Floor - Tile Ceramic/ Porcelain | 1st Floor                   | 3,561    | SF   | 6    | \$7,537  |                   |
|                                  | Lighting - Pendent/Surface      | 1st Floor                   | 20       | EA   | 6    | \$2,478  |                   |
|                                  | Lighting - Wall Mounted         | 1st Floor                   | 17       | EA   | 6    | \$2,106  |                   |
|                                  | Pool Basin                      | 1st Floor                   | 1,501    | SF   | 6    | \$50,785 |                   |
|                                  | Pool Deck                       | 1st Floor                   | 1,100    | SF   | 6    | \$10,445 |                   |
|                                  | Pool Deck Drains                | 1st Floor                   | 1        | EA   | 6    | \$422    |                   |
|                                  | Walls - Masonry                 | 1st Floor                   | 3,290    | SF   | 6    | \$10,350 |                   |
|                                  | Walls - Plaster/Drywall         | 1st Floor                   | 90       | SF   | 6    | \$279    | Beyond door entry |
|                                  | Walls - Structural Glazed Tile  | 1st Floor                   | 90       | SF   | 6    | \$283    | Beyond door entry |
| <b>Prep Room</b>                 |                                 |                             |          |      |      |          |                   |
|                                  | Casework                        | 303A prep rm                | 40       | LF   | 6    | \$1,010  |                   |
|                                  | Ceiling - Lay-in                | 303A prep rm                | 195      | SF   | 6    | \$586    |                   |
|                                  | Doors - Transom Window          | 303A prep rm                | 22       | SF   | 6    | \$372    |                   |
|                                  | Doors - Wood Doors inclu hw     | 303A prep rm                | 1        | EA   | 6    | \$301    |                   |
|                                  | Floor - Tile                    | 303A prep rm                | 195      | SF   | 6    | \$427    |                   |
|                                  | Lighting - Lay-in               | 303A prep rm                | 4        | EA   | 7    | \$0      |                   |
|                                  | Walls - Plaster/Drywall         | 303A prep rm                | 550      | SF   | 6    | \$1,518  |                   |
|                                  | Work Sink                       | 303A prep rm                | 1        | EA   | 6    | \$379    |                   |
|                                  | Casework                        | 203A prep rm                | 32       | LF   | 6    | \$808    |                   |
|                                  | Ceiling - Lay-in                | 203A prep rm                | 122      | SF   | 6    | \$366    |                   |
|                                  | Doors - Wood Doors inclu hw     | 203A prep rm                | 1        | EA   | 6    | \$301    |                   |
|                                  | Floor - Tile                    | 203A prep rm                | 122      | SF   | 6    | \$267    |                   |
|                                  | Lighting - Lay-in               | 203A prep rm                | 3        | EA   | 6    | \$357    |                   |
|                                  | Walls - Plaster/Drywall         | 203A prep rm                | 480      | SF   | 6    | \$1,325  |                   |
|                                  | Work Sink                       | 203A prep rm                | 1        | EA   | 6    | \$379    |                   |
|                                  | Casework                        | 207A prep room, in room 207 | 36       | LF   | 6    | \$909    |                   |
|                                  | Ceiling - Lay-in                | 207A prep room, in room 207 | 122      | SF   | 6    | \$366    |                   |
|                                  | Doors - Wood Doors inclu hw     | 207A prep room, in room 207 | 1        | EA   | 6    | \$301    |                   |
|                                  | Floor - Tile                    | 207A prep room, in room 207 | 122      | SF   | 6    | \$267    |                   |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group            | Item - Type                     | Location                       | Quantity | Unit | Rank | Cost    | Comments            |
|------------------|---------------------------------|--------------------------------|----------|------|------|---------|---------------------|
| <b>Prep Room</b> |                                 |                                |          |      |      |         |                     |
|                  | Lighting - Lay-in               | 207A prep room, in room 207    | 3        | EA   | 7    | \$0     |                     |
|                  | Walls - Plaster/Drywall         | 207A prep room, in room 207    | 480      | SF   | 6    | \$1,325 |                     |
|                  | Work Sink                       | 207A prep room, in room 207    | 1        | EA   | 6    | \$379   |                     |
|                  | Casework                        | 304A prep rm                   | 40       | LF   | 6    | \$1,010 |                     |
|                  | Ceiling - Lay-in                | 304A prep rm                   | 40       | SF   | 5    | \$277   | Water stained tiles |
|                  | Ceiling - Lay-in                | 304A prep rm                   | 160      | SF   | 6    | \$480   |                     |
|                  | Doors - Transom Window          | 304A prep rm                   | 22       | SF   | 6    | \$372   |                     |
|                  | Doors - Wood Doors inclu hw     | 304A prep rm                   | 1        | EA   | 6    | \$301   |                     |
|                  | Floor - Tile                    | 304A prep rm                   | 200      | SF   | 6    | \$438   |                     |
|                  | Lighting - Lay-in               | 304A prep rm                   | 4        | EA   | 6    | \$476   |                     |
|                  | Walls - Plaster/Drywall         | 304A prep rm                   | 616      | SF   | 6    | \$1,700 |                     |
|                  | Work Sink                       | 304A prep rm                   | 1        | EA   | 6    | \$379   |                     |
| <b>Restroom</b>  |                                 |                                |          |      |      |         |                     |
|                  | Accessories                     | Girl's Restroom Next to rm 218 | 349      | SF   | 6    | \$3,219 |                     |
|                  | Ceiling - Plaster/Drywall       | Girl's Restroom Next to rm 218 | 349      | SF   | 6    | \$1,208 |                     |
|                  | Doors - Side-lite               | Girl's Restroom Next to rm 218 | 16       | SF   | 6    | \$267   |                     |
|                  | Doors - Transom Window          | Girl's Restroom Next to rm 218 | 15       | SF   | 6    | \$254   |                     |
|                  | Doors - Wood Doors inclu hw     | Girl's Restroom Next to rm 218 | 1        | EA   | 6    | \$301   |                     |
|                  | Floor Drain                     | Girl's Restroom Next to rm 218 | 1        | EA   | 6    | \$1,059 |                     |
|                  | Floor - Tile Ceramic/ Porcelain | Girl's Restroom Next to rm 218 | 349      | SF   | 6    | \$739   |                     |
|                  | Hand Dryer                      | Girl's Restroom Next to rm 218 | 2        | EA   | 6    | \$460   |                     |
|                  | Lavatory                        | Girl's Restroom Next to rm 218 | 1        | EA   | 6    | \$320   | Steel basin         |
|                  | Lighting - Lay-in               | Girl's Restroom Next to rm 218 | 9        | EA   | 7    | \$0     |                     |
|                  | Partitions                      | Girl's Restroom Next to rm 218 | 5        | EA   | 6    | \$1,485 |                     |
|                  | Walls - Structural Glazed Tile  | Girl's Restroom Next to rm 218 | 694      | SF   | 6    | \$2,183 |                     |
|                  | Water Closet                    | Girl's Restroom Next to rm 218 | 5        | EA   | 6    | \$1,680 |                     |
|                  | Accessories                     | 102A-1 Principal Toilet        | 50       | SF   | 6    | \$461   |                     |
|                  | Ceiling - Lay-in                | 102A-1 Principal Toilet        | 50       | SF   | 6    | \$150   |                     |
|                  | Doors - Wood Doors inclu hw     | 102A-1 Principal Toilet        | 1        | EA   | 6    | \$301   |                     |
|                  | Floor Drain                     | 102A-1 Principal Toilet        | 1        | EA   | 6    | \$1,059 |                     |
|                  | Floor - Tile/Sheet              | 102A-1 Principal Toilet        | 50       | SF   | 6    | \$50    |                     |
|                  | Lavatory                        | 102A-1 Principal Toilet        | 1        | EA   | 6    | \$320   |                     |
|                  | Lighting - Pendent/Surface      | 102A-1 Principal Toilet        | 1        | EA   | 6    | \$124   |                     |
|                  | Walls - Plaster/Drywall         | 102A-1 Principal Toilet        | 125      | SF   | 6    | \$345   |                     |
|                  | Water Closet                    | 102A-1 Principal Toilet        | 1        | EA   | 6    | \$336   |                     |
|                  | Accessories                     | 115A Girl's Toilet             | 349      | SF   | 6    | \$3,219 |                     |
|                  | Ceiling - Plaster/Drywall       | 115A Girl's Toilet             | 349      | SF   | 6    | \$1,208 |                     |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                       | Quantity | Unit | Rank | Cost    | Comments         |
|-----------------|---------------------------------|--------------------------------|----------|------|------|---------|------------------|
| <b>Restroom</b> |                                 |                                |          |      |      |         |                  |
|                 | Doors - Side-lite               | 115A Girl's Toilet             | 12       | SF   | 6    | \$201   |                  |
|                 | Doors - Transom Window          | 115A Girl's Toilet             | 16       | SF   | 6    | \$271   |                  |
|                 | Doors - Wood Doors inclu hw     | 115A Girl's Toilet             | 1        | EA   | 6    | \$301   |                  |
|                 | Floor Drain                     | 115A Girl's Toilet             | 1        | EA   | 6    | \$1,059 |                  |
|                 | Floor - Tile Ceramic/ Porcelain | 115A Girl's Toilet             | 349      | SF   | 6    | \$739   |                  |
|                 | Hand Dryer                      | 115A Girl's Toilet             | 2        | EA   | 6    | \$460   |                  |
|                 | Lavatory                        | 115A Girl's Toilet             | 2        | EA   | 6    | \$639   |                  |
|                 | Lighting - Lay-in               | 115A Girl's Toilet             | 9        | EA   | 6    | \$1,071 |                  |
|                 | Partitions                      | 115A Girl's Toilet             | 4        | EA   | 6    | \$1,188 |                  |
|                 | Walls - Structural Glazed Tile  | 115A Girl's Toilet             | 694      | SF   | 6    | \$2,183 |                  |
|                 | Water Closet                    | 115A Girl's Toilet             | 5        | EA   | 6    | \$1,680 |                  |
|                 | Accessories                     | 1st Fl South Boy's Room        | 297      | SF   | 6    | \$2,739 |                  |
|                 | Ceiling - Plaster/Drywall       | 1st Fl South Boy's Room        | 297      | SF   | 6    | \$1,028 |                  |
|                 | Doors - Side-lite               | 1st Fl South Boy's Room        | 16       | SF   | 6    | \$267   |                  |
|                 | Doors - Steel Doors incl hw     | 1st Fl South Boy's Room        | 1        | EA   | 6    | \$301   |                  |
|                 | Doors - Transom Window          | 1st Fl South Boy's Room        | 16       | SF   | 6    | \$271   |                  |
|                 | Floor Drain                     | 1st Fl South Boy's Room        | 1        | EA   | 6    | \$1,059 |                  |
|                 | Floor - Tile Ceramic/ Porcelain | 1st Fl South Boy's Room        | 297      | SF   | 6    | \$629   |                  |
|                 | Hand Dryer                      | 1st Fl South Boy's Room        | 2        | EA   | 6    | \$460   |                  |
|                 | Lavatory                        | 1st Fl South Boy's Room        | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Lay-in               | 1st Fl South Boy's Room        | 4        | EA   | 6    | \$476   |                  |
|                 | Partitions                      | 1st Fl South Boy's Room        | 2        | EA   | 6    | \$594   |                  |
|                 | Urinals                         | 1st Fl South Boy's Room        | 4        | EA   | 6    | \$1,344 |                  |
|                 | Walls - Structural Glazed Tile  | 1st Fl South Boy's Room        | 585      | SF   | 6    | \$1,840 |                  |
|                 | Water Closet                    | 1st Fl South Boy's Room        | 2        | EA   | 6    | \$672   |                  |
|                 | Accessories                     | 1st floor next Auditorium Mens | 80       | SF   | 6    | \$738   |                  |
|                 | Ceiling - Plaster/Drywall       | 1st floor next Auditorium Mens | 80       | SF   | 6    | \$277   |                  |
|                 | Doors - Side-lite               | 1st floor next Auditorium Mens | 21       | SF   | 6    | \$351   | Solid wood panel |
|                 | Doors - Wood Doors inclu hw     | 1st floor next Auditorium Mens | 1        | EA   | 6    | \$301   |                  |
|                 | Floor - Tile Ceramic/ Porcelain | 1st floor next Auditorium Mens | 80       | SF   | 6    | \$169   |                  |
|                 | Hand Dryer                      | 1st floor next Auditorium Mens | 1        | EA   | 6    | \$230   |                  |
|                 | Lavatory                        | 1st floor next Auditorium Mens | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Lay-in               | 1st floor next Auditorium Mens | 2        | EA   | 7    | \$0     |                  |
|                 | Partitions                      | 1st floor next Auditorium Mens | 1        | EA   | 6    | \$297   |                  |
|                 | Student Lockers - One Tier      | 1st floor next Auditorium Mens | 1        | EA   | 6    | \$93    |                  |
|                 | Urinals                         | 1st floor next Auditorium Mens | 2        | EA   | 6    | \$672   |                  |
|                 | Walls - Masonry                 | 1st floor next Auditorium Mens | 196      | SF   | 6    | \$617   | glazed           |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                             | Quantity | Unit | Rank | Cost    | Comments         |
|-----------------|---------------------------------|--------------------------------------|----------|------|------|---------|------------------|
| <b>Restroom</b> |                                 |                                      |          |      |      |         |                  |
|                 | Walls - Plaster/Drywall         | 1st floor next Auditorium Mens       | 75       | SF   | 6    | \$207   |                  |
|                 | Water Closet                    | 1st floor next Auditorium Mens       | 1        | EA   | 6    | \$336   |                  |
|                 | Accessories                     | 1st floor next to Auditorium (Women) | 100      | SF   | 6    | \$922   |                  |
|                 | Ceiling - Plaster/Drywall       | 1st floor next to Auditorium (Women) | 100      | SF   | 6    | \$346   |                  |
|                 | Doors - Side-lite               | 1st floor next to Auditorium (Women) | 21       | SF   | 6    | \$351   | solid wood panel |
|                 | Doors - Wood Doors inclu hw     | 1st floor next to Auditorium (Women) | 1        | EA   | 6    | \$301   |                  |
|                 | Floor - Tile Ceramic/ Porcelain | 1st floor next to Auditorium (Women) | 100      | SF   | 6    | \$212   |                  |
|                 | Hand Dryer                      | 1st floor next to Auditorium (Women) | 1        | EA   | 6    | \$230   |                  |
|                 | Lavatory                        | 1st floor next to Auditorium (Women) | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Lay-in               | 1st floor next to Auditorium (Women) | 3        | EA   | 7    | \$0     |                  |
|                 | Partitions                      | 1st floor next to Auditorium (Women) | 2        | EA   | 6    | \$594   |                  |
|                 | Walls - Masonry                 | 1st floor next to Auditorium (Women) | 245      | SF   | 6    | \$771   | glazed           |
|                 | Walls - Plaster/Drywall         | 1st floor next to Auditorium (Women) | 95       | SF   | 6    | \$262   |                  |
|                 | Water Closet                    | 1st floor next to Auditorium (Women) | 1        | EA   | 6    | \$336   |                  |
|                 | Accessories                     | 222C restroom                        | 44       | SF   | 6    | \$406   |                  |
|                 | Ceiling - Plaster/Drywall       | 222C restroom                        | 44       | SF   | 6    | \$152   |                  |
|                 | Doors - Transom Window          | 222C restroom                        | 6        | SF   | 6    | \$102   |                  |
|                 | Doors - Wood Doors inclu hw     | 222C restroom                        | 1        | EA   | 6    | \$301   |                  |
|                 | Floor - Tile Ceramic/ Porcelain | 222C restroom                        | 44       | SF   | 6    | \$93    |                  |
|                 | Lavatory                        | 222C restroom                        | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Pendant/Surface      | 222C restroom                        | 1        | EA   | 4    | \$541   | T12              |
|                 | Partitions                      | 222C restroom                        | 1        | EA   | 6    | \$297   |                  |
|                 | Walls - Plaster/Drywall         | 222C restroom                        | 320      | SF   | 6    | \$883   |                  |
|                 | Water Closet                    | 222C restroom                        | 1        | EA   | 6    | \$336   |                  |
|                 | Accessories                     | 223C staff/coach Shower rm           | 106      | SF   | 6    | \$978   |                  |
|                 | Ceiling - Plaster/Drywall       | 223C staff/coach Shower rm           | 106      | SF   | 6    | \$367   |                  |
|                 | Doors - Wood Doors inclu hw     | 223C staff/coach Shower rm           | 1        | EA   | 6    | \$301   |                  |
|                 | Floor Drain                     | 223C staff/coach Shower rm           | 2        | EA   | 6    | \$2,118 |                  |
|                 | Floor - Tile Ceramic/ Porcelain | 223C staff/coach Shower rm           | 106      | SF   | 6    | \$224   |                  |
|                 | Hand Dryer                      | 223C staff/coach Shower rm           | 1        | EA   | 6    | \$230   |                  |
|                 | Lavatory                        | 223C staff/coach Shower rm           | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Lay-in               | 223C staff/coach Shower rm           | 2        | EA   | 7    | \$0     |                  |
|                 | Showers                         | 223C staff/coach Shower rm           | 1        | EA   | 6    | \$311   |                  |
|                 | Student Lockers - One Tier      | 223C staff/coach Shower rm           | 5        | EA   | 6    | \$464   |                  |
|                 | Walls - Plaster/Drywall         | 223C staff/coach Shower rm           | 90       | SF   | 6    | \$248   |                  |
|                 | Walls - Tile Ceramic/ Porcelain | 223C staff/coach Shower rm           | 341      | SF   | 6    | \$770   |                  |
|                 | Water Closet                    | 223C staff/coach Shower rm           | 1        | EA   | 6    | \$336   |                  |



**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                          | Quantity | Unit | Rank | Cost    | Comments    |
|-----------------|---------------------------------|-----------------------------------|----------|------|------|---------|-------------|
| <b>Restroom</b> |                                 |                                   |          |      |      |         |             |
|                 | Accessories                     | Boys restroom across from rm 213B | 297      | SF   | 6    | \$2,739 |             |
|                 | Ceiling - Plaster/Drywall       | Boys restroom across from rm 213B | 297      | SF   | 6    | \$1,028 |             |
|                 | Doors - Side-lite               | Boys restroom across from rm 213B | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Boys restroom across from rm 213B | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Boys restroom across from rm 213B | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Boys restroom across from rm 213B | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Boys restroom across from rm 213B | 297      | SF   | 6    | \$629   |             |
|                 | Hand Dryer                      | Boys restroom across from rm 213B | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Boys restroom across from rm 213B | 1        | EA   | 6    | \$320   |             |
|                 | Lighting - Lay-in               | Boys restroom across from rm 213B | 4        | EA   | 7    | \$0     |             |
|                 | Partitions                      | Boys restroom across from rm 213B | 2        | EA   | 6    | \$594   |             |
|                 | Urinals                         | Boys restroom across from rm 213B | 4        | EA   | 6    | \$1,344 |             |
|                 | Walls - Structural Glazed Tile  | Boys restroom across from rm 213B | 585      | SF   | 6    | \$1,840 |             |
|                 | Water Closet                    | Boys restroom across from rm 213B | 2        | EA   | 6    | \$672   |             |
|                 | Accessories                     | Boys restroom next to 311         | 297      | SF   | 6    | \$2,739 |             |
|                 | Ceiling - Plaster/Drywall       | Boys restroom next to 311         | 297      | SF   | 6    | \$1,028 |             |
|                 | Doors - Side-lite               | Boys restroom next to 311         | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Boys restroom next to 311         | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Boys restroom next to 311         | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Boys restroom next to 311         | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Boys restroom next to 311         | 297      | SF   | 6    | \$629   |             |
|                 | Hand Dryer                      | Boys restroom next to 311         | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Boys restroom next to 311         | 1        | EA   | 6    | \$320   | Steel basin |
|                 | Lighting - Lay-in               | Boys restroom next to 311         | 4        | EA   | 7    | \$0     |             |
|                 | Partitions                      | Boys restroom next to 311         | 2        | EA   | 6    | \$594   |             |
|                 | Urinals                         | Boys restroom next to 311         | 4        | EA   | 6    | \$1,344 |             |
|                 | Walls - Structural Glazed Tile  | Boys restroom next to 311         | 585      | SF   | 6    | \$1,840 |             |
|                 | Water Closet                    | Boys restroom next to 311         | 2        | EA   | 6    | \$672   |             |
|                 | Accessories                     | Boys restroom next to rm 212      | 297      | SF   | 6    | \$2,739 |             |
|                 | Ceiling - Plaster/Drywall       | Boys restroom next to rm 212      | 297      | SF   | 6    | \$1,028 |             |
|                 | Doors - Side-lite               | Boys restroom next to rm 212      | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Boys restroom next to rm 212      | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Boys restroom next to rm 212      | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Boys restroom next to rm 212      | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Boys restroom next to rm 212      | 297      | SF   | 6    | \$629   |             |
|                 | Hand Dryer                      | Boys restroom next to rm 212      | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Boys restroom next to rm 212      | 1        | EA   | 6    | \$320   | Steel basin |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                                       | Quantity | Unit | Rank | Cost    | Comments    |
|-----------------|---------------------------------|--|----------|------|------|---------|-------------|
| <b>Restroom</b> |                                 |  |          |      |      |         |             |
|                 | Lighting - Lay-in               | Boys restroom next to rm 212                   | 4        | EA   | 7    | \$0     |             |
|                 | Partitions                      | Boys restroom next to rm 212                   | 2        | EA   | 6    | \$594   |             |
|                 | Urinals                         | Boys restroom next to rm 212                   | 4        | EA   | 6    | \$1,344 |             |
|                 | Walls - Structural Glazed Tile  | Boys restroom next to rm 212                   | 585      | SF   | 6    | \$1,840 |             |
|                 | Water Closet                    | Boys restroom next to rm 212                   | 2        | EA   | 6    | \$672   |             |
|                 | Accessories                     | Boys restroom next to rm 312                   | 297      | SF   | 6    | \$2,739 |             |
|                 | Ceiling - Plaster/Drywall       | Boys restroom next to rm 312                   | 297      | SF   | 6    | \$1,028 |             |
|                 | Doors - Side-lite               | Boys restroom next to rm 312                   | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Boys restroom next to rm 312                   | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Boys restroom next to rm 312                   | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Boys restroom next to rm 312                   | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Boys restroom next to rm 312                   | 297      | SF   | 6    | \$629   |             |
|                 | Hand Dryer                      | Boys restroom next to rm 312                   | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Boys restroom next to rm 312                   | 1        | EA   | 6    | \$320   | steel basin |
|                 | Lighting - Lay-in               | Boys restroom next to rm 312                   | 4        | EA   | 7    | \$0     |             |
|                 | Partitions                      | Boys restroom next to rm 312                   | 2        | EA   | 6    | \$594   |             |
|                 | Urinals                         | Boys restroom next to rm 312                   | 4        | EA   | 6    | \$1,344 |             |
|                 | Walls - Structural Glazed Tile  | Boys restroom next to rm 312                   | 585      | SF   | 6    | \$1,840 |             |
|                 | Water Closet                    | Boys restroom next to rm 312                   | 2        | EA   | 6    | \$672   |             |
|                 | Accessories                     | Girls restroom across from Lunchroom/Cafeteria | 349      | SF   | 6    | \$3,219 |             |
|                 | Ceiling - Plaster/Drywall       | Girls restroom across from Lunchroom/Cafeteria | 349      | SF   | 6    | \$1,208 |             |
|                 | Doors - Side-lite               | Girls restroom across from Lunchroom/Cafeteria | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Girls restroom across from Lunchroom/Cafeteria | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Girls restroom across from Lunchroom/Cafeteria | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Girls restroom across from Lunchroom/Cafeteria | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Girls restroom across from Lunchroom/Cafeteria | 349      | SF   | 6    | \$739   |             |
|                 | Hand Dryer                      | Girls restroom across from Lunchroom/Cafeteria | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Girls restroom across from Lunchroom/Cafeteria | 1        | EA   | 6    | \$320   | Steel basin |
|                 | Lighting - Lay-in               | Girls restroom across from Lunchroom/Cafeteria | 9        | EA   | 7    | \$0     |             |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                                       | Quantity | Unit | Rank | Cost    | Comments    |
|-----------------|---------------------------------|--|----------|------|------|---------|-------------|
| <b>Restroom</b> |                                 |  |          |      |      |         |             |
|                 | Partitions                      | Girls restroom across from Lunchroom/Cafeteria | 5        | EA   | 6    | \$1,485 |             |
|                 | Walls - Structural Glazed Tile  | Girls restroom across from Lunchroom/Cafeteria | 914      | SF   | 6    | \$2,875 |             |
|                 | Water Closet                    | Girls restroom across from Lunchroom/Cafeteria | 5        | EA   | 6    | \$1,680 |             |
|                 | Accessories                     | Girls restroom next to rm 217A                 | 349      | SF   | 6    | \$3,219 |             |
|                 | Ceiling - Plaster/Drywall       | Girls restroom next to rm 217A                 | 349      | SF   | 6    | \$1,208 |             |
|                 | Doors - Side-lite               | Girls restroom next to rm 217A                 | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Girls restroom next to rm 217A                 | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Girls restroom next to rm 217A                 | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Girls restroom next to rm 217A                 | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Girls restroom next to rm 217A                 | 349      | SF   | 6    | \$739   |             |
|                 | Hand Dryer                      | Girls restroom next to rm 217A                 | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Girls restroom next to rm 217A                 | 1        | EA   | 6    | \$320   | Steel basin |
|                 | Lighting - Lay-in               | Girls restroom next to rm 217A                 | 9        | EA   | 7    | \$0     |             |
|                 | Partitions                      | Girls restroom next to rm 217A                 | 5        | EA   | 6    | \$1,485 |             |
|                 | Walls - Structural Glazed Tile  | Girls restroom next to rm 217A                 | 914      | SF   | 6    | \$2,875 |             |
|                 | Water Closet                    | Girls restroom next to rm 217A                 | 5        | EA   | 6    | \$1,680 |             |
|                 | Accessories                     | Girls restroom next to rm 317                  | 349      | SF   | 6    | \$3,219 |             |
|                 | Ceiling - Plaster/Drywall       | Girls restroom next to rm 317                  | 349      | SF   | 6    | \$1,208 |             |
|                 | Doors - Side-lite               | Girls restroom next to rm 317                  | 16       | SF   | 6    | \$267   |             |
|                 | Doors - Transom Window          | Girls restroom next to rm 317                  | 15       | SF   | 6    | \$254   |             |
|                 | Doors - Wood Doors inclu hw     | Girls restroom next to rm 317                  | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | Girls restroom next to rm 317                  | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | Girls restroom next to rm 317                  | 349      | SF   | 6    | \$739   |             |
|                 | Hand Dryer                      | Girls restroom next to rm 317                  | 2        | EA   | 6    | \$460   |             |
|                 | Lavatory                        | Girls restroom next to rm 317                  | 1        | EA   | 6    | \$320   | steel basin |
|                 | Lighting - Lay-in               | Girls restroom next to rm 317                  | 9        | EA   | 7    | \$0     |             |
|                 | Partitions                      | Girls restroom next to rm 317                  | 5        | EA   | 6    | \$1,485 |             |
|                 | Walls - Structural Glazed Tile  | Girls restroom next to rm 317                  | 914      | SF   | 6    | \$2,875 |             |
|                 | Water Closet                    | Girls restroom next to rm 317                  | 5        | EA   | 6    | \$1,680 |             |
|                 | Accessories                     | In Girls Locker Room Office                    | 49       | SF   | 6    | \$452   |             |
|                 | Ceiling - Plaster/Drywall       | In Girls Locker Room Office                    | 49       | SF   | 6    | \$170   |             |
|                 | Doors - Steel Doors incl hw     | In Girls Locker Room Office                    | 1        | EA   | 6    | \$301   |             |
|                 | Floor Drain                     | In Girls Locker Room Office                    | 1        | EA   | 6    | \$1,059 |             |
|                 | Floor - Tile Ceramic/ Porcelain | In Girls Locker Room Office                    | 49       | SF   | 6    | \$104   |             |
|                 | Lavatory                        | In Girls Locker Room Office                    | 1        | EA   | 6    | \$320   |             |

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                     | Location                    | Quantity | Unit | Rank | Cost    | Comments      |
|-----------------|---------------------------------|-----------------------------|----------|------|------|---------|---------------|
| <b>Restroom</b> |                                 |                             |          |      |      |         |               |
|                 | Lighting - Lay-in               | In Girls Locker Room Office | 1        | EA   | 6    | \$119   |               |
|                 | Walls - Plaster/Drywall         | In Girls Locker Room Office | 128      | SF   | 6    | \$353   |               |
|                 | Walls - Tile Ceramic/ Porcelain | In Girls Locker Room Office | 128      | SF   | 6    | \$289   |               |
|                 | Water Closet                    | In Girls Locker Room Office | 1        | EA   | 6    | \$336   |               |
|                 | Accessories                     | In Room 222B                | 27       | SF   | 6    | \$249   |               |
|                 | Ceiling - Plaster/Drywall       | In Room 222B                | 27       | SF   | 6    | \$93    |               |
|                 | Doors - Transom Window          | In Room 222B                | 6        | SF   | 6    | \$102   |               |
|                 | Doors - Wood Doors inclu hw     | In Room 222B                | 1        | EA   | 6    | \$301   |               |
|                 | Floor - Tile Ceramic/ Porcelain | In Room 222B                | 27       | SF   | 6    | \$57    |               |
|                 | Lavatory                        | In Room 222B                | 1        | EA   | 6    | \$320   |               |
|                 | Lighting - Pendant/Surface      | In Room 222B                | 1        | EA   | 4    | \$541   | T12           |
|                 | Walls - Plaster/Drywall         | In Room 222B                | 240      | SF   | 6    | \$662   |               |
|                 | Water Closet                    | In Room 222B                | 1        | EA   | 6    | \$336   |               |
|                 | Accessories                     | Staff toilet next to rm 218 | 92       | SF   | 6    | \$849   |               |
|                 | Ceiling - Plaster/Drywall       | Staff toilet next to rm 218 | 92       | SF   | 6    | \$318   |               |
|                 | Doors - Transom Window          | Staff toilet next to rm 218 | 6        | SF   | 6    | \$102   |               |
|                 | Doors - Wood Doors inclu hw     | Staff toilet next to rm 218 | 1        | EA   | 6    | \$301   |               |
|                 | Floor Drain                     | Staff toilet next to rm 218 | 1        | EA   | 6    | \$1,059 |               |
|                 | Floor - Tile Ceramic/ Porcelain | Staff toilet next to rm 218 | 92       | SF   | 6    | \$195   |               |
|                 | Hand Dryer                      | Staff toilet next to rm 218 | 1        | EA   | 6    | \$230   |               |
|                 | Lavatory                        | Staff toilet next to rm 218 | 1        | EA   | 6    | \$320   |               |
|                 | Lighting - Lay-in               | Staff toilet next to rm 218 | 2        | EA   | 7    | \$0     |               |
|                 | Partitions                      | Staff toilet next to rm 218 | 2        | EA   | 6    | \$594   |               |
|                 | Walls - Masonry                 | Staff toilet next to rm 218 | 146      | SF   | 6    | \$459   | Toilet stalls |
|                 | Walls - Plaster/Drywall         | Staff toilet next to rm 218 | 323      | SF   | 6    | \$891   |               |
|                 | Water Closet                    | Staff toilet next to rm 218 | 2        | EA   | 6    | \$672   |               |

**Rooms (Other Than Classrooms) Subtotal:**
**\$1,956,806**
**Building: Main**
**Category: Building Interior**

| Group           | Item - Type                          | Location  | Quantity | Unit | Rank | Cost     | Comments |
|-----------------|--------------------------------------|-----------|----------|------|------|----------|----------|
| <b>Corridor</b> |                                      |           |          |      |      |          |          |
|                 | Ceiling - Lay-in                     | 1st Floor | 9,245    | SF   | 6    | \$27,763 |          |
|                 | Doors - Wood Doors include hw        | 1st Floor | 4        | EA   | 6    | \$1,204  |          |
|                 | Drinking Fountains - Single Fountain | 1st Floor | 8        | EA   | 6    | \$2,206  |          |
|                 | Floor - Terrazzo                     | 1st Floor | 1,849    | SF   | 7    | \$0      |          |

**Building: Main**
**Category: Building Interior**

| Group           | Item - Type                          | Location  | Quantity | Unit | Rank | Cost     | Comments                       |
|-----------------|--------------------------------------|-----------|----------|------|------|----------|--------------------------------|
| <b>Corridor</b> |                                      |           |          |      |      |          |                                |
|                 | Floor - Tile/Sheet                   | 1st Floor | 7,396    | SF   | 6    | \$4,019  |                                |
|                 | Lighting - Lay-in                    | 1st Floor | 124      | EA   | 6    | \$14,753 |                                |
|                 | Student Lockers - One Tier           | 1st Floor | 723      | EA   | 6    | \$67,120 |                                |
|                 | Walls - Plaster/Drywall              | 1st Floor | 6,210    | SF   | 6    | \$27,529 |                                |
|                 | Walls - Structural Glazed Tile       | 1st Floor | 6,210    | SF   | 6    | \$19,537 |                                |
|                 | Ceiling - Lay-in                     | 2nd Floor | 9,245    | SF   | 6    | \$27,763 |                                |
|                 | Ceiling - Plaster/Drywall            | 2nd Floor | 985      | SF   | 5    | \$12,409 | Peeling cracking paint/plaster |
|                 | Doors - Steel Doors incl hw          | 2nd Floor | 1        | EA   | 6    | \$301    |                                |
|                 | Doors - Wood Doors include hw        | 2nd Floor | 6        | EA   | 6    | \$1,806  |                                |
|                 | Drinking Fountains - Double Fountain | 2nd Floor | 3        | EA   | 6    | \$1,008  |                                |
|                 | Floor - Concrete                     | 2nd Floor | 360      | SF   | 6    | \$190    |                                |
|                 | Floor - Terrazzo                     | 2nd Floor | 2,475    | SF   | 5    | \$93,153 |                                |
|                 | Floor - Tile/Sheet                   | 2nd Floor | 7,396    | SF   | 6    | \$4,019  |                                |
|                 | Lighting - Lay-in                    | 2nd Floor | 121      | EA   | 6    | \$14,396 |                                |
|                 | Lighting - Pendent/Surface           | 2nd Floor | 16       | EA   | 6    | \$1,982  |                                |
|                 | Student Lockers - One Tier           | 2nd Floor | 818      | EA   | 6    | \$75,940 |                                |
|                 | Walls - Concrete Block               | 2nd Floor | 250      | SF   | 6    | \$733    |                                |
|                 | Walls - Plaster/Drywall              | 2nd Floor | 8,644    | SF   | 6    | \$38,319 |                                |
|                 | Walls - Structural Glazed Tile       | 2nd Floor | 9,523    | SF   | 6    | \$29,959 |                                |
|                 | Ceiling - Lay-in                     | 3rd Floor | 9,245    | SF   | 6    | \$27,763 |                                |
|                 | Ceiling - Plaster/Drywall            | 3rd Floor | 985      | SF   | 6    | \$6,099  |                                |
|                 | Doors - Steel Doors incl hw          | 3rd Floor | 1        | EA   | 6    | \$301    |                                |
|                 | Doors - Wood Doors include hw        | 3rd Floor | 6        | EA   | 6    | \$1,806  |                                |
|                 | Drinking Fountains - Double Fountain | 3rd Floor | 3        | EA   | 6    | \$1,008  |                                |
|                 | Floor - Concrete                     | 3rd Floor | 360      | SF   | 6    | \$190    |                                |
|                 | Floor - Terrazzo                     | 3rd Floor | 2,475    | SF   | 6    | \$20,775 |                                |
|                 | Floor - Tile/Sheet                   | 3rd Floor | 7,396    | SF   | 6    | \$4,019  |                                |
|                 | Lighting - Lay-in                    | 3rd Floor | 121      | EA   | 6    | \$14,396 |                                |
|                 | Lighting - Pendent/Surface           | 3rd Floor | 16       | EA   | 6    | \$1,982  |                                |
|                 | Student Lockers - One Tier           | 3rd Floor | 818      | EA   | 6    | \$75,940 |                                |
|                 | Walls - Concrete Block               | 3rd Floor | 250      | SF   | 6    | \$733    |                                |
|                 | Walls - Plaster/Drywall              | 3rd Floor | 8,644    | SF   | 6    | \$38,319 |                                |
|                 | Walls - Structural Glazed Tile       | 3rd Floor | 9,523    | SF   | 6    | \$29,959 |                                |
|                 | Ceiling - Plaster/Drywall            | Basement  | 3,698    | SF   | 6    | \$22,898 |                                |
|                 | Floor - Concrete Epoxy/ Painted      | Basement  | 3,698    | SF   | 6    | \$1,798  |                                |
|                 | Lighting - Pendent/Surface           | Basement  | 60       | EA   | 6    | \$7,434  |                                |
|                 | Walls - Concrete Block               | Basement  | 3,105    | SF   | 6    | \$9,102  |                                |

**Building: Main**
**Category: Building Interior**

| Group           | Item - Type                    | Location                    | Quantity | Unit | Rank | Cost     | Comments  |
|-----------------|--------------------------------|-----------------------------|----------|------|------|----------|---|
| <b>Corridor</b> |                                |                             |          |      |      |          |   |
|                 | Walls - Plaster/Drywall        | Basement                    | 3,105    | SF   | 6    | \$13,764 |   |
| <b>Safety</b>   |                                |                             |          |      |      |          |   |
|                 | Camera Viewing Station         | 1st Floor                   | 3        | EA   | 6    | \$2,048  |   |
|                 | Metal Dedector                 | 1st Floor                   | 3        | EA   | 6    | \$2,642  | Two at door#1, one at door#2                    |
|                 | Security Cameras               | 1st Floor / Entire Building | 16       | EA   | 5    | \$11,003 | Majority of camera images wavy and hard to view |
|                 | Security Cameras               | 1st Floor / Entire Building | 1        | EA   | 5    | \$688    | Not working properly                            |
|                 | Security Cameras               | 1st Floor / Entire Building | 2        | EA   | 6    | \$388    |   |
| <b>Stairs</b>   |                                |                             |          |      |      |          |   |
|                 | Ceiling - Plaster/Drywall      | Stairwell # 1               | 303      | SF   | 6    | \$2,218  |   |
|                 | Floor - Terrazzo               | Stairwell # 1               | 582      | SF   | 7    | \$0      |   |
|                 | Handrails                      | Stairwell # 1               | 120      | LF   | 6    | \$1,040  |   |
|                 | Lighting - Pendent/Surface     | Stairwell # 1               | 4        | EA   | 6    | \$496    |   |
|                 | Stairs - Terrazzo              | Stairwell # 1               | 60       | LF   | 7    | \$0      |   |
|                 | Walls - Plaster/Drywall        | Stairwell # 1               | 540      | SF   | 6    | \$1,490  |   |
|                 | Walls - Structural Glazed Tile | Stairwell # 1               | 756      | SF   | 6    | \$2,378  |   |
|                 | Ceiling - Plaster/Drywall      | Stairwell # 2               | 142      | SF   | 6    | \$1,040  |   |
|                 | Floor - Terrazzo               | Stairwell # 2               | 291      | SF   | 7    | \$0      |   |
|                 | Handrails                      | Stairwell # 2               | 60       | LF   | 6    | \$520    |   |
|                 | Lighting - Pendent/Surface     | Stairwell # 2               | 4        | EA   | 6    | \$496    |   |
|                 | Stairs - Terrazzo              | Stairwell # 2               | 30       | LF   | 7    | \$0      |   |
|                 | Walls - Masonry                | Stairwell # 2               | 378      | SF   | 6    | \$1,189  |   |
|                 | Walls - Plaster/Drywall        | Stairwell # 2               | 270      | SF   | 6    | \$745    |   |
|                 | Ceiling - Plaster/Drywall      | Stairwell # 3               | 100      | SF   | 5    | \$1,739  | Water damage                                    |
|                 | Ceiling - Plaster/Drywall      | Stairwell # 3               | 303      | SF   | 6    | \$2,218  |   |
|                 | Floor - Terrazzo               | Stairwell # 3               | 582      | SF   | 7    | \$0      |   |
|                 | Handrails                      | Stairwell # 3               | 120      | LF   | 6    | \$1,040  |   |
|                 | Lighting - Pendent/Surface     | Stairwell # 3               | 4        | EA   | 6    | \$496    |   |
|                 | Stairs - Terrazzo              | Stairwell # 3               | 60       | LF   | 7    | \$0      |   |
|                 | Walls - Masonry                | Stairwell # 3               | 756      | SF   | 6    | \$2,378  |   |
|                 | Walls - Plaster/Drywall        | Stairwell # 3               | 540      | SF   | 6    | \$1,490  |   |
|                 | Walls - Plaster/Drywall        | Stairwell # 3               | 100      | SF   | 5    | \$535    | Wall cracking                                   |
|                 | Ceiling - Plaster/Drywall      | Stairwell # 4               | 383      | SF   | 6    | \$2,804  |   |
|                 | Floor - Terrazzo               | Stairwell # 4               | 700      | SF   | 7    | \$0      |   |
|                 | Handrails                      | Stairwell # 4               | 120      | LF   | 6    | \$1,040  |   |
|                 | Lighting - Pendent/Surface     | Stairwell # 4               | 7        | EA   | 6    | \$867    |   |
|                 | Stairs - Terrazzo              | Stairwell # 4               | 60       | LF   | 7    | \$0      |   |

**Building: Main**
**Category: Building Interior**

| Group                      | Item - Type                 | Location        | Quantity | Unit | Rank | Cost     | Comments |
|----------------------------|-----------------------------|-----------------|----------|------|------|----------|----------|
| <b>Stairs</b>              |                             |                 |          |      |      |          |          |
|                            | Walls - Masonry             | Stairwell # 4   | 1,120    | SF   | 6    | \$3,524  |          |
|                            | Walls - Plaster/Drywall     | Stairwell # 4   | 540      | SF   | 6    | \$1,490  |          |
|                            | Ceiling - Plaster/Drywall   | Stairwell # 5   | 303      | SF   | 6    | \$2,218  |          |
|                            | Floor - Terrazzo            | Stairwell # 5   | 582      | SF   | 7    | \$0      |          |
|                            | Handrails                   | Stairwell # 5   | 120      | LF   | 6    | \$1,040  |          |
|                            | Lighting - Pendent/Surface  | Stairwell # 5   | 4        | EA   | 6    | \$496    |          |
|                            | Stairs - Terrazzo           | Stairwell # 5   | 60       | LF   | 7    | \$0      |          |
|                            | Walls - Masonry             | Stairwell # 5   | 756      | SF   | 6    | \$2,378  |          |
|                            | Walls - Plaster/Drywall     | Stairwell # 5   | 540      | SF   | 6    | \$1,490  |          |
|                            | Ceiling - Plaster/Drywall   | Stairwell # 6   | 83       | SF   | 6    | \$608    |          |
|                            | Floor - Terrazzo            | Stairwell # 6   | 243      | SF   | 7    | \$0      |          |
|                            | Handrails                   | Stairwell # 6   | 132      | LF   | 6    | \$1,144  |          |
|                            | Lighting - Wall Mounted     | Stairwell # 6   | 3        | EA   | 6    | \$372    |          |
|                            | Stairs - Terrazzo           | Stairwell # 6   | 60       | LF   | 7    | \$0      |          |
|                            | Walls - Plaster/Drywall     | Stairwell # 6   | 1,053    | SF   | 6    | \$2,906  |          |
| <b>Vertical Conveyance</b> |                             |                 |          |      |      |          |          |
|                            | Elevator - Freight Elevator | Entire Building | 1        | EA   | 6    | \$19,238 |          |

**Building Interior Subtotal:**
**\$824,288**
**Total Building Cost**
**\$9,716,899**
**Building: Addition**
**Category: Building Exterior**

| Group           | Item - Type                                    | Location          | Quantity | Unit | Rank | Cost    | Comments                   |
|-----------------|--|-------------------|----------|------|------|---------|----------------------------|
| <b>Entrance</b> |  |                   |          |      |      |         |                            |
|                 | Exterior Doors - Exterior Stainless Steel Door | Entrance 10-West  | 4        | EA   | 6    | \$2,184 |                            |
|                 | Exterior Doors - Exterior Stainless Steel Door | Entrance 11-West  | 4        | EA   | 6    | \$2,184 |                            |
|                 | Exterior Doors - Exterior Stainless Steel Door | Entrance 12-NW    | 4        | EA   | 6    | \$2,184 |                            |
|                 | Exterior Doors - Exterior Stainless Steel Door | Entrance 1-East   | 4        | EA   | 6    | \$2,184 |                            |
|                 | Exterior Doors - Exterior Stainless Steel Door | Exit 1A-South     | 2        | EA   | 6    | \$1,092 |                            |
|                 | Exterior Doors - Exterior Steel Door           | Roof access doors | 1        | EA   | 5    | \$1,341 | Bent, not closing properly |
|                 | Exterior Doors - Exterior Steel Door           | Roof access doors | 6        | EA   | 6    | \$2,883 |                            |
|                 | Exterior Doors - Transom Lite                  | Entrance 10-West  | 8        | EA   | 6    | \$2,507 |                            |
|                 | Exterior Doors - Transom Lite                  | Entrance 11-West  | 8        | EA   | 6    | \$2,507 |                            |
|                 | Exterior Doors - Transom Lite                  | Entrance 12-NW    | 8        | EA   | 6    | \$2,507 |                            |

**Building: Addition**
**Category: Building Exterior**

| Group              | Item - Type   | Location        | Quantity | Unit | Rank | Cost      | Comments   |
|--------------------|---|-----------------|----------|------|------|-----------|--|
| <b>Entrance</b>    |   |                 |          |      |      |           |  |
|                    | Exterior Doors - Transom Lite                         | Exit 1A-South   | 4        | EA   | 6    | \$1,253   |  |
| <b>Foundation</b>  |   |                 |          |      |      |           |  |
|                    | Foundation - Concrete                                 | Entire Building | 810      | LF   | 7    | \$0       |  |
|                    | Superstructure - Steel                                | Entire Building | 73,769   | SF   | 7    | \$0       |  |
| <b>Lighting</b>    |   |                 |          |      |      |           |  |
|                    | Exterior Lighting - Parapet or Roof Mounted           | Entire Building | 18       | EA   | 6    | \$9,658   |  |
|                    | Exterior Lighting - Wall Mounted                      | Entire Building | 19       | EA   | 6    | \$5,486   |  |
| <b>Roof System</b> |   |                 |          |      |      |           |  |
|                    | Chimney - Metal Flue                                  | Roof 3          | 130      | LF   | 6    | \$20,559  |  |
|                    | Coping - Stone  | Roof 2          | 720      | LF   | 6    | \$23,125  |  |
|                    | Coping - Stone  | Roof 2          | 50       | LF   | 5    | \$10,962  | Several areas with loose and missing mortar joints   |
|                    | Coping - Stone  | Roof 3          | 10       | LF   | 5    | \$2,192   | Several areas with loose and missing mortar joints   |
|                    | Coping - Stone  | Roof 3          | 425      | LF   | 6    | \$13,650  |  |
|                    | Downspouts - Interior Downspouts                      | Roof 2          | 1,700    | LF   | 6    | \$56,496  |  |
|                    | Downspouts - Interior Downspouts                      | Roof 3          | 120      | LF   | 6    | \$3,988   |  |
|                    | Parapet - Parapet < 16" Height                        | Roof 3          | 395      | LF   | 6    | \$8,416   |  |
|                    | Parapet - Parapet > 30"                               | Roof 2          | 745      | LF   | 6    | \$47,621  |  |
|                    | Parapet - Parapet > 30"                               | Roof 2          | 25       | LF   | 5    | \$9,492   | Several areas with loose and missing mortar joints / Several areas of modified bitumen cracking with open seams throughout |
|                    | Parapet - Parapet > 30"                               | Roof 3          | 40       | LF   | 6    | \$2,557   |  |
|                    | Roof Structure - Steel / Metal Deck/ Concrete Topping | Roof 2          | 18,350   | SF   | 7    | \$0       |  |
|                    | Roof Structure - Steel / Metal Deck/ Concrete Topping | Roof 3          | 4,795    | SF   | 7    | \$0       |  |
|                    | Roof - Modified Bitumen                               | Roof 2          | 18,050   | SF   | 6    | \$169,840 |  |
|                    | Roof - Modified Bitumen                               | Roof 2          | 300      | SF   | 5    | \$8,567   | Several areas around roof penetrations cracking with open seams  |
|                    | Roof - Modified Bitumen                               | Roof 3          | 4,595    | SF   | 6    | \$43,236  |  |
|                    | Roof - Modified Bitumen                               | Roof 3          | 200      | SF   | 5    | \$5,711   | Several areas around roof penetrations cracking with open seams, ponding occurring around roof drains                      |
| <b>Walls</b>       |   |                 |          |      |      |           |  |
|                    | Exterior Walls - Brick                                | Entire Building | 35,660   | SF   | 6    | \$239,671 |  |
|                    | Exterior Walls - Brick                                | Entire Building | 200      | SF   | 5    | \$4,762   | Several areas above perimeter flashing with loose and missing mortar joints  |
|                    | Exterior Walls - Concrete Block                       | Entire Building | 2,965    | SF   | 6    | \$19,928  | Outside chiller  |
|                    | Exterior Walls - Stone-Cast                           | Entire Building | 1,970    | SF   | 6    | \$13,240  |  |



**Building: Addition**
**Category: Building Exterior**

| Group                              | Item - Type                         | Location                    | Quantity | Unit | Rank | Cost             | Comments     |
|------------------------------------|-------------------------------------|-----------------------------|----------|------|------|------------------|--------------|
| <b>Windows</b>                     |                                     |                             |          |      |      |                  |              |
|                                    | Guard - Guards perforated           | Entire Building / 1st Floor | 2,585    | SF   | 6    | \$33,010         |              |
|                                    | Lintels - Steel                     | Entire Building             | 1,100    | LF   | 7    | \$0              |              |
|                                    | Windows - Decorative                | Entire Building             | 1,730    | SF   | 6    | \$12,914         | At corridors |
|                                    | Windows - Louver                    | Entire Building             | 546      | SF   | 6    | \$4,076          |              |
|                                    | Windows - Sash Aluminum Double-pane | Entire Building             | 7,450    | SF   | 6    | \$55,611         |              |
| <b>Building Exterior Subtotal:</b> |                                     |                             |          |      |      | <b>\$847,596</b> |              |

**Building: Addition**
**Category: Electrical System**

| Group                     | Item - Type  | Location        | Quantity | Unit | Rank | Cost     | Comments                                |
|---------------------------|--|-----------------|----------|------|------|----------|---|
| <b>Emergency System</b>   |  |                 |          |      |      |          |   |
|                           | Automatic Transfer Switch                          | Electrical Room | 1        | EA   | 6    | \$408    |   |
|                           | Emergency A/C Power - Corridors and Stairs         | Entire Building | 17,143   | SF   | 6    | \$5,148  | Generator powered from Main             |
|                           | Emergency A/C Power - Students Toilets             | Entire Building | 1,428    | SF   | 6    | \$531    | Generator powered from Main             |
|                           | Emergency Battery Packs - Corridors and Stairs     | Entire Building | 31       | EA   | 6    | \$6,278  |   |
|                           | Emergency Battery Packs - Students Toilets         | Entire Building | 6        | EA   | 6    | \$1,215  |   |
|                           | Exit Signs - Corridors and Stairs                  | Entire Building | 10       | EA   | 7    | \$0      | Generator powered from Main, Lights out |
|                           | Exit Signs - Corridors and Stairs                  | Entire Building | 39       | EA   | 7    | \$0      | Generator powered from Main             |
|                           | Security System - CCTV                             | Entire Building | 73,769   | SF   | 6    | \$22,153 | Served from Main                        |
|                           | Security System - Intrusion Detection              | Entire Building | 73,769   | SF   | 6    | \$18,988 |   |
| <b>Main Service</b>       |  |                 |          |      |      |          |   |
|                           | Independent Electrical Service for emergency power | Electrical Room | 1        | EA   | 7    | \$0      | Emergency feed from ComEd               |
|                           | Main Electrical Service - 2000 A 120/208/3PH       | Electrical Room | 3        | EA   | 7    | \$0      |   |
|                           | PA System  | Entire Building | 73,769   | SF   | 6    | \$24,263 | Serves from Main Building               |
| <b>Power Distribution</b> |  |                 |          |      |      |          |   |
|                           | Lighting and Power Panels - 100 A                  | Electrical Room | 1        | EA   | 6    | \$299    | Emergency fuse type                     |
|                           | Lighting and Power Panels - 100 A                  | Electrical Room | 2        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - 100 A                  | Electrical Room | 4        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 2        | EA   | 7    | \$0      |   |
|                           | Lighting and Power Panels - Above 100 A            | Electrical Room | 13       | EA   | 7    | \$0      |   |
|                           | Main Distribution Panels - 400 - 600 amp           | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Main Distribution Panels - 400 - 600 amp           | Electrical Room | 1        | EA   | 7    | \$0      |   |
|                           | Main Distribution Panels - Greater than 600 amp    | Electrical Room | 1        | EA   | 7    | \$0      |   |

**Building: Addition**
**Category: Electrical System**

| Group                     | Item - Type                      | Location        | Quantity | Unit | Rank | Cost    | Comments  |
|---------------------------|----------------------------------|-----------------|----------|------|------|---------|-----------|
| <b>Power Distribution</b> |                                  |                 |          |      |      |         |           |
|                           | Transformers - 277/480 - 120/208 | Electrical Room | 2        | EA   | 6    | \$2,530 | Emergency |
|                           | Transformers - 277/480 - 120/208 | Electrical Room | 2        | EA   | 6    | \$2,530 |           |
|                           | Transformers - 277/480 - 120/208 | Electrical Room | 1        | EA   | 6    | \$1,265 |           |

**Electrical System Subtotal:**
**\$85,607**
**Building: Addition**
**Category: Safty System**

| Group                     | Item - Type              | Location                          | Quantity | Unit | Rank | Cost     | Comments |
|---------------------------|--------------------------|-----------------------------------|----------|------|------|----------|----------|
| <b>Fire Alarm</b>         |                          |                                   |          |      |      |          |          |
|                           | Fire Alarm Strobe Lights | Electrical Room / Entire Building | 73,769   | SF   | 6    | \$26,372 |          |
|                           | Fire Alarm_System        | Electrical Room / Entire Building | 73,769   | SF   | 6    | \$35,866 |          |
|                           | Fire Pump Controller     | Electrical Room / Mechanical Room | 1        | EA   | 7    | \$0      |          |
| <b>Pump Room Assembly</b> |                          |                                   |          |      |      |          |          |
|                           | Fire Pump - 25-50 hp     | Mechanical Room                   | 1        | EA   | 6    | \$1,558  |          |
|                           | Jockey Pump              | Mechanical Room                   | 1        | EA   | 6    | \$758    |          |
| <b>Sprinkler System</b>   |                          |                                   |          |      |      |          |          |
|                           | Sprinkler Heads          | Entire Building                   | 73,769   | SF   | 7    | \$0      |          |
|                           | Sprinkler Piping         | Entire Building                   | 73,769   | SF   | 7    | \$0      |          |
|                           | Wet Sprinkler System     | Entire Building                   | 73,769   | SF   | 7    | \$0      |          |

**Safty System Subtotal:**
**\$64,555**
**Building: Addition**
**Category: Mechanical System**

| Group                   | Item - Type   | Location               | Quantity | Unit | Rank | Cost    | Comments                                    |
|-------------------------|---|------------------------|----------|------|------|---------|---|
| <b>Air Conditioning</b> |   |                        |          |      |      |         |   |
|                         | Chemical Pot Feeder   | Roof / Mechanical Room | 1        | EA   | 6    | \$606   |   |
|                         | Chiller-Air Cooled- Recipricating-Roof Mounted - 101 - 200 tons | Roof                   | 1        | EA   | 6    | \$4,314 | Serves Main Building's Lunch and Auditorium |
|                         | Chiller-Air Cooled- Recipricating-Roof Mounted - 201 - 300 tons | Roof                   | 1        | EA   | 6    | \$4,314 | Serves Addition's AH's                      |
|                         | Condensing Unit- Roof Mounted - 5-10 tons                       | Roof                   | 1        | EA   | 6    | \$3,334 | Serves Photo shop                           |
|                         | Condensing Unit- Roof Mounted - Less than 5 tons                | Roof                   | 1        | EA   | 6    | \$3,334 | Serves MDF room259                          |
|                         | Condensing Unit- Roof Mounted - Less than 5 tons                | Roof                   | 1        | EA   | 6    | \$3,334 |   |
|                         | Glycol Feed   | Roof / Mechanical Room | 1        | EA   | 6    | \$490   |   |
|                         | Pipes - Chilled Water Pipe- Steel                               | Roof / Mechanical Room | 200      | LF   | 7    | \$0     |   |

**Building: Addition**
**Category: Mechanical System**

| Group                       | Item - Type  | Location                                 | Quantity | Unit | Rank | Cost      | Comments  |
|-----------------------------|--|--|----------|------|------|-----------|---|
| <b>Air Handling Systems</b> |  |  |          |      |      |           |   |
|                             | Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm | Mechanical Room                          | 1        | EA   | 6    | \$3,350   |   |
|                             | Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm | Mechanical Room                          | 1        | EA   | 6    | \$3,350   |   |
|                             | Air Intake   | Mechanical Room / Roof                   | 1        | EA   | 7    | \$0       |   |
|                             | Air Intake   | Mechanical Room / Roof                   | 1        | EA   | 7    | \$0       |   |
|                             | Fan Power Box - Fan Power Box with Hot Water Coil  | Entire Building                          | 39       | EA   | 6    | \$19,219  | Water connections are starting to deteriorate and leak. |
|                             | Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM   | Mechanical Room / East Courtyard Facades | 2        | EA   | 6    | \$3,714   |   |
|                             | VAV Box  | Mechanical Room / 1st Floor              | 3        | EA   | 6    | \$837     | Split AH load   |
|                             | VAV Box  | Mechanical Room / 2nd Floor              | 3        | EA   | 6    | \$837     | Split AH load   |
|                             | VAV Box  | Mechanical Room / 3rd Floor              | 3        | EA   | 6    | \$837     | Split AH load   |
|                             | VAV Box  | Mechanical Room / Entire Building        | 9        | EA   | 6    | \$2,512   |   |
|                             | Zone Dampers   | Mechanical Room                          | 33       | EA   | 6    | \$27,490  |   |
|                             | Zone Dampers   | Mechanical Room / Entire Building        | 32       | EA   | 6    | \$26,657  |   |
| <b>Boiler Systems</b>       |  |  |          |      |      |           |   |
|                             | Boiler Auxiliary- Condensing Hot Water - 1001 - 2000 HP  | Boiler Room                              | 2        | EA   | 6    | \$6,176   |   |
|                             | Chemical Pot Feeder  | Boiler Room                              | 1        | EA   | 6    | \$725     |   |
|                             | Combustion Dampers   | Boiler Room                              | 2        | EA   | 6    | \$818     |   |
|                             | Condensing- Hot Water Boiler - 1001 - 2000 MBH   | Boiler Room                              | 2        | EA   | 6    | \$1,996   |   |
|                             | Glycol Feed System   | Boiler Room / Mechanical Room            | 1        | EA   | 6    | \$539     |   |
|                             | Hot Water Pump   | Boiler Room / Mechanical Room            | 2        | EA   | 6    | \$748     | Serves Addition   |
|                             | Hot Water Pump   | Boiler Room / Mechanical Room            | 2        | EA   | 6    | \$748     | Serves Lunch, Assembly hall in Main                     |
| <b>Heating Devices</b>      |  |  |          |      |      |           |   |
|                             | Cabinet Heaters - With Hot Water Coil  | Entire Building                          | 24       | EA   | 6    | \$8,504   |   |
|                             | Unit Heater - Hot Water  | Entire Building / Mechanical Room        | 8        | EA   | 6    | \$2,233   |   |
| <b>Mechanical Plumbing</b>  |  |  |          |      |      |           |   |
|                             | Chilled Water Pump - 10 - 20 HP  | Mechanical Room                          | 2        | EA   | 6    | \$2,485   |   |
|                             | Hydronic Supply and Return - Steel   | Entire Building                          | 500      | LF   | 6    | \$38,388  | Serves Hot water to devices and equipment               |
|                             | Hydronic Supply and Return - Steel   | Entire Building / Mechanical Room        | 200      | LF   | 6    | \$15,355  | Serves Chilled water to AH's                            |
| <b>Temperature Control</b>  |  |  |          |      |      |           |   |
|                             | DDC System   | Entire Building                          | 73,769   | SF   | 5    | \$121,313 | DDC and VAV do not communicate.                         |
|                             | Electric Controls  | Entire Building                          | 73,769   | SF   | 6    | \$0       |   |
|                             | Thermostats - DDC  | Entire Building                          | 62       | EA   | 6    | \$0       |   |

**Building: Addition**
**Category: Mechanical System**

| Group              | Item - Type                                    | Location                                | Quantity | Unit | Rank | Cost | Comments  |
|--------------------|--|---|----------|------|------|------|---|
| <b>Ventilation</b> |  |   |          |      |      |      |   |
|                    | Exhaust Fans- Indoor - 500 - 1500 CFM          | Roof, Mechanical Room / Mechanical Room | 1        | EA   | 7    | \$0  | Serves Boiler room in wall exhaust                    |
|                    | Exhaust Fans- Roof Mounted - 500 - 1500 CFM    | Roof, Mechanical Room / Roof            | 2        | EA   | 7    | \$0  |   |
|                    | Exhaust Fans- Roof Mounted - Less than 500 CFM | Roof, Mechanical Room / Roof            | 1        | EA   | 7    | \$0  |   |
|                    | Lab Exhaust Hood                               | Roof, Mechanical Room / Roof            | 3        | EA   | 7    | \$0  | Not in Service, Serves TV Studio, off since aprox2010 |

**Mechanical System Subtotal:**
**\$308,559**
**Building: Addition**
**Category: Plumbing System**

| Group            | Item - Type  | Location        | Quantity | Unit | Rank | Cost  | Comments |
|------------------|--|-----------------|----------|------|------|-------|----------|
| <b>Hot Water</b> |  |                 |          |      |      |       |          |
|                  | Gas Heater - 300001 - 600000 BTU/HR                | Mechanical Room | 2        | EA   | 6    | \$620 |          |
| <b>Piping</b>    |  |                 |          |      |      |       |          |
|                  | Domestic Piping-Cold Water from Risers to Fixtures | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Domestic Piping-Cold Water Horizontal Lines        | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Domestic Piping-Cold Water Risers                  | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Domestic Piping-Hot Water from Risers to Fixtures  | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Domestic Piping-Hot Water Horizontal Lines         | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Domestic Piping-Hot Water Return Lines             | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Domestic Piping-Hot Water Return Risers            | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Sanitary Piping                                    | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Storm Piping                                       | Entire Building | 73,769   | SF   | 7    | \$0   |          |
|                  | Vent Piping  | Entire Building | 73,769   | SF   | 7    | \$0   |          |

**Plumbing System Subtotal:**
**\$620**
**Building: Addition**
**Category: Classrooms**

| Group                              | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|------------------------------------|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #151 (Music Room)</b> |                             |           |          |      |      |         |          |
|                                    | Ceiling - Plaster/Drywall   | 1st Floor | 2,750    | SF   | 6    | \$9,517 |          |
|                                    | Doors - Wood Doors inclu hw | 1st Floor | 4        | EA   | 6    | \$1,204 |          |
|                                    | Floor - Tile/Sheet          | 1st Floor | 2,750    | SF   | 6    | \$2,753 |          |
|                                    | Lighting - Lay-in           | 1st Floor | 32       | EA   | 6    | \$3,807 |          |

**Building: Addition**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #151 (Music Room)</b>        |                             |           |          |      |      |         |          |
|   | Marker Board                | 1st Floor | 12       | LF   | 6    | \$257   |          |
|   | Sound Panels                | 1st Floor | 480      | EA   | 6    | \$1,936 |          |
|   | Walls - Concrete Block      | 1st Floor | 2,510    | SF   | 6    | \$7,358 |          |
| <b>Classroom #151A (Office)</b>           |                             |           |          |      |      |         |          |
|   | Ceiling - Lay-in            | 1st Floor | 600      | SF   | 6    | \$1,802 |          |
|   | Doors - Steel Doors incl hw | 1st Floor | 2        | EA   | 6    | \$602   |          |
|   | Floor - Tile/Sheet          | 1st Floor | 600      | SF   | 6    | \$601   |          |
|   | Lighting - Lay-in           | 1st Floor | 5        | EA   | 6    | \$595   |          |
|   | Walls - Concrete Block      | 1st Floor | 1,000    | SF   | 6    | \$2,932 |          |
|   | Walls - Plaster/Drywall     | 1st Floor | 1,200    | SF   | 6    | \$3,312 |          |
| <b>Classroom #154 (Regular Classroom)</b> |                             |           |          |      |      |         |          |
|   | Casework                    | 1st Floor | 18       | LF   | 6    | \$455   |          |
|   | Ceiling - Lay-in            | 1st Floor | 1,203    | SF   | 6    | \$3,613 |          |
|   | Doors - Side-lite           | 1st Floor | 6        | SF   | 6    | \$100   |          |
|   | Doors - Steel Doors incl hw | 1st Floor | 1        | EA   | 6    | \$301   |          |
|   | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301   |          |
|   | Floor - Tile/Sheet          | 1st Floor | 1,203    | SF   | 6    | \$1,204 |          |
|   | Lighting - Lay-in           | 1st Floor | 15       | EA   | 6    | \$1,785 |          |
|   | Marker Board                | 1st Floor | 24       | LF   | 6    | \$514   |          |
|   | Walls - Concrete Block      | 1st Floor | 1,794    | SF   | 6    | \$5,259 |          |
| <b>Classroom #156 (Music Room)</b>        |                             |           |          |      |      |         |          |
|   | Ceiling - Lay-in            | 1st Floor | 1,292    | SF   | 6    | \$3,880 |          |
|   | Doors - Steel Doors incl hw | 1st Floor | 3        | EA   | 6    | \$903   |          |
|   | Floor - Tile/Sheet          | 1st Floor | 1,292    | SF   | 6    | \$1,293 |          |
|   | Lighting - Lay-in           | 1st Floor | 18       | EA   | 6    | \$2,142 |          |
|   | Marker Board                | 1st Floor | 20       | LF   | 6    | \$428   |          |
|   | Sound Panels                | 1st Floor | 20       | EA   | 6    | \$81    |          |
|   | Walls - Concrete Block      | 1st Floor | 3,230    | SF   | 6    | \$9,469 |          |
| <b>Classroom #159 (Band Room)</b>         |                             |           |          |      |      |         |          |
|   | Ceiling - Plaster/Drywall   | 1st Floor | 2,750    | SF   | 6    | \$9,517 |          |
|   | Doors - Wood Doors incl hw  | 1st Floor | 4        | EA   | 6    | \$1,204 |          |
|   | Floor - Tile/Sheet          | 1st Floor | 2,750    | SF   | 6    | \$2,753 |          |
|   | Instrument Storage Casework | 1st Floor | 30       | LF   | 6    | \$0     |          |
|   | Lighting - Lay-in           | 1st Floor | 37       | EA   | 6    | \$4,402 |          |
|   | Risers                      | 1st Floor | 240      | LF   | 6    | \$5,402 |          |

**Building: Addition**
**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost     | Comments |
|---|-----------------------------|-----------|----------|------|------|----------|----------|
| <b>Classroom #159 (Band Room)</b>           |                             |           |          |      |      |          |          |
|   | Sound Panels                | 1st Floor | 20       | EA   | 6    | \$81     |          |
|   | Walls - Concrete Block      | 1st Floor | 2,330    | SF   | 6    | \$6,830  |          |
| <b>Classroom #159A (Office)</b>             |                             |           |          |      |      |          |          |
|   | Ceiling - Lay-in            | 1st Floor | 650      | SF   | 6    | \$1,952  |          |
|   | Doors - Steel Doors incl hw | 1st Floor | 2        | EA   | 6    | \$602    |          |
|   | Floor - Tile/Sheet          | 1st Floor | 650      | SF   | 6    | \$651    |          |
|   | Lighting - Lay-in           | 1st Floor | 7        | EA   | 6    | \$833    |          |
|   | Walls - Concrete Block      | 1st Floor | 1,000    | SF   | 6    | \$2,932  |          |
|   | Walls - Plaster/Drywall     | 1st Floor | 1,200    | SF   | 6    | \$3,312  |          |
| <b>Classroom #160 (Regular Classroom)</b>   |                             |           |          |      |      |          |          |
|   | Ceiling - Lay-in            | 1st Floor | 594      | SF   | 6    | \$1,784  |          |
|   | Doors - Side-lite           | 1st Floor | 12       | SF   | 6    | \$201    |          |
|   | Doors - Wood Doors inclu hw | 1st Floor | 1        | EA   | 6    | \$301    |          |
|   | Floor - Tile/Sheet          | 1st Floor | 594      | SF   | 6    | \$595    |          |
|   | Lighting - Lay-in           | 1st Floor | 9        | EA   | 6    | \$1,071  |          |
|   | Marker Board                | 1st Floor | 20       | LF   | 6    | \$428    |          |
|   | Storage/ Closet             | 1st Floor | 6        | SF   | 6    | \$44     |          |
|   | Walls - Concrete Block      | 1st Floor | 992      | SF   | 6    | \$2,908  |          |
| <b>Classroom #251 (Science Lab Level 1)</b> |                             |           |          |      |      |          |          |
|   | Casework                    | 2nd Floor | 90       | LF   | 6    | \$2,273  |          |
|   | Ceiling - Lay-in            | 2nd Floor | 1,525    | SF   | 6    | \$4,580  |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602    |          |
|   | Eye Wash Station            | 2nd Floor | 2        | EA   | 6    | \$672    |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 1,525    | SF   | 6    | \$1,527  |          |
|   | Fume Hood                   | 2nd Floor | 1        | EA   | 6    | \$816    |          |
|   | Gas Line                    | 2nd Floor | 8        | EA   | 6    | \$4,073  |          |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 7    | \$0      |          |
|   | Marker Board                | 2nd Floor | 45       | LF   | 7    | \$0      |          |
|   | Science Lab Elements        | 2nd Floor | 1,525    | SF   | 6    | \$10,337 |          |
|   | Science Lab Shower          | 2nd Floor | 1        | EA   | 6    | \$379    |          |
|   | Walls - Concrete Block      | 2nd Floor | 1,285    | SF   | 6    | \$3,767  |          |
|   | Work Sink                   | 2nd Floor | 11       | EA   | 6    | \$4,169  |          |
| <b>Classroom #253 (Science Lab Level 1)</b> |                             |           |          |      |      |          |          |
|   | Casework                    | 2nd Floor | 80       | LF   | 6    | \$2,020  |          |
|   | Ceiling - Lay-in            | 2nd Floor | 1,450    | SF   | 6    | \$4,354  |          |

**Building: Addition**
**Category: Classrooms**

| Group                                       | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| <b>Classroom #253 (Science Lab Level 1)</b> |                             |           |          |      |      |         |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 2        | EA   | 6    | \$602   |          |
|   | Eye Wash Station            | 2nd Floor | 2        | EA   | 6    | \$672   |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 1,450    | SF   | 6    | \$1,451 |          |
|   | Fume Hood                   | 2nd Floor | 1        | EA   | 6    | \$816   |          |
|   | Gas Line                    | 2nd Floor | 8        | EA   | 6    | \$4,073 |          |
|   | Lighting - Lay-in           | 2nd Floor | 21       | EA   | 7    | \$0     |          |
|   | Marker Board                | 2nd Floor | 45       | LF   | 7    | \$0     |          |
|   | Science Lab Elements        | 2nd Floor | 1,450    | SF   | 6    | \$9,828 |          |
|   | Science Lab Shower          | 2nd Floor | 1        | EA   | 6    | \$379   |          |
|   | Walls - Concrete Block      | 2nd Floor | 1,309    | SF   | 6    | \$3,837 |          |
|   | Work Sink                   | 2nd Floor | 11       | EA   | 6    | \$4,169 |          |
| <b>Classroom #254 (Regular Classroom)</b>   |                             |           |          |      |      |         |          |
|   | Casework                    | 2nd Floor | 19       | LF   | 6    | \$480   |          |
|   | Ceiling - Lay-in            | 2nd Floor | 915      | SF   | 6    | \$2,748 |          |
|   | Doors - Side-lite           | 2nd Floor | 6        | SF   | 6    | \$100   |          |
|   | Doors - Steel Doors incl hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 915      | SF   | 6    | \$916   |          |
|   | Lighting - Lay-in           | 2nd Floor | 12       | EA   | 7    | \$0     |          |
|   | Marker Board                | 2nd Floor | 10       | LF   | 7    | \$0     |          |
|   | Storage/ Closet             | 2nd Floor | 5        | SF   | 6    | \$36    |          |
|   | Walls - Concrete Block      | 2nd Floor | 696      | SF   | 6    | \$2,040 |          |
|   | Walls - Plaster/Drywall     | 2nd Floor | 295      | SF   | 6    | \$814   |          |
| <b>Classroom #255 (Science Lab Level 2)</b> |                             |           |          |      |      |         |          |
|   | Casework                    | 2nd Floor | 120      | LF   | 6    | \$3,030 |          |
|   | Ceiling - Lay-in            | 2nd Floor | 1,208    | SF   | 6    | \$3,628 |          |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |          |
|   | Eye Wash Station            | 2nd Floor | 1        | EA   | 6    | \$336   |          |
|   | Floor - Tile/Sheet          | 2nd Floor | 1,208    | SF   | 6    | \$1,209 |          |
|   | Fume Hood                   | 2nd Floor | 1        | EA   | 6    | \$816   |          |
|   | Gas Line                    | 2nd Floor | 7        | EA   | 6    | \$3,564 |          |
|   | Lighting - Lay-in           | 2nd Floor | 19       | EA   | 7    | \$0     |          |
|   | Marker Board                | 2nd Floor | 45       | LF   | 6    | \$964   |          |
|   | Science Lab Elements        | 2nd Floor | 1,208    | SF   | 6    | \$8,188 |          |
|   | Science Lab Shower          | 2nd Floor | 1        | EA   | 6    | \$379   |          |
|   | Walls - Concrete Block      | 2nd Floor | 1,320    | SF   | 6    | \$3,870 |          |
|   | Work Sink                   | 2nd Floor | 10       | EA   | 6    | \$3,790 |          |

**Building: Addition**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments          |
|---|-----------------------------|-----------|----------|------|------|---------|-------------------|
| <b>Classroom #256 (Regular Classroom)</b> |                             |           |          |      |      |         |                   |
|   | Casework                    | 2nd Floor | 6        | LF   | 6    | \$152   |                   |
|   | Ceiling - Lay-in            | 2nd Floor | 915      | SF   | 6    | \$2,748 |                   |
|   | Doors - Side-lite           | 2nd Floor | 6        | SF   | 6    | \$100   |                   |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 6        | EA   | 6    | \$1,806 |                   |
|   | Floor - Tile/Sheet          | 2nd Floor | 915      | SF   | 6    | \$916   |                   |
|   | Lighting - Lay-in           | 2nd Floor | 12       | EA   | 7    | \$0     |                   |
|   | Marker Board                | 2nd Floor | 10       | LF   | 7    | \$0     |                   |
|   | Walls - Concrete Block      | 2nd Floor | 426      | SF   | 6    | \$1,249 |                   |
|   | Walls - Plaster/Drywall     | 2nd Floor | 538      | SF   | 6    | \$1,485 |                   |
| <b>Classroom #257 (Regular Classroom)</b> |                             |           |          |      |      |         |                   |
|   | Ceiling - Lay-in            | 2nd Floor | 768      | SF   | 6    | \$2,306 |                   |
|   | Doors - Side-lite           | 2nd Floor | 6        | SF   | 6    | \$100   |                   |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |                   |
|   | Floor - Tile/Sheet          | 2nd Floor | 768      | SF   | 6    | \$769   |                   |
|   | Lighting - Lay-in           | 2nd Floor | 13       | EA   | 7    | \$0     |                   |
|   | Marker Board                | 2nd Floor | 12       | LF   | 7    | \$0     |                   |
|   | Walls - Concrete Block      | 2nd Floor | 920      | SF   | 6    | \$2,697 |                   |
|   | Walls - Plaster/Drywall     | 2nd Floor | 228      | SF   | 6    | \$629   |                   |
| <b>Classroom #258 (Regular Classroom)</b> |                             |           |          |      |      |         |                   |
|   | Casework                    | 2nd Floor | 13       | LF   | 6    | \$328   |                   |
|   | Ceiling - Lay-in            | 2nd Floor | 750      | SF   | 6    | \$2,252 |                   |
|   | Doors - Side-lite           | 2nd Floor | 6        | SF   | 6    | \$100   |                   |
|   | Doors - Wood Doors inclu hw | 2nd Floor | 1        | EA   | 6    | \$301   |                   |
|   | Floor - Tile/Sheet          | 2nd Floor | 750      | SF   | 6    | \$751   |                   |
|   | Lighting - Lay-in           | 2nd Floor | 9        | EA   | 7    | \$0     |                   |
|   | Marker Board                | 2nd Floor | 10       | LF   | 7    | \$0     |                   |
|   | Storage/ Closet             | 2nd Floor | 5        | SF   | 6    | \$36    |                   |
|   | Walls - Concrete Block      | 2nd Floor | 870      | SF   | 6    | \$2,550 |                   |
| <b>Classroom #259 (Computer Lab)</b>      |                             |           |          |      |      |         |                   |
|   | Ceiling - Lay-in            |           | 1,443    | SF   | 6    | \$4,333 |                   |
|   | Charging Station            |           | 8        | EA   | 6    | \$3,877 |                   |
|   | Doors - Wood Doors inclu hw |           | 4        | EA   | 6    | \$1,204 |                   |
|   | Floor - Tile/Sheet          |           | 1,443    | SF   | 6    | \$1,444 |                   |
|   | Lighting - Lay-in           |           | 22       | EA   | 6    | \$2,617 |                   |
|   | Marker Board                |           | 20       | LF   | 7    | \$0     |                   |
|   | Storage/ Closet             |           | 179      | SF   | 6    | \$1,298 | 259A tech storage |



**Building: Addition**
**Category: Classrooms**

| Group  | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments              |
|--|-----------------------------|-----------|----------|------|------|---------|-----------------------|
| <b>Classroom #259 (Computer Lab)</b>             |                             |           |          |      |      |         |                       |
|  | Walls - Concrete Block      |           | 1,170    | SF   | 6    | \$3,430 |                       |
| <b>Classroom #260 (Regular Classroom)</b>        |                             |           |          |      |      |         |                       |
|  | Casework                    | 2nd Floor | 9        | LF   | 6    | \$227   |                       |
|  | Ceiling - Lay-in            | 2nd Floor | 565      | SF   | 6    | \$1,697 |                       |
|  | Doors - Side-lite           | 2nd Floor | 6        | SF   | 6    | \$100   |                       |
|  | Doors - Steel Doors incl hw | 2nd Floor | 1        | EA   | 6    | \$301   |                       |
|  | Floor - Tile/Sheet          | 2nd Floor | 565      | SF   | 6    | \$566   |                       |
|  | Lighting - Lay-in           | 2nd Floor | 9        | EA   | 7    | \$0     |                       |
|  | Marker Board                | 2nd Floor | 10       | LF   | 6    | \$214   |                       |
|  | Walls - Concrete Block      | 2nd Floor | 756      | SF   | 6    | \$2,216 |                       |
| <b>Classroom #261 (Computer Lab)</b>             |                             |           |          |      |      |         |                       |
|  | Ceiling - Lay-in            | 2nd Floor | 1,543    | SF   | 6    | \$4,634 |                       |
|  | Doors - Wood Doors inclu hw | 2nd Floor | 4        | EA   | 6    | \$1,204 |                       |
|  | Floor - Tile/Sheet          | 2nd Floor | 1,543    | SF   | 6    | \$1,545 |                       |
|  | Lighting - Lay-in           | 2nd Floor | 22       | EA   | 7    | \$0     |                       |
|  | Marker Board                | 2nd Floor | 12       | LF   | 7    | \$0     |                       |
|  | Storage/ Closet             | 2nd Floor | 204      | SF   | 6    | \$1,479 | 261A storage          |
|  | Walls - Concrete Block      | 2nd Floor | 1,005    | SF   | 6    | \$2,946 |                       |
|  | Walls - Plaster/Drywall     | 2nd Floor | 565      | SF   | 6    | \$1,559 |                       |
| <b>Classroom #351 (Other Instructional Use)</b>  |                             |           |          |      |      |         |                       |
|  | Ceiling - Exposed           | 3rd Floor | 2,110    | SF   | 6    | \$3,138 |                       |
|  | Doors - Steel Doors incl hw | 3rd Floor | 4        | EA   | 6    | \$1,204 |                       |
|  | Floor - Tile/Sheet          | 3rd Floor | 2,110    | SF   | 6    | \$2,112 |                       |
|  | Lighting - Pendent/Surface  | 3rd Floor | 18       | EA   | 4    | \$9,732 | Incandescent fixtures |
|  | Marker Board                | 3rd Floor | 16       | LF   | 7    | \$0     |                       |
|  | Walls - Concrete Block      | 3rd Floor | 2,540    | SF   | 6    | \$7,446 |                       |
| <b>Classroom #351A (Other Instructional Use)</b> |                             |           |          |      |      |         |                       |
|  | Ceiling - Lay-in            | 3rd Floor | 488      | SF   | 6    | \$1,465 |                       |
|  | Doors - Steel Doors incl hw | 3rd Floor | 2        | EA   | 6    | \$602   |                       |
|  | Doors - Transom Window      | 3rd Floor | 115      | SF   | 6    | \$1,947 |                       |
|  | Floor - Tile/Sheet          | 3rd Floor | 488      | SF   | 6    | \$488   |                       |
|  | Lighting - Lay-in           | 3rd Floor | 5        | EA   | 6    | \$595   |                       |
|  | Walls - Concrete Block      | 3rd Floor | 840      | SF   | 6    | \$2,462 |                       |
| <b>Classroom #351B (Other Instructional Use)</b> |                             |           |          |      |      |         |                       |
|  | Ceiling - Lay-in            | 3rd Floor | 464      | SF   | 6    | \$1,393 |                       |

**Building: Addition**
**Category: Classrooms**

| Group  | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                    |
|--|-----------------------------|-----------|----------|------|------|---------|-----------------------------|
| <b>Classroom #351B (Other Instructional Use)</b> |                             |           |          |      |      |         |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 24       | SF   | 5    | \$192   | Water damaged ceiling tiles |
|  | Doors - Steel Doors incl hw | 3rd Floor | 2        | EA   | 6    | \$602   |                             |
|  | Doors - Transom Window      | 3rd Floor | 58       | SF   | 6    | \$982   |                             |
|  | Floor - Tile/Sheet          | 3rd Floor | 488      | SF   | 6    | \$488   |                             |
|  | Lighting - Lay-in           | 3rd Floor | 5        | EA   | 7    | \$0     |                             |
|  | Walls - Concrete Block      | 3rd Floor | 840      | SF   | 6    | \$2,462 |                             |
| <b>Classroom #354 (Regular Classroom)</b>        |                             |           |          |      |      |         |                             |
|  | Casework                    | 3rd Floor | 18       | LF   | 6    | \$455   |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 900      | SF   | 6    | \$2,703 |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 15       | SF   | 5    | \$120   | Water damaged ceiling tiles |
|  | Doors - Side-lite           | 3rd Floor | 6        | SF   | 6    | \$100   |                             |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                             |
|  | Floor - Tile/Sheet          | 3rd Floor | 915      | SF   | 6    | \$916   |                             |
|  | Lighting - Lay-in           | 3rd Floor | 12       | EA   | 7    | \$0     |                             |
|  | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |                             |
|  | Storage/ Closet             | 3rd Floor | 5        | SF   | 6    | \$36    |                             |
|  | Walls - Concrete Block      | 3rd Floor | 939      | SF   | 6    | \$2,753 |                             |
|  | Walls - Plaster/Drywall     | 3rd Floor | 264      | SF   | 6    | \$729   |                             |
| <b>Classroom #355 (Regular Classroom)</b>        |                             |           |          |      |      |         |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 1,100    | SF   | 6    | \$3,303 |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 10       | SF   | 5    | \$80    | Water damaged ceiling tiles |
|  | Doors - Side-lite           | 3rd Floor | 12       | SF   | 6    | \$201   |                             |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |                             |
|  | Floor - Tile/Sheet          | 3rd Floor | 1,110    | SF   | 6    | \$1,111 |                             |
|  | Lighting - Lay-in           | 3rd Floor | 16       | EA   | 7    | \$0     |                             |
|  | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |                             |
|  | Storage/ Closet             | 3rd Floor | 189      | SF   | 6    | \$1,370 |                             |
|  | Walls - Concrete Block      | 3rd Floor | 1,230    | SF   | 6    | \$3,606 |                             |
| <b>Classroom #356 (Regular Classroom)</b>        |                             |           |          |      |      |         |                             |
|  | Casework                    | 3rd Floor | 20       | LF   | 6    | \$505   |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 895      | SF   | 6    | \$2,688 |                             |
|  | Ceiling - Lay-in            | 3rd Floor | 20       | SF   | 5    | \$160   |                             |
|  | Doors - Side-lite           | 3rd Floor | 6        | SF   | 6    | \$100   |                             |
|  | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                             |
|  | Floor - Tile/Sheet          | 3rd Floor | 915      | SF   | 6    | \$916   |                             |
|  | Lighting - Lay-in           | 3rd Floor | 12       | EA   | 7    | \$0     |                             |

**Building: Addition**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                    |
|---|-----------------------------|-----------|----------|------|------|---------|-----------------------------|
| <b>Classroom #356 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Marker Board                | 3rd Floor | 10       | LF   | 6    | \$214   |                             |
|   | Storage/ Closet             | 3rd Floor | 5        | SF   | 6    | \$36    |                             |
|   | Walls - Concrete Block      | 3rd Floor | 462      | SF   | 6    | \$1,354 |                             |
|   | Walls - Plaster/Drywall     | 3rd Floor | 528      | SF   | 6    | \$1,457 |                             |
| <b>Classroom #357 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Casework                    | 3rd Floor | 33       | LF   | 6    | \$833   |                             |
|   | Ceiling - Lay-in            | 3rd Floor | 1,070    | SF   | 6    | \$3,213 |                             |
|   | Ceiling - Lay-in            | 3rd Floor | 40       | SF   | 5    | \$319   | Water damaged ceiling tiles |
|   | Doors - Side-lite           | 3rd Floor | 6        | SF   | 6    | \$100   |                             |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 2        | EA   | 6    | \$602   |                             |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,110    | SF   | 6    | \$1,111 |                             |
|   | Lighting - Lay-in           | 3rd Floor | 16       | EA   | 7    | \$0     |                             |
|   | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |                             |
|   | Storage/ Closet             | 3rd Floor | 189      | SF   | 6    | \$1,370 |                             |
|   | Walls - Concrete Block      | 3rd Floor | 1,230    | SF   | 6    | \$3,606 |                             |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 6    | \$1,137 |                             |
| <b>Classroom #358 (Regular Classroom)</b> |                             |           |          |      |      |         |                             |
|   | Casework                    | 3rd Floor | 14       | LF   | 6    | \$354   |                             |
|   | Ceiling - Lay-in            | 3rd Floor | 915      | SF   | 6    | \$2,748 |                             |
|   | Doors - Side-lite           | 3rd Floor | 8        | SF   | 6    | \$134   |                             |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                             |
|   | Floor - Tile/Sheet          | 3rd Floor | 915      | SF   | 6    | \$916   |                             |
|   | Lighting - Lay-in           | 3rd Floor | 9        | EA   | 7    | \$0     |                             |
|   | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |                             |
|   | Storage/ Closet             | 3rd Floor | 5        | SF   | 6    | \$36    |                             |
|   | Walls - Concrete Block      | 3rd Floor | 786      | SF   | 6    | \$2,304 |                             |
|   | Walls - Plaster/Drywall     | 3rd Floor | 258      | SF   | 6    | \$712   |                             |
| <b>Classroom #359 (Art Room)</b>          |                             |           |          |      |      |         |                             |
|   | Casework                    | 3rd Floor | 50       | LF   | 6    | \$1,263 |                             |
|   | Ceiling - Lay-in            | 3rd Floor | 1,090    | SF   | 6    | \$3,273 |                             |
|   | Ceiling - Lay-in            | 3rd Floor | 20       | SF   | 5    | \$160   | Water damaged ceiling tiles |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 4        | EA   | 6    | \$1,204 |                             |
|   | Floor - Tile/Sheet          | 3rd Floor | 1,110    | SF   | 6    | \$1,111 |                             |
|   | Lighting - Lay-in           | 3rd Floor | 20       | EA   | 7    | \$0     |                             |
|   | Marker Board                | 3rd Floor | 10       | LF   | 7    | \$0     |                             |
|   | Walls - Concrete Block      | 3rd Floor | 1,940    | SF   | 6    | \$5,687 |                             |

**Building: Addition**
**Category: Classrooms**

| Group                                     | Item - Type                 | Location  | Quantity | Unit | Rank | Cost    | Comments                      |
|---|-----------------------------|-----------|----------|------|------|---------|-------------------------------|
| <b>Classroom #359 (Art Room)</b>          |                             |           |          |      |      |         |                               |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 6    | \$1,137 |                               |
| <b>Classroom #360 (Regular Classroom)</b> |                             |           |          |      |      |         |                               |
|   | Casework                    | 3rd Floor | 12       | LF   | 6    | \$303   |                               |
|   | Ceiling - Lay-in            | 3rd Floor | 565      | SF   | 6    | \$1,697 |                               |
|   | Doors - Side-lite           | 3rd Floor | 6        | SF   | 6    | \$100   |                               |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 1        | EA   | 6    | \$301   |                               |
|   | Floor - Tile                | 3rd Floor | 565      | SF   | 6    | \$1,236 |                               |
|   | Lighting - Lay-in           | 3rd Floor | 9        | EA   | 7    | \$0     |                               |
|   | Marker Board                | 3rd Floor | 12       | LF   | 7    | \$0     |                               |
|   | Walls - Concrete Block      | 3rd Floor | 990      | SF   | 6    | \$2,902 |                               |
| <b>Classroom #361 (Art Room)</b>          |                             |           |          |      |      |         |                               |
|   | Casework                    | 3rd Floor | 10       | LF   | 6    | \$253   |                               |
|   | Ceiling - Lay-in            | 3rd Floor | 1,100    | SF   | 6    | \$3,303 |                               |
|   | Ceiling - Lay-in            | 3rd Floor | 10       | SF   | 5    | \$80    | Weather damaged ceiling tiles |
|   | Doors - Wood Doors inclu hw | 3rd Floor | 4        | EA   | 6    | \$1,204 |                               |
|   | Floor - Tile                | 3rd Floor | 1,110    | SF   | 6    | \$2,429 |                               |
|   | Lighting - Lay-in           | 3rd Floor | 20       | EA   | 6    | \$2,380 |                               |
|   | Marker Board                | 3rd Floor | 24       | LF   | 6    | \$514   |                               |
|   | Storage/ Closet             | 3rd Floor | 8        | SF   | 6    | \$58    |                               |
|   | Storage/ Closet             | 3rd Floor | 8        | SF   | 6    | \$58    |                               |
|   | Walls - Concrete Block      | 3rd Floor | 1,595    | SF   | 6    | \$4,676 |                               |
|   | Work Sink                   | 3rd Floor | 3        | EA   | 6    | \$1,137 |                               |
| <b>Classroom #361A (Art Room)</b>         |                             |           |          |      |      |         |                               |
|   | Casework                    | 3rd Floor | 20       | LF   | 6    | \$505   |                               |
|   | Ceiling - Lay-in            | 3rd Floor | 30       | SF   | 5    | \$208   | Water damaged ceiling tiles   |
|   | Ceiling - Lay-in            | 3rd Floor | 220      | SF   | 6    | \$661   |                               |
|   | Doors - Steel Doors incl hw | 3rd Floor | 1        | EA   | 6    | \$301   |                               |
|   | Floor - Tile                | 3rd Floor | 250      | SF   | 6    | \$547   |                               |
|   | Kiln                        | 3rd Floor | 2        | EA   | 6    | \$4,642 |                               |
|   | Lighting - Lay-in           | 3rd Floor | 4        | EA   | 7    | \$0     |                               |
|   | Walls - Concrete Block      | 3rd Floor | 645      | SF   | 6    | \$1,891 |                               |
|   | Work Sink                   | 3rd Floor | 1        | EA   | 6    | \$379   |                               |

**Classrooms Subtotal:**
**\$406,398**
**Building: Addition**

**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location            | Quantity | Unit | Rank | Cost    | Comments     |
|--------------------------------------|-----------------------------|---------------------|----------|------|------|---------|--------------|
| <b>Administrative Suites/Offices</b> |                             |                     |          |      |      |         |              |
|                                      | Ceiling - Lay-in            | 151B Music Library  | 185      | SF   | 6    | \$556   |              |
|                                      | Doors - Steel Doors incl hw | 151B Music Library  | 1        | EA   | 6    | \$301   |              |
|                                      | Floor - Tile/Sheet          | 151B Music Library  | 185      | SF   | 6    | \$185   |              |
|                                      | Lighting - Lay-in           | 151B Music Library  | 4        | EA   | 6    | \$476   |              |
|                                      | Power Distribution          | 151B Music Library  | 8        | EA   | 7    | \$0     |              |
|                                      | Walls - Concrete Block      | 151B Music Library  | 462      | SF   | 6    | \$1,354 |              |
|                                      | Ceiling - Lay-in            | 151C Pracitice Room | 170      | SF   | 6    | \$511   |              |
|                                      | Doors - Wood Doors inclu hw | 151C Pracitice Room | 2        | EA   | 6    | \$602   |              |
|                                      | Floor - Tile/Sheet          | 151C Pracitice Room | 170      | SF   | 6    | \$170   |              |
|                                      | Lighting - Lay-in           | 151C Pracitice Room | 2        | EA   | 6    | \$238   |              |
|                                      | Power Distribution          | 151C Pracitice Room | 8        | EA   | 7    | \$0     |              |
|                                      | Walls - Concrete Block      | 151C Pracitice Room | 425      | SF   | 6    | \$1,246 |              |
|                                      | Ceiling - Lay-in            | 151D Pracitice Room | 99       | SF   | 6    | \$297   |              |
|                                      | Floor - Tile/Sheet          | 151D Pracitice Room | 99       | SF   | 6    | \$99    |              |
|                                      | Lighting - Lay-in           | 151D Pracitice Room | 1        | EA   | 6    | \$119   |              |
|                                      | Power Distribution          | 151D Pracitice Room | 4        | EA   | 7    | \$0     |              |
|                                      | Walls - Concrete Block      | 151D Pracitice Room | 123      | SF   | 6    | \$361   |              |
|                                      | Walls - Plaster/Drywall     | 151D Pracitice Room | 123      | SF   | 6    | \$339   |              |
|                                      | Walls - Plaster/Drywall     | 151D Pracitice Room | 5        | SF   | 5    | \$26    | Hole in wall |
|                                      | Ceiling - Lay-in            | 151E Practice Room  | 99       | SF   | 6    | \$297   |              |
|                                      | Floor - Tile/Sheet          | 151E Practice Room  | 99       | SF   | 6    | \$99    |              |
|                                      | Lighting - Lay-in           | 151E Practice Room  | 1        | EA   | 6    | \$119   |              |
|                                      | Power Distribution          | 151E Practice Room  | 4        | EA   | 7    | \$0     |              |
|                                      | Walls - Concrete Block      | 151E Practice Room  | 70       | SF   | 6    | \$205   |              |
|                                      | Walls - Plaster/Drywall     | 151E Practice Room  | 200      | SF   | 6    | \$552   |              |
|                                      | Ceiling - Lay-in            | 151F Practice Room  | 185      | SF   | 6    | \$556   |              |
|                                      | Doors - Steel Doors incl hw | 151F Practice Room  | 1        | EA   | 6    | \$301   |              |
|                                      | Floor - Tile/Sheet          | 151F Practice Room  | 185      | SF   | 6    | \$185   |              |
|                                      | Lighting - Lay-in           | 151F Practice Room  | 4        | EA   | 6    | \$476   |              |
|                                      | Power Distribution          | 151F Practice Room  | 8        | EA   | 7    | \$0     |              |
|                                      | Walls - Concrete Block      | 151F Practice Room  | 462      | SF   | 6    | \$1,354 |              |
|                                      | Ceiling - Lay-in            | 159B Practice Room  | 99       | SF   | 6    | \$297   |              |
|                                      | Floor - Tile/Sheet          | 159B Practice Room  | 99       | SF   | 6    | \$99    |              |
|                                      | Lighting - Lay-in           | 159B Practice Room  | 1        | EA   | 6    | \$119   |              |
|                                      | Power Distribution          | 159B Practice Room  | 4        | EA   | 7    | \$0     |              |
|                                      | Walls - Concrete Block      | 159B Practice Room  | 70       | SF   | 6    | \$205   |              |
|                                      | Walls - Plaster/Drywall     | 159B Practice Room  | 200      | SF   | 6    | \$552   |              |
|                                      | Ceiling - Lay-in            | 159C Practice Room  | 99       | SF   | 6    | \$297   |              |
|                                      | Floor - Tile/Sheet          | 159C Practice Room  | 99       | SF   | 6    | \$99    |              |

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

| Group                                | Item - Type                 | Location                 | Quantity | Unit | Rank | Cost     | Comments                              |
|--------------------------------------|-----------------------------|--------------------------|----------|------|------|----------|---------------------------------------|
| <b>Administrative Suites/Offices</b> |                             |                          |          |      |      |          |                                       |
|                                      | Lighting - Lay-in           | 159C Practice Room       | 1        | EA   | 6    | \$119    |                                       |
|                                      | Power Distribution          | 159C Practice Room       | 4        | EA   | 7    | \$0      |                                       |
|                                      | Walls - Concrete Block      | 159C Practice Room       | 70       | SF   | 6    | \$205    |                                       |
|                                      | Walls - Plaster/Drywall     | 159C Practice Room       | 200      | SF   | 6    | \$552    |                                       |
|                                      | Ceiling - Lay-in            | 159D Practice Room       | 99       | SF   | 6    | \$297    |                                       |
|                                      | Floor - Tile/Sheet          | 159D Practice Room       | 99       | SF   | 6    | \$99     |                                       |
|                                      | Lighting - Lay-in           | 159D Practice Room       | 1        | EA   | 6    | \$119    |                                       |
|                                      | Power Distribution          | 159D Practice Room       | 4        | EA   | 7    | \$0      |                                       |
|                                      | Walls - Concrete Block      | 159D Practice Room       | 70       | SF   | 6    | \$205    |                                       |
|                                      | Walls - Plaster/Drywall     | 159D Practice Room       | 200      | SF   | 6    | \$552    |                                       |
|                                      | Ceiling - Lay-in            | 159E Practice Room       | 205      | SF   | 6    | \$616    |                                       |
|                                      | Doors - Steel Doors incl hw | 159E Practice Room       | 2        | EA   | 6    | \$602    |                                       |
|                                      | Doors - Wood Doors inclu hw | 159E Practice Room       | 8        | EA   | 6    | \$2,408  |                                       |
|                                      | Floor - Tile/Sheet          | 159E Practice Room       | 205      | SF   | 6    | \$205    |                                       |
|                                      | Lighting - Lay-in           | 159E Practice Room       | 4        | EA   | 6    | \$476    |                                       |
|                                      | Power Distribution          | 159E Practice Room       | 8        | EA   | 7    | \$0      |                                       |
|                                      | Walls - Concrete Block      | 159E Practice Room       | 512      | SF   | 6    | \$1,501  |                                       |
| <b>MDF_IDF</b>                       |                             |                          |          |      |      |          |                                       |
|                                      | AC Unit                     | MDF1 in room 259         | 1        | EA   | 6    | \$496    |                                       |
|                                      | Doors - Steel Doors incl hw | MDF1 in room 259         | 1        | EA   | 6    | \$301    |                                       |
|                                      | Finishes                    | MDF1 in room 259         | 303      | SF   | 6    | \$2,162  |                                       |
|                                      | Ventilation and Cooling     | MDF1 in room 259         | 1        | EA   | 6    | \$1,855  |                                       |
| <b>Mechanical/ Service Rooms</b>     |                             |                          |          |      |      |          |                                       |
|                                      | Janitor's Closet            | 1st Floor                | 40       | SF   | 6    | \$287    | I-30 Janitor's Closet                 |
|                                      | Janitor's Closet            | 2nd Floor                | 38       | SF   | 6    | \$272    | JC2 janitor closet across from rm 251 |
|                                      | Mechanical/ Service Rooms   | 2nd Floor                | 131      | SF   | 6    | \$939    | EL2 Electrical                        |
|                                      | Storage Room                | 2nd Floor                | 121      | SF   | 6    | \$867    | 2B Storage                            |
|                                      | Storage Room                | 2nd Floor                | 53       | SF   | 6    | \$380    | 2C Storage                            |
|                                      | Janitor's Closet            | 3rd Floor                | 33       | SF   | 6    | \$236    | JC3 next to boys restroom             |
|                                      | Mechanical/ Service Rooms   | 3rd Floor                | 89       | SF   | 6    | \$638    | EL3 electrical                        |
|                                      | Storage Room                | 3rd Floor                | 74       | SF   | 6    | \$530    | 359B Darkroom storage                 |
|                                      | Storage Room                | 3rd Floor                | 125      | SF   | 6    | \$896    | 3B Lunch room storage                 |
|                                      | Storage Room                | 3rd Floor                | 53       | SF   | 6    | \$380    | 3C                                    |
|                                      | Mechanical/ Service Rooms   | 4th Floor                | 2,760    | SF   | 6    | \$19,773 | 430 Fan Room                          |
| <b>Prep Room</b>                     |                             |                          |          |      |      |          |                                       |
|                                      | Casework                    | 251A prep room in rm 251 | 40       | LF   | 6    | \$1,010  |                                       |

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

| Group            | Item - Type                    | Location                 | Quantity | Unit | Rank | Cost    | Comments |
|------------------|--------------------------------|--------------------------|----------|------|------|---------|----------|
| <b>Prep Room</b> |                                |                          |          |      |      |         |          |
|                  | Ceiling - Lay-in               | 251A prep room in rm 251 | 215      | SF   | 6    | \$646   |          |
|                  | Doors - Steel Doors incl hw    | 251A prep room in rm 251 | 1        | EA   | 6    | \$301   |          |
|                  | Floor - Tile                   | 251A prep room in rm 251 | 215      | SF   | 6    | \$470   |          |
|                  | Lighting - Lay-in              | 251A prep room in rm 251 | 3        | EA   | 7    | \$0     |          |
|                  | Walls - Concrete Block         | 251A prep room in rm 251 | 590      | SF   | 6    | \$1,730 |          |
|                  | Work Sink                      | 251A prep room in rm 251 | 1        | EA   | 6    | \$379   |          |
|                  | Casework                       | 253A prep room in rm 253 | 40       | LF   | 6    | \$1,010 |          |
|                  | Ceiling - Lay-in               | 253A prep room in rm 253 | 215      | SF   | 6    | \$646   |          |
|                  | Doors - Steel Doors incl hw    | 253A prep room in rm 253 | 1        | EA   | 6    | \$301   |          |
|                  | Floor - Tile                   | 253A prep room in rm 253 | 215      | SF   | 6    | \$470   |          |
|                  | Lighting - Lay-in              | 253A prep room in rm 253 | 3        | EA   | 7    | \$0     |          |
|                  | Walls - Concrete Block         | 253A prep room in rm 253 | 590      | SF   | 6    | \$1,730 |          |
|                  | Work Sink                      | 253A prep room in rm 253 | 1        | EA   | 6    | \$379   |          |
|                  | Casework                       | 255A prep rm in rm 255   | 44       | LF   | 6    | \$1,111 |          |
|                  | Ceiling - Lay-in               | 255A prep rm in rm 255   | 238      | SF   | 6    | \$715   |          |
|                  | Doors - Steel Doors incl hw    | 255A prep rm in rm 255   | 1        | EA   | 6    | \$301   |          |
|                  | Floor - Tile                   | 255A prep rm in rm 255   | 238      | SF   | 6    | \$521   |          |
|                  | Lighting - Lay-in              | 255A prep rm in rm 255   | 4        | EA   | 7    | \$0     |          |
|                  | Walls - Concrete Block         | 255A prep rm in rm 255   | 613      | SF   | 6    | \$1,797 |          |
|                  | Work Sink                      | 255A prep rm in rm 255   | 1        | EA   | 6    | \$379   |          |
| <b>Restroom</b>  |                                |                          |          |      |      |         |          |
|                  | Accessories                    | 1st Floor Boys Room      | 284      | SF   | 6    | \$2,619 |          |
|                  | Ceiling - Plaster/Drywall      | 1st Floor Boys Room      | 284      | SF   | 6    | \$983   |          |
|                  | Doors - Steel Doors incl hw    | 1st Floor Boys Room      | 1        | EA   | 6    | \$301   |          |
|                  | Floor Drain                    | 1st Floor Boys Room      | 1        | EA   | 6    | \$1,059 |          |
|                  | Floor - Concrete               | 1st Floor Boys Room      | 284      | SF   | 6    | \$150   |          |
|                  | Hand Dryer                     | 1st Floor Boys Room      | 2        | EA   | 6    | \$460   |          |
|                  | Lavatory                       | 1st Floor Boys Room      | 4        | EA   | 6    | \$1,278 |          |
|                  | Lighting - Lay-in              | 1st Floor Boys Room      | 8        | EA   | 6    | \$952   |          |
|                  | Partitions                     | 1st Floor Boys Room      | 3        | EA   | 6    | \$891   |          |
|                  | Urinals                        | 1st Floor Boys Room      | 3        | EA   | 6    | \$1,008 |          |
|                  | Walls - Structural Glazed Tile | 1st Floor Boys Room      | 571      | SF   | 6    | \$1,796 |          |
|                  | Water Closet                   | 1st Floor Boys Room      | 3        | EA   | 6    | \$1,008 |          |
|                  | Accessories                    | 1st Floor Girls Room     | 288      | SF   | 6    | \$2,656 |          |
|                  | Ceiling - Plaster/Drywall      | 1st Floor Girls Room     | 288      | SF   | 6    | \$997   |          |
|                  | Floor Drain                    | 1st Floor Girls Room     | 1        | EA   | 6    | \$1,059 |          |
|                  | Floor - Concrete               | 1st Floor Girls Room     | 288      | SF   | 6    | \$152   |          |

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                    | Location                                   | Quantity | Unit | Rank | Cost    | Comments         |
|-----------------|--------------------------------|--|----------|------|------|---------|------------------|
| <b>Restroom</b> |                                |  |          |      |      |         |                  |
|                 | Hand Dryer                     | 1st Floor Girls Room                       | 2        | EA   | 6    | \$460   |                  |
|                 | Lavatory                       | 1st Floor Girls Room                       | 4        | EA   | 6    | \$1,278 |                  |
|                 | Lighting - Lay-in              | 1st Floor Girls Room                       | 8        | EA   | 6    | \$952   |                  |
|                 | Partitions                     | 1st Floor Girls Room                       | 4        | EA   | 6    | \$1,188 |                  |
|                 | Walls - Structural Glazed Tile | 1st Floor Girls Room                       | 572      | SF   | 6    | \$1,800 |                  |
|                 | Water Closet                   | 1st Floor Girls Room                       | 5        | EA   | 6    | \$1,680 |                  |
|                 | Accessories                    | 1st Floor Staff Restroom                   | 38       | SF   | 6    | \$350   |                  |
|                 | Ceiling - Lay-in               | 1st Floor Staff Restroom                   | 38       | SF   | 6    | \$114   |                  |
|                 | Doors - Steel Doors incl hw    | 1st Floor Staff Restroom                   | 1        | EA   | 6    | \$301   |                  |
|                 | Floor Drain                    | 1st Floor Staff Restroom                   | 1        | EA   | 6    | \$1,059 |                  |
|                 | Floor - Concrete               | 1st Floor Staff Restroom                   | 38       | SF   | 6    | \$20    |                  |
|                 | Lavatory                       | 1st Floor Staff Restroom                   | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Lay-in              | 1st Floor Staff Restroom                   | 1        | EA   | 6    | \$119   |                  |
|                 | Walls - Structural Glazed Tile | 1st Floor Staff Restroom                   | 198      | SF   | 6    | \$623   |                  |
|                 | Water Closet                   | 1st Floor Staff Restroom                   | 1        | EA   | 6    | \$336   |                  |
|                 | Accessories                    | 2nd Floor Boys Restroom across from rm 251 | 284      | SF   | 6    | \$2,619 |                  |
|                 | Ceiling - Plaster/Drywall      | 2nd Floor Boys Restroom across from rm 251 | 284      | SF   | 6    | \$983   |                  |
|                 | Floor Drain                    | 2nd Floor Boys Restroom across from rm 251 | 1        | EA   | 6    | \$1,059 |                  |
|                 | Floor - Terrazzo               | 2nd Floor Boys Restroom across from rm 251 | 284      | SF   | 6    | \$621   |                  |
|                 | Hand Dryer                     | 2nd Floor Boys Restroom across from rm 251 | 2        | EA   | 6    | \$460   |                  |
|                 | Lavatory                       | 2nd Floor Boys Restroom across from rm 251 | 4        | EA   | 6    | \$1,278 |                  |
|                 | Lighting - Lay-in              | 2nd Floor Boys Restroom across from rm 251 | 8        | EA   | 7    | \$0     |                  |
|                 | Partitions                     | 2nd Floor Boys Restroom across from rm 251 | 3        | EA   | 6    | \$891   |                  |
|                 | Student Lockers                | 2nd Floor Boys Restroom across from rm 251 | 1        | EA   | 7    | \$0     |                  |
|                 | Urinals                        | 2nd Floor Boys Restroom across from rm 251 | 3        | EA   | 6    | \$1,008 |                  |
|                 | Walls - Structural Glazed Tile | 2nd Floor Boys Restroom across from rm 251 | 658      | SF   | 6    | \$2,070 |                  |
|                 | Walls - Structural Glazed Tile | 2nd Floor Boys Restroom across from rm 251 | 213      | SF   | 6    | \$929   | Stall partitions |
|                 | Water Closet                   | 2nd Floor Boys Restroom across from rm 251 | 1        | EA   | 5    | \$1,344 | not flushing     |



**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                    | Location                                    | Quantity | Unit | Rank | Cost    | Comments                   |
|-----------------|--------------------------------|---|----------|------|------|---------|----------------------------|
| <b>Restroom</b> |                                |   |          |      |      |         |                            |
|                 | Water Closet                   | 2nd Floor Boys Restroom across from rm 251  | 1        | EA   | 4    | \$7,669 | missing                    |
|                 | Water Closet                   | 2nd Floor Boys Restroom across from rm 251  | 1        | EA   | 6    | \$336   |                            |
|                 | Accessories                    | 2nd Floor Girls Restroom across from rm 259 | 288      | SF   | 6    | \$2,656 |                            |
|                 | Ceiling - Plaster/Drywall      | 2nd Floor Girls Restroom across from rm 259 | 288      | SF   | 6    | \$997   |                            |
|                 | Floor Drain                    | 2nd Floor Girls Restroom across from rm 259 | 1        | EA   | 6    | \$1,059 |                            |
|                 | Floor - Terrazzo               | 2nd Floor Girls Restroom across from rm 259 | 288      | SF   | 6    | \$630   |                            |
|                 | Hand Dryer                     | 2nd Floor Girls Restroom across from rm 259 | 2        | EA   | 6    | \$460   |                            |
|                 | Lavatory                       | 2nd Floor Girls Restroom across from rm 259 | 4        | EA   | 6    | \$1,278 |                            |
|                 | Lighting - Lay-in              | 2nd Floor Girls Restroom across from rm 259 | 8        | EA   | 6    | \$952   |                            |
|                 | Partitions                     | 2nd Floor Girls Restroom across from rm 259 | 3        | EA   | 6    | \$891   |                            |
|                 | Walls - Structural Glazed Tile | 2nd Floor Girls Restroom across from rm 259 | 572      | SF   | 6    | \$1,800 |                            |
|                 | Water Closet                   | 2nd Floor Girls Restroom across from rm 259 | 5        | EA   | 6    | \$1,680 |                            |
|                 | Accessories                    | 2nd Floor Staff Restroom In girls restroom  | 38       | SF   | 6    | \$350   |                            |
|                 | Ceiling - Lay-in               | 2nd Floor Staff Restroom In girls restroom  | 38       | SF   | 5    | \$226   | Water damage missing tiles |
|                 | Doors - Steel Doors incl hw    | 2nd Floor Staff Restroom In girls restroom  | 1        | EA   | 6    | \$301   |                            |
|                 | Floor Drain                    | 2nd Floor Staff Restroom In girls restroom  | 1        | EA   | 6    | \$1,059 |                            |
|                 | Floor - Terrazzo               | 2nd Floor Staff Restroom In girls restroom  | 38       | SF   | 6    | \$83    |                            |
|                 | Lavatory                       | 2nd Floor Staff Restroom In girls restroom  | 1        | EA   | 6    | \$320   |                            |
|                 | Lighting - Lay-in              | 2nd Floor Staff Restroom In girls restroom  | 1        | EA   | 7    | \$0     |                            |
|                 | Walls - Structural Glazed Tile | 2nd Floor Staff Restroom In girls restroom  | 198      | SF   | 6    | \$623   |                            |
|                 | Water Closet                   | 2nd Floor Staff Restroom In girls restroom  | 1        | EA   | 6    | \$336   |                            |

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                    | Location                                   | Quantity | Unit | Rank | Cost    | Comments                             |
|-----------------|--------------------------------|--|----------|------|------|---------|--------------------------------------|
| <b>Restroom</b> |                                |  |          |      |      |         |                                      |
|                 | Accessories                    | 3rd Floor Boys Restroom across from rm 351 | 284      | SF   | 6    | \$2,619 |                                      |
|                 | Ceiling - Plaster/Drywall      | 3rd Floor Boys Restroom across from rm 351 | 284      | SF   | 6    | \$983   |                                      |
|                 | Floor Drain                    | 3rd Floor Boys Restroom across from rm 351 | 1        | EA   | 6    | \$1,059 |                                      |
|                 | Floor - Terrazzo               | 3rd Floor Boys Restroom across from rm 351 | 284      | SF   | 6    | \$621   |                                      |
|                 | Hand Dryer                     | 3rd Floor Boys Restroom across from rm 351 | 2        | EA   | 6    | \$460   |                                      |
|                 | Lavatory                       | 3rd Floor Boys Restroom across from rm 351 | 4        | EA   | 6    | \$1,278 |                                      |
|                 | Lighting - Lay-in              | 3rd Floor Boys Restroom across from rm 351 | 8        | EA   | 7    | \$0     |                                      |
|                 | Partitions                     | 3rd Floor Boys Restroom across from rm 351 | 3        | EA   | 6    | \$891   | Structural glazed tile w/metal doors |
|                 | Urinals                        | 3rd Floor Boys Restroom across from rm 351 | 3        | EA   | 6    | \$1,008 |                                      |
|                 | Walls - Structural Glazed Tile | 3rd Floor Boys Restroom across from rm 351 | 227      | SF   | 6    | \$990   | Stall partitions                     |
|                 | Walls - Structural Glazed Tile | 3rd Floor Boys Restroom across from rm 351 | 725      | SF   | 6    | \$2,281 |                                      |
|                 | Water Closet                   | 3rd Floor Boys Restroom across from rm 351 | 3        | EA   | 6    | \$1,008 |                                      |
|                 | Accessories                    | 3rd Floor Girls Room Across from rm 359    | 288      | SF   | 6    | \$2,656 |                                      |
|                 | Ceiling - Plaster/Drywall      | 3rd Floor Girls Room Across from rm 359    | 288      | SF   | 6    | \$997   |                                      |
|                 | Floor Drain                    | 3rd Floor Girls Room Across from rm 359    | 1        | EA   | 6    | \$1,059 |                                      |
|                 | Floor - Terrazzo               | 3rd Floor Girls Room Across from rm 359    | 288      | SF   | 6    | \$630   |                                      |
|                 | Hand Dryer                     | 3rd Floor Girls Room Across from rm 359    | 2        | EA   | 6    | \$460   |                                      |
|                 | Lavatory                       | 3rd Floor Girls Room Across from rm 359    | 4        | EA   | 6    | \$1,278 |                                      |
|                 | Lighting - Lay-in              | 3rd Floor Girls Room Across from rm 359    | 8        | EA   | 7    | \$0     |                                      |
|                 | Partitions                     | 3rd Floor Girls Room Across from rm 359    | 4        | EA   | 6    | \$1,188 | structural glazed tile w/metal doors |
|                 | Walls - Structural Glazed Tile | 3rd Floor Girls Room Across from rm 359    | 675      | SF   | 6    | \$2,124 |                                      |

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

| Group           | Item - Type                    | Location                                   | Quantity | Unit | Rank | Cost    | Comments         |
|-----------------|--------------------------------|--|----------|------|------|---------|------------------|
| <b>Restroom</b> |                                |  |          |      |      |         |                  |
|                 | Walls - Structural Glazed Tile | 3rd Floor Girls Room Across from rm 359    | 286      | SF   | 6    | \$1,247 | Stall partitions |
|                 | Water Closet                   | 3rd Floor Girls Room Across from rm 359    | 5        | EA   | 6    | \$1,680 |                  |
|                 | Accessories                    | 3rd Floor Staff Restroom In girls restroom | 38       | SF   | 6    | \$350   |                  |
|                 | Ceiling - Lay-in               | 3rd Floor Staff Restroom In girls restroom | 38       | SF   | 6    | \$114   |                  |
|                 | Doors - Steel Doors incl hw    | 3rd Floor Staff Restroom In girls restroom | 1        | EA   | 5    | \$1,174 | Missing hardware |
|                 | Floor Drain                    | 3rd Floor Staff Restroom In girls restroom | 1        | EA   | 6    | \$1,059 |                  |
|                 | Floor - Terrazzo               | 3rd Floor Staff Restroom In girls restroom | 38       | SF   | 6    | \$83    |                  |
|                 | Lavatory                       | 3rd Floor Staff Restroom In girls restroom | 1        | EA   | 6    | \$320   |                  |
|                 | Lighting - Lay-in              | 3rd Floor Staff Restroom In girls restroom | 1        | EA   | 7    | \$0     |                  |
|                 | Walls - Structural Glazed Tile | 3rd Floor Staff Restroom In girls restroom | 198      | SF   | 6    | \$623   |                  |
|                 | Water Closet                   | 3rd Floor Staff Restroom In girls restroom | 1        | EA   | 6    | \$336   |                  |

**Rooms (Other Than Classrooms) Subtotal:**
**\$160,072**
**Building: Addition**
**Category: Building Interior**

| Group           | Item - Type                          | Location  | Quantity | Unit | Rank | Cost     | Comments |
|-----------------|--------------------------------------|-----------|----------|------|------|----------|----------|
| <b>Corridor</b> |                                      |           |          |      |      |          |          |
|                 | Ceiling - Lay-in                     | 1st Floor | 4,709    | SF   | 6    | \$14,141 |          |
|                 | Doors - Steel Doors incl hw          | 1st Floor | 8        | EA   | 6    | \$2,408  |          |
|                 | Doors - Store Front                  | 1st Floor | 6        | EA   | 6    | \$7,249  |          |
|                 | Drinking Fountains - Double Fountain | 1st Floor | 1        | EA   | 6    | \$336    |          |
|                 | Floor - Terrazzo                     | 1st Floor | 4,709    | SF   | 7    | \$0      |          |
|                 | Lighting - Lay-in                    | 1st Floor | 39       | EA   | 6    | \$4,640  |          |
|                 | Lighting - Pendent/Surface           | 1st Floor | 10       | EA   | 6    | \$1,239  |          |
|                 | Stairs - Terrazzo                    | 1st Floor | 8        | LF   | 7    | \$0      |          |
|                 | Walls - Structural Glazed Tile       | 1st Floor | 6,782    | SF   | 6    | \$21,336 |          |
|                 | Ceiling - Lay-in                     | 2nd Floor | 4,709    | SF   | 6    | \$14,141 |          |
|                 | Doors - Steel Doors incl hw          | 2nd Floor | 8        | EA   | 6    | \$2,408  |          |

**Building: Addition**

**Category: Building Interior**

| Group           | Item - Type                          | Location                    | Quantity | Unit | Rank | Cost     | Comments  |
|-----------------|--------------------------------------|-----------------------------|----------|------|------|----------|---|
| <b>Corridor</b> |                                      |                             |          |      |      |          |   |
|                 | Drinking Fountains - Double Fountain | 2nd Floor                   | 1        | EA   | 6    | \$336    |   |
|                 | Floor - Terrazzo                     | 2nd Floor                   | 4,709    | SF   | 7    | \$0      |   |
|                 | Lighting - Lay-in                    | 2nd Floor                   | 47       | EA   | 7    | \$0      |   |
|                 | Student Lockers - One Tier           | 2nd Floor                   | 199      | EA   | 6    | \$18,474 |   |
|                 | Walls - Structural Glazed Tile       | 2nd Floor                   | 6,782    | SF   | 6    | \$21,336 |   |
|                 | Ceiling - Lay-in                     | 3rd Floor                   | 4,609    | SF   | 6    | \$13,841 |   |
|                 | Ceiling - Lay-in                     | 3rd Floor                   | 100      | SF   | 5    | \$892    | Water damaged ceiling tiles                     |
|                 | Doors - Steel Doors incl hw          | 3rd Floor                   | 6        | EA   | 6    | \$1,806  |   |
|                 | Drinking Fountains - Double Fountain | 3rd Floor                   | 1        | EA   | 6    | \$336    |   |
|                 | Floor - Terrazzo                     | 3rd Floor                   | 4,709    | SF   | 7    | \$0      |   |
|                 | Lighting - Lay-in                    | 3rd Floor                   | 51       | EA   | 7    | \$0      |   |
|                 | Student Lockers - One Tier           | 3rd Floor                   | 199      | EA   | 6    | \$18,474 |   |
|                 | Walls - Structural Glazed Tile       | 3rd Floor                   | 6,782    | SF   | 6    | \$21,336 |   |
| <b>Safety</b>   |                                      |                             |          |      |      |          |   |
|                 | Metal Dedector                       | 2nd Floor / 1st Floor       | 1        | EA   | 6    | \$881    |   |
|                 | Camera Viewing Station               | 2nd Floor                   | 1        | EA   | 6    | \$683    | 3 in main building                              |
|                 | Security Cameras                     | 2nd Floor / Entire Building | 21       | EA   | 6    | \$4,075  | Majority of camera images wavy and hard to view |
|                 | Security Cameras                     | 2nd Floor / Entire Building | 5        | EA   | 6    | \$970    |   |
| <b>Stairs</b>   |                                      |                             |          |      |      |          |   |
|                 | Ceiling - Plaster/Drywall            | Stairwell # 7               | 306      | SF   | 6    | \$2,240  |   |
|                 | Floor - Terrazzo                     | Stairwell # 7               | 784      | SF   | 7    | \$0      |   |
|                 | Handrails                            | Stairwell # 7               | 120      | LF   | 6    | \$1,040  |   |
|                 | Lighting - Lay-in                    | Stairwell # 7               | 2        | EA   | 6    | \$238    |   |
|                 | Lighting - Pendent/Surface           | Stairwell # 7               | 2        | EA   | 6    | \$248    |   |
|                 | Stairs - Terrazzo                    | Stairwell # 7               | 60       | LF   | 7    | \$0      |   |
|                 | Walls - Concrete Block               | Stairwell # 7               | 2,046    | SF   | 6    | \$5,998  |   |
|                 | Walls - Masonry                      | Stairwell # 7               | 1,008    | SF   | 6    | \$3,171  |   |
|                 | Ceiling - Lay-in                     | Stairwell # 8               | 228      | SF   | 6    | \$685    |   |
|                 | Floor - Terrazzo                     | Stairwell # 8               | 1,116    | SF   | 7    | \$0      |   |
|                 | Handrails                            | Stairwell # 8               | 168      | LF   | 6    | \$1,456  |   |
|                 | Lighting - Lay-in                    | Stairwell # 8               | 2        | EA   | 6    | \$238    |   |
|                 | Lighting - Pendent/Surface           | Stairwell # 8               | 4        | EA   | 6    | \$496    |   |
|                 | Stairs - Terrazzo                    | Stairwell # 8               | 84       | LF   | 7    | \$0      |   |
|                 | Walls - Concrete Block               | Stairwell # 8               | 1,408    | SF   | 6    | \$4,128  |   |
|                 | Walls - Masonry                      | Stairwell # 8               | 2,448    | SF   | 6    | \$7,701  |   |
|                 | Ceiling - Lay-in                     | Stairwell # 9               | 228      | SF   | 6    | \$685    |   |

**Building: Addition**
**Category: Building Interior**

| Group         | Item - Type                | Location      | Quantity | Unit | Rank | Cost    | Comments |
|---------------|----------------------------|---------------|----------|------|------|---------|----------|
| <b>Stairs</b> |                            |               |          |      |      |         |          |
|               | Floor - Terrazzo           | Stairwell # 9 | 1,116    | SF   | 7    | \$0     |          |
|               | Handrails                  | Stairwell # 9 | 168      | LF   | 6    | \$1,456 |          |
|               | Lighting - Lay-in          | Stairwell # 9 | 2        | EA   | 6    | \$238   |          |
|               | Lighting - Pendent/Surface | Stairwell # 9 | 4        | EA   | 6    | \$496   |          |
|               | Stairs - Terrazzo          | Stairwell # 9 | 84       | LF   | 7    | \$0     |          |
|               | Walls - Concrete Block     | Stairwell # 9 | 2,448    | SF   | 6    | \$7,176 |          |
|               | Walls - Masonry            | Stairwell # 9 | 1,408    | SF   | 6    | \$4,430 |          |

**Vertical Conveyance**

|  |                               |  |   |    |   |          |  |
|--|-------------------------------|--|---|----|---|----------|--|
|  | Elevator - Hydraulic Elevator |  | 1 | EA | 6 | \$19,238 |  |
|--|-------------------------------|--|---|----|---|----------|--|

**Building Interior Subtotal:**
**\$232,694**
**Total Building Cost**
**\$2,106,102**
**SITE**
**Category: Site**

| Group                 | Item - Type                    | Location    | Quantity | Unit | Rank | Cost     | Comments                                       |
|-----------------------|--------------------------------|-------------|----------|------|------|----------|--|
| <b>Civil/Drainage</b> |                                |             |          |      |      |          |  |
|                       | Civil/ Drainage - Catch Basin  | Entire Site | 21       | EA   | 6    | \$22,971 |  |
|                       | Civil/ Drainage - Site Manhole | Entire Site | 10       | EA   | 6    | \$14,927 |  |
|                       | Civil/ Drainage - Site Manhole | Entire Site | 1        | EA   | 4    | \$5,941  | East of entrance 8 - Cover cracked with a hole |

**Fencing**

|  |                                   |             |       |    |   |          |  |
|--|-----------------------------------|-------------|-------|----|---|----------|--|
|  | Fencing - Chain Link              | Entire Site | 80    | LF | 4 | \$7,344  | Around gas meter / mechanical equipment south of west parking lot - rusting throughout |
|  | Fencing - New Standard Ornamental | Entire Site | 2,195 | LF | 6 | \$70,028 |  |
|  | Fencing - New Standard Ornamental | Entire Site | 5     | LF | 5 | \$0      | SE corner - Section of fence damaged, bent   |

**Landscape**

|  |                                 |             |        |    |   |          |   |
|--|---------------------------------|-------------|--------|----|---|----------|---|
|  | Irrigation                      | Entire Site | 21,975 | SF | 4 | \$98,986 | North - Around Addition - Not working, heads broken due to vandalism throughout |
|  | Landscape - Grass               | Entire Site | 44,155 | SF | 6 | \$36,622 |   |
|  | Landscape - Grass               | Entire Site | 20     | SF | 5 | \$0      | East of entrance 8 - Sink holes around electrical transformer                   |
|  | Landscape - Hardscape- Concrete | Entire Site | 4,745  | SF | 6 | \$24,495 |   |
|  | Landscape - Hardscape- Concrete | Entire Site | 40     | SF | 5 | \$510    | Concrete slab underneath generator sinking north of west parking lot            |

**SITE**
**Category: Site**

| Group              | Item - Type                     | Location                    | Quantity | Unit | Rank | Cost     | Comments  |
|--------------------|---------------------------------|-----------------------------|----------|------|------|----------|---|
| <b>Landscape</b>   |                                 |                             |          |      |      |          |   |
|                    | Lighting - Pole Mounted         | Entire Site                 | 4        | EA   | 5    | \$8,139  | 3-ground spotlights damaged and not working at NE corner  |
|                    | Lighting - Pole Mounted         | Entire Site                 | 10       | EA   | 6    | \$10,837 |   |
|                    | Parkway trees                   | Entire Site                 | 43       | EA   | 6    | \$28,382 |   |
|                    | Parkway trees                   | Entire Site                 | 1        | EA   | 5    | \$1,402  | East adjacent to entrance 3 - Leaning into street   |
|                    | Planting Beds/ Area             | Entire Site                 | 6,570    | SF   | 6    | \$10,804 |   |
|                    | Retaining Wall - Concrete       | Entire Site                 | 700      | SF   | 6    | \$16,406 |   |
|                    | Retaining Wall - Concrete       | Entire Site                 | 20       | SF   | 5    | \$1,470  | Areas cracked, chipped with tops of wall missing  |
|                    | Retaining Wall - Masonry        | Entire Site                 | 850      | SF   | 6    | \$12,410 |   |
|                    | Trash Receptacles               | Entire Site                 | 5        | EA   | 6    | \$1,561  |   |
| <b>Parking Lot</b> |                                 |                             |          |      |      |          |   |
|                    | Concrete Curbs                  | NW                          | 1,025    | LF   | 6    | \$13,162 |   |
|                    | Concrete Curbs                  | West                        | 1,265    | LF   | 6    | \$16,244 |   |
|                    | Interior Plantings              | NW                          | 80       | LF   | 6    | \$3,403  |   |
|                    | Lighting - Pole Mounted         | NW                          | 3        | EA   | 6    | \$4,357  |   |
|                    | Lighting - Pole Mounted         | West                        | 3        | EA   | 6    | \$4,357  |   |
|                    | Surface - Asphalt               | NW                          | 29,310   | SF   | 6    | \$70,833 |   |
|                    | Surface - Asphalt               | NW                          | 20       | SF   | 5    | \$118    | Cracked with pothole around catch basin cover   |
|                    | Surface - Asphalt               | West                        | 30,610   | SF   | 6    | \$73,975 |   |
|                    | Trash Compactor                 | NW                          | 1        | EA   | 6    | \$0      | South side adjacent to entrance 9A - overhead door  |
|                    | Trash Enclosure - Masonry       | NW                          | 400      | SF   | 6    | \$15,781 | Adjacent to entrance 9A- overhead door  |
| <b>Sidewalks</b>   |                                 |                             |          |      |      |          |   |
|                    | Sidewalks - Internal Walks      | Entire Site                 | 907      | LF   | 6    | \$10,895 |   |
|                    | Sidewalks - Internal Walks      | Entire Site                 | 40       | LF   | 5    | \$2,311  | Entrance 8 - Top of stair landing cracked with missing and loose pieces in front of door / Entrance 7 - Top of stair landing cracked with small gaps / Exit 6 - Top of stair landing cracked, spalling, uneven with missing and loose pieces - large hole |
|                    | Sidewalks - Perimeter Sidewalks | Entire Site                 | 23,330   | SF   | 6    | \$46,373 | Concrete  |
|                    | Sidewalks - Perimeter Sidewalks | Entire Site                 | 600      | SF   | 5    | \$5,731  | SW corner adjacent to exit 6 - Areas cracked, sinking, uneven with gaps and potholes / South - Areas cracked, sinking, upheaving, uneven with gaps and potholes   |
|                    | Sidewalks - Perimeter Sidewalks | Entire Site                 | 760      | SF   | 6    | \$1,978  | NE corner - Pavers  |
| <b>Signage</b>     |                                 |                             |          |      |      |          |   |
|                    | Flag Pole - Flag Pole           | Site Northeast / North East | 2        | EA   | 7    | \$0      |   |

**SITE**

**Category: Site**

| Group | Item - Type                                 | Location                    | Quantity | Unit | Rank | Cost | Comments                             |
|-------|---|-----------------------------|----------|------|------|------|--------------------------------------|
|       | Marquee - Free Standing Back lighted w/ LED | Site Northeast / North East | 1        | EA   | 7    | \$0  |                                      |
|       | Monument - Sign                             | Site Northeast / North East | 1        | EA   | 6    | \$0  | Masonry / Concrete freestanding wall |

**Site Subtotal:** **\$642,760**

**Total Site Cost** **\$642,760**

|                                    |                     |
|------------------------------------|---------------------|
| <b>Campus Total <sup>2 3</sup></b> | <b>\$12,465,760</b> |
|------------------------------------|---------------------|

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

**Definitions**

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.





**Classroom Summary**

| Current Usage       | Intended Usage      | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|---------------------|---------------------|---------------|-------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| <b>Main</b>         |                     |               |             |                        |           |               |              |                |                    |                      |             |             |             |             |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 308         | 308                    | 735       | 1             | 9            | 42             | 186                | 18                   | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 309A        | 309A                   | 622       | 1             | 8            | 18             | 150                | 6                    | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 310         | 310                    | 745       | 1             | 9            | 29             | 147                | 14                   | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 311         | 311                    | 725       | 1             | 9            | 32             | 186                | 12                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 312         | 312                    | 735       | 1             | 10           | 24             | 186                | 18                   | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 313A        | 313A                   | 403       | 1             | 4            | 21             | 84                 | 8                    | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 313B        | 313B                   | 320       |               | 6            | 14             | 63                 | 64                   | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 314A        | 314A                   | 506       | 1             | 10           | 22             | 105                | 10                   | 50          | Y           | N           | N           |
| Regular Classroom   | Multi Purpose Room  | 3rd Floor     | 315         | 315                    | 1,450     | 1             | 4            | 3              | 372                | 18                   | 50          | Y           | N           | N           |
| Regular Classroom   | Art Room            | 3rd Floor     | 317         | 317                    | 790       | 1             | 8            | 24             | 210                | 14                   | 50          | Y           | N           | N           |
| Regular Classroom   | Choral Room         | 3rd Floor     | 318         | 318                    | 1,552     | 1             | 10           | 30             | 350                | 56                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Art Room            | 3rd Floor     | 321         | 321                    | 790       | 1             | 12           | 34             | 210                | 14                   | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 325         | 325                    | 790       | 1             | 8            | 18             | 210                | 14                   | 50          | Y           | N           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 327         | 327                    | 790       | 1             | 8            | 18             | 210                | 14                   | 50          | Y           | N           | N           |
| Science Classroom   | Science Classroom   | 2nd Floor     | 207         | 207                    | 1,014     | 1             | 4            | 76             | 279                | 27                   | 50          | Y           | N           | N           |
| Science Lab Level 1 | Science Lab Level 3 | 2nd Floor     | 203         | 203                    | 1,494     | 1             | 4            | 65             | 372                | 18                   | 50          | Y           | N           | N           |
| Science Lab Level 2 | Science Lab Level 2 | 3rd Floor     | 304         | 304                    | 1,063     | 1             | 2            | 50             | 341                | 33                   | 50          | Y           | Y           | Y           |
| Science Lab Level 3 | Science Lab Level 3 | 2nd Floor     | 204         | 204                    | 1,092     | 1             | 8            | 76             | 279                | 36                   | 50          | Y           | N           | Y           |
| Science Lab Level 3 | Science Lab Level 3 | 3rd Floor     | 301         | 301                    | 950       | 2             | 8            | 82             | 209                | 17                   | 50          | Y           | N           | N           |
| Science Lab Level 3 | Science Lab Level 3 | 3rd Floor     | 302         | 302                    | 1,097     | 2             | 2            | 80             | 209                | 24                   | 50          | Y           | N           | N           |
| Science Lab Level 3 | Science Lab Level 3 | 3rd Floor     | 303         | 303                    | 969       | 1             | 1            | 82             | 248                | 24                   | 50          | Y           | N           | N           |

**Addition**

|                         |                         |           |      |      |       |   |    |    |     |    |    |   |   |   |
|-------------------------|-------------------------|-----------|------|------|-------|---|----|----|-----|----|----|---|---|---|
| Art Room                | Art Room                | 3rd Floor | 359  | 359  | 1,110 | 1 | 14 | 36 | 180 | 12 | 50 | Y | N | N |
| Art Room                | Art Room                | 3rd Floor | 361  | 361  | 1,100 | 1 | 14 | 36 | 480 | 20 | 50 | Y | N | N |
| Art Room                | Art Room                | 3rd Floor | 361A | 361A | 250   | 0 | 0  | 8  | 0   | 0  | 40 | N | Y | N |
| Band Room               | Band Room               | 1st Floor | 159  | 159  | 2,750 | 1 | 36 | 70 | 660 | 44 | 50 | Y | N | Y |
| Computer Lab            | Regular Classroom       |           | 259  | 259  | 1,443 | 1 | 14 | 36 | 168 | 12 | 50 | Y | Y | N |
| Computer Lab            | Computer Lab            | 2nd Floor | 261  | 261  | 1,543 | 1 | 14 | 36 | 405 | 30 | 50 | Y | Y | N |
| Music Room              | Music Room              | 1st Floor | 151  | 151  | 2,750 | 1 | 36 | 70 | 480 | 32 | 50 | Y | N | N |
| Music Room              | Music Room              | 1st Floor | 156  | 156  | 1,292 | 1 | 26 | 90 | 264 | 16 | 40 | N | N | N |
| Office                  | Music Room              | 1st Floor | 151A | 151A | 600   | 4 | 4  | 16 | 0   | 0  | 40 | N | N | N |
| Office                  | Music Room              | 1st Floor | 159A | 159A | 650   | 5 | 5  | 20 | 0   | 0  | 40 | N | N | N |
| Other Instructional Use | Other Instructional Use | 3rd Floor | 351  | 351  | 2,110 | 1 | 16 | 50 | 434 | 28 | 50 | Y | Y | N |
| Other Instructional Use | Other Instructional Use | 3rd Floor | 351A | 351A | 488   | 1 | 4  | 40 | 0   | 0  | 40 | N | Y | N |
| Other Instructional Use | Other Instructional Use | 3rd Floor | 351B | 351B | 488   | 1 | 4  | 40 | 0   | 0  | 40 | N | Y | N |
| Regular Classroom       | Regular Classroom       | 1st Floor | 154  | 154  | 1,203 | 1 | 14 | 26 | 288 | 32 | 50 | Y | Y | N |

## Classroom Summary

| Current Usage       | Intended Usage      | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|---------------------|---------------------|---------------|-------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| <b>Addition</b>     |                     |               |             |                        |           |               |              |                |                    |                      |             |             |             |             |
| Regular Classroom   | Regular Classroom   | 1st Floor     | 160         | 160                    | 594       | 1             | 18           | 40             | 144                | 16                   | 50          | Y           | N           | Y           |
| Regular Classroom   | Regular Classroom   | 2nd Floor     | 254         | 254                    | 915       | 1             | 12           | 40             | 176                | 12                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 2nd Floor     | 256         | 256                    | 915       | 1             | 12           | 40             | 216                | 12                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 2nd Floor     | 257         | 257                    | 768       | 1             | 14           | 36             | 120                | 8                    | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 2nd Floor     | 258         | 258                    | 750       | 1             | 10           | 30             | 108                | 8                    | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 2nd Floor     | 260         | 260                    | 565       | 1             | 12           | 30             | 108                | 8                    | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 354         | 354                    | 915       | 1             | 12           | 40             | 168                | 12                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 355         | 355                    | 1,110     | 1             | 14           | 36             | 120                | 8                    | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 356         | 356                    | 915       | 1             | 12           | 40             | 162                | 12                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 357         | 357                    | 1,110     | 1             | 14           | 36             | 120                | 8                    | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 358         | 358                    | 915       | 1             | 12           | 40             | 216                | 24                   | 50          | Y           | Y           | N           |
| Regular Classroom   | Regular Classroom   | 3rd Floor     | 360         | 360                    | 565       | 1             | 12           | 30             | 144                | 16                   | 50          | Y           | Y           | N           |
| Science Lab Level 1 | Science Lab Level 1 | 2nd Floor     | 251         | 251                    | 1,525     | 1             | 14           | 36             | 300                | 20                   | 50          | Y           | Y           | N           |
| Science Lab Level 1 | Science Lab Level 1 | 2nd Floor     | 253         | 253                    | 1,450     | 1             | 14           | 36             | 180                | 18                   | 50          | Y           | Y           | Y           |
| Science Lab Level 2 | Science Lab Level 2 | 2nd Floor     | 255         | 255                    | 1,208     | 1             | 14           | 36             | 210                | 14                   | 50          | Y           | Y           | N           |