

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1939	3	175,896	\$9,603,686
Addition 1	1959	3	78,034	\$2,626,752
Addition 2	1974	2	135,040	\$5,870,669
SITE				\$2,602,509
Campus Total			388,970	\$20,703,616

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior FRP Door	#13- NE- CT YRD	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#5.2- NE- Boiler Room	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#5.3- N	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#5.4- NW	3	EA	6	\$1,894	
	Exterior Doors - Exterior FRP Door	#6- NW	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#7- W	3	EA	6	\$1,894	
	Exterior Doors - Exterior FRP Door	#8- SW	2	EA	6	\$1,263	
	Exterior Doors - Exterior Steel Door	#14- NE- CT YRD	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#15- NE- ComEd Vault	1	EA	4	\$3,823	deterioration
	Exterior Doors - Exterior Steel Door	Roof	1	EA	5	\$1,341	rust & flaking paint
	Exterior Doors - Overhead Rolling/ Garage Door	#16- NW- Dock	3	EA	6	\$4,300	
	Exterior Doors - Overhead Rolling/ Garage Door	#17 - at dock	1	EA	6	\$1,433	
	Exterior Doors - Transom Lite	#5.4- NW	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#6- NW	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#7- W	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#8- SW	2	EA	6	\$627	
	Exterior Stairs - Concrete	#13- NE- CT YRD	60	LF	5	\$6,575	spalling
	Exterior Stairs - Concrete	#14- NE- CT YRD	3	LF	5	\$329	concrete at door is spalling

Building: Main
Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Stairs - Concrete	#14- NE- CT YRD	43	LF	6	\$3,516	
	Exterior Stairs - Concrete	#5.4- NW	60	LF	5	\$6,575	spalling
	Exterior Stairs - Concrete	#6- NW	60	LF	6	\$4,906	
	Exterior Stairs - Concrete	#7- W	240	LF	6	\$19,624	
	Exterior Stairs - Concrete	#8- SW	48	LF	5	\$5,260	spalling
	Stair Handrail - Steel_Stair Handrail	#14- NE- CT YRD	75	LF	6	\$650	
	Stair Handrail - Steel_Stair Handrail	#5.4- NW	20	LF	6	\$173	
	Stair Handrail - Steel_Stair Handrail	#6- NW	20	LF	6	\$173	
	Stair Handrail - Steel_Stair Handrail	#7- W	5	LF	5	\$57	bent
	Stair Handrail - Steel_Stair Handrail	#7- W	30	LF	6	\$260	
	Stair Handrail - Steel_Stair Handrail	#8- SW	18	LF	6	\$156	
Foundation							
	Foundation - Concrete	Entire Building	1,510	LF	7	\$0	
	Foundation - Concrete	Entire Building / Boiler Room	40	LF	6	\$7,769	Cracks, seepage
	Superstructure - Concrete	Entire Building	175,896	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	12	EA	6	\$6,438	
	Exterior Lighting - Wall Mounted	Entire Building	1	EA	5	\$427	broken fixture
	Exterior Lighting - Wall Mounted	Entire Building	10	EA	6	\$2,887	
Roof System							
	Chimney - Brick Chimney- Stainless Steel Liner	Main Roof	85	LF	6	\$81,148	
	Coping - Terra Cotta	Low N Roof	19	LF	6	\$610	
	Coping - Terra Cotta	Low S Roof	19	LF	6	\$610	
	Coping - Terra Cotta	Main Roof	1,510	LF	6	\$48,498	
	Coping - Terra Cotta	Penthouse 1 Roof	100	LF	6	\$3,212	
	Coping - Terra Cotta	Penthouse 2 Roof	62	LF	6	\$1,991	
	Coping - Terra Cotta	Penthouse 3 Roof	160	LF	6	\$5,139	
	Coping - Terra Cotta	Penthouse 4 Roof	62	LF	6	\$1,991	
	Downspouts - Interior Downspouts	Low N Roof	10	LF	6	\$332	
	Downspouts - Interior Downspouts	Low S Roof	10	LF	6	\$332	
	Downspouts - Interior Downspouts	Main Roof	17	LF	6	\$565	
	Downspouts - Interior Downspouts	Penthouse 1 Roof	58	LF	6	\$1,928	
	Downspouts - Interior Downspouts	Penthouse 2 Roof	58	LF	6	\$1,928	
	Downspouts - Interior Downspouts	Penthouse 3 Roof	58	LF	6	\$1,928	
	Downspouts - Interior Downspouts	Penthouse 4 Roof	58	LF	6	\$1,928	
	Parapet - 16" - 30" Height	Low N Roof	19	LF	6	\$759	

Building: Main
Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Parapet - 16" - 30" Height	Low S Roof	19	LF	6	\$759	
	Parapet - 16" - 30" Height	Main Roof	100	LF	6	\$3,995	
	Parapet - 16" - 30" Height	Penthouse 1 Roof	100	LF	6	\$3,995	
	Parapet - 16" - 30" Height	Penthouse 2 Roof	62	LF	6	\$2,477	
	Parapet - 16" - 30" Height	Penthouse 3 Roof	160	LF	6	\$6,393	
	Parapet - 16" - 30" Height	Penthouse 4 Roof	62	LF	6	\$2,477	
	Parapet - Parapet > 30"	Main Roof	1,410	LF	6	\$90,129	
	Roof Structure - Concrete	Low N Roof	215	SF	7	\$0	
	Roof Structure - Concrete	Low S Roof	215	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Main Roof	45,750	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Penthouse 1 Roof	635	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Penthouse 2 Roof	235	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Penthouse 3 Roof	1,448	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Penthouse 4 Roof	235	SF	7	\$0	
	Roof - Modified Bitumen	Low N Roof	215	SF	6	\$2,023	
	Roof - Modified Bitumen	Low S Roof	215	SF	5	\$4,523	Water ponding
	Roof - Modified Bitumen	Main Roof	45,750	SF	5	\$962,365	Worn surface
	Roof - Modified Bitumen	Penthouse 1 Roof	635	SF	5	\$13,357	worn surface
	Roof - Modified Bitumen	Penthouse 2 Roof	235	SF	5	\$4,943	Worn surface
	Roof - Modified Bitumen	Penthouse 3 Roof	1,448	SF	5	\$30,459	Worn surface
	Roof - Modified Bitumen	Penthouse 4 Roof	235	SF	5	\$4,943	Worn surface
Walls							
	Cheek-Wall - Stone	Entire Building	48	SF	6	\$492	
	Cheek-Wall - Stone	Entire Building	25	SF	6	\$256	
	Cheek-Wall - Stone	Entire Building	48	SF	6	\$492	
	Cheek-Wall - Stone	Entire Building	40	SF	6	\$410	
	Cheek-Wall - Stone	Entire Building / Courtyard	32	SF	6	\$328	
	Cornice - Terra Cotta	Entire Building	1,510	LF	6	\$52,363	
	Exterior Walls - Brick	Entire Building	75,500	SF	6	\$507,436	
	Exterior Walls - Stone-Cast	Entire Building	1,510	SF	6	\$10,149	
	Exterior Walls - Terra Cotta	Entire Building	2,642	SF	6	\$17,757	
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	1,460	SF	6	\$16,368	
	Lintels - Steel	Entire Building	1,321	LF	6	\$38,347	
	Lintels - Terra Cotta	Entire Building	54	LF	6	\$0	
	Windows - Casement Steel	Entire Building / Penthouse	36	SF	5	\$2,944	rust, broken panes

Building: Main
Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Windows							
	Windows - Insulated Panel	Entire Building	3,193	SF	6	\$23,834	
	Windows - Sash Aluminum Double-pane	Entire Building	9,909	SF	6	\$73,967	
	Windows - Wood- Single-pane	Entire Building / Courtyard	80	SF	4	\$10,501	deteriorating, broken panes

Building Exterior Subtotal:
\$2,131,622
Building: Main
Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Mechanical Room and Electrical Room / Electrical Room	2	EA	6	\$816	Location: Boiler Room
	Automatic Transfer Switch	Mechanical Room and Electrical Room / Mechanical Room	1	EA	6	\$408	Location: Basement
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	7,825	SF	6	\$4,140	
	Emergency A/C Power - Corridors and Stairs	Entire Building	26,026	SF	6	\$7,816	
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	4,543	SF	6	\$1,689	
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	2,680	SF	6	\$996	
	Emergency A/C Power - Gym	Entire Building / 3rd Floor	1,431	SF	6	\$532	
	Emergency A/C Power - Pool	Entire Building / 1st Floor	1,660	SF	6	\$617	
	Emergency A/C Power - Students Toilets	Entire Building	1,750	SF	6	\$651	
	Emergency Generator- Outdoor- Diesel - 60 - 100 KW	Entire Building / North Courtyard	1	EA	6	\$9,865	Exposed Extension Cord for Trickle Charge of the Battery
	Exit Signs - Auditorium	Entire Building / 1st Floor	14	EA	6	\$2,096	Includes: Auditorium & 2nd Floor Balcony
	Exit Signs - Corridors and Stairs	Entire Building	34	EA	6	\$5,091	
	Exit Signs - Gym	Entire Building / 2nd Floor	2	EA	6	\$315	Location: Boy's Gym
	Exit Signs - Gym	Entire Building / 3rd Floor	1	EA	6	\$157	Location: Girl's Gym
	Exit Signs - Pool	Entire Building / 1st Floor	2	EA	6	\$310	
	Security System - CCTV	Entire Building	175,896	SF	6	\$52,822	Also serves Addition 1
	Security System - Intrusion Detection	Entire Building	186,327	SF	6	\$47,961	
	Security System - Intrusion Detection	Entire Building	175,896	SF	6	\$45,276	
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	1	EA	6	\$10,867	
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	6	\$11,555	
	PA System	Entire Building	175,896	SF	6	\$57,852	Serves & links all three buildings (Location: Main Building)

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Main Corridor
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Main Corridor (CCT No's 41 Missing Blank Cover)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Main Corridor (CCT No's: 2, 25/27 & 26/28 Popped)
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Room 203
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Room 205
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Projection Room
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Girl's Gym
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Girl's Gym
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Room 206
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	7	\$0	Location: Basement
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	7	\$0	Location: Basement
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	4	\$4,849	Location: Basement
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	7	\$0	Location: Basement
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	4	\$4,849	Location: Basement
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	7	\$0	Location: Basement
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	Location: Assembly Hall
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	Location: Room 113
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	Location: Corridor (Main)
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	Location: Assembly Hall
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	Location: Main Corridor (CCT No's 39 & 41 Missing Blank Covers)
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Room 208
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	Location: Main Corridor
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	Location: Main Corridor
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Room 211
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	Location: Boy's Gym CCTs blank covers Missing
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	Location: Main Corridor
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	Location: Boy's Gym CCTs blank covers Missing
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Room 306
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	6	\$497	Location: Room 308
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Room 312
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Room 305
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	6	\$497	Location: Main Corridor
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Room 306
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	6	\$497	Location: Room 340 (Blown Fuses)
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Room 310

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution							
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Locaton: Room 316
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Locaton: Room 308
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Locaton: Room 302
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	6	\$497	Location: Main Corridor
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Locaton: Room 303
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: ROTC Room (CCT Blank Mlssing No. 37)
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	4	\$6,578	Location: Basement
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	4	\$6,578	Blanks Missing from CCTS: 16,22,24,26,25,27,29
	Main Distribution Panels - 400 - 600 amp	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Switch Gear Room 346
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	4	\$13,694	Location: Basement
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	Location: Basement
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	4	\$13,694	Location: Basement
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	4	\$13,694	Location: Basement
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	4	\$13,694	Location: Basement
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	4	\$13,694	Location: Basement
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	4	\$13,694	Location: Basement
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	4	\$21,104	Location: Basement
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	4	\$21,104	Location: Basement
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	1	EA	7	\$0	Location: Chiller Room
	Main Distribution Panels - Less than 400 amp	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Switch Gear Room 346
	Main Distribution Panels - Less than 400 amp	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Switch Gear Room 346
	Main Distribution Panels - Less than 400 amp	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Switch Gear Room 346
	Main Distribution Panels - Less than 400 amp	Entire Building / Electrical Room	1	EA	4	\$8,819	Location: Basement
	Main Distribution Panels - Less than 400 amp	Entire Building / Electrical Room	1	EA	4	\$8,819	Location: Basement
	Main Distribution Panels - Less than 400 amp	Entire Building / Electrical Room	1	EA	4	\$8,819	Location: Basement

Electrical System Subtotal: \$431,174

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	175,896	SF	6	\$62,883	
	Fire Alarm_System	Entire Building	175,896	SF	6	\$85,521	

Safty System Subtotal: \$148,403

Building: Main
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Chemical Pot Feeder	Mechanical Room and Roof / Mechanical Room	1	EA	6	\$725	
	Chiller-Water Cooled- Cetrifugal - 201-300 tons	Mechanical Room and Roof / Mechanical Room	1	EA	4	\$265,275	Corrosion on Bundle, Refrigerant Leaks/Oil Present
	Chiller-Water Cooled- Cetrifugal - Greater than 400	Mechanical Room and Roof / Mechanical Room	1	EA	6	\$10,320	
	Cooling Tower - Open Cell	Mechanical Room and Roof / Roof	1	EA	5	\$50,291	
	Glycol Feed	Mechanical Room and Roof / Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Steel	Mechanical Room and Roof / Entire Building	1,000	LF	6	\$1,888	
	Pressure Fill System	Mechanical Room and Roof / Mechanical Room	1	EA	6	\$1,405	
Air Handling Systems							
	Air Handling Unit- Built Up- Multi Zone- Daul Temperature Coils - 25001 - 35000 cfm	Basement and Roof / Basement	1	EA	5	\$78,608	
	Air Handling Unit- Built Up- Multi Zone- Daul Temperature Coils - 25001 - 35000 cfm	Basement and Roof / Basement	1	EA	5	\$78,608	
	Air Handling Unit- Built Up- Multi Zone- Daul Temperature Coils - 25001 - 35000 cfm	Basement and Roof / Basement	1	EA	5	\$78,608	
	Air Handling Unit- Built Up- Single Zone- Daul Temperature Coils - 15001 - 25000 cfm	Entire Building / Basement	1	EA	5	\$44,262	Serves: Auditorium
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Basement and Roof / Basement	1	EA	5	\$66,438	
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Basement and Roof / Basement	1	EA	5	\$66,438	
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Basement and Roof / Basement	1	EA	5	\$66,438	Serves: Gym
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 4000-8000 cfm	Basement	1	EA	5	\$26,442	Serves: Pool
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 8001-12000 cfm	Basement	1	EA	4	\$107,826	Abandoned (Metal Shop No Long Used)
	Air Intake	Basement / Roof	2	EA	5	\$14,941	
	Air Intake	Basement and Roof / Roof	3	EA	6	\$17,294	
	Air Intake	Basement and Roof / Roof	4	EA	6	\$23,059	
	Air Intake	Entire Building / Roof	1	EA	6	\$5,765	
	Auxiliaries - 15001 - 25000 cfm	Basement and Roof / Basement	3	EA	5	\$44,698	
	Auxiliaries - 15001 - 25000 cfm	Entire Building / Basement	1	EA	5	\$14,899	Serves: Auditorium
	Auxiliaries - 25001 - 35000 cfm	Basement and Roof / Basement	3	EA	5	\$49,732	
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	Entire Building / Attic	1	EA	6	\$2,433	Location: Attic Staircase
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Attic	1	EA	4	\$50,272	
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Attic	1	EA	4	\$50,272	Serves: Gym

Building: Main
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Attic	1	EA	4	\$50,272	
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Attic	1	EA	4	\$50,272	
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Attic	1	EA	4	\$50,272	
	Return Duct Work - Masonry and Ducts- Missing or Existing Shaft	Basement and Roof / Entire Building	300	LF	5	\$394,024	corrosion, leaks
	Return Duct Work - Masonry and Ducts- Missing or Existing Shaft	Basement and Roof / Entire Building	300	LF	5	\$394,024	corrosion
	Return Duct Work - Masonry and Ducts- Missing or Existing Shaft	Entire Building / 1st Floor	100	LF	5	\$131,341	corrosion
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 21 - 30 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 21 - 30 tons	Roof	1	EA	6	\$2,792	
	Zone Dampers	Basement and Roof / Basement	50	EA	6	\$41,652	
	Zone Dampers	Basement	8	EA	5	\$15,308	
Boiler Systems							
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 201 - 300 HP	Boiler Room	3	EA	6	\$2,994	
	Chemical Feed System	Boiler Room / Basement	2	EA	6	\$2,156	
	Chemical Feeder	Boiler Room	2	EA	6	\$2,156	
	Combustion Dampers	Boiler Room	3	EA	6	\$1,227	
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	
	Feed Water Pumps and Tank	Boiler Room / Mechanical Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 201 - 300 HP	Boiler Room	3	EA	6	\$2,994	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	2,000	LF	6	\$3,775	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	2,000	LF	6	\$3,775	
	Steam Traps	Boiler Room / Entire Building	100	EA	5	\$131,490	50 to 100
Heat Exchangers							
	Heat Exchanger - Steam to Hot Water Shell Type	Basement and Mechanical Room / Basement	1	EA	4	\$32,861	
	Heat Exchanger - Steam to Hot Water Shell Type	Basement and Mechanical Room / Mechanical Room	1	EA	6	\$0	
Heating Devices							
	Fin Tube - Hot Water	1st Floor	9	LF	5	\$733	
	Radiators - Steam	Entire Building	12	EA	5	\$20,104	
	Unit Heater - Electric	Boiler Room and Basement / Basement	1	EA	6	\$278	
	Unit Heater - Gas	Boiler Room and Basement / Boiler Room	1	EA	6	\$278	

Building: Main
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Heating Devices							
	Wall Heater - Electric	Entire Building / 1st Floor	2	EA	4	\$2,165	Location: Girl's Lockerroom
	Wall Heater - Electric	Entire Building	22	EA	5	\$11,805	Restrooms (Boy's Girls) Lounges etc.
Mechanical Plumbing							
	Chilled Water Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
	Condenser Pump - 10 - 20 HP	Mechanical Room	1	EA	4	\$50,530	
	Condenser Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - 21 - 50 HP	Mechanical Room and Basement / Mechanical Room	3	EA	4	\$213,170	Location: Mechanical Room
	Hot Water Pump - Less than 10	Mechanical Room and Basement / Basement	3	EA	6	\$3,334	domestic water heater
	Hot Water Pump - Less than 10	Mechanical Room and Basement / Basement	1	EA	4	\$36,909	
	Hydronic Supply and Return - Steel	Entire Building	2,000	LF	6	\$153,553	
Temperature Control							
	Pneumatic System	Entire Building	175,896	SF	5	\$606,190	
	Thermostats - Pneumatic	Entire Building	125	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Mechanical Room, Roof 2nd and 3rd Floor / Roof	8	EA	6	\$4,739	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Mechanical Room, Roof 2nd and 3rd Floor / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Mechanical Room, Roof 2nd and 3rd Floor / Lower Roof	1	EA	4	\$4,245	Elevator Penthouse (Fan is Abandoned)
	Lab Exhaust Hood	Mechanical Room, Roof 2nd and 3rd Floor / 2nd Floor	2	EA	6	\$2,495	Location: Room 211
	Lab Exhaust Hood	Mechanical Room, Roof 2nd and 3rd Floor / 3rd Floor	1	EA	4	\$20,892	Location: Classroom 310
	Lab Exhaust Hood	Mechanical Room, Roof 2nd and 3rd Floor / 3rd Floor	2	EA	4	\$41,785	Location: Classroom 312
	Lab Exhaust Hood	Mechanical Room, Roof 2nd and 3rd Floor / 3rd Floor	3	EA	6	\$3,743	Location: Room 307
Mechanical System Subtotal:						\$3,721,206	

Building: Main
Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Main
Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	6	\$310	
	Gas Heater - Greater than 600000 BTU/HR	Boiler Room	1	EA	4	\$43,134	
	Hot Water Storage Tank_Gas - 501 - 1000 Gallons	Boiler Room / Basement	1	EA	5	\$2,249	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	175,896	SF	6	\$35,214	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	175,896	SF	6	\$42,760	many clamps
	Domestic Piping-Cold Water Risers	Entire Building	175,896	SF	6	\$32,699	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	175,896	SF	6	\$27,668	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	175,896	SF	6	\$32,699	
	Domestic Piping-Hot Water Return Lines	Entire Building	175,896	SF	6	\$25,153	
	Domestic Piping-Hot Water Return Risers	Entire Building	175,896	SF	6	\$25,153	
	Sanitary Piping	Entire Building	175,896	SF	6	\$160,980	
	Storm Piping	Entire Building	175,896	SF	6	\$153,434	
	Vent Piping	Entire Building	175,896	SF	6	\$118,220	
Pool Systems							
	Pool Drain Piping	Basement	100	LF	6	\$2,863	
	Pool Filtration System including Pump	Basement	1	EA	6	\$12,330	Corrosion & Leaking
	Pool Hot Water Heater - Electric	Basement	1	EA	6	\$907	
	Pool Supply and Return Piping	Basement	100	LF	6	\$4,805	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room and Basement / Basement	2	EA	4	\$92,316	
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room and Basement / Basement	2	EA	4	\$50,881	
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room and Basement / Basement	1	EA	6	\$1,446	
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room and Basement / Basement	1	EA	4	\$25,441	
	Pumps - Sump-Duplex	Mechanical Room and Basement / Basement	2	EA	4	\$31,498	
	Pumps - Sump-Duplex	Mechanical Room and Basement / Basement	2	EA	6	\$2,774	Location: Basement
	Pumps - Sump-Simplex	Mechanical Room and Basement / Mechanical Room	1	EA	6	\$745	Location: Basement
Plumbing System Subtotal:						\$925,680	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #101 (Regular Classroom)							
	Casework	1st Floor	12	LF	6	\$303	
	Ceiling - Lay-in	1st Floor	1,112	SF	6	\$3,339	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	5	SF	5	\$29	damaged
	Floor - Tile	1st Floor	1,112	SF	6	\$2,433	
	Lighting - Lay-in	1st Floor	22	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Storage/ Closet	1st Floor	58	SF	6	\$421	
	Walls - Plaster/Drywall	1st Floor	1,445	SF	6	\$3,988	
Classroom #105 (Regular Classroom)							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	737	SF	6	\$2,213	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	733	SF	6	\$1,604	
	Floor - Tile	1st Floor	4	SF	5	\$23	damaged
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,117	SF	6	\$3,083	
Classroom #106 (Regular Classroom)							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	748	SF	6	\$2,246	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,117	SF	6	\$3,083	
Classroom #107 (Computer Lab)							
	Casework	1st Floor	28	LF	6	\$707	
	Ceiling	1st Floor	1,470		6	\$0	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,470	SF	6	\$3,216	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #107 (Computer Lab)							
	Lighting - Lay-in	1st Floor	42	EA	7	\$0	
	Marker Board	1st Floor	32	LF	7	\$0	
	Storage/ Closet	1st Floor	6	SF	6	\$44	
	Walls - Plaster/Drywall	1st Floor	2,027	SF	6	\$5,594	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #108 (Regular Classroom)							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	748	SF	6	\$2,246	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,117	SF	6	\$3,083	
Classroom #110 (Regular Classroom)							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	748	SF	6	\$2,246	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,117	SF	6	\$3,083	
Classroom #113 (Computer Lab)							
	Casework	1st Floor	26	LF	6	\$657	
	Ceiling - Lay-in	1st Floor	12	SF	5	\$96	water damage
	Ceiling - Lay-in	1st Floor	1,458	SF	6	\$4,378	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	2	SF	5	\$12	damaged
	Floor - Tile	1st Floor	1,468	SF	6	\$3,212	
	Lighting - Lay-in	1st Floor	42	EA	7	\$0	
	Marker Board	1st Floor	28	LF	7	\$0	
	Storage/ Closet	1st Floor	6	SF	6	\$44	
	Walls - Plaster/Drywall	1st Floor	1,005	SF	6	\$2,774	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #113 (Computer Lab)							
	Work Sink	1st Floor	1	EA	5	\$1,508	faucet leaks
Classroom #114 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	748	SF	6	\$2,246	
	Chalk Board	1st Floor	34	LF	4	\$3,121	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	4	SF	5	\$23	damaged
	Floor - Tile	1st Floor	744	SF	6	\$1,628	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,117	SF	6	\$3,083	
Classroom #116 (Regular Classroom)							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	746	SF	6	\$2,240	
	Ceiling - Lay-in	1st Floor	2	SF	5	\$16	water damaged
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,117	SF	6	\$3,083	
Classroom #117 (Office)							
	Ceiling - Lay-in	1st Floor	412	SF	6	\$1,237	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	412	SF	6	\$901	
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	846	SF	6	\$2,335	
	Work Sink	1st Floor	1	EA	5	\$1,508	no faucet
Classroom #119 (Art Room)							
	Ceiling - Lay-in	1st Floor	1	SF	5	\$8	water damaged
	Ceiling - Lay-in	1st Floor	1,829	SF	6	\$5,492	
	Doors - Side-lite	1st Floor	42	SF	6	\$702	
	Doors - Transom Window	1st Floor	36	SF	6	\$610	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #119 (Art Room)							
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,830	SF	5	\$8,217	damaged throughout
	Instructional Surface	1st Floor	16	LF	6	\$539	
	Lighting - Lay-in	1st Floor	36	EA	7	\$0	
	Walls - Concrete Block	1st Floor	1,940	SF	6	\$5,687	
	Walls - Plaster/Drywall	1st Floor	100	SF	6	\$276	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #201 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	370	SF	6	\$1,111	
	Chalk Board	2nd Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	370	SF	6	\$810	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	763	SF	6	\$2,106	
Classroom #203 (Regular Classroom)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Lay-in	2nd Floor	1,150	SF	6	\$3,453	
	Chalk Board	2nd Floor	30	LF	4	\$2,754	
	Doors - Transom Window	2nd Floor	27	SF	6	\$457	1 pane needs replacing, cracked
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Tile	2nd Floor	1,135	SF	6	\$2,483	
	Floor - Tile	2nd Floor	15	SF	5	\$86	damaged
	Lighting - Lay-in	2nd Floor	22	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,472	SF	6	\$4,063	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #204 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	370	SF	6	\$1,111	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	365	SF	6	\$799	
	Floor - Tile	2nd Floor	5	SF	5	\$29	damaged
	Lighting - Lay-in	2nd Floor	4	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #204 (Regular Classroom)							
	Walls - Metal Panel	2nd Floor	320	SF	6	\$2,389	FRP
	Walls - Plaster/Drywall	2nd Floor	620	SF	6	\$1,711	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #205 (Regular Classroom)							
	Casework	2nd Floor	12	LF	6	\$303	
	Ceiling - Lay-in	2nd Floor	1	SF	5	\$8	water damaged
	Ceiling - Lay-in	2nd Floor	778	SF	6	\$2,336	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	778	SF	5	\$3,493	damaged throughout
	Lighting - Lay-in	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	30	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	249	SF	6	\$1,859	FRP
	Walls - Plaster/Drywall	2nd Floor	899	SF	6	\$2,481	
Classroom #206 (Regular Classroom)							
	Casework	2nd Floor	19	LF	6	\$480	
	Ceiling - Lay-in	2nd Floor	1,073	SF	6	\$3,222	
	Doors - Transom Window	2nd Floor	27	SF	6	\$457	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Carpet	2nd Floor	1,073	SF	6	\$2,286	
	Lighting - Lay-in	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	22	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,470	SF	6	\$4,057	
	Walls - Structural Glazed Tile	2nd Floor	84	SF	6	\$264	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #207 (Regular Classroom)							
	Casework	2nd Floor	12	LF	6	\$303	
	Ceiling - Lay-in	2nd Floor	731	SF	6	\$2,195	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	731	SF	6	\$1,599	
	Floor - Tile	2nd Floor	18	SF	5	\$104	damaged
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #209 (Regular Classroom)							
	Casework	2nd Floor	12	LF	6	\$303	
	Ceiling - Lay-in	2nd Floor	737	SF	6	\$2,213	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	5	\$1,174	delaminating
	Floor - Tile	2nd Floor	737	SF	6	\$1,612	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	
Classroom #210 (Regular Classroom)							
	Casework	2nd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	2nd Floor	912	SF	6	\$2,739	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	912	SF	6	\$1,943	
	Lighting - Lay-in	2nd Floor	17	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,260	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	2	SF	5	\$10	hole
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #211 (Science)							
	Casework	2nd Floor	12	LF	6	\$303	
	Ceiling - Lay-in	2nd Floor	760	SF	6	\$2,282	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	760	SF	6	\$761	
	Lighting - Lay-in	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	
	Work Sink	2nd Floor	5	EA	6	\$1,895	
Classroom #212 (Regular Classroom)							
	Casework	2nd Floor	35	LF	6	\$884	
	Ceiling - Lay-in	2nd Floor	864	SF	6	\$2,595	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #212 (Regular Classroom)							
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	864	SF	6	\$1,890	
	Floor - Tile	2nd Floor	8	SF	5	\$46	damaged tiles
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,306	SF	6	\$3,604	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #213 (Science)							
	Casework	2nd Floor	71	LF	6	\$1,793	
	Ceiling - Lay-in	2nd Floor	1,090	SF	6	\$3,273	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile	2nd Floor	1,090	SF	6	\$2,385	
	Fume Hood	2nd Floor	1	EA	6	\$816	
	Gas Line	2nd Floor	7	EA	6	\$3,564	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	2nd Floor	1,394	SF	6	\$3,847	
	Walls - Structural Glazed Tile	2nd Floor	26	SF	6	\$82	
	Work Sink	2nd Floor	10	EA	6	\$3,790	
Classroom #214 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	688	SF	6	\$2,066	
	Chalk Board	2nd Floor	6	LF	4	\$551	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	688	SF	6	\$1,505	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	32	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,096	SF	6	\$3,025	
Classroom #216 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	688	SF	6	\$2,066	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #216 (Regular Classroom)							
	Chalk Board	2nd Floor	6	LF	4	\$551	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	688	SF	6	\$1,505	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,096	SF	6	\$3,025	
Classroom #217 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	748	SF	6	\$2,246	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	7	SF	5	\$40	damaged
	Floor - Tile	2nd Floor	741	SF	6	\$1,621	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	
Classroom #219 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	748	SF	6	\$2,246	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	742	SF	6	\$1,623	
	Floor - Tile	2nd Floor	6	SF	5	\$35	damaged
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	14	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	
Classroom #221 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	748	SF	6	\$2,246	
	Chalk Board	2nd Floor	32	LF	4	\$2,938	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #221 (Regular Classroom)							
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	
	Walls - Structural Glazed Tile	2nd Floor	26	SF	6	\$82	
Classroom #300 (Science)							
	Casework	3rd Floor	14	LF	6	\$354	
	Ceiling - Lay-in	3rd Floor	584	SF	6	\$1,754	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	584	SF	6	\$1,278	
	Lighting - Lay-in	3rd Floor	8	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	767	SF	6	\$2,117	
	Walls - Structural Glazed Tile	3rd Floor	329	SF	6	\$1,035	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #301 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	386	SF	6	\$1,159	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	386	SF	6	\$845	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	835	SF	6	\$2,305	
Classroom #302 (Science)							
	Ceiling - Lay-in	3rd Floor	978	SF	6	\$2,937	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	978	SF	6	\$2,140	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Masonry	3rd Floor	201	SF	6	\$632	
	Walls - Plaster/Drywall	3rd Floor	1,086	SF	6	\$2,997	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #302L (Other Instructional Use)							
	Ceiling - Lay-in	3rd Floor	690	SF	6	\$2,072	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #302L (Other Instructional Use)							
	Floor - Tile	3rd Floor	690	SF	6	\$1,510	
	Lighting - Lay-in	3rd Floor	11	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,102	SF	6	\$3,041	
Classroom #303 (Science)							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	1,039	SF	6	\$3,120	
	Doors - Transom Window	3rd Floor	27	SF	6	\$457	
	Doors - Wood Doors inclu hw	3rd Floor	3	EA	6	\$903	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,039	SF	6	\$2,273	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	5	EA	6	\$2,546	
	Lighting - Lay-in	3rd Floor	20	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,470	SF	6	\$4,057	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #304 (Special Program)							
	Ceiling - Lay-in	3rd Floor	2,714	SF	6	\$8,150	
	Doors - Transom Window	3rd Floor	36	SF	6	\$610	
	Doors - Wood Doors inclu hw	3rd Floor	4	EA	6	\$1,204	
	Floor - Tile	3rd Floor	2,714	SF	6	\$5,938	
	Lighting - Lay-in	3rd Floor	59	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1	SF	6	\$4	NO OCCUPANCY PLACARD POSTED IN THE ROTC . Code Violation
	Walls - Plaster/Drywall	3rd Floor	2,332	SF	6	\$6,436	
Classroom #304A (Special Program)							
	Ceiling - Lay-in	3rd Floor	476	SF	6	\$1,429	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	476	SF	6	\$1,041	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	927	SF	6	\$2,558	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #305 (Science Lab Level 2)							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	965	SF	6	\$2,898	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	965	SF	6	\$2,111	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	20	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,225	SF	6	\$3,381	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #306 (Computer Lab)							
	Ceiling - Lay-in	3rd Floor	2,284	SF	6	\$6,859	
	Ceiling - Plaster/Drywall	3rd Floor	20	SF	5	\$183	water damage
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	2,284	SF	5	\$10,256	missing tile throughout
	Lighting - Lay-in	3rd Floor	39	EA	7	\$0	
	Lighting - Wall Mounted	3rd Floor	4	EA	6	\$496	3 open elec boxes & 1 open clock box- exposing wiring
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	2,019	SF	6	\$5,572	
Classroom #307 (Science)							
	Ceiling - Lay-in	3rd Floor	750	SF	6	\$2,252	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	750	SF	6	\$1,641	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,143	SF	6	\$3,155	
	Walls - Structural Glazed Tile	3rd Floor	26	SF	6	\$82	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #308 (Science)							
	Ceiling - Lay-in	3rd Floor	1,286	SF	6	\$3,862	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #308 (Science)							
	Doors - Transom Window	3rd Floor	27	SF	6	\$457	
	Doors - Wood Doors inclu hw	3rd Floor	3	EA	6	\$903	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,286	SF	6	\$1,287	
	Gas Line	3rd Floor	16	EA	6	\$8,146	
	Lighting - Lay-in	3rd Floor	24	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,470	SF	6	\$4,057	
	Walls - Structural Glazed Tile	3rd Floor	52	SF	6	\$164	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #310 (Science)							
	Ceiling - Lay-in	3rd Floor	1,286	SF	6	\$3,862	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,286	SF	6	\$2,814	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	24	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,470	SF	6	\$4,057	
	Walls - Structural Glazed Tile	3rd Floor	26	SF	6	\$82	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #311 (Science Lab Level 2)							
	Ceiling - Lay-in	3rd Floor	1,037	SF	6	\$3,114	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Eye Wash Station	3rd Floor	2	EA	6	\$672	
	Floor - Tile	3rd Floor	1,037	SF	6	\$2,269	
	Gas Line	3rd Floor	8	EA	6	\$4,073	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,470	SF	6	\$4,057	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #311 (Science Lab Level 2)							
	Work Sink	3rd Floor	8	EA	6	\$3,032	
Classroom #312 (Science)							
	Ceiling - Lay-in	3rd Floor	1,138	SF	6	\$3,417	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,138	SF	6	\$2,490	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	24	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,471	SF	6	\$4,060	
	Walls - Structural Glazed Tile	3rd Floor	52	SF	6	\$164	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #313 (Science Lab Level 2)							
	Ceiling - Lay-in	3rd Floor	1,176	SF	6	\$3,532	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,176	SF	6	\$2,573	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Storage/ Closet	3rd Floor	10	SF	5	\$161	Vault - Damaged door
	Walls - Plaster/Drywall	3rd Floor	1,470	SF	6	\$4,057	
	Work Sink	3rd Floor	8	EA	6	\$3,032	
Classroom #316 (Science)							
	Ceiling - Lay-in	3rd Floor	1,138	SF	6	\$3,417	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,138	SF	6	\$2,490	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	20	EA	7	\$0	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #316 (Science)							
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,471	SF	6	\$4,060	
	Walls - Structural Glazed Tile	3rd Floor	52	SF	6	\$164	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classroom #317 (Regular Classroom)							
	Casework	3rd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	3rd Floor	748	SF	6	\$2,246	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,117	SF	6	\$3,083	
Classroom #319 (Regular Classroom)							
	Casework	3rd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	3rd Floor	748	SF	6	\$2,246	
	Chalk Board	3rd Floor	6	LF	6	\$134	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,117	SF	6	\$3,083	
Classroom #321 (Regular Classroom)							
	Casework	3rd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	3rd Floor	748	SF	6	\$2,246	
	Chalk Board	3rd Floor	12	LF	6	\$268	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	748	SF	6	\$1,637	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,117	SF	6	\$3,083	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classrooms Subtotal:						\$525,537	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st- 110A- Special Ed Office	191	SF	6	\$574	
	Doors - Wood Doors inclu hw	1st- 110A- Special Ed Office	1	EA	6	\$301	
	Floor - Tile	1st- 110A- Special Ed Office	191	SF	6	\$418	
	Lighting - Lay-in	1st- 110A- Special Ed Office	4	EA	7	\$0	
	Power Distribution	1st- 110A- Special Ed Office	8	EA	6	\$16,999	
	Storage/ Closet	1st- 110A- Special Ed Office	100	SF	6	\$725	
	Walls - Plaster/Drywall	1st- 110A- Special Ed Office	646	SF	6	\$1,783	
	Work Sink	1st- 110A- Special Ed Office	1	EA	6	\$508	inside the closet
	Ceiling - Lay-in	1st- Engineer's Office	133	SF	6	\$399	
	Doors - Wood Doors inclu hw	1st- Engineer's Office	1	EA	4	\$3,413	broken at lock
	Floor - Carpet	1st- Engineer's Office	133	SF	6	\$283	
	Lighting - Pendent/Surface	1st- Engineer's Office	3	EA	7	\$0	
	Power Distribution	1st- Engineer's Office	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	1st- Engineer's Office	482	SF	6	\$1,330	
	Work Sink	1st- Engineer's Office	1	EA	5	\$1,508	faucet leaking
	Ceiling - Plaster/Drywall	1st Floor - Pool Office	82	SF	6	\$284	
	Doors - Side-lite	1st Floor - Pool Office	6	SF	6	\$100	
	Doors - Steel Doors incl hw	1st Floor - Pool Office	3	EA	6	\$903	
	Floor - Tile	1st Floor - Pool Office	82	SF	6	\$179	
	Lighting - Pendent/Surface	1st Floor - Pool Office	2	EA	6	\$248	
	Power Distribution	1st Floor - Pool Office	4	EA	6	\$8,500	
	Storage/ Closet	1st Floor - Pool Office	36	SF	6	\$261	
	Walls - Structural Glazed Tile	1st Floor - Pool Office	470	SF	6	\$1,479	
	Ceiling - Lay-in	1st- Rm 101A	187	SF	6	\$562	
	Doors - Side-lite	1st- Rm 101A	65	SF	6	\$1,087	
	Doors - Transom Window	1st- Rm 101A	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st- Rm 101A	1	EA	6	\$301	
	Floor - Tile	1st- Rm 101A	187	SF	6	\$409	
	Floor - Tile	1st- Rm 101A	20	SF	5	\$115	damaged
	Lighting - Lay-in	1st- Rm 101A	4	EA	7	\$0	
	Power Distribution	1st- Rm 101A	4	EA	6	\$8,500	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Storage/ Closet	1st- Rm 101A	44	SF	6	\$319	
	Walls - Plaster/Drywall	1st- Rm 101A	564	SF	6	\$1,557	
	Ceiling - Lay-in	1st- Rm 109 & 109A	357	SF	6	\$1,072	
	Doors - Wood Doors inclu hw	1st- Rm 109 & 109A	2	EA	6	\$602	
	Floor - Tile	1st- Rm 109 & 109A	357	SF	6	\$781	
	Lighting - Lay-in	1st- Rm 109 & 109A	7	EA	7	\$0	
	Power Distribution	1st- Rm 109 & 109A	18	EA	6	\$38,248	
	Walls - Plaster/Drywall	1st- Rm 109 & 109A	1,005	SF	6	\$2,774	
	Ceiling - Lay-in	1st- Rm 112- Case Manager	328	SF	6	\$985	
	Ceiling - Lay-in	1st- Rm 112- Case Manager	4	SF	5	\$32	water damaged
	Doors - Side-lite	1st- Rm 112- Case Manager	18	SF	6	\$301	
	Doors - Transom Window	1st- Rm 112- Case Manager	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st- Rm 112- Case Manager	1	EA	6	\$301	
	Floor - Tile	1st- Rm 112- Case Manager	327	SF	6	\$715	
	Floor - Tile	1st- Rm 112- Case Manager	5	SF	5	\$29	damaged
	Lighting - Lay-in	1st- Rm 112- Case Manager	11	EA	7	\$0	
	Power Distribution	1st- Rm 112- Case Manager	16	EA	6	\$33,998	
	Storage/ Closet	1st- Rm 112- Case Manager	12	SF	6	\$87	
	Walls - Plaster/Drywall	1st- Rm 112- Case Manager	984	SF	6	\$2,716	
	Work Slnk	1st- Rm 112- Case Manager	1	EA	6	\$508	
	Ceiling - Lay-in	1st- Rm 112A- Conference Rm	161	SF	6	\$483	
	Doors - Wood Doors inclu hw	1st- Rm 112A- Conference Rm	1	EA	6	\$301	
	Floor - Tile	1st- Rm 112A- Conference Rm	153	SF	6	\$335	
	Floor - Tile	1st- Rm 112A- Conference Rm	8	SF	5	\$46	cracking
	Lighting - Lay-in	1st- Rm 112A- Conference Rm	4	EA	7	\$0	
	Power Distribution	1st- Rm 112A- Conference Rm	4	EA	6	\$8,500	
	Storage/ Closet	1st- Rm 112A- Conference Rm	2	SF	6	\$15	
	Walls - Plaster/Drywall	1st- Rm 112A- Conference Rm	546	SF	6	\$1,507	
	Ceiling - Plaster/Drywall	1st- Rm 112B- Conference Rm	128	SF	6	\$443	
	Doors - Wood Doors inclu hw	1st- Rm 112B- Conference Rm	1	EA	6	\$301	
	Floor - Wood	1st- Rm 112B- Conference Rm	128	SF	5	\$1,872	needs refinishing
	Lighting - Pendent/Surface	1st- Rm 112B- Conference Rm	2	EA	7	\$0	
	Power Distribution	1st- Rm 112B- Conference Rm	6	EA	6	\$12,749	
	Storage/ Closet	1st- Rm 112B- Conference Rm	3	SF	6	\$22	
	Walls - Plaster/Drywall	1st- Rm 112B- Conference Rm	476	SF	6	\$1,314	
	Ceiling - Lay-in	2nd- Police Office (says Teacher's RR on door)	125	SF	6	\$375	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Transom Window	2nd- Police Office (says Teacher's RR on door)	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd- Police Office (says Teacher's RR on door)	1	EA	6	\$301	
	Floor - Carpet	2nd- Police Office (says Teacher's RR on door)	125	SF	6	\$266	
	Lighting - Lay-in	2nd- Police Office (says Teacher's RR on door)	2	EA	7	\$0	
	Power Distribution	2nd- Police Office (says Teacher's RR on door)	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	2nd- Police Office (says Teacher's RR on door)	517	SF	6	\$1,427	
	Ceiling - Lay-in	2nd- Rm 206- Social Studies Office	172	SF	6	\$517	
	Doors - Side-lite	2nd- Rm 206- Social Studies Office	26	SF	6	\$435	
	Doors - Wood Doors inclu hw	2nd- Rm 206- Social Studies Office	2	EA	6	\$602	
	Floor - Carpet	2nd- Rm 206- Social Studies Office	137	SF	6	\$292	
	Floor - Wood	2nd- Rm 206- Social Studies Office	35	SF	6	\$247	
	Lighting - Lay-in	2nd- Rm 206- Social Studies Office	2	EA	7	\$0	
	Power Distribution	2nd- Rm 206- Social Studies Office	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	2nd- Rm 206- Social Studies Office	640	SF	6	\$1,766	
	Ceiling - Lay-in	2nd- Rm 208- Social Studies Office	138	SF	6	\$414	
	Doors - Transom Window	2nd- Rm 208- Social Studies Office	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd- Rm 208- Social Studies Office	3	EA	6	\$903	
	Floor - Carpet	2nd- Rm 208- Social Studies Office	138	SF	6	\$294	
	Lighting - Lay-in	2nd- Rm 208- Social Studies Office	2	EA	7	\$0	
	Power Distribution	2nd- Rm 208- Social Studies Office	6	EA	6	\$12,749	
	Storage/ Closet	2nd- Rm 208- Social Studies Office	11	SF	6	\$80	
	Walls - Plaster/Drywall	2nd- Rm 208- Social Studies Office	640	SF	6	\$1,766	
	Ceiling - Lay-in	2nd- Rm 220 PE Office	640	SF	6	\$1,922	
	Doors - Side-lite	2nd- Rm 220 PE Office	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd- Rm 220 PE Office	3	EA	6	\$903	
	Floor - Tile	2nd- Rm 220 PE Office	640	SF	5	\$2,874	damaged throughout
	Lighting - Lay-in	2nd- Rm 220 PE Office	10	EA	7	\$0	
	Power Distribution	2nd- Rm 220 PE Office	10	EA	6	\$21,249	
	Storage/ Closet	2nd- Rm 220 PE Office	10	SF	6	\$73	
	Walls - Plaster/Drywall	2nd- Rm 220 PE Office	886	SF	6	\$2,445	
	Walls - Structural Glazed Tile	2nd- Rm 220 PE Office	180	SF	6	\$566	
	Ceiling - Plaster/Drywall	2nd- Rm 248- Asst Engineer Office	137	SF	5	\$1,256	water damage
	Doors - Transom Window	2nd- Rm 248- Asst Engineer Office	9	SF	6	\$152	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Wood Doors inclu hw	2nd- Rm 248- Asst Engineer Office	1	EA	6	\$301	
	Floor - Tile	2nd- Rm 248- Asst Engineer Office	137	SF	6	\$300	
	Lighting - Pendent/Surface	2nd- Rm 248- Asst Engineer Office	3	EA	7	\$0	
	Lighting - Wall Mounted	2nd- Rm 248- Asst Engineer Office	1	EA	7	\$0	
	Power Distribution	2nd- Rm 248- Asst Engineer Office	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	2nd- Rm 248- Asst Engineer Office	611	SF	6	\$1,686	
	Work Slnk	2nd- Rm 248- Asst Engineer Office	1	EA	6	\$508	missing a faucet handle
	Ceiling - Lay-in	3rd- 304B- ROTC Office	258	SF	6	\$775	
	Doors - Side-lite	3rd- 304B- ROTC Office	90	SF	6	\$1,505	
	Doors - Transom Window	3rd- 304B- ROTC Office	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd- 304B- ROTC Office	1	EA	6	\$301	
	Floor - Tile	3rd- 304B- ROTC Office	258	SF	6	\$564	
	Lighting - Lay-in	3rd- 304B- ROTC Office	4	EA	7	\$0	
	Power Distribution	3rd- 304B- ROTC Office	14	EA	6	\$29,748	
	Walls - Plaster/Drywall	3rd- 304B- ROTC Office	656	SF	6	\$1,810	
	Ceiling - Lay-in	3rd- Biology Office (between 308+310)	346	SF	6	\$1,039	
	Doors - Wood Doors inclu hw	3rd- Biology Office (between 308+310)	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd- Biology Office (between 308+310)	346	SF	6	\$346	
	Lighting - Lay-in	3rd- Biology Office (between 308+310)	4	EA	7	\$0	
	Power Distribution	3rd- Biology Office (between 308+310)	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	3rd- Biology Office (between 308+310)	763	SF	6	\$2,106	
	Work Slnk	3rd- Biology Office (between 308+310)	1	EA	6	\$508	
Auditorium & Theater							
	Balcony Seating	1st Floor	216	EA	6	\$37,566	
	Ceiling - Plaster/Drywall	1st Floor	7,925	SF	6	\$66,070	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	in vestibule
	Doors - Wood Doors inclu hw	1st Floor	10	EA	6	\$3,010	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	5	\$1,174	Door has a missing mullion. Location in vestibule
	Floor - Carpet	1st Floor	4,457	SF	6	\$9,497	
	Floor - Concrete	1st Floor	1,352	SF	6	\$715	
	Floor - Terrazzo	1st Floor	751	SF	6	\$1,643	
	Floor - Tile	1st Floor	139	SF	6	\$304	
	Floor - Wood	1st Floor	1,224	SF	6	\$8,629	
	Lighting - Chandelier, Incandescent	1st Floor	10	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	53	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	8	EA	7	\$0	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Auditorium & Theater							
	Main Floor Seating	1st Floor	313	EA	6	\$54,436	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	1,224	SF	6	\$7,071	
	Stage Curtain	1st Floor	4	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	7	\$0	
	Stage-Stairs - Wood	1st Floor	10	LF	6	\$117	
	Stairs - Terrazzo	1st Floor	48	LF	6	\$367	
	Walls - Plaster/Drywall	1st Floor	10,919	SF	6	\$51,995	
	Walls - Sound Panel	1st Floor	1	SF	6	\$4	NO OCCUPANCY PLACARD POSTED IN A CONSPICUOUS SPOT. (I found one lying on a cart in the stage hallway.)
	Walls - Structural Glazed Tile	1st Floor	190	SF	6	\$598	in vestibule
Gymnasia							
	Ceiling - Plaster/Drywall	2nd- Rm 218	4,543	SF	6	\$25,076	
	Doors - Wood Doors inclu hw	2nd- Rm 218	4	EA	6	\$1,204	
	Floor - Wood	2nd- Rm 218	4,543	SF	6	\$32,028	
	Lighting - Metal Halide/Sodium Vapor	2nd- Rm 218	17	EA	6	\$2,273	
	Storage/ Closet	2nd- Rm 218	146	SF	7	\$0	
	Walls - Structural Glazed Tile	2nd- Rm 218	5,962	SF	6	\$18,756	
	Ceiling - Plaster/Drywall	2nd- Rm 222	2,680	SF	6	\$14,793	
	Doors - Steel Doors incl hw	2nd- Rm 222	3	EA	6	\$903	
	Floor - Wood	2nd- Rm 222	2,680	SF	6	\$18,894	
	Lighting - Metal Halide/Sodium Vapor	2nd- Rm 222	11	EA	6	\$1,471	
	Storage/ Closet	2nd- Rm 222	146	SF	7	\$0	
	Walls - Structural Glazed Tile	2nd- Rm 222	6	SF	5	\$383	crack in SGT
	Walls - Structural Glazed Tile	2nd- Rm 222	4,603	SF	6	\$14,481	
	Ceiling - Lay-in	3rd- Rm 320	1,317	SF	6	\$3,955	
	Ceiling - Splined	3rd- Rm 320	114	SF	6	\$93	
	Doors - Transom Window	3rd- Rm 320	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd- Rm 320	2	EA	6	\$602	
	Floor - Wood	3rd- Rm 320	1,431	SF	6	\$10,088	
	Lighting - Pendent/Surface	3rd- Rm 320	20	EA	7	\$0	
	Storage/ Closet	3rd- Rm 320	56	SF	6	\$406	
	Walls - Plaster/Drywall	3rd- Rm 320	141	SF	6	\$389	
	Walls - Structural Glazed Tile	3rd- Rm 320	2,118	SF	6	\$6,663	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Accessories	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	64	SF	6	\$251	
	Ceiling - Plaster/ Drywall	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	197	SF	6	\$682	
	Doors - Transom Window	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$301	
	Floor Drain	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	64	SF	6	\$135	
	Floor - Tile/Sheet	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	133	SF	6	\$133	
	Lavatory	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	3	EA	7	\$0	
	Lighting - Wall Mounted	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	7	\$0	
	Partitions	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$297	
	Showers	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$311	
	Student Lockers - One Tier	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	10	EA	6	\$928	
	Urinals	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$336	
	Walls - Plaster/Drywall	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	976	SF	6	\$2,694	
	Walls - Tile Ceramic/ Porcelain	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	64	SF	6	\$145	shower walls
	Water Closet	1st- Custodial Staff Locker Rm (sign says Male Help Rm)	1	EA	6	\$336	
	Accessories	1st Floor - Room 118	2,340	SF	6	\$9,169	
	Benches, ped mounted	1st Floor - Room 118	45	LF	6	\$4,900	
	Ceiling - Plaster/ Drywall	1st Floor - Room 118	2,340	SF	6	\$8,098	
	Doors - Steel Doors incl hw	1st Floor - Room 118	5	EA	6	\$1,505	
	Doors - Transom Window	1st Floor - Room 118	30	SF	6	\$508	
	Doors - Wood Doors inclu hw	1st Floor - Room 118	4	EA	6	\$1,204	
	Floor Drain	1st Floor - Room 118	11	EA	6	\$11,651	
	Floor - Tile Ceramic/ Porcelain	1st Floor - Room 118	2,340	SF	6	\$4,952	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Hand Dryer	1st Floor - Room 118	13	EA	6	\$2,991	
	Lavatory	1st Floor - Room 118	2	EA	6	\$639	
	Lighting - Chandelier, Incandescent	1st Floor - Room 118	52	EA	6	\$24,833	
	Partitions	1st Floor - Room 118	5	EA	6	\$1,485	
	Showers	1st Floor - Room 118	14	EA	6	\$4,360	
	Storage/ Closet	1st Floor - Room 118	154	SF	6	\$1,117	
	Storage/ Closet	1st Floor - Room 118	61	SF	6	\$442	Laundry Room
	Student Lockers - Two Tier	1st Floor - Room 118	181	EA	6	\$8,402	
	Walls - Structural Glazed Tile	1st Floor - Room 118	2,515	SF	6	\$7,912	
	Water Closet	1st Floor - Room 118	5	EA	6	\$1,680	
	Accessories	1st Floor - Room 122	2,340	SF	6	\$9,169	
	Benches, ped mounted	1st Floor - Room 122	90	LF	6	\$9,799	
	Ceiling - Plaster/ Drywall	1st Floor - Room 122	2,340	SF	6	\$8,098	
	Doors - Steel Doors incl hw	1st Floor - Room 122	2	EA	6	\$602	
	Doors - Transom Window	1st Floor - Room 122	30	SF	6	\$508	
	Doors - Wood Doors inclu hw	1st Floor - Room 122	4	EA	6	\$1,204	
	Floor Drain	1st Floor - Room 122	6	EA	6	\$6,355	
	Floor - Tile Ceramic/ Porcelain	1st Floor - Room 122	2,340	SF	6	\$4,952	Some missing tile
	Hand Dryer	1st Floor - Room 122	12	EA	6	\$2,761	
	Lavatory	1st Floor - Room 122	2	EA	6	\$639	
	Lighting - Chandelier, Incandescent	1st Floor - Room 122	54	EA	6	\$25,788	
	Partitions	1st Floor - Room 122	4	EA	6	\$1,188	
	Showers	1st Floor - Room 122	16	EA	6	\$4,983	
	Storage/ Closet	1st Floor - Room 122	135	SF	6	\$979	
	Student Lockers - Two Tier	1st Floor - Room 122	1,232	EA	6	\$57,187	
	Walls - Structural Glazed Tile	1st Floor - Room 122	2,515	SF	6	\$7,912	
	Water Closet	1st Floor - Room 122	4	EA	6	\$1,344	
	Ceiling - Plaster/ Drywall	3rd- Rm 348- Staff Locker Room	164	SF	6	\$568	
	Doors - Transom Window	3rd- Rm 348- Staff Locker Room	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd- Rm 348- Staff Locker Room	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd- Rm 348- Staff Locker Room	18	SF	6	\$38	
	Floor - Tile/Sheet	3rd- Rm 348- Staff Locker Room	146	SF	5	\$656	damaged & missing
	Lavatory	3rd- Rm 348- Staff Locker Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	3rd- Rm 348- Staff Locker Room	3	EA	7	\$0	
	Walls - Plaster/Drywall	3rd- Rm 348- Staff Locker Room	963	SF	6	\$2,658	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	87	SF	6	\$623	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	1st Floor	562	SF	6	\$4,026	Tank/Fan room
	Storage Room	1st Floor	327	SF	6	\$2,343	
	Vaults	1st Floor	186	SF	6	\$1,333	inside rm 112
	Janitor's Closet	2nd Floor	31	SF	5	\$500	water damage on ceiling
	Janitor's Closet	2nd Floor	56	SF	6	\$401	
	Storage Room	2nd Floor	544	SF	6	\$3,897	
	Storage Room	2nd Floor	254	SF	5	\$4,097	Rm 202- water damage on ceiling
	Vaults	2nd Floor	95	SF	6	\$681	
	Air Intake Plenums	3rd Floor	285	SF	6	\$1,765	
	Janitor's Closet	3rd Floor	31	SF	6	\$222	
	Mechanical/ Service Rooms	3rd Floor	245	SF	6	\$1,755	
	Storage Room	3rd Floor	359	SF	6	\$2,572	Both 300A rooms
	Vaults	3rd Floor	112	SF	6	\$802	Inside Rm 313
Pool & Natatorium							
	Accessories	1st Floor	1,660	SF	6	\$1,139	
	Bleachers Seating/Plank Seating	1st Floor	45	EA	6	\$1,302	
	Ceiling - Plaster/ Drywall	1st Floor	1,660	SF	6	\$9,163	
	Doors - Steel Doors incl hw	1st Floor	5	EA	6	\$1,505	
	Doors - Transom Window	1st Floor	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Terrazzo	1st Floor	110	SF	6	\$241	
	Lighting - Pendent/Surface	1st Floor	40	EA	6	\$4,956	
	Pool Basin	1st Floor	1,440	SF	6	\$48,721	
	Pool Deck	1st Floor	220	SF	6	\$2,089	
	Pool Deck Drains	1st Floor	8	EA	6	\$3,377	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Plaster/Drywall	1st Floor	1,060	SF	6	\$3,289	
	Walls - Structural Glazed Tile	1st Floor	1,060	SF	6	\$3,335	
Prep Room							
	Ceiling - Plaster/Drywall	2nd- 204A- Projection Rm for Auditorium	195	SF	6	\$675	
	Doors - Wood Doors inclu hw	2nd- 204A- Projection Rm for Auditorium	2	EA	6	\$602	
	Floor - Concrete	2nd- 204A- Projection Rm for Auditorium	195	SF	6	\$103	
	Lighting - Pendent/Surface	2nd- 204A- Projection Rm for Auditorium	3	EA	7	\$0	
	Walls - Plaster/Drywall	2nd- 204A- Projection Rm for Auditorium	527	SF	6	\$1,454	
	Ceiling - Lay-in	2nd- Rm 213A (Prep Rm & Science Office)	109	SF	6	\$327	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Prep Room							
	Doors - Wood Doors inclu hw	2nd- Rm 213A (Prep Rm & Science Office)	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd- Rm 213A (Prep Rm & Science Office)	109	SF	6	\$109	
	Lighting - Lay-in	2nd- Rm 213A (Prep Rm & Science Office)	2	EA	7	\$0	
	Walls - Plaster/Drywall	2nd- Rm 213A (Prep Rm & Science Office)	431	SF	6	\$1,190	
	Work Sink	2nd- Rm 213A (Prep Rm & Science Office)	1	EA	6	\$379	
	Ceiling - Lay-in	3rd- 305A	284	SF	6	\$853	
	Doors - Wood Doors inclu hw	3rd- 305A	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd- 305A	284	SF	6	\$284	
	Lighting - Lay-in	3rd- 305A	4	EA	7	\$0	
	Walls - Plaster/Drywall	3rd- 305A	732	SF	6	\$2,020	
	Work Sink	3rd- 305A	1	EA	6	\$379	
	Ceiling - Lay-in	3rd- 311A	284	SF	6	\$853	
	Doors - Wood Doors inclu hw	3rd- 311A	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	3rd- 311A	1	EA	4	\$3,413	delaminating & puling apart by hinges
	Floor - Tile/Sheet	3rd- 311A	284	SF	6	\$284	
	Lighting - Lay-in	3rd- 311A	3	EA	7	\$0	
	Walls - Plaster/Drywall	3rd- 311A	732	SF	6	\$2,020	
	Work Sink	3rd- 311A	1	EA	6	\$379	
	Ceiling - Lay-in	3rd- 312A	316	SF	6	\$949	
	Doors - Wood Doors inclu hw	3rd- 312A	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd- 312A	316	SF	6	\$316	
	Lighting - Lay-in	3rd- 312A	4	EA	7	\$0	
	Walls - Plaster/Drywall	3rd- 312A	764	SF	6	\$2,109	
	Work Sink	3rd- 312A	1	EA	6	\$379	
Restroom							
	Accessories	1st- Engineer's Toilet	19	SF	6	\$175	
	Ceiling - Exposed	1st- Engineer's Toilet	1	SF	6	\$1	ROOM IS VERY COLD. COLD AIR IS POARING IN FROM SOMEWHERE & COULD CAUSE TOILET TO FREEZE.
	Ceiling - Plaster/Drywall	1st- Engineer's Toilet	19	SF	6	\$66	
	Doors - Wood Doors inclu hw	1st- Engineer's Toilet	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Engineer's Toilet	19	SF	6	\$40	
	Lighting - Pendent/Surface	1st- Engineer's Toilet	1	EA	7	\$0	
	Walls - Plaster/Drywall	1st- Engineer's Toilet	185	SF	6	\$511	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	1st- Engineer's Toilet	1	EA	6	\$336	
	Accessories	1st- Inside 112B	28	SF	6	\$258	
	Ceiling - Plaster/Drywall	1st- Inside 112B	28	SF	6	\$97	
	Doors - Wood Doors inclu hw	1st- Inside 112B	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Inside 112B	28	SF	6	\$59	
	Lavatory	1st- Inside 112B	1	EA	6	\$320	
	Lighting - Wall Mounted	1st- Inside 112B	1	EA	7	\$0	
	Walls - Plaster/Drywall	1st- Inside 112B	168	SF	6	\$464	
	Water Closet	1st- Inside 112B	1	EA	6	\$336	
	Accessories	1st- Men's- Auditorium Lobby	106	SF	6	\$978	
	Ceiling - Plaster/Drywall	1st- Men's- Auditorium Lobby	106	SF	6	\$367	
	Doors - Wood Doors inclu hw	1st- Men's- Auditorium Lobby	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Men's- Auditorium Lobby	106	SF	6	\$224	
	Hand Dryer	1st- Men's- Auditorium Lobby	1	EA	4	\$1,079	does not work
	Lavatory	1st- Men's- Auditorium Lobby	2	EA	6	\$639	
	Lighting - Pendant/Surface	1st- Men's- Auditorium Lobby	2	EA	7	\$0	
	Partitions	1st- Men's- Auditorium Lobby	2	EA	6	\$594	
	Walls - Plaster/Drywall	1st- Men's- Auditorium Lobby	94	SF	6	\$259	
	Walls - Tile Ceramic/ Porcelain	1st- Men's- Auditorium Lobby	374	SF	6	\$845	
	Water Closet	1st- Men's- Auditorium Lobby	2	EA	6	\$672	
	Accessories	1st- Men's Faculty	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	1st- Men's Faculty	260	SF	6	\$900	
	Doors - Steel Doors incl hw	1st- Men's Faculty	1	EA	6	\$301	
	Floor Drain	1st- Men's Faculty	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Men's Faculty	260	SF	6	\$550	
	Hand Dryer	1st- Men's Faculty	1	EA	6	\$230	
	Lavatory	1st- Men's Faculty	2	EA	6	\$639	
	Lighting - Lay-in	1st- Men's Faculty	10	EA	7	\$0	
	Partitions	1st- Men's Faculty	3	EA	6	\$891	
	Urinals	1st- Men's Faculty	8	EA	6	\$2,688	
	Walls - Structural Glazed Tile	1st- Men's Faculty	554	SF	6	\$1,743	
	Water Closet	1st- Men's Faculty	4	EA	6	\$1,344	
	Accessories	1st- Women's- Auditorium Lobby	106	SF	6	\$978	
	Ceiling - Plaster/Drywall	1st- Women's- Auditorium Lobby	106	SF	6	\$367	
	Doors - Wood Doors inclu hw	1st- Women's- Auditorium Lobby	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Women's- Auditorium Lobby	106	SF	6	\$224	
	Hand Dryer	1st- Women's- Auditorium Lobby	1	EA	4	\$1,079	does not work

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	1st- Women's- Auditorium Lobby	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st- Women's- Auditorium Lobby	2	EA	7	\$0	
	Partitions	1st- Women's- Auditorium Lobby	2	EA	6	\$594	
	Walls - Plaster/Drywall	1st- Women's- Auditorium Lobby	94	SF	6	\$259	
	Walls - Tile Ceramic/ Porcelain	1st- Women's- Auditorium Lobby	374	SF	6	\$845	
	Water Closet	1st- Women's- Auditorium Lobby	2	EA	6	\$672	
	Accessories	1st- Women's Faculty	429	SF	6	\$3,957	
	Ceiling - Plaster/Drywall	1st- Women's Faculty	429	SF	6	\$1,485	
	Doors - Wood Doors inclu hw	1st- Women's Faculty	1	EA	6	\$301	
	Floor Drain	1st- Women's Faculty	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	1st- Women's Faculty	429	SF	6	\$908	
	Hand Dryer	1st- Women's Faculty	1	EA	6	\$230	
	Lavatory	1st- Women's Faculty	3	EA	6	\$959	
	Lighting - Lay-in	1st- Women's Faculty	16	EA	7	\$0	
	Partitions	1st- Women's Faculty	7	EA	6	\$2,078	
	Walls - Structural Glazed Tile	1st- Women's Faculty	1,025	SF	6	\$3,225	
	Water Closet	1st- Women's Faculty	8	EA	6	\$2,688	
	Accessories	2nd- Asst Engineer's Toilet	19	SF	6	\$175	
	Ceiling - Plaster/Drywall	2nd- Asst Engineer's Toilet	19	SF	5	\$174	peeling
	Doors - Wood Doors inclu hw	2nd- Asst Engineer's Toilet	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd- Asst Engineer's Toilet	19	SF	6	\$40	
	Lighting - Pendent/Surface	2nd- Asst Engineer's Toilet	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd- Asst Engineer's Toilet	185	SF	6	\$511	
	Water Closet	2nd- Asst Engineer's Toilet	1	EA	6	\$336	
	Accessories	2nd- Inside Police Office	64	SF	6	\$590	
	Ceiling - Plaster/Drywall	2nd- Inside Police Office	64	SF	6	\$221	
	Doors - Wood Doors inclu hw	2nd- Inside Police Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd- Inside Police Office	64	SF	6	\$135	
	Lavatory	2nd- Inside Police Office	1	EA	5	\$1,590	leaking faucet
	Lavatory	2nd- Inside Police Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd- Inside Police Office	1	EA	6	\$124	
	Lighting - Wall Mounted	2nd- Inside Police Office	1	EA	7	\$0	
	Partitions	2nd- Inside Police Office	2	EA	6	\$594	
	Walls - Plaster/Drywall	2nd- Inside Police Office	370	SF	6	\$1,021	
	Walls - Plaster/Drywall	2nd- Inside Police Office	10	SF	5	\$51	peeling paint
	Water Closet	2nd- Inside Police Office	2	EA	6	\$672	
	Accessories	2nd- Inside Rm 220	333	SF	6	\$3,071	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	2nd- Inside Rm 220	333	SF	6	\$1,152	
	Doors - Wood Doors inclu hw	2nd- Inside Rm 220	1	EA	6	\$301	
	Floor Drain	2nd- Inside Rm 220	1	EA	6	\$1,059	
	Floor - Tile	2nd- Inside Rm 220	321	SF	6	\$702	
	Floor - Tile Ceramic/ Porcelain	2nd- Inside Rm 220	12	SF	6	\$25	shower base
	Lavatory	2nd- Inside Rm 220	1	EA	5	\$1,590	both faucets leaking
	Lighting - Pendent/Surface	2nd- Inside Rm 220	1	EA	7	\$0	
	Lighting - Wall Mounted	2nd- Inside Rm 220	1	EA	7	\$0	
	Showers	2nd- Inside Rm 220	1	EA	6	\$311	
	Walls - Plaster/Drywall	2nd- Inside Rm 220	832	SF	5	\$6,306	peeling & water damaged
	Walls - Tile Ceramic/ Porcelain	2nd- Inside Rm 220	66	SF	6	\$149	shower walls
	Water Closet	2nd- Inside Rm 220	1	EA	5	\$1,344	possibly leaking, floor underneath is damaged
	Accessories	2nd- Men's Faculty	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	2nd- Men's Faculty	260	SF	6	\$900	
	Doors - Steel Doors incl hw	2nd- Men's Faculty	1	EA	6	\$301	
	Floor Drain	2nd- Men's Faculty	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd- Men's Faculty	260	SF	6	\$550	
	Lavatory	2nd- Men's Faculty	2	EA	6	\$639	
	Lighting - Lay-in	2nd- Men's Faculty	10	EA	7	\$0	
	Partitions	2nd- Men's Faculty	3	EA	6	\$891	
	Urinals	2nd- Men's Faculty	8	EA	6	\$2,688	
	Walls - Structural Glazed Tile	2nd- Men's Faculty	554	SF	6	\$1,743	
	Water Closet	2nd- Men's Faculty	4	EA	6	\$1,344	
	Accessories	2nd- Women's Faculty	429	SF	6	\$3,957	
	Ceiling - Plaster/Drywall	2nd- Women's Faculty	429	SF	6	\$1,485	
	Doors - Wood Doors inclu hw	2nd- Women's Faculty	1	EA	6	\$301	
	Floor Drain	2nd- Women's Faculty	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	2nd- Women's Faculty	429	SF	6	\$908	
	Hand Dryer	2nd- Women's Faculty	1	EA	6	\$230	
	Lavatory	2nd- Women's Faculty	3	EA	6	\$959	
	Lighting - Lay-in	2nd- Women's Faculty	16	EA	7	\$0	
	Partitions	2nd- Women's Faculty	7	EA	6	\$2,078	
	Walls - Structural Glazed Tile	2nd- Women's Faculty	1,025	SF	6	\$3,225	
	Water Closet	2nd- Women's Faculty	8	EA	6	\$2,688	
	Accessories	3rd- Men's Faculty	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	3rd- Men's Faculty	260	SF	6	\$900	
	Doors - Steel Doors incl hw	3rd- Men's Faculty	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	3rd- Men's Faculty	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd- Men's Faculty	260	SF	6	\$550	
	Lavatory	3rd- Men's Faculty	2	EA	6	\$639	
	Lighting - Lay-in	3rd- Men's Faculty	10	EA	7	\$0	
	Partitions	3rd- Men's Faculty	3	EA	6	\$891	
	Urinals	3rd- Men's Faculty	8	EA	6	\$2,688	
	Walls - Structural Glazed Tile	3rd- Men's Faculty	554	SF	6	\$1,743	
	Water Closet	3rd- Men's Faculty	4	EA	6	\$1,344	
	Accessories	3rd- Women's Faculty	429	SF	6	\$3,957	
	Ceiling - Plaster/Drywall	3rd- Women's Faculty	429	SF	6	\$1,485	
	Doors - Wood Doors inclu hw	3rd- Women's Faculty	1	EA	6	\$301	
	Floor Drain	3rd- Women's Faculty	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	3rd- Women's Faculty	429	SF	6	\$908	
	Hand Dryer	3rd- Women's Faculty	1	EA	6	\$230	
	Lavatory	3rd- Women's Faculty	1	EA	5	\$1,590	missing a faucet
	Lavatory	3rd- Women's Faculty	2	EA	6	\$639	
	Lighting - Lay-in	3rd- Women's Faculty	16	EA	7	\$0	
	Partitions	3rd- Women's Faculty	7	EA	6	\$2,078	
	Walls - Structural Glazed Tile	3rd- Women's Faculty	1,025	SF	6	\$3,225	
	Water Closet	3rd- Women's Faculty	1	EA	5	\$1,344	out of order
	Water Closet	3rd- Women's Faculty	7	EA	6	\$2,352	

Rooms (Other Than Classrooms) Subtotal: \$1,260,480

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor - E Corridor	1,678	SF	6	\$5,039	
	Drinking Fountains - Double Fountain	1st Floor - E Corridor	1	EA	6	\$336	
	Floor - Tile/Sheet	1st Floor - E Corridor	1,678	SF	6	\$912	
	Lighting - Lay-in	1st Floor - E Corridor	14	EA	6	\$1,666	
	Student Lockers - One Tier	1st Floor - E Corridor	88	EA	6	\$8,170	
	Walls - Plaster/Drywall	1st Floor - E Corridor	1,065	SF	6	\$4,721	
	Walls - Structural Glazed Tile	1st Floor - E Corridor	1,065	SF	6	\$3,350	
	Ceiling - Plaster/Drywall	1st Floor - Engineer Office Corridor	452	SF	6	\$2,799	
	Doors - Transom Window	1st Floor - Engineer Office Corridor	12	EA	6	\$203	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Doors - Wood Doors include hw	1st Floor - Engineer Office Corridor	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	1st Floor - Engineer Office Corridor	452	SF	6	\$220	
	Lighting - Pendent/Surface	1st Floor - Engineer Office Corridor	6	EA	7	\$0	
	Stairs - Concrete Stairs	1st Floor - Engineer Office Corridor	4	LF	6	\$33	
	Walls - Plaster/Drywall	1st Floor - Engineer Office Corridor	1,733	SF	6	\$7,682	
	Ceiling	1st Floor - Pool Corridor	168	SF	6	\$0	
	Floor - Tile Ceramic/ Porcelain	1st Floor - Pool Corridor	168	SF	6	\$468	
	Lighting - Pendent/Surface	1st Floor - Pool Corridor	8	EA	6	\$991	
	Walls - Structural Glazed Tile	1st Floor - Pool Corridor	415	SF	6	\$1,306	
	Ceiling - Lay-in	1st Floor - S Corridor	3,866	SF	6	\$11,610	
	Drinking Fountains - Double Fountain	1st Floor - S Corridor	2	EA	6	\$672	
	Drinking Fountains - Single Fountain	1st Floor - S Corridor	1	EA	6	\$276	
	Floor - Tile/Sheet	1st Floor - S Corridor	3,866	SF	6	\$2,101	
	Lighting - Lay-in	1st Floor - S Corridor	30	EA	6	\$3,569	
	Student Lockers - One Tier	1st Floor - S Corridor	202	EA	6	\$18,753	
	Walls - Plaster/Drywall	1st Floor - S Corridor	1,616	SF	6	\$7,164	
	Walls - Structural Glazed Tile	1st Floor - S Corridor	1,616	SF	6	\$5,084	
	Ceiling - Lay-in	1st Floor - W Corridor	2,018	SF	6	\$6,060	
	Drinking Fountains - Double Fountain	1st Floor - W Corridor	1	EA	6	\$336	
	Floor - Tile/Sheet	1st Floor - W Corridor	2,018	SF	6	\$1,097	
	Lighting - Lay-in	1st Floor - W Corridor	18	EA	6	\$2,142	
	Student Lockers - One Tier	1st Floor - W Corridor	117	EA	6	\$10,862	
	Walls - Plaster/Drywall	1st Floor - W Corridor	900	SF	6	\$3,990	
	Walls - Structural Glazed Tile	1st Floor - W Corridor	900	SF	6	\$2,831	
	Ceiling - Lay-in	2nd Floor - E Corridor	1,678	SF	6	\$5,039	
	Drinking Fountains - Double Fountain	2nd Floor - E Corridor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor - E Corridor	1,678	SF	6	\$912	
	Lighting - Lay-in	2nd Floor - E Corridor	14	EA	6	\$1,666	
	Student Lockers - One Tier	2nd Floor - E Corridor	88	EA	6	\$8,170	
	Walls - Plaster/Drywall	2nd Floor - E Corridor	1,065	SF	6	\$4,721	
	Walls - Structural Glazed Tile	2nd Floor - E Corridor	1,065	SF	6	\$3,350	
	Ceiling - Lay-in	2nd Floor - S Corridor	3,866	SF	6	\$11,610	
	Drinking Fountains - Double Fountain	2nd Floor - S Corridor	2	EA	6	\$672	
	Drinking Fountains - Single Fountain	2nd Floor - S Corridor	1	EA	6	\$276	
	Floor - Tile/Sheet	2nd Floor - S Corridor	3,866	SF	6	\$2,101	
	Lighting - Lay-in	2nd Floor - S Corridor	30	EA	6	\$3,569	
	Student Lockers - One Tier	2nd Floor - S Corridor	202	EA	6	\$18,753	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Walls - Plaster/Drywall	2nd Floor - S Corridor	1,616	SF	6	\$7,164	
	Walls - Structural Glazed Tile	2nd Floor - S Corridor	1,616	SF	6	\$5,084	
	Ceiling - Lay-in	2nd Floor - W Corridor	2,018	SF	6	\$6,060	
	Drinking Fountains - Double Fountain	2nd Floor - W Corridor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor - W Corridor	2,018	SF	6	\$1,097	
	Lighting - Lay-in	2nd Floor - W Corridor	18	EA	6	\$2,142	
	Student Lockers - One Tier	2nd Floor - W Corridor	117	EA	6	\$10,862	
	Walls - Plaster/Drywall	2nd Floor - W Corridor	900	SF	6	\$3,990	
	Walls - Structural Glazed Tile	2nd Floor - W Corridor	900	SF	6	\$2,831	
	Ceiling - Plaster/Drywall	2nd Floor	311	SF	6	\$1,926	
	Doors - Transom Window	2nd Floor	12	EA	6	\$203	
	Doors - Wood Doors include hw	2nd Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	2nd Floor	311	SF	6	\$151	
	Lighting - Pendent/Surface	2nd Floor	5	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,199	SF	6	\$5,315	
	Ceiling - Lay-in	3rd Floor - E Corridor	1,678	SF	6	\$5,039	
	Drinking Fountains - Double Fountain	3rd Floor - E Corridor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor - E Corridor	1,678	SF	6	\$912	
	Lighting - Lay-in	3rd Floor - E Corridor	14	EA	6	\$1,666	
	Student Lockers - One Tier	3rd Floor - E Corridor	88	EA	6	\$8,170	
	Walls - Plaster/Drywall	3rd Floor - E Corridor	1,065	SF	6	\$4,721	
	Walls - Structural Glazed Tile	3rd Floor - E Corridor	1,065	SF	6	\$3,350	
	Ceiling - Lay-in	3rd Floor - S Corridor	3,866	SF	6	\$11,610	
	Drinking Fountains - Double Fountain	3rd Floor - S Corridor	2	EA	6	\$672	
	Drinking Fountains - Single Fountain	3rd Floor - S Corridor	1	EA	6	\$276	
	Floor - Tile/Sheet	3rd Floor - S Corridor	3,866	SF	6	\$2,101	
	Lighting - Lay-in	3rd Floor - S Corridor	30	EA	6	\$3,569	
	Student Lockers - One Tier	3rd Floor - S Corridor	202	EA	6	\$18,753	
	Walls - Plaster/Drywall	3rd Floor - S Corridor	1,616	SF	6	\$7,164	
	Walls - Structural Glazed Tile	3rd Floor - S Corridor	1,616	SF	6	\$5,084	
	Ceiling - Lay-in	3rd Floor - W Corridor	2,018	SF	6	\$6,060	
	Drinking Fountains - Double Fountain	3rd Floor - W Corridor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor - W Corridor	2,018	SF	6	\$1,097	
	Lighting - Lay-in	3rd Floor - W Corridor	18	EA	6	\$2,142	
	Student Lockers - One Tier	3rd Floor - W Corridor	117	EA	6	\$10,862	
	Walls - Plaster/Drywall	3rd Floor - W Corridor	900	SF	6	\$3,990	
	Walls - Structural Glazed Tile	3rd Floor - W Corridor	900	SF	6	\$2,831	

Building: Main
Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Plaster/Drywall	3rd Floor	229	SF	6	\$1,418	
	Doors - Transom Window	3rd Floor	12	EA	6	\$203	
	Doors - Wood Doors include hw	3rd Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	3rd Floor	229	SF	6	\$111	
	Lighting - Pendent/Surface	3rd Floor	5	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,199	SF	6	\$5,315	
Safety							
	Camera Viewing Station	1st Floor	5	EA	6	\$3,413	Vice Principal, Security Desk, Engineer, MDF & Main
	Security Cameras	1st Floor / Entire Building	6	EA	6	\$1,164	
	Security Cameras	1st Floor / Entire Building	3	EA	6	\$582	
Stairs							
	Ceiling - Plaster/Drywall	Girl's Locker Room 118	1,385	SF	6	\$10,140	
	Floor - Terrazzo	Girl's Locker Room 118	238	SF	6	\$1,998	
	Handrails	Girl's Locker Room 118	96	LF	6	\$832	
	Lighting - Pendent/Surface	Girl's Locker Room 118	5	EA	6	\$619	
	Stairs - Terrazzo	Girl's Locker Room 118	48	LF	6	\$445	
	Walls - Plaster/Drywall	Girl's Locker Room 118	1,388	SF	5	\$6,332	Cracking, peeling
	Walls - Structural Glazed Tile	Girl's Locker Room 118	1,388	SF	6	\$4,367	Minimal cracking
	Ceiling - Plaster/Drywall	Girl's Locker Room 122	345	SF	6	\$2,526	
	Floor - Terrazzo	Girl's Locker Room 122	235	SF	6	\$1,973	
	Handrails	Girl's Locker Room 122	86	LF	6	\$745	
	Lighting - Pendent/Surface	Girl's Locker Room 122	5	EA	6	\$619	
	Stairs - Terrazzo	Girl's Locker Room 122	43	LF	6	\$399	
	Walls - Plaster/Drywall	Girl's Locker Room 122	1,555	SF	5	\$7,093	Peeling, cracking
	Walls - Structural Glazed Tile	Girl's Locker Room 122	1,555	SF	6	\$4,892	
	Ceiling - Plaster/Drywall	next to Engineer Office / 3rd Floor	160	SF	6	\$1,171	
	Floor - Concrete Epoxy/ Painted	next to Engineer Office	61	SF	6	\$30	
	Handrails	next to Engineer Office	141	LF	6	\$1,222	
	Stairs - Concrete	next to Engineer Office	67	LF	6	\$556	
	Walls - Plaster/Drywall	next to Engineer Office	1,440	SF	6	\$3,974	
	Ceiling - Lay-in	Stair 6D	850	SF	6	\$2,553	
	Floor - Terrazzo	Stair 6D	850	SF	6	\$7,135	
	Handrails	Stair 6D	127	LF	6	\$1,101	
	Lighting - Lay-in	Stair 6D	4	EA	6	\$476	
	Lighting - Pendent/Surface	Stair 6D	4	EA	6	\$496	
	Stairs - Terrazzo	Stair 6D	59	LF	6	\$548	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Walls - Plaster/Drywall	Stair 6D	2,625	SF	6	\$7,245	
	Walls - Structural Glazed Tile	Stair 6D	2,625	SF	6	\$8,258	
	Ceiling - Lay-in	Stair Main	1,164	SF	6	\$3,495	
	Floor - Terrazzo	Stair Main	796	SF	6	\$6,682	
	Handrails	Stair Main	196	LF	6	\$1,698	
	Lighting - Lay-in	Stair Main	6	EA	6	\$714	
	Lighting - Pendent/Surface	Stair Main	7	EA	6	\$867	
	Stairs - Terrazzo	Stair Main	98	LF	6	\$910	
	Walls - Plaster/Drywall	Stair Main	1,915	SF	6	\$5,285	
	Walls - Structural Glazed Tile	Stair Main	1,915	SF	6	\$6,025	
Vertical Conveyance							
	Elevator - Hydraulic Elevator	North	1	EA	6	\$19,238	

Building Interior Subtotal: \$459,582

Total Building Cost \$9,603,686

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior FRP Door	#10- NE	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#8.1- SW	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#8.2- SE	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#8.3- E	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#9- E	3	EA	6	\$1,894	
	Exterior Doors - Exterior Steel Door	Roof	1	EA	6	\$481	flaking paint
	Exterior Doors - Transom Lite	#8.1- SW	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#8.2- SE	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#9- E	3	EA	6	\$940	
	Exterior Stairs - Concrete	#8.1- SW	42	LF	6	\$3,434	
	Exterior Stairs - Concrete	#8.2- SE	42	LF	6	\$3,434	
	Exterior Stairs - Concrete	#9- E	72	LF	6	\$5,887	
	Exterior Stairs - Stone	#10- NE	6	LF	6	\$678	
	Exterior Stairs - Stone	#8.3- E	3	LF	6	\$339	
	Ramp Handrail - Steel_Ramp Handrail	#9- E	110	LF	6	\$953	

Building: Addition 1
Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Ramps - Concrete	#9- E	55	LF	6	\$8,263	
	Stair Handrail - Steel_Stair Handrail	#8.1- SW	5	LF	6	\$43	
	Stair Handrail - Steel_Stair Handrail	#8.2- SE	18	LF	6	\$156	
	Stair Handrail - Steel_Stair Handrail	#9- E	24	LF	6	\$208	
Foundation							
	Foundation - Concrete	Entire Building	1,051	LF	7	\$0	
	Superstructure - Concrete	Entire Building	78,034	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	5	EA	6	\$2,683	
	Exterior Lighting - Wall Mounted	Entire Building	6	EA	6	\$1,732	
Roof System							
	Coping - Terra Cotta	Low E Roof	17	LF	6	\$546	
	Coping - Terra Cotta	Low S Roof	134	LF	6	\$4,304	
	Coping - Terra Cotta	Low SW Roof	23	LF	6	\$739	
	Coping - Terra Cotta	Main Roof	754	LF	6	\$24,217	
	Coping - Terra Cotta	Mid E Roof	226	LF	6	\$7,259	
	Coping - Terra Cotta	Mid S Roof	372	LF	6	\$11,948	
	Downspouts - Exterior Downspouts	Low SW Roof	4	LF	6	\$133	
	Downspouts - Interior Downspouts	Low E Roof	12	LF	6	\$399	
	Downspouts - Interior Downspouts	Low S Roof	15	LF	6	\$498	
	Downspouts - Interior Downspouts	Low SW Roof	12	LF	6	\$399	
	Downspouts - Interior Downspouts	Main Roof	336	LF	6	\$11,166	
	Downspouts - Interior Downspouts	Mid E Roof	70	LF	6	\$2,326	
	Downspouts - Interior Downspouts	Mid S Roof	120	LF	6	\$3,988	
	Parapet - 16" - 30" Height	Low E Roof	17	LF	6	\$679	
	Parapet - Parapet > 30"	Low S Roof	134	LF	6	\$8,565	
	Parapet - Parapet > 30"	Low SW Roof	23	LF	6	\$1,470	
	Parapet - Parapet > 30"	Main Roof	754	LF	6	\$48,196	
	Parapet - Parapet > 30"	Mid E Roof	226	LF	6	\$14,446	
	Parapet - Parapet > 30"	Mid S Roof	372	LF	6	\$23,779	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Low E Roof	130	SF	7	\$0	Steel and bar joist frame with light weight concrete topping
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Low S Roof	555	SF	7	\$0	Steel and bar joist frame with light weight concrete topping
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main Roof	15,964	SF	7	\$0	Steel and bar joist frame with light weight concrete topping

Building: Addition 1
Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Mid E Roof	2,770	SF	7	\$0	Steel and bar joist frame with light weight concrete topping
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Mid S Roof	8,400	SF	7	\$0	Steel and bar joist frame with light weight concrete topping
	Roof Structure - Steel with Clay Tile Arch	Low SW Roof	1,045	SF	7	\$0	Steel and bar joist frame with light weight concrete topping
	Roof - Modified Bitumen	Low E Roof	130	SF	5	\$2,735	Worn surface, water ponding
	Roof - Modified Bitumen	Low S Roof	555	SF	5	\$11,675	Worn surface, water ponding
	Roof - Modified Bitumen	Low SW Roof	1,045	SF	5	\$21,982	Water ponding
	Roof - Modified Bitumen	Main Roof	15,964	SF	5	\$335,808	Worn surface
	Roof - Modified Bitumen	Mid E Roof	2,770	SF	5	\$58,268	Worn surface
	Roof - Modified Bitumen	Mid S Roof	8,400	SF	5	\$176,697	Worn surface
Walls							
	Cheek-Wall - Stone	Entire Building	40	SF	6	\$410	
	Cheek-Wall - Stone	Entire Building	40	SF	6	\$410	
	Cheek-Wall - Stone	Entire Building	25	SF	6	\$256	
	Exterior Walls - Brick	Entire Building	36,192	SF	6	\$243,246	
	Exterior Walls - Stone-Cast	Entire Building	754	SF	6	\$5,068	
	Exterior Walls - Terra Cotta	Entire Building	626	SF	6	\$4,207	
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	120	SF	6	\$1,345	
	Lintels - Steel	Entire Building	626	LF	6	\$18,172	
	Lintels - Terra Cotta	Entire Building	6	LF	6	\$0	
	Windows - Casement Aluminum Double-pane	Entire Building	4,698	SF	6	\$35,069	
	Windows - Decorative	Entire Building	480	SF	6	\$3,583	glass block
	Windows - Insulated Panel	Entire Building	1,566	SF	6	\$11,690	metal
Building Exterior Subtotal:						\$1,132,476	

Building: Addition 1
Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	1st and 2nd Floor / 1st Floor	1	EA	6	\$408	Location: Main Corridor, Just Outside Room 180A
	Automatic Transfer Switch	1st and 2nd Floor / 2nd Floor	1	EA	6	\$408	Location: Main Corridor
	Emergency A/C Power - Corridors and Stairs	Entire Building	15,089	SF	6	\$4,531	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	8,201	SF	6	\$3,049	

Building: Addition 1

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	1,865	SF	6	\$693	
	Emergency A/C Power - Students Toilets	Entire Building	2,698	SF	6	\$1,003	
	Exit Signs - Corridors and Stairs	Entire Building	18	EA	6	\$2,695	
	Exit Signs - Gym	Entire Building / 1st Floor	4	EA	6	\$630	
	Security System - CCTV	Entire Building	78,034	SF	6	\$23,434	
	Security System - Intrusion Detection	Entire Building	78,034	SF	6	\$20,086	
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Also serves Addition 2
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	6	\$11,555	Also seves Addition 2
	PA System	Entire Building	78,034	SF	6	\$25,665	Serves & links all three buildings (Location: Main Building)
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Corridor (Main)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Corridor (Main)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Corridor (Main)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Room 139A
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Corridor (Main)
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Corridor (Main)
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Location: Corridor (Main)
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Electrical Room
	Lighting and Power Panels - Above 100 A	Entire Building / 3rd Floor	1	EA	7	\$0	Location: Room 342
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Main Distribution Panels - 400 - 600 amp	Entire Building / 2nd Floor	1	EA	4	\$13,694	Location: Electrical Room
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room

Building: Addition 1
Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Electrical System Subtotal:						\$109,348	

Building: Addition 1
Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	78,034	SF	6	\$27,897	
	Fire Alarm_System	Entire Building	78,034	SF	6	\$37,940	
Safty System Subtotal:						\$65,837	

Building: Addition 1
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Heat Pump- Ceiling Mounted- Electric Heating & DX Cooling Self Contained Air Cooled Compressor - Greater than 5 tons	2nd Floor	1	EA	6	\$1,929	Location: MDF Room
Air Handling Systems							
	Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM	Attic	1	EA	6	\$1,857	Location: Attic Staircase
Heating Devices							
	Cabinet Heaters - With Electric Coil	Entire Building / 1st Floor	4	EA	6	\$1,426	Restrooms (Boy's & Girl's)
	Cabinet Heaters - With Electric Coil	Entire Building / 2nd Floor	1	EA	6	\$357	
	Fin Tube - Electric	1st Floor	6	LF	5	\$306	
	Unit Heater - Electric	Basement and 2nd Floor / 2nd Floor	1	EA	6	\$278	
	Unit Heater - Electric	Basement and 2nd Floor / Basement	2	EA	6	\$556	
Temperature Control							
	Pneumatic System	Entire Building	78,034	SF	6	\$41,288	also some Johnson Controls equipment
	Thermostats - Pneumatic	Entire Building	53	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Basement, Roof / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Basement, Roof / Roof	1	EA	6	\$592	
	Roof Mounted Duct Work	Basement, Roof / Roof	20	LF	6	\$7,580	
Mechanical System Subtotal:						\$56,762	

Building: Addition 1
Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 300001 - 600000 BTU/HR	2nd Floor	1	EA	5	\$2,249	Mechanical Room
	Gas Heater - 300001 - 600000 BTU/HR	2nd Floor	2	EA	6	\$620	Mechanical Room, Also serves addition 2
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	78,034	SF	6	\$15,622	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	78,034	SF	6	\$18,970	
	Domestic Piping-Cold Water Risers	Entire Building	78,034	SF	6	\$14,507	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	78,034	SF	6	\$12,275	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	78,034	SF	6	\$14,507	
	Domestic Piping-Hot Water Return Lines	Entire Building	78,034	SF	6	\$11,159	
	Domestic Piping-Hot Water Return Risers	Entire Building	78,034	SF	6	\$11,159	
	Sanitary Piping	Entire Building	78,034	SF	6	\$71,417	
	Storm Piping	Entire Building	78,034	SF	6	\$68,069	
	Vent Piping	Entire Building	78,034	SF	6	\$52,447	
Pumps							
	Pumps - Ejector-Simplex	Basement	1	EA	6	\$745	under elevator
	Pumps - Ejector-Simplex	Basement	4	EA	6	\$2,980	
Plumbing System Subtotal:						\$296,725	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #134 (Regular Classroom)							
	Casework	1st Floor	7	LF	6	\$177	
	Ceiling - Lay-in	1st Floor	699	SF	6	\$2,099	
	Chalk Board	1st Floor	52	LF	4	\$4,774	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	699	SF	6	\$1,529	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	936	SF	6	\$2,583	
Classroom #136 (Regular Classroom)							
	Casework	1st Floor	7	LF	6	\$177	
	Ceiling - Lay-in	1st Floor	671	SF	6	\$2,015	
	Chalk Board	1st Floor	52	LF	4	\$4,774	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #136 (Regular Classroom)							
	Floor - Tile	1st Floor	671	SF	6	\$1,468	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	919	SF	6	\$2,536	
Classroom #138 (Regular Classroom)							
	Casework	1st Floor	7	LF	6	\$177	
	Ceiling - Lay-in	1st Floor	690	SF	6	\$2,072	
	Chalk Board	1st Floor	52	LF	4	\$4,774	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	690	SF	6	\$1,510	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	941	SF	6	\$2,597	
Classroom #139 (Computer Lab)							
	Ceiling - Lay-in	1st Floor	1,752	SF	6	\$5,261	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,752	SF	6	\$3,833	
	Lighting - Lay-in	1st Floor	39	EA	7	\$0	
	Marker Board	1st Floor	43	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,652	SF	6	\$4,559	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #140 (Regular Classroom)							
	Casework	1st Floor	6	LF	6	\$152	
	Ceiling - Lay-in	1st Floor	1,045	SF	6	\$3,138	
	Chalk Board	1st Floor	26	LF	4	\$2,387	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,045	SF	6	\$2,286	
	Lighting - Pendent/Surface	1st Floor	20	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Walls - Concrete Block	1st Floor	462	SF	6	\$1,354	
	Walls - Plaster/Drywall	1st Floor	696	SF	6	\$1,921	
Classroom #142 (Other Instructional Use)							
	Casework	1st Floor	5	LF	6	\$126	
	Ceiling - Lay-in	1st Floor	1,035	SF	6	\$3,108	
	Chalk Board	1st Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,035	SF	6	\$2,264	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #142 (Other Instructional Use)							
	Lighting - Lay-in	1st Floor	20	EA	7	\$0	
	Walls - Concrete Block	1st Floor	864	SF	6	\$2,533	
	Walls - Plaster/Drywall	1st Floor	218	SF	6	\$602	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #228 (Weight)							
	Ceiling - Plaster/Drywall	2nd Floor	1,865	SF	6	\$6,454	
	Doors - Side-lite	2nd Floor	14	SF	6	\$234	Solid wood panel
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Weight/ Fitness Room Floor Matting	2nd Floor	1,865	SF	6	\$9,761	
	Lighting - Pendent/Surface	2nd Floor	54	EA	7	\$0	
	Storage/ Closet	2nd Floor	720	SF	6	\$5,220	
	Walls - Plaster/Drywall	2nd Floor	1,950	SF	6	\$5,382	
	Work Sink	2nd Floor	1	EA	5	\$1,508	slop sink - damaged
	Work Sink	2nd Floor	1	EA	6	\$379	water fountain
Classroom #232 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	640	SF	6	\$1,922	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	640	SF	6	\$1,400	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Storage/ Closet	2nd Floor	52	SF	6	\$377	
	Walls - Plaster/Drywall	2nd Floor	938	SF	6	\$2,589	
Classroom #234 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	491	SF	6	\$1,474	
	Ceiling - Plaster/Drywall	2nd Floor	182	SF	6	\$630	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	673	SF	6	\$1,472	
	Lighting - Lay-in	2nd Floor	22	EA	7	\$0	9 - recessed cans / 1 - charging station
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	971	SF	6	\$2,680	
Classroom #236 (Special Education)							
	Casework	2nd Floor	36	LF	6	\$909	
	Ceiling - Lay-in	2nd Floor	642	SF	6	\$1,928	
	Ceiling - Plaster/Drywall	2nd Floor	393	SF	6	\$1,360	
	Chalk Board	2nd Floor	5	LF	4	\$459	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #236 (Special Education)							
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,035	SF	6	\$2,264	
	Lighting - Lay-in	2nd Floor	22	EA	7	\$0	10 - recessed cans
	Marker Board	2nd Floor	15	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,175	SF	6	\$3,243	
Classroom #237 (Regular Classroom)							
	Casework	2nd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Chalk Board	2nd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	686	SF	6	\$1,501	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	932	SF	6	\$2,572	
Classroom #238 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	596	SF	6	\$1,790	
	Ceiling - Plaster/Drywall	2nd Floor	132	SF	6	\$457	
	Chalk Board	2nd Floor	17	LF	4	\$1,561	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	728	SF	6	\$1,593	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	969	SF	6	\$2,674	
Classroom #239 (Computer Lab)							
	Casework	2nd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	2nd Floor	1,382	SF	6	\$4,150	
	Ceiling - Lay-in	2nd Floor	10	SF	5	\$80	cracked tiles / holes
	Chalk Board	2nd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,392	SF	6	\$3,046	
	Lighting - Lay-in	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,416	SF	6	\$3,908	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #240 (Regular Classroom)							
	Casework	2nd Floor	5	LF	6	\$126	
	Ceiling - Lay-in	2nd Floor	647	SF	6	\$1,943	
	Chalk Board	2nd Floor	3	LF	4	\$275	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	647	SF	6	\$1,416	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	1 outlet damaged
	Marker Board	2nd Floor	16	LF	7	\$0	
	Storage/ Closet	2nd Floor	8	SF	6	\$58	
	Walls - Plaster/Drywall	2nd Floor	891	SF	6	\$2,459	
Classroom #242 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	362	SF	6	\$1,087	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	362	SF	6	\$792	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	5	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	485	SF	6	\$1,422	
	Walls - Plaster/Drywall	2nd Floor	235	SF	6	\$649	
Classroom #324 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	630	SF	6	\$1,892	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	630	SF	6	\$1,378	
	Lighting - Lay-in	3rd Floor	10	EA	6	\$1,190	1 outlet junction box and strip damaged - exposed wiring
	Marker Board	3rd Floor	4	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	988	SF	6	\$2,727	
Classroom #332 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	5	SF	5	\$40	stains
	Ceiling - Lay-in	3rd Floor	694	SF	6	\$2,084	
	Chalk Board	3rd Floor	49	LF	4	\$4,498	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	699	SF	6	\$1,529	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	945	SF	6	\$2,608	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #334 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	690	SF	6	\$2,072	
	Chalk Board	3rd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	690	SF	6	\$1,510	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	938	SF	6	\$2,589	
Classroom #336 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	686	SF	6	\$2,060	
	Chalk Board	3rd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	686	SF	6	\$1,501	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
Classroom #337 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	695	SF	6	\$2,087	
	Chalk Board	3rd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	695	SF	6	\$1,521	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	938	SF	6	\$2,589	
Classroom #338 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	690	SF	6	\$2,072	
	Chalk Board	3rd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	690	SF	6	\$1,510	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	941	SF	6	\$2,597	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #339 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	694	SF	6	\$2,084	
	Chalk Board	3rd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	694	SF	6	\$1,518	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	937	SF	6	\$2,586	
Classroom #340 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	690	SF	6	\$2,072	
	Chalk Board	3rd Floor	11	LF	4	\$1,010	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	690	SF	6	\$1,510	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	22	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	938	SF	6	\$2,589	
Classroom #341 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	694	SF	6	\$2,084	
	Chalk Board	3rd Floor	31	LF	4	\$2,846	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	694	SF	6	\$1,518	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	939	SF	6	\$2,592	
Classroom #342 (Computer Lab)							
	Ceiling - Lay-in	3rd Floor	700	SF	6	\$2,102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	700	SF	6	\$1,532	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	6	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	943	SF	6	\$2,603	
Classroom #342A (Computer Lab)							
	Ceiling - Lay-in	3rd Floor	340	SF	6	\$1,021	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #342A (Computer Lab)							
	Ceiling - Lay-in	3rd Floor	5	SF	5	\$40	stains
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	345	SF	6	\$755	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	9	LF	7	\$0	
	Storage/ Closet	3rd Floor	20	SF	6	\$145	built-in
	Student Lockers - One Tier	3rd Floor	1	EA	6	\$93	
	Walls - Plaster/Drywall	3rd Floor	782	SF	6	\$2,158	base trim falling off

Classrooms Subtotal:

\$261,919

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	AC Unit	1st - 124 Office	1	EA	4	\$6,086	Not on dedicated circuit
	Ceiling - Plaster/Drywall	1st - 124 Office	271	SF	6	\$938	
	Doors - Wood Doors inclu hw	1st - 124 Office	2	EA	6	\$602	
	Floor - Tile	1st - 124 Office	271	SF	6	\$593	
	Lighting - Pendent/Surface	1st - 124 Office	4	EA	7	\$0	
	Power Distribution	1st - 124 Office	4	EA	6	\$8,500	
	Walls - Concrete Block	1st - 124 Office	886	SF	6	\$2,597	
	Ceiling - Plaster/Drywall	1st - 125 Coat Check	408	SF	6	\$1,412	
	Doors - Wood Doors inclu hw	1st - 125 Coat Check	1	EA	6	\$301	
	Floor - Tile	1st - 125 Coat Check	408	SF	6	\$893	
	Lighting - Pendent/Surface	1st - 125 Coat Check	6	EA	7	\$0	
	Power Distribution	1st - 125 Coat Check	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st - 125 Coat Check	1,179	SF	6	\$3,254	
	Ceiling - Plaster/Drywall	1st - 128 Gym Office	489	SF	6	\$1,692	
	Doors - Side-lite	1st - 128 Gym Office	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	1st - 128 Gym Office	1	EA	6	\$301	
	Floor - Tile	1st - 128 Gym Office	489	SF	6	\$1,070	
	Lighting - Pendent/Surface	1st - 128 Gym Office	2	EA	7	\$0	
	Power Distribution	1st - 128 Gym Office	4	EA	6	\$8,500	
	Storage/ Closet	1st - 128 Gym Office	31	SF	6	\$225	
	Walls - Concrete Block	1st - 128 Gym Office	480	SF	6	\$1,407	
	Work Slnk	1st - 128 Gym Office	1	EA	6	\$508	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Plaster/Drywall	2nd - 228A Office inside 228 Gym	137	SF	6	\$474	
	Doors - Side-lite	2nd - 228A Office inside 228 Gym	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd - 228A Office inside 228 Gym	1	EA	6	\$301	
	Floor - Tile	2nd - 228A Office inside 228 Gym	137	SF	6	\$300	
	Lighting - Pendant/Surface	2nd - 228A Office inside 228 Gym	3	EA	7	\$0	
	Walls - Plaster/Drywall	2nd - 228A Office inside 228 Gym	512	SF	6	\$1,413	
	Ceiling - Plaster/Drywall	2nd - 228B Office inside 228 Gym	128	SF	6	\$443	
	Doors - Side-lite	2nd - 228B Office inside 228 Gym	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd - 228B Office inside 228 Gym	1	EA	6	\$301	
	Floor - Tile	2nd - 228B Office inside 228 Gym	128	SF	5	\$575	areas coming up / missing / cracked
	Lighting - Pendant/Surface	2nd - 228B Office inside 228 Gym	3	EA	7	\$0	
	Power Distribution	2nd - 228B Office inside 228 Gym	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	2nd - 228B Office inside 228 Gym	10	SF	5	\$51	cracks / peeling
	Walls - Plaster/Drywall	2nd - 228B Office inside 228 Gym	492	SF	6	\$1,358	
	Ceiling - Plaster/Drywall	2nd - 228C Office inside 228 Gym	130	SF	6	\$450	
	Doors - Side-lite	2nd - 228C Office inside 228 Gym	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd - 228C Office inside 228 Gym	1	EA	6	\$301	
	Floor - Tile	2nd - 228C Office inside 228 Gym	130	SF	6	\$284	
	Lighting - Pendant/Surface	2nd - 228C Office inside 228 Gym	3	EA	7	\$0	
	Power Distribution	2nd - 228C Office inside 228 Gym	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	2nd - 228C Office inside 228 Gym	493	SF	6	\$1,361	
	Ceiling - Plaster/Drywall	2nd - 228D Office inside 228 Gym	133	SF	6	\$460	
	Doors - Side-lite	2nd - 228D Office inside 228 Gym	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd - 228D Office inside 228 Gym	1	EA	6	\$301	
	Floor - Tile	2nd - 228D Office inside 228 Gym	133	SF	5	\$597	bad condition
	Lighting - Pendant/Surface	2nd - 228D Office inside 228 Gym	3	EA	7	\$0	
	Power Distribution	2nd - 228D Office inside 228 Gym	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	2nd - 228D Office inside 228 Gym	498	SF	6	\$1,374	
	Ceiling - Lay-in	2nd - Nurses	318	SF	6	\$955	
	Doors - Steel Doors incl hw	2nd - Nurses	1	EA	6	\$301	
	Floor - Carpet	2nd - Nurses	318	SF	6	\$678	
	Lighting - Lay-in	2nd - Nurses	4	EA	7	\$0	
	Power Distribution	2nd - Nurses	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	2nd - Nurses	697	SF	6	\$1,924	
	Ceiling - Lay-in	3rd - 330 Office	308	SF	6	\$925	
	Doors - Wood Doors inclu hw	3rd - 330 Office	1	EA	6	\$301	
	Floor - Carpet	3rd - 330 Office	308	SF	6	\$656	

Building: Addition 1
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	3rd - 330 Office	4	EA	7	\$0	
	Power Distribution	3rd - 330 Office	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	3rd - 330 Office	683	SF	6	\$1,885	
Gymnasias							
	Bleacher Seating	1st - 126 Gym	2	EA	6	\$58	2 pull-out sections at each side of gym
	Ceiling - Exposed	1st - 126 Gym	8,201	SF	6	\$12,197	
	Ceiling - Plaster/Drywall	1st - 126 Gym	294	SF	6	\$1,623	
	Doors - Steel Doors incl hw	1st - 126 Gym	8	EA	6	\$2,408	
	Floor - Tile Ceramic/ Porcelain	1st - 126 Gym	168	SF	6	\$356	
	Floor - Tile/Sheet	1st - 126 Gym	126	SF	5	\$566	vestibules / bad condition / missing / coming off floor
	Floor - Wood	1st - 126 Gym	8,201	SF	6	\$57,816	
	Lighting - Pendent/Surface	1st - 126 Gym	36	EA	6	\$4,460	
	Storage/ Closet	1st - 126 Gym	539	SF	6	\$3,908	
	Walls - Concrete Block	1st - 126 Gym	224	SF	6	\$657	
	Walls - Structural Glazed Tile	1st - 126 Gym	3,642	SF	6	\$11,458	
	Walls - Vinyl Coated Gypsum Panel	1st - 126 Gym	40	SF	5	\$295	stains at roof drain penetrations
	Walls - Vinyl Coated Gypsum Panel	1st - 126 Gym	4,628	SF	6	\$12,773	
Locker/Shower Room							
	Accessories	1st - inside 128 Gym Office	27	SF	5	\$236	shower bad condition
	Ceiling - Plaster/ Drywall	1st - inside 128 Gym Office	27	SF	5	\$258	
	Doors - Wood Doors inclu hw	1st - inside 128 Gym Office	1	EA	6	\$301	door width not 32"
	Floor Drain	1st - inside 128 Gym Office	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st - inside 128 Gym Office	27	SF	5	\$121	old / bad condition
	Showers	1st - inside 128 Gym Office	1	EA	5	\$2,714	bad condition
	Student Lockers - One Tier	1st - inside 128 Gym Office	1	EA	5	\$140	old
	Walls - Concrete Block	1st - inside 128 Gym Office	196	SF	6	\$575	
	Accessories	Basement - 015 Mens Locker Room	498	SF	6	\$1,951	
	Benches, ped mounted	Basement - 015 Mens Locker Room	16	LF	6	\$1,742	
	Ceiling - Plaster/ Drywall	Basement - 015 Mens Locker Room	2,789	SF	6	\$9,652	
	Ceiling - Plaster/ Drywall	Basement - 015 Mens Locker Room	40	SF	5	\$522	stained / holes / peeling
	Doors - Steel Doors incl hw	Basement - 015 Mens Locker Room	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Basement - 015 Mens Locker Room	1	EA	6	\$301	
	Floor Drain	Basement - 015 Mens Locker Room	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	Basement - 015 Mens Locker Room	2,829	SF	5	\$4,855	old / bad condition
	Floor - Tile Ceramic/ Porcelain	Basement - 015 Mens Locker Room	50	SF	5	\$1,045	wavy floor at shower area
	Floor - Tile Ceramic/ Porcelain	Basement - 015 Mens Locker Room	458	SF	6	\$969	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Hand Dryer	Basement - 015 Mens Locker Room	1	EA	6	\$230	
	Lavatory	Basement - 015 Mens Locker Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	Basement - 015 Mens Locker Room	86	EA	7	\$0	
	Partitions	Basement - 015 Mens Locker Room	1	EA	6	\$297	Granite Slab
	Showers	Basement - 015 Mens Locker Room	14	EA	5	\$38,003	several heads damaged
	Storage/ Closet	Basement - 015 Mens Locker Room	424	SF	6	\$3,074	towel rm included
	Student Lockers - One Tier	Basement - 015 Mens Locker Room	28	EA	6	\$2,599	
	Student Lockers - Two Tier	Basement - 015 Mens Locker Room	152	EA	6	\$7,056	
	Urinals	Basement - 015 Mens Locker Room	4	EA	6	\$1,344	
	Walls - Concrete Block	Basement - 015 Mens Locker Room	3,549	SF	6	\$10,404	several walls peeling
	Walls - Structural Glazed Tile	Basement - 015 Mens Locker Room	2,141	SF	6	\$6,736	
	Water Closet	Basement - 015 Mens Locker Room	2	EA	6	\$672	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	66	SF	5	\$1,065	ceiling stained / peeling
	Janitor's Closet	1st Floor	28	SF	6	\$201	
	Storage Room	1st Floor	309	SF	5	\$4,984	football storage / vertical crack
	Storage Room	1st Floor	402	SF	6	\$2,880	125 Bookroom / 139A Studio
	Janitor's Closet	2nd Floor	29	SF	6	\$208	
	Janitor's Closet	2nd Floor	65	SF	5	\$1,048	water leak at closet adjacent to 239
	Storage Room	2nd Floor	538	SF	6	\$3,854	floor of a storage room bad condition
	Janitor's Closet	3rd Floor	95	SF	6	\$681	
	Storage Room	3rd Floor	285	SF	5	\$4,597	328 - Crack in wall
Restroom							
	Accessories	1st - inside 128 Gym Office	19	SF	6	\$175	
	Ceiling - Plaster/Drywall	1st - inside 128 Gym Office	19	SF	6	\$66	
	Doors - Wood Doors inclu hw	1st - inside 128 Gym Office	1	EA	6	\$301	
	Floor - Tile	1st - inside 128 Gym Office	19	SF	6	\$42	
	Lighting - Pendent/Surface	1st - inside 128 Gym Office	1	EA	6	\$124	old incandescence
	Walls - Concrete Block	1st - inside 128 Gym Office	162	SF	6	\$475	
	Water Closet	1st - inside 128 Gym Office	1	EA	6	\$336	
	Accessories	1st - Men adjacent to 125 CC	299	SF	6	\$2,758	
	Ceiling - Plaster/Drywall	1st - Men adjacent to 125 CC	299	SF	6	\$1,035	
	Doors - Wood Doors inclu hw	1st - Men adjacent to 125 CC	1	EA	6	\$301	
	Floor Drain	1st - Men adjacent to 125 CC	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st - Men adjacent to 125 CC	5	SF	5	\$104	damaged
	Floor - Tile Ceramic/ Porcelain	1st - Men adjacent to 125 CC	294	SF	6	\$622	

Building: Addition 1
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Hand Dryer	1st - Men adjacent to 125 CC	1	EA	5	\$590	not working
	Lavatory	1st - Men adjacent to 125 CC	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st - Men adjacent to 125 CC	6	EA	7	\$0	
	Partitions	1st - Men adjacent to 125 CC	1	EA	6	\$297	
	Urinals	1st - Men adjacent to 125 CC	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	1st - Men adjacent to 125 CC	479	SF	6	\$1,322	
	Walls - Structural Glazed Tile	1st - Men adjacent to 125 CC	479	SF	6	\$1,507	
	Water Closet	1st - Men adjacent to 125 CC	2	EA	6	\$672	
	Accessories	1st - Unisex across from 142	276	SF	6	\$2,546	
	Benches	1st - Unisex across from 142	7	LF	6	\$101	
	Ceiling - Plaster/Drywall	1st - Unisex across from 142	276	SF	6	\$955	
	Doors - Steel Doors incl hw	1st - Unisex across from 142	1	EA	6	\$301	
	Floor Drain	1st - Unisex across from 142	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st - Unisex across from 142	276	SF	6	\$584	
	Hand Dryer	1st - Unisex across from 142	1	EA	6	\$230	
	Lavatory	1st - Unisex across from 142	1	EA	6	\$320	
	Lighting - Lay-in	1st - Unisex across from 142	7	EA	7	\$0	
	Partitions	1st - Unisex across from 142	1	EA	6	\$297	
	Walls - Plaster/Drywall	1st - Unisex across from 142	350	SF	6	\$966	
	Walls - Structural Glazed Tile	1st - Unisex across from 142	350	SF	6	\$1,101	
	Water Closet	1st - Unisex across from 142	1	EA	6	\$336	
	Accessories	1st - Women across from Gym	298	SF	6	\$2,749	
	Ceiling - Plaster/Drywall	1st - Women across from Gym	298	SF	6	\$1,031	
	Doors - Wood Doors inclu hw	1st - Women across from Gym	1	EA	6	\$301	
	Floor Drain	1st - Women across from Gym	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st - Women across from Gym	298	SF	6	\$631	
	Hand Dryer	1st - Women across from Gym	1	EA	6	\$230	
	Lavatory	1st - Women across from Gym	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st - Women across from Gym	5	EA	7	\$0	
	Lighting - Wall Mounted	1st - Women across from Gym	1	EA	7	\$0	
	Partitions	1st - Women across from Gym	2	EA	6	\$594	Granite slabs
	Walls - Plaster/Drywall	1st - Women across from Gym	228	SF	6	\$629	
	Walls - Structural Glazed Tile	1st - Women across from Gym	465	SF	6	\$1,463	
	Water Closet	1st - Women across from Gym	3	EA	6	\$1,008	
	Accessories	1st - Womens	297	SF	6	\$2,739	
	Benches	1st - Womens	7	LF	6	\$101	
	Ceiling - Plaster/Drywall	1st - Womens	297	SF	6	\$1,028	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Steel Doors incl hw	1st - Womens	1	EA	6	\$301	
	Floor Drain	1st - Womens	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st - Womens	297	SF	6	\$629	
	Hand Dryer	1st - Womens	1	EA	6	\$230	
	Lavatory	1st - Womens	1	EA	6	\$320	
	Lighting - Lay-in	1st - Womens	11	EA	7	\$0	
	Partitions	1st - Womens	3	EA	6	\$891	
	Walls - Plaster/Drywall	1st - Womens	238	SF	6	\$657	
	Walls - Structural Glazed Tile	1st - Womens	555	SF	6	\$1,746	
	Water Closet	1st - Womens	2	EA	6	\$672	
	Accessories	2nd - inside Nurses	45	SF	6	\$415	
	Ceiling - Plaster/Drywall	2nd - inside Nurses	45	SF	6	\$156	
	Doors - Steel Doors incl hw	2nd - inside Nurses	1	EA	6	\$301	
	Floor - Tile	2nd - inside Nurses	45	SF	6	\$98	
	Hand Dryer	2nd - inside Nurses	1	EA	6	\$230	
	Lavatory	2nd - inside Nurses	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd - inside Nurses	1	EA	7	\$0	
	Partitions	2nd - inside Nurses	1	EA	6	\$297	Granite Slab
	Walls - Plaster/Drywall	2nd - inside Nurses	5	SF	5	\$26	damaged around toilet
	Walls - Plaster/Drywall	2nd - inside Nurses	249	SF	6	\$687	
	Water Closet	2nd - inside Nurses	1	EA	6	\$336	
	Accessories	2nd - Mens	276	SF	6	\$2,546	
	Ceiling - Plaster/Drywall	2nd - Mens	276	SF	6	\$955	
	Doors - Steel Doors incl hw	2nd - Mens	1	EA	6	\$301	
	Floor Drain	2nd - Mens	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Mens	276	SF	6	\$584	
	Hand Dryer	2nd - Mens	1	EA	6	\$230	
	Lavatory	2nd - Mens	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Mens	7	EA	7	\$0	
	Partitions	2nd - Mens	1	EA	6	\$297	
	Urinals	2nd - Mens	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	2nd - Mens	210	SF	6	\$580	
	Walls - Structural Glazed Tile	2nd - Mens	489	SF	6	\$1,538	
	Water Closet	2nd - Mens	2	EA	6	\$672	
	Accessories	2nd - Womens	297	SF	6	\$2,739	
	Ceiling - Plaster/Drywall	2nd - Womens	297	SF	6	\$1,028	
	Doors - Steel Doors incl hw	2nd - Womens	1	EA	6	\$301	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	2nd - Womens	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Womens	297	SF	6	\$629	
	Hand Dryer	2nd - Womens	1	EA	6	\$230	
	Lavatory	2nd - Womens	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Womens	11	EA	7	\$0	
	Partitions	2nd - Womens	3	EA	6	\$891	
	Walls - Plaster/Drywall	2nd - Womens	238	SF	6	\$657	
	Walls - Structural Glazed Tile	2nd - Womens	558	SF	6	\$1,755	
	Water Closet	2nd - Womens	4	EA	6	\$1,344	
	Accessories	3rd - Girls	337	SF	6	\$3,108	
	Ceiling - Plaster/Drywall	3rd - Girls	337	SF	6	\$1,166	
	Doors - Steel Doors incl hw	3rd - Girls	1	EA	6	\$301	
	Floor Drain	3rd - Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd - Girls	337	SF	6	\$713	
	Hand Dryer	3rd - Girls	1	EA	6	\$230	
	Lavatory	3rd - Girls	2	EA	6	\$639	
	Lighting - Lay-in	3rd - Girls	10	EA	7	\$0	
	Partitions	3rd - Girls	3	EA	6	\$891	
	Walls - Plaster/Drywall	3rd - Girls	10	SF	5	\$51	stained / peeling / cracks
	Walls - Plaster/Drywall	3rd - Girls	237	SF	6	\$654	
	Walls - Structural Glazed Tile	3rd - Girls	575	SF	6	\$1,809	
	Water Closet	3rd - Girls	4	EA	6	\$1,344	
	Accessories	3rd - Men	276	SF	6	\$2,546	
	Ceiling - Plaster/Drywall	3rd - Men	276	SF	6	\$955	
	Doors - Steel Doors incl hw	3rd - Men	1	EA	6	\$301	
	Floor Drain	3rd - Men	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd - Men	276	SF	6	\$584	
	Hand Dryer	3rd - Men	1	EA	6	\$230	
	Lavatory	3rd - Men	2	EA	6	\$639	
	Lighting - Lay-in	3rd - Men	7	EA	7	\$0	
	Partitions	3rd - Men	1	EA	6	\$297	
	Urinals	3rd - Men	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	3rd - Men	210	SF	6	\$580	
	Walls - Structural Glazed Tile	3rd - Men	489	SF	6	\$1,538	
	Water Closet	3rd - Men	2	EA	6	\$672	
	Accessories	3rd - Women inside 330 Office	48	SF	6	\$443	
	Ceiling - Plaster/Drywall	3rd - Women inside 330 Office	48	SF	6	\$166	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	3rd - Women inside 330 Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd - Women inside 330 Office	48	SF	6	\$102	
	Lavatory	3rd - Women inside 330 Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	3rd - Women inside 330 Office	1	EA	7	\$0	
	Lighting - Wall Mounted	3rd - Women inside 330 Office	1	EA	7	\$0	
	Partitions	3rd - Women inside 330 Office	1	EA	6	\$297	granite slab
	Walls - Plaster/Drywall	3rd - Women inside 330 Office	5	SF	5	\$26	peeling / stained
	Walls - Plaster/Drywall	3rd - Women inside 330 Office	240	SF	6	\$662	
	Water Closet	3rd - Women inside 330 Office	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$441,337

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	3,724	SF	6	\$11,183	
	Ceiling - Plaster/Drywall	1st Floor	466	SF	6	\$2,885	
	Ceiling - Splined	1st Floor	1,472	SF	6	\$4,252	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Doors - Transom Window	1st Floor	76	EA	6	\$1,287	
	Doors - Wood Doors include hw	1st Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	
	Floor - Terrazzo	1st Floor	1,772	SF	6	\$14,874	
	Floor - Tile Ceramic/ Porcelain	1st Floor	422	SF	6	\$1,177	
	Floor - Tile/Sheet	1st Floor	3,724	SF	6	\$2,024	
	Lighting - Lay-in	1st Floor	49	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	6	EA	7	\$0	
	Stairs - Terrazzo	1st Floor	4	LF	6	\$37	
	Student Lockers - One Tier	1st Floor	231	EA	6	\$21,445	
	Walls - Concrete Block	1st Floor	1,680	SF	6	\$4,925	
	Walls - Plaster/Drywall	1st Floor	3,747	SF	6	\$16,610	
	Walls - Structural Glazed Tile	1st Floor	3,270	SF	6	\$10,287	
	Ceiling - Lay-in	2nd Floor	4,357	SF	6	\$13,084	
	Ceiling - Plaster/Drywall	2nd Floor	124	SF	6	\$768	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Terrazzo	2nd Floor	338	SF	6	\$2,837	

Building: Addition 1
Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Floor - Tile/Sheet	2nd Floor	4,143	SF	6	\$2,251	
	Lighting - Lay-in	2nd Floor	41	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	2	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	275	EA	6	\$25,530	
	Walls - Plaster/Drywall	2nd Floor	1,957	SF	6	\$8,675	
	Walls - Structural Glazed Tile	2nd Floor	1,957	SF	6	\$6,157	
	Ceiling - Plaster/Drywall	3rd Floor	4,274	SF	6	\$26,464	
	Doors - Side-lite	3rd Floor	32	EA	6	\$535	
	Doors - Transom Window	3rd Floor	7	EA	6	\$119	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	6	\$551	
	Floor - Terrazzo	3rd Floor	250	SF	6	\$2,099	
	Floor - Tile/Sheet	3rd Floor	4,024	SF	6	\$2,187	
	Lighting - Pendent/Surface	3rd Floor	45	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	200	EA	6	\$18,567	
	Walls - Plaster/Drywall	3rd Floor	2,140	SF	6	\$9,487	
	Walls - Structural Glazed Tile	3rd Floor	4,345	SF	6	\$13,669	
Safety							
	Security Cameras	Entire Building	3	EA	6	\$582	6 in the Main, 3 in the 1st Addition, None in 2nd Addition
	Security Cameras	Entire Building	2	EA	6	\$388	
Stairs							
	Ceiling - Plaster/Drywall	from gym up to weight room	137	SF	6	\$1,003	
	Floor - Concrete Epoxy/ Painted	from gym up to weight room	16	SF	6	\$8	
	Handrails	from gym up to weight room	28	LF	6	\$243	
	Lighting - Pendent/Surface	from gym up to weight room	2	EA	7	\$0	
	Stairs - Concrete	from gym up to weight room	20	LF	6	\$166	
	Walls - Concrete Block	from gym up to weight room	1,456	SF	6	\$4,268	
	Ceiling - Plaster/Drywall	Mens Locker rm 015 up to Gym floor	110	SF	6	\$805	
	Floor - Concrete Epoxy/ Painted	Mens Locker rm 015 up to Gym floor	25	SF	6	\$12	
	Handrails	Mens Locker rm 015 up to Gym floor	26	LF	6	\$225	
	Lighting - Pendent/Surface	Mens Locker rm 015 up to Gym floor	1	EA	7	\$0	
	Stairs - Concrete	Mens Locker rm 015 up to Gym floor	17	LF	6	\$141	
	Walls - Structural Glazed Tile	Mens Locker rm 015 up to Gym floor	913	SF	6	\$2,872	
	Ceiling - Plaster/Drywall	Mens locker room from corridor	90	SF	6	\$659	
	Floor - Concrete Epoxy/ Painted	Mens locker room from corridor	23	SF	6	\$11	
	Handrails	Mens locker room from corridor	44	LF	6	\$381	
	Lighting - Wall Mounted	Mens locker room from corridor	1	EA	7	\$0	

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Stairs - Concrete	Mens locker room from corridor	23	LF	6	\$191	
	Walls - Concrete Block	Mens locker room from corridor	1,125	SF	6	\$3,298	
	Ceiling - Plaster/Drywall	North	372	SF	6	\$2,724	
	Floor - Terrazzo	North	223	SF	6	\$1,872	
	Handrails	North	103	LF	6	\$893	
	Lighting - Pendent/Surface	North	4	EA	7	\$0	
	Stairs - Terrazzo	North	47	LF	6	\$436	
	Walls - Plaster/Drywall	North	899	SF	6	\$2,481	
	Walls - Structural Glazed Tile	North	446	SF	6	\$1,403	
	Ceiling - Plaster/Drywall	South	372	SF	6	\$2,724	
	Floor - Terrazzo	South	223	SF	6	\$1,872	
	Handrails	South	103	LF	6	\$893	
	Lighting - Pendent/Surface	South	4	EA	7	\$0	
	Stairs - Terrazzo	South	47	LF	6	\$436	
	Walls - Plaster/Drywall	South	899	SF	6	\$2,481	
	Walls - Structural Glazed Tile	South	446	SF	6	\$1,403	

Building Interior Subtotal:

\$262,349

Total Building Cost

\$2,626,752

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio	#1- S- Main Accessible	1	EA	5	\$994	broken call button
	Exterior Doors - Exterior Steel Door	#11- SW	4	EA	6	\$1,922	
	Exterior Doors - Exterior Steel Door	#2- SE	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.5- SE	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#3- NE	2	EA	6	\$961	FRP panels on doors
	Exterior Doors - Exterior Steel Door	#3.1- NE	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#3.2- NE	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#4- N	4	EA	6	\$1,922	FRP Panels
	Exterior Doors - Exterior Steel Door	#4.1- NW	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#4.2- NW	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#4.3- NW	2	EA	6	\$961	not in use

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Steel Door	#5- W	2	EA	6	\$961	FRP panels applied
	Exterior Doors - Exterior Steel Door	#5.1- W	2	EA	5	\$2,683	dents
	Exterior Doors - Side lite	#2.5- SE	2	EA	6	\$627	
	Exterior Doors - Side lite	#3.1- NE	2	EA	6	\$627	
	Exterior Doors - Side lite	#3.2- NE	2	EA	6	\$627	
	Exterior Doors - Side lite	#4.1- NW	2	EA	6	\$627	
	Exterior Doors - Side lite	#4.2- NW	2	EA	6	\$627	
	Exterior Doors - Side lite	#5- W	2	EA	6	\$627	
	Exterior Doors - Store Front	#1- S- Main Accessible	4	EA	6	\$2,184	
	Exterior Doors - Store Front	#12- SW	2	EA	6	\$1,092	
	Exterior Doors - Transom Lite	#1- S- Main Accessible	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#11- SW	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#12- SW	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#2- SE	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#2.5- SE	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#3.1- NE	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#3.2- NE	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#4- N	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#4.1- NW	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#4.2- NW	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#5- W	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#5.1- W	1	EA	6	\$313	
	Exterior Stairs - Concrete	#2.5- SE	5	LF	6	\$409	
	Exterior Stairs - Concrete	#3- NE	30	LF	6	\$2,453	
	Power Door Operator and Controls	#1- S- Main Accessible	1	EA	6	\$0	
	Stair Handrail - Steel_Stair Handrail	#3- NE	4	LF	6	\$35	
Foundation							
	Foundation - Concrete	Entire Building	1,550	LF	7	\$0	
	Foundation - Concrete	Entire Building / Basement	10	LF	6	\$1,942	cracks, efflorescence, seepage
	Superstructure - Concrete	Entire Building	40	SF	6	\$0	seepage, cracks, spalling, efflorescence, exposed steel of ceiling deck
	Superstructure - Concrete	Entire Building	135,000	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	8	EA	6	\$4,292	
	Exterior Lighting - Wall Mounted	Entire Building	20	EA	6	\$5,775	

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Chimney - Metal Flue	Main Roof	108	LF	6	\$17,080	
	Coping - Stone	Main Roof	1,550	LF	6	\$49,783	
	Downspouts - Interior Downspouts	Main Roof	480	LF	6	\$15,952	
	Parapet - 16" - 30" Height	Main Roof	1,550	LF	6	\$61,929	
	Roof Structure - Concrete	Main Roof	694,040	SF	7	\$0	
	Roof - Modified Bitumen	Main Roof	69,404	SF	5	\$1,459,934	Worn surface, some minor water ponding
Walls							
	Canopy - Metal	Entire Building	256	SF	6	\$5,499	
	Exterior Walls - Precast Panel Wall	Entire Building	49,600	SF	6	\$333,362	
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	8,644	SF	6	\$96,910	
	Guard - Guards perforated	Entire Building	828	SF	6	\$10,573	
	Lintels - Steel	Entire Building	29	LF	6	\$842	
	Windows - Sash Aluminum Double-pane	Entire Building	10,260	SF	6	\$76,587	
Building Exterior Subtotal:						\$2,168,859	

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	1st Floor	1	EA	6	\$408	Location: Electrical Room (Main)
	Automatic Transfer Switch	1st Floor	1	EA	6	\$408	Location: Electrical Room (East No. 2)
	Automatic Transfer Switch	1st Floor	1	EA	6	\$408	Location: Electrical Room (East No. 2)
	Emergency A/C Power - Corridors and Stairs	Entire Building	27,928	SF	6	\$8,387	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	239	SF	6	\$89	
	Emergency A/C Power - Lunchrooms	Entire Building / 2nd Floor	17,033	SF	6	\$6,333	
	Emergency A/C Power - Multipurpose Room	Entire Building / 1st Floor	1,895	SF	6	\$705	
	Emergency A/C Power - Multipurpose Room	Entire Building / 2nd Floor	2,038	SF	6	\$758	
	Emergency A/C Power - Students Toilets	Entire Building	2,257	SF	6	\$839	
	Exit Signs - Corridors and Stairs	Entire Building	20	EA	6	\$2,995	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	1	EA	6	\$150	
	Exit Signs - Lunchroom	Entire Building / 2nd Floor	9	EA	6	\$1,348	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	2	EA	6	\$299	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	2	EA	6	\$299	
	Security System - Intrusion Detection	Entire Building	135,040	SF	6	\$34,759	

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
Main Service							
	Independent Electrical Service for emergency power	1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	PA System	Entire Building	135,040	SF	6	\$44,415	Serves & links all three buildings (Location: Main Building)
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East No. 2)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Serving Line
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	Location: Electrical Room (Main) (Blank for Main Breaker Missing)
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East)
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Closet
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Closet
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Closet (Missing CCT Blank No. 13)
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Closet
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Office 256
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: MDF Room
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Closet
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: MDF Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location: MDF Room
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	7	\$0	Location Facility Dining Room 271
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East No. 2)
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Main Distribution Panels - 400 - 600 amp	Entire Building / 2nd Floor	1	EA	7	\$0	Location: Electrical Closet
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East)
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Main Distribution Panels - Greater than 600 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East)
	Main Distribution Panels - Less than 400 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East)
	Main Distribution Panels - Less than 400 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Main Distribution Panels - Less than 400 amp	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution							
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (East)
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)
	Transformers - 277/480 - 120/208	Entire Building / 1st Floor	1	EA	7	\$0	Location: Electrical Room (Main)

Electrical System Subtotal:

\$102,899

Building: Addition 2

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Fire Pump Room / 1st Floor	1	EA	6	\$6,406	Location: Fire Pump Room (Link between: Addition #1 & Main Building) Also Serves Addition 1 and the Main Building
	Fire Alarm Strobe Lights	Fire Pump Room / Entire Building	135,040	SF	6	\$48,277	
	Fire Alarm_System	Fire Pump Room / Entire Building	135,040	SF	6	\$65,656	
	Fire Pump Controller	Fire Pump Room / 1st Floor	1	EA	6	\$1,823	Location: Fire Pump Room Also serves Addition 1
Pump Room Assembly							
	Fire Pump - 25-50 hp	Fire Pump Room / 1st Floor	1	EA	4	\$38,011	Location: Fire Pump Room (Shaft Corroded, Leaking, Frame Deteriated & Water Dripping into a Bucket) Also serves Addition 1
	Jockey Pump	Fire Pump Room / 1st Floor	1	EA	6	\$758	Location: Frie Pump Room. Also serves Addition 1
Sprinkler System							
	Sprinkler Heads	Entire Building	135,040	SF	6	\$0	Corrosion Present on Sprinkler Head
	Sprinkler Piping	Entire Building	135,040	SF	6	\$25,104	
	Wet Sprinkler System	Entire Building	135,040	SF	6	\$34,759	

Safty System Subtotal:

\$220,794

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	Serves: Elevator Room

Building: Addition 2
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	PVC Traps, Drainlines either broken off, missing, not connected or cut off at unit
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating Coil - 5 - 10 tons	Roof	1	EA	5	\$8,634	Corrosion Entire Top & Additonal spots on all side panels, Soft Metal Present espcrially the top.
Heating Devices							
	Cabinet Heaters - With Electric Coil	Entire Building / 1st Floor	2	EA	6	\$713	Location: Storage Room
	Cabinet Heaters - With Electric Coil	Entire Building	12	EA	6	\$4,279	Includes, Restroom, Mechanical Spaces, Storerooms etc.
	Fin Tube - Electric	1st Floor	6	LF	5	\$306	
	Unit Heater - Electric	Loading dock	1	EA	6	\$278	
Temperature Control							
	DDC System	Entire Building	135,040	SF	6	\$77,243	
	Thermostats - DDC	Entire Building	53	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	Expansion Joint Missing, Rusted & Soft Metal
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	Expansion Joint Riped, Rusted & Soft Metal
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Ventilation							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	Rusted & Soft Metal
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / Roof	1	EA	6	\$592	Expansion Joint Riped, Holes, Rusted & Soft Metal
	Type I Exhaust Hood- Culinary Arts	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / 1st Floor	1	EA	7	\$0	
	Type I Exhaust Hood- Kitchen	Roof, Art Rooms 181/182/183, 2nd Floor, Kitchen / 2nd Floor	1	EA	7	\$0	
Mechanical System Subtotal:						\$126,428	

Building: Addition 2

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	6	\$310	
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	6	\$310	
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	4	\$34,950	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	135,040	SF	6	\$27,035	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	135,040	SF	6	\$32,828	
	Domestic Piping-Cold Water Risers	Entire Building	135,040	SF	6	\$25,104	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	135,040	SF	6	\$21,242	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	135,040	SF	6	\$25,104	
	Domestic Piping-Hot Water Return Lines	Entire Building	135,040	SF	6	\$19,311	
	Domestic Piping-Hot Water Return Risers	Entire Building	135,040	SF	6	\$19,311	
	Sanitary Piping	Entire Building	135,040	SF	6	\$123,589	
	Storm Piping	Entire Building	135,040	SF	6	\$117,795	
	Vent Piping	Entire Building	135,040	SF	6	\$90,760	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	1st Floor	1	EA	6	\$1,977	Location: Fire Pump Room. Also serves Addition 1
	Pumps - Sump-Duplex	1st Floor	1	EA	6	\$1,387	Location: Fire Pump Room

Building: Addition 2

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Plumbing System Subtotal:						\$541,012	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #145 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	750	SF	6	\$2,252	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	750	SF	6	\$1,641	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	479	SF	6	\$1,404	
	Walls - Metal Panel	1st Floor	208	SF	6	\$1,553	
	Walls - Plaster/Drywall	1st Floor	684	SF	6	\$1,888	
Classroom #149 (Computer Lab)							
	Ceiling - Lay-in	1st Floor	887	SF	6	\$2,664	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	887	SF	6	\$1,941	
	Lighting - Pendent/Surface	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	11	LF	6	\$236	
	Walls - Concrete Block	1st Floor	185	SF	6	\$542	
	Walls - Metal Panel	1st Floor	1,110	SF	6	\$8,286	
Classroom #150 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	324	SF	6	\$973	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	324	SF	6	\$709	
	Lighting - Pendent/Surface	1st Floor	8	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Metal Panel	1st Floor	321	SF	6	\$2,396	
	Walls - Plaster/Drywall	1st Floor	596	SF	6	\$1,645	
Classroom #151 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	485	SF	6	\$1,456	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #151 (Regular Classroom)							
	Floor - Tile	1st Floor	485	SF	6	\$1,061	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Walls - Metal Panel	1st Floor	550	SF	6	\$4,106	
	Walls - Plaster/Drywall	1st Floor	550	SF	6	\$1,518	
Classroom #152 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	633	SF	6	\$1,901	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	633	SF	6	\$1,385	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Metal Panel	1st Floor	678	SF	6	\$5,061	
	Walls - Plaster/Drywall	1st Floor	677	SF	6	\$1,868	
	Walls - Plaster/Drywall	1st Floor	1	SF	5	\$5	hole in wall
Classroom #153 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	885	SF	6	\$2,658	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	885	SF	6	\$1,936	
	Lighting - Pendent/Surface	1st Floor	17	EA	7	\$0	
	Walls - Concrete Block	1st Floor	185	SF	6	\$542	
	Walls - Metal Panel	1st Floor	1,122	SF	6	\$8,375	
Classroom #154 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	893	SF	6	\$2,682	
	Chalk Board	1st Floor	10	LF	4	\$918	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	893	SF	6	\$1,954	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Walls - Concrete Block	1st Floor	180	SF	6	\$528	
	Walls - Metal Panel	1st Floor	745	SF	6	\$5,561	
Classroom #156 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	887	SF	6	\$2,664	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #156 (Regular Classroom)							
	Floor - Tile	1st Floor	887	SF	6	\$1,941	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	176	SF	6	\$516	
	Walls - Metal Panel	1st Floor	1,219	SF	6	\$9,099	
Classroom #159 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	885	SF	6	\$2,658	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	885	SF	6	\$1,936	
	Lighting - Pendent/Surface	1st Floor	17	EA	7	\$0	
	Walls - Concrete Block	1st Floor	187	SF	6	\$548	
	Walls - Metal Panel	1st Floor	1,111	SF	6	\$8,293	
Classroom #160 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	890	SF	6	\$2,673	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	890	SF	6	\$1,947	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Walls - Concrete Block	1st Floor	372	SF	6	\$1,091	
	Walls - Metal Panel	1st Floor	745	SF	6	\$5,561	
Classroom #161 (Computer Lab)							
	Ceiling - Lay-in	1st Floor	891	SF	6	\$2,676	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	891	SF	6	\$1,949	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Metal Panel	1st Floor	1,115	SF	6	\$8,323	
	Walls - Plaster/Drywall	1st Floor	372	SF	6	\$1,027	
Classroom #172 (Music Room)							
	Ceiling - Lay-in	1st Floor	785	SF	6	\$2,357	
	Chalk Board	1st Floor	6	LF	4	\$551	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Carpet	1st Floor	785	SF	6	\$1,673	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #172 (Music Room)							
	Lighting - Lay-in	1st Floor	11	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Sound System	1st Floor	1	EA	6	\$1,442	
	Walls - Concrete Block	1st Floor	370	SF	6	\$1,085	
	Walls - Metal Panel	1st Floor	740	SF	6	\$5,524	
	Walls - Plaster/Drywall	1st Floor	370	SF	6	\$1,021	
Classroom #173 (Choral Room)							
	Ceiling - Lay-in	1st Floor	1,375	SF	6	\$4,129	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Carpet	1st Floor	565	SF	6	\$1,204	
	Floor - Tile	1st Floor	810	SF	6	\$1,772	
	Lighting - Lay-in	1st Floor	26	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	1	EA	7	\$0	
	Marker Board	1st Floor	18	LF	7	\$0	
	Risers	1st Floor	40	LF	6	\$900	
	Walls - Concrete Block	1st Floor	464	SF	6	\$1,360	
	Walls - Plaster/Drywall	1st Floor	928	SF	6	\$2,561	
	Walls - Tile	1st Floor	464	SF	6	\$1,015	Spline
Classroom #174 (Band Room)							
	Ceiling - Plaster/Drywall	1st Floor	143	SF	6	\$495	
	Doors - Wood Doors inclu hw	1st Floor	4	EA	6	\$1,204	
	Floor - Carpet	1st Floor	2,007	SF	6	\$4,276	
	Floor - Tile	1st Floor	140	SF	6	\$306	
	Floor - Tile	1st Floor	3	SF	5	\$17	damaged
	Lighting - Lay-in	1st Floor	38	EA	7	\$0	
	Risers	1st Floor	40	LF	6	\$900	
	Storage/ Closet	1st Floor	283	SF	6	\$2,052	
	Student Lockers - Three Tiers	1st Floor	288	EA	6	\$8,912	5 tier
	Walls - Concrete Block	1st Floor	4,929	SF	6	\$14,449	at least 50% is covered with spline
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #175 (Music Room)							
	Ceiling - Lay-in	1st Floor	732	SF	6	\$2,198	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	732	SF	6	\$1,602	
	Lighting - Lay-in	1st Floor	11	EA	6	\$1,309	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #175 (Music Room)							
	Walls - Concrete Block	1st Floor	678	SF	6	\$1,988	
	Walls - Metal Panel	1st Floor	339	SF	6	\$2,530	
	Walls - Plaster/Drywall	1st Floor	339	SF	6	\$936	
Classroom #176 (Music Room)							
	Ceiling - Lay-in	1st Floor	740	SF	6	\$2,222	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	740	SF	6	\$1,619	
	Lighting - Pendent/Surface	1st Floor	1	EA	6	\$124	cover missing
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	14	LF	7	\$0	
	Walls - Concrete Block	1st Floor	678	SF	6	\$1,988	
	Walls - Metal Panel	1st Floor	339	SF	6	\$2,530	
	Walls - Plaster/Drywall	1st Floor	339	SF	6	\$936	
Classroom #181/182/183 (Art Room)							
	Ceiling - Lay-in	1st Floor	4,800	SF	6	\$14,414	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Side-lite	1st Floor	40	SF	6	\$669	
	Doors - Wood Doors inclu hw	1st Floor	4	EA	6	\$1,204	
	Floor - Tile	1st Floor	11	SF	5	\$63	damaged
	Floor - Tile	1st Floor	4,789	SF	6	\$10,478	
	Instructional Surface	1st Floor	42	LF	6	\$1,414	
	Kiln	1st Floor	2	EA	6	\$4,642	
	Lighting - Pendent/Surface	1st Floor	90	EA	7	\$0	
	Storage/ Closet	1st Floor	530	SF	6	\$3,843	
	Walls - Concrete Block	1st Floor	3,447	SF	6	\$10,105	
	Walls - Metal Panel	1st Floor	1,477	SF	6	\$11,025	
	Walls - Plaster/Drywall	1st Floor	4,924	SF	6	\$13,590	
	Work Sink	1st Floor	5	EA	6	\$1,895	
Classroom #184 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	588	SF	6	\$1,766	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	588	SF	6	\$1,286	
	Lighting - Pendent/Surface	1st Floor	11	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #184 (Regular Classroom)							
	Walls - Concrete Block	1st Floor	125	SF	6	\$366	
	Walls - Metal Panel	1st Floor	1,113	SF	6	\$8,308	
Classroom #185 (Laboratory/Shop)							
	Ceiling - Plaster/Drywall	1st Floor	490	SF	6	\$1,696	
	Ceiling - Plaster/Drywall	1st Floor	10	SF	5	\$125	separating where 2 sheets of drywall meet.
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	500	SF	6	\$1,094	
	Lighting - Lay-in	1st Floor	5	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	1	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	5	EA	7	\$0	
	Storage/ Closet	1st Floor	242	SF	6	\$1,755	Room 185A & attached storage closet
	Walls - Concrete Block	1st Floor	723	SF	6	\$2,119	
	Work Sink	1st Floor	1	EA	6	\$379	photo wash sink
Classroom #187 (Other Instructional Use)							
	Ceiling - Splined	1st Floor	3,720	SF	6	\$3,032	
	Chalk Board	1st Floor	46	LF	4	\$4,223	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	886	SF	6	\$1,938	mezzanine level
	Floor - Wood	1st Floor	2,834	SF	5	\$41,458	needs refinishing
	Lighting - Lay-in	1st Floor	28	EA	7	\$0	can lights
	Lighting - Pendent/Surface	1st Floor	19	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	1	EA	7	\$0	
	Storage/ Closet	1st Floor	294	SF	6	\$2,132	
	Walls - Concrete Block	1st Floor	6,240	SF	6	\$18,293	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #191 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	846	SF	6	\$2,541	
	Doors - Side-lite	1st Floor	14	SF	6	\$234	
	Doors - Store Front	1st Floor	2	EA	6	\$2,416	
	Doors - Transom Window	1st Floor	46	SF	6	\$779	
	Floor - Carpet	1st Floor	846	SF	6	\$1,803	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Walls - Concrete Block	1st Floor	379	SF	6	\$1,111	
	Walls - Metal Panel	1st Floor	380	SF	6	\$2,837	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #196 (Computer Lab)							
	Ceiling - Lay-in	1st Floor	1,206	SF	6	\$3,622	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor	1st Floor	1,206		6	\$0	
	Lighting - Pendent/Surface	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Walls - Concrete Block	1st Floor	1,738	SF	6	\$5,095	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #245 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	750	SF	6	\$2,252	
	Chalk Board	2nd Floor	10	LF	4	\$918	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	750	SF	6	\$1,641	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	250	SF	6	\$733	
	Walls - Metal Panel	2nd Floor	512	SF	6	\$3,822	
Classroom #247 (Computer Lab)							
	Casework	2nd Floor	33	LF	6	\$833	
	Ceiling - Lay-in	2nd Floor	1,302	SF	6	\$3,910	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,302	SF	6	\$2,849	
	Lighting - Pendent/Surface	2nd Floor	26	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	295	SF	6	\$865	
	Walls - Metal Panel	2nd Floor	1,088	SF	6	\$8,121	
Classroom #250 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	982	SF	6	\$2,949	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Transom Window	2nd Floor	119	SF	6	\$2,015	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	982	SF	6	\$2,149	
	Lighting - Pendent/Surface	2nd Floor	30	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	99	SF	6	\$290	
	Walls - Metal Panel	2nd Floor	1,080	SF	6	\$8,062	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #250 (Computer Lab)							
Classroom #251 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	777	SF	6	\$2,333	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Transom Window	2nd Floor	108	SF	6	\$1,829	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	777	SF	6	\$1,700	
	Lighting - Pendent/Surface	2nd Floor	15	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	395	SF	6	\$1,158	
	Walls - Metal Panel	2nd Floor	694	SF	6	\$5,180	
	Wireless System	2nd Floor	1	EA	6	\$372	
Classroom #252 (Computer Lab)							
	Casework	2nd Floor	85	LF	6	\$2,147	
	Ceiling - Lay-in	2nd Floor	1,350	SF	6	\$4,054	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,350	SF	6	\$2,954	
	Lighting - Pendent/Surface	2nd Floor	23	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	135	SF	6	\$396	
	Walls - Plaster/Drywall	2nd Floor	1,062	SF	6	\$2,931	
Classroom #254 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	1,319	SF	6	\$3,961	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,319	SF	6	\$2,886	
	Lighting - Lay-in	2nd Floor	23	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	275	SF	6	\$806	
	Walls - Plaster/Drywall	2nd Floor	741	SF	6	\$2,045	
Classroom #255 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	883	SF	6	\$2,652	
	Chalk Board	2nd Floor	10	LF	4	\$918	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	883	SF	6	\$1,932	
	Lighting - Pendent/Surface	2nd Floor	17	EA	7	\$0	
	Marker Board	2nd Floor	11	LF	7	\$0	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #255 (Regular Classroom)							
	Walls - Metal Panel	2nd Floor	1,011	SF	6	\$7,547	
Classroom #257 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	893	SF	6	\$2,682	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	893	SF	6	\$1,954	
	Lighting - Pendent/Surface	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Walls - Concrete Block	1st Floor	180	SF	6	\$528	
	Walls - Metal Panel	1st Floor	805	SF	6	\$6,009	
Classroom #258 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	885	SF	6	\$2,658	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	885	SF	6	\$1,936	
	Lighting - Pendent/Surface	2nd Floor	17	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	90	SF	6	\$264	
	Walls - Metal Panel	2nd Floor	900	SF	6	\$6,718	
Classroom #259 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	889	SF	6	\$2,670	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	889	SF	6	\$1,945	
	Lighting - Pendent/Surface	2nd Floor	18	EA	7	\$0	exposed wiring at hole in speaker
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	90	SF	6	\$264	
	Walls - Metal Panel	2nd Floor	900	SF	6	\$6,718	
Classroom #260 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	890	SF	6	\$2,673	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	890	SF	6	\$1,947	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	90	SF	6	\$264	

Building: Addition 2
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #260 (Regular Classroom)							
	Walls - Metal Panel	2nd Floor	900	SF	6	\$6,718	
Classroom #261 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	885	SF	6	\$2,658	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	885	SF	6	\$1,936	
	Lighting - Pendent/Surface	2nd Floor	17	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	180	SF	6	\$528	
	Walls - Metal Panel	2nd Floor	600	SF	6	\$4,479	
Classroom #262 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	880	SF	6	\$2,643	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	875	SF	6	\$1,914	
	Floor - Tile	3rd Floor	5	SF	5	\$29	missing / cracked
	Lighting - Pendent/Surface	3rd Floor	17	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	151	SF	6	\$443	
	Walls - Metal Panel	3rd Floor	861	SF	6	\$6,427	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classrooms Subtotal:						\$563,426	

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st - 162 Forum	1,790	SF	6	\$5,375	
	Doors - Side-lite	1st - 162 Forum	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	1st - 162 Forum	1	EA	6	\$301	
	Floor - Carpet	1st - 162 Forum	1,790	SF	6	\$3,814	
	Lighting - Pendent/Surface	1st - 162 Forum	36	EA	7	\$0	
	Power Distribution	1st - 162 Forum	22	EA	6	\$46,747	
	Walls - Concrete Block	1st - 162 Forum	372	SF	6	\$1,091	
	Walls - Metal Panel	1st - 162 Forum	1,331	SF	6	\$9,935	
	Work Slnk	1st - 162 Forum	1	EA	6	\$508	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st - 253 Office	228	SF	6	\$685	
	Doors - Wood Doors inclu hw	1st - 253 Office	1	EA	6	\$301	
	Floor - Tile	1st - 253 Office	228	SF	6	\$499	
	Lighting - Pendent/Surface	1st - 253 Office	14	EA	6	\$1,735	
	Power Distribution	1st - 253 Office	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	1st - 253 Office	617	SF	6	\$1,703	
	Ceiling - Lay-in	1st- 180G- Conference Room/Storage	293	SF	6	\$880	
	Doors - Wood Doors inclu hw	1st- 180G- Conference Room/Storage	1	EA	6	\$301	
	Floor - Carpet	1st- 180G- Conference Room/Storage	293	SF	6	\$624	
	Lighting - Lay-in	1st- 180G- Conference Room/Storage	6	EA	7	\$0	
	Power Distribution	1st- 180G- Conference Room/Storage	8	EA	6	\$16,999	
	Walls - Metal Panel	1st- 180G- Conference Room/Storage	863	SF	6	\$6,442	
	Ceiling - Plaster/Drywall	1st- 180H- Journalism Office	535	SF	6	\$1,851	
	Doors - Wood Doors inclu hw	1st- 180H- Journalism Office	1	EA	6	\$301	
	Floor - Tile	1st- 180H- Journalism Office	535	SF	6	\$1,171	
	Lighting - Lay-in	1st- 180H- Journalism Office	12	EA	7	\$0	
	Power Distribution	1st- 180H- Journalism Office	30	EA	6	\$63,746	
	Walls - Concrete Block	1st- 180H- Journalism Office	1,175	SF	6	\$3,445	
	Work Slnk	1st- 180H- Journalism Office	1	EA	6	\$508	
	Ceiling - Lay-in	1st- Rm 155- Bilingual Office	366	SF	6	\$1,099	
	Doors - Side-lite	1st- Rm 155- Bilingual Office	11	SF	6	\$184	
	Doors - Wood Doors inclu hw	1st- Rm 155- Bilingual Office	1	EA	6	\$301	
	Floor - Tile	1st- Rm 155- Bilingual Office	366	SF	6	\$801	
	Lighting - Lay-in	1st- Rm 155- Bilingual Office	7	EA	7	\$0	
	Power Distribution	1st- Rm 155- Bilingual Office	14	EA	6	\$29,748	
	Walls - Metal Panel	1st- Rm 155- Bilingual Office	803	SF	6	\$5,994	
	Walls - Plaster/Drywall	1st- Rm 155- Bilingual Office	184	SF	6	\$508	
	Ceiling - Lay-in	1st- Rm 157- Int Baccalauerette Office	352	SF	6	\$1,057	
	Doors - Side-lite	1st- Rm 157- Int Baccalauerette Office	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st- Rm 157- Int Baccalauerette Office	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 157- Int Baccalauerette Office	352	SF	6	\$750	
	Lighting - Lay-in	1st- Rm 157- Int Baccalauerette Office	7	EA	7	\$0	
	Power Distribution	1st- Rm 157- Int Baccalauerette Office	14	EA	6	\$29,748	
	Walls - Concrete Block	1st- Rm 157- Int Baccalauerette Office	48	SF	6	\$141	
	Walls - Metal Panel	1st- Rm 157- Int Baccalauerette Office	921	SF	6	\$6,875	
	Ceiling - Lay-in	1st- Rm 158- Program Office	352	SF	6	\$1,057	
	Doors - Side-lite	1st- Rm 158- Program Office	10	SF	6	\$167	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Wood Doors inclu hw	1st- Rm 158- Program Office	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 158- Program Office	352	SF	6	\$750	
	Lighting - Lay-in	1st- Rm 158- Program Office	10	EA	7	\$0	
	Power Distribution	1st- Rm 158- Program Office	14	EA	6	\$29,748	
	Walls - Metal Panel	1st- Rm 158- Program Office	969	SF	6	\$7,233	
	Ceiling - Lay-in	1st- Rm 163- Audiology	312	SF	6	\$937	
	Doors - Side-lite	1st- Rm 163- Audiology	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st- Rm 163- Audiology	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 163- Audiology	312	SF	6	\$665	
	Lighting - Lay-in	1st- Rm 163- Audiology	4	EA	7	\$0	
	Power Distribution	1st- Rm 163- Audiology	8	EA	6	\$16,999	
	Walls - Concrete Block	1st- Rm 163- Audiology	214	SF	6	\$627	
	Walls - Metal Panel	1st- Rm 163- Audiology	642	SF	6	\$4,792	
	Ceiling - Lay-in	1st- Rm 163A- IBCC Office	195	SF	6	\$586	
	Doors - Wood Doors inclu hw	1st- Rm 163A- IBCC Office	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 163A- IBCC Office	195	SF	6	\$415	
	Lighting - Lay-in	1st- Rm 163A- IBCC Office	3	EA	7	\$0	
	Power Distribution	1st- Rm 163A- IBCC Office	4	EA	6	\$8,500	
	Walls - Metal Panel	1st- Rm 163A- IBCC Office	700	SF	6	\$5,225	
	Ceiling - Lay-in	1st- Rm 164- Asst Principal	288	SF	6	\$865	
	Doors - Side-lite	1st- Rm 164- Asst Principal	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st- Rm 164- Asst Principal	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 164- Asst Principal	288	SF	6	\$614	
	Lighting - Lay-in	1st- Rm 164- Asst Principal	4	EA	7	\$0	
	Power Distribution	1st- Rm 164- Asst Principal	10	EA	6	\$21,249	
	Walls - Concrete Block	1st- Rm 164- Asst Principal	214	SF	6	\$627	
	Walls - Metal Panel	1st- Rm 164- Asst Principal	642	SF	6	\$4,792	
	Ceiling - Lay-in	1st- Rm 166- Main Office	1,522	SF	6	\$4,571	
	Doors - Side-lite	1st- Rm 166- Main Office	100	SF	6	\$1,672	
	Doors - Transom Window	1st- Rm 166- Main Office	37	SF	6	\$626	
	Doors - Wood Doors inclu hw	1st- Rm 166- Main Office	2	EA	6	\$602	
	Floor - Carpet	1st- Rm 166- Main Office	1,522	SF	6	\$3,243	
	Lighting - Pendent/Surface	1st- Rm 166- Main Office	31	EA	7	\$0	
	Power Distribution	1st- Rm 166- Main Office	38	EA	7	\$0	
	Storage/ Closet	1st- Rm 166- Main Office	234	SF	6	\$1,697	
	Walls - Concrete Block	1st- Rm 166- Main Office	437	SF	6	\$1,281	
	Walls - Metal Panel	1st- Rm 166- Main Office	2,175	SF	6	\$16,236	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st- Rm 166A- Asst Principal	219	SF	6	\$658	
	Doors - Wood Doors inclu hw	1st- Rm 166A- Asst Principal	2	EA	6	\$602	
	Floor - Carpet	1st- Rm 166A- Asst Principal	219	SF	6	\$467	
	Lighting - Lay-in	1st- Rm 166A- Asst Principal	3	EA	7	\$0	
	Power Distribution	1st- Rm 166A- Asst Principal	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	1st- Rm 166A- Asst Principal	738	SF	6	\$2,037	
	Ceiling - Lay-in	1st- Rm 166B- Conference Room	220	SF	6	\$661	
	Doors - Wood Doors inclu hw	1st- Rm 166B- Conference Room	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 166B- Conference Room	220	SF	6	\$469	
	Lighting - Lay-in	1st- Rm 166B- Conference Room	5	EA	7	\$0	
	Power Distribution	1st- Rm 166B- Conference Room	10	EA	6	\$21,249	
	Walls - Concrete Block	1st- Rm 166B- Conference Room	482	SF	6	\$1,413	
	Walls - Plaster/Drywall	1st- Rm 166B- Conference Room	428	SF	6	\$1,181	
	Ceiling - Lay-in	1st- Rm 166C- Buisness Manager	97	SF	6	\$291	
	Doors - Side-lite	1st- Rm 166C- Buisness Manager	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	1st- Rm 166C- Buisness Manager	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 166C- Buisness Manager	97	SF	6	\$207	
	Lighting - Lay-in	1st- Rm 166C- Buisness Manager	2	EA	7	\$0	
	Power Distribution	1st- Rm 166C- Buisness Manager	8	EA	6	\$16,999	
	Walls - Metal Panel	1st- Rm 166C- Buisness Manager	365	SF	6	\$2,725	
	Walls - Plaster/Drywall	1st- Rm 166C- Buisness Manager	122	SF	6	\$337	
	Ceiling - Lay-in	1st- Rm 166D- Payroll	97	SF	6	\$291	
	Doors - Side-lite	1st- Rm 166D- Payroll	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	1st- Rm 166D- Payroll	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 166D- Payroll	97	SF	6	\$207	
	Lighting - Lay-in	1st- Rm 166D- Payroll	2	EA	7	\$0	
	Power Distribution	1st- Rm 166D- Payroll	8	EA	6	\$16,999	
	Walls - Concrete Block	1st- Rm 166D- Payroll	122	SF	6	\$358	
	Walls - Metal Panel	1st- Rm 166D- Payroll	244	SF	6	\$1,821	
	Walls - Plaster/Drywall	1st- Rm 166D- Payroll	122	SF	6	\$337	
	Ceiling - Lay-in	1st- Rm 168- Principal	387	SF	6	\$1,162	
	Doors - Wood Doors inclu hw	1st- Rm 168- Principal	2	EA	6	\$602	
	Floor - Carpet	1st- Rm 168- Principal	387	SF	6	\$825	
	Lighting - Lay-in	1st- Rm 168- Principal	8	EA	7	\$0	
	Power Distribution	1st- Rm 168- Principal	12	EA	6	\$25,499	
	Walls - Concrete Block	1st- Rm 168- Principal	329	SF	6	\$964	
	Walls - Metal Panel	1st- Rm 168- Principal	658	SF	6	\$4,912	

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st- Rm 171- Attendance Office	393	SF	6	\$1,180	
	Doors - Wood Doors inclu hw	1st- Rm 171- Attendance Office	1	EA	6	\$301	
	Floor - Tile	1st- Rm 171- Attendance Office	383	SF	6	\$838	
	Floor - Tile	1st- Rm 171- Attendance Office	10	SF	5	\$58	damaged
	Lighting - Lay-in	1st- Rm 171- Attendance Office	7	EA	7	\$0	
	Power Distribution	1st- Rm 171- Attendance Office	10	EA	6	\$21,249	
	Walls - Metal Panel	1st- Rm 171- Attendance Office	988	SF	6	\$7,375	
	Work Slnk	1st- Rm 171- Attendance Office	1	EA	6	\$508	
	Ceiling - Lay-in	1st- Rm 180E- English Office	145	SF	6	\$435	
	Doors - Side-lite	1st- Rm 180E- English Office	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	1st- Rm 180E- English Office	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 180E- English Office	145	SF	6	\$309	
	Lighting - Lay-in	1st- Rm 180E- English Office	3	EA	7	\$0	
	Power Distribution	1st- Rm 180E- English Office	6	EA	6	\$12,749	
	Walls - Metal Panel	1st- Rm 180E- English Office	562	SF	6	\$4,195	
	Ceiling - Lay-in	1st- Rm 180F- Drama Office	126	SF	6	\$378	
	Doors - Side-lite	1st- Rm 180F- Drama Office	22	SF	6	\$368	
	Doors - Wood Doors inclu hw	1st- Rm 180F- Drama Office	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 180F- Drama Office	126	SF	6	\$268	
	Lighting - Lay-in	1st- Rm 180F- Drama Office	2	EA	7	\$0	
	Power Distribution	1st- Rm 180F- Drama Office	6	EA	6	\$12,749	
	Walls - Concrete Block	1st- Rm 180F- Drama Office	140	SF	6	\$410	
	Walls - Metal Panel	1st- Rm 180F- Drama Office	422	SF	6	\$3,150	
	Ceiling - Lay-in	1st- Rm 186- Video Tape Room	292	SF	6	\$877	
	Doors - Wood Doors inclu hw	1st- Rm 186- Video Tape Room	1	EA	6	\$301	
	Floor - Tile	1st- Rm 186- Video Tape Room	292	SF	6	\$639	
	Lighting - Lay-in	1st- Rm 186- Video Tape Room	8	EA	7	\$0	
	Power Distribution	1st- Rm 186- Video Tape Room	8	EA	6	\$16,999	
	Walls - Concrete Block	1st- Rm 186- Video Tape Room	480	SF	6	\$1,407	
	Ceiling - Lay-in	2nd - 249 Computer Tech Office	880	SF	6	\$2,643	
	Doors - Wood Doors inclu hw	2nd - 249 Computer Tech Office	1	EA	6	\$301	
	Floor - Tile	2nd - 249 Computer Tech Office	880	SF	6	\$1,925	
	Lighting - Lay-in	2nd - 249 Computer Tech Office	18	EA	7	\$0	
	Power Distribution	2nd - 249 Computer Tech Office	16	EA	6	\$33,998	
	Storage/ Closet	2nd - 249 Computer Tech Office	22	SF	6	\$160	
	Walls - Metal Panel	2nd - 249 Computer Tech Office	828	SF	6	\$6,181	
	Ceiling - Lay-in	2nd - 256 Deans	495	SF	6	\$1,486	

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Wood Doors inclu hw	2nd - 256 Deans	1	EA	6	\$301	
	Floor - Tile	2nd - 256 Deans	495	SF	6	\$1,083	
	Lighting - Pendent/Surface	2nd - 256 Deans	10	EA	7	\$0	
	Power Distribution	2nd - 256 Deans	36	EA	7	\$0	
	Storage/ Closet	2nd - 256 Deans	12	SF	6	\$87	
	Walls - Concrete Block	2nd - 256 Deans	147	SF	6	\$431	
	Walls - Metal Panel	2nd - 256 Deans	742	SF	6	\$5,539	
	Ceiling - Lay-in	2nd - 256A inside 256	177	SF	6	\$532	
	Doors - Wood Doors inclu hw	2nd - 256A inside 256	1	EA	6	\$301	
	Floor - Tile	2nd - 256A inside 256	177	SF	6	\$387	
	Lighting - Pendent/Surface	2nd - 256A inside 256	3	EA	7	\$0	
	Power Distribution	2nd - 256A inside 256	6	EA	6	\$12,749	
	Walls - Metal Panel	2nd - 256A inside 256	535	SF	6	\$3,994	
	Ceiling - Lay-in	2nd - 256B inside 256	244	SF	6	\$733	
	Doors - Wood Doors inclu hw	2nd - 256B inside 256	1	EA	6	\$301	
	Floor - Tile	2nd - 256B inside 256	244	SF	6	\$534	
	Lighting - Pendent/Surface	2nd - 256B inside 256	3	EA	7	\$0	
	Power Distribution	2nd - 256B inside 256	8	EA	6	\$16,999	
	Walls - Metal Panel	2nd - 256B inside 256	532	SF	6	\$3,971	
	Ceiling - Lay-in	2nd - 256C Office	207	SF	6	\$622	
	Doors - Wood Doors inclu hw	2nd - 256C Office	2	EA	6	\$602	
	Floor - Tile	2nd - 256C Office	207	SF	6	\$453	
	Lighting - Pendent/Surface	2nd - 256C Office	4	EA	7	\$0	
	Power Distribution	2nd - 256C Office	4	EA	6	\$8,500	
	Walls - Metal Panel	2nd - 256C Office	207	SF	6	\$1,874	glass window wall
	Walls - Metal Panel	2nd - 256C Office	407	SF	6	\$3,038	
	Ceiling - Lay-in	2nd - 263 Reading Room	365	SF	6	\$1,096	
	Doors - Side-lite	2nd - 263 Reading Room	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd - 263 Reading Room	1	EA	6	\$301	
	Floor - Tile	2nd - 263 Reading Room	365	SF	6	\$799	
	Lighting - Pendent/Surface	2nd - 263 Reading Room	5	EA	7	\$0	
	Power Distribution	2nd - 263 Reading Room	10	EA	6	\$21,249	
	Walls - Concrete Block	2nd - 263 Reading Room	100	SF	6	\$293	
	Walls - Metal Panel	2nd - 263 Reading Room	705	SF	6	\$5,263	
	Work Sink	2nd - 263 Reading Room	1	EA	6	\$508	
	Ceiling - Lay-in	2nd - 264 Office	357	SF	6	\$1,072	
	Doors - Wood Doors inclu hw	2nd - 264 Office	1	EA	6	\$301	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Tile	2nd - 264 Office	357	SF	6	\$781	
	Lighting - Pendant/Surface	2nd - 264 Office	11	EA	7	\$0	
	Power Distribution	2nd - 264 Office	6	EA	6	\$12,749	
	Walls - Concrete Block	2nd - 264 Office	263	SF	6	\$771	
	Walls - Metal Panel	2nd - 264 Office	555	SF	6	\$4,143	
	Ceiling - Lay-in	2nd - 270 Counselor Area	1,192	SF	6	\$3,580	
	Doors - Side-lite	2nd - 270 Counselor Area	72	SF	6	\$1,204	
	Doors - Wood Doors inclu hw	2nd - 270 Counselor Area	3	EA	6	\$903	
	Floor - Tile	2nd - 270 Counselor Area	1,192	SF	6	\$2,608	
	Lighting - Pendant/Surface	2nd - 270 Counselor Area	26	EA	7	\$0	
	Power Distribution	2nd - 270 Counselor Area	18	EA	6	\$38,248	
	Walls - Concrete Block	2nd - 270 Counselor Area	165	SF	6	\$484	
	Walls - Metal Panel	2nd - 270 Counselor Area	1,655	SF	6	\$12,354	
	Ceiling - Lay-in	2nd - 270A inside 270	128	SF	6	\$384	
	Doors - Side-lite	2nd - 270A inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270A inside 270	1	EA	6	\$301	
	Floor - Tile	2nd - 270A inside 270	128	SF	6	\$280	
	Lighting - Pendant/Surface	2nd - 270A inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270A inside 270	2	EA	6	\$4,250	
	Walls - Metal Panel	2nd - 270A inside 270	230	SF	6	\$1,717	
	Walls - Plaster/Drywall	2nd - 270A inside 270	160	SF	6	\$442	
	Ceiling - Lay-in	2nd - 270B inside 270	119	SF	6	\$357	
	Doors - Side-lite	2nd - 270B inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270B inside 270	1	EA	6	\$301	
	Floor - Tile	2nd - 270B inside 270	119	SF	6	\$260	
	Lighting - Pendant/Surface	2nd - 270B inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270B inside 270	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	2nd - 270B inside 270	442	SF	6	\$1,220	
	Ceiling - Lay-in	2nd - 270C inside 270	118	SF	6	\$354	
	Doors - Side-lite	2nd - 270C inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270C inside 270	1	EA	6	\$301	
	Floor - Tile	2nd - 270C inside 270	118	SF	6	\$258	
	Lighting - Pendant/Surface	2nd - 270C inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270C inside 270	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	2nd - 270C inside 270	453	SF	6	\$1,250	
	Ceiling - Lay-in	2nd - 270D inside 270	95	SF	6	\$285	
	Doors - Side-lite	2nd - 270D inside 270	18	SF	6	\$301	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Wood Doors inclu hw	2nd - 270D inside 270	1	EA	6	\$301	
	Floor - Carpet	2nd - 270D inside 270	95	SF	6	\$202	
	Lighting - Pendent/Surface	2nd - 270D inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270D inside 270	4	EA	6	\$8,500	
	Walls - Metal Panel	2nd - 270D inside 270	400	SF	6	\$2,986	
	Ceiling - Lay-in	2nd - 270E inside 270	96	SF	6	\$288	
	Doors - Side-lite	2nd - 270E inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270E inside 270	2	EA	6	\$602	
	Floor - Carpet	2nd - 270E inside 270	96	SF	6	\$205	
	Lighting - Pendent/Surface	2nd - 270E inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270E inside 270	6	EA	6	\$12,749	
	Walls - Metal Panel	2nd - 270E inside 270	400	SF	6	\$2,986	
	Ceiling - Lay-in	2nd - 270F inside 270	94	SF	6	\$282	
	Doors - Side-lite	2nd - 270F inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270F inside 270	1	EA	6	\$301	
	Floor - Carpet	2nd - 270F inside 270	94	SF	6	\$200	
	Lighting - Pendent/Surface	2nd - 270F inside 270	2	EA	6	\$248	
	Power Distribution	2nd - 270F inside 270	2	EA	6	\$4,250	
	Walls - Metal Panel	2nd - 270F inside 270	393	SF	6	\$2,934	
	Ceiling - Lay-in	2nd - 270G inside 270	99	SF	6	\$297	
	Doors - Side-lite	2nd - 270G inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270G inside 270	1	EA	6	\$301	
	Floor - Carpet	2nd - 270G inside 270	99	SF	6	\$211	
	Lighting - Pendent/Surface	2nd - 270G inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270G inside 270	4	EA	6	\$8,500	
	Walls - Concrete Block	2nd - 270G inside 270	100	SF	6	\$293	
	Walls - Metal Panel	2nd - 270G inside 270	300	SF	6	\$2,239	
	Ceiling - Lay-in	2nd - 270H inside 270	97	SF	6	\$291	
	Doors - Side-lite	2nd - 270H inside 270	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 270H inside 270	1	EA	6	\$301	
	Floor - Carpet	2nd - 270H inside 270	97	SF	6	\$207	
	Lighting - Pendent/Surface	2nd - 270H inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270H inside 270	4	EA	6	\$8,500	
	Walls - Concrete Block	2nd - 270H inside 270	100	SF	6	\$293	
	Walls - Metal Panel	2nd - 270H inside 270	300	SF	6	\$2,239	
	Ceiling - Lay-in	2nd - 270J inside 270	95	SF	6	\$285	
	Doors - Wood Doors inclu hw	2nd - 270J inside 270	1	EA	6	\$301	

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Carpet	2nd - 270J inside 270	95	SF	6	\$202	
	Lighting - Pendent/Surface	2nd - 270J inside 270	2	EA	7	\$0	
	Power Distribution	2nd - 270J inside 270	4	EA	6	\$8,500	
	Walls - Metal Panel	2nd - 270J inside 270	400	SF	6	\$2,986	
	Ceiling - Lay-in	2nd - 270K/L inside 215	190	SF	6	\$571	
	Doors - Side-lite	2nd - 270K/L inside 215	36	SF	6	\$602	
	Doors - Wood Doors inclu hw	2nd - 270K/L inside 215	2	EA	6	\$602	
	Floor - Tile	2nd - 270K/L inside 215	190	SF	6	\$416	
	Lighting - Pendent/Surface	2nd - 270K/L inside 215	4	EA	7	\$0	
	Power Distribution	2nd - 270K/L inside 215	10	EA	6	\$21,249	
	Walls - Concrete Block	2nd - 270K/L inside 215	193	SF	6	\$566	
	Walls - Metal Panel	2nd - 270K/L inside 215	393	SF	6	\$2,934	
	Ceiling - Lay-in	2nd - 271A Faculty Lounge	880	SF	6	\$2,643	
	Doors - Wood Doors inclu hw	2nd - 271A Faculty Lounge	2	EA	6	\$602	
	Floor - Tile	2nd - 271A Faculty Lounge	880	SF	6	\$1,925	
	Lighting - Pendent/Surface	2nd - 271A Faculty Lounge	18	EA	7	\$0	
	Power Distribution	2nd - 271A Faculty Lounge	36	EA	7	\$0	
	Walls - Concrete Block	2nd - 271A Faculty Lounge	287	SF	6	\$841	
	Walls - Metal Panel	2nd - 271A Faculty Lounge	597	SF	6	\$4,456	
	Ceiling - Lay-in	2nd - 271B Computer Lounge	565	SF	6	\$1,697	
	Floor - Tile	2nd - 271B Computer Lounge	565	SF	6	\$1,236	
	Lighting - Pendent/Surface	2nd - 271B Computer Lounge	9	EA	7	\$0	
	Power Distribution	2nd - 271B Computer Lounge	24	EA	6	\$50,997	
	Walls - Concrete Block	2nd - 271B Computer Lounge	274	SF	6	\$803	
	Walls - Metal Panel	2nd - 271B Computer Lounge	484	SF	6	\$3,613	
	Ceiling - Lay-in	2nd - 272 Office inside 271	95	SF	6	\$285	
	Doors - Side-lite	2nd - 272 Office inside 271	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 272 Office inside 271	1	EA	6	\$301	
	Floor - Carpet	2nd - 272 Office inside 271	95	SF	6	\$202	
	Lighting	2nd - 272 Office inside 271	2		6	\$0	
	Power Distribution	2nd - 272 Office inside 271	6	EA	6	\$12,749	
	Walls - Metal Panel	2nd - 272 Office inside 271	396	SF	6	\$2,956	
	Ceiling - Lay-in	2nd - 273 Office inside 271	95	SF	6	\$285	
	Doors - Side-lite	2nd - 273 Office inside 271	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 273 Office inside 271	1	EA	6	\$301	
	Floor - Carpet	2nd - 273 Office inside 271	95	SF	6	\$202	
	Lighting - Pendent/Surface	2nd - 273 Office inside 271	2	EA	7	\$0	

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	2nd - 273 Office inside 271	6	EA	6	\$12,749	
	Walls - Metal Panel	2nd - 273 Office inside 271	395	SF	6	\$2,949	
	Ceiling - Lay-in	2nd - 274 Office inside 271	95	SF	6	\$285	
	Doors - Side-lite	2nd - 274 Office inside 271	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 274 Office inside 271	1	EA	6	\$301	
	Floor - Carpet	2nd - 274 Office inside 271	95	SF	6	\$202	
	Lighting - Pendent/Surface	2nd - 274 Office inside 271	2	EA	7	\$0	
	Power Distribution	2nd - 274 Office inside 271	6	EA	6	\$12,749	
	Walls - Metal Panel	2nd - 274 Office inside 271	396	SF	6	\$2,956	
	Ceiling - Lay-in	2nd - 275 Office inside 271	95	SF	6	\$285	
	Doors - Side-lite	2nd - 275 Office inside 271	18	SF	6	\$301	
	Doors - Wood Doors inclu hw	2nd - 275 Office inside 271	1	EA	6	\$301	
	Floor - Carpet	2nd - 275 Office inside 271	95	SF	6	\$202	
	Lighting - Pendent/Surface	2nd - 275 Office inside 271	2	EA	7	\$0	
	Power Distribution	2nd - 275 Office inside 271	6	EA	6	\$12,749	
	Walls - Metal Panel	2nd - 275 Office inside 271	394	SF	6	\$2,941	
	Ceiling - Splined	2nd - Office inside Kitchen	110	SF	6	\$90	
	Doors - Side-lite	2nd - Office inside Kitchen	100	SF	6	\$1,672	
	Doors - Wood Doors inclu hw	2nd - Office inside Kitchen	1	EA	6	\$301	
	Floor - Tile	2nd - Office inside Kitchen	110	SF	6	\$241	
	Lighting - Lay-in	2nd - Office inside Kitchen	2	EA	7	\$0	
	Power Distribution	2nd - Office inside Kitchen	6	EA	6	\$12,749	
	Walls - Concrete Block	2nd - Office inside Kitchen	323	SF	6	\$947	
Kitchen							
	Ceiling - Splined	2nd - Inside 215 Dining	3,063	SF	5	\$21,813	dirty / bad condition / stains
	Doors - Wood Doors inclu hw	2nd - Inside 215 Dining	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	2nd - Inside 215 Dining	3,063	SF	5	\$5,256	dirty / bad condition
	Lighting - Lay-in	2nd - Inside 215 Dining	55	EA	7	\$0	
	Lighting - Pendent/Surface	2nd - Inside 215 Dining	1	EA	5	\$183	old light next to elevator used for hanging car scents
	Lighting - Pendent/Surface	2nd - Inside 215 Dining	7	EA	7	\$0	
	Storage/ Closet	2nd - Inside 215 Dining	975	SF	6	\$7,069	390 sq.ft. coolers
	Storage/ Closet	2nd - Inside 215 Dining	21	SF	5	\$339	Janitors - bad condition / smells bad
	Walls - Concrete Block	2nd - Inside 215 Dining	3,887	SF	6	\$11,395	
Library							
	Casework	1st Floor	159	LF	6	\$4,015	
	Ceiling - Lay-in	1st Floor	6,288	SF	6	\$18,883	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Library							
	Doors - Side-lite	1st Floor	125	SF	6	\$2,090	
	Doors - Store Front	1st Floor	3	EA	6	\$3,625	
	Doors - Transom Window	1st Floor	155	SF	6	\$2,624	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Carpet	1st Floor	6,288	SF	6	\$13,398	
	Lighting - Pendent/Surface	1st Floor	126	EA	7	\$0	
	Walls - Concrete Block	1st Floor	490	SF	6	\$1,436	
	Walls - Concrete Block	1st Floor	1	SF	5	\$14	NO OCCUPANCY PLACARD POSTED
	Walls - Metal Panel	1st Floor	3,451	SF	6	\$25,760	
Lunch & Multipurpose Room							
	Ceiling - Plaster/Drywall	1st- Rm 166E- Main Office Break Room	239	SF	6	\$827	
	Doors - Wood Doors inclu hw	1st- Rm 166E- Main Office Break Room	1	EA	6	\$301	
	Floor - Tile	1st- Rm 166E- Main Office Break Room	231	SF	6	\$505	
	Floor - Tile	1st- Rm 166E- Main Office Break Room	8	SF	5	\$46	cracked
	Lighting - Lay-in	1st- Rm 166E- Main Office Break Room	2	EA	7	\$0	cans
	Lighting - Pendent/Surface	1st- Rm 166E- Main Office Break Room	4	EA	7	\$0	
	Walls - Concrete Block	1st- Rm 166E- Main Office Break Room	496	SF	6	\$1,454	
	Ceiling - Lay-in	1st- Rm 190- All Purpose Room	1,895	SF	6	\$5,691	
	Doors - Side-lite	1st- Rm 190- All Purpose Room	39	SF	6	\$652	
	Doors - Store Front	1st- Rm 190- All Purpose Room	2	EA	6	\$2,416	
	Doors - Transom Window	1st- Rm 190- All Purpose Room	49	SF	6	\$830	
	Doors - Wood Doors inclu hw	1st- Rm 190- All Purpose Room	1	EA	6	\$301	
	Floor - Carpet	1st- Rm 190- All Purpose Room	1,895	SF	6	\$4,038	
	Lighting - Pendent/Surface	1st- Rm 190- All Purpose Room	37	EA	7	\$0	
	Market Board	1st- Rm 190- All Purpose Room	10	LF	7	\$0	
	Walls - Concrete Block	1st- Rm 190- All Purpose Room	213	SF	6	\$624	
	Walls - Plaster/Drywall	1st- Rm 190- All Purpose Room	768	SF	6	\$2,120	
	Ceiling - Lay-in	2nd - 215 Student Dining	14,903	SF	6	\$44,754	
	Doors - Side-lite	2nd - 215 Student Dining	360	SF	6	\$6,018	
	Doors - Store Front	2nd - 215 Student Dining	4	EA	6	\$4,833	
	Doors - Transom Window	2nd - 215 Student Dining	32	SF	6	\$542	
	Doors - Wood Doors inclu hw	2nd - 215 Student Dining	8	EA	6	\$2,408	
	Floor - Tile	2nd - 215 Student Dining	14,903	SF	6	\$32,606	
	Lighting - Lay-in	2nd - 215 Student Dining	194	EA	7	\$0	
	Serving Line	2nd - 215 Student Dining	20	LF	6	\$1,190	pass thru openings
	Student Lockers - One Tier	2nd - 215 Student Dining	19	EA	6	\$1,764	
	Walls - Concrete Block	2nd - 215 Student Dining	3,990	SF	6	\$11,697	

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Ceiling - Lay-in	2nd - 215A Box Office	554	SF	5	\$3,296	old / stained / bad condition / tiles missing
	Doors - Wood Doors inclu hw	2nd - 215A Box Office	2	EA	6	\$602	
	Floor - Tile	2nd - 215A Box Office	554	SF	6	\$1,212	
	Lighting - Pendent/Surface	2nd - 215A Box Office	11	EA	7	\$0	
	Storage/ Closet	2nd - 215A Box Office	243	SF	6	\$1,762	
	Walls - Concrete Block	2nd - 215A Box Office	80	SF	6	\$235	
	Walls - Metal Panel	2nd - 215A Box Office	482	SF	6	\$3,598	glass window walls
	Walls - Plaster/Drywall	2nd - 215A Box Office	588	SF	6	\$1,623	
	Ceiling - Lay-in	2nd - 271 Faculty Dining	2,130	SF	6	\$6,396	
	Doors - Wood Doors inclu hw	2nd - 271 Faculty Dining	2	EA	6	\$602	
	Floor - Tile	2nd - 271 Faculty Dining	2,130	SF	6	\$4,660	
	Lighting - Pendent/Surface	2nd - 271 Faculty Dining	36	EA	7	\$0	
	Walls - Concrete Block	2nd - 271 Faculty Dining	1,520	SF	6	\$4,456	
	Walls - Metal Panel	2nd - 271 Faculty Dining	980	SF	6	\$7,315	
	Ceiling - Splined	2nd - Servery Room 1 inside 215	986	SF	5	\$7,022	dirty / bad condition
	Doors - Wood Doors inclu hw	2nd - Servery Room 1 inside 215	3	EA	6	\$903	
	Floor - Concrete Epoxy/ Painted	2nd - Servery Room 1 inside 215	986	SF	5	\$1,692	dirty / bad condition
	Lighting - Lay-in	2nd - Servery Room 1 inside 215	18	EA	7	\$0	
	Serving Line	2nd - Servery Room 1 inside 215	72	LF	6	\$4,285	
	Walls - Concrete Block	2nd - Servery Room 1 inside 215	989	SF	6	\$2,899	
	Ceiling - Splined	2nd - Servery Room 2 inside 215	458	SF	5	\$3,262	old / stains / bad condition
	Doors - Wood Doors inclu hw	2nd - Servery Room 2 inside 215	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	2nd - Servery Room 2 inside 215	458	SF	6	\$242	
	Lighting - Lay-in	2nd - Servery Room 2 inside 215	11	EA	7	\$0	
	Serving Line	2nd - Servery Room 2 inside 215	35	LF	6	\$2,083	
	Walls - Concrete Block	2nd - Servery Room 2 inside 215	1,010	SF	6	\$2,961	
MDF_IDF							
	Doors - Wood Doors inclu hw	2nd - 249A MDF	2	EA	6	\$602	
	Finishes	2nd - 249A MDF	1,564	SF	6	\$11,160	449 sq.ft. lay-in ceiling / 449 sq.ft. tile / 666 sq.ft. metal panels
	Ventilation and Cooling	2nd - 249A MDF	1	EA	6	\$1,855	cool temp in room
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	63	SF	6	\$451	
	Mechanical/ Service Rooms	1st Floor	243	SF	6	\$1,741	
	Storage Room	1st Floor	575	SF	6	\$4,119	
	Vaults	1st Floor	131	SF	6	\$939	in Main Office
	Janitor's Closet	2nd Floor	76	SF	6	\$544	inside 215 / faculty 271

Building: Addition 2
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	2nd Floor	357	SF	6	\$2,558	electrical room inside 215 next to elevator / compressor room inside 215 / mech rm next to women by link
	Storage Room	2nd Floor	67	SF	6	\$480	251 Bookroom with a sink
Prep Room							
	Ceiling - Exposed	1st- Practice Booth in hall by 172	68	SF	6	\$101	
	Doors - Side-lite	1st- Practice Booth in hall by 172	16	SF	6	\$267	
	Doors - Store Front	1st- Practice Booth in hall by 172	1	EA	6	\$1,208	
	Floor - Carpet	1st- Practice Booth in hall by 172	68	SF	6	\$145	
	Lighting - Pendent/Surface	1st- Practice Booth in hall by 172	2	EA	7	\$0	
	Walls - Metal Panel	1st- Practice Booth in hall by 172	231	SF	6	\$1,724	
Restroom							
	Accessories	1st- Inside Rm 166B	21	SF	6	\$194	
	Ceiling - Plaster/Drywall	1st- Inside Rm 166B	21	SF	6	\$73	
	Doors - Wood Doors inclu hw	1st- Inside Rm 166B	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st- Inside Rm 166B	21	SF	6	\$44	
	Lavatory	1st- Inside Rm 166B	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st- Inside Rm 166B	1	EA	7	\$0	
	Lighting - Wall Mounted	1st- Inside Rm 166B	1	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	1st- Inside Rm 166B	148	SF	6	\$334	
	Water Closet	1st- Inside Rm 166B	1	EA	6	\$336	
	Accessories	1st- Men (near link)	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	1st- Men (near link)	182	SF	6	\$630	
	Ceiling - Plaster/Drywall	1st- Men (near link)	2	SF	5	\$25	water damage
	Floor Drain	1st- Men (near link)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Men (near link)	184	SF	6	\$389	
	Hand Dryer	1st- Men (near link)	1	EA	6	\$230	
	Lavatory	1st- Men (near link)	2	EA	6	\$639	
	Lighting - Lay-in	1st- Men (near link)	5	EA	7	\$0	
	Partitions	1st- Men (near link)	2	EA	6	\$594	
	Urinals	1st- Men (near link)	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	1st- Men (near link)	435	SF	6	\$983	
	Walls - Tile Ceramic/ Porcelain	1st- Men (near link)	1	SF	5	\$21	damaged tiles
	Water Closet	1st- Men (near link)	2	EA	6	\$672	
	Accessories	1st- Men (near Main Office)	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	1st- Men (near Main Office)	184	SF	6	\$637	
	Doors - Wood Doors inclu hw	1st- Men (near Main Office)	1	EA	6	\$301	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	1st- Men (near Main Office)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Men (near Main Office)	184	SF	6	\$389	
	Hand Dryer	1st- Men (near Main Office)	1	EA	6	\$230	
	Lavatory	1st- Men (near Main Office)	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st- Men (near Main Office)	4	EA	7	\$0	
	Partitions	1st- Men (near Main Office)	1	EA	6	\$297	
	Urinals	1st- Men (near Main Office)	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	1st- Men (near Main Office)	436	SF	6	\$985	
	Water Closet	1st- Men (near Main Office)	1	EA	6	\$336	
	Accessories	1st- Men (near Rm 172)	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	1st- Men (near Rm 172)	180	SF	6	\$623	
	Ceiling - Plaster/Drywall	1st- Men (near Rm 172)	4	SF	5	\$50	water damage
	Doors - Steel Doors incl hw	1st- Men (near Rm 172)	1	EA	6	\$301	
	Floor Drain	1st- Men (near Rm 172)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Men (near Rm 172)	184	SF	6	\$389	
	Hand Dryer	1st- Men (near Rm 172)	1	EA	6	\$230	
	Lavatory	1st- Men (near Rm 172)	2	EA	6	\$639	
	Lighting - Lay-in	1st- Men (near Rm 172)	5	EA	7	\$0	
	Partitions	1st- Men (near Rm 172)	2	EA	6	\$594	
	Urinals	1st- Men (near Rm 172)	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	1st- Men (near Rm 172)	435	SF	6	\$983	
	Water Closet	1st- Men (near Rm 172)	2	EA	6	\$672	
	Accessories	1st- Men (near Rm 185)	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	1st- Men (near Rm 185)	174	SF	6	\$602	
	Ceiling - Plaster/Drywall	1st- Men (near Rm 185)	10	SF	5	\$125	active leak in ceiling, dripping water from above
	Doors - Wood Doors inclu hw	1st- Men (near Rm 185)	1	EA	6	\$301	
	Floor Drain	1st- Men (near Rm 185)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Men (near Rm 185)	184	SF	6	\$389	
	Hand Dryer	1st- Men (near Rm 185)	1	EA	6	\$230	
	Lavatory	1st- Men (near Rm 185)	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st- Men (near Rm 185)	5	EA	7	\$0	
	Partitions	1st- Men (near Rm 185)	1	EA	6	\$297	
	Urinals	1st- Men (near Rm 185)	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	1st- Men (near Rm 185)	435	SF	6	\$983	
	Walls - Tile Ceramic/ Porcelain	1st- Men (near Rm 185)	1	SF	5	\$21	damaged tile
	Water Closet	1st- Men (near Rm 185)	1	EA	6	\$336	
	Accessories	1st- Women (near 176)	188	SF	6	\$1,734	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	1st- Women (near 176)	188	SF	6	\$651	
	Doors - Steel Doors incl hw	1st- Women (near 176)	1	EA	6	\$301	
	Floor Drain	1st- Women (near 176)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Women (near 176)	188	SF	6	\$398	
	Hand Dryer	1st- Women (near 176)	1	EA	6	\$230	
	Lavatory	1st- Women (near 176)	2	EA	6	\$639	
	Lighting - Lay-in	1st- Women (near 176)	5	EA	7	\$0	
	Partitions	1st- Women (near 176)	3	EA	6	\$891	
	Walls - Tile Ceramic/ Porcelain	1st- Women (near 176)	436	SF	6	\$985	
	Water Closet	1st- Women (near 176)	4	EA	6	\$1,344	
	Accessories	1st- Women (near link)	188	SF	6	\$1,734	
	Ceiling - Plaster/Drywall	1st- Women (near link)	188	SF	6	\$651	
	Floor Drain	1st- Women (near link)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Women (near link)	188	SF	6	\$398	
	Hand Dryer	1st- Women (near link)	1	EA	6	\$230	
	Lavatory	1st- Women (near link)	2	EA	6	\$639	
	Lighting - Lay-in	1st- Women (near link)	5	EA	7	\$0	
	Partitions	1st- Women (near link)	4	EA	6	\$1,188	
	Walls - Tile Ceramic/ Porcelain	1st- Women (near link)	436	SF	6	\$985	
	Water Closet	1st- Women (near link)	5	EA	6	\$1,680	
	Accessories	1st- Women (near Main Office)	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	1st- Women (near Main Office)	184	SF	6	\$637	
	Doors - Wood Doors inclu hw	1st- Women (near Main Office)	1	EA	6	\$301	
	Floor Drain	1st- Women (near Main Office)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Women (near Main Office)	184	SF	6	\$389	
	Hand Dryer	1st- Women (near Main Office)	1	EA	6	\$230	
	Lavatory	1st- Women (near Main Office)	2	EA	6	\$639	
	Lighting - Pendant/Surface	1st- Women (near Main Office)	5	EA	7	\$0	
	Partitions	1st- Women (near Main Office)	4	EA	6	\$1,188	
	Walls - Tile Ceramic/ Porcelain	1st- Women (near Main Office)	436	SF	6	\$985	
	Water Closet	1st- Women (near Main Office)	5	EA	6	\$1,680	
	Accessories	1st- Women (near Rm 185)	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	1st- Women (near Rm 185)	184	SF	6	\$637	
	Doors - Wood Doors inclu hw	1st- Women (near Rm 185)	1	EA	6	\$301	
	Floor Drain	1st- Women (near Rm 185)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st- Women (near Rm 185)	184	SF	6	\$389	
	Hand Dryer	1st- Women (near Rm 185)	1	EA	6	\$230	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	1st- Women (near Rm 185)	1	EA	5	\$1,590	damaged glazing
	Lavatory	1st- Women (near Rm 185)	1	EA	6	\$320	
	Lighting - Pendant/Surface	1st- Women (near Rm 185)	5	EA	7	\$0	
	Partitions	1st- Women (near Rm 185)	3	EA	6	\$891	
	Walls - Tile Ceramic/ Porcelain	1st- Women (near Rm 185)	436	SF	6	\$985	
	Water Closet	1st- Women (near Rm 185)	4	EA	6	\$1,344	
	Accessories	2nd - Men inside 271 Faculty	161	SF	6	\$1,485	
	Ceiling - Plaster/Drywall	2nd - Men inside 271 Faculty	161	SF	6	\$557	
	Doors - Wood Doors inclu hw	2nd - Men inside 271 Faculty	1	EA	6	\$301	
	Floor Drain	2nd - Men inside 271 Faculty	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Men inside 271 Faculty	161	SF	6	\$341	
	Hand Dryer	2nd - Men inside 271 Faculty	1	EA	6	\$230	
	Lavatory	2nd - Men inside 271 Faculty	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Men inside 271 Faculty	4	EA	7	\$0	
	Partitions	2nd - Men inside 271 Faculty	1	EA	6	\$297	
	Urinals	2nd - Men inside 271 Faculty	2	EA	6	\$672	
	Walls - Tile Ceramic/ Porcelain	2nd - Men inside 271 Faculty	454	SF	6	\$1,026	
	Water Closet	2nd - Men inside 271 Faculty	1	EA	6	\$336	
	Accessories	2nd - Men next to link to addition 1	182	SF	6	\$1,679	
	Ceiling - Plaster/Drywall	2nd - Men next to link to addition 1	182	SF	6	\$630	
	Doors - Wood Doors inclu hw	2nd - Men next to link to addition 1	1	EA	6	\$301	
	Floor Drain	2nd - Men next to link to addition 1	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Men next to link to addition 1	182	SF	6	\$385	
	Hand Dryer	2nd - Men next to link to addition 1	1	EA	6	\$230	
	Lavatory	2nd - Men next to link to addition 1	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Men next to link to addition 1	5	EA	7	\$0	
	Partitions	2nd - Men next to link to addition 1	1	EA	6	\$297	granite slab
	Urinals	2nd - Men next to link to addition 1	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	2nd - Men next to link to addition 1	509	SF	6	\$1,150	
	Water Closet	2nd - Men next to link to addition 1	1	EA	6	\$336	
	Accessories	2nd - Mens across from 264	134	SF	6	\$1,236	
	Ceiling - Plaster/Drywall	2nd - Mens across from 264	124	SF	6	\$429	
	Ceiling - Plaster/Drywall	2nd - Mens across from 264	10	SF	5	\$125	stains / peeling
	Doors - Wood Doors inclu hw	2nd - Mens across from 264	1	EA	6	\$301	
	Floor Drain	2nd - Mens across from 264	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Mens across from 264	134	SF	6	\$284	
	Hand Dryer	2nd - Mens across from 264	1	EA	6	\$230	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	2nd - Mens across from 264	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Mens across from 264	4	EA	7	\$0	
	Partitions	2nd - Mens across from 264	1	EA	6	\$297	
	Urinals	2nd - Mens across from 264	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	2nd - Mens across from 264	504	SF	7	\$0	
	Water Closet	2nd - Mens across from 264	1	EA	6	\$336	
	Accessories	2nd - Mens inside 215	198	SF	6	\$1,826	
	Ceiling - Plaster/Drywall	2nd - Mens inside 215	198	SF	6	\$685	
	Floor Drain	2nd - Mens inside 215	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Mens inside 215	198	SF	6	\$419	
	Hand Dryer	2nd - Mens inside 215	1	EA	6	\$230	
	Lavatory	2nd - Mens inside 215	1	EA	6	\$320	
	Lighting - Lay-in	2nd - Mens inside 215	4	EA	7	\$0	
	Partitions	2nd - Mens inside 215	1	EA	6	\$297	
	Urinals	2nd - Mens inside 215	4	EA	6	\$1,344	
	Walls - Tile Ceramic/ Porcelain	2nd - Mens inside 215	534	SF	6	\$1,207	
	Water Closet	2nd - Mens inside 215	2	EA	6	\$672	
	Accessories	2nd - Mens inside Kitchen	101	SF	6	\$932	
	Ceiling - Splined	2nd - Mens inside Kitchen	101	SF	5	\$719	old / dirty/ bad condition
	Doors - Wood Doors inclu hw	2nd - Mens inside Kitchen	1	EA	6	\$301	
	Floor Drain	2nd - Mens inside Kitchen	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Mens inside Kitchen	101	SF	6	\$214	
	Hand Dryer	2nd - Mens inside Kitchen	1	EA	6	\$230	
	Lavatory	2nd - Mens inside Kitchen	1	EA	6	\$320	
	Lighting - Lay-in	2nd - Mens inside Kitchen	2	EA	7	\$0	
	Partitions	2nd - Mens inside Kitchen	1	EA	6	\$297	
	Student Lockers - One Tier	2nd - Mens inside Kitchen	12	EA	5	\$1,682	old / bad condition
	Urinals	2nd - Mens inside Kitchen	1	EA	6	\$336	
	Walls - Tile Ceramic/ Porcelain	2nd - Mens inside Kitchen	420	SF	6	\$949	
	Water Closet	2nd - Mens inside Kitchen	1	EA	6	\$336	
	Accessories	2nd - Women across from 264	199	SF	6	\$1,835	
	Ceiling - Plaster/Drywall	2nd - Women across from 264	199	SF	6	\$689	
	Doors - Wood Doors inclu hw	2nd - Women across from 264	1	EA	6	\$301	
	Floor Drain	2nd - Women across from 264	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Women across from 264	199	SF	6	\$421	
	Hand Dryer	2nd - Women across from 264	1	EA	6	\$230	
	Lavatory	2nd - Women across from 264	2	EA	6	\$639	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Lay-in	2nd - Women across from 264	4	EA	7	\$0	
	Partitions	2nd - Women across from 264	3	EA	6	\$891	
	Walls - Tile Ceramic/ Porcelain	2nd - Women across from 264	504	SF	6	\$1,139	
	Water Closet	2nd - Women across from 264	4	EA	6	\$1,344	
	Accessories	2nd - Women inside 215	203	SF	6	\$1,872	
	Ceiling - Plaster/Drywall	2nd - Women inside 215	203	SF	6	\$703	
	Floor Drain	2nd - Women inside 215	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Women inside 215	203	SF	6	\$430	
	Hand Dryer	2nd - Women inside 215	1	EA	6	\$230	
	Lavatory	2nd - Women inside 215	1	EA	6	\$320	
	Lighting - Lay-in	2nd - Women inside 215	4	EA	7	\$0	
	Partitions	2nd - Women inside 215	4	EA	6	\$1,188	
	Walls - Tile Ceramic/ Porcelain	2nd - Women inside 215	535	SF	6	\$1,209	
	Water Closet	2nd - Women inside 215	5	EA	6	\$1,680	
	Accessories	2nd - Women inside 271 Faculty	161	SF	6	\$1,485	
	Ceiling - Plaster/Drywall	2nd - Women inside 271 Faculty	161	SF	6	\$557	
	Doors - Wood Doors inclu hw	2nd - Women inside 271 Faculty	1	EA	6	\$301	
	Floor Drain	2nd - Women inside 271 Faculty	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Women inside 271 Faculty	161	SF	6	\$341	
	Hand Dryer	2nd - Women inside 271 Faculty	1	EA	6	\$230	
	Lavatory	2nd - Women inside 271 Faculty	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Women inside 271 Faculty	4	EA	7	\$0	
	Partitions	2nd - Women inside 271 Faculty	2	EA	6	\$594	
	Walls - Tile Ceramic/ Porcelain	2nd - Women inside 271 Faculty	454	SF	6	\$1,026	
	Water Closet	2nd - Women inside 271 Faculty	3	EA	6	\$1,008	
	Accessories	2nd - Women next to link to addition 1	199	SF	6	\$1,835	
	Ceiling - Plaster/Drywall	2nd - Women next to link to addition 1	199	SF	6	\$689	
	Doors - Steel Doors incl hw	2nd - Women next to link to addition 1	1	EA	6	\$301	
	Floor Drain	2nd - Women next to link to addition 1	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Women next to link to addition 1	199	SF	6	\$421	
	Hand Dryer	2nd - Women next to link to addition 1	1	EA	6	\$230	
	Lavatory	2nd - Women next to link to addition 1	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Women next to link to addition 1	4	EA	7	\$0	
	Partitions	2nd - Women next to link to addition 1	3	EA	6	\$891	
	Walls - Tile Ceramic/ Porcelain	2nd - Women next to link to addition 1	527	SF	6	\$1,191	
	Water Closet	2nd - Women next to link to addition 1	4	EA	6	\$1,344	
	Accessories	2nd - Womens inside Kitchen	144	SF	6	\$1,328	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Splined	2nd - Womens inside Kitchen	144	SF	5	\$1,025	old / stained / bad condition
	Doors - Wood Doors inclu hw	2nd - Womens inside Kitchen	1	EA	6	\$301	
	Floor Drain	2nd - Womens inside Kitchen	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd - Womens inside Kitchen	144	SF	6	\$305	
	Hand Dryer	2nd - Womens inside Kitchen	1	EA	6	\$230	
	Lavatory	2nd - Womens inside Kitchen	2	EA	6	\$639	
	Lighting - Lay-in	2nd - Womens inside Kitchen	3	EA	7	\$0	
	Partitions	2nd - Womens inside Kitchen	1	EA	6	\$297	
	Student Lockers - One Tier	2nd - Womens inside Kitchen	15	EA	6	\$1,393	
	Walls - Tile Ceramic/ Porcelain	2nd - Womens inside Kitchen	360	SF	6	\$813	
	Water Closet	2nd - Womens inside Kitchen	2	EA	6	\$672	

Rooms (Other Than Classrooms) Subtotal:

\$1,585,738

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	15,661	SF	6	\$47,030	
	Ceiling - Plaster/Drywall	1st Floor	1,986	SF	6	\$12,297	
	Doors - Side-lite	1st Floor	792	EA	6	\$13,240	
	Doors - Steel Doors incl hw	1st Floor	12	EA	6	\$3,612	
	Doors - Store Front	1st Floor	20	EA	6	\$24,164	
	Doors - Transom Window	1st Floor	90	EA	6	\$1,524	
	Drinking Fountains - Single Fountain	1st Floor	4	EA	6	\$1,103	
	Floor - Carpet	1st Floor	294	SF	6	\$626	
	Floor - Terrazzo	1st Floor	4,534	SF	6	\$38,059	
	Floor - Tile/Sheet	1st Floor	15	SF	5	\$86	
	Floor - Tile/Sheet	1st Floor	15,800	SF	6	\$8,586	
	Lighting - Lay-in	1st Floor	56	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	190	EA	7	\$0	
	Student Lockers - One Tier	1st Floor	87	EA	6	\$8,077	
	Walls - Concrete Block	1st Floor	7,479	SF	6	\$21,925	
	Walls - Metal Panel	1st Floor	6,135	SF	6	\$55,533	
	Walls - Metal Panel	1st Floor	7,294	SF	6	\$54,447	
	Walls - Structural Glazed Tile	1st Floor	1,852	SF	6	\$5,826	
	Ceiling - Lay-in	2nd Floor	6,510	SF	6	\$19,550	

Building: Addition 2
Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Plaster/Drywall	2nd Floor	239	SF	6	\$1,480	
	Doors - Side-lite	2nd Floor	80	EA	6	\$1,337	
	Doors - Steel Doors incl hw	2nd Floor	8	EA	6	\$2,408	
	Doors - Store Front	2nd Floor	10	EA	6	\$12,082	
	Doors - Transom Window	2nd Floor	48	EA	6	\$813	
	Drinking Fountains - Single Fountain	2nd Floor	1	EA	6	\$276	
	Floor - Terrazzo	2nd Floor	940	SF	6	\$7,890	
	Floor - Tile/Sheet	2nd Floor	5,809	SF	6	\$3,157	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	108	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	242	EA	6	\$22,466	
	Walls - Concrete Block	2nd Floor	2,858	SF	6	\$8,378	
	Walls - Metal Panel	2nd Floor	10,514	SF	6	\$78,483	
	Walls - Structural Glazed Tile	2nd Floor	140	SF	6	\$440	
Safety							
	Metal Dedector	Entire Building / 1st Floor	2	EA	6	\$1,761	Located in Main Lobby
	Security Cameras	Entire Building	1	EA	6	\$194	
Stairs							
	Ceiling - Lay-in	North East / 2nd Floor	366	SF	6	\$1,099	
	Floor - Terrazzo	North East	138	SF	6	\$1,158	
	Handrails	North East	95	LF	6	\$823	
	Lighting - Pendent/Surface	North East	4	EA	7	\$0	
	Stairs - Terrazzo	North East	26	LF	6	\$241	
	Walls - Concrete Block	North East	400	SF	6	\$1,173	
	Ceiling - Lay-in	North West / 2nd Floor	266	SF	6	\$799	
	Floor - Terrazzo	North West	138	SF	6	\$1,158	
	Handrails	North West	95	LF	6	\$823	
	Lighting - Pendent/Surface	North West	4	EA	7	\$0	
	Stairs - Terrazzo	North West	26	LF	6	\$241	
	Walls - Concrete Block	North West	400	SF	6	\$1,173	
	Ceiling - Lay-in	South East / 2nd Floor	366	SF	6	\$1,099	
	Floor - Terrazzo	South East	138	SF	6	\$1,158	
	Handrails	South East	95	LF	6	\$823	
	Lighting - Pendent/Surface	South East	4	EA	7	\$0	
	Stairs - Terrazzo	South East	26	LF	6	\$241	
	Walls - Concrete Block	South East	400	SF	6	\$1,173	

Building: Addition 2
Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Ceiling - Lay-in	South West / 2nd Floor	366	SF	6	\$1,099	
	Floor - Terrazzo	South West	138	SF	6	\$1,158	
	Handrails	South West	95	LF	6	\$823	
	Lighting - Pendent/Surface	South West	4	EA	7	\$0	
	Stairs - Terrazzo	South West	26	LF	6	\$241	
	Walls - Concrete Block	South West	400	SF	6	\$1,173	

Vertical Conveyance

	Elevator - Hydraulic Elevator	North	1	EA	5	\$86,984	Needs repairs often & floor tiles needs replacing
--	-------------------------------	-------	---	----	---	----------	---

Building Interior Subtotal:
\$561,512
Total Building Cost
\$5,870,669
SITE
Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Athletic							
	Metal Bleachers	Entire Site	200	LF	6	\$8,923	Location: SE
	Surface - Asphalt	SE	12,970	SF	5	\$59,165	Cracks, sink holes
	Surface - Natural	Entire Site	34,260	SF	6	\$28,415	Location: SE
	Surface - Natural	SE	37,600	SF	6	\$36,025	Location: Soccer
	Surface - Natural	SE	61,500	SF	6	\$51,008	Location: Football

Civil/Drainage

	Civil/ Drainage - Catch Basin	Entire Site	22	EA	6	\$24,064	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	6	\$310	Location: Dock
	Civil/ Drainage - Site Drain	Entire Site / Courtyard	3	EA	6	\$931	
	Civil/ Drainage - Site Manhole	Entire Site	26	EA	6	\$38,811	

Fencing

	Fencing - Chain Link	Entire Site	995	LF	6	\$18,682	Location: SE
	Fencing - New Standard Ornamental	Entire Site	1,056	LF	6	\$33,690	

Landscape

	Benches	Entire Site / North	7	EA	6	\$3,010	
	Irrigation	Entire Site	319,500	SF	5	\$858,944	Location: Baseball field. Not working
	Landscape - Grass	Entire Site	435,800	SF	6	\$361,453	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Landscape							
	Landscape - Hardscape- Concrete	Entire Site	2,000	SF	5	\$21,936	Location: Trash enclosure: cracks
	Landscape - Hardscape- Concrete	Entire Site	3,600	SF	6	\$21,879	Location: at door ramp
	Landscape - Hardscape- Concrete	Entire Site / Courtyard	302	SF	4	\$6,430	Deteriorating
	Landscape - Hardscape- Concrete	Entire Site / East	60	SF	5	\$765	Cracks, movement
	Landscape - Hardscape- Concrete	Entire Site / North	1,645	SF	5	\$18,043	Cracks, movementpitting
	Landscape - Hardscape- Concrete	Entire Site / North	40	SF	5	\$510	Cracks, pitting, movement
	Landscape - Hardscape- Pavers	Entire Site / North	660	SF	6	\$3,737	
	Parkway trees	Entire Site	102	EA	6	\$67,325	
	Planting Beds/ Area	Entire Site	2,220	SF	6	\$3,651	
	Retaining Wall - Concrete	Entire Site	1,070	SF	6	\$29,607	
	Retaining Wall - Concrete	Entire Site	20	SF	5	\$1,470	Location: NE Parking Lot: cracks, movement
	Retaining Wall - Concrete	Entire Site	1,800	SF	5	\$96,268	Location: Dock ramp: cracks, seepage, efflorescence
	Retaining Wall - Concrete	Entire Site / Courtyard	306	SF	5	\$22,496	Cracks, seepage
	Retaining Wall - Masonry	Entire Site	90	SF	5	\$3,775	Location: NW: movement
	Trash Receptacles	Entire Site	10	EA	6	\$3,123	
Parking Lot							
	Concrete Curbs	NE	650	LF	6	\$8,347	
	Concrete Curbs	NW	335	LF	6	\$4,302	
	Concrete Curbs	SE / South	685	LF	6	\$8,796	
	Concrete Curbs	SW	150	LF	6	\$1,926	
	Drivers Ed_Mobile Trailer	SW - drivers education parking lot	1	EA	6	\$0	rust at metal roof
	Interior Plantings	NE	50	LF	6	\$2,127	
	Lighting - Lighting	NE	3	EA	5	\$2,642	Ballasts
	Lighting - Lighting	NW	2	EA	5	\$1,762	Need ballasts
	Lighting - Lighting	SE	3	EA	5	\$2,642	Ballasts
	Lighting - Pole Mounted	NW	4	EA	6	\$5,810	Rust
	Lighting - Pole Mounted	SE	3	EA	6	\$4,357	
	Lighting - Pole Mounted	SW	12	EA	6	\$17,430	
	Surface - Asphalt	NE	27,465	SF	5	\$125,287	Cracks, potholes
	Surface - Asphalt	NW	18,930	SF	6	\$45,748	
	Surface - Asphalt	SE	23,050	SF	5	\$105,147	cracks and potholes
	Surface - Asphalt	SW	40,000	SF	5	\$182,468	Cracks, potholes
	Trash Compactor	NW	1	EA	6	\$0	
	Trash Enclosure - Chain Links	NW	1,162	SF	6	\$20,389	
	Vehicular Screening	NE	200	LF	6	\$15,747	
	Vehicular Screening	NW	140	LF	6	\$11,023	Location: NW

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	15	LF	5	\$867	Location: Door 2 water ponding
	Sidewalks - Internal Walks	Entire Site	3,445	LF	5	\$146,608	Location: Door 5 Asphalt spalling, cracks
	Sidewalks - Internal Walks	Entire Site	20	LF	5	\$1,155	Location: SE
	Sidewalks - Internal Walks	Entire Site / North Courtyard	40	LF	5	\$2,311	Location: N: Cracks, pitting, movement
	Sidewalks - Internal Walks	Entire Site / West	30	LF	5	\$1,733	Cracks
	Sidewalks - Perimeter Sidewalks	Entire Site	28,235	SF	6	\$56,123	
Signage							
	Flag Pole - Flag Pole	Entire Site / North	1	EA	6	\$1,657	some rust
	Flag Pole - Flag Pole	Entire Site / West	1	EA	6	\$1,657	rust at base
	Marquee - Building Mounted Back Lighted	Entire Site	1	EA	6	\$0	Location: Door4
	Marquee - Free Standing Back lighted w/ LED	Entire Site	1	EA	6	\$0	
	Marquee - Free Standing Back lighted w/ LED	Entire Site / South	1	EA	6	\$0	
	Monument - Building Mounted Cut Letter Sign	Entire Site	1	EA	6	\$0	Location: Door 9
	Monument - Building Mounted Cut Letter Sign	Entire Site	1	EA	6	\$0	Location: Door 1
	Monument - Building Mounted Cut Letter Sign	Entire Site	1	EA	6	\$0	Location: Door 8.1
	Monument - Building Mounted Cut Letter Sign	Entire Site	1	EA	6	\$0	Location: Door 7
Site Subtotal:						\$2,602,509	
Total Site Cost						\$2,602,509	
Campus Total ^{2 3}						\$20,703,616	

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.

- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement “EA” for “each.” Other items, like chimneys, are measured in terms of linear feet (“LF”). Still other items, like flooring, are generally measured in square feet (“SF”).
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Special Program	1st Floor	119	121	1,830	1	2	32	300	100	40	N	N	N
Computer Lab	Library	1st Floor	107	107	1,470	36	36	160	240	72	40	N	Y	N
Computer Lab	Computer Lab	1st Floor	113	113	1,470	36	36	160	240	72	40	N	N	N
Computer Lab	Lunch Room	3rd Floor	306	304	2,284	1	45	94	200	90	40	N	Y	N
Office	Regular Classroom	1st Floor	117	117	412	1	2	12	60	18	40	N	N	N
Other Instructional Use	Lunch Room	3rd Floor	302L	NA	690	1	6	16	0	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	101	101	1,112	1	1	12	180	54	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	105	105	737	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	106	106	748	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	108	108	748	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	110	110	748	1	2	14	120	36	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	114	114	748	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	116	116	748	1	2	10	120	36	40	N	N	N
Regular Classroom	Office	2nd Floor	201	244	370	1	2	12	45	0	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	203	201	1,150	2	2	12	180	54	40	N	Y	N
Regular Classroom		2nd Floor	204	NA	370	1	4	8	86	18	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	778	1	2	4	240	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	1,073	1	2	18	180	54	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	731	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	209	209	737	1	2	10	120	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	210	210	912	1	2	10	180	42	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	212	212	864	1	2	10	140	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	214	214	688	1	2	10	120	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	216	216	688	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	217	217	748	1	2	12	120	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	219	219	748	1	2	14	120	36	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	221	221	748	1	2	10	120	36	40	N	N	Y
Regular Classroom	Office	3rd Floor	301	344	386	2	3	14	40	0	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	317	317	748	1	2	10	120	30	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	319	319	748	1	2	10	120	36	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	321	321	748	1	2	10	120	36	40	N	N	Y
Science	Regular Classroom	2nd Floor	211	211	760	1	4	22	120	36	40	N	Y	N
Science	Science	2nd Floor	213	213	1,090	1	27	62	180	60	40	N	N	N
Science	Science	3rd Floor	300	NA	584	1	3	10	60	18	40	N	Y	N
Science	Store Room	3rd Floor	302	NA	978	1	3	26	120	36	40	N	Y	N
Science	Laboratory/Shop	3rd Floor	303	301	1,039	1	3	28	180	54	40	N	Y	Y
Science	Science	3rd Floor	307	307	750	1	3	24	240	36	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Science	Science	3rd Floor	308	306/308	1,286	1	2	12	220	54	40	N	Y	Y
Science	Science	3rd Floor	310	310	1,286	1	2	34	220	54	40	N	Y	N
Science	Science	3rd Floor	312	312	1,138	1	3	26	180	54	40	N	Y	N
Science	Science	3rd Floor	316	316	1,138	1	3	26	180	54	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	305	303	965	1	3	26	180	42	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	311	311	1,037	1	10	36	180	36	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	313	313	1,176	1	43	40	180	60	40	N	Y	Y
Special Program	Lunch Room	3rd Floor	304	302	2,714	1	1	10	0	0	40	N	Y	N
Special Program	Special Program	3rd Floor	304A	NA	476	1	12	32	60	12	40	N	Y	N

Addition 1														
Computer Lab	Regular Classroom	1st Floor	139	139 / 137	1,752	2	38	152	390	45	40	N	N	Y
Computer Lab	Regular Classroom	2nd Floor	239	241	1,392	1	31	158	312	36	40	N	N	Y
Computer Lab	Regular Classroom	3rd Floor	342	342	700	2	31	84	156	18	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	342A	342	345	1	0	28	78	9	40	N	Y	N
Other Instructional Use	Regular Classroom	1st Floor	142	142	1,035	2	3	14	234	27	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	134	134	699	2	3	18	156	18	40	N	N	Y
Regular Classroom	Regular Classroom	1st Floor	136	136	671	2	3	18	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	138	138	690	3	3	16	156	18	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	140	140	1,045	4	3	32	234	27	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	232	234	640	0	2	22	156	18	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	234	234	673	2	5	30	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	237	239	686	2	3	57	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	238	241	728	2	3	24	156	18	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	240	241	647	0	2	30	156	18	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	242	242	362	2	3	16	78	9	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	324	334	630	2	3	28	234	27	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	332	332	699	2	3	18	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	334	334	690	2	3	18	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	336	336	686	2	2	18	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	337	337	695	3	3	18	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	338	338	690	2	2	16	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	339	339	694	2	3	18	156	18	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	340	340	690	2	3	18	156	18	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	341	341	694	2	3	18	156	18	40	N	Y	Y
Special Education	Regular Classroom	2nd Floor	236	233	1,035	2	3	15	234	27	40	N	Y	N
Weight	Music Room	2nd Floor	228	228	1,865	0	0	12	312	27	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
---------------	----------------	---------------	-------------	------------------------	-----------	---------------	--------------	----------------	--------------------	----------------------	-------------	-------------	-------------	-------------

Addition 1
Addition 2

Art Room	Art Room	1st Floor	181/182/183		4,800	3	6	30	2,062	207	40	N	Y	N
Band Room	Band Room	1st Floor	174	NA	2,150	1	2	8	952	95	40	N	N	N
Choral Room	Choral Room	1st Floor	173	NA	1,375	1	2	12	756	73	40	N	N	N
Computer Lab	Regular Classroom	1st Floor	149	NA	887	1	26	48	186	18	40	N	Y	N
Computer Lab	Computer Lab	1st Floor	161	NA	891	1	22	42	168	34	40	N	N	N
Computer Lab	Computer Lab	1st Floor	196	NA	1,206	3	37	76	0	0	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	247	NA	1,302	2	21	46	93	6	40	N	Y	Y
Computer Lab	Regular Classroom	2nd Floor	250	NA	982	2	30	70	0	0	40	N	Y	Y
Computer Lab	Regular Classroom	2nd Floor	251	NA	777	0	34	64	0	0	40	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	252	NA	1,350	1	37	76	93	9	40	N	N	Y
Computer Lab	Regular Classroom	2nd Floor	254	NA	1,319	2	37	82	465	45	40	N	N	Y
Laboratory/Shop	Laboratory/Shop	1st Floor	185	NA	500	1	1	10	0	0	40	N	N	N
Music Room	Office	1st Floor	172	NA	785	1	9	44	224	45	40	N	N	N
Music Room	Music Room	1st Floor	175	NA	732	1	2	14	140	28	40	N	N	N
Music Room	Music Room	1st Floor	176	NA	740	1	2	12	308	62	40	N	N	N
Other Instructional Use	Other Instructional Use	1st Floor	187	NA	3,720	1	2	18	0	0	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	145	NA	750	1	2	10	324	65	40	N	N	Y
Regular Classroom	Office	1st Floor	150	NA	324	1	2	18	0	0	40	N	N	N
Regular Classroom	Office	1st Floor	151	NA	485	1	4	16	0	0	40	N	N	N
Regular Classroom	Office	1st Floor	152	NA	633	1	2	10	0	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	153	NA	885	2	3	12	186	18	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	154	NA	893	1	3	12	372	36	40	N	Y	N
Regular Classroom	Office	1st Floor	156	NA	887	11	5	18	93	9	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	159	NA	885	2	3	16	186	18	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	160	NA	890	2	3	12	372	36	40	N	Y	N
Regular Classroom	Office	1st Floor	184	NA	588	1	6	12	0	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	191	NA	846	0	0	8	0	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	245	NA	750	2	3	18	341	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	255	NA	883	1	5	22	186	6	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	257	NA	893	2	3	14	372	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	258	NA	885	1	2	12	186	6	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	259	NA	889	2	3	31	372	12	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	260	NA	890	2	3	14	186	12	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	261	NA	885	2	3	18	372	12	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	262	NA	880	2	3	16	186	6	40	N	Y	Y

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Addition 2														