

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1929	3	106,900	\$4,031,015
Addition 1	1965	3	73,900	\$4,139,440
Addition 2	1974	1	37,400	\$2,583,194
SITE				\$335,451
Campus Total			218,200	\$11,089,099

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Door 1 - Southeast	1	EA	6	\$702	
	Entrance Control - Audio	Door 6 - Courtyard center	1	EA	6	\$497	
	Exterior Doors - Exterior Steel Door	Door 6 - Courtyard center	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	Door 1 - Southeast	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	Door 13 - East center	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	Door 2 - Northeast	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	Door 5 - Courtyard north	1	EA	5	\$1,341	
	Exterior Doors - Exterior Wood Door	Door 5.1 - Courtyard north	1	EA	5	\$1,341	
	Exterior Doors - Exterior Wood Door	Door 7 - Courtyard south	1	EA	5	\$1,341	
	Exterior Doors - Overhead Rolling/ Garage Door	Door 5.7 - Courtyard center	1	EA	6	\$1,433	
	Exterior Doors - Transom Lite	Door 1 - Southeast	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Door 2 - Northeast	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Door 5 - Courtyard north	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Door 5.1 - Courtyard north	2	EA	5	\$1,643	
	Exterior Doors - Transom Lite	Door 7 - Courtyard south	1	EA	5	\$822	
	Exterior Stairs - Concrete	Door 1 - Southeast	90	LF	6	\$7,359	
	Exterior Stairs - Concrete	Door 13 - East center	3	LF	6	\$245	
	Exterior Stairs - Concrete	Door 2 - Northeast	90	LF	6	\$7,359	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Stairs - Concrete	Door 5 - Courtyard north	60	LF	6	\$4,906	
	Exterior Stairs - Concrete	Door 5 - Courtyard north	7	LF	5	\$767	Spalling
	Exterior Stairs - Concrete	Door 7 - Courtyard south	2	LF	4	\$327	Cracked, missing
	Exterior Stairs - Concrete	Door 7 - Courtyard south	65	LF	6	\$5,315	
	Stair Handrail - Steel_Stair Handrail	Door 1 - Southeast	15	LF	6	\$130	
	Stair Handrail - Steel_Stair Handrail	Door 2 - Northeast	15	LF	6	\$130	
	Stair Handrail - Steel_Stair Handrail	Door 5 - Courtyard north	20	LF	5	\$230	Rust
	Stair Handrail - Steel_Stair Handrail	Door 7 - Courtyard south	20	LF	5	\$230	Rust
Foundation							
	Foundation - Concrete	Entire Building	753	LF	7	\$0	
	Foundation - Concrete	Entire Building	200	LF	7	\$0	
	Superstructure - Concrete	Entire Building	106,900	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	5	EA	6	\$2,683	
	Exterior Lighting - Wall Mounted	Entire Building	5	EA	6	\$1,444	
Roof System							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 4	20	LF	4	\$112,639	Cracking
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 4	5	LF	5	\$14,258	Needs tuck pointing
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 4	50	LF	6	\$47,734	
	Coping - Metal	Roof 1	350	LF	6	\$11,241	
	Coping - Metal	Roof 2	167	LF	6	\$5,364	
	Coping - Stone	Roof 1	190	LF	6	\$6,102	
	Coping - Terra Cotta	Roof 1	550	LF	6	\$17,665	
	Coping - Terra Cotta	Roof 3	150	LF	6	\$4,818	
	Coping - Terra Cotta	Roof 4	188	LF	6	\$6,038	
	Coping - Terra Cotta	Roof 5	43	LF	6	\$1,381	
	Downspouts - Exterior Downspouts	Roof 1	450	LF	6	\$14,955	
	Downspouts - Exterior Downspouts	Roof 2	41	LF	6	\$1,363	
	Downspouts - Exterior Downspouts	Roof 5	20	LF	6	\$665	
	Downspouts - Interior Downspouts	Roof 3	65	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 4	120	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof 3	150	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof 4	188	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof 5	43	LF	6	\$1,718	
	Parapet - Parapet < 16" Height	Roof 1	350	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 2	167	LF	7	\$0	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Parapet - Parapet > 30"	Roof 1	540	LF	6	\$34,517	
	Roof Structure - Concrete	Roof 1	24,850	SF	7	\$0	
	Roof Structure - Concrete	Roof 2	1,487	SF	7	\$0	
	Roof Structure - Concrete	Roof 3	1,300	SF	7	\$0	
	Roof Structure - Concrete	Roof 5	300	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 4	2,985	SF	7	\$0	
	Roof - EPDM/ Synthetic Rubber	Roof 1	24,850	SF	6	\$210,370	
	Roof - EPDM/ Synthetic Rubber	Roof 2	1,487	SF	6	\$12,588	Ponding
	Roof - EPDM/ Synthetic Rubber	Roof 3	1,300	SF	6	\$11,005	
	Roof - EPDM/ Synthetic Rubber	Roof 4	2,985	SF	6	\$25,270	
	Roof - EPDM/ Synthetic Rubber	Roof 5	300	SF	6	\$2,540	
Walls							
	Cheek-Wall - Concrete	Entire Building	40	SF	6	\$410	
	Exterior Walls - Brick	Entire Building	35,900	SF	7	\$0	
	Exterior Walls - Terra Cotta	Entire Building	300	SF	5	\$4,676	Missing mortar
	Exterior Walls - Terra Cotta	Entire Building	5,890	SF	6	\$39,587	
Windows							
	Guard - Guards perforated	Entire Building	3,190	SF	7	\$0	
	Lintels - Steel	Entire Building	6	LF	5	\$2,028	
	Lintels - Steel	Entire Building	213	LF	6	\$6,183	
	Lintels - Terra Cotta	Entire Building	900	LF	6	\$0	
	Windows - Casement Steel	Entire Building	840	SF	5	\$68,697	
	Windows - Decorative	Entire Building / Basement	45	SF	4	\$14,702	
	Windows - Sash Aluminum Double-pane	Entire Building	9,970	SF	6	\$74,422	
Building Exterior Subtotal:						\$797,005	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	ATS Room inside Boiler Room / Boiler Room	2	EA	6	\$816	
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	6,580	SF	6	\$3,481	
	Emergency A/C Power - Corridors and Stairs	Entire Building	11,380	SF	6	\$3,417	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	2,880	SF	6	\$1,071	Boy's gym/ROTC

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Gym	Entire Building / 3rd Floor	6,240	SF	6	\$2,320	Girl's gym.
	Emergency Generator- Outdoor- Diesel - 60 - 100 KW	Site West	1	EA	6	\$9,865	Serves main and additions.
	Exit Signs - Auditorium	Entire Building / 1st Floor	13	EA	6	\$1,947	
	Exit Signs - Corridors and Stairs	Entire Building	23	EA	6	\$3,444	
	Exit Signs - Gym	Entire Building / 1st Floor	4	EA	6	\$630	Boys Gym/ROTC
	Exit Signs - Gym	Entire Building / 3rd Floor	4	EA	6	\$630	Girls Gym
	Security System - CCTV	Entire Building	106,900	SF	6	\$32,102	(4) new cameras are not recording but work. Security is working to correct issue.
	Security System - Intrusion Detection	Entire Building	106,900	SF	6	\$27,516	
	UPS - Less than 30 KW	2nd Floor	1	EA	6	\$7,886	MDF Room
Main Service							
	Independent Electrical Service for emergency power	Boiler Room	1	EA	6	\$2,921	Secondary feed from the utility company.
	Main Electrical Service - Greater than 3000 A 120/208/3PH	Boiler Room	1	EA	6	\$16,381	No model number available.
	PA System	Entire Building	106,900	SF	5	\$73,376	Speakers are deteriorating throughout building and need replacement. Serves main and additions. Control console located in main building.
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 3rd Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building	5	EA	6	\$1,496	
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	Auditorium lighting panel.
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	4	\$6,578	Exposed wires.
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
	Lighting and Power Panels - Above 100 A	Entire Building	8	EA	6	\$3,976	
	Lighting and Power Panels - Above 100 A	Entire Building / Mechanical Room	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building / Mechanical Room	2	EA	3	\$13,156	Live front, exposed buss bar.
	Main Distribution Panels - 400 - 600 amp	Entire Building	2	EA	6	\$1,055	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Mechanical Room	1	EA	6	\$528	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	1	EA	6	\$730	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	1	EA	6	\$730	
Electrical System Subtotal:						\$219,633	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Entire Building / Mechanical Room	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Entire Building	106,900	SF	6	\$38,217	
	Fire Alarm_System	Entire Building	106,900	SF	6	\$51,975	

Safty System Subtotal:

\$96,597

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Ground Mounted - Less than 5 tons	Central Courtyard	1	EA	6	\$3,334	MDF Room split system.
Air Handling Systems							
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 25001 - 35000 cfm	Mechanical Room	1	EA	5	\$55,649	Serves north classrooms and offices.
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 25001 - 35000 cfm	Mechanical Room	1	EA	5	\$55,649	Serves south classrooms and offices.
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Mechanical Room	1	EA	5	\$66,438	Serves the auditorium, gyms and locker rooms.
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Site - East	1	EA	6	\$5,765	
	Auxiliaries - 15001 - 25000 cfm	Mechanical Room	1	EA	6	\$5,788	
	Auxiliaries - 25001 - 35000 cfm	Mechanical Room	1	EA	6	\$6,511	
	Auxiliaries - 25001 - 35000 cfm	Mechanical Room	1	EA	6	\$6,511	
	Reheat Boxes - Reheat Boxes with Steam Coil	Mechanical Room / Plenum	5	EA	6	\$5,256	
	Reheat Boxes - Reheat Boxes with Steam Coil	Mechanical Room / Plenum	6	EA	6	\$6,307	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	7	\$0	
	Zone Dampers	Mechanical Room	5	EA	6	\$4,165	
	Zone Dampers	Mechanical Room / Plenum	20	EA	6	\$16,661	
	Zone Dampers	Mechanical Room / Plenum	17	EA	6	\$14,162	

Boiler Systems

	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 151 - 200 HP	Boiler Room	1	EA	6	\$2,545	
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - Greater than 300 HP	Boiler Room	1	EA	6	\$998	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	

Building: Main
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Boiler Systems							
	Combustion Dampers	Boiler Room	1	EA	6	\$409	
	Combustion Dampers	Boiler Room	2	EA	6	\$818	(1) for boiler, (1) for domestic water heaters.
	Condensate Pump	Boiler Room / Mechanical Room	1	EA	6	\$2,021	
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	(4) pumps, (2) at 2 HP and (2) at 1.5 HP.
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 151 - 200 HP	Boiler Room	1	EA	6	\$2,545	The 2 boilers share the same auxiliary equipment
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - Greater than 300 HP	Boiler Room	1	EA	6	\$998	The 2 boilers share the same auxiliary equipment
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	400	LF	6	\$755	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	400	LF	6	\$755	
	Steam Traps	Boiler Room / Entire Building	56	EA	5	\$73,634	
	Vacuum Pump	Boiler Room / Mechanical Room	1	EA	6	\$2,471	
Heat Exchangers							
	Heat Exchanger - Steam to Hot Water Shell Type	Boiler Room	1	EA	6	\$0	Serves addition 1 unit ventilators and addition 1 perimeter heaters.
Heating Devices							
	Radiators - Steam	Entire Building	14	EA	6	\$3,889	Manual control valves.
	Wall Heater - Electric	Entire Building / 2nd Floor	1	EA	4	\$1,083	Missing covers.
	Wall Heater - Electric	Entire Building	6	EA	6	\$833	
Mechanical Plumbing							
	Hot Water Pump - Less than 10	Boiler Room	4	EA	6	\$4,445	Serves addition 1 unit ventilators and addition 1 perimeter heaters.
	Hydronic Supply and Return - Copper	Basement	150	LF	6	\$7,870	Piping to/from addition 1.
Temperature Control							
	Electric Thermostat	Entire Building / 2nd Floor	1	EA	6	\$0	MDF Room
	Pneumatic System	Entire Building	106,900	SF	5	\$368,409	System requires calibration.
	Thermostats - Pneumatic	Entire Building	42	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	4	\$6,392	Housing deteriorated. Motor exposed to weather.
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	4	EA	6	\$2,370	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	5	EA	6	\$2,962	
	Lab Exhaust Hood	Entire Building	2	EA	6	\$2,495	Fume hoods not exhausted to outdoors. Recirculate only.
Mechanical System Subtotal:						\$756,044	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	6	\$310	
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	2	EA	4	\$69,899	Past useful life and showing signs of corrosion.
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	Boiler Room	1	EA	6	\$678	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	106,900	SF	6	\$21,401	Piping is forming clogs causing pressure issues,
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	106,900	SF	6	\$25,987	Piping is forming clogs causing pressure issues,
	Domestic Piping-Cold Water Risers	Entire Building	106,900	SF	6	\$19,873	Piping is forming clogs causing pressure issues,
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	106,900	SF	6	\$16,815	Piping is forming clogs causing pressure issues,
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	106,900	SF	6	\$19,873	Piping is forming clogs causing pressure issues,
	Domestic Piping-Hot Water Return Lines	Entire Building	106,900	SF	6	\$15,287	Piping is forming clogs causing pressure issues,
	Domestic Piping-Hot Water Return Risers	Entire Building	106,900	SF	6	\$15,287	Piping is forming clogs causing pressure issues,
	Sanitary Piping	Entire Building	106,900	SF	6	\$97,835	Piping is forming clogs causing drainage issues.
	Storm Piping	Entire Building	106,900	SF	6	\$93,249	Exterior site storm restricter plate causing back-up.
	Vent Piping	Entire Building	106,900	SF	6	\$71,847	
Pumps							
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room	1	EA	6	\$1,446	Serves main and additions.
	Pumps - Sump-Duplex	Mechanical Room	1	EA	6	\$1,387	

Plumbing System Subtotal:

\$471,174

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #108 (Regular Classroom)							
	AC Units	1st Floor	2	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	1,085	SF	6	\$3,755	
	Chalk Board	1st Floor	14	LF	4	\$1,285	
	Doors - Transom Window	1st Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Carpet	1st Floor	1,085	SF	6	\$2,312	
	Lighting - Pendent/Surface	1st Floor	8	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,210	SF	6	\$3,339	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #109 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	12	LF	6	\$303	
	Ceiling - Plaster/Drywall	1st Floor	770	SF	6	\$2,665	
	Chalk Board	1st Floor	14	LF	4	\$1,285	
	Doors - Transom Window	1st Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,220	SF	6	\$3,367	
Classroom #110 (Special Education)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	4	LF	6	\$101	
	Ceiling - Plaster/Drywall	1st Floor	350	SF	6	\$1,211	
	Doors - Transom Window	1st Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	350	SF	6	\$350	
	Lighting - Pendent/Surface	1st Floor	4	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Storage/ Closet	1st Floor	180	SF	6	\$1,305	
	Walls - Plaster/Drywall	1st Floor	585	SF	6	\$1,615	
Classroom #200 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	6	\$2,665	
	Chalk Board	2nd Floor	53	LF	4	\$4,866	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	5	\$9,246	Peeling
Classroom #201 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	6	\$2,665	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #201 (Regular Classroom)							
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	5	\$9,246	Peeling
Classroom #202 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	6	\$2,665	
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	1,210	SF	6	\$3,339	
	Walls - Plaster/Drywall	2nd Floor	10	SF	5	\$51	At window
Classroom #203 (Regular Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	6	\$2,665	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	14	EA	6	\$1,735	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #204 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	6	\$2,665	
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	14	EA	6	\$1,735	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #205 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	730	SF	6	\$2,526	
	Ceiling - Plaster/Drywall	2nd Floor	40	SF	5	\$500	Peeling paint
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	14	EA	6	\$1,735	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #206 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	5	\$7,058	Peeling paint
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	14	EA	6	\$1,735	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #207 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Plaster/Drywall	2nd Floor	770	SF	5	\$7,058	Peeling paint
	Chalk Board	2nd Floor	16	LF	6	\$357	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	14	EA	6	\$1,735	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #208 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Splined	2nd Floor	750	SF	6	\$611	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #208 (Regular Classroom)							
	Ceiling - Splined	2nd Floor	20	SF	6	\$21	Water damage
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	850	SF	6	\$2,346	
	Walls - Plaster/Drywall	2nd Floor	50	SF	6	\$193	Water damage at wall by window
Classroom #209 (Special Education)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Ceiling - Splined	2nd Floor	280	SF	6	\$228	
	Ceiling - Splined	2nd Floor	10	SF	5	\$97	Water damage at wall
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	290	SF	6	\$290	
	Lighting - Pendent/Surface	2nd Floor	6	EA	6	\$743	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	2nd Floor	575	SF	6	\$1,587	
	Walls - Plaster/Drywall	2nd Floor	10	SF	5	\$51	Water damage at wall
Classroom #210 (Science Lab Level 1)							
	AC Units	2nd Floor	2	EA	6	\$991	
	Casework	2nd Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	2nd Floor	930	SF	6	\$2,793	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	930	SF	6	\$931	
	Gas Line	2nd Floor	5	EA	6	\$2,546	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	7	LF	6	\$150	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	2nd Floor	1,120	SF	6	\$3,091	
	Work Sink	2nd Floor	11	EA	6	\$4,169	
Classroom #300 (Science)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Plaster/Drywall	3rd Floor	770	SF	6	\$2,665	
	Chalk Board	3rd Floor	14	LF	6	\$312	

Building: Main
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #300 (Science)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	3rd Floor	14	EA	6	\$1,735	
	Walls - Plaster/Drywall	3rd Floor	670	SF	6	\$1,849	
	Walls - Plaster/Drywall	3rd Floor	250	SF	5	\$1,105	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #302 (Science)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	120	LF	6	\$3,030	
	Ceiling - Plaster/Drywall	3rd Floor	1,085	SF	6	\$3,755	
	Chalk Board	3rd Floor	14	LF	6	\$312	
	Doors - Side-lite	3rd Floor	2	SF	6	\$33	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Floor - Tile/Sheet	3rd Floor	1,085	SF	6	\$1,086	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Pendent/Surface	3rd Floor	20	EA	6	\$2,478	
	Storage/ Closet	3rd Floor	97	SF	6	\$703	
	Walls - Plaster/Drywall	3rd Floor	1,210	SF	6	\$3,339	
	Work Sink	3rd Floor	4	EA	6	\$1,516	
Classroom #303 (Science)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Plaster/Drywall	3rd Floor	770	SF	5	\$7,058	Peeling paint
	Chalk Board	3rd Floor	14	LF	4	\$1,285	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	70	SF	6	\$144	
	Floor - Tile/Sheet	3rd Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	3rd Floor	14	EA	6	\$1,735	
	Walls - Plaster/Drywall	3rd Floor	970	SF	6	\$2,677	
	Walls - Plaster/Drywall	3rd Floor	250	SF	5	\$1,105	Peeling paint
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #305 (Science)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	120	LF	6	\$3,030	
	Ceiling - Plaster/Drywall	3rd Floor	1,085	SF	6	\$3,755	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #305 (Science)							
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,085	SF	6	\$1,086	
	Lighting - Pendent/Surface	3rd Floor	18	EA	6	\$2,230	
	Marker Board	3rd Floor	10	LF	6	\$214	
	Storage/ Closet	3rd Floor	97	SF	6	\$703	
	Walls - Plaster/Drywall	3rd Floor	1,130	SF	6	\$3,119	
	Walls - Plaster/Drywall	3rd Floor	80	SF	5	\$408	Peeling paint
	Work Sink	3rd Floor	3	EA	6	\$1,137	
Classroom #307 (Science)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	120	LF	6	\$3,030	
	Ceiling - Plaster/Drywall	3rd Floor	1,085	SF	6	\$3,755	
	Chalk Board	3rd Floor	7	LF	4	\$643	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,085	SF	6	\$1,086	
	Lighting - Pendent/Surface	3rd Floor	22	EA	6	\$2,726	
	Storage/ Closet	3rd Floor	97	SF	6	\$703	
	Walls - Plaster/Drywall	3rd Floor	1,210	SF	5	\$9,171	Peeling paint
	Work Sink	3rd Floor	3	EA	6	\$1,137	
Classroom #308 (Science)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Plaster/Drywall	3rd Floor	770	SF	6	\$2,665	
	Chalk Board	3rd Floor	14	LF	6	\$312	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	770	SF	6	\$771	
	Lighting - Pendent/Surface	3rd Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #310 (Science Lab Level 1)							
	Casework	3rd Floor	120	LF	6	\$3,030	
	Ceiling - Plaster/Drywall	3rd Floor	1,085	SF	6	\$3,755	
	Chalk Board	3rd Floor	14	LF	4	\$1,285	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,085	SF	6	\$1,086	
	Gas Line	3rd Floor	29	EA	6	\$14,765	
	Lighting - Pendent/Surface	3rd Floor	22	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #310 (Science Lab Level 1)							
	Science Lab Elements	3rd Floor	1,085	SF	6	\$7,354	
	Walls - Plaster/Drywall	3rd Floor	1,190	SF	6	\$3,284	
	Walls - Plaster/Drywall	3rd Floor	20	SF	5	\$102	Water damaged
	Work Sink	3rd Floor	15	EA	6	\$5,685	

Classrooms Subtotal:

\$301,212

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Plaster/Drywall	102A-Asst. Principal	220	SF	6	\$761	
	Doors - Side-lite	102A-Asst. Principal	48	SF	6	\$802	
	Doors - Transom Window	102A-Asst. Principal	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	102A-Asst. Principal	2	EA	6	\$602	
	Floor - Carpet	102A-Asst. Principal	220	SF	6	\$469	
	Lighting - Pendent/Surface	102A-Asst. Principal	2	EA	7	\$0	
	Power Distribution	102A-Asst. Principal	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	102A-Asst. Principal	600	SF	6	\$1,656	
	Work Slnk	102A-Asst. Principal	1	EA	6	\$508	
	AC Unit	102B-Copy Room	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	102B-Copy Room	185	SF	6	\$640	
	Doors - Transom Window	102B-Copy Room	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	102B-Copy Room	1	EA	6	\$301	
	Floor - Carpet	102B-Copy Room	185	SF	6	\$394	
	Lighting - Pendent/Surface	102B-Copy Room	2	EA	7	\$0	
	Power Distribution	102B-Copy Room	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	102B-Copy Room	600	SF	6	\$1,656	
	Ceiling - Plaster/Drywall	102	165	SF	6	\$571	
	Doors - Transom Window	102	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	102	1	EA	6	\$301	
	Floor - Carpet	102	165	SF	6	\$352	
	Lighting - Pendent/Surface	102	2	EA	7	\$0	
	Power Distribution	102	4	EA	6	\$8,500	
	Storage/ Closet	102	80	SF	6	\$580	
	Walls - Plaster/Drywall	102	655	SF	6	\$1,808	
	Ceiling - Plaster/Drywall	3rd across 303 Psychologist	94	SF	5	\$862	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Transom Window	3rd across 303 Psychologist	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd across 303 Psychologist	1	EA	6	\$301	
	Floor - Concrete	3rd across 303 Psychologist	94	SF	6	\$50	
	Lighting - Pendent/Surface	3rd across 303 Psychologist	2	EA	6	\$248	
	Power Distribution	3rd across 303 Psychologist	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	3rd across 303 Psychologist	20	SF	5	\$102	Water damaged
	Walls - Plaster/Drywall	3rd across 303 Psychologist	578	SF	6	\$1,595	
	Ceiling - Plaster/Drywall	3rd gym office	130	SF	6	\$450	
	Doors - Side-lite	3rd gym office	24	SF	6	\$401	
	Doors - Wood Doors inclu hw	3rd gym office	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd gym office	130	SF	6	\$130	
	Lighting - Pendent/Surface	3rd gym office	2	EA	7	\$0	
	Power Distribution	3rd gym office	6	EA	6	\$12,749	
	Walls - Concrete Block	3rd gym office	420	SF	6	\$1,231	
	Ceiling - Exposed	Basement Engineer's Office	249	SF	6	\$370	
	Doors - Wood Doors inclu hw	Basement Engineer's Office	1	EA	6	\$301	
	Floor - Concrete	Basement Engineer's Office	249	SF	6	\$132	
	Lighting - Pendent/Surface	Basement Engineer's Office	2	EA	6	\$248	
	Power Distribution	Basement Engineer's Office	6	EA	6	\$12,749	
	Walls - Concrete Block	Basement Engineer's Office	576	SF	6	\$1,689	
	AC Unit	Counseling Office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	Counseling Office	740	SF	6	\$2,561	
	Doors - Transom Window	Counseling Office	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	Counseling Office	2	EA	6	\$602	
	Floor - Carpet	Counseling Office	740	SF	6	\$1,577	
	Lighting - Pendent/Surface	Counseling Office	12	EA	7	\$0	
	Power Distribution	Counseling Office	20	EA	6	\$42,498	
	Walls - Metal Panel	Counseling Office	300	SF	6	\$2,239	Metal Partitions
	Walls - Plaster/Drywall	Counseling Office	1,130	SF	6	\$3,119	
	AC Unit	Discipline Office FP #100	2	EA	7	\$0	
	Ceiling - Plaster/Drywall	Discipline Office FP #100	770	SF	6	\$2,665	
	Doors - Transom Window	Discipline Office FP #100	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	Discipline Office FP #100	2	EA	6	\$602	
	Floor - Carpet	Discipline Office FP #100	700	SF	6	\$1,491	
	Floor - Tile/Sheet	Discipline Office FP #100	70	SF	6	\$70	
	Lighting - Pendent/Surface	Discipline Office FP #100	12	EA	7	\$0	
	Walls - Plaster/Drywall	Discipline Office FP #100	1,420	SF	6	\$3,919	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	AC Unit	in main office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	in main office	156	SF	6	\$540	
	Doors - Wood Doors inclu hw	in main office	1	EA	6	\$301	
	Floor - Carpet	in main office	156	SF	6	\$332	
	Lighting - Pendent/Surface	in main office	4	EA	7	\$0	
	Power Distribution	in main office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	in main office	500	SF	6	\$1,380	
	Ceiling - Plaster/Drywall	JROTC office in 1st fl gym	120	SF	6	\$415	
	Doors - Wood Doors inclu hw	JROTC office in 1st fl gym	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	JROTC office in 1st fl gym	120	SF	6	\$254	
	Lighting - Pendent/Surface	JROTC office in 1st fl gym	2	EA	7	\$0	
	Power Distribution	JROTC office in 1st fl gym	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	JROTC office in 1st fl gym	50	SF	6	\$138	
	Walls - Structural Glazed Tile	JROTC office in 1st fl gym	331	SF	6	\$1,041	Glazed Brick
	Ceiling - Lay-in	library office in library	220	SF	6	\$661	
	Doors - Side-lite	library office in library	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	library office in library	1	EA	6	\$301	
	Floor - Carpet	library office in library	220	SF	6	\$469	
	Lighting - Pendent/Surface	library office in library	4	EA	7	\$0	
	Power Distribution	library office in library	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	library office in library	470	SF	6	\$1,297	
	AC Unit	Main Office	2	EA	7	\$0	
	Ceiling - Plaster/Drywall	Main Office	710	SF	6	\$2,457	
	Doors - Transom Window	Main Office	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	Main Office	1	EA	6	\$301	
	Floor - Carpet	Main Office	570	SF	6	\$1,214	
	Floor - Tile/Sheet	Main Office	70	SF	6	\$70	
	Lighting - Pendent/Surface	Main Office	14	EA	7	\$0	
	Power Distribution	Main Office	10	EA	6	\$21,249	
	Storage/ Closet	Main Office	140	SF	6	\$1,015	
	Walls - Plaster/Drywall	Main Office	1,420	SF	6	\$3,919	
	AC Unit	prncipals office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	prncipals office	275	SF	6	\$952	
	Doors - Transom Window	prncipals office	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	prncipals office	2	EA	6	\$602	
	Floor - Carpet	prncipals office	275	SF	6	\$586	
	Lighting - Pendent/Surface	prncipals office	6	EA	7	\$0	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	prncipals office	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	prncipals office	870	SF	6	\$2,401	
Auditorium & Theater							
	Balcony Seating	1st Floor	144	EA	6	\$25,044	
	Ceiling - Plaster/Drywall	1st Floor	6,580	SF	6	\$54,857	
	Doors - Wood Doors inclu hw	1st Floor	10	EA	6	\$3,010	
	Floor - Tile/Sheet	1st Floor	5,225	SF	6	\$5,230	
	Floor - Wood	1st Floor	1,355	SF	6	\$9,553	
	Lighting - Chandelier, Incandescent	1st Floor	5	EA	7	\$0	
	Main Floor Seating	1st Floor	512	EA	6	\$89,045	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage Curtain	1st Floor	8	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor	8	LF	6	\$94	
	Walls - Plaster/Drywall	1st Floor	7,210	SF	6	\$34,333	
Gymnasia							
	Bleacher Seating	1st Floor	68	EA	6	\$1,968	
	Ceiling - Plaster/Drywall	1st Floor	2,880	SF	6	\$15,897	
	Doors - Wood Doors inclu hw	1st Floor	6	EA	6	\$1,806	
	Floor - Wood	1st Floor	2,880	SF	6	\$20,304	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	8	EA	7	\$0	
	Storage/ Closet	1st Floor	240	SF	6	\$1,740	
	Walls - Plaster/Drywall	1st Floor	4,144	SF	6	\$11,437	
	Walls - Structural Glazed Tile	1st Floor	1,421	SF	6	\$4,470	Glazed Brick
	Bleacher Seating	3rd Floor	272	EA	6	\$7,873	
	Ceiling - Exposed	3rd Floor	6,240	SF	6	\$9,280	
	Doors - Steel Doors incl hw	3rd Floor	6	EA	6	\$1,806	
	Floor - Wood	3rd Floor	6,240	SF	6	\$43,991	
	Lighting - Pendent/Surface	3rd Floor	36	EA	6	\$4,460	
	Scoreboards	3rd Floor	1	EA	6	\$2,244	
	Walls - Concrete Block	3rd Floor	3,955	SF	6	\$11,594	
	Walls - Structural Glazed Tile	3rd Floor	2,030	SF	6	\$6,386	
Library							
	AC Unit	1st Floor	3	EA	7	\$0	
	Casework	1st Floor	140	LF	6	\$3,536	
	Ceiling - Lay-in	1st Floor	1,905	SF	6	\$5,721	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Library							
	Doors - Transom Window	1st Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Carpet	1st Floor	1,905	SF	6	\$4,059	
	Lighting - Pendent/Surface	1st Floor	36	EA	7	\$0	
	Storage/ Closet	1st Floor	180	SF	6	\$1,305	
	Walls - Plaster/Drywall	1st Floor	1,550	SF	6	\$4,278	
Locker/Shower Room							
	Accessories	3rd Floor Boys Gym locker	1,660	SF	6	\$6,504	
	Benches, ped mounted	3rd Floor Boys Gym locker	11	LF	6	\$1,198	
	Ceiling - Plaster/ Drywall	3rd Floor Boys Gym locker	1,660	SF	6	\$5,745	
	Doors - Wood Doors inclu hw	3rd Floor Boys Gym locker	2	EA	6	\$602	
	Floor Drain	3rd Floor Boys Gym locker	5	EA	6	\$5,296	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Boys Gym locker	1,660	SF	6	\$3,513	
	Lavatory	3rd Floor Boys Gym locker	1	EA	6	\$320	
	Lighting - Lay-in	3rd Floor Boys Gym locker	4	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor Boys Gym locker	29	EA	6	\$3,593	
	Partitions	3rd Floor Boys Gym locker	2	EA	6	\$594	
	Showers	3rd Floor Boys Gym locker	12	EA	6	\$3,737	
	Storage/ Closet	3rd Floor Boys Gym locker	150	SF	6	\$1,088	
	Student Lockers - One Tier	3rd Floor Boys Gym locker	100	EA	6	\$9,284	
	Student Lockers - Two Tier	3rd Floor Boys Gym locker	415	EA	6	\$19,263	
	Walls - Structural Glazed Tile	3rd Floor Boys Gym locker	3,150	SF	6	\$9,910	
	Water Closet	3rd Floor Boys Gym locker	1	EA	6	\$336	
Lunch & Multipurpose Room							
	AC Unit	Faculty Lounge 1st fl	2	EA	7	\$0	
	Ceiling - Lay-in	Faculty Lounge 1st fl	850	SF	6	\$2,553	
	Doors - Transom Window	Faculty Lounge 1st fl	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	Faculty Lounge 1st fl	4	EA	6	\$1,204	
	Floor - Tile/Sheet	Faculty Lounge 1st fl	850	SF	6	\$851	
	Lighting - Lay-in	Faculty Lounge 1st fl	1	EA	7	\$0	
	Lighting - Pendent/Surface	Faculty Lounge 1st fl	12	EA	7	\$0	
	Walls - Plaster/Drywall	Faculty Lounge 1st fl	1,510	SF	6	\$4,167	
MDF_IDF							
	AC Unit	2nd Floor	2	EA	6	\$991	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
MDF_IDF							
	Finishes	2nd Floor	233	SF	6	\$1,663	
Mechanical/ Service Rooms							
	Janitor's Closet	2nd Floor	30	SF	6	\$215	
	Janitor's Closet	2nd Floor	30	SF	5	\$484	Peeling paint
	Storage Room	2nd Floor	251	SF	6	\$1,798	Math Book Room
	Storage Room	2nd Floor	101	SF	6	\$724	Social Study Storage
	Storage Room	2nd Floor	107	SF	6	\$767	206 A
	Air Intake Plenums	Basement	960	SF	6	\$5,944	
	Air Tunnel	Basement	3,000	SF	6	\$18,576	
	Auditorium Plenums	Basement	6,300	SF	6	\$39,009	
	Boiler Room	Basement	3,800	SF	6	\$27,224	
	Crawl Space - Unfinished	Basement	12,460	SF	6	\$77,151	
	Interior Stairs	Basement	56	LF	6	\$505	
	Storage Room	Basement	379	SF	6	\$2,715	
Prep Room							
	Casework	307A	60	LF	6	\$1,515	
	Ceiling - Plaster/Drywall	307A	245	SF	6	\$848	
	Doors - Wood Doors inclu hw	307A	1	EA	6	\$301	
	Floor - Tile	307A	245	SF	6	\$536	
	Lighting - Pendent/Surface	307A	4	EA	7	\$0	
	Walls - Plaster/Drywall	307A	816	SF	6	\$2,252	
Restroom							
	Accessories	1 st fl womens	50	SF	6	\$461	
	Ceiling - Lay-in	1 st fl womens	50	SF	6	\$150	
	Doors - Wood Doors inclu hw	1 st fl womens	1	EA	6	\$301	
	Floor - Tile/Sheet	1 st fl womens	50	SF	6	\$50	
	Lavatory	1 st fl womens	1	EA	6	\$320	
	Lighting - Wall Mounted	1 st fl womens	1	EA	7	\$0	
	Walls - Plaster/Drywall	1 st fl womens	212	SF	6	\$585	
	Water Closet	1 st fl womens	1	EA	6	\$336	
	Accessories	1st fl mens	50	SF	6	\$461	
	Ceiling - Lay-in	1st fl mens	50	SF	6	\$150	
	Doors - Wood Doors inclu hw	1st fl mens	1	EA	6	\$301	
	Floor - Tile/Sheet	1st fl mens	50	SF	6	\$50	
	Lavatory	1st fl mens	1	EA	6	\$320	
	Lighting - Wall Mounted	1st fl mens	1	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	1st fl mens	212	SF	6	\$585	
	Water Closet	1st fl mens	1	EA	6	\$336	
	Accessories	2nd across 202 Girls Storage	258	SF	6	\$2,380	
	Ceiling - Plaster/Drywall	2nd across 202 Girls Storage	258	SF	5	\$2,365	
	Doors - Wood Doors inclu hw	2nd across 202 Girls Storage	2	EA	6	\$602	
	Floor Drain	2nd across 202 Girls Storage	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd across 202 Girls Storage	258	SF	5	\$4,121	
	Lighting - Pendent/Surface	2nd across 202 Girls Storage	4	EA	6	\$496	
	Partitions	2nd across 202 Girls Storage	7	EA	5	\$5,256	
	Walls - Structural Glazed Tile	2nd across 202 Girls Storage	837	SF	6	\$2,633	
	Accessories	2nd near 210 Boys Storage	258	SF	6	\$2,380	
	Ceiling - Plaster/Drywall	2nd near 210 Boys Storage	258	SF	6	\$893	
	Doors - Wood Doors inclu hw	2nd near 210 Boys Storage	2	EA	6	\$602	
	Floor Drain	2nd near 210 Boys Storage	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd near 210 Boys Storage	258	SF	6	\$546	
	Lavatory	2nd near 210 Boys Storage	2	EA	5	\$3,179	
	Lighting - Pendent/Surface	2nd near 210 Boys Storage	4	EA	6	\$496	
	Partitions	2nd near 210 Boys Storage	3	EA	6	\$891	
	Urinals	2nd near 210 Boys Storage	6	EA	5	\$8,064	
	Walls - Structural Glazed Tile	2nd near 210 Boys Storage	837	SF	6	\$2,633	
	Water Closet	2nd near 210 Boys Storage	1	EA	5	\$1,344	
	Accessories	3rd across from 302 Storage	320	SF	5	\$6,333	
	Ceiling - Plaster/Drywall	3rd across from 302 Storage	320	SF	5	\$2,933	Peeling paint
	Doors - Transom Window	3rd across from 302 Storage	24	SF	6	\$406	
	Doors - Wood Doors inclu hw	3rd across from 302 Storage	2	EA	6	\$602	
	Floor Drain	3rd across from 302 Storage	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd across from 302 Storage	320	SF	6	\$677	
	Lavatory	3rd across from 302 Storage	2	EA	5	\$3,179	
	Lighting - Pendent/Surface	3rd across from 302 Storage	4	EA	6	\$496	
	Partitions	3rd across from 302 Storage	7	EA	6	\$2,078	
	Walls - Structural Glazed Tile	3rd across from 302 Storage	771	SF	6	\$2,426	
	Water Closet	3rd across from 302 Storage	7	EA	6	\$2,352	
	Accessories	Boys 1st fl	250	SF	6	\$2,306	
	Ceiling - Plaster/Drywall	Boys 1st fl	250	SF	6	\$865	
	Doors - Wood Doors inclu hw	Boys 1st fl	2	EA	6	\$602	
	Floor Drain	Boys 1st fl	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Boys 1st fl	250	SF	6	\$529	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Hand Dryer	Boys 1st fl	2	EA	6	\$460	
	Lavatory	Boys 1st fl	2	EA	6	\$639	
	Lighting - Pendent/Surface	Boys 1st fl	4	EA	7	\$0	
	Partitions	Boys 1st fl	2	EA	6	\$594	
	Urinals	Boys 1st fl	6	EA	6	\$2,016	
	Walls - Structural Glazed Tile	Boys 1st fl	800	SF	6	\$2,517	Glazed Brick
	Water Closet	Boys 1st fl	2	EA	6	\$672	
	Accessories	girls 1st fl	250	SF	6	\$2,306	
	Ceiling - Plaster/Drywall	girls 1st fl	250	SF	6	\$865	
	Doors - Wood Doors inclu hw	girls 1st fl	2	EA	6	\$602	
	Floor Drain	girls 1st fl	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	girls 1st fl	250	SF	6	\$529	
	Lavatory	girls 1st fl	2	EA	6	\$639	
	Lighting - Pendent/Surface	girls 1st fl	4	EA	7	\$0	
	Partitions	girls 1st fl	8	EA	6	\$2,375	
	Walls - Structural Glazed Tile	girls 1st fl	800	SF	6	\$2,517	Glazed Brick
	Water Closet	girls 1st fl	8	EA	6	\$2,688	
	Accessories	in 3rd fl gym office	30	SF	6	\$277	
	Ceiling - Plaster/Drywall	in 3rd fl gym office	30	SF	6	\$104	
	Doors - Wood Doors inclu hw	in 3rd fl gym office	1	EA	6	\$301	
	Floor - Tile/Sheet	in 3rd fl gym office	30	SF	6	\$30	
	Lavatory	in 3rd fl gym office	1	EA	6	\$320	
	Lighting - Pendent/Surface	in 3rd fl gym office	1	EA	6	\$124	
	Walls - Structural Glazed Tile	in 3rd fl gym office	133	SF	6	\$418	
	Water Closet	in 3rd fl gym office	1	EA	6	\$336	
	Accessories	in main office	22	SF	6	\$203	
	Ceiling - Plaster/Drywall	in main office	22	SF	6	\$76	hot water is broken
	Doors - Wood Doors inclu hw	in main office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	in main office	22	SF	6	\$47	
	Lavatory	in main office	1	EA	6	\$320	
	Lighting - Pendent/Surface	in main office	1	EA	7	\$0	
	Walls - Plaster/Drywall	in main office	24	SF	6	\$66	
	Water Closet	in main office	1	EA	6	\$336	
	Ceiling - Plaster/Drywall	in principal's office	22	SF	6	\$76	
	Doors - Wood Doors inclu hw	in principal's office	1	EA	6	\$301	
	Floor - Tile/Sheet	in principal's office	22	SF	6	\$22	
	Lavatory	in principal's office	1	EA	6	\$320	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Pendent/Surface	in principal's office	1	EA	7	\$0	
	Walls - Plaster/Drywall	in principal's office	190	SF	6	\$524	
	Water Closet	in principal's office	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$1,032,104

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	50	SF	5	\$446	Stained ceiling tiles throughout
	Ceiling - Lay-in	1st Floor	3,157	SF	6	\$9,480	
	Ceiling - Plaster/Drywall	1st Floor	4,720	SF	6	\$29,226	
	Ceiling - Plaster/Drywall	1st Floor	60	SF	5	\$1,047	
	Doors - Wood Doors include hw	1st Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Water Cooler	1st Floor	2	EA	6	\$633	
	Floor - Terrazzo	1st Floor	875	SF	6	\$7,345	
	Floor - Tile/Sheet	1st Floor	7,052	SF	6	\$3,832	
	Lighting - Pendent/Surface	1st Floor	87	EA	6	\$10,779	
	Stairs - Terrazzo	1st Floor	12	LF	6	\$111	
	Student Lockers - One Tier	1st Floor	224	EA	6	\$20,795	
	Walls - Concrete Block	1st Floor	4,266	SF	6	\$12,506	
	Walls - Plaster/Drywall	1st Floor	3,715	SF	6	\$16,469	
	Walls - Structural Glazed Tile	1st Floor	5,496	SF	6	\$17,290	
	Ceiling - Plaster/Drywall	2nd Floor	3,095	SF	6	\$19,164	
	Drinking Fountains - Single Water Cooler	2nd Floor	2	EA	6	\$633	
	Floor - Terrazzo	2nd Floor	700	SF	6	\$5,876	
	Floor - Tile/Sheet	2nd Floor	2,395	SF	6	\$1,301	
	Lighting - Pendent/Surface	2nd Floor	40	EA	6	\$4,956	
	Student Lockers - One Tier	2nd Floor	158	EA	6	\$14,668	
	Walls - Plaster/Drywall	2nd Floor	2,900	SF	6	\$12,856	
	Walls - Structural Glazed Tile	2nd Floor	2,668	SF	6	\$8,394	
	Ceiling - Plaster/Drywall	3rd Floor	3,100	SF	6	\$19,195	
	Ceiling - Splined	3rd Floor	465	SF	6	\$1,343	
	Drinking Fountains - Single Water Cooler	3rd Floor	2	EA	6	\$633	
	Floor - Terrazzo	3rd Floor	500	SF	6	\$4,197	
	Floor - Tile/Sheet	3rd Floor	3,065	SF	6	\$1,666	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Lighting - Pendent/Surface	3rd Floor	40	EA	6	\$4,956	
	Student Lockers - One Tier	3rd Floor	158	EA	6	\$14,668	
	Walls - Plaster/Drywall	3rd Floor	2,850	SF	6	\$12,634	
	Walls - Plaster/Drywall	3rd Floor	50	SF	6	\$311	Peeling paint
	Walls - Structural Glazed Tile	3rd Floor	3,948	SF	6	\$12,420	
Safety							
	Camera Viewing Station	1st Floor	4	EA	6	\$2,730	
	Metal Dedector	1st Floor	2	EA	6	\$1,761	
	Security Cameras	1st Floor / Entire Building	10	EA	6	\$1,940	
	Security Cameras	1st Floor / Entire Building	2	EA	6	\$388	
Stairs							
	Ceiling - Plaster/Drywall	Exit stair from Gym North	307	SF	6	\$2,248	
	Floor - Terrazzo	Exit stair from Gym North	252	SF	6	\$2,115	
	Handrails	Exit stair from Gym North	117	LF	6	\$1,014	
	Lighting - Pendent/Surface	Exit stair from Gym North	4	EA	7	\$0	
	Lighting - Wall Mounted	Exit stair from Gym North	1	EA	6	\$124	
	Stairs - Terrazzo	Exit stair from Gym North	50	LF	6	\$464	
	Walls - Plaster/Drywall	Exit stair from Gym North	1,680	SF	6	\$4,637	
	Walls - Structural Glazed Tile	Exit stair from Gym North	120	SF	5	\$6,924	Cracking
	Walls - Structural Glazed Tile	Exit stair from Gym North	1,000	SF	6	\$3,146	
	Ceiling - Plaster/Drywall	Exit stair from Gym South	307	SF	6	\$2,248	
	Floor - Terrazzo	Exit stair from Gym South	252	SF	6	\$2,115	
	Handrails	Exit stair from Gym South	117	LF	6	\$1,014	
	Lighting - Pendent/Surface	Exit stair from Gym South	4	EA	7	\$0	
	Lighting - Wall Mounted	Exit stair from Gym South	1	EA	7	\$0	
	Stairs - Terrazzo	Exit stair from Gym South	502	LF	6	\$4,659	
	Walls - Structural Glazed Tile	Exit stair from Gym South	1,120	SF	6	\$3,524	
	Ceiling - Plaster/Drywall	North East Stair	335	SF	6	\$2,453	
	Ceiling - Plaster/Drywall	North East Stair	20	SF	5	\$409	Water damaged
	Floor - Terrazzo	North East Stair	255	SF	6	\$2,140	
	Handrails - Plaster/Drywall	North East Stair	115	LF	6	\$317	
	Lighting - Pendent/Surface	North East Stair	2	EA	7	\$0	
	Stairs - Terrazzo	North East Stair	58	LF	6	\$538	
	Walls - Plaster/Drywall	North East Stair	1,100	SF	6	\$3,036	
	Walls - Plaster/Drywall	North East Stair	30	SF	5	\$186	Water damaged
	Walls - Structural Glazed Tile	North East Stair	760	SF	6	\$2,391	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Ceiling - Plaster/Drywall	North West Stair	355	SF	6	\$2,599	
	Floor - Terrazzo	North West Stair	255	SF	6	\$2,140	
	Handrails	North West Stair	115	LF	6	\$997	
	Lighting - Pendent/Surface	North West Stair	2	EA	7	\$0	
	Stairs - Terrazzo	North West Stair	58	LF	6	\$538	
	Walls - Plaster/Drywall	North West Stair	580	SF	6	\$1,601	
	Walls - Structural Glazed Tile	North West Stair	870	SF	6	\$2,737	
	Ceiling - Plaster/Drywall	South East Stair	330	SF	6	\$2,416	
	Ceiling - Plaster/Drywall	South East Stair	25	SF	5	\$512	Water damaged at ceiling and wall
	Floor - Terrazzo	South East Stair	255	SF	6	\$2,140	
	Handrails	South East Stair	115	LF	6	\$997	
	Lighting - Pendent/Surface	South East Stair	2	EA	7	\$0	
	Stairs - Terrazzo	South East Stair	58	LF	6	\$538	
	Walls - Plaster/Drywall	South East Stair	30	SF	5	\$186	
	Walls - Plaster/Drywall	South East Stair	1,100	SF	6	\$3,036	
	Walls - Structural Glazed Tile	South East Stair	760	SF	6	\$2,391	
	Ceiling - Plaster/Drywall	South West Stair	355	SF	6	\$2,599	
	Floor - Terrazzo	South West Stair	255	SF	6	\$2,140	
	Handrails	South West Stair	115	LF	6	\$997	
	Lighting - Pendent/Surface	South West Stair	2	EA	6	\$248	
	Stairs - Terrazzo	South West Stair	58	LF	6	\$538	
	Walls - Plaster/Drywall	South West Stair	580	SF	6	\$1,601	
	Walls - Structural Glazed Tile	South West Stair	870	SF	6	\$2,737	

Building Interior Subtotal: \$357,245

Total Building Cost \$4,031,015

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Wood Door	Door 12 - South	3	EA	6	\$1,442	
	Exterior Doors - Exterior Wood Door	Door 3 - Northeast	3	EA	6	\$1,442	
	Exterior Doors - Exterior Wood Door	Door 4 - Northwest	3	EA	6	\$1,442	
	Exterior Doors - Exterior Wood Door	Door 7.5 - Courtyard basement	1	EA	6	\$481	

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Transom Lite	Door 3 - Northeast	3	EA	6	\$940	
	Exterior Stairs - Concrete	Door 12 - South	57	LF	6	\$4,661	
	Exterior Stairs - Concrete	Door 3 - Northeast	54	LF	6	\$4,415	
	Exterior Stairs - Concrete	Door 4 - Northwest	79	LF	6	\$6,460	
	Exterior Stairs - Concrete	Door 7.5 - Courtyard basement	64	LF	6	\$5,233	
	Stair Handrail - Steel_Stair Handrail	Door 12 - South	6	LF	5	\$69	Rust
	Stair Handrail - Steel_Stair Handrail	Door 3 - Northeast	18	LF	5	\$207	Rust
	Stair Handrail - Steel_Stair Handrail	Door 4 - Northwest	18	LF	5	\$207	Rust
	Stair Handrail - Steel_Stair Handrail	Door 7.5 - Courtyard basement	20	LF	5	\$230	Rust
Foundation							
	Foundation - Concrete	Entire Building	744	LF	7	\$0	
	Foundation - Concrete	Entire Building / South Façade	120	LF	6	\$23,307	Wall cracks at piers, settling of foundation
	Superstructure - Concrete	Entire Building	73,900	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	13	EA	6	\$6,975	
	Exterior Lighting - Wall Mounted	Entire Building	8	EA	6	\$2,310	
Roof System							
	Coping - Metal	Roof 1	480	LF	6	\$15,417	
	Coping - Metal	Roof 2	473	LF	6	\$15,192	
	Coping - Metal	Roof 4	23	LF	4	\$2,037	Heavy rust
	Coping - Metal	Roof 4	150	LF	6	\$4,818	
	Coping - Metal	Roof 5	15	LF	6	\$482	
	Coping - Terra Cotta	Roof 3	28	LF	6	\$899	
	Downspouts - Exterior Downspouts	Roof 5	30	LF	6	\$997	
	Downspouts - Exterior Downspouts	Roof 6	20	LF	6	\$665	
	Downspouts - Interior Downspouts	Roof 1	105	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 2	70	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 3	15	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 4	54	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof 3	28	LF	6	\$1,119	
	Parapet - 16" - 30" Height	Roof 4	23	LF	6	\$919	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 1	12,526	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 2	10,692	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 3	90	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 4	2,127	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 5	200	SF	7	\$0	

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 6	160	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Roof 5	200	SF	5	\$4,722	
	Roof - Asphalt Gravel Ballast	Roof 6	160	SF	5	\$3,777	
	Roof - EPDM/ Synthetic Rubber	Roof 1	12,526	SF	4	\$323,315	Surface worn through to fibers, leaks
	Roof - EPDM/ Synthetic Rubber	Roof 2	10,692	SF	4	\$275,977	Surface worn through to fibers, leaks
	Roof - EPDM/ Synthetic Rubber	Roof 3	771	SF	6	\$6,527	
	Roof - EPDM/ Synthetic Rubber	Roof 4	2,127	SF	4	\$54,901	Bubbles, cracking, worn
	Roof - Metal	Roof 3	861	SF	6	\$11,537	
Walls							
	Canopy - Metal	Entire Building	380	SF	6	\$8,162	
	Canopy - Metal	Entire Building	76	SF	4	\$13,785	
	Cheek-Wall - Concrete	Entire Building	10	SF	6	\$103	
	Exterior Walls - Brick	Entire Building	16,556	SF	6	\$111,273	
	Exterior Walls - Brick	Entire Building / South Façade	465	SF	5	\$11,071	Cracks at piers and net is to catch debris from upper roof
	Exterior Walls - Stone-Cut	Entire Building	630	SF	6	\$4,234	
	Exterior Walls - Stucco	Entire Building	50	SF	4	\$1,819	Deterioration, separation
Windows							
	Guard - Guards perforated	Entire Building	1,560	SF	7	\$0	
	Lintels - Steel	Entire Building	1,593	LF	6	\$46,243	
	Windows - Sash Aluminum Double-pane	Entire Building	10,675	SF	6	\$79,685	

Building Exterior Subtotal: \$1,059,492

Building: Addition 1

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Corridors and Stairs	Entire Building	12,291	SF	6	\$3,691	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	5,128	SF	6	\$1,907	
	Exit Signs - Corridors and Stairs	Entire Building	19	EA	6	\$2,845	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	4	EA	6	\$599	
	Security System - CCTV	Entire Building	73,900	SF	6	\$22,192	
	Security System - Intrusion Detection	Entire Building	73,900	SF	6	\$19,022	

Building: Addition 1

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Main Service							
	PA System	Entire Building	73,900	SF	6	\$24,306	Serves main and additions. Control console located in main building.
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	Panel cover removed.
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	2	EA	6	\$1,055	
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	1	EA	6	\$528	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
Electrical System Subtotal:						\$85,131	

Building: Addition 1

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	73,900	SF	6	\$26,419	
	Fire Alarm_System	Entire Building	73,900	SF	6	\$35,930	
Safty System Subtotal:						\$62,349	

Building: Addition 1

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	7	\$0	Serves Goodman FCU.
Air Handling Systems							
	Fan Coil Unit- Celing Mounted - Electric	2nd Floor	1	EA	6	\$820	No model number available. New Condensing Unit.

Building: Addition 1

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building	6	EA	6	\$2,126	
	Fin Tube - Hot Water	Entire Building	300	LF	6	\$2,831	
Mechanical Plumbing							
	Hydronic Supply and Return - Copper	Entire Building	800	LF	6	\$41,973	Heat exchanger and pumps located in main building.
Temperature Control							
	Electric Thermostat	Entire Building / 2nd Floor	2	EA	6	\$0	Serve new Carrier Unit Ventilators.
	Pneumatic System	Entire Building	73,900	SF	5	\$254,682	System requires calibration.
	Thermostats - Pneumatic	Entire Building	47	EA	6	\$0	
Unit Ventilation							
	Unit Ventilators- Ceiling Mounted- Hot Water & Chilled Water Coils	2nd Floor	2	EA	5	\$15,801	No model number available. Hot water only.
	Unit Ventilators- Floor Mounted- Hot Water Heating Coils Only	Entire Building / 2nd Floor	2	EA	7	\$0	
	Unit Ventilators- Floor Mounted- Hot Water Heating Coils Only	Entire Building	45	EA	4	\$836,939	No model number available.
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	5	EA	6	\$2,962	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Entire Building / Roof	4	EA	6	\$2,370	
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	2	\$28,265	No fire suppression system.
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	6	\$920	Servery

Mechanical System Subtotal:

\$1,193,614

Building: Addition 1

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	73,900	SF	6	\$14,795	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	73,900	SF	6	\$17,965	
	Domestic Piping-Cold Water Risers	Entire Building	73,900	SF	6	\$13,738	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	73,900	SF	6	\$11,624	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	73,900	SF	6	\$13,738	
	Domestic Piping-Hot Water Return Lines	Entire Building	73,900	SF	6	\$10,568	
	Domestic Piping-Hot Water Return Risers	Entire Building	73,900	SF	6	\$10,568	

Building: Addition 1

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Sanitary Piping	Entire Building	73,900	SF	6	\$67,633	
	Storm Piping	Entire Building	73,900	SF	6	\$64,463	
	Vent Piping	Entire Building	73,900	SF	6	\$49,668	
Pumps							
	Pumps - Sump-Duplex	Electrical Room	1	EA	6	\$1,387	

Plumbing System Subtotal: \$276,147

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #111 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Concrete Block	1st Floor	975	SF	6	\$2,858	
Classroom #112 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Concrete Block	1st Floor	975	SF	6	\$2,858	
Classroom #113 (Science Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	115	LF	6	\$2,904	
	Ceiling - Plaster/Drywall	1st Floor	1,107	SF	6	\$3,831	
	Chalk Board	1st Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface	1st Floor	27	EA	7	\$0	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #113 (Science Classroom)							
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	1,185	SF	6	\$3,474	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classroom #114 (Science Classroom)							
	Casework	1st Floor	18	LF	6	\$455	
	Ceiling - Plaster/Drywall	1st Floor	550	SF	6	\$1,903	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	550	SF	6	\$551	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	60	SF	6	\$435	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #115 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	16	LF	6	\$404	
	Ceiling - Plaster/Drywall	1st Floor	1,107	SF	6	\$3,831	
	Chalk Board	1st Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface	1st Floor	27	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	1,185	SF	6	\$3,474	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classroom #117 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Walls - Concrete Block	1st Floor	975	SF	6	\$2,858	
Classroom #120 (Art Room)							
	Ceiling - Lay-in	1st Floor	1,107	SF	6	\$3,324	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #120 (Art Room)							
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface	1st Floor	27	EA	7	\$0	
	Storage/ Closet	1st Floor	40	SF	6	\$290	
	Walls - Concrete Block	1st Floor	1,185	SF	6	\$3,474	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classroom #122 (Other)							
	Casework	1st Floor	48	LF	6	\$1,212	
	Ceiling - Plaster/Drywall	1st Floor	1,107	SF	6	\$3,831	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface	1st Floor	27	EA	7	\$0	
	Storage/ Closet	1st Floor	40	SF	6	\$290	
	Walls - Concrete Block	1st Floor	1,185	SF	6	\$3,474	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classroom #211 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	
Classroom #212 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #213 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Splined	2nd Floor	736	SF	6	\$600	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	
Classroom #214 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	
Classroom #215 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	
Classroom #216 (Computer Lab)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	1,107	SF	6	\$3,324	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,107	SF	6	\$1,108	
	Lighting - Lay-in	2nd Floor	27	EA	6	\$3,212	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	1,185	SF	6	\$3,474	
	Wireless System	2nd Floor	1	EA	6	\$372	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #216 (Computer Lab)							
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #217 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	736	SF	6	\$2,547	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	
Classroom #218 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Splined	2nd Floor	643	SF	6	\$524	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	643	SF	5	\$2,887	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Marker Board	2nd Floor	5	LF	6	\$107	
	Walls - Concrete Block	2nd Floor	960	SF	6	\$2,814	
Classroom #220 (Music Room)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Ceiling - Splined	2nd Floor	1,500	SF	6	\$1,223	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	2nd Floor	1,500	SF	6	\$7,851	Rubber mat
	Lighting - Pendent/Surface	2nd Floor	27	EA	6	\$3,345	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Storage/ Closet	2nd Floor	30	SF	6	\$218	
	Walls - Concrete Block	2nd Floor	585	SF	6	\$1,715	
	Walls - Plaster/Drywall	2nd Floor	585	SF	6	\$1,615	
Classroom #221 (Regular Classroom)							
	AC Units	2nd Floor	2	EA	7	\$0	
	Ceiling - Splined	2nd Floor	2,313	SF	6	\$1,885	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	2,313	SF	6	\$2,315	
	Lighting - Pendent/Surface	2nd Floor	31	EA	7	\$0	Multiple Light Fixture Covers Missing

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #221 (Regular Classroom)							
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	1,150	SF	6	\$3,371	
	Walls - Plaster/Drywall	2nd Floor	1,150	SF	6	\$3,174	
Classroom #223 (Regular Classroom)							
	AC Units	2nd Floor	2	EA	6	\$991	
	Casework	2nd Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	2nd Floor	1,120	SF	6	\$3,876	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,120	SF	6	\$1,121	
	Lighting - Pendent/Surface	2nd Floor	30	EA	6	\$3,717	
	Walls - Concrete Block	2nd Floor	980	SF	6	\$2,873	Work Sink Provided
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #225 (Computer Lab)							
	AC Units	2nd Floor	4	EA	6	\$1,982	
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Plaster/Drywall	2nd Floor	1,500	SF	6	\$5,191	
	Chalk Board	2nd Floor	20	LF	6	\$446	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Carpet	2nd Floor	1,500	SF	5	\$7,701	Trip hazard
	Lighting - Pendent/Surface	2nd Floor	36	EA	6	\$4,460	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	1,170	SF	6	\$3,430	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #226 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	736	SF	6	\$2,210	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	736	SF	6	\$737	
	Lighting - Lay-in	2nd Floor	18	EA	6	\$2,142	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	975	SF	6	\$2,858	
Classroom #311 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #311 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	736	SF	6	\$2,210	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	736	SF	6	\$737	
	Lighting - Lay-in	3rd Floor	21	EA	6	\$2,498	
	Marker Board	3rd Floor	40	LF	6	\$857	
	Walls - Concrete Block	3rd Floor	975	SF	6	\$2,858	
	Walls - Plaster/Drywall	3rd Floor	50	SF	5	\$379	Peeling paint
Classroom #312 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	736	SF	6	\$2,210	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	736	SF	6	\$737	
	Lighting - Lay-in	3rd Floor	18	EA	6	\$2,142	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	975	SF	6	\$2,858	
	Walls - Plaster/Drywall	3rd Floor	50	SF	5	\$379	Peeled paint
Classroom #313 (Computer Lab)							
	AC Units	3rd Floor	1	EA	4	\$6,086	Not working
	AC Units	3rd Floor	1	EA	7	\$0	
	Ceiling - Lay-in	3rd Floor	1,120	SF	6	\$3,363	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,120	SF	6	\$1,121	
	Lighting - Lay-in	3rd Floor	30	EA	6	\$3,569	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	1,135	SF	6	\$3,327	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #314							
	Ceiling - Lay-in	3rd Floor	736	SF	6	\$2,210	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	736	SF	6	\$1,610	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	975	SF	6	\$2,858	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #315 (Computer Lab)							
	AC Units	3rd Floor	2	EA	6	\$991	
	Ceiling - Lay-in	3rd Floor	1,120	SF	6	\$3,972	
	Ceiling - Lay-in	3rd Floor	1,112	SF	5	\$7,712	Water stain
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,120	SF	6	\$1,121	
	Lighting - Lay-in	3rd Floor	30	EA	5	\$4,866	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	1,135	SF	6	\$3,327	
	Walls - Plaster/Drywall	3rd Floor	36	SF	5	\$273	Peeling paint
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #316 (Computer Lab)							
	AC Units		2	EA	6	\$991	
	Casework		20	LF	6	\$505	
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		1,107	SF	6	\$1,108	
	Lighting - Lay-in		27	EA	6	\$3,212	
	Marker Board		20	LF	6	\$428	
	Walls - Concrete Block		1,185	SF	6	\$3,474	
	Work Sink		1	EA	6	\$379	
Classroom #317 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	736	SF	6	\$2,210	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	736	SF	6	\$737	
	Lighting - Lay-in	3rd Floor	21	EA	6	\$2,498	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	975	SF	6	\$2,858	
Classroom #318 (Computer Lab)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	1,120	SF	6	\$3,363	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,120	SF	6	\$1,121	
	Lighting - Lay-in	3rd Floor	30	EA	6	\$3,569	
	Marker Board	3rd Floor	20	LF	6	\$428	

Building: Addition 1
Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #318 (Computer Lab)							
	Walls - Concrete Block	3rd Floor	1,325	SF	6	\$3,884	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #319 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	736	SF	6	\$2,210	
	Ceiling - Lay-in	3rd Floor	12	SF	5	\$96	Water stain
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	724	SF	6	\$725	
	Lighting - Lay-in	3rd Floor	18	EA	6	\$2,142	
	Marker Board	3rd Floor	40	LF	6	\$857	
	Walls - Concrete Block	3rd Floor	975	SF	6	\$2,858	
Classroom #320 (Choral Room)							
	AC Units		2	EA	6	\$991	
	Casework		32	LF	6	\$808	
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Chalk Board		16	LF	6	\$357	
	Doors - Wood Doors inclu hw		3	EA	6	\$903	
	Floor - Tile/Sheet		1,087	SF	6	\$1,088	
	Floor - Tile/Sheet		20	SF	5	\$115	
	Lighting - Lay-in		27	EA	6	\$3,212	
	Walls - Concrete Block		1,185	SF	6	\$3,474	
Classroom #322 (Band Room)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	1,250	SF	6	\$3,754	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,240	SF	6	\$1,241	
	Floor - Tile/Sheet	3rd Floor	10	SF	5	\$58	Damaged
	Lighting - Lay-in	3rd Floor	37	EA	6	\$4,402	
	Walls - Concrete Block	3rd Floor	1,250	SF	6	\$3,664	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #323 (Art Room)							
	AC Units	3rd Floor	2	EA	4	\$12,173	Not working
	Casework	3rd Floor	75	LF	6	\$1,894	
	Ceiling - Lay-in	3rd Floor	1,120	SF	6	\$3,363	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #323 (Art Room)							
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,120	SF	6	\$1,121	
	Lighting - Lay-in	3rd Floor	30	EA	6	\$3,569	
	Walls - Concrete Block	3rd Floor	1,150	SF	6	\$3,371	
	Walls - Plaster/Drywall	3rd Floor	50	SF	5	\$379	Peeling paint
	Work Sink	3rd Floor	2	EA	6	\$758	
Classroom #324 (Regular Classroom)							
	AC Units		1	EA	4	\$6,086	Not working
	Ceiling - Lay-in		375	SF	6	\$1,126	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		375	SF	6	\$375	
	Lighting - Lay-in		6	EA	6	\$714	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		700	SF	6	\$2,052	
Classroom #325 (Art Room)							
	AC Units	3rd Floor	1	EA	4	\$6,086	Not working
	Casework	3rd Floor	75	LF	6	\$1,894	
	Ceiling - Lay-in	3rd Floor	1,120	SF	6	\$3,363	
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,120	SF	6	\$1,121	
	Instructional Surface	3rd Floor	10	LF	6	\$337	
	Lighting - Lay-in	3rd Floor	30	EA	6	\$3,569	
	Walls - Concrete Block	3rd Floor	980	SF	6	\$2,873	
	Work Sink	3rd Floor	2	EA	6	\$758	
Classroom #326 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Ceiling - Lay-in	3rd Floor	736	SF	6	\$2,210	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	736	SF	6	\$1,610	
	Lighting - Lay-in	3rd Floor	18	EA	6	\$2,142	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	965	SF	6	\$2,829	
	Walls - Concrete Block	3rd Floor	10	SF	5	\$141	Cracking

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classrooms Subtotal:						\$458,489	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	AC Unit	1st FL-Nurse office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st FL-Nurse office	275	SF	6	\$952	
	Doors - Wood Doors inclu hw	1st FL-Nurse office	2	EA	6	\$602	
	Floor - Tile/Sheet	1st FL-Nurse office	275	SF	6	\$275	
	Lighting - Pendent/Surface	1st FL-Nurse office	3	EA	7	\$0	
	Power Distribution	1st FL-Nurse office	10	EA	6	\$21,249	
	Walls - Concrete Block	1st FL-Nurse office	650	SF	6	\$1,905	
	AC Unit	211A Social Work	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	211A Social Work	275	SF	6	\$952	
	Doors - Wood Doors inclu hw	211A Social Work	1	EA	6	\$301	
	Floor - Carpet	211A Social Work	275	SF	6	\$586	
	Lighting - Pendent/Surface	211A Social Work	3	EA	7	\$0	
	Power Distribution	211A Social Work	10	EA	6	\$21,249	
	Walls - Concrete Block	211A Social Work	650	SF	6	\$1,905	
	Ceiling - Plaster/Drywall	222	252	SF	6	\$872	
	Doors - Wood Doors inclu hw	222	1	EA	6	\$301	
	Floor - Tile/Sheet	222	252	SF	6	\$252	
	Lighting - Pendent/Surface	222	3	EA	7	\$0	
	Power Distribution	222	6	EA	6	\$12,749	
	Walls - Concrete Block	222	597	SF	6	\$1,750	
	AC Unit	227 Asst. Principals Office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	227 Asst. Principals Office	275	SF	6	\$952	
	Doors - Wood Doors inclu hw	227 Asst. Principals Office	1	EA	6	\$301	
	Floor - Carpet	227 Asst. Principals Office	275	SF	6	\$586	
	Lighting - Pendent/Surface	227 Asst. Principals Office	3	EA	7	\$0	T12 Bulbs
	Power Distribution	227 Asst. Principals Office	10	EA	6	\$21,249	
	Walls - Concrete Block	227 Asst. Principals Office	650	SF	6	\$1,905	
	AC Unit	327	1	EA	6	\$496	
	Ceiling - Lay-in	327	275	SF	6	\$826	
	Doors - Transom Window	327	1	SF	6	\$17	
	Floor - Tile	327	275	SF	6	\$602	

Building: Addition 1
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	327	3	EA	6	\$357	
	Power Distribution	327	10	EA	6	\$21,249	
	Walls - Concrete Block	327	650	SF	6	\$1,905	
	Ceiling - Plaster/Drywall	Kitchen Office	80	SF	6	\$277	
	Doors - Wood Doors inclu hw	Kitchen Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Kitchen Office	80	SF	6	\$169	
	Lighting - Pendent/Surface	Kitchen Office	2	EA	7	\$0	
	Power Distribution	Kitchen Office	4	EA	6	\$8,500	
	Walls - Structural Glazed Tile	Kitchen Office	350	SF	6	\$1,101	
Kitchen							
	Ceiling - Plaster/Drywall	1st Floor	960	SF	6	\$3,322	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Floor	960	SF	6	\$2,032	
	Lighting - Pendent/Surface	1st Floor	19	EA	7	\$0	
	Storage/ Closet	1st Floor	120	SF	6	\$870	
	Walls - Structural Glazed Tile	1st Floor	1,880	SF	6	\$5,914	
Lunch & Multipurpose Room							
	Ceiling - Plaster/Drywall	1st floor girls	1,500	SF	6	\$5,191	
	Doors - Wood Doors inclu hw	1st floor girls	2	EA	6	\$602	
	Floor - Tile/Sheet	1st floor girls	1,500	SF	6	\$1,502	
	Lighting - Pendent/Surface	1st floor girls	20	EA	7	\$0	
	Market Board	1st floor girls	12	LF	6	\$257	
	Storage/ Closet	1st floor girls	60	SF	6	\$435	
	Walls - Concrete Block	1st floor girls	400	SF	6	\$1,173	
	Walls - Structural Glazed Tile	1st floor girls	1,000	SF	6	\$3,146	
	Ceiling - Splined	1st Floor	4,028	SF	6	\$3,283	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	4,028	SF	6	\$4,032	2888 SF is Vinyl Tile with the remaining 1,140 ceramic tile
	Lighting - Pendent/Surface	1st Floor	61	EA	7	\$0	
	Serving Line	1st Floor	16	LF	6	\$952	
	Walls - Structural Glazed Tile	1st Floor	4,580	SF	6	\$14,409	
Mechanical/ Service Rooms							
	Janitor's Closet	2nd Floor	57	SF	6	\$408	
	Janitor's Closet	2nd Floor	77	SF	6	\$552	
	Storage Room	2nd Floor	389	SF	6	\$2,787	218 Book storage

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Crawl Space - Unfinished	Basement	73,000	SF	6	\$452,009	
Restroom							
	Accessories	1st Fl - Boys	290	SF	6	\$2,675	
	Ceiling - Plaster/Drywall	1st Fl - Boys	290	SF	6	\$1,004	
	Doors - Wood Doors inclu hw	1st Fl - Boys	2	EA	6	\$602	
	Floor Drain	1st Fl - Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl - Boys	290	SF	6	\$614	
	Hand Dryer	1st Fl - Boys	2	EA	6	\$460	
	Lavatory	1st Fl - Boys	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Fl - Boys	4	EA	7	\$0	
	Partitions	1st Fl - Boys	4	EA	6	\$1,188	
	Urinals	1st Fl - Boys	4	EA	6	\$1,344	
	Walls - Structural Glazed Tile	1st Fl - Boys	760	SF	6	\$2,391	
	Water Closet	1st Fl - Boys	4	EA	6	\$1,344	
	Accessories	1st FL - Girls	290	SF	6	\$2,675	
	Ceiling - Plaster/Drywall	1st FL - Girls	290	SF	6	\$1,004	
	Doors - Wood Doors inclu hw	1st FL - Girls	2	EA	6	\$602	
	Floor Drain	1st FL - Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FL - Girls	290	SF	6	\$614	
	Hand Dryer	1st FL - Girls	2	EA	6	\$460	
	Lavatory	1st FL - Girls	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st FL - Girls	4	EA	7	\$0	
	Partitions	1st FL - Girls	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	1st FL - Girls	760	SF	6	\$2,391	
	Water Closet	1st FL - Girls	6	EA	6	\$2,016	
	Accessories	1st FL - Nurse Office	80	SF	6	\$738	
	Ceiling - Plaster/Drywall	1st FL - Nurse Office	80	SF	6	\$277	
	Doors - Wood Doors inclu hw	1st FL - Nurse Office	1	EA	6	\$301	
	Floor Drain	1st FL - Nurse Office	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st FL - Nurse Office	80	SF	6	\$80	
	Lavatory	1st FL - Nurse Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st FL - Nurse Office	1	EA	7	\$0	
	Partitions	1st FL - Nurse Office	2	EA	6	\$594	
	Walls - Concrete Block	1st FL - Nurse Office	340	SF	6	\$997	
	Water Closet	1st FL - Nurse Office	2	EA	6	\$672	
	Accessories	1st floor girls inside locker room	70	SF	6	\$646	
	Ceiling - Plaster/Drywall	1st floor girls inside locker room	70	SF	6	\$242	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	1st floor girls inside locker room	1	EA	6	\$301	
	Floor Drain	1st floor girls inside locker room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor girls inside locker room	70	SF	6	\$148	
	Lavatory	1st floor girls inside locker room	2	EA	6	\$639	
	Lighting - Lay-in	1st floor girls inside locker room	1	EA	7	\$0	
	Partitions	1st floor girls inside locker room	2	EA	6	\$594	
	Walls - Structural Glazed Tile	1st floor girls inside locker room	250	SF	6	\$787	
	Water Closet	1st floor girls inside locker room	2	EA	6	\$672	
	Accessories	211A Women staff	60	SF	6	\$553	
	Ceiling - Plaster/Drywall	211A Women staff	60	SF	6	\$208	
	Doors - Wood Doors inclu hw	211A Women staff	1	EA	6	\$301	
	Floor - Tile/Sheet	211A Women staff	60	SF	5	\$269	
	Lavatory	211A Women staff	1	EA	5	\$1,590	
	Lighting - Pendant/Surface	211A Women staff	1	EA	6	\$124	
	Partitions	211A Women staff	2	EA	5	\$1,502	
	Walls - Concrete Block	211A Women staff	318	SF	6	\$932	
	Water Closet	211A Women staff	2	EA	6	\$672	
	Accessories	2nd across 214 Girls	320	SF	6	\$2,952	
	Ceiling - Plaster/Drywall	2nd across 214 Girls	320	SF	6	\$1,107	
	Doors - Wood Doors inclu hw	2nd across 214 Girls	3	EA	6	\$903	
	Floor Drain	2nd across 214 Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd across 214 Girls	320	SF	6	\$677	
	Lavatory	2nd across 214 Girls	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	2nd across 214 Girls	4	EA	6	\$496	
	Partitions	2nd across 214 Girls	7	EA	6	\$2,078	
	Walls - Structural Glazed Tile	2nd across 214 Girls	771	SF	6	\$2,426	
	Water Closet	2nd across 214 Girls	7	EA	6	\$2,352	
	Accessories	2nd FL across 226 Men staff- ASST. Principals Office	80	SF	6	\$738	
	Ceiling - Plaster/Drywall	2nd FL across 226 Men staff- ASST. Principals Office	80	SF	6	\$277	
	Doors - Wood Doors inclu hw	2nd FL across 226 Men staff- ASST. Principals Office	1	EA	6	\$301	
	Floor Drain	2nd FL across 226 Men staff- ASST. Principals Office	1	EA	6	\$1,059	
	Floor - Tile/Sheet	2nd FL across 226 Men staff- ASST. Principals Office	80	SF	6	\$80	
	Lavatory	2nd FL across 226 Men staff- ASST. Principals Office	1	EA	6	\$320	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Pendent/Surface	2nd FL across 226 Men staff- ASST. Principals Office	1	EA	6	\$124	
	Partitions	2nd FL across 226 Men staff- ASST. Principals Office	1	EA	6	\$297	
	Water Closet	2nd FL across 226 Men staff- ASST. Principals Office	1	EA	6	\$336	
	Accessories	2nd next to 220 Boys Storage	320	SF	6	\$2,952	
	Ceiling - Plaster/Drywall	2nd next to 220 Boys Storage	320	SF	6	\$1,107	
	Doors - Wood Doors inclu hw	2nd next to 220 Boys Storage	2	EA	6	\$602	
	Floor Drain	2nd next to 220 Boys Storage	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd next to 220 Boys Storage	320	SF	6	\$677	
	Lighting - Pendent/Surface	2nd next to 220 Boys Storage	4	EA	6	\$496	
	Walls - Structural Glazed Tile	2nd next to 220 Boys Storage	771	SF	6	\$2,426	
	Accessories	3rd near 314 Men	80	SF	6	\$738	
	Ceiling - Plaster/Drywall	3rd near 314 Men	80	SF	6	\$277	
	Doors - Wood Doors inclu hw	3rd near 314 Men	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd near 314 Men	80	SF	6	\$169	
	Lavatory	3rd near 314 Men	1	EA	6	\$320	
	Lighting - Pendent/Surface	3rd near 314 Men	1	EA	6	\$124	
	Partitions	3rd near 314 Men	1	EA	6	\$297	
	Urinals	3rd near 314 Men	1	EA	6	\$336	
	Walls - Concrete Block	3rd near 314 Men	290	SF	6	\$850	
	Water Closet	3rd near 314 Men	1	EA	6	\$336	
	Accessories	3rd near 318 Girls Storage	320	SF	6	\$2,952	
	Ceiling - Plaster/Drywall	3rd near 318 Girls Storage	320	SF	6	\$1,107	
	Doors - Wood Doors inclu hw	3rd near 318 Girls Storage	3	EA	6	\$903	
	Floor - Tile Ceramic/ Porcelain	3rd near 318 Girls Storage	320	SF	6	\$677	Space used as storage
	Lavatory	3rd near 318 Girls Storage	4	EA	5	\$6,359	
	Lighting - Pendent/Surface	3rd near 318 Girls Storage	4	EA	6	\$496	
	Walls - Structural Glazed Tile	3rd near 318 Girls Storage	771	SF	6	\$2,426	
	Water Closet	3rd near 318 Girls Storage	7	EA	6	\$2,352	
	Accessories	3rd near 320 Boys Storage	320	SF	6	\$2,952	
	Ceiling - Plaster/Drywall	3rd near 320 Boys Storage	320	SF	6	\$1,107	
	Doors - Wood Doors inclu hw	3rd near 320 Boys Storage	2	EA	6	\$602	
	Floor Drain	3rd near 320 Boys Storage	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd near 320 Boys Storage	320	SF	6	\$677	Space used as storage
	Lighting - Pendent/Surface	3rd near 320 Boys Storage	4	EA	6	\$496	
	Urinals	3rd near 320 Boys Storage	2	EA	5	\$2,688	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Structural Glazed Tile	3rd near 320 Boys Storage	771	SF	6	\$2,426	
	Accessories	3rd near 327 Unisex	80	SF	6	\$738	
	Ceiling - Lay-in	3rd near 327 Unisex	80	SF	6	\$240	
	Doors - Wood Doors inclu hw	3rd near 327 Unisex	1	EA	6	\$301	
	Floor Drain	3rd near 327 Unisex	1	EA	6	\$1,059	
	Floor - Tile/Sheet	3rd near 327 Unisex	80	SF	6	\$80	
	Lavatory	3rd near 327 Unisex	1	EA	6	\$320	
	Lighting - Lay-in	3rd near 327 Unisex	1	EA	6	\$119	
	Partitions	3rd near 327 Unisex	2	EA	6	\$594	
	Walls - Concrete Block	3rd near 327 Unisex	340	SF	6	\$997	
	Water Closet	3rd near 327 Unisex	2	EA	6	\$672	

Rooms (Other Than Classrooms) Subtotal:

\$739,823

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	228	SF	6	\$685	
	Ceiling - Plaster/Drywall	1st Floor	3,993	SF	6	\$24,724	
	Doors - Store Front	1st Floor	3	EA	6	\$3,625	
	Doors - Transom Window	1st Floor	18	EA	6	\$305	
	Doors - Wood Doors include hw	1st Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	1st Floor	3	EA	4	\$11,724	
	Drinking Fountains - Single Water Cooler	1st Floor	1	EA	6	\$317	
	Floor - Tile Ceramic/ Porcelain	1st Floor	312	SF	6	\$870	
	Floor - Tile/Sheet	1st Floor	3,973	SF	6	\$2,159	
	Floor - Tile/Sheet	1st Floor	30	SF	6	\$32	metal ramp
	Floor - Tile/Sheet	1st Floor	20	SF	5	\$115	missing or damaged
	Lighting - Lay-in	1st Floor	52	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	2	EA	6	\$248	
	Student Lockers - One Tier	1st Floor	100	EA	6	\$9,284	
	Walls - Concrete Block	1st Floor	1,235	SF	6	\$3,620	
	Walls - Structural Glazed Tile	1st Floor	4,940	SF	6	\$15,541	
	Ceiling - Plaster/Drywall	2nd Floor	3,993	SF	6	\$24,724	
	Drinking Fountains - Single Fountain	2nd Floor	4	EA	4	\$15,632	
	Floor - Tile/Sheet	2nd Floor	3,993	SF	6	\$2,170	

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Lighting - Pendent/Surface	2nd Floor	52	EA	6	\$6,443	
	Student Lockers - One Tier	2nd Floor	116	EA	6	\$10,769	
	Walls - Concrete Block	2nd Floor	1,235	SF	6	\$3,620	
	Walls - Plaster/Drywall	2nd Floor	309	SF	5	\$2,280	peeling paint
	Walls - Structural Glazed Tile	2nd Floor	4,940	SF	6	\$15,541	
	Ceiling - Lay-in	3rd Floor	3,993	SF	6	\$11,991	
	Ceiling - Lay-in	3rd Floor	32	SF	5	\$286	water staining
	Doors - Steel Doors incl hw	3rd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	4	\$7,816	
	Floor - Tile/Sheet	3rd Floor	3,983	SF	6	\$2,164	
	Floor - Tile/Sheet	3rd Floor	10	SF	5	\$58	Misisng or damaged tiles throughout
	Lighting - Lay-in	3rd Floor	52	EA	6	\$6,187	
	Student Lockers - One Tier	3rd Floor	124	EA	6	\$11,512	
	Walls - Concrete Block	3rd Floor	1,235	SF	6	\$3,620	
	Walls - Plaster/Drywall	3rd Floor	309	SF	5	\$2,280	Peeling paint
	Walls - Structural Glazed Tile	3rd Floor	4,940	SF	6	\$15,541	
Safety							
	Metal Dedector	Entire Building / 1st Floor	1	EA	6	\$881	
	Security Cameras	Entire Building	3	EA	6	\$582	
	Security Cameras	Entire Building	3	EA	6	\$582	
Stairs							
	Ceiling - Plaster/Drywall	Basement North	210	SF	6	\$1,538	
	Floor - Concrete	Basement North	80	SF	6	\$42	
	Handrails	Basement North	42	LF	6	\$364	
	Lighting - Pendent/Surface	Basement North	1	EA	6	\$124	
	Stairs - Concrete	Basement North	20	LF	6	\$166	
	Walls - Concrete Block	Basement North	945	SF	6	\$2,770	
	Ceiling - Plaster/Drywall	Basement South	210	SF	6	\$1,538	
	Floor - Concrete	Basement South	80	SF	6	\$42	
	Handrails	Basement South	42	LF	6	\$364	
	Lighting - Pendent/Surface	Basement South	1	EA	7	\$0	
	Stairs - Concrete	Basement South	20	LF	6	\$166	
	Walls - Concrete Block	Basement South	945	SF	6	\$2,770	
	Ceiling - Lay-in	North Stair	705	SF	6	\$2,117	
	Floor - Terrazzo	North Stair	610	SF	6	\$5,120	
	Handrails	North Stair	132	LF	6	\$1,144	

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Lighting - Lay-in	North Stair	5	EA	6	\$595	
	Lighting - Wall Mounted	North Stair	2	EA	6	\$248	
	Stairs - Terrazzo	North Stair	66	LF	6	\$613	
	Walls - Concrete Block	North Stair	1,216	SF	6	\$3,565	
	Walls - Structural Glazed Tile	North Stair	1,216	SF	6	\$3,826	
	Ceiling - Lay-in	South Stair	705	SF	6	\$2,117	
	Floor - Terrazzo	South Stair	610	SF	6	\$5,120	
	Handrails	South Stair	132	LF	6	\$1,144	
	Lighting - Lay-in	South Stair	5	EA	6	\$595	
	Lighting - Wall Mounted	South Stair	2	EA	6	\$248	
	Stairs - Terrazzo	South Stair	36	LF	6	\$334	
	Walls - Concrete Block	South Stair	1,216	SF	6	\$3,565	
	Walls - Structural Glazed Tile	South Stair	1,216	SF	6	\$3,826	

Building Interior Subtotal:

\$264,394

Total Building Cost

\$4,139,440

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Steel Door	Door 10 - North	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Door 11 - South	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Door 14 - Roof	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	Door 8 - North courtyard	4	EA	6	\$1,922	
	Exterior Doors - Exterior Wood Door	Door 9 - Northeast gym	1	EA	6	\$481	
	Exterior Doors - Transom Lite	Door 11 - South	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Door 8 - North courtyard	4	EA	6	\$1,253	
	Exterior Stairs - Concrete	Door 10 - North	18	LF	6	\$1,472	
	Exterior Stairs - Concrete	Door 11 - South	40	LF	6	\$3,271	
	Exterior Stairs - Concrete	Door 8 - North courtyard	40	LF	6	\$3,271	
	Exterior Stairs - Concrete	Door 9 - Northeast gym	14	LF	6	\$1,145	
	Ramp Handrail - Steel_Ramp Handrail	Door 8 - North courtyard	30	LF	5	\$318	Rust
	Ramps - Concrete	Door 8 - North courtyard	30	LF	6	\$4,507	
	Stair Handrail - Steel_Stair Handrail	Door 10 - North	12	LF	5	\$138	Rust

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Stair Handrail - Steel_Stair Handrail	Door 11 - South	12	LF	5	\$138	Rust
	Stair Handrail - Steel_Stair Handrail	Door 8 - North courtyard	20	LF	5	\$230	Rust
	Stair Handrail - Steel_Stair Handrail	Door 9 - Northeast gym	10	LF	5	\$115	Rust
Foundation							
	Foundation - Concrete	Entire Building	592	LF	7	\$0	
	Foundation - Concrete	Entire Building / South East	50	LF	5	\$27,597	Active movement of foundation, large, expanding step cracks in masonry above
	Superstructure - Metal Deck/ Concrete Topping	Entire Building	37,400	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	6	EA	6	\$3,219	
	Exterior Lighting - Wall Mounted	Entire Building	12	EA	6	\$3,465	
Roof System							
	Chimney - Metal Flue	Roof 1	15	LF	6	\$2,372	
	Coping - Metal	Roof 1	600	LF	6	\$19,271	
	Coping - Metal	Roof 1 / North West	78	LF	4	\$6,907	Heavy rust
	Coping - Metal	Roof 2	108	LF	6	\$3,469	
	Coping - Metal	Roof 3	109	LF	6	\$3,501	
	Downspouts - Interior Downspouts	Roof 1	180	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 2	12	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 3	17	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 1	678	LF	6	\$14,446	
	Parapet - Parapet < 16" Height	Roof 2	108	LF	6	\$2,301	
	Parapet - Parapet < 16" Height	Roof 3	109	LF	6	\$2,322	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 1	22,507	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 2	2,158	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 3	5,138	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Roof 1	22,507	SF	6	\$228,835	
	Roof - Asphalt Gravel Ballast	Roof 2	2,158	SF	4	\$60,484	vegetation, ponding
	Roof - Asphalt Gravel Ballast	Roof 3	5,138	SF	6	\$52,240	
Walls							
	Cheek-Wall - Concrete	Entire Building	20	SF	6	\$205	
	Exterior Walls - Brick	Entire Building	20,020	SF	6	\$134,554	
	Exterior Walls - Brick	Entire Building / South East	280	SF	4	\$46,102	Actively expanding large step cracks
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building / South Façade	230	SF	4	\$17,484	Deteriorated, separating
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building / South Façade	120	SF	6	\$782	

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Windows							
	Guard - Guards perforated	Entire Building	360	SF	6	\$4,597	
	Lintels - Steel	Entire Building	50	LF	6	\$1,451	
	Windows - Sash Aluminum Double-pane	Entire Building	360	SF	6	\$2,687	

Building Exterior Subtotal: \$659,269

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Corridors and Stairs	Entire Building	5,575	SF	6	\$1,674	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	7,830	SF	6	\$2,911	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	4,000	SF	6	\$1,487	
	Exit Signs - Corridors and Stairs	Entire Building	4	EA	6	\$599	
	Exit Signs - Gym	Entire Building / 1st Floor	5	EA	6	\$787	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	2	EA	6	\$299	
	Exit Signs - Pool	Entire Building / 1st Floor	3	EA	6	\$465	
	Security System - CCTV	Entire Building	37,400	SF	6	\$11,231	
	Security System - Intrusion Detection	Entire Building	37,400	SF	6	\$9,627	

Main Service

	PA System	Mechanical Room	37,400	SF	6	\$12,301	Serves main and additions. Control console located in main building.
--	-----------	-----------------	--------	----	---	----------	--

Power Distribution

	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Mechanical Room	1	EA	6	\$528	

Electrical System Subtotal: \$45,591

Building: Addition 2

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Addition 2

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	37,400	SF	6	\$13,371	
	Fire Alarm_System	Entire Building	37,400	SF	6	\$18,184	

Safty System Subtotal: \$31,554

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - 11-20 tons	Roof	1	EA	6	\$3,727	
	Condensing Unit- Roof Mounted - 5-10 tons	Roof	1	EA	5	\$9,590	Serves pool AHU. Nameplate damaged, no model number available.

Air Handling Systems

	Air Handling Unit-Package Single Zone- Indoor- Hot Water and DX Cooling Coils - 8001-12000 cfm	Mechanical Room	1	EA	5	\$38,893	Serves the pool.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - 4000-8000 cfm	Mechanical Room	1	EA	5	\$26,442	Serves the lunchroom.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - 8001-12000 cfm	Mechanical Room	1	EA	5	\$34,175	Serves the Gym.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - Less than 4000 cfm	Mechanical Room	1	EA	5	\$20,373	Serves the Girl's Locker Room.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water Coils - Less than 4000 cfm	Mechanical Room	1	EA	5	\$20,373	Serves the Boy's Locker Room.
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / South Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / South Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / West Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / West Façade	1	EA	6	\$5,765	

Boiler Systems

	Boiler Auxiliary- Non Condensing Hot Water - Less than 500 MBH	Mechanical Room	11	EA	5	\$186,074	
	Chemical Pot Feeder	Mechanical Room	1	EA	6	\$725	
	Combustion Dampers	Mechanical Room	1	EA	6	\$409	
	Hot Water Pump	Mechanical Room	2	EA	6	\$748	
	Non Condensing- Flexible Tube- Atmospheric- Hot Water Boiler - Less than 500 MBH	Mechanical Room	11	EA	5	\$253,505	Have significant draft issues causing exhaust to back feed into space.
	Water Fill System	Mechanical Room	1	EA	6	\$1,168	

Building: Addition 2
Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Heating Devices							
	Unit Heater - Hot Water	Mechanical Room	1	EA	6	\$279	
	Wall Heater - Electric	Entire Building	4	EA	6	\$556	
Mechanical Plumbing							
	Hydronic Supply and Return - Copper	Entire Building	150	LF	6	\$7,870	
Temperature Control							
	Pneumatic System	Entire Building	37,400	SF	6	\$19,788	System needs calibration.
	Thermostats - Pneumatic	Entire Building	6	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	9	EA	6	\$5,332	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	1	EA	6	\$296	
Mechanical System Subtotal:						\$660,332	

Building: Addition 2
Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	3	EA	6	\$930	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	37,400	SF	6	\$7,487	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	37,400	SF	6	\$9,092	
	Domestic Piping-Cold Water Risers	Entire Building	37,400	SF	6	\$6,953	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	37,400	SF	6	\$5,883	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	37,400	SF	6	\$6,953	
	Domestic Piping-Hot Water Return Lines	Entire Building	37,400	SF	6	\$5,348	
	Domestic Piping-Hot Water Return Risers	Entire Building	37,400	SF	6	\$5,348	
	Sanitary Piping	Entire Building	37,400	SF	6	\$34,228	
	Storm Piping	Entire Building	37,400	SF	6	\$32,624	
	Vent Piping	Entire Building	37,400	SF	6	\$25,137	
Pool Systems							
	Pool Drain Piping	1st Floor	50	LF	6	\$1,431	
	Pool Filtration System including Pump	1st Floor / Mechanical Room	1	EA	6	\$12,330	
	Pool Hot Water Heater - Gas Fired	1st Floor / Mechanical Room	1	EA	6	\$310	

Building: Addition 2

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pool Systems							
	Pool Supply and Return Piping	1st Floor	100	LF	6	\$4,805	

Plumbing System Subtotal:

\$158,859

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	125B - PE Office	105	SF	6	\$315	
	Doors - Side-lite	125B - PE Office	24	SF	6	\$401	
	Doors - Wood Doors inclu hw	125B - PE Office	1	EA	6	\$301	
	Floor - Tile	125B - PE Office	105	SF	6	\$230	
	Lighting - Lay-in	125B - PE Office	1	EA	7	\$0	
	Power Distribution	125B - PE Office	4	EA	6	\$8,500	
	Walls - Concrete Block	125B - PE Office	375	SF	6	\$1,099	
	Ceiling - Lay-in	Football Coach Office	231	SF	6	\$694	
	Doors - Wood Doors inclu hw	Football Coach Office	1	EA	6	\$301	
	Floor - Tile	Football Coach Office	231	SF	6	\$505	
	Lighting - Lay-in	Football Coach Office	2	EA	7	\$0	
	Power Distribution	Football Coach Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Football Coach Office	630	SF	6	\$1,847	
	Ceiling - Lay-in	Gym Office	125	SF	6	\$375	
	Doors - Wood Doors inclu hw	Gym Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Gym Office	125	SF	6	\$125	
	Lighting - Lay-in	Gym Office	2	EA	6	\$238	
	Power Distribution	Gym Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Gym Office	415	SF	6	\$1,217	

Gymnasia

	Bleacher Seating	1st Floor	520	EA	6	\$15,050	
	Ceiling - Lay-in	1st Floor	7,830	SF	6	\$23,513	
	Doors - Wood Doors inclu hw	1st Floor	6	EA	6	\$1,806	
	Floor - Wood	1st Floor	7,830	SF	6	\$55,201	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	44	EA	6	\$5,884	
	Scoreboards	1st Floor	1	EA	6	\$2,244	
	Storage/ Closet	1st Floor	230	SF	6	\$1,668	
	Walls - Concrete Block	1st Floor	8,600	SF	6	\$25,211	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Accessories	Men's Locker Room	3,041	SF	6	\$11,915	
	Benches, ped mounted	Men's Locker Room	40	LF	6	\$4,355	
	Ceiling - Plaster/ Drywall	Men's Locker Room	3,041	SF	6	\$10,524	
	Doors - Wood Doors inclu hw	Men's Locker Room	2	EA	6	\$602	
	Floor Drain	Men's Locker Room	27	EA	6	\$28,597	
	Floor - Tile Ceramic/ Porcelain	Men's Locker Room	3,016	SF	6	\$6,383	
	Floor - Tile Ceramic/ Porcelain	Men's Locker Room	25	SF	5	\$522	
	Hand Dryer	Men's Locker Room	2	EA	6	\$460	
	Lavatory	Men's Locker Room	3	EA	6	\$959	
	Lighting - Pendent/Surface	Men's Locker Room	30	EA	7	\$0	
	Partitions	Men's Locker Room	3	EA	6	\$891	
	Showers	Men's Locker Room	22	EA	6	\$6,851	
	Storage/ Closet	Men's Locker Room	96	SF	6	\$696	
	Student Lockers - One Tier	Men's Locker Room	120	EA	6	\$11,140	
	Urinals	Men's Locker Room	3	EA	6	\$1,008	
	Walls - Concrete Block	Men's Locker Room	6,460	SF	6	\$18,937	
	Water Closet	Men's Locker Room	3	EA	6	\$1,008	
	Accessories	Women's Locker Room	3,041	SF	6	\$11,915	
	Benches, ped mounted	Women's Locker Room	40	LF	6	\$4,355	
	Ceiling - Plaster/ Drywall	Women's Locker Room	3,041	SF	6	\$10,524	
	Doors - Wood Doors inclu hw	Women's Locker Room	2	EA	6	\$602	
	Floor Drain	Women's Locker Room	16	EA	6	\$16,947	
	Floor - Tile Ceramic/ Porcelain	Women's Locker Room	3,041	SF	6	\$6,436	
	Hand Dryer	Women's Locker Room	6	EA	6	\$1,380	
	Lavatory	Women's Locker Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	Women's Locker Room	30	EA	7	\$0	
	Partitions	Women's Locker Room	4	EA	6	\$1,188	
	Showers	Women's Locker Room	11	EA	6	\$3,426	
	Storage/ Closet	Women's Locker Room	96	SF	6	\$696	
	Student Lockers - One Tier	Women's Locker Room	120	EA	6	\$11,140	
	Walls - Concrete Block	Women's Locker Room	6,460	SF	6	\$18,937	
	Water Closet	Women's Locker Room	4	EA	6	\$1,344	
Lunch & Multipurpose Room							
	Ceiling - Lay-in	003 - Lunchroom	4,000	SF	6	\$12,012	
	Ceiling - Lay-in	003 - Lunchroom	660	SF	6	\$1,982	
	Doors - Wood Doors inclu hw	003 - Lunchroom	4	EA	6	\$1,204	
	Doors - Wood Doors inclu hw	003 - Lunchroom	5	EA	6	\$1,505	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Floor - Tile	003 - Lunchroom	660	SF	6	\$1,444	
	Floor - Tile/Sheet	003 - Lunchroom	4,000	SF	6	\$4,004	
	Lighting - Lay-in	003 - Lunchroom	16	EA	7	\$0	
	Lighting - Lay-in	003 - Lunchroom	45	EA	7	\$0	
	Serving Line	003 - Lunchroom	54	LF	6	\$3,214	
	Walls - Concrete Block	003 - Lunchroom	2,250	SF	6	\$6,596	
	Walls - Concrete Block	003 - Lunchroom	980	SF	6	\$2,873	
	Walls - Concrete Block	003 - Lunchroom	30	SF	5	\$423	Peeling paint at window wall
	Walls - Concrete Block	003 - Lunchroom	20	SF	5	\$282	Cracking
	Ceiling - Lay-in	2nd FL - Weight Room	550	SF	6	\$1,652	
	Ceiling - Splined	2nd FL - Weight Room	1,130	SF	6	\$921	
	Floor - Tile/Sheet	2nd FL - Weight Room	1,680	SF	5	\$7,544	Includes Interlocking Weight Room Flooring Tiles with vinyl tile underneath. Vinyl Tile ranking is a 5 and Interlocking Weight Room Flooring is ranked as 6.
	Lighting - Pendant/Surface	2nd FL - Weight Room	20	EA	4	\$10,813	T-12 bulbs
	Walls - Concrete Block	2nd FL - Weight Room	1,704	SF	6	\$4,995	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	25	SF	6	\$179	
	Mechanical/ Service Rooms	1st Floor	355	SF	6	\$2,543	
	Mechanical/ Service Rooms	1st Floor	41	SF	6	\$294	
	Mechanical/ Service Rooms	1st Floor	70	SF	6	\$502	
	Mechanical/ Service Rooms	2nd Floor	2,340	SF	6	\$16,764	
	Crawl Space - Unfinished	Basement	35,000	SF	6	\$216,717	
Pool & Natatorium							
	Accessories	1st Floor	6,910	SF	6	\$4,743	
	Ceiling - Plaster/ Drywall	1st Floor	6,910	SF	6	\$38,142	Sprayed on acoustical
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Lighting - Pendant/Surface	1st Floor	31	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	7	EA	7	\$0	
	Pool Basin	1st Floor	3,874	SF	6	\$131,072	
	Pool Deck	1st Floor	3,040	SF	6	\$28,865	
	Pool Deck Drains	1st Floor	8	EA	6	\$3,377	
	Storage/ Closet	1st Floor	105	SF	6	\$761	
	Walls - Concrete Block	1st Floor	6,980	SF	6	\$20,462	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Accessories	125 A - Unisex	155	SF	6	\$1,430	
	Ceiling - Plaster/Drywall	125 A - Unisex	155	SF	6	\$536	
	Doors - Wood Doors inclu hw	125 A - Unisex	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	125 A - Unisex	155	SF	6	\$328	
	Lavatory	125 A - Unisex	1	EA	6	\$320	
	Lighting - Pendent/Surface	125 A - Unisex	1	EA	6	\$124	
	Walls - Concrete Block	125 A - Unisex	420	SF	6	\$1,231	
	Water Closet	125 A - Unisex	1	EA	6	\$336	
	Accessories	125 B - PE Office	65	SF	6	\$600	
	Ceiling - Plaster/Drywall	125 B - PE Office	65	SF	6	\$225	
	Doors - Wood Doors inclu hw	125 B - PE Office	1	EA	6	\$301	
	Floor Drain	125 B - PE Office	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	125 B - PE Office	65	SF	6	\$138	
	Lavatory	125 B - PE Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	125 B - PE Office	1	EA	6	\$124	
	Walls - Concrete Block	125 B - PE Office	315	SF	6	\$923	
	Water Closet	125 B - PE Office	1	EA	6	\$336	
	Accessories	2nd FL - Boys	315	SF	6	\$2,905	
	Ceiling - Plaster/Drywall	2nd FL - Boys	315	SF	6	\$1,090	
	Doors - Wood Doors inclu hw	2nd FL - Boys	1	EA	6	\$301	
	Floor Drain	2nd FL - Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd FL - Boys	315	SF	6	\$667	
	Lavatory	2nd FL - Boys	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd FL - Boys	3	EA	4	\$1,622	T-12 bulbs
	Partitions	2nd FL - Boys	2	EA	6	\$594	
	Urinals	2nd FL - Boys	2	EA	6	\$672	
	Walls - Concrete Block	2nd FL - Boys	700	SF	6	\$2,052	
	Water Closet	2nd FL - Boys	2	EA	6	\$672	
	Accessories	2nd FL - Girls	315	SF	6	\$2,905	
	Ceiling - Plaster/Drywall	2nd FL - Girls	315	SF	6	\$1,090	
	Doors - Wood Doors inclu hw	2nd FL - Girls	1	EA	6	\$301	
	Floor Drain	2nd FL - Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd FL - Girls	315	SF	6	\$667	
	Hand Dryer	2nd FL - Girls	1	EA	6	\$230	
	Lavatory	2nd FL - Girls	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd FL - Girls	3	EA	4	\$1,622	T-12 bulbs
	Partitions	2nd FL - Girls	3	EA	6	\$891	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Concrete Block	2nd FL - Girls	700	SF	6	\$2,052	
	Water Closet	2nd FL - Girls	3	EA	6	\$1,008	
	Accessories	Gym Office (Coach Locker room)	189	SF	6	\$1,743	
	Ceiling - Plaster/Drywall	Gym Office (Coach Locker room)	89	SF	6	\$308	
	Doors - Wood Doors inclu hw	Gym Office (Coach Locker room)	1	EA	6	\$301	
	Floor Drain	Gym Office (Coach Locker room)	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	Gym Office (Coach Locker room)	189	SF	6	\$400	
	Lighting - Pendant/Surface	Gym Office (Coach Locker room)	3	EA	4	\$1,622	T-12 bulbs
	Showers	Gym Office (Coach Locker room)	4	EA	4	\$18,882	Inoperable
	Student Lockers - One Tier	Gym Office (Coach Locker room)	11	EA	6	\$1,021	
	Walls - Concrete Block	Gym Office (Coach Locker room)	580	SF	6	\$1,700	
	Walls - Concrete Block	Gym Office (Coach Locker room)	20	SF	5	\$282	Cracking

Rooms (Other Than Classrooms) Subtotal:

\$946,633

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	64	SF	5	\$571	Water staining and damage at several ceiling tiles
	Ceiling - Lay-in	1st Floor	3,143	SF	6	\$9,438	
	Ceiling - Plaster/Drywall	1st Floor	168	SF	6	\$1,040	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	4	\$7,816	Water pressure very low
	Drinking Fountains - Single Water Cooler	1st Floor	1	EA	6	\$317	
	Floor - Terrazzo	1st Floor	66	SF	6	\$554	
	Floor - Tile Ceramic/ Porcelain	1st Floor	102	SF	6	\$284	
	Floor - Tile/Sheet	1st Floor	3,207	SF	6	\$1,743	
	Floor - Tile/Sheet	1st Floor	50	SF	5	\$288	Damaged or missing
	Lighting - Lay-in	1st Floor	22	EA	6	\$2,617	
	Walls - Concrete Block	1st Floor	4,618	SF	6	\$13,538	
	Ceiling - Lay-in	2nd Floor	1,160	SF	6	\$3,483	Water staining and damage at several ceiling tiles
	Drinking Fountains - Single Fountain	2nd Floor	1	EA	6	\$276	
	Floor - Tile/Sheet	2nd Floor	1,160	SF	6	\$630	
	Lighting - Lay-in	2nd Floor	20	EA	6	\$2,380	
	Walls - Concrete Block	2nd Floor	2,470	SF	6	\$7,241	
	Ceiling - Lay-in	2nd Gym Corridor	10	SF	5	\$89	Water stained ceiling tiles

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	2nd Gym Corridor	705	SF	6	\$2,117	
	Drinking Fountains - Single Fountain	2nd Gym Corridor	1	EA	4	\$3,908	
	Floor - Carpet	2nd Gym Corridor	715	SF	6	\$1,523	
	Lighting - Lay-in	2nd Gym Corridor	8	EA	7	\$0	
	Walls - Concrete Block	2nd Gym Corridor	1,350	SF	6	\$3,958	
	Ceiling - Lay-in	Gym Corridor	765	SF	6	\$2,297	Water staining and damage at several ceiling tiles
	Drinking Fountains - Single Fountain	Gym Corridor	2	EA	6	\$551	
	Floor - Tile Ceramic/ Porcelain	Gym Corridor	150	SF	6	\$418	
	Floor - Tile/Sheet	Gym Corridor	615	SF	6	\$334	
	Lighting - Lay-in	Gym Corridor	8	EA	7	\$0	
	Walls - Concrete Block	Gym Corridor	1,458	SF	6	\$4,274	
Safety							
	Security Cameras	Entire Building	1	EA	6	\$194	
	Security Cameras	Entire Building	5	EA	6	\$970	
Stairs							
	Ceiling - Lay-in	North Stair	115	SF	5	\$758	damaged
	Floor - Tile Ceramic/ Porcelain	North Stair	16	SF	6	\$107	
	Handrails	North Stair	40	LF	6	\$347	
	Lighting - Lay-in	North Stair	1	EA	7	\$0	
	Lighting - Wall Mounted	North Stair	2	EA	7	\$0	
	Stairs - Concrete	North Stair	22	LF	6	\$182	
	Walls - Concrete Block	North Stair	720	SF	6	\$2,111	
	Ceiling - Lay-in	South Stair	110	SF	6	\$330	
	Floor - Concrete	South Stair	102	SF	6	\$54	
	Handrails	South Stair	40	LF	6	\$347	
	Lighting - Lay-in	South Stair	1	EA	6	\$119	
	Lighting - Wall Mounted	South Stair	2	EA	6	\$248	
	Stairs - Terrazzo	South Stair	20	LF	6	\$186	
	Walls - Concrete Block	South Stair	720	SF	6	\$2,111	

Building Interior Subtotal: \$80,955

Total Building Cost \$2,583,194

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	3	EA	7	\$0	
	Civil/ Drainage - Catch Basin	Entire Site / Parking Lot	2	EA	4	\$8,239	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	6	\$310	
	Civil/ Drainage - Site Manhole	Entire Site / North Courtyard	9	EA	7	\$0	
Fencing							
	Fencing - Chain Link	Entire Site	770	LF	7	\$0	
	Fencing - Chain Link	Entire Site / South West	20	LF	5	\$1,220	
	Fencing - New Standard Ornamental	Entire Site	788	LF	7	\$0	
	Fencing - New Standard Ornamental	Entire Site / North	8	LF	5	\$1,139	
Landscape							
	Landscape - Grass	Entire Site	36,260	SF	6	\$30,074	
	Landscape - Hardscape- Concrete	Entire Site	2,375	SF	6	\$14,434	
	Landscape - Hardscape- Concrete	Entire Site	2,380	SF	5	\$26,104	
	Landscape - Hardscape- Concrete	Entire Site	685	SF	4	\$11,794	
	Landscape - Hardscape- Pavers	Entire Site	450	SF	6	\$2,548	
	Parkway trees	Entire Site	54	EA	7	\$0	
	Planting Beds/ Area	Entire Site	1,350	SF	5	\$4,093	
	Retaining Wall - Concrete	Entire Site	13	SF	4	\$1,798	
	Retaining Wall - Concrete	Entire Site	190	SF	6	\$4,453	
	Retaining Wall - Concrete	Entire Site	60	SF	5	\$3,778	
	Trash Receptacles	Entire Site	2	EA	6	\$625	
Parking Lot							
	Surface - Asphalt	Site northwest	6,190	SF	5	\$32,309	cracks
	Surface - Asphalt	Site northwest / Parking Lot	17,330	SF	4	\$136,796	potholes, cracks
	Surface - Concrete	Site northwest	560	SF	6	\$1,353	cracks
	Trash Compactor	Site northwest	1	EA	6	\$0	
Sidewalks							
	Sidewalks - Perimeter Sidewalks	Entire Site	13,620	SF	6	\$27,072	
	Sidewalks - Perimeter Sidewalks	Entire Site	3,310	SF	5	\$27,311	
Signage							
	Flag Pole - Building Mounted Flag Pole	East	1	EA	7	\$0	
	Marquee - Free Standing Back lighted w/ LED	East	1	EA	7	\$0	
Site Subtotal:						\$335,451	

Total Site Cost**\$335,451****Campus Total ^{2 3}****\$11,089,099**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	1st Floor	108	108	1,085	1	9	24	186	90	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	109	109	770	1	3	16	132	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	200	200	770	1	6	16	132	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	201	201	770	1	6	16	132	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	202	202	770	1	6	16	132	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	203	203	770	1	6	16	132	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	204	204	770	1	6	16	132	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	770	1	6	16	132	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	206	206	770	1	6	16	132	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	770	1	6	16	132	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	770	1	6	16	132	60	40	N	Y	Y
Science	Regular Classroom	3rd Floor	300	300	770	1	3	16	132	60	40	N	Y	Y
Science	Science Classroom	3rd Floor	302	302	1,085	1	9	80	198	90	40	N	N	N
Science	Regular Classroom	3rd Floor	303	303	770	1	3	16	132	60	40	N	Y	N
Science	Science Classroom	3rd Floor	305	305	1,085	1	9	80	198	90	40	N	N	Y
Science	Science Classroom	3rd Floor	307	307	1,085	1	9	80	198	90	40	N	N	Y
Science	Regular Classroom	3rd Floor	308	308	770	1	3	16	132	60	40	N	Y	Y
Science Lab Level 1	Science Lab Level 1	2nd Floor	210	210	930	1	14	32	80	40	40	N	N	Y
Science Lab Level 1	Science Lab Level 1	3rd Floor	310	310	1,085	1	9	80	198	90	40	N	N	N
Special Education	Regular Classroom	1st Floor	110	109	350	1	4	10	66	30	40	N	Y	N
Special Education	Regular Classroom	2nd Floor	209	208	290	1	4	10	66	30	40	N	Y	N

Addition 1														
Art Room	Regular Classroom	1st Floor	120	120	1,107	1	2	12	96	48	40	N	Y	Y
Art Room	Regular Classroom	3rd Floor	323	323	1,207	1	8	20	144	72	40	N	N	Y
Art Room	Regular Classroom	3rd Floor	325	325	1,120	1	8	16	144	72	40	N	N	Y
Band Room	Regular Classroom	3rd Floor	322	322	1,250	1	4	24	192	96	40	N	N	N
Choral Room	Regular Classroom		320	320	1,107	1	2	12	96	48	40	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	216	216	1,107	1	8	24	144	72	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	225	225	1,500	1	30	60	192	96	40	N	Y	Y
Computer Lab	Regular Classroom	3rd Floor	313	313	1,120	1	36	72	144	72	40	N	N	Y
Computer Lab	Regular Classroom	3rd Floor	315	315	1,120	1	36	72	144	72	40	N	N	Y
Computer Lab	Regular Classroom		316	316	1,107	1	34	68	144	72	40	N	N	Y
Computer Lab	Regular Classroom	3rd Floor	318	318	1,120	1	24	54	48	24	40	N	N	Y
Music Room	Regular Classroom	2nd Floor	220	220	1,500	0	2	16	192	96	40	N	N	N
Other	Regular Classroom	1st Floor	122	122	1,107	1	2	12	144	72	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	111	111	736	1	6	20	96	48	40	N	N	Y

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Addition 1														
Regular Classroom	Regular Classroom	1st Floor	112	112	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	1st Floor	115	115	1,107	1	2	20	144	72	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	117	117	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	211	211	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	212	212	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	213	213	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	214	214	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	215	215	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	217	217	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	218	218	643	1	6	20	96	48	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	221	222	2,313	1	1	62	252	126	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	223	223	1,120	1	8	16	144	72	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	226	226	736	1	2	12	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	311	311	736	1	6	16	96	48	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	312	312	736	1	6	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	317	317	736	1	6	16	96	48	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	319	319	736	1	6	16	96	48	40	N	N	Y
Regular Classroom	Regular Classroom		324	324	375		2	8	48	24	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	326	326	736	0	2	12	96	48	40	N	N	N
Science Classroom	Regular Classroom	1st Floor	113	113	1,107	1	2	20	144	72	40	N	Y	N
Science Classroom	Regular Classroom	1st Floor	114	114	550	1	12	24	72	36	40	N	N	N
	Other Instructional Use	3rd Floor	314	MR	736	1	2	6	96	48	40	N	N	N