

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1974	8	354,518	\$12,251,660
Linked Addition-Main Athletic	1974	2	78,824	\$3,558,095
SITE				\$1,578,918
Campus Total			433,342	\$17,388,672

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	#2 W	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	#5 N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#6 E	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#7 E	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#8 E	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#9 S	1	EA	6	\$481	
	Exterior Doors - Overhead Rolling/ Garage Door	#9.5 BSMT SE OHD	1	EA	6	\$1,433	
	Exterior Doors - Store Front	#1 S	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#2 W	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#3 W	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#4 N	2	EA	6	\$1,092	
	Power Door Operator and Controls	#2 W	2	EA	6	\$0	
Foundation							
	Foundation - Concrete	Entire Building	128	LF	5	\$70,648	Location: dock area - Leaks
	Foundation - Concrete	Entire Building	842	LF	7	\$0	
	Superstructure - Steel	Entire Building	354,518	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	29	EA	6	\$8,374	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Chimney - Metal Flue	Main Roof	12	LF	6	\$1,898	
	Coping - Metal	High Roof	491	LF	6	\$15,770	
	Coping - Metal	Main Roof	792	LF	6	\$25,437	
	Downspouts - Interior Downspouts	High Roof	1,080	LF	6	\$35,892	
	Downspouts - Interior Downspouts	Main Roof	1,980	LF	6	\$65,802	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	High Roof	14,233	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main Roof	22,867	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	High Roof	14,233	SF	6	\$144,711	
	Roof - Asphalt Gravel Ballast	Main Roof	22,867	SF	6	\$232,496	
Walls							
	Exterior Walls - Brick	Entire Building	23,696	SF	6	\$159,261	
	Exterior Walls - Stone-Cast	Entire Building	4,658	SF	6	\$31,306	
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	5,876	SF	6	\$65,877	
	Curtain wall - Louver	Entire Building	1,216	SF	6	\$13,633	
	Guard - Guards wire guard	Entire Building	2,700	SF	6	\$34,479	
	Windows - Casement Aluminum Double-pane	Entire Building	5,967	SF	6	\$44,541	

Building Exterior Subtotal:

\$960,472

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Mechanical Room / Electrical Room	2	EA	7	\$0	
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	11,594	SF	6	\$6,134	
	Emergency A/C Power - Corridors and Stairs	Entire Building	71,986	SF	6	\$21,617	
	Emergency A/C Power - Students Toilets	Entire Building	5,000	SF	6	\$1,859	
	Emergency Battery Packs - Auditorium and Aisle Lighting	Entire Building / 1st Floor	10	EA	6	\$2,025	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	131	EA	6	\$26,528	
	Emergency Battery Packs - Lunchrooms	Entire Building	8	EA	6	\$1,620	
	Emergency Generator- Indoor- Diesel - 201 - 250 KW	Loading Dock	1	EA	6	\$12,554	
	Exit Signs - Auditorium	Entire Building / 1st Floor	10	EA	6	\$1,497	
	Exit Signs - Corridors and Stairs	Entire Building	129	EA	6	\$19,318	
	Exit Signs - Lunchroom	Entire Building	8	EA	6	\$1,198	
	Security System - CCTV	Entire Building	354,518	SF	6	\$106,462	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Security System - Intrusion Detection	Entire Building	354,518	SF	6	\$91,253	
Main Service							
	Main Electrical Service - 2000 A 277/480/3PH	Mechanical Room	3	EA	6	\$25,985	SWBD #A-4
	Main Electrical Service - 800 A and Less than 277/480/3PH	Mechanical Room	1	EA	7	\$0	Fed from Edison vault
	PA System	Entire Building	354,518	SF	7	\$0	Serves both buildings
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building	1	EA	4	\$4,849	Emergency fuse panel is old and deteriorated.
	Lighting and Power Panels - 100 A	Entire Building	1	EA	4	\$4,849	Panel is old and deteriorated.
	Lighting and Power Panels - 100 A	Entire Building	5	EA	7	\$0	
	Lighting and Power Panels - 100 A	Entire Building	6	EA	6	\$1,795	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	Emergency fuse panels
	Lighting and Power Panels - Above 100 A	Entire Building	61	EA	6	\$30,319	
	Lighting and Power Panels - Above 100 A	Entire Building	14	EA	4	\$92,089	Panels are old and deteriorated.
	Lighting and Power Panels - Above 100 A	Entire Building	38	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building	3	EA	4	\$41,082	Panels are old and deteriorated.
	Main Distribution Panels - 400 - 600 amp	Entire Building	5	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building	10	EA	6	\$5,277	
	Main Distribution Panels - Greater than 600 amp	Entire Building	2	EA	4	\$42,209	Panels are old and deteriorated.
	Main Distribution Panels - Greater than 600 amp	Entire Building	4	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building	13	EA	6	\$9,492	
	Main Distribution Panels - Less than 400 amp	Entire Building	1	EA	6	\$503	
	Main Distribution Panels - Less than 400 amp	Entire Building	1	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Entire Building	4	EA	4	\$35,276	Panels are old and deteriorated.
	Transformers - 277/480 - 120/208	Entire Building	1	EA	6	\$1,265	
	Transformers - 277/480 - 120/208	Entire Building	2	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building	1	EA	6	\$1,265	
Electrical System Subtotal:						\$588,918	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Entire Building / Electrical Room	1	EA	7	\$0	
	Fire Alarm Strobe Lights	Entire Building	354,518	SF	7	\$0	
	Fire Alarm_System	Entire Building	354,518	SF	7	\$0	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Pump Controller	Entire Building / Mechanical Room	1	EA	6	\$1,823	
Pump Room Assembly							
	Fire Pump - Greater than 75hp	Mechanical Room	1	EA	6	\$1,558	
	Jockey Pump	Mechanical Room	1	EA	6	\$758	
Sprinkler System							
	Combination Wet and Dry Sprinkler System	Entire Building	354,518	SF	7	\$0	
	Sprinkler Heads	Entire Building	354,518	SF	7	\$0	
	Sprinkler Piping	Entire Building	354,518	SF	7	\$0	
Safty System Subtotal:						\$4,139	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Chemical Pot Feeder	Penthouse	1	EA	6	\$725	
	Chiller-Water Cooled- Cetrifugal - Greater than 400	Penthouse	1	EA	6	\$10,320	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	7	\$0	
	Cooling Tower - Closed Cell	Penthouse	2	EA	6	\$9,938	
	Pipes - Chilled Water Pipe- Steel	Penthouse / Entire Building	5,000	LF	6	\$9,438	
	Pressure Fill System	Penthouse	1	EA	6	\$1,405	
Air Handling Systems							
	Air Handling Unit- Built Up- Multi Zone- Hot Water and Chilled Water Coils - Greater than 35000 cfm	Penthouse	1	EA	5	\$112,879	S3A serves 4th thru 8th floors. Unit has chilled water coils only.
	Air Handling Unit- Built Up- Multi Zone- Hot Water and Chilled Water Coils - Greater than 35000 cfm	Penthouse	1	EA	5	\$112,879	S4A serves 4th thru 8th floors. Unit has chilled water coils only.
	Air Handling Unit- Built Up- Multi Zone- Hot Water and DX Cooling Coils - Greater than 35000 cfm	Penthouse	1	EA	5	\$112,879	S5A serves 2nd & 3rd floors. Unit has chilled water coils only.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	5	\$48,592	AS-3A serves 1st floor lobby. Unit has chilled water coils only.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	5	\$48,592	AS-2A serves Lower Level. Unit has chilled water coils only.
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	5	\$60,486	AS-1A serves Auditorium. Unit has chilled water coils only.
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Intake	Penthouse / Roof	1	EA	6	\$5,765	
	Air Intake	Penthouse / Roof	1	EA	6	\$5,765	
	Air Intake	Penthouse / Roof	1	EA	6	\$5,765	
	Auxiliaries - Greater than 35000 cfm	Penthouse	1	EA	5	\$18,883	
	Auxiliaries - Greater than 35000 cfm	Penthouse	1	EA	5	\$18,883	
	Auxiliaries - Greater than 35000 cfm	Penthouse	1	EA	5	\$18,883	
	Indoor Return Fans- Centrifugal Squirrel Cage - 10001 - 20000 CFM	Entire Building / Mechanical Room	2	EA	5	\$24,437	
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Mechanical Room	1	EA	5	\$16,255	
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Entire Building / Penthouse	3	EA	5	\$48,766	
	Make Up Air Unit- Roof Mounted- Electric Coils - Less than 6000 cfm	Roof	1	EA	5	\$19,234	
	Make Up Air Unit- Roof Mounted- Electric and Chilled Water Coils - Less than 6000 cfm	Roof	1	EA	5	\$24,722	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Penthouse / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Penthouse / Entire Building	100	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Penthouse / Entire Building	100	LF	7	\$0	
	VAV Box	Entire Building	90	EA	5	\$119,875	Served by S3A.
	VAV Box	Entire Building	90	EA	5	\$119,875	Served by S4A.
	VAV Box	Entire Building	78	EA	5	\$103,892	Served by S5A.
Heating Devices							
	Duct Heater - Electric	Entire Building	257		5	\$516,201	Units have over 40 years of service and are significantly deteriorated.
	Fin Tube - Electric	Entire Building	5,430	LF	7	\$0	Perimeter electric heaters
	Unit Heater - Electric	Entire Building / 8th Floor	12	EA	6	\$3,334	
	Unit Heater - Electric	Entire Building / Basement	5	EA	6	\$1,389	
	Wall Heater - Electric	Entire Building	4	EA	6	\$556	
Mechanical Plumbing							
	Chilled Water Pump - 21 - 50 HP	Penthouse	2	EA	6	\$2,485	
	Condenser Pump - 21 - 50 HP	Penthouse	2	EA	6	\$2,485	
Temperature Control							
	DDC System	Entire Building	354,518	SF	5	\$583,005	System has more than 15 years of service and needs upgrading.
	Electric Thermostat	Entire Building / 4th Floor	1	EA	6	\$0	Controls MDF room split system cooling
	Thermostats - DDC	Entire Building	206	EA	6	\$0	
Ventilation							
	Exhaust Fans- Indoor - Greater than 8000 CFM	Entire Building	8	EA	6	\$4,739	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	3	EA	6	\$1,777	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	7	\$0	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	
	Lab Exhaust Hood	Entire Building	3	EA	7	\$0	
	Lab Exhaust Hood	Entire Building	2	EA	6	\$2,495	
	Roof Mounted Duct Work	Entire Building / Roof	19	LF	6	\$7,201	
	Type I Exhaust Hood- Kitchen	Entire Building	3	EA	7	\$0	
	Type II Exhaust Hood- Warming Kitchen	Entire Building	6	EA	7	\$0	

Mechanical System Subtotal:

\$2,223,277

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - Greater than 600000 BTU/HR	Penthouse	1	EA	7	\$0	
	Gas Heater - Greater than 600000 BTU/HR	Penthouse	1	EA	6	\$310	
	Hot Water Storage Tank_Gas - 501 - 1000 Gallons	Penthouse	1	EA	6	\$678	

Piping

	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	354,518	SF	6	\$70,975	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	354,518	SF	6	\$86,183	
	Domestic Piping-Cold Water Risers	Entire Building	354,518	SF	6	\$65,905	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	354,518	SF	6	\$55,766	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	354,518	SF	6	\$65,905	
	Domestic Piping-Hot Water Return Lines	Entire Building	354,518	SF	6	\$50,696	
	Domestic Piping-Hot Water Return Risers	Entire Building	354,518	SF	6	\$50,696	
	Sanitary Piping	Entire Building	354,518	SF	4	\$1,231,915	Piping is substantially deteriorated.
	Storm Piping	Entire Building	354,518	SF	6	\$309,246	
	Vent Piping	Entire Building	354,518	SF	6	\$238,272	

Pumps

	Pumps - Domestic Booster Pump-Duplex	Entire Building / Mechanical Room	1	EA	6	\$1,977	
	Pumps - Ejector-Duplex	Entire Building / Mechanical Room	1	EA	6	\$1,387	
	Pumps - Ejector-Simplex	Entire Building / Mechanical Room	1	EA	6	\$745	
	Pumps - Ejector-Simplex	Entire Building / Mechanical Room	1	EA	4	\$11,443	Pump has more than 40 years of service and should be replaced.
	Pumps - Sump-Simplex	Entire Building / Basement	1	EA	6	\$745	Elevator sump pit

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pumps							
	Pumps - Sump-Simplex	Entire Building / Loading Dock	1	EA	6	\$745	

Plumbing System Subtotal:

\$2,243,588

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #001 (Music Room)							
	Ceiling - Lay-in	Basement	1,282	SF	6	\$3,850	
	Doors - Wood Doors inclu hw	Basement	2	EA	6	\$602	
	Floor - Tile/Sheet	Basement	1,282	SF	6	\$1,283	900 SF is carpet
	Lighting - Lay-in	Basement	40	EA	7	\$0	
	Marker Board	Basement	16	LF	6	\$343	
	Sound System	Basement	1	EA	6	\$1,442	
	Walls - Concrete Block	Basement	2,020	SF	6	\$5,922	
Classroom #002 (Music Room)							
	Ceiling - Lay-in	Basement	1,806	SF	6	\$5,423	
	Doors - Wood Doors inclu hw	Basement	2	EA	6	\$602	
	Floor - Tile/Sheet	Basement	1,806	SF	6	\$1,808	1227 SF is carpeted
	Lighting - Lay-in	Basement	46	EA	7	\$0	
	Marker Board	Basement	16	LF	6	\$343	
	Sound System	Basement	1	EA	6	\$1,442	
	Walls - Concrete Block	Basement	1,227	SF	6	\$4,123	
	Walls - Concrete Block	Basement	2,240	SF	6	\$6,567	
	Work Sink	Basement	1	EA	6	\$379	
Classroom #008 (Store Room)							
	Ceiling - Splined	Basement	500	SF	6	\$408	
	Doors - Wood Doors inclu hw	Basement	2	EA	6	\$602	
	Floor - Carpet	Basement	500	SF	6	\$1,065	
	Lighting - Lay-in	Basement	13	EA	7	\$0	
	Walls - Concrete Block	Basement	1,100	SF	6	\$3,225	
Classroom #009 (Music Room)							
	Ceiling - Splined	Basement	767	SF	6	\$625	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Carpet	Basement	767	SF	6	\$1,634	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #009 (Music Room)							
	Lighting - Lay-in	Basement	24	EA	7	\$0	
	Marker Board	Basement	8	LF	6	\$171	
	Walls - Concrete Block	Basement	1,292	SF	6	\$3,787	
Classroom #011 (Regular Classroom)							
	Ceiling - Splined	Basement	767	SF	6	\$625	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Tile/Sheet	Basement	767	SF	6	\$768	
	Lighting - Lay-in	Basement	24	EA	7	\$0	
	Marker Board	Basement	8	LF	6	\$171	
	Walls - Concrete Block	Basement	1,292	SF	6	\$3,787	
Classroom #026 (Other Instructional Use)							
	Ceiling - Exposed		2,280	SF	6	\$3,391	
	Chalk Board		10	LF	4	\$918	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Concrete		2,280	SF	6	\$1,206	
	Lighting - Pendent/Surface		50	EA	6	\$6,195	
	Storage/ Closet		550	SF	6	\$3,988	
	Walls - Concrete Block		1,400	SF	6	\$4,104	
	Work Sink		1	EA	6	\$379	
Classroom #041 (Music Room)							
	Ceiling - Lay-in	Basement	305	SF	6	\$916	
	Floor - Carpet	Basement	305	SF	6	\$650	
	Lighting - Lay-in	Basement	6	EA	6	\$714	
	Sound Panels	Basement	360	EA	6	\$1,452	
	Walls - Concrete Block	Basement	750	SF	6	\$2,199	
	Walls - Plaster/Drywall	Basement	190	SF	6	\$524	
Classroom #201 (Regular Classroom)							
	Ceiling - Splined	2nd Floor	880	SF	6	\$717	
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	880	SF	6	\$881	
	Lighting - Lay-in	2nd Floor	24	EA	6	\$2,855	
	Storage/ Closet	2nd Floor	94	SF	6	\$682	
	Walls - Concrete Block	2nd Floor	400	SF	6	\$1,173	
	Walls - Metal Panel	2nd Floor	600	SF	6	\$4,479	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #202 (Art Room)							
	Ceiling - Splined	2nd Floor	900	SF	6	\$734	Scuff markings
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	24	EA	6	\$2,855	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	94	SF	6	\$682	No Key
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroom #203 (Regular Classroom)							
	Ceiling - Splined	2nd Floor	900	SF	6	\$734	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	24	EA	6	\$2,855	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	263	SF	6	\$1,907	
	Walls - Concrete Block	2nd Floor	98	SF	6	\$287	
	Walls - Masonry	2nd Floor	150	SF	6	\$472	
	Walls - Metal Panel	2nd Floor	1,215	SF	6	\$9,069	
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classroom #204 (Regular Classroom)							
	Ceiling - Splined	2nd Floor	900	SF	6	\$734	
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	25	EA	6	\$2,974	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	263	SF	6	\$1,907	
	Walls - Masonry	2nd Floor	100	SF	6	\$315	
	Walls - Metal Panel	2nd Floor	1,227	SF	6	\$9,159	
Classroom #205 (Art Room)							
	Ceiling - Splined	2nd Floor	2	SF	5	\$19	Missing tiles
	Ceiling - Splined	2nd Floor	1,948	SF	6	\$1,588	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	Wood panel
	Doors - Transom Window	2nd Floor	24	SF	6	\$406	Wood panel

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #205 (Art Room)							
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,950	SF	6	\$1,952	
	Lighting - Lay-in	2nd Floor	60	EA	6	\$7,139	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	383	SF	5	\$6,178	
	Walls - Concrete Block	2nd Floor	521	SF	6	\$1,527	
	Walls - Metal Panel	2nd Floor	1,565	SF	6	\$11,682	
Classroom #207 (Other Instructional Use)							
	Ceiling - Lay-in	2nd Floor	1,767	SF	6	\$5,306	
	Doors - Side-lite	2nd Floor	9	SF	6	\$150	Wood panel
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,767	SF	6	\$1,769	
	Lighting - Lay-in	2nd Floor	27	EA	6	\$3,212	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	66	SF	6	\$479	
	Walls - Plaster/Drywall	2nd Floor	1,956	SF	6	\$5,398	
Classroom #208 (Store Room)							
	Ceiling - Splined	2nd Floor	692	SF	6	\$564	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	Wood panel
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	692	SF	6	\$693	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	23	SF	6	\$167	The other rooms were blocked
	Walls - Metal Panel	2nd Floor	1,170	SF	6	\$8,734	
Classroom #212 (Vacant)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Ceiling - Splined	2nd Floor	1	SF	5	\$10	water stain
	Ceiling - Splined	2nd Floor	899	SF	6	\$733	
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	25	EA	6	\$2,974	
	Marker Board	2nd Floor	8	LF	6	\$171	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #212 (Vacant)							
	Storage/ Closet	2nd Floor	254	SF	6	\$1,842	
	Walls - Concrete Block	2nd Floor	842	SF	6	\$2,468	
	Walls - Masonry	2nd Floor	200	SF	6	\$629	
	Walls - Plaster/Drywall	2nd Floor	285	SF	6	\$787	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #216 (Art Room)							
	Ceiling - Lay-in	2nd Floor	1,820	SF	6	\$5,465	
	Doors - Transom Window	2nd Floor	16	SF	6	\$271	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,820	SF	6	\$1,822	
	Kiln	2nd Floor	2	EA	6	\$4,642	
	Lighting - Lay-in	2nd Floor	48	EA	6	\$5,711	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Storage/ Closet	2nd Floor	436	SF	6	\$3,161	
	Walls - Concrete Block	2nd Floor	220	SF	6	\$645	
	Walls - Plaster/Drywall	2nd Floor	1,100	SF	6	\$3,036	
Classroom #217 (Computer Lab)							
	Ceiling - Splined	2nd Floor	2	SF	5	\$19	Scuffed and loose/missing tiles
	Ceiling - Splined	2nd Floor	1,818	SF	6	\$1,482	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	2nd Floor	24	SF	6	\$406	wood panel
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Tile/Sheet	2nd Floor	1,820	SF	6	\$1,822	
	Lighting - Lay-in	2nd Floor	66	EA	6	\$7,852	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Concrete Block	2nd Floor	220	SF	6	\$645	
	Walls - Masonry	2nd Floor	300	SF	6	\$944	
	Walls - Metal Panel	2nd Floor	900	SF	6	\$6,718	
	Wireless System	2nd Floor	1	EA	6	\$372	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #304 (Other Instructional Use)							
	Ceiling - Splined	3rd Floor	450	SF	6	\$367	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Transom Window	3rd Floor	1	SF	6	\$17	
	Floor - Carpet	3rd Floor	450	SF	6	\$959	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #304 (Other Instructional Use)							
	Lighting - Lay-in	3rd Floor	15	EA	6	\$1,785	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Walls - Concrete Block	3rd Floor	55	SF	6	\$161	
	Walls - Metal Panel	3rd Floor	760	SF	6	\$5,673	
Classroom #305 (Store Room)							
	Ceiling - Splined	3rd Floor	2	SF	5	\$19	Damaged and loose tiles
	Ceiling - Splined	3rd Floor	448	SF	6	\$365	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Carpet	3rd Floor	450	SF	6	\$959	
	Lighting - Lay-in	3rd Floor	15	EA	6	\$1,785	
	Marker Board	3rd Floor	8	LF	6	\$171	
	Walls - Concrete Block	3rd Floor	55	SF	6	\$161	
	Walls - Metal Panel	3rd Floor	760	SF	6	\$5,673	
Classroom #310 (Vacant)							
	Ceiling - Splined	3rd Floor	770	SF	6	\$628	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	770	SF	6	\$771	
	Lighting - Lay-in	3rd Floor	20	EA	6	\$2,380	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Walls - Concrete Block	3rd Floor	65	SF	6	\$191	
	Walls - Metal Panel	3rd Floor	908	SF	6	\$6,778	
Classroom #314 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	2	SF	5	\$19	Holes and loose tiles
	Ceiling - Splined	3rd Floor	768	SF	6	\$626	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Carpet	3rd Floor	770	SF	6	\$1,641	
	Lighting - Lay-in	3rd Floor	20	EA	6	\$2,380	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	19	SF	6	\$138	
	Walls - Concrete Block	3rd Floor	250	SF	6	\$733	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #314 (Regular Classroom)							
	Walls - Metal Panel	3rd Floor	550	SF	6	\$4,106	
Classroom #315 (Regular Classroom)							
	Ceiling - Splined	3rd Floor	450	SF	6	\$367	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	450	SF	6	\$450	
	Lighting - Lay-in	3rd Floor	15	EA	6	\$1,785	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Walls - Concrete Block	3rd Floor	55	SF	6	\$161	
	Walls - Metal Panel	3rd Floor	760	SF	6	\$5,673	
Classroom #318 (Other Instructional Use)							
	Ceiling - Splined	3rd Floor	605	SF	6	\$493	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Transom Window	3rd Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	3rd Floor	605	SF	6	\$606	
	Lighting - Lay-in	3rd Floor	16	EA	6	\$1,904	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Walls - Concrete Block	3rd Floor	65	SF	6	\$191	
	Walls - Metal Panel	3rd Floor	806	SF	6	\$6,016	
Classroom #401 (Regular Classroom)							
	Ceiling - Splined	4th Floor	900	SF	6	\$734	
	Doors - Side-lite	4th Floor	10	SF	6	\$167	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	900	SF	6	\$901	
	Lighting - Lay-in	4th Floor	24	EA	6	\$2,855	
	Marker Board	4th Floor	8	LF	6	\$171	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	908	SF	6	\$6,778	
Classroom #402 (Regular Classroom)							
	Ceiling - Splined	4th Floor	900	SF	6	\$734	
	Doors - Side-lite	4th Floor	20	SF	6	\$334	
	Doors - Transom Window	4th Floor	24	SF	6	\$406	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	900	SF	5	\$4,041	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #402 (Regular Classroom)							
	Lighting - Lay-in	4th Floor	24	EA	5	\$3,893	
	Marker Board	4th Floor	8	LF	6	\$171	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	908	SF	6	\$6,778	
Classroom #403 (Regular Classroom)							
	Ceiling - Splined	4th Floor	605	SF	6	\$493	Missing tile
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	806	SF	6	\$6,016	
Classroom #404 (Vacant)							
	Ceiling - Splined	4th Floor	1	SF	5	\$10	Water stain
	Ceiling - Splined	4th Floor	604	SF	6	\$492	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	806	SF	6	\$6,016	
Classroom #405 (Regular Classroom)							
	Ceiling - Splined	4th Floor	1	SF	5	\$10	Damaged and missing tile
	Ceiling - Splined	4th Floor	1,181	SF	6	\$963	
	Doors - Transom Window	4th Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	1,182	SF	6	\$1,183	
	Lighting - Lay-in	4th Floor	32	EA	6	\$3,807	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Masonry	4th Floor	320	SF	6	\$1,007	
	Walls - Metal Panel	4th Floor	1,191	SF	6	\$8,890	
Classroom #407 (Regular Classroom)							
	Ceiling - Plaster/Drywall	4th Floor	604	SF	6	\$2,090	
	Ceiling - Splined	4th Floor	1	SF	6	\$1	water stains
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #407 (Regular Classroom)							
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	806	SF	6	\$6,016	
Classroom #408 (Vacant)							
	Ceiling - Splined	4th Floor	584	SF	6	\$476	
	Doors - Side-lite	4th Floor	10	SF	6	\$167	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	584	SF	6	\$585	
	Lighting - Lay-in	4th Floor	15	EA	6	\$1,785	
	Walls - Metal Panel	4th Floor	976	SF	6	\$7,285	
Classroom #409 (Computer Lab)							
	Ceiling - Splined	4th Floor	2	SF	5	\$19	Water stains
	Ceiling - Splined	4th Floor	1,154	SF	6	\$941	
	Doors - Side-lite	4th Floor	10	SF	6	\$167	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Carpet	4th Floor	1,156	SF	6	\$2,463	
	Lighting - Lay-in	4th Floor	30	EA	6	\$3,569	
	Marker Board	4th Floor	12	LF	6	\$257	
	Student Lockers - Two Tiers	4th Floor	8	EA	6	\$371	
	Walls - Concrete Block	4th Floor	166	SF	6	\$487	
	Walls - Masonry	4th Floor	166	SF	5	\$6,860	
	Walls - Metal Panel	4th Floor	765	SF	6	\$5,710	
	Work Sink	4th Floor	1	EA	6	\$379	
Classroom #410 (Regular Classroom)							
	Ceiling - Splined	4th Floor	758	SF	6	\$618	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	758	SF	6	\$759	
	Lighting - Lay-in	4th Floor	20	EA	6	\$2,380	
	Marker Board	4th Floor	8	LF	6	\$171	
	Walls - Masonry	4th Floor	105	SF	6	\$330	
	Walls - Metal Panel	4th Floor	1,217	SF	6	\$9,084	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #411 (Regular Classroom)							
	Ceiling - Splined	4th Floor	758	SF	6	\$618	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	758	SF	5	\$3,404	
	Lighting - Lay-in	4th Floor	20	EA	6	\$2,380	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Metal Panel	4th Floor	1,216	SF	6	\$9,077	
	Walls - Plaster/Drywall	4th Floor	1	SF	5	\$8	Peeling paint
Classroom #412 (Regular Classroom)							
	Ceiling - Splined	4th Floor	758	SF	6	\$618	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	758	SF	6	\$759	
	Lighting - Lay-in	4th Floor	20	EA	6	\$2,380	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Metal Panel	4th Floor	1,217	SF	6	\$9,084	
Classroom #413 (Regular Classroom)							
	Ceiling - Splined	4th Floor	758	SF	6	\$618	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	758	SF	6	\$759	
	Lighting - Lay-in	4th Floor	20	EA	6	\$2,380	
	Marker Board	4th Floor	16	LF	6	\$343	
	Walls - Metal Panel	4th Floor	1,217	SF	6	\$9,084	
Classroom #414 (Vacant)							
	Ceiling - Splined	4th Floor	770	SF	6	\$628	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Carpet	4th Floor	770	SF	6	\$1,641	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	60	SF	6	\$176	
	Walls - Metal Panel	4th Floor	250	SF	6	\$1,866	
	Walls - Plaster/Drywall	4th Floor	1	SF	5	\$5	Peeling paint
	Walls - Plaster/Drywall	4th Floor	549	SF	6	\$1,515	
Classroom #415 (Regular Classroom)							
	Ceiling - Splined	4th Floor	2	SF	5	\$19	Water stains
	Ceiling - Splined	4th Floor	756	SF	6	\$616	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #415 (Regular Classroom)							
	Floor - Tile/Sheet	4th Floor	758	SF	6	\$759	
	Lighting - Lay-in	4th Floor	24	EA	6	\$2,855	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	98	SF	6	\$287	
	Walls - Masonry	4th Floor	158	SF	6	\$497	
	Walls - Metal Panel	4th Floor	1,217	SF	6	\$9,084	
Classroom #416 (Regular Classroom)							
	Ceiling - Splined	4th Floor	665	SF	6	\$542	
	Chalk Board	4th Floor	4	LF	4	\$367	
	Doors - Side-lite	4th Floor	10	SF	6	\$167	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Transom Window	4th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	4th Floor	665	SF	6	\$666	
	Lighting - Lay-in	4th Floor	18	EA	6	\$2,142	
	Walls - Metal Panel	4th Floor	1,280	SF	6	\$9,555	
Classroom #417 (Regular Classroom)							
	Ceiling - Splined	4th Floor	900	SF	6	\$734	
	Doors - Side-lite	4th Floor	10	SF	6	\$167	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Transom Window	4th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	4th Floor	900	SF	6	\$901	
	Lighting - Lay-in	4th Floor	24	EA	5	\$3,893	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Masonry	4th Floor	130	SF	6	\$409	
	Walls - Metal Panel	4th Floor	872	SF	6	\$6,509	
	Work Sink	4th Floor	1	EA	6	\$379	
Classroom #418 (Vacant)							
	Ceiling - Splined	4th Floor	605	SF	6	\$493	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	806	SF	6	\$6,016	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #419 (Regular Classroom)							
	Ceiling - Splined	4th Floor	605	SF	6	\$493	
	Doors - Steel Doors incl hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	806	SF	6	\$6,016	
Classroom #420 (Vacant)							
	Ceiling - Splined	4th Floor	605	SF	6	\$493	
	Doors - Transom Window	4th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	506	SF	6	\$3,777	
	Walls - Plaster/Drywall	4th Floor	300	SF	6	\$828	
Classroom #422 (Other Instructional Use)							
	Ceiling - Splined	4th Floor	605	SF	6	\$493	
	Doors - Side-lite	4th Floor	10	SF	6	\$167	
	Doors - Transom Window	4th Floor	12	SF	6	\$203	
	Doors - Transom Window	4th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	4th Floor	605	SF	6	\$606	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	65	SF	6	\$191	
	Walls - Metal Panel	4th Floor	806	SF	6	\$6,016	
Classroom #424 (Store Room)							
	Ceiling - Splined	4th Floor	450	SF	6	\$367	Scuff markings
	Doors - Transom Window	4th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	4th Floor	450	SF	6	\$450	
	Lighting - Lay-in	4th Floor	15	EA	6	\$1,785	
	Marker Board	4th Floor	12	LF	6	\$257	
	Walls - Concrete Block	4th Floor	55	SF	5	\$565	
	Walls - Metal Panel	4th Floor	304	SF	6	\$2,269	
	Walls - Plaster/Drywall	4th Floor	455	SF	6	\$1,256	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #425 (Office)							
	Ceiling - Splined	4th Floor	450	SF	6	\$367	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	450	SF	6	\$450	
	Lighting - Lay-in	4th Floor	10	EA	6	\$1,190	
	Marker Board	4th Floor	16	LF	6	\$343	
	Walls - Concrete Block	4th Floor	180	SF	6	\$528	
	Walls - Plaster/Drywall	4th Floor	455	SF	6	\$1,256	
Classroom #499 (Regular Classroom)							
	Ceiling - Splined	4th Floor	1,386	SF	6	\$1,130	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	1,386	SF	6	\$1,387	
	Lighting - Lay-in	4th Floor	40	EA	6	\$4,759	
	Marker Board	4th Floor	8	LF	6	\$171	
	Walls - Concrete Block	4th Floor	280	SF	6	\$821	
	Walls - Metal Panel	4th Floor	760	SF	6	\$5,673	
Classroom #501 (Regular Classroom)							
	Ceiling - Splined	5th Floor	900	SF	6	\$734	
	Doors - Side-lite	5th Floor	10	SF	6	\$167	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	900	SF	6	\$901	
	Lighting - Lay-in	5th Floor	24	EA	6	\$2,855	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	908	SF	6	\$6,778	
Classroom #502 (Regular Classroom)							
	Ceiling - Splined	5th Floor	900	SF	5	\$6,409	Hole
	Doors - Side-lite	5th Floor	10	SF	6	\$167	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	
	Doors - Transom Window	5th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	5th Floor	900	SF	5	\$4,041	
	Lighting - Lay-in	5th Floor	24	EA	6	\$2,855	
	Marker Board	5th Floor	14	LF	6	\$300	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	908	SF	6	\$6,778	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #503 (Regular Classroom)							
	Ceiling - Splined	5th Floor	605	SF	6	\$493	
	Doors - Transom Window	5th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	12	LF	6	\$257	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	806	SF	6	\$6,016	
Classroom #504 (Regular Classroom)							
	Ceiling - Splined	5th Floor	1	SF	5	\$10	Water stains and damaged tiles
	Ceiling - Splined	5th Floor	604	SF	6	\$492	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	12	EA	6	\$1,428	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	14	LF	6	\$300	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	806	SF	6	\$6,016	
Classroom #505 (Regular Classroom)							
	Ceiling - Splined	5th Floor	1,182	SF	6	\$963	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	Wood panel
	Doors - Wood Doors inclu hw	5th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	5th Floor	1,182	SF	6	\$1,183	
	Lighting - Lay-in	5th Floor	32	EA	6	\$3,807	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Masonry	5th Floor	320	SF	6	\$1,007	
	Walls - Metal Panel	5th Floor	1,191	SF	6	\$8,890	
Classroom #507 (Regular Classroom)							
	Ceiling - Splined	5th Floor	605	SF	6	\$493	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	5	\$1,174	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	1	SF	5	\$40	Cracks along corner
	Walls - Metal Panel	5th Floor	805	SF	6	\$6,009	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #509 (Computer Lab)							
	Ceiling - Splined	5th Floor	2	SF	5	\$19	Water stains
	Ceiling - Splined	5th Floor	1,154	SF	6	\$941	
	Doors - Side-lite	5th Floor	10	SF	6	\$167	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Carpet	5th Floor	1,156	SF	6	\$2,463	
	Lighting - Lay-in	5th Floor	30	EA	6	\$3,569	
	Marker Board	5th Floor	12	LF	6	\$257	
	Student Lockers - Two Tiers	5th Floor	8	EA	6	\$371	
	Walls - Concrete Block	5th Floor	166	SF	6	\$487	
	Walls - Masonry	5th Floor	260	SF	6	\$818	
	Walls - Metal Panel	5th Floor	765	SF	6	\$5,710	
Classroom #510 (Regular Classroom)							
	Ceiling - Splined	5th Floor	1	SF	5	\$10	Damaged tile
	Ceiling - Splined	5th Floor	757	SF	6	\$617	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	1	SF	5	\$6	Damaged tile
	Floor - Tile/Sheet	5th Floor	757	SF	6	\$758	
	Lighting - Lay-in	5th Floor	20	EA	6	\$2,380	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Masonry	5th Floor	189	SF	6	\$595	
	Walls - Metal Panel	5th Floor	1,217	SF	6	\$9,084	
Classroom #511 (Regular Classroom)							
	Ceiling - Splined	5th Floor	758	SF	6	\$618	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	758	SF	6	\$759	
	Lighting - Lay-in	5th Floor	20	EA	6	\$2,380	
	Marker Board	5th Floor	12	LF	6	\$257	
	Walls - Metal Panel	5th Floor	1	SF	5	\$40	Peeling paint
	Walls - Metal Panel	5th Floor	1,216	SF	6	\$9,077	
Classroom #512 (Regular Classroom)							
	Ceiling - Splined	5th Floor	758	SF	6	\$618	
	Chalk Board	5th Floor	4	LF	4	\$367	
	Doors - Transom Window	5th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	5th Floor	758	SF	6	\$759	
	Lighting - Lay-in	5th Floor	20	EA	6	\$2,380	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #512 (Regular Classroom)							
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Metal Panel	5th Floor	1	SF	5	\$40	Peeling paint
	Walls - Metal Panel	5th Floor	1,216	SF	6	\$9,077	
Classroom #513 (Regular Classroom)							
	Ceiling - Splined	5th Floor	1	SF	5	\$10	Dirt and hole
	Ceiling - Splined	5th Floor	757	SF	6	\$617	
	Chalk Board	5th Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	758	SF	6	\$759	
	Lighting - Lay-in	5th Floor	20	EA	6	\$2,380	
	Walls - Metal Panel	5th Floor	1,217	SF	6	\$9,084	
Classroom #514 (Vacant)							
	Ceiling - Splined	5th Floor	758	SF	6	\$618	
	Chalk Board	5th Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	758	SF	6	\$759	
	Lighting - Lay-in	5th Floor	20	EA	6	\$2,380	
	Marker Board	5th Floor	18	LF	6	\$386	
	Walls - Metal Panel	5th Floor	1	SF	5	\$40	Peeling paint
	Walls - Metal Panel	5th Floor	1,216	SF	6	\$9,077	
Classroom #515 (Regular Classroom)							
	Ceiling - Splined	5th Floor	1	SF	5	\$10	Spray paint
	Ceiling - Splined	5th Floor	757	SF	6	\$617	
	Chalk Board	5th Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	758	SF	6	\$759	
	Lighting - Lay-in	5th Floor	20	EA	6	\$2,380	
	Marker Board	5th Floor	10	LF	6	\$214	
	Walls - Masonry	5th Floor	125	SF	6	\$393	
	Walls - Metal Panel	5th Floor	1,217	SF	6	\$9,084	
Classroom #516 (Vacant)							
	Ceiling - Splined	5th Floor	665	SF	6	\$542	
	Doors - Steel Doors incl hw	5th Floor	10	EA	6	\$3,010	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	
	Doors - Transom Window	5th Floor	1	SF	6	\$17	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #516 (Vacant)							
	Floor - Tile/Sheet	5th Floor	665	SF	6	\$666	
	Lighting - Lay-in	5th Floor	18	EA	6	\$2,142	
	Marker Board	5th Floor	12	LF	6	\$257	
	Walls - Metal Panel	5th Floor	1,280	SF	6	\$9,555	
Classroom #517 (Regular Classroom)							
	Ceiling - Splined	5th Floor	2	SF	5	\$19	Water stains
	Ceiling - Splined	5th Floor	898	SF	6	\$732	
	Doors - Side-lite	5th Floor	10	SF	6	\$167	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	
	Doors - Transom Window	5th Floor	1	SF	6	\$17	
	Floor - Tile/Sheet	5th Floor	900	SF	6	\$901	
	Lighting - Lay-in	5th Floor	24	EA	6	\$2,855	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Masonry	5th Floor	130	SF	6	\$409	
	Walls - Metal Panel	5th Floor	872	SF	6	\$6,509	
	Work Sink	5th Floor	1	EA	6	\$379	
Classroom #518 (Vacant)							
	Ceiling - Splined	5th Floor	605	SF	6	\$493	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	12	LF	6	\$257	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	806	SF	6	\$6,016	
Classroom #519 (Special Education)							
	Ceiling - Splined	5th Floor	605	SF	6	\$493	
	Chalk Board	5th Floor	4	LF	4	\$367	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	806	SF	6	\$6,016	
Classroom #520 (Vacant)							
	Ceiling - Splined	5th Floor	2	SF	5	\$19	Missing and loose tiles

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #520 (Vacant)							
	Ceiling - Splined	5th Floor	603	SF	6	\$492	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	18	LF	6	\$386	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	806	SF	6	\$6,016	
Classroom #522 (Other Instructional Use)							
	Ceiling - Splined	5th Floor	605	SF	6	\$493	
	Doors - Side-lite	5th Floor	10	SF	6	\$167	
	Doors - Transom Window	5th Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	605	SF	6	\$606	
	Lighting - Lay-in	5th Floor	16	EA	6	\$1,904	
	Marker Board	5th Floor	12	LF	6	\$257	
	Walls - Concrete Block	5th Floor	65	SF	6	\$191	
	Walls - Metal Panel	5th Floor	806	SF	6	\$6,016	
Classroom #524 (Vacant)							
	Ceiling - Splined	5th Floor	450	SF	6	\$367	Hole
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	450	SF	6	\$450	
	Lighting - Lay-in	5th Floor	15	EA	6	\$1,785	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Concrete Block	5th Floor	55	SF	6	\$161	
	Walls - Metal Panel	5th Floor	304	SF	6	\$2,269	
	Walls - Plaster/Drywall	5th Floor	1	SF	5	\$5	Scuffed marks and peeling plaster
	Walls - Plaster/Drywall	5th Floor	454	SF	6	\$1,253	
Classroom #525 (Office)							
	Ceiling - Splined	5th Floor	1	SF	5	\$10	Hole and chipped tiles
	Ceiling - Splined	5th Floor	449	SF	6	\$366	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	450	SF	6	\$450	
	Lighting - Lay-in	5th Floor	10	EA	6	\$1,190	
	Marker Board	5th Floor	16	LF	6	\$343	
	Walls - Concrete Block	5th Floor	180	SF	6	\$528	
	Walls - Plaster/Drywall	5th Floor	455	SF	6	\$1,256	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #525 (Office)							
Classroom #599 (Regular Classroom)							
	Ceiling - Splined	5th Floor	1,386	SF	6	\$1,130	
	Doors - Wood Doors inclu hw	5th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	5th Floor	1,386	SF	6	\$1,387	
	Lighting - Lay-in	5th Floor	40	EA	6	\$4,759	
	Marker Board	5th Floor	8	LF	6	\$171	
	Walls - Concrete Block	5th Floor	280	SF	6	\$821	
	Walls - Metal Panel	5th Floor	760	SF	6	\$5,673	
Classroom #601 (Regular Classroom)							
	Ceiling - Splined		900	SF	6	\$734	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		24	EA	6	\$2,855	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		908	SF	6	\$6,778	
Classroom #602 (Regular Classroom)							
	Ceiling - Splined		900	SF	6	\$734	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		24	EA	6	\$2,855	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		65	SF	6	\$191	
Classroom #603 (Regular Classroom)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #604 (Regular Classroom)							
	Ceiling - Splined		2	SF	5	\$19	Water stains
	Ceiling - Splined		603	SF	6	\$492	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #605 (Regular Classroom)							
	Ceiling - Splined		1,182	SF	6	\$963	
	Doors - Transom Window		16	SF	6	\$271	Wood panel
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		1,182	SF	6	\$1,183	
	Lighting - Lay-in		32	EA	6	\$3,807	
	Marker Board		8	LF	6	\$171	
	Walls - Masonry		320	SF	6	\$1,007	
	Walls - Metal Panel		1,191	SF	6	\$8,890	
Classroom #607 (Regular Classroom)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #608 (Vacant)							
	Ceiling - Splined		584	SF	6	\$476	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		584	SF	6	\$585	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Walls - Metal Panel		976	SF	6	\$7,285	
Classroom #609 (Computer Lab)							
	Ceiling - Splined		2	SF	5	\$19	water stains

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #609 (Computer Lab)							
	Ceiling - Splined		1,154	SF	6	\$941	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		1,156	SF	6	\$2,463	
	Lighting - Lay-in		30	EA	6	\$3,569	
	Marker Board		8	LF	6	\$171	
	Student Lockers - Two Tiers		8	EA	6	\$371	
	Walls - Concrete Block		166	SF	6	\$487	
	Walls - Masonry		260	SF	6	\$818	
	Walls - Metal Panel		765	SF	6	\$5,710	
Classroom #610 (Regular Classroom)							
	Ceiling - Splined		1	SF	5	\$10	Water stain
	Ceiling - Splined		757	SF	6	\$617	
	Chalk Board		4	LF	6	\$89	
	Doors - Steel Doors incl hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	6	\$2,380	
	Marker Board		8	LF	6	\$171	
	Walls - Masonry		189	SF	6	\$595	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #611 (Regular Classroom)							
	Ceiling - Splined		758	SF	6	\$618	Hole in ceiling
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	6	\$2,380	
	Marker Board		12	LF	6	\$257	
	Walls - Metal Panel		1	SF	5	\$40	Peeling paint
	Walls - Metal Panel		1,216	SF	6	\$9,077	
Classroom #612 (Regular Classroom)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	6	\$89	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		750	SF	6	\$751	
	Lighting - Lay-in		20	EA	6	\$2,380	
	Marker Board		8	LF	6	\$171	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #612 (Regular Classroom)							
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #613 (Regular Classroom)							
	Ceiling - Splined		2	SF	5	\$19	Damaged tiles
	Ceiling - Splined		755	SF	6	\$615	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	6	\$2,380	
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #614 (Regular Classroom)							
	Ceiling - Splined		758	SF	6	\$618	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	6	\$2,380	
	Marker Board		12	LF	6	\$257	
	Walls - Metal Panel		1	SF	5	\$40	Holes in wall
	Walls - Metal Panel		1,216	SF	6	\$9,077	
Classroom #615 (Regular Classroom)							
	Ceiling - Splined		758	SF	5	\$5,398	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	6	\$2,380	
	Marker Board		12	LF	6	\$257	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #616 (Special Education)							
	Ceiling - Splined		665	SF	6	\$542	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Transom Window		1	SF	6	\$17	
	Floor - Tile/Sheet		665	SF	6	\$666	
	Lighting - Lay-in		18	EA	6	\$2,142	
	Marker Board		6	LF	6	\$129	
	Walls - Metal Panel		1,280	SF	6	\$9,555	
Classroom #617 (Regular Classroom)							
	Ceiling - Splined		2	SF	5	\$19	Water stains

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #617 (Regular Classroom)							
	Ceiling - Splined		898	SF	6	\$732	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		24	EA	6	\$2,855	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Masonry		130	SF	6	\$409	
	Walls - Metal Panel		872	SF	6	\$6,509	
Classroom #618 (Regular Classroom)							
	Ceiling - Splined		605	SF	6	\$493	Loose tile
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #619 (Regular Classroom)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		26	LF	6	\$557	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #620 (Regular Classroom)							
	Ceiling - Splined		2	SF	5	\$19	Holes and stains
	Ceiling - Splined		603	SF	6	\$492	
	Doors - Transom Window		1	SF	6	\$17	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #622 (Other Instructional Use)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	6	\$1,904	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #624 (Office)							
	Ceiling - Splined		450	SF	6	\$367	
	Doors - Transom Window		1	SF	6	\$17	
	Floor - Tile/Sheet		450	SF	6	\$450	
	Lighting - Lay-in		15	EA	6	\$1,785	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		55	SF	6	\$161	
	Walls - Metal Panel		304	SF	6	\$2,269	
	Walls - Plaster/Drywall		455	SF	6	\$1,256	
Classroom #625 (Office)							
	Ceiling - Splined		1	SF	5	\$10	Missing tiles
	Ceiling - Splined		449	SF	6	\$366	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		450	SF	6	\$450	
	Lighting - Lay-in		10	EA	6	\$1,190	
	Marker Board		16	LF	6	\$343	
	Walls - Concrete Block		180	SF	6	\$528	
	Walls - Plaster/Drywall		455	SF	6	\$1,256	
Classroom #699 (Regular Classroom)							
	Ceiling - Splined		1	SF	6	\$1	Water stain and damaged tiles
	Ceiling - Splined		1,386	SF	6	\$1,130	
	Doors - Transom Window		1	SF	6	\$17	
	Floor - Tile/Sheet		1,386	SF	6	\$1,387	
	Lighting - Lay-in		40	EA	6	\$4,759	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		280	SF	6	\$821	
	Walls - Metal Panel		760	SF	6	\$5,673	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #699 (Regular Classroom)							
Classroom #701 (Vacant)							
	Ceiling - Lay-in		900	SF	6	\$2,703	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		24	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		908	SF	6	\$6,778	
Classroom #702 (Vacant)							
	Ceiling - Lay-in		900	SF	6	\$2,703	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		24	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		908	SF	6	\$6,778	
Classroom #703 (Vacant)							
	Ceiling - Lay-in		605	SF	6	\$1,817	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #704 (Vacant)							
	Ceiling - Lay-in		605	SF	6	\$1,817	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #704 (Vacant)							
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #705 (Vacant)							
	Ceiling - Splined		1,182	SF	6	\$963	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		1,182	SF	6	\$1,183	
	Lighting - Lay-in		32	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Masonry		320	SF	6	\$1,007	
	Walls - Metal Panel		1,191	SF	6	\$8,890	
Classroom #707 (Vacant)							
	Ceiling - Lay-in		605	SF	6	\$1,817	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #709 (Computer Lab)							
	Ceiling - Lay-in		1,156	SF	6	\$3,471	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		1,156	SF	6	\$2,463	
	Lighting - Lay-in		30	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		166	SF	6	\$487	
	Walls - Masonry		260	SF	6	\$818	
	Walls - Metal Panel		765	SF	6	\$5,710	
	Work Sink		1	EA	6	\$379	
Classroom #710 (Vacant)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	4	\$367	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #710 (Vacant)							
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #711 (Vacant)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	4	\$367	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #712 (Vacant)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	4	\$367	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #713 (Vacant)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	4	\$367	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #714 (Vacant)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	6	\$89	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	5	\$3,244	Lights not working
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #715 (Vacant)							
	Ceiling - Splined		758	SF	6	\$618	
	Chalk Board		4	LF	6	\$89	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		758	SF	6	\$759	
	Lighting - Lay-in		20	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Metal Panel		1,217	SF	6	\$9,084	
Classroom #716C (Store Room)							
	Ceiling - Splined		665	SF	6	\$542	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		665	SF	6	\$666	
	Lighting - Lay-in		18	EA	7	\$0	
	Marker Board		4	LF	6	\$86	
	Walls - Metal Panel		1,280	SF	6	\$9,555	
Classroom #717 (Vacant)							
	Ceiling - Splined		900	SF	6	\$734	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		24	EA	7	\$0	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Masonry		130	SF	6	\$409	
	Walls - Metal Panel		872	SF	6	\$6,509	
	Work Sink		1	EA	6	\$379	
Classroom #718 (Vacant)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #719 (Vacant)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #720 (Vacant)							
	Ceiling - Splined		605	SF	6	\$493	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		605	SF	6	\$606	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		65	SF	6	\$191	
	Walls - Metal Panel		806	SF	6	\$6,016	
Classroom #724 (Vacant)							
	Ceiling - Splined		900	SF	6	\$734	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		900	SF	6	\$901	
	Lighting - Lay-in		25	EA	7	\$0	
	Walls - Concrete Block		230	SF	6	\$674	
	Walls - Metal Panel		304	SF	6	\$2,269	
	Walls - Plaster/Drywall		304	SF	6	\$839	
Classroom #799 (Vacant)							
	Ceiling - Lay-in		1,386	SF	6	\$4,162	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,386	SF	6	\$1,387	
	Lighting - Lay-in		40	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		280	SF	6	\$821	
	Walls - Metal Panel		760	SF	6	\$5,673	
Classroom #801 (Other Instructional Use)							
	Ceiling - Splined		1,320	SF	6	\$1,076	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #801 (Other Instructional Use)							
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,320	SF	6	\$1,321	
	Lighting - Lay-in		38	EA	7	\$0	
	Walls - Structural Glazed Tile		1,460	SF	6	\$4,593	Ceramic Tile
	Work Sink		10	EA	6	\$3,790	
Classroom #802 (Other Instructional Use)							
	Ceiling - Splined		593	SF	6	\$483	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		593	SF	6	\$594	
	Lighting - Lay-in		16	EA	7	\$0	
	Walls - Plaster/Drywall		870	SF	6	\$2,401	
Classroom #804 (Regular Classroom)							
	Ceiling - Splined		728	SF	6	\$593	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		728	SF	6	\$729	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		385	SF	6	\$1,129	
	Walls - Metal Panel		355	SF	6	\$2,650	
Classroom #805 (Regular Classroom)							
	Ceiling - Splined		665	SF	6	\$542	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		665	SF	6	\$666	
	Lighting - Lay-in		18	EA	7	\$0	
	Marker Board		4	LF	6	\$86	
	Walls - Metal Panel		1,280	SF	6	\$9,555	
Classroom #806 (Store Room)							
	Ceiling - Splined		882	SF	6	\$719	
	Doors - Side-lite		10	SF	6	\$167	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #806 (Store Room)							
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Transom Window		1	SF	6	\$17	
	Floor - Tile/Sheet		882	SF	6	\$883	
	Lighting - Lay-in		24	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Concrete Block		400	SF	6	\$1,173	
	Walls - Metal Panel		590	SF	6	\$4,404	
Classroom #807 (Regular Classroom)							
	Ceiling - Splined		460	SF	6	\$375	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		460	SF	6	\$980	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Metal Panel		816	SF	6	\$6,091	
	Work Sink		1	EA	6	\$379	
Classroom #808 (Computer Lab)							
	Ceiling - Splined		1,035	SF	6	\$844	
	Chalk Board		12	LF	6	\$268	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		1,035	SF	6	\$2,205	
	Lighting - Lay-in		30	EA	7	\$0	
	Walls - Metal Panel		1,114	SF	6	\$8,316	
	Work Sink		1	EA	6	\$379	
Classroom #809 (Regular Classroom)							
	Ceiling - Splined		903	SF	6	\$736	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		903	SF	6	\$904	
	Lighting - Lay-in		23	EA	7	\$0	
	Walls - Metal Panel		1,000	SF	6	\$7,465	
	Work Sink		1	EA	6	\$379	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #810 (Science Lab Level 1)							
	Ceiling - Splined		1,483	SF	6	\$1,209	
	Doors - Side-lite		20	SF	6	\$334	
	Doors - Transom Window		24	SF	6	\$406	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Eye Wash Station		1	EA	6	\$336	
	Floor - Tile/Sheet		1,483	SF	6	\$1,484	
	Lighting - Lay-in		24	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Science Lab Elements		1,483	SF	6	\$10,052	
	Science Lab Shower		1	EA	6	\$379	
	Walls - Plaster/Drywall		1,200	SF	6	\$3,312	
	Work Sink		11	EA	6	\$4,169	
Classroom #812 (Store Room)							
	Ceiling - Splined		1,223	SF	6	\$997	
	Chalk Board		12	LF	6	\$268	
	Doors - Side-lite		20	SF	6	\$334	
	Doors - Transom Window		24	SF	6	\$406	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Eye Wash Station		1	EA	6	\$336	
	Floor - Tile/Sheet		1,223	SF	6	\$1,224	
	Lighting - Lay-in		40	EA	7	\$0	
	Science Lab Elements		1,223	SF	6	\$8,290	
	Science Lab Shower		1	EA	6	\$379	
	Walls - Concrete Block		1,100	SF	6	\$3,225	
	Work Sink		11	EA	6	\$4,169	
Classroom #813 (Vacant)							
	Ceiling - Splined		1,223	SF	6	\$997	
	Doors - Side-lite		20	SF	6	\$334	
	Doors - Transom Window		24	SF	6	\$406	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Eye Wash Station		1	EA	6	\$336	
	Floor - Tile/Sheet		1,223	SF	6	\$1,224	
	Gas Line		40	EA	6	\$20,365	
	Lighting - Lay-in		24	EA	7	\$0	
	Marker Board		24	LF	6	\$514	
	Science Lab Elements		1,223	SF	6	\$8,290	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #813 (Vacant)							
	Science Lab Shower		1	EA	6	\$379	
	Walls - Concrete Block		845	SF	6	\$2,477	
	Walls - Metal Panel		355	SF	6	\$2,650	
	Work Sink		10	EA	6	\$3,790	
Classroom #814 (Regular Classroom)							
	Ceiling - Splined		380	SF	6	\$310	
	Chalk Board		4	LF	4	\$367	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		380	SF	6	\$380	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		6	LF	6	\$129	
	Walls - Metal Panel		875	SF	6	\$6,532	
	Work Sink		1	EA	6	\$379	
Classroom #815 (Regular Classroom)							
	Ceiling - Splined		380	SF	6	\$310	
	Chalk Board		4	LF	4	\$367	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		380	SF	6	\$380	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		6	LF	6	\$129	
	Work Sink		1	EA	6	\$379	
Classroom #816 (Science Lab Level 2)							
	Ceiling - Splined		1,225	SF	6	\$998	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,225	SF	6	\$1,226	
	Lighting - Lay-in		35	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Science Lab Elements		1,225	SF	6	\$8,303	
	Walls - Metal Panel		1,557	SF	6	\$11,622	
	Work Sink		8	EA	6	\$3,032	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #816 (Science Lab Level 2)							
Classroom #817 (Science Lab Level 2)							
	Ceiling - Splined		1,093	SF	6	\$891	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,093	SF	6	\$1,094	
	Gas Line		9	EA	6	\$4,582	
	Lighting - Lay-in		35	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Science Lab Elements		1,093	SF	6	\$7,409	
	Walls - Metal Panel		1,487	SF	6	\$11,100	
	Work Sink		9	EA	6	\$3,411	
Classroom #819 (Computer Lab)							
	Ceiling - Lay-in		40	SF	5	\$238	Water damage
	Ceiling - Splined		740	SF	6	\$603	
	Chalk Board		6	LF	6	\$134	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		780	SF	6	\$781	
	Lighting - Lay-in		24	EA	7	\$0	
	Walls - Metal Panel		1,309	SF	6	\$9,771	
Classroom #820 (Science Lab Level 2)							
	Ceiling - Splined		1,093	SF	6	\$891	
	Chalk Board		12	LF	6	\$268	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,093	SF	6	\$1,094	
	Gas Line		9	EA	6	\$4,582	
	Lighting - Lay-in		35	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Science Lab Elements		1,093	SF	6	\$7,409	
	Walls - Metal Panel		1,353	SF	6	\$10,100	
	Work Sink		9	EA	6	\$3,411	
Classroom #821 (Science Lab Level 2)							
	Ceiling - Splined		1,093	SF	6	\$891	
	Chalk Board		12	LF	6	\$268	
	Doors - Side-lite		10	SF	6	\$167	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #821 (Science Lab Level 2)							
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,093	SF	6	\$1,094	
	Lighting - Lay-in		35	EA	7	\$0	
	Marker Board		6	LF	6	\$129	
	Science Lab Elements		1,093	SF	6	\$7,409	
	Walls - Metal Panel		1,353	SF	6	\$10,100	
	Work Sink		9	EA	6	\$3,411	
Classroom #822 (Science Lab Level 1)							
	Ceiling - Splined		1,223	SF	6	\$997	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Eye Wash Station		1	EA	6	\$336	
	Floor - Tile/Sheet		1,223	SF	6	\$1,224	
	Lighting - Lay-in		40	EA	7	\$0	
	Marker Board		24	LF	6	\$514	
	Science Lab Elements		1,223	SF	6	\$8,290	
	Science Lab Shower		1	EA	6	\$379	
	Walls - Concrete Block		845	SF	6	\$2,477	
	Walls - Metal Panel		355	SF	6	\$2,650	
	Work Sink		10	EA	6	\$3,790	
Classroom #823 (Regular Classroom)							
	Ceiling - Splined		380	SF	6	\$310	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		380	SF	6	\$380	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		12	LF	6	\$257	
	Walls - Metal Panel		875	SF	6	\$6,532	
	Work Sink		1	EA	6	\$379	
Classroom #824 (Regular Classroom)							
	Ceiling - Splined		380	SF	6	\$310	
	Chalk Board		8	LF	6	\$178	
	Doors - Side-lite		10	SF	6	\$167	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #824 (Regular Classroom)							
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		380	SF	6	\$380	
	Lighting - Lay-in		16	EA	7	\$0	
	Marker Board		6	LF	6	\$129	
	Walls - Metal Panel		875	SF	6	\$6,532	
	Work Sink		1	EA	6	\$379	
Classroom #826 (Science Lab Level 1)							
	Ceiling - Splined		1,223	SF	6	\$997	
	Doors - Side-lite		10	SF	6	\$167	
	Doors - Transom Window		12	SF	6	\$203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Eye Wash Station		1	EA	6	\$336	
	Floor - Tile/Sheet		1,223	SF	6	\$1,224	
	Lighting - Lay-in		40	EA	7	\$0	
	Marker Board		24	LF	6	\$514	
	Science Lab Elements		1,223	SF	6	\$8,290	
	Science Lab Shower		1	EA	6	\$379	
	Walls - Concrete Block		845	SF	6	\$2,477	
	Walls - Metal Panel		355	SF	6	\$2,650	
	Work Sink		10	EA	6	\$3,790	
Classroom #N/A (Store Room)							
	Ceiling - Splined		2	SF	5	\$19	Damaged and missing tiles
	Ceiling - Splined		500	SF	6	\$408	
	Ceiling - Splined	4th Floor	500	SF	5	\$3,561	
	Ceiling - Splined	4th Floor	2	SF	5	\$19	Damaged and missing tiles
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		502	SF	6	\$1,070	Stains
	Floor - Carpet	4th Floor	502	SF	6	\$1,070	Stains
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Lighting - Lay-in		12	EA	6	\$1,428	
	Walls - Concrete Block	4th Floor	83	SF	6	\$243	
	Walls - Concrete Block		83	SF	6	\$243	
	Walls - Masonry	4th Floor	304	SF	6	\$956	
	Walls - Masonry		304	SF	6	\$956	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #N/A (Store Room)							
	Walls - Metal Panel		347	SF	6	\$2,590	
	Walls - Metal Panel	4th Floor	247	SF	6	\$1,844	

Classrooms Subtotal:

\$1,708,265

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Exposed	015 Rehersal Room	822	SF	6	\$1,222	
	Doors - Transom Window	015 Rehersal Room	1	SF	6	\$17	
	Floor - Wood	015 Rehersal Room	822	SF	6	\$5,795	
	Lighting - Pendent/Surface	015 Rehersal Room	12	EA	6	\$1,487	
	Power Distribution	015 Rehersal Room	4	EA	7	\$0	
	Walls - Concrete Block	015 Rehersal Room	1,435	SF	6	\$4,207	
	Ceiling - Lay-in	100D Auditorium support on stage	113	SF	5	\$672	
	Doors - Wood Doors inclu hw	100D Auditorium support on stage	1	EA	6	\$301	
	Floor - Tile/Sheet	100D Auditorium support on stage	113	SF	6	\$113	
	Lighting - Metal Halide/Sodium Vapor	100D Auditorium support on stage	4	EA	5	\$907	
	Power Distribution	100D Auditorium support on stage	4	EA	6	\$8,500	
	Walls - Concrete Block	100D Auditorium support on stage	298	SF	6	\$874	
	AC Unit	100E Office	2	EA	6	\$991	
	Ceiling - Splined	100E Office	608	SF	6	\$496	
	Doors - Wood Doors inclu hw	100E Office	1	EA	6	\$301	
	Floor - Carpet	100E Office	608	SF	6	\$1,295	
	Lighting - Lay-in	100E Office	9	EA	6	\$1,071	
	Power Distribution	100E Office	12	EA	6	\$25,499	
	Storage/ Closet	100E Office	234	SF	6	\$1,697	#100F
	Walls - Concrete Block	100E Office	945	SF	6	\$2,770	
	Walls - Plaster/Drywall	100E Office	130	SF	6	\$359	
	Work Slnk	100E Office	1	EA	6	\$508	
	Ceiling - Splined	100G Conf. room	222	SF	6	\$181	
	Doors - Transom Window	100G Conf. room	1	SF	6	\$17	
	Floor - Carpet	100G Conf. room	222	SF	6	\$473	
	Lighting - Lay-in	100G Conf. room	6	EA	6	\$714	
	Power Distribution	100G Conf. room	4	EA	6	\$8,500	
	Walls - Concrete Block	100G Conf. room	438	SF	6	\$1,284	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	AC Unit	100J Office	1	EA	6	\$496	
	Ceiling - Splined	100J Office	461	SF	6	\$376	
	Doors - Wood Doors inclu hw	100J Office	1	EA	6	\$301	
	Floor - Carpet	100J Office	461	SF	6	\$982	
	Lighting - Pendent/Surface	100J Office	9	EA	6	\$1,115	
	Power Distribution	100J Office	10	EA	6	\$21,249	
	Walls - Concrete Block	100J Office	788	SF	6	\$2,310	
	Ceiling - Splined	200 Z (200K) Work Room	215	SF	6	\$175	
	Floor - Tile/Sheet	200 Z (200K) Work Room	215	SF	6	\$215	
	Lighting - Lay-in	200 Z (200K) Work Room	6	EA	6	\$714	
	Power Distribution	200 Z (200K) Work Room	8	EA	6	\$16,999	
	Walls - Metal Panel	200 Z (200K) Work Room	450	SF	6	\$3,359	
	Ceiling - Splined	200I Teacher's Cafeteria	2	SF	5	\$19	Damaged and missing tiles
	Ceiling - Splined	200I Teacher's Cafeteria	143	SF	6	\$117	
	Doors - Transom Window	200I Teacher's Cafeteria	1	SF	6	\$17	
	Floor - Tile Quarry	200I Teacher's Cafeteria	145	SF	6	\$307	
	Lighting - Lay-in	200I Teacher's Cafeteria	6	EA	6	\$714	
	Walls - Concrete Block	200I Teacher's Cafeteria	398	SF	6	\$1,167	
	Work Slnk	200I Teacher's Cafeteria	1	EA	6	\$508	
	Ceiling - Splined	213 Copy Room	1	SF	5	\$10	Damaged tile
	Ceiling - Splined	213 Copy Room	437	SF	6	\$356	
	Doors - Side-lite	213 Copy Room	10	SF	6	\$167	
	Doors - Transom Window	213 Copy Room	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	213 Copy Room	1	EA	5	\$1,174	
	Floor - Carpet	213 Copy Room	438	SF	6	\$933	
	Lighting - Lay-in	213 Copy Room	15	EA	6	\$1,785	
	Power Distribution	213 Copy Room	14	EA	6	\$29,748	
	Storage/ Closet	213 Copy Room	254	SF	6	\$1,842	
	Walls - Masonry	213 Copy Room	155	SF	6	\$488	
	Walls - Metal Panel	213 Copy Room	894	SF	6	\$6,673	
	Ceiling - Splined	214 Work Room	438	SF	6	\$357	
	Doors - Side-lite	214 Work Room	10	SF	6	\$167	
	Doors - Transom Window	214 Work Room	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	214 Work Room	1	EA	6	\$301	
	Floor - Carpet	214 Work Room	438	SF	6	\$933	
	Lighting - Lay-in	214 Work Room	15	EA	6	\$1,785	
	Power Distribution	214 Work Room	14	EA	6	\$29,748	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Metal Panel	214 Work Room	894	SF	6	\$6,673	
	Work Slnk	214 Work Room	1	EA	6	\$508	
	Ceiling - Lay-in	218 Conference Room	1,026	SF	6	\$3,081	
	Doors - Transom Window	218 Conference Room	16	SF	6	\$271	Wood panel
	Doors - Wood Doors inclu hw	218 Conference Room	2	EA	6	\$602	
	Floor - Tile/Sheet	218 Conference Room	1,026	SF	6	\$1,027	
	Lighting - Lay-in	218 Conference Room	28	EA	6	\$3,331	
	Power Distribution	218 Conference Room	50	EA	6	\$106,244	
	Storage/ Closet	218 Conference Room	92	SF	6	\$667	
	Walls - Masonry	218 Conference Room	350	SF	6	\$1,101	
	Walls - Metal Panel	218 Conference Room	950	SF	6	\$7,091	
	Ceiling - Splined	301 Film Lab in Library	770	SF	6	\$628	
	Doors - Side-lite	301 Film Lab in Library	90	SF	6	\$1,505	
	Doors - Wood Doors inclu hw	301 Film Lab in Library	1	EA	6	\$301	
	Floor - Carpet	301 Film Lab in Library	770	SF	6	\$1,641	
	Lighting - Lay-in	301 Film Lab in Library	20	EA	6	\$2,380	
	Power Distribution	301 Film Lab in Library	9	EA	6	\$19,124	
	Walls - Concrete Block	301 Film Lab in Library	220	SF	6	\$645	
	Walls - Metal Panel	301 Film Lab in Library	547	SF	6	\$4,083	
	Ceiling - Splined	306 Office	1	SF	5	\$10	Loose tile
	Ceiling - Splined	306 Office	604	SF	6	\$492	
	Doors - Side-lite	306 Office	10	SF	6	\$167	
	Doors - Transom Window	306 Office	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	306 Office	1	EA	6	\$301	
	Floor - Carpet	306 Office	605	SF	6	\$1,289	
	Lighting - Lay-in	306 Office	20	EA	6	\$2,380	
	Power Distribution	306 Office	18	EA	6	\$38,248	
	Walls - Concrete Block	306 Office	65	SF	6	\$191	
	Walls - Metal Panel	306 Office	608	SF	6	\$4,538	
	Ceiling - Splined	307 Office	1	SF	5	\$10	Damaged tiles
	Ceiling - Splined	307 Office	449	SF	6	\$366	
	Doors - Transom Window	307 Office	8	SF	6	\$135	wood panel
	Doors - Wood Doors inclu hw	307 Office	1	EA	6	\$301	
	Floor - Carpet	307 Office	450	SF	6	\$959	
	Lighting - Lay-in	307 Office	12	EA	6	\$1,428	
	Power Distribution	307 Office	18	EA	6	\$38,248	
	Walls - Concrete Block	307 Office	55	SF	6	\$161	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Metal Panel	307 Office	765	SF	6	\$5,710	
	Ceiling - Splined	311 Office	364	SF	6	\$297	
	Doors - Wood Doors inclu hw	311 Office	1	EA	6	\$301	
	Floor - Carpet	311 Office	364	SF	6	\$776	
	Lighting - Lay-in	311 Office	12	EA	6	\$1,428	
	Power Distribution	311 Office	9	EA	6	\$19,124	
	Walls - Concrete Block	311 Office	65	SF	6	\$191	
	Walls - Metal Panel	311 Office	252	SF	6	\$1,881	
	Walls - Plaster/Drywall	311 Office	406	SF	6	\$1,121	
	Ceiling - Splined	312 Office	364	SF	6	\$297	
	Doors - Wood Doors inclu hw	312 Office	1	EA	6	\$301	
	Floor - Carpet	312 Office	364	SF	6	\$776	
	Lighting - Lay-in	312 Office	12	EA	6	\$1,428	
	Power Distribution	312 Office	9	EA	5	\$34,665	
	Walls - Concrete Block	312 Office	41	SF	6	\$120	
	Walls - Metal Panel	312 Office	261	SF	6	\$1,948	
	Walls - Plaster/Drywall	312 Office	416	SF	6	\$1,148	
	Ceiling - Splined	316 Parent University	900	SF	6	\$734	
	Doors - Side-lite	316 Parent University	10	SF	6	\$167	
	Doors - Transom Window	316 Parent University	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	316 Parent University	1	EA	6	\$301	
	Floor - Tile/Sheet	316 Parent University	900	SF	6	\$901	
	Lighting - Lay-in	316 Parent University	24	EA	6	\$2,855	
	Power Distribution	316 Parent University	18	EA	6	\$38,248	
	Storage/ Closet	316 Parent University	48	SF	6	\$348	
	Walls - Concrete Block	316 Parent University	136	SF	6	\$399	
	Walls - Metal Panel	316 Parent University	700	SF	6	\$5,225	
	Walls - Plaster/Drywall	316 Parent University	608	SF	6	\$1,678	
	Ceiling - Splined	317 Office	1,175	SF	6	\$958	
	Doors - Transom Window	317 Office	24	SF	6	\$406	
	Doors - Wood Doors inclu hw	317 Office	2	EA	6	\$602	
	Floor - Tile/Sheet	317 Office	1,175	SF	6	\$1,176	
	Lighting - Lay-in	317 Office	32	EA	6	\$3,807	
	Power Distribution	317 Office	12	EA	6	\$25,499	
	Storage/ Closet	317 Office	215	SF	6	\$1,559	
	Walls - Masonry	317 Office	346	SF	6	\$1,089	
	Walls - Metal Panel	317 Office	145	SF	6	\$1,082	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Plaster/Drywall	317 Office	5	SF	5	\$26	Peeling paint
	Walls - Plaster/Drywall	317 Office	1,320	SF	6	\$3,643	
	Ceiling - Splined	319 Parent University	593	SF	6	\$483	
	Doors - Side-lite	319 Parent University	10	SF	6	\$167	
	Doors - Transom Window	319 Parent University	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	319 Parent University	1	EA	6	\$301	
	Floor - Carpet	319 Parent University	593	SF	6	\$1,264	
	Lighting - Lay-in	319 Parent University	16	EA	6	\$1,904	
	Power Distribution	319 Parent University	6	EA	6	\$12,749	
	Walls - Metal Panel	319 Parent University	1,164	SF	6	\$8,689	
	Ceiling - Splined	320 Teacher Cafeteria	545	SF	4	\$5,689	
	Doors - Side-lite	320 Teacher Cafeteria	10	SF	6	\$167	
	Doors - Transom Window	320 Teacher Cafeteria	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	320 Teacher Cafeteria	1	EA	6	\$301	
	Floor - Carpet	320 Teacher Cafeteria	545	SF	6	\$1,161	
	Lighting - Lay-in	320 Teacher Cafeteria	14	EA	6	\$1,666	
	Power Distribution	320 Teacher Cafeteria	6	EA	6	\$12,749	
	Walls - Concrete Block	320 Teacher Cafeteria	83	SF	6	\$243	
	Walls - Masonry	320 Teacher Cafeteria	282	SF	5	\$11,654	
	Walls - Metal Panel	320 Teacher Cafeteria	510	SF	6	\$3,807	
	Ceiling - Splined	321 Office (Use as Storage)	1	SF	5	\$10	Damage tiles
	Ceiling - Splined	321 Office (Use as Storage)	64	SF	6	\$52	
	Doors - Transom Window	321 Office (Use as Storage)	1	SF	6	\$17	
	Floor - Tile/Sheet	321 Office (Use as Storage)	65	SF	6	\$65	
	Lighting - Lay-in	321 Office (Use as Storage)	1	EA	6	\$119	
	Power Distribution	321 Office (Use as Storage)	2	EA	6	\$4,250	
	Walls - Metal Panel	321 Office (Use as Storage)	185	SF	6	\$1,381	
	Ceiling - Splined	406 Office	211	SF	5	\$1,503	
	Doors - Side-lite	406 Office	10	SF	6	\$167	
	Doors - Transom Window	406 Office	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	406 Office	1	EA	6	\$301	
	Floor - Tile/Sheet	406 Office	211	SF	5	\$947	
	Lighting - Lay-in	406 Office	6	EA	6	\$714	
	Power Distribution	406 Office	10	EA	5	\$38,516	
	Walls - Plaster/Drywall	406 Office	584	SF	6	\$1,612	
	Ceiling - Splined	408A Office	148	SF	6	\$121	
	Floor - Carpet	408A Office	148	SF	6	\$315	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	408A Office	6	EA	6	\$714	
	Power Distribution	408A Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	408A Office	304	SF	6	\$839	
	Ceiling - Splined	408B Office (Vacant)	148	SF	6	\$121	
	Doors - Side-lite	408B Office (Vacant)	10	SF	6	\$167	
	Doors - Transom Window	408B Office (Vacant)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	408B Office (Vacant)	1	EA	6	\$301	
	Floor - Carpet	408B Office (Vacant)	148	SF	6	\$315	
	Lighting - Lay-in	408B Office (Vacant)	6	EA	6	\$714	
	Power Distribution	408B Office (Vacant)	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	408B Office (Vacant)	304	SF	6	\$839	
	Work Slnk	408B Office (Vacant)	1	EA	6	\$508	
	Ceiling - Splined	421 Office	1	SF	5	\$10	Water stain
	Ceiling - Splined	421 Office	279	SF	6	\$227	
	Doors - Side-lite	421 Office	10	SF	6	\$167	
	Doors - Transom Window	421 Office	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	421 Office	1	EA	6	\$301	
	Floor - Carpet	421 Office	280	SF	6	\$597	
	Lighting - Lay-in	421 Office	8	EA	6	\$952	
	Power Distribution	421 Office	10	EA	6	\$21,249	
	Walls - Concrete Block	421 Office	35	SF	6	\$103	
	Walls - Plaster/Drywall	421 Office	608	SF	6	\$1,678	
	Ceiling - Splined	423 Office Suite (A - D)	605	SF	6	\$493	
	Doors - Side-lite	423 Office Suite (A - D)	10	SF	6	\$167	
	Doors - Transom Window	423 Office Suite (A - D)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	423 Office Suite (A - D)	1	EA	6	\$301	
	Floor - Carpet	423 Office Suite (A - D)	605	SF	6	\$1,289	
	Lighting - Lay-in	423 Office Suite (A - D)	28	EA	6	\$3,331	
	Power Distribution	423 Office Suite (A - D)	18	EA	6	\$38,248	
	Walls - Concrete Block	423 Office Suite (A - D)	65	SF	6	\$191	
	Walls - Metal Panel	423 Office Suite (A - D)	806	SF	6	\$6,016	
	Ceiling - Splined	506 Office (Vacant)	211	SF	5	\$1,503	
	Doors - Side-lite	506 Office (Vacant)	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	506 Office (Vacant)	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	506 Office (Vacant)	12	EA	6	\$3,612	
	Floor - Carpet	506 Office (Vacant)	211	SF	6	\$450	
	Lighting - Lay-in	506 Office (Vacant)	6	EA	6	\$714	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	506 Office (Vacant)	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	506 Office (Vacant)	584	SF	6	\$1,612	
	Ceiling - Splined	508 Office	584	SF	6	\$476	
	Doors - Side-lite	508 Office	10	SF	6	\$167	
	Doors - Store Front	508 Office	12	EA	5	\$35,632	
	Doors - Wood Doors inclu hw	508 Office	1	EA	6	\$301	
	Floor - Carpet	508 Office	584	SF	5	\$2,998	
	Lighting - Lay-in	508 Office	15	EA	6	\$1,785	
	Power Distribution	508 Office	22	EA	6	\$46,747	
	Walls - Metal Panel	508 Office	976	SF	6	\$7,285	
	Ceiling - Splined	508A Office	147	SF	6	\$120	
	Ceiling - Splined	508A Office	1	SF	5	\$10	Water stain
	Floor - Carpet	508A Office	148	SF	6	\$315	
	Lighting - Lay-in	508A Office	6	EA	6	\$714	
	Power Distribution	508A Office	4	EA	6	\$8,500	
	Storage/ Closet	508A Office	145	SF	6	\$1,051	#508B
	Walls - Plaster/Drywall	508A Office	304	SF	6	\$839	
	Work Slnk	508A Office	1	EA	6	\$508	
	Ceiling - Splined	509A Office (Vacant)	3	SF	5	\$29	Missing tiles
	Ceiling - Splined	509A Office (Vacant)	247	SF	6	\$201	
	Doors - Wood Doors inclu hw	509A Office (Vacant)	1	EA	6	\$301	
	Floor - Carpet	509A Office (Vacant)	250	SF	6	\$533	
	Lighting - Lay-in	509A Office (Vacant)	6	EA	6	\$714	
	Power Distribution	509A Office (Vacant)	4	EA	6	\$8,500	
	Walls - Concrete Block	509A Office (Vacant)	60	SF	6	\$176	
	Walls - Masonry	509A Office (Vacant)	150	SF	6	\$472	
	Walls - Metal Panel	509A Office (Vacant)	350	SF	6	\$2,613	
	Ceiling - Splined	515A Office (Vacant)	501	SF	6	\$408	
	Ceiling - Splined	515A Office (Vacant)	1	SF	5	\$10	Damaged tile
	Doors - Wood Doors inclu hw	515A Office (Vacant)	1	EA	5	\$1,174	
	Floor - Carpet	515A Office (Vacant)	502	SF	6	\$1,070	Stains
	Lighting - Lay-in	515A Office (Vacant)	12	EA	6	\$1,428	
	Power Distribution	515A Office (Vacant)	6	EA	6	\$12,749	
	Walls - Concrete Block	515A Office (Vacant)	83	SF	6	\$243	
	Walls - Masonry	515A Office (Vacant)	304	SF	6	\$956	
	Walls - Metal Panel	515A Office (Vacant)	347	SF	6	\$2,590	
	Ceiling - Splined	521 Office	280	SF	6	\$228	Hole

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Side-lite	521 Office	10	SF	6	\$167	
	Doors - Transom Window	521 Office	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	521 Office	1	EA	6	\$301	
	Floor - Carpet	521 Office	280	SF	6	\$597	
	Lighting - Lay-in	521 Office	8	EA	6	\$952	
	Power Distribution	521 Office	10	EA	6	\$21,249	
	Walls - Concrete Block	521 Office	35	SF	6	\$103	
	Walls - Plaster/Drywall	521 Office	608	SF	6	\$1,678	
	Ceiling - Splined	523 Office Suite (A - D)	605	SF	6	\$493	
	Doors - Side-lite	523 Office Suite (A - D)	10	SF	6	\$167	
	Doors - Transom Window	523 Office Suite (A - D)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	523 Office Suite (A - D)	1	EA	6	\$301	
	Floor - Carpet	523 Office Suite (A - D)	605	SF	6	\$1,289	
	Lighting - Lay-in	523 Office Suite (A - D)	28	EA	6	\$3,331	
	Power Distribution	523 Office Suite (A - D)	18	EA	6	\$38,248	
	Walls - Concrete Block	523 Office Suite (A - D)	65	SF	6	\$191	
	Walls - Plaster/Drywall	523 Office Suite (A - D)	806	SF	7	\$0	
	Ceiling - Splined	606 Office	211	SF	5	\$1,503	
	Doors - Side-lite	606 Office	10	SF	6	\$167	
	Doors - Transom Window	606 Office	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	606 Office	1	EA	6	\$301	
	Floor - Carpet	606 Office	211	SF	5	\$1,083	
	Lighting - Lay-in	606 Office	6	EA	6	\$714	
	Power Distribution	606 Office	10	EA	5	\$38,516	
	Walls - Plaster/Drywall	606 Office	584	SF	6	\$1,612	
	Ceiling - Splined	608A Office	148	SF	6	\$121	
	Floor - Carpet	608A Office	148	SF	6	\$315	
	Lighting - Lay-in	608A Office	6	EA	6	\$714	
	Power Distribution	608A Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	608A Office	304	SF	6	\$839	
	Ceiling - Splined	608B Office (Vacant)	148	SF	6	\$121	
	Doors - Side-lite	608B Office (Vacant)	10	SF	6	\$167	
	Doors - Transom Window	608B Office (Vacant)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	608B Office (Vacant)	1	EA	6	\$301	
	Floor - Carpet	608B Office (Vacant)	148	SF	6	\$315	
	Lighting - Lay-in	608B Office (Vacant)	6	EA	6	\$714	
	Power Distribution	608B Office (Vacant)	4	EA	6	\$8,500	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Plaster/Drywall	608B Office (Vacant)	304	SF	6	\$839	
	Work Slnk	608B Office (Vacant)	1	EA	6	\$508	
	Ceiling - Splined	609A Office (Vacant)	250	SF	6	\$204	Loose tile
	Doors - Transom Window	609A Office (Vacant)	1	SF	6	\$17	
	Floor - Carpet	609A Office (Vacant)	250	SF	6	\$533	
	Lighting - Lay-in	609A Office (Vacant)	6	EA	6	\$714	
	Power Distribution	609A Office (Vacant)	4	EA	6	\$8,500	
	Walls - Concrete Block	609A Office (Vacant)	60	SF	6	\$176	
	Walls - Masonry	609A Office (Vacant)	150	SF	6	\$472	
	Walls - Metal Panel	609A Office (Vacant)	350	SF	6	\$2,613	
	Ceiling - Splined	621 Office	1	SF	5	\$10	Damaged tiles
	Ceiling - Splined	621 Office	279	SF	6	\$227	
	Doors - Side-lite	621 Office	10	SF	6	\$167	
	Doors - Transom Window	621 Office	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	621 Office	1	EA	6	\$301	
	Floor - Carpet	621 Office	280	SF	5	\$1,437	
	Lighting - Lay-in	621 Office	8	EA	5	\$1,298	
	Power Distribution	621 Office	10	EA	6	\$21,249	
	Walls - Concrete Block	621 Office	35	SF	6	\$103	
	Walls - Plaster/Drywall	621 Office	608	SF	6	\$1,678	Metal Panel
	Ceiling - Lay-in	Dressing Room behind Theater	227	SF	6	\$682	
	Doors - Wood Doors inclu hw	Dressing Room behind Theater	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Dressing Room behind Theater	227	SF	6	\$480	
	Lighting - Lay-in	Dressing Room behind Theater	8	EA	6	\$952	
	Lighting - Wall Mounted	Dressing Room behind Theater	4	EA	6	\$496	
	Power Distribution	Dressing Room behind Theater	4	EA	6	\$8,500	
	Walls - Concrete Block	Dressing Room behind Theater	775	SF	6	\$2,272	
	Ceiling - Plaster/Drywall	Employee Lounge in Kitchen	88	SF	6	\$305	
	Doors - Wood Doors inclu hw	Employee Lounge in Kitchen	1	EA	6	\$301	
	Floor - Tile/Sheet	Employee Lounge in Kitchen	88	SF	6	\$88	
	Lighting - Lay-in	Employee Lounge in Kitchen	4	EA	7	\$0	
	Power Distribution	Employee Lounge in Kitchen	4	EA	6	\$8,500	
	Walls - Concrete Block	Employee Lounge in Kitchen	225	SF	6	\$660	
	Ceiling - Plaster/Drywall	Engineer's Office	165	SF	6	\$571	
	Doors - Wood Doors inclu hw	Engineer's Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Engineer's Office	165	SF	6	\$165	
	Lighting - Lay-in	Engineer's Office	4	EA	6	\$476	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	Engineer's Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Engineer's Office	535	SF	6	\$1,568	
	Ceiling - Plaster/Drywall	Kitchen Supervisor's Office	99	SF	6	\$343	
	Doors - Wood Doors inclu hw	Kitchen Supervisor's Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Kitchen Supervisor's Office	99	SF	6	\$210	
	Lighting - Lay-in	Kitchen Supervisor's Office	4	EA	7	\$0	
	Power Distribution	Kitchen Supervisor's Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Kitchen Supervisor's Office	395	SF	6	\$1,158	
	Ceiling - Splined	Located in 300 MDF room	153	SF	6	\$125	
	Doors - Wood Doors inclu hw	Located in 300 MDF room	1	EA	6	\$301	
	Floor - Carpet	Located in 300 MDF room	153	SF	6	\$326	
	Lighting - Lay-in	Located in 300 MDF room	6	EA	6	\$714	
	Power Distribution	Located in 300 MDF room	4	EA	6	\$8,500	
	Walls - Metal Panel	Located in 300 MDF room	310	SF	6	\$2,314	
	Walls - Plaster/Drywall	Located in 300 MDF room	150	SF	6	\$414	
	Ceiling - Splined	Main Office 200	1,310	SF	6	\$1,068	
	Doors - Side-lite	Main Office 200	60	SF	6	\$1,003	
	Doors - Store Front	Main Office 200	2	EA	6	\$2,416	
	Doors - Transom Window	Main Office 200	24	SF	6	\$406	
	Floor - Tile/Sheet	Main Office 200	1,310	SF	5	\$5,882	
	Lighting - Lay-in	Main Office 200	36	EA	5	\$5,839	
	Power Distribution	Main Office 200	18	EA	6	\$38,248	
	Storage/ Closet	Main Office 200	145	SF	5	\$2,339	#200B
	Walls - Concrete Block	Main Office 200	350	SF	6	\$1,026	
	Walls - Metal Panel	Main Office 200	750	SF	6	\$5,598	
	Ceiling - Plaster/Drywall	Maintenance Office	211	SF	6	\$730	
	Doors - Side-lite	Maintenance Office	24	SF	6	\$401	
	Doors - Wood Doors inclu hw	Maintenance Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Maintenance Office	211	SF	6	\$211	
	Lighting - Lay-in	Maintenance Office	6	EA	6	\$714	
	Power Distribution	Maintenance Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Maintenance Office	525	SF	6	\$1,539	
	Ceiling - Splined	Nurse/Health Office 219A/219M	5	SF	5	\$48	Damaged and missing tiles
	Ceiling - Splined	Nurse/Health Office 219A/219M	730	SF	6	\$595	
	Doors - Side-lite	Nurse/Health Office 219A/219M	10	SF	6	\$167	
	Doors - Transom Window	Nurse/Health Office 219A/219M	1	SF	6	\$17	
	Doors - Transom Window	Nurse/Health Office 219A/219M	12	SF	6	\$203	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Tile/Sheet	Nurse/Health Office 219A/219M	735	SF	6	\$736	
	Lighting - Lay-in	Nurse/Health Office 219A/219M	19	EA	6	\$2,261	
	Walls - Concrete Block	Nurse/Health Office 219A/219M	106	SF	6	\$311	
	Walls - Metal Panel	Nurse/Health Office 219A/219M	1,167	SF	6	\$8,711	
	Ceiling - Splined	Office 003 (037)	620	SF	6	\$505	
	Doors - Wood Doors inclu hw	Office 003 (037)	1	EA	6	\$301	
	Floor - Carpet	Office 003 (037)	620	SF	6	\$1,321	
	Lighting - Lay-in	Office 003 (037)	12	EA	7	\$0	
	Power Distribution	Office 003 (037)	8	EA	6	\$16,999	
	Walls - Concrete Block	Office 003 (037)	600	SF	6	\$1,759	
	Ceiling - Splined	Office 200 A (200M)	150	SF	6	\$122	
	Doors - Side-lite	Office 200 A (200M)	40	SF	6	\$669	
	Doors - Store Front	Office 200 A (200M)	20	EA	6	\$24,164	
	Doors - Wood Doors inclu hw	Office 200 A (200M)	1	EA	5	\$1,174	
	Floor - Tile/Sheet	Office 200 A (200M)	150	SF	6	\$150	
	Lighting - Lay-in	Office 200 A (200M)	3	EA	6	\$357	
	Power Distribution	Office 200 A (200M)	8	EA	6	\$16,999	
	Walls - Concrete Block	Office 200 A (200M)	55	SF	6	\$161	
	Walls - Metal Panel	Office 200 A (200M)	250	SF	6	\$1,866	
	Ceiling - Splined	Office 200 B (200L)	150	SF	6	\$122	
	Doors - Transom Window	Office 200 B (200L)	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	Office 200 B (200L)	1	EA	6	\$301	
	Floor - Tile/Sheet	Office 200 B (200L)	150	SF	6	\$150	
	Lighting - Lay-in	Office 200 B (200L)	6	EA	5	\$973	
	Power Distribution	Office 200 B (200L)	8	EA	5	\$30,813	
	Walls - Metal Panel	Office 200 B (200L)	500	SF	6	\$3,732	
	Ceiling - Splined	Office 200 D (waiting area)	290	SF	5	\$2,065	
	Doors - Side-lite	Office 200 D (waiting area)	12	SF	6	\$201	
	Doors - Store Front	Office 200 D (waiting area)	16	EA	5	\$47,509	
	Doors - Transom Window	Office 200 D (waiting area)	1	SF	5	\$42	
	Floor - Tile/Sheet	Office 200 D (waiting area)	290	SF	6	\$290	
	Lighting - Lay-in	Office 200 D (waiting area)	12	EA	6	\$1,428	
	Power Distribution	Office 200 D (waiting area)	8	EA	6	\$16,999	
	Storage/ Closet	Office 200 D (waiting area)	76	SF	6	\$551	#200F
	Walls - Metal Panel	Office 200 D (waiting area)	400	SF	6	\$2,986	
	Ceiling - Splined	Office 200 J (200E Prin. Office)	515	SF	6	\$420	
	Doors - Side-lite	Office 200 J (200E Prin. Office)	10	SF	6	\$167	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Transom Window	Office 200 J (200E Prin. Office)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Office 200 J (200E Prin. Office)	1	EA	6	\$301	
	Floor - Tile/Sheet	Office 200 J (200E Prin. Office)	515	SF	6	\$516	
	Lighting - Lay-in	Office 200 J (200E Prin. Office)	10	EA	6	\$1,190	
	Power Distribution	Office 200 J (200E Prin. Office)	8	EA	6	\$16,999	
	Walls - Concrete Block	Office 200 J (200E Prin. Office)	90	SF	6	\$264	
	Walls - Metal Panel	Office 200 J (200E Prin. Office)	500	SF	6	\$3,732	
	Ceiling - Splined	Office 200 K (200A use as storage)	2	SF	5	\$19	Damaged and missing tiles
	Ceiling - Splined	Office 200 K (200A use as storage)	213	SF	6	\$174	
	Doors - Transom Window	Office 200 K (200A use as storage)	8	SF	6	\$135	Wood panel
	Doors - Wood Doors inclu hw	Office 200 K (200A use as storage)	1	EA	6	\$301	
	Floor - Tile/Sheet	Office 200 K (200A use as storage)	215	SF	6	\$215	
	Lighting - Lay-in	Office 200 K (200A use as storage)	3	EA	6	\$357	
	Power Distribution	Office 200 K (200A use as storage)	8	EA	6	\$16,999	
	Walls - Metal Panel	Office 200 K (200A use as storage)	450	SF	6	\$3,359	
	AC Unit	Office 200E (200F Asst. Prin.)	1	EA	6	\$496	
	Ceiling - Splined	Office 200E (200F Asst. Prin.)	150	SF	6	\$122	Scuffed markings
	Doors - Side-lite	Office 200E (200F Asst. Prin.)	10	SF	6	\$167	
	Doors - Transom Window	Office 200E (200F Asst. Prin.)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Office 200E (200F Asst. Prin.)	1	EA	6	\$301	
	Floor - Tile/Sheet	Office 200E (200F Asst. Prin.)	150	SF	6	\$150	
	Lighting - Lay-in	Office 200E (200F Asst. Prin.)	3	EA	6	\$357	
	Power Distribution	Office 200E (200F Asst. Prin.)	8	EA	6	\$16,999	
	Walls - Concrete Block	Office 200E (200F Asst. Prin.)	55	SF	6	\$161	
	Walls - Metal Panel	Office 200E (200F Asst. Prin.)	250	SF	6	\$1,866	
	AC Unit	Office 200G	1	EA	6	\$496	
	Ceiling - Splined	Office 200G	2	SF	5	\$19	Damaged tiles
	Ceiling - Splined	Office 200G	298	SF	6	\$243	
	Doors - Side-lite	Office 200G	10	SF	6	\$167	
	Doors - Transom Window	Office 200G	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Office 200G	1	EA	6	\$301	
	Floor - Tile/Sheet	Office 200G	300	SF	6	\$300	
	Lighting - Lay-in	Office 200G	8	EA	6	\$952	
	Power Distribution	Office 200G	8	EA	5	\$30,813	
	Walls - Concrete Block	Office 200G	65	SF	6	\$191	
	Walls - Metal Panel	Office 200G	550	SF	6	\$4,106	
	Ceiling - Splined	Office 300B	160	SF	6	\$130	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Steel Doors incl hw	Office 300B	1	EA	6	\$301	
	Floor - Carpet	Office 300B	160	SF	6	\$341	
	Lighting - Lay-in	Office 300B	4	EA	6	\$476	
	Power Distribution	Office 300B	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Office 300B	500	SF	6	\$1,380	
	Ceiling - Splined	Office 313 Suite (A,B, & G)	2	SF	5	\$19	Damaged tiles
	Ceiling - Splined	Office 313 Suite (A,B, & G)	743	SF	6	\$606	
	Doors - Side-lite	Office 313 Suite (A,B, & G)	10	SF	6	\$167	
	Doors - Transom Window	Office 313 Suite (A,B, & G)	12	SF	6	\$203	
	Doors - Transom Window	Office 313 Suite (A,B, & G)	1	SF	6	\$17	
	Floor - Carpet	Office 313 Suite (A,B, & G)	745	SF	6	\$1,587	
	Lighting - Lay-in	Office 313 Suite (A,B, & G)	24	EA	6	\$2,855	
	Power Distribution	Office 313 Suite (A,B, & G)	18	EA	6	\$38,248	
	Walls - Concrete Block	Office 313 Suite (A,B, & G)	115	SF	6	\$337	
	Walls - Metal Panel	Office 313 Suite (A,B, & G)	806	SF	6	\$6,016	
	Walls - Plaster/Drywall	Office 313 Suite (A,B, & G)	2	SF	5	\$10	Peeling paint
	Walls - Plaster/Drywall	Office 313 Suite (A,B, & G)	598	SF	6	\$1,650	
	Ceiling - Splined	Office 623 Suite (A-D)	605	SF	6	\$493	
	Doors - Side-lite	Office 623 Suite (A-D)	10	SF	6	\$167	
	Doors - Transom Window	Office 623 Suite (A-D)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Office 623 Suite (A-D)	1	EA	6	\$301	
	Floor - Carpet	Office 623 Suite (A-D)	605	SF	6	\$1,289	
	Lighting - Lay-in	Office 623 Suite (A-D)	28	EA	6	\$3,331	
	Power Distribution	Office 623 Suite (A-D)	18	EA	6	\$38,248	
	Walls - Concrete Block	Office 623 Suite (A-D)	65	SF	6	\$191	
	Walls - Plaster/Drywall	Office 623 Suite (A-D)	806	SF	6	\$2,224	
	Ceiling - Splined	Office 710A	250	SF	6	\$204	
	Doors - Wood Doors inclu hw	Office 710A	1	EA	6	\$301	
	Floor - Carpet	Office 710A	250	SF	6	\$533	
	Lighting - Lay-in	Office 710A	6	EA	7	\$0	
	Power Distribution	Office 710A	4	EA	6	\$8,500	
	Walls - Concrete Block	Office 710A	150	SF	6	\$440	Masonry
	Walls - Concrete Block	Office 710A	60	SF	6	\$202	
	Walls - Plaster/Drywall	Office 710A	350	SF	6	\$966	Metal Panel
	Ceiling - Splined	Office 721 (720A)	280	SF	6	\$228	
	Doors - Side-lite	Office 721 (720A)	10	SF	6	\$167	
	Doors - Transom Window	Office 721 (720A)	12	SF	6	\$203	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Wood Doors inclu hw	Office 721 (720A)	1	EA	6	\$301	
	Floor - Carpet	Office 721 (720A)	280	SF	6	\$597	
	Lighting - Lay-in	Office 721 (720A)	8	EA	7	\$0	
	Power Distribution	Office 721 (720A)	10	EA	6	\$21,249	
	Walls - Concrete Block	Office 721 (720A)	35	SF	6	\$103	
	Walls - Plaster/Drywall	Office 721 (720A)	608	SF	6	\$1,678	Metal Panel
	Ceiling - Splined	Office 723 Suite (A - D)	605	SF	6	\$493	
	Doors - Side-lite	Office 723 Suite (A - D)	10	SF	6	\$167	
	Doors - Transom Window	Office 723 Suite (A - D)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Office 723 Suite (A - D)	5	EA	6	\$1,505	
	Floor - Tile/Sheet	Office 723 Suite (A - D)	605	SF	6	\$606	300 SF is carpeted
	Lighting - Lay-in	Office 723 Suite (A - D)	28	EA	7	\$0	
	Power Distribution	Office 723 Suite (A - D)	18	EA	6	\$38,248	
	Walls - Concrete Block	Office 723 Suite (A - D)	65	SF	6	\$191	
	Walls - Plaster/Drywall	Office 723 Suite (A - D)	806	SF	6	\$2,224	
	Ceiling - Splined	Room 071A	88	SF	6	\$72	
	Doors - Wood Doors inclu hw	Room 071A	1	EA	6	\$301	
	Floor - Carpet	Room 071A	88	SF	6	\$188	
	Lighting - Lay-in	Room 071A	2	EA	7	\$0	
	Power Distribution	Room 071A	4	EA	6	\$8,500	
	Walls - Concrete Block	Room 071A	392	SF	6	\$1,149	
	Ceiling - Splined	Room 207A (Work Room #1)	211	SF	6	\$172	
	Doors - Side-lite	Room 207A (Work Room #1)	12	SF	6	\$201	
	Doors - Transom Window	Room 207A (Work Room #1)	1	SF	6	\$17	
	Floor - Tile/Sheet	Room 207A (Work Room #1)	211	SF	6	\$211	
	Lighting - Lay-in	Room 207A (Work Room #1)	3	EA	6	\$357	
	Power Distribution	Room 207A (Work Room #1)	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Room 207A (Work Room #1)	455	SF	6	\$1,256	
	Ceiling - Splined	Room 207D (work room #2)	27	SF	5	\$192	
	Doors - Side-lite	Room 207D (work room #2)	24	SF	6	\$401	
	Doors - Store Front	Room 207D (work room #2)	1	EA	6	\$1,208	
	Floor - Tile/Sheet	Room 207D (work room #2)	275	SF	6	\$275	
	Lighting - Lay-in	Room 207D (work room #2)	6	EA	6	\$714	
	Power Distribution	Room 207D (work room #2)	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Room 207D (work room #2)	655	SF	6	\$1,808	
	Ceiling - Splined	Room 301B Office in Library	2	SF	5	\$19	Damaged and missing tiles
	Ceiling - Splined	Room 301B Office in Library	850	SF	6	\$693	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Side-lite	Room 301B Office in Library	10	SF	6	\$167	
	Doors - Transom Window	Room 301B Office in Library	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Room 301B Office in Library	1	EA	6	\$301	
	Floor - Carpet	Room 301B Office in Library	852	SF	6	\$1,815	
	Lighting - Lay-in	Room 301B Office in Library	22	EA	6	\$2,617	
	Power Distribution	Room 301B Office in Library	10	EA	6	\$21,249	
	Walls - Concrete Block	Room 301B Office in Library	108	SF	6	\$317	
	Walls - Masonry	Room 301B Office in Library	282	SF	6	\$887	
	Walls - Metal Panel	Room 301B Office in Library	937	SF	6	\$6,994	
	Ceiling - Splined	Room 302	745	SF	6	\$607	
	Doors - Side-lite	Room 302	10	SF	6	\$167	
	Doors - Transom Window	Room 302	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Room 302	1	EA	6	\$301	
	Floor - Carpet	Room 302	745	SF	6	\$1,587	
	Lighting - Lay-in	Room 302	20	EA	6	\$2,380	
	Power Distribution	Room 302	4	EA	6	\$8,500	
	Walls - Concrete Block	Room 302	90	SF	6	\$264	
	Walls - Metal Panel	Room 302	547	SF	6	\$4,083	
	Walls - Plaster/Drywall	Room 302	300	SF	6	\$828	
	Ceiling - Splined	Room 303	605	SF	6	\$493	
	Doors - Side-lite	Room 303	10	SF	6	\$167	
	Doors - Store Front	Room 303	12	EA	6	\$14,498	
	Doors - Wood Doors inclu hw	Room 303	1	EA	6	\$301	
	Floor - Carpet	Room 303	605	SF	6	\$1,289	
	Lighting - Lay-in	Room 303	16	EA	6	\$1,904	
	Power Distribution	Room 303	18	EA	6	\$38,248	
	Walls - Concrete Block	Room 303	65	SF	6	\$191	
	Walls - Metal Panel	Room 303	608	SF	6	\$4,538	
	Ceiling - Splined	Room 308 (Use as Storage)	1	SF	5	\$10	Damaged tile
	Ceiling - Splined	Room 308 (Use as Storage)	449	SF	6	\$366	
	Doors - Side-lite	Room 308 (Use as Storage)	10	SF	6	\$167	
	Doors - Transom Window	Room 308 (Use as Storage)	12	SF	6	\$203	
	Doors - Transom Window	Room 308 (Use as Storage)	1	SF	6	\$17	
	Floor - Carpet	Room 308 (Use as Storage)	450	SF	6	\$959	
	Lighting - Lay-in	Room 308 (Use as Storage)	16	EA	6	\$1,904	
	Power Distribution	Room 308 (Use as Storage)	18	EA	6	\$38,248	
	Walls - Concrete Block	Room 308 (Use as Storage)	55	SF	6	\$161	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Metal Panel	Room 308 (Use as Storage)	765	SF	6	\$5,710	
	Ceiling - Splined	Room 309	770	SF	6	\$628	
	Doors - Side-lite	Room 309	10	SF	6	\$167	
	Doors - Transom Window	Room 309	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Room 309	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 309	770	SF	6	\$771	
	Lighting - Lay-in	Room 309	20	EA	6	\$2,380	
	Power Distribution	Room 309	9	EA	6	\$19,124	
	Walls - Concrete Block	Room 309	220	SF	6	\$645	
	Walls - Metal Panel	Room 309	547	SF	6	\$4,083	
	Ceiling - Splined	Room 322, Dean's Office	1	SF	5	\$10	Damaged tiles
	Ceiling - Splined	Room 322, Dean's Office	204	SF	6	\$166	
	Doors - Transom Window	Room 322, Dean's Office	8	SF	6	\$135	Wood panel
	Doors - Wood Doors inclu hw	Room 322, Dean's Office	1	EA	6	\$301	
	Floor - Carpet	Room 322, Dean's Office	205	SF	6	\$437	
	Lighting - Lay-in	Room 322, Dean's Office	4	EA	6	\$476	
	Power Distribution	Room 322, Dean's Office	6	EA	6	\$12,749	
	Walls - Masonry	Room 322, Dean's Office	196	SF	6	\$617	
	Walls - Plaster/Drywall	Room 322, Dean's Office	522	SF	6	\$1,441	
	Ceiling - Splined	Room 708 Teacher's Lounge	584	SF	6	\$476	
	Doors - Side-lite	Room 708 Teacher's Lounge	10	SF	6	\$167	
	Doors - Transom Window	Room 708 Teacher's Lounge	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Room 708 Teacher's Lounge	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 708 Teacher's Lounge	584	SF	6	\$585	
	Lighting - Lay-in	Room 708 Teacher's Lounge	15	EA	7	\$0	
	Power Distribution	Room 708 Teacher's Lounge	22	EA	6	\$46,747	
	Walls - Plaster/Drywall	Room 708 Teacher's Lounge	976	SF	6	\$2,694	The walls are Metal Panels
	Ceiling - Splined	Room 708A	211	SF	6	\$172	
	Doors - Wood Doors inclu hw	Room 708A	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 708A	211	SF	6	\$211	
	Lighting - Lay-in	Room 708A	6	EA	7	\$0	
	Power Distribution	Room 708A	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	Room 708A	584	SF	6	\$1,612	
	Ceiling - Splined	Room 708B	148	SF	6	\$121	
	Doors - Wood Doors inclu hw	Room 708B	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 708B	148	SF	6	\$148	
	Lighting - Lay-in	Room 708B	6	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	Room 708B	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Room 708B	304	SF	6	\$839	
	Ceiling - Splined	Room 722 (Storage)	605	SF	6	\$493	
	Doors - Side-lite	Room 722 (Storage)	10	SF	6	\$167	
	Doors - Transom Window	Room 722 (Storage)	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	Room 722 (Storage)	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 722 (Storage)	605	SF	6	\$606	
	Lighting - Lay-in	Room 722 (Storage)	16	EA	7	\$0	
	Power Distribution	Room 722 (Storage)	18	EA	6	\$38,248	
	Walls - Concrete Block	Room 722 (Storage)	65	SF	6	\$191	
	Walls - Plaster/Drywall	Room 722 (Storage)	806	SF	6	\$2,224	Metal Panel
	Ceiling - Splined	Room 800, Teacher's Work Area	635	SF	6	\$518	
	Doors - Wood Doors inclu hw	Room 800, Teacher's Work Area	2	EA	6	\$602	
	Floor - Tile/Sheet	Room 800, Teacher's Work Area	635	SF	6	\$636	
	Lighting - Pendant/Surface	Room 800, Teacher's Work Area	6	EA	7	\$0	
	Power Distribution	Room 800, Teacher's Work Area	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Room 800, Teacher's Work Area	925	SF	6	\$2,553	Metal Panel
Auditorium & Theater							
	Ceiling - Lay-in	1st Floor	11,594	SF	6	\$34,817	
	Doors - Wood Doors inclu hw	1st Floor	4	EA	6	\$1,204	
	Floor - Carpet	1st Floor	7,642	SF	6	\$16,283	
	Floor - Terrazzo	1st Floor	3,952	SF	6	\$8,647	
	Lighting - Lay-in	1st Floor	146	EA	6	\$17,370	
	Main Floor Seating	1st Floor	623	EA	6	\$108,350	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	998	SF	6	\$5,766	Wood
	Stage Curtain	1st Floor	3	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Storage/ Closet	1st Floor	1,976	SF	6	\$14,326	Storage area behind stage
	Walls - Masonry	1st Floor	11,594	SF	6	\$36,475	
Clinic							
	Ceiling - Lay-in	Health Area 221,221F,211D	578	SF	6	\$1,736	
	Doors - Wood Doors inclu hw	Health Area 221,221F,211D	1	EA	6	\$301	
	Floor - Tile Quarry	Health Area 221,221F,211D	578	SF	6	\$1,223	
	Lighting - Lay-in	Health Area 221,221F,211D	14	EA	7	\$0	
	Walls - Concrete Block	Health Area 221,221F,211D	110	SF	6	\$322	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Clinic							
	Walls - Plaster/Drywall	Health Area 221,221F,211D	980	SF	6	\$2,705	
	Ceiling - Lay-in	Health Clinic Suite 222	645	SF	6	\$1,937	
	Floor - Tile/Sheet	Health Clinic Suite 222	645	SF	6	\$646	
	Lighting - Lay-in	Health Clinic Suite 222	10	EA	6	\$1,190	
	Walls - Concrete Block	Health Clinic Suite 222	98	SF	6	\$287	
	Walls - Plaster/Drywall	Health Clinic Suite 222	910	SF	6	\$2,512	
Kitchen							
	Ceiling - Splined	4th Floor for Student Cafeteria	454	SF	6	\$370	
	Doors - Wood Doors inclu hw	4th Floor for Student Cafeteria	2	EA	6	\$602	
	Floor - Tile Quarry	4th Floor for Student Cafeteria	454	SF	6	\$961	
	Lighting - Lay-in	4th Floor for Student Cafeteria	10	EA	6	\$1,190	
	Walls - Concrete Block	4th Floor for Student Cafeteria	797	SF	6	\$2,336	
	Ceiling - Splined	5th Floor for Student Cafeteria	454	SF	6	\$370	
	Doors - Wood Doors inclu hw	5th Floor for Student Cafeteria	2	EA	6	\$602	
	Floor - Tile Quarry	5th Floor for Student Cafeteria	454	SF	6	\$961	
	Lighting - Lay-in	5th Floor for Student Cafeteria	10	EA	6	\$1,190	
	Walls - Concrete Block	5th Floor for Student Cafeteria	797	SF	6	\$2,336	
	Ceiling - Splined	6th Floor for Student Cafeteria	454	SF	6	\$370	
	Doors - Steel Doors incl hw	6th Floor for Student Cafeteria	1	EA	6	\$301	
	Floor - Tile Quarry	6th Floor for Student Cafeteria	454	SF	6	\$961	
	Lighting - Lay-in	6th Floor for Student Cafeteria	10	EA	6	\$1,190	
	Serving Line	6th Floor for Student Cafeteria	15	LF	6	\$893	
	Walls - Concrete Block	6th Floor for Student Cafeteria	797	SF	6	\$2,336	
	Ceiling - Splined	7th Floor for Student Lunchroom	454	SF	6	\$370	
	Doors - Steel Doors incl hw	7th Floor for Student Lunchroom	1	EA	6	\$301	
	Floor - Tile Quarry	7th Floor for Student Lunchroom	454	SF	6	\$961	
	Lighting - Lay-in	7th Floor for Student Lunchroom	10	EA	6	\$1,190	
	Serving Line	7th Floor for Student Lunchroom	15	LF	6	\$893	
	Walls - Concrete Block	7th Floor for Student Lunchroom	797	SF	6	\$2,336	
	Ceiling - Plaster/Drywall	Lower Level	3,553	SF	6	\$12,296	
	Doors - Wood Doors inclu hw	Lower Level	4	EA	6	\$1,204	
	Floor - Tile Quarry	Lower Level	3,553	SF	6	\$7,520	
	Lighting - Lay-in	Lower Level	60	EA	7	\$0	
	Walls - Concrete Block	Lower Level	8,171	SF	6	\$23,953	
Library							
	Ceiling - Lay-in	3rd Floor	7,814	SF	6	\$23,465	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Library							
	Doors - Side-lite	3rd Floor	80	SF	6	\$1,337	
	Doors - Store Front	3rd Floor	4	EA	6	\$4,833	
	Doors - Transom Window	3rd Floor	48	SF	6	\$813	
	Floor - Carpet	3rd Floor	7,814	SF	6	\$16,649	
	Lighting - Lay-in	3rd Floor	208	EA	6	\$24,747	
	Walls - Masonry	3rd Floor	9,457	SF	6	\$29,752	
Locker/Shower Room							
	Accessories	Men's Locker Room in the Dressing Room	265	SF	6	\$1,038	
	Benches, ped mounted	Men's Locker Room in the Dressing Room	4	LF	6	\$436	
	Ceiling - Plaster/ Drywall	Men's Locker Room in the Dressing Room	265	SF	6	\$917	
	Doors - Wood Doors inclu hw	Men's Locker Room in the Dressing Room	2	EA	6	\$602	
	Floor Drain	Men's Locker Room in the Dressing Room	3	EA	6	\$3,177	
	Floor - Tile Ceramic/ Porcelain	Men's Locker Room in the Dressing Room	265	SF	6	\$561	
	Hand Dryer	Men's Locker Room in the Dressing Room	1	EA	6	\$230	
	Lavatory	Men's Locker Room in the Dressing Room	1	EA	6	\$320	
	Lighting - Lay-in	Men's Locker Room in the Dressing Room	7	EA	6	\$833	
	Partitions	Men's Locker Room in the Dressing Room	1	EA	6	\$297	
	Showers	Men's Locker Room in the Dressing Room	2	EA	6	\$623	
	Student Lockers - One Tier	Men's Locker Room in the Dressing Room	9	EA	6	\$836	
	Urinals	Men's Locker Room in the Dressing Room	1	EA	6	\$336	
	Walls - Concrete Block	Men's Locker Room in the Dressing Room	302	SF	6	\$885	
	Walls - Tile Ceramic/ Porcelain	Men's Locker Room in the Dressing Room	265	SF	6	\$599	
	Water Closet	Men's Locker Room in the Dressing Room	1	EA	6	\$336	
	Ceiling - Splined (Moister Resistance)	Staff Lockers Between Storage 200B & 218	104	SF	6	\$109	Loose tiles

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Doors - Wood Doors inclu hw	Staff Lockers Between Storage 200B & 218	1	EA	6	\$301	
	Floor - Tile/Sheet	Staff Lockers Between Storage 200B & 218	104	SF	6	\$104	
	Lighting - Lay-in	Staff Lockers Between Storage 200B & 218	6	EA	6	\$714	
	Student Lockers - One Tier	Staff Lockers Between Storage 200B & 218	25	EA	6	\$2,321	
	Walls - Metal Panel	Staff Lockers Between Storage 200B & 218	600	SF	6	\$4,479	
	Accessories	Women's Locker Room in the Dressing room	265	SF	6	\$1,038	
	Benches, ped mounted	Women's Locker Room in the Dressing room	4	LF	6	\$436	
	Ceiling - Plaster/ Drywall	Women's Locker Room in the Dressing room	265	SF	6	\$917	
	Doors - Wood Doors inclu hw	Women's Locker Room in the Dressing room	2	EA	6	\$602	
	Floor Drain	Women's Locker Room in the Dressing room	3	EA	6	\$3,177	
	Floor - Tile Ceramic/ Porcelain	Women's Locker Room in the Dressing room	265	SF	5	\$4,233	
	Hand Dryer	Women's Locker Room in the Dressing room	1	EA	6	\$230	
	Lavatory	Women's Locker Room in the Dressing room	1	EA	6	\$320	
	Lighting - Lay-in	Women's Locker Room in the Dressing room	7	EA	6	\$833	
	Partitions	Women's Locker Room in the Dressing room	1	EA	6	\$297	
	Showers	Women's Locker Room in the Dressing room	2	EA	6	\$623	
	Student Lockers - One Tier	Women's Locker Room in the Dressing room	9	EA	6	\$836	
	Walls - Concrete Block	Women's Locker Room in the Dressing room	302	SF	6	\$885	
	Walls - Tile Ceramic/ Porcelain	Women's Locker Room in the Dressing room	101	SF	6	\$228	
	Water Closet	Women's Locker Room in the Dressing room	1	EA	6	\$336	
Lunch & Multipurpose Room							
	Ceiling - Splined	426 Cafeteria	2,783	SF	5	\$19,819	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Doors - Transom Window	426 Cafeteria	4	SF	6	\$68	
	Floor - Tile/Sheet	426 Cafeteria	2,783	SF	6	\$2,786	
	Lighting - Lay-in	426 Cafeteria	88	EA	6	\$10,470	
	Serving Line	426 Cafeteria	28	LF	6	\$1,666	
	Walls - Concrete Block	426 Cafeteria	528	SF	6	\$1,548	
	Walls - Masonry	426 Cafeteria	1,180	SF	6	\$3,712	
	Walls - Metal Panel	426 Cafeteria	1,034	SF	6	\$7,718	
	Ceiling - Splined	526 Cafeteria	2,780	SF	6	\$2,266	
	Ceiling - Splined	526 Cafeteria	3	SF	5	\$29	Loose tiles and missing tile
	Doors - Wood Doors inclu hw	526 Cafeteria	4	EA	6	\$1,204	
	Floor - Tile/Sheet	526 Cafeteria	2,783	SF	6	\$2,786	
	Lighting - Lay-in	526 Cafeteria	88	EA	6	\$10,470	
	Serving Line	526 Cafeteria	28	LF	6	\$1,666	
	Walls - Concrete Block	526 Cafeteria	528	SF	6	\$1,548	
	Walls - Masonry	526 Cafeteria	1,180	SF	6	\$3,712	
	Walls - Metal Panel	526 Cafeteria	1,034	SF	6	\$7,718	
	Ceiling - Splined	626 Cafeteria	1	SF	5	\$10	Damaged and missing tile
	Ceiling - Splined	626 Cafeteria	2,782	SF	6	\$2,268	
	Doors - Wood Doors inclu hw	626 Cafeteria	4	EA	6	\$1,204	
	Floor - Tile/Sheet	626 Cafeteria	2,783	SF	6	\$2,786	
	Lighting - Lay-in	626 Cafeteria	88	EA	7	\$0	
	Serving Line	626 Cafeteria	28	LF	6	\$1,666	
	Walls - Concrete Block	626 Cafeteria	528	SF	6	\$1,774	
	Walls - Concrete Block	626 Cafeteria	1,180	SF	6	\$3,459	
	Walls - Plaster/Drywall	626 Cafeteria	1,034	SF	6	\$2,854	
	Ceiling - Splined	726 Cafeteria (used as fitness room)	2,783	SF	6	\$2,268	
	Doors - Wood Doors inclu hw	726 Cafeteria (used as fitness room)	4	EA	6	\$1,204	
	Floor - Tile/Sheet	726 Cafeteria (used as fitness room)	2,783	SF	6	\$2,786	
	Lighting - Lay-in	726 Cafeteria (used as fitness room)	88	EA	7	\$0	
	Serving Line	726 Cafeteria (used as fitness room)	28	LF	6	\$1,666	
	Walls - Concrete Block	726 Cafeteria (used as fitness room)	528	SF	6	\$1,774	
	Walls - Concrete Block	726 Cafeteria (used as fitness room)	1,180	SF	6	\$3,459	
	Walls - Plaster/Drywall	726 Cafeteria (used as fitness room)	1,034	SF	6	\$2,854	Actually Metal Panels
MDF_IDF							
	Doors - Wood Doors inclu hw	240 MDF Room	1	EA	6	\$301	
	Finishes	240 MDF Room	228	SF	6	\$1,627	Painted conc. blocks
	Doors - Wood Doors inclu hw	2nd floor MDF Room	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
MDF_IDF							
	Finishes	2nd floor MDF Room	581	SF	6	\$4,146	Painted conc. blocks
	Ventilation and Cooling	2nd floor MDF Room	1	EA	6	\$1,855	
	Doors - Side-lite	300 MDF Room	10	SF	6	\$167	
	Doors - Transom Window	300 MDF Room	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	300 MDF Room	1	EA	6	\$301	
	Finishes	300 MDF Room	584	SF	6	\$4,167	Metal panel
	Finishes	300 MDF Room	292	SF	6	\$2,084	Painted plaster/Drywall
	Finishes	300 MDF Room	87	SF	6	\$621	Painted conc. blocks
	Doors - Wood Doors inclu hw	340 MDF Room	1	EA	6	\$301	
	Finishes	340 MDF Room	228	SF	6	\$1,627	Painted conc. blocks
	Doors - Wood Doors inclu hw	440 MDF Room	1	EA	6	\$301	
	Finishes	440 MDF Room	228	SF	6	\$1,627	Painted conc. blocks
	Doors - Wood Doors inclu hw	540 MDF Room	1	EA	6	\$301	
	Finishes	540 MDF Room	228	SF	6	\$1,627	Painted conc. blocks
	Doors - Wood Doors inclu hw	640 MDF Room	1	EA	6	\$301	
	Finishes	640 MDF Room	228	SF	6	\$1,627	Painted conc. blocks
	Doors - Wood Doors inclu hw	740 MDF Room	1	EA	6	\$301	
	Finishes	740 MDF Room	228	SF	6	\$1,627	Painted conc. blocks
Mechanical/ Service Rooms							
	Storage Room	1st Floor	364	SF	6	\$2,608	Yard storage Door#8
	Janitor's Closet	2nd Floor	35	SF	6	\$251	
	Mechanical/ Service Rooms	2nd Floor	52	SF	6	\$373	Elec. clos.
	Mechanical/ Service Rooms	2nd Floor	168	SF	6	\$1,204	Elec clos. in main office
	Storage Room	2nd Floor	864	SF	6	\$6,190	#211, #210, #209
	Vaults	2nd Floor	230	SF	7	\$0	Located in main office
	Janitor's Closet	3rd Floor	40	SF	6	\$287	
	Mechanical/ Service Rooms	3rd Floor	54	SF	6	\$387	Elec. clos.
	Storage Room	3rd Floor	443	SF	6	\$3,174	Located in #300 MDF room
	Storage Room	3rd Floor	305	SF	6	\$2,185	Book Storage #323
	Janitor's Closet	4th Floor	10	SF	6	\$72	
	Mechanical/ Service Rooms	4th Floor	98	SF	6	\$702	Elec. clos. and escalator clos
	Storage Room	4th Floor	250	SF	6	\$1,791	#409A
	Janitor's Closet	5th Floor	41	SF	6	\$294	
	Mechanical/ Service Rooms	5th Floor	96	SF	6	\$688	Elec clos. and escalator clos
	Janitor's Closet	6th Floor	10	SF	6	\$72	
	Mechanical/ Service Rooms	6th Floor	98	SF	6	\$702	Elec. clos and escalator clos.
	Janitor's Closet	7th Floor	10	SF	6	\$72	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	7th Floor	98	SF	6	\$702	Elec. clos and escalator clos.
	Janitor's Closet	8th Floor	10	SF	6	\$72	
	Mechanical/ Service Rooms	8th Floor	98	SF	6	\$702	Elec. clos and escalator clos.
	Mechanical/ Service Rooms	Basement	4,589	SF	6	\$32,877	
	Loading Docks	Lower level	4,755	SF	6	\$34,066	Receiving area
	Mechanical/ Service Rooms	Lower level	501	SF	5	\$8,081	Mech and Generator room
	Storage Room	Lower level	9,319	SF	6	\$66,764	
	Mechanical/ Service Rooms	Penthouse mechanical rooms	6,529	SF	6	\$46,776	
Restroom							
	Accessories	019A Toilet in Lower Level	28	SF	6	\$258	
	Ceiling - Lay-in	019A Toilet in Lower Level	28	SF	6	\$84	
	Doors - Wood Doors inclu hw	019A Toilet in Lower Level	1	EA	6	\$301	
	Floor - Tile/Sheet	019A Toilet in Lower Level	28	SF	6	\$28	
	Lavatory	019A Toilet in Lower Level	1	EA	6	\$320	
	Lighting - Lay-in	019A Toilet in Lower Level	1	EA	6	\$119	
	Walls - Concrete Block	019A Toilet in Lower Level	167	SF	6	\$490	
	Water Closet	019A Toilet in Lower Level	1	EA	6	\$336	
	Accessories	100H Men's Staff	155	SF	6	\$1,430	
	Ceiling - Plaster/Drywall	100H Men's Staff	155	SF	6	\$536	
	Doors - Transom Window	100H Men's Staff	8	SF	6	\$135	Wood panel
	Doors - Wood Doors inclu hw	100H Men's Staff	1	EA	6	\$301	
	Floor - Tile	100H Men's Staff	155	SF	6	\$339	
	Lavatory	100H Men's Staff	2	EA	6	\$639	
	Lighting - Pendent/Surface	100H Men's Staff	3	EA	6	\$372	
	Partitions	100H Men's Staff	1	EA	6	\$297	
	Walls - Concrete Block	100H Men's Staff	348	SF	6	\$1,020	
	Water Closet	100H Men's Staff	2	EA	6	\$672	
	Accessories	100I Women's Staff	36	SF	6	\$332	
	Ceiling - Plaster/Drywall	100I Women's Staff	36	SF	6	\$125	
	Doors - Wood Doors inclu hw	100I Women's Staff	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	100I Women's Staff	36	SF	6	\$76	
	Lavatory	100I Women's Staff	1	EA	6	\$320	
	Lighting - Pendent/Surface	100I Women's Staff	1	EA	6	\$124	
	Walls - Concrete Block	100I Women's Staff	168	SF	6	\$492	
	Water Closet	100I Women's Staff	1	EA	6	\$336	
	Accessories	200 H Unisex staff	50	SF	6	\$461	
	Ceiling - Plaster/Drywall	200 H Unisex staff	50	SF	6	\$173	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	200 H Unisex staff	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	200 H Unisex staff	50	SF	6	\$106	
	Lavatory	200 H Unisex staff	1	EA	6	\$320	
	Lighting - Pendent/Surface	200 H Unisex staff	1	EA	6	\$124	
	Walls - Concrete Block	200 H Unisex staff	230	SF	6	\$674	
	Water Closet	200 H Unisex staff	1	EA	6	\$336	
	Accessories	200C Unisex Staff	50	SF	6	\$461	
	Ceiling - Plaster/Drywall	200C Unisex Staff	50	SF	6	\$173	
	Doors - Wood Doors inclu hw	200C Unisex Staff	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	200C Unisex Staff	50	SF	6	\$106	
	Lavatory	200C Unisex Staff	1	EA	6	\$320	
	Lighting - Pendent/Surface	200C Unisex Staff	1	EA	6	\$124	
	Walls - Concrete Block	200C Unisex Staff	230	SF	6	\$674	
	Water Closet	200C Unisex Staff	1	EA	6	\$336	
	Accessories	221A Toilet in Clinic	61	SF	6	\$563	
	Ceiling - Lay-in	221A Toilet in Clinic	61	SF	6	\$183	
	Doors - Wood Doors inclu hw	221A Toilet in Clinic	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	221A Toilet in Clinic	61	SF	6	\$129	
	Lavatory	221A Toilet in Clinic	1	EA	6	\$320	
	Lighting - Lay-in	221A Toilet in Clinic	1	EA	6	\$119	
	Walls - Concrete Block	221A Toilet in Clinic	189	SF	6	\$554	
	Walls - Plaster/Drywall	221A Toilet in Clinic	356	SF	6	\$983	
	Water Closet	221A Toilet in Clinic	1	EA	6	\$336	
	Accessories	221E Toilet in Clinic	61	SF	6	\$563	
	Ceiling - Lay-in	221E Toilet in Clinic	61	SF	6	\$183	
	Doors - Wood Doors inclu hw	221E Toilet in Clinic	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	221E Toilet in Clinic	61	SF	6	\$129	
	Lavatory	221E Toilet in Clinic	1	EA	6	\$320	
	Lighting - Lay-in	221E Toilet in Clinic	1	EA	6	\$119	
	Lighting - Wall Mounted	221E Toilet in Clinic	1	EA	6	\$124	
	Walls - Concrete Block	221E Toilet in Clinic	545	SF	6	\$1,598	
	Water Closet	221E Toilet in Clinic	1	EA	6	\$336	
	Accessories	2nd Floor Men's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	2nd Floor Men's Restroom	63	SF	6	\$218	Hole
	Doors - Wood Doors inclu hw	2nd Floor Men's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Men's Restroom	63	SF	6	\$133	
	Lavatory	2nd Floor Men's Restroom	1	EA	6	\$320	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Lay-in	2nd Floor Men's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	2nd Floor Men's Restroom	224	SF	6	\$657	
	Water Closet	2nd Floor Men's Restroom	1	EA	6	\$336	
	Accessories	2nd Floor Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	2nd Floor Men's Room	316	SF	6	\$1,094	
	Floor Drain	2nd Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Men's Room	316	SF	6	\$669	
	Hand Dryer	2nd Floor Men's Room	3	EA	6	\$690	
	Lavatory	2nd Floor Men's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	2nd Floor Men's Room	5	EA	6	\$595	
	Partitions	2nd Floor Men's Room	3	EA	6	\$891	
	Urinals	2nd Floor Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	2nd Floor Men's Room	576	SF	6	\$1,689	
	Water Closet	2nd Floor Men's Room	3	EA	6	\$1,008	
	Accessories	2nd Floor Unisex Staff Restroom	102	SF	6	\$941	
	Ceiling - Plaster/Drywall	2nd Floor Unisex Staff Restroom	102	SF	6	\$353	
	Doors - Transom Window	2nd Floor Unisex Staff Restroom	6	SF	6	\$102	Wood panel
	Doors - Wood Doors inclu hw	2nd Floor Unisex Staff Restroom	1	EA	6	\$301	
	Floor Drain	2nd Floor Unisex Staff Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Unisex Staff Restroom	102	SF	6	\$216	
	Hand Dryer	2nd Floor Unisex Staff Restroom	1	EA	6	\$230	
	Lavatory	2nd Floor Unisex Staff Restroom	1	EA	6	\$320	
	Lighting - Lay-in	2nd Floor Unisex Staff Restroom	2	EA	6	\$238	
	Walls - Concrete Block	2nd Floor Unisex Staff Restroom	340	SF	6	\$997	
	Water Closet	2nd Floor Unisex Staff Restroom	1	EA	6	\$336	
	Accessories	2nd Floor Women's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	2nd Floor Women's Restroom	63	SF	6	\$218	
	Doors - Steel Doors incl hw	2nd Floor Women's Restroom	1	EA	6	\$301	
	Floor Drain	2nd Floor Women's Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Women's Restroom	63	SF	6	\$133	
	Hand Dryer	2nd Floor Women's Restroom	1	EA	6	\$230	
	Lavatory	2nd Floor Women's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	2nd Floor Women's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	2nd Floor Women's Restroom	224	SF	6	\$657	
	Water Closet	2nd Floor Women's Restroom	1	EA	6	\$336	
	Accessories	2nd Floor Women's Room	309	SF	6	\$2,850	
	Ceiling - Plaster/Drywall	2nd Floor Women's Room	309	SF	6	\$1,069	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	2nd Floor Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	2nd Floor Women's Room	3	EA	6	\$690	
	Lavatory	2nd Floor Women's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	2nd Floor Women's Room	5	EA	6	\$595	
	Partitions	2nd Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd Floor Women's Room	556	SF	6	\$1,630	
	Water Closet	2nd Floor Women's Room	6	EA	6	\$2,016	
	Accessories	3rd Floor Men's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	3rd Floor Men's Restroom	63	SF	6	\$218	Hole
	Doors - Wood Doors inclu hw	3rd Floor Men's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Men's Restroom	63	SF	6	\$133	
	Lavatory	3rd Floor Men's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	3rd Floor Men's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	3rd Floor Men's Restroom	224	SF	6	\$657	
	Water Closet	3rd Floor Men's Restroom	1	EA	6	\$336	
	Accessories	3rd Floor Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	3rd Floor Men's Room	316	SF	6	\$1,094	
	Floor Drain	3rd Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Men's Room	316	SF	6	\$669	
	Hand Dryer	3rd Floor Men's Room	3	EA	6	\$690	
	Lavatory	3rd Floor Men's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	3rd Floor Men's Room	5	EA	6	\$595	
	Partitions	3rd Floor Men's Room	3	EA	6	\$891	
	Urinals	3rd Floor Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	3rd Floor Men's Room	576	SF	6	\$1,689	
	Water Closet	3rd Floor Men's Room	3	EA	6	\$1,008	
	Accessories	3rd Floor Women's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	3rd Floor Women's Restroom	63	SF	6	\$218	
	Doors - Wood Doors inclu hw	3rd Floor Women's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Women's Restroom	63	SF	6	\$133	
	Lavatory	3rd Floor Women's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	3rd Floor Women's Restroom	1	EA	6	\$119	
	Partitions	3rd Floor Women's Restroom	1	EA	6	\$297	
	Walls - Concrete Block	3rd Floor Women's Restroom	224	SF	6	\$657	
	Water Closet	3rd Floor Women's Restroom	1	EA	6	\$336	
	Benches	3rd Floor Women's Room	309	LF	6	\$4,472	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	3rd Floor Women's Room	309	SF	6	\$1,069	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	3rd Floor Women's Room	3	EA	6	\$690	
	Lighting - Lay-in	3rd Floor Women's Room	5	EA	6	\$595	
	Partitions	3rd Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	3rd Floor Women's Room	556	SF	6	\$1,630	
	Water Closet	3rd Floor Women's Room	6	EA	6	\$2,016	
	Accessories	4th Floor Men's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	4th Floor Men's Restroom	63	SF	6	\$218	Hole
	Doors - Wood Doors inclu hw	4th Floor Men's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	4th Floor Men's Restroom	63	SF	6	\$133	
	Lavatory	4th Floor Men's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	4th Floor Men's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	4th Floor Men's Restroom	224	SF	6	\$657	
	Water Closet	4th Floor Men's Restroom	1	EA	6	\$336	
	Accessories	4th Floor Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	4th Floor Men's Room	316	SF	6	\$1,094	
	Floor Drain	4th Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	4th Floor Men's Room	316	SF	6	\$669	
	Hand Dryer	4th Floor Men's Room	3	EA	6	\$690	
	Lavatory	4th Floor Men's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	4th Floor Men's Room	5	EA	6	\$595	
	Partitions	4th Floor Men's Room	3	EA	6	\$891	
	Urinals	4th Floor Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	4th Floor Men's Room	576	SF	6	\$1,689	
	Water Closet	4th Floor Men's Room	3	EA	6	\$1,008	
	Accessories	4th Floor Unisex Staff Restroom	102	SF	6	\$941	
	Ceiling - Plaster/Drywall	4th Floor Unisex Staff Restroom	102	SF	6	\$353	
	Doors - Wood Doors inclu hw	4th Floor Unisex Staff Restroom	1	EA	6	\$301	
	Floor Drain	4th Floor Unisex Staff Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	4th Floor Unisex Staff Restroom	102	SF	6	\$216	
	Hand Dryer	4th Floor Unisex Staff Restroom	1	EA	6	\$230	
	Lavatory	4th Floor Unisex Staff Restroom	1	EA	6	\$320	
	Lighting - Lay-in	4th Floor Unisex Staff Restroom	1	EA	6	\$119	
	Walls - Concrete Block	4th Floor Unisex Staff Restroom	340	SF	6	\$997	
	Water Closet	4th Floor Unisex Staff Restroom	1	EA	6	\$336	
	Accessories	4th Floor Women's Room	309	SF	6	\$2,850	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	4th Floor Women's Room	309	SF	6	\$1,069	
	Floor Drain	4th Floor Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	4th Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	4th Floor Women's Room	3	EA	6	\$690	
	Lavatory	4th Floor Women's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	4th Floor Women's Room	5	EA	6	\$595	
	Partitions	4th Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	4th Floor Women's Room	556	SF	6	\$1,630	
	Water Closet	4th Floor Women's Room	6	EA	6	\$2,016	
	Accessories	5th Floor Men's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	5th Floor Men's Restroom	63	SF	6	\$218	Hole
	Doors - Wood Doors inclu hw	5th Floor Men's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	5th Floor Men's Restroom	63	SF	6	\$133	
	Lavatory	5th Floor Men's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	5th Floor Men's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	5th Floor Men's Restroom	224	SF	6	\$657	
	Water Closet	5th Floor Men's Restroom	1	EA	6	\$336	
	Accessories	5th Floor Men's room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	5th Floor Men's room	316	SF	6	\$1,094	
	Floor Drain	5th Floor Men's room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	5th Floor Men's room	316	SF	6	\$669	
	Hand Dryer	5th Floor Men's room	3	EA	6	\$690	
	Lavatory	5th Floor Men's room	4	EA	6	\$1,278	
	Lighting - Lay-in	5th Floor Men's room	5	EA	6	\$595	
	Partitions	5th Floor Men's room	2	EA	6	\$594	
	Urinals	5th Floor Men's room	3	EA	6	\$1,008	
	Walls - Concrete Block	5th Floor Men's room	576	SF	6	\$1,689	
	Water Closet	5th Floor Men's room	3	EA	6	\$1,008	
	Accessories	5th Floor Women's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	5th Floor Women's Restroom	63	SF	6	\$218	
	Doors - Wood Doors inclu hw	5th Floor Women's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	5th Floor Women's Restroom	63	SF	6	\$133	
	Lavatory	5th Floor Women's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	5th Floor Women's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	5th Floor Women's Restroom	224	SF	6	\$657	
	Water Closet	5th Floor Women's Restroom	1	EA	6	\$336	
	Accessories	5th Floor Women's Room	309	SF	6	\$2,850	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	5th Floor Women's Room	309	SF	6	\$1,069	
	Floor Drain	5th Floor Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	5th Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	5th Floor Women's Room	3	EA	6	\$690	
	Lavatory	5th Floor Women's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	5th Floor Women's Room	5	EA	6	\$595	
	Partitions	5th Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	5th Floor Women's Room	556	SF	6	\$1,630	
	Water Closet	5th Floor Women's Room	6	EA	6	\$2,016	
	Accessories	6th Floor Men's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	6th Floor Men's Restroom	63	SF	6	\$218	hole
	Doors - Wood Doors inclu hw	6th Floor Men's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	6th Floor Men's Restroom	63	SF	6	\$133	
	Lavatory	6th Floor Men's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	6th Floor Men's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	6th Floor Men's Restroom	224	SF	6	\$657	
	Water Closet	6th Floor Men's Restroom	1	EA	6	\$336	
	Accessories	6th Floor Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	6th Floor Men's Room	316	SF	6	\$1,094	
	Floor Drain	6th Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	6th Floor Men's Room	316	SF	6	\$669	
	Hand Dryer	6th Floor Men's Room	3	EA	6	\$690	
	Lavatory	6th Floor Men's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	6th Floor Men's Room	5	EA	6	\$595	
	Partitions	6th Floor Men's Room	3	EA	6	\$891	
	Urinals	6th Floor Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	6th Floor Men's Room	576	SF	6	\$1,689	
	Water Closet	6th Floor Men's Room	3	EA	6	\$1,008	
	Accessories	6th Floor Unisex Staff Restroom	102	SF	6	\$941	
	Ceiling - Plaster/Drywall	6th Floor Unisex Staff Restroom	102	SF	6	\$353	
	Doors - Transom Window	6th Floor Unisex Staff Restroom	6	SF	6	\$102	Wood panel
	Doors - Wood Doors inclu hw	6th Floor Unisex Staff Restroom	1	EA	6	\$301	
	Floor Drain	6th Floor Unisex Staff Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	6th Floor Unisex Staff Restroom	102	SF	6	\$216	
	Hand Dryer	6th Floor Unisex Staff Restroom	1	EA	6	\$230	
	Lavatory	6th Floor Unisex Staff Restroom	1	EA	6	\$320	
	Lighting - Lay-in	6th Floor Unisex Staff Restroom	2	EA	6	\$238	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Concrete Block	6th Floor Unisex Staff Restroom	340	SF	6	\$997	
	Water Closet	6th Floor Unisex Staff Restroom	1	EA	6	\$336	
	Accessories	6th Floor Women's Room	309	SF	6	\$2,850	
	Ceiling - Plaster/Drywall	6th Floor Women's Room	309	SF	6	\$1,069	
	Floor Drain	6th Floor Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	6th Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	6th Floor Women's Room	3	EA	6	\$690	
	Lavatory	6th Floor Women's Room	4	EA	6	\$1,278	
	Lighting - Lay-in	6th Floor Women's Room	5	EA	6	\$595	
	Partitions	6th Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	6th Floor Women's Room	556	SF	7	\$0	
	Water Closet	6th Floor Women's Room	6	EA	6	\$2,016	
	Accessories	7th Floor Men's Restroom	63	SF	6	\$581	
	Benches	7th Floor Men's Restroom	63	LF	6	\$912	
	Doors - Wood Doors inclu hw	7th Floor Men's Restroom	1	EA	6	\$301	
	Floor Drain	7th Floor Men's Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	7th Floor Men's Restroom	63	SF	6	\$133	
	Hand Dryer	7th Floor Men's Restroom	1	EA	6	\$230	
	Lavatory	7th Floor Men's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	7th Floor Men's Restroom	1	EA	7	\$0	
	Walls - Concrete Block	7th Floor Men's Restroom	224	SF	6	\$657	
	Water Closet	7th Floor Men's Restroom	1	EA	6	\$336	
	Accessories	7th Floor Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	7th Floor Men's Room	316	SF	6	\$1,094	
	Floor Drain	7th Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	7th Floor Men's Room	316	SF	6	\$669	
	Hand Dryer	7th Floor Men's Room	2	EA	6	\$460	
	Lavatory	7th Floor Men's Room	3	EA	6	\$959	
	Lighting - Lay-in	7th Floor Men's Room	5	EA	7	\$0	
	Partitions	7th Floor Men's Room	3	EA	6	\$891	
	Urinals	7th Floor Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	7th Floor Men's Room	576	SF	6	\$1,689	
	Water Closet	7th Floor Men's Room	3	EA	6	\$1,008	
	Accessories	7th Floor Women's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	7th Floor Women's Restroom	63	SF	6	\$218	
	Doors - Wood Doors inclu hw	7th Floor Women's Restroom	1	EA	6	\$301	
	Floor Drain	7th Floor Women's Restroom	1	EA	6	\$1,059	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor - Tile Ceramic/ Porcelain	7th Floor Women's Restroom	63	SF	6	\$133	
	Hand Dryer	7th Floor Women's Restroom	1	EA	6	\$230	
	Lavatory	7th Floor Women's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	7th Floor Women's Restroom	1	EA	7	\$0	
	Walls - Concrete Block	7th Floor Women's Restroom	224	SF	6	\$657	
	Water Closet	7th Floor Women's Restroom	1	EA	6	\$336	
	Accessories	7th Floor Women's Room	309	SF	6	\$2,850	
	Ceiling - Plaster/Drywall	7th Floor Women's Room	309	SF	6	\$1,069	
	Floor Drain	7th Floor Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	7th Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	7th Floor Women's Room	2	EA	6	\$460	
	Lavatory	7th Floor Women's Room	3	EA	6	\$959	
	Lighting - Lay-in	7th Floor Women's Room	5	EA	7	\$0	
	Partitions	7th Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	7th Floor Women's Room	556	SF	6	\$1,630	
	Water Closet	7th Floor Women's Room	6	EA	6	\$2,016	
	Accessories	8th Floor Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	8th Floor Men's Room	316	SF	6	\$1,094	
	Floor Drain	8th Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	8th Floor Men's Room	316	SF	6	\$669	
	Hand Dryer	8th Floor Men's Room	2	EA	6	\$460	
	Lavatory	8th Floor Men's Room	3	EA	6	\$959	
	Lighting - Lay-in	8th Floor Men's Room	5	EA	7	\$0	
	Partitions	8th Floor Men's Room	3	EA	6	\$891	
	Urinals	8th Floor Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	8th Floor Men's Room	576	SF	6	\$1,689	
	Water Closet	8th Floor Men's Room	3	EA	6	\$1,008	
	Accessories	8th Floor Women's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	8th Floor Women's Restroom	63	SF	6	\$218	
	Doors - Wood Doors inclu hw	8th Floor Women's Restroom	1	EA	6	\$301	
	Floor Drain	8th Floor Women's Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	8th Floor Women's Restroom	63	SF	6	\$133	
	Hand Dryer	8th Floor Women's Restroom	1	EA	6	\$230	
	Lavatory	8th Floor Women's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	8th Floor Women's Restroom	1	EA	7	\$0	
	Walls - Concrete Block	8th Floor Women's Restroom	224	SF	6	\$657	
	Water Closet	8th Floor Women's Restroom	1	EA	6	\$336	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Accessories	8th Floor Women's Room	309	SF	6	\$2,850	
	Ceiling - Plaster/Drywall	8th Floor Women's Room	309	SF	6	\$1,069	
	Floor Drain	8th Floor Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	8th Floor Women's Room	309	SF	6	\$654	
	Hand Dryer	8th Floor Women's Room	2	EA	6	\$460	
	Lavatory	8th Floor Women's Room	3	EA	6	\$959	
	Lighting - Lay-in	8th Floor Women's Room	5	EA	7	\$0	
	Partitions	8th Floor Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	8th Floor Women's Room	556	SF	6	\$1,630	
	Water Closet	8th Floor Women's Room	6	EA	6	\$2,016	
	Accessories	8th Flr Men's Restroom	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	8th Flr Men's Restroom	63	SF	6	\$218	
	Doors - Wood Doors inclu hw	8th Flr Men's Restroom	1	EA	6	\$301	
	Floor Drain	8th Flr Men's Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	8th Flr Men's Restroom	63	SF	6	\$133	
	Hand Dryer	8th Flr Men's Restroom	1	EA	6	\$230	
	Lavatory	8th Flr Men's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	8th Flr Men's Restroom	1	EA	7	\$0	
	Walls - Concrete Block	8th Flr Men's Restroom	224	SF	6	\$657	
	Water Closet	8th Flr Men's Restroom	1	EA	6	\$336	
	Accessories	Accessible Unisex Locker room in Dressing Room	104	SF	6	\$959	
	Benches	Accessible Unisex Locker room in Dressing Room	4	LF	6	\$58	
	Ceiling - Lay-in	Accessible Unisex Locker room in Dressing Room	104	SF	6	\$312	
	Doors - Wood Doors inclu hw	Accessible Unisex Locker room in Dressing Room	2	EA	6	\$602	
	Floor Drain	Accessible Unisex Locker room in Dressing Room	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	Accessible Unisex Locker room in Dressing Room	104	SF	6	\$220	
	Hand Dryer	Accessible Unisex Locker room in Dressing Room	1	EA	6	\$230	
	Lavatory	Accessible Unisex Locker room in Dressing Room	1	EA	6	\$320	
	Lighting - Lay-in	Accessible Unisex Locker room in Dressing Room	3	EA	7	\$0	
	Partitions	Accessible Unisex Locker room in Dressing Room	1	EA	6	\$297	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Showers	Accessible Unisex Locker room in Dressing Room	1	EA	6	\$311	
	Student Lockers - One Tier	Accessible Unisex Locker room in Dressing Room	3	EA	5	\$420	
	Walls - Concrete Block	Accessible Unisex Locker room in Dressing Room	295	SF	6	\$865	
	Walls - Tile Ceramic/ Porcelain	Accessible Unisex Locker room in Dressing Room	97	SF	6	\$219	
	Water Closet	Accessible Unisex Locker room in Dressing Room	1	EA	6	\$336	
	Accessories	Lower Level Men's Room	316	SF	6	\$2,915	
	Ceiling - Plaster/Drywall	Lower Level Men's Room	316	SF	6	\$1,094	
	Floor - Tile Ceramic/ Porcelain	Lower Level Men's Room	316	SF	6	\$669	
	Hand Dryer	Lower Level Men's Room	2	EA	6	\$460	
	Lavatory	Lower Level Men's Room	3	EA	6	\$959	
	Lighting - Lay-in	Lower Level Men's Room	5	EA	7	\$0	
	Partitions	Lower Level Men's Room	3	EA	6	\$891	
	Student Lockers - One Tier	Lower Level Men's Room	3	EA	6	\$279	
	Urinals	Lower Level Men's Room	3	EA	6	\$1,008	
	Walls - Concrete Block	Lower Level Men's Room	576	SF	6	\$1,689	
	Water Closet	Lower Level Men's Room	3	EA	6	\$1,008	
	Accessories	Lower Level Women's Room	309	SF	6	\$2,850	
	Ceiling - Plaster/Drywall	Lower Level Women's Room	309	SF	6	\$1,069	
	Floor Drain	Lower Level Women's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Lower Level Women's Room	309	SF	6	\$654	
	Hand Dryer	Lower Level Women's Room	2	EA	6	\$460	
	Lavatory	Lower Level Women's Room	3	EA	6	\$959	
	Lighting - Lay-in	Lower Level Women's Room	5	EA	7	\$0	
	Partitions	Lower Level Women's Room	5	EA	6	\$1,485	
	Walls - Concrete Block	Lower Level Women's Room	556	SF	6	\$1,630	
	Water Closet	Lower Level Women's Room	6	EA	6	\$2,016	
	Accessories	Men's Room in Lower Level	173	SF	6	\$1,596	
	Ceiling - Plaster/Drywall	Men's Room in Lower Level	173	SF	6	\$599	
	Doors - Wood Doors inclu hw	Men's Room in Lower Level	1	EA	6	\$301	
	Floor Drain	Men's Room in Lower Level	1	EA	6	\$1,059	
	Floor - Tile/Sheet	Men's Room in Lower Level	173	SF	6	\$173	
	Lavatory	Men's Room in Lower Level	1	EA	6	\$320	
	Lighting - Lay-in	Men's Room in Lower Level	3	EA	7	\$0	
	Partitions	Men's Room in Lower Level	1	EA	6	\$297	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Showers	Men's Room in Lower Level	1	EA	6	\$311	
	Student Lockers - One Tier	Men's Room in Lower Level	6	EA	6	\$557	
	Walls - Concrete Block	Men's Room in Lower Level	565	SF	6	\$1,656	
	Water Closet	Men's Room in Lower Level	1	EA	6	\$336	
	Accessories	Toilet in Engineer's Office	43	SF	6	\$397	
	Ceiling - Plaster/Drywall	Toilet in Engineer's Office	43	SF	6	\$149	
	Doors - Wood Doors inclu hw	Toilet in Engineer's Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Toilet in Engineer's Office	43	SF	6	\$43	
	Lavatory	Toilet in Engineer's Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	Toilet in Engineer's Office	1	EA	6	\$124	
	Showers	Toilet in Engineer's Office	1	EA	6	\$311	
	Walls - Concrete Block	Toilet in Engineer's Office	210	SF	6	\$616	
	Water Closet	Toilet in Engineer's Office	1	EA	6	\$336	
	Accessories	Toilet in Maintenance Office	32	SF	6	\$295	
	Ceiling - Plaster/Drywall	Toilet in Maintenance Office	32	SF	6	\$111	
	Doors - Transom Window	Toilet in Maintenance Office	1	SF	6	\$17	
	Floor Drain	Toilet in Maintenance Office	1	EA	6	\$1,059	
	Floor - Tile/Sheet	Toilet in Maintenance Office	32	SF	6	\$32	
	Lavatory	Toilet in Maintenance Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	Toilet in Maintenance Office	1	EA	6	\$124	
	Walls - Concrete Block	Toilet in Maintenance Office	235	SF	6	\$689	
	Water Closet	Toilet in Maintenance Office	1	EA	6	\$336	
	Accessories	Women's Room, Lower Level	198	SF	6	\$1,826	
	Ceiling - Plaster/Drywall	Women's Room, Lower Level	198	SF	6	\$685	
	Doors - Wood Doors inclu hw	Women's Room, Lower Level	1	EA	6	\$301	
	Floor - Tile/Sheet	Women's Room, Lower Level	198	SF	6	\$198	
	Lavatory	Women's Room, Lower Level	1	EA	6	\$320	
	Lighting - Lay-in	Women's Room, Lower Level	7	EA	7	\$0	
	Partitions	Women's Room, Lower Level	1	EA	6	\$297	
	Student Lockers - One Tier	Women's Room, Lower Level	26	EA	6	\$2,414	
	Walls - Concrete Block	Women's Room, Lower Level	452	SF	6	\$1,325	
	Water Closet	Women's Room, Lower Level	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal: \$3,300,949

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Splined	Entire Building	20	SF	5	\$193	Damaged tiles
	Ceiling - Splined	Entire Building	71,132	SF	6	\$205,472	
	Doors - Store Front	Entire Building	14	EA	6	\$16,915	
	Drinking Fountains - Double Water Cooler	Entire Building	20	EA	6	\$7,539	
	Floor - Tile/Sheet	Entire Building	71,152	SF	6	\$38,664	
	Lighting - Lay-in	Entire Building	1,296	EA	6	\$154,193	
	Student Lockers - One Tier	Entire Building	1,561	EA	6	\$144,916	
	Walls - Concrete Block	Entire Building	8,685	SF	6	\$25,460	
	Walls - Masonry	Entire Building	17,369	SF	6	\$54,643	
	Walls - Plaster/Drywall	Entire Building	80,608	SF	6	\$357,335	
Safety							
	Camera Viewing Station	Entire Building	3	EA	6	\$2,048	
	Security Cameras	Entire Building	24	EA	6	\$4,657	
	Security Cameras	Entire Building	59	EA	6	\$11,448	
Stairs							
	Ceiling - Plaster/Drywall	Stair A	278	SF	6	\$2,035	
	Floor - Terrazzo	Stair A	278	SF	6	\$2,334	
	Handrails	Stair A	408	LF	6	\$3,536	
	Lighting - Pendent/Surface	Stair A	14	EA	7	\$0	
	Stairs - Terrazzo	Stair A	228	LF	6	\$2,116	
	Walls - Masonry	Stair A	8,880	SF	6	\$27,936	
	Ceiling - Plaster/Drywall	Stair B	278	SF	6	\$2,035	
	Floor - Terrazzo	Stair B	278	SF	6	\$2,334	
	Handrails	Stair B	408	LF	6	\$3,536	
	Lighting - Pendent/Surface	Stair B	13	EA	7	\$0	
	Stairs - Terrazzo	Stair B	204	LF	6	\$1,893	
	Walls - Masonry	Stair B	8,880	SF	6	\$27,936	
	Ceiling - Plaster/Drywall	Stair C	278	SF	6	\$2,035	
	Floor - Terrazzo	Stair C	278	SF	6	\$2,334	
	Handrails	Stair C	408	LF	6	\$3,536	
	Lighting - Pendent/Surface	Stair C	13	EA	7	\$0	
	Stairs - Terrazzo	Stair C	204	LF	6	\$1,893	
	Walls - Masonry	Stair C	8,880	SF	6	\$27,936	
Vertical Conveyance							
	Elevator - Hydraulic Elevator		2	EA	6	\$38,476	
	Escalator		1	EA	6	\$46,667	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Building Interior Subtotal:						\$1,222,052	

Total Building Cost

\$12,251,660

Building: Linked Addition-Main Athletic

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Steel Door	#10 S	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#11.5 W	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#12 W	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#15 E	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#16 E	2	EA	6	\$961	
	Exterior Doors - Store Front	#11 S	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#13 N	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#14 N	2	EA	6	\$1,092	
	Exterior Stairs - Concrete	#15 E	20	LF	6	\$1,635	
	Exterior Stairs - Concrete	#16 E	20	LF	6	\$1,635	
Foundation							
	Foundation - Concrete	Entire Building	842	LF	7	\$0	
	Superstructure - Steel	Entire Building	78,824	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	29	EA	6	\$8,374	
Roof System							
	Chimney - Metal Flue	Main Roof	16	LF	6	\$2,530	
	Coping - Metal	Main Roof	1,114	LF	6	\$35,779	
	Downspouts - Interior Downspouts	Main Roof	90	LF	5	\$19,918	Three roof drains not draining, causing standing water on the roof.
	Downspouts - Interior Downspouts	Main Roof	690	LF	6	\$22,931	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main Roof	40,926	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Main Roof	4,001	SF	4	\$141,205	Areas of ponding
	Roof - Asphalt Gravel Ballast	Main Roof	36,925	SF	6	\$375,428	
Walls							
	Exterior Walls - Brick	Entire Building	18,364	SF	6	\$123,424	
	Exterior Walls - Stone-Cast	Entire Building	4,658	SF	6	\$31,306	

Building: Linked Addition-Main Athletic

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls							
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	5,876	SF	6	\$65,877	
	Curtain wall - Louver	Entire Building	1,216	SF	6	\$13,633	
	Guard - Guards wire guard	Entire Building / 1st Floor	2,700	SF	6	\$34,479	
	Windows - Casement Aluminum Double-pane	Entire Building	5,967	SF	6	\$44,541	

Building Exterior Subtotal:

\$929,816

Building: Linked Addition-Main Athletic

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	1	EA	7	\$0	
	Emergency A/C Power - Corridors and Stairs	Entire Building	13,504	SF	6	\$4,055	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	20,090	SF	6	\$7,469	
	Emergency A/C Power - Pool	Entire Building / 1st Floor	6,735	SF	6	\$2,504	
	Emergency A/C Power - Students Toilets	Entire Building	839	SF	6	\$312	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	30	EA	6	\$6,075	
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	10	EA	6	\$2,025	
	Emergency Battery Packs - Pool	Entire Building / 1st Floor	14	EA	6	\$2,835	
	Exit Signs - Corridors and Stairs	Entire Building	25	EA	6	\$3,744	
	Exit Signs - Gym	Entire Building / 1st Floor	10	EA	6	\$1,574	
	Exit Signs - Pool	Entire Building / 1st Floor	8	EA	6	\$1,240	
	Security System - CCTV	Entire Building	78,824	SF	6	\$23,671	
	Security System - Intrusion Detection	Entire Building	78,824	SF	6	\$20,289	

Main Service

	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	Secondary service from utility company.
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	6	\$11,555	
	PA System	Entire Building	78,824	SF	6	\$25,925	Serves both buildings. Control console located in Main.

Power Distribution

	Lighting and Power Panels - 100 A	Entire Building	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building	4	EA	4	\$19,397	Panels are old and deteriorated.
	Lighting and Power Panels - 100 A	Entire Building	1	EA	7	\$0	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	4	\$9,699	Emergency fuse panels are old and deteriorated.

Building: Linked Addition-Main Athletic

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution							
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building	5	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	4	\$19,733	Panels are old and deteriorated.
	Main Distribution Panels - 400 - 600 amp	Entire Building	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building	2	EA	6	\$1,055	
	Main Distribution Panels - 400 - 600 amp	Entire Building	2	EA	4	\$27,388	Panels are old and deteriorated.
	Main Distribution Panels - Greater than 600 amp	Entire Building	2	EA	4	\$42,209	Panels are old and deteriorated.
	Main Distribution Panels - Less than 400 amp	Entire Building	1	EA	6	\$503	
	Main Distribution Panels - Less than 400 amp	Entire Building	1	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building	2	EA	7	\$0	

Electrical System Subtotal:

\$236,975

Building: Linked Addition-Main Athletic

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Entire Building / Electrical Room	1	EA	7	\$0	
	Fire Alarm Strobe Lights	Entire Building	78,824	SF	7	\$0	
	Fire Alarm_System	Entire Building	78,824	SF	7	\$0	

Safty System Subtotal:

\$0

Building: Linked Addition-Main Athletic

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - Greater than 50 tons	Roof	1	EA	7	\$0	
Air Handling Systems							
	Air Handling Unit- Package Multi Zone- Indoor- Electric Coils - 20001-30000 cfm	Mechanical Room	1	EA	5	\$70,185	AS-2R
	Air Handling Unit- Package Single Zone- Indoor- Electric and DX Cooling Coil - 20001-30000 cfm	Mechanical Room	1	EA	5	\$70,185	
	Air Handling Unit- Package Single Zone- Indoor- Electric Coil - 12001-20000 cfm	Mechanical Room	2	EA	5	\$83,029	AS-4R & AS-3R
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	2	EA	6	\$11,529	

Building: Linked Addition-Main Athletic

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Dehumidification Unit- Outdoor- Electric Heating- DX Cooling with Self Contained Compressor - Greater than 8000 cfm	Roof	1	EA	6	\$12,236	
	Indoor Return Fans- Centrifugal Squirrel Cage - 10001 - 20000 CFM	Mechanical Room / Mechanical Building/Central Plant	3	EA	6	\$5,571	
	Make Up Air Unit- Roof Mounted- Gas Heating - Less than 6000 cfm	Roof	1	EA	7	\$0	
	Zone Dampers	Mechanical Room / Entire Building	10	EA	6	\$8,330	
Heating Devices							
	Cabinet Heaters - With Electric Coil	Entire Building	12	EA	4	\$40,318	Units are old, substantially deteriorated and not working nor needed.
	Duct Heater - Electric	Entire Building	20		4	\$126,175	Duct heaters are old and live front.
	Duct Heater - Electric	Entire Building / Mechanical Room	1		7	\$0	
	Fin Tube - Electric	Entire Building	160	LF	7	\$0	
Temperature Control							
	DDC System	Entire Building	78,824	SF	5	\$129,626	Served from Main building
	Thermostats - DDC	Entire Building	29	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	7	\$0	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	7	\$0	
	Roof Mounted Duct Work	Entire Building / Roof	84	LF	7	\$0	
	Type I Exhaust Hood- Culinary Arts	Entire Building / 2nd Floor	1	EA	7	\$0	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 2nd Floor	1	EA	7	\$0	
Mechanical System Subtotal:						\$568,715	

Building: Linked Addition-Main Athletic

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - Greater than 600000 BTU/HR	Mechanical Room	1	EA	5	\$2,249	Past useful life expectancy, but still operational.
	Gas Heater - Greater than 600000 BTU/HR	Mechanical Room	1	EA	5	\$2,249	Past useful life expectancy, but still operational.
	Hot Water Storage Tank_Gas - 501 - 1000 Gallons	Mechanical Room	1	EA	6	\$678	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	78,824	SF	6	\$15,781	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	78,824	SF	6	\$19,162	

Building: Linked Addition-Main Athletic

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water Risers	Entire Building	78,824	SF	6	\$14,653	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	78,824	SF	6	\$12,399	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	78,824	SF	6	\$14,653	
	Domestic Piping-Hot Water Return Lines	Entire Building	78,824	SF	6	\$11,272	
	Domestic Piping-Hot Water Return Risers	Entire Building	78,824	SF	6	\$11,272	
	Sanitary Piping	Entire Building	78,824	SF	6	\$72,140	
	Storm Piping	Entire Building	78,824	SF	6	\$68,758	
	Vent Piping	Entire Building	78,824	SF	6	\$52,978	
Pool Systems							
	Pool Drain Piping	Pool filter room	50	LF	4	\$5,064	Pipes are leaking resulting in pool closure for since 2013.
	Pool Filtration System including Pump	Pool filter room	1	EA	6	\$12,330	
	Pool Hot Water Heater - Gas Fired	Pool filter room	1	EA	6	\$310	
	Pool Supply and Return Piping	Pool filter room	100	LF	6	\$4,805	
Pumps							
	Pumps - Ejector-Duplex	Mechanical Room	1	EA	6	\$1,387	
	Pumps - Sump-Simplex	Mechanical Room / Basement	1	EA	6	\$745	Elevator sump pit
Plumbing System Subtotal:						\$322,886	

Building: Linked Addition-Main Athletic

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #230 (Regular Classroom)							
	Casework	2nd Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	2nd Floor	1,374	SF	6	\$4,126	
	Doors - Steel Doors incl hw	2nd Floor	2	EA	6	\$602	
	Doors - Transom Window	2nd Floor	16	SF	6	\$271	
	Floor - Tile/Sheet	2nd Floor	1,374	SF	6	\$1,375	
	Lighting - Lay-in	2nd Floor	52	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Walls - Concrete Block	2nd Floor	1,050	SF	6	\$3,078	
Classroom #231 (Other Instructional Use)							
	Ceiling - Lay-in	2nd Floor	1,793	SF	6	\$5,384	
	Doors - Steel Doors incl hw	2nd Floor	2	EA	6	\$602	

Building: Linked Addition-Main Athletic

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #231 (Other Instructional Use)							
	Doors - Transom Window	2nd Floor	20	SF	6	\$339	
	Floor - Tile/Sheet	2nd Floor	1,793	SF	6	\$1,795	
	Lighting - Lay-in	2nd Floor	61	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	1,550	SF	6	\$4,544	
	Work Sink	2nd Floor	6	EA	6	\$2,274	
Classroom #232 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	1,374	SF	6	\$4,126	
	Doors - Steel Doors incl hw	2nd Floor	2	EA	6	\$602	
	Doors - Transom Window	2nd Floor	20	SF	6	\$339	
	Floor - Tile/Sheet	2nd Floor	1,374	SF	6	\$1,375	
	Lighting - Lay-in	2nd Floor	43	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	1,050	SF	6	\$3,078	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #236 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	896	SF	6	\$2,691	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Floor - Tile/Sheet	2nd Floor	896	SF	6	\$897	
	Lighting - Lay-in	2nd Floor	26	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	996	SF	6	\$2,920	
Classroom #238 (Regular Classroom)							
	Ceiling - Lay-in		2,175	SF	6	\$6,532	
	Doors - Steel Doors incl hw		4	EA	6	\$1,204	
	Floor - Tile/Sheet		2,175	SF	6	\$2,177	
	Lighting - Lay-in		73	EA	7	\$0	
	Marker Board		8	LF	6	\$171	
	Walls - Concrete Block		1,592	SF	6	\$4,667	
Classroom #239 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	885	SF	6	\$2,658	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Floor - Tile/Sheet	2nd Floor	885	SF	6	\$886	

Building: Linked Addition-Main Athletic

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #239 (Regular Classroom)							
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	1,022	SF	6	\$2,996	
Classroom #240 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	19	SF	6	\$57	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	885	SF	6	\$886	
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	1,022	SF	6	\$2,996	

Classrooms Subtotal: \$70,066

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	Office G237	710	SF	6	\$2,132	
	Doors - Transom Window	Office G237	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	Office G237	1	EA	6	\$301	
	Floor - Tile/Sheet	Office G237	710	SF	6	\$711	
	Lighting - Lay-in	Office G237	20	EA	7	\$0	
	Power Distribution	Office G237	8	EA	6	\$16,999	
	Walls - Concrete Block	Office G237	740	SF	6	\$2,169	
	Ceiling - Lay-in	Office G241	86	SF	6	\$258	
	Doors - Steel Doors incl hw	Office G241	1	EA	6	\$301	
	Floor - Wood	Office G241	86	SF	6	\$606	
	Lighting - Wall Mounted	Office G241	1	EA	7	\$0	
	Power Distribution	Office G241	2	EA	6	\$4,250	
	Walls - Concrete Block	Office G241	253	SF	6	\$742	
	Ceiling - Lay-in	Room 107 in the gym	86	SF	6	\$258	
	Doors - Steel Doors incl hw	Room 107 in the gym	1	EA	6	\$301	
	Floor - Wood	Room 107 in the gym	86	SF	6	\$606	
	Lighting - Wall Mounted	Room 107 in the gym	1	EA	7	\$0	
	Power Distribution	Room 107 in the gym	2	EA	6	\$4,250	

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Concrete Block	Room 107 in the gym	253	SF	6	\$742	
	Ceiling - Lay-in	Room 120 in the gym	86	SF	6	\$258	
	Doors - Steel Doors incl hw	Room 120 in the gym	1	EA	6	\$301	
	Floor - Wood	Room 120 in the gym	86	SF	6	\$606	
	Lighting - Lay-in	Room 120 in the gym	1	EA	7	\$0	
	Power Distribution	Room 120 in the gym	2	EA	6	\$4,250	
	Walls - Concrete Block	Room 120 in the gym	253	SF	6	\$742	
	Ceiling - Lay-in	Room 121 in the gym	86	SF	6	\$258	
	Doors - Steel Doors incl hw	Room 121 in the gym	1	EA	6	\$301	
	Floor - Wood	Room 121 in the gym	86	SF	6	\$606	
	Lighting - Wall Mounted	Room 121 in the gym	1	EA	7	\$0	
	Power Distribution	Room 121 in the gym	2	EA	6	\$4,250	
	Walls - Concrete Block	Room 121 in the gym	253	SF	6	\$742	
	Ceiling - Splined	Room G231A	356	SF	6	\$290	
	Doors - Steel Doors incl hw	Room G231A	1	EA	6	\$301	
	Floor - Tile/Sheet	Room G231A	356	SF	6	\$356	
	Lighting - Lay-in	Room G231A	10	EA	7	\$0	
	Power Distribution	Room G231A	12	EA	6	\$25,499	
	Walls - Concrete Block	Room G231A	862	SF	6	\$2,527	
Gymnasia							
	Bleacher Seating	1st Floor	1,008	EA	6	\$29,175	
	Ceiling - Exposed	1st Floor	13,980	SF	6	\$20,791	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Floor - Wood	1st Floor	13,980	SF	6	\$98,558	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	28	EA	7	\$0	
	Scoreboards	1st Floor	2	EA	6	\$4,489	
	Sound System	1st Floor	1	EA	6	\$41,654	
	Walls - Concrete Block	1st Floor	16,021	SF	6	\$46,966	Walls are masonry
	Ceiling - Exposed	Girl's Gym Room 104	6,110	SF	6	\$9,087	
	Doors - Steel Doors incl hw	Girl's Gym Room 104	8	EA	6	\$2,408	
	Floor - Wood	Girl's Gym Room 104	6,110	SF	6	\$43,075	
	Lighting - Lay-in	Girl's Gym Room 104	36	EA	7	\$0	
	Walls - Concrete Block	Girl's Gym Room 104	6,610	SF	6	\$19,377	Walls are actually masonry
	Ceiling - Plaster/Drywall	Weight room in basement	1,976	SF	6	\$10,907	
	Doors - Steel Doors incl hw	Weight room in basement	4	EA	6	\$1,204	
	Floor - Weight/ Fitness Room Floor Matting	Weight room in basement	1,976	SF	6	\$10,342	
	Lighting - Pendent/Surface	Weight room in basement	24	EA	7	\$0	

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymnasia							
	Walls - Plaster/Drywall	Weight room in basement	5,842	SF	6	\$16,123	
Locker/Shower Room							
	Accessories	Girl's Locker Room	2,474	SF	6	\$9,694	
	Benches, ped mounted	Girl's Locker Room	60	LF	6	\$6,533	
	Ceiling - Plaster/ Drywall	Girl's Locker Room	2,474	SF	6	\$8,562	
	Doors - Steel Doors incl hw	Girl's Locker Room	1	EA	6	\$301	
	Floor Drain	Girl's Locker Room	22	EA	6	\$23,301	
	Floor - Concrete	Girl's Locker Room	2,474	SF	6	\$1,309	
	Hand Dryer	Girl's Locker Room	2	EA	6	\$460	
	Lavatory	Girl's Locker Room	3	EA	6	\$959	
	Lighting - Lay-in	Girl's Locker Room	30	EA	7	\$0	
	Partitions	Girl's Locker Room	3	EA	6	\$891	
	Showers	Girl's Locker Room	18	EA	6	\$5,605	
	Student Lockers - One Tier	Girl's Locker Room	261	EA	6	\$24,230	
	Walls - Concrete Block	Girl's Locker Room	5,426	SF	6	\$15,906	
	Water Closet	Girl's Locker Room	3	EA	6	\$1,008	
	Accessories	Men's Locker Room	3,194	SF	6	\$12,515	
	Benches, ped mounted	Men's Locker Room	100	LF	6	\$10,888	
	Ceiling - Plaster/ Drywall	Men's Locker Room	3,194	SF	6	\$11,053	
	Doors - Steel Doors incl hw	Men's Locker Room	1	EA	6	\$301	
	Floor Drain	Men's Locker Room	20	EA	6	\$21,183	
	Floor - Concrete	Men's Locker Room	3,194	SF	6	\$1,690	
	Hand Dryer	Men's Locker Room	1	EA	6	\$230	
	Lavatory	Men's Locker Room	3	EA	6	\$959	
	Lighting - Lay-in	Men's Locker Room	30	EA	7	\$0	
	Partitions	Men's Locker Room	4	EA	6	\$1,188	
	Showers	Men's Locker Room	22	EA	6	\$6,851	
	Student Lockers - One Tier	Men's Locker Room	267	EA	6	\$24,787	
	Urinals	Men's Locker Room	3	EA	6	\$1,008	
	Walls - Concrete Block	Men's Locker Room	7,327	SF	6	\$21,479	
	Water Closet	Men's Locker Room	3	EA	6	\$1,008	
Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	2nd Floor	3,342	SF	6	\$23,943	
	Storage Room	2nd Floor	690	SF	6	\$4,943	Teacher's office, Applied arts storage,
	Mechanical/ Service Rooms	Basement	3,432	SF	6	\$24,588	Pool tank
	Storage Room	Basement	698	SF	6	\$5,001	PE storages L5A, L5B, L4A, L4B

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pool & Natatorium							
	Accessories	1st floor (Vacant or under renovation)	6,735	SF	6	\$4,623	
	Bleachers Seating/Plank Seating	1st floor (Vacant or under renovation)	100	EA	6	\$2,894	
	Ceiling - Splined (Moister Resistance)	1st floor (Vacant or under renovation)	6,735	SF	6	\$7,031	
	Doors - Steel Doors incl hw	1st floor (Vacant or under renovation)	4	EA	6	\$1,204	
	Lighting - Pendent/Surface	1st floor (Vacant or under renovation)	160	EA	6	\$19,823	
	Pool Basin	1st floor (Vacant or under renovation)	3,432	SF	6	\$116,118	
	Pool Deck	1st floor (Vacant or under renovation)	1,846	SF	6	\$17,528	
	Pool Deck Drains	1st floor (Vacant or under renovation)	34	EA	6	\$14,350	
	Walls - Structural Glazed Tile	1st floor (Vacant or under renovation)	6,908	SF	6	\$21,733	
Restroom							
	Accessories	1st Floor Men's Room	197	SF	6	\$1,817	
	Accessories	1st Floor Men's Room	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	1st Floor Men's Room	63	SF	6	\$218	
	Ceiling - Plaster/Drywall	1st Floor Men's Room	197	SF	6	\$682	
	Doors - Steel Doors incl hw	1st Floor Men's Room	1	EA	6	\$301	
	Doors - Steel Doors incl hw	1st Floor Men's Room	1	EA	6	\$301	
	Floor Drain	1st Floor Men's Room	1	EA	6	\$1,059	
	Floor Drain	1st Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st Floor Men's Room	197	SF	6	\$197	
	Floor - Tile/Sheet	1st Floor Men's Room	63	SF	6	\$63	
	Hand Dryer	1st Floor Men's Room	1	EA	6	\$230	
	Hand Dryer	1st Floor Men's Room	2	EA	6	\$460	
	Lavatory	1st Floor Men's Room	1	EA	6	\$320	
	Lavatory	1st Floor Men's Room	3	EA	6	\$959	
	Lighting - Lay-in	1st Floor Men's Room	2	EA	7	\$0	
	Lighting - Lay-in	1st Floor Men's Room	4	EA	7	\$0	
	Partitions	1st Floor Men's Room	2	EA	6	\$594	
	Urinals	1st Floor Men's Room	2	EA	6	\$672	
	Walls - Concrete Block	1st Floor Men's Room	259	SF	6	\$759	
	Walls - Concrete Block	1st Floor Men's Room	451	SF	6	\$1,322	
	Water Closet	1st Floor Men's Room	1	EA	6	\$336	
	Water Closet	1st Floor Men's Room	2	EA	6	\$672	
	Accessories	1st Floor Women's Room	173	SF	6	\$1,596	
	Ceiling - Plaster/Drywall	1st Floor Women's Room	173	SF	6	\$599	
	Doors - Steel Doors incl hw	1st Floor Women's Room	1	EA	6	\$301	
	Floor Drain	1st Floor Women's Room	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	1st Floor Women's Room	173	SF	6	\$366	

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Hand Dryer	1st Floor Women's Room	2	EA	6	\$460	
	Lavatory	1st Floor Women's Room	3	EA	6	\$959	
	Lighting - Lay-in	1st Floor Women's Room	4	EA	7	\$0	
	Partitions	1st Floor Women's Room	4	EA	6	\$1,188	
	Walls - Concrete Block	1st Floor Women's Room	412	SF	6	\$1,208	
	Water Closet	1st Floor Women's Room	5	EA	6	\$1,680	
	Accessories	1st Floor	129	SF	6	\$1,190	
	Ceiling - Plaster/Drywall	1st Floor	129	SF	6	\$446	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor	129	SF	6	\$273	
	Hand Dryer	1st Floor	2	EA	6	\$460	
	Lavatory	1st Floor	1	EA	6	\$320	
	Lighting - Lay-in	1st Floor	2	EA	7	\$0	
	Walls - Concrete Block	1st Floor	129	SF	6	\$378	
	Water Closet	1st Floor	1	EA	6	\$336	
	Accessories	2nd Floor Men's Room	197	SF	6	\$1,817	
	Accessories	2nd Floor Men's Room	63	SF	6	\$581	
	Ceiling - Plaster/Drywall	2nd Floor Men's Room	197	SF	6	\$682	
	Ceiling - Plaster/Drywall	2nd Floor Men's Room	63	SF	6	\$218	
	Doors - Steel Doors incl hw	2nd Floor Men's Room	1	EA	6	\$301	
	Doors - Steel Doors incl hw	2nd Floor Men's Room	1	EA	6	\$301	
	Floor Drain	2nd Floor Men's Room	1	EA	6	\$1,059	
	Floor Drain	2nd Floor Men's Room	1	EA	6	\$1,059	
	Floor - Tile/Sheet	2nd Floor Men's Room	197	SF	6	\$197	
	Floor - Tile/Sheet	2nd Floor Men's Room	63	SF	6	\$63	
	Hand Dryer	2nd Floor Men's Room	2	EA	6	\$460	
	Hand Dryer	2nd Floor Men's Room	1	EA	6	\$230	
	Lavatory	2nd Floor Men's Room	3	EA	6	\$959	
	Lavatory	2nd Floor Men's Room	1	EA	6	\$320	
	Lighting - Lay-in	2nd Floor Men's Room	4	EA	7	\$0	
	Lighting - Lay-in	2nd Floor Men's Room	2	EA	7	\$0	
	Partitions	2nd Floor Men's Room	2	EA	6	\$594	
	Urinals	2nd Floor Men's Room	2	EA	6	\$672	
	Walls - Concrete Block	2nd Floor Men's Room	451	SF	6	\$1,322	
	Walls - Concrete Block	2nd Floor Men's Room	259	SF	6	\$759	
	Water Closet	2nd Floor Men's Room	2	EA	6	\$672	

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	2nd Floor Men's Room	1	EA	6	\$336	
	Accessories	2nd Floor Women's Room	173	SF	6	\$1,596	
	Ceiling - Plaster/Drywall	2nd Floor Women's Room	173	SF	6	\$599	
	Doors - Steel Doors incl hw	2nd Floor Women's Room	1	EA	6	\$301	
	Floor Drain	2nd Floor Women's Room	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Women's Room	173	SF	6	\$366	
	Hand Dryer	2nd Floor Women's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Women's Room	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor Women's Room	4	EA	7	\$0	
	Partitions	2nd Floor Women's Room	4	EA	6	\$1,188	
	Walls - Concrete Block	2nd Floor Women's Room	412	SF	6	\$1,208	
	Water Closet	2nd Floor Women's Room	5	EA	6	\$1,680	
	Accessories	2nd Floor	129	SF	6	\$1,190	
	Ceiling - Plaster/Drywall	2nd Floor	129	SF	6	\$446	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	129	SF	6	\$273	
	Hand Dryer	2nd Floor	2	EA	6	\$460	
	Lavatory	2nd Floor	1	EA	6	\$320	
	Lighting - Lay-in	2nd Floor	2	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	368	SF	6	\$1,079	
	Water Closet	2nd Floor	1	EA	6	\$336	
	Accessories	Accessible Unisex Restroom in girl's Shower Room	95	SF	6	\$876	
	Ceiling - Plaster/Drywall	Accessible Unisex Restroom in girl's Shower Room	95	SF	6	\$329	
	Doors - Steel Doors incl hw	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$301	
	Floor Drain	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Accessible Unisex Restroom in girl's Shower Room	95	SF	6	\$201	
	Hand Dryer	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$230	
	Lavatory	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$320	
	Lighting - Lay-in	Accessible Unisex Restroom in girl's Shower Room	2	EA	7	\$0	
	Partitions	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$297	

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Showers	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$311	
	Walls - Concrete Block	Accessible Unisex Restroom in girl's Shower Room	324	SF	6	\$950	
	Water Closet	Accessible Unisex Restroom in girl's Shower Room	1	EA	6	\$336	
	Accessories	Men's Room off the gym	90	SF	6	\$830	
	Ceiling - Plaster/Drywall	Men's Room off the gym	90	SF	6	\$311	
	Doors - Steel Doors incl hw	Men's Room off the gym	1	EA	6	\$301	
	Floor Drain	Men's Room off the gym	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's Room off the gym	90	SF	6	\$190	
	Hand Dryer	Men's Room off the gym	2	EA	6	\$460	
	Lavatory	Men's Room off the gym	2	EA	6	\$639	
	Lighting - Lay-in	Men's Room off the gym	2	EA	7	\$0	
	Partitions	Men's Room off the gym	1	EA	6	\$297	
	Urinals	Men's Room off the gym	1	EA	6	\$336	
	Walls - Concrete Block	Men's Room off the gym	306	SF	6	\$897	
	Water Closet	Men's Room off the gym	1	EA	6	\$336	
	Accessories	Next to Men's Locker room	95	SF	6	\$876	
	Ceiling - Plaster/Drywall	Next to Men's Locker room	95	SF	6	\$329	
	Doors - Steel Doors incl hw	Next to Men's Locker room	1	EA	6	\$301	
	Floor Drain	Next to Men's Locker room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Next to Men's Locker room	95	SF	6	\$201	
	Hand Dryer	Next to Men's Locker room	1	EA	6	\$230	
	Lavatory	Next to Men's Locker room	1	EA	6	\$320	
	Lighting - Lay-in	Next to Men's Locker room	2	EA	7	\$0	
	Showers	Next to Men's Locker room	1	EA	6	\$311	
	Walls - Concrete Block	Next to Men's Locker room	324	SF	6	\$950	
	Water Closet	Next to Men's Locker room	1	EA	6	\$336	
	Accessories	Women's Room off the gym	90	SF	6	\$830	
	Ceiling - Plaster/Drywall	Women's Room off the gym	99	SF	6	\$343	
	Doors - Steel Doors incl hw	Women's Room off the gym	1	EA	6	\$301	
	Floor Drain	Women's Room off the gym	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Room off the gym	99	SF	6	\$210	
	Hand Dryer	Women's Room off the gym	2	EA	6	\$460	
	Lavatory	Women's Room off the gym	2	EA	6	\$639	
	Lighting - Lay-in	Women's Room off the gym	2	EA	7	\$0	
	Partitions	Women's Room off the gym	1	EA	6	\$297	

Building: Linked Addition-Main Athletic

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Concrete Block	Women's Room off the gym	322	SF	6	\$944	
	Water Closet	Women's Room off the gym	2	EA	6	\$672	

Rooms (Other Than Classrooms) Subtotal:

\$987,032

Building: Linked Addition-Main Athletic

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Splined	Entire Building (Link Addition/Recreation Building)	12,668	SF	6	\$36,593	
	Doors - Steel Doors incl hw	Entire Building (Link Addition/Recreation Building)	4	EA	6	\$1,204	At link
	Drinking Fountains - Double Water Cooler	Entire Building (Link Addition/Recreation Building)	4	EA	5	\$18,060	
	Floor - Terrazzo	Entire Building (Link Addition/Recreation Building)	6,701	SF	5	\$252,210	
	Floor - Tile/Sheet	Entire Building (Link Addition/Recreation Building)	5,967	SF	6	\$3,242	
	Lighting - Lay-in	Entire Building (Link Addition/Recreation Building)	158	EA	6	\$18,798	
	Walls - Masonry	Entire Building (Link Addition/Recreation Building)	14,407	SF	6	\$45,324	
Safety							
	Security Cameras	Entire Building	11	EA	6	\$2,134	
	Security Cameras	Entire Building	31	EA	6	\$6,015	
Stairs							
	Ceiling - Plaster/Drywall	Stair D	418	SF	6	\$3,060	
	Floor - Terrazzo	Stair D	418	SF	6	\$3,509	
	Handrails	Stair D	158	LF	6	\$1,369	
	Lighting - Pendant/Surface	Stair D	20	EA	7	\$0	
	Stairs - Terrazzo	Stair D	79	LF	6	\$733	
	Walls - Masonry	Stair D	3,800	SF	6	\$11,955	
	Ceiling - Plaster/Drywall	Stair E	418	SF	6	\$3,060	
	Floor - Terrazzo	Stair E	418	SF	6	\$3,509	
	Handrails	Stair E	158	LF	6	\$1,369	
	Lighting - Pendant/Surface	Stair E	20	EA	7	\$0	
	Stairs - Terrazzo	Stair E	79	LF	6	\$733	

Building: Linked Addition-Main Athletic

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Walls - Plaster/Drywall	Stair E	3,800	SF	6	\$10,488	
Vertical Conveyance							
	Elevator - Hydraulic Elevator	Entire Building	1	EA	6	\$19,238	

Building Interior Subtotal: \$442,604

Total Building Cost \$3,558,095

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Athletic							
	Lighting	East	4	EA	6	\$14,417	
	Lighting	North	9	EA	6	\$32,438	
	Metal Bleachers	North	560	LF	6	\$24,985	
	Surface - Asphalt	East	12,835	SF	5	\$58,549	
	Surface - Natural	NE site of Athletic Building	76,423	SF	6	\$63,385	
	Surface - Natural	North	167,548	SF	6	\$138,964	
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	35	EA	6	\$38,284	
	Civil/ Drainage - Site Drain	Entire Site	13	EA	6	\$4,033	
	Civil/ Drainage - Site Manhole	Entire Site	18	EA	6	\$26,869	
Fencing							
	Fencing - Chain Link	Entire Site	3,032	LF	6	\$56,929	
	Fencing - Guard Rail	Entire Site	288	LF	6	\$3,328	
	Fencing - New Standard Ornamental	Entire Site	756	LF	6	\$24,119	
	Fencing - Wood Fencing w/ Steel Frame	Entire Site	260	LF	6	\$3,409	West of parking lot
Landscape							
	Benches	Entire Site	24	EA	6	\$10,321	
	Irrigation	Entire Site	97,418	SF	5	\$261,899	Location: North baseball field - does not work
	Landscape - Grass	Entire Site	111,381	SF	6	\$92,379	
	Landscape - Hardscape- Concrete	Entire Site	33,186	SF	6	\$171,316	
	Parkway trees	Entire Site	44	EA	6	\$29,042	
	Planting Beds/ Area	Entire Site / South East	7,893	SF	6	\$12,980	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Landscape							
	Retaining Wall - Concrete	Entire Site / South Courtyard	2,340	SF	6	\$54,844	
	Retaining Wall - Masonry	Entire Site	4,109	SF	6	\$59,993	
	Trash Receptacles	Entire Site / North Courtyard	1	EA	6	\$312	
	Walking Path - Crushed Stone	Entire Site / North West	502	SF	6	\$1,062	
Parking Lot							
	Concrete Curbs	Parking Lot- South	182	LF	6	\$2,337	
	Concrete Curbs	Parking Lot- West	628	LF	6	\$8,064	
	Interior Plantings	Parking Lot- West	780	LF	6	\$33,183	
	Lighting - Pole Mounted	Parking Lot- West	10	EA	6	\$14,525	
	Surface - Asphalt	Parking Lot- West	30,456	SF	5	\$138,931	Need seal coating
	Surface - Asphalt	Parking Lot- West	1,500	SF	4	\$15,894	Potholes
	Surface - Concrete	Parking Lot- South	4,110	SF	6	\$9,933	
	Trash Compactor	Parking Lot- South	1	EA	6	\$0	
	Trash Enclosure - Chain Links	Parking Lot- South	155	SF	6	\$2,720	
	Vehicular Screening	Parking Lot- West	718	LF	6	\$56,532	
Service Garage							
	Service Garage - Underground	SE - lower level	6,000	SF	6	\$55,084	
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	2,055	LF	6	\$24,685	
	Sidewalks - Perimeter Sidewalks	Entire Site	12,520	SF	6	\$24,886	
Signage							
	Flag Pole - Flag Pole	Entire Site	5	EA	6	\$8,284	
	Marquee - Free Standing Back lighted w/ LED	Entire Site / Main Entrance	1	EA	6	\$0	
	Monument - Sign	Entire Site	1	EA	6	\$0	Along Division Street

Site Subtotal:

\$1,578,918

Total Site Cost

\$1,578,918

Campus Total ^{2 3}

\$17,388,672

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
 - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Regular Classroom	2nd Floor	202	202	900	1	8	16	180	24	50	N	N	N
Art Room	Computer Lab	2nd Floor	205	205	1,950	1	30	50	420	56	50	N	Y	Y
Art Room	Art Room	2nd Floor	216	216	1,820	2	10	64	384	108	40	N	N	N
Computer Lab	Other Instructional Use	2nd Floor	217	217	1,820	1	30	64	384	108	50	N	N	N
Computer Lab	Computer Lab	4th Floor	409	409	1,156	1	21	46	288	36	50	N	N	N
Computer Lab	Computer Lab	5th Floor	509	509	1,156	1	21	46	288	36	50	N	N	N
Computer Lab	Computer Lab		609	609	1,156	1	21	46	288	36	50	N	N	N
Computer Lab	Computer Lab		709	709	1,156	1	21	46	288	36	50	N	N	N
Computer Lab	Computer Lab		808	808	1,035	1	32	70	288	36	50	N	Y	N
Computer Lab	Computer Lab		819	819	780	1	50	60	0	0	50	N	N	N
Music Room	Music Room	Basement	001	038	1,282	0	0	8	0	0	50	N	N	N
Music Room	Music Room	Basement	002	043	1,806	0	0	10	0	0	50	N	N	N
Music Room	Regular Classroom	Basement	009	049	767	1	2	6	0	0	50	N	N	N
Music Room	Music Room	Basement	041	041	305	0	0	6	0	0	50	N	N	N
Office	Regular Classroom	4th Floor	425	425	450	1	5		288	36	40	N	N	N
Office	Special Education	5th Floor	525	525	450	1	5	14	288	36	50	N	N	N
Office	Regular Classroom		624	624	450	1	5	14	96	12	50	N	N	N
Office	Regular Classroom		625	625	450	1	5	14	288	36	50	N	N	N
Other Instructional Use	Other Instructional Use		026	018	2,280	1	8	30	0	0	40	N	Y	N
Other Instructional Use	Other Instructional Use	2nd Floor	207	207/207C	1,767	2	6	20	0	0	40	N	Y	Y
Other Instructional Use	Regular Classroom	3rd Floor	304	304	450	1	5	14	96	12	50	N	N	N
Other Instructional Use	Regular Classroom	3rd Floor	318	318	605	1	8	20	160	20	50	N	N	N
Other Instructional Use	Regular Classroom	4th Floor	422	422	605	1	8	18	128	16	50	N	N	N
Other Instructional Use	Special Education	5th Floor	522	522	605	1	8	18	128	16	50	N	N	N
Other Instructional Use	Regular Classroom		622	622	605	1	8	18	128	16	50	N	N	N
Other Instructional Use	Other Instructional Use		801	801	1,320	0	0	26	0	0	50	N	Y	N
Other Instructional Use	Other Instructional Use		802	802	593	1	0	8	128	36	50	N	N	N
Regular Classroom	Regular Classroom	Basement	011	050	767	1	2	6	0	0	50	N	N	N
Regular Classroom	Art Room	2nd Floor	201	201	880	1	8	20	192	24	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	203	203	900	1	8	16	180	24	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	204	204	900	1	8	16	360	48	50	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	314	314	770	1	8	18	352	44	50	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	315	450	1	8	18	96	12	50	N	N	N
Regular Classroom	Regular Classroom	4th Floor	401	401	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	402	402	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	403	403	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom	4th Floor	405	405	1,182	1	28	90	0	0	50	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	4th Floor	407	407	605	1	8	20	128	16	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	410	410	758	1	2	6	352	44	50	N	N	N
Regular Classroom	Regular Classroom	4th Floor	411	411	758	1	2	6	160	20	50	N	N	N
Regular Classroom	Regular Classroom	4th Floor	412	412	758	1	2	6	160	20	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	413	413	758	1	2	6	160	20	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	415	415	758	1	2	6	352	44	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	416	416	665	1	15	44	0	0	50	N	N	N
Regular Classroom	Regular Classroom	4th Floor	417	417	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom	4th Floor	419	419	605	1	8	18	128	16	50	N	N	N
Regular Classroom	Regular Classroom	4th Floor	499	499	1,386	1	8	20	480	135	50	N	N	Y
Regular Classroom	Regular Classroom	5th Floor	501	501	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom	5th Floor	502	502	900	1	8	20	192	24	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	503	503	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	504	504	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	505	505	1,182	1	28	90	0	0	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	507	507	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	510	510	758	1	2	6	352	44	50	N	N	Y
Regular Classroom	Regular Classroom	5th Floor	511	511	758	1	2	6	160	20	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	512	512	758	1	2	6	160	20	50	N	N	N
Regular Classroom	Regular Classroom	5th Floor	513	513	758	1	2	6	160	20	50	N	N	Y
Regular Classroom	Regular Classroom	5th Floor	515	515	758	1	2	6	352	44	50	N	N	Y
Regular Classroom	Regular Classroom	5th Floor	517	517	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom	5th Floor	599	599	1,386	1	8	20	480	135	50	N	N	Y
Regular Classroom	Regular Classroom		601	601	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom		602	602	900	1	8	20	192	24	50	N	N	N
Regular Classroom	Regular Classroom		603	603	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom		604	604	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom		605	605	1,182	1	28	90	0	0	50	N	N	N
Regular Classroom	Regular Classroom		607	607	605	1	8	20	128	16	50	N	N	N
Regular Classroom	Regular Classroom		610	610	758	1	2	6	352	44	50	N	N	Y
Regular Classroom	Regular Classroom		611	611	758	1	2	6	160	20	50	N	N	N
Regular Classroom	Regular Classroom		612	612	758	1	2	6	160	20	50	N	N	Y
Regular Classroom	Regular Classroom		613	613	758	1	2	6	160	20	50	N	N	Y
Regular Classroom	Regular Classroom		614	614	758	1	2	6	352	44	50	N	N	N
Regular Classroom	Regular Classroom		615	615	758	1	2	6	352	44	50	N	N	Y
Regular Classroom	Regular Classroom		617	617	900	1	8	20	192	24	50	N	N	Y
Regular Classroom	Regular Classroom		618	618	605	1	8	18	128	16	50	N	N	Y

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom		619	619	605	1	8	18	128	16	50	N	N	N
Regular Classroom	Regular Classroom		620	620	605	1	8	18	128	16	50	N	N	Y
Regular Classroom	Regular Classroom		699	699	1,386	1	8	20	480	135	50	N	N	Y
Regular Classroom	Other Instructional Use		804	804	728	1	8	24	160	45	50	N	N	N
Regular Classroom	Regular Classroom		805	805	665	1	15	44	0	0	50	N	N	N
Regular Classroom	Special Education		807	807	460	0	0	8	96	27	50	N	Y	N
Regular Classroom	Regular Classroom		809	809	903	1	8	18	192	24	50	N	Y	N
Regular Classroom	Special Education		814	814	380	1	2	6	0	0	50	N	N	N
Regular Classroom	Special Education		815	815	380	1	2	6	0	0	50	N	N	N
Regular Classroom	Regular Classroom		823	823	380	1	2	6	0	0	50	N	N	N
Regular Classroom	Regular Classroom		824	824	380	1	2	6	0	0	50	N	N	N
Science Lab Level 1	Science Lab Level 1		810	810	1,483	1	32	100	320	40	50	N	Y	N
Science Lab Level 1	Science Lab Level 1		822	822	1,223	1	8	30	224	28	50	N	N	N
Science Lab Level 1	Science Lab Level 1		826	826	1,223	1	8	30	224	28	50	N	N	N
Science Lab Level 2	Science Lab Level 2		816	816	1,225	1	2	30	448	56	50	N	N	N
Science Lab Level 2	Science Lab Level 2		817	817	1,093	1	2	20	224	28	50	N	N	N
Science Lab Level 2	Science Lab Level 2		820	820	1,093	1	4	30	224	28	50	N	N	N
Science Lab Level 2	Science Lab Level 2		821	821	1,093	1	4	30	448	56	50	N	N	N
Special Education	Special Education	5th Floor	519	519	605	1	8	18	128	16	50	N	N	Y
Special Education	Special Education		616	616	665	1	15	44	0	0	50	N	N	N
Store Room	Music Room	Basement	008	039	500	0	0	6	0	0	50	N	N	N
Store Room	Regular Classroom	2nd Floor	208	208	692	1	8	28	0	0	50	N	N	N
Store Room	Regular Classroom	3rd Floor	305	305	450	1	5	14	96	12	50	N	N	N
Store Room	Regular Classroom	4th Floor	424	424	450	1	5	14	96	12	40	N	N	N
Store Room	Regular Classroom		716C	716C	665	1	15	44	0	0	50	N	N	N
Store Room	Computer Lab		806	806	882	1	8	30	192	54	50	N	N	N
Store Room	Science Lab Level 1		812	812	1,223	1	8	30	224	28	50	N	N	N
Store Room	Regular Classroom	4th Floor	N/A	415A	502	1	2	6	192	24	40	N	N	N
Store Room	Regular Classroom		N/A	615A	502	1	2	6	192	24	40	N	N	N
Vacant	Regular Classroom	2nd Floor	212	212	900	1	8	16	360	48	50	N	N	Y
Vacant	Regular Classroom	3rd Floor	310	310	770	1	8	18	192	54	50	N	N	N
Vacant	Regular Classroom	4th Floor	404	404	605	1	8	20	128	16	50	N	N	N
Vacant	Regular Classroom	4th Floor	408	408	584	1	4	22	0	0	50	N	N	N
Vacant	Regular Classroom	4th Floor	414	414	770	1	8	18	352	44	50	N	N	N
Vacant	Regular Classroom	4th Floor	418	418	605	1	8	18	128	16	50	N	N	N
Vacant	Regular Classroom	4th Floor	420	420	605	1	8	18	128	16	50	N	N	N
Vacant	Special Education	5th Floor	514	514	758	1	2	6	352	44	50	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Vacant	Regular Classroom	5th Floor	516	516	665	1	15	44	0	0	50	N	N	N
Vacant	Special Education	5th Floor	518	518	605	1	8	18	128	16	50	N	N	N
Vacant	Special Education	5th Floor	520	520	605	1	8	18	128	16	50	N	N	N
Vacant	Special Education	5th Floor	524	524	450	1	5	14	96	12	50	N	N	N
Vacant	Regular Classroom		608	608	584	1	4	22	0	0	50	N	N	N
Vacant	Regular Classroom		701	701	900	1	8	20	192	24	50	N	N	N
Vacant	Regular Classroom		702	702	900	1	8	20	192	24	50	N	N	N
Vacant	Regular Classroom		703	703	605	1	8	20	128	16	50	N	N	N
Vacant	Regular Classroom		704	704	605	1	8	20	128	16	50	N	N	N
Vacant	Regular Classroom		705	705	1,182	1	28	90	0	0	50	N	N	N
Vacant	Regular Classroom		707	707	605	1	8	20	128	16	50	N	N	N
Vacant	Regular Classroom		710	710	758	1	2	6	352	44	50	N	N	N
Vacant	Regular Classroom		711	711	758	1	2	6	160	20	50	N	N	N
Vacant	Regular Classroom		712	712	758	1	2	6	160	20	50	N	N	N
Vacant	Regular Classroom		713	713	758	1	2	6	160	20	50	N	N	N
Vacant	Regular Classroom		714	714	758	1	2	6	352	44	50	N	N	N
Vacant	Regular Classroom		715	715	758	1	2	6	352	44	50	N	N	N
Vacant	Regular Classroom		717	717	900	1	8	20	192	24	50	N	N	Y
Vacant	Regular Classroom		718	718	605	1	8	18	128	16	50	N	N	N
Vacant	Regular Classroom		719	719	605	1	8	18	128	16	50	N	N	N
Vacant	Regular Classroom		720	720	605	1	8	18	128	16	50	N	N	N
Vacant	Computer Lab		724	724	900	1	28	60	320	48	50	N	N	N
Vacant	Regular Classroom		799	799	1,386	1	8	20	480	135	50	N	N	N
Vacant	Science Lab Level 1		813	813	1,223	1	8	30	224	28	50	N	N	N

Linked Addition-Main Athletic

Other Instructional Use	Other Instructional Use	2nd Floor	231	G231	1,793	0	0	10	256	72	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	230	G230	1,374	0	0	10	448	126	50	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	232	G232	1,374	1	27	60	448	126	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	236	G236	896	1	8	30	288	36	50	N	N	Y
Regular Classroom	Regular Classroom		238	G238	2,175	1	8	30	0	0	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	239	G239	885	1	1	4	288	36	50	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	240	G240	885	1	1	4	288	36	50	N	N	N