

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1911	3	61,724	\$3,289,540
Addition 2	1999	3	70,296	\$2,364,113
Gymnasium	1992	1	5,637	\$155,194
Lunch room/Kitchen	1999	1	9,359	\$278,322
SITE				\$387,994
Campus Total			147,016	\$6,475,163

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Entrance 7-NW	1	EA	6	\$702	
	Exterior Doors - Exterior FRP Door	Entrance 16-South	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Entrance 6-West / Assembly Hall Vestibule	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Entrance 7-NW	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Entrance 8-North	4	EA	6	\$2,526	
	Exterior Doors - Exterior Steel Door	4th floor mechanical room - roof access doors	4	EA	6	\$1,922	
	Exterior Doors - Transom Lite	Entrance 16-South	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 6-West / Assembly Hall Vestibule	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 7-NW	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 8-North	4	EA	7	\$0	
	Exterior Stairs - Concrete	Entrance 16-South	12	LF	7	\$0	
	Exterior Stairs - Concrete	Entrance 6-West / Assembly Hall Vestibule	140	LF	7	\$0	
	Exterior Stairs - Concrete	Entrance 7-NW	37	LF	7	\$0	
	Exterior Stairs - Concrete	Entrance 7-NW	3	LF	5	\$329	Area cracked, chipped with gaps

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Power Door Operator and Controls	Entrance 7-NW	1	EA	5	\$0	Not working properly
	Ramp Handrail - Steel_Ramp Handrail	Entrance 6-West / Assembly Hall Vestibule	120	LF	6	\$1,040	Rusting and peeling throughout
	Ramp Handrail - Steel_Ramp Handrail	Entrance 7-NW	20	LF	6	\$173	
	Ramps - Concrete	Entrance 6-West / Assembly Hall Vestibule	60	LF	7	\$0	
	Ramps - Concrete	Entrance 7-NW	20	LF	7	\$0	
	Stair Handrail - Steel_Stair Handrail	Entrance 6-West / Assembly Hall Vestibule	30	LF	6	\$260	
	Stair Handrail - Steel_Stair Handrail	Entrance 7-NW	20	LF	6	\$173	
Foundation							
	Foundation - Masonry	Entire Building	500	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	61,724	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	11	EA	6	\$5,902	
	Exterior Lighting - Wall Mounted	Entire Building	8	EA	6	\$2,310	
Roof System							
	Cell Tower	Roof 4	1	EA	6	\$736	Freestanding - not attached to building or chimney
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 4	80	LF	7	\$0	
	Coping - Metal	Roof 3	110	LF	6	\$3,533	
	Coping - Stone	Roof 3	425	LF	7	\$0	
	Coping - Stone	Roof 4	265	LF	6	\$8,511	
	Downspouts - Exterior Downspouts	Roof 3	330	LF	6	\$10,967	Outside Yard Storage included
	Downspouts - Interior Downspouts	Roof 3	110	LF	6	\$3,656	2-strainer caps missing
	Downspouts - Interior Downspouts	Roof 4	250	LF	6	\$8,308	
	Parapet - 16" - 30" Height	Roof 3	70	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof 4	265	LF	6	\$10,588	
	Parapet - Parapet < 16" Height	Roof 3	465	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 3	200	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 3	13,695	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 4	15,670	SF	7	\$0	
	Roof - Metal	Roof 3	750	SF	6	\$10,049	
	Roof - Metal	Roof 4	300	SF	4	\$14,406	Fresh air intake sloped metal roofs - Both rusted, corroded with holes throughout / Water penetration occurring
	Roof - Modified Bitumen	Roof 3	13,145	SF	6	\$123,687	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Roof - Modified Bitumen	Roof 4	1,000	SF	5	\$24,739	Several areas blistering, bubbling, worn out throughout / Ripped adjacent to south fresh air intake
	Roof - Modified Bitumen	Roof 4	14,370	SF	7	\$0	
Walls							
	Canopy - Concrete/ Stucco	Entire Building	1,000	SF	6	\$33,090	N, S
	Cheek-Wall - Concrete	Entire Building	240	SF	7	\$0	West
	Cheek-Wall - Stone	Entire Building	200	SF	6	\$2,051	N, S
	Cornice - Metal Projecting	Entire Building	580	LF	4	\$501,704	Majority rusted with loose pieces throughout
	Exterior Walls - Brick	Entire Building	33,756	SF	6	\$226,874	
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	756	SF	6	\$4,292	
	Exterior Walls - Stone-Cast	Entire Building	2,994	SF	6	\$20,123	
Windows							
	Curtain wall - Insulated Panel	Entire Building	756	SF	6	\$8,476	
	Guard - Guards wire guard	Entire Building	1,820	SF	6	\$23,241	
	Lintels - Steel	Entire Building	805	LF	6	\$23,368	
	Skylite - Glass Single-Pane	Entire Building	191	SF	5	\$11,433	Cracked glass with rusted frames throughout
	Windows - Sash Lexan	Entire Building	4,615	SF	6	\$34,449	
	Windows - Sash Lexan	Entire Building	2,000	SF	5	\$58,716	Several windows not working properly, screwed shut to prevent from falling out of frames
Building Exterior Subtotal:						\$1,189,910	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	Serves main and gymnasium addition.
	Emergency A/C Power - Corridors and Stairs	Entire Building	10,393	SF	6	\$3,121	
	Emergency A/C Power - Multipurpose Room	Entire Building / 1st Floor	6,067	SF	6	\$2,256	
	Emergency Battery Packs - Multipurpose Room	Entire Building / 1st Floor	4	EA	4	\$2,316	Over 20 years of age
	Exit Signs - Corridors and Stairs	Entire Building	18	EA	2	\$9,819	Poor condition. No battery back-up or generator.
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	8	EA	2	\$4,364	No battery back-up or generator.
	Security System - Intrusion Detection	Entire Building	61,724	SF	6	\$15,888	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Emergency feed from ComEd. Serves main and gymnasium addition.
	Main Electrical Service - 1200 A 120/208/3PH	Electrical Room	1	EA	6	\$5,078	Serves main and gymnasium addition.
	PA System	Entire Building	61,724	SF	7	\$0	Serves main and all additions. Control console located in Addition 2.
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	Emergency fuse type
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	Emergency breaker type
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	8	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	

Electrical System Subtotal:

\$43,847

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	61,724	SF	6	\$22,066	
	Fire Alarm_System	Entire Building	61,724	SF	5	\$68,847	Panel located in Addition 2.

Safty System Subtotal:

\$90,913

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Handling Unit- Built Up- Single Zone- Steam Coils - 8001 - 15000 cfm	Mechanical Room	1	EA	6	\$4,341	Serves GymAtrorium
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Mechanical Room	1	EA	6	\$5,788	Serves North side of building floors 1,2,3
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Mechanical Room	1	EA	6	\$5,788	Serves South side of building floors 1,2,3
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Auxiliaries - 15001 - 25000 cfm	Mechanical Room	1	EA	6	\$5,788	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Auxiliaries - 15001 - 25000 cfm	Mechanical Room	1	EA	6	\$5,788	
	Auxiliaries - 8001 - 15000 cfm	Mechanical Room	1	EA	6	\$4,341	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / 1st Floor	100	LF	5	\$96,198	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	5	\$96,198	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	7	\$0	
	Zone Dampers	Mechanical Room	20	EA	6	\$16,661	Adjustments needed
	Zone Dampers	Mechanical Room	24	EA	6	\$19,993	Adjustments needed.
Boiler Systems							
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 101 - 150 HP	Boiler Room	2	EA	5	\$24,345	
	Chemical Feed System	Boiler Room / Mechanical Room	1	EA	6	\$1,078	
	Chemical Feeder	Boiler Room / Mechanical Room	1	EA	6	\$1,078	
	Combustion Dampers	Boiler Room	2	EA	6	\$818	
	Condensate Pump	Boiler Room / Mechanical Room	3	EA	5	\$54,588	
	Feed Water Pumps and Tank	Boiler Room / Mechanical Room	1	EA	5	\$36,450	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 101 - 150 HP	Boiler Room	2	EA	5	\$24,345	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	500	LF	6	\$944	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	500	LF	6	\$944	
	Steam Traps	Boiler Room / Mechanical Room	16	EA	5	\$21,038	(3) AHU's and (2) radiators.
Heating Devices							
	Radiators - Steam	1st Floor	2	EA	5	\$3,351	Manual controls.
	Unit Heater - Electric	Entire Building	4	EA	6	\$1,111	
	Unit Heater - Gas	Entire Building / Boiler Room	1	EA	6	\$278	
	Wall Heater - Electric	Entire Building	8	EA	6	\$1,111	
Temperature Control							
	Pneumatic System	Entire Building	61,724	SF	5	\$212,719	
	Thermostats - Pneumatic	Entire Building	36	EA	6	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	3	EA	6	\$1,777	

Mechanical System Subtotal: \$652,622

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	1	EA	6	\$310	
	Gas Heater - Less than 150000 BTU/HR	Mechanical Room	1	EA	5	\$2,249	Nearing end of useful life.
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	61,724	SF	6	\$12,357	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	61,724	SF	6	\$15,005	Pipe clamps installed
	Domestic Piping-Cold Water Risers	Entire Building	61,724	SF	6	\$11,474	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	61,724	SF	6	\$9,709	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	61,724	SF	6	\$11,474	Pipe clamps installed
	Domestic Piping-Hot Water Return Lines	Entire Building	61,724	SF	6	\$8,827	
	Domestic Piping-Hot Water Return Risers	Entire Building	61,724	SF	6	\$8,827	
	Sanitary Piping	Entire Building	61,724	SF	6	\$56,490	
	Storm Piping	Entire Building	61,724	SF	6	\$53,842	
	Vent Piping	Entire Building	61,724	SF	6	\$41,485	
Pumps							
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room	1	EA	6	\$1,446	
	Pumps - Sump-Simplex	Mechanical Room	1	EA	6	\$745	
Plumbing System Subtotal:						\$234,240	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #100 (Regular Classroom)							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	915	SF	6	\$2,748	
	Doors - Transom Window	1st Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	915	SF	6	\$916	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	1st Floor	1,220	SF	6	\$3,367	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #101 (Regular Classroom)							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	30	LF	6	\$758	
	Ceiling - Lay-in	1st Floor	815	SF	6	\$2,447	
	Chalk Board	1st Floor	50	LF	4	\$4,590	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #101 (Regular Classroom)							
	Doors - Transom Window	1st Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	815	SF	6	\$1,737	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	16	LF	6	\$343	
	Storage/ Closet	1st Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	1st Floor	1,220	SF	6	\$3,367	
Classroom #102 (Regular Classroom)							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	30	LF	6	\$758	
	Ceiling - Lay-in	1st Floor	815	SF	6	\$2,447	
	Chalk Board	1st Floor	50	LF	4	\$4,590	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	815	SF	6	\$1,737	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	16	LF	6	\$343	
	Storage/ Closet	1st Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	1st Floor	1,220	SF	6	\$3,367	
Classroom #103 (Regular Classroom)							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	30	LF	6	\$758	
	Ceiling - Lay-in	1st Floor	815	SF	6	\$2,447	
	Chalk Board	1st Floor	50	LF	4	\$4,590	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	1st Floor	6	EA	6	\$714	
	Marker Board	1st Floor	20	LF	6	\$428	
	Storage/ Closet	1st Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	1st Floor	1,220	SF	6	\$3,367	
Classroom #104 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #104 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
	Walls - Plaster/Drywall	2nd Floor	20	SF	5	\$102	Peering paint
Classroom #105 (Regular Classroom)							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	915	SF	6	\$2,748	
	Chalk Board	1st Floor	30	LF	4	\$2,754	
	Doors - Transom Window	1st Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	915	SF	6	\$6,451	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	8	LF	6	\$171	
	Storage/ Closet	1st Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	1st Floor	1,220	SF	6	\$3,367	
Classroom #200 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	415	SF	6	\$1,246	
	Doors - Transom Window	2nd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	415	SF	6	\$415	
	Lighting - Lay-in	2nd Floor	6	EA	6	\$714	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	2nd Floor	930	SF	6	\$2,567	
Classroom #201 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #201 (Regular Classroom)							
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	815	SF	6	\$816	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #202 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #203 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	815	SF	6	\$816	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,321	SF	6	\$3,646	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #204 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #204 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	5	\$645	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #205 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #206 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #207 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #207 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #208 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #209 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	2nd Floor	815	SF	6	\$2,447	
	Chalk Board	2nd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	2nd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	1,220	SF	6	\$3,367	
Classroom #210 (Regular Classroom)							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	533	SF	6	\$1,601	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #210 (Regular Classroom)							
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	533	SF	6	\$3,758	
	Lighting - Lay-in	2nd Floor	6	EA	6	\$714	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	2nd Floor	920	SF	6	\$2,539	
Classroom #300 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	3rd Floor	417	SF	6	\$1,252	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	417	SF	6	\$417	
	Lighting - Lay-in	3rd Floor	6	EA	6	\$714	
	Marker Board	3rd Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	3rd Floor	996	SF	6	\$2,749	
Classroom #301 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #302 (Regular Classroom)							
	AC Units	3rd Floor	2	EA	6	\$991	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #302 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #303 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #304 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #305 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #305 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #306 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #307 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #308 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #308 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #309 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	815	SF	6	\$2,447	
	Chalk Board	3rd Floor	50	LF	4	\$4,590	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	815	SF	6	\$5,746	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	3rd Floor	1,220	SF	6	\$3,367	
Classroom #310 (Regular Classroom)							
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	533	SF	6	\$1,601	
	Chalk Board	3rd Floor	16	LF	4	\$1,469	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	533	SF	6	\$3,758	
	Lighting - Lay-in	3rd Floor	6	EA	6	\$714	
	Marker Board	3rd Floor	8	LF	6	\$171	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	Wardrobe
	Walls - Plaster/Drywall	3rd Floor	920	SF	6	\$2,539	
Classroom #311 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	415	SF	6	\$1,246	
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	415	SF	6	\$415	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #311 (Regular Classroom)							
	Lighting - Lay-in	3rd Floor	6	EA	6	\$714	
	Marker Board	3rd Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	3rd Floor	930	SF	6	\$2,567	

Classrooms Subtotal:

\$492,559

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Plaster/Drywall	102 A Office	98	SF	6	\$339	
	Doors - Wood Doors inclu hw	102 A Office	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	102 A Office	98	SF	6	\$52	
	Lighting - Pendent/Surface	102 A Office	1	EA	6	\$124	
	Power Distribution	102 A Office	2	EA	7	\$0	
	Walls - Plaster/Drywall	102 A Office	186	SF	6	\$513	
	Ceiling - Lay-in	106 Office	470	SF	6	\$1,411	
	Doors - Side-lite	106 Office	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	106 Office	1	EA	6	\$301	
	Floor - Tile/Sheet	106 Office	470	SF	6	\$470	
	Lighting - Lay-in	106 Office	8	EA	6	\$952	
	Power Distribution	106 Office	12	EA	7	\$0	
	Walls - Plaster/Drywall	106 Office	700	SF	6	\$1,932	
	AC Unit	211 ADJ Room	1	EA	6	\$496	
	Ceiling - Lay-in	211 ADJ Room	415	SF	6	\$1,246	
	Doors - Transom Window	211 ADJ Room	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	211 ADJ Room	1	EA	6	\$301	
	Floor - Tile/Sheet	211 ADJ Room	415	SF	6	\$415	
	Lighting - Lay-in	211 ADJ Room	6	EA	6	\$714	
	Power Distribution	211 ADJ Room	8	EA	7	\$0	
	Walls - Plaster/Drywall	211 ADJ Room	930	SF	6	\$2,567	
	AC Unit	99 Office	1	EA	6	\$496	
	Ceiling - Lay-in	99 Office	490	SF	6	\$1,471	
	Doors - Transom Window	99 Office	80	SF	6	\$1,354	
	Doors - Wood Doors inclu hw	99 Office	1	EA	6	\$301	
	Floor - Carpet	99 Office	210	SF	6	\$447	
	Floor - Tile/Sheet	99 Office	280	SF	6	\$280	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	99 Office	9	EA	6	\$1,071	
	Power Distribution	99 Office	12	EA	7	\$0	
	Storage/ Closet	99 Office	20	SF	6	\$145	
	Walls - Plaster/Drywall	99 Office	730	SF	6	\$2,015	
	AC Unit	99-1 Conference	1	EA	6	\$496	
	Ceiling - Lay-in	99-1 Conference	187	SF	6	\$562	
	Doors - Transom Window	99-1 Conference	70	SF	6	\$1,185	
	Doors - Wood Doors inclu hw	99-1 Conference	1	EA	6	\$301	
	Floor - Carpet	99-1 Conference	187	SF	6	\$398	
	Lighting - Lay-in	99-1 Conference	3	EA	6	\$357	
	Power Distribution	99-1 Conference	8	EA	7	\$0	
	Walls - Plaster/Drywall	99-1 Conference	355	SF	6	\$980	
	Ceiling - Plaster/Drywall	Assistant Engineer's Office	167	SF	6	\$578	
	Doors - Wood Doors inclu hw	Assistant Engineer's Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Assistant Engineer's Office	167	SF	6	\$167	
	Lighting - Pendent/Surface	Assistant Engineer's Office	3	EA	6	\$372	
	Power Distribution	Assistant Engineer's Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Assistant Engineer's Office	317	SF	6	\$875	
	Ceiling - Exposed	Custodian Office	190	SF	6	\$283	
	Doors - Wood Doors inclu hw	Custodian Office	1	EA	6	\$301	
	Floor - Concrete	Custodian Office	190	SF	6	\$101	
	Lighting - Pendent/Surface	Custodian Office	2	EA	6	\$248	
	Power Distribution	Custodian Office	6	EA	7	\$0	
	Walls - Masonry	Custodian Office	361	SF	6	\$1,136	
	Ceiling - Plaster/Drywall	Engineer's Office	179	SF	6	\$619	
	Doors - Wood Doors inclu hw	Engineer's Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Engineer's Office	179	SF	6	\$179	
	Lighting - Pendent/Surface	Engineer's Office	1	EA	6	\$124	
	Power Distribution	Engineer's Office	4	EA	7	\$0	
	Storage/ Closet	Engineer's Office	30	SF	6	\$218	
	Walls - Plaster/Drywall	Engineer's Office	650	SF	6	\$1,794	
	Work Slnk	Engineer's Office	1	EA	6	\$508	
	Ceiling - Plaster/Drywall	P.E Office	127	SF	6	\$439	
	Doors - Wood Doors inclu hw	P.E Office	1	EA	6	\$301	
	Floor - Tile/Sheet	P.E Office	127	SF	6	\$127	
	Lighting - Pendent/Surface	P.E Office	3	EA	6	\$372	
	Power Distribution	P.E Office	6	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Plaster/Drywall	P.E Office	241	SF	6	\$665	
Gymnasia							
	Ceiling - Lay-in	1st Floor	2,890	SF	6	\$8,679	
	Ceiling - Plaster/Drywall	1st Floor	3,033	SF	6	\$16,742	
	Doors - Wood Doors inclu hw	1st Floor	7	EA	6	\$2,107	
	Floor - Wood	1st Floor	6,067	SF	6	\$42,772	
	Lighting - Pendent/Surface	1st Floor	17	EA	6	\$2,106	
	Main Floor Seating	1st Floor	425	EA	6	\$73,915	
	Sound System	1st Floor	1	EA	6	\$41,654	
	Stage	1st Floor	420	SF	6	\$2,426	
	Stage Lighting System	1st Floor	1	EA	6	\$12,369	
	Stage-Stairs - Wood	1st Floor	14	LF	6	\$164	
	Walls - Masonry	1st Floor	3,164	SF	6	\$9,954	Brick
Mechanical/ Service Rooms							
	Air Intake Plenums	1st Floor	1,250	SF	6	\$7,740	
	Air Tunnel	1st Floor	3,680	SF	6	\$22,786	
	Boiler Room	1st Floor	1,511	SF	6	\$10,825	
	Coal Room	1st Floor	276	SF	6	\$1,977	
	Interior Stairs	1st Floor	15	LF	6	\$135	
	Janitor's Closet	1st Floor	120	SF	6	\$860	
	Mechanical/ Service Rooms	1st Floor	2,150	SF	6	\$15,403	
	Storage Room	1st Floor	150	SF	6	\$1,075	
	Storage Room	1st Floor	205	SF	6	\$1,469	Outside Yard Storage - In between main and Lunchroom addition
	Janitor's Closet	2nd Floor	20	SF	6	\$143	
	Mechanical/ Service Rooms	2nd Floor	50	SF	6	\$358	
	Janitor's Closet	3rd Floor	20	SF	6	\$143	
	Mechanical/ Service Rooms	3rd Floor	50	SF	6	\$358	
Restroom							
	Accessories	1st Floor Boy's Room	467	SF	6	\$4,307	
	Accessories	1st Floor Boy's Room	467	SF	6	\$4,307	
	Ceiling - Plaster/Drywall	1st Floor Boy's Room	467	SF	6	\$1,616	
	Ceiling - Plaster/Drywall	1st Floor Boy's Room	467	SF	6	\$1,616	
	Doors - Wood Doors inclu hw	1st Floor Boy's Room	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	1st Floor Boy's Room	1	EA	6	\$301	
	Floor Drain	1st Floor Boy's Room	1	EA	6	\$1,059	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	1st Floor Boy's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor Boy's Room	467	SF	6	\$988	
	Floor - Tile Ceramic/ Porcelain	1st Floor Boy's Room	467	SF	6	\$988	
	Hand Dryer	1st Floor Boy's Room	2	EA	6	\$460	
	Hand Dryer	1st Floor Boy's Room	2	EA	6	\$460	
	Lavatory	1st Floor Boy's Room	2	EA	6	\$639	
	Lavatory	1st Floor Boy's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Floor Boy's Room	4	EA	6	\$496	
	Lighting - Pendent/Surface	1st Floor Boy's Room	4	EA	6	\$496	
	Partitions	1st Floor Boy's Room	2	EA	6	\$594	
	Partitions	1st Floor Boy's Room	2	EA	6	\$594	
	Urinals	1st Floor Boy's Room	5	EA	6	\$1,680	
	Walls - Masonry	1st Floor Boy's Room	532	SF	6	\$1,674	Brick
	Walls - Masonry	1st Floor Boy's Room	532	SF	6	\$1,674	Brick
	Walls - Plaster/Drywall	1st Floor Boy's Room	532	SF	6	\$1,468	
	Walls - Plaster/Drywall	1st Floor Boy's Room	532	SF	6	\$1,468	
	Water Closet	1st Floor Boy's Room	2	EA	6	\$672	
	Water Closet	1st Floor Boy's Room	2	EA	6	\$672	
	Accessories	1st Floor Girl's Room	468	SF	6	\$4,317	
	Ceiling - Plaster/Drywall	1st Floor Girl's Room	468	SF	6	\$1,620	
	Floor Drain	1st Floor Girl's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor Girl's Room	468	SF	6	\$990	
	Hand Dryer	1st Floor Girl's Room	2	EA	6	\$460	
	Lavatory	1st Floor Girl's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Floor Girl's Room	4	EA	6	\$496	
	Partitions	1st Floor Girl's Room	6	EA	6	\$1,782	
	Walls - Masonry	1st Floor Girl's Room	532	SF	6	\$1,674	Brick
	Walls - Plaster/Drywall	1st Floor Girl's Room	532	SF	6	\$1,468	
	Water Closet	1st Floor Girl's Room	7	EA	6	\$2,352	
	Accessories	1st Floor	50	SF	6	\$461	
	Ceiling - Plaster/Drywall	1st Floor	50	SF	6	\$173	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Floor	50	SF	6	\$106	
	Lavatory	1st Floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st Floor	1	EA	6	\$124	
	Walls - Plaster/Drywall	1st Floor	352	SF	6	\$971	
	Water Closet	1st Floor	1	EA	6	\$336	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Accessories	2nd Floor Boy's Room	467	SF	6	\$4,307	
	Ceiling - Plaster/Drywall	2nd Floor Boy's Room	467	SF	6	\$1,616	
	Floor Drain	2nd Floor Boy's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Boy's Room	467	SF	6	\$988	
	Hand Dryer	2nd Floor Boy's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Boy's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd Floor Boy's Room	4	EA	6	\$496	
	Partitions	2nd Floor Boy's Room	2	EA	6	\$594	
	Urinals	2nd Floor Boy's Room	5	EA	6	\$1,680	
	Walls - Masonry	2nd Floor Boy's Room	532	SF	6	\$1,674	Brick
	Walls - Plaster/Drywall	2nd Floor Boy's Room	532	SF	6	\$1,468	
	Water Closet	2nd Floor Boy's Room	2	EA	6	\$672	
	Accessories	2nd Floor Girl's Room	468	SF	6	\$4,317	
	Ceiling - Plaster/Drywall	2nd Floor Girl's Room	468	SF	6	\$1,620	
	Floor Drain	2nd Floor Girl's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Girl's Room	468	SF	6	\$990	
	Hand Dryer	2nd Floor Girl's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Girl's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd Floor Girl's Room	4	EA	6	\$496	
	Partitions	2nd Floor Girl's Room	6	EA	6	\$1,782	
	Walls - Masonry	2nd Floor Girl's Room	532	SF	6	\$1,674	Brick
	Walls - Plaster/Drywall	2nd Floor Girl's Room	532	SF	6	\$1,468	
	Water Closet	2nd Floor Girl's Room	7	EA	6	\$2,352	
	Accessories	2nd Floor	50	SF	6	\$461	
	Ceiling - Plaster/Drywall	2nd Floor	50	SF	6	\$173	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	50	SF	6	\$106	
	Lavatory	2nd Floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd Floor	1	EA	6	\$124	
	Partitions	2nd Floor	1	EA	6	\$297	
	Walls - Plaster/Drywall	2nd Floor	352	SF	6	\$971	
	Water Closet	2nd Floor	1	EA	6	\$336	
	Accessories	3rd Floor Boy's Room	467	SF	6	\$4,307	
	Ceiling - Plaster/Drywall	3rd Floor Boy's Room	467	SF	6	\$1,616	
	Floor Drain	3rd Floor Boy's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Boy's Room	467	SF	6	\$988	
	Hand Dryer	3rd Floor Boy's Room	2	EA	6	\$460	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	3rd Floor Boy's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	3rd Floor Boy's Room	4	EA	6	\$496	
	Partitions	3rd Floor Boy's Room	2	EA	6	\$594	
	Urinals	3rd Floor Boy's Room	5	EA	6	\$1,680	
	Walls - Masonry	3rd Floor Boy's Room	532	SF	6	\$1,674	Brick
	Walls - Plaster/Drywall	3rd Floor Boy's Room	532	SF	6	\$1,468	
	Water Closet	3rd Floor Boy's Room	2	EA	6	\$672	
	Accessories	3rd Floor Girl's Room	468	SF	6	\$4,317	
	Ceiling - Plaster/Drywall	3rd Floor Girl's Room	468	SF	6	\$1,620	
	Floor Drain	3rd Floor Girl's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Girl's Room	468	SF	6	\$990	
	Hand Dryer	3rd Floor Girl's Room	2	EA	6	\$460	
	Lavatory	3rd Floor Girl's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	3rd Floor Girl's Room	4	EA	6	\$496	
	Partitions	3rd Floor Girl's Room	6	EA	6	\$1,782	
	Walls - Masonry	3rd Floor Girl's Room	532	SF	6	\$1,674	Brick
	Walls - Plaster/Drywall	3rd Floor Girl's Room	532	SF	6	\$1,468	
	Water Closet	3rd Floor Girl's Room	7	EA	6	\$2,352	
	Accessories	3rd Floor	50	SF	6	\$461	
	Ceiling - Plaster/Drywall	3rd Floor	50	SF	6	\$173	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	3rd Floor	50	SF	6	\$106	
	Lavatory	3rd Floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	3rd Floor	1	EA	6	\$124	
	Partitions	3rd Floor	1	EA	6	\$297	
	Walls - Plaster/Drywall	3rd Floor	352	SF	6	\$971	
	Water Closet	3rd Floor	1	EA	6	\$336	
	Accessories	99 Staff Unisex Toilet	37	SF	6	\$341	
	Ceiling - Plaster/Drywall	99 Staff Unisex Toilet	37	SF	6	\$128	
	Doors - Wood Doors inclu hw	99 Staff Unisex Toilet	1	EA	6	\$301	
	Floor - Tile/Sheet	99 Staff Unisex Toilet	37	SF	6	\$37	
	Lavatory	99 Staff Unisex Toilet	1	EA	6	\$320	
	Lighting - Pendent/Surface	99 Staff Unisex Toilet	1	EA	6	\$124	
	Walls - Plaster/Drywall	99 Staff Unisex Toilet	340	SF	6	\$938	
	Water Closet	99 Staff Unisex Toilet	1	EA	6	\$336	
	Accessories	In Boiler Room Area	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	In Boiler Room Area	16	SF	6	\$55	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	In Boiler Room Area	1	EA	6	\$301	
	Floor - Concrete	In Boiler Room Area	16	SF	6	\$8	
	Lighting - Wall Mounted	In Boiler Room Area	1	EA	6	\$124	
	Walls - Concrete Block	In Boiler Room Area	223	SF	6	\$654	
	Water Closet	In Boiler Room Area	1	EA	6	\$336	
	Accessories	Unisex Toilet in room 105	46	SF	6	\$424	
	Ceiling - Plaster/Drywall	Unisex Toilet in room 105	46	SF	6	\$159	
	Doors - Wood Doors inclu hw	Unisex Toilet in room 105	1	EA	6	\$301	
	Floor - Tile/Sheet	Unisex Toilet in room 105	46	SF	6	\$46	
	Lavatory	Unisex Toilet in room 105	1	EA	6	\$320	
	Lighting - Wall Mounted	Unisex Toilet in room 105	1	EA	6	\$124	
	Walls - Plaster/Drywall	Unisex Toilet in room 105	340	SF	6	\$938	
	Water Closet	Unisex Toilet in room 105	2	EA	6	\$672	

Rooms (Other Than Classrooms) Subtotal:

\$438,976

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	3,071	SF	6	\$9,222	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
	Doors - Wood Doors include hw	1st Floor	12	EA	6	\$3,612	
	Drinking Fountains - Single Fountain	1st Floor	3	EA	6	\$827	
	Floor - Concrete Epoxy/ Painted	1st Floor	3,071	SF	6	\$1,493	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Lighting - Pendent/Surface	1st Floor	37	EA	6	\$4,584	
	Walls - Plaster/Drywall	1st Floor	4,481	SF	6	\$19,864	
	Ceiling - Lay-in	2nd Floor	3,071	SF	6	\$9,222	
	Drinking Fountains - Single Fountain	2nd Floor	4	EA	6	\$1,103	
	Floor - Asphalt Floor	2nd Floor	3,071	SF	6	\$4,655	
	Lighting - Lay-in	2nd Floor	29	EA	6	\$3,450	
	Walls - Plaster/Drywall	2nd Floor	4,481	SF	6	\$19,864	
	Ceiling - Lay-in	3rd Floor	3,071	SF	6	\$9,222	
	Drinking Fountains - Single Fountain	3rd Floor	3	EA	6	\$827	
	Floor - Concrete Epoxy/ Painted	3rd Floor	3,071	SF	6	\$1,493	
	Lighting - Lay-in	3rd Floor	29	EA	6	\$3,450	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Walls - Plaster/Drywall	3rd Floor	4,481	SF	6	\$19,864	
Stairs							
	Ceiling - Plaster/Drywall	Stairwell # 1	321	SF	6	\$2,350	
	Floor - Asphalt	Stairwell # 1	590	SF	6	\$4,573	
	Handrails	Stairwell # 1	180	LF	6	\$1,560	
	Lighting - Pendent/Surface	Stairwell # 1	6	EA	6	\$743	
	Lighting - Wall Mounted	Stairwell # 1	2	EA	6	\$248	
	Stairs - Asphalt	Stairwell # 1	60	LF	6	\$557	
	Walls - Plaster/Drywall	Stairwell # 1	2,052	SF	6	\$5,663	
	Ceiling - Plaster/Drywall	Stairwell # 2	321	SF	6	\$2,350	
	Floor - Asphalt	Stairwell # 2	590	SF	6	\$4,573	
	Handrails	Stairwell # 2	180	LF	6	\$1,560	
	Lighting - Pendent/Surface	Stairwell # 2	6	EA	6	\$743	
	Lighting - Wall Mounted	Stairwell # 2	2	EA	6	\$248	
	Stairs - Asphalt	Stairwell # 2	60	LF	6	\$557	
	Walls - Plaster/Drywall	Stairwell # 2	2,052	SF	6	\$5,663	

Building Interior Subtotal: \$146,474

Total Building Cost \$3,289,540

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Entrance 5-North	1	EA	6	\$702	
	Entrance Control - Audio and Video	Main Entrance 1-South	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	Entrance 3A-West / Outside Electrical Room	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 3B-West / Outside Pump Room	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Exit 2-South	2	EA	6	\$961	
	Exterior Doors - Side lite	Entrance 3-West	4	EA	7	\$0	
	Exterior Doors - Store Front	Entrance 3-West	2	EA	6	\$1,092	
	Exterior Doors - Store Front	Entrance 4-NW	2	EA	6	\$1,092	
	Exterior Doors - Store Front	Entrance 5-North	2	EA	6	\$1,092	

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Store Front	Main Entrance 1-South	6	EA	6	\$3,276	
	Exterior Doors - Transom Lite	Entrance 3A-West / Outside Electrical Room	1	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 3B-West / Outside Pump Room	1	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 3-West	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 5-North	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Main Entrance 1-South	6	EA	7	\$0	
Foundation							
	Foundation - Concrete	Entire Building	628	LF	7	\$0	
	Superstructure - Steel	Entire Building	70,296	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	26	EA	6	\$7,507	7-At outside chiller enclosure
	Exterior Lighting - Wall Mounted	Entire Building	1	EA	5	\$427	
Roof System							
	Cell Tower	Roof 2	1	EA	6	\$736	Building mounted
	Chimney - Metal Flue	Roof 1	25	LF	7	\$0	
	Coping - Metal	Roof 1	50	LF	7	\$0	
	Coping - Stone	Roof 1	410	LF	7	\$0	S, W, N coping at outside chiller enclosure screen walls included
	Coping - Stone	Roof 2	675	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 1	195	LF	6	\$6,480	
	Downspouts - Interior Downspouts	Roof 2	545	LF	6	\$18,112	1-strainer cap missing
	Parapet - 16" - 30" Height	Roof 1	300	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 1	50	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 2	45	LF	7	\$0	Above entrance 5 and adjacent to main entrance 1
	Parapet - Parapet > 30"	Roof 2	630	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 1	5,830	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 2	15,035	SF	7	\$0	
	Roof - Modified Bitumen	Roof 1	5,830	SF	7	\$0	
	Roof - Modified Bitumen	Roof 2	14,035	SF	7	\$0	
	Roof - Modified Bitumen	Roof 2	1,000	SF	6	\$13,800	Majority of area underneath chiller blistering, bubbling, worn-out throughout
Walls							
	Exterior Walls - Brick	Entire Building	33,896	SF	7	\$0	
	Exterior Walls - Concrete Block	Entire Building	1,168	SF	7	\$0	

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls							
	Exterior Walls - Stone-Cast	Entire Building	6,834	SF	7	\$0	
Windows							
	Guard - Guards perforated	Entire Building	2,294	SF	6	\$29,294	
	Lintels - Steel	Entire Building	906	LF	7	\$0	
	Windows - Louver	Entire Building	750	SF	7	\$0	Mechanical
	Windows - Sash Aluminum Double-pane	Entire Building	6,590	SF	7	\$0	

Building Exterior Subtotal:

\$86,716

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	1	EA	7	\$0	Serves Addition 2 and Lunchroom Addition.
	Emergency A/C Power - Corridors and Stairs	Entire Building	19,592	SF	6	\$5,883	independent service
	Emergency Battery Packs - Corridors and Stairs	Entire Building	16	EA	6	\$3,240	
	Emergency Battery Packs - Students Toilets	Entire Building	6	EA	6	\$1,215	
	Exit Signs - Corridors and Stairs	Entire Building	29	EA	2	\$15,819	Independent service. No battery back-up or generator.
	Security System - Intrusion Detection	Entire Building	70,296	SF	6	\$18,094	
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Emergency feed from ComEd. Serves Addition 2 and Lunchroom Addition.
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	1	EA	7	\$0	Serves Addition 2 and Lunchroom Addition.
	PA System	Entire Building	70,296	SF	7	\$0	Serves entire site, Control console located in Addition 2.
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	Emergency panel
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	3	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	Motor control
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	10	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	2	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	7	\$0	Emergency power
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	7	\$0	

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution							
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	7	\$0	

Electrical System Subtotal: \$44,551

Building: Addition 2

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Mechanical Room	2	EA	6	\$12,812	Serves entire site
	Fire Alarm Strobe Lights	Mechanical Room / Entire Building	70,296	SF	6	\$25,131	
	Fire Alarm_System	Mechanical Room / Entire Building	70,296	SF	5	\$78,408	
	Fire Pump Controller	Mechanical Room	1	EA	6	\$1,823	

Pump Room Assembly

	Fire Pump - 25-50 hp	Mechanical Room	1	EA	6	\$1,558	Also serves Gym, Lunch room additions. Not the Main.
	Jockey Pump	Mechanical Room	1	EA	6	\$758	

Sprinkler System

	Sprinkler Heads	Entire Building	70,296	SF	7	\$0	
	Sprinkler Piping	Entire Building	70,296	SF	7	\$0	
	Wet Sprinkler System	Entire Building	70,296	SF	7	\$0	

Safty System Subtotal: \$120,489

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Chiller-Air Cooled- Recipricating-Roof Mounted - 101 - 200 tons	Roof	1	EA	6	\$4,314	Serves Addition 2 and Lunchroom Addition.
	Glycol Feed	Roof / Mechanical Room	1	EA	5	\$0	
	Heat Pump- Ceiling Mounted- Hot Water Heating & DX Cooling- Self Contained Air Cooled Compressor - Less than 3 tons	Electrical Room	1	EA	5	\$3,914	Serves MDF
	Pipes - Chilled Water Pipe- Copper	Roof / Entire Building	100	LF	6	\$189	
	Pipes - Chilled Water Pipe- Steel	Roof / Entire Building	400	LF	6	\$755	

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves floor 1
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves floors 2,3
	Air Intake	Mechanical Room / Façade- SW	2	EA	7	\$0	
	Air Intake	Mechanical Room / Façade- SW	1	EA	7	\$0	
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building / 1st Floor	17	EA	5	\$26,785	Served from AH-1
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building / 2nd Floor	16	EA	5	\$25,209	Served from AH-2
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building / 3rd Floor	25	EA	5	\$39,389	Served from AH-2
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	Entire Building / Mechanical Room	1	EA	6	\$1,857	Serves floor 1
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	Entire Building / Mechanical Room	1	EA	6	\$2,433	Serves floors 2,3
	VAV Box	Mechanical Room / 1st Floor	7	EA	5	\$9,324	Refer to fan power box section for additional
	VAV Box	Mechanical Room / 2nd Floor	6	EA	5	\$7,992	Refer to fan power box section for additional
	VAV Box	Mechanical Room / 3rd Floor	1	EA	5	\$1,332	Refer to fan power box section for additional zones.
Boiler Systems							
	Boiler Auxiliary- Non Condensing Hot Water - 1001 - 2000 MBH	Boiler Room	4	EA	5	\$137,886	
	Combustion Dampers	Boiler Room	4	EA	6	\$1,636	
	Glycol Feed System	Boiler Room / Mechanical Room	1	EA	5	\$1,724	
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - 1001 - 2000 MBH	Boiler Room	4	EA	5	\$186,797	Serves Addition 2 and Lunchroom Addition.
Gas Booster							
	Gas Booster	Mechanical Room	2	EA	7	\$0	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building	8	EA	6	\$2,835	
	Unit Heater - Electric	Entire Building / Mechanical Room	2	EA	6	\$556	
	Unit Heater - Hot Water	Entire Building	6	EA	6	\$1,675	
Mechanical Plumbing							
	Chilled Water Pump - 10 - 20 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - 10 - 20 HP	Boiler Room	2	EA	6	\$2,485	
	Hot Water Pump - Less than 10	Boiler Room / Mechanical Room	2	EA	6	\$2,222	
	Hydronic Supply and Return - Copper	Entire Building	1,300	LF	6	\$68,207	Also serves Lunch Addition. Not the main.
	Hydronic Supply and Return - Steel	Entire Building	600	LF	6	\$46,066	Also serves Lunch Addition. Not the main.
Temperature Control							
	DDC System	Entire Building	70,296	SF	5	\$115,602	Also serves Kitchen, gym additions. Not the Main.
	Thermostats - DDC	Entire Building	77	EA	6	\$0	

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Temperature Control							
Ventilation							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / 2nd Floor	1	EA	6	\$592	
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / Electrical Room	1	EA	6	\$592	

Mechanical System Subtotal: \$701,550

Building: Addition 2

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	2	EA	5	\$4,498	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	70,296	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	70,296	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	70,296	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	70,296	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	70,296	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	70,296	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	70,296	SF	7	\$0	
	Sanitary Piping	Entire Building	70,296	SF	7	\$0	
	Storm Piping	Entire Building	70,296	SF	7	\$0	
	Vent Piping	Entire Building	70,296	SF	7	\$0	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	
	Pumps - Sump-Simplex	Mechanical Room	1	EA	6	\$745	

Plumbing System Subtotal: \$7,220

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #110 (Pre School)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,220	SF	6	\$3,664	
	Chalk Board	1st Floor	12	LF	4	\$1,102	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #110 (Pre School)							
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,220	SF	6	\$1,221	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	46	SF	6	\$334	
	Walls - Concrete Block	1st Floor	1,060	SF	6	\$3,107	
	Walls - Plaster/Drywall	1st Floor	306	SF	6	\$845	
	Work Sink	1st Floor	1	EA	6	\$379	drinking fountain
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #111 (Pre School)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,172	SF	6	\$3,520	
	Chalk Board	1st Floor	10	LF	6	\$223	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,172	SF	6	\$1,173	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	6	\$171	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Concrete Block	1st Floor	692	SF	6	\$2,029	
	Walls - Plaster/Drywall	1st Floor	692	SF	6	\$1,910	
	Work Sink	1st Floor	2	EA	6	\$758	
	Work Sink	1st Floor	1	EA	6	\$379	Drinking fountain
Classroom #112 (Kindergarten)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,220	SF	6	\$3,664	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,220	SF	6	\$1,221	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Concrete Block	1st Floor	754	SF	6	\$2,210	
	Walls - Plaster/Drywall	1st Floor	612	SF	6	\$1,689	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #112 (Kindergarten)							
	Work Sink	1st Floor	2	EA	6	\$758	1 drinking fountain
Classroom #113 (Pre School)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,172	SF	6	\$3,520	
	Chalk Board	1st Floor	10	LF	6	\$223	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,172	SF	6	\$1,173	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Concrete Block	1st Floor	692	SF	6	\$2,029	
	Walls - Plaster/Drywall	1st Floor	692	SF	6	\$1,910	
	Work Sink	1st Floor	2	EA	6	\$758	
	Work Sink	1st Floor	1	EA	6	\$379	Drinking fountain
Classroom #114 (Kindergarten)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,220	SF	6	\$3,664	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,220	SF	6	\$1,221	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Concrete Block	1st Floor	754	SF	6	\$2,210	
	Walls - Plaster/Drywall	1st Floor	612	SF	6	\$1,689	
	Work Sink	1st Floor	2	EA	6	\$758	
	Work Sink	1st Floor	1	EA	6	\$379	Drinking fountain
Classroom #115 (Kindergarten)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,172	SF	6	\$3,520	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,172	SF	6	\$1,173	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #115 (Kindergarten)							
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Concrete Block	1st Floor	692	SF	6	\$2,029	
	Walls - Plaster/Drywall	1st Floor	692	SF	6	\$1,910	
	Work Sink	1st Floor	2	EA	6	\$758	
	Work Sink	1st Floor	1	EA	6	\$379	Drinking fountain
Classroom #116 (Kindergarten)							
	Casework	1st Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	1st Floor	1,220	SF	6	\$3,664	
	Chalk Board	1st Floor	50	LF	6	\$1,115	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,220	SF	6	\$1,221	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	50	SF	6	\$363	
	Walls - Concrete Block	1st Floor	1,060	SF	6	\$3,107	
	Walls - Plaster/Drywall	1st Floor	306	SF	6	\$845	
	Work Sink	1st Floor	2	EA	6	\$758	
	Work Sink	1st Floor	1	EA	6	\$379	Drinking fountain
Classroom #117 (Regular Classroom)							
	Casework	1st Floor	22	LF	6	\$556	
	Ceiling - Lay-in	1st Floor	450	SF	6	\$1,351	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	450	SF	6	\$450	
	Lighting - Lay-in	1st Floor	6	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	5	SF	6	\$36	
	Walls - Concrete Block	1st Floor	364	SF	6	\$1,067	
	Walls - Plaster/Drywall	1st Floor	364	SF	6	\$1,005	
Classroom #119 (Regular Classroom)							
	Casework	1st Floor	32	LF	6	\$808	
	Ceiling - Lay-in	1st Floor	450	SF	6	\$1,351	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #119 (Regular Classroom)							
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	450	SF	6	\$450	
	Lighting - Lay-in	1st Floor	6	EA	7	\$0	
	Storage/ Closet	1st Floor	5	SF	6	\$36	
	Walls - Concrete Block	1st Floor	364	SF	6	\$1,067	
	Walls - Plaster/Drywall	1st Floor	364	SF	6	\$1,005	
Classroom #213 (Regular Classroom)							
	Casework	2nd Floor	23	LF	6	\$581	
	Ceiling - Lay-in	2nd Floor	450	SF	6	\$1,351	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	450	SF	6	\$450	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	364	SF	6	\$1,067	
	Walls - Plaster/Drywall	2nd Floor	238	SF	6	\$657	
Classroom #214 (Regular Classroom)							
	Casework	2nd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	2nd Floor	9	SF	7	\$0	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	924	SF	6	\$2,709	
	Walls - Plaster/Drywall	2nd Floor	237	SF	6	\$654	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #215 (Regular Classroom)							
	Casework	2nd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	2nd Floor	925	SF	6	\$2,778	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #215 (Regular Classroom)							
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	925	SF	6	\$926	
	Lighting - Lay-in	2nd Floor	1	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	2nd Floor	474	SF	6	\$1,308	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #216 (Regular Classroom)							
	Casework	2nd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	2nd Floor	900	SF	6	\$2,703	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	2nd Floor	474	SF	6	\$1,308	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #217 (Regular Classroom)							
	Casework	2nd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	2nd Floor	900	SF	6	\$2,703	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	2nd Floor	474	SF	6	\$1,308	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #218 (Regular Classroom)							
	Casework	2nd Floor	40	LF	6	\$1,010	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #218 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	900	SF	6	\$2,703	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	474	SF	6	\$1,390	
	Walls - Plaster/Drywall	2nd Floor	699	SF	6	\$1,929	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #219 (Regular Classroom)							
	Casework	2nd Floor	22	LF	6	\$556	
	Ceiling - Lay-in	2nd Floor	450	SF	6	\$1,351	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	450	SF	6	\$450	
	Lighting - Lay-in	2nd Floor	6	EA	6	\$714	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	364	SF	6	\$1,067	
	Walls - Plaster/Drywall	2nd Floor	364	SF	6	\$1,005	
Classroom #220 (Regular Classroom)							
	Casework	2nd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	2nd Floor	900	SF	6	\$2,703	
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	900	SF	6	\$901	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	410	SF	6	\$1,202	
	Walls - Plaster/Drywall	2nd Floor	640	SF	6	\$1,766	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #221 (Regular Classroom)							
	Casework	2nd Floor	58	LF	6	\$1,465	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #221 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	1,034	SF	6	\$3,105	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,034	SF	6	\$1,035	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	637	SF	6	\$1,867	
	Walls - Plaster/Drywall	2nd Floor	637	SF	6	\$1,758	
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classroom #222A (Regular Classroom)							
	Casework	2nd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	2nd Floor	653	SF	6	\$1,961	
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	653	SF	6	\$1,391	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	374	SF	6	\$1,096	
	Walls - Plaster/Drywall	2nd Floor	1,024	SF	6	\$2,826	
Classroom #223 (Computer Lab)							
	Casework	2nd Floor	130	LF	6	\$3,283	
	Ceiling - Lay-in	2nd Floor	1,221	SF	6	\$3,667	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Charging Station	2nd Floor	4	EA	6	\$1,939	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,221	SF	6	\$1,222	
	Lighting - Lay-in	2nd Floor	16	EA	7	\$0	
	Storage/ Closet	2nd Floor	132	SF	6	\$957	
	Walls - Concrete Block	2nd Floor	703	SF	6	\$2,061	
	Walls - Plaster/Drywall	2nd Floor	703	SF	6	\$1,940	
	Wireless System	2nd Floor	1	EA	6	\$372	
Classroom #225 (Regular Classroom)							
	Casework	2nd Floor	20	LF	6	\$505	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #225 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	425	SF	6	\$1,276	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	425	SF	6	\$425	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	5	SF	6	\$36	
	Walls - Concrete Block	2nd Floor	602	SF	6	\$1,765	
Classroom #313 (Regular Classroom)							
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	398	SF	6	\$1,195	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	398	SF	6	\$398	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	22	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	331	SF	6	\$970	
	Walls - Plaster/Drywall	3rd Floor	243	SF	6	\$671	
Classroom #314/316 (Regular Classroom)							
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	918	SF	6	\$2,757	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Wood Doors inclu hw	3rd Floor	6	EA	6	\$1,806	
	Floor - Tile/Sheet	3rd Floor	918	SF	6	\$919	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	730	SF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	320	SF	6	\$883	
Classroom #315 (Regular Classroom)							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	925	SF	6	\$2,778	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	925	SF	6	\$926	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #315 (Regular Classroom)							
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	3rd Floor	494	SF	6	\$1,363	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #317 (Regular Classroom)							
	Casework	3rd Floor	26	LF	6	\$657	
	Ceiling - Lay-in	3rd Floor	880	SF	6	\$2,643	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	880	SF	6	\$881	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	3rd Floor	477	SF	6	\$1,316	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #318 (Regular Classroom)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	900	SF	6	\$901	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	410	SF	6	\$1,202	
	Walls - Plaster/Drywall	3rd Floor	699	SF	6	\$1,929	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #319 (Regular Classroom)							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	377	SF	6	\$1,132	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #319 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	377	SF	6	\$377	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	330	SF	6	\$967	
	Walls - Plaster/Drywall	3rd Floor	330	SF	6	\$911	
Classroom #320 (Regular Classroom)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	900	SF	6	\$901	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	410	SF	6	\$1,202	
	Walls - Plaster/Drywall	3rd Floor	699	SF	6	\$1,929	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #321 (Regular Classroom)							
	Casework	3rd Floor	45	LF	6	\$1,136	
	Ceiling - Lay-in	3rd Floor	1,034	SF	6	\$3,105	
	Chalk Board	3rd Floor	10	LF	4	\$918	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	1,034	SF	6	\$1,035	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	637	SF	6	\$1,867	
	Walls - Plaster/Drywall	3rd Floor	637	SF	6	\$1,758	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #322 (Regular Classroom)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #322 (Regular Classroom)							
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	900	SF	6	\$901	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	410	SF	6	\$1,202	
	Walls - Plaster/Drywall	3rd Floor	640	SF	6	\$1,766	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #323 (Regular Classroom)							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	465	SF	6	\$1,396	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	465	SF	6	\$465	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	22	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	366	SF	6	\$1,073	
	Walls - Plaster/Drywall	3rd Floor	264	SF	6	\$729	
Classroom #324 (Regular Classroom)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	900	SF	6	\$901	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	410	SF	6	\$1,202	
	Walls - Plaster/Drywall	3rd Floor	640	SF	6	\$1,766	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #325 (Regular Classroom)							
	Casework	3rd Floor	28	LF	6	\$707	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #325 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	925	SF	6	\$2,778	
	Chalk Board	3rd Floor	12	LF	6	\$268	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	925	SF	6	\$926	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	3rd Floor	494	SF	6	\$1,363	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #326 (Regular Classroom)							
	Casework	3rd Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	900	SF	6	\$901	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	474	SF	6	\$1,390	
	Walls - Plaster/Drywall	3rd Floor	699	SF	6	\$1,929	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #327 (Regular Classroom)							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	440	SF	6	\$1,321	
	Ceiling - Lay-in	3rd Floor	10	SF	5	\$80	Water damaged tiles
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	450	SF	6	\$450	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	364	SF	6	\$1,067	
	Walls - Plaster/Drywall	3rd Floor	243	SF	6	\$671	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #328 (Regular Classroom)							
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	
	Chalk Board	3rd Floor	12	LF	6	\$268	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	900	SF	6	\$901	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Storage/ Closet	3rd Floor	5	SF	6	\$36	
	Walls - Concrete Block	3rd Floor	699	SF	6	\$2,049	
	Walls - Plaster/Drywall	3rd Floor	474	SF	6	\$1,308	
	Work Sink	3rd Floor	1	EA	6	\$379	

Classrooms Subtotal:

\$331,939

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	3rd floor office next to staff restroom	175	SF	6	\$526	
	Doors - Wood Doors inclu hw	3rd floor office next to staff restroom	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd floor office next to staff restroom	175	SF	6	\$175	
	Lighting - Lay-in	3rd floor office next to staff restroom	3	EA	7	\$0	
	Power Distribution	3rd floor office next to staff restroom	4	EA	7	\$0	
	Walls - Concrete Block	3rd floor office next to staff restroom	653	SF	6	\$1,914	
	Ceiling - Lay-in	Faculty Room, 1st Floor	476	SF	6	\$1,429	
	Doors - Wood Doors inclu hw	Faculty Room, 1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	Faculty Room, 1st Floor	476	SF	6	\$476	
	Lighting - Lay-in	Faculty Room, 1st Floor	6	EA	7	\$0	
	Power Distribution	Faculty Room, 1st Floor	8	EA	7	\$0	
	Walls - Concrete Block	Faculty Room, 1st Floor	739	SF	6	\$2,166	
	Walls - Plaster/Drywall	Faculty Room, 1st Floor	336	SF	6	\$927	
	Work Sink	Faculty Room, 1st Floor	1	EA	6	\$508	
	Ceiling - Lay-in	Library office	149	SF	6	\$447	
	Doors - Transom Window	Library office	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	Library office	1	EA	6	\$301	
	Floor - Tile/Sheet	Library office	149	SF	6	\$149	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	Library office	3	EA	7	\$0	
	Power Distribution	Library office	8	EA	6	\$16,999	
	Storage/ Closet	Library office	68	SF	6	\$493	
	Walls - Concrete Block	Library office	170	SF	6	\$498	
	Walls - Plaster/Drywall	Library office	309	SF	6	\$853	
	Work Slnk	Library office	1	EA	6	\$508	
	Ceiling - Lay-in	Main Office	154,846	SF	6	\$465,003	
	Doors - Transom Window	Main Office	64	SF	6	\$1,084	
	Doors - Wood Doors inclu hw	Main Office	2	EA	6	\$602	
	Floor - Carpet	Main Office	615	SF	6	\$1,310	
	Floor - Terrazzo	Main Office	240	SF	6	\$525	
	Lighting - Lay-in	Main Office	13	EA	7	\$0	
	Power Distribution	Main Office	16	EA	7	\$0	
	Storage/ Closet	Main Office	23	SF	6	\$167	
	Walls - Concrete Block	Main Office	1,809	SF	6	\$5,303	
	Walls - Plaster/Drywall	Main Office	514	SF	6	\$1,419	
	Ceiling - Lay-in	Music room next to 2nd flr staff restroom	10	SF	5	\$80	Water damaged tiles
	Ceiling - Lay-in	Music room next to 2nd flr staff restroom	165	SF	6	\$495	
	Doors - Wood Doors inclu hw	Music room next to 2nd flr staff restroom	1	EA	6	\$301	
	Floor - Tile/Sheet	Music room next to 2nd flr staff restroom	175	SF	6	\$175	
	Lighting - Lay-in	Music room next to 2nd flr staff restroom	3	EA	7	\$0	
	Power Distribution	Music room next to 2nd flr staff restroom	4	EA	7	\$0	
	Walls - Concrete Block	Music room next to 2nd flr staff restroom	653	SF	6	\$1,914	
	Ceiling - Lay-in	Next to room 222A	64	SF	6	\$192	
	Doors - Wood Doors inclu hw	Next to room 222A	1	EA	6	\$301	
	Floor - Tile/Sheet	Next to room 222A	64	SF	6	\$64	
	Lighting - Lay-in	Next to room 222A	1	EA	7	\$0	
	Power Distribution	Next to room 222A	2	EA	7	\$0	
	Walls - Concrete Block	Next to room 222A	160	SF	6	\$469	
	Walls - Plaster/Drywall	Next to room 222A	160	SF	6	\$442	
	Ceiling - Lay-in	Office in room 221	175	SF	6	\$526	
	Doors - Wood Doors inclu hw	Office in room 221	1	EA	6	\$301	
	Floor - Tile/Sheet	Office in room 221	175	SF	6	\$175	
	Lighting - Lay-in	Office in room 221	2	EA	6	\$238	
	Power Distribution	Office in room 221	6	EA	7	\$0	
	Walls - Concrete Block	Office in room 221	368	SF	6	\$1,079	
	Walls - Plaster/Drywall	Office in room 221	176	SF	6	\$486	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	Principals office	311	SF	6	\$934	
	Doors - Transom Window	Principals office	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	Principals office	2	EA	6	\$602	
	Floor - Carpet	Principals office	311	SF	6	\$663	
	Lighting - Lay-in	Principals office	5	EA	7	\$0	
	Power Distribution	Principals office	16	EA	7	\$0	
	Walls - Concrete Block	Principals office	501	SF	6	\$1,469	
	Walls - Plaster/Drywall	Principals office	645	SF	6	\$1,780	
Library							
	Casework	Room 222	191	LF	6	\$4,823	
	Ceiling - Lay-in	Room 222	1,570	SF	6	\$4,715	
	Doors - Side-lite	Room 222	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	Room 222	1	EA	6	\$301	
	Floor - Carpet	Room 222	1,570	SF	6	\$3,345	
	Lighting - Lay-in	Room 222	18	EA	7	\$0	
	Walls - Concrete Block	Room 222	1,277	SF	6	\$3,744	
	Walls - Plaster/Drywall	Room 222	562	SF	6	\$1,551	
MDF_IDF							
	AC Unit	2nd Floor	1	EA	6	\$496	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Finishes	2nd Floor	148	SF	6	\$1,056	
	Ventilation and Cooling	2nd Floor	1	EA	6	\$1,855	
Mechanical/ Service Rooms							
	Interior Stairs	1st Floor	3	LF	6	\$27	Terazzo
	Janitor's Closet	1st Floor	28	SF	6	\$201	In boys restroom
	Mechanical/ Service Rooms	1st Floor	305	SF	6	\$2,185	West - Outside electrical room
	Mechanical/ Service Rooms	1st Floor	65	SF	6	\$466	Elevator Machine room
	Mechanical/ Service Rooms	1st Floor	170	SF	6	\$1,218	West - Outside pump room
	Mechanical/ Service Rooms	1st Floor	64	SF	6	\$459	Pipe chase In boys restroom ,JC
	Mechanical/ Service Rooms	1st Floor	22	SF	6	\$158	Electrical closet Across from room 122
	Vaults	1st Floor	221	SF	6	\$1,583	In main office
	Janitor's Closet	2nd Floor	28	SF	6	\$201	in boys restroom
	Mechanical/ Service Rooms	2nd Floor	64	SF	6	\$459	Pipe chase in boys restroom, JC
	Mechanical/ Service Rooms	2nd Floor	22	SF	6	\$158	Electrical closet across from 222A
	Mechanical/ Service Rooms	2nd Floor	12	SF	6	\$86	Electrical closet next to room 213
	Janitor's Closet	3rd Floor	28	SF	6	\$201	In boys restroom

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	3rd Floor	64	SF	6	\$459	Pipe chase in boys restroom, JC
	Mechanical/ Service Rooms	3rd Floor	12	SF	6	\$86	electrical closet next to room 313
	Mechanical/ Service Rooms	3rd Floor	22	SF	6	\$158	electrical closet across from room 322
	Mechanical/ Service Rooms	4th Floor	4,630	SF	6	\$33,171	All mechanicals for Addition 2, on 4th floor. Mechanical service room.
Restroom							
	Accessories	1st Floor Boy's Room	241	SF	6	\$2,223	
	Ceiling - Plaster/Drywall	1st Floor Boy's Room	241	SF	6	\$834	
	Floor Drain	1st Floor Boy's Room	2	EA	6	\$2,118	
	Floor - Terrazzo	1st Floor Boy's Room	241	SF	6	\$527	
	Hand Dryer	1st Floor Boy's Room	2	EA	6	\$460	
	Lavatory	1st Floor Boy's Room	3	EA	6	\$959	
	Lighting - Lay-in	1st Floor Boy's Room	6	EA	7	\$0	
	Partitions	1st Floor Boy's Room	3	EA	6	\$891	Structural glazed tile
	Urinals	1st Floor Boy's Room	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	1st Floor Boy's Room	995	SF	6	\$3,130	
	Water Closet	1st Floor Boy's Room	3	EA	6	\$1,008	
	Accessories	1st Floor Girl's Room	293	SF	6	\$2,702	
	Ceiling - Plaster/Drywall	1st Floor Girl's Room	293	SF	6	\$1,014	
	Floor Drain	1st Floor Girl's Room	2	EA	6	\$2,118	
	Floor - Terrazzo	1st Floor Girl's Room	293	SF	6	\$641	
	Hand Dryer	1st Floor Girl's Room	2	EA	6	\$460	
	Lavatory	1st Floor Girl's Room	3	EA	6	\$959	
	Lighting - Lay-in	1st Floor Girl's Room	6	EA	7	\$0	
	Partitions	1st Floor Girl's Room	5	EA	6	\$1,485	
	Walls - Structural Glazed Tile	1st Floor Girl's Room	1,155	SF	6	\$3,634	
	Water Closet	1st Floor Girl's Room	6	EA	6	\$2,016	
	Accessories	1st floor staff restroom	42	SF	6	\$387	
	Ceiling - Lay-in	1st floor staff restroom	42	SF	6	\$126	
	Doors - Wood Doors inclu hw	1st floor staff restroom	1	EA	6	\$301	
	Floor Drain	1st floor staff restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	1st floor staff restroom	42	SF	6	\$92	
	Lavatory	1st floor staff restroom	1	EA	6	\$320	
	Lighting - Lay-in	1st floor staff restroom	1	EA	7	\$0	
	Walls - Structural Glazed Tile	1st floor staff restroom	213	SF	6	\$670	
	Water Closet	1st floor staff restroom	1	EA	6	\$336	
	Accessories	2nd Floor Boy's Room	241	SF	6	\$2,223	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	2nd Floor Boy's Room	241	SF	6	\$834	
	Floor Drain	2nd Floor Boy's Room	2	EA	6	\$2,118	
	Floor - Terrazzo	2nd Floor Boy's Room	241	SF	6	\$527	
	Hand Dryer	2nd Floor Boy's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Boy's Room	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor Boy's Room	6	EA	7	\$0	
	Partitions	2nd Floor Boy's Room	3	EA	6	\$891	Structural glazed tile
	Urinals	2nd Floor Boy's Room	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	2nd Floor Boy's Room	995	SF	6	\$3,130	
	Water Closet	2nd Floor Boy's Room	3	EA	6	\$1,008	
	Accessories	2nd Floor Girl's Room	293	SF	6	\$2,702	
	Ceiling - Plaster/Drywall	2nd Floor Girl's Room	293	SF	6	\$1,014	
	Floor Drain	2nd Floor Girl's Room	2	EA	6	\$2,118	
	Floor - Terrazzo	2nd Floor Girl's Room	293	SF	6	\$641	
	Hand Dryer	2nd Floor Girl's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Girl's Room	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor Girl's Room	6	EA	7	\$0	
	Partitions	2nd Floor Girl's Room	5	EA	6	\$1,485	
	Walls - Structural Glazed Tile	2nd Floor Girl's Room	1,155	SF	6	\$3,634	
	Water Closet	2nd Floor Girl's Room	6	EA	6	\$2,016	
	Accessories	2nd floor staff restroom	42	SF	6	\$387	
	Ceiling - Lay-in	2nd floor staff restroom	42	SF	6	\$126	
	Doors - Wood Doors inclu hw	2nd floor staff restroom	1	EA	6	\$301	
	Floor Drain	2nd floor staff restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd floor staff restroom	42	SF	6	\$92	
	Lavatory	2nd floor staff restroom	1	EA	6	\$320	
	Lighting - Lay-in	2nd floor staff restroom	1	EA	7	\$0	
	Walls - Structural Glazed Tile	2nd floor staff restroom	213	SF	6	\$670	
	Water Closet	2nd floor staff restroom	1	EA	6	\$336	
	Accessories	3rd Floor Boy's Room	241	SF	6	\$2,223	
	Ceiling - Plaster/Drywall	3rd Floor Boy's Room	241	SF	6	\$834	
	Floor Drain	3rd Floor Boy's Room	2	EA	6	\$2,118	
	Floor - Terrazzo	3rd Floor Boy's Room	241	SF	6	\$527	
	Hand Dryer	3rd Floor Boy's Room	2	EA	6	\$460	
	Lavatory	3rd Floor Boy's Room	3	EA	6	\$959	
	Lighting - Lay-in	3rd Floor Boy's Room	6	EA	7	\$0	
	Partitions	3rd Floor Boy's Room	3	EA	6	\$891	Structural glazed tile

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Urinals	3rd Floor Boy's Room	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	3rd Floor Boy's Room	995	SF	6	\$3,130	
	Water Closet	3rd Floor Boy's Room	3	EA	6	\$1,008	
	Accessories	3rd Floor Girl's Restroom	293	SF	6	\$2,702	
	Ceiling - Plaster/Drywall	3rd Floor Girl's Restroom	293	SF	6	\$1,014	
	Floor Drain	3rd Floor Girl's Restroom	2	EA	6	\$2,118	
	Floor - Terrazzo	3rd Floor Girl's Restroom	293	SF	6	\$641	
	Hand Dryer	3rd Floor Girl's Restroom	2	EA	6	\$460	
	Lavatory	3rd Floor Girl's Restroom	3	EA	6	\$959	
	Lighting - Lay-in	3rd Floor Girl's Restroom	6	EA	7	\$0	
	Partitions	3rd Floor Girl's Restroom	5	EA	6	\$1,485	
	Walls - Structural Glazed Tile	3rd Floor Girl's Restroom	1,155	SF	6	\$3,634	
	Water Closet	3rd Floor Girl's Restroom	6	EA	6	\$2,016	
	Accessories	3rd floor staff restroom	42	SF	6	\$387	
	Ceiling - Lay-in	3rd floor staff restroom	42	SF	6	\$126	
	Doors - Wood Doors inclu hw	3rd floor staff restroom	1	EA	6	\$301	
	Floor Drain	3rd floor staff restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd floor staff restroom	42	SF	6	\$92	
	Lavatory	3rd floor staff restroom	1	EA	6	\$320	
	Lighting - Lay-in	3rd floor staff restroom	1	EA	7	\$0	
	Walls - Structural Glazed Tile	3rd floor staff restroom	213	SF	6	\$670	
	Water Closet	3rd floor staff restroom	1	EA	6	\$336	
	Accessories	In Room 110	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 110	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 110	1	EA	6	\$301	
	Floor Drain	In Room 110	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 110	36	SF	6	\$79	
	Lavatory	In Room 110	1	EA	6	\$320	
	Lighting - Lay-in	In Room 110	1	EA	6	\$119	
	Walls - Structural Glazed Tile	In Room 110	200	SF	6	\$629	
	Water Closet	In Room 110	1	EA	6	\$336	
	Accessories	In Room 111	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 111	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 111	1	EA	6	\$301	
	Floor Drain	In Room 111	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 111	36	SF	6	\$79	
	Lavatory	In Room 111	1	EA	6	\$320	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Lay-in	In Room 111	1	EA	6	\$119	
	Walls - Structural Glazed Tile	In Room 111	200	SF	6	\$629	
	Water Closet	In Room 111	1	EA	6	\$336	
	Accessories	In Room 112	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 112	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 112	1	EA	6	\$301	
	Floor Drain	In Room 112	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 112	36	SF	6	\$79	
	Lavatory	In Room 112	1	EA	6	\$320	
	Lighting - Lay-in	In Room 112	1	EA	7	\$0	
	Walls - Structural Glazed Tile	In Room 112	200	SF	6	\$629	
	Water Closet	In Room 112	1	EA	6	\$336	
	Accessories	In Room 113	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 113	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 113	1	EA	6	\$301	
	Floor Drain	In Room 113	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 113	36	SF	6	\$79	
	Lavatory	In Room 113	1	EA	6	\$320	
	Lighting - Lay-in	In Room 113	1	EA	7	\$0	
	Walls - Structural Glazed Tile	In Room 113	200	SF	6	\$629	
	Water Closet	In Room 113	1	EA	6	\$336	
	Accessories	In Room 114	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 114	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 114	1	EA	6	\$301	
	Floor Drain	In Room 114	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 114	36	SF	6	\$79	
	Lavatory	In Room 114	1	EA	6	\$320	
	Lighting - Lay-in	In Room 114	1	EA	7	\$0	
	Walls - Structural Glazed Tile	In Room 114	200	SF	6	\$629	
	Water Closet	In Room 114	1	EA	6	\$336	
	Accessories	In Room 115	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 115	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 115	1	EA	6	\$301	
	Floor Drain	In Room 115	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 115	36	SF	6	\$79	
	Lavatory	In Room 115	1	EA	6	\$320	
	Lighting - Lay-in	In Room 115	1	EA	7	\$0	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Structural Glazed Tile	In Room 115	200	SF	6	\$629	
	Water Closet	In Room 115	1	EA	6	\$336	
	Accessories	In Room 116	36	SF	6	\$332	
	Ceiling - Lay-in	In Room 116	36	SF	6	\$108	
	Doors - Wood Doors inclu hw	In Room 116	1	EA	6	\$301	
	Floor Drain	In Room 116	1	EA	6	\$1,059	
	Floor - Terrazzo	In Room 116	36	SF	6	\$79	
	Lavatory	In Room 116	1	EA	6	\$320	
	Lighting - Lay-in	In Room 116	1	EA	7	\$0	
	Walls - Structural Glazed Tile	In Room 116	200	SF	6	\$629	
	Water Closet	In Room 116	1	EA	6	\$336	
	Accessories	Main office restroom	42	SF	6	\$387	
	Ceiling - Lay-in	Main office restroom	42	SF	6	\$126	
	Doors - Wood Doors inclu hw	Main office restroom	1	EA	6	\$301	
	Floor Drain	Main office restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	Main office restroom	53	SF	6	\$116	
	Lavatory	Main office restroom	1	EA	6	\$320	
	Lighting - Lay-in	Main office restroom	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Main office restroom	233	SF	6	\$733	
	Water Closet	Main office restroom	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$701,369

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	7,097	SF	6	\$21,312	
	Ceiling - Plaster/Drywall	1st Floor	60	SF	6	\$372	
	Doors - Steel Doors incl hw	1st Floor	13	EA	6	\$3,913	
	Doors - Store Front	1st Floor	2	EA	6	\$2,416	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	
	Floor - Terrazzo	1st Floor	7,097	SF	6	\$59,573	
	Lighting - Lay-in	1st Floor	143	EA	7	\$0	
	Stairs - Terrazzo	1st Floor	3	LF	6	\$28	
	Walls - Concrete Block	1st Floor	11,684	SF	6	\$34,252	Brick
	Ceiling - Lay-in	2nd Floor	5,647	SF	6	\$16,958	

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Doors - Steel Doors incl hw	2nd Floor	10	EA	6	\$3,010	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Terrazzo	2nd Floor	5,647	SF	6	\$47,401	
	Lighting - Lay-in	2nd Floor	120	EA	7	\$0	
	Walls - Structural Glazed Tile	2nd Floor	7,636	SF	6	\$24,023	
	Ceiling - Lay-in	3rd Floor	5,647	SF	6	\$16,958	
	Doors - Steel Doors incl hw	3rd Floor	10	EA	6	\$3,010	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	6	\$551	
	Floor - Terrazzo	3rd Floor	5,647	SF	6	\$47,401	
	Lighting - Lay-in	3rd Floor	120	EA	7	\$0	
	Walls - Structural Glazed Tile	3rd Floor	7,636	SF	6	\$24,023	Brick
Stairs							
	Ceiling - Exposed	Stairwell #1	72	SF	6	\$107	
	Ceiling - Lay-in	Stairwell #1	480	SF	6	\$1,441	
	Floor - Terrazzo	Stairwell #1	373	SF	6	\$3,131	
	Handrails	Stairwell #1	130	LF	6	\$1,127	
	Lighting - Lay-in	Stairwell #1	8	EA	7	\$0	
	Lighting - Wall Mounted	Stairwell #1	2	EA	7	\$0	
	Stairs - Terrazzo	Stairwell #1	54	LF	6	\$501	
	Walls - Structural Glazed Tile	Stairwell #1	1,874	SF	6	\$5,896	
	Ceiling - Exposed	Stairwell #2	368	SF	6	\$547	
	Ceiling - Lay-in	Stairwell #2	341	SF	6	\$1,024	
	Floor - Terrazzo	Stairwell #2	455	SF	6	\$3,819	
	Handrails	Stairwell #2	162	LF	6	\$1,404	
	Lighting - Lay-in	Stairwell #2	6	EA	7	\$0	
	Lighting - Pendent/Surface	Stairwell #2	1	EA	7	\$0	
	Lighting - Wall Mounted	Stairwell #2	4	EA	7	\$0	
	Stairs - Terrazzo	Stairwell #2	77	LF	6	\$715	
	Walls - Plaster/Drywall	Stairwell #2	45	SF	6	\$124	
	Walls - Structural Glazed Tile	Stairwell #2	4,070	SF	6	\$12,804	
	Ceiling - Lay-in	Stairwell #3	480	SF	6	\$1,441	
	Floor - Terrazzo	Stairwell #3	373	SF	6	\$3,131	
	Handrails	Stairwell #3	130	LF	6	\$1,127	
	Lighting - Lay-in	Stairwell #3	8	EA	7	\$0	
	Lighting - Wall Mounted	Stairwell #3	2	EA	7	\$0	
	Stairs - Terrazzo	Stairwell #3	54	LF	6	\$501	
	Walls - Structural Glazed Tile	Stairwell #3	1,874	SF	6	\$5,896	

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
Vertical Conveyance							
	Elevator - Hydraulic Elevator	Entire Building	1	EA	6	\$19,238	

Building Interior Subtotal: \$370,278

Total Building Cost \$2,364,113

Building: Gymnasium

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Steel Door	Entrance 13-East / Kitchen	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 14-SE	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 15A-South / Inner court	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 15-South	2	EA	6	\$961	
	Exterior Doors - Side lite	Entrance 14-SE	2	EA	7	\$0	
	Exterior Doors - Side lite	Entrance 15A-South / Inner court	2	EA	7	\$0	
	Exterior Doors - Side lite	Entrance 15-South	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 14-SE	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 15A-South / Inner court	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 15-South	2	EA	7	\$0	
	Exterior Stairs - Concrete	Entrance 14-SE	30	LF	7	\$0	
	Stair Handrail - Steel_Stair Handrail	Entrance 14-SE	25	LF	7	\$0	
Foundation							
	Foundation - Concrete	Entire Building	244	LF	7	\$0	
	Superstructure - Steel	Entire Building	5,637	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	6	EA	6	\$1,732	
Roof System							
	Coping - Stone	Roof 6	260	LF	7	\$0	
	Downspouts - Exterior Downspouts	Roof 6	135	LF	6	\$4,486	
	Downspouts - Interior Downspouts	Roof 6	88	LF	6	\$2,925	
	Parapet - Parapet < 16" Height	Roof 6	260	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 6	5,637	SF	7	\$0	

Building: Gymnasium

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Roof - Metal	Roof 6	1,920	SF	7	\$0	
	Roof - Modified Bitumen	Roof 6	3,717	SF	7	\$0	
Walls							
	Exterior Walls - Brick	Entire Building	6,336	SF	7	\$0	
	Exterior Walls - Stone-Cast	Entire Building	244	SF	6	\$1,640	
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	413	SF	6	\$4,630	
	Lintels - Steel	Entire Building	98	LF	7	\$0	
	Windows - Decorative	Entire Building	755	SF	6	\$5,636	
Building Exterior Subtotal:						\$24,894	

Building: Gymnasium

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Corridors and Stairs	Entire Building	758	SF	7	\$0	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	1,646	SF	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	2	EA	2	\$1,091	No battery back-up or generator.
	Exit Signs - Gym	Entire Building	2	EA	2	\$1,157	Lights out. No battery back-up or generator.
	Security System - Intrusion Detection	Entire Building	5,637	SF	6	\$1,451	
Main Service							
	PA System	Entire Building	5,637	SF	7	\$0	Serves main and all additions. Control console located in Addition 2.
Electrical System Subtotal:						\$3,698	

Building: Gymnasium

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	5,637	SF	6	\$2,015	
	Fire Alarm_System	Entire Building	5,637	SF	5	\$6,288	Panel located in Addition 2.

Building: Gymnasium

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Sprinkler System							
	Sprinkler Heads	Entire Building	5,637	SF	7	\$0	
	Sprinkler Piping	Entire Building	5,637	SF	7	\$0	
	Wet Sprinkler System	Entire Building	5,637	SF	7	\$0	Served from Addition 2

Safty System Subtotal:

\$8,303

Building: Gymnasium

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Roof Top Unit-Single Zone-Roof Mounted- DX Cooling Only with Self Contained Compressor - 21 - 30 tons	Roof	1	EA	5	\$25,152	Heating is not working. Parts need to be ordered
Temperature Control							
	DDC System	Entire Building	5,637	SF	7	\$0	Served from Addition 2
	Thermostats - DDC	Entire Building	1	EA	7	\$0	
Ventilation							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	1	EA	6	\$592	

Mechanical System Subtotal:

\$25,744

Building: Gymnasium

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Storm Piping	Entire Building	5,637	SF	7	\$0	

Plumbing System Subtotal:

\$0

Building: Gymnasium

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	103A, Gym Teacher's Office	189	SF	6	\$568	
	Doors - Steel Doors incl hw	103A, Gym Teacher's Office	1	EA	6	\$301	
	Floor - Tile/Sheet	103A, Gym Teacher's Office	189	SF	6	\$189	

Building: Gymnasium

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	103A, Gym Teacher's Office	2	EA	6	\$238	
	Power Distribution	103A, Gym Teacher's Office	6	EA	7	\$0	
	Walls - Concrete Block	103A, Gym Teacher's Office	451	SF	6	\$1,322	
	Ceiling - Lay-in	Faculty Lounge	273	SF	6	\$820	
	Floor - Tile/Sheet	Faculty Lounge	273	SF	6	\$273	
	Lighting - Lay-in	Faculty Lounge	2	EA	6	\$238	
	Power Distribution	Faculty Lounge	6	EA	7	\$0	
	Walls - Concrete Block	Faculty Lounge	614	SF	6	\$1,800	
	Ceiling - Lay-in	Parent's Room	252	SF	6	\$757	
	Doors - Wood Doors inclu hw	Parent's Room	1	EA	6	\$301	
	Floor - Tile/Sheet	Parent's Room	252	SF	6	\$252	
	Lighting - Lay-in	Parent's Room	2	EA	6	\$238	
	Power Distribution	Parent's Room	8	EA	7	\$0	
	Walls - Plaster/Drywall	Parent's Room	655	SF	6	\$1,808	
Gymnasia							
	Ceiling - Exposed	1st Floor	1,646	SF	6	\$2,448	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Sport Flooring	1st Floor	1,646	SF	6	\$3,554	Rubber Floor
	Lighting - Pendent/Surface	1st Floor	10	EA	6	\$1,239	
	Sound System	1st Floor	1	EA	6	\$41,654	
	Walls - Concrete Block	1st Floor	5,244	SF	6	\$15,373	
Restroom							
	Accessories	Boy Toilet Across from Parent's Room	37	SF	6	\$341	
	Ceiling - Plaster/Drywall	Boy Toilet Across from Parent's Room	37	SF	6	\$128	
	Doors - Wood Doors inclu hw	Boy Toilet Across from Parent's Room	1	EA	6	\$301	
	Floor Drain	Boy Toilet Across from Parent's Room	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	Boy Toilet Across from Parent's Room	37	SF	6	\$20	
	Lavatory	Boy Toilet Across from Parent's Room	1	EA	6	\$320	
	Lighting - Lay-in	Boy Toilet Across from Parent's Room	1	EA	6	\$119	
	Walls - Concrete Block	Boy Toilet Across from Parent's Room	112	SF	6	\$328	
	Water Closet	Boy Toilet Across from Parent's Room	1	EA	6	\$336	
	Accessories	Girl Toilet Across from Parent's Room	47	SF	6	\$434	
	Ceiling - Plaster/Drywall	Girl Toilet Across from Parent's Room	47	SF	6	\$163	
	Doors - Steel Doors incl hw	Girl Toilet Across from Parent's Room	1	EA	6	\$301	
	Floor Drain	Girl Toilet Across from Parent's Room	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	Girl Toilet Across from Parent's Room	47	SF	6	\$25	

Building: Gymnasium

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	Girl Toilet Across from Parent's Room	1	EA	6	\$320	
	Lighting - Lay-in	Girl Toilet Across from Parent's Room	1	EA	6	\$119	
	Walls - Concrete Block	Girl Toilet Across from Parent's Room	122	SF	6	\$358	
	Water Closet	Girl Toilet Across from Parent's Room	1	EA	6	\$336	
	Accessories	Unisex Toilet	47	SF	6	\$434	
	Ceiling - Plaster/Drywall	Unisex Toilet	47	SF	6	\$163	
	Doors - Steel Doors incl hw	Unisex Toilet	1	EA	6	\$301	
	Floor Drain	Unisex Toilet	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	Unisex Toilet	47	SF	6	\$25	
	Lavatory	Unisex Toilet	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Toilet	1	EA	6	\$119	
	Walls - Concrete Block	Unisex Toilet	122	SF	6	\$358	
	Water Closet	Unisex Toilet	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$83,153

Building: Gymnasium

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	758	SF	6	\$2,276	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Floor - Tile/Sheet	1st Floor	758	SF	6	\$412	
	Lighting - Lay-in	1st Floor	8	EA	6	\$952	
	Student Lockers - Two Tiers	1st Floor	12	EA	6	\$557	
	Walls - Concrete Block	1st Floor	1,365	SF	6	\$4,001	

Building Interior Subtotal:

\$9,402

Total Building Cost

\$155,194

Building: Lunch room/Kitchen

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Lunch room/Kitchen

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Exterior Steel Door	Entrance 8A-NE / Outside Yard Storage	2	EA	5	\$2,683	Bottoms of doors and frame rusting, corroding with holes - not working properly
	Exterior Doors - Exterior Steel Door	Exit 10-NE / Lunchroom	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Exit 11-East / Lunchroom	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Exit 12-East	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Exit 9-SW / Lunchroom	2	EA	6	\$961	
	Exterior Stairs - Concrete	Exit 12-East	25	LF	7	\$0	
	Ramp Handrail - Steel_Ramp Handrail	Exit 10-NE / Lunchroom	115	LF	6	\$997	Rusting and peeling throughout
	Ramp Handrail - Steel_Ramp Handrail	Exit 11-East / Lunchroom	140	LF	7	\$0	
	Ramp Handrail - Steel_Ramp Handrail	Exit 9-SW / Lunchroom	40	LF	7	\$0	
	Ramps - Concrete	Exit 10-NE / Lunchroom	55	LF	7	\$0	
	Ramps - Concrete	Exit 11-East / Lunchroom	55	LF	7	\$0	
	Ramps - Concrete	Exit 9-SW / Lunchroom	10	LF	7	\$0	
	Stair Handrail - Steel_Stair Handrail	Exit 12-East	12	LF	6	\$104	
Foundation							
	Foundation - Concrete	Entire Building	338	LF	7	\$0	
	Superstructure - Steel	Entire Building	9,359	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	10	EA	6	\$2,887	
Roof System							
	Chimney - Metal Flue	Roof 5	30	LF	6	\$4,744	
	Coping - Stone	Roof 5	380	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 5	150	LF	6	\$4,985	
	Parapet - 16" - 30" Height	Roof 5	380	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 5	9,359	SF	7	\$0	
	Roof - Modified Bitumen	Roof 5	9,359	SF	7	\$0	
Walls							
	Cheek-Wall - Concrete	Entire Building	570	SF	7	\$0	
	Exterior Walls - Brick	Entire Building	8,630	SF	7	\$0	
	Exterior Walls - Brick	Entire Building	550	SF	7	\$0	
	Exterior Walls - Stone-Cast	Entire Building	2,704	SF	6	\$18,174	
Windows							
	Clerestory - Glass Double-Pane	Entire Building	336	SF	7	\$0	
	Lintels - Steel	Entire Building	64	LF	7	\$0	
	Windows - Louver	Entire Building	80	SF	7	\$0	

Building: Lunch room/Kitchen

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Windows							

Building Exterior Subtotal:

\$37,457

Building: Lunch room/Kitchen

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							

	Emergency A/C Power - Corridors and Stairs	Entire Building	1,341	SF	6	\$403	
	Emergency A/C Power - Lunchrooms	Entire Building	5,733	SF	6	\$2,132	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	2	EA	6	\$405	
	Emergency Battery Packs - Lunchrooms	Entire Building	5	EA	6	\$1,013	
	Exit Signs - Corridors and Stairs	Entire Building / 1st Floor	1	EA	2	\$545	No battery back-up or generator.
	Exit Signs - Lunchroom	Entire Building / 1st Floor	6	EA	2	\$3,273	No battery back-up or generator.
	Security System - Intrusion Detection	Entire Building	9,359	SF	6	\$2,409	

Main Service

	PA System	Entire Building	9,359	SF	7	\$0	Serves main and all additions. Control console located in Addition 2.
--	-----------	-----------------	-------	----	---	-----	---

Power Distribution

	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building	1	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	7	\$0	

Electrical System Subtotal:

\$10,179

Building: Lunch room/Kitchen

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							

	Fire Alarm Strobe Lights	Entire Building	9,359	SF	6	\$3,346	
	Fire Alarm_System	Entire Building	9,359	SF	5	\$10,439	Panel located in Addition 2.

Sprinkler System

	Sprinkler Heads	Entire Building	9,359	SF	7	\$0	
	Sprinkler Piping	Entire Building	9,359	SF	7	\$0	
	Wet Sprinkler System	Entire Building	9,359	SF	7	\$0	Fire pump located in Addition 2.

Building: Lunch room/Kitchen

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Sprinkler System							

Safty System Subtotal:

\$13,785

Building: Lunch room/Kitchen

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							

Pipes - Chilled Water Pipe- Steel	Entire Building	100	LF	6	\$189	Chiller located in Addition 2.
-----------------------------------	-----------------	-----	----	---	-------	--------------------------------

Air Handling Systems

Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	5	\$48,592	Coils have multiple leaks fixed.
Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
Auxiliaries - 12001-20000 cfm	Mechanical Room	1	EA	5	\$0	Coils have multiple leaks fixed.
Fan Power Box - Fan Power Box with Hot Water Coil	Kitchen / Lunch room / Mechanical Room	4	EA	5	\$6,302	Serves Lunch room
Fan Power Box - Fan Power Box with Hot Water Coil	Kitchen / Lunch room / Mechanical Room	5	EA	5	\$7,878	Serves Kitchen
Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	Mechanical Room	1	EA	6	\$1,857	
Make Up Air Unit- Roof Mounted- Gas Heating - Less than 6000 cfm	Roof	1	EA	4	\$51,634	Does not work or has been disconnected

Heating Devices

Cabinet Heaters - With Hot Water Coil	Entire Building	2	EA	7	\$0	
Unit Heater - Electric	Mechanical Room	1	EA	6	\$278	
Unit Heater - Hot Water	Mechanical Room	2	EA	7	\$0	

Mechanical Plumbing

Hydronic Supply and Return - Copper	Entire Building	150	LF	7	\$0	Boilers located in Addition 2.
Hydronic Supply and Return - Steel	Entire Building	100	LF	7	\$0	Boilers located in Addition 2.

Temperature Control

DDC System	Entire Building	9,359	SF	7	\$0	Served from Addition 2
Thermostats - DDC	Entire Building	9	EA	7	\$0	

Ventilation

Exhaust Fans- Indoor - 1501 - 8000 CFM	Entire Building / Mechanical Room	1	EA	6	\$592	
Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	6	\$592	
Roof Mounted Duct Work	Entire Building / Roof	10	LF	6	\$3,790	
Type I Exhaust Hood- Kitchen	Entire Building	2	EA	6	\$2,495	
Type II Exhaust Hood- Warming Kitchen	Entire Building	2	EA	6	\$1,840	Cleaning and testing is needed.

Building: Lunch room/Kitchen

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical System Subtotal:						\$126,041	

Building: Lunch room/Kitchen

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Electric Heater - Greater than 50 KW	Dish Washer Area / 1st Floor	1	EA	5	\$2,652	Does not heat up any longer and leaks. Out of service since 2010
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	2	EA	5	\$4,498	Nearing end of useful life.
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	9,359	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	9,359	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	9,359	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	9,359	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	9,359	SF	7	\$0	
	Sanitary Piping	Entire Building	9,359	SF	7	\$0	
	Storm Piping	Entire Building	9,359	SF	7	\$0	
	Vent Piping	Entire Building	9,359	SF	7	\$0	
Plumbing System Subtotal:						\$7,150	

Building: Lunch room/Kitchen

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	Kitchen Manager's Office	66	SF	6	\$198	
	Doors - Steel Doors incl hw	Kitchen Manager's Office	1	EA	6	\$301	
	Floor - Concrete	Kitchen Manager's Office	66	SF	6	\$35	
	Lighting - Lay-in	Kitchen Manager's Office	1	EA	6	\$119	
	Power Distribution	Kitchen Manager's Office	6	EA	7	\$0	
	Walls - Concrete Block	Kitchen Manager's Office	243	SF	6	\$712	
Kitchen							
	Ceiling - Lay-in	1st Floor	407	SF	6	\$1,222	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	407	SF	6	\$215	
	Lighting - Lay-in	1st Floor	5	EA	6	\$595	

Building: Lunch room/Kitchen

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Kitchen							
	Walls - Concrete Block	1st Floor	649	SF	6	\$1,903	
	Ceiling - Lay-in	Dishwash	178	SF	6	\$535	
	Doors - Steel Doors incl hw	Dishwash	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Dishwash	178	SF	6	\$94	
	Lighting - Lay-in	Dishwash	2	EA	6	\$238	
	Walls - Concrete Block	Dishwash	338	SF	6	\$991	
	Ceiling - Lay-in	Servery Line	893	SF	6	\$2,682	
	Doors - Steel Doors incl hw	Servery Line	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	Servery Line	893	SF	6	\$472	
	Lighting - Lay-in	Servery Line	13	EA	6	\$1,547	
	Serving Line	Servery Line	60	LF	6	\$3,571	
	Walls - Concrete Block	Servery Line	1,696	SF	6	\$4,972	
Locker/Shower Room							
	Accessories	In Kitchen Area	75	SF	6	\$294	
	Ceiling - Lay-In	In Kitchen Area	75	SF	6	\$225	
	Doors - Wood Doors inclu hw	In Kitchen Area	1	EA	6	\$301	
	Floor - Concrete	In Kitchen Area	75	SF	6	\$40	
	Lavatory	In Kitchen Area	1	EA	6	\$320	
	Lighting - Lay-in	In Kitchen Area	1	EA	6	\$119	
	Student Lockers - One Tier	In Kitchen Area	9	EA	6	\$836	
	Walls - Concrete Block	In Kitchen Area	345	SF	6	\$1,011	
	Water Closet	In Kitchen Area	1	EA	6	\$336	
Lunch & Multipurpose Room							
	Ceiling - Exposed	1st Floor	5,733	SF	6	\$8,526	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	1st Floor	5,733	SF	6	\$3,033	Concrete
	Lighting - Chandelier, Incandescent	1st Floor	3	EA	6	\$1,433	
	Lighting - Lay-in	1st Floor	21	EA	6	\$2,498	
	Lighting - Pendent/Surface	1st Floor	17	EA	6	\$2,106	
	Serving Line	1st Floor	45	LF	6	\$2,678	
	Walls - Concrete Block	1st Floor	8,902	SF	6	\$26,096	

Rooms (Other Than Classrooms) Subtotal:

\$72,060

Building: Lunch room/Kitchen

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	1,341	SF	6	\$4,027	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	1st Floor	1,341	SF	6	\$652	
	Lighting - Lay-in	1st Floor	11	EA	6	\$1,309	
	Walls - Concrete Block	1st Floor	1,829	SF	6	\$5,362	

Building Interior Subtotal: \$11,650

Total Building Cost \$278,322

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	9	EA	6	\$9,845	
	Civil/ Drainage - Site Manhole	Entire Site	6	EA	7	\$0	

Fencing

	Fencing - Guard Rail	Entire Site	110	LF	6	\$1,271	East - trash compactor enclosure
	Fencing - New Standard Ornamental	Entire Site	1,441	LF	6	\$45,973	
	Fencing - New Standard Ornamental	Entire Site	20	LF	5	\$2,848	SE - Sections damaged, bent near entrance 13

Landscape

	Benches	Entire Site	15	EA	6	\$6,451	
	Landscape - Grass	Entire Site	10,827	SF	6	\$8,980	
	Landscape - Hardscape- Asphalt	Entire Site	23,003	SF	7	\$0	
	Landscape - Hardscape- Concrete	Entire Site	500	SF	5	\$6,378	Several areas in between perimeter sidewalk and main entrance 1 cracked, chipped, spalling with loose pieces throughout
	Landscape - Hardscape- Concrete	Entire Site	13,441	SF	7	\$0	
	Lighting - Pole Mounted	Entire Site	2	EA	6	\$2,167	Spotlights at Masonry Monument Sign
	Parkway trees	Entire Site	36	EA	6	\$23,762	
	Planting Beds/ Area	Entire Site	5,364	SF	6	\$8,821	
	Retaining Wall - Concrete	Entire Site	600	SF	6	\$14,063	Entrance 6, 7 / SE - In between alley
	Retaining Wall - Masonry	Entire Site	6	SF	5	\$350	South - Main Entrance 1 - Sections of stone paver wall loose, missing
	Retaining Wall - Masonry	Entire Site	54	SF	6	\$788	South - Main Entrance 1 - Stone paver
	Trash Receptacles	Entire Site	1	EA	6	\$312	

Parking Lot

	Concrete Curbs	NW	635	LF	7	\$0	
--	----------------	----	-----	----	---	-----	--

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Parking Lot							
	Interior Plantings	NW	60	LF	6	\$2,553	
	Lighting - Pole Mounted	NW	4	EA	6	\$5,810	
	Surface - Asphalt	NW	17,951	SF	6	\$43,382	
	Surface - Asphalt	South - Main Entrance 1	2,050	SF	6	\$4,954	Cracking throughout
	Surface - Concrete	NW	7,516	SF	7	\$0	
	Trash Compactor	NW / East	1	EA	6	\$0	East side of lunchroom addition
	Trash Enclosure - Masonry	NW / North East	2,860	SF	6	\$112,838	
	Vehicular Screening	NW	375	LF	6	\$29,526	
Playground							
	Equipment - Pre K 3-5	Entire Site	1	EA	6	\$3,546	
	Surface - Square Rubber Mats	Entire Site	2,150	SF	6	\$11,591	
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	1,122	LF	6	\$13,477	
	Sidewalks - Perimeter Sidewalks	Entire Site	20	SF	5	\$191	SE - Area cracked, sinking with gaps
	Sidewalks - Perimeter Sidewalks	Entire Site	13,729	SF	6	\$27,289	
Signage							
	Flag Pole - Building Mounted Flag Pole	Entire Site	1	EA	6	\$828	NW - In between entrances 7, 8 - No flag
	Flag Pole - Flag Pole	Entire Site	1	EA	7	\$0	South - Main Entrance 1
	Marquee - Building Mounted Back Lighted w/ LED	Entire Site / South Façade	1	EA	6	\$0	
	Marquee - Free Standing Back Lighted	Entire Site / North West	1	EA	6	\$0	
	Monument - Sign	Entire Site	1	EA	6	\$0	Location: Main Entrance 1-S - Wall mounted
	Monument - Sign	Entire Site	1	EA	7	\$0	Location: Main Entrance 1-S - Masonry

Site Subtotal: **\$387,994**

Total Site Cost **\$387,994**

Campus Total ^{2 3} **\$6,475,163**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
 - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Library	1st Floor	100	100	915	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	101	101	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	102	102	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	103	103	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	104	104	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Kindergarten	1st Floor	105	105	915	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	200	NA	415	1	0	8	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	202	202	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	203	203	815	1	1	15	120	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	204	204	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	205	205	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	206	206	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	207	207	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	208	208	815	1	3	16	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	209	209	815	1	0	10	132	66	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	210	210	533	1	3	12	88	44	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	300	NA	417	1	1	8	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	815	1	1	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	302	302	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	303	303	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	304	304	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	305	305	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	306	306	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	307	307	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	308	308	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	309	309	815	1	0	10	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	310	310	533	1	0	8	88	44	40	N	Y	Y
Regular Classroom	Office	3rd Floor	311	Adj. Room	415	1	0	8	66	33	50	N	Y	N

Addition 2														
Computer Lab	Regular Classroom	2nd Floor	223	NA	1,221	1	40	50	176	88	50	N	Y	Y
Kindergarten	Kindergarten	1st Floor	112	NA	1,220	1	4	20	232	116	50	N	Y	N
Kindergarten	Kindergarten	1st Floor	114	NA	1,220	1	4	20	232	116	50	N	Y	N
Kindergarten	Pre School	1st Floor	115	NA	1,172	1	4	12	176	88	50	N	N	N
Kindergarten	Kindergarten	1st Floor	116	NA	1,220	1	4	20	232	116	50	N	Y	N
Pre School	Pre School	1st Floor	110	NA	1,220	1	4	20	232	116	50	N	Y	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Addition 2														
Pre School	Pre School	1st Floor	111	NA	1,172	1	4	12	176	88	50	N	N	N
Pre School	Pre School	1st Floor	113	NA	1,172	1	4	12	176	88	50	N	N	N
Regular Classroom	Regular Classroom	1st Floor	117	NA	450	1	3	10	66	33	50	N	N	N
Regular Classroom	Regular Classroom	1st Floor	119	NA	450	1	3	10	66	33	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	213	NA	450	1	2	6	66	33	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	214	NA	900	1	4	20	132	66	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	215	NA	925	1	2	10	132	66	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	216	NA	900	1	4	20	132	66	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	217	NA	900	1	2	6	66	33	50	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	218	NA	900	1	4	20	132	66	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	219	NA	450	1	2	6	66	33	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	220	NA	900	1	4	20	132	66	50	N	Y	N
Regular Classroom	Art Room	2nd Floor	221	NA	1,034	1	2	10	154	77	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	222A	NA	653	1	2	10	132	66	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	225	N/A	425	1	3	10	66	33	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	313	NA	398	1	1	10	66	33	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	314/316	NA	918	1	4	20	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	315	NA	925	1	2	10	132	66	50	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	317	NA	880	1	2	12	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	318	NA	900	1	4	20	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	319	NA	377	1	2	10	66	33	50	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	320	NA	900	1	4	20	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	321	NA	1,034	1	2	10	154	77	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	322	NA	900	1	4	20	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	323	NA	465	1	2	6	44	22	50	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	324	NA	900	1	4	20	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	325	NA	925	1	2	10	132	66	50	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	326	NA	900	1	4	20	132	66	50	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	327	NA	450	1	2	6	66	33	50	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	328	NA	900	1	4	20	132	66	50	N	Y	N