

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	2000	3	102,700	\$4,190,725
SITE				\$411,485
Campus Total			102,700	\$4,602,210

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio	#2- SE / South East	1	EA	6	\$497	
	Entrance Control - Audio and Video	#1- Main Accessible- E / East	1	EA	6	\$702	
	Entrance Control - Audio and Video	#5- W	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	#3- S / South	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#3.5- SW / South West	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#4- SW	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#5- W	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	#6- NW / North West	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#7- NE / North East	2	EA	6	\$961	
	Exterior Doors - Side lite	#1- Main Accessible- E / East	4	EA	6	\$1,253	
	Exterior Doors - Store Front	#1- Main Accessible- E / East	4	EA	6	\$2,184	
	Exterior Doors - Store Front	#2- SE / South East	3	EA	6	\$1,638	
	Exterior Doors - Store Front	#8- NE / North East	3	EA	6	\$1,638	
	Exterior Doors - Transom Lite	#1- Main Accessible- E / East	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#2- SE / South East	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#5- W	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#8- NE / North East	3	EA	6	\$940	
	Power Door Operator and Controls	#1- Main Accessible- E / East	2	EA	6	\$0	
	Power Door Operator and Controls	#5- W	1	EA	6	\$0	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Foundation							
	Foundation - Concrete	Entire Building	10	LF	5	\$5,519	gap at wall to sidewalk abutment is allowing for foundation movement resulting in wall cracks.
	Foundation - Concrete	Entire Building	1,181	LF	7	\$0	
	Superstructure - Steel	Entire Building	98,739	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	23	EA	6	\$6,641	
Roof System							
	Chimney - Metal Flue	Mid N roof	38	LF	6	\$6,009	
	Chimney - Metal Flue	Mid N roof	38	LF	6	\$6,009	
	Coping - Stone	Low E roof	279	LF	5	\$30,553	some open joints and starting to spall
	Coping - Stone	Main upper roof	810	LF	5	\$88,703	starting to show signs of spalling at surface, open joints
	Coping - Stone	Mid N roof	261	LF	5	\$28,582	starting to spall, some open joints
	Coping - Stone	Mid S roof	258	LF	5	\$28,253	starting to spall & some open joints
	Downspouts - Interior Downspouts	Low E roof	336	LF	6	\$11,166	
	Downspouts - Interior Downspouts	Main upper roof	900	LF	6	\$29,910	
	Downspouts - Interior Downspouts	Mid N roof	180	LF	6	\$5,982	
	Downspouts - Interior Downspouts	Mid S roof	180	LF	6	\$5,982	
	Parapet - 16" - 30" Height	Low E roof	279	LF	6	\$11,147	
	Parapet - Parapet > 30"	Main upper roof	810	LF	6	\$51,776	
	Parapet - Parapet > 30"	Mid N roof	261	LF	5	\$64,393	some open joints & efflorescence
	Parapet - Parapet > 30"	Mid S roof	258	LF	5	\$63,653	some efflorescence and open joints
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Low E roof	1,817	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Main upper roof	24,955	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Mid N roof	6,961	SF	7	\$0	poor seams, surface wear, some vegetation growth
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Mid S roof	6,781	SF	7	\$0	
	Roof - Modified Bitumen	Low E roof	1,817	SF	5	\$38,221	poor seams, surface wear, some water ponding
	Roof - Modified Bitumen	Main upper roof	24,955	SF	4	\$684,094	surface wear, poor seams - some open joints, some water ponding @ chiller equipment supports, bubbles at NE, some vegetation growth at SE
	Roof - Modified Bitumen	Mid N roof	6,961	SF	5	\$146,427	
	Roof - Modified Bitumen	Mid S roof	6,781	SF	5	\$142,640	poor seams and surface wear
Walls							
	Canopy - Metal	Entire Building	728	SF	6	\$15,636	rust
	Cornice - Cast Stone	Entire Building	3,573	LF	6	\$123,903	some open joints, starting to show spalling patterns on surface

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls							
	Exterior Walls - Brick	Entire Building	5	SF	6	\$45	Graffiti at SW elevation
	Exterior Walls - Brick	Entire Building	20	SF	4	\$3,293	vertical cracks on corner
	Exterior Walls - Brick	Entire Building	936	SF	5	\$22,286	spalling, efflorescence, open joints
	Exterior Walls - Brick	Entire Building	44,134	SF	6	\$296,625	
	Exterior Walls - Stone-Cast	Entire Building	3,573	SF	6	\$24,014	starting to show spalling patterns on surface & seal wall to adjacent sidewalk to avoid water intrusion at foundation level.
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	384	SF	6	\$4,305	
	Curtain wall - Louver	Entire Building	390	SF	6	\$4,372	
	Guard - Guards perforated	Entire Building / 1st Floor	2,176	SF	5	\$33,357	dents, tears, missing paint
	Lintels - Steel	Entire Building	549	LF	6	\$15,937	
	Windows - Sash Aluminum Double-pane	Entire Building	3,608	SF	6	\$26,932	
Building Exterior Subtotal:						\$2,044,509	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	19,528	SF	6	\$5,864	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	4,102	SF	6	\$1,525	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	3,703	SF	6	\$1,377	
	Emergency A/C Power - Multipurpose Room	Entire Building / 1st Floor	1,800	SF	6	\$669	2'd feed from ComEd,
	Emergency Battery Packs - Corridors and Stairs	Entire Building	25	EA	6	\$5,063	
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	2	EA	6	\$405	
	Emergency Battery Packs - Lunchrooms	Entire Building / 1st Floor	4	EA	6	\$810	
	Emergency Battery Packs - Multipurpose Room	Entire Building / 1st Floor	2	EA	6	\$405	
	Emergency Battery Packs - Students Toilets	Entire Building	12	EA	6	\$2,430	
	Exit Signs - Corridors and Stairs	Entire Building	39	EA	2	\$21,274	
	Exit Signs - Gym	Entire Building / 1st Floor	3	EA	2	\$1,735	no generator, no battery packs, functional, on emergency lighting circuit
	Exit Signs - Lunchroom	Entire Building / 1st Floor	4	EA	2	\$2,182	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	4	EA	2	\$2,182	
	Security System - CCTV	Entire Building	102,700	SF	5	\$80,774	
	Security System - Intrusion Detection	Entire Building	102,700	SF	6	\$26,435	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	2'd feed from ComEd
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	7	\$0	
	PA System	Entire Building	102,700	SF	6	\$33,778	
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	Emergency fuse panel
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	
	Lighting and Power Panels - 100 A	Entire Building	5	EA	6	\$1,496	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	2000 installation
	Lighting and Power Panels - Above 100 A	Entire Building	6	EA	6	\$2,982	
	Lighting and Power Panels - Above 100 A	Entire Building	6	EA	6	\$2,982	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	1	EA	6	\$730	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	small general purpose transformer

Electrical System Subtotal:

\$202,947

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Engineers Office	1	EA	6	\$6,406	engineer's office, original
	Fire Alarm Strobe Lights	Engineers Office / Entire Building	102,700	SF	6	\$36,715	
	Fire Alarm_System	Engineers Office / Entire Building	102,700	SF	6	\$49,933	
	Fire Pump Controller	Engineers Office	1	EA	6	\$1,823	Pump room
Pump Room Assembly							
	Fire Pump - 25-50 hp	Pump Room	1	EA	6	\$1,558	in pump room
	Jockey Pump	Pump Room	1	EA	6	\$758	in pump room
Sprinkler System							
	Sprinkler Heads	Entire Building	102,700	SF	7	\$0	
	Sprinkler Piping	Entire Building	102,700	SF	7	\$0	
	Wet Sprinkler System	Entire Building	102,700	SF	7	\$0	2000 installation

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Safty System Subtotal:						\$97,192	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	6	\$606	
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	6	\$606	
	Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons	Roof	1	EA	5	\$63,450	
	Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons	Roof	1	EA	5	\$63,450	
	Glycol Feed	Roof / 2nd Floor	1	EA	6	\$490	
	Glycol Feed	Roof / Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Galvanized	Roof / Entire Building	400	LF	6	\$755	
	Pipes - Chilled Water Pipe- Galvanized	Roof / Entire Building	400	LF	6	\$755	
	Pressure Fill System	Roof / Mechanical Room	1	EA	6	\$1,405	
	Pressure Fill System	Roof / Mechanical Room	1	EA	6	\$1,405	

Air Handling Systems

	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	6	\$3,350	serves gym and auditorium (multi-purpose room), north mechanical room, 2'd floor
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	6	\$3,350	serves first floor, located at 2'd floor
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	Mechanical Room	1	EA	6	\$3,350	serves gym, south end, 2'd floor
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	6	\$3,350	serves 2'd and 3'd floors, largest AHU, located at 2'd floor
	Air Intake	Mechanical Room / North Façade	1	EA	6	\$5,765	room 219, north mechanical room, from side wall leuvers
	Air Intake	Mechanical Room / North Façade	1	EA	6	\$5,765	room 219, side wall leuvers of north mechanical room
	Air Intake	Mechanical Room / South Façade	1	EA	6	\$5,765	room 235, from side wall leuvers of south mechanical room
	Air Intake	Mechanical Room / South Façade	1	EA	6	\$5,765	room 235, from side wall of south mechanical room
	Fan Coil Unit- Celing Mounted - Electric	Electrical Room	1	EA	6	\$820	in MDF room, Liebert condensor unit is on the roof, 2'd floor
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building	60	EA	5	\$94,534	above ceiling panels
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	Mechanical Room	1	EA	6	\$1,857	north mechanical room, 2'd floor
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	Mechanical Room	1	EA	6	\$2,433	north mechanical room, largest return fan, 2'd floor
	Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM	Mechanical Room	1	EA	6	\$1,857	serves gym, auditorium and first floor, 2'd floor
	Make Up Air Unit- Roof Mounted- Gas Heating - Less than 6000 cfm	Roof	1	EA	6	\$3,350	no cooling

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	VAV Box	Mechanical Room / 1st Floor	16	EA	6	\$4,467	serves first floor 16 zones
	VAV Box	Mechanical Room / Entire Building	32	EA	6	\$8,933	2 floors, 32 zones, located above ceiling panel, nameplate not visible
Boiler Systems							
	Boiler Auxiliary- Non Condensing Hot Water - 2001 - 3000 MBH	Boiler Room	3	EA	6	\$6,139	
	Chemical Pot Feeder	Boiler Room	1	EA	6	\$725	
	Combustion Dampers	Boiler Room / 3rd Floor	3	EA	6	\$1,227	
	Non Condensing- Flexible Tube- Atmospheric- Hot Water Boiler - 2001 - 3000 MBH	Boiler Room	3	EA	6	\$2,994	
	Water Fill System	Boiler Room	1	EA	6	\$1,168	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building / 1st Floor	2	EA	6	\$709	
	Fin Tube - Hot Water	Entire Building	96	LF	7	\$0	in bathrooms
	Unit Heater - Electric	Entire Building	3	EA	6	\$833	
	Unit Heater - Electric	Entire Building	2	EA	7	\$0	personal heater, less than 1000W, 120V, in offices
	Unit Heater - Hot Water	Entire Building	4	EA	6	\$1,117	
Mechanical Plumbing							
	Chilled Water Pump - 10 - 20 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - 10 - 20 HP	Mechanical Room	3	EA	6	\$3,727	estimated 300 gpm, 2000, 3 boilers
	Hydronic Supply and Return - Galvanized	Entire Building	800	LF	7	\$0	hot water supply and return
Temperature Control							
	DDC System	Entire Building	102,700	SF	5	\$168,890	used for approximately 75% of temperature control
	Thermostats - DDC	Entire Building	74	EA	6	\$0	
Ventilation							
	Exhaust Fans- Indoor - Less than 500 CFM	Roof / 2nd Floor	2	EA	6	\$592	north and south mechanical room
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	3	EA	6	\$1,777	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof	2	EA	6	\$592	
	Type I Exhaust Hood- Kitchen	Roof / 1st Floor	2	EA	6	\$2,495	cooking kitchen
	Type II Exhaust Hood- Warming Kitchen	Roof / 1st Floor	1	EA	6	\$920	dishwasher

Mechanical System Subtotal:

\$485,104

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 300001 - 600000 BTU/HR	Mechanical Room	2	EA	6	\$620	
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	Mechanical Room	1	EA	7	\$0	vertical tank
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	102,700	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	102,700	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	102,700	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	102,700	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	102,700	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	102,700	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	102,700	SF	7	\$0	
	Sanitary Piping	Entire Building	102,700	SF	7	\$0	
	Storm Piping	Entire Building	102,700	SF	7	\$0	
	Vent Piping	Entire Building	102,700	SF	7	\$0	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Entire Building / Mechanical Room	1	EA	6	\$1,977	
	Pumps - Sump-Simplex	Entire Building / 1st Floor	1	EA	6	\$745	under elevator
Plumbing System Subtotal:						\$3,342	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #100 (Regular Classroom)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	854	SF	6	\$2,565	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	9	SF	6	\$65	
	Walls - Concrete Block	1st Floor	920	SF	6	\$2,697	
	Walls - Plaster/Drywall	1st Floor	920	SF	6	\$2,539	
Classroom #101 (Regular Classroom)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	940	SF	6	\$2,823	
	Chalk Board	1st Floor	12	LF	4	\$1,102	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #101 (Regular Classroom)							
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	1st Floor	13	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	9	SF	6	\$65	
	Walls - Concrete Block	1st Floor	615	SF	6	\$1,803	
	Walls - Plaster/Drywall	1st Floor	615	SF	6	\$1,697	
Classroom #103 (Regular Classroom)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	940	SF	6	\$2,823	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	1st Floor	13	EA	6	\$1,547	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	9	SF	6	\$65	
	Walls - Concrete Block	1st Floor	615	SF	6	\$1,803	
	Walls - Plaster/Drywall	1st Floor	615	SF	6	\$1,697	
Classroom #104 (Regular Classroom)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	854	SF	6	\$2,565	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	854	SF	6	\$855	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	9	SF	6	\$65	
	Walls - Concrete Block	1st Floor	923	SF	6	\$2,706	
	Walls - Plaster/Drywall	1st Floor	308	SF	6	\$850	
Classroom #105 (Regular Classroom)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	940	SF	6	\$2,823	
	Chalk Board	1st Floor	12	LF	4	\$1,102	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #105 (Regular Classroom)							
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	1st Floor	13	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	9	SF	6	\$65	
	Walls - Concrete Block	1st Floor	615	SF	6	\$1,803	
	Walls - Plaster/Drywall	1st Floor	615	SF	6	\$1,697	
Classroom #107 (Regular Classroom)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	940	SF	6	\$2,823	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	1st Floor	13	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	9	SF	6	\$65	
	Walls - Concrete Block	1st Floor	615	SF	6	\$1,803	
Classroom #109 (Kindergarten)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	990	SF	6	\$2,973	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	990	SF	6	\$2,166	
	Lighting - Lay-in	1st Floor	16	EA	6	\$1,904	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	87	SF	6	\$631	
	Walls - Concrete Block	1st Floor	920	SF	6	\$2,697	
	Walls - Plaster/Drywall	1st Floor	920	SF	6	\$2,539	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #111 (Kindergarten)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	990	SF	6	\$2,973	
	Chalk Board	1st Floor	12	LF	4	\$1,102	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #111 (Kindergarten)							
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	990	SF	7	\$0	
	Lighting - Lay-in	1st Floor	16	EA	6	\$1,904	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	85	SF	6	\$616	
	Walls - Concrete Block	1st Floor	920	SF	6	\$2,697	
	Walls - Plaster/Drywall	1st Floor	920	SF	6	\$2,539	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #113 (Kindergarten)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	990	SF	6	\$2,973	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	990	SF	6	\$991	
	Lighting - Lay-in	1st Floor	16	EA	6	\$1,904	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	85	SF	6	\$616	
	Walls - Concrete Block	1st Floor	920	SF	6	\$2,697	
	Walls - Plaster/Drywall	1st Floor	920	SF	6	\$2,539	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #115 (Kindergarten)							
	Casework	1st Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	1st Floor	990	SF	6	\$2,973	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	990	SF	6	\$2,166	
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	85	SF	6	\$616	
	Walls - Concrete Block	1st Floor	920	SF	6	\$2,697	
	Walls - Plaster/Drywall	1st Floor	920	SF	6	\$2,539	
	Work Sink	1st Floor	2	EA	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #200 (Regular Classroom)							
	Casework	2nd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	2nd Floor	854	SF	6	\$2,565	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	2nd Floor	475	SF	6	\$1,311	
Classroom #201 (Computer Lab)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Lay-in	2nd Floor	1,403	SF	6	\$4,213	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,403	SF	6	\$3,070	
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	134	SF	6	\$972	
	Walls - Concrete Block	2nd Floor	943	SF	6	\$2,764	
	Walls - Plaster/Drywall	2nd Floor	943	SF	6	\$2,603	
	Wireless System	2nd Floor	1	EA	7	\$0	
Classroom #202 (Regular Classroom)							
	Casework	2nd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	2nd Floor	854	SF	6	\$2,565	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	2nd Floor	475	SF	6	\$1,311	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #203 (Science)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Lay-in	2nd Floor	1,246	SF	6	\$3,742	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile	2nd Floor	1,243	SF	6	\$2,720	
	Floor - Tile	2nd Floor	3	SF	4	\$39	damagd and missing pieces
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Science Lab Elements	2nd Floor	1,246	SF	6	\$8,446	
	Storage/ Closet	2nd Floor	134	SF	6	\$972	
	Walls - Concrete Block	2nd Floor	685	SF	6	\$2,008	
	Walls - Plaster/Drywall	2nd Floor	685	SF	6	\$1,891	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroom #204 (Regular Classroom)							
	Casework	2nd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	2nd Floor	854	SF	6	\$2,565	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	2nd Floor	475	SF	6	\$1,311	
Classroom #206 (Regular Classroom)							
	Casework	2nd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	2nd Floor	854	SF	6	\$2,565	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #206 (Regular Classroom)							
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	712	SF	6	\$2,087	
	Walls - Plaster/Drywall	2nd Floor	237	SF	6	\$654	
Classroom #207 (Regular Classroom)							
	Casework	3rd Floor	43	LF	6	\$1,086	
	Ceiling - Lay-in	3rd Floor	940	SF	6	\$2,823	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	3rd Floor	13	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	550	SF	6	\$1,612	
	Walls - Plaster/Drywall	3rd Floor	550	SF	6	\$1,518	
Classroom #208 (Special Program)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	595	SF	6	\$1,787	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	595	SF	6	\$1,302	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	355	SF	6	\$1,041	
	Walls - Plaster/Drywall	2nd Floor	355	SF	6	\$980	
Classroom #209 (Regular Classroom)							
	Casework	2nd Floor	43	LF	6	\$1,086	
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$64	stained
	Ceiling - Lay-in	2nd Floor	932	SF	6	\$2,799	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	2nd Floor	13	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #209 (Regular Classroom)							
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	804	SF	6	\$2,357	
	Walls - Plaster/Drywall	2nd Floor	274	SF	6	\$756	
Classroom #210 (Special Program)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	595	SF	6	\$1,787	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	595	SF	6	\$1,302	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	355	SF	6	\$1,041	
	Walls - Plaster/Drywall	2nd Floor	355	SF	6	\$980	
Classroom #211 (Other Instructional Use)							
	Casework	2nd Floor	43	LF	6	\$1,086	
	Ceiling - Lay-in	2nd Floor	934	SF	6	\$2,805	
	Ceiling - Lay-in	2nd Floor	6	SF	5	\$48	stained tiles
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	940	SF	6	\$2,057	
	Lighting - Lay-in	2nd Floor	13	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	824	SF	6	\$2,416	
	Walls - Plaster/Drywall	2nd Floor	274	SF	6	\$756	
Classroom #212 (Special Program)							
	Casework	2nd Floor	3	LF	6	\$76	
	Ceiling - Lay-in	2nd Floor	595	SF	6	\$1,787	
	Chalk Board	2nd Floor	10	LF	4	\$918	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	595	SF	6	\$1,302	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #212 (Special Program)							
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	355	SF	6	\$1,041	
	Walls - Plaster/Drywall	2nd Floor	355	SF	6	\$980	
Classroom #214 (Regular Classroom)							
	Casework	2nd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	2nd Floor	854	SF	6	\$2,565	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	2nd Floor	475	SF	6	\$1,311	
Classroom #216 (Regular Classroom)							
	Casework	2nd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	2nd Floor	854	SF	6	\$2,565	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	2nd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	12	LF	6	\$257	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Concrete Block	2nd Floor	456	SF	6	\$1,337	
	Walls - Plaster/Drywall	2nd Floor	456	SF	6	\$1,259	
Classroom #300 (Store Room)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	2	SF	5	\$16	stained
	Ceiling - Lay-in	3rd Floor	852	SF	6	\$2,559	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #300 (Store Room)							
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	712	SF	6	\$2,087	
	Walls - Plaster/Drywall	3rd Floor	237	SF	6	\$654	
Classroom #301 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	6	\$2,565	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	712	SF	6	\$2,087	
	Walls - Plaster/Drywall	3rd Floor	237	SF	6	\$654	
Classroom #302 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	2	SF	5	\$16	stained
	Ceiling - Lay-in	3rd Floor	854	SF	6	\$2,565	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	712	SF	6	\$2,087	
	Walls - Plaster/Drywall	3rd Floor	237	SF	6	\$654	
Classroom #303 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	6	\$2,565	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #303 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Splined	3rd Floor	12	SF	6	\$0	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	712	SF	6	\$2,087	
	Walls - Plaster/Drywall	3rd Floor	237	SF	6	\$654	
Classroom #304 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	6	\$2,565	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	5	\$700	Paint finish peeling
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1	SF	5	\$6	broken tile
	Floor - Tile	3rd Floor	853	SF	6	\$1,866	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	3rd Floor	475	SF	5	\$3,600	peeling and torn
Classroom #305 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	5	\$5,080	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	3rd Floor	475	SF	6	\$1,311	
Classroom #306 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	5	\$5,080	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #306 (Regular Classroom)							
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	3rd Floor	475	SF	6	\$1,311	
Classroom #307 (Music Room)							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	1,040	SF	5	\$6,187	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	20	SF	6	\$334	2 @ 10 sf each
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	1,040	SF	6	\$2,275	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	566	SF	6	\$1,659	
	Walls - Plaster/Drywall	3rd Floor	566	SF	6	\$1,562	
	Work Sink	3rd Floor	2	EA	6	\$758	
Classroom #308 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	5	\$5,080	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	3rd Floor	475	SF	6	\$1,311	
Classroom #309 (Music Room)							
	Ceiling - Lay-in	3rd Floor	1,040	SF	5	\$6,187	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #309 (Music Room)							
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	2 @ 10 sf each
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	1,040	SF	6	\$2,275	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	34	SF	6	\$247	
	Walls - Concrete Block	3rd Floor	566	SF	6	\$1,659	
	Walls - Plaster/Drywall	3rd Floor	566	SF	6	\$1,562	
Classroom #310 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	2	SF	5	\$16	stained tile
	Ceiling - Lay-in	3rd Floor	852	SF	6	\$2,559	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	456	SF	6	\$1,337	
	Walls - Plaster/Drywall	3rd Floor	456	SF	5	\$3,456	scratched, peeling and torn
Classroom #311 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	5	\$5,080	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	854	SF	6	\$2,504	
	Walls - Plaster/Drywall	3rd Floor	854	SF	5	\$6,472	Paint peeling
Classroom #312 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #312 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	854	SF	5	\$5,080	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	5	\$1,174	damaged @ door handle
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	3	\$3,413	no lockset
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	456	SF	6	\$1,337	
	Walls - Plaster/Drywall	3rd Floor	456	SF	6	\$1,259	
Classroom #313 (Computer Lab)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	5	\$5,080	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	475	SF	6	\$1,392	
	Walls - Plaster/Drywall	3rd Floor	475	SF	6	\$1,311	
	Wireless System	3rd Floor	1	EA	7	\$0	
Classroom #314 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	846	SF	5	\$5,033	
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	stained tiles
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	456	SF	6	\$1,337	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #314 (Regular Classroom)							
	Walls - Plaster/Drywall	3rd Floor	456	SF	6	\$1,259	
Classroom #315 (Regular Classroom)							
	Casework	3rd Floor	41	LF	6	\$1,035	
	Ceiling - Lay-in	3rd Floor	854	SF	6	\$2,565	
	Chalk Board	3rd Floor	12	LF	6	\$268	
	Doors - Side-lite	3rd Floor	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	854	SF	6	\$1,868	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Concrete Block	3rd Floor	456	SF	6	\$1,337	
	Walls - Plaster/Drywall	3rd Floor	456	SF	6	\$1,259	

Classrooms Subtotal:

\$488,591

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st flr #102	864	SF	6	\$2,595	
	Doors - Side-lite	1st flr #102	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st flr #102	1	EA	6	\$301	
	Floor - Tile	1st flr #102	864	SF	6	\$1,890	
	Lighting - Lay-in	1st flr #102	12	EA	7	\$0	
	Power Distribution	1st flr #102	12	EA	6	\$25,499	
	Walls - Concrete Block	1st flr #102	615	SF	6	\$1,803	
	Walls - Plaster/Drywall	1st flr #102	615	SF	6	\$1,697	
	Work Slnk	1st flr #102	1	EA	6	\$508	
	Ceiling - Lay-in	1st flr #108	587	SF	6	\$1,763	
	Doors - Side-lite	1st flr #108	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st flr #108	1	EA	6	\$301	
	Floor - Tile	1st flr #108	587	SF	6	\$1,284	
	Lighting - Lay-in	1st flr #108	8	EA	7	\$0	
	Power Distribution	1st flr #108	6	EA	6	\$12,749	
	Storage/ Closet	1st flr #108	9	SF	6	\$65	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Concrete Block	1st flr #108	1,018	SF	6	\$2,984	
	Work Slnk	1st flr #108	1	EA	6	\$508	
	Ceiling - Lay-in	1st flr engineer's office room 171	143	SF	6	\$429	
	Doors - Steel Doors incl hw	1st flr engineer's office room 171	1	EA	6	\$301	
	Floor - Tile	1st flr engineer's office room 171	143	SF	6	\$313	
	Lighting - Lay-in	1st flr engineer's office room 171	2	EA	7	\$0	
	Power Distribution	1st flr engineer's office room 171	6	EA	6	\$12,749	
	Walls - Concrete Block	1st flr engineer's office room 171	498	SF	6	\$1,460	
	Ceiling - Lay-in	1st flr inside gym	105	SF	6	\$315	
	Doors - Side-lite	1st flr inside gym	10	SF	6	\$167	
	Doors - Steel Doors incl hw	1st flr inside gym	1	EA	6	\$301	
	Floor - Tile	1st flr inside gym	105	SF	6	\$230	
	Lighting - Lay-in	1st flr inside gym	2	EA	6	\$238	
	Power Distribution	1st flr inside gym	6	EA	6	\$12,749	
	Walls - Concrete Block	1st flr inside gym	361	SF	6	\$1,058	
	Ceiling - Lay-in	1st flr main office suite	1,689	SF	6	\$5,072	
	Doors - Side-lite	1st flr main office suite	10	SF	5	\$700	Paint peeling
	Doors - Wood Doors inclu hw	1st flr main office suite	1	EA	6	\$301	
	Floor - Tile	1st flr main office suite	1,689	SF	6	\$3,695	
	Lighting - Lay-in	1st flr main office suite	33	EA	7	\$0	
	Power Distribution	1st flr main office suite	39	EA	7	\$0	
	Storage/ Closet	1st flr main office suite	27	SF	6	\$196	
	Walls - Concrete Block	1st flr main office suite	780	SF	6	\$2,287	
	Walls - Plaster/Drywall	1st flr main office suite	2,340	SF	6	\$6,458	
	Ceiling - Lay-in	1st flr west of classroom #105	121	SF	6	\$363	
	Doors - Wood Doors inclu hw	1st flr west of classroom #105	1	EA	6	\$301	
	Floor - Tile	1st flr west of classroom #105	121	SF	6	\$265	
	Lighting - Lay-in	1st flr west of classroom #105	2	EA	7	\$0	
	Power Distribution	1st flr west of classroom #105	6	EA	6	\$12,749	
	Walls - Concrete Block	1st flr west of classroom #105	396	SF	6	\$1,161	
	Ceiling - Lay-in	West of Classroom 107	121	SF	6	\$363	
	Doors - Steel Doors incl hw	West of Classroom 107	1	EA	6	\$301	
	Floor - Tile	West of Classroom 107	121	SF	6	\$265	
	Lighting - Lay-in	West of Classroom 107	2	EA	7	\$0	
	Power Distribution	West of Classroom 107	6	EA	6	\$12,749	
	Walls - Concrete Block	West of Classroom 107	396	SF	6	\$1,161	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymnasia							
	Ceiling - Exposed	1st Floor	4,102	SF	6	\$6,100	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Floor - Tile/Sheet	1st Floor	4,102	SF	6	\$4,106	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	16	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	9	EA	7	\$0	
	Storage/ Closet	1st Floor	187	SF	6	\$1,356	
	Walls - Concrete Block	1st Floor	7,814	SF	6	\$22,907	
Kitchen							
	Ceiling - Lay-in	1st Floor	2,079	SF	6	\$6,243	
	Doors - Steel Doors incl hw	1st Floor	9	EA	6	\$2,709	
	Floor - Concrete Epoxy/ Painted	1st Floor	2,079	SF	6	\$1,100	
	Lighting - Lay-in	1st Floor	26	EA	6	\$3,093	
	Storage/ Closet	1st Floor	156	SF	6	\$1,131	
	Walls - Concrete Block	1st Floor	3,431	SF	6	\$10,058	
Library							
	Casework	room 205	84	LF	6	\$2,121	
	Ceiling - Lay-in	room 205	3,203	SF	6	\$9,619	
	Doors - Side-lite	room 205	20	SF	6	\$334	2 @ 10 sf each
	Doors - Wood Doors inclu hw	room 205	2	EA	6	\$602	
	Floor - Carpet	room 205	3,203	SF	6	\$6,825	
	Lighting - Lay-in	room 205	50	EA	7	\$0	
	Walls - Concrete Block	room 205	2,762	SF	6	\$8,097	
	Walls - Plaster/Drywall	room 205	920	SF	6	\$2,539	Smart board ranked a "6"
Lunch & Multipurpose Room							
	Ceiling - Exposed	1st Floor	3,131	SF	6	\$4,656	
	Ceiling - Lay-in	1st Floor	572	SF	6	\$1,718	
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Floor - Tile/Sheet	1st Floor	3,703	SF	6	\$3,707	
	Lighting - Lay-in	1st Floor	8	EA	6	\$952	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	12	EA	6	\$1,605	
	Serving Line	1st Floor	40	LF	6	\$2,381	
	Storage/ Closet	1st Floor	75	SF	6	\$544	
	Walls - Concrete Block	1st Floor	6,395	SF	6	\$18,747	
	Walls - Plaster/Drywall	1st Floor	987	SF	6	\$2,724	
	Ceiling - Lay-in	1st flr #106	1,800	SF	6	\$5,405	
	Chalk Board	1st flr #106	12	LF	4	\$1,102	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Doors - Side-lite	1st flr #106	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st flr #106	2	EA	6	\$602	
	Floor - Tile	1st flr #106	1,800	SF	6	\$3,938	
	Lighting - Lay-in	1st flr #106	24	EA	7	\$0	
	Market Board	1st flr #106	12	LF	6	\$257	
	Storage/ Closet	1st flr #106	198	SF	6	\$1,436	
	Walls - Concrete Block	1st flr #106	1,242	SF	6	\$3,641	
	Walls - Metal Panel	1st flr #106	240	SF	6	\$1,792	Fabric type Folding partition wall panel
	Walls - Plaster/Drywall	1st flr #106	622	SF	6	\$1,717	
MDF_IDF							
	Doors - Steel Doors incl hw	room 236	1	EA	6	\$301	
	Finishes	room 236	141	SF	6	\$1,006	
	Ventilation and Cooling	room 236	1	EA	6	\$1,855	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	32	SF	6	\$229	
	Mechanical/ Service Rooms	1st Floor	234	SF	6	\$1,676	electrical room next to engineer's office
	Mechanical/ Service Rooms	1st Floor	121	SF	6	\$867	Elevator mech room
	Storage Room	1st Floor	1,050	SF	6	\$7,523	Next to engineer's office
	Vaults	1st Floor	66	SF	6	\$473	
	Janitor's Closet	2nd Floor	15	SF	6	\$107	
	Mechanical/ Service Rooms	2nd Floor	144	SF	6	\$1,032	Room 218A, Electrical Closet
	Mechanical/ Service Rooms	2nd Floor	2,532	SF	6	\$18,140	Mechanical Room # 2, Room 219
	Mechanical/ Service Rooms	2nd Floor	97	SF	6	\$695	electrical closet Room 234
	Mechanical/ Service Rooms	2nd Floor	1,879	SF	6	\$13,462	Mechanical Room #235
	Janitor's Closet	3rd Floor	15	SF	6	\$107	
	Mechanical/ Service Rooms	3rd Floor	47	SF	6	\$337	
	Storage Room	3rd Floor	39	SF	6	\$279	Room 315A
Restroom							
	Accessories	1st floor inside kindergarten #109	41	SF	6	\$378	
	Ceiling - Lay-in	1st floor inside kindergarten #109	41	SF	6	\$123	
	Doors - Wood Doors inclu hw	1st floor inside kindergarten #109	1	EA	6	\$301	
	Floor Drain	1st floor inside kindergarten #109	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st floor inside kindergarten #109	41	SF	6	\$41	
	Lavatory	1st floor inside kindergarten #109	1	EA	6	\$320	
	Lighting - Lay-in	1st floor inside kindergarten #109	1	EA	6	\$119	
	Walls - Structural Glazed Tile	1st floor inside kindergarten #109	234	SF	6	\$736	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	1st floor inside kindergarten #109	1	EA	6	\$336	
	Accessories	1st floor inside kindergarten #111	41	SF	6	\$378	
	Ceiling - Lay-in	1st floor inside kindergarten #111	41	SF	6	\$123	
	Doors - Wood Doors inclu hw	1st floor inside kindergarten #111	1	EA	6	\$301	
	Floor Drain	1st floor inside kindergarten #111	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st floor inside kindergarten #111	41	SF	6	\$41	
	Lavatory	1st floor inside kindergarten #111	1	EA	7	\$0	
	Lighting - Lay-in	1st floor inside kindergarten #111	1	EA	6	\$119	
	Walls - Structural Glazed Tile	1st floor inside kindergarten #111	234	SF	6	\$736	
	Water Closet	1st floor inside kindergarten #111	1	EA	6	\$336	
	Accessories	1st floor inside kindergarten #113	41	SF	6	\$378	
	Ceiling - Lay-in	1st floor inside kindergarten #113	41	SF	6	\$123	
	Doors - Wood Doors inclu hw	1st floor inside kindergarten #113	1	EA	6	\$301	
	Floor Drain	1st floor inside kindergarten #113	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st floor inside kindergarten #113	41	SF	6	\$41	
	Lavatory	1st floor inside kindergarten #113	1	EA	6	\$320	
	Lighting - Lay-in	1st floor inside kindergarten #113	1	EA	7	\$0	
	Walls - Structural Glazed Tile	1st floor inside kindergarten #113	234	SF	6	\$736	
	Water Closet	1st floor inside kindergarten #113	1	EA	6	\$336	
	Accessories	1st floor inside kindergarten #115	41	SF	6	\$378	
	Ceiling - Lay-in	1st floor inside kindergarten #115	41	SF	6	\$123	
	Doors - Wood Doors inclu hw	1st floor inside kindergarten #115	1	EA	6	\$301	
	Floor Drain	1st floor inside kindergarten #115	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st floor inside kindergarten #115	41	SF	6	\$41	
	Lavatory	1st floor inside kindergarten #115	1	EA	7	\$0	
	Lighting - Lay-in	1st floor inside kindergarten #115	1	EA	6	\$119	
	Walls - Structural Glazed Tile	1st floor inside kindergarten #115	234	SF	6	\$736	
	Water Closet	1st floor inside kindergarten #115	1	EA	6	\$336	
	Accessories	1st flr inside kitchen, men's	78	SF	6	\$719	
	Ceiling - Lay-in	1st flr inside kitchen, men's	78	SF	6	\$234	
	Doors - Steel Doors incl hw	1st flr inside kitchen, men's	2	EA	6	\$602	
	Floor Drain	1st flr inside kitchen, men's	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	1st flr inside kitchen, men's	78	SF	6	\$41	
	Lavatory	1st flr inside kitchen, men's	1	EA	6	\$320	
	Lighting - Lay-in	1st flr inside kitchen, men's	2	EA	7	\$0	
	Partitions	1st flr inside kitchen, men's	1	EA	6	\$297	
	Student Lockers - One Tier	1st flr inside kitchen, men's	4	EA	6	\$371	Staff lockers

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Structural Glazed Tile	1st flr inside kitchen, men's	454	SF	6	\$1,428	
	Water Closet	1st flr inside kitchen, men's	1	EA	6	\$336	
	Accessories	1st flr inside kitchen, women's	78	SF	6	\$719	
	Ceiling - Lay-in	1st flr inside kitchen, women's	78	SF	6	\$234	
	Doors - Steel Doors incl hw	1st flr inside kitchen, women's	2	EA	6	\$602	
	Floor Drain	1st flr inside kitchen, women's	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	1st flr inside kitchen, women's	78	SF	6	\$41	
	Lavatory	1st flr inside kitchen, women's	1	EA	6	\$320	
	Lighting - Lay-in	1st flr inside kitchen, women's	2	EA	7	\$0	
	Partitions	1st flr inside kitchen, women's	1	EA	6	\$297	
	Student Lockers - One Tier	1st flr inside kitchen, women's	4	EA	6	\$371	Staff Lockers
	Walls - Structural Glazed Tile	1st flr inside kitchen, women's	454	SF	6	\$1,428	
	Water Closet	1st flr inside kitchen, women's	1	EA	6	\$336	
	Accessories	1st flr inside main office	39	SF	6	\$360	
	Ceiling - Lay-in	1st flr inside main office	39	SF	6	\$117	
	Doors - Wood Doors inclu hw	1st flr inside main office	1	EA	6	\$301	
	Floor Drain	1st flr inside main office	1	EA	6	\$1,059	
	Floor - Tile/Sheet	1st flr inside main office	39	SF	6	\$39	
	Lavatory	1st flr inside main office	1	EA	6	\$320	
	Lighting - Lay-in	1st flr inside main office	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st flr inside main office	234	SF	6	\$646	
	Water Closet	1st flr inside main office	1	EA	6	\$336	
	Accessories	1st flr north end of corridor	187	SF	6	\$1,725	
	Accessories	1st flr north end of corridor	187	SF	6	\$1,725	
	Accessories	1st flr north end of corridor	43	SF	6	\$397	
	Ceiling - Lay-in	1st flr north end of corridor	187	SF	6	\$562	
	Ceiling - Lay-in	1st flr north end of corridor	187	SF	6	\$562	
	Ceiling - Lay-in	1st flr north end of corridor	43	SF	6	\$129	
	Doors - Steel Doors incl hw	1st flr north end of corridor	1	EA	6	\$301	
	Floor Drain	1st flr north end of corridor	1	EA	6	\$1,059	
	Floor Drain	1st flr north end of corridor	2	EA	6	\$2,118	
	Floor Drain	1st flr north end of corridor	2	EA	6	\$2,118	
	Floor - Terrazzo	1st flr north end of corridor	187	SF	6	\$409	
	Floor - Terrazzo	1st flr north end of corridor	43	SF	6	\$94	
	Floor - Terrazzo	1st flr north end of corridor	187	SF	6	\$409	
	Lavatory	1st flr north end of corridor	3	EA	6	\$959	
	Lavatory	1st flr north end of corridor	3	EA	6	\$959	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	1st flr north end of corridor	1	EA	6	\$320	
	Lighting - Lay-in	1st flr north end of corridor	3	EA	6	\$357	
	Lighting - Lay-in	1st flr north end of corridor	3	EA	6	\$357	
	Lighting - Lay-in	1st flr north end of corridor	1	EA	6	\$119	
	Partitions	1st flr north end of corridor	4	EA	6	\$1,188	
	Partitions	1st flr north end of corridor	2	EA	6	\$594	
	Urinals	1st flr north end of corridor	2	EA	6	\$672	
	Walls - Structural Glazed Tile	1st flr north end of corridor	513	SF	6	\$1,614	
	Walls - Structural Glazed Tile	1st flr north end of corridor	513	SF	6	\$1,614	
	Walls - Structural Glazed Tile	1st flr north end of corridor	228	SF	6	\$717	
	Water Closet	1st flr north end of corridor	4	EA	6	\$1,344	
	Water Closet	1st flr north end of corridor	1	EA	6	\$336	
	Water Closet	1st flr north end of corridor	2	EA	6	\$672	
	Accessories	1st flr south end of corridor	187	SF	6	\$1,725	
	Accessories	1st flr south end of corridor	187	SF	6	\$1,725	
	Accessories	1st flr south end of corridor	43	SF	6	\$397	
	Ceiling - Lay-in	1st flr south end of corridor	187	SF	6	\$562	
	Ceiling - Lay-in	1st flr south end of corridor	43	SF	6	\$129	
	Ceiling - Lay-in	1st flr south end of corridor	187	SF	6	\$562	
	Doors - Steel Doors incl hw	1st flr south end of corridor	1	EA	6	\$301	
	Floor Drain	1st flr south end of corridor	2	EA	6	\$2,118	
	Floor Drain	1st flr south end of corridor	1	EA	6	\$1,059	
	Floor Drain	1st flr south end of corridor	2	EA	6	\$2,118	
	Floor - Terrazzo	1st flr south end of corridor	43	SF	6	\$94	
	Floor - Terrazzo	1st flr south end of corridor	187	SF	6	\$409	
	Floor - Terrazzo	1st flr south end of corridor	187	SF	6	\$409	
	Lavatory	1st flr south end of corridor	3	EA	6	\$959	
	Lavatory	1st flr south end of corridor	3	EA	6	\$959	
	Lavatory	1st flr south end of corridor	1	EA	6	\$320	
	Lighting - Lay-in	1st flr south end of corridor	3	EA	7	\$0	
	Lighting - Lay-in	1st flr south end of corridor	3	EA	7	\$0	
	Lighting - Lay-in	1st flr south end of corridor	1	EA	6	\$119	
	Partitions	1st flr south end of corridor	4	EA	6	\$1,188	
	Partitions	1st flr south end of corridor	2	EA	6	\$594	
	Urinals	1st flr south end of corridor	2	EA	6	\$672	
	Walls - Structural Glazed Tile	1st flr south end of corridor	513	SF	6	\$1,614	
	Walls - Structural Glazed Tile	1st flr south end of corridor	228	SF	6	\$717	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Structural Glazed Tile	1st flr south end of corridor	513	SF	6	\$1,614	
	Water Closet	1st flr south end of corridor	2	EA	6	\$672	
	Water Closet	1st flr south end of corridor	1	EA	6	\$336	
	Water Closet	1st flr south end of corridor	4	EA	6	\$1,344	
	Accessories	2nd Floor North	191	SF	6	\$1,762	
	Accessories	2nd Floor North	191	SF	6	\$1,762	
	Accessories	2nd Floor North	191	SF	6	\$1,762	
	Ceiling - Plaster/Drywall	2nd Floor North	191	SF	6	\$661	
	Ceiling - Plaster/Drywall	2nd Floor North	191	SF	6	\$661	
	Ceiling - Plaster/Drywall	2nd Floor North	191	SF	6	\$661	
	Floor Drain	2nd Floor North	2	EA	6	\$2,118	
	Floor Drain	2nd Floor North	2	EA	6	\$2,118	
	Floor Drain	2nd Floor North	2	EA	6	\$2,118	
	Floor - Terrazzo	2nd Floor North	191	SF	6	\$418	
	Floor - Terrazzo	2nd Floor North	191	SF	6	\$418	
	Floor - Terrazzo	2nd Floor North	191	SF	6	\$418	
	Lavatory	2nd Floor North	3	EA	6	\$959	
	Lavatory	2nd Floor North	3	EA	6	\$959	
	Lavatory	2nd Floor North	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor North	4	EA	7	\$0	
	Lighting - Lay-in	2nd Floor North	3	EA	7	\$0	
	Lighting - Lay-in	2nd Floor North	3	EA	7	\$0	
	Partitions	2nd Floor North	2	EA	6	\$594	
	Partitions	2nd Floor North	3	EA	6	\$891	
	Partitions	2nd Floor North	3	EA	6	\$891	
	Urinals	2nd Floor North	2	EA	6	\$672	
	Walls - Structural Glazed Tile	2nd Floor North	225	SF	6	\$708	
	Walls - Structural Glazed Tile	2nd Floor North	225	SF	6	\$708	
	Walls - Structural Glazed Tile	2nd Floor North	225	SF	6	\$708	
	Water Closet	2nd Floor North	4	EA	6	\$1,344	
	Water Closet	2nd Floor North	4	EA	6	\$1,344	
	Water Closet	2nd Floor North	2	EA	6	\$672	
	Accessories	2nd Floor South	191	SF	6	\$1,762	
	Accessories	2nd Floor South	191	SF	6	\$1,762	
	Ceiling - Plaster/Drywall	2nd Floor South	191	SF	6	\$661	
	Ceiling - Plaster/Drywall	2nd Floor South	191	SF	6	\$661	
	Floor Drain	2nd Floor South	2	EA	6	\$2,118	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	2nd Floor South	2	EA	6	\$2,118	
	Floor - Terrazzo	2nd Floor South	191	SF	6	\$418	
	Floor - Terrazzo	2nd Floor South	191	SF	6	\$418	
	Lavatory	2nd Floor South	3	EA	6	\$959	
	Lavatory	2nd Floor South	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor South	3	EA	7	\$0	
	Lighting - Lay-in	2nd Floor South	4	EA	6	\$476	
	Partitions	2nd Floor South	2	EA	6	\$594	
	Partitions	2nd Floor South	3	EA	6	\$891	
	Urinals	2nd Floor South	2	EA	6	\$672	
	Walls - Structural Glazed Tile	2nd Floor South	225	SF	6	\$708	
	Walls - Structural Glazed Tile	2nd Floor South	225	SF	6	\$708	
	Water Closet	2nd Floor South	4	EA	6	\$1,344	
	Water Closet	2nd Floor South	2	EA	6	\$672	
	Accessories	3rd Floor North	191	SF	6	\$1,762	
	Accessories	3rd Floor North	191	SF	6	\$1,762	
	Ceiling - Plaster/Drywall	3rd Floor North	191	SF	6	\$661	
	Ceiling - Plaster/Drywall	3rd Floor North	191	SF	6	\$661	
	Floor Drain	3rd Floor North	2	EA	6	\$2,118	
	Floor Drain	3rd Floor North	2	EA	6	\$2,118	
	Floor - Terrazzo	3rd Floor North	191	SF	6	\$418	
	Floor - Terrazzo	3rd Floor North	191	SF	6	\$418	
	Lavatory	3rd Floor North	3	EA	6	\$959	
	Lavatory	3rd Floor North	3	EA	6	\$959	
	Lighting - Lay-in	3rd Floor North	4	EA	6	\$476	
	Lighting - Lay-in	3rd Floor North	3	EA	7	\$0	
	Partitions	3rd Floor North	2	EA	6	\$594	
	Partitions	3rd Floor North	3	EA	6	\$891	
	Urinals	3rd Floor North	2	EA	6	\$672	
	Walls - Structural Glazed Tile	3rd Floor North	225	SF	6	\$708	
	Walls - Structural Glazed Tile	3rd Floor North	225	SF	6	\$708	
	Water Closet	3rd Floor North	2	EA	6	\$672	
	Water Closet	3rd Floor North	4	EA	6	\$1,344	
	Accessories	3rd Floor South	191	SF	6	\$1,762	
	Accessories	3rd Floor South	191	SF	6	\$1,762	
	Ceiling - Plaster/Drywall	3rd Floor South	191	SF	6	\$661	
	Ceiling - Plaster/Drywall	3rd Floor South	191	SF	6	\$661	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	3rd Floor South	2	EA	6	\$2,118	
	Floor Drain	3rd Floor South	2	EA	6	\$2,118	
	Floor - Terrazzo	3rd Floor South	191	SF	6	\$418	
	Floor - Terrazzo	3rd Floor South	191	SF	6	\$418	
	Lavatory	3rd Floor South	3	EA	6	\$959	
	Lavatory	3rd Floor South	3	EA	6	\$959	
	Lighting - Lay-in	3rd Floor South	3	EA	7	\$0	
	Lighting - Lay-in	3rd Floor South	4	EA	7	\$0	
	Partitions	3rd Floor South	2	EA	6	\$594	
	Partitions	3rd Floor South	3	EA	6	\$891	
	Urinals	3rd Floor South	2	EA	6	\$672	
	Walls - Structural Glazed Tile	3rd Floor South	225	SF	6	\$708	
	Walls - Structural Glazed Tile	3rd Floor South	225	SF	6	\$708	
	Water Closet	3rd Floor South	4	EA	6	\$1,344	
	Water Closet	3rd Floor South	2	EA	6	\$672	
	Accessories	Unisex Room, 2nd Floor North	57	SF	6	\$526	
	Ceiling - Lay-in	Unisex Room, 2nd Floor North	57	SF	6	\$171	
	Doors - Wood Doors inclu hw	Unisex Room, 2nd Floor North	1	EA	6	\$301	
	Floor Drain	Unisex Room, 2nd Floor North	1	EA	6	\$1,059	
	Floor - Terrazzo	Unisex Room, 2nd Floor North	57	SF	6	\$125	
	Lavatory	Unisex Room, 2nd Floor North	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 2nd Floor North	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Unisex Room, 2nd Floor North	69	SF	6	\$217	
	Water Closet	Unisex Room, 2nd Floor North	1	EA	6	\$336	
	Accessories	Unisex Room, 2nd Floor South	57	SF	6	\$526	
	Ceiling - Lay-in	Unisex Room, 2nd Floor South	57	SF	6	\$171	
	Doors - Wood Doors inclu hw	Unisex Room, 2nd Floor South	1	EA	6	\$301	
	Floor Drain	Unisex Room, 2nd Floor South	1	EA	6	\$1,059	
	Floor - Terrazzo	Unisex Room, 2nd Floor South	57	SF	6	\$125	
	Lavatory	Unisex Room, 2nd Floor South	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 2nd Floor South	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Unisex Room, 2nd Floor South	69	SF	6	\$217	
	Water Closet	Unisex Room, 2nd Floor South	1	EA	6	\$336	
	Accessories	Unisex Room, 3rd Floor	40	SF	6	\$369	
	Ceiling - Lay-in	Unisex Room, 3rd Floor	40	SF	6	\$120	
	Doors - Wood Doors inclu hw	Unisex Room, 3rd Floor	1	EA	6	\$301	
	Floor Drain	Unisex Room, 3rd Floor	1	EA	6	\$1,059	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor - Terrazzo	Unisex Room, 3rd Floor	40	SF	6	\$88	
	Lavatory	Unisex Room, 3rd Floor	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 3rd Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Unisex Room, 3rd Floor	61	SF	6	\$192	
	Water Closet	Unisex Room, 3rd Floor	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$491,825

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	5,842	SF	6	\$17,544	
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Doors - Store Front	1st Floor	4	EA	6	\$4,833	
	Drinking Fountains - Double Fountain	1st Floor	2	EA	6	\$672	
	Floor - Terrazzo	1st Floor	5,842	SF	6	\$49,038	
	Lighting - Lay-in	1st Floor	166	EA	7	\$0	
	Walls - Concrete Block	1st Floor	7,715	SF	6	\$22,617	
	Ceiling - Lay-in	2nd Floor	4,918	SF	6	\$14,769	
	Doors - Steel Doors incl hw	2nd Floor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	2nd Floor	2	EA	6	\$672	
	Floor - Terrazzo	2nd Floor	4,918	SF	6	\$41,282	
	Lighting - Lay-in	2nd Floor	133	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	6,384	SF	6	\$18,715	
	Ceiling - Lay-in	3rd Floor	4,918	SF	6	\$14,769	
	Doors - Steel Doors incl hw	3rd Floor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	3rd Floor	2	EA	6	\$672	
	Floor - Terrazzo	3rd Floor	4,918	SF	6	\$41,282	
	Lighting - Lay-in	3rd Floor	133	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	6,384	SF	6	\$18,715	

Safety

	Camera Viewing Station	Entire Building	3	EA	6	\$2,048	
	Security Cameras	Entire Building	4	EA	3	\$5,302	Dont work
	Security Cameras	Entire Building	5	EA	6	\$970	
	Security Cameras	Entire Building	5	EA	6	\$970	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Safety							
	Security Cameras	Entire Building	9	EA	3	\$11,930	Don't work
Stairs							
	Handrails	North	128	LF	6	\$1,109	
	Ceiling - Lay-in	North	1,221	SF	6	\$3,667	
	Floor - Terrazzo	North	1,400	SF	6	\$11,752	
	Lighting - Lay-in	North	18	EA	7	\$0	
	Stairs - Terrazzo	North	60	LF	6	\$557	
	Walls - Concrete Block	North	4,280	SF	6	\$12,547	
	Ceiling - Lay-in	South	1,671	SF	6	\$5,018	
	Floor - Terrazzo	South	1,400	SF	6	\$11,752	
	Handrails	South	128	LF	6	\$1,109	
	Lighting - Lay-in	South	18	EA	7	\$0	
	Stairs - Terrazzo	South	60	LF	6	\$557	
	Walls - Concrete Block	South	4,280	SF	6	\$12,547	
	Floor - Terrazzo	West / Vault	1,050	SF	6	\$8,814	
	Ceiling - Lay-in	West	1,292	SF	6	\$3,880	
	Handrails	West	128	LF	6	\$1,109	
	Lighting - Lay-in	West	17	EA	7	\$0	
	Stairs - Terrazzo	West	60	LF	6	\$557	
	Walls - Concrete Block	West	3,680	SF	6	\$10,788	
Vertical Conveyance							
	Elevator - Elevator- Roped Holeless Hydraulic	1st Floor	1	EA	6	\$19,238	

Building Interior Subtotal:

\$377,216

Total Building Cost

\$4,190,725

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	10	EA	6	\$10,938	
	Civil/ Drainage - Site Manhole	Entire Site	4	EA	6	\$5,971	
Fencing							
	Fencing - New Standard Ornamental	Entire Site	6	LF	5	\$0	Location: Door 5 - missing balluster

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fencing							
	Fencing - New Standard Ornamental	Entire Site	16	LF	5	\$2,278	Location: S end of parking lot - bent
	Fencing - New Standard Ornamental	Entire Site	1,400	LF	6	\$44,665	some rust
	Fencing - New Standard Ornamental	Entire Site / Site South	16	LF	4	\$3,592	severed posts
Landscape							
	Landscape - Grass	Entire Site	21,501	SF	6	\$17,833	
	Landscape - Grass	Entire Site / South West	400	SF	5	\$606	bare soil
	Landscape - Hardscape- Concrete	Entire Site / Site - East	4,927	SF	6	\$25,435	
	Landscape - Hardscape- Pavers	Entire Site / Site - East	720	SF	6	\$4,077	
	Parkway trees	Entire Site / Entire Building	31	EA	6	\$20,461	
	Planting Beds/ Area	Entire Site	3,610	SF	6	\$5,937	
	Play Area - Asphalt/ Hardscape	Entire Site / Site South	2,963	SF	6	\$7,161	some water ponding
	Retaining Wall - Concrete	Entire Site	210	SF	5	\$11,231	Location: E planter boxes
	Trash Receptacles	Entire Site / Site South	1	EA	6	\$312	
Parking Lot							
	Concrete Curbs	SW parking lot / South West	588	LF	5	\$15,438	some cracks
	Interior Plantings	SW parking lot / South West	190	LF	6	\$8,083	
	Lighting - Pole Mounted	SW parking lot / South West	4	EA	6	\$5,810	
	Surface - Asphalt	SW parking lot / South West	6,088	SF	6	\$14,713	some water ponding
	Trash Compactor	SW parking lot	1	EA	6	\$0	Nothwest in the southwest parking lot
	Trash Enclosure - Masonry	SW parking lot / South West	1,508	SF	5	\$106,442	efflorescence & bent gate
	Vehicular Screening	SW parking lot / South West	157	LF	5	\$22,357	sparse
Playground							
	Equipment - Pre K 3-5	South / Site South	1	EA	6	\$3,546	graffiti
	Equipment - School Age 5-12	South / Site South	1	EA	6	\$3,546	graffiti
	Surface - Poured Surface	South / Site South	4,803	SF	6	\$35,166	
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	5	LF	5	\$289	Location: Door #5 - cracks
	Sidewalks - Internal Walks	Entire Site	2	LF	5	\$116	Location: Door #2 - cracks
	Sidewalks - Internal Walks	Entire Site	1,099	LF	6	\$13,201	
	Sidewalks - Internal Walks	Entire Site / Site South	40	LF	6	\$629	graffiti
	Sidewalks - Perimeter Sidewalks	Entire Site	10,060	SF	6	\$19,996	
Signage							
	Flag Pole - Flag Pole	East / Site - East	1	EA	6	\$1,657	
	Monument - Building Mounted Cut Letter Sign	East / East Façade	1	EA	6	\$0	
	Monument - Sign-Lighted	East / Site - East	1	EA	6	\$0	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Signage							

Site Subtotal: **\$411,485**

Total Site Cost **\$411,485**

Campus Total ^{2 3} **\$4,602,210**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Computer Lab	Computer Lab	2nd Floor	201	2-33	1,403	1	47	100	120	56	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	313	3-20	854	1	9	24	45	23	40	N	N	N
Kindergarten	Kindergarten	1st Floor	109	1-55	990	1	9	20	90	42	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	111	1-58	990	1	9	20	90	42	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	113	1-61	990	1	9	20	90	42	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	115	1-64	990	1	9	20	90	42	40	N	Y	N
Music Room	Art Room	3rd Floor	307	3-25	1,040	1	4	14	61	30	40	N	N	N
Music Room	Music Room	3rd Floor	309	3-22	1,040	1	4	14	61	30	40	N	Y	N
Other Instructional Use	Regular Classroom	2nd Floor	211	2-22	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	100	1-24	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	101	1-44	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	103	1-46	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	104	1-11	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	105	1-48	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	107	1-50	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	200	2-13	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	2-12	854	1	9	24	45	23	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	204	2-11	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	206	2-10	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	207	2-26	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	209	2-24	940	1	9	20	90	42	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	214	2-06	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	216	2-05	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	301	3-29	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	302	3-12	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	303	3-28	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	304	3-11	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	305	3-27	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	306	3-10	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	308	3-08	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	310	3-07	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	311	3-21	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	312	3-06	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	314	3-05	854	1	9	24	45	23	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	315	3-19	854	1	9	24	45	23	40	N	Y	N
Science	Science	2nd Floor	203	2-31	1,246	1	5	92	120	56	40	N	Y	N
Special Program	Regular Classroom	2nd Floor	208	2-09	595	1	7	8	60	28	40	N	Y	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Special Program	Regular Classroom	2nd Floor	210	2-08	595	1	7	8	60	28	40	N	Y	N
Special Program	Regular Classroom	2nd Floor	212	2-07	595	1	7	8	60	28	40	N	Y	N
Store Room	Regular Classroom	3rd Floor	300	3-13	854	1	9	24	45	23	40	N	Y	N