

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1954	3	56,857	\$3,101,117
SITE				\$212,267
Campus Total			56,857	\$3,313,383

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio	Door 4 - West	1	EA	6	\$497	
	Exterior Doors - Exterior FRP Door	Door 1 - East	3	EA	6	\$1,894	
	Exterior Doors - Exterior FRP Door	Door 2 - Southeast	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	Door 3 - South center	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	Door 4 - West	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	Door 5 - West	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	Door 6 - North	3	EA	6	\$1,894	
	Exterior Doors - Side lite	Door 2 - Southeast	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Door 1 - East	3	EA	6	\$940	
	Exterior Doors - Transom Lite	Door 4 - West	2	EA	6	\$627	
	Exterior Doors - Transom Lite	Door 5 - West	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Door 6 - North	3	EA	6	\$940	
	Exterior Stairs - Concrete	Door 1 - East	45	LF	6	\$3,680	
	Exterior Stairs - Concrete	Door 2 - Southeast	52	LF	6	\$4,252	
	Exterior Stairs - Concrete	Door 3 - South center	6	LF	7	\$0	Spalling
	Exterior Stairs - Concrete	Door 4 - West	5	LF	5	\$548	Cracked
	Exterior Stairs - Concrete	Door 4 - West	40	LF	7	\$0	
	Exterior Stairs - Concrete	Door 5 - West	43	LF	7	\$0	
	Exterior Stairs - Concrete	Door 6 - North	61	LF	6	\$4,988	
	Exterior Stairs - Concrete	Door 6 - North	5	LF	4	\$818	Cracking and settling
	Exterior Stairs - Steel or Aluminum	Door 3 - South center	24	LF	6	\$92	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Ramp Handrail - Steel_Ramp Handrail	Door 1 - East	128	LF	6	\$1,109	
	Ramp Handrail - Steel_Ramp Handrail	Door 5 - West	70	LF	6	\$607	
	Ramps - Concrete	Door 1 - East	64	LF	7	\$0	
	Ramps - Concrete	Door 5 - West	35	LF	6	\$5,258	
	Stair Handrail - Steel_Stair Handrail	Door 1 - East	20	LF	6	\$173	
	Stair Handrail - Steel_Stair Handrail	Door 2 - Southeast	35	LF	6	\$303	
	Stair Handrail - Steel_Stair Handrail	Door 3 - South center	12	LF	6	\$104	
	Stair Handrail - Steel_Stair Handrail	Door 4 - West	16	LF	6	\$139	
	Stair Handrail - Steel_Stair Handrail	Door 5 - West	16	LF	6	\$139	
Foundation							
	Foundation - Concrete	Entire Building	675	LF	7	\$0	
	Foundation - Concrete	Entire Building	90	LF	7	\$0	Seepage
	Superstructure - Concrete	Entire Building	56,857	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	9	EA	6	\$4,829	
Roof System							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 3	55	LF	6	\$52,508	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 3	15	LF	5	\$42,773	top 15', mortar loss, spalling
	Chimney - Metal Flue	Roof 2	15	LF	7	\$0	
	Coping - Metal	Roof 1	540	LF	6	\$17,344	
	Coping - Metal	Roof 4	6	LF	7	\$0	
	Coping - Metal	Roof 5	31	LF	6	\$996	
	Coping - Metal	Roof 6	15	LF	7	\$0	
	Coping - Stone	Roof 2	300	LF	6	\$9,635	
	Coping - Stone	Roof 3	65	LF	6	\$2,088	
	Downspouts - Exterior Downspouts	Roof 4	26	LF	6	\$864	
	Downspouts - Exterior Downspouts	Roof 5	38	LF	6	\$1,263	
	Downspouts - Interior Downspouts	Roof 1	135	LF	6	\$4,486	
	Downspouts - Interior Downspouts	Roof 2	60	LF	6	\$1,994	
	Downspouts - Interior Downspouts	Roof 3	15	LF	6	\$498	
	Downspouts - Interior Downspouts	Roof 6	12	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof 2	300	LF	6	\$11,986	
	Parapet - 16" - 30" Height	Roof 3	35	LF	6	\$1,398	
	Parapet - Parapet < 16" Height	Roof 1	540	LF	6	\$11,506	
	Parapet - Parapet < 16" Height	Roof 3	30	LF	6	\$639	
	Parapet - Parapet < 16" Height	Roof 4	6	LF	6	\$128	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Parapet - Parapet < 16" Height	Roof 5	31	LF	6	\$661	
	Parapet - Parapet < 16" Height	Roof 6	15	LF	7	\$0	
	Roof Structure - Concrete	Roof 1	13,315	SF	7	\$0	
	Roof Structure - Concrete	Roof 2	5,686	SF	7	\$0	
	Roof Structure - Concrete	Roof 3	1,200	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 4	60	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 5	66	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 6	65	SF	7	\$0	
	Roof - EPDM/ Synthetic Rubber	Roof 1	13,315	SF	6	\$112,719	
	Roof - EPDM/ Synthetic Rubber	Roof 2	5,686	SF	6	\$48,135	
	Roof - EPDM/ Synthetic Rubber	Roof 3	1,200	SF	6	\$10,159	
	Roof - Modified Bitumen	Roof 4	60	SF	6	\$565	
	Roof - Modified Bitumen	Roof 5	66	SF	6	\$621	
	Roof - Modified Bitumen	Roof 6	65	SF	6	\$612	
Walls							
	Canopy - Concrete/ Stucco	Entire Building / North Façade	138	SF	6	\$4,566	
	Canopy - Concrete/ Stucco	Entire Building / West Façade	82	SF	6	\$3,005	
	Cheek-Wall - Concrete	Entire Building / North	20	SF	5	\$472	Extensive cracking
	Exterior Walls - Brick	Entire Building	50	SF	5	\$1,190	Spalling, cracking
	Exterior Walls - Brick	Entire Building	14,520	SF	6	\$97,589	
	Exterior Walls - Stone-Cast	Entire Building	1,285	SF	6	\$8,636	
	Exterior Walls - Terra Cotta	Entire Building	220	SF	6	\$1,479	
Windows							
	Guard - Guards perforated	Entire Building	2,612	SF	6	\$33,355	
	Guard - Guards wire guard	Entire Building / South Façade	37	SF	6	\$472	
	Lintels - Brick	Entire Building	82	LF	6	\$0	
	Lintels - Steel	Entire Building	868	LF	6	\$25,197	
	Windows - Decorative	Entire Building	511	SF	6	\$3,814	
	Windows - Sash Aluminum Double-pane	Entire Building	3,295	SF	6	\$24,596	
	Windows - Sash Aluminum	Entire Building	3,295	SF	5	\$118,315	Not operable

Building Exterior Subtotal:

\$694,197

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	3	EA	6	\$1,224	for AC generators
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	2,937	SF	6	\$1,554	
	Emergency A/C Power - Corridors and Stairs	Entire Building	10,286	SF	6	\$3,089	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	2,406	SF	6	\$895	
	Emergency A/C Power - Students Toilets	Entire Building	1,560	SF	6	\$580	
	Emergency Generator- Outdoor- Diesel - 201 - 250 KW	Site West	1	EA	7	\$0	
	Exit Signs - Auditorium	Entire Building / 1st Floor	4	EA	6	\$599	
	Exit Signs - Corridors and Stairs	Entire Building	17	EA	6	\$2,546	
	Exit Signs - Gym	Entire Building / 1st Floor	2	EA	6	\$315	
	Security System - CCTV	Entire Building	56,857	SF	6	\$17,074	
	Security System - Intrusion Detection	Entire Building	56,857	SF	6	\$14,635	
Main Service							
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	1	EA	7	\$0	
	PA System	Entire Building	56,857	SF	6	\$18,700	
Power Distribution							
	Lighting and Power Panels - Above 100 A	Entire Building	7	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	4	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	2004 update
Electrical System Subtotal:						\$61,211	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Mechanical Room	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Mechanical Room / Entire Building	56,857	SF	6	\$20,326	
	Fire Alarm_System	Mechanical Room / Entire Building	56,857	SF	6	\$27,644	
Safty System Subtotal:						\$54,376	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Ground Mounted - Less than 5 tons	1st Floor	1	EA	6	\$3,334	in kindergarden classroom, portable AC unit
	Condensing Unit- Ground Mounted - Less than 5 tons	Electrical Room	1	EA	7	\$0	condensor coil vented out of room through window
Air Handling Systems							
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$71,321	
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - Less than 8000 cfm	Mechanical Room	1	EA	5	\$36,019	
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 8001-12000 cfm	Mechanical Room	1	EA	5	\$34,175	supply for gym
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - Less than 4000 cfm	Mechanical Room	1	EA	5	\$20,373	serves lunchroom located in basement near cafeteria
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Auxiliaries - Greater than 35000 cfm	Mechanical Room	1	EA	6	\$8,716	
	Auxiliaries - Less than 8000 cfm	Mechanical Room	1	EA	6	\$3,321	
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	Attic	1	EA	6	\$2,433	
	Indoor Return Fans- Centrifugal Squirrel Cage - Less than 5000 CFM	Attic	2	EA	6	\$2,564	
	Reheat Boxes - Reheat Boxes with Steam Coil	Mechanical Room / Plenum	11	EA	5	\$47,171	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	200	LF	6	\$0	
	Return Duct Work - Sheet Metal- Exterior Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	5	\$104,477	5 is not a listed option
	Zone Dampers	Mechanical Room / 1st Floor	3	EA	6	\$2,499	
	Zone Dampers	Mechanical Room / Plenum	37	EA	5	\$78,668	
Boiler Systems							
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 151 - 200 HP	Boiler Room	2	EA	5	\$34,033	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	
	Combustion Dampers	Boiler Room	1	EA	6	\$409	
	Condensate Pump	Boiler Room / Mechanical Room	2	EA	5	\$36,392	
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 151 - 200 HP	Boiler Room	2	EA	5	\$34,033	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	300	LF	5	\$3,659	many leaks
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	300	LF	6	\$566	
	Steam Traps	Boiler Room / Entire Building	55	EA	5	\$72,319	
	Vacuum Pump	Boiler Room / Mechanical Room	1	EA	5	\$14,406	
Gas Booster							
	Gas Booster	Boiler Room	2	EA	6	\$998	not used

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Heating Devices							
	Fin Tube - Electric	Entire Building	16	LF	6	\$151	
	Radiators - Steam	Entire Building / Boiler Room	1	EA	4	\$3,657	
	Radiators - Steam	Entire Building	4	EA	6	\$1,111	in bathrooms
	Wall Heater - Electric	Entire Building	2	EA	6	\$278	
	Wall Heater - Electric	Entire Building	4	EA	5	\$2,146	
Temperature Control							
	DDC System	Entire Building	56,857	SF	4	\$360,183	not operational, software upgrade needed, manual controls
	Thermostats - DDC	Entire Building	29	EA	4	\$23,755	damaged, do not work
	Thermostats - DDC	Entire Building	8	EA	6	\$0	
Ventilation							
	Exhaust Fans- Indoor - Greater than 8000 CFM	1st 2nd floor and roof / 2nd Floor	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	1st 2nd floor and roof / Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	1st 2nd floor and roof / Roof	1	EA	4	\$4,245	
	Type I Exhaust Hood- Culinary Arts	1st 2nd floor and roof / 1st Floor	1	EA	6	\$1,248	
Mechanical System Subtotal:						\$1,037,120	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	5	\$2,249	
	Gas Heater - Less than 150000 BTU/HR	Boiler Room	1	EA	6	\$310	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	56,857	SF	6	\$11,383	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	56,857	SF	6	\$13,822	mionor leaks are frequently repaired
	Domestic Piping-Cold Water Risers	Entire Building	56,857	SF	6	\$10,570	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	56,857	SF	6	\$8,944	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	56,857	SF	6	\$10,570	
	Domestic Piping-Hot Water Return Lines	Entire Building	56,857	SF	6	\$8,131	
	Domestic Piping-Hot Water Return Risers	Entire Building	56,857	SF	6	\$8,131	
	Sanitary Piping	Entire Building	56,857	SF	6	\$52,036	
	Storm Piping	Entire Building	56,857	SF	6	\$49,596	
	Vent Piping	Entire Building	56,857	SF	6	\$38,214	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pumps							
	Pumps - Domestic Booster Pump-Simplex	Basement, Boiler Room 1st Floor / Boiler Room	1	EA	6	\$1,446	
	Pumps - Ejector-Simplex	Basement, Boiler Room 1st Floor / Boiler Room	1	EA	6	\$745	
	Pumps - Sump-Simplex	Basement, Boiler Room 1st Floor / 1st Floor	1	EA	6	\$745	
	Pumps - Sump-Simplex	Basement, Boiler Room 1st Floor / Basement	4	EA	6	\$2,980	4 in basement tunnels

Plumbing System Subtotal:

\$219,869

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #101 (Office)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	1st Floor	744	SF	6	\$2,575	
	Chalk Board	1st Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	744	SF	6	\$1,628	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Storage/ Closet	1st Floor	14	SF	6	\$102	
	Walls - Plaster/Drywall	1st Floor	943	SF	6	\$2,603	
Classroom #102 (Pre School)							
	AC Units	1st Floor	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st Floor	1,059	SF	6	\$3,665	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,059	SF	6	\$2,317	
	Lighting - Pendent/Surface	1st Floor	21	EA	6	\$2,602	
	Storage/ Closet	1st Floor	48	SF	6	\$348	
	Walls - Plaster/Drywall	1st Floor	1,607	SF	6	\$4,435	
Classroom #103 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	1st Floor	726	SF	6	\$2,512	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #103 (Regular Classroom)							
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	726	SF	6	\$727	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	16	LF	7	\$0	
	Storage/ Closet	1st Floor	14	SF	6	\$102	
	Walls - Plaster/Drywall	1st Floor	921	SF	6	\$2,542	
Classroom #104 (Kindergarten)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	1st Floor	708	SF	6	\$2,450	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	708	SF	6	\$1,549	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	
	Storage/ Closet	1st Floor	48	SF	6	\$348	
	Walls - Plaster/Drywall	1st Floor	1,011	SF	6	\$2,790	
Classroom #105 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	38	LF	6	\$960	
	Ceiling - Plaster/Drywall	1st Floor	726	SF	6	\$2,512	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	20	LF	7	\$0	
	Storage/ Closet	1st Floor	16	SF	6	\$116	
	Walls - Plaster/Drywall	1st Floor	921	SF	6	\$2,542	
Classroom #106 (Kindergarten)							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	1st Floor	727	SF	6	\$2,516	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	727	SF	6	\$1,591	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	
	Marker Board	1st Floor	20	LF	7	\$0	
	Storage/ Closet	1st Floor	16	SF	6	\$116	
	Student Lockers - One Tier	1st Floor	12	EA	6	\$1,114	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #106 (Kindergarten)							
	Walls - Plaster/Drywall	1st Floor	1,027	SF	6	\$2,834	
Classroom #107 (Regular Classroom)							
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	726	SF	6	\$2,512	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	20	LF	7	\$0	
	Storage/ Closet	1st Floor	16	SF	6	\$116	
	Walls - Plaster/Drywall	1st Floor	3	SF	5	\$15	cracking
	Walls - Plaster/Drywall	1st Floor	918	SF	6	\$2,534	
Classroom #201 (Music Room)							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	744	SF	6	\$2,575	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	744	SF	6	\$1,628	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	943	SF	6	\$2,603	
Classroom #202 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	25	SF	5	\$312	Location: NE corner; water damage
	Ceiling - Plaster/Drywall	2nd Floor	744	SF	6	\$2,575	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	744	SF	5	\$3,341	cracking throughout
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	943	SF	6	\$2,603	
Classroom #203 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #203 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	726	SF	6	\$2,512	
	Chalk Board	2nd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	921	SF	6	\$2,542	
Classroom #204 (Science Classroom)							
	AC Units	2nd Floor	2	EA	7	\$0	
	Casework	2nd Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	2nd Floor	1,056	SF	6	\$3,654	
	Chalk Board	2nd Floor	15	LF	4	\$1,377	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,056	SF	6	\$2,310	
	Lighting - Pendent/Surface	2nd Floor	23	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,101	SF	6	\$3,039	
	Work Sink	2nd Floor	4	EA	6	\$1,516	
Classroom #206 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	726	SF	6	\$2,512	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	726	SF	6	\$727	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	921	SF	6	\$2,542	
	Walls - Plaster/Drywall	2nd Floor	25	SF	5	\$128	Location: West wall; water damage near ceiling
Classroom #207 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	726	SF	6	\$2,512	
	Chalk Board	2nd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #207 (Regular Classroom)							
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	921	SF	6	\$2,542	
Classroom #208 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	726	SF	6	\$2,512	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	921	SF	6	\$2,542	
Classroom #301 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	744	SF	6	\$2,575	
	Chalk Board	3rd Floor	14	LF	4	\$1,285	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	744	SF	6	\$1,628	
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	943	SF	6	\$2,603	
Classroom #302 (Multi Purpose Room)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	3rd Floor	943	SF	6	\$3,263	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	744	SF	5	\$3,341	water damage; tile cracking and warping throughout
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	943	SF	6	\$2,603	
Classroom #303 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #303 (Regular Classroom)							
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
	Walls - Plaster/Drywall	3rd Floor	40	SF	5	\$204	Location: West wall; cracking
Classroom #304 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	6	\$2,512	
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	40	SF	5	\$204	Location: East wall; cracking
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
Classroom #305 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	6	\$2,512	
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	40	SF	5	\$204	Location: West wall; cracking
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
Classroom #306 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	7	\$0	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	726	SF	6	\$1,588	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #306 (Regular Classroom)							
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
	Walls - Plaster/Drywall	3rd Floor	40	SF	5	\$204	Location: East wall; cracking
Classroom #307 (Store Room)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	7	\$0	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	726	SF	4	\$7,018	cracking throughout
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
	Walls - Plaster/Drywall	3rd Floor	40	SF	5	\$204	cracking
Classroom #308 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	6	\$2,512	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
	Walls - Plaster/Drywall	3rd Floor	40	SF	5	\$204	Location: East wall; cracking
Classroom #310 (Computer Lab)							
	AC Units	3rd Floor	2	EA	7	\$0	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	3rd Floor	726	SF	6	\$2,512	
	Chalk Board	3rd Floor	34	LF	4	\$3,121	
	Charging Station	3rd Floor	1	EA	6	\$485	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	921	SF	6	\$2,542	
	Wireless System	3rd Floor	1	EA	6	\$372	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #311 (Other Instructional Use)							
	AC Units	3rd Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	3rd Floor	584	SF	6	\$2,021	
	Chalk Board	3rd Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	584	SF	5	\$2,622	water damage, warping throughout
	Lighting - Pendent/Surface	3rd Floor	11	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	858	SF	6	\$2,368	

Classroom #312 (Art Room)

	AC Units	3rd Floor	2	EA	7	\$0	
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Plaster/Drywall	3rd Floor	25	SF	5	\$312	water damage
	Ceiling - Plaster/Drywall	3rd Floor	1,116	SF	6	\$3,862	
	Chalk Board	3rd Floor	40	LF	4	\$3,672	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,116	SF	6	\$2,442	
	Lighting - Pendent/Surface	3rd Floor	20	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,217	SF	6	\$3,359	
	Work Sink	3rd Floor	1	EA	6	\$379	

Classrooms Subtotal:

\$268,148

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	AC Unit	1st Floor - Room 110	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st Floor - Room 110	364	SF	6	\$1,260	
	Doors - Wood Doors inclu hw	1st Floor - Room 110	1	EA	6	\$301	
	Floor - Tile	1st Floor - Room 110	364	SF	6	\$796	
	Lighting - Pendent/Surface	1st Floor - Room 110	4	EA	6	\$496	
	Power Distribution	1st Floor - Room 110	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	1st Floor - Room 110	720	SF	6	\$1,987	
	Ceiling - Plaster/Drywall	1st Floor- 108 Conference	218	SF	6	\$754	
	Doors - Wood Doors inclu hw	1st Floor- 108 Conference	1	EA	6	\$301	
	Floor - Tile	1st Floor- 108 Conference	218	SF	6	\$477	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Pendent/Surface	1st Floor- 108 Conference	4	EA	6	\$496	
	Power Distribution	1st Floor- 108 Conference	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	1st Floor- 108 Conference	608	SF	6	\$1,678	
	Work Slnk	1st Floor- 108 Conference	1	EA	6	\$508	
	Ceiling - Exposed	1st Floor-Gym Office	88	SF	6	\$131	
	Doors - Wood Doors inclu hw	1st Floor-Gym Office	1	EA	6	\$301	
	Floor - Concrete	1st Floor-Gym Office	88	SF	6	\$47	
	Lighting - Pendent/Surface	1st Floor-Gym Office	1	EA	6	\$124	
	Power Distribution	1st Floor-Gym Office	2	EA	6	\$4,250	
	Walls - Concrete Block	1st Floor-Gym Office	290	SF	6	\$850	
	AC Unit	1st Floor-Main Office	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st Floor-Main Office	443	SF	6	\$1,533	
	Doors - Side-lite	1st Floor-Main Office	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor-Main Office	1	EA	6	\$301	
	Floor - Tile	1st Floor-Main Office	443	SF	6	\$969	
	Lighting - Pendent/Surface	1st Floor-Main Office	9	EA	6	\$1,115	
	Power Distribution	1st Floor-Main Office	10	EA	6	\$21,249	
	Storage/ Closet	1st Floor-Main Office	16	SF	6	\$116	
	Walls - Plaster/Drywall	1st Floor-Main Office	848	SF	6	\$2,340	
	AC Unit	1st Floor-Principal Office	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st Floor-Principal Office	171	SF	6	\$592	
	Doors - Wood Doors inclu hw	1st Floor-Principal Office	1	EA	6	\$301	
	Floor - Tile	1st Floor-Principal Office	171	SF	6	\$374	
	Lighting - Pendent/Surface	1st Floor-Principal Office	94	EA	6	\$11,646	
	Power Distribution	1st Floor-Principal Office	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	1st Floor-Principal Office	443	SF	6	\$1,223	
	AC Unit	2nd Floor - 205 Counselor's Office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor - 205 Counselor's Office	726	SF	6	\$2,512	
	Doors - Wood Doors inclu hw	2nd Floor - 205 Counselor's Office	1	EA	6	\$301	
	Floor - Tile	2nd Floor - 205 Counselor's Office	726	SF	6	\$1,588	
	Lighting - Pendent/Surface	2nd Floor - 205 Counselor's Office	16	EA	7	\$0	
	Power Distribution	2nd Floor - 205 Counselor's Office	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	2nd Floor - 205 Counselor's Office	921	SF	6	\$2,542	
	Ceiling - Plaster/Drywall	2nd Floor - 211 Office	240	SF	6	\$831	
	Doors - Wood Doors inclu hw	2nd Floor - 211 Office	1	EA	6	\$301	
	Floor - Tile	2nd Floor - 211 Office	240	SF	6	\$525	
	Lighting - Pendent/Surface	2nd Floor - 211 Office	2	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	2nd Floor - 211 Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	2nd Floor - 211 Office	480	SF	6	\$1,325	
	Ceiling - Plaster/Drywall	Basement Custodial Breakroom	80	SF	6	\$277	
	Doors - Wood Doors inclu hw	Basement Custodial Breakroom	1	EA	6	\$301	
	Floor - Concrete	Basement Custodial Breakroom	80	SF	6	\$42	
	Lighting - Pendent/Surface	Basement Custodial Breakroom	1	EA	7	\$0	
	Power Distribution	Basement Custodial Breakroom	2	EA	6	\$4,250	
	Walls - Concrete Block	Basement Custodial Breakroom	375	SF	6	\$1,099	
	Ceiling - Plaster/Drywall	Engineer's Office	86	SF	6	\$298	
	Doors - Wood Doors inclu hw	Engineer's Office	1	EA	6	\$301	
	Floor - Wood	Engineer's Office	86	SF	6	\$606	
	Lighting - Pendent/Surface	Engineer's Office	1	EA	7	\$0	
	Power Distribution	Engineer's Office	6	EA	6	\$12,749	
	Walls - Concrete Block	Engineer's Office	168	SF	6	\$492	
	Ceiling - Exposed	Kitchen Office B24	169	SF	6	\$251	
	Doors - Wood Doors inclu hw	Kitchen Office B24	1	EA	6	\$301	
	Floor - Tile	Kitchen Office B24	169	SF	6	\$370	Rubber
	Lighting - Pendent/Surface	Kitchen Office B24	2	EA	6	\$248	
	Power Distribution	Kitchen Office B24	6	EA	6	\$12,749	
	Walls - Concrete Block	Kitchen Office B24	706	SF	6	\$2,070	
	Ceiling - Plaster/Drywall	Office 211	130	SF	6	\$450	
	Doors - Wood Doors inclu hw	Office 211	1	EA	6	\$301	
	Floor - Tile	Office 211	130	SF	6	\$284	
	Lighting - Pendent/Surface	Office 211	92	EA	7	\$0	
	Power Distribution	Office 211	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Office 211	380	SF	6	\$1,049	
Auditorium & Theater							
	Ceiling - Plaster/Drywall	1st Floor - Room 118	588	SF	6	\$4,902	
	Ceiling - Splined	1st Floor - Room 118	1,766	SF	6	\$1,439	
	Doors - Steel Doors incl hw	1st Floor - Room 118	4	EA	6	\$1,204	
	Floor - Concrete	1st Floor - Room 118	1,422	SF	6	\$752	
	Floor - Tile	1st Floor - Room 118	948	SF	6	\$2,074	
	Floor - Wood	1st Floor - Room 118	567	SF	6	\$3,997	
	Lighting - Lay-in	1st Floor - Room 118	50	EA	6	\$5,949	
	Lighting - Pendent/Surface	1st Floor - Room 118	8	EA	6	\$991	
	Main Floor Seating	1st Floor - Room 118	324	EA	6	\$56,349	
	Sound System	1st Floor - Room 118	1	EA	6	\$10,721	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Auditorium & Theater							
	Stage	1st Floor - Room 118	567	SF	6	\$3,276	
	Stage Curtain	1st Floor - Room 118	1	EA	6	\$0	
	Stage Lift	1st Floor - Room 118	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor - Room 118	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor - Room 118	14	LF	6	\$164	
	Storage/ Closet	1st Floor - Room 118	80	SF	6	\$580	
	Storage/ Closet	1st Floor - Room 118	15	SF	6	\$109	
	Storage/ Closet	1st Floor - Room 118	50	SF	6	\$363	
	Walls - Plaster/Drywall	1st Floor - Room 118	2,818	SF	5	\$24,380	water damage on west wall and stage area
	Walls - Structural Glazed Tile	1st Floor - Room 118	1,879	SF	6	\$5,911	
Gymnasia							
	Ceiling - Lay-in	1st Floor	2,406	SF	6	\$7,225	
	Doors - Wood Doors inclu hw	1st Floor	5	EA	6	\$1,505	
	Floor - Wood	1st Floor	2,406	SF	6	\$16,962	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	12	EA	7	\$0	
	Walls - Concrete Block	1st Floor	2,206	SF	6	\$6,467	
	Walls - Structural Glazed Tile	1st Floor	1,280	SF	6	\$4,027	
Library							
	AC Unit	Room 210	2	EA	7	\$0	
	Casework	Room 210	80	LF	6	\$2,020	
	Ceiling - Splined	Room 210	1,372	SF	6	\$1,118	
	Doors - Wood Doors inclu hw	Room 210	2	EA	6	\$602	
	Floor - Carpet	Room 210	1,000	SF	6	\$2,131	
	Floor - Carpet	Room 210	372	SF	4	\$3,905	ripping and stains
	Lighting - Pendent/Surface	Room 210	35	EA	7	\$0	
	Walls - Plaster/Drywall	Room 210	1,259	SF	6	\$3,475	
Lunch & Multipurpose Room							
	AC Unit	Basement	2	EA	6	\$991	
	Ceiling - Splined	Basement	1,888	SF	6	\$1,539	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Tile	Basement	1,888	SF	6	\$4,131	
	Lighting - Pendent/Surface	Basement	44	EA	7	\$0	
	Serving Line	Basement	34	LF	6	\$2,024	
	Walls - Concrete Block	Basement	996	SF	6	\$2,920	
	Walls - Structural Glazed Tile	Basement	368	SF	6	\$1,158	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
MDF_IDF							
	AC Unit	1st Floor - 108B	1	EA	6	\$496	
	Doors - Wood Doors inclu hw	1st Floor - 108B	1	EA	6	\$301	
	Finishes	1st Floor - 108B	132	SF	6	\$942	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	37	SF	6	\$265	north end
	Janitor's Closet	1st Floor	32	SF	6	\$229	south end
	Vaults	1st Floor	55	SF	6	\$394	used for storage Main Office
	Janitor's Closet	2nd Floor	24	SF	6	\$172	203J
	Storage Room	2nd Floor	64	SF	6	\$459	
	Janitor's Closet	3rd Floor	24	SF	6	\$172	
	Storage Room	3rd Floor	64	SF	6	\$459	
	Air Tunnel	Basement	4,500	SF	6	\$27,864	
	Boiler Room	Basement	650	SF	6	\$4,657	
	Mechanical/ Service Rooms	Basement	2,250	SF	6	\$16,120	
	Storage Room	Basement	64	SF	6	\$459	
	Storage Room	Basement	64	SF	6	\$459	
	Storage Room	Basement	64	SF	6	\$459	
	Storage Room	Basement	64	SF	6	\$459	
Restroom							
	Accessories	1st Floor- Men's Restroom	100	SF	6	\$922	
	Ceiling - Plaster/Drywall	1st Floor- Men's Restroom	100	SF	6	\$346	
	Doors - Wood Doors inclu hw	1st Floor- Men's Restroom	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Floor- Men's Restroom	100	SF	6	\$212	
	Lavatory	1st Floor- Men's Restroom	1	EA	6	\$320	
	Lighting - Pendant/Surface	1st Floor- Men's Restroom	2	EA	6	\$248	
	Partitions	1st Floor- Men's Restroom	1	EA	5	\$751	No door provided
	Urinals	1st Floor- Men's Restroom	2	EA	6	\$672	
	Walls - Plaster/Drywall	1st Floor- Men's Restroom	82	SF	6	\$226	
	Walls - Structural Glazed Tile	1st Floor- Men's Restroom	329	SF	6	\$1,035	
	Water Closet	1st Floor- Men's Restroom	1	EA	6	\$336	
	Accessories	1st Floor- Women's Restroom	97	SF	6	\$895	
	Ceiling - Plaster/Drywall	1st Floor- Women's Restroom	97	SF	6	\$336	
	Doors - Wood Doors inclu hw	1st Floor- Women's Restroom	1	EA	6	\$301	
	Floor - Tile	1st Floor- Women's Restroom	97	SF	6	\$212	
	Lavatory	1st Floor- Women's Restroom	1	EA	6	\$320	
	Lighting - Pendant/Surface	1st Floor- Women's Restroom	1	EA	6	\$124	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	1st Floor- Women's Restroom	112	SF	6	\$309	
	Walls - Structural Glazed Tile	1st Floor- Women's Restroom	198	SF	6	\$623	
	Water Closet	1st Floor- Women's Restroom	1	EA	6	\$336	
	Accessories	1st Floor-Boys Restroom	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	1st Floor-Boys Restroom	260	SF	6	\$900	
	Doors - Wood Doors inclu hw	1st Floor-Boys Restroom	1	EA	6	\$301	
	Floor Drain	1st Floor-Boys Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor-Boys Restroom	260	SF	6	\$550	
	Hand Dryer	1st Floor-Boys Restroom	2	EA	6	\$460	
	Lavatory	1st Floor-Boys Restroom	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Floor-Boys Restroom	3	EA	6	\$372	
	Partitions	1st Floor-Boys Restroom	2	EA	6	\$594	
	Walls - Concrete Block	1st Floor-Boys Restroom	67	SF	6	\$196	
	Walls - Plaster/Drywall	1st Floor-Boys Restroom	164	SF	6	\$453	
	Walls - Structural Glazed Tile	1st Floor-Boys Restroom	492	SF	6	\$1,548	
	Water Closet	1st Floor-Boys Restroom	2	EA	6	\$672	
	Accessories	1st Floor-Girls Restroom	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	1st Floor-Girls Restroom	260	SF	6	\$900	
	Doors - Wood Doors inclu hw	1st Floor-Girls Restroom	1	EA	6	\$301	
	Floor Drain	1st Floor-Girls Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor-Girls Restroom	260	SF	6	\$550	
	Hand Dryer	1st Floor-Girls Restroom	2	EA	6	\$460	
	Lavatory	1st Floor-Girls Restroom	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st Floor-Girls Restroom	3	EA	6	\$372	
	Partitions	1st Floor-Girls Restroom	5	EA	6	\$1,485	
	Walls - Concrete Block	1st Floor-Girls Restroom	67	SF	6	\$196	
	Walls - Plaster/Drywall	1st Floor-Girls Restroom	164	SF	6	\$453	
	Walls - Structural Glazed Tile	1st Floor-Girls Restroom	492	SF	6	\$1,548	
	Water Closet	1st Floor-Girls Restroom	5	EA	6	\$1,680	
	Accessories	1st Floor-Main Office Restroom	53	SF	6	\$489	
	Ceiling - Exposed	1st Floor-Main Office Restroom	53	SF	6	\$79	
	Doors - Wood Doors inclu hw	1st Floor-Main Office Restroom	1	EA	6	\$301	
	Floor - Tile	1st Floor-Main Office Restroom	53	SF	6	\$116	
	Lavatory	1st Floor-Main Office Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st Floor-Main Office Restroom	2	EA	6	\$248	
	Partitions	1st Floor-Main Office Restroom	1	EA	6	\$297	
	Walls - Concrete Block	1st Floor-Main Office Restroom	36	SF	6	\$106	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	1st Floor-Main Office Restroom	1	EA	6	\$336	
	Accessories	2nd Floor Boys	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	2nd Floor Boys	260	SF	6	\$900	
	Floor Drain	2nd Floor Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Boys	260	SF	6	\$550	
	Hand Dryer	2nd Floor Boys	2	EA	6	\$460	
	Lavatory	2nd Floor Boys	2	EA	6	\$639	
	Lighting - Lay-in	2nd Floor Boys	1	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor Boys	3	EA	7	\$0	
	Partitions	2nd Floor Boys	2	EA	6	\$594	
	Urinals	2nd Floor Boys	2	EA	6	\$672	
	Walls - Concrete Block	2nd Floor Boys	67	SF	6	\$196	
	Walls - Plaster/Drywall	2nd Floor Boys	164	SF	6	\$453	
	Walls - Structural Glazed Tile	2nd Floor Boys	492	SF	6	\$1,548	
	Water Closet	2nd Floor Boys	2	EA	6	\$672	
	Accessories	2nd Floor Girls	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	2nd Floor Girls	260	SF	6	\$900	
	Floor Drain	2nd Floor Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Girls	260	SF	6	\$550	
	Hand Dryer	2nd Floor Girls	2	EA	6	\$460	
	Lavatory	2nd Floor Girls	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd Floor Girls	3	EA	7	\$0	
	Partitions	2nd Floor Girls	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd Floor Girls	67	SF	6	\$196	
	Walls - Plaster/Drywall	2nd Floor Girls	164	SF	6	\$453	
	Walls - Structural Glazed Tile	2nd Floor Girls	492	SF	6	\$1,548	
	Water Closet	2nd Floor Girls	5	EA	6	\$1,680	
	Accessories	2nd Floor Women's Staff	59	SF	6	\$544	
	Accessories	2nd Floor Women's Staff	59	SF	6	\$544	
	Ceiling - Plaster/Drywall	2nd Floor Women's Staff	59	SF	6	\$204	
	Ceiling - Plaster/Drywall	2nd Floor Women's Staff	59	SF	6	\$204	
	Doors - Wood Doors inclu hw	2nd Floor Women's Staff	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor Women's Staff	1	EA	6	\$301	
	Floor - Tile	2nd Floor Women's Staff	59	SF	6	\$129	
	Floor - Tile/Sheet	2nd Floor Women's Staff	59	SF	6	\$59	
	Lavatory	2nd Floor Women's Staff	1	EA	6	\$320	
	Lavatory	2nd Floor Women's Staff	1	EA	6	\$320	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Pendent/Surface	2nd Floor Women's Staff	1	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor Women's Staff	1	EA	7	\$0	
	Partitions	2nd Floor Women's Staff	2	EA	6	\$594	
	Partitions	2nd Floor Women's Staff	2	EA	6	\$594	
	Walls - Plaster/Drywall	2nd Floor Women's Staff	267	SF	6	\$737	
	Walls - Plaster/Drywall	2nd Floor Women's Staff	267	SF	6	\$737	
	Water Closet	2nd Floor Women's Staff	2	EA	6	\$672	
	Water Closet	2nd Floor Women's Staff	2	EA	6	\$672	
	Accessories	3rd Floor Boys	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	3rd Floor Boys	260	SF	6	\$900	
	Floor Drain	3rd Floor Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Boys	260	SF	6	\$550	
	Hand Dryer	3rd Floor Boys	2	EA	6	\$460	
	Lavatory	3rd Floor Boys	2	EA	6	\$639	
	Lighting - Pendent/Surface	3rd Floor Boys	3	EA	7	\$0	
	Partitions	3rd Floor Boys	2	EA	6	\$594	
	Urinals	3rd Floor Boys	2	EA	6	\$672	
	Walls - Concrete Block	3rd Floor Boys	67	SF	6	\$196	
	Walls - Plaster/Drywall	3rd Floor Boys	164	SF	6	\$453	
	Walls - Structural Glazed Tile	3rd Floor Boys	492	SF	6	\$1,548	
	Water Closet	3rd Floor Boys	2	EA	6	\$672	
	Accessories	3rd Floor Girls	260	SF	6	\$2,398	
	Ceiling - Plaster/Drywall	3rd Floor Girls	260	SF	6	\$900	
	Floor Drain	3rd Floor Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Girls	260	SF	6	\$550	
	Hand Dryer	3rd Floor Girls	2	EA	6	\$460	
	Lavatory	3rd Floor Girls	2	EA	6	\$639	
	Lighting - Pendent/Surface	3rd Floor Girls	3	EA	7	\$0	
	Partitions	3rd Floor Girls	5	EA	6	\$1,485	
	Walls - Concrete Block	3rd Floor Girls	67	SF	6	\$196	
	Walls - Plaster/Drywall	3rd Floor Girls	164	SF	6	\$453	
	Walls - Structural Glazed Tile	3rd Floor Girls	492	SF	6	\$1,548	
	Water Closet	3rd Floor Girls	5	EA	6	\$1,680	
	Accessories	Engineer's Restroom	26	SF	6	\$240	
	Ceiling - Plaster/Drywall	Engineer's Restroom	26	SF	6	\$90	
	Doors - Wood Doors inclu hw	Engineer's Restroom	1	EA	6	\$301	
	Floor - Tile	Engineer's Restroom	26	SF	6	\$57	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	Engineer's Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Engineer's Restroom	2	EA	7	\$0	
	Walls - Concrete Block	Engineer's Restroom	95	SF	6	\$278	
	Water Closet	Engineer's Restroom	1	EA	6	\$336	
	Accessories	In Room 102	47	SF	6	\$434	
	Ceiling - Plaster/Drywall	In Room 102	47	SF	6	\$163	
	Doors - Wood Doors inclu hw	In Room 102	1	EA	6	\$301	
	Floor Drain	In Room 102	1	EA	6	\$1,059	
	Floor - Tile	In Room 102	47	SF	6	\$103	
	Hand Dryer	In Room 102	1	EA	6	\$230	
	Lavatory	In Room 102	1	EA	6	\$320	
	Lighting - Pendent/Surface	In Room 102	2	EA	6	\$248	
	Walls - Plaster/Drywall	In Room 102	271	SF	6	\$748	
	Water Closet	In Room 102	1	EA	6	\$336	
	Accessories	Women's Staff Locker Room Basement	19	SF	6	\$175	
	Ceiling - Exposed	Women's Staff Locker Room Basement	19	SF	6	\$28	
	Doors - Wood Doors inclu hw	Women's Staff Locker Room Basement	1	EA	6	\$301	
	Floor - Concrete	Women's Staff Locker Room Basement	19	SF	6	\$10	
	Lavatory	Women's Staff Locker Room Basement	1	EA	6	\$320	
	Lighting - Pendent/Surface	Women's Staff Locker Room Basement	2	EA	7	\$0	
	Walls - Concrete Block	Women's Staff Locker Room Basement	93	SF	6	\$273	
	Water Closet	Women's Staff Locker Room Basement	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$544,771

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	64	SF	6	\$192	
	Ceiling - Plaster/Drywall	1st Floor	3,712	SF	6	\$22,984	
	Doors - Wood Doors include hw	1st Floor	12	EA	6	\$3,612	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	
	Floor - Terrazzo	1st Floor	42	SF	6	\$353	
	Floor - Tile/Sheet	1st Floor	3,776	SF	6	\$2,052	
	Lighting - Lay-in	1st Floor	64	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	56	EA	6	\$6,938	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Stairs - Terrazzo	1st Floor	5	LF	6	\$46	
	Student Lockers - One Tier	1st Floor	111	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	2,583	SF	6	\$11,450	
	Walls - Structural Glazed Tile	1st Floor	2,583	SF	6	\$8,126	
	Ceiling - Plaster/Drywall	2nd Floor	1,941	SF	5	\$24,453	excessive peeling throughout
	Doors - Wood Doors include hw	2nd Floor	1	EA	6	\$301	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	2nd Floor	1,941	SF	6	\$1,055	
	Lighting - Pendent/Surface	2nd Floor	22	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	125	EA	6	\$11,604	
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$6,206	
	Walls - Structural Glazed Tile	2nd Floor	1,400	SF	6	\$4,404	
	Ceiling - Plaster/Drywall	3rd Floor	1,877	SF	6	\$11,622	
	Doors - Wood Doors include hw	3rd Floor	1	EA	6	\$301	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	3rd Floor	1,877	SF	6	\$1,020	
	Lighting - Pendent/Surface	3rd Floor	22	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	162	EA	6	\$15,039	
	Walls - Plaster/Drywall	3rd Floor	1,316	SF	6	\$5,834	
	Walls - Structural Glazed Tile	3rd Floor	1,316	SF	6	\$4,140	
	Ceiling - Exposed	Basement	1,355	SF	6	\$2,015	
	Floor - Concrete Epoxy/ Painted	Basement	1,355	SF	6	\$659	
	Floor - Tile/Sheet	Basement	259	SF	6	\$141	
	Lighting - Pendent/Surface	Basement	2	EA	6	\$248	
	Walls - Concrete Block	Basement	1,263	SF	5	\$12,968	
Safety							
	Camera Viewing Station		1	EA	6	\$683	
	Security Cameras		10	EA	6	\$1,940	
Stairs							
	Ceiling - Plaster/Drywall	North West	294	SF	6	\$2,153	
	Floor - Terrazzo	North West	175	SF	6	\$1,469	
	Handrails	North West	64	LF	6	\$555	
	Lighting - Pendent/Surface	North West	2	EA	7	\$0	
	Stairs - Terrazzo	North West	32	LF	6	\$297	
	Walls - Concrete Block	North West	96	SF	6	\$281	
	Walls - Plaster/Drywall	North West	481	SF	6	\$1,328	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Ceiling - Plaster/Drywall	Stair North	732	SF	6	\$5,359	
	Floor - Terrazzo	Stair North	385	SF	6	\$3,232	
	Floor - Tile Ceramic/ Porcelain	Stair North	100	SF	6	\$671	
	Handrails	Stair North	93	LF	6	\$806	
	Lighting - Pendent/Surface	Stair North	2	EA	7	\$0	
	Stairs - Terrazzo	Stair North	45	LF	6	\$418	
	Walls - Plaster/Drywall	Stair North	787	SF	6	\$2,577	
	Walls - Plaster/Drywall	Stair North	787	SF	6	\$2,577	
	Ceiling - Plaster/Drywall	Stair South	840	SF	6	\$6,150	
	Floor - Terrazzo	Stair South	541	SF	6	\$4,541	
	Floor - Tile Ceramic/ Porcelain	Stair South	100	SF	6	\$671	
	Floor - Tile/Sheet	Stair South	36	SF	6	\$20	
	Handrails	Stair South	93	LF	6	\$806	
	Lighting - Pendent/Surface	Stair South	2	EA	7	\$0	
	Stairs - Terrazzo	Stair South	45	LF	6	\$418	
	Walls - Plaster/Drywall	Stair South	985	SF	6	\$2,719	
	Walls - Structural Glazed Tile	Stair South	985	SF	6	\$3,099	

Vertical Conveyance

	Elevator - Elevator- Roped Holeless Hydraulic		1	EA	6	\$19,238	
--	---	--	---	----	---	----------	--

Building Interior Subtotal:

\$221,424

Total Building Cost

\$3,101,117

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	2	EA	5	\$5,140	Parking lot CB is above grade, CB near door 2 is clogged
	Civil/ Drainage - Catch Basin	Entire Site	1	EA	6	\$1,094	Location: in crawlspace
	Civil/ Drainage - Catch Basin	Entire Site / Site South	1	EA	6	\$1,094	
Fencing							
	Fencing - Chain Link	Entire Site	862	LF	6	\$16,185	
	Fencing - New Standard Ornamental	Entire Site	233	LF	6	\$7,433	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Landscape							
	Landscape - Grass	Entire Site / Site - East	3,499	SF	6	\$2,902	
	Landscape - Hardscape- Concrete	Entire Site	324	SF	6	\$1,673	
	Parkway trees	Entire Site	18	EA	6	\$11,881	
	Play Area - Asphalt/ Hardscape	Entire Site / North West	7,296	SF	6	\$17,632	
	Retaining Wall - Concrete	Entire Site / Site South	500	SF	6	\$11,719	
Parking Lot							
	Surface - Asphalt	Parking Lot- West	17,552	SF	5	\$80,067	Alligator cracking
	Surface - Concrete	Parking Lot- West	1,100	SF	6	\$2,658	
Playground							
	Equipment - School Age 5-12	Northwest	1	EA	6	\$3,546	
	Surface - Poured Surface	Northwest	2,650	SF	7	\$0	
Sidewalks							
	Sidewalks - Perimeter Sidewalks	Entire Site	14,915	SF	6	\$29,647	
	Sidewalks - Perimeter Sidewalks	Entire Site / Site West	2,375	SF	5	\$19,596	Broken, cracked
Signage							
	Flag Pole - Flag Pole	Southeast	1	EA	7	\$0	
	Marquee - Free Standing Back Lighted	Southeast	1	EA	7	\$0	
Site Subtotal:						\$212,267	
Total Site Cost						\$212,267	
Campus Total ^{2 3}						\$3,313,383	

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
 - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Regular Classroom	3rd Floor	312	312	1,116	4	19	36	108	15	40	Y	N	N
Computer Lab	Regular Classroom	3rd Floor	310	310	726	1	38	72	121	15	40	Y	N	Y
Kindergarten	Regular Classroom	1st Floor	104	104	708	1	0	10	108	42	40	N	N	N
Kindergarten	Regular Classroom	1st Floor	106	106	727	1	1	6	108	42	40	N	Y	N
Multi Purpose Room	Regular Classroom	3rd Floor	302	302	744	1	0	8	132	18	40	Y	N	N
Music Room	Regular Classroom	2nd Floor	201	201	744	1	2	8	132	18	40	Y	N	N
Office	Regular Classroom	1st Floor	101	101	744	1	0	8	132	18	40	Y	Y	N
Other Instructional Use	Regular Classroom	3rd Floor	311	311	584	1	2	4	132	18	40	Y	N	N
Pre School	Regular Classroom	1st Floor	102	102	1,059	1	1	12	162	63	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	103	103	726	1	0	6	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	105	105	726	1	0	8	132	18	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	107	107	726	1	0	6	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	744	1	2	10	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	203	203	726	1	2	6	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	726	1	2	10	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	726	1	2	6	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	726	1	1	9	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	744	1	0	8	132	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	303	303	726	1	0	6	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	304	304	726	1	0	32	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	305	305	726	1	0	20	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	306	306	726	1	0	6	132	18	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	308	308	726	1	0	6	132	18	40	Y	N	N
Science Classroom	Laboratory/Shop	2nd Floor	204	204	1,056	1	2	22	198	27	40	Y	N	Y
Store Room	Regular Classroom	3rd Floor	307	307	726	1	0	6	132	18	40	Y	N	N