

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1926	2	60,092	\$2,940,563
4-Classroom Modular	2013	1	4,158	\$36,958
Addition	1998	2	53,326	\$1,443,252
SITE				\$134,279
Campus Total			117,576	\$4,555,052

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Intranc	e						
	Exterior Doors	12	1	EA	4	\$0	deteriorated
	Exterior Doors - Exterior Steel Door	10	2	EA	5	\$2,683	
	Exterior Doors - Exterior Steel Door	11	2	EA	5	\$2,683	
	Exterior Doors - Exterior Steel Door	12	1	EA	5	\$1,341	
	Exterior Doors - Exterior Steel Door	13	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	14	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	15	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	5	1	EA	7	\$0	
	Exterior Doors - Exterior Steel Door	5	1	EA	5	\$1,341	
	Exterior Doors - Exterior Steel Door	6	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	7	1	EA	4	\$3,823	deteriorating
	Exterior Doors - Exterior Steel Door	8	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	9	2	EA	5	\$2,683	
	Exterior Doors - Exterior Steel Door	Boiler Door	1	EA	5	\$1,341	
	Exterior Doors - Exterior Steel Door	Yard Storage	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	Boiler Room	1	EA	4	\$3,823	deteriorated
	Exterior Doors - Transom Lite	10	2	EA	5	\$1,643	
	Exterior Doors - Transom Lite	11	2	EA	5	\$1,643	



Building: Main

Group	ltem - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrar			. ,				
	Exterior Doors - Transom Lite	12	2	EA	5	\$1,643	
	Exterior Doors - Transom Lite	5	2	EA	5	\$1,643	
	Exterior Doors - Transom Lite	6	2	EA	6	\$627	
	Exterior Doors - Transom Lite	7	1	EA	6	\$313	
	Exterior Doors - Transom Lite	8	2	EA	5	\$1,643	
	Exterior Doors - Transom Lite	9	2	EA	5	\$1,643	
	Exterior Doors - Transom Lite	Boiler Door	2	EA	7	\$0	
	Exterior Stairs - Concrete	6	80	LF	6	\$6,541	
	Exterior Stairs - Concrete	7	20	LF	6	\$1,635	
	Exterior Stairs - Concrete	8	80	LF	6	\$6,541	
	Exterior Stairs - Concrete	9	50	LF	5	\$5,479	
	Exterior Stairs - Stone	10	50	LF	5	\$13,559	
	Exterior Stairs - Stone	11	6	LF	7	\$0	
	Exterior Stairs - Stone	12	23	LF	6	\$2,599	
	Exterior Stairs - Stone	5	50	LF	5	\$13,559	
Found	lation						
	Foundation - Concrete	Entire Building	8	LF	5	\$4,415	Foundation is cracked and spalled, with exposed rebar, allowing seepage into the boiler room. Water infiltration has corroded conduit along walls. Attempts to alleviate water infiltration by building engineer have proved unsuccessful.
	Foundation - Concrete	Entire Building	1,060	LF	7	\$0	
	Superstructure - Concrete	Entire Building	60,092	SF	7	\$0	
Lighti	ng						
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	3	EA	6	\$1,610	
	Exterior Lighting - Wall Mounted	Entire Building	21	EA	6	\$6,064	
Roof S	System						
	Coping - Stone	А	1,004	LF	6	\$32,246	
	Coping - Stone	В	32	LF	6	\$1,028	
	Coping - Stone	С	210	LF	6	\$6,745	
	Downspouts - Exterior Downspouts	А	128	LF	6	\$4,254	
	Downspouts - Interior Downspouts	А	252	LF	6	\$8,375	
	Downspouts - Interior Downspouts	В	32	LF	5	\$7,082	
	Downspouts - Interior Downspouts	С	18	LF	6	\$598	
	Parapet - 16" - 30" Height	А	22	LF	6	\$879	
	Parapet - 16" - 30" Height	С	55	LF	6	\$2,197	



Building: Main

Category: Building Exterior

of System Parapet - Parapet < 16" Height Parapet - Parapet > 30" Parapet - Parapet > 30"	B A	32	LF			
Parapet - Parapet > 30"	А		IE			
				6	\$682	
Parapot Parapot > $20"$	0	563	LF	6	\$35,988	
Falaper - Falaper > 30	C	155	LF	6	\$9,908	
Roof Structure - Concrete	A	34,118	SF	7	\$0	
Roof Structure - Concrete	В	120	SF	7	\$0	
Roof Structure - Concrete	С	2,750	SF	7	\$0	
Roof - Metal	A	1,551	SF	5	\$42,740	
Roof - Modified Bitumen	A	27,773	SF	6	\$261,327	
Roof - Modified Bitumen	В	120	SF	6	\$1,129	
Roof - Modified Bitumen	С	2,750	SF	6	\$25,876	
Roof - Slate Shingle	A	4,794	SF	6	\$41,407	
lls						
Cheek-Wall - Stone	Entire Building	202	SF	6	\$2,071	
Cheek-Wall - Stone	Entire Building / West Façade	78	SF	5	\$1,856	
Cheek-Wall - Stone	Entire Building / West Façade	6	SF	4	\$1,161	cracked
Cornice - Masonry Projecting Limestone	Entire Building	1,099	LF	6	\$38,111	
Cornice - Masonry Projecting Limestone	Entire Building / North Façade	1	LF	5	\$189	
Exterior Walls - Brick	Entire Building	6,050	SF	5	\$127,869	
Exterior Walls - Brick	Entire Building	34,280	SF	6	\$230,396	
Exterior Walls - Stone-Cast	Entire Building	227	SF	5	\$3,999	
Exterior Walls - Stone-Cast	Entire Building	2,041	SF	6	\$13,718	
ndows						
Guard - Guards perforated	Entire Building	1,476	SF	7	\$0	
Guard - Guards perforated	Entire Building / North Façade	24	SF	5	\$368	
Lintels - Steel	Entire Building	705	LF	6	\$20,465	
Skylite - Glass Single-Pane	Entire Building	50	SF	6	\$1,195	
Windows - Sash Aluminum Double-pane	Entire Building	5,130	SF	6	\$38,293	
ilding Exterior Subtotal:				\$	1,080,307	

Building: Main

Category: Electrical System

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Emergency System					
Automatic Transfer Switch	Electrical Room	1	EA	6	\$408
Emergency A/C Power - Corridors and Stairs	Entire Building	14,511	SF	6	\$4,358



Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerge	ency System						
	Emergency Battery Packs - Auditoium and Aisle Lighting	Entire Building / 1st Floor	2	EA	6	\$405	
	Emergency Battery Packs - Corridors and Stairs	Entire Building / 1st Floor	1	EA	6	\$203	
	Exit Signs - Auditoium	Entire Building	6	EA	2	\$3,273	No UPS or generator is installed and exit signs are not equipped with battery backup.
	Exit Signs - Corridors and Stairs	Entire Building	15	EA	2	\$8,182	No UPS or generator is installed and exit signs are not equipped with battery backup.
	Exit Signs - Gym	Entire Building	3	EA	2	\$1,735	No UPS or generator is installed and exit signs are not equipped with battery backup.
Main S	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 1200 A 120/240/3PH	Electrical Room	1	EA	4	\$39,073	Switchgear is greater than 50 years of age and is deteriorated.
Power	Distribution						
	Lighting and Power Panels - 100 A	Entire Building / Boiler Room	1	EA	7	\$0	
	Lighting and Power Panels - 100 A	Entire Building	2	EA	4	\$9,699	
	Lighting and Power Panels - 100 A	Entire Building	5	EA	6	\$1,496	
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	4	\$6,578	
	Lighting and Power Panels - Above 100 A	Entire Building / Mechanical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Mechanical Room	1	EA	6	\$497	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Mechanical Room	1	EA	4	\$13,694	
	Main Distribution Panels - Less than 400 amp	Entire Building	2	EA	4	\$17,638	
Flact	ical System Subtatal					¢110 150	

Electrical System Subtotal:

\$110,158

Building: Main

Category	/:	Safty	System
----------	----	-------	--------

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm						
Fire Alarm Panel	Entire Building / Basement	1	EA	4	\$49,477	Panel is obsolete, in poor condition and cannot be upgraded.
Fire Alarm Panel	Entire Building / Basement	1	EA	7	\$0	
Fire Alarm Strobe Lights	Entire Building	60,092	SF	7	\$0	
Fire Alarm_System	Entire Building	60,092	SF	4	\$119,445	System is obsolete, in poor condition and cannot be upgraded.
Fire Alarm_System	Entire Building	53,326	SF	7	\$0	



Group Item - Type	Location	Quantity Unit Rank	Cost Comments
Safty System Subtotal:		\$1	168,922

Building: Main

Category: Mechanical System

Categ	ory: Mechanical System						
Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Han	dling Systems						
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 15001 - 25000 cfm	Mechanical Room	2	EA	5	\$88,525	
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 4000- 8000 cfm	Mechanical Room	2	EA	5	\$52,885	
	Air Intake	Mechanical Room / Basement	4	EA	4	\$70,463	OA provided when doors to outside on ground level are manually opened.
	Auxiliaries - 15001 - 25000 cfm	Mechanical Room	2	EA	5	\$29,798	
	Reheat Boxes - Reheat Boxes with Steam Coil	Mechanical Room	17	EA	5	\$72,901	
	Return Duct Work - Masonry and Ducts- Missing or Existing Shaft	Mechanical Room / Entire Building	100	LF	2	\$0	No return ductwork exists. Return air is provided from the basement.
	Zone Dampers	Mechanical Room	34	EA	5	\$72,289	
Boiler S	ystems						
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler $$ - 151 - 200 HP	Boiler Room	2	EA	5	\$34,033	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	
	Combustion Dampers	Boiler Room	2	EA	4	\$13,106	Manually operated
	Condensate Pump	Boiler Room	2	EA	5	\$36,392	
	Feed Water Pumps and Tank	Boiler Room	1	EA	5	\$36,450	Pumps in good condition, tank heavily corroded
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 151 - 200 HP	Boiler Room	2	EA	5	\$34,033	Outdated and consume too much fuel.
	Piping - Condensate Pipe- Steel	Boiler Room / Mechanical Room	650	LF	4	\$117,777	Pipes are leaking (multiple pipe clamps on condensate return)
	Piping - Steam Pipe- Steel	Boiler Room / Mechanical Room	650	LF	5	\$9,156	
	Steam Traps	Boiler Room / Mechanical Room	38	EA	5	\$49,966	
Gas Bo	oster						
	Gas Booster	Boiler Room	2	EA	6	\$998	
Heating	Devices						
	Fin Tube - Steam	Entire Building / 2nd Floor	5	LF	5	\$407	
	Radiators - Steam	Entire Building	12	EA	5	\$20,104	
	Unit Heater - Electric	Entire Building	9	EA	6	\$2,500	
	Unit Heater - Gas	Entire Building / Boiler Room	1	EA	5	\$1,527	
	Wall Heater - Electric	Entire Building / Electrical Room	3	EA	6	\$417	



Building: Main

Category: Mechanical System

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
eating	Devices						
empera	ature Control						
	Pneumatic System	Entire Building	60,092	SF	3	\$312,791	Majority of the pneumatic controls do not work. Damper actuators are not working and there are many leaks in pneumatic lines.
	Thermostats - Pneumatic	Entire Building	34	EA	4	\$25,066	Thermostats are not working and cannot be refurbished.
entilati	ion						
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	2	EA	4	\$8,489	Exhaust fan is more than 20 years of age and is working however fan is vibrating. Unit not cost effective to be repaired.
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof	1	EA	4	\$1,942	Exhaust fan is more than 20 years of age and is working however fan is vibrating. Unit not cost effective to be repaired.
lecha	anical System Subtotal:				\$	1,093,093	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lot Wa	ter						
	Gas Heater - 150000 - 300000 BTU/HR	Boiler Room	1	EA	4	\$19,938	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	60,092	SF	6	\$12,030	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	60,092	SF	6	\$14,608	
	Domestic Piping-Cold Water Risers	Entire Building	60,092	SF	6	\$11,171	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	60,092	SF	6	\$9,452	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	60,092	SF	6	\$11,171	
	Domestic Piping-Hot Water Return Lines	Entire Building	60,092	SF	6	\$8,593	
	Domestic Piping-Hot Water Return Risers	Entire Building	60,092	SF	6	\$8,593	
	Sanitary Piping	Entire Building	60,092	SF	6	\$54,996	
	Storm Piping	Entire Building	60,092	SF	6	\$52,418	
	Vent Piping	Entire Building	60,092	SF	6	\$40,388	
umps							
	Pumps - Ejector-Duplex	Mechanical Room	1	EA	6	\$1,387	
	Pumps - Sump-Simplex	Mechanical Room	1	EA	6	\$745	



Category: Plu	mbing	System
---------------	-------	--------

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Plumbing System Subtotal:					\$245,492	
Building: Main						
Category: Classrooms						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #101 (Regular Classroom)						
AC Units	1st Floor	1	EA	7	\$0	
Casework	1st Floor	35	LF	7	\$0	
Ceiling - Plaster/Drywall	1st Floor	800	SF	7	\$0	
Chalk Board	1st Floor	20	LF	4	\$1,836	
Doors - Transom Window	1st Floor	9	SF	7	\$0	
Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
Floor - Wood	1st Floor	800	SF	7	\$0	
Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
Walls - Plaster/Drywall	1st Floor	1,170	SF	7	\$0	
lassroom #102 (Regular Classroom)						
AC Units	1st Floor	1	EA	7	\$0	
Casework	1st Floor	8	LF	7	\$0	
Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
Chalk Board	1st Floor	16	LF	4	\$1,469	
Doors - Transom Window	1st Floor	9	SF	7	\$0	
Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
Floor - Wood	1st Floor	750	SF	7	\$0	
Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
lassroom #103 (Art Room)						
AC Units	1st Floor	1	EA	7	\$0	
Casework	1st Floor	16	LF	7	\$0	
Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
Chalk Board	1st Floor	16	LF	4	\$1,469	
Doors - Transom Window	1st Floor	9	SF	7	\$0	
Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
Floor - Wood	1st Floor	750	SF	7	\$0	
Lighting - Pendent/Surface	1st Floor	12	EA	6	\$1,487	
Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
Work Sink	1st Floor	1	EA	7	\$0	



-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	om #104 (Regular Classroom)		,	•		••••	
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	24	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	24	LF	7	\$0	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Tile/Sheet	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
ssro	om #105 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	16	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	7	\$0	
	Floor - Tile/Sheet	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
ssro	om #106 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	16	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	32	LF	4	\$2,938	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
ssro	om #107 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	24	LF	4	\$2,203	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	7	\$0	



Building: Main

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lassro	om #107 (Regular Classroom)						
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
lassro	om #108 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	12	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	775	SF	7	\$0	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Wood	1st Floor	775	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	925	SF	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	210	SF	7	\$0	brick fireplace decor
lassro	om #109 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	453	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	1	EA	7	\$0	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	6	EA	7	\$0	
	Floor - Wood	1st Floor	453	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	6	EA	6	\$743	
	Storage/ Closet	1st Floor	78	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,134	SF	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	210	SF	7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	
lassro	om #110 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	18	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	32	LF	4	\$2,938	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	



Building: Main

-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	oom #111 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	18	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	40	LF	4	\$3,672	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	7	\$0	
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
Classro	oom #111A (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	450	SF	7	\$0	
	Chalk Board	1st Floor	25	LF	4	\$2,295	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Tile/Sheet	1st Floor	450	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	8	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	890	SF	7	\$0	
Classrc	oom #112 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	12	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
Classrc	oom #113 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	12	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	715	SF	7	\$0	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Wood	1st Floor	715	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	



Building: Main

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ssro	om #113 (Regular Classroom)						
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	
sro	om #114 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	12	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	16	LF	4	\$1,469	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
assro	om #115 (Regular Classroom)						
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	750	SF	7	\$0	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	7	\$0	
	Floor - Wood	1st Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,092	SF	7	\$0	
sro	om #200 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
ssro	om #201 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	

Building: Main

	Item - Type	Location	Quantity	Unit	Pank	Cost	Comments
-		Location	Quantity	Unit	Rank	COST	Comments
Classic	colling Lowin	2nd Floor	760	0E	6	¢0.050	
	Ceiling - Lay-in	2nd Floor 2nd Floor	750	SF LF	6	\$2,252 \$2,672	
	Chalk Board Doors - Transom Window	2nd Floor 2nd Floor	40	LF SF	4 7	\$3,672 \$0	
		2nd Floor 2nd Floor	9			\$0 \$0	
	Doors - Wood Doors inclu hw		2	EA	7		
	Floor - Wood	2nd Floor 2nd Floor	750	SF	7	\$0 \$0	
	Lighting - Pendent/Surface		12	EA	7	\$0 \$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
Classro	oom #202 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	12	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
Classro	oom #203 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
Classro	oom #204 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	6	\$2,252	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0,012	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
			12	_ / (ψυ	



Building: Main

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	om #204 (Regular Classroom)						
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
roc	om #205 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	30	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Floor - Carpet	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
ssroc	om #205A (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	25	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	450	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	7	\$0	
	Floor - Carpet	2nd Floor	450	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	6	EA	7	\$0	
	Storage/ Closet	2nd Floor	8	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	884	SF	7	\$0	
sroc	om #206 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	6	\$2,252	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
sroc	om #207 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	



Building: Main

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
issro	oom #207 (Regular Classroom)						
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
issro	oom #208 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Weight/ Fitness Room Floor Matting	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
ssro	oom #209 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
ssro	oom #210 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	



Bissecond 211 (Regular Classroom) 2xx Floor 1 E 7 \$0 Casework 2xx Floor 720 0 7 \$0 Craite Casy 2xx Floor 730 0 8' 7 \$0 Craite Road Modew 2xx Floor 90 8' 7 \$0 Doors - Transom Window 2xx Floor 90 5'' 7 \$0 Doors - Mood Doors inclu Nw 2xx Floor 90 5'' 7 \$0 Doors - Mood Doors inclu Nw 2xx Floor 1000 5'' 7 \$0 Pioor - Wood 2xx Floor 1000 5'' 7 \$0 ReademStraffic Regular Classroom 1000 5'' 7 \$0 Casework 2xx Floor 1000 5'' 7 \$0 Casework 2xx Floor 1000 5''' 7 \$0 Casework 2xx Floor 1000 5''' 7 \$0 Casework 2xx Floor 1000 5'''' 7 \$0 Casework 2xx Floor 1000 5'''	-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
A Unis 2hr Floor 12 EA 7 \$0 Gaswork 2hr Floor 12 E 7 \$0 Oaling - Lay in 2hr Floor 70 S F 7 \$0 Doos - Trastom Window 2hr Floor 9 S 7 \$0 Doos - Trastom Window 2hr Floor 9 S 7 \$0 Doos - Trastom Window 2hr Floor 12 EA 7 \$0 Doos - Trastom Window 2hr Floor 12 EA 7 \$0 Lighting - PendentSurface 2hr Floor 12 EA 7 \$0 Caller - Casword 2hr Floor 12 EA 7 \$0 Calling - Lay in 2hr Floor 12 EA 7 \$0 Calling - Lay in 2hr Floor 70 12 E 7 \$0 Calling - Lay in 2hr Floor 70 12 E 7 \$0 Doos - Transtom Window 2hr Floor 12 EA 7 \$0 Doos - Transtom Window 2hr Fl	-		200ddon	quantity	Unit		0000	
Casework Centing - Layin Centing - Layin Centing - Layin Centing - Layin Const Transon Window Const Transon WindowProve New Yes Const Transon Window Const Transon	2.40010		2nd Floor	1	EA	7	\$0	
Ching - LayinZin FloorGeFFFSConsik Board2nd Floor2SSSSDoors - Transom Window2nd Floor2SFSDoors - Wood Doors inclu tw2nd Floor70SSSFloor - Wood2nd Floor70SSSLighting - Pendent/Surface2nd Floor10SF7SOWalls - Plaster/Dryvall2nd Floor1STSSA C Units2nd Floor1SF7SOCasework2nd Floor1SF7SOCasework2nd Floor1SF7SOCasework2nd Floor1SF7SODoors - Fransom Window2nd Floor1SF7SODoors - Fransom Window2nd Floor1SF7SODoors - Fransom Window2nd Floor10SF7SODoors - Fransom Window2nd Floor10SF7SODoors - Fransom Window2nd Floor10SF7SODoors - Fransom Window2nd Floor10SF7SODoors - Fransom Window2nd Floor10SF7SOCasework2nd Floor1SF7SOCasework2nd Floor1SF7 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>								
Chair								
Doors - Transent Window2nd Floor98F750Doors - Wood Doors incluit w2nd Floor705F750Lighting - Pendent Startace2nd Floor705F750Walls - Plaster/Dryvall2nd Floor705F750Walls - Plaster/Dryvall2nd Floor105F750Calling - Layin2nd Floor1FA750Calling - Layin2nd Floor12FA750Calling - Layin2nd Floor705F750Doors - Wood Doors incluit w2nd Floor40FF750Doors - Wood Doors incluit w2nd Floor40FF750Doors - Wood Doors incluit w2nd Floor705F750Doors - Wood Doors incluit w2nd Floor705F750Lighting - Pendent/Surface2nd Floor705F750Lighting - Pendent/Surface2nd Floor705F750Walls - Plaster/Drywall2nd Floor705F750Calling - Layin2nd Floor705F750Calling - Layin2nd Floor705F750Calling - Layin2nd Floor705F750Calling - Layin2nd Floor705F750Doors - Franson Window2nd Floor705F750Doors - Franso								
Dors - Wood Dors indu hw 2nd Floor 70 5 7 50 Hoor - Wood 2nd Floor 70 5 7 50 Ughting - Penderu/Surface 2nd Floor 1,022 5 7 50 Vails - Plaster/Dywail 2nd Floor 1,022 5 7 50 Cauring - Lay-in 2nd Floor 1,022 5 7 50 Calling - Lay-in 2nd Floor 1 5 7 50 Calling - Lay-in 2nd Floor 70 5 5 7 50 Calling - Lay-in 2nd Floor 40 15 4 53,672 Doors - Wood Doors indu hw 2nd Floor 20 5 7 50 Doors - Wood 2nd Floor 1007 2 5 7 50 Doors - Wood 2nd Floor 1007 2 5 7 50 Calling - Lay-in 2nd Floor 1007 2 5 7 50 Calling - La					SF			
Floor Wood 2nd Floor 100 970 97 900 Walls Pendent/Surface 2nd Floor 102 24 7 \$30 Walls Pendent/Surface 102 24 7 \$30 Calescort 2nd Floor 12 24 7 \$30 Calescort 2nd Floor 1 24 7 \$30 Calescort 2nd Floor 1 24 7 \$30 Calescort 2nd Floor 1 4 \$357 \$30 Constration 2nd Floor 70 \$16 \$4 \$357 Doors - Transom Window 2nd Floor 7 \$10 \$30 Doors - Wood Doors indu hw 2nd Floor 102 24 7 \$30 Walls - Paster/Drywall 2nd Floor 102 24 7 \$30 Walls - Paster/Drywall 2nd Floor 102 24 \$35,672 Caling - Lay-in 2nd Floor 102 24 \$35								
Liphing - Pendent/Surface 2nd Floor 12 EA 7 S0 Walls - Plaster/Dywall 2nd Floor 1,002 87 7 S0 AL Units 2nd Floor 1 EA 7 S0 Casework 2nd Floor 12 EF 7 S0 Celling - Lay-in 2nd Floor 12 EF 7 S0 Constreame 2nd Floor 40 EF 7 S0 Doors - Mood Doors inclu hw 2nd Floor 40 EF 7 S0 Doors - Mood Doors inclu hw 2nd Floor 70 S1 S0 S0 Ploor - Mood Doors inclu hw 2nd Floor 1092 EF 7 S0 Valls - Plaster/Drywall 2nd Floor 1092 EF 7 S0 Casework 2nd Floor 1092 EF 7 S0 Casework 2nd Floor 1092 EF 7 S0 Casework 2nd Floor 2nd Floor 1092 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>								
Wails Plaster/Dywall 2nd Floor 1,09 S 7 \$0 Hassroom #212 (Regular Classroom) 2nd Floor 1 EA 7 \$0 Casework 2nd Floor 1 EA 7 \$0 Casework 2nd Floor 7 \$0 \$0 \$0 Casework 2nd Floor 7 \$0								
AC Units 2nd Floor 1 EA 7 \$0 Casework 2nd Floor 12 LF 7 \$0 Casework 2nd Floor 12 LF 7 \$0 Caling Lay-in 2nd Floor 10 LF 4 \$3.672 Doors - Transom Window 2nd Floor 9 SF 7 \$0 Doors - Wood Doors inclu hw 2nd Floor 9 SF 7 \$0 Floor - Wood 2nd Floor 7 \$0 \$1 SF 7 \$0 Lighting - Pandent/Surface 2nd Floor 10 SF 7 \$0 Casework 2nd Floor 10 LF 7 \$0 Casework 2nd Floor 10 LF 7 <t\$< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t\$<>								
AC Units 2nd Floor 1 EA 7 S0 Casework 2nd Floor 750 SF 7 S0 Chailk Board 2nd Floor 40 LF 4 \$3,672 Doors - Transom Window 2nd Floor 9 SF 7 S0 Doors - Wood Doors inclu hw 2nd Floor 9 SF 7 S0 Highting - Pendent/Surface 2nd Floor 10,82 SF 7 S0 Lighting - Pendent/Surface 2nd Floor 10,82 SF 7 S0 Casework 2nd Floor 10,82 SF 7 S0 Casework 2nd Floor 10,82 SF 7 S0 Casework 2nd Floor 12 EF 7 S0 Casework 2nd Floor 12 EF 7 S0 Casework 2nd Floor 70 S5 7 S0 Casework 2nd Floor 12 EF 7 S0 Cosemork 2nd Floor 12 EA 7 S0	Classro							
Casework 2nd Floor 12 LF 7 \$0 Caling - Layin 2nd Floor 750 SF 7 \$0 Chalk Board 2nd Floor 40 \$16 4 \$3,672 Doors - Transom Window 2nd Floor 9 SF 7 \$0 Doors - Wood Doors inclu tww 2nd Floor 28 7 \$0 Lighting - Pendent/Surface 2nd Floor 12 EA 7 \$0 Walls - Pleater/Drywall 2nd Floor 109 SF 7 \$0 Casework 2nd Floor 109 SF 7 \$0 Casework 2nd Floor 12 LF 7 \$0 Casework 2nd Floor 750 SF 7 \$0 Caling - Layin 2nd Floor 70 \$1 \$2 \$2 \$0 Doors - Transom Window 2nd Floor 70 \$1 \$3 \$2 \$2 \$0 Chalk Board 2nd Floor 12 LF 7 \$0 \$0 \$2 \$2 \$0 \$2	C185510		2nd Floor	1	FΔ	7	02	
Ceiling - Lay-in 2nd Floor 7 \$0 Chalk Beard 2nd Floor 40 4 \$3,672 Doors - Transom Window 2nd Floor 9 \$F 7 \$0 Doors - Wood Doors inclu hw 2nd Floor 28 7 \$0 Floor - Wood 2nd Floor 70 \$1 \$1 \$1 Lighting - Pendent/Surface 2nd Floor 12 \$2 7 \$0 Walls - Plaster/Drywall 2nd Floor 12 \$2 7 \$0 Ceasework 2nd Floor 12 \$2 7 \$0 Casework 2nd Floor 12 \$2 7 \$0 Casework 2nd Floor 2 \$4 \$7 \$0 Casework 2nd Floor 9 \$5 7 \$0 Colinis 2nd Floor 7 \$1								
Chalk Board 2nd Floor 40 LF 4 \$3,672 Doors - Transom Window 2nd Floor 9 SF 7 \$0 Doors - Wood Doors inclu hw 2nd Floor 2R 7 \$0 Floor - Wood 2nd Floor 70 SF 7 \$0 Hoor - Wood 2nd Floor 70 SF 7 \$0 Walls - Plaster/Dywall 2nd Floor 12 EA 7 \$0 Walls - Plaster/Dywall 2nd Floor 12 EA 7 \$0 Casework 2nd Floor 12 EA 7 \$0 Casework 2nd Floor 7 S0 \$0								
Doors - Transom Window 2nd Floor 9 SF 7 \$0 Doors - Wood Doors inclu hw 2nd Floor 2 EA 7 \$0 Floor - Wood 2nd Floor 750 SF 7 \$0 Lighting - Pendent/Surface 2nd Floor 1,02 SF 7 \$0 Walls - Plaster/Drywall 2nd Floor 1,02 SF 7 \$0 Casework 2nd Floor 2 EA 7 \$0 Casework 2nd Floor 2 EA 7 \$0 Casework 2nd Floor 2 EF 7 \$0 Casework 2nd Floor 2 EF 7 \$0 Casework 2nd Floor 2 EF 7 \$0 Coling - Lay-in 2nd Floor 9 SF 7 \$0 Doors - Wood 2nd Floor 9 SF 7 \$0 Doors - Wood 2nd Floor 1 EA 7 \$0								
Doors - Wood Doors inclu hw2nd Floor2EA7\$0Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor1.092EA7\$0Walls - Plaster/Drywall2nd Floor1.092EA7\$0Casework2nd Floor2EA7\$0Caling - Lay-in2nd Floor2EA7\$0Chalk Board2nd Floor2EF7\$0Conserving - Lay-in2nd Floor12EF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0Doors - Transom Window2nd Floor10EA7\$0Doors - Transom Window2nd Floor10EA7\$0Doors - Transom Window2nd Floor10EA7\$0Doors - Transom Window2nd Floor10EA7\$0Doors - Transom Window2nd Floor10EA7\$0Walls - Plaster/Drywall2nd Floor1EA7\$0Casework2nd Floor <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>								
Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor1,09EA7\$0Walts - Plaster/Drywall2nd Floor1,09SF7\$0Clonguter Lab:A Units2nd Floor2EA7\$0Casework2nd Floor12LF7\$0Casework2nd Floor750SF7\$0Caling - Lay-in2nd Floor750SF7\$0Conduct Doors inclu hw2nd Floor9SF7\$0Doors - Transon Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor9SF7\$0Floor - Wood2nd Floor10EA7\$0Unity - Pendent/Surface2nd Floor10EA7\$0Walts - Plaster/Drywall2nd Floor10EA7\$0Wireless System2nd Floor10EA7\$0Casework2nd Floor10EA7\$0Casework2nd Floor1EA7\$0Caling - Lay-in2nd Floor1EA7\$0Chalk Board2nd Floor1EA7\$0Chalk Board2nd Floor1EA7\$0Coling - Lay-in2nd Floor5F7\$0Chalk Board2nd Floor4EA\$3,672Chalk Board <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>								
Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1,0925F7\$0Clasewort Laby2nd Floor2EA7\$0Casework2nd Floor12LF7\$0Celling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor750SF7\$0Valls - Plaster/Drywall2nd Floor109SF7\$0Vireless System2nd Floor109SF7\$0Vireless System2nd Floor109SF7\$0Casework2nd Floor109SF7\$0Casework2nd Floor109SF7\$0Vireless System2nd Floor109SF7\$0Casework2nd Floor2nd Floor1SF7\$0Casework2nd Floor1SF7\$0\$0Casework2nd Floor1SF7\$0\$0Casework2nd Floor2nd FloorSF7\$0\$0Casework2nd Floor2nd FloorSF7<								
Walls - Plaster/Drywall 2nd Floor 1,092 SF 7 \$0 Ctassroom #213 (Computer Lab) AC Units 2nd Floor 2 EA 7 \$0 AC Units 2nd Floor 12 LF 7 \$0 Casswork 2nd Floor 750 SF 7 \$0 Chalk Board 2nd Floor 40 LF 7 \$0 Doors - Transom Window 2nd Floor 40 LF 4 \$3,672 Doors - Transom Window 2nd Floor 1 EA 7 \$0 Doors - Wood Doors inclu hw 2nd Floor 1 EA 7 \$0 Floor - Wood 2nd Floor 12 EA 7 \$0 Lighting - Pendent/Surface 2nd Floor 102 EA 7 \$0 Wireless System 2nd Floor 10,92 EF 7 \$0 Vireless System 2nd Floor 1,92 EF 7 \$0 Casework 2nd Floor 2nd Floor 1 EA 7 \$0 Casework 2nd					-			
AC Units2nd Floor2EA7\$0Casework2nd Floor12LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3.672Doors - Transom Window2nd Floor40LF7\$0Doors - Wood Doors inclu hw2nd Floor40LF7\$0Floor - Wood2nd Floor19SF7\$0Floor - Wood2nd Floor750SF7\$0Floor - Wood2nd Floor12EA7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1.92SF7\$0Walls - Plaster/Drywall2nd Floor1.92SF7\$0Casework2nd Floor1.92SF7\$0Casework2nd Floor1.92SF7\$0Casework2nd Floor1.92SF7\$0Casework2nd Floor1.92SF7\$0Casework2nd Floor1.92SF7\$0Casework2nd Floor1.92SF7\$0Casework2nd Floor20LF7\$0\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4								
AC Units2nd Floor2EA7\$0Casework2nd Floor12LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor9SF7\$0Floor - Wood2nd Floor1EA7\$0Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Wireless System2nd Floor1,02SF7\$0Wireless System2nd Floor1,02SF7\$0Casework2nd Floor1EA7\$0Casework2nd Floor1,02SF7\$0Casework2nd Floor1EA7\$0Casework2nd Floor20LF7\$0Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor20LF7\$0Chalk Board2nd Floor750SF7\$0Doors - Transom Window2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor40LF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF<			2110 11001	1,092	5	'	φυ	
Casework2nd Floor12LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor1EA7\$0Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor70SF7\$0Walls - Plaster/Drywall2nd Floor10EA7\$0Wireless System2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Casework2nd Floor20LF7\$0\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor40LF4\$3,672	Classro	oom #213 (Computer Lab)						
Ceiling - Lay-in2nd Floor750SF7%0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor1EA7\$0Floor - Wood2nd Floor1EA7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wreless System2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Ceiling - Lay-in2nd Floor2nd Floor1EA7\$0Chalk Board2nd Floor1002SF7\$0\$1Chalk Board2nd Floor1002SF7\$0\$1Chalk Board2nd Floor1EA7\$0\$1Chalk Board2nd Floor1EA7\$0\$1Chalk Board2nd Floor20LF7\$0\$1Casework2nd Floor20LF7\$0\$1Ceiling - Lay-in2nd Floor750SF7\$0\$1Chalk Board2nd Floor40LF4\$3,672\$0\$1Doors - Transom Window2nd Floor9SF7\$0\$1Chalk Board2nd Floor9SF7\$0\$1Chalk		AC Units	2nd Floor	2	EA	7	\$0	
Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor1EA7\$0Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wireless System2nd Floor1,092SF7\$0Chastroch ClassroomClassroomAC Units2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Ceiling - Lay-in2nd Floor1EA7\$0Chalk Board2nd Floor4U\$1\$1\$2Doors - Transon Window2nd Floor1EA7\$0Chalk Board2nd Floor1EA7\$0Chalk Board2nd Floor1EA7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transon Window2nd Floor9SF7\$0		Casework	2nd Floor	12	LF	7	\$0	
Doors - Transom Window2nd Floor9SF7\$0Doors - Wood Doors inclu hw2nd Floor1EA7\$0Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1092SF7\$0Wireless System2nd Floor1EA7\$0Xassrow2nd Floor1EA7\$0Classrow2nd Floor1EA7\$0Classrow2nd Floor1EA7\$0Classrow2nd Floor1EA7\$0Classrow2nd Floor1EA7\$0Classrow2nd Floor1EA7\$0Chalk Board2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0		Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
Doors - Wood Doors inclu hw2nd Floor1EA7\$0Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wireless System2nd Floor1EA7\$0Classroot2nd Floor1EA7\$0Classroot2nd Floor1EA7\$0Classroot2nd Floor1EA7\$0Classroot2nd Floor1EA7\$0Casework2nd Floor10EA7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0		Chalk Board	2nd Floor	40	LF	4	\$3,672	
Floor - Wood2nd Floor750SF7\$0Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wireless System2nd Floor1EA7\$0Classroom#214 (Science Classroom)AC Units2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0		Doors - Transom Window	2nd Floor	9	SF	7	\$0	
Lighting - Pendent/Surface2nd Floor12EA7\$0Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wireless System2nd Floor1EA7\$0Classroom #214 (Science Classroom)AC Units2nd Floor1EA7\$0Casework2nd Floor1EA7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Dors - Transom Window2nd Floor9SF7\$0		Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wireless System2nd Floor1EA7\$0Classroom #214 (Science Classroom)AC Units2nd Floor1EA7\$0Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0		Floor - Wood	2nd Floor	750	SF	7	\$0	
Walls - Plaster/Drywall2nd Floor1,092SF7\$0Wireless System2nd Floor1EA7\$0Classroom #214 (Science Classroom)AC Units2nd Floor1EA7\$0Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0		Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
Wireless System2nd Floor1EA7\$0Classroom #214 (Science Classroom)AC Units2nd Floor1EA7\$0Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0			2nd Floor	1,092	SF	7		
AC Units2nd Floor1EA7\$0Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0		-	2nd Floor	1		7		
AC Units2nd Floor1EA7\$0Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0	Classro	nom #214 (Science Classroom)						
Casework2nd Floor20LF7\$0Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0			2nd Floor	1	EA	7	\$0	
Ceiling - Lay-in2nd Floor750SF7\$0Chalk Board2nd Floor40LF4\$3,672Doors - Transom Window2nd Floor9SF7\$0								
Chalk Board 2nd Floor 40 LF 4 \$3,672 Doors - Transom Window 2nd Floor 9 SF 7 \$0								
Doors - Transom Window 2nd Floor 9 SF 7 \$0								
					0.	,	ψυ	



Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	om #214 (Science Classroom)						
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Lighting - Wall Mounted	2nd Floor	1	EA	7	\$0	gas
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
	Work Sink	2nd Floor	1	EA	7	\$0	
Classro	om #215 (Regular Classroom)						
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
	Chalk Board	2nd Floor	40	LF	4	\$3,672	
	Doors - Transom Window	2nd Floor	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Floor - Wood	2nd Floor	750	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	7	\$0	
Class	ooms Subtotal:					\$96,532	

Building: Main

up Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ninistrative Suites/Offices						
AC Unit	100A	1	EA	7	\$0	
Ceiling - Plaster/Drywall	100A	300	SF	7	\$0	
Doors - Transom Window	100A	9	SF	7	\$0	
Doors - Wood Doors inclu hw	100A	1	EA	7	\$0	
Floor - Tile Ceramic/ Porcelain	100A	459	SF	7	\$0	
Lighting - Pendent/Surface	100A	4	EA	6	\$496	
Power Distribution	100A	2	EA	7	\$0	
Walls - Masonry	100A	616	SF	7	\$0	
Walls - Plaster/Drywall	100A	264	SF	7	\$0	
AC Unit	100B Asst. Principal	1	EA	7	\$0	
Ceiling - Plaster/Drywall	100B Asst. Principal	96	SF	7	\$0	
Doors - Transom Window	100B Asst. Principal	24	SF	7	\$0	
Doors - Wood Doors inclu hw	100B Asst. Principal	1	EA	7	\$0	



Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admin	istrative Suites/Offices						
	Floor - Carpet	100B Asst. Principal	96	SF	7	\$0	
	Lighting - Pendent/Surface	100B Asst. Principal	2	EA	7	\$0	
	Power Distribution	100B Asst. Principal	2	EA	7	\$0	
	Walls - Plaster/Drywall	100B Asst. Principal	546	SF	7	\$0	
	Ceiling - Plaster/Drywall	100C, Counselor	165	SF	7	\$0	
	Doors - Wood Doors inclu hw	100C, Counselor	1	EA	7	\$0	
	Floor - Wood	100C, Counselor	165	SF	7	\$0	
	Lighting - Pendent/Surface	100C, Counselor	2	EA	7	\$0	
	Walls - Plaster/Drywall	100C, Counselor	676	SF	7	\$0	
	AC Unit	105 A Counselor Office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	105 A Counselor Office	390	SF	7	\$0	
	Doors - Transom Window	105 A Counselor Office	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	105 A Counselor Office	1	EA	7	\$0	
	Floor - Carpet	105 A Counselor Office	390	SF	7	\$0	
	Lighting - Pendent/Surface	105 A Counselor Office	6	EA	7	\$0	
	Power Distribution	105 A Counselor Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	105 A Counselor Office	1,144	SF	7	\$0	
	Ceiling - Plaster/Drywall	204A Resource Room	640	SF	7	\$0	
	Doors - Wood Doors inclu hw	204A Resource Room	1	EA	7	\$0	
	Floor - Terrazzo	204A Resource Room	120	SF	7	\$0	stairs
	Floor - Tile Ceramic/ Porcelain	204A Resource Room	640	SF	6	\$1,354	
	Lighting - Pendent/Surface	204A Resource Room	9	EA	7	\$0	
	Power Distribution	204A Resource Room	2	EA	7	\$0	
	Walls - Masonry	204A Resource Room	672	SF	7	\$0	
	Walls - Plaster/Drywall	204A Resource Room	784	SF	7	\$0	
	AC Unit	211 A	1	EA	7	\$0	
	Ceiling - Lay-in	211 A	350	SF	7	\$0	
	Doors - Transom Window	211 A	9	SF	7	\$0	
	Doors - Wood Doors inclu hw	211 A	1	EA	7	\$0	
	Floor - Terrazzo	211 A	350	SF	7	\$0	
	Lighting - Pendent/Surface	211 A	6	EA	7	\$0	
	Walls - Plaster/Drywall	211 A	1,300	SF	7	\$0	
	Ceiling - Plaster/Drywall	Copy Room by Gym	156	SF	7	\$0	
	Doors - Steel Doors incl hw	Copy Room by Gym	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Copy Room by Gym	156	SF	4	\$4,363	patched with concrete
	Lighting - Pendent/Surface	Copy Room by Gym	2	EA	7	\$0	
	Power Distribution	Copy Room by Gym	4	EA	7	\$0	



up Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ninistrative Suites/Offices						
Walls - Concrete Block	Copy Room by Gym	120	SF	7	\$0	
Walls - Masonry	Copy Room by Gym	180	SF	7	\$0	
Walls - Plaster/Drywall	Copy Room by Gym	140	SF	7	\$0	
Ceiling - Plaster/Drywall	Gym Office (Boys' Locker)	459	SF	7	\$0	
Doors - Wood Doors inclu hw	Gym Office (Boys' Locker)	1	EA	7	\$0	
Floor - Tile Ceramic/ Porcelain	Gym Office (Boys' Locker)	459	SF	7	\$0	
Lighting - Pendent/Surface	Gym Office (Boys' Locker)	4	EA	6	\$496	
Power Distribution	Gym Office (Boys' Locker)	2	EA	7	\$0	
Walls - Masonry	Gym Office (Boys' Locker)	616	SF	7	\$0	
Walls - Plaster/Drywall	Gym Office (Boys' Locker)	264	SF	7	\$0	
litorium & Theater						
Balcony Seating	1st Floor	94	EA	7	\$0	
Ceiling - Plaster/Drywall	1st Floor	2,960	SF	7	\$0	
Ceiling - Plaster/Drywall	1st Floor	400	SF	7	\$0	under balcony
Doors - Wood Doors inclu hw	1st Floor	9	EA	7	\$0	
Floor - Concrete	1st Floor	2,320	SF	6	\$1,228	asphalt
Floor - Concrete	1st Floor	315	SF	7	\$0	balcony floor
Floor - Terrazzo	1st Floor	192	SF	7	\$0	
Floor - Wood	1st Floor	600	SF	7	\$0	
Lighting - Pendent/Surface	1st Floor	37	EA	7	\$0	
Main Floor Seating	1st Floor	288	EA	7	\$0	
Sound System	1st Floor	1	EA	7	\$0	
Stage	1st Floor	680	SF	7	\$0	
Stage Curtain	1st Floor	3	EA	7	\$0	
Stage Lighting System	1st Floor	1	EA	7	\$0	
Stage-Stairs - Terrazzo	1st Floor	30	LF	7	\$0	
Stairs - Asphalt	1st Floor	315	LF	7	\$0	concrete
Stairs - Terrazzo	1st Floor	60	LF	7	\$0	
Walls - Plaster/Drywall	1st Floor	7,000	SF	7	\$0	
Walls - Structural Glazed Tile	1st Floor	680	SF	7	\$0	marble wainscott
nnasia						
Ceiling - Lay-in	1st Floor	2,800	SF	7	\$0	
Doors - Transom Window	1st Floor	18	SF	7	\$0	
Doors - Wood Doors inclu hw	1st Floor	3	EA	7	\$0	
Floor - Wood	1st Floor	2,800	SF	7	\$0	
Lighting - Metal Halide/Sodium Vapor	1st Floor	12	EA	7	\$0	



Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymna	sia						
	Scoreboards	1st Floor	1	EA	7	\$0	
	Walls - Masonry	1st Floor	1,540	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	3,520	SF	7	\$0	
MDF_I)F						
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Finishes	2nd Floor	108	SF	7	\$0	
Mechar	nical/ Service Rooms						
	Janitor's Closet	1st Floor	72	SF	6	\$516	by gym and by assembly hall
	Mechanical/ Service Rooms	2nd Floor	72	SF	6		by gym and by assembly hall
	Air Tunnel	Basement	424	SF	5	\$5,645	
	Boiler Room	Basement	2,545	SF	5		Boiler House
	Coal Room	Basement	1,051	SF	5	\$16,953	
	Mechanical/ Service Rooms	Basement	3,186	SF	5	\$51,391	
Restro	om						
	Accessories	100B, Asst. Principal	25	SF	7	\$0	
	Ceiling - Plaster/Drywall	100B, Asst. Principal	25	SF	7	\$0	
	Doors - Wood Doors inclu hw	100B, Asst. Principal	1	EA	7	\$0	
	Floor - Carpet	100B, Asst. Principal	25	SF	7	\$0	
	Lavatory	100B, Asst. Principal	1	EA	7	\$0	
	Lighting - Wall Mounted	100B, Asst. Principal	1	EA	7	\$0	
	Walls - Plaster/Drywall	100B, Asst. Principal	260	SF	7	\$0	
	Water Closet	100B, Asst. Principal	1	EA	7	\$0	
	Accessories	105A	90	SF	7	\$0	
	Ceiling - Plaster/Drywall	105A	90	SF	7	\$0	
	Doors - Wood Doors inclu hw	105A	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	105A	90	SF	7	\$0	
	Lavatory	105A	1	EA	7	\$0	
	Lighting - Pendent/Surface	105A	2	EA	7	\$0	
	Walls - Plaster/Drywall	105A	494	SF	7	\$0	
	Water Closet	105A	1	EA	7	\$0	
	Accessories	109	192	SF	7	\$0	
	Ceiling - Plaster/Drywall	109	191	SF	7	\$0	
	Doors - Transom Window	109	108	SF	7	\$0	
	Doors - Wood Doors inclu hw	109	5	EA	7	\$0	
	Floor - Terrazzo	109	144	SF	7	\$0	
	Floor - Tile Ceramic/ Porcelain	109	48	SF	7	\$0	



p Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
oom						
Lavatory	109	2	EA	7	\$0	
Lighting - Pendent/Surface	109	4	EA	7	\$0	
Partitions	109	2	EA	7	\$0	
Walls - Plaster/Drywall	109	1,584	SF	7	\$0	
Water Closet	109	2	EA	7	\$0	
Accessories	113 A	36	SF	7	\$0	
Ceiling - Plaster/Drywall	113 A	36	SF	7	\$0	
Doors - Wood Doors inclu hw	113 A	1	EA	7	\$0	
Floor - Tile/Sheet	113 A	36	SF	6	\$36	
Lavatory	113 A	1	EA	7	\$0	
Lighting - Pendent/Surface	113 A	1	EA	4	\$541	incandescent
Walls - Plaster/Drywall	113 A	192	SF	7	\$0	
Water Closet	113 A	1	EA	7	\$0	
Accessories	2nd Floor @ Auditorium	84	SF	7	\$0	
Ceiling - Plaster/Drywall	2nd Floor @ Auditorium	84	SF	7	\$0	
Doors - Wood Doors inclu hw	2nd Floor @ Auditorium	1	EA	7	\$0	
Floor - Tile Ceramic/ Porcelain	2nd Floor @ Auditorium	84	SF	7	\$0	
Lavatory	2nd Floor @ Auditorium	2	EA	7	\$0	
Lighting - Pendent/Surface	2nd Floor @ Auditorium	2	EA	7	\$0	
Partitions	2nd Floor @ Auditorium	2	EA	7	\$0	
Walls - Masonry	2nd Floor @ Auditorium	200	SF	7	\$0	
Walls - Plaster/Drywall	2nd Floor @ Auditorium	200	SF	7	\$0	
Water Closet	2nd Floor @ Auditorium	2	EA	7	\$0	
Accessories	Boy's restroom, 1st floor by Assembly Hall	246	SF	7	\$0	
Ceiling - Plaster/Drywall	Boy's restroom, 1st floor by Assembly Hall	246	SF	7	\$0	
Doors - Transom Window	Boy's restroom, 1st floor by Assembly Hall	18	SF	7	\$0	
Doors - Wood Doors inclu hw	Boy's restroom, 1st floor by Assembly Hall	2	EA	6	\$602	
Floor Drain	Boy's restroom, 1st floor by Assembly Hall	1	EA	7	\$0	
Floor - Tile Ceramic/ Porcelain	Boy's restroom, 1st floor by Assembly Hall	246	SF	7	\$0	
Lavatory	Boy's restroom, 1st floor by Assembly Hall	4	EA	7	\$0	
Lighting - Pendent/Surface	Boy's restroom, 1st floor by Assembly Hall	4	EA	7	\$0	



Building: Main

-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om		-				
	Partitions	Boy's restroom, 1st floor by Assembly Hall	2	EA	7	\$0	
	Urinals	Boy's restroom, 1st floor by Assembly Hall	4	EA	7	\$0	
	Walls - Masonry	Boy's restroom, 1st floor by Assembly Hall	270	SF	7	\$0	
	Walls - Plaster/Drywall	Boy's restroom, 1st floor by Assembly Hall	578	SF	7	\$0	
	Walls - Structural Glazed Tile	Boy's restroom, 1st floor by Assembly Hall	156	SF	7	\$0	
	Water Closet	Boy's restroom, 1st floor by Assembly Hall	2	EA	7	\$0	
	Accessories	Boys' Restroom, 1st floor by gym	246	SF	7	\$0	
	Ceiling - Plaster/Drywall	Boys' Restroom, 1st floor by gym	246	SF	7	\$0	
	Doors - Transom Window	Boys' Restroom, 1st floor by gym	18	SF	7	\$0	
	Doors - Wood Doors inclu hw	Boys' Restroom, 1st floor by gym	2	EA	6	\$602	
	Floor Drain	Boys' Restroom, 1st floor by gym	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Boys' Restroom, 1st floor by gym	246	SF	7	\$0	
	Lavatory	Boys' Restroom, 1st floor by gym	2	EA	7	\$0	
	Lighting - Pendent/Surface	Boys' Restroom, 1st floor by gym	4	EA	7	\$0	
	Partitions	Boys' Restroom, 1st floor by gym	2	EA	7	\$0	
	Urinals	Boys' Restroom, 1st floor by gym	4	EA	7	\$0	
	Walls - Masonry	Boys' Restroom, 1st floor by gym	270	SF	7	\$0	
	Walls - Plaster/Drywall	Boys' Restroom, 1st floor by gym	518	SF	7	\$0	
	Walls - Structural Glazed Tile	Boys' Restroom, 1st floor by gym	156	SF	7	\$0	
	Water Closet	Boys' Restroom, 1st floor by gym	2	EA	7	\$0	
	Accessories	Boys' Restroom, 2nd floor by Assembly Hall	246	SF	7	\$0	
	Ceiling - Plaster/Drywall	Boys' Restroom, 2nd floor by Assembly Hall	246	SF	7	\$0	
	Doors - Transom Window	Boys' Restroom, 2nd floor by Assembly Hall	18	SF	7	\$0	
	Doors - Wood Doors inclu hw	Boys' Restroom, 2nd floor by Assembly Hall	2	EA	6	\$602	
	Floor Drain	Boys' Restroom, 2nd floor by Assembly Hall	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Boys' Restroom, 2nd floor by Assembly Hall	246	SF	7	\$0	
	Lavatory	Boys' Restroom, 2nd floor by Assembly Hall	2	EA	7	\$0	



Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Lighting - Pendent/Surface	Boys' Restroom, 2nd floor by Assembly Hall	4	EA	7	\$0	
	Partitions	Boys' Restroom, 2nd floor by Assembly Hall	2	EA	7	\$0	
	Urinals	Boys' Restroom, 2nd floor by Assembly Hall	3	EA	7	\$0	
	Urinals	Boys' Restroom, 2nd floor by Assembly Hall	1	EA	4	\$7,669	has been removed, piping remains
	Walls - Masonry	Boys' Restroom, 2nd floor by Assembly Hall	270	SF	7	\$0	
	Walls - Plaster/Drywall	Boys' Restroom, 2nd floor by Assembly Hall	518	SF	7	\$0	
	Walls - Structural Glazed Tile	Boys' Restroom, 2nd floor by Assembly Hall	156	SF	7	\$0	
	Water Closet	Boys' Restroom, 2nd floor by Assembly Hall	2	EA	7	\$0	
	Accessories	Boys' Restroom, 2nd Floor by gym	246	SF	7	\$0	
	Ceiling - Plaster/Drywall	Boys' Restroom, 2nd Floor by gym	246	SF	7	\$0	
	Doors - Transom Window	Boys' Restroom, 2nd Floor by gym	18	SF	7	\$0	
	Doors - Wood Doors inclu hw	Boys' Restroom, 2nd Floor by gym	2	EA	6	\$602	
	Floor Drain	Boys' Restroom, 2nd Floor by gym	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Boys' Restroom, 2nd Floor by gym	246	SF	7	\$0	
	Lavatory	Boys' Restroom, 2nd Floor by gym	2	EA	7	\$0	
	Lighting - Pendent/Surface	Boys' Restroom, 2nd Floor by gym	4	EA	7	\$0	
	Partitions	Boys' Restroom, 2nd Floor by gym	2	EA	7	\$0	
	Urinals	Boys' Restroom, 2nd Floor by gym	4	EA	7	\$0	
	Walls - Masonry	Boys' Restroom, 2nd Floor by gym	270	SF	7	\$0	
	Walls - Plaster/Drywall	Boys' Restroom, 2nd Floor by gym	518	SF	7	\$0	
	Walls - Structural Glazed Tile	Boys' Restroom, 2nd Floor by gym	156	SF	7	\$0	
	Water Closet	Boys' Restroom, 2nd Floor by gym	2	EA	7	\$0	
	Ceiling - Plaster/Drywall	Engineer's Toilet	14	SF	6	\$48	
	Doors - Wood Doors inclu hw	Engineer's Toilet	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Engineer's Toilet	14	SF	6	\$7	
	Lighting - Pendent/Surface	Engineer's Toilet	1	EA	6	\$124	
	Walls - Plaster/Drywall	Engineer's Toilet	173	SF	5	\$1,311	
	Water Closet	Engineer's Toilet	1	EA	6	\$336	
	Accessories	Girl's Restroom 1st Floor by Assembly Hall	324	SF	7	\$0	
	Ceiling - Plaster/Drywall	Girl's Restroom 1st Floor by Assembly Hall	325	SF	7	\$0	



Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	m						
	Doors - Transom Window	Girl's Restroom 1st Floor by Assembly Hall	18	SF	7	\$0	
	Doors - Wood Doors inclu hw	Girl's Restroom 1st Floor by Assembly Hall	2	EA	6	\$602	
	Floor Drain	Girl's Restroom 1st Floor by Assembly Hall	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Girl's Restroom 1st Floor by Assembly Hall	324	SF	7	\$0	
	Lavatory	Girl's Restroom 1st Floor by Assembly Hall	2	EA	7	\$0	
	Lighting - Pendent/Surface	Girl's Restroom 1st Floor by Assembly Hall	4	EA	7	\$0	
	Partitions	Girl's Restroom 1st Floor by Assembly Hall	5	EA	7	\$0	
	Walls - Masonry	Girl's Restroom 1st Floor by Assembly Hall	240	SF	7	\$0	
	Walls - Plaster/Drywall	Girl's Restroom 1st Floor by Assembly Hall	546	SF	7	\$0	
	Walls - Structural Glazed Tile	Girl's Restroom 1st Floor by Assembly Hall	132	SF	7	\$0	
	Water Closet	Girl's Restroom 1st Floor by Assembly Hall	5	EA	7	\$0	
	Accessories	Girls' Restroom, 1st Floor by gym	324	SF	7	\$0	
	Ceiling - Plaster/Drywall	Girls' Restroom, 1st Floor by gym	324	SF	7	\$0	
	Doors - Transom Window	Girls' Restroom, 1st Floor by gym	18	SF	7	\$0	
	Doors - Wood Doors inclu hw	Girls' Restroom, 1st Floor by gym	2	EA	6	\$602	
	Floor Drain	Girls' Restroom, 1st Floor by gym	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Girls' Restroom, 1st Floor by gym	324	SF	7	\$0	
	Lavatory	Girls' Restroom, 1st Floor by gym	2	EA	7	\$0	
	Lighting - Pendent/Surface	Girls' Restroom, 1st Floor by gym	4	EA	7	\$0	
	Partitions	Girls' Restroom, 1st Floor by gym	5	EA	7	\$0	
	Walls - Masonry	Girls' Restroom, 1st Floor by gym	240	SF	7	\$0	
	Walls - Plaster/Drywall	Girls' Restroom, 1st Floor by gym	546	SF	6	\$1,507	
	Walls - Structural Glazed Tile	Girls' Restroom, 1st Floor by gym	132	SF	7	\$0	
	Water Closet	Girls' Restroom, 1st Floor by gym	5	EA	7	\$0	
	Accessories	Girls' Restroom, 2nd floor by Assembly Hall	324	SF	7	\$0	
	Ceiling - Plaster/Drywall	Girls' Restroom, 2nd floor by Assembly Hall	324	SF	7	\$0	
	Doors - Transom Window	Girls' Restroom, 2nd floor by Assembly Hall	18	SF	7	\$0	



Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Doors - Wood Doors inclu hw	Girls' Restroom, 2nd floor by Assembly Hall	2	EA	6	\$602	
	Floor Drain	Girls' Restroom, 2nd floor by Assembly Hall	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Girls' Restroom, 2nd floor by Assembly Hall	324	SF	7	\$0	
	Lavatory	Girls' Restroom, 2nd floor by Assembly Hall	2	EA	7	\$0	
	Lighting - Pendent/Surface	Girls' Restroom, 2nd floor by Assembly Hall	4	EA	7	\$0	
	Partitions	Girls' Restroom, 2nd floor by Assembly Hall	5	EA	7	\$0	
	Walls - Masonry	Girls' Restroom, 2nd floor by Assembly Hall	240	SF	7	\$0	
	Walls - Plaster/Drywall	Girls' Restroom, 2nd floor by Assembly Hall	546	SF	7	\$0	
	Walls - Structural Glazed Tile	Girls' Restroom, 2nd floor by Assembly Hall	132	SF	7	\$0	
	Water Closet	Girls' Restroom, 2nd floor by Assembly Hall	5	EA	7	\$0	
	Accessories	Girls' Restroom, 2nd Floor by gym	324	SF	7	\$0	
	Ceiling - Plaster/Drywall	Girls' Restroom, 2nd Floor by gym	324	SF	7	\$0	
	Doors - Transom Window	Girls' Restroom, 2nd Floor by gym	18	SF	7	\$0	
	Doors - Wood Doors inclu hw	Girls' Restroom, 2nd Floor by gym	2	EA	6	\$602	
	Floor Drain	Girls' Restroom, 2nd Floor by gym	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Girls' Restroom, 2nd Floor by gym	324	SF	7	\$0	
	Lavatory	Girls' Restroom, 2nd Floor by gym	2	EA	7	\$0	
	Lighting - Pendent/Surface	Girls' Restroom, 2nd Floor by gym	4	EA	7	\$0	
	Partitions	Girls' Restroom, 2nd Floor by gym	5	EA	7	\$0	
	Walls - Masonry	Girls' Restroom, 2nd Floor by gym	240	SF	7	\$0	
	Walls - Plaster/Drywall	Girls' Restroom, 2nd Floor by gym	546	SF	7	\$0	
	Walls - Structural Glazed Tile	Girls' Restroom, 2nd Floor by gym	132	SF	7	\$0	
	Water Closet	Girls' Restroom, 2nd Floor by gym	5	EA	7	\$0	
	Accessories	Men's Auditorium Vest	72	SF	7	\$0	
	Ceiling - Plaster/Drywall	Men's Auditorium Vest	72	SF	7	\$0	
	Floor - Tile Ceramic/ Porcelain	Men's Auditorium Vest	72	SF	7	\$0	
	Lavatory	Men's Auditorium Vest	1	EA	7	\$0	
	Lighting - Pendent/Surface	Men's Auditorium Vest	1	EA	7	\$0	
	Partitions	Men's Auditorium Vest	1	EA	6	\$297	
	Urinals	Men's Auditorium Vest	1	EA	6	\$336	



Category: Rooms (Other Than Classrooms)

Group Item - Ty	/pe	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
Walls - M	<i>l</i> asonry	Men's Auditorium Vest	175	SF	7	\$0	being used at storage
Walls - P	Plaster/Drywall	Men's Auditorium Vest	175	SF	7	\$0	
Water Cl	loset	Men's Auditorium Vest	1	EA	6	\$336	
Accesso	ries	Women's Auditorium Vest	120	SF	7	\$0	
Ceiling -	Plaster/Drywall	Women's Auditorium Vest	120	SF	7	\$0	
Floor - Ti	ile Ceramic/ Porcelain	Women's Auditorium Vest	120	SF	7	\$0	
Lavatory		Women's Auditorium Vest	1	EA	7	\$0	
Lighting	- Pendent/Surface	Women's Auditorium Vest	1	EA	7	\$0	
Partitions	3	Women's Auditorium Vest	1	EA	7	\$0	
Walls - M	<i>l</i> asonry	Women's Auditorium Vest	230	SF	7	\$0	
Walls - P	Plaster/Drywall	Women's Auditorium Vest	230	SF	7	\$0	
Water Cl	oset	Women's Auditorium Vest	1	EA	6	\$336	Being used as an office

Rooms (Other Than Classrooms) Subtotal:

\$142,011

Building: Main

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
orrido	r						
	Ceiling - Plaster/Drywall	Auditorium Entry Vestibule / 1st Floor	154	SF	7	\$0	
	Doors - Wood Doors include hw	Auditorium Entry Vestibule / 1st Floor	2	EA	7	\$0	
	Floor - Terrazzo	Auditorium Entry Vestibule / 1st Floor	154	SF	7	\$0	
	Lighting - Pendent/Surface	Auditorium Entry Vestibule / 1st Floor	1	EA	7	\$0	
	Walls - Plaster/Drywall	Auditorium Entry Vestibule / 1st Floor	600	SF	7	\$0	
	Ceiling - Plaster/Drywall	Corridor 1, 1st floor / 1st Floor	1,248	SF	7	\$0	
	Drinking Fountains - Single Water Cooler	Corridor 1, 1st floor / 1st Floor	2	EA	7	\$0	
	Floor - Terrazzo	Corridor 1, 1st floor / 1st Floor	216	SF	7	\$0	
	Floor - Tile/Sheet	Corridor 1, 1st floor / 1st Floor	1,032	SF	7	\$0	
	Lighting - Pendent/Surface	Corridor 1, 1st floor / 1st Floor	10	EA	7	\$0	
	Student Lockers - One Tier	Corridor 1, 1st floor / 1st Floor	48	EA	7	\$0	
	Walls - Plaster/Drywall	Corridor 1, 1st floor / 1st Floor	2,366	SF	7	\$0	
	Ceiling - Plaster/Drywall	Corridor 1, 2nd floor / 2nd Floor	1,248	SF	7	\$0	
	Drinking Fountains - Single Fountain	Corridor 1, 2nd floor / 2nd Floor	2	EA	7	\$0	
	Floor - Terrazzo	Corridor 1, 2nd floor / 2nd Floor	216	SF	7	\$0	
	Floor - Tile/Sheet	Corridor 1, 2nd floor / 2nd Floor	1,032	SF	7	\$0	
	Lighting - Pendent/Surface	Corridor 1, 2nd floor / 2nd Floor	10	EA	7	\$0	
	Student Lockers - One Tier	Corridor 1, 2nd floor / 2nd Floor	68	EA	7	\$0	



Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	r						
	Walls - Plaster/Drywall	Corridor 1, 2nd floor / 2nd Floor	2,366	SF	7	\$0	
	Ceiling - Plaster/Drywall	Corridor 2, 1st floor / 1st Floor	3,640	SF	7	\$0	
	Drinking Fountains - Single Water Cooler	Corridor 2, 1st floor / 1st Floor	4	EA	7	\$0	
	Floor - Terrazzo	Corridor 2, 1st floor / 1st Floor	520	SF	7	\$0	
	Floor - Tile/Sheet	Corridor 2, 1st floor / 1st Floor	3,120	SF	7	\$0	
	Lighting - Pendent/Surface	Corridor 2, 1st floor / 1st Floor	30	EA	7	\$0	
	Student Lockers - One Tier	Corridor 2, 1st floor / 1st Floor	226	EA	7	\$0	
	Walls - Plaster/Drywall	Corridor 2, 1st floor / 1st Floor	6,370	SF	7	\$0	
	Ceiling - Plaster/Drywall	Corridor 2, 2nd Floor / 2nd Floor	3,640	SF	7	\$0	
	Drinking Fountains - Single Water Cooler	Corridor 2, 2nd Floor / 2nd Floor	4	EA	7	\$0	
	Floor - Terrazzo	Corridor 2, 2nd Floor / 2nd Floor	520	SF	7	\$0	
	Floor - Tile/Sheet	Corridor 2, 2nd Floor / 2nd Floor	3,120	SF	7	\$0	
	Lighting - Pendent/Surface	Corridor 2, 2nd Floor / 2nd Floor	30	EA	7	\$0	
	Student Lockers - One Tier	Corridor 2, 2nd Floor / 2nd Floor	226	EA	7	\$0	
	Walls - Plaster/Drywall	Corridor 2, 2nd Floor / 2nd Floor	6,370	SF	7	\$0	
	Ceiling - Plaster/Drywall	Corridor 3, 1st floor / 1st Floor	480	SF	7	\$0	
	Floor - Terrazzo	Corridor 3, 1st floor / 1st Floor	80	SF	7	\$0	
	Floor - Tile/Sheet	Corridor 3, 1st floor / 1st Floor	400	SF	7	\$0	
	Lighting - Pendent/Surface	Corridor 3, 1st floor / 1st Floor	6	EA	7	\$0	
	Student Lockers - One Tier	Corridor 3, 1st floor / 1st Floor	5	EA	7	\$0	
	Walls - Plaster/Drywall	Corridor 3, 1st floor / 1st Floor	1,040	SF	7	\$0	
	Ceiling - Lay-in	Corridor 3, 2nd floor / 2nd Floor	480	SF	7	\$0	
	Floor - Terrazzo	Corridor 3, 2nd floor / 2nd Floor	80	SF	7	\$0	
	Floor - Tile/Sheet	Corridor 3, 2nd floor / 2nd Floor	400	SF	7	\$0	
	Lighting - Pendent/Surface	Corridor 3, 2nd floor / 2nd Floor	6	EA	7	\$0	
	Student Lockers - One Tier	Corridor 3, 2nd floor / 2nd Floor	5	EA	7	\$0	
	Walls - Plaster/Drywall	Corridor 3, 2nd floor / 2nd Floor	1,040	SF	7	\$0	
	Ceiling - Plaster/Drywall	Vestibule #1	98	SF	7	\$0	
	Doors - Wood Doors include hw	Vestibule #1	2	EA	7	\$0	
	Floor - Terrazzo	Vestibule #1	154	SF	7	\$0	
	Lighting - Pendent/Surface	Vestibule #1	1	EA	7	\$0	
	Walls - Masonry	Vestibule #1	210	SF	7	\$0	
	Walls - Plaster/Drywall	Vestibule #1	126	SF	7	\$0	
	Ceiling - Plaster/Drywall	Vestibule 2, 1st floor / 1st Floor	98	SF	7	\$0	
	Doors - Wood Doors include hw	Vestibule 2, 1st floor / 1st Floor	3	EA	7	\$0	
	Floor - Terrazzo	Vestibule 2, 1st floor / 1st Floor	98	SF	7	\$0	
	Lighting - Pendent/Surface	Vestibule 2, 1st floor / 1st Floor	1	EA	7	\$0	



Building: Main

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	pr						
	Walls - Masonry	Vestibule 2, 1st floor / 1st Floor	210	SF	7	\$0	
	Walls - Plaster/Drywall	Vestibule 2, 1st floor / 1st Floor	126	SF	7	\$0	
	Ceiling - Plaster/Drywall	Vestibule 3, 1st floor / 1st Floor	98	SF	7	\$0	
	Doors - Wood Doors include hw	Vestibule 3, 1st floor / 1st Floor	3	EA	7	\$0	
	Floor - Terrazzo	Vestibule 3, 1st floor / 1st Floor	98	SF	7	\$0	
	Lighting - Pendent/Surface	Vestibule 3, 1st floor / 1st Floor	1	EA	7	\$0	
	Walls - Masonry	Vestibule 3, 1st floor / 1st Floor	210	SF	7	\$0	
	Walls - Plaster/Drywall	Vestibule 3, 1st floor / 1st Floor	126	SF	7	\$0	
	Ceiling - Plaster/Drywall	Vestibule 4	98	SF	7	\$0	
	Doors - Wood Doors include hw	Vestibule 4	2	EA	7	\$0	
	Floor - Terrazzo	Vestibule 4	98	SF	7	\$0	
	Lighting - Pendent/Surface	Vestibule 4	1	EA	7	\$0	
	Walls - Masonry	Vestibule 4	210	SF	7	\$0	
	Walls - Plaster/Drywall	Vestibule 4	126	SF	7	\$0	
	Ceiling - Plaster/Drywall	Vestibule 5	84	SF	7	\$0	
	Doors - Wood Doors include hw	Vestibule 5	2	EA	7	\$0	
	Floor - Terrazzo	Vestibule 5	84	SF	7	\$0	
	Lighting - Pendent/Surface	Vestibule 5	1	EA	7	\$0	
	Walls - Masonry	Vestibule 5	240	SF	7	\$0	
	Walls - Plaster/Drywall	Vestibule 5	96	SF	7	\$0	
afety							
	Camera Viewing Station		2	EA	6	\$1,365	
	Security Cameras		10	EA	6	\$1,940	
airs							
	Ceiling - Plaster/Drywall	Auditorium Balcony Stairs	32	SF	7	\$0	
	Floor - Terrazzo	Auditorium Balcony Stairs	96	SF	7	\$0	
	Handrails	Auditorium Balcony Stairs	30	LF	7	\$0	
	Stairs - Terrazzo	Auditorium Balcony Stairs	76	LF	7	\$0	
	Walls - Plaster/Drywall	Auditorium Balcony Stairs	160	SF	7	\$0	
	Ceiling - Exposed	Stair 1	75	SF	7	\$0	
	Ceiling - Lay-in	Stair 1	392	SF	7	\$0	
	Ceiling - Plaster/Drywall	Stair 1	140	SF	7	\$0	
	Floor - Terrazzo	Stair 1	254	SF	7	\$0	
	Handrails	Stair 1	34	LF	7	\$0	
				EA	7	\$0 \$0	
	Lighting - Pendent/Surface	Stair 1	6				



Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Walls - Plaster/Drywall	Stair 1	1,890	SF	7	\$0	
	Ceiling - Exposed	Stair 2	75	SF	7	\$0	
	Ceiling - Lay-in	Stair 2	392	SF	7	\$0	
	Ceiling - Plaster/Drywall	Stair 2	140	SF	7	\$0	
	Floor - Terrazzo	Stair 2	254	SF	7	\$0	
	Handrails	Stair 2	38	LF	7	\$0	
	Lighting - Pendent/Surface	Stair 2	6	EA	7	\$0	
	Stairs - Terrazzo	Stair 2	231	LF	7	\$0	
	Walls - Plaster/Drywall	Stair 2	1,890	SF	7	\$0	
	Ceiling - Exposed	Stair 3	75	SF	7	\$0	
	Ceiling - Lay-in	Stair 3	392	SF	7	\$0	
	Ceiling - Plaster/Drywall	Stair 3	140	SF	7	\$0	
	Floor - Terrazzo	Stair 3	254	SF	7	\$0	
	Handrails	Stair 3	39	LF	7	\$0	
	Lighting - Pendent/Surface	Stair 3	6	EA	6	\$743	
	Stairs - Terrazzo	Stair 3	231	LF	7	\$0	
	Walls - Plaster/Drywall	Stair 3	1,890	SF	7	\$0	
	Ceiling - Exposed	Stair 4	75	SF	7	\$0	
	Ceiling - Lay-in	Stair 4	392	SF	7	\$0	
	Ceiling - Plaster/Drywall	Stair 4	140	SF	7	\$0	
	Floor - Terrazzo	Stair 4	254	SF	7	\$0	
	Handrails	Stair 4	34	LF	7	\$0	
	Lighting - Pendent/Surface	Stair 4	6	EA	7	\$0	
	Stairs - Terrazzo	Stair 4	203	LF	7	\$0	
	Walls - Plaster/Drywall	Stair 4	1,890	SF	7	\$0	
	Ceiling - Exposed	Stair 5	75	SF	7	\$0	
	Ceiling - Lay-in	Stair 5	192	SF	7	\$0	
	Floor - Terrazzo	Stair 5	174	SF	7	\$0	
	Handrails	Stair 5	32	LF	7	\$0	
	Lighting - Pendent/Surface	Stair 5	2	EA	7	\$0	
	Stairs - Terrazzo	Stair 5	174	LF	7	\$0	
	Walls - Plaster/Drywall	Stair 5	1,188	SF	7	\$0	
Vertical	Conveyance						
	Elevator - Hydraulic Elevator		1	EA	7	\$0	
Buildi	ng Interior Subtotal:					\$4,049	



Total Building Cost

\$2,940,563

	ory: Building Exterior		_			-	-
-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrand	-						
	Entrance Control - Audio and Video	17	1	EA	7	\$0	
	Exterior Doors - Exterior Steel Door	16	2	EA	7	\$0	
	Exterior Doors - Exterior Steel Door	17	2	EA	7	\$0	
Founda	tion						
	Foundation - Concrete	Entire Building	258	LF	7	\$0	
	Superstructure - Metal Deck/ Concrete Topping	Entire Building	4,158	SF	7	\$0	
Lighting	g						
	Exterior Lighting - Wall Mounted	Entire Building	8	EA	7	\$0	
Roof Sy	/stem						
	Downspouts - Exterior Downspouts	Modular Pitched Roof - Roof E	52	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Modular Pitched Roof - Roof E	4,158	SF	7	\$0	
	Roof - Metal	Modular Pitched Roof - Roof E	4,158	SF	7	\$0	
Walls							
	Exterior Walls - Vinyl Siding	Entire Building	3,066	SF	7	\$0	
Windov	vs						
	Guard - Guards perforated	Entire Building	288	SF	7	\$0	
	Lintels - Steel	Entire Building	60	LF	7	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	288	SF	7	\$0	
Buildi	ng Exterior Subtotal:					\$0	
Buildi	ng: 4-Classroom Modular						
Categ	ory: Electrical System						
Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerge	ency System						
	Emergency Battery Packs - Corridors and Stairs	Entire Building	4	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	2	EA	7	\$0	
	Security System - Intrusion Detection	Entire Building / Electrical Room	4,158	SF	6	\$1,070	
Main Se	ervice						
	Main Electrical Service - 800 A and Less than 120/240/3PH	North Facade / North Façade	1	EA	7	\$0	



Building: 4-Classroom Modular

Bulluling. 4-Classicolli Mouulai						
Category: Electrical System						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution						
Lighting and Power Panels - Above 100 A	Entire Building	2	EA	7	\$0	
Electrical System Subtotal:					\$1,070	
Building: 4-Classroom Modular						
Category: Safty System						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Sprinkler System						
Sprinkler Heads	Electrical Room / Entire Building	4,158	SF	6	\$0	
Sprinkler Piping	Electrical Room / Entire Building	4,158	SF	6	\$773	
Wet Sprinkler System	Electrical Room / Entire Building	4,158	SF	6	\$1,070	
Safty System Subtotal:					\$1,843	
Building: 4-Classroom Modular						
Category: Mechanical System						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Temperature Control						
Electric Controls	Entire Building	4	SF	7	\$0	
Unit Ventilation						
Unit Ventilators - Vertical Package Electric Heat & Self Contained Cooling	Entire Building	4	EA	7	\$0	
Ventilation						
Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof	1	EA	6	\$296	
Mechanical System Subtotal:					\$296	
Building: 4-Classroom Modular						
Category: Plumbing System						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water						
Electric Heater - Less than 20 KW	Mechanical Room	1	EA	7	\$0	
Piping						
Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	4,158	SF	6	\$832	
	Dogo 20 of 57					Accomment Date: 0/2



Building: 4-Classroom Modular

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	4,158	SF	6	\$1,011	
	Domestic Piping-Cold Water Risers	Entire Building	4,158	SF	6	\$773	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	4,158	SF	6	\$654	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	4,158	SF	6	\$773	
	Domestic Piping-Hot Water Return Lines	Entire Building	4,158	SF	6	\$595	
	Domestic Piping-Hot Water Return Risers	Entire Building	4,158	SF	6	\$595	
	Sanitary Piping	Entire Building	4,158	SF	6	\$3,805	
	Storm Piping	Entire Building	4,158	SF	6	\$3,627	
	Vent Piping	Entire Building / Electrical Room	4,158	SF	6	\$2,795	

Plumbing System Subtotal:

\$15,459

Building: 4-Classroom Modular

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
oom #M135 (Regular Classroom)						
Casework	1st Floor	3	LF	6	\$76	
Ceiling - Lay-in	1st Floor	800	SF	7	\$0	
Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
Floor - Tile/Sheet	1st Floor	800	SF	6	\$801	
Lighting - Lay-in	1st Floor	12	EA	7	\$0	
Marker Board	1st Floor	12	LF	6	\$257	
Storage/ Closet	1st Floor	76	SF	6	\$551	
Walls - Plaster/Drywall	1st Floor	828	SF	6	\$2,285	
Work Sink	1st Floor	1	EA	7	\$0	
oom #M136 (Regular Classroom)						
Casework	1st Floor	3	LF	7	\$0	
Ceiling - Lay-in	1st Floor	800	SF	7	\$0	
Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0	
Floor - Tile/Sheet	1st Floor	800	SF	6	\$801	
Lighting - Lay-in	1st Floor	12	EA	7	\$0	
Marker Board	1st Floor	12	LF	6	\$257	
Walls - Plaster/Drywall	1st Floor	828	SF	6	\$2,285	
Work Sink	1st Floor	1	EA	7	\$0	
oom #M137 (Regular Classroom)						
Casework	1st Floor	3	LF	7	\$0	



Building: 4-Classroom Modular

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments				
Classro	assroom #M137 (Regular Classroom)										
	Ceiling - Lay-in	1st Floor	800	SF	7	\$0					
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0					
	Floor - Tile/Sheet	1st Floor	800	SF	6	\$801					
	Lighting - Lay-in	1st Floor	12	EA	7	\$0					
	Marker Board	1st Floor	12	LF	6	\$257					
	Storage/ Closet	1st Floor	76	SF	6	\$551					
	Walls - Plaster/Drywall	1st Floor	828	SF	6	\$2,285					
	Work Sink	1st Floor	1	EA	7	\$0					
Classro	om #M138 (Regular Classroom)										
	Casework	1st Floor	3	LF	6	\$76					
	Ceiling - Lay-in	1st Floor	800	SF	7	\$0					
	Doors - Wood Doors inclu hw	1st Floor	1	EA	7	\$0					
	Floor - Tile/Sheet	1st Floor	800	SF	7	\$0					
	Lighting - Lay-in	1st Floor	12	EA	7	\$0					
	Marker Board	1st Floor	12	LF	7	\$0					
	Walls - Plaster/Drywall	1st Floor	828	SF	7	\$0					
	Work Sink	1st Floor	1	EA	7	\$0					

Classrooms Subtotal:

\$11,283

Building: 4-Classroom Modular

oup Iter	m - Type	Location	Quantity	Unit	Rank	Cost	Comments			
echanical/ Service Rooms										
Me	chanical/ Service Rooms	1st Floor	90	SF	6	\$645	Mechanical			
Me	chanical/ Service Rooms	1st Floor	90	SF	6	\$645	Electrical Room			
stroom										
Acc	cessories	Restroom-Boy's Modular	155	SF	7	\$0	mirror, soap and toilet paper dispensers			
Cei	iling - Lay-in	Restroom-Boy's Modular	155	SF	7	\$0				
Doc	ors - Wood Doors inclu hw	Restroom-Boy's Modular	1	EA	7	\$0				
Flo	or Drain	Restroom-Boy's Modular	1	EA	6	\$1,059				
Flo	or - Tile/Sheet	Restroom-Boy's Modular	155	SF	6	\$155				
Har	nd Dryer	Restroom-Boy's Modular	1	EA	6	\$230				
Lav	vatory	Restroom-Boy's Modular	1	EA	6	\$320				
Ligi	hting - Lay-in	Restroom-Boy's Modular	1	EA	7	\$0				
Par	rtitions	Restroom-Boy's Modular	1	EA	6	\$297				



Building: 4-Classroom Modular

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments					
Restro	Restroom											
	Urinals	Restroom-Boy's Modular	2	EA	7	\$0						
	Walls - Vinyl Coated Gypsum Panel	Restroom-Boy's Modular	377	SF	7	\$0						
	Water Closet	Restroom-Boy's Modular	2	EA	7	\$0						
	Accessories	Restroom-Gir'ls Modular	165	SF	7	\$0	mirror, soap and toilet paper dispensers					
	Ceiling - Lay-in	Restroom-Gir'ls Modular	165	SF	7	\$0						
	Doors - Wood Doors inclu hw	Restroom-Gir'ls Modular	1	EA	7	\$0						
	Floor Drain	Restroom-Gir'ls Modular	1	EA	6	\$1,059						
	Floor - Tile/Sheet	Restroom-Gir'ls Modular	165	SF	7	\$0						
	Hand Dryer	Restroom-Gir'ls Modular	1	EA	7	\$0						
	Lavatory	Restroom-Gir'ls Modular	2	EA	7	\$0						
	Lighting - Lay-in	Restroom-Gir'ls Modular	2	EA	7	\$0						
	Partitions	Restroom-Gir'ls Modular	4	EA	6	\$1,188						
	Walls - Vinyl Coated Gypsum Panel	Restroom-Gir'ls Modular	390	SF	6	\$1,076						
	Water Closet	Restroom-Gir'ls Modular	4	EA	7	\$0						
	Accessories	Restroom-Unisex Modular	47	SF	7	\$0	soap dispenser and mirror					
	Ceiling - Lay-in	Restroom-Unisex Modular	47	SF	7	\$0						
	Doors - Wood Doors inclu hw	Restroom-Unisex Modular	1	EA	7	\$0						
	Floor Drain	Restroom-Unisex Modular	1	EA	7	\$0						
	Floor - Tile/Sheet	Restroom-Unisex Modular	47	SF	7	\$0						
	Hand Dryer	Restroom-Unisex Modular	1	EA	7	\$0						
	Lavatory	Restroom-Unisex Modular	1	EA	7	\$0						
	Lighting - Lay-in	Restroom-Unisex Modular	1	EA	7	\$0						
	Walls - Vinyl Coated Gypsum Panel	Restroom-Unisex Modular	198	SF	7	\$0						
	Water Closet	Restroom-Unisex Modular	1	EA	7	\$0						
						* • • = •						

Rooms (Other Than Classrooms) Subtotal:

\$6,674

Building: 4-Classroom Modular

Group	Item - Type	Location	Quantity	Unit	Rank	Cost Co	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	612	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	4	EA	7	\$0	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	7	\$0	
	Floor - Tile/Sheet	1st Floor	612	SF	6	\$333	
	Lighting - Lay-in	1st Floor	7	EA	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	1,109	SF	7	\$0	



Building: 4-Classroom Modular

Category: Building Interior				
Group Item - Type	Location	Quantity Unit Rank	Cost Comments	
Corridor				
Building Interior Subtotal:			\$333	
Total Building Cost		\$3(6,958	

Total Building Cost

Building: Addition

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entran	ce						
	Exterior Doors - Exterior Steel Door	15	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	3	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	3.1	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	4	2	EA	6	\$961	
	Exterior Doors - Side lite	1	4	EA	7	\$0	
	Exterior Doors - Store Front	1	2	EA	7	\$0	
	Exterior Doors - Store Front	2	2	EA	6	\$1,092	
	Exterior Doors - Transom Lite	1	2	EA	7	\$0	
	Exterior Doors - Transom Lite	2	2	EA	7	\$0	
Founda	ation						
	Foundation - Concrete	Entire Building	929	LF	7	\$0	
	Superstructure - Metal Deck/ Concrete Topping	Entire Building	53,326	SF	7	\$0	
Lightin	g						
	Exterior Lighting - Wall Mounted	Entire Building	15	EA	7	\$0	
	Exterior Lighting - Wall Mounted	Entire Building	4	EA	6	\$1,155	
Roof S	ystem						
	Coping - Stone	D	933	LF	6	\$29,966	
	Downspouts - Interior Downspouts	D	544	LF	6	\$18,079	
	Parapet - 16" - 30" Height	D	633	LF	6	\$25,291	
	Parapet - Parapet > 30"	D	300	LF	6	\$19,176	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	D	31,148	SF	7	\$0	
	Roof - Modified Bitumen	D	31,148	SF	6	\$293,084	
Walls							
	Exterior Walls - Brick	Entire Building	25,022	SF	7	\$0	
	Exterior Walls - Brick	Entire Building	253	SF	6	\$2,297	



Building: Addition

Category: Building Exterior

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls						
Exterior Walls - Stone-Cast	Entire Building	929	SF	6	\$6,244	
Windows						
Guard - Guards wire guard	Entire Building	2,340	SF	7	\$0	
Lintels - Steel	Entire Building	579	LF	6	\$16,808	
Windows - Decorative	Entire Building	288	SF	7	\$0	
Windows - Louver	Entire Building / North	240	SF	7	\$0	
Windows - Sash Aluminum Double-pane	Entire Building	60	SF	5	\$3,232	
Windows - Sash Aluminum Double-pane	Entire Building	4,374	SF	7	\$0	
Building Exterior Subtotal:					\$419,788	

Building Exterior Subtotal:

Building: Addition

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerge	ency System						
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	12,708	SF	6	\$3,816	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	10	EA	7	\$0	
	Emergency Battery Packs - Multipurpose Room	Entire Building / 1st Floor	3	EA	7	\$0	
	Emergency Battery Packs - Students Toilets	Entire Building	4	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	16	EA	7	\$0	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	3	EA	7	\$0	
	Security System - CCTV	Entire Building	113,418	SF	6	\$34,059	
	Security System - Intrusion Detection	Entire Building	113,418	SF	6	\$29,194	
Main S	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	1	EA	7	\$0	
	PA System	Entire Building	117,576	SF	6	\$38,671	Room 205A, old library was split in half such that small room does not have PA service.
Power	Distribution						
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	12	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	



Building: Addition

Category: Electrical System						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Electrical System Subtotal:					\$107,413	
Building: Addition						
Category: Safty System						
Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm						
Fire Alarm Strobe Lights	Entire Building	53,326	SF	7	\$0	
Fire Pump Controller	Entire Building / Mechanical Room	1	EA	6	\$1,823	Fire pump room was not accessible at the time of assessment due to construction and therefore ranking remains from previous assessment.
Pump Room Assembly						
Fire Pump - 25-50 hp	Mechanical Room	1	EA	7	\$0	Fire pump room was not accessible at the time of assessment due to construction and therefore ranking remains from previous assessment.
Jockey Pump	Mechanical Room	1	EA	7	\$0	Fire pump room was not accessible at the time of assessment due to construction and therefore ranking remains from previous assessment.
Sprinkler System						
Sprinkler Heads	Entire Building	53,326	SF	7	\$0	
Sprinkler Piping	Entire Building	53,326	SF	7	\$0	
Wet Sprinkler System	Entire Building	53,326	SF	7	\$0	
Safty System Subtotal:					\$1,823	
Building: Addition						
Category: Mechanical System						

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Cor	nditioning						
	Chemical Pot Feeder	Roof / Boiler Room	1	EA	5	\$1,685	
	Chiller-Air Cooled-Screw Type-Roof Mounted - 201 - 300 tons	Roof	1	EA	5	\$70,096	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	2	EA	4	\$22,267	Significant degradation and deformation.
	Glycol Feed	Roof / Boiler Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Galvanized	Roof / Mechanical Room	200	LF	7	\$0	
Air Han	Idling Systems						
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	7	\$0	



Building: Addition

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments		
Air Han	Air Handling Systems								
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 8001-12000 cfm	Mechanical Room	1	EA	7	\$0			
	Air Intake	Mechanical Room / North Façade	2	EA	7	\$0			
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building	44	EA	7	\$0			
	Make Up Air Unit- Roof Mounted- Gas Heating - Less than 6000 cfm	Roof	1	EA	6	\$3,350			
	VAV Box	Mechanical Room / Entire Building	6	EA	7	\$0			
Boiler S	Systems								
	Boiler Auxiliary- Non Condensing Hot Water - 1001 - 2000 MBH	Boiler Room	2	EA	6	\$4,093			
	Chemical Pot Feeder	Boiler Room	1	EA	5	\$1,685			
	Combustion Dampers	Boiler Room	2	EA	7	\$0			
	Glycol Feed System	Boiler Room	1	EA	6	\$539			
	Hot Water Pump	Boiler Room	2	EA	5	\$9,407			
	Non Condensing- Flexible Tube- Atmospheric- Hot Water Boiler - 1001 - 2000 MBH	Boiler Room	2	EA	5	\$93,399			
Gas Bo	oster								
	Gas Booster	Boiler Room	2	EA	6	\$998			
Heating	Devices								
	Unit Heater - Hot Water	Boiler Room	2	EA	6	\$558			
Mechar	ical Plumbing								
	Chilled Water Pump - 10 - 20 HP	Mechanical Room / 2nd Floor	2	EA	6	\$2,485			
	Hot Water Pump - Less than 10	Mechanical Room	2	EA	6	\$2,222			
Temper	ature Control								
	DDC System	Entire Building	53,326	SF	7	\$0			
	Thermostats - DDC	Entire Building	50	EA	7	\$0			
Ventilat	ion								
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	6	\$592			
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	4	\$6,392			
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	1	EA	4	\$4,245			
	Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Entire Building / Roof	2	EA	6	\$1,185			
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	7	\$0			
Moch	anical System Subtotal:					\$225 689			

Mechanical System Subtotal:

\$225,689

Building: Addition



Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lot Wat	ter						
	Gas Heater - 150000 - 300000 BTU/HR	Boiler Room	2	EA	7	\$0	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	53,326	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	53,326	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	53,326	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	53,326	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	53,326	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	53,326	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	53,326	SF	7	\$0	
	Sanitary Piping	Entire Building	53,326	SF	7	\$0	
	Storm Piping	Entire Building	53,326	SF	7	\$0	
	Vent Piping	Entire Building	53,326	SF	7	\$0	
lumb	bing System Subtotal:					\$0	

Building: Addition

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	om #125 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		30	SF	4	\$422	water damage
	Ceiling - Lay-in		861	SF	7	\$0	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		891	SF	6	\$892	
	Lighting - Lay-in		12	EA	6	\$1,428	
	Walls - Concrete Block		975	SF	6	\$2,858	
	Walls - Plaster/Drywall		303	SF	6	\$836	
	Work Sink		1	EA	7	\$0	
Classro	om #126 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		15	SF	5	\$120	water damage
	Ceiling - Lay-in		880	SF	6	\$2,643	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	

Category: Classrooms

-					_		
	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #126 (Regular Classroom)						
	Floor - Tile/Sheet		895	SF	7	\$0	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		675	SF	6	\$1,979	
	Walls - Plaster/Drywall		606	SF	6	\$1,672	
	Work Sink		1	EA	7	\$0	
Classro	oom #127 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		891	SF	6	\$2,676	
	Ceiling - Lay-in		10	SF	4	\$141	water damage
	Chalk Board		20	LF	4	\$1,836	-
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		901	SF	6	\$902	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		680	SF	6	\$1,993	
	Walls - Plaster/Drywall		606	SF	6	\$1,672	
	Work Sink		1	EA	7	\$0	
Classro	oom #128 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		897	SF	7	\$0	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		897	SF	6	\$898	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		667	SF	6	\$1,955	
	Walls - Plaster/Drywall		606	SF	6	\$1,672	
	Work Sink		1	EA	7	\$0	
Classro	oom #129 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		893	SF	6	\$2,682	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		893	SF	6	\$894	
	Lighting - Lay-in		12	EA	7	\$0	
			893	SF	6	\$894	

Building: Addition

-	ory: Classrooms						
	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lassro	oom #129 (Regular Classroom)						
	Walls - Concrete Block		664	SF	6	\$1,947	
	Walls - Plaster/Drywall		606	SF	6	\$1,672	
	Work Sink		1	EA	7	\$0	
lassro	oom #130 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		836	SF	6	\$2,511	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		836	SF	6	\$837	
	Lighting - Lay-in		12	EA	6	\$1,428	
	Marker Board		3	LF	6	\$64	
	Walls - Concrete Block		920	SF	6	\$2,697	
	Walls - Plaster/Drywall		303	SF	6	\$836	
	Work Sink		1	EA	6	\$379	
lassro	oom #131 (Pre School)						
	Casework		17	LF	6	\$429	
	Ceiling - Lay-in		999	SF	7	\$0	
	Chalk Board		12	LF	4	\$1,102	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		2	EA	7	\$0	
	Floor - Tile/Sheet		999	SF	6	\$1,000	
	Lighting - Lay-in		17	EA	7	\$0	
	Storage/ Closet		90	SF	6	\$653	
	Walls - Concrete Block		1,087	SF	6	\$3,187	
	Walls - Plaster/Drywall		303	SF	6	\$836	
	Work Sink		2	EA	7	\$0	
lassro	oom #132 (Regular Classroom)						
	Casework	1st Floor	17	LF	6	\$429	
	Ceiling - Lay-in	1st Floor	999	SF	7	\$0	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	7	SF	6	\$117	
	Doors - Wood Doors inclu hw	1st Floor	3	EA	6	\$903	
	Floor - Carpet	1st Floor	999	SF	6	\$2,129	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	/			SF			

Building: Addition

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	oom #132 (Regular Classroom)						
	Walls - Concrete Block	1st Floor	657	SF	6	\$1,926	
	Walls - Plaster/Drywall	1st Floor	610	SF	6	\$1,684	
	Work Sink	1st Floor	1	EA	7	\$0	
assro	oom #133 (Kindergarten)						
	Casework		18	LF	6	\$455	
	Ceiling - Lay-in		1,071	SF	6	\$3,216	
	Chalk Board		10	LF	4	\$918	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		1,071	SF	6	\$1,072	
	Lighting - Lay-in		17	EA	7	\$0	
	Storage/ Closet		40	SF	6	\$290	
	Walls - Concrete Block		750	SF	6	\$2,199	
	Walls - Plaster/Drywall		596	SF	6	\$1,645	
	Work Sink		2	EA	7	\$0	
assro	oom #134 (Regular Classroom)						
	Casework		17	LF	6	\$429	
	Ceiling - Lay-in		960	SF	6	\$2,883	
	Chalk Board		12	LF	4	\$1,102	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile		960	SF	7	\$0	
	Lighting - Lay-in		17	EA	7	\$0	
	Storage/ Closet		138	SF	6	\$1,001	
	Walls - Concrete Block		1,025	SF	6	\$3,005	
	Walls - Plaster/Drywall		305	SF	6	\$842	
	Work Sink		1	EA	7	\$0	
assro	oom #221 (Regular Classroom)						
	Casework		16	LF	6	\$404	
	Ceiling - Lay-in		372	SF	7	\$0	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		372	SF	7	\$0	
	Lighting - Lay-in		6	EA	6	\$714	
	Walls - Concrete Block		457	SF	6	\$1,340	
	Walls - Plaster/Drywall		248	SF	6	\$684	

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	oom #221 (Regular Classroom)						
Classro	oom #222 (Regular Classroom)			. –			
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		894	SF	6	\$2,685	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		894	SF	6	\$895	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		585	SF	6	\$1,715	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	7	\$0	
Classro	oom #223 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		894	SF	6	\$2,685	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		894	SF	6	\$895	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		585	SF	6	\$1,715	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	7	\$0	
Classro	oom #224 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		894	SF	6	\$2,685	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		894	SF	6	\$895	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		585	SF	6	\$1,715	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	6	\$379	
Classro	oom #225 (Regular Classroom)						
510351	Casework		38	LF	6	\$960	
					č	ψυ00	

Building: Addition

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	oom #225 (Regular Classroom)						
	Ceiling - Lay-in		10	SF	4	\$141	water damage
	Ceiling - Lay-in		884	SF	6	\$2,655	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		894	SF	6	\$895	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		585	SF	6	\$1,715	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	6	\$379	
Classro	oom #226 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		891	SF	7	\$0	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		891	SF	6	\$892	
	Lighting - Lay-in		12	EA	6	\$1,428	
	Marker Board		10	LF	6	\$214	
	Walls - Concrete Block		465	SF	6	\$1,363	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	7	\$0	
Classro	oom #227 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		930	SF	7	\$0	
	Chalk Board		10	LF	4	\$918	
	Doors - Side-lite		7	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		930	SF	6	\$931	
	Lighting - Lay-in		12	EA	7	\$0	
	Marker Board		10	LF	6	\$214	
	Walls - Concrete Block		465	SF	6	\$1,363	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	7	\$0	
Classro	oom #228 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		20	SF	4	\$281	water damage

Building: Addition

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	oom #228 (Regular Classroom)						
	Ceiling - Lay-in		908	SF	6	\$2,727	
	Chalk Board		10	LF	4	\$918	
	Doors - Transom Window		7	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		928	SF	6	\$929	
	Lighting - Lay-in		12	EA	7	\$0	
	Marker Board		10	LF	6	\$214	
	Walls - Concrete Block		465	SF	6	\$1,363	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	7	\$0	
assro	oom #229 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		835	SF	7	\$0	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		835	SF	6	\$836	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		793	SF	6	\$2,325	
	Walls - Plaster/Drywall		249	SF	6	\$687	
assro	oom #230 (Regular Classroom)						
	Casework		24	LF	6	\$606	
	Ceiling - Lay-in		398	SF	7	\$0	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		398	SF	6	\$398	
	Lighting - Lay-in		6	EA	7	\$0	
	Walls - Concrete Block		484	SF	6	\$1,419	
	Walls - Plaster/Drywall		249	SF	5	\$1,887	
assro	oom #231 (Regular Classroom)						
	Casework		38	LF	6	\$960	
	Ceiling - Lay-in		10	SF	4	\$141	water damage
	Ceiling - Lay-in		918	SF	6	\$2,757	
	Chalk Board		24	LF	4	\$2,203	
	onan board		— •		•	φ_,200	

Building: Addition

Classroom Jewand Duris indu Iw I F 7 8 Ploor - TileSheet 28 6 \$3929 \$392 \$392 Liphing - Layin 12 EA 7 \$40 Waite - Ducrete Block 002 SF 6 \$31,76 Waite - Ducrete Block 498 SF 6 \$31,77 Classroom 49 SF 6 \$32,79 Classroom F232 (Regular Classroom) 5 6 \$22,700 Catage classroom 38 LF 6 \$22,700 Catage classroom 28 F 6 \$32,700 Dooms - Scientifie 7 SF 6 \$17,700 Dooms - Scientifie 7 SF 6 \$17,700 Proor - TileSheet 28 SF 6 \$17,700 Waits - Parater Difywait 12 EA 7 \$00 Vaits - Steeline 5 5 ST 5 Dooons - Scideline 5 5	Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
For - Tile/Sheat 928 SF 6 \$200 Lighting - Lay-in 600 SF 6 \$1.765 Valla - Concrete Block 600 SF 6 \$1.765 Valla - Plaste/Upynall 418 SF 6 \$1.374 Casework 1 EA 6 \$2.700 Casework 590 SF 6 \$2.900 Construction Interview 291 SF 6 \$2.900 Construction Interview 292 SF 6 \$2.900 Construction Interview 292 SF 6 \$2.900 Construction Interview 292 SF 6 \$3.137 Doors - Vood Doors inclu Interview 292 SF 6 \$1.175 Doors - Vood Doors inclu Interview 293 SF 6 \$1.765 Walls - Poster/Dryvall 498 SF 6 \$1.765 Walls - Poster/Dryvall 293 SF 6 \$3.175 Doors - Stabilitio 293<	-							
Ighting - Layin12EA78Walls - Concrete Block4988F6\$17.65Walls - Concrete Block4988F6\$17.65Work Sink1EA7\$890Clasuro Drywall5F6\$22.70Caling - Layin298SF6\$21.70Chalk Board24F4\$22.03Chalk Board24F6\$21.70Chark Board24F6\$1.71Doors - Stole-life7SF6\$1.71Doors - Stole-life299SF6\$1.71Doors - Stole-life298SF6\$1.71Doors - Stole-life298SF6\$1.71Doors - Stole-life298SF6\$1.71Doors - Stole-life298SF6\$1.71Doors - Stole-life298SF6\$1.71Walls - Concrete Block298SF6\$1.71Walls - Plaster/Drywall298SF6\$1.71Doors - Stole-life38LF6\$1.71Doors - Stole-life38LF6\$1.71Doors - Stole-life38LF6\$1.71Doors - Stole-life38LF6\$1.71Doors - Stole-life38LF6\$1.71Doors - Stole-life38LF6\$1.71Doors - Stole-life29SF6\$1.71 <td></td> <td>Doors - Wood Doors inclu hw</td> <td></td> <td>1</td> <td>EA</td> <td>7</td> <td>\$0</td> <td></td>		Doors - Wood Doors inclu hw		1	EA	7	\$0	
Walls - Concrete Block Walls - Plaster/Dynail Walls - Plaster/Dynail Walls - Plaster/DynailGelSF6\$1,75Cataseon1E6\$1,374Cataseon23E6\$2,790Cataseon28SF6\$2,700Cataseon24E4\$2,203Consol24F6\$117Consol24F6\$117Consol28SF6\$117Consol29SF6\$117Consol200724F7\$00Consol200726\$1,7826\$117Consol200726\$1,7826\$117Malls - Concrete Block603SF6\$1,778Walls - Concrete Block603SF6\$1,778Walls - Concrete Block603SF6\$1,778Walls - Concrete Block63SF6\$1,778Walls - Concrete Block63SF6\$1,778Conson233F6\$1,778Conson24SF6\$1,719Conson24SF6\$1,719Conson24SF6\$1,719Conson24SF6\$1,719Conson24SF6\$1,719Conson25SF6\$1,719Conson24SF6\$1,719Conson25SF6 <td></td> <td>Floor - Tile/Sheet</td> <td></td> <td>928</td> <td>SF</td> <td>6</td> <td>\$929</td> <td></td>		Floor - Tile/Sheet		928	SF	6	\$929	
Wate. Plasserophyseal 498 57 6 \$ \$ \$ 3,37 Wate. Sink E 6 \$ \$ \$ 373 Casserom #22 (Reguiar Classroom) 5 6 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$		Lighting - Lay-in		12	EA	7	\$0	
Work Sink 1 2 6 \$337 Classcoor #232 (Reguta Classroor) 5 6 \$27.90 Ceiting - Lay-in 629 5 6 \$27.90 Chark Board 24 12 4 \$22.00 Chark Board 24 12 4 \$22.00 Chors - Wood Doors inclu two 1 EA 7 \$50 Chors - Wood Doors inclu two 1 EA 7 \$50 Chors - Mood Doors inclu two 1 EA 7 \$50 Chors - Mood Doors inclu two 1 EA 6 \$17.80 Wark Sink 1 EA 6 \$17.80 Work Sink 1 EA 6 \$17.80 Doors - Wood Doors inclu two 1 EA 6 \$37.90 Doors - Wood Doors inclu two 1 EA 6 \$38.91 Doors - Wood Doors inclu two 1 EA 6 \$38.91 Doors - Wood Doors inclu two 1 EA 6		Walls - Concrete Block		602	SF	6	\$1,765	
Classroom #232 (Regular Classroom) Classroom #232 (Regular Classroom) Casework S8 LF 6 S3670 Cacling - Lay-in Cable 7 SF 6 S2790 Doors - Side-life 7 SF 6 S117 Doors - Nodo Doors inclu hw 1 EA 7 S0 Floor - Tile/Sheat 229 SF 6 S1373 Ploors - Side-life 7 S0 - Walls - Concrete Block 6093 SF 6 S1.78 Walls - Plaster/DDynall 498 SF 6 S1.78 Walls - Plaster/DDynall 498 SF 6 S1.74 More Side-life 6 S1.74 S0 Doors - Side-life 6 S1.74 S0 Doors - Side-life 7 S0 S0 Doors - Wood Doors inclu hw 1 EA 6 S1.71 Doors - Side-life 5 6 S1.71 S0 Doors - Nood Doors inclu hw 1		Walls - Plaster/Drywall		498	SF	6	\$1,374	
Casework 38 LF 6 \$980 Cealing Lay-in 929 SF 6 \$22,790 Chalk Board 24 LF 4 \$22,03 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 7 \$0 Floor - Tile/Sheet 929 SF 6 \$330 Lighting - Lay-in 12 EA 7 \$0 Walls - Charete Block 603 SF 6 \$1,764 Walls - Plaster/Dywall 498 SF 6 \$3,784 Work Sink 1 EA 6 \$379 Casework 88 LF 6 \$960 Limited access to this classroom was provided Ceairing - Lay-in 983 SF 7 \$0 \$0007 \$117 Doors - Wood Doors inclu hw 1 EA 7 \$0 \$10 \$17 Doors - Side-lite 7 SF 6 \$11 \$2		Work Sink		1	EA	6	\$379	
Ceiling - Lay-in 92 SF 6 \$2,203 Chalk Board 24 LF 4 \$2,203 Doors - Side-lite 7 SF 6 \$317 Doors - Wood Doors inclu hw 1 EA 7 \$90 \$160 Floor - Tile/Sheat 929 SF 6 \$1373 Liphing - Lay-in 12 EA 7 \$00 Walls - Concrete Block 603 SF 6 \$1,743 Walls - Concrete Block 63 SF 6 \$1,743 Work Sink 1 EA 7 \$00 Casework 83 LF 6 \$90 Imited access to this classroom was provided Doors - Side-lite Casework 83 SF 6 \$9137 Doors - Side-lite Casework 83 SF 6 \$90 Doors - Side-lite See	Classro	oom #232 (Regular Classroom)						
Chalk BoardCALF4\$2,203Doors - Side-life7SF65117Doors - Wood Doors inclu hw12EA7\$03Floor - Tile/Sheet929SF6\$33,30Ughting - Lay-in12EA7\$15Walls - Diaster/Dryvall498SF6\$17,78Walls - Diaster/Dryvall498SF6\$13,78Work Sink1LK6\$10Casework883LF6\$900Limited access to this classroom was providedCaling - Lay-in893SF7\$50\$17,78Doors - Side-life7SF6\$301Doors - Side-life7SF6\$301Doors - Side-life7SF6\$31,74Doors - Side-life7SF6\$31,74Doors - Side-life7SF6\$31,74Doors - Side-life7SF6\$31,74Doors - Side-life7SF6\$31,74Walls - Diaster/Dryvall4SF6\$31,74Walls - Diaster/Dryvall4SF6\$31,74Walls - Diaster/Dryvall4SF6\$31,74Walls - Diaster/Dryvall8SF6\$31,74Walls - Diaster/Dryvall8SF6\$31,74Walls - Diaster/Dryvall8SF6\$31,74Caling Lay-in84SF6\$31,74 <td></td> <td>Casework</td> <td></td> <td>38</td> <td>LF</td> <td>6</td> <td>\$960</td> <td></td>		Casework		38	LF	6	\$960	
Doors - Side-life 7 SF 6 \$\$17 Doors - Wood Doors inclu hw 1 EA 7 \$\$00 Floor - Tile/Sheet 929 SF 6 \$\$930 Lighting - Lay-in 12 EA 7 \$\$00 Walls - Concrete Block 603 SF 6 \$\$1,781 Walls - Concrete Block 6 \$\$1,781 \$\$ \$\$ Walls - Concrete Block 498 SF 6 \$\$1,781 Work Sink 1 EA 6 \$\$1,781 Clasuromt #233 (Regular Classroom) 1 EA 6 \$\$1,775 Casework 38 SF 7 \$\$0 Casework 833 SF 7 \$\$0 Doors - Side-life 7 \$\$6 \$\$171 Doors - Side-life 7 \$\$0 \$\$171 Doors - Side-life \$\$173 \$\$175 \$\$171 Doors - Side-life \$\$173 \$\$175 \$\$1715 Word Sink <td< td=""><td></td><td>Ceiling - Lay-in</td><td></td><td>929</td><td>SF</td><td>6</td><td>\$2,790</td><td></td></td<>		Ceiling - Lay-in		929	SF	6	\$2,790	
Doors Wood Doors inclu hw 1 EA 7 \$00 Floor - Tile/Sheet 929 SF 6 \$330 Lighting - Lay,in 603 SF 6 \$11,76 Walls - Diaster/Drynall 498 SF 6 \$13,76 Work Sink 1 EA 7 \$00 Cassework 6 \$13,77 \$100 <		Chalk Board		24	LF	4	\$2,203	
Floor - Tile/Sheet 92 SF 6 \$930 Lighting - Layin 12 EA 7 \$0 Walls - Concrete Block 603 SF 6 \$1,76 Walls - Blaster/Dywall 498 SF 6 \$3,77 Work Sink 1 EA 7 \$0 Casework 8 SF 6 \$3,77 Castroom #233 (Regular Classroom) SF 6 \$1,17 \$1 \$2 \$6 \$1,17 Castroom fold hw 1 EA 6 \$301 \$1 \$2 \$3 \$5 6 \$1,17 Doors - Wood Doors inclu hw 1 EA 7 \$30 \$1 \$4 \$1,17 \$1 \$4 \$1,17 \$1 \$1 \$4 \$1,17 \$1 </td <td></td> <td>Doors - Side-lite</td> <td></td> <td>7</td> <td>SF</td> <td>6</td> <td>\$117</td> <td></td>		Doors - Side-lite		7	SF	6	\$117	
Lighting - Layin 12 EA 7 50 Walls - Concrete Block 63 SF 6 \$1,776 Walls - Poster/Drywall 498 SF 6 \$1,374 Work Sink 1 EA 6 \$1,374 Work Sink 1 EA 6 \$1,374 Classeroom/ Casework 883 SF 7 \$50 Doors - Side-lite 7 SF 6 \$117 Doors - Side-lite 7 SF 6 \$301 Floor - Tile/Sheet 83 SF 6 \$31,71 Doors - Wood Doors inclu hw 1 EA 7 \$50 Highting - Lay-in 12 EA 7 \$50 Walls - Plaster/Drywall 498 SF 6 \$1,175 Walls - Concrete Block 585 SF 6 \$1,374 Work Sink 1 EA 7 \$50 Calling - Lay-in 1 EA		Doors - Wood Doors inclu hw		1	EA	7	\$0	
Walls - Concrete Block 603 SF 6 \$1,768 Walls - Plaster/Drywall 493 SF 6 \$1,374 Work Sink 1 EA 8 \$1,374 Classroom Classroom Ceasework 38 LF 6 \$960 Limited access to this classroom was provided Ceiting - Lay-in 893 SF 6 \$117 Doors - Stide-lite 7 SF 6 \$117 Floors - Wood Doors inclu hw 1 EA 7 \$89 5 6 \$117 Doors - Stide-lite 1 EA 7 \$89 5 6 \$117 Biologita - Lay-in 12 EA 7 \$89 5 6 \$1175 Walls - Concrete Block 58 SF 6 \$1175 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5		Floor - Tile/Sheet		929	SF	6	\$930	
Walls - Plaster/Dryvall Work Sink 498 SF 6 \$1,374 Casswork 1 EA 6 \$339 Casswork 33 LF 6 \$960 Limited access to this classroom was provided Casswork 33 SF 7 \$0 \$0 \$1000000000000000000000000000000000000		Lighting - Lay-in		12	EA	7	\$0	
Work Sink 1 EA 6 \$379 Classroom #233 (Regular Classroom) Casework 38 LF 6 \$990 Limited access to this classroom was provided Casework 39 SF 7 \$0 Imited access to this classroom was provided Casework 7 SF 6 \$10 56 \$10 Doors - Side-lite 7 SF 6 \$301 56 \$10 56 \$10 56 \$10 56 \$10 56 \$10 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$11 56 \$115 \$11 \$11 \$11 \$11 \$11 \$11 \$11 \$11 \$11 \$11 \$11 \$11		Walls - Concrete Block		603	SF	6	\$1,768	
Classroom #233 (Regular Classroom) Casework 38 LF 6 \$960 Limited access to this classroom was provided Ceiling - Lay-in 893 SF 7 \$00 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$894 Lighting - Lay-in 893 SF 6 \$174 Walls - Concrete Block 585 SF 6 \$1,715 Walls - Plaster/Drywall 498 SF 6 \$1,715 Work Sink 1 EA 7 \$20 Ceiling - Lay-in 498 SF 6 \$1,715 Work Sink 1 EA 7 \$20 Classroom 498 SF 6 \$1,715 Casework 84 SF 6 \$1,715 Ceiling - Lay-in 848 SF 6 \$20,55 Ceiling - Lay-in 848 SF 6 \$22,655 Ceiling - Lay-in 10 SF 4 \$141 Chalk Board		Walls - Plaster/Drywall		498	SF	6	\$1,374	
Casework 38 LF 6 \$960 Limited access to this classroom was provided Ceiling - Lay-in 893 SF 7 \$00 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 893 SF 6 \$894 Lighting - Lay-in 12 EA 7 \$00 Walls - Concrete Block 585 SF 6 \$1,175 Walls - Concrete Block 585 SF 6 \$1,374 Work Sink 1 EA 7 \$00 Classroom #234 (Regular Classroom) 1 EA 7 \$00 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,203 Doors - Side-lite <td></td> <td>Work Sink</td> <td></td> <td>1</td> <td>EA</td> <td>6</td> <td>\$379</td> <td></td>		Work Sink		1	EA	6	\$379	
Ceiling - Lay-in 893 SF 7 \$0 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 893 SF 6 \$894 Lighting - Lay-in 12 EA 7 \$\$ Walls - Concrete Block 585 S 6 \$1,775 Walls - Plaster/Drywall 498 SF 6 \$1,374 Work Sink 1 EA 7 \$0 Casework Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,203 set damage Chalk Board 7 SF 6 \$117 Doors - Side-lite 7 SF 6 \$117 Doors - Side-lite	Classro	oom #233 (Regular Classroom)						
Doors Side-lite 7 SF 6 \$117 Doors Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 893 SF 6 \$894 Lighting - Lay-in 12 EA 7 \$0 Walls - Plaster/Drywall 585 SF 6 \$1,715 Work Sink 1 EA 7 \$0 Classroom #234 (Regular Classroom) Classroom #234 (Regular Classroom) Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,203 14 \$2,203 Doors - Wood Doors inclu hw 7 SF 6 \$301 15 Doors - Wood Doors inclu hw 7 SF 6 \$117 Doors - Wood Doors inclu hw 884 SF 6 \$2,655 Ceiling - Lay-in SF 4 \$114 </td <td></td> <td>Casework</td> <td></td> <td>38</td> <td>LF</td> <td>6</td> <td>\$960</td> <td>Limited access to this classroom was provided</td>		Casework		38	LF	6	\$960	Limited access to this classroom was provided
Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 893 SF 6 \$894 Lighting - Lay-in 12 EA 7 \$0 Walls - Concrete Block 585 SF 6 \$1,715 Walls - Plaster/Drywall 498 SF 6 \$1,374 Work Sink 1 EA 7 \$0 Classroom#234 (Regular Classroom) Casework 38 LF 6 \$960 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,2655 Ocors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 <tr< td=""><td></td><td>Ceiling - Lay-in</td><td></td><td>893</td><td>SF</td><td>7</td><td>\$0</td><td></td></tr<>		Ceiling - Lay-in		893	SF	7	\$0	
Floor - Tile/Sheet 893 SF 6 \$894 Lighting - Lay-in 12 EA 7 \$0 Walls - Plaster/Drywall 498 SF 6 \$17,15 Wark Sink 1 EA 7 \$0 Casseroom #234 (Regular Classroom) 1 EA 7 \$0 Casework 38 LF 6 \$960 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 884 SF 6 \$2,655 Chalk Board 24 LF 4 \$2,203 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 7 SF 6 \$2,655 Floor - Tile/Sheet 24 LF 4 \$2,203		Doors - Side-lite		7	SF	6	\$117	
Lighting - Lay-in12EA7\$0Walls - Concrete Block5855856\$1,715Walls - Plaster/Drywall4985856\$1,374Work Sink1EA7\$0Classroom#234 (Regular Classroom)Casework38LF6\$960Ceiling - Lay-in884SF6\$2,655Ceiling - Lay-in10SF4\$141Manage10SF4\$141Doors - Side-lite74SF6\$171Doors - Side-lite74SF6\$117Floor - Tile/Sheet894SF6\$301		Doors - Wood Doors inclu hw		1	EA	6	\$301	
Walls - Concrete Block 585 SF 6 \$1,715 Walls - Plaster/Drywall 498 SF 6 \$1,374 Work Sink 1 EA 7 \$0 Classroom #234 (Regular Classroom) Classroom #234 (Regular Classroom) Casework 38 LF 6 \$960 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,203 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 894 SF 6 \$895		Floor - Tile/Sheet		893	SF	6	\$894	
Walls - Plaster/Drywall Work Sink498SF6\$1,374Description1EA7\$0Classroom #234 (Regular Classroom)38LF6\$960Casework38SF6\$2,655Ceiling - Lay-in884SF6\$2,655Ceiling - Lay-in10SF4\$141Chalk Board24LF4\$2,203Doors - Side-lite7SF6\$117Doors - Side-lite7SF6\$301Floor - Tile/Sheet894SF6\$895		Lighting - Lay-in		12	EA	7	\$0	
Work Sink1EA7\$0Classroom #234 (Regular Classroom)Casework38LF6\$960Casework884SF6\$2,655Ceiling - Lay-in884SF4\$141Chalk Board24LF4\$2,203Doors - Side-lite7SF6\$117Doors - Wood Doors inclu hw1EA6\$301Floor - Tile/Sheet894SF6\$895		Walls - Concrete Block		585	SF	6	\$1,715	
ClassroomCasework38LF6\$960Ceiling - Lay-in884SF6\$2,655Ceiling - Lay-in10SF4\$141water damageChalk Board24LF4\$2,203Doors - Side-lite7SF6\$117Doors - Wood Doors inclu hw1EA6\$301Floor - Tile/Sheet894SF6\$895		Walls - Plaster/Drywall		498	SF	6	\$1,374	
Casework 38 LF 6 \$960 Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,203 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 894 SF 6 \$895		Work Sink		1	EA	7	\$0	
Ceiling - Lay-in 884 SF 6 \$2,655 Ceiling - Lay-in 10 SF 4 \$141 water damage Chalk Board 24 LF 4 \$2,203 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 894 SF 6 \$895	Classro	oom #234 (Regular Classroom)						
Ceiling - Lay-in10SF4\$141water damageChalk Board24LF4\$2,203Doors - Side-lite7SF6\$117Doors - Wood Doors inclu hw1EA6\$301Floor - Tile/Sheet894SF6\$895		Casework		38	LF	6	\$960	
Chalk Board 24 LF 4 \$2,203 Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 894 SF 6 \$895		Ceiling - Lay-in		884	SF	6	\$2,655	
Doors - Side-lite 7 SF 6 \$117 Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 894 SF 6 \$895		Ceiling - Lay-in		10	SF	4	\$141	water damage
Doors - Wood Doors inclu hw 1 EA 6 \$301 Floor - Tile/Sheet 894 SF 6 \$895		Chalk Board		24	LF	4	\$2,203	
Floor - Tile/Sheet 894 SF 6 \$895		Doors - Side-lite		7	SF	6	\$117	
		Doors - Wood Doors inclu hw		1	EA	6	\$301	
Lighting - Lay-in 12 EA 7 \$0		Floor - Tile/Sheet		894	SF	6	\$895	
		Lighting - Lay-in		12	EA	7	\$0	

Building: Addition

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #234 (Regular Classroom)						
	Walls - Concrete Block		585	SF	6	\$1,715	
	Walls - Plaster/Drywall		498	SF	6	\$1,374	
	Work Sink		1	EA	7	\$0	
lassro	oom #235 (Computer Lab)						
	Casework		38	LF	6	\$960	
	Ceiling - Exposed		30	SF	4	\$137	water damage
	Ceiling - Lay-in		877	SF	6	\$2,634	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Side-lite		7	SF	6	\$117	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		907	SF	6	\$908	
	Lighting - Lay-in		12	EA	7	\$0	
	Walls - Concrete Block		843	SF	6	\$2,471	
	Walls - Plaster/Drywall		249	SF	6	\$687	
	Wireless System		1	EA	7	\$0	
	Work Sink		1	EA	6	\$379	
	na anna Osch (a fal					****	

Classrooms Subtotal:

\$224,115

Building: Addition

oup Ite	m - Type	Location	Quantity	Unit	Rank	Cost	Comments
ministra	tive Suites/Offices						
Ce	eiling - Lay-in	Room 118B-Kitchen Office	60	SF	6	\$180	
Do	oors - Side-lite	Room 118B-Kitchen Office	14	SF	6	\$234	
Do	oors - Steel Doors incl hw	Room 118B-Kitchen Office	1	EA	6	\$301	
Flo	oor - Epoxy/ Painted	Room 118B-Kitchen Office	60	SF	6	\$32	
Lig	ghting - Lay-in	Room 118B-Kitchen Office	1	EA	7	\$0	
Po	ower Distribution	Room 118B-Kitchen Office	8	EA	7	\$0	
W	alls - Concrete Block	Room 118B-Kitchen Office	274	SF	6	\$803	
Ce	eiling - Lay-in	Room 120A-Principal's Office	171	SF	6	\$514	
Do	oors - Wood Doors inclu hw	Room 120A-Principal's Office	1	EA	7	\$0	
Flo	por - Carpet	Room 120A-Principal's Office	171	SF	7	\$0	
Lig	ghting - Lay-in	Room 120A-Principal's Office	2	EA	7	\$0	
Po	ower Distribution	Room 120A-Principal's Office	6	EA	7	\$0	
W	alls - Concrete Block	Room 120A-Principal's Office	93	SF	6	\$273	



oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
minis	strative Suites/Offices						
	Walls - Plaster/Drywall	Room 120A-Principal's Office	444	SF	6	\$1,225	
	Ceiling - Lay-in	Room 120B-Conference Room	171	SF	7	\$0	
	Doors - Wood Doors inclu hw	Room 120B-Conference Room	1	EA	7	\$0	
	Floor - Carpet	Room 120B-Conference Room	171	SF	7	\$0	
	Lighting - Lay-in	Room 120B-Conference Room	2	EA	7	\$0	
	Power Distribution	Room 120B-Conference Room	6	EA	7	\$0	
	Walls - Concrete Block	Room 120B-Conference Room	93	SF	6	\$273	
	Walls - Plaster/Drywall	Room 120B-Conference Room	444	SF	7	\$0	
	Ceiling - Lay-in	Room 120C-Work Room	159	SF	7	\$0	
	Doors - Steel Doors incl hw	Room 120C-Work Room	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 120C-Work Room	159	SF	6	\$159	
	Lighting - Lay-in	Room 120C-Work Room	4	EA	7	\$0	
	Power Distribution	Room 120C-Work Room	4	EA	7	\$0	
	Walls - Concrete Block	Room 120C-Work Room	596	SF	6	\$1,747	
	Work Sink	Room 120C-Work Room	1	EA	6	\$508	
	Ceiling - Lay-in	Room 120D-Faculty Lounge	455	SF	7	\$0	
	Doors - Wood Doors inclu hw	Room 120D-Faculty Lounge	1	EA	7	\$0	
	Floor - Carpet	Room 120D-Faculty Lounge	455	SF	6	\$969	stains
	Lighting - Lay-in	Room 120D-Faculty Lounge	6	EA	6	\$714	
	Power Distribution	Room 120D-Faculty Lounge	6	EA	6	\$12,749	
	Walls - Concrete Block	Room 120D-Faculty Lounge	663	SF	6	\$1,944	
	Walls - Plaster/Drywall	Room 120D-Faculty Lounge	364	SF	6	\$1,005	
	Work SInk	Room 120D-Faculty Lounge	1	EA	6	\$508	
	Ceiling - Lay-in	Room 120-Main Office	556	SF	6	\$1,670	
	Doors - Side-lite	Room 120-Main Office	102	SF	6	\$1,705	
	Doors - Wood Doors inclu hw	Room 120-Main Office	1	EA	6	\$301	
	Floor - Carpet	Room 120-Main Office	371	SF	6	\$790	
	Floor - Terrazzo	Room 120-Main Office	185	SF	6	\$405	
	Lighting - Lay-in	Room 120-Main Office	8	EA	6	\$952	
	Power Distribution	Room 120-Main Office	8	EA	7	\$0	
	Walls - Concrete Block	Room 120-Main Office	746	SF	6	\$2,187	
	Walls - Plaster/Drywall	Room 120-Main Office	714	SF	6	\$1,971	
	Ceiling - Lay-in	Room 121-Assistant Principal	133	SF	7	\$0	
	Doors - Wood Doors inclu hw	Room 121-Assistant Principal	1	EA	6	\$301	
	Floor - Carpet	Room 121-Assistant Principal	133	SF	7	\$0	
	Lighting - Lay-in	Room 121-Assistant Principal	2	EA	7	\$0	
	Power Distribution	Room 121-Assistant Principal	4	EA	7	\$0	



up Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ninistrative Suites/Offices						
Walls - Concrete Block	Room 121-Assistant Principal	266	SF	6	\$780	
Walls - Plaster/Drywall	Room 121-Assistant Principal	287	SF	6	\$792	
Work SInk	Room 121-Assistant Principal	1	EA	6	\$508	
Ceiling - Lay-in	Room 123-Mail Room	134	SF	6	\$402	
Doors - Wood Doors inclu hw	Room 123-Mail Room	2	EA	6	\$602	
Floor - Carpet	Room 123-Mail Room	134	SF	6	\$286	
Lighting - Lay-in	Room 123-Mail Room	2	EA	7	\$0	
Power Distribution	Room 123-Mail Room	2	EA	7	\$0	
Storage/ Closet	Room 123-Mail Room	14	SF	6	\$102	
Walls - Concrete Block	Room 123-Mail Room	129	SF	6	\$378	
Walls - Plaster/Drywall	Room 123-Mail Room	129	SF	6	\$356	
Ceiling - Lay-in	Room 216C	125	SF	7	\$0	
Doors - Steel Doors incl hw	Room 216C	1	EA	7	\$0	
Floor - Tile Quarry	Room 216C	125	SF	6	\$265	
Lighting - Lay-in	Room 216C	2	EA	7	\$0	
Power Distribution	Room 216C	6	EA	6	\$12,749	
Walls - Concrete Block	Room 216C	417	SF	6	\$1,222	
Ceiling - Lay-in	Room 220-Office	243	SF	7	\$0	
Doors - Steel Doors incl hw	Room 220-Office	1	EA	6	\$301	
Floor - Tile/Sheet	Room 220-Office	243	SF	6	\$243	
Lighting - Lay-in	Room 220-Office	4	EA	7	\$0	
Power Distribution	Room 220-Office	4	EA	6	\$8,500	
Walls - Concrete Block	Room 220-Office	576	SF	6	\$1,689	
chen						
Ceiling - Lay-in	Kitchen	2,304	SF	6	\$6,919	
Doors - Steel Doors incl hw	Kitchen	3	EA	6	\$903	
Doors - Wood Doors inclu hw	Kitchen	6	EA	6	\$1,806	
Floor - Epoxy/ Painted	Kitchen	1,295	SF	5	\$2,222	
Floor - Tile/Sheet	Kitchen	1,009	SF	5	\$4,531	
Lighting - Lay-in	Kitchen	30	EA	7	\$0	
Storage/ Closet	Kitchen	133	SF	6	\$964	
Walls - Concrete Block	Kitchen	2,540	SF	6	\$7,446	
ch & Multipurpose Room						
Ceiling - Exposed	Lunchroom/Multipurpose Room	4,718	SF	6	\$7,017	
Doors - Steel Doors incl hw	Lunchroom/Multipurpose Room	4	EA	6	\$1,204	
Doors - Transom Window	Lunchroom/Multipurpose Room	4	SF	6	\$68	



Building: Addition

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch	& Multipurpose Room						
	Floor - Concrete Epoxy/ Painted	Lunchroom/Multipurpose Room	4,718	SF	6	\$2,496	
	Lighting - Pendent/Surface	Lunchroom/Multipurpose Room	12	EA	7	\$0	
	Serving Line	Lunchroom/Multipurpose Room	8	LF	6	\$476	
	Storage/ Closet	Lunchroom/Multipurpose Room	258	SF	6	\$1,871	
	Walls - Concrete Block	Lunchroom/Multipurpose Room	8,429	SF	6	\$24,710	
MDF I	DF						
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Finishes	2nd Floor	136	SF	6	\$970	
Mecha	nical/ Service Rooms						
Weena	Janitor's Closet	1st Floor	40	SF	6	\$287	Room 135-Janitor's Closet
	Mechanical/ Service Rooms	1st Floor	254	SF	6	\$1,820	Rooom 122-Electrical Room
	Mechanical/ Service Rooms	1st Floor	70	SF	6	\$502	Room 116-Elevator Room
	Janitor's Closet	2nd Floor	22	SF	6	\$158	219-Janitor's Closet
	Mechanical/ Service Rooms	2nd Floor	2,576	SF	6		Fan Room
	Mechanical/ Service Rooms	2nd Floor	2,010	SF	6	\$158	236-Electrical
	Mechanical/ Service Rooms	2nd Floor	25	SF	6		218-Electrical
	Storage Room	2nd Floor	54	SF	6		217A-Storage
	Storage Room	2nd Floor	72	SF	6		217B-Storage
Restro							Ŭ
Restro	Accessories	Restroom 134A	40	SF	7	\$0	soap dispenser and mirror
	Ceiling - Lay-in	Restroom 134A	40	SF	6	\$120	
	Doors - Wood Doors inclu hw	Restroom 134A	-10	EA	7	\$0	
	Floor Drain	Restroom 134A	1	EA	6	\$1,059	
	Floor - Tile/Sheet	Restroom 134A	40	SF	6	\$40	
	Lavatory	Restroom 134A	1	EA	6	\$320	
	Lighting - Lay-in	Restroom 134A	1	EA	7	¢0⊒0 \$0	
	Walls - Structural Glazed Tile	Restroom 134A	231	SF	6	\$727	
	Water Closet	Restroom 134A	1	EA	6	\$336	
	Accessories	Restroom 1st Floor Boys	324	SF	7	\$0	soap and paper towel dispenser
	Ceiling - Plaster/Drywall	Restroom 1st Floor Boys	324	SF	6	\$1,121	
	Floor Drain	Restroom 1st Floor Boys	1	EA	6	\$1,059	
	Floor - Terrazzo	Restroom 1st Floor Boys	324	SF	6	\$709	
	Hand Dryer	Restroom 1st Floor Boys	2	EA	7	\$0	
	Lavatory	Restroom 1st Floor Boys	4	EA	6	\$1,278	
	Lighting - Lay-in	Restroom 1st Floor Boys	7	EA	6	\$833	
	Partitions	Restroom 1st Floor Boys	3	EA	6	\$891	



Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
om						
Urinals	Restroom 1st Floor Boys	4	EA	7	\$0	
Walls - Structural Glazed Tile	Restroom 1st Floor Boys	700	SF	6	\$2,202	
Water Closet	Restroom 1st Floor Boys	3	EA	6	\$1,008	
Accessories	Restroom 1st Floor Girls	325	SF	7	\$0	soap and paper towel dispensers
Ceiling - Plaster/Drywall	Restroom 1st Floor Girls	325	SF	6	\$1,125	
Floor Drain	Restroom 1st Floor Girls	1	EA	6	\$1,059	
Floor - Terrazzo	Restroom 1st Floor Girls	325	SF	6	\$711	
Hand Dryer	Restroom 1st Floor Girls	2	EA	7	\$0	
Lavatory	Restroom 1st Floor Girls	4	EA	6	\$1,278	
Lighting - Lay-in	Restroom 1st Floor Girls	7	EA	7	\$0	
Partitions	Restroom 1st Floor Girls	7	EA	6	\$2,078	
Walls - Structural Glazed Tile	Restroom 1st Floor Girls	700	SF	6	\$2,202	
Water Closet	Restroom 1st Floor Girls	7	EA	6	\$2,352	
Accessories	Restroom 1st Floor Unisex	57	SF	7	\$0	soap and paper towel dispenser
Ceiling - Lay-in	Restroom 1st Floor Unisex	57	SF	7	\$0	
Doors - Steel Doors incl hw	Restroom 1st Floor Unisex	1	EA	6	\$301	
Floor Drain	Restroom 1st Floor Unisex	1	EA	6	\$1,059	
Floor - Terrazzo	Restroom 1st Floor Unisex	57	SF	6	\$125	
Lavatory	Restroom 1st Floor Unisex	1	EA	7	\$0	
Lighting - Lay-in	Restroom 1st Floor Unisex	1	EA	7	\$0	
Walls - Structural Glazed Tile	Restroom 1st Floor Unisex	280	SF	6	\$881	
Water Closet	Restroom 1st Floor Unisex	1	EA	6	\$336	
Accessories	Restroom 2nd Floor Boys	324	SF	7	\$0	soap and paper towel dispensers
Ceiling - Plaster/Drywall	Restroom 2nd Floor Boys	324	SF	6	\$1,121	
Floor Drain	Restroom 2nd Floor Boys	1	EA	6	\$1,059	
Floor - Terrazzo	Restroom 2nd Floor Boys	324	SF	6	\$709	
Lavatory	Restroom 2nd Floor Boys	4	EA	6	\$1,278	
Lighting - Lay-in	Restroom 2nd Floor Boys	7	EA	6	\$833	
Partitions	Restroom 2nd Floor Boys	3	EA	6	\$891	
Urinals	Restroom 2nd Floor Boys	4	EA	7	\$0	
Walls - Structural Glazed Tile	Restroom 2nd Floor Boys	700	SF	6	\$2,202	
Water Closet	Restroom 2nd Floor Boys	3	EA	6	\$1,008	
Accessories	Restroom 2nd Floor Girls	325	SF	7	\$0	soap dispenser and paper towel dispenser
Ceiling - Plaster/Drywall	Restroom 2nd Floor Girls	325	SF	5	\$2,979	water damage
Floor Drain	Restroom 2nd Floor Girls	1	EA	6	\$1,059	<u> </u>
Floor - Terrazzo	Restroom 2nd Floor Girls	325	SF	6	\$711	
Lavatory	Restroom 2nd Floor Girls	4	EA	6	\$1,278	



Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
om						
Lighting - Lay-in	Restroom 2nd Floor Girls	7	EA	7	\$0	
Partitions	Restroom 2nd Floor Girls	7	EA	6	\$2,078	
Walls - Structural Glazed Tile	Restroom 2nd Floor Girls	700	SF	6	\$2,202	
Water Closet	Restroom 2nd Floor Girls	7	EA	6	\$2,352	
Accessories	Restroom 2nd Floor North Unisex	57	SF	7	\$0	soap dispenser and paper towel dispenser
Ceiling - Lay-in	Restroom 2nd Floor North Unisex	57	SF	6	\$171	
Doors - Steel Doors incl hw	Restroom 2nd Floor North Unisex	1	EA	6	\$301	
Floor Drain	Restroom 2nd Floor North Unisex	1	EA	6	\$1,059	
Floor - Terrazzo	Restroom 2nd Floor North Unisex	57	SF	6	\$125	
Lavatory	Restroom 2nd Floor North Unisex	1	EA	7	\$0	
Lighting - Lay-in	Restroom 2nd Floor North Unisex	1	EA	7	\$0	
Walls - Structural Glazed Tile	Restroom 2nd Floor North Unisex	280	SF	6	\$881	
Water Closet	Restroom 2nd Floor North Unisex	1	EA	6	\$336	
Accessories	Restroom Kitchen	34	SF	7	\$0	soap and toilet paper dispenser
Ceiling - Lay-in	Restroom Kitchen	34	SF	6	\$102	
Doors - Steel Doors incl hw	Restroom Kitchen	1	EA	6	\$301	
Floor Drain	Restroom Kitchen	1	EA	6	\$1,059	
Floor - Epoxy/ Painted	Restroom Kitchen	34	SF	6	\$18	
Lavatory	Restroom Kitchen	1	EA	7	\$0	
Lighting - Lay-in	Restroom Kitchen	1	EA	7	\$0	
Walls - Concrete Block	Restroom Kitchen	212	SF	6	\$621	
Water Closet	Restroom Kitchen	1	EA	6	\$336	
Accessories	Restroom-131A	40	SF	7	\$0	mirror, toilet paper and soap dispensers
Ceiling - Lay-in	Restroom-131A	40	SF	7	\$0	
Doors - Wood Doors inclu hw	Restroom-131A	1	EA	7	\$0	
Floor Drain	Restroom-131A	1	EA	6	\$1,059	
Floor - Tile/Sheet	Restroom-131A	405	SF	6	\$405	
Lavatory	Restroom-131A	1	EA	6	\$320	
Lighting - Lay-in	Restroom-131A	1	EA	7	\$0	
Walls - Structural Glazed Tile	Restroom-131A	231	SF	6	\$727	
Water Closet	Restroom-131A	1	EA	6	\$336	
Accessories	Restroom-132A	40	SF	7	\$0	mirror, soap and toilet paper dispensers
Ceiling - Lay-in	Restroom-132A	40	SF	7	\$0	
Doors - Wood Doors inclu hw	Restroom-132A	1	EA	7	\$0	
Floor Drain	Restroom-132A	1	EA	5	\$2,094	
Floor - Tile Quarry	Restroom-132A	40	SF	5	\$927	
Lavatory	Restroom-132A	1	EA	6	\$320	



Building: Addition

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Lighting - Lay-in	Restroom-132A	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Restroom-132A	231	SF	6	\$727	
	Water Closet	Restroom-132A	1	EA	6	\$336	
	Accessories	Restroom-133A	40	SF	7	\$0	mirror, soap and toilet paper dispensers
	Ceiling - Lay-in	Restroom-133A	40	SF	7	\$0	
	Doors - Wood Doors inclu hw	Restroom-133A	1	EA	7	\$0	
	Floor Drain	Restroom-133A	1	EA	6	\$1,059	
	Floor - Tile/Sheet	Restroom-133A	40	SF	6	\$40	
	Lavatory	Restroom-133A	1	EA	6	\$320	
	Lighting - Lay-in	Restroom-133A	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Restroom-133A	231	SF	6	\$727	
	Water Closet	Restroom-133A	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$212,272

Building: Addition

Category: Building Interior

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
rrido	r						
	Ceiling - Lay-in	1st Floor	30	SF	4	\$468	Water damage
	Ceiling - Lay-in	1st Floor	6,534	SF	6	\$19,622	
	Ceiling - Plaster/Drywall	1st Floor	204	SF	7	\$0	
	Doors - Side-lite	1st Floor	28	EA	6	\$468	
	Doors - Steel Doors incl hw	1st Floor	4	EA	7	\$0	
	Doors - Store Front	1st Floor	6	EA	7	\$0	
	Doors - Transom Window	1st Floor	40	EA	6	\$677	
	Doors - Wood Doors include hw	1st Floor	2	EA	7	\$0	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	7	\$0	
	Floor - Terrazzo	1st Floor	6,768	SF	6	\$56,811	
	Lighting - Lay-in	1st Floor	27	EA	7	\$0	
	Lighting - Lay-in	1st Floor	133	EA	7	\$0	
	Stairs - Terrazzo	1st Floor	70	LF	6	\$650	
	Walls - Concrete Block	1st Floor	6,052	SF	6	\$17,741	
	Ceiling - Lay-in	2nd Floor	30	SF	4	\$468	Water damage
	Ceiling - Lay-in	2nd Floor	6,615	SF	6	\$19,865	
	Doors - Steel Doors incl hw	2nd Floor	10	EA	6	\$3,010	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	7	\$0	



Building: Addition

Category: Building Interior

oup Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
rridor							
Floor - Terrazzo		2nd Floor	6,615	SF	6	\$55,527	
Lighting - Lay-in		2nd Floor	129	EA	6	\$15,348	
Lighting - Lay-in		2nd Floor	25	EA	6	\$2,974	
Walls - Concrete Blo	ck	2nd Floor	6,943	SF	6	\$20,353	
irs							
Ceiling - Lay-in		Stair No. 1 / North	10	SF	4	\$156	
Ceiling - Lay-in		Stair No. 1 / North	270	SF	6	\$811	
Floor - Terrazzo		Stair No. 1 / North	424	SF	6	\$3,559	
Handrails		Stair No. 1 / North	68	LF	6	\$589	
Lighting - Lay-in		Stair No. 1 / North	8	EA	7	\$0	
Stairs - Terrazzo		Stair No. 1 / North	180	LF	6	\$1,671	
Walls - Concrete Blo	ck	Stair No. 1 / North	2,104	SF	6	\$6,168	
Ceiling - Lay-in		Stair No. 3 / South	522	SF	6	\$1,568	
Floor - Terrazzo		Stair No. 3 / South	269	SF	6	\$2,258	
Handrails		Stair No. 3 / South	68	LF	6	\$589	
Lighting - Lay-in		Stair No. 3 / South	8	EA	7	\$0	
Stairs - Terrazzo		Stair No. 3 / South	173	LF	6	\$1,606	
Walls - Concrete Blo	ck	Stair No. 3 / South	2,043	SF	6	\$5,989	
Ceiling - Lay-in		Stair No.2 / West	144	SF	7	\$0	
Ceiling - Plaster/Dry	wall	Stair No.2 / West	215	SF	7	\$0	
Floor - Terrazzo		Stair No.2 / West	435	SF	6	\$3,651	
Handrails		Stair No.2 / West	6	LF	6	\$52	
Lighting - Lay-in		Stair No.2 / West	9	EA	6	\$1,071	
Stairs - Terrazzo		Stair No.2 / West	186	LF	6	\$1,726	
Walls - Concrete Blo	ck	Stair No.2 / West	2,149	SF	6	\$6,300	
Walls - Plaster/Dryw	all	Stair No.2 / West	89	SF	5	\$406	
ilding Interior Subt	otal:					\$252,152	
tal Building Cost					\$1	,443,252	

SITE

Category: Site

Group Item - Type	Location	Quantity Unit Rank	Cost Comments					
Civil/Drainage								
Civil/ Drainage - Catch Basin	Entire Site	7 EA 7	\$0					



SITE

Category: Site

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ivil/Dra	inage						
	Civil/ Drainage - Site Manhole	Entire Site	13	EA	7	\$0	
encing							
	Fencing - Chain Link	Entire Site / Site - East	48	LF	6	\$901	
	Fencing - New Standard Ornamental	Entire Site	1,515	LF	6	\$48,333	
andsca	pe						
	Landscape - Grass	Entire Site	21,968	SF	7	\$0	southwest site under construction
	Landscape - Grass	Entire Site / Site - East	1,200	SF	5	\$1,819	dirt
	Landscape - Hardscape- Concrete	Entire Site	10,551	SF	7	\$0	
	Parkway trees	Entire Site	35	EA	7	\$0	
	Parkway trees	Entire Site / Site West	1	EA	4	\$2,624	stump
	Retaining Wall - Masonry	Entire Site / East	320	SF	4		cracking spalling
	Retaining Wall - Masonry	Entire Site / East	320	SF	6	\$5,523	
arking	Lot						
uning	Concrete Curbs	East	701	LF	7	\$0	
	Interior Plantings	East	4	LF	7	\$0	
	Surface - Asphalt	East	19,256	SF	6	\$46,536	
	Trash Compactor	East	1	EA	6	\$0	
	Vehicular Screening	East	113	LF	7	\$0	
idewall	(S						
	Sidewalks - Perimeter Sidewalks	Entire Site	17,222	SF	7	\$0	
	Sidewalks - Perimeter Sidewalks	Entire Site	16	SF	4		trees heaving iron grates above sidewalk
ignage							
5 . 5	Flag Pole - Building Mounted Flag Pole	Entire Site / West	1	EA	6	\$828	
	Flag Pole - Flag Pole	Entire Site / East	1	EA	7	\$0	
	Marquee - Building Mounted Back Lighted w/ LED	Entire Site / East	1	EA	7	\$0	
	Monument - Sign	Entire Site / East	1	EA	7	\$0	
ite Su	ıbtotal:					\$134,279	
otal 9	Site Cost					\$134,279	
Utar c						φ134,279	
amr	ous Total ^{2 3}				\$4.5	555,052	



¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated.
- Unit means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.
- Campus Total also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.



Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main								ļļ						4
Art Room	Regular Classroom	1st Floor	103	NA	750	0	4	6	162	72	40	Y	Y	Ν
Computer Lab	Regular Classroom	2nd Floor	213	NA	750	0	39	80	162	72	40	Y	Ν	Ν
Regular Classroom	Regular Classroom	1st Floor	101	NA	800	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	102	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	104	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	105	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	106	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	107	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	108	NA	775	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	109	NA	453	0	0	0	90	36	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	110	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	111	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	111A	111A	450	0	0	6	54	18	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	112	NA	750	0	4	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	113	NA	715	0	1	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	114	NA	750	0	4	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	1st Floor	115	NA	750	0	4	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	200	NA	750	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	201	NA	750	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	202	NA	750	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	203	NA	750	0	4	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	204	NA	750	0	1	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	205	205	750	0	0	6	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	205A	205A	450	0	0	6	54	18	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	206	NA	750	0	1	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	207	NA	750	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	208	NA	750	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	209	NA	720	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	210	NA	750	0	2	8	162	72	40	Y	Y	Ν
Regular Classroom	Regular Classroom	2nd Floor	211	NA	750	0	4	6	162	72	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	212	NA	750	0	2	8	162	72	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	215	NA	750	0	4	6	162	72	40	Y	Y	N
Science Classroom	Science Classroom	2nd Floor	214	NA	750	0	4	6	162	72	40	Y	Y	Ν
4-Classroom Mod	lular													
Regular Classroom	Regular Classroom	1st Floor	M135		876	1	2	18	56	28	40	Ν	N	Ν
Regular Classroom	Regular Classroom	1st Floor	M136		800	1	4	28	56	28	40	Ν	N	N



Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
4-Classroom Mod	dular		-					••		•				+
Regular Classroom	Regular Classroom	1st Floor	M137		876	1	5	24	56	28	40	Ν	N	Ν
Regular Classroom	Regular Classroom	1st Floor	M138		800	1	4	28	56	28	40	Ν	Ν	Ν
Addition														
Computer Lab	Regular Classroom		235	NA	907	2	45	130	120	60	40	Ν	Ν	Ν
Kindergarten	Pre School		133	NA	1,111	1	8	18	208	104	40	Ν	Ν	Ν
Pre School	Pre School		131	NA	1,089	1	4	18	156	78	40	Ν	N	Ν
Regular Classroom	Regular Classroom		125	NA	891	2	7	26	156	78	62	Ν	N	Ν
Regular Classroom	Regular Classroom		126	NA	895	2	7	26	156	78	40	Ν	N	Ν
Regular Classroom	Regular Classroom		127	NA	901	2	7	26	156	78	40	Ν	N	Ν
Regular Classroom	Regular Classroom		128	NA	897	2	7	26	156	78	40	Ν	N	Ν
Regular Classroom	Regular Classroom		129	NA	893	2	7	26	156	78	40	Ν	N	Ν
Regular Classroom	Regular Classroom		130	NA	836	2	7	26	156	78	40	Ν	N	Ν
Regular Classroom	Regular Classroom	1st Floor	132	NA	1,132	1	7	26	208	104	40	Ν	N	Ν
Regular Classroom	Regular Classroom		134	NA	1,098	1	8	26	160	80	40	Ν	N	Ν
Regular Classroom	Regular Classroom		221	NA	372	1	4	10	57	19	40	Ν	N	Ν
Regular Classroom	Regular Classroom		222	NA	894	2	2	26	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		223	NA	894	2	7	26	120	60	40	Ν	Y	Ν
Regular Classroom	Regular Classroom		224	NA	894	2	7	26	120	60	40	Ν	Y	Ν
Regular Classroom	Regular Classroom		225	NA	894	2	7	26	120	60	40	Ν	Y	Ν
Regular Classroom	Regular Classroom		226	NA	891	2	7	26	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		227	NA	930	2	7	26	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		228	NA	928	2	7	26	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		229	NA	835	2	7	26	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		230	NA	398	1	9	18	60	30	40	Ν	N	Ν
Regular Classroom	Regular Classroom		231	NA	928	2	5	18	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		232	NA	929	2	5	18	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		233	NA	893	2	9	18	120	60	40	Ν	N	Ν
Regular Classroom	Regular Classroom		234	NA	894	2	5	18	120	60	40	Ν	Y	Ν