

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1892	3	50,700	\$2,508,526
Addition	1970	1	5,685	\$410,122
SITE				\$388,821
<b>Campus Total</b>			<b>56,385</b>	<b>\$3,307,469</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio and Video	#1 N	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	#2 Exit E	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#5 S	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#6 S	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	#4 E	1	EA	4	\$3,823	Damaged
	Exterior Doors - Store Front	#1 N	4	EA	6	\$2,184	
	Exterior Doors - Store Front	#3 E	3	EA	6	\$1,638	
	Exterior Doors - Store Front	#9 N	3	EA	6	\$1,638	
	Exterior Doors - Transom Lite	#1 N	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#3 E	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#9 N	3	EA	6	\$940	
	Exterior Stairs - Concrete	#1 N	13	LF	6	\$1,063	
<b>Fire Escape</b>							
	Fire Escape	South Façade	80	LF	5	\$84,002	
<b>Foundation</b>							
	Foundation - Masonry	Entire Building / Boiler Room	28	LF	5	\$9,337	Seepage
	Foundation - Masonry	Entire Building	624	LF	7	\$0	
	Superstructure - Heavy Timber	Entire Building	50,700	SF	7	\$0	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Lighting</b>							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	24	EA	6	\$12,877	
	Exterior Lighting - Wall Mounted	Entire Building	7	EA	6	\$2,021	
<b>Roof System</b>							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	#5	7	LF	5	\$19,961	Need tuck pointing
	Chimney - Brick Chimney- Concrete/ Mortar Liner	#5	42	LF	6	\$40,097	
	Coping - Clay Tile	#1	80	LF	6	\$2,569	
	Coping - Clay Tile	#4	30	LF	6	\$964	
	Coping - Clay Tile	#5	137	LF	6	\$4,400	
	Coping - Clay Tile	#7	48	LF	6	\$1,542	
	Coping - Clay Tile	#8	62	LF	6	\$1,991	
	Coping - Metal	#2	30	LF	6	\$964	
	Coping - Metal	#3	164	LF	6	\$5,267	
	Coping - Metal	#5	20	LF	6	\$642	
	Coping - Stone	#4	30	LF	6	\$964	
	Coping - Stone	#6	38	LF	6	\$1,220	
	Coping - Stone	#7	96	LF	6	\$3,083	
	Downspouts - Exterior Downspouts	#1	26	LF	6	\$864	
	Downspouts - Exterior Downspouts	#4	28	LF	6	\$931	
	Downspouts - Exterior Downspouts	#6	13	LF	6	\$432	
	Downspouts - Exterior Downspouts	#8	26	LF	6	\$864	
	Downspouts - Interior Downspouts	#2	15	LF	6	\$498	
	Downspouts - Interior Downspouts	#3	72	LF	6	\$2,393	
	Downspouts - Interior Downspouts	#5	42	LF	6	\$1,396	
	Downspouts - Interior Downspouts	#7	30	LF	6	\$997	
	Parapet - 16" - 30" Height	#3	164	LF	6	\$6,552	
	Parapet - 16" - 30" Height	#4	60	LF	6	\$2,397	
	Parapet - 16" - 30" Height	#5	157	LF	6	\$6,273	
	Parapet - 16" - 30" Height	#7	144	LF	6	\$5,753	
	Parapet - Parapet < 16" Height	#1	80	LF	6	\$1,705	
	Parapet - Parapet < 16" Height	#2	30	LF	6	\$639	
	Parapet - Parapet < 16" Height	#6	38	LF	6	\$810	
	Parapet - Parapet < 16" Height	#8	62	LF	6	\$1,321	
	Roof Structure - Heavy Timber	#1	738	SF	7	\$0	
	Roof Structure - Heavy Timber	#2	144	SF	7	\$0	
	Roof Structure - Heavy Timber	#3	3,075	SF	7	\$0	
	Roof Structure - Heavy Timber	#4	4,721	SF	7	\$0	
	Roof Structure - Heavy Timber	#5	3,078	SF	7	\$0	

**Building: Main**
**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
	Roof Structure - Heavy Timber	#6	345	SF	7	\$0	
	Roof Structure - Heavy Timber	#7	1,429	SF	7	\$0	
	Roof Structure - Heavy Timber	#8	1,686	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	#1	738	SF	6	\$7,503	
	Roof - Asphalt Gravel Ballast	#2	144	SF	6	\$1,464	
	Roof - Asphalt Gravel Ballast	#3	3,075	SF	6	\$31,264	
	Roof - Asphalt Gravel Ballast	#4	4,721	SF	6	\$48,000	
	Roof - Asphalt Gravel Ballast	#5	3,078	SF	6	\$31,295	
	Roof - Asphalt Gravel Ballast	#6	345	SF	6	\$3,508	
	Roof - Asphalt Gravel Ballast	#7	1,429	SF	6	\$14,529	
	Roof - Asphalt Gravel Ballast	#8	1,686	SF	5	\$39,805	
<b>Walls</b>							
	Cornice - Masonry Projecting Limestone	Entire Building	70	LF	6	\$2,427	
	Cornice - Metal Projecting	Entire Building	450	LF	6	\$15,605	
	Exterior Walls - Brick	Entire Building	412	SF	5	\$9,810	
	Exterior Walls - Brick	Entire Building	23,600	SF	6	\$158,616	
	Exterior Walls - Stone-Cast	Entire Building	72	SF	5	\$968	Spalled with open joints
	Exterior Walls - Stone-Cut	Entire Building	2,200	SF	6	\$14,786	
<b>Windows</b>							
	Guard - Guards wire guard	Entire Building	1,816	SF	6	\$23,190	
	Lintels - Brick	Entire Building	372	LF	6	\$0	
	Lintels - Steel	Entire Building	33	LF	6	\$958	
	Lintels - Stone	Entire Building	302	LF	6	\$0	
	Skylite - Glass Single-Pane	Entire Building / Main Roof	81	SF	4	\$21,854	corroded steel frames-wire glass
	Windows - Sash Lexan	Entire Building	5,960	SF	5	\$174,973	
	Windows - Sash Lexan	Entire Building / South Façade	512	SF	4	\$67,205	Hazy and yellowed

**Building Exterior Subtotal:**
**\$908,796**
**Building: Main**
**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	6,802	SF	6	\$2,043	
	Emergency A/C Power - Multipurpose Room	Entire Building	2,877	SF	6	\$1,070	

**Building: Main**
**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Emergency Battery Packs - Corridors and Stairs	Entire Building	2	EA	6	\$405	
	Emergency Battery Packs - Students Toilets	Entire Building	2	EA	6	\$405	
	Exit Signs - Corridors and Stairs	Entire Building	17	EA	2	\$9,273	no battery packs
	Exit Signs - Lunchroom	Entire Building	5	EA	2	\$2,727	no battery packs
	Security System - CCTV	Entire Building	50,700	SF	5	\$39,876	
	Security System - Intrusion Detection	Entire Building	50,700	SF	6	\$13,050	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 1200 A 120/208/3PH	Electrical Room	1	EA	6	\$5,078	
	PA System	Entire Site	50,700	SF	6	\$16,675	serves main and addition
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	1	EA	6	\$299	Current unknown
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	7	\$0	LP-PT
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building / 2nd Floor	1	EA	6	\$497	door latch is broken
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	7	\$0	

**Electrical System Subtotal:**
**\$99,965**
**Building: Main**
**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Entire Building / Electrical Room	1	EA	4	\$49,477	Panel is over 40 years old and not upgradable
	Fire Alarm_System	Entire Building / Electrical Room	50,700	SF	6	\$24,650	There are no strobe lights in the classrooms, serves main building only
	Fire Pump Controller	Entire Building / Mechanical Room	1	EA	5	\$8,100	

**Building: Main**
**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Pump Room Assembly</b>							
	Fire Pump - Less than 25hp	Mechanical Room	1	EA	5	\$5,674	
<b>Sprinkler System</b>							
	Dry Sprinkler System	Entire Building	50,700	SF	5	\$18,125	
<b>Safty System Subtotal:</b>						<b>\$106,027</b>	

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - Greater than 35000 cfm	Entire Building / Basement	1	EA	5	\$95,595	
	Air Intake	Entire Building / North Façade	1	EA	5	\$7,471	
	Auxiliaries - Greater than 35000 cfm	Entire Building / Basement	1	EA	5	\$18,883	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Entire Building	100	LF	5	\$96,198	
	Zone Dampers	Entire Building / Basement	29	EA	6	\$24,158	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 101 - 150 HP	Entire Building / Boiler Room	1	EA	6	\$2,545	
	Chemical Feed System	Entire Building / Boiler Room	1	EA	5	\$3,075	
	Chemical Feeder	Entire Building / Boiler Room	1	EA	5	\$3,075	
	Combustion Dampers	Entire Building / Boiler Room	1	EA	5	\$2,552	
	Condensate Pump	Entire Building / Boiler Room	1	EA	6	\$2,021	
	Condensate Pump	Entire Building / Mechanical Room	1	EA	6	\$2,021	
	Feed Water Pumps and Tank	Entire Building / Boiler Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 101 - 150 HP	Entire Building / Boiler Room	1	EA	5	\$12,173	There is no back-up boiler
	Piping - Condensate Pipe- Steel	Entire Building	300	LF	5	\$3,659	
	Piping - Steam Pipe- Steel	Entire Building	300	LF	5	\$4,226	
	Steam Traps	Entire Building	50	EA	5	\$65,745	
<b>Gas Booster</b>							
	Gas Booster	Boiler Room	1	EA	6	\$499	
<b>Heating Devices</b>							
	Fin Tube - Steam	Entire Building	63	LF	5	\$5,130	
	Fin Tube - Steam	Entire Building	30	LF	6	\$283	

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Heating Devices</b>							
	Radiators - Steam	Entire Building	34	EA	5	\$56,961	
	Unit Heater - Gas	Boiler Room	1	EA	6	\$278	
	Wall Heater - Electric	Entire Building	9	EA	5	\$4,829	
<b>Temperature Control</b>							
	Pneumatic System	Entire Building	50,700	SF	6	\$26,825	
	Thermostats - Pneumatic	Entire Building	26	EA	6	\$0	
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	2	EA	6	\$1,185	
	Type I Exhaust Hood- Kitchen	Roof / 1st Floor	1	EA	6	\$1,248	
<b>Mechanical System Subtotal:</b>						<b>\$443,178</b>	

**Building: Main**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	1	EA	5	\$2,249	serves main and gym
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	50,700	SF	6	\$10,150	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	50,700	SF	6	\$12,325	
	Domestic Piping-Cold Water Risers	Entire Building	50,700	SF	6	\$9,425	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	50,700	SF	6	\$7,975	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	50,700	SF	6	\$9,425	
	Domestic Piping-Hot Water Return Lines	Entire Building	50,700	SF	6	\$7,250	
	Domestic Piping-Hot Water Return Risers	Entire Building	50,700	SF	6	\$7,250	
	Sanitary Piping	Entire Building	50,700	SF	6	\$46,401	
	Storm Piping	Entire Building	50,700	SF	6	\$44,226	
	Vent Piping	Entire Building	50,700	SF	6	\$34,075	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room	1	EA	5	\$8,937	
<b>Plumbing System Subtotal:</b>						<b>\$199,688</b>	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #101 (Pre School)</b>							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	6	LF	7	\$0	
	Doors - Transom Window	1st Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	952	SF	6	\$953	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	28	LF	7	\$0	
	Storage/ Closet	1st Floor	135	SF	6	\$979	
	Walls - Plaster/Drywall	1st Floor	1,400	SF	6	\$3,864	
<b>Classroom #102 (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	952	SF	6	\$3,294	
	Doors - Transom Window	1st Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	28	LF	7	\$0	
	Storage/ Closet	1st Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	1st Floor	1,400	SF	6	\$3,864	
<b>Classroom #103 (Kindergarten)</b>							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	6	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	952	SF	6	\$2,859	
	Doors - Transom Window	1st Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	47	LF	7	\$0	
	Storage/ Closet	1st Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	1st Floor	1,400	SF	6	\$3,864	
<b>Classroom #105 (Special Education)</b>							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	952	SF	6	\$3,294	
	Doors - Transom Window	1st Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #105 (Special Education)</b>							
	Floor - Wood	1st Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Storage/ Closet	1st Floor	135	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,400	SF	6	\$3,864	
<b>Classroom #107 (Music Room)</b>							
	AC Units	1st Floor	1	EA	7	\$0	
	Casework	1st Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	723	SF	6	\$2,502	
	Doors - Transom Window	1st Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	723	SF	6	\$5,097	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,133	SF	6	\$3,127	
<b>Classroom #201 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	952	SF	6	\$3,294	Painted tin
	Doors - Transom Window	2nd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	37	LF	7	\$0	
	Storage/ Closet	2nd Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$3,864	
<b>Classroom #202 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	952	SF	6	\$3,294	Painted tin
	Doors - Transom Window	2nd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	37	LF	7	\$0	
	Storage/ Closet	2nd Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$3,864	



**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #202 (Regular Classroom)</b>							
<b>Classroom #203 (Other Instructional Use)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	401	SF	6	\$1,388	Painted tin
	Doors - Transom Window	2nd Floor	15	SF	6	\$254	
	Floor - Wood	2nd Floor	401	SF	6	\$2,827	
	Lighting - Pendent/Surface	2nd Floor	6	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	656	SF	6	\$1,810	
<b>Classroom #204 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	1,180	SF	6	\$4,084	Painted tin
	Doors - Transom Window	2nd Floor	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	1,000	SF	6	\$7,050	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,500	SF	6	\$4,140	
<b>Classroom #205 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	952	SF	6	\$3,294	Painted tin
	Doors - Transom Window	2nd Floor	70	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	37	LF	7	\$0	
	Storage/ Closet	2nd Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$3,864	
<b>Classroom #207 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	952	SF	6	\$2,859	
	Doors - Wood Doors inclu hw	2nd Floor	15	EA	6	\$4,515	
	Floor - Tile/Sheet	2nd Floor	952	SF	6	\$953	
	Lighting - Pendent/Surface	2nd Floor	14	EA	6	\$1,735	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #207 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$3,864	
<b>Classroom #208 (Art Room)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	6	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	952	SF	6	\$3,294	Painted tin
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Transom Window	2nd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	37	LF	7	\$0	
	Storage/ Closet	2nd Floor	165	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$3,864	
<b>Classroom #301 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	6	LF	7	\$0	
	Ceiling - Lay-in	3rd Floor	952	SF	6	\$2,859	
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Transom Window	3rd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Storage/ Closet	3rd Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	3rd Floor	1,400	SF	6	\$3,864	
<b>Classroom #302 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	6	LF	7	\$0	
	Ceiling - Lay-in	3rd Floor	952	SF	6	\$2,859	
	Doors - Transom Window	3rd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	952	SF	6	\$6,712	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	51	LF	7	\$0	
	Storage/ Closet	3rd Floor	165	SF	6	\$1,196	
	Walls - Plaster/Drywall	3rd Floor	1,400	SF	6	\$3,864	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #302 (Regular Classroom)</b>							
<b>Classroom #303 (Computer Lab)</b>							
	AC Units	3rd Floor	1	EA	5	\$1,826	improper bracing
	Ceiling - Lay-in	3rd Floor	790	SF	6	\$2,372	
	Charging Station	3rd Floor	1	EA	7	\$0	
	Doors - Transom Window	3rd Floor	30	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	790	SF	6	\$791	
	Lighting - Pendent/Surface	3rd Floor	10	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,334	SF	6	\$3,682	
	Wireless System	3rd Floor	1	EA	7	\$0	
<b>Classroom #304 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	5	\$1,826	Improper bracing
	Casework	3rd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	3rd Floor	952	SF	6	\$2,859	
	Doors - Transom Window	3rd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	952	SF	6	\$953	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	14	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,400	SF	6	\$3,864	
<b>Classroom #305 (Play Room)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	790	SF	6	\$2,372	
	Doors - Transom Window	3rd Floor	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	790	SF	6	\$791	
	Lighting - Pendent/Surface	3rd Floor	10	EA	7	\$0	
	Marker Board	3rd Floor	32	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,334	SF	6	\$3,682	
<b>Classroom #306 (Science)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	952	SF	6	\$2,859	
	Doors - Transom Window	3rd Floor	15	SF	7	\$0	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #306 (Science)</b>							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	952	SF	6	\$953	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	17	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,400	SF	6	\$3,864	
<b>Classroom #307 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	3rd Floor	952	SF	6	\$2,859	
	Doors - Transom Window	3rd Floor	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	952	SF	6	\$953	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	30	LF	7	\$0	
	Storage/ Closet	3rd Floor	135	SF	6	\$979	
	Walls - Plaster/Drywall	3rd Floor	1,400	SF	6	\$3,864	
<b>Classroom #308 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		952	SF	6	\$2,859	
	Chalk Board		12	LF	4	\$1,102	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		952	SF	6	\$953	
	Lighting - Pendent/Surface		14	EA	6	\$1,735	
	Marker Board		32	LF	6	\$685	
	Walls - Plaster/Drywall		1,400	SF	6	\$3,864	

**Classrooms Subtotal:**
**\$245,791**
**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	AC Unit	1st Floor-101A Faculty Lounge	1	EA	5	\$1,826	improper supports
	Ceiling - Plaster/Drywall	1st Floor-101A Faculty Lounge	416	SF	6	\$1,440	
	Doors - Wood Doors inclu hw	1st Floor-101A Faculty Lounge	1	EA	6	\$301	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Floor - Tile	1st Floor-101A Faculty Lounge	416	SF	6	\$910	
	Lighting - Pendent/Surface	1st Floor-101A Faculty Lounge	4	EA	6	\$496	
	Walls - Plaster/Drywall	1st Floor-101A Faculty Lounge	1,115	SF	6	\$3,077	
	Work Slnk	1st Floor-101A Faculty Lounge	1	EA	6	\$508	
	AC Unit	1st Floor-104 Office	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st Floor-104 Office	390	SF	6	\$1,350	
	Doors - Transom Window	1st Floor-104 Office	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	1st Floor-104 Office	1	EA	6	\$301	
	Floor - Wood	1st Floor-104 Office	390	SF	6	\$2,749	
	Lighting - Pendent/Surface	1st Floor-104 Office	5	EA	6	\$619	
	Power Distribution	1st Floor-104 Office	8	EA	6	\$16,999	
	Storage/ Closet	1st Floor-104 Office	10	SF	6	\$73	
	Walls - Plaster/Drywall	1st Floor-104 Office	1,372	SF	6	\$3,787	
	Ceiling - Plaster/Drywall	1st Floor-104A Principals Office	700	SF	6	\$2,422	
	Doors - Wood Doors inclu hw	1st Floor-104A Principals Office	2	EA	6	\$602	
	Floor - Tile	1st Floor-104A Principals Office	700	SF	6	\$1,532	
	Lighting - Pendent/Surface	1st Floor-104A Principals Office	8	EA	6	\$991	
	Power Distribution	1st Floor-104A Principals Office	44	EA	7	\$0	
	Storage/ Closet	1st Floor-104A Principals Office	72	SF	6	\$522	
	Walls - Plaster/Drywall	1st Floor-104A Principals Office	1,400	SF	6	\$3,864	
	AC Unit	1st Floor-Main Office	1	EA	5	\$1,826	improper supports
	Ceiling - Lay-in	1st Floor-Main Office	450	SF	6	\$1,351	
	Ceiling - Lay-in	1st Floor-Main Office	5	SF	5	\$40	cracked tile
	Doors - Side-lite	1st Floor-Main Office	48	SF	6	\$802	
	Doors - Transom Window	1st Floor-Main Office	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	1st Floor-Main Office	1	EA	6	\$301	
	Floor - Tile	1st Floor-Main Office	525	SF	6	\$1,149	
	Lighting - Lay-in	1st Floor-Main Office	5	EA	6	\$595	
	Power Distribution	1st Floor-Main Office	24	EA	6	\$50,997	
	Walls - Plaster/Drywall	1st Floor-Main Office	1,700	SF	6	\$4,692	
	AC Unit	206 Teacher storage/work room	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	206 Teacher storage/work room	705	SF	6	\$2,440	
	Doors - Transom Window	206 Teacher storage/work room	15	SF	7	\$0	
	Doors - Wood Doors inclu hw	206 Teacher storage/work room	1	EA	6	\$301	
	Floor - Tile/Sheet	206 Teacher storage/work room	705	SF	6	\$706	
	Lighting - Pendent/Surface	206 Teacher storage/work room	9	EA	7	\$0	
	Walls - Plaster/Drywall	206 Teacher storage/work room	1,155	SF	6	\$3,188	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Plaster/Drywall	Basement-Engingeer's Office	380	SF	6	\$1,315	
	Doors - Wood Doors inclu hw	Basement-Engingeer's Office	1	EA	6	\$301	
	Floor - Tile	Basement-Engingeer's Office	380	SF	6	\$831	
	Lighting - Pendent/Surface	Basement-Engingeer's Office	4	EA	6	\$496	
	Power Distribution	Basement-Engingeer's Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Basement-Engingeer's Office	785	SF	6	\$2,167	
	Ceiling - Plaster/Drywall	Basement-Lunchroom Manager's Office	200	SF	6	\$692	
	Doors - Steel Doors incl hw	Basement-Lunchroom Manager's Office	1	EA	5	\$1,174	no hardware
	Floor - Concrete Epoxy/ Painted	Basement-Lunchroom Manager's Office	200	SF	6	\$106	Asphalt
	Lighting - Pendent/Surface	Basement-Lunchroom Manager's Office	2	EA	6	\$248	
	Power Distribution	Basement-Lunchroom Manager's Office	4	EA	6	\$8,500	
	Storage/ Closet	Basement-Lunchroom Manager's Office	5	SF	6	\$36	
	Walls - Masonry	Basement-Lunchroom Manager's Office	10	SF	5	\$572	crumbling, efflorescence
	Walls - Masonry	Basement-Lunchroom Manager's Office	440	SF	6	\$1,384	
	Ceiling - Plaster/Drywall	Basement-Parent's Resource Room	480	SF	6	\$1,661	
	Doors - Wood Doors inclu hw	Basement-Parent's Resource Room	1	EA	6	\$301	
	Floor - Wood	Basement-Parent's Resource Room	480	SF	6	\$3,384	
	Lighting - Pendent/Surface	Basement-Parent's Resource Room	6	EA	6	\$743	
	Power Distribution	Basement-Parent's Resource Room	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	Basement-Parent's Resource Room	875	SF	6	\$2,415	
<b>Kitchen</b>							
	Ceiling - Plaster/Drywall	Basement-Kitchen and Lunchroom	988	SF	6	\$3,419	
	Doors - Wood Doors inclu hw	Basement-Kitchen and Lunchroom	1	EA	6	\$301	
	Floor - Tile	Basement-Kitchen and Lunchroom	988	SF	6	\$2,162	
	Lighting - Pendent/Surface	Basement-Kitchen and Lunchroom	6	EA	6	\$743	
	Serving Line	Basement-Kitchen and Lunchroom	20	LF	6	\$1,190	
	Storage/ Closet	Basement-Kitchen and Lunchroom	65	SF	6	\$471	
	Walls - Masonry	Basement-Kitchen and Lunchroom	1,220	SF	6	\$3,838	
<b>Library</b>							
	AC Unit	1st Floor-106 Library	1	EA	5	\$1,826	improper supports
	Casework	1st Floor-106 Library	45	LF	6	\$1,136	
	Ceiling - Lay-in	1st Floor-106 Library	952	SF	6	\$2,859	
	Ceiling - Lay-in	1st Floor-106 Library	16	SF	5	\$128	broken tiles
	Doors - Transom Window	1st Floor-106 Library	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	1st Floor-106 Library	1	EA	6	\$301	
	Floor - Carpet	1st Floor-106 Library	968	SF	4	\$8,901	ripped, bubbling throughout

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Library</b>							
	Lighting - Pendant/Surface	1st Floor-106 Library	14	EA	6	\$1,735	
	Storage/ Closet	1st Floor-106 Library	135	SF	6	\$979	broken hardware
	Walls - Plaster/Drywall	1st Floor-106 Library	1,695	SF	6	\$4,678	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Plaster/Drywall	Basement-Lunchroom, at Girl's Playroom	925	SF	6	\$3,201	
	Floor - Concrete Epoxy/ Painted	Basement-Lunchroom, at Girl's Playroom	925	SF	6	\$489	
	Lighting - Pendant/Surface	Basement-Lunchroom, at Girl's Playroom	6	EA	6	\$743	
	Lighting - Wall Mounted	Basement-Lunchroom, at Girl's Playroom	1	EA	6	\$124	
	Serving Line	Basement-Lunchroom, at Girl's Playroom	5	LF	6	\$298	
	Walls - Masonry	Basement-Lunchroom, at Girl's Playroom	5	SF	5	\$286	crumbling
	Walls - Masonry	Basement-Lunchroom, at Girl's Playroom	350	SF	6	\$1,101	
	Walls - Plaster/Drywall	Basement-Lunchroom, at Girl's Playroom	305	SF	6	\$842	
	Walls - Vinyl Coated Gypsum Panel	Basement-Lunchroom, at Girl's Playroom	335	SF	6	\$925	
	Ceiling - Plaster/Drywall	Basement-Multipurpose Room at Boy's Playroom	945	SF	6	\$3,270	
	Floor - Concrete Epoxy/ Painted	Basement-Multipurpose Room at Boy's Playroom	945	SF	6	\$500	Asphalt
	Lighting - Pendant/Surface	Basement-Multipurpose Room at Boy's Playroom	7	EA	6	\$867	
	Walls - Masonry	Basement-Multipurpose Room at Boy's Playroom	600	SF	6	\$1,888	
	Walls - Plaster/Drywall	Basement-Multipurpose Room at Boy's Playroom	600	SF	6	\$1,656	
<b>MDF_IDF</b>							
	AC Unit	1st Floor	1	EA	6	\$496	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Finishes	1st Floor	195	SF	6	\$1,391	
<b>Mechanical/ Service Rooms</b>							
	Storage Room	1st Floor	125	SF	5	\$2,016	plaster has holes, lay in tile has water discoloration
	Boiler Room	Basement	1,075	SF	6	\$7,702	
	Coal Room	Basement	440	SF	6	\$3,152	
	Crawl Space - Unfinished	Basement	295	SF	6	\$1,827	
	Mechanical/ Service Rooms	Basement	606	SF	6	\$4,342	pump room
	Mechanical/ Service Rooms	Basement	150	SF	6	\$1,075	
	Storage Room	Basement	180	SF	6	\$1,290	
	Storage Room	Basement	450	SF	6	\$3,224	
	Storage Room	Basement	185	SF	6	\$1,325	kitchen storage

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	1st Floor-101A Unisex Restroom 1	35	SF	6	\$323	
	Ceiling - Plaster/Drywall	1st Floor-101A Unisex Restroom 1	35	SF	6	\$121	
	Doors - Steel Doors incl hw	1st Floor-101A Unisex Restroom 1	1	EA	6	\$301	
	Floor - Tile	1st Floor-101A Unisex Restroom 1	35	SF	6	\$77	
	Lighting - Pendent/Surface	1st Floor-101A Unisex Restroom 1	1	EA	6	\$124	
	Walls - Metal Panel	1st Floor-101A Unisex Restroom 1	45	SF	6	\$336	wood panel
	Walls - Plaster/Drywall	1st Floor-101A Unisex Restroom 1	170	SF	6	\$469	
	Water Closet	1st Floor-101A Unisex Restroom 1	1	EA	6	\$336	
	Accessories	1st Floor-101A Unisex Restroom 2	35	SF	6	\$323	
	Ceiling - Plaster/Drywall	1st Floor-101A Unisex Restroom 2	35	SF	6	\$121	
	Doors - Steel Doors incl hw	1st Floor-101A Unisex Restroom 2	1	EA	6	\$301	
	Floor - Tile	1st Floor-101A Unisex Restroom 2	35	SF	6	\$77	
	Lighting - Pendent/Surface	1st Floor-101A Unisex Restroom 2	1	EA	6	\$124	
	Walls - Metal Panel	1st Floor-101A Unisex Restroom 2	45	SF	6	\$336	wood panel
	Walls - Plaster/Drywall	1st Floor-101A Unisex Restroom 2	170	SF	6	\$469	
	Water Closet	1st Floor-101A Unisex Restroom 2	1	EA	6	\$336	
	Accessories	1st Floor-Main Office Unisex Restroom	75	SF	6	\$692	
	Ceiling - Plaster/Drywall	1st Floor-Main Office Unisex Restroom	75	SF	6	\$260	
	Doors - Wood Doors inclu hw	1st Floor-Main Office Unisex Restroom	1	EA	6	\$301	
	Floor - Tile	1st Floor-Main Office Unisex Restroom	75	SF	6	\$164	
	Lavatory	1st Floor-Main Office Unisex Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st Floor-Main Office Unisex Restroom	1	EA	6	\$124	
	Walls - Plaster/Drywall	1st Floor-Main Office Unisex Restroom	490	SF	6	\$1,352	
	Water Closet	1st Floor-Main Office Unisex Restroom	1	EA	6	\$336	
	Accessories	Basement-Boy's Restroom	455	SF	6	\$4,197	
	Ceiling - Plaster/Drywall	Basement-Boy's Restroom	455	SF	6	\$1,575	
	Floor Drain	Basement-Boy's Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement-Boy's Restroom	455	SF	6	\$963	
	Lavatory	Basement-Boy's Restroom	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	Basement-Boy's Restroom	6	EA	6	\$743	
	Lighting - Wall Mounted	Basement-Boy's Restroom	1	EA	6	\$124	
	Partitions	Basement-Boy's Restroom	5	EA	6	\$1,485	
	Urinals	Basement-Boy's Restroom	9	EA	6	\$3,024	
	Walls - Concrete Block	Basement-Boy's Restroom	650	SF	6	\$1,905	
	Walls - Plaster/Drywall	Basement-Boy's Restroom	536	SF	6	\$1,479	
	Water Closet	Basement-Boy's Restroom	5	EA	6	\$1,680	
	Accessories	Basement-Girl's Restroom	500	SF	6	\$4,612	



**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Ceiling - Splined	Basement-Girl's Restroom	500	SF	5	\$3,561	water discoloration, bulging, missing
	Doors - Wood Doors inclu hw	Basement-Girl's Restroom	2	EA	6	\$602	no hardware
	Floor Drain	Basement-Girl's Restroom	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	Basement-Girl's Restroom	500	SF	6	\$1,058	
	Lavatory	Basement-Girl's Restroom	4	EA	6	\$1,278	
	Lighting - Pendant/Surface	Basement-Girl's Restroom	4	EA	6	\$496	
	Partitions	Basement-Girl's Restroom	12	EA	6	\$3,563	
	Walls - Concrete Block	Basement-Girl's Restroom	500	SF	6	\$1,466	
	Walls - Plaster/Drywall	Basement-Girl's Restroom	390	SF	6	\$1,076	
	Water Closet	Basement-Girl's Restroom	12	EA	6	\$4,032	
	Accessories	Basement-Janitor's Suite/Bathroom	500	SF	6	\$4,612	
	Ceiling - Exposed	Basement-Janitor's Suite/Bathroom	500	SF	6	\$744	
	Doors - Wood Doors inclu hw	Basement-Janitor's Suite/Bathroom	1	EA	6	\$301	
	Floor Drain	Basement-Janitor's Suite/Bathroom	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	Basement-Janitor's Suite/Bathroom	500	SF	6	\$265	
	Lavatory	Basement-Janitor's Suite/Bathroom	2	EA	6	\$639	
	Lighting - Pendant/Surface	Basement-Janitor's Suite/Bathroom	4	EA	6	\$496	
	Partitions	Basement-Janitor's Suite/Bathroom	6	EA	6	\$1,782	
	Showers	Basement-Janitor's Suite/Bathroom	6	EA	6	\$1,868	
	Walls - Masonry	Basement-Janitor's Suite/Bathroom	830	SF	6	\$2,611	
	Accessories	Basement-Lunchroom Unisex Restroom	100	SF	6	\$922	
	Ceiling - Plaster/Drywall	Basement-Lunchroom Unisex Restroom	100	SF	6	\$346	
	Doors - Wood Doors inclu hw	Basement-Lunchroom Unisex Restroom	2	EA	6	\$602	
	Floor - Epoxy/ Painted	Basement-Lunchroom Unisex Restroom	100	SF	6	\$53	
	Lavatory	Basement-Lunchroom Unisex Restroom	1	EA	6	\$320	
	Lighting - Pendant/Surface	Basement-Lunchroom Unisex Restroom	1	EA	6	\$124	
	Partitions	Basement-Lunchroom Unisex Restroom	1	EA	6	\$297	
	Student Lockers - One Tier	Basement-Lunchroom Unisex Restroom	5	EA	6	\$464	
	Walls - Masonry	Basement-Lunchroom Unisex Restroom	450	SF	6	\$1,416	
	Water Closet	Basement-Lunchroom Unisex Restroom	1	EA	6	\$336	
	Accessories	Basement-Staff Restroom, near Boy's Playroom	136	SF	6	\$1,254	
	Ceiling - Plaster/Drywall	Basement-Staff Restroom, near Boy's Playroom	136	SF	6	\$471	
	Doors - Wood Doors inclu hw	Basement-Staff Restroom, near Boy's Playroom	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Basement-Staff Restroom, near Boy's Playroom	136	SF	6	\$72	paint peeling throughout

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lavatory	Basement-Staff Restroom, near Boy's Playroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Basement-Staff Restroom, near Boy's Playroom	2	EA	6	\$248	
	Partitions	Basement-Staff Restroom, near Boy's Playroom	1	EA	6	\$297	
	Walls - Metal Panel	Basement-Staff Restroom, near Boy's Playroom	225	SF	6	\$1,680	wood panel
	Walls - Plaster/Drywall	Basement-Staff Restroom, near Boy's Playroom	275	SF	6	\$759	peeling paint throughout
	Water Closet	Basement-Staff Restroom, near Boy's Playroom	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal:**
**\$342,169**
**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Plaster/Drywall	1st Floor	1,150	SF	6	\$7,121	
	Ceiling - Plaster/Drywall	1st Floor	230	SF	6	\$1,694	
	Drinking Fountains - Triple Fountain	1st Floor	1	EA	6	\$444	
	Floor - Concrete Epoxy/ Painted	1st Floor	312	SF	6	\$152	
	Floor - Tile Ceramic/ Porcelain	1st Floor	15	SF	6	\$42	
	Floor - Wood	1st Floor	1,150	SF	6	\$8,107	
	Lighting - Pendent/Surface	1st Floor	13	EA	6	\$1,611	
	Walls - Plaster/Drywall	1st Floor	3,428	SF	6	\$15,196	
	Ceiling - Plaster/Drywall	2nd Floor	868	SF	6	\$5,375	
	Drinking Fountains - Double Fountain	2nd Floor	1	EA	6	\$336	
	Floor - Wood	2nd Floor	868	SF	6	\$6,119	
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	2nd Floor	2,110	SF	6	\$9,354	
	Ceiling - Lay-in	3rd Floor	848	SF	6	\$2,547	
	Ceiling - Lay-in	3rd Floor	20	SF	5	\$178	Water damage
	Drinking Fountains - Double Fountain	3rd Floor	1	EA	6	\$336	
	Floor - Wood	3rd Floor	868	SF	6	\$6,119	
	Lighting - Pendent/Surface	3rd Floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	3rd Floor	2,110	SF	6	\$9,354	
	Ceiling - Plaster/Drywall	Ground Floor	2,330	SF	6	\$14,427	

**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Plaster/Drywall	Ground Floor	30	SF	5	\$523	water discoloration, peeling
	Doors - Transom Window	Ground Floor	35	EA	6	\$593	
	Doors - Wood Doors include hw	Ground Floor	8	EA	6	\$2,408	
	Floor - Concrete Epoxy/ Painted	Ground Floor	150	SF	5	\$326	cracked
	Floor - Concrete Epoxy/ Painted	Ground Floor	2,755	SF	6	\$1,339	
	Lighting - Pendent/Surface	Ground Floor	21	EA	6	\$2,602	
	Lighting - Wall Mounted	Ground Floor	4	EA	6	\$496	
	Stairs - Concrete Stairs	Ground Floor	3	LF	6	\$25	to exit
	Stairs - Concrete Stairs	Ground Floor	5	LF	6	\$41	to addition
	Walls - Masonry	Ground Floor	652	SF	6	\$2,051	
	Walls - Masonry	Ground Floor	20	SF	5	\$1,144	crumbling
	Walls - Metal Panel	Ground Floor	340	SF	6	\$2,538	
	Walls - Plaster/Drywall	Ground Floor	5,505	SF	6	\$24,404	
	Walls - Plaster/Drywall	Ground Floor	5	SF	5	\$50	hole
<b>Safety</b>							
	Camera Viewing Station	Entire Building	1	EA	6	\$683	
	Security Cameras	Entire Building	5	EA	6	\$970	
	Security Cameras	Entire Building	2	EA	6	\$388	
<b>Stairs</b>							
	Ceiling - Lay-in	E Stairs #3	250	SF	6	\$751	
	Floor - Concrete Epoxy/ Painted	E Stairs #3	258	SF	6	\$125	
	Handrails	E Stairs #3	156	LF	6	\$1,352	
	Lighting - Pendent/Surface	E Stairs #3	6	EA	6	\$743	
	Stairs - Concrete	E Stairs #3	75	LF	6	\$622	
	Walls - Plaster/Drywall	E Stairs #3	4,132	SF	6	\$11,404	
	Ceiling - Plaster/Drywall	N Stair #1	115	SF	6	\$842	
	Floor - Concrete Epoxy/ Painted	N Stair #1	55	SF	6	\$27	
	Handrails	N Stair #1	48	LF	6	\$416	
	Lighting - Wall Mounted	N Stair #1	1	EA	6	\$124	
	Stairs - Concrete	N Stair #1	20	LF	6	\$166	
	Walls - Plaster/Drywall	N Stair #1	1,000	SF	6	\$2,760	
	Ceiling - Lay-in	W Stair #2	232	SF	6	\$697	
	Ceiling - Plaster/Drywall	W Stair #2	10	SF	5	\$205	water discoloration
	Ceiling - Plaster/Drywall	W Stair #2	226	SF	6	\$1,655	
	Floor - Concrete Epoxy/ Painted	W Stair #2	510	SF	6	\$248	
	Handrails	W Stair #2	204	LF	6	\$1,768	

**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Lighting - Pendent/Surface	W Stair #2	5	EA	6	\$619	
	Lighting - Wall Mounted	W Stair #2	1	EA	6	\$124	
	Stairs - Concrete	W Stair #2	82	LF	6	\$680	
	Walls - Plaster/Drywall	W Stair #2	2,000	SF	6	\$5,520	

**Building Interior Subtotal:**
**\$162,912**
**Total Building Cost**
**\$2,508,526**
**Building: Addition**
**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#7 S	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#8 N	2	EA	6	\$961	
	Exterior Stairs - Concrete	#7 S	16	LF	6	\$1,308	
	Exterior Stairs - Concrete	#8 N	18	LF	6	\$1,472	
	Stair Handrail - Steel_Stair Handrail	#7 S	12	LF	6	\$104	
	Stair Handrail - Steel_Stair Handrail	#8 N	12	LF	6	\$104	

**Foundation**

	Foundation - Concrete	Entire Building	300	LF	7	\$0	
	Superstructure - Slab on Grade	Entire Building	5,685	SF	7	\$0	

**Lighting**

	Exterior Lighting - Parapet or Roof Mounted	Entire Building / Roof	7	EA	6	\$3,756	
	Exterior Lighting - Wall Mounted	Entire Building	2	EA	6	\$577	

**Roof System**

	Chimney - Metal Flue	#10	12	LF	6	\$1,898	
	Coping - Metal	#10	300	LF	6	\$9,635	
	Coping - Metal	#9	30	LF	6	\$964	
	Downspouts - Interior Downspouts	#10	36	LF	6	\$1,196	
	Downspouts - Interior Downspouts	#9	13	LF	6	\$432	
	Roof Structure - Heavy Timber	#9	627	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	#10	5,148	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	#10	5,148	SF	4	\$144,288	Ponding, leaking and air bubbles
	Roof - Asphalt Gravel Ballast	#9	627	SF	6	\$6,375	

**Building: Addition**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	6,600	SF	6	\$44,359	
<b>Windows</b>							
	Lintels - Steel	Entire Building	64	LF	6	\$1,858	
	Windows - Sash Lexan	Entire Building	312	SF	4	\$40,953	Hazy and yellowed

**Building Exterior Subtotal: \$261,201**

**Building: Addition**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Emergency A/C Power - Corridors and Stairs	Entire Building	1,525	SF	6	\$458	
	Emergency A/C Power - Multipurpose Room	Entire Building	3,900	SF	6	\$1,450	
<b>Main Service</b>							
	PA System	Entire Building	5,685	SF	6	\$1,870	Fed from main building
<b>Power Distribution</b>							
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	4	\$6,578	Panel is deteriorated

**Electrical System Subtotal: \$10,853**

**Building: Addition**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Heating Devices</b>							
	Unit Heater - Gas	Entire Building	2	EA	6	\$556	
	Wall Heater - Electric	Entire Building	8	EA	6	\$1,111	
	Wall Heater - Electric	Entire Building	1	EA	5	\$537	
<b>Temperature Control</b>							
	Electric Thermostat	Entire Building	2	EA	6	\$0	serve 2 unit heaters only

**Mechanical System Subtotal: \$2,203**

**Building: Addition**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Piping</b>							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	5,685	SF	6	\$1,382	Galvanized piping has more than 40 years or service.
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	5,685	SF	6	\$1,057	Galvanized piping has more than 40 years or service.
	Domestic Piping-Hot Water Return Lines	Entire Building	5,685	SF	6	\$813	Galvanized piping has more than 40 years or service.
	Sanitary Piping	Entire Building	5,685	SF	6	\$5,203	
	Storm Piping	Entire Building	5,685	SF	6	\$4,959	
	Vent Piping	Entire Building	5,685	SF	6	\$3,821	

**Plumbing System Subtotal:**

**\$17,235**

**Building: Addition**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	Gym Office	120	SF	6	\$360	
	Doors - Wood Doors inclu hw	Gym Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Gym Office	120	SF	6	\$120	
	Lighting - Lay-in	Gym Office	2	EA	7	\$0	
	Power Distribution	Gym Office	2	EA	7	\$0	
	Walls - Concrete Block	Gym Office	320	SF	6	\$938	
<b>Gymnasia</b>							
	Ceiling - Exposed	Ground floor	3,900	SF	6	\$5,800	
	Ceiling - Plaster/Drywall	Ground floor	600	SF	6	\$3,312	
	Doors - Hardware	Ground floor	2	EA	6	\$423	
	Floor - Tile/Sheet	Ground floor	598	SF	6	\$599	
	Floor - Wood	Ground floor	3,900	SF	6	\$27,495	
	Lighting - Metal Halide/Sodium Vapor	Ground floor	10	EA	7	\$0	
	Lighting - Pendent/Surface	Ground floor	6	EA	7	\$0	
	Sound System	Ground floor	1	EA	6	\$41,654	
	Stage	Ground floor	750	SF	6	\$4,333	
	Stage Curtain	Ground floor	9	EA	7	\$0	
	Stage-Stairs - Wood	Ground floor	10	LF	6	\$117	
	Storage/ Closet	Ground floor	120	SF	6	\$870	
	Walls - Concrete Block	Ground floor	4,800	SF	6	\$14,071	
	Walls - Structural Glazed Tile	Ground floor	1,425	SF	6	\$4,483	

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	Gym, Boys Restroom	70	SF	7	\$0	
	Ceiling - Plaster/Drywall	Gym, Boys Restroom	70	SF	6	\$242	
	Doors - Wood Doors inclu hw	Gym, Boys Restroom	2	EA	6	\$602	
	Floor - Tile Ceramic/ Porcelain	Gym, Boys Restroom	70	SF	6	\$148	
	Lavatory	Gym, Boys Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Gym, Boys Restroom	1	EA	6	\$124	
	Partitions	Gym, Boys Restroom	1	EA	7	\$0	
	Showers	Gym, Boys Restroom	1	EA	6	\$311	
	Student Lockers - Two Tiers	Gym, Boys Restroom	18	EA	6	\$836	
	Walls - Structural Glazed Tile	Gym, Boys Restroom	340	SF	6	\$1,070	
	Water Closet	Gym, Boys Restroom	1	EA	6	\$336	
	Accessories	Gym, Girls Restroom	70	SF	7	\$0	
	Ceiling - Plaster/Drywall	Gym, Girls Restroom	70	SF	6	\$242	
	Doors - Wood Doors inclu hw	Gym, Girls Restroom	2	EA	6	\$602	
	Floor - Tile Ceramic/ Porcelain	Gym, Girls Restroom	70	SF	6	\$148	
	Lavatory	Gym, Girls Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Gym, Girls Restroom	1	EA	7	\$0	
	Partitions	Gym, Girls Restroom	1	EA	7	\$0	
	Showers	Gym, Girls Restroom	1	EA	6	\$311	
	Student Lockers - Two Tiers	Gym, Girls Restroom	18	EA	6	\$836	
	Walls - Structural Glazed Tile	Gym, Girls Restroom	340	SF	6	\$1,070	
	Water Closet	Gym, Girls Restroom	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal:**
**\$112,729**
**Building: Addition**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Exposed	Ground floor	40	SF	6	\$59	
	Doors - Steel Doors incl hw	Ground floor	4	EA	6	\$1,204	
	Floor - Concrete Epoxy/ Painted	Ground floor	40	SF	6	\$19	
	Lighting - Chandelier, Incandescent	Ground floor	3	EA	6	\$1,433	
	Stairs - Concrete Stairs	Ground floor	4	LF	6	\$33	
	Walls - Concrete Block	Ground floor	370	SF	6	\$1,085	
	Walls - Plaster/Drywall	Ground floor	160	SF	6	\$709	
	Walls - Structural Glazed Tile	Ground floor	370	SF	6	\$1,164	

**Building: Addition**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
<b>Safety</b>							
	Security Cameras	Entire Building	1	EA	6	\$194	

**Building Interior Subtotal: \$5,901**

**Total Building Cost \$410,122**

**SITE**
**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site	8	EA	6	\$8,751	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	6	\$310	
	Civil/ Drainage - Site Manhole	Entire Site	6	EA	6	\$8,956	

**Fencing**

	Fencing - Chain Link	Entire Site	694	LF	6	\$13,030	west and south sides
	Fencing - Chain Link	Entire Site / South	10	LF	4	\$918	Damaged
	Fencing - Iron and Concrete Post	Entire Site / Site North	158	LF	5	\$19,246	some bent posts and loose panels
	Fencing - New Standard Ornamental	Entire Site	680	LF	6	\$21,694	

**Landscape**

	Benches	Entire Site	11	EA	6	\$4,730	
	Landscape - Hardscape- Asphalt	Entire Site	4,290	SF	4	\$33,864	West and north of addition; numerous cracks
	Landscape - Hardscape- Asphalt	Entire Site	9,556	SF	6	\$23,094	
	Landscape - Hardscape- Concrete	Entire Site	3,837	SF	6	\$19,808	
	Landscape - Hardscape- Pavers	Entire Site / Site North	720	SF	6	\$4,077	
	Parkway trees	Entire Site	24	EA	6	\$15,841	
	Planting Beds/ Area	Entire Site / South East	2,281	SF	6	\$3,751	
	Play Area - Asphalt/ Hardscape	Entire Site / South West	13,438	SF	6	\$32,476	
	Play Area - Synthetic Turf Play Field	Entire Site / East Courtyard	7,708	SF	6	\$33,618	
	Trash Receptacles	Entire Site	5	EA	6	\$1,561	

**Parking Lot**

	Lighting - Pole Mounted	S Parking Lot	4	EA	6	\$5,810	
	Lighting - Pole Mounted	S Parking Lot / East Courtyard	4	EA	6	\$5,810	
	Surface - Asphalt	S Parking Lot	25,885	SF	6	\$62,556	



**SITE**

**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Parking Lot</b>							
	Trash Enclosure - Chain Links	S Parking Lot	740	SF	6	\$12,984	
<b>Playground</b>							
	Equipment - Combo 3-12	E Playground	1	EA	6	\$7,092	
	Surface - Poured Surface	E Playground	2,322	SF	6	\$17,001	
<b>Sidewalks</b>							
	Sidewalks - Internal Walks	Entire Site	202	LF	6	\$2,426	
	Sidewalks - Perimeter Sidewalks	Entire Site	10,960	SF	6	\$21,785	
<b>Signage</b>							
	Flag Pole - Flag Pole	Entire Site / Site North	1	EA	5	\$7,630	corroded
	Marquee - Free Standing Back Lighted	Entire Site / North West	1	EA	6	\$0	
	Monument - Building Mounted Cut Letter Sign	Entire Site	1	EA	6	\$0	Location: entrance #1

**Site Subtotal:** **\$388,821**

**Total Site Cost** **\$388,821**

**Campus Total <sup>2 3</sup>** **\$3,307,469**

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

**Definitions**

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**

- 
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Regular Classroom	2nd Floor	208	208	952	1	2	10	100	60	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	303	303	790	5	4	62	60	36	40	N	Y	N
Kindergarten	Regular Classroom	1st Floor	103	103	952	1	2	10	110	60	40	N	Y	N
Music Room	Regular Classroom	1st Floor	107	107	723	2	2	28	108	60	40	N	Y	N
Other Instructional Use	Regular Classroom	2nd Floor	203	203	401		4	2	60	36	40	N	Y	N
Play Room	Regular Classroom	3rd Floor	305	305	790	3		10	44	26	40	N	Y	N
Pre School	Regular Classroom	1st Floor	101	101	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	102	102	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	204	204	950	1	2	10	106	66	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	952	1	2	10	110	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	302	302	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	304	304	952	1	2	10	56	32	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	307	952	1	2	10	100	60	40	N	Y	N
Regular Classroom	Regular Classroom		308	308	952	1	2	10	100	60	40	N	Y	N
Science	Regular Classroom	3rd Floor	306	306	952	1	2	10	56	32	40	N	Y	N
Special Education	Gymnasium	1st Floor	105	105	952	1	2	10	110	60	40	N	Y	N