

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1905	4	77,064	\$4,548,767
4-Classroom Modular	1984	1	3,231	\$206,861
Linked Addition	1996	3	43,135	\$1,866,419
SITE				\$381,198
<b>Campus Total</b>			<b>123,430</b>	<b>\$7,003,244</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#12 - W	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	#2 - E	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	#3 Exit - E	1	EA	5	\$1,341	Paint peeling
	Exterior Doors - Exterior Steel Door	#3.3 Exit - S	2	EA	5	\$2,683	Dented and paint peeling
	Exterior Doors - Exterior Steel Door	#3.4 Exit - S	2	EA	5	\$2,683	Dented and peeling paint
	Exterior Doors - Exterior Wood Door	#3.2 - S	1	EA	6	\$481	
	Exterior Doors - Side lite	#3 Exit - E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#12 - W	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#2 - E	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#3 Exit - E	1	EA	6	\$313	
	Exterior Stairs - Concrete	#12 - W	10	LF	6	\$818	
	Exterior Stairs - Concrete	#2 - E	30	LF	5	\$3,287	Cracks and missing pieces
	Exterior Stairs - Steel or Aluminum	#3.3 Exit - S	60	LF	6	\$231	
	Exterior Stairs - Steel or Aluminum	#3.4 Exit - S	60	LF	6	\$231	
	Stair Handrail - Steel_Stair Handrail	#3.3 Exit - S	26	LF	6	\$225	
	Stair Handrail - Steel_Stair Handrail	#3.4 Exit - S	26	LF	6	\$225	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	785	LF	7	\$0	

## Building: Main

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Foundation</b>							
	Superstructure - Steel with Clay Tile Arch	Entire Building	77,064	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	8	EA	6	\$2,310	
<b>Roof System</b>							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Entire Building	50	LF	6	\$47,734	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Entire Building	25	LF	5	\$71,289	Need tuck pointing
	Coping - Metal	Entire Building	512	LF	6	\$16,444	
	Coping - Stone	Entire Building	566	LF	6	\$18,179	
	Coping - Terra Cotta	Entire Building	456	LF	6	\$14,646	
	Downspouts - Exterior Downspouts	Entire Building	186	LF	5	\$15,020	Heads need to be cleaned
	Downspouts - Interior Downspouts	Entire Building	420	LF	5	\$92,949	Heads need to be cleaned
	Parapet - 16" - 30" Height	Entire Building	1,176	LF	6	\$46,986	
	Parapet - Parapet > 30"	Entire Building	136	LF	6	\$8,693	
	Roof Structure - Steel with Clay Tile Arch	Entire Building	21,566	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Entire Building	10,566	SF	6	\$107,428	
	Roof - Asphalt Shingle	Entire Building / Main Roof	8,288	SF	6	\$38,044	
	Roof - Metal	Entire Building	3,524	SF	6	\$47,218	
<b>Walls</b>							
	Cornice - Metal Projecting	Entire Building	986	LF	5	\$148,344	Peeling paint
	Exterior Walls - Brick	Entire Building	12,650	SF	6	\$85,021	
	Exterior Walls - Brick	Entire Building / South Façade	4,360	SF	5	\$92,150	Need tuck pointing
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	3,650	SF	6	\$20,721	
	Exterior Walls - Stone-Cast	Entire Building	6,660	SF	6	\$44,762	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building / 1st Floor	2,856	SF	6	\$36,471	
	Lintels - Brick	Entire Building	42	LF	6	\$0	
	Lintels - Steel	Entire Building	746	LF	6	\$21,656	
	Lintels - Stone	Entire Building	232	LF	6	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	9,600	SF	6	\$71,660	Windows not well insulated
	Windows - Sash Aluminum Double-pane	Entire Building	456	SF	5	\$24,564	Boys and girls restrooms and staircase windows are screwed shut. Windows not well insulated.

**Building Exterior Subtotal:**

**\$1,089,884**

## Building: Main

## Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Automatic Transfer Switch	Electrical Room / Entire Building	1	EA	5	\$0	older style, 20 years old
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	2,228	SF	6	\$1,179	
	Emergency A/C Power - Corridors and Stairs	Entire Building	15,339	SF	6	\$4,606	
	Emergency A/C Power - Gym	Entire Building / 3rd Floor	2,407	SF	6	\$895	
	Emergency A/C Power - Students Toilets	Entire Building	1,140	SF	6	\$424	
	Emergency Battery Packs - Auditorium and Aisle Lighting	Entire Building / 1st Floor	4	EA	6	\$810	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	7	EA	6	\$1,418	
	Exit Signs - Auditorium	Entire Building / 1st Floor	8	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	15	EA	7	\$0	
	Exit Signs - Gym	Entire Building / 1st Floor	2	EA	7	\$0	
	Security System - CCTV	Entire Building	77,064	SF	5	\$60,611	on outside only
	Security System - Intrusion Detection	Entire Building	77,064	SF	6	\$19,836	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 1600 A 120/208/3PH	Electrical Room	1	EA	6	\$5,641	
	PA System	Entire Building	77,064	SF	5	\$52,897	connected to other building sections
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	2	EA	6	\$994	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	6	\$497	fuse panel
	Lighting and Power Panels - Above 100 A	Entire Building	4	EA	6	\$1,988	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	6	\$3,021	
	Transformers - 120/240 - 120/208	Entire Building / Mechanical Room	1	EA	4	\$29,047	

**Electrical System Subtotal:**

**\$191,437**

## Building: Main

### Category: Safety System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Entire Building / Boiler Room	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Entire Building	77,064	SF	5	\$59,509	

**Building: Main**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm_System	Entire Building	77,064	SF	5	\$85,957	

**Safty System Subtotal:**

**\$151,872**

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Basement / Mechanical Room	1	EA	5	\$66,438	serves gym and auditorium
	Air Handling Unit- Built Up-Multi Zone-Double Delivery- Steam Coils - 45001 - 60000 cfm	Basement / Mechanical Room	1	EA	5	\$238,245	serves school, except gym and auditorium
	Air Intake	Basement / Roof	1	EA	5	\$7,471	
	Air Intake	Basement / Roof	1	EA	7	\$0	
	Auxiliaries - 15001 - 25000 cfm	Basement / Mechanical Room	1	EA	6	\$5,788	
	Auxiliaries - 45001 - 60000 cfm	Basement / Mechanical Room	1	EA	6	\$10,328	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	5	\$96,198	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Basement / Entire Building	100	LF	5	\$96,198	
	Zone Dampers	Basement / Entire Building	30	EA	5	\$57,406	East and west 13 + 17 dampers, no reheat boxes
	Zone Dampers	Basement / Mechanical Room	7	EA	5	\$13,395	cold + hot decks, no reheat boxes, no tunnel in school
<b>Boiler Systems</b>							
	Boiler Auxiliary- Steam Boiler - 101 - 150 HP	Boiler Room	2	EA	5	\$24,345	
	Chemical Feed System	Boiler Room	1	EA	5	\$3,075	
	Combustion Dampers	Boiler Room	2	EA	5	\$5,104	
	Condensate Pump	Boiler Room / Mechanical Room	2	EA	5	\$36,392	
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	
	Non Condensing- Water Tube- Flexible Tube- Atmospheric- Steam Boiler - 101 - 150 HP	Boiler Room	2	EA	5	\$137,581	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	400	LF	6	\$755	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	400	LF	6	\$755	
	Steam Traps	Boiler Room / Entire Building	50	EA	5	\$65,745	
<b>Heating Devices</b>							
	Unit Heater - Electric	Entire Building	5	EA	4	\$10,006	
	Unit Heater - Steam	Entire Building / Boiler Room	1	EA	5	\$909	
	Wall Heater - Electric	Entire Building / 2nd Floor	1	EA	6	\$139	
	Wall Heater - Electric	Entire Building	9	EA	4	\$9,743	

## Building: Main

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Temperature Control</b>							
	Pneumatic System	Entire Building	77,064	SF	4	\$401,134	mostly manual controls
	Thermostats - Pneumatic	Entire Building	17	EA	4	\$12,533	
	Thermostats - Pneumatic	Entire Building	17	EA	6	\$0	
<b>Ventilation</b>							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Basement, Roof and Attic / Basement	2	EA	4	\$8,489	old centrifical blowers in bathrooms, basement
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Basement, Roof and Attic / Roof	1	EA	6	\$592	
	Roof Mounted Duct Work	Basement, Roof and Attic / Attic	40	LF	6	\$15,161	

**Mechanical System Subtotal: \$1,326,468**

## Building: Main

### Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 150000 - 300000 BTU/HR	Boiler Room	1	EA	5	\$2,249	
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	77,064	SF	4	\$55,101	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	77,064	SF	4	\$111,304	1905 construction. engineer's comment, old, leaks, clamps used.
	Domestic Piping-Cold Water Risers	Entire Building	77,064	SF	4	\$61,713	frequent repairs
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	77,064	SF	4	\$41,877	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	77,064	SF	4	\$99,181	
	Domestic Piping-Hot Water Return Lines	Entire Building	77,064	SF	4	\$66,121	
	Domestic Piping-Hot Water Return Risers	Entire Building	77,064	SF	4	\$37,469	
	Sanitary Piping	Entire Building	77,064	SF	6	\$70,529	
	Storm Piping	Entire Building	77,064	SF	6	\$67,223	
	Vent Piping	Entire Building	77,064	SF	6	\$51,795	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Simplex	Mechanical Room	1	EA	4	\$25,441	
	Pumps - Sump-Simplex	Mechanical Room / Boiler Room	1	EA	5	\$5,627	
	Pumps - Sump-Simplex	Mechanical Room	1	EA	5	\$5,627	near front entrance stairs

**Plumbing System Subtotal: \$701,254**

## Building: Main

## Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #001 (Art Room)</b>							
	Casework	Basement	34	LF	6	\$859	
	Ceiling - Lay-in	Basement	1,230	SF	6	\$3,694	
	Chalk Board	Basement	6	LF	4	\$551	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Tile	Basement	1,230	SF	6	\$2,691	
	Lighting - Lay-in	Basement	16	EA	7	\$0	
	Marker Board	Basement	18	LF	6	\$386	
	Storage/ Closet	Basement	44	SF	6	\$319	
	Walls - Concrete Block	Basement	707	SF	6	\$2,073	
	Walls - Plaster/Drywall	Basement	707	SF	6	\$1,951	
<b>Classroom #003 (Regular Classroom)</b>							
	Casework	Basement	16	LF	6	\$404	
	Ceiling - Plaster/Drywall	Basement	588	SF	6	\$2,035	
	Chalk Board	Basement	6	LF	4	\$551	
	Doors - Transom Window	Basement	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Basement	1	EA	5	\$1,174	scratched and worn
	Floor - Tile	Basement	588	SF	6	\$1,286	
	Lighting - Pendent/Surface	Basement	8	EA	7	\$0	
	Marker Board	Basement	9	LF	6	\$193	
	Walls - Masonry	Basement	507	SF	6	\$1,595	
	Walls - Vinyl Coated Gypsum Panel	Basement	169	SF	6	\$466	
	Work Sink	Basement	1	EA	5	\$1,508	old and worn
<b>Classroom #005 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	Basement	289	SF	5	\$2,649	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Wood	Basement	289	SF	6	\$2,037	
	Lighting - Pendent/Surface	Basement	4	EA	7	\$0	
	Walls - Masonry	Basement	434	SF	6	\$1,365	
	Work Sink	Basement	1	EA	6	\$379	
<b>Classroom #007 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	Basement	830	SF	6	\$2,872	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Wood	Basement	830	SF	6	\$5,851	
	Lighting - Pendent/Surface	Basement	18	EA	7	\$0	
	Lighting - Pendent/Surface	Basement	2	EA	5	\$365	2 lights missing
	Marker Board	Basement	15	LF	6	\$321	
	Walls - Masonry	Basement	1,420	SF	6	\$4,467	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #009 (Pre School)</b>							
	Ceiling - Plaster/Drywall	Basement	1,210	SF	6	\$4,187	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Wood	Basement	1,210	SF	6	\$8,530	
	Lighting - Pendent/Surface	Basement	18	EA	7	\$0	
	Marker Board	Basement	10	LF	6	\$214	
	Storage/ Closet	Basement	72	SF	6	\$522	
	Walls - Masonry	Basement	2,000	SF	6	\$6,292	
<b>Classroom #101 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	890	SF	6	\$3,080	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	890	SF	5	\$13,020	stain needed
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	6	\$214	
	Storage/ Closet	1st Floor	513	SF	6	\$3,719	
	Walls - Plaster/Drywall	1st Floor	1,330	SF	6	\$3,671	
<b>Classroom #102 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	890	SF	6	\$3,080	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	890	SF	6	\$6,274	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	48	LF	6	\$1,028	
	Storage/ Closet	1st Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	1st Floor	1,006	SF	6	\$2,776	
<b>Classroom #103 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	840	SF	6	\$2,907	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	840	SF	6	\$1,838	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	8	LF	6	\$171	
	Storage/ Closet	1st Floor	250	SF	6	\$1,813	
	Walls - Plaster/Drywall	1st Floor	1,480	SF	6	\$4,085	
	Work Sink	1st Floor	1	EA	6	\$379	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #103 (Regular Classroom)</b>							
<b>Classroom #104 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	840	SF	6	\$2,907	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	840	SF	6	\$5,922	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	48	LF	6	\$1,028	
	Storage/ Closet	1st Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	1st Floor	975	SF	6	\$2,691	
<b>Classroom #106 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	840	SF	6	\$2,907	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Wood	1st Floor	840	SF	6	\$5,922	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	48	LF	6	\$1,028	
	Storage/ Closet	1st Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	1st Floor	975	SF	6	\$2,691	
<b>Classroom #107 (Regular Classroom)</b>							
	Ceiling - Lay-in	1st Floor	840	SF	6	\$2,523	
	Chalk Board	1st Floor	15	LF	4	\$1,377	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	840	SF	6	\$5,922	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	140	SF	6	\$1,015	
	Walls - Plaster/Drywall	1st Floor	1,480	SF	6	\$4,085	
<b>Classroom #108 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	890	SF	6	\$3,080	
	Chalk Board	1st Floor	24	LF	4	\$2,203	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	890	SF	6	\$6,274	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	



**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #108 (Regular Classroom)</b>							
	Marker Board	1st Floor	36	LF	6	\$771	
	Storage/ Closet	1st Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	1st Floor	1,006	SF	6	\$2,776	
<b>Classroom #109 (Pre School)</b>							
	Ceiling - Plaster/Drywall	1st Floor	890	SF	6	\$3,080	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	890	SF	6	\$1,947	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	18	LF	6	\$386	
	Storage/ Closet	1st Floor	125	SF	6	\$906	
	Walls - Plaster/Drywall	1st Floor	1,480	SF	5	\$11,217	
<b>Classroom #201 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	890	SF	6	\$3,080	
	Chalk Board	2nd Floor	15	LF	4	\$1,377	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	890	SF	5	\$13,020	stain floor
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	22	LF	6	\$471	
	Storage/ Closet	2nd Floor	240	SF	5	\$3,871	
	Walls - Plaster/Drywall	2nd Floor	1,330	SF	5	\$10,080	
<b>Classroom #202 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	890	SF	6	\$3,080	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	890	SF	6	\$6,274	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	6	\$771	
	Storage/ Closet	2nd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	2nd Floor	1,006	SF	6	\$2,776	
<b>Classroom #203 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	840	SF	6	\$2,907	
	Chalk Board	2nd Floor	15	LF	4	\$1,377	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #203 (Regular Classroom)</b>							
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	840	SF	6	\$5,922	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	6	\$771	
	Storage/ Closet	2nd Floor	130	SF	6	\$943	
	Walls - Plaster/Drywall	2nd Floor	1,480	SF	6	\$4,085	
<b>Classroom #204 (Computer Lab)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	840	SF	6	\$2,907	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	Solid wood panel
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	840	SF	6	\$5,922	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	6	\$771	
	Storage/ Closet	2nd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
	Wireless System	2nd Floor	1	EA	7	\$0	
<b>Classroom #205 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	795	SF	5	\$7,287	paint above window
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	795	SF	6	\$5,605	
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Storage/ Closet	2nd Floor	150	SF	5	\$2,420	paint wall
	Walls - Plaster/Drywall	2nd Floor	1,400	SF	6	\$3,864	
<b>Classroom #206 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	840	SF	6	\$2,907	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Wood	2nd Floor	1	SF	6	\$7	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	6	\$771	
	Storage/ Closet	2nd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	2nd Floor	994	SF	6	\$2,743	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #206 (Regular Classroom)</b>							
<b>Classroom #208 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	890	SF	6	\$3,080	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	890	SF	6	\$6,274	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	6	\$771	
	Storage/ Closet	2nd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	2nd Floor	1,009	SF	6	\$2,785	
<b>Classroom #209 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	890	SF	6	\$3,080	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	890	SF	5	\$13,020	Worn
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	22	LF	6	\$471	
	Storage/ Closet	2nd Floor	10	SF	6	\$73	
	Walls - Plaster/Drywall	2nd Floor	1,430	SF	6	\$3,947	
<b>Classroom #301 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	890	SF	6	\$3,080	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	890	SF	5	\$13,020	stain needed
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	42	LF	6	\$900	
	Storage/ Closet	3rd Floor	200	SF	6	\$1,450	
	Walls - Plaster/Drywall	3rd Floor	1,276	SF	6	\$3,522	
<b>Classroom #302 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	890	SF	6	\$3,080	
	Chalk Board	3rd Floor	36	LF	4	\$3,305	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	890	SF	6	\$6,274	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #302 (Regular Classroom)</b>							
	Storage/ Closet	3rd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
<b>Classroom #303 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	840	SF	6	\$2,907	
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	840	SF	5	\$12,288	stain needed
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Storage/ Closet	3rd Floor	130	SF	6	\$943	
	Walls - Plaster/Drywall	3rd Floor	1,176	SF	6	\$3,246	
<b>Classroom #304 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	865	SF	5	\$7,929	holes and peeling
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	865	SF	6	\$6,098	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	48	LF	6	\$1,028	
	Storage/ Closet	3rd Floor	52	SF	6	\$377	
	Walls - Plaster/Drywall	3rd Floor	994	SF	5	\$7,534	peeling
<b>Classroom #305 (Science)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	795	SF	6	\$2,751	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	795	SF	5	\$11,630	Worn
	Lighting - Pendent/Surface	3rd Floor	14	EA	6	\$1,735	
	Marker Board	3rd Floor	24	LF	6	\$514	
	Storage/ Closet	3rd Floor	168	SF	6	\$1,218	
	Walls - Plaster/Drywall	3rd Floor	1,086	SF	6	\$2,997	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #306 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	865	SF	5	\$7,929	peeling
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	865	SF	6	\$6,098	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #306 (Regular Classroom)</b>							
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	6	\$514	
	Storage/ Closet	3rd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	3rd Floor	994	SF	5	\$7,534	peeling
<b>Classroom #307 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	840	SF	6	\$2,907	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	840	SF	5	\$12,288	stain needed
	Lighting - Pendent/Surface	3rd Floor	13	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	1	EA	5	\$183	Does not work
	Marker Board	3rd Floor	25	LF	6	\$536	
	Storage/ Closet	3rd Floor	150	SF	6	\$1,088	
	Walls - Plaster/Drywall	3rd Floor	1,176	SF	6	\$3,246	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #308 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	890	SF	6	\$3,080	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	890	SF	6	\$6,274	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	48	LF	6	\$1,028	
	Storage/ Closet	3rd Floor	152	SF	6	\$1,102	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
<b>Classroom #309 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	890	SF	6	\$3,080	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Lighting - Pendent/Surface	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	25	LF	6	\$536	
	Storage/ Closet	3rd Floor	192	SF	6	\$1,392	
	Walls - Plaster/Drywall	3rd Floor	1,176	SF	6	\$3,246	

**Classrooms Subtotal:**

**\$519,908**

**Building: Main**

## Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	AC Unit	2nd Floor	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	2nd Floor	160	SF	6	\$554	
	Ceiling - Plaster/Drywall	2nd Floor	250	SF	6	\$865	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	160	SF	6	\$350	
	Floor - Wood	2nd Floor	250	SF	6	\$1,762	
	Lighting - Pendent/Surface	2nd Floor	2	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	450	SF	6	\$1,242	holes in walls
	Walls - Plaster/Drywall	2nd Floor	160	SF	6	\$442	
	Ceiling - Plaster/Drywall	Office, Room 002	360	SF	6	\$1,246	
	Doors - Wood Doors inclu hw	Office, Room 002	1	EA	6	\$301	
	Floor - Tile	Office, Room 002	360	SF	6	\$788	
	Lighting - Pendent/Surface	Office, Room 002	7	EA	7	\$0	
	Power Distribution	Office, Room 002	8	EA	6	\$16,999	
	Walls - Masonry	Office, Room 002	207	SF	6	\$651	28' marker board, ranked "6"
	Walls - Metal Panel	Office, Room 002	207	SF	6	\$1,545	
	Ceiling - Plaster/Drywall	Parent's Library (Former Band Room)	605	SF	6	\$2,094	
	Doors - Wood Doors inclu hw	Parent's Library (Former Band Room)	1	EA	6	\$301	
	Floor - Tile	Parent's Library (Former Band Room)	605	SF	5	\$2,717	holes in tiles
	Lighting - Pendent/Surface	Parent's Library (Former Band Room)	8	EA	7	\$0	
	Power Distribution	Parent's Library (Former Band Room)	10	EA	6	\$21,249	
	Walls - Masonry	Parent's Library (Former Band Room)	348	SF	6	\$1,095	
	Walls - Plaster/Drywall	Parent's Library (Former Band Room)	348	SF	6	\$960	
<b>Auditorium &amp; Theater</b>							
	Balcony Seating	1st Floor	80	EA	6	\$13,913	
	Ceiling - Plaster/Drywall	1st Floor	2,228	SF	6	\$18,575	
	Doors - Wood Doors inclu hw	1st Floor	6	EA	6	\$1,806	
	Floor - Wood	1st Floor	2,228	SF	6	\$15,707	
	Lighting - Chandelier, Incandescent	1st Floor	14	EA	6	\$6,686	
	Lighting - Wall Mounted	1st Floor	6	EA	6	\$743	
	Main Floor Seating	1st Floor	320	EA	6	\$55,653	
	Stage	1st Floor	722	SF	6	\$4,171	
	Stage Curtain	1st Floor	2	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Auditorium &amp; Theater</b>							
	Stage-Stairs - Wood	1st Floor	8	LF	6	\$94	
	Walls - Plaster/Drywall	1st Floor	2,677	SF	6	\$12,748	
<b>Gymnasia</b>							
	Ceiling - Exposed	1st Floor	2,407	SF	6	\$3,580	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Wood	1st Floor	2,407	SF	6	\$16,969	
	Lighting - Metal Halide/ High Pressure Sodium	1st Floor	12	EA	6	\$1,605	
	Walls - Plaster/Drywall	1st Floor	1,384	SF	6	\$4,532	beadboard
	Walls - Plaster/Drywall	1st Floor	1,384	SF	6	\$4,532	
<b>MDF_IDF</b>							
	AC Unit	2nd Floor	1	EA	6	\$496	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Finishes	2nd Floor	78	SF	6	\$557	
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	1st Floor	43	SF	6	\$308	
	Janitor's Closet	2nd Floor	43	SF	6	\$308	
	Air Intake Plenums	Basement	2,644	SF	6	\$16,371	
	Boiler Room	Basement	1,454	SF	6	\$10,417	
	Coal Room	Basement	416	SF	6	\$2,980	
	Mechanical/ Service Rooms	Basement	223	SF	6	\$1,598	switchgear room
	Storage Room	Basement	1,233	SF	6	\$8,834	
<b>Restroom</b>							
	Accessories	Basement	597	SF	6	\$5,506	
	Accessories	Basement	543	SF	6	\$5,008	
	Ceiling - Plaster/Drywall	Basement	543	SF	5	\$4,977	peeling
	Ceiling - Plaster/Drywall	Basement	597	SF	5	\$5,472	water damage
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Basement	4	EA	6	\$1,204	
	Floor Drain	Basement	2	EA	6	\$2,118	
	Floor Drain	Basement	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	Basement	543	SF	6	\$1,149	
	Floor - Tile Ceramic/ Porcelain	Basement	597	SF	6	\$1,263	
	Hand Dryer	Basement	1	EA	6	\$230	
	Hand Dryer	Basement	1	EA	6	\$230	
	Lavatory	Basement	1	EA	6	\$320	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lavatory	Basement	1	EA	6	\$320	
	Lighting - Pendent/Surface	Basement	9	EA	7	\$0	
	Lighting - Pendent/Surface	Basement	12	EA	7	\$0	
	Partitions	Basement	4	EA	6	\$1,188	
	Partitions	Basement	14	EA	6	\$4,157	
	Urinals	Basement	10	EA	6	\$3,360	
	Walls - Concrete Block	Basement	172	SF	6	\$504	
	Walls - Concrete Block	Basement	156	SF	6	\$457	
	Walls - Structural Glazed Tile	Basement	468	SF	5	\$23,778	cracked and missing tiles
	Walls - Structural Glazed Tile	Basement	514	SF	5	\$26,115	missing and cracked
	Water Closet	Basement	14	EA	6	\$4,704	
	Water Closet	Basement	4	EA	6	\$1,344	

### Rooms (Other Than Classrooms) Subtotal:

**\$364,549**

## Building: Main

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Plaster/Drywall	1st Floor	3,107	SF	6	\$19,238	
	Drinking Fountains - Double Fountain	1st Floor	2	EA	6	\$672	
	Floor - Epoxy/ Painted	1st Floor	3,107	SF	6	\$1,644	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	3,573	SF	6	\$15,839	
	Ceiling - Plaster/Drywall	2nd Floor	3,107	SF	6	\$19,238	
	Drinking Fountains - Double Fountain	2nd Floor	2	EA	6	\$672	
	Floor - Epoxy/ Painted	2nd Floor	3,107	SF	6	\$1,644	
	Lighting - Pendent/Surface	2nd Floor	18	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	3,573	SF	6	\$15,839	
	Ceiling - Plaster/Drywall	3rd Floor	3,107	SF	6	\$19,238	
	Drinking Fountains - Double Fountain	3rd Floor	2	EA	6	\$672	
	Floor - Epoxy/ Painted	3rd Floor	3,107	SF	6	\$1,644	
	Lighting - Pendent/Surface	3rd Floor	18	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	3,573	SF	6	\$15,839	
	Ceiling - Plaster/Drywall	Basement	2,763	SF	6	\$17,108	
	Drinking Fountains - Triple Fountain	Basement	2	EA	6	\$887	
	Floor - Epoxy/ Painted	Basement	2,763	SF	6	\$1,462	



## Building: Main

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Lighting - Pendent/Surface	Basement	16	EA	7	\$0	
	Walls - Masonry	Basement	1,589	SF	6	\$4,999	
	Walls - Plaster/Drywall	Basement	1,589	SF	6	\$7,044	
<b>Safety</b>							
	Metal Dedector	Entire Building / 1st Floor	1	EA	6	\$881	
	Camera Viewing Station	Entire Building	1	EA	6	\$683	
	Security Cameras	Entire Building	5	EA	6	\$970	
<b>Stairs</b>							
	Ceiling - Plaster/Drywall	North East	651	SF	6	\$4,766	
	Floor - Epoxy/ Painted	North East	651	SF	6	\$344	
	Handrails	North East	324	LF	6	\$2,808	
	Lighting - Pendent/Surface	North East	6	EA	7	\$0	
	Stairs - Asphalt	North East	156	LF	6	\$1,448	
	Walls - Plaster/Drywall	North East	750	SF	6	\$2,070	
	Ceiling - Plaster/Drywall	North	651	SF	6	\$4,766	
	Floor - Epoxy/ Painted	North	651	SF	6	\$344	
	Handrails	North	324	LF	6	\$2,808	
	Lighting - Pendent/Surface	North	6	EA	7	\$0	
	Stairs - Asphalt	North	156	LF	6	\$1,448	
	Walls - Plaster/Drywall	North	750	SF	6	\$2,070	
	Ceiling - Plaster/Drywall	South East	651	SF	6	\$4,766	
	Floor - Epoxy/ Painted	South East	651	SF	6	\$344	
	Handrails	South East	324	LF	6	\$2,808	
	Lighting - Pendent/Surface	South East	6	EA	7	\$0	
	Stairs - Asphalt	South East	156	LF	6	\$1,448	
	Walls - Plaster/Drywall	South East	750	SF	6	\$2,070	
	Ceiling - Plaster/Drywall	South	651	SF	6	\$4,766	
	Floor - Epoxy/ Painted	South	651	SF	6	\$344	
	Handrails	South	324	LF	6	\$2,808	
	Lighting - Pendent/Surface	South	6	EA	7	\$0	
	Stairs - Asphalt	South	156	LF	6	\$1,448	
	Walls - Plaster/Drywall	South	750	SF	6	\$2,070	
	Ceiling - Plaster/Drywall	West	651	SF	6	\$4,766	
	Floor - Epoxy/ Painted	West	651	SF	6	\$344	
	Handrails	West	324	LF	6	\$2,808	
	Lighting - Pendent/Surface	West	6	EA	7	\$0	

## Building: Main

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Stairs - Asphalt	West	156	LF	6	\$1,448	
	Walls - Plaster/Drywall	West	750	SF	6	\$2,070	

### Building Interior Subtotal:

**\$203,395**

### Total Building Cost

**\$4,548,767**

## Building: 4-Classroom Modular

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#13 - S	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#14 - N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#15 - N	1	EA	6	\$481	
	Exterior Stairs - Wood	#13 - S	32	LF	4	\$2,869	Deformed
	Exterior Stairs - Wood	#14 - N	25	LF	6	\$96	
	Exterior Stairs - Wood	#15 - N	25	LF	6	\$96	
	Ramp Handrail - Wood_Ramp Handrail	#13 - S	84	LF	6	\$728	
	Ramps - Wood Ramp	#13 - S	42	LF	6	\$6,310	
	Stair Handrail - Wood_Stair Handrail	#13 - S	12	LF	6	\$104	
	Stair Handrail - Wood_Stair Handrail	#14 - N	12	LF	6	\$104	
	Stair Handrail - Wood_Stair Handrail	#15 - N	12	LF	6	\$104	

### Foundation

	Foundation - Concrete	Entire Building	300	LF	7	\$0	
	Superstructure - Steel	Entire Building	3,231	SF	7	\$0	

### Lighting

	Exterior Lighting - Wall Mounted	Entire Building	3	EA	6	\$866	
--	----------------------------------	-----------------	---	----	---	-------	--

### Roof System

	Coping - Metal	Entire Building	237	LF	6	\$7,612	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	3,231	SF	7	\$0	
	Roof - EPDM/ Synthetic Rubber	Entire Building	3,231	SF	6	\$27,352	

### Walls

	Exterior Walls - Wood Siding	Entire Building	2,844	SF	5	\$20,701	Peeling paint
--	------------------------------	-----------------	-------	----	---	----------	---------------

**Building: 4-Classroom Modular**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Windows</b>							
	Guard - Guards wire guard	Entire Building	400	SF	6	\$5,108	
	Lintels - Steel	Entire Building	80	LF	6	\$2,322	
	Windows - Sash Aluminum Double-pane	Entire Building	400	SF	6	\$2,986	

**Building Exterior Subtotal:**

**\$79,280**

**Building: 4-Classroom Modular**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Emergency Battery Packs - Corridors and Stairs	1st Floor / Entire Building	4	EA	6	\$810	
	Exit Signs - Corridors and Stairs	1st Floor	4	EA	6	\$599	
	Security System - CCTV	Entire Building	3,231	SF	5	\$2,541	limited use
	Security System - Intrusion Detection	Entire Building	3,231	SF	5	\$3,234	
<b>Main Service</b>							
	PA System	Entire Building	3,231	SF	5	\$2,218	
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	1st Floor	1	EA	6	\$299	fuse panel
	Lighting and Power Panels - Above 100 A	1st Floor	2	EA	6	\$994	

**Electrical System Subtotal:**

**\$10,695**

**Building: 4-Classroom Modular**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	1st Floor	1	EA	4	\$49,477	
	Fire Alarm_System	1st Floor	3,231	SF	4	\$6,422	

**Safty System Subtotal:**

**\$55,899**

**Building: 4-Classroom Modular**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: 4-Classroom Modular**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Temperature Control</b>							
	Electric Thermostat	1st Floor / Entire Building	4	EA	6	\$0	
<b>Unit Ventilation</b>							
	Unit Ventilators - Vertical Package Electric Heat & Self Contained Cooling	West Facade / West Façade	4	EA	4	\$0	
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	2	EA	4	\$8,489	roof not accessed, photographed from neighboring roof

**Mechanical System Subtotal: \$8,489**

**Building: 4-Classroom Modular**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Electric Heater - Less than 20 KW	1st Floor	1	EA	4	\$7,667	under sink,
<b>Piping</b>							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	3,231	SF	6	\$785	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	3,231	SF	6	\$601	
	Domestic Piping-Hot Water Return Lines	Entire Building	3,231	SF	6	\$462	
	Sanitary Piping	Entire Building	3,231	SF	6	\$2,957	
	Storm Piping	Entire Building	3,231	SF	6	\$2,818	
	Vent Piping	Entire Building	3,231	SF	6	\$2,172	

**Plumbing System Subtotal: \$17,462**

**Building: 4-Classroom Modular**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #M001 (Regular Classroom)</b>							
	Ceiling - Lay-in	1st Floor	740	SF	6	\$2,222	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	740	SF	6	\$1,619	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	6	LF	6	\$129	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	851	SF	6	\$2,349	

**Building: 4-Classroom Modular**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #M002 (Regular Classroom)</b>							
	Ceiling - Lay-in	1st Floor	740	SF	6	\$2,222	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	740	SF	6	\$1,619	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	6	LF	6	\$129	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	851	SF	6	\$2,349	
<b>Classroom #M003 (Regular Classroom)</b>							
	Ceiling - Lay-in	1st Floor	740	SF	6	\$2,222	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	740	SF	6	\$1,619	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	6	LF	6	\$129	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	851	SF	6	\$2,349	
<b>Classroom #M004 (Regular Classroom)</b>							
	Ceiling - Lay-in	1st Floor	740	SF	6	\$2,222	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	740	SF	6	\$1,619	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	6	LF	6	\$129	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	851	SF	6	\$2,349	

**Classrooms Subtotal:**

**\$26,478**

**Building: 4-Classroom Modular**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	1st Floor	43	SF	6	\$397	
	Ceiling - Lay-in	1st Floor	43	SF	6	\$129	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor - Tile	1st Floor	43	SF	6	\$94	
	Lavatory	1st Floor	1	EA	6	\$320	
	Lighting - Lay-in	1st Floor	1	EA	7	\$0	
	Walls - Metal Panel	1st Floor	51	SF	6	\$381	
	Water Closet	1st Floor	1	EA	6	\$336	

**Building: 4-Classroom Modular**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	Bathroom #2	43	SF	6	\$397	
	Ceiling - Lay-in	Bathroom #2	43	SF	6	\$129	
	Doors - Wood Doors inclu hw	Bathroom #2	1	EA	6	\$301	
	Floor Drain	Bathroom #2	1	EA	6	\$1,059	
	Floor - Tile	Bathroom #2	43	SF	6	\$94	
	Lavatory	Bathroom #2	1	EA	6	\$320	
	Lighting - Lay-in	Bathroom #2	1	EA	7	\$0	
	Walls - Metal Panel	Bathroom #2	51	SF	6	\$381	
	Water Closet	Bathroom #2	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal: \$6,032**

**Building: 4-Classroom Modular**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	245	SF	6	\$736	
	Doors - Wood Doors include hw	1st Floor	2	EA	6	\$602	
	Drinking Fountains - Single Fountain	1st Floor	1	EA	6	\$276	
	Floor - Tile/Sheet	1st Floor	245	SF	6	\$133	
	Lighting - Lay-in	1st Floor	2	EA	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	282	SF	6	\$778	

**Building Interior Subtotal: \$2,525**

**Total Building Cost \$206,861**

**Building: Linked Addition**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio	#4 - E	1	EA	6	\$497	
	Exterior Doors - Exterior Steel Door	#10 - N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#3.5 Exit - N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#3.6 - N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#3.7 Exit - N	1	EA	6	\$481	

## Building: Linked Addition

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#3.8 Exit - N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#9 - W	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#9.5 - N	1	EA	6	\$481	
	Exterior Doors - Side lite	#4 - E	2	EA	6	\$627	
	Exterior Doors - Side lite	#5 Exit - S	2	EA	6	\$627	
	Exterior Doors - Side lite	#6 Exit - S	2	EA	6	\$627	
	Exterior Doors - Side lite	#7 Exit - S	2	EA	6	\$627	
	Exterior Doors - Side lite	#8 Exit - S	2	EA	6	\$627	
	Exterior Doors - Store Front	#11 - N	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#4 - E	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#5 Exit - S	1	EA	6	\$546	
	Exterior Doors - Store Front	#6 Exit - S	1	EA	6	\$546	
	Exterior Doors - Store Front	#7 Exit - S	1	EA	6	\$546	
	Exterior Doors - Store Front	#8 Exit - S	1	EA	6	\$546	
	Exterior Doors - Transom Lite	#11 - N	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#4 - E	4	EA	6	\$1,253	
	Exterior Doors - Transom Lite	#5 Exit - S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#6 Exit - S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#7 Exit - S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#8 Exit - S	2	EA	6	\$627	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	745	LF	7	\$0	
	Superstructure - Steel	Entire Building	43,135	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	26	EA	6	\$7,507	
<b>Roof System</b>							
	Chimney - Metal Flue	Entire Building	10	LF	6	\$1,581	
	Coping - Metal	Entire Building	112	LF	6	\$3,597	
	Coping - Stone	Entire Building	745	LF	6	\$23,928	
	Downspouts - Interior Downspouts	Entire Building	435	LF	5	\$96,268	Heads need to be cleaned.
	Parapet - 16" - 30" Height	Entire Building	605	LF	6	\$24,172	
	Parapet - Parapet > 30"	Entire Building	140	LF	6	\$8,949	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	13,552	SF	7	\$0	
	Roof - Modified Bitumen	Entire Building	13,552	SF	4	\$371,502	Leaking and worn

**Building: Linked Addition**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	22,650	SF	6	\$152,231	
	Exterior Walls - Concrete Block	Entire Building	1,524	SF	6	\$10,243	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building / 1st Floor	1,554	SF	6	\$19,844	
	Lintels - Steel	Entire Building	832	LF	6	\$24,152	
	Storefront Windows	Entire Building	350	SF	6	\$3,924	
	Windows - Casement Aluminum Double-pane	Entire Building	5,356	SF	6	\$39,980	

**Building Exterior Subtotal: \$804,590**

**Building: Linked Addition**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	10,020	SF	6	\$3,009	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	3,044	SF	6	\$1,132	
	Emergency A/C Power - Students Toilets	Entire Building	1,290	SF	6	\$480	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	12	EA	6	\$2,430	
	Emergency Battery Packs - Lunchrooms	Entire Building / 1st Floor	4	EA	6	\$810	
	Exit Signs - Corridors and Stairs	Entire Building	19	EA	7	\$0	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	4	EA	7	\$0	
	Security System - CCTV	Entire Building	43,135	SF	6	\$12,953	
	Security System - Intrusion Detection	Entire Building	43,135	SF	6	\$11,103	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	1	EA	6	\$10,867	
	PA System	Entire Building	43,135	SF	6	\$14,187	connected with other 2 building sections
<b>Power Distribution</b>							
	Lighting and Power Panels - Above 100 A	Entire Building / 1st Floor	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building	1	EA	6	\$497	fuse panel
	Lighting and Power Panels - Above 100 A	Entire Building	4	EA	6	\$1,988	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	supplies modular building
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	3	EA	6	\$2,191	
	Main Distribution Panels - Less than 400 amp	Entire Building / Electrical Room	2	EA	6	\$1,006	



**Building: Linked Addition**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Electrical System Subtotal:</b>						<b>\$67,006</b>	

**Building: Linked Addition**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Mechanical Room	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Mechanical Room / Entire Building	43,135	SF	6	\$15,421	
	Fire Alarm_System	Mechanical Room / Entire Building	43,135	SF	6	\$20,972	
	Fire Pump Controller	Mechanical Room	1	EA	6	\$1,823	
<b>Pump Room Assembly</b>							
	Fire Pump - 51-75hp	Mechanical Room	1	EA	6	\$1,558	
	Jockey Pump	Mechanical Room	1	EA	6	\$758	
<b>Sprinkler System</b>							
	Sprinkler Heads	Entire Building	43,135	SF	7	\$0	
	Sprinkler Piping	Entire Building	43,135	SF	6	\$8,019	
	Wet Sprinkler System	Entire Building	43,135	SF	6	\$11,103	
<b>Safty System Subtotal:</b>						<b>\$66,059</b>	

**Building: Linked Addition**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	6	\$606	
	Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons	Roof	1	EA	5	\$63,450	needs frequent repairs
	Condensing Unit- Ground Mounted - Less than 5 tons	2nd Floor	1	EA	6	\$3,334	condensor exhaust goes through a window
	Pipes - Chilled Water Pipe- Galvanized	Roof / Entire Building	400	LF	6	\$755	
	Pressure Fill System	Roof / Mechanical Room	1	EA	6	\$1,405	
<b>Air Handling Systems</b>							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room / 2nd Floor	1	EA	6	\$3,350	
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room / 2nd Floor	1	EA	6	\$3,350	
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room / 2nd Floor	1	EA	6	\$3,350	

**Building: Linked Addition**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Intake	Mechanical Room / 2nd Floor	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / 2nd Floor	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / 2nd Floor	1	EA	6	\$5,765	
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building	24	EA	6	\$11,827	
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	Mechanical Room	3	EA	6	\$5,571	for each AHU
	VAV Box	Mechanical Room / 1st Floor	12	EA	6	\$3,350	
	VAV Box	Mechanical Room / 2nd Floor	12	EA	6	\$3,350	
	VAV Box	Mechanical Room / 3rd Floor	12	EA	6	\$3,350	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Non Condensing Hot Water - 2001 - 3000 MBH	Mechanical Room	2	EA	6	\$4,093	
	Chemical Pot Feeder	Mechanical Room	1	EA	6	\$725	
	Combustion Dampers	Mechanical Room	2	EA	6	\$818	
	Non Condensing- Flexible Tube- Atmospheric- Hot Water Boiler - 2001 - 3000 MBH	Mechanical Room	2	EA	6	\$1,996	
	Piping - Dual Temperature Pipes- Galvanized	Mechanical Room / Entire Building	800	LF	6	\$1,510	hot water
	Water Fill System	Mechanical Room	1	EA	6	\$1,168	
<b>Heating Devices</b>							
	Cabinet Heaters - With Hot Water Coil	1st Floor	4	EA	5	\$7,019	
	Fin Tube - Hot Water	Entire Building	48	LF	6	\$453	
	Unit Heater - Electric	Mechanical Room	1	EA	6	\$278	
<b>Mechanical Plumbing</b>							
	Chilled Water Pump - 10 - 20 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - 10 - 20 HP	Mechanical Room	2	EA	6	\$2,485	
<b>Temperature Control</b>							
	DDC System	Entire Building	43,135	SF	6	\$24,673	
	Thermostats - DDC	Entire Building	36	EA	6	\$0	
	Thermostats - DDC	Entire Building	3	EA	4	\$2,457	
<b>Ventilation</b>							
	Exhaust Fans- Indoor - Less than 500 CFM	Entire Building / Mechanical Room	1	EA	6	\$296	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	4	EA	6	\$2,370	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	6	\$592	
<b>Mechanical System Subtotal:</b>						<b>\$181,314</b>	

**Building: Linked Addition**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	1	EA	7	\$0	1 year old
	Gas Heater - Less than 150000 BTU/HR	Mechanical Room	1	EA	7	\$0	1 year old
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	43,135	SF	6	\$8,636	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	43,135	SF	6	\$10,486	
	Domestic Piping-Cold Water Risers	Entire Building	43,135	SF	6	\$8,019	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	43,135	SF	6	\$6,785	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	43,135	SF	6	\$8,019	
	Domestic Piping-Hot Water Return Lines	Entire Building	43,135	SF	6	\$6,168	
	Domestic Piping-Hot Water Return Risers	Entire Building	43,135	SF	6	\$6,168	
	Sanitary Piping	Entire Building	43,135	SF	6	\$39,477	
	Storm Piping	Entire Building	43,135	SF	6	\$37,627	
	Vent Piping	Entire Building	43,135	SF	6	\$28,991	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Duplex	1st Floor and Mechanical Room / Mechanical Room	1	EA	5	\$15,514	
	Pumps - Sump-Simplex	1st Floor and Mechanical Room / 1st Floor	1	EA	6	\$745	

**Plumbing System Subtotal:**

**\$176,635**

**Building: Linked Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #401 (Kindergarten)</b>							
	Casework	1st Floor	25	LF	6	\$631	
	Ceiling - Lay-in	1st Floor	775	SF	6	\$2,327	
	Doors - Side-lite	1st Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	775	SF	6	\$1,696	
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	
	Storage/ Closet	1st Floor	20	SF	6	\$145	
	Walls - Concrete Block	1st Floor	480	SF	6	\$1,407	
	Walls - Plaster/Drywall	1st Floor	480	SF	6	\$1,325	
	Work Sink	1st Floor	1	EA	6	\$379	

## Building: Linked Addition

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #402 (Kindergarten)</b>							
	Casework	1st Floor	25	LF	6	\$631	
	Ceiling - Lay-in	1st Floor	985	SF	6	\$2,958	
	Chalk Board	1st Floor	6	LF	4	\$551	
	Doors - Side-lite	1st Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	985	SF	6	\$2,155	
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	18	LF	6	\$386	
	Storage/ Closet	1st Floor	44	SF	6	\$319	
	Walls - Concrete Block	1st Floor	566	SF	6	\$1,659	
	Walls - Plaster/Drywall	1st Floor	566	SF	6	\$1,562	
	Work Sink	1st Floor	1	EA	6	\$379	
<b>Classroom #403 (Kindergarten)</b>							
	Casework	1st Floor	25	LF	6	\$631	
	Ceiling - Lay-in	1st Floor	1,110	SF	6	\$3,333	
	Doors - Side-lite	1st Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,110	SF	6	\$2,429	
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Concrete Block	1st Floor	605	SF	6	\$1,774	
	Walls - Plaster/Drywall	1st Floor	605	SF	6	\$1,670	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #404 (Pre School)</b>							
	Casework	1st Floor	34	LF	6	\$859	
	Ceiling - Lay-in	1st Floor	1,110	SF	6	\$3,333	
	Chalk Board	1st Floor	6	LF	4	\$551	
	Doors - Side-lite	1st Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,110	SF	6	\$2,429	
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	18	LF	6	\$386	
	Storage/ Closet	1st Floor	44	SF	6	\$319	
	Walls - Concrete Block	1st Floor	645	SF	6	\$1,891	
	Walls - Plaster/Drywall	1st Floor	645	SF	6	\$1,780	
	Work Sink	1st Floor	1	EA	6	\$379	

**Building: Linked Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #501 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	870	SF	6	\$2,613	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	870	SF	6	\$1,903	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	75	SF	6	\$544	
	Walls - Concrete Block	2nd Floor	510	SF	6	\$1,495	
	Walls - Plaster/Drywall	2nd Floor	510	SF	6	\$1,408	
<b>Classroom #502 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	870	SF	6	\$2,613	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	870	SF	6	\$1,903	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	75	SF	6	\$544	
	Walls - Concrete Block	2nd Floor	510	SF	6	\$1,495	
	Walls - Plaster/Drywall	2nd Floor	510	SF	6	\$1,408	
<b>Classroom #503 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	1,155	SF	6	\$3,468	stained ceiling tiles
	Doors - Side-lite	2nd Floor	24	SF	6	\$401	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,155	SF	6	\$2,527	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	64	SF	6	\$464	
	Walls - Concrete Block	2nd Floor	515	SF	6	\$1,510	
	Walls - Plaster/Drywall	2nd Floor	515	SF	6	\$1,421	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #504 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	575	SF	6	\$1,727	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	575	SF	6	\$1,258	
	Lighting - Lay-in	2nd Floor	8	EA	7	\$0	

**Building: Linked Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #504 (Regular Classroom)</b>							
	Marker Board	2nd Floor	26	LF	6	\$557	
	Storage/ Closet	2nd Floor	16	SF	6	\$116	
	Walls - Concrete Block	2nd Floor	415	SF	6	\$1,217	
	Walls - Plaster/Drywall	2nd Floor	415	SF	6	\$1,145	
<b>Classroom #505 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	870	SF	6	\$2,613	stained ceiling tiles
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	870	SF	4	\$7,477	cracked floor tiles
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Marker Board	2nd Floor	18	LF	6	\$386	
	Storage/ Closet	2nd Floor	34	SF	6	\$247	
	Walls - Concrete Block	2nd Floor	478	SF	6	\$1,401	
	Walls - Plaster/Drywall	2nd Floor	478	SF	6	\$1,319	
<b>Classroom #506 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	870	SF	6	\$2,613	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	870	SF	6	\$1,903	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Storage/ Closet	2nd Floor	75	SF	6	\$544	
	Walls - Concrete Block	2nd Floor	510	SF	6	\$1,495	
	Walls - Plaster/Drywall	2nd Floor	510	SF	6	\$1,408	
<b>Classroom #507 (Office)</b>							
	Ceiling - Lay-in	2nd Floor	240	SF	6	\$721	
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	240	SF	6	\$525	
	Lighting - Pendent/Surface	2nd Floor	4	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Storage/ Closet	2nd Floor	8	SF	6	\$58	
	Walls - Concrete Block	2nd Floor	380	SF	6	\$1,114	
<b>Classroom #509 (Language Lab)</b>							
	Ceiling - Lay-in	2nd Floor	150	SF	6	\$450	

## Building: Linked Addition

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #509 (Language Lab)</b>							
	Chalk Board	2nd Floor	8	LF	6	\$178	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	150	SF	6	\$320	
	Lighting - Pendent/Surface	2nd Floor	2	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	300	SF	6	\$828	
<b>Classroom #511 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	510	SF	6	\$1,532	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	510	SF	6	\$1,116	
	Lighting - Metal Halide/ High Pressure Sodium	2nd Floor	8	EA	7	\$0	
	Storage/ Closet	2nd Floor	8	SF	6	\$58	
	Student Lockers - One Tier	2nd Floor	12	EA	6	\$1,114	
	Walls - Plaster/Drywall	2nd Floor	860	SF	6	\$2,374	
<b>Classroom #601 (Computer Lab)</b>							
	Ceiling - Lay-in	3rd Floor	1,155	SF	6	\$3,468	stained ceiling tiles
	Doors - Side-lite	3rd Floor	24	SF	6	\$401	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	1,145	SF	6	\$2,505	
	Floor - Tile	3rd Floor	10	SF	5	\$58	missing tiles
	Lighting - Lay-in	3rd Floor	16	EA	6	\$1,904	
	Marker Board	3rd Floor	26	LF	6	\$557	
	Storage/ Closet	3rd Floor	18	SF	6	\$131	
	Walls - Concrete Block	3rd Floor	635	SF	6	\$1,862	
	Walls - Plaster/Drywall	3rd Floor	635	SF	6	\$1,753	
<b>Classroom #602 (Special Education)</b>							
	Ceiling - Lay-in	3rd Floor	575	SF	6	\$1,727	
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	575	SF	6	\$1,258	
	Lighting - Lay-in	3rd Floor	8	EA	7	\$0	
	Marker Board	3rd Floor	26	LF	6	\$557	
	Storage/ Closet	3rd Floor	16	SF	6	\$116	
	Walls - Concrete Block	3rd Floor	415	SF	6	\$1,217	
	Walls - Plaster/Drywall	3rd Floor	415	SF	6	\$1,145	

**Building: Linked Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #603 (Regular Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	575	SF	6	\$1,727	
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	575	SF	6	\$1,258	
	Lighting - Lay-in	3rd Floor	8	EA	7	\$0	
	Marker Board	3rd Floor	26	LF	6	\$557	
	Storage/ Closet	3rd Floor	16	SF	6	\$116	
	Walls - Concrete Block	3rd Floor	415	SF	6	\$1,217	
	Walls - Plaster/Drywall	3rd Floor	415	SF	6	\$1,145	
<b>Classroom #604 (Regular Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	870	SF	6	\$2,613	
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	870	SF	6	\$1,903	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	75	SF	6	\$544	
	Walls - Concrete Block	3rd Floor	510	SF	6	\$1,495	
	Walls - Plaster/Drywall	3rd Floor	510	SF	6	\$1,408	
<b>Classroom #605 (Regular Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	1,155	SF	6	\$3,468	
	Chalk Board	3rd Floor	10	LF	4	\$918	
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,155	SF	6	\$2,527	
	Lighting - Lay-in	3rd Floor	16	EA	6	\$1,904	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	55	SF	6	\$399	
	Walls - Concrete Block	3rd Floor	635	SF	6	\$1,862	
	Walls - Plaster/Drywall	3rd Floor	635	SF	6	\$1,753	
<b>Classroom #607 (Regular Classroom)</b>							
	Ceiling - Exposed	3rd Floor	1,155	SF	5	\$3,171	rusted deck from water damage
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,155	SF	6	\$2,527	
	Lighting - Pendent/Surface	3rd Floor	20	EA	7	\$0	



## Building: Linked Addition

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #607 (Regular Classroom)</b>							
	Marker Board	3rd Floor	18	LF	6	\$386	
	Storage/ Closet	3rd Floor	8	SF	6	\$58	
	Walls - Concrete Block	3rd Floor	635	SF	6	\$1,862	
	Walls - Plaster/Drywall	3rd Floor	635	SF	6	\$1,753	
<b>Classroom #611 (Regular Classroom)</b>							
	Ceiling - Exposed	3rd Floor	890	SF	6	\$1,324	
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	890	SF	6	\$1,947	
	Lighting - Lay-in	3rd Floor	13	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	490	SF	6	\$1,436	
	Walls - Metal Panel	3rd Floor	750	SF	6	\$5,598	
	Walls - Plaster/Drywall	3rd Floor	490	SF	6	\$1,352	

### Classrooms Subtotal:

**\$185,667**

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	Assistant Principal's Office	149	SF	6	\$447	
	Doors - Wood Doors inclu hw	Assistant Principal's Office	1	EA	6	\$301	
	Floor - Carpet	Assistant Principal's Office	149	SF	6	\$317	
	Lighting - Lay-in	Assistant Principal's Office	2	EA	7	\$0	
	Power Distribution	Assistant Principal's Office	8	EA	6	\$16,999	
	Walls - Concrete Block	Assistant Principal's Office	86	SF	6	\$252	
	Walls - Plaster/Drywall	Assistant Principal's Office	86	SF	6	\$237	
	Ceiling - Lay-in	Kitchen Manager's Office	147	SF	6	\$441	
	Doors - Steel Doors incl hw	Kitchen Manager's Office	1	EA	6	\$301	
	Floor - Tile	Kitchen Manager's Office	147	SF	6	\$322	
	Lighting - Lay-in	Kitchen Manager's Office	2	EA	7	\$0	
	Power Distribution	Kitchen Manager's Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Kitchen Manager's Office	169	SF	6	\$495	
	Ceiling - Lay-in	Main Office	493	SF	6	\$1,480	
	Doors - Side-lite	Main Office	224	SF	6	\$3,745	
	Doors - Wood Doors inclu hw	Main Office	2	EA	6	\$602	

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Floor - Carpet	Main Office	370	SF	6	\$788	
	Floor - Tile Quarry	Main Office	123	SF	6	\$260	
	Lighting - Lay-in	Main Office	6	EA	7	\$0	
	Power Distribution	Main Office	10	EA	6	\$21,249	
	Walls - Concrete Block	Main Office	283	SF	6	\$830	
	Walls - Plaster/Drywall	Main Office	283	SF	6	\$781	
	Ceiling - Lay-in	Office, Room 508	142	SF	6	\$426	
	Doors - Wood Doors inclu hw	Office, Room 508	1	EA	6	\$301	
	Floor - Tile	Office, Room 508	142	SF	5	\$638	broken tiles
	Lighting - Lay-in	Office, Room 508	3	EA	7	\$0	
	Power Distribution	Office, Room 508	6	EA	6	\$12,749	
	Walls - Concrete Block	Office, Room 508	41	SF	6	\$120	
	Walls - Plaster/Drywall	Office, Room 508	122	SF	6	\$337	6' chalkboard ranked "4"
	Ceiling - Lay-in	Office, Room 509	142	SF	6	\$426	
	Doors - Wood Doors inclu hw	Office, Room 509	1	EA	6	\$301	
	Floor - Tile	Office, Room 509	142	SF	6	\$311	
	Lighting - Lay-in	Office, Room 509	2	EA	7	\$0	
	Power Distribution	Office, Room 509	6	EA	6	\$12,749	
	Walls - Concrete Block	Office, Room 509	41	SF	6	\$120	
	Walls - Plaster/Drywall	Office, Room 509	122	SF	4	\$1,228	
	Ceiling - Lay-in	Office, Room 510	142	SF	6	\$426	
	Doors - Wood Doors inclu hw	Office, Room 510	1	EA	6	\$301	
	Floor - Tile	Office, Room 510	142	SF	6	\$311	
	Lighting - Lay-in	Office, Room 510	2	EA	7	\$0	
	Power Distribution	Office, Room 510	6	EA	6	\$12,749	
	Walls - Concrete Block	Office, Room 510	41	SF	6	\$120	
	Walls - Plaster/Drywall	Office, Room 510	122	SF	6	\$337	
	Work Slnk	Office, Room 510	1	EA	6	\$508	
	Ceiling - Lay-in	Office, Room 608, near Room 307	285	SF	6	\$856	
	Doors - Side-lite	Office, Room 608, near Room 307	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	Office, Room 608, near Room 307	1	EA	6	\$301	
	Floor - Tile	Office, Room 608, near Room 307	285	SF	6	\$624	
	Lighting - Lay-in	Office, Room 608, near Room 307	4	EA	7	\$0	
	Power Distribution	Office, Room 608, near Room 307	8	EA	6	\$16,999	
	Walls - Concrete Block	Office, Room 608, near Room 307	327	SF	6	\$959	6' marker board ranked "6"
<b>Kitchen</b>							
	Ceiling - Lay-in	1st Floor	438	SF	6	\$1,315	

**Building: Linked Addition**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Kitchen</b>							
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	438	SF	6	\$232	
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Walls - Concrete Block	1st Floor	503	SF	6	\$1,475	
<b>Library</b>							
	Casework	Room 600, 3rd Floor	124	LF	6	\$3,131	
	Ceiling - Lay-in	Room 600, 3rd Floor	2,104	SF	6	\$6,318	
	Doors - Side-lite	Room 600, 3rd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	Room 600, 3rd Floor	1	EA	6	\$301	
	Floor - Carpet	Room 600, 3rd Floor	2,104	SF	6	\$4,483	work sink ranked "6"
	Lighting - Lay-in	Room 600, 3rd Floor	30	EA	7	\$0	
	Walls - Concrete Block	Room 600, 3rd Floor	1,210	SF	6	\$3,547	
	Walls - Plaster/Drywall	Room 600, 3rd Floor	1,210	SF	6	\$3,339	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Lay-in	1st Floor	3,044	SF	6	\$9,141	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Floor - Tile	1st Floor	3,044	SF	6	\$6,660	
	Lighting - Lay-in	1st Floor	40	EA	7	\$0	
	Serving Line	1st Floor	8	LF	6	\$476	
	Walls - Concrete Block	1st Floor	3,500	SF	6	\$10,260	
	Ceiling - Lay-in	Room 500 Teacher's Lunch Room	210	SF	6	\$631	
	Doors - Wood Doors inclu hw	Room 500 Teacher's Lunch Room	1	EA	6	\$301	
	Floor - Carpet	Room 500 Teacher's Lunch Room	210	SF	6	\$447	
	Lighting - Lay-in	Room 500 Teacher's Lunch Room	3	EA	7	\$0	
	Market Board	Room 500 Teacher's Lunch Room	6	LF	6	\$129	
	Walls - Concrete Block	Room 500 Teacher's Lunch Room	183	SF	6	\$536	
	Walls - Plaster/Drywall	Room 500 Teacher's Lunch Room	61	SF	6	\$168	
<b>MDF_IDF</b>							
	AC Unit	2nd Floor	1	EA	6	\$496	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Finishes	2nd Floor	65	SF	6	\$464	
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	1st Floor	34	SF	6	\$244	
	Vaults	1st Floor	103	SF	6	\$738	in main office
	Boiler Room	2nd Floor	2,103	SF	6	\$15,067	

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	2nd Floor	34	SF	6	\$244	
	Mechanical/ Service Rooms	2nd Floor	132	SF	6	\$946	electrical room
	Janitor's Closet	3rd Floor	26	SF	6	\$186	
	Mechanical/ Service Rooms	3rd Floor	135	SF	6	\$967	electrical room
	Storage Room	3rd Floor	66	SF	6	\$473	
<b>Restroom</b>							
	Accessories	1st Floor	215	SF	6	\$1,983	
	Accessories	1st Floor	215	SF	6	\$1,983	
	Accessories	1st Floor	44	SF	6	\$406	
	Ceiling - Lay-in	1st Floor	44	SF	6	\$132	
	Ceiling - Plaster/Drywall	1st Floor	215	SF	6	\$744	
	Ceiling - Plaster/Drywall	1st Floor	215	SF	6	\$744	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor - Tile	1st Floor	44	SF	6	\$96	
	Floor - Tile Ceramic/ Porcelain	1st Floor	215	SF	6	\$455	
	Floor - Tile Ceramic/ Porcelain	1st Floor	215	SF	6	\$455	
	Hand Dryer	1st Floor	1	EA	6	\$230	
	Hand Dryer	1st Floor	2	EA	6	\$460	
	Lavatory	1st Floor	2	EA	6	\$639	
	Lavatory	1st Floor	2	EA	6	\$639	
	Lavatory	1st Floor	1	EA	6	\$320	
	Lighting - Lay-in	1st Floor	3	EA	7	\$0	
	Lighting - Lay-in	1st Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	1	EA	7	\$0	
	Partitions	1st Floor	1	EA	6	\$297	
	Partitions	1st Floor	4	EA	6	\$1,188	
	Urinals	1st Floor	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	1st Floor	44	SF	6	\$121	
	Walls - Structural Glazed Tile	1st Floor	247	SF	6	\$777	
	Walls - Structural Glazed Tile	1st Floor	247	SF	6	\$777	
	Walls - Tile Ceramic/ Porcelain	1st Floor	44	SF	6	\$99	
	Water Closet	1st Floor	1	EA	6	\$336	
	Water Closet	1st Floor	4	EA	6	\$1,344	

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	2nd Floor	215	SF	6	\$1,983	
	Accessories	2nd Floor	215	SF	6	\$1,983	
	Ceiling - Plaster/Drywall	2nd Floor	215	SF	6	\$744	
	Ceiling - Plaster/Drywall	2nd Floor	215	SF	6	\$744	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	215	SF	6	\$455	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	215	SF	6	\$455	
	Hand Dryer	2nd Floor	1	EA	6	\$230	
	Hand Dryer	2nd Floor	2	EA	6	\$460	
	Lavatory	2nd Floor	2	EA	6	\$639	
	Lavatory	2nd Floor	2	EA	6	\$639	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Partitions	2nd Floor	4	EA	6	\$1,188	
	Partitions	2nd Floor	1	EA	6	\$297	
	Urinals	2nd Floor	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	2nd Floor	247	SF	6	\$777	
	Walls - Structural Glazed Tile	2nd Floor	247	SF	6	\$777	
	Water Closet	2nd Floor	4	EA	6	\$1,344	
	Water Closet	2nd Floor	1	EA	6	\$336	
	Accessories	3rd Floor	215	SF	6	\$1,983	
	Accessories	3rd Floor	215	SF	6	\$1,983	
	Ceiling - Plaster/Drywall	3rd Floor	215	SF	6	\$744	
	Ceiling - Plaster/Drywall	3rd Floor	215	SF	6	\$744	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor Drain	3rd Floor	1	EA	6	\$1,059	
	Floor Drain	3rd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor	215	SF	6	\$455	
	Floor - Tile Ceramic/ Porcelain	3rd Floor	215	SF	6	\$455	
	Hand Dryer	3rd Floor	1	EA	6	\$230	
	Hand Dryer	3rd Floor	2	EA	6	\$460	
	Lavatory	3rd Floor	2	EA	6	\$639	
	Lavatory	3rd Floor	2	EA	6	\$639	

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	
	Partitions	3rd Floor	4	EA	6	\$1,188	
	Partitions	3rd Floor	1	EA	6	\$297	
	Urinals	3rd Floor	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	3rd Floor	247	SF	6	\$777	
	Walls - Structural Glazed Tile	3rd Floor	247	SF	6	\$777	
	Water Closet	3rd Floor	1	EA	6	\$336	
	Water Closet	3rd Floor	4	EA	6	\$1,344	
	Accessories	In Room 403	39	SF	6	\$360	
	Ceiling - Plaster/Drywall	In Room 403	39	SF	6	\$135	
	Doors - Wood Doors inclu hw	In Room 403	1	EA	6	\$301	
	Floor Drain	In Room 403	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	In Room 403	39	SF	6	\$83	
	Lavatory	In Room 403	1	EA	6	\$320	
	Lighting - Lay-in	In Room 403	1	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	In Room 403	48	SF	6	\$108	
	Water Closet	In Room 403	1	EA	6	\$336	
	Accessories	Men's Staff Room, 1st Floor	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	Men's Staff Room, 1st Floor	38	SF	6	\$132	
	Doors - Steel Doors incl hw	Men's Staff Room, 1st Floor	1	EA	6	\$301	
	Floor Drain	Men's Staff Room, 1st Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's Staff Room, 1st Floor	38	SF	6	\$80	
	Lavatory	Men's Staff Room, 1st Floor	1	EA	6	\$320	
	Lighting - Lay-in	Men's Staff Room, 1st Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Men's Staff Room, 1st Floor	49	SF	6	\$154	
	Water Closet	Men's Staff Room, 1st Floor	1	EA	6	\$336	
	Accessories	Men's Staff Room, 2nd Floor	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	Men's Staff Room, 2nd Floor	38	SF	6	\$132	
	Doors - Steel Doors incl hw	Men's Staff Room, 2nd Floor	1	EA	6	\$301	
	Floor Drain	Men's Staff Room, 2nd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's Staff Room, 2nd Floor	38	SF	6	\$80	
	Lavatory	Men's Staff Room, 2nd Floor	1	EA	6	\$320	
	Lighting - Lay-in	Men's Staff Room, 2nd Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Men's Staff Room, 2nd Floor	49	SF	6	\$154	
	Water Closet	Men's Staff Room, 2nd Floor	1	EA	6	\$336	
	Accessories	Men's Staff Room, 3rd Floor	38	SF	6	\$350	

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Ceiling - Plaster/Drywall	Men's Staff Room, 3rd Floor	38	SF	6	\$132	
	Doors - Steel Doors incl hw	Men's Staff Room, 3rd Floor	1	EA	6	\$301	
	Floor Drain	Men's Staff Room, 3rd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's Staff Room, 3rd Floor	38	SF	6	\$80	
	Lavatory	Men's Staff Room, 3rd Floor	1	EA	6	\$320	
	Lighting - Lay-in	Men's Staff Room, 3rd Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Men's Staff Room, 3rd Floor	49	SF	6	\$154	
	Water Closet	Men's Staff Room, 3rd Floor	1	EA	6	\$336	
	Accessories	Women's Staff Room, 1st Floor	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	Women's Staff Room, 1st Floor	38	SF	6	\$132	
	Doors - Steel Doors incl hw	Women's Staff Room, 1st Floor	1	EA	6	\$301	
	Floor Drain	Women's Staff Room, 1st Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Staff Room, 1st Floor	38	SF	6	\$80	
	Lavatory	Women's Staff Room, 1st Floor	1	EA	6	\$320	
	Lighting - Lay-in	Women's Staff Room, 1st Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Women's Staff Room, 1st Floor	49	SF	6	\$154	
	Water Closet	Women's Staff Room, 1st Floor	1	EA	6	\$336	
	Accessories	Women's Staff Room, 2nd Floor	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	Women's Staff Room, 2nd Floor	38	SF	6	\$132	
	Doors - Steel Doors incl hw	Women's Staff Room, 2nd Floor	1	EA	6	\$301	
	Floor Drain	Women's Staff Room, 2nd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Staff Room, 2nd Floor	38	SF	6	\$80	
	Lavatory	Women's Staff Room, 2nd Floor	1	EA	6	\$320	
	Lighting - Lay-in	Women's Staff Room, 2nd Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Women's Staff Room, 2nd Floor	49	SF	6	\$154	
	Water Closet	Women's Staff Room, 2nd Floor	1	EA	6	\$336	
	Accessories	Women's Staff Room, 3rd Floor	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	Women's Staff Room, 3rd Floor	38	SF	6	\$132	
	Doors - Steel Doors incl hw	Women's Staff Room, 3rd Floor	1	EA	6	\$301	
	Floor Drain	Women's Staff Room, 3rd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Staff Room, 3rd Floor	38	SF	6	\$80	
	Lavatory	Women's Staff Room, 3rd Floor	1	EA	6	\$320	
	Lighting - Lay-in	Women's Staff Room, 3rd Floor	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Women's Staff Room, 3rd Floor	49	SF	6	\$154	
	Water Closet	Women's Staff Room, 3rd Floor	1	EA	6	\$336	

**Building: Linked Addition**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Rooms (Other Than Classrooms) Subtotal:</b>						<b>\$268,378</b>	

**Building: Linked Addition**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	2,309	SF	6	\$6,934	
	Doors - Wood Doors include hw	1st Floor	2	EA	6	\$602	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	1st Floor	2,309	SF	6	\$1,255	
	Lighting - Pendent/Surface	1st Floor	17	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	2,655	SF	6	\$11,770	
	Ceiling - Plaster/Drywall	2nd Floor	2,309	SF	6	\$14,297	
	Doors - Wood Doors include hw	2nd Floor	2	EA	6	\$602	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	2nd Floor	2,309	SF	6	\$1,255	
	Lighting - Lay-in	2nd Floor	17	EA	7	\$0	
	Walls - Masonry	2nd Floor	2,655	SF	6	\$8,353	
	Ceiling - Lay-in	3rd Floor	2,309	SF	6	\$6,934	
	Doors - Wood Doors include hw	3rd Floor	2	EA	6	\$602	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	3rd Floor	2,309	SF	6	\$1,255	
	Lighting - Lay-in	3rd Floor	17	EA	7	\$0	
	Walls - Masonry	3rd Floor	2,655	SF	6	\$8,353	
<b>Safety</b>							
	Security Cameras	Entire Building	7	EA	6	\$1,358	
<b>Stairs</b>							
	Ceiling - Lay-in	North	1,833	SF	6	\$5,504	
	Floor - Rubber Floor	North	917	SF	6	\$1,980	
	Floor - Tile	North	917	SF	6	\$498	
	Handrails	North	228	LF	6	\$1,976	
	Lighting - Lay-in	North	6	EA	6	\$714	
	Lighting - Wall Mounted	North	9	EA	6	\$1,115	
	Stairs - Rubber	North	96	LF	6	\$1,032	
	Walls - Masonry	North	2,106	SF	6	\$6,625	
	Ceiling - Lay-in	South	1,260	SF	6	\$3,784	



**Building: Linked Addition**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Floor - Rubber Floor	South	680	SF	6	\$1,468	
	Floor - Tile	South	680	SF	6	\$370	
	Handrails	South	198	LF	6	\$1,716	
	Lighting - Lay-in	South	3	EA	7	\$0	
	Stairs - Rubber	South	90	LF	6	\$968	
	Walls - Masonry	South	1,449	SF	6	\$4,559	
<b>Vertical Conveyance</b>							
	Elevator - Elevator- Roped Holeless Hydraulic	1st Floor	1	EA	6	\$19,238	

**Building Interior Subtotal: \$116,770**

**Total Building Cost \$1,866,419**

**SITE**

**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site	5	EA	6	\$5,469	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	6	\$310	Courtyard between main and annex
	Civil/ Drainage - Site Manhole	Entire Site	8	EA	6	\$11,942	

**Fencing**

	Fencing - Chain Link	Entire Site / West Courtyard	415	LF	6	\$7,792	
	Fencing - Iron and Concrete Post	Entire Site / South West	32	LF	6	\$1,174	
	Fencing - New Standard Ornamental	Entire Site	867	LF	6	\$27,660	

**Landscape**

	Benches	Entire Site / West Courtyard	5	EA	6	\$2,150	
	Landscape - Grass	Entire Site	5,250	SF	6	\$4,354	
	Landscape - Hardscape- Concrete	Entire Site	10,250	SF	6	\$52,914	
	Landscape - Hardscape- Pavers	Entire Site	624	SF	6	\$3,534	
	Parkway trees	Entire Site	22	EA	6	\$14,521	
	Planting Beds/ Area	Entire Site / East Courtyard	655	SF	6	\$1,077	
	Play Area - Asphalt/ Hardscape	Entire Site / South West	13,250	SF	6	\$32,021	
	Trash Receptacles	Entire Site / West Courtyard	1	EA	6	\$312	

## SITE

### Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Parking Lot</b>							
	Concrete Curbs	NE Courtyard	338	LF	6	\$4,340	
	Concrete Curbs	SW Courtyard	364	LF	6	\$4,674	
	Interior Plantings	NE Courtyard	15	LF	6	\$638	
	Interior Plantings	SW Courtyard	15	LF	6	\$638	
	Surface - Asphalt	NE Courtyard	6,155	SF	6	\$14,875	
	Surface - Asphalt	SW Courtyard	7,627	SF	6	\$18,432	
	Trash Enclosure - Masonry	SW Courtyard	1,428	SF	6	\$56,340	
	Vehicular Screening	NE Courtyard	338	LF	6	\$26,613	
	Vehicular Screening	SW Courtyard	242	LF	6	\$19,054	
<b>Playground</b>							
	Equipment - Pre K 3-5	South Courtyard	1	EA	6	\$3,546	
	Equipment - School Age 5-12	South Courtyard	1	EA	6	\$3,546	
	Surface - Poured Surface	South Courtyard	4,325	SF	6	\$31,666	
<b>Sidewalks</b>							
	Sidewalks - Internal Walks	Entire Site	245	LF	6	\$2,943	
	Sidewalks - Perimeter Sidewalks	Entire Site	13,586	SF	6	\$27,005	
<b>Signage</b>							
	Flag Pole - Flag Pole	Entire Site / North East	1	EA	6	\$1,657	
	Marquee - Free Standing Back Lighted	Entire Site / North East	1	EA	6	\$0	
<b>Site Subtotal:</b>						<b>\$381,198</b>	
<b>Total Site Cost</b>						<b>\$381,198</b>	
<b>Campus Total <sup>2 3</sup></b>						<b>\$7,003,244</b>	

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

**Definitions**

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
  - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
  - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Art Room	Basement	001	001	1,230	1	1	10	98	42	40	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	204	204	840	1	3	116	88	45	40	N	N	N
Pre School	Pre School	Basement	009	009	1,210	1	1	18	84	36	40	N	Y	N
Pre School	Kindergarten	1st Floor	109	109	890	1	2	8	150	54	40	N	Y	N
Regular Classroom	Regular Classroom	Basement	003	003	588	1	2	12	56	24	40	N	Y	N
Regular Classroom	Regular Classroom	Basement	005	005	289	1	2	4	28	12	40	N	N	N
Regular Classroom	Regular Classroom	Basement	007	007	830	1	2	16	56	24	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	101	101	890	1	8	21	150	54	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	102	102	890	1	8	20	100	36	40	N	Y	N
Regular Classroom	Library	1st Floor	103	103	840	1	3	20	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	104	104	840	1	3	8	110	55	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	106	106	840	1	8	16	110	55	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	107	107	840	1	8	20	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	108	108	890	1	8	18	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	890	1	3	21	150	54	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	890	1	4	21	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	203	203	840	1	3	20	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	795	1	3	20	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	840	1	8	16	110	55	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	890	1	4	21	100	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	209	209	890	1	3	21	150	54	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	890	1	3	21	84	42	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	302	302	890	1	2	8	84	42	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	303	303	840	1	2	20	84	42	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	304	304	865	1	3	16	110	55	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	306	306	865	1	3	16	110	55	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	307	307	840	1	3	20	84	42	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	308	308	890	1	3	8	84	42	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	309	309	890	1	3	21	84	42	40	N	Y	N
Science	Regular Classroom	3rd Floor	305	305	795	1	3	20	84	42	40	N	Y	N
<b>4-Classroom Modular</b>														
Regular Classroom	Regular Classroom	1st Floor	M001	M001	740	1	3	8	100	36	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	M002	M002	740	1	3	8	100	36	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	M003	M003	740	1	3	8	100	36	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	M004	M004	740	1	3	8	100	36	40	Y	N	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Linked Addition</b>														
Computer Lab	Computer Lab	3rd Floor	601	303	1,155	1	10	160	160	12	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	401	109	775	1	2	18	245	12	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	402	111	985	1	2	26	145	6	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	403	113	1,110	1	2	30	185	9	40	N	Y	N
Language Lab	Language Lab	2nd Floor	509	509	150	1	2	6	54	24	40	N	Y	N
Office	Office	2nd Floor	507	507	240	1	2	6	25	24	40	N	Y	N
Pre School	Kindergarten	1st Floor	404	114	1,110	1	2	30	185	9	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	501	208	870	1	2	14	120	9	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	502	209	870	1	2	14	120	9	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	503	210	1,155	1	3	30	160	12	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	504	211	575	1	2	12	80	6	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	505	212	870	1	2	14	120	9	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	506	213	870	1	2	14	120	9	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	511	511	510	1	2	6	56	24	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	603	305	575	1	2	12	80	6	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	604	306	870	1	2	14	120	9	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	605	307	1,155	1	6	30	160	12	40	N	Y	N
Regular Classroom	Multi Purpose Room	3rd Floor	607	309	1,155	2	3	16	160	12	40	N	Y	N
Regular Classroom	Multi Purpose Room	3rd Floor	611	609	890	1	2	10	160	12	40	N	Y	N
Special Education	Special Program	3rd Floor	602	304	575	1	2	12	80	6	40	N	Y	N