

#### **Facility Assessment Report**

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About\_CPS/Policies\_and\_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1943	2	38,534	\$2,153,073
Addition	2015	1	37,942	\$36,963
SITE				\$260,833
Campus Total			76,476	\$2,450,869

**Building: Main** 

**Category: Building Exterior** 

July	ory: Building Extorior									
Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments			
Entrand	Entrance									
	Entrance Control - Audio and Video	#1 E	1	EA	6	\$702				
	Entrance Control - Audio and Video	#7 W	1	EA	6	\$702				
	Exterior Doors - Exterior FRP Door	#6.2 W / Basement	1	EA	6	\$631				
	Exterior Doors - Exterior Steel Door	#1 E	2	EA	6	\$961				
	Exterior Doors - Exterior Steel Door	#2 E	2	EA	6	\$961				
	Exterior Doors - Exterior Steel Door	#3 S	2	EA	6	\$961				
	Exterior Doors - Exterior Steel Door	#7 W	2	EA	6	\$961				
	Exterior Doors - Exterior Steel Door	#8 E	2	EA	6	\$961				
	Exterior Doors - Exterior Wood Door	#6.1 W	2	EA	4	\$7,645	Rotting			
	Exterior Doors - Transom Lite	#1 E	2	EA	6	\$627	Wood			
	Exterior Doors - Transom Lite	#2 E	2	EA	6	\$627	Wood			
	Exterior Doors - Transom Lite	#3 S	2	EA	6	\$627	Wood			
	Exterior Doors - Transom Lite	#8 E	1	EA	6	\$313				
	Exterior Stairs - Concrete	#1 E	57	LF	6	\$4,661				
	Exterior Stairs - Concrete	#2 E	57	LF	6	\$4,661				
	Exterior Stairs - Concrete	#3 S	57	LF	6	\$4,661				
	Exterior Stairs - Concrete	#6.2 W	60	LF	6	\$4,906				
	Exterior Stairs - Concrete	#7 W	40	LF	6	\$3,271				
	Exterior Stairs - Concrete	#8 E	73	LF	6	\$5,969				

5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

**Category: Building Exterior** 

	Item - Type	Location	Quantity	Hnit	Dank	Cost	Comments
Entran	**	Location	Quantity	Onit	Nalik	Cost	Comments
chtrane		#1 ⊑	0	1.5	6	¢00.4	
	Exterior Stairs - Stone	#1 E	8	LF LF	6	\$904	
	Exterior Stairs - Stone	#2 E			6	\$904	
	Exterior Stairs - Stone	#3 S	8	LF	6	\$904	
	Ramp Handrail - Steel_Ramp Handrail	#7 W	17	LF	6	\$147	
	Ramps - Concrete	#7 W	45	LF	5	\$23,923	
	Stair Handrail - Steel_Stair Handrail	#1 E	7	LF	6	\$61	
	Stair Handrail - Steel_Stair Handrail	#2 E	7	LF	6	\$61	
	Stair Handrail - Steel_Stair Handrail	#3 S	7	LF	6	\$61	
	Stair Handrail - Steel_Stair Handrail	#6.2 W	24	LF	6	\$208	
	Stair Handrail - Steel_Stair Handrail	#7 W	100	LF	6	\$867	
	Stair Handrail - Steel_Stair Handrail	#8 E	7	LF	6	\$61	
Founda	ation						
	Foundation - Concrete	Entire Building	785	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	38,534	SF	7	\$0	
Lightin		-					
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	8	EA	6	\$4,292	
	Exterior Lighting - Wall Mounted	Entire Building	8	EA	6	\$2,310	
	Exterior Eighting - VV all Modified	Entire Ballaling	0		5	ΨΖ,310	
Roof S	ystem						
	Cell Tower	Roof #1	1	EA	6	\$736	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof #1	15	LF	6	\$14,320	
	Coping - Stone	Roof #1	631	LF	6	\$20,266	
	Coping - Stone	Roof #2	253	LF	6	\$8,126	
	Downspouts - Interior Downspouts	Roof #1	180	LF	6	\$5,982	
	Downspouts - Interior Downspouts	Roof #2	70	LF	6	\$2,326	
	Parapet - 16" - 30" Height	Roof #2	253	LF	6	\$10,108	
	Parapet - Parapet < 16" Height	Roof #1	631	LF	6	\$13,445	
	Roof Structure - Steel with Clay Tile Arch	Roof #1	14,307	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #2	4,285	SF	7	\$0	
	Roof - Modified Bitumen	Roof #1	14,307	SF	6	\$134,620	
	Roof - Modified Bitumen	Roof #2	4,285	SF	6	\$40,319	
Walls							
	Cheek-Wall - Concrete	Entire Building	216	SF	6	\$2,215	
	Exterior Walls - Brick	Entire Building	22,475	SF	6	\$151,054	
	Exterior Walls - Stone-Cast	Entire Building	3,140	SF	6	\$21,104	
		-	•				



5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

**Category: Building Exterior** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments				
Windo	Vindows										
	Curtain wall - Insulated Panel	Entire Building	1,776	SF	6	\$19,911					
	Curtain wall - Louver	Entire Building	60	SF	6	\$673					
	Guard - Guards wire guard	Entire Building	200	SF	6	\$2,554					
	Lintels - Steel	Entire Building	350	LF	6	\$10,160					
	Lintels - Stone	Entire Building	285	LF	6	\$0					
	Windows - Decorative	Entire Building	252	SF	6	\$1,881					
	Windows - Sash Aluminum Double-pane	Entire Building	720	SF	6	\$5,375					
	Windows - Sash Aluminum Double-pane	Entire Building	1,200	SF	5	\$64,642	Broken Balances				
	Windows - Sash Lexan	Entire Building	1,077	SF	5	\$31,618					

**Building Exterior Subtotal:** 

\$640,944

**Building: Main** 

**Category: Electrical System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerg	ency System						
	Automatic Transfer Switch	Electrical Room	1	EA	4	\$8,200	
	Emergency A/C Power - Corridors and Stairs	Entire Building	7,484	SF	6	\$2,247	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	3,787	SF	6	\$1,408	
	Emergency Battery Packs - Corridors and Stairs	Entire Building / 2nd Floor	11	EA	6	\$2,228	
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	2	EΑ	6	\$405	
	Emergency Battery Packs - Students Toilets	Entire Building	4	EΑ	6	\$810	
	Exit Signs - Corridors and Stairs	Entire Building	16	EA	2	\$8,728	
	Exit Signs - Gym	Entire Building / 1st Floor	3	EA	2	\$1,735	
	Security System - CCTV	Entire Building	38,534	SF	6	\$11,572	
	Security System - Intrusion Detection	Entire Building	38,534	SF	6	\$9,919	
Main S	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	
	Main Electrical Service - 800 A and 120/208/3PH	Electrical Room	1	EA	6	\$3,570	
	PA System	Entire Building	38,534	SF	6	\$12,674	connected to annex
Power	Distribution						
	Lighting and Power Panels - 100 A	1st floor, Entire Building, Electrical room / 1st Floor	1	EA	7	\$0	
	Lighting and Power Panels - 100 A	1st floor, Entire Building, Electrical room / Entire Building	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	1st floor, Entire Building, Electrical room / Entire Building	4	EA	7	\$0	
ODIOL	F DADV	Dags 2 of 26					Assessment Date: 11/10/



5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

**Category: Electrical System** 

Group Item - Type	Location	Quantity Unit Rank	Cost Comments
Power Distribution			
Main Distribution Panels - 400 - 600 amp	1st floor, Entire Building, Electrical room / Electrical Room	1 EA 7	\$0

Electrical System Subtotal: \$63,495

**Building: Main** 

Category: Safty System

Group Item - Type	Location	Quantity Unit Ra	ank Cost (	Comments
Fire Alarm				
Fire Alarm Panel	Electrical Room	1 EA	7 \$0	
Fire Alarm Strobe Lights	Electrical Room / Entire Building	38,534 SF	6 \$13,776	
Fire Alarm_System	Electrical Room / Entire Building	38,534 SF	6 \$18,735	

Safty System Subtotal: \$32,511

**Building: Main** 

**Category: Mechanical System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Con	ditioning						
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	6	\$725	
	Chiller-Air Cooled-Scroll Type-Roof Mounted - 50 - 100 tons	Roof	1	EA	6	\$3,659	
	Condensing Unit- Ground Mounted - Less than 5 tons	2nd Floor	2	EA	6	\$6,667	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	serves computer room
	Glycol Feed	Roof / Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Steel	Roof / Entire Building	300	LF	6	\$566	
	Pressure Fill System	Roof / Mechanical Room	1	EA	6	\$1,405	
Air Han	dling Systems						
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000	Mechanical Room	1	EA	5	\$66,438	serves north side
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 8001 - 15000 cfm	Mechanical Room	1	EA	5	\$50,003	serves south side
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	
	Auxiliaries - 15001 - 25000 cfm	Mechanical Room	1	EA	5	\$14,899	
	Auxiliaries - 8001 - 15000 cfm	Mechanical Room	1	EA	5	\$12,908	
	Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM	Attic	1	EA	6	\$1,857	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	250	LF	7	\$0	
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	7	\$0	
ODIOLE	PARK	Dana 4 of 20					A

5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

**Category: Mechanical System** 

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems						
Roof Top Unit-Single Zone-Roof Mounted- Gas Heating Coil - 11 - 20 tons	Roof	1	EA	5	\$14,565	serves gymm does not cool
Zone Dampers	Mechanical Room	17	EA	6	\$14,162	
Zone Dampers	Mechanical Room	10	EA	6	\$8,330	
Boiler Systems						
Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 50 - 75 H	IP Mechanical Room	2	EA	4	\$23,013	
Chemical Feeder	Mechanical Room	1	EA	5	\$3,075	
Combustion Dampers	Mechanical Room	2	EA	6	\$818	
Condensate Pump	Mechanical Room	1	EA	5	\$18,196	
Feed Water Pumps and Tank	Mechanical Room / Boiler Room	1	EA	5	\$36,450	
Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 50 - 75 HP	Mechanical Room / Boiler Room	2	EA	4	\$75,476	
Piping - Condensate Pipe- Steel	Mechanical Room / Entire Building	300	LF	6	\$566	
Piping - Steam Pipe- Steel	Mechanical Room / Entire Building	300	LF	6	\$566	
Steam Traps	Mechanical Room / Entire Building	30	EA	5	\$39,447	
Heating Devices						
Unit Heater - Electric	Entire Building	3	EA	5	\$3,023	
Mechanical Plumbing						
Chilled Water Pump - Less than 10	Mechanical Room	2	EA	6	\$2,222	
Femperature Control						
Electric Thermostat	Entire Building	3	EA	6	\$0	
Pneumatic System	Entire Building	38,534	SF	5	\$132,800	
Thermostats - Pneumatic	Entire Building	20	EA	6	\$0	
Thermostats - Pneumatic	Entire Building	7	EA	4	\$5,161	
Unit Ventilation						
Unit Ventilators- Floor Mounted- Steam Heating & Chilled Water Coils	Entire Building	21	EA	5	\$227,681	
Ventilation						
Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof	2	EA	6	\$592	
Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof	1	EA	4	\$1,942	
Mechanical System Subtotal:					\$771 036	_

Mechanical System Subtotal:

\$771,036

**Building: Main** 

**Category: Plumbing System** 



5424 N Oketo Ave Chicago, IL 60656

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Wat	er						
	Gas Heater - Less than 150000 BTU/HR	Boiler Room	1	EA	6	\$310	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	38,534	SF	6	\$7,715	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	38,534	SF	6	\$9,368	
	Domestic Piping-Cold Water Risers	Entire Building	38,534	SF	6	\$7,163	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	38,534	SF	6	\$6,061	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	38,534	SF	6	\$7,163	
	Domestic Piping-Hot Water Return Lines	Entire Building	38,534	SF	6	\$5,510	
	Domestic Piping-Hot Water Return Risers	Entire Building	38,534	SF	6	\$5,510	
	Sanitary Piping	Entire Building	38,534	SF	6	\$35,266	
	Storm Piping	Entire Building	38,534	SF	6	\$33,613	
	Vent Piping	Entire Building	38,534	SF	6	\$25,899	
Pumps							
	Pumps - Sump-Duplex	Boiler Room / Mechanical Room	1	EA	6	\$1,387	
	Pumps - Sump-Simplex	Boiler Room	1	EA	6	\$745	
Plumb	oing System Subtotal:					\$145,711	

**Building: Main** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments			
Classro	Classroom #100 (Special Education)									
	Casework	1st Floor	5	LF	6	\$126				
	Ceiling - Plaster/Drywall	1st Floor	340	SF	6	\$1,177				
	Chalk Board	1st Floor	20	LF	4	\$1,836				
	Doors - Transom Window	1st Floor	9	SF	6	\$152				
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301				
	Floor - Tile/Sheet	1st Floor	340	SF	6	\$340				
	Lighting - Pendent/Surface	1st Floor	6	EA	7	\$0				
	Marker Board	1st Floor	6	LF	7	\$0				
	Walls - Plaster/Drywall	1st Floor	860	SF	6	\$2,374				
Classro	oom #101 (Music Room)									
	Casework	1st Floor	8	LF	6	\$202	*69 LF of bleacher seating			
	Ceiling - Plaster/Drywall	1st Floor	700	SF	6	\$2,422				
	Doors - Transom Window	1st Floor	9	SF	6	\$152				
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301				
	Floor - Wood	1st Floor	700	SF	6	\$4,935				
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0				

5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #101 (Music Room)						
	Walls - Plaster/Drywall	1st Floor	1,166	SF	6	\$3,218	
Classro	oom #102 (Regular Classroom)						
	Casework	1st Floor	12	LF	6	\$303	
	Ceiling - Plaster/Drywall	1st Floor	690	SF	6	\$2,388	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	690	SF	6	\$691	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	15	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	945	SF	6	\$2,608	
Classro	oom #103 (Kindergarten)						
	Casework	1st Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	1st Floor	700	SF	6	\$2,422	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	21	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,166	SF	6	\$3,218	
Classro	oom #104 (Kindergarten)						
	Casework	1st Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	1st Floor	825	SF	6	\$2,855	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	825	SF	6	\$5,816	
	Lighting - Pendent/Surface	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	54	SF	6	\$392	
	Walls - Plaster/Drywall	1st Floor	1,277	SF	6	\$3,524	
Classro	oom #105 (Regular Classroom)						
	Casework	1st Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	1st Floor	700	SF	6	\$2,422	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	700	SF	6	\$701	

5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #105 (Regular Classroom)						
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	21	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,166	SF	6	\$3,218	
Classro	oom #106 (Regular Classroom)						
	Casework	1st Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	1st Floor	720	SF	6	\$2,492	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	720	SF	6	\$721	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	21	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,190	SF	6	\$3,284	
Classro	oom #108 (Regular Classroom)						
	Casework	1st Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	1st Floor	825	SF	6	\$2,855	
	Chalk Board	1st Floor	42	LF	4	\$3,856	
	Doors - Transom Window	1st Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	825	SF	6	\$826	
	Lighting - Pendent/Surface	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Storage/ Closet	1st Floor	60	SF	6	\$435	
	Walls - Plaster/Drywall	1st Floor	1,262	SF	6	\$3,483	
	Walls - Plaster/Drywall	1st Floor	15	SF	5	\$77	* Peeling paint
Classro	oom #109 (Regular Classroom)						
	Casework	1st Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	1st Floor	700	SF	6	\$2,422	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	700	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	14	EA	6	\$1,735	
	Marker Board	1st Floor	29	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,166	SF	6	\$3,218	
Classro	oom #110 (Regular Classroom)						
	Casework	1st Floor	10	LF	6	\$253	

5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

	Item - Type	Location	Quantity	Linit	Dank	Cost	Comments
•	oom #110 (Regular Classroom)	Location	Quantity	Unit	Kalik	COSI	Comments
Classi	Ceiling - Plaster/Drywall	1st Floor	700	SF	6	¢2.422	
	Doors - Transom Window	1st Floor	700	SF	6	\$2,422 \$152	
			9				
	Doors - Wood Doors inclu hw	1st Floor	•	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	21	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,166	SF	6	\$3,218	
Classr	oom #200 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	700	SF	6	\$2,422	
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Transom Window	2nd Floor	9	SF	5	\$381	Transom boarded/covered
	Doors - Wood Doors inclu hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	2nd Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	2nd Floor	14	EΑ	7	\$0	
	Marker Board	2nd Floor	21	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,166	SF	6	\$3,218	
Classr	oom #201 (Art Room)						
	Casework	2nd Floor	12	LF	6	\$303	
	Doors - Transom Window	2nd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	2nd Floor	2	EΑ	6	\$602	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	1,227	SF	6	\$2,597	
	Lighting - Pendent/Surface	2nd Floor	16	EΑ	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Storage/ Closet	2nd Floor	104	SF	6	\$754	Art prep room
	Walls - Plaster/Drywall	2nd Floor	1,513	SF	6	\$4,176	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classr	oom #202 (Regular Classroom)						
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	700	SF	6	\$2,422	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	700	SF	6	\$4,935	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,166	SF	6	\$3,218	



5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	om #202 (Regular Classroom)	Location	Quantity	Offic	Num	COSI	Comments
C105510C	Jiii #202 (Negulai Classicolli)						
Classroc	om #204 (Science Classroom)						
	Casework	2nd Floor	48	LF	6	\$1,212	
	Ceiling - Plaster/Drywall	2nd Floor	700	SF	6	\$2,422	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	14	LF	7	\$0	
	Storage/ Closet	2nd Floor	10	SF	6	\$73	
	Walls - Plaster/Drywall	2nd Floor	1,166	SF	6	\$3,218	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroo	om #205 (Regular Classroom)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	2nd Floor	700	SF	6	\$2,422	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	21	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,166	SF	6	\$3,218	
Classroo	om #206 (Regular Classroom)						
	Casework	2nd Floor	21	LF	6	\$530	
	Ceiling - Plaster/Drywall	2nd Floor	720	SF	6	\$2,492	
	Chalk Board	2nd Floor	4	LF	4	\$367	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	720	SF	6	\$721	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,159	SF	6	\$3,199	
Classroo	om #207 (Regular Classroom)						
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Plaster/Drywall	2nd Floor	400	SF	6	\$1,384	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	



**Building: Main** 

**Category: Classrooms** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classr	oom #207 (Regular Classroom)						
	Floor - Tile/Sheet	2nd Floor	400	SF	6	\$400	
	Lighting - Pendent/Surface	2nd Floor	4	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	864	SF	6	\$2,385	
Classr	oom #208 (Regular Classroom)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	2nd Floor	700	SF	6	\$2,422	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,166	SF	6	\$3,218	
Classr	oom #209 (Regular Classroom)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	2nd Floor	720	SF	6	\$2,492	
	Chalk Board	2nd Floor	4	LF	4	\$367	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	2nd Floor	720	SF	6	\$721	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,190	SF	6	\$3,284	
Classr	oom #210 (Regular Classroom)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Plaster/Drywall	2nd Floor	700	SF	6	\$2,422	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	700	SF	6	\$701	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	32	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,166	SF	6	\$3,218	
						<b>#</b> 405 000	

Classrooms Subtotal:

\$165,663

**Building: Main** 

5424 N Oketo Ave Chicago, IL 60656

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Ceiling - Exposed	Basement-Engineers Office	135	SF	6	\$201	
	Doors - Wood Doors inclu hw	Basement-Engineers Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Basement-Engineers Office	135	SF	6	\$135	
	Lighting - Pendent/Surface	Basement-Engineers Office	3	EA	6	\$372	
	Power Distribution	Basement-Engineers Office	6	EA	7	\$0	
	Walls - Structural Glazed Tile	Basement-Engineers Office	418	SF	6	\$1,315	
	Ceiling - Plaster/Drywall	Room 104 Wardrobe/Office	140	SF	6	\$484	
	Doors - Wood Doors inclu hw	Room 104 Wardrobe/Office	1	EA	6	\$301	
	Floor - Wood	Room 104 Wardrobe/Office	140	SF	6	\$987	
	Lighting - Pendent/Surface	Room 104 Wardrobe/Office	2	EA	7	\$0	
	Power Distribution	Room 104 Wardrobe/Office	6	EA	7	\$0	
	Storage/ Closet	Room 104 Wardrobe/Office	20	SF	6	\$145	
	Walls - Plaster/Drywall	Room 104 Wardrobe/Office	754	SF	6	\$2,081	
	Ceiling - Plaster/Drywall	Room 108 Wardrobe/Office	140	SF	6	\$484	
	Doors - Side-lite	Room 108 Wardrobe/Office	6	SF	5	\$420	*Sidelite Boarded/covered
	Doors - Wood Doors inclu hw	Room 108 Wardrobe/Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 108 Wardrobe/Office	140	SF	6	\$140	
	Lighting - Pendent/Surface	Room 108 Wardrobe/Office	2	EA	7	\$0	
	Power Distribution	Room 108 Wardrobe/Office	6	EA	7	\$0	
	Storage/ Closet	Room 108 Wardrobe/Office	32	SF	6	\$232	
	Walls - Plaster/Drywall	Room 108 Wardrobe/Office	750	SF	6	\$2,070	
	Ceiling - Plaster/Drywall	Room 211-Office	226	SF	6	\$782	
	Doors - Wood Doors inclu hw	Room 211-Office	1	EA	6	\$301	
	Floor - Concrete	Room 211-Office	226	SF	6	\$120	
	Lighting - Pendent/Surface	Room 211-Office	2	EA	7	\$0	
	Power Distribution	Room 211-Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	Room 211-Office	499	SF	6	\$1,377	
	Ceiling - Plaster/Drywall	Teacher's Lounge on 2nd Floor	252	SF	6	\$872	
	Doors - Wood Doors inclu hw	Teacher's Lounge on 2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	Teacher's Lounge on 2nd Floor	252	SF	6	\$252	
	Lighting - Pendent/Surface	Teacher's Lounge on 2nd Floor	3	EA	7	\$0	
	Power Distribution	Teacher's Lounge on 2nd Floor	4	EA	7	\$0	
	Walls - Plaster/Drywall	Teacher's Lounge on 2nd Floor	555	SF	6	\$1,532	
Gymna	sia						
	Bleacher Seating	1st Floor	64	EA	6	\$1,852	
	Ceiling - Lay-in	1st Floor	2,400	SF	6	\$7,207	
	Doors - Wood Doors inclu hw	1st Floor	6	EA	6	\$1,806	
	Floor - Sport Flooring	1st Floor	2,400	SF	6	\$5,182	
	· · · · · ·		•			•	

5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymna	sia						
	Lighting - Metal Halide/Sodium Vapor	1st Floor	20	EA	7	\$0	
	Scoreboards	1st Floor	1	EA	6	\$2,244	
	Sound System	1st Floor	1	EA	6	\$41,654	
	Stage	1st Floor	260	SF	6	\$1,502	
	Stage Curtain	1st Floor	8	EA	7	\$0	
	Stage Lighting System	1st Floor	1	EA	6	\$12,369	
	Stage-Stairs - Tile	1st Floor	6	LF	6	\$56	
	Storage/ Closet	1st Floor	20	SF	6	\$145	
	Walls - Structural Glazed Tile	1st Floor	4,000	SF	6	\$12,584	
Mechar	nical/ Service Rooms						
	Janitor's Closet	1st Floor	50	SF	6	\$358	
	Janitor's Closet	1st Floor	20	SF	6	\$143	
	Janitor's Closet	2nd Floor	9	SF	6	\$64	
	Janitor's Closet	2nd Floor	75	SF	6	\$537	
	Janitor's Closet	2nd Floor	20	SF	6	\$143	
	Storage Room	2nd Floor	32	SF	6	\$229	Book Storage
	Boiler Room	Basement-Boiler Room	1,368	SF	6	\$9,801	
	Coal Room	Basement-Boiler Room	360	SF	6	\$2,579	
Restroc	om						
	Accessories	1st Floor Boy's Room	269	SF	6	\$2,481	
	Ceiling - Plaster/Drywall	1st Floor Boy's Room	269	SF	6	\$931	
	Doors - Transom Window	1st Floor Boy's Room	36	SF	6	\$610	
	Doors - Wood Doors inclu hw	1st Floor Boy's Room	2	EΑ	6	\$602	
	Floor Drain	1st Floor Boy's Room	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor Boy's Room	8	SF	5	\$167	*Floor tile damaged/miissing
	Floor - Tile Ceramic/ Porcelain	1st Floor Boy's Room	269	SF	6	\$569	
	Hand Dryer	1st Floor Boy's Room	3	EΑ	6	\$690	
	Lavatory	1st Floor Boy's Room	2	EΑ	6	\$639	
	Lighting - Pendent/Surface	1st Floor Boy's Room	4	EA	7	\$0	
	Partitions	1st Floor Boy's Room	3	EA	6	\$891	
	Urinals	1st Floor Boy's Room	6	EA	6	\$2,016	
	Walls - Plaster/Drywall	1st Floor Boy's Room	162	SF	6	\$447	
	Walls - Structural Glazed Tile	1st Floor Boy's Room	651	SF	6	\$2,048	
	Water Closet	1st Floor Boy's Room	3	EA	6	\$1,008	
	Accessories	1st Floor Girl's Room	271	SF	6	\$2,500	
	Ceiling - Plaster/Drywall	1st Floor Girl's Room	271	SF	6	\$938	

**Building: Main** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Doors - Transom Window	1st Floor Girl's Room	36	SF	6	\$610	
	Doors - Wood Doors inclu hw	1st Floor Girl's Room	2	EA	6	\$602	
	Floor Drain	1st Floor Girl's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor Girl's Room	2	SF	5	\$42	*Floor tile damaged/missing
	Floor - Tile Ceramic/ Porcelain	1st Floor Girl's Room	271	SF	6	\$574	
	Hand Dryer	1st Floor Girl's Room	2	EA	6	\$460	
	Lavatory	1st Floor Girl's Room	2	EΑ	6	\$639	
	Lighting - Pendent/Surface	1st Floor Girl's Room	4	EA	7	\$0	
	Partitions	1st Floor Girl's Room	6	EA	6	\$1,782	
	Walls - Plaster/Drywall	1st Floor Girl's Room	158	SF	6	\$436	
	Walls - Structural Glazed Tile	1st Floor Girl's Room	635	SF	6	\$1,998	
	Water Closet	1st Floor Girl's Room	7	EΑ	6	\$2,352	
	Accessories	1st Floor Men's Room	62	SF	6	\$572	
	Ceiling - Plaster/Drywall	1st Floor Men's Room	62	SF	6	\$215	
	Doors - Wood Doors inclu hw	1st Floor Men's Room	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Floor Men's Room	62	SF	6	\$131	
	Lavatory	1st Floor Men's Room	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st Floor Men's Room	2	EA	7	\$0	
	Partitions	1st Floor Men's Room	1	EΑ	6	\$297	
	Walls - Plaster/Drywall	1st Floor Men's Room	329	SF	6	\$908	
	Water Closet	1st Floor Men's Room	1	EΑ	6	\$336	
	Accessories	2nd Floor Boy's Room	269	SF	6	\$2,481	
	Ceiling - Plaster/Drywall	2nd Floor Boy's Room	269	SF	6	\$931	
	Doors - Transom Window	2nd Floor Boy's Room	36	SF	6	\$610	
	Doors - Wood Doors inclu hw	2nd Floor Boy's Room	2	EA	6	\$602	
	Floor Drain	2nd Floor Boy's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Boy's Room	269	SF	6	\$569	
	Hand Dryer	2nd Floor Boy's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Boy's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd Floor Boy's Room	4	EA	7	\$0	
	Partitions	2nd Floor Boy's Room	3	EA	6	\$891	
	Urinals	2nd Floor Boy's Room	6	EA	6	\$2,016	
	Walls - Plaster/Drywall	2nd Floor Boy's Room	162	SF	6	\$447	
	Walls - Structural Glazed Tile	2nd Floor Boy's Room	651	SF	6	\$2,048	
	Water Closet	2nd Floor Boy's Room	3	EA	6	\$1,008	
	Accessories	2nd Floor Girl's Room	271	SF	6	\$2,500	
	Ceiling - Plaster/Drywall	2nd Floor Girl's Room	271	SF	6	\$938	

**Building: Main** 

up	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
tro	om						
	Doors - Transom Window	2nd Floor Girl's Room	36	SF	6	\$610	
	Doors - Wood Doors inclu hw	2nd Floor Girl's Room	2	EA	6	\$602	
	Floor Drain	2nd Floor Girl's Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Girl's Room	271	SF	6	\$574	
	Hand Dryer	2nd Floor Girl's Room	2	EA	6	\$460	
	Lavatory	2nd Floor Girl's Room	2	EA	6	\$639	
	Lighting - Pendent/Surface	2nd Floor Girl's Room	4	EA	7	\$0	
	Partitions	2nd Floor Girl's Room	6	EA	6	\$1,782	
	Walls - Plaster/Drywall	2nd Floor Girl's Room	158	SF	6	\$436	
	Walls - Structural Glazed Tile	2nd Floor Girl's Room	635	SF	6	\$1,998	
	Water Closet	2nd Floor Girl's Room	7	EA	6	\$2,352	
	Accessories	Basement-Custodian Restroom	32	SF	6	\$295	
	Ceiling - Exposed	Basement-Custodian Restroom	32	SF	6	\$48	
	Doors - Wood Doors inclu hw	Basement-Custodian Restroom	1	EA	6	\$301	
	Floor - Concrete	Basement-Custodian Restroom	32	SF	6	\$17	
	Lavatory	Basement-Custodian Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Basement-Custodian Restroom	1	EA	7	\$0	
	Walls - Structural Glazed Tile	Basement-Custodian Restroom	277	SF	6	\$871	
	Walls - Structural Glazed Tile	Basement-Custodian Restroom	6	SF	5	\$383	*Damage to wall
	Water Closet	Basement-Custodian Restroom	1	EA	6	\$336	
	Accessories	In Teacher's Lounge, 2nd Floor	40	SF	6	\$369	
	Ceiling - Plaster/Drywall	In Teacher's Lounge, 2nd Floor	40	SF	6	\$138	
	Doors - Wood Doors inclu hw	In Teacher's Lounge, 2nd Floor	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	In Teacher's Lounge, 2nd Floor	40	SF	6	\$85	
	Lavatory	In Teacher's Lounge, 2nd Floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	In Teacher's Lounge, 2nd Floor	1	EA	7	\$0	
	Partitions	In Teacher's Lounge, 2nd Floor	1	EA	6	\$297	
	Walls - Plaster/Drywall	In Teacher's Lounge, 2nd Floor	179	SF	6	\$494	
	Water Closet	In Teacher's Lounge, 2nd Floor	1	EA	6	\$336	
	Accessories	In the Engineer's Office	29	SF	6	\$267	
	Ceiling - Exposed	In the Engineer's Office	29	SF	6	\$43	
	Doors - Wood Doors inclu hw	In the Engineer's Office	1	EA	6	\$301	
	Floor - Concrete	In the Engineer's Office	29	SF	6	\$15	
	Lavatory	In the Engineer's Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	In the Engineer's Office	1	EA	7	\$0	
	Walls - Concrete Block	In the Engineer's Office	259	SF	6	\$759	
	Water Closet	In the Engineer's Office	1	EΑ	6	\$336	



5424 N Oketo Ave Chicago, IL 60656

**Building: Main** 

**Category: Rooms (Other Than Classrooms)** 

Group Item - Type Location Quantity Unit Rank Cost Comments

Rooms (Other Than Classrooms) Subtotal:

\$181,852

**Building: Main** 

**Category: Building Interior** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	or						
	Ceiling - Plaster/Drywall	1st Floor	2,962	SF	6	\$18,340	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Transom Window	1st Floor	21	EA	6	\$356	
	Doors - Wood Doors include hw	1st Floor	9	EA	6	\$2,709	
	Drinking Fountains - Double Fountain	1st Floor	2	EA	6	\$672	
	Floor - Tile/Sheet	1st Floor	3,381	SF	6	\$1,837	
	Lighting - Pendent/Surface	1st Floor	35	EA	7	\$0	
	Student Lockers - One Tier	1st Floor	157	EA	6	\$14,575	
	Walls - Plaster/Drywall	1st Floor	1,480	SF	6	\$6,561	
	Walls - Structural Glazed Tile	1st Floor	1,481	SF	6	\$4,659	
	Ceiling - Plaster/Drywall	2nd Floor	2,688	SF	6	\$16,644	
	Doors - Steel Doors incl hw	2nd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	2nd Floor	2	EA	6	\$672	
	Floor - Tile/Sheet	2nd Floor	2,688	SF	6	\$1,461	
	Lighting - Pendent/Surface	2nd Floor	33	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	157	EA	6	\$14,575	
	Walls - Plaster/Drywall	2nd Floor	1,680	SF	6	\$7,447	
	Walls - Structural Glazed Tile	2nd Floor	1,679	SF	6	\$5,282	
Stairs							
	Ceiling - Plaster/Drywall	Stair, Tower, Entire Building	2,415	SF	6	\$17,682	
	Floor - Terrazzo	Stair, Tower, Entire Building	2,415	SF	6	\$20,272	
	Handrails	Stair, Tower, Entire Building	414	LF	6	\$3,588	
	Lighting - Pendent/Surface	Stair, Tower, Entire Building	24	EA	7	\$0	
	Stairs - Terrazzo	Stair, Tower, Entire Building	180	LF	6	\$1,671	
	Walls - Plaster/Drywall	Stair, Tower, Entire Building	1,871	SF	6	\$5,164	
	Walls - Structural Glazed Tile	Stair, Tower, Entire Building	1,872	SF	6	\$5,889	

**Building Interior Subtotal:** 

\$151,861



5424 N Oketo Ave Chicago, IL 60656

Total Building Cost \$2,153,073

**Building: Addition** 

**Category: Building Exterior** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrand	ce						
	Entrance Control - Audio and Video	#4 S	1	EA	7	\$0	
	Entrance Control - Audio and Video	#5 W	1	EΑ	7	\$0	
	Entrance Control - Audio and Video	#6 N	1	EΑ	7	\$0	
	Exterior Doors - Exterior FRP Door	#4.1 S	2	EA	7	\$0	
	Exterior Doors - Exterior FRP Door	#5.1 N	1	EA	7	\$0	
	Exterior Doors - Store Front	#4 S	4	EA	7	\$0	
	Exterior Doors - Store Front	#5 W	2	EA	7	\$0	
	Exterior Doors - Store Front	#6 N	2	EA	7	\$0	
	Exterior Doors - Transom Lite	#4 S	4	EA	7	\$0	
	Exterior Doors - Transom Lite	#5 W	2	EA	7	\$0	
	Exterior Doors - Transom Lite	#6 N	2	EA	7	\$0	
	Power Door Operator and Controls	#4 S	2	EA	7	\$0	
Founda	tion						
	Foundation - Concrete	Entire Building	663	LF	7	\$0	
	Superstructure - Metal Deck/ Concrete Topping	Entire Building	37,942	SF	7	\$0	
Lighting	9						
	Exterior Lighting - Wall Mounted	Entire Building	16	EA	7	\$0	
	Exterior Lighting - Wall Mounted	Entire Building / Site West	2	EA	7	\$0	
Roof Sy	/stem						
	Coping - Metal	Roof #1	663	LF	7	\$0	
	Coping - Metal	Roof #2	166	LF	7	\$0	
	Coping - Stone	Roof #2 / Site West	75	LF	7	\$0	
	Downspouts - Exterior Downspouts	Roof #1	299	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof #2	58	LF	7	\$0	
	Parapet - 16" - 30" Height	Roof #1	663	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof #2	166	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof #1	19,507	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof #2	2,198	SF	7	\$0	
	Roof - Modified Bitumen	Roof #1	19,507	SF	7	\$0	
	Roof - Modified Bitumen	Roof #2	2,198	SF	7	\$0	
Walls							
	Canopy - Concrete/ Stucco	Entire Building / South Façade	447	SF	7	\$0	
	Canopy - Metal	Entire Building / North Entrances	32	SF	7	\$0	



5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Building Exterior** 

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments				
Walls										
Exterior Walls - Brick	Entire Building	17,512	SF	7	\$0					
Exterior Walls - Brick	Entire Building / Site West	580	SF	7	\$0					
Exterior Walls - Stone-Cast	Entire Building	860	SF	7	\$0					
Windows	lindows									
Guard - Guards perforated	Entire Building	2,379	SF	7	\$0					
Lintels - Steel	Entire Building	580	LF	7	\$0					
Windows - Decorative	Entire Building	906	SF	7	\$0					
Windows - Sash Aluminum Double-pane	Entire Building	3,263	SF	7	\$0					

**Building Exterior Subtotal:** 

\$0

**Building: Addition** 

**Category: Electrical System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerge	ncy System						
	Automatic Transfer Switch	Electrical Room	2	EA	7	\$0	
	Emergency A/C Power - Corridors and Stairs	Entire Building	4,350	SF	7	\$0	
	Emergency A/C Power - Students Toilets	Entire Building	1,150	SF	7	\$0	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	22	EA	7	\$0	
	Emergency Battery Packs - Lunchrooms	Entire Building / 1st Floor	7	EA	7	\$0	
	Emergency Battery Packs - Multipurpose Room	Entire Building / 1st Floor	5	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	18	EΑ	7	\$0	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	6	EΑ	7	\$0	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	3	EΑ	7	\$0	
	Security System - CCTV	Entire Building	37,942	SF	7	\$0	
	Security System - Intrusion Detection	Entire Building	37,942	SF	7	\$0	
	UPS - Less than 30 KW	Electrical Room	1	EA	7	\$0	
Main Se	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	
	Main Electrical Service - 1200 A 277/480/3PH	Electrical Room	1	EΑ	7	\$0	
	PA System	Entire Building	37,942	SF	7	\$0	
Power I	Distribution						
	Lighting and Power Panels - 100 A	Entire Building	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	6	EΑ	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	7	\$0	



5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Electrical System** 

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments	
Power Distribution						
Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	2	EA	7	\$0	
Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	
Main Distribution Panels - Greater than 600 amp	Entire Building	1	EA	7	\$0	
Transformers - 277/480 - 120/208	Entire Building / Electrical Room	2	EA	7	\$0	
Electrical System Subtotal:					<b>\$0</b>	

**Building: Addition** 

**Category: Safty System** 

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments	
Fire Alarm						
Fire Alarm Panel	Electrical Room	1	EA	7	\$0	
Fire Alarm Strobe Lights	Electrical Room / Entire Building	37,942	SF	7	\$0	
Fire Alarm_System	Electrical Room / Entire Building	37,942	SF	7	\$0	
Fire Pump Controller	Electrical Room / Mechanical Room	1	EA	7	\$0	
Pump Room Assembly						
Fire Pump - 25-50 hp	1st Floor	1	EA	7	\$0	
Jockey Pump	1st Floor	1	EA	7	\$0	
Safty System Subtotal:					\$0	

**Building: Addition** 

**Category: Mechanical System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments			
Air Cor	r Conditioning									
	Chemical Pot Feeder	Site West / Mechanical Room	1	EA	7	\$0				
	Chiller-Air Cooled-Scroll Type-Ground Mounted - 101 - 150 tons	Site West	1	EA	7	\$0				
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	7	\$0				
	Glycol Feed	Site West / Mechanical Room	1	EA	7	\$0				
	Pipes - Chilled Water Pipe- Copper	Site West / Entire Building	300	LF	7	\$0				
	Pressure Fill System	Site West / Mechanical Room	1	EA	7	\$0				
Air Har	dling Systems									
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	Mechanical Room	1	EA	7	\$0				
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	Mechanical Room	1	EA	7	\$0				

5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Mechanical System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Han	dling Systems						
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 10 - 20 tons	Roof	1	EA	7	\$0	
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 10 - 20 tons	Roof	1	EA	7	\$0	
Boiler S	systems						
	Boiler Auxiliary- Condensing Hot Water - 1001 - 2000 HP	Boiler Room	2	EA	7	\$0	
	Chemical Pot Feeder	Boiler Room / Mechanical Room	1	EA	7	\$0	
	Condensing- Hot Water Boiler - 1001 - 2000 MBH	Boiler Room	2	EΑ	7	\$0	
	Glycol Feed System	Boiler Room / Mechanical Room	1	EΑ	7	\$0	
	Water Fill System	Boiler Room / Mechanical Room	1	EA	7	\$0	
Gas Bo	oster						
	Gas Booster	Boiler Room	2	EA	7	\$0	
Heating	Devices						
	Cabinet Heaters - With Hot Water Coil	Entire Building	4	EA	7	\$0	
	Unit Heater - Electric	Entire Building / 2nd Floor	1	EA	7	\$0	
	Unit Heater - Hot Water	Entire Building / 1st Floor	2	EA	7	\$0	
	Wall Heater - Electric	Entire Building	4	EA	7	\$0	
Mechar	ical Plumbing						
	Chilled Water Pump - 10 - 20 HP	Mechanical Room	2	EA	7	\$0	
	Daul Temperature Pump - 10 - 20 HP	Mechanical Room	2	EΑ	7	\$0	
	Hot Water Pump - Less than 10	Mechanical Room / Boiler Room	2	EA	7	\$0	
	Hydronic Supply and Return - Copper	Entire Building	600	LF	7	\$0	
Temper	ature Control						
	DDC System	Entire Building	37,942	SF	7	\$0	
	Electric Thermostat	Entire Building	3	EΑ	7	\$0	
	Thermostats - DDC	Entire Building	28	EA	7	\$0	
Ventilat	ion						
	Exhaust Fans- Indoor - Less than 500 CFM	Entire Building	2	EA	7	\$0	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	4	EA	7	\$0	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	7	\$0	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	7	\$0	
Mecha	anical System Subtotal:					\$0	

Mechanical System Subtotal:



5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Plumbing System** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Wa	ter						
	Gas Heater - Less than 150000 BTU/HR	Boiler Room	2	EA	7	\$0	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	37,942	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	37,942	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	37,942	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building / Entire Site	37,942	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	37,942	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	37,942	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	37,942	SF	7	\$0	
	Sanitary Piping	Entire Building	37,942	SF	7	\$0	
	Storm Piping	Entire Building	37,942	SF	7	\$0	
	Vent Piping	Entire Building	37,942	SF	7	\$0	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	1st Floor / 2nd Floor	1	EA	7	\$0	
	Pumps - Sump-Simplex	1st Floor	1	EA	7	\$0	
Plumb	oing System Subtotal:					\$0	

**Building: Addition** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	om #153 (Kindergarten)						
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	1,010	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	2	EA	7	\$0	
	Floor - Tile	1st Floor	1,010	SF	7	\$0	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Storage/ Closet	1st Floor	70	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,184	SF	7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	
Classro	oom #155 (Kindergarten)						
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	1,010	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	2	EA	7	\$0	

5424 N Oketo Ave Chicago, IL 60656

### **Building: Addition**

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	oom #155 (Kindergarten)	Location	Qualitity	Oill	Nain	CUSI	Commence
Cidool	Floor - Tile	1st Floor	1,010	SF	7	\$0	
		1st Floor	1,010	SF EA	7 7	\$0 \$0	
	Lighting - Lay-in Marker Board	1st Floor	14	LF	7 7	\$0 \$0	
		1st Floor	70			\$0 \$0	
	Storage/ Closet	1st Floor		SF SF	7		
	Walls - Plaster/Drywall		1,184		7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	
Classro	oom #157 (Kindergarten)						
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	1,010	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	2	EA	7	\$0	
	Floor - Tile	1st Floor	1,010	SF	7	\$0	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Storage/ Closet	1st Floor	70	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,184	SF	7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	
Classro	oom #159 (Pre School)						
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	1,010	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	2	EA	7	\$0	
	Floor - Tile	1st Floor	1,010	SF	7	\$0	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Storage/ Closet	1st Floor	70	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,184	SF	7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	
Classro	oom #161 (Pre School)						
	Casework	1st Floor	8	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	1,010	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	2	EA	7	\$0	
	Floor - Tile	1st Floor	1,010	SF	7	\$0	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Storage/ Closet	1st Floor	70	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,184	SF	7	\$0	
	Work Sink	1st Floor	1	EA	7	\$0	



5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #161 (Pre School)						
Classroom #252 (Faculty Lounge)						
Ceiling - Lay-in	2nd Floor	750	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	750	SF	7	\$0	
Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	1,050	SF	7	\$0	
Classroom #253 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	737	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	737	SF	7	\$0	
Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	947	SF	7	\$0	
Classroom #254 (Science)						
Ceiling - Lay-in	2nd Floor	1,066	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	2	EA	7	\$0	
Eye Wash Station	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	1,066	SF	7	\$0	
Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Storage/ Closet	2nd Floor	100	SF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	1,444	SF	7	\$0	
Work Sink	2nd Floor	2	EA	7	\$0	
Classroom #255 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	737	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	737	SF	7	\$0	
Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	924	SF	7	\$0	
Classroom #256 (Computer Lab)						
Ceiling - Lay-in	2nd Floor	900	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	900	SF	7	\$0	
ORIOI E PARK	Page 23	of 26				Assessment Date: 11/18/1

5424 N Oketo Ave Chicago, IL 60656

### **Building: Addition**

Group Item - Type	Location	Quantity	Unit	Pank	Cost	Comments
Group Item - Type Classroom #256 (Computer Lab)	Location	Quantity	Jiiit	Kalik	COST	Comments
Lighting - Lay-in	2nd Floor	13	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0 \$0	
Walls - Plaster/Drywall	2nd Floor	2,020	SF	7	\$0 \$0	
Wireless System	2nd Floor	2,020	EA	7	\$0 \$0	
·	2110 1 1001	•	_, .	•	ΨΟ	
Classroom #257 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	737	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	737	SF	7	\$0	
Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	924	SF	7	\$0	
Classroom #258 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	828	SF	6	\$2,486	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	828	SF	7	\$0	
Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	1,204	SF	7	\$0	
Classroom #259 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	737	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	737	SF	7	\$0	
Lighting - Lay-in	2nd Floor	8	EΑ	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	924	SF	7	\$0	
Classroom #261 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	737	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
Floor - Tile	2nd Floor	737	SF	7	\$0	
Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
Marker Board	2nd Floor	10	LF	7	\$0	
Walls - Plaster/Drywall	2nd Floor	924	SF	7	\$0	
Classroom #262 (Regular Classroom)						
Ceiling - Lay-in	2nd Floor	828	SF	7	\$0	
Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
ORIOI E PARK	Page 24	of 36				Assessment Date: 11/18/15

5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Classrooms** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #262 (Regular Classroom)						
	Floor - Tile	2nd Floor	828	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,204	SF	7	\$0	
Classro	oom #264 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	828	SF	7	\$0	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	828	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,204	SF	7	\$0	
Classro	oom #268 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	828	SF	7	\$0	
	Doors - Steel Doors incl hw	2nd Floor	1	EΑ	7	\$0	
	Floor - Tile	2nd Floor	828	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,204	SF	7	\$0	
						•	

Classrooms Subtotal: \$2,486

**Building: Addition** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments			
Admini	Iministrative Suites/Offices									
	Ceiling - Lay-in	151 - Kitchen office	70	SF	7	\$0				
	Doors - Side-lite	151 - Kitchen office	48	SF	7	\$0				
	Doors - Steel Doors incl hw	151 - Kitchen office	1	EA	7	\$0				
	Floor - Tile	151 - Kitchen office	70	SF	7	\$0				
	Lighting - Lay-in	151 - Kitchen office	2	EA	7	\$0				
	Power Distribution	151 - Kitchen office	2	EA	7	\$0				
	Walls - Plaster/Drywall	151 - Kitchen office	272	SF	7	\$0				
	Ceiling - Lay-in	151 - Main office	835	SF	7	\$0				
	Doors - Side-lite	151 - Main office	116	SF	7	\$0				
	Doors - Steel Doors incl hw	151 - Main office	2	EA	7	\$0				
	Floor - Tile	151 - Main office	835	SF	7	\$0				



	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	strative Suites/Offices						
	Lighting - Lay-in	151 - Main office	14	EA	7	\$0	
	Power Distribution	151 - Main office	5	EA	7	\$0	
	Storage/ Closet	151 - Main office	44	SF	7	\$0	
	Walls - Plaster/Drywall	151 - Main office	1,124	SF	7	\$0	
	Ceiling - Lay-in	151A - Principal's office	168	SF	7	\$0	
	Doors - Steel Doors incl hw	151A - Principal's office	1	EA	7	\$0	
	Floor - Carpet	151A - Principal's office	168	SF	7	\$0	
	Lighting - Lay-in	151A - Principal's office	2	EA	7	\$0	
	Power Distribution	151A - Principal's office	3	EA	7	\$0	
	Walls - Plaster/Drywall	151A - Principal's office	364	SF	7	\$0	
	Ceiling - Lay-in	260 - Admin office	268	SF	7	\$0	
	Doors - Steel Doors incl hw	260 - Admin office	1	EA	7	\$0	
	Floor - Tile	260 - Admin office	268	SF	7	\$0	
	Lighting - Lay-in	260 - Admin office	4	EA	7	\$0	
	Power Distribution	260 - Admin office	4	EA	7	\$0	
	Walls - Plaster/Drywall	260 - Admin office	946	SF	7	\$0	
	Ceiling - Lay-in	276 - Workroom	331	SF	7	\$0	
	Doors - Steel Doors incl hw	276 - Workroom	1	EA	7	\$0	
	Floor - Tile	276 - Workroom	331	SF	7	\$0	
	Lighting - Lay-in	276 - Workroom	5	EA	7	\$0	
	Power Distribution	276 - Workroom	4	EA	7	\$0	
	Walls - Plaster/Drywall	276 - Workroom	810	SF	7	\$0	
	Ceiling - Lay-in	Conference in Main office	223	SF	7	\$0	
	Doors - Steel Doors incl hw	Conference in Main office	1	EA	7	\$0	
	Floor - Carpet	Conference in Main office	1	SF	7	\$0	
	Lighting - Lay-in	Conference in Main office	4	EA	7	\$0	
	Power Distribution	Conference in Main office	4	EA	7	\$0	
	Walls - Plaster/Drywall	Conference in Main office	444	SF	7	\$0	
Kitcher	1						
	Ceiling - Lay-in	1st Floor	2,231	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	8	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	1st Floor	2,231	SF	7	\$0	
	Lighting - Lay-in	1st Floor	30	EA	7	\$0	
	Serving Line	1st Floor	25	LF	7	\$0	
	Storage/ Closet	1st Floor	302	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	2,119	SF	7	\$0	
	•						

5424 N Oketo Ave Chicago, IL 60656

### **Building: Addition**


Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Librar	у						
	Ceiling - Exposed	Library - 251	1,714	SF	7	\$0	
	Doors - Steel Doors incl hw	Library - 251	4	EA	7	\$0	
	Doors - Transom Window	Library - 251	30	SF	7	\$0	
	Floor - Carpet	Library - 251	1,714	SF	7	\$0	
	Lighting - Pendent/Surface	Library - 251	12	EA	7	\$0	
	Walls - Plaster/Drywall	Library - 251	2,277	SF	7	\$0	
Lunch	& Multipurpose Room						
	Ceiling - Exposed	Lunchroom - 150	4,136	SF	7	\$0	
	Doors - Side-lite	Lunchroom - 150	144	SF	7	\$0	
	Doors - Steel Doors incl hw	Lunchroom - 150	10	EA	7	\$0	
	Floor - Tile	Lunchroom - 150	4,136	SF	6	\$9,049	
	Lighting - Lay-in	Lunchroom - 150	24	EA	7	\$0	Recessed incandescent
	Lighting - Pendent/Surface	Lunchroom - 150	30	EA	7	\$0	
	Walls - Plaster/Drywall	Lunchroom - 150	1,300	SF	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	Lunchroom - 150	1,240	SF	7	\$0	
MDF_I	DF						
	Doors - Steel Doors incl hw	266	1	EA	7	\$0	
	Finishes	266	1,696	SF	7	\$0	
	Ventilation and Cooling	266	1	EA	6	\$1,855	
Mecha	anical/ Service Rooms						
	Janitor's Closet	1st Floor	52	SF	6	\$373	
	Mechanical/ Service Rooms	1st Floor	399	SF	6	\$2,859	
	Janitor's Closet	2nd Floor	52	SF	6	\$373	
	Mechanical/ Service Rooms	2nd Floor	97	SF	6	\$695	
	Storage Room	2nd Floor	160	SF	7	\$0	
	Storage Room	2nd Floor	220	SF	7	\$0	
Restro	oom						
	Accessories	1st Floor Boys	261	SF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor Boys	261	SF	7	\$0	
	Floor Drain	1st Floor Boys	1	EA	7	\$0	
	Floor - Tile Quarry	1st Floor Boys	261	SF	7	\$0	
	Hand Dryer	1st Floor Boys	2	EA	7	\$0	
	Lavatory	1st Floor Boys	3	EA	7	\$0	
	Lighting - Lay-in	1st Floor Boys	9	EA	7	\$0	
	Partitions	1st Floor Boys	4	EA	7	\$0	



Ulrinals	oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls - Flaster/Drywall         1st Floor Boys         365         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st Floor Boys         2         EA         7         \$0           Accessories         1st Floor Girls         261         SF         7         \$0           Ceiling - Plaster/Drywall         1st Floor Girls         261         SF         7         \$0           Floor Drain         1st Floor Girls         1         EA         7         \$0           Floor - Tile Quarry         1st Floor Girls         261         SF         7         \$0           Hand Dryer         1st Floor Girls         2         EA         7         \$0           Levatory         1st Floor Girls         3         EA         7         \$0           Lavatory         1st Floor Girls         36         EA         7         \$0           Partitions         1st Floor Girls         365         SF         7         \$0           Walls - Plaster/Drywall         1st Floor Girls         365         SF         7         \$0           Walls - Plaster/Drywall         1st Floor Girls         365         SF         7         \$0           Walls - Plaster/Drywall	estro	om						
Wals - Tile Ceramic/ Porcelain         1st Floor Boys         365         SF         7         \$0           Water Closet         1st Floor Girls         261         SF         7         \$0           Ceiling - Plaster/Dywall         1st Floor Girls         261         SF         7         \$0           Floor Drain         1st Floor Girls         261         SF         7         \$0           Floor - Tile Quarry         1st Floor Girls         261         SF         7         \$0           Hand Dryer         1st Floor Girls         261         SF         7         \$0           Lawatory         1st Floor Girls         3         EA         7         \$0           Lawatory         1st Floor Girls         9         EA         7         \$0           Layining - Layin         1st Floor Girls         36         SF         7         \$0           Walls - Tille Ceramic/ Porcelain         1st Floor Girls         365         SF         7         \$0           Walls - Tille Ceramic/ Porcelain         1st Floor Girls         365         SF         7         \$0           Water Closet         1st Floor Girls         365         SF         7         \$0           Water Closet <td></td> <td>Urinals</td> <td>1st Floor Boys</td> <td>3</td> <td></td> <td>7</td> <td></td> <td></td>		Urinals	1st Floor Boys	3		7		
Water Closet         1st Floor Girls         2 EA         7         \$0           Accessories         1st Floor Girls         261         SF         7         \$0           Ceiling - Plaster/Drywall         1st Floor Girls         1         EA         7         \$0           Floor - Tille Quarry         1st Floor Girls         281         SF         7         \$0           Hand Dryer         1st Floor Girls         2         EA         7         \$0           Lavatory         1st Floor Girls         3         EA         7         \$0           Lavatory         1st Floor Girls         4         EA         7         \$0           Partitions         1st Floor Girls         4         EA         7         \$0           Walls - Plaster/Drywall         1st Floor Girls         365         SF         7         \$0           Walls - Tile Caramic/ Parcelain         1st Floor Girls         365         SF         7         \$0           Walls - Tile Caramic/ Parcelain         1st Floor Girls         365         SF         7         \$0           Walls - Tile Caramic/ Parcelain         1st Floor Girls         365         SF         7         \$0           Walls - Tile Caramic/ Parcelain<		Walls - Plaster/Drywall	1st Floor Boys	365	SF	7	\$0	
Accessories		Walls - Tile Ceramic/ Porcelain	1st Floor Boys	365	SF	7	\$0	
Ceiling - Plaster/Drywall		Water Closet	1st Floor Boys	2	EΑ	7	\$0	
Floor Orain		Accessories	1st Floor Girls	261	SF	7	\$0	
Floor - Tile Quarry		Ceiling - Plaster/Drywall	1st Floor Girls	261	SF	7	\$0	
Hand Dryer		Floor Drain	1st Floor Girls	1	EA	7	\$0	
Lavatory		Floor - Tile Quarry	1st Floor Girls	261	SF	7	\$0	
Lighting - Lay-in		Hand Dryer	1st Floor Girls	2	EA	7	\$0	
Partitions         1st Floor Girls         4         EA         7         \$0           Walls - Plaster/Drywall         1st Floor Girls         365         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st Floor Girls         5         EA         7         \$0           Water Closet         1st Floor Girls         5         EA         7         \$0           Accessories         1st floor staff unisex         49         SF         7         \$0           Ceiling - Lay-in         1st floor staff unisex         49         SF         7         \$0           Floor Drain         1st floor staff unisex         1         EA         7         \$0           Floor Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         49         SF         7         \$0           Lavatory         1st floor staff unisex         49         SF         7         \$0           Layatory         1st floor staff unisex         1         EA         7         \$0           Layatory         1st floor staff unisex         1         EA         7         \$0           Walls - Tile Cerami		Lavatory	1st Floor Girls	3	EA	7	\$0	
Walls - Plaster/Drywall         1st Floor Girls         365         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st Floor Girls         365         SF         7         \$0           Water Closet         1st Floor Staff unisex         48         SF         7         \$0           Accessories         1st floor staff unisex         49         SF         7         \$0           Ceiling - Lay-in         1st floor staff unisex         1         EA         7         \$0           Doors - Steel Doors incl hw         1st floor staff unisex         1         EA         7         \$0           Floor Drain         1st floor staff unisex         1         EA         7         \$0           Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Layatory         1st floor staff unisex         1         EA         7         \$0           Lighting - Lay-in         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         15         SF         7		Lighting - Lay-in	1st Floor Girls	9	EA	7	\$0	
Walls - Tile Ceramic/ Porcelain         1st Floor Girls         365         SF         7         \$0           Water Closet         1st Floor Girls         5         EA         7         \$0           Accessories         1st floor staff unisex         49         SF         7         \$0           Celing - Lay-in         1st floor staff unisex         49         SF         7         \$0           Doors - Steel Doors incl hw         1st floor staff unisex         1         EA         7         \$0           Floor Trial Quarry         1st floor staff unisex         1         EA         7         \$0           Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Dywall         1st floor staff unisex         1         EA         7         \$0           Walls - Tile Ceramic/ Porcelain         1st floor staff unisex         1         EA         7         \$0           Walls - Tile Ceramic/ Porcelain         1st floor staff unisex         1         EA		Partitions	1st Floor Girls	4	EA	7	\$0	
Water Closet         1st Floor Girls         5         EA         7         \$0           Accessories         1st floor staff unisex         49         SF         7         \$0           Ceiling - Lay-in         1st floor staff unisex         49         SF         7         \$0           Doors - Steel Doors incl hw         1st floor staff unisex         1         EA         7         \$0           Floor Drain         1st floor staff unisex         1         EA         7         \$0           Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         119         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st floor staff unisex         119         SF         7         \$0           Water Closet         1st floor staff unisex         1 EA         7         \$0           Water Closet         2nd Floor Boys         261         SF         7         \$0		Walls - Plaster/Drywall	1st Floor Girls	365	SF	7	\$0	
Accessories         1st floor staff unisex         49         SF         7         \$0           Celling - Lay-in         1st floor staff unisex         49         SF         7         \$0           Doors - Steel Doors incl hw         1st floor staff unisex         1         EA         7         \$0           Floor Drain         1st floor staff unisex         49         SF         7         \$0           Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         19         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st floor staff unisex         125         SF         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Water Closet         1st floor Boys         261         SF         7         \$0           Ceiling - Plaster/Drywall         2nd Floor Boys         261         SF         7         \$0		Walls - Tile Ceramic/ Porcelain	1st Floor Girls	365	SF	7	\$0	
Ceiling - Lay-in         1st floor staff unisex         49         SF         7         \$0           Doors - Steel Doors incl hw         1st floor staff unisex         1         EA         7         \$0           Floor Drain         1st floor staff unisex         1         EA         7         \$0           Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Lighting - Lay-in         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         1         EA         7         \$0           Walls - Tille Ceramic/ Porcelain         1st floor staff unisex         125         SF         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Accessories         2nd Floor Boys         261         SF         7         \$0           Celling - Plaster/Drywall         2nd Floor Boys         261         SF         7 <td< td=""><td></td><td>Water Closet</td><td>1st Floor Girls</td><td>5</td><td>EA</td><td>7</td><td>\$0</td><td></td></td<>		Water Closet	1st Floor Girls	5	EA	7	\$0	
Doors - Steel Doors incl hw         1st floor staff unisex         1 EA 7         \$0           Floor Drain         1st floor staff unisex         1 EA 7         \$0           Floor - Tile Quarry         1st floor staff unisex         49 SF 7         \$0           Hand Dryer         1st floor staff unisex         1 EA 7         \$0           Lavatory         1st floor staff unisex         1 EA 7         \$0           Lighting - Lay-in         1st floor staff unisex         1 EA 7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         119 SF 7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         125 SF 7         \$0           Water Closet         1st floor staff unisex         125 SF 7         \$0           Accessories         2nd Floor Boys         261 SF 7         \$0           Ceiling - Plaster/Drywall         2nd Floor Boys         261 SF 7         \$0           Floor Tile Quarry         2nd Floor Boys         261 SF 7         \$0           Floor - Tile Quarry         2nd Floor Boys         261 SF 7         \$0           Hand Dryer         2nd Floor Boys         261 SF 7         \$0           Lavatory         2nd Floor Boys         2 EA 7         \$0 <td< td=""><td></td><td>Accessories</td><td>1st floor staff unisex</td><td>49</td><td>SF</td><td>7</td><td>\$0</td><td></td></td<>		Accessories	1st floor staff unisex	49	SF	7	\$0	
Floor Drain         1st floor staff unisex         1         EA         7         \$0           Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Lighting - Lay-in         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         119         SF         7         \$0           Water Closet         1st floor staff unisex         125         SF         7         \$0           Accessories         2nd Floor Staff unisex         1         EA         7         \$0           Accessories         2nd Floor Boys         261         SF         7         \$0           Accessories         2nd Floor Boys         261         SF         7         \$0           Ceiling - Plaster/Drywall         2nd Floor Boys         261         SF         7         \$0           Floor - Tile Quarry         2nd Floor Boys         2         EA         7         \$0           Lavator		Ceiling - Lay-in	1st floor staff unisex	49	SF	7	\$0	
Floor - Tile Quarry         1st floor staff unisex         49         SF         7         \$0           Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Lighting - Lay-in         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         119         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st floor staff unisex         125         SF         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Accessories         2nd Floor Boys         261         SF         7         \$0           Accessories         2nd Floor Boys         261         SF         7         \$0           Ceiling - Plaster/Drywall         2nd Floor Boys         261         SF         7         \$0           Floor - Tile Quarry         2nd Floor Boys         261         SF         7         \$0           Hand Dryer         2nd Floor Boys         3         EA         7         \$0		Doors - Steel Doors incl hw	1st floor staff unisex	1	EA	7	\$0	
Hand Dryer         1st floor staff unisex         1         EA         7         \$0           Lavatory         1st floor staff unisex         1         EA         7         \$0           Lighting - Lay-in         1st floor staff unisex         1         EA         7         \$0           Walls - Plaster/Drywall         1st floor staff unisex         119         SF         7         \$0           Water Closet         1st floor staff unisex         125         SF         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Ceiling - Plaster/Drywall         2nd Floor Boys         261         SF         7         \$0           Floor Drain         2nd Floor Boys         2         EA         7         \$0           Hand Dr		Floor Drain	1st floor staff unisex	1	EA	7	\$0	
Lavatory 1st floor staff unisex 1 EA 7 \$0 Lighting - Lay-in 1st floor staff unisex 1 EA 7 \$0 Walls - Plaster/Drywall 1st floor staff unisex 119 SF 7 \$0 Walls - Tile Ceramic/ Porcelain 1st floor staff unisex 125 SF 7 \$0 Water Closet 1st floor staff unisex 125 SF 7 \$0 Water Closet 1st floor staff unisex 1 EA 7 \$0 Accessories 2nd Floor Boys 261 SF 7 \$0 Ceiling - Plaster/Drywall 2nd Floor Boys 261 SF 7 \$0 Floor Drain 2nd Floor Boys 1 EA 7 \$0 Floor - Tile Quarry 2nd Floor Boys 261 SF 7 \$0 Hand Dryer 2nd Floor Boys 261 SF 7 \$0 Lavatory 2nd Floor Boys 3 EA 7 \$0 Lighting - Lay-in 2nd Floor Boys 9 EA 7 \$0 Urinals 2nd Floor Boys 3 EA 7 \$0 Walls - Plaster/Drywall 2nd Floor Boys 3 EA 7 \$0 Urinals 2nd Floor Boys 3 EA 7 \$0 Walls - Plaster/Drywall 2nd Floor Boys 3 EA 7 \$0 Walls - Plaster/Drywall 2nd Floor Boys 3 EA 7 \$0		Floor - Tile Quarry	1st floor staff unisex	49	SF	7	\$0	
Lighting - Lay-in       1st floor staff unisex       1 EA 7       \$0         Walls - Plaster/Drywall       1st floor staff unisex       119 SF 7       \$0         Walls - Tile Ceramic/ Porcelain       1st floor staff unisex       125 SF 7       \$0         Water Closet       1st floor staff unisex       1 EA 7       \$0         Accessories       2nd Floor Boys       261 SF 7       \$0         Ceiling - Plaster/Drywall       2nd Floor Boys       261 SF 7       \$0         Floor Drain       2nd Floor Boys       1 EA 7       \$0         Floor - Tile Quarry       2nd Floor Boys       261 SF 7       \$0         Hand Dryer       2nd Floor Boys       261 SF 7       \$0         Lavatory       2nd Floor Boys       2 EA 7       \$0         Lighting - Lay-in       2nd Floor Boys       3 EA 7       \$0         Partitions       2nd Floor Boys       4 EA 7       \$0         Urinals       2nd Floor Boys       4 EA 7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       3 EA 7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       3 EA 7       \$0		Hand Dryer	1st floor staff unisex	1	EA	7	\$0	
Walls - Plaster/Drywall         1st floor staff unisex         119         SF         7         \$0           Walls - Tile Ceramic/ Porcelain         1st floor staff unisex         125         SF         7         \$0           Water Closet         1st floor staff unisex         1         EA         7         \$0           Accessories         2nd Floor Boys         261         SF         7         \$0           Ceiling - Plaster/Drywall         2nd Floor Boys         261         SF         7         \$0           Floor Drain         2nd Floor Boys         1         EA         7         \$0           Floor - Tile Quarry         2nd Floor Boys         261         SF         7         \$0           Hand Dryer         2nd Floor Boys         2         EA         7         \$0           Lavatory         2nd Floor Boys         3         EA         7         \$0           Lighting - Lay-in         2nd Floor Boys         9         EA         7         \$0           Partitions         2nd Floor Boys         4         EA         7         \$0           Walls - Plaster/Drywall         2nd Floor Boys         3         EA         7         \$0		Lavatory	1st floor staff unisex	1	EA	7	\$0	
Walls - Tile Ceramic/ Porcelain       1st floor staff unisex       125       SF       7       \$0         Water Closet       1st floor staff unisex       1       EA       7       \$0         Accessories       2nd Floor Boys       261       SF       7       \$0         Ceiling - Plaster/Drywall       2nd Floor Boys       261       SF       7       \$0         Floor Drain       2nd Floor Boys       1       EA       7       \$0         Floor - Tile Quarry       2nd Floor Boys       261       SF       7       \$0         Hand Dryer       2nd Floor Boys       2       EA       7       \$0         Lavatory       2nd Floor Boys       3       EA       7       \$0         Lighting - Lay-in       2nd Floor Boys       9       EA       7       \$0         Partitions       2nd Floor Boys       4       EA       7       \$0         Urinals       2nd Floor Boys       3       EA       7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       365       SF       7       \$0		Lighting - Lay-in	1st floor staff unisex	1	EA	7	\$0	
Water Closet       1st floor staff unisex       1 EA 7       \$0         Accessories       2nd Floor Boys       261 SF 7       \$0         Ceiling - Plaster/Drywall       2nd Floor Boys       261 SF 7       \$0         Floor Drain       2nd Floor Boys       1 EA 7       \$0         Floor - Tile Quarry       2nd Floor Boys       261 SF 7       \$0         Hand Dryer       2nd Floor Boys       2 EA 7       \$0         Lavatory       2nd Floor Boys       3 EA 7       \$0         Lighting - Lay-in       2nd Floor Boys       9 EA 7       \$0         Partitions       2nd Floor Boys       4 EA 7       \$0         Urinals       2nd Floor Boys       3 EA 7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       3 EA 7       \$0		Walls - Plaster/Drywall	1st floor staff unisex	119	SF	7	\$0	
Accessories 2nd Floor Boys 261 SF 7 \$0 Ceiling - Plaster/Drywall 2nd Floor Boys 261 SF 7 \$0 Floor Drain 2nd Floor Boys 1 EA 7 \$0 Floor - Tile Quarry 2nd Floor Boys 261 SF 7 \$0 Hand Dryer 2nd Floor Boys 2 EA 7 \$0 Lavatory 2nd Floor Boys 3 EA 7 \$0 Lighting - Lay-in 2nd Floor Boys 9 EA 7 \$0 Partitions 2nd Floor Boys 9 EA 7 \$0 Urinals 2nd Floor Boys 3 EA 7 \$0 Walls - Plaster/Drywall 2nd Floor Boys 3 EA 7 \$0 Walls - Plaster/Drywall 2nd Floor Boys 3 EA 7 \$0		Walls - Tile Ceramic/ Porcelain	1st floor staff unisex	125	SF	7	\$0	
Ceiling - Plaster/Drywall2nd Floor Boys261SF7\$0Floor Drain2nd Floor Boys1EA7\$0Floor - Tile Quarry2nd Floor Boys261SF7\$0Hand Dryer2nd Floor Boys2EA7\$0Lavatory2nd Floor Boys3EA7\$0Lighting - Lay-in2nd Floor Boys9EA7\$0Partitions2nd Floor Boys4EA7\$0Urinals2nd Floor Boys3EA7\$0Walls - Plaster/Drywall2nd Floor Boys365SF7\$0		Water Closet	1st floor staff unisex	1	EA	7	\$0	
Floor Drain       2nd Floor Boys       1       EA       7       \$0         Floor - Tile Quarry       2nd Floor Boys       261       SF       7       \$0         Hand Dryer       2nd Floor Boys       2       EA       7       \$0         Lavatory       2nd Floor Boys       3       EA       7       \$0         Lighting - Lay-in       2nd Floor Boys       9       EA       7       \$0         Partitions       2nd Floor Boys       4       EA       7       \$0         Urinals       2nd Floor Boys       3       EA       7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       365       SF       7       \$0		Accessories	2nd Floor Boys	261	SF	7	\$0	
Floor - Tile Quarry       2nd Floor Boys       261       SF       7       \$0         Hand Dryer       2nd Floor Boys       2       EA       7       \$0         Lavatory       2nd Floor Boys       3       EA       7       \$0         Lighting - Lay-in       2nd Floor Boys       9       EA       7       \$0         Partitions       2nd Floor Boys       4       EA       7       \$0         Urinals       2nd Floor Boys       3       EA       7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       365       SF       7       \$0		Ceiling - Plaster/Drywall	2nd Floor Boys	261	SF	7	\$0	
Hand Dryer       2nd Floor Boys       2 EA 7       \$0         Lavatory       2nd Floor Boys       3 EA 7       \$0         Lighting - Lay-in       2nd Floor Boys       9 EA 7       \$0         Partitions       2nd Floor Boys       4 EA 7       \$0         Urinals       2nd Floor Boys       3 EA 7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       3 EA 7       \$0		Floor Drain	2nd Floor Boys	1	EA	7	\$0	
Lavatory       2nd Floor Boys       3 EA 7       \$0         Lighting - Lay-in       2nd Floor Boys       9 EA 7       \$0         Partitions       2nd Floor Boys       4 EA 7       \$0         Urinals       2nd Floor Boys       3 EA 7       \$0         Walls - Plaster/Drywall       2nd Floor Boys       3 EA 7       \$0		Floor - Tile Quarry	2nd Floor Boys	261	SF	7	\$0	
Lighting - Lay-in2nd Floor Boys9EA7\$0Partitions2nd Floor Boys4EA7\$0Urinals2nd Floor Boys3EA7\$0Walls - Plaster/Drywall2nd Floor Boys365SF7\$0		Hand Dryer	2nd Floor Boys	2	EA	7	\$0	
Partitions         2nd Floor Boys         4 EA 7         \$0           Urinals         2nd Floor Boys         3 EA 7         \$0           Walls - Plaster/Drywall         2nd Floor Boys         365 SF 7         \$0		Lavatory	2nd Floor Boys	3	EA	7	\$0	
Urinals         2nd Floor Boys         3 EA 7         \$0           Walls - Plaster/Drywall         2nd Floor Boys         365 SF 7         \$0		Lighting - Lay-in	2nd Floor Boys	9	EA	7	\$0	
Walls - Plaster/Drywall 2nd Floor Boys 365 SF 7 \$0		Partitions	2nd Floor Boys	4	EA	7	\$0	
		Urinals	2nd Floor Boys	3	EA	7	\$0	
Walls - Tile Ceramic/ Porcelain 2nd Floor Boys 365 SF 7 \$0		Walls - Plaster/Drywall	2nd Floor Boys	365	SF	7	\$0	
		Walls - Tile Ceramic/ Porcelain	2nd Floor Boys	365	SF	7	\$0	



oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stro	om						
	Water Closet	2nd Floor Boys	2	EA	7	\$0	
	Accessories	2nd Floor Girls	261	SF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor Girls	261	SF	7	\$0	
	Floor Drain	2nd Floor Girls	1	EΑ	7	\$0	
	Floor - Tile Quarry	2nd Floor Girls	261	SF	7	\$0	
	Hand Dryer	2nd Floor Girls	2	EA	7	\$0	
	Lavatory	2nd Floor Girls	3	EA	7	\$0	
	Lighting - Lay-in	2nd Floor Girls	9	EΑ	7	\$0	
	Partitions	2nd Floor Girls	4	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor Girls	365	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	2nd Floor Girls	365	SF	7	\$0	
	Water Closet	2nd Floor Girls	5	EA	7	\$0	
	Accessories	2nd floor staff unisex	49	SF	7	\$0	
	Ceiling - Lay-in	2nd floor staff unisex	49	SF	7	\$0	
	Doors - Steel Doors incl hw	2nd floor staff unisex	1	EΑ	7	\$0	
	Floor Drain	2nd floor staff unisex	1	EΑ	7	\$0	
	Floor - Tile Quarry	2nd floor staff unisex	49	SF	7	\$0	
	Hand Dryer	2nd floor staff unisex	1	EΑ	7	\$0	
	Lavatory	2nd floor staff unisex	1	EΑ	7	\$0	
	Lighting - Lay-in	2nd floor staff unisex	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd floor staff unisex	119	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	2nd floor staff unisex	125	SF	7	\$0	
	Water Closet	2nd floor staff unisex	1	EA	7	\$0	
	Accessories	Kindergarten 153	86	SF	7	\$0	
	Ceiling - Lay-in	Kindergarten 153	86	SF	7	\$0	
	Doors - Steel Doors incl hw	Kindergarten 153	1	EA	7	\$0	
	Floor Drain	Kindergarten 153	1	EA	7	\$0	
	Floor - Tile Quarry	Kindergarten 153	86	SF	7	\$0	
	Hand Dryer	Kindergarten 153	1	EA	7	\$0	
	Lavatory	Kindergarten 153	1	EA	7	\$0	
	Lighting - Lay-in	Kindergarten 153	1	EA	7	\$0	
	Walls - Plaster/Drywall	Kindergarten 153	177	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	Kindergarten 153	171	SF	7	\$0	
	Water Closet	Kindergarten 153	1	EA	7	\$0	
	Accessories	Kindergarten 155	86	SF	7	\$0	
	Ceiling - Lay-in	Kindergarten 155	86	SF	7	\$0	
	Doors - Steel Doors incl hw	Kindergarten 155	1	EΑ	7	\$0	





F H L L V	Floor Drain Floor - Tile Quarry Hand Dryer Lavatory Lighting - Lay-in Valls - Plaster/Drywall Valls - Tile Ceramic/ Porcelain Vater Closet Laccessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155 Kindergarten 157	1 86 1 1 1 177 171	EA SF EA EA SF SF	7 7 7 7 7	\$0 \$0 \$0 \$0 \$0 \$0	
F H L L V	Floor - Tile Quarry Hand Dryer Lavatory Lighting - Lay-in Valls - Plaster/Drywall Valls - Tile Ceramic/ Porcelain Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155	86 1 1 1 177 171	SF EA EA SF	7 7 7 7	\$0 \$0 \$0 \$0	
L L \ \	Hand Dryer Lavatory Lighting - Lay-in Valls - Plaster/Drywall Valls - Tile Ceramic/ Porcelain Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155	1 1 1 177 171	EA EA EA SF	7 7 7	\$0 \$0 \$0	
L \ \ \ \ \	avatory ighting - Lay-in Valls - Plaster/Drywall Valls - Tile Ceramic/ Porcelain Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155 Kindergarten 155 Kindergarten 155 Kindergarten 155 Kindergarten 155 Kindergarten 157	1 1 177 171	EA EA SF	7 7	\$0 \$0	
L \ \ \ \	ighting - Lay-in Valls - Plaster/Drywall Valls - Tile Ceramic/ Porcelain Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155 Kindergarten 155 Kindergarten 155 Kindergarten 155 Kindergarten 157	1 177 171	EA SF	7	\$0	
\ \ <i>\</i>	Valls - Plaster/Drywall Valls - Tile Ceramic/ Porcelain Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155 Kindergarten 155 Kindergarten 155 Kindergarten 157	177 171	SF			
\ \ (	Valls - Tile Ceramic/ Porcelain Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155 Kindergarten 155 Kindergarten 157	171		7	¢ο	
\ ,	Vater Closet Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 155 Kindergarten 157		SF		ΦU	
(	Accessories Ceiling - Lay-in Doors - Steel Doors incl hw	Kindergarten 157	1	٠.	7	\$0	
(	Ceiling - Lay-in Doors - Steel Doors incl hw	_		EA	7	\$0	
	Doors - Steel Doors incl hw	Kindergarten 157	86	SF	7	\$0	
		randorganton 101	86	SF	7	\$0	
[		Kindergarten 157	1	EA	7	\$0	
F	loor Drain	Kindergarten 157	1	EA	7	\$0	
F	Floor - Tile Quarry	Kindergarten 157	86	SF	7	\$0	
H	land Dryer	Kindergarten 157	1	EA	7	\$0	
L	avatory	Kindergarten 157	1	EA	7	\$0	
L	ighting - Lay-in	Kindergarten 157	1	EA	7	\$0	
١	Valls - Plaster/Drywall	Kindergarten 157	177	SF	7	\$0	
\	Valls - Tile Ceramic/ Porcelain	Kindergarten 157	171	SF	7	\$0	
\	Vater Closet	Kindergarten 157	1	EA	7	\$0	
A	Accessories	Kitchen staff	46	SF	7	\$0	
(	Ceiling - Lay-in	Kitchen staff	46	SF	7	\$0	
[	Doors - Steel Doors incl hw	Kitchen staff	1	EA	7	\$0	
F	Floor Drain	Kitchen staff	1	EA	7	\$0	
F	Floor - Tile Quarry	Kitchen staff	46	SF	7	\$0	
ŀ	land Dryer	Kitchen staff	1	EA	7	\$0	
L	avatory	Kitchen staff	1	EA	7	\$0	
L	ighting - Lay-in	Kitchen staff	1	EA	7	\$0	
5	Student Lockers - One Tier	Kitchen staff	11	EA	7	\$0	Staff lockers - outside of restroom
\	Valls - Plaster/Drywall	Kitchen staff	246	SF	7	\$0	
\	Vater Closet	Kitchen staff	1	EA	7	\$0	
A	Accessories	PreK 159	86	SF	7	\$0	
(	Ceiling - Lay-in	PreK 159	86	SF	7	\$0	
[	Doors - Steel Doors incl hw	PreK 159	1	EΑ	7	\$0	
F	Floor Drain	PreK 159	1	EA	7	\$0	
F	Floor - Tile Quarry	PreK 159	86	SF	7	\$0	
ŀ	land Dryer	PreK 159	1	EA	7	\$0	
L	avatory	PreK 159	1	EA	7	\$0	

5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Rooms (Other Than Classrooms)** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	m						
	Lighting - Lay-in	PreK 159	1	EA	7	\$0	
	Walls - Plaster/Drywall	PreK 159	177	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	PreK 159	171	SF	7	\$0	
	Water Closet	PreK 159	1	EΑ	7	\$0	
	Accessories	PreK 161	86	SF	7	\$0	
	Ceiling - Lay-in	PreK 161	86	SF	7	\$0	
	Doors - Steel Doors incl hw	PreK 161	1	EA	7	\$0	
	Floor Drain	PreK 161	1	EΑ	7	\$0	
	Floor - Tile Quarry	PreK 161	86	SF	7	\$0	
	Hand Dryer	PreK 161	1	EΑ	7	\$0	
	Lavatory	PreK 161	1	EΑ	7	\$0	
	Lighting - Lay-in	PreK 161	1	EA	7	\$0	
	Walls - Plaster/Drywall	PreK 161	177	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	PreK 161	171	SF	7	\$0	
	Water Closet	PreK 161	1	EA	7	\$0	

Rooms (Other Than Classrooms) Subtotal:

\$15,203

**Building: Addition** 

**Category: Building Interior** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	r						
	Ceiling - Lay-in	1st Floor	2,480	SF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	850	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	15	EA	7	\$0	
	Doors - Transom Window	1st Floor	36	EA	7	\$0	
	Drinking Fountains - Single Water Cooler	1st Floor	3	EA	7	\$0	
	Floor - Tile Quarry	1st Floor	279	SF	7	\$0	
	Floor - Tile/Sheet	1st Floor	2,880	SF	7	\$0	
	Lighting - Chandelier, Incandescent	1st Floor	15	EA	7	\$0	
	Lighting - Lay-in	1st Floor	40	EA	7	\$0	
	Stairs - Concrete Stairs	1st Floor	6	LF	7	\$0	
	Walls - Concrete Block	1st Floor	252	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	5,443	SF	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	1,697	SF	7	\$0	
	Ceiling - Lay-in	2nd Floor	4	SF	5	\$36	
	Ceiling - Lay-in	2nd Floor	2,122	SF	7	\$0	

5424 N Oketo Ave Chicago, IL 60656

**Building: Addition** 

**Category: Building Interior** 

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	or						
	Ceiling - Plaster/Drywall	2nd Floor	74	SF	7	\$0	
	Doors - Steel Doors incl hw	2nd Floor	7	EA	7	\$0	
	Drinking Fountains - Single Water Cooler	2nd Floor	3	EA	7	\$0	
	Floor - Tile/Sheet	2nd Floor	3,200	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	28	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	18	EA	7	\$0	
	Student Lockers - Two Tiers	2nd Floor	302	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	252	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	5,955	SF	7	\$0	
Stairs							
	Ceiling - Lay-in	East	403	SF	7	\$0	
	Floor - Tile	East	147	SF	7	\$0	
	Handrails	East	168	LF	7	\$0	
	Lighting - Wall Mounted	East	3	EA	7	\$0	
	Stairs - Asphalt	East	40	LF	7	\$0	
	Walls - Plaster/Drywall	East	1,326	SF	7	\$0	
	Ceiling - Lay-in	West	488	SF	7	\$0	
	Floor - Tile	West	550	SF	7	\$0	
	Handrails	West	194	LF	7	\$0	
	Lighting - Lay-in	West	3	EΑ	7	\$0	
	Lighting - Wall Mounted	West	7	EΑ	7	\$0	
	Stairs - Asphalt	West	40	LF	7	\$0	
	Walls - Plaster/Drywall	West	2,322	SF	7	\$0	
Vertical	l Conveyance						
	Elevator - Hydraulic Elevator	1st Floor	1	EA	6	\$19,238	
Buildi	ing Interior Subtotal:					\$19,274	
Total	Building Cost					\$36,963	

#### SITE

**Category: Site** 

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Civil/Drainage					
Civil/ Drainage - Catch Basin	Entire Site	18	EA	6	\$19,689

5424 N Oketo Ave Chicago, IL 60656

#### SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Dr	••						
	Civil/ Drainage - Site Drain	Entire Site	1	EA	6	\$310	
	Civil/ Drainage - Site Manhole	Entire Site	10	EA	6	\$14,927	
Fancin	~						
Fencing	Fencing - New Standard Ornamental	Entire Site	1,583	LF	6	\$50,503	
	rending - New Standard Offiamental	Entire Site	1,303	LF	O	φ50,505	
Landsc	аре						
	Benches	Entire Site	9	EA	6	\$3,870	
	Landscape - Grass	Entire Site	25,700	SF	5	\$38,956	Reseed
	Landscape - Hardscape- Concrete	Entire Site	9,770	SF	7	\$0	
	Landscape - Hardscape- Concrete	Entire Site	100	SF	6	\$709	Ponding issues at base of stairs near door #7
	Landscape - Hardscape- Concrete	Entire Site / Site - East	1,016	SF	6	\$7,206	
	Landscape - Hardscape- Pavers	Entire Site / Site - East	368	SF	6	\$2,084	
	Parkway trees	Entire Site	6	EA	6	\$3,960	
	Planting Beds/ Area	Entire Site	6,577	SF	6	\$10,816	
	Play Area - Synthetic Turf Play Field	Entire Site / North West	8,911	SF	7	\$0	
	Retaining Wall - Concrete	Entire Site	140	SF	6	\$3,281	at basement door #6.2
	Trash Receptacles	Entire Site	8	EA	6	\$2,498	
Parking	ı Lot						
	Concrete Curbs	Parking Lot- East	784	LF	6	\$10,068	
	Interior Plantings	Parking Lot- East	72	LF	6	\$3,063	
	Surface - Asphalt	Parking Lot- East	18,514	SF	6	\$44,743	
	Trash Compactor	Parking Lot- East	1	EA	7	\$0	
	Trash Enclosure - Masonry	Parking Lot- East	337	SF	7	\$0	
Playgro	ound						
	Equipment - Pre K 3-5	Northwest / North West	1	EA	6	\$3,546	
	Equipment - School Age 5-12	Northwest / North West	1	EA	6	\$3,546	
	Surface - Poured Surface	Northwest / North West	1,194	SF	6	\$8,742	
Sidewa	lks						
	Sidewalks - Internal Walks	Entire Site	1,263	LF	6	\$15,171	
	Sidewalks - Perimeter Sidewalks	Entire Site	5,779	SF	6	\$11,487	
Signag	e						
33	Flag Pole - Building Mounted Flag Pole	East Facade, Site East and Northeast / East Façade	1	EA	7	\$0	
	Flag Pole - Flag Pole	East Facade, Site East and Northeast / Site - East	1	EA	6	\$1,657	



5424 N Oketo Ave Chicago, IL 60656

#### SITE

Category: Site

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Signage						
Marquee - Free Standing Back Lighted	East Facade, Site East and Northeast / North East	1	EA	7	\$0	
Site Subtotal:					\$260,833	
Total Site Cost					\$260,833	

Campus Total <sup>2 3</sup>	\$2,450,869
-----------------------------	-------------

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

#### **Definitions**

- Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated.
- Unit means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.
- Campus Total also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

<sup>&</sup>lt;sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>&</sup>lt;sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.



5424 N Oketo Ave Chicago, IL 60656

#### **Classroom Summary**

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main				-			1	-						
Art Room	Art Room	2nd Floor	201	201-203	1,227	1	6	20	216	54	50	N	N	N
Kindergarten	Regular Classroom	1st Floor	103	103	700	1	6	6	108	54	50	N	Υ	N
Kindergarten	Kindergarten	1st Floor	104	104	825	1	0	6	126	63	50	N	Υ	Υ
Music Room	Regular Classroom	1st Floor	101	101	700	1	6	6	108	54	50	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	102	102	690	1	6	10	108	54	50	N	N	N
Regular Classroom	Regular Classroom	1st Floor	105	105	700	1	6	6	108	54	50	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	106	106	720	1	6	6	108	54	50	N	Υ	Υ
Regular Classroom	Regular Classroom	1st Floor	108	108	825	1	6	12	126	63	50	N	Υ	Υ
Regular Classroom	Regular Classroom	1st Floor	109	109	700	1	6	6	108	54	50	N	Υ	Υ
Regular Classroom	Regular Classroom	1st Floor	110	110	700	1	6	6	108	54	50	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	200	200	700	1	6	10	108	54	50	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	202	202	700	1	13	44	108	54	50	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	205	205	700	1	6	6	108	54	50	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	720	1	6	6	108	54	50	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	400	0	4	6	54	27	50	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	700	1	6	6	108	54	50	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	209	209	720	1	6	6	108	54	50	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	210	210	700	1	6	6	108	54	50	N	Υ	N
Science Classroom	Science Classroom	2nd Floor	204	204	700	1	6	32	108	54	50	N	Υ	Υ
Special Education	Office	1st Floor	100	100	340	1	2	10	54	27	50	N	Υ	N
Addition														
Computer Lab	Computer Lab	2nd Floor	256	256	900	1	16	20	136	12	40	N	N	N
Faculty Lounge	Regular Classroom	2nd Floor	252	252	750	1	6	18	90	12	40	N	N	N
Kindergarten	Kindergarten	1st Floor	153	153	1,010	1	6	18	136	12	40	N	N	N
Kindergarten	Kindergarten	1st Floor	155	155	1,010	1	6	18	136	12	40	N	N	N
Kindergarten	Kindergarten	1st Floor	157	157	1,010	1	6	18	136	12	40	N	N	N
Pre School	Pre School	1st Floor	159	159	1,010	1	6	18	136	12	40	N	N	N
Pre School	Pre School	1st Floor	161	161	1,010	1	6	18	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	253	253	737	1	6	20	113	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	255	255	737	1	6	20	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	257	257	737	1	6	20	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	258	258	828	1	6	18	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	259	259	737	1	6	20	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	261	261	737	1	6	20	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	262	262	828	1	6	18	136	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	264	264	828	1	6	18	136	12	40	N	N	N



5424 N Oketo Ave Chicago, IL 60656

### **Classroom Summary**

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Addition														
Regular Classroom	Regular Classroom	2nd Floor	268	268	828	1	6	20	136	12	40	N	N	N
Science	Science	2nd Floor	254	254	1,066	1	6	16	136	12	40	N	N	N