

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1915	3	59,563	\$2,933,520
Addition	1999	2	71,850	\$2,209,603
Field House	0	1	1,825	\$312,795
SITE				\$565,651
<b>Campus Total</b>			<b>133,238</b>	<b>\$6,021,569</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio	#1 N	1	EA	6	\$497	
	Exterior Doors - Exterior Steel Door	#10.1_Exit E	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#10.2 E	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#8 W	4	EA	6	\$1,922	
	Exterior Doors - Exterior Steel Door	#9.1_Exit W	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#9.2_Exit W	1	EA	6	\$481	
	Exterior Doors - Side lite	#9.1_Exit W	6	EA	6	\$1,880	
	Exterior Doors - Store Front	#1 N	8	EA	6	\$4,369	
	Exterior Doors - Store Front	#10 S	4	EA	6	\$2,184	
	Exterior Doors - Store Front	#11 N	4	EA	6	\$2,184	
	Exterior Doors - Store Front	#7 W	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#9 W	4	EA	6	\$2,184	
	Exterior Doors - Transom Lite	#1 N	4	EA	6	\$1,253	
	Exterior Doors - Transom Lite	#10 S	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#11 N	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#8 W	4	EA	6	\$1,253	
	Exterior Doors - Transom Lite	#9 W	4	EA	6	\$1,253	
	Exterior Stairs - Concrete	#10 S	80	LF	6	\$6,541	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Stairs - Concrete	#11 N	72	LF	6	\$5,887	
	Exterior Stairs - Concrete	#8 W	12	LF	6	\$981	
	Exterior Stairs - Concrete	#9 W	26	LF	6	\$2,126	
	Exterior Stairs - Concrete	#9.1_Exit W	9	LF	6	\$736	
	Exterior Stairs - Concrete	#9.2_Exit W	12	LF	6	\$981	
	Stair Handrail - Steel_Stair Handrail	#11 N	50	LF	6	\$433	
<b>Foundation</b>							
	Foundation - Masonry	Entire Building	29,016	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	59,563	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	11	EA	6	\$5,902	
	Exterior Lighting - Wall Mounted	Entire Building	11	EA	6	\$3,176	
<b>Roof System</b>							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof #1	80	LF	6	\$76,375	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof #1	5	LF	5	\$14,258	Needs tuckpointing
	Chimney - Metal Flue	Roof #2	7	LF	4	\$11,617	Rusted out
	Coping - Stone	Roof #2	188	LF	6	\$6,038	
	Coping - Stone	Roof #3	120	LF	6	\$3,854	
	Coping - Terra Cotta	Roof #1	599	LF	6	\$19,239	
	Coping - Terra Cotta	Roof #2	165	LF	6	\$5,299	
	Downspouts - Exterior Downspouts	Roof #2	12	LF	6	\$399	w/ 293 LF Metal Gutter
	Downspouts - Interior Downspouts	Roof #1	560	LF	6	\$18,611	
	Downspouts - Interior Downspouts	Roof #2	80	LF	6	\$2,659	
	Downspouts - Interior Downspouts	Roof #3	40	LF	6	\$1,329	
	Parapet - 16" - 30" Height	Roof #1	299	LF	6	\$11,946	
	Parapet - 16" - 30" Height	Roof #2	80	LF	6	\$3,196	
	Parapet - Parapet < 16" Height	Roof #2	273	LF	6	\$5,817	
	Parapet - Parapet < 16" Height	Roof #3	192	LF	6	\$4,091	
	Parapet - Parapet > 30"	Roof #1	300	LF	6	\$19,176	
	Roof Structure - Steel with Clay Tile Arch	Roof #1	16,519	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #2	10,534	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #3	1,900	SF	7	\$0	
	Roof - Modified Bitumen	Roof #1	16,519	SF	6	\$155,434	
	Roof - Modified Bitumen	Roof #2	10,534	SF	6	\$99,119	
	Roof - Modified Bitumen	Roof #3	1,900	SF	5	\$39,967	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Walls</b>							
	Cheek-Wall - Concrete	Entire Building	122	SF	6	\$1,251	
	Cornice - Metal Projecting	Entire Building	607	LF	6	\$21,049	
	Exterior Walls - Brick	Entire Building	33,738	SF	6	\$226,753	
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building / Lower Roof	768	SF	6	\$4,360	
	Exterior Walls - Stone-Cast	Entire Building	7,125	SF	6	\$47,887	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building	3,921	SF	6	\$50,071	
	Lintels - Steel	Entire Building	936	LF	6	\$27,171	scrape/ Paint
	Skylite - Glass Single-Pane	Entire Building	26	SF	6	\$621	only single pane
	Windows - Sash Aluminum Double-pane	Entire Building	7,853	SF	6	\$58,620	

**Building Exterior Subtotal:**

**\$987,325**

**Building: Main**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	6,620	SF	6	\$3,503	
	Emergency A/C Power - Corridors and Stairs	Entire Building	10,786	SF	6	\$3,239	building has ATS
	Emergency Battery Packs - Auditorium and Aisle Lighting	Entire Building / 1st Floor	3	EA	6	\$608	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	24	EA	6	\$4,860	
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	6	EA	6	\$1,215	
	Exit Signs - Auditorium	Entire Building / 1st Floor	4	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	24	EA	7	\$0	with battery packs
	Exit Signs - Gym	Entire Building / 1st Floor	3	EA	7	\$0	
	Security System - CCTV	Entire Building	59,563	SF	6	\$17,887	
	Security System - Intrusion Detection	Entire Building	59,563	SF	6	\$15,332	
<b>Main Service</b>							
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	1	EA	6	\$8,232	
	PA System	Entire Building	59,563	SF	6	\$19,590	connects to addition
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building	3	EA	4	\$14,548	rusted, loose cover, more than 50 years old, live
	Lighting and Power Panels - 100 A	Entire Building	8	EA	6	\$2,393	
	Lighting and Power Panels - Above 100 A	Entire Building	6	EA	7	\$0	

**Building: Main**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Power Distribution</b>							
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Mechanical Room	2	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	1	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	step-up type

**Electrical System Subtotal:**

**\$93,078**

**Building: Main**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Mechanical Room	1	EA	6	\$6,406	Serves Main and Additon
	Fire Alarm Strobe Lights	Mechanical Room / Entire Building	59,563	SF	6	\$21,294	
	Fire Alarm_System	Mechanical Room / Entire Building	59,563	SF	7	\$0	

**Safty System Subtotal:**

**\$27,700**

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Condensing Unit- Roof Mounted - 5-10 tons	Lower Roof	1	EA	5	\$9,590	serves elevator room. located on lower roof of main building
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up- Single Zone- Steam Coils - 4000 - 8000 cfm	Mechanical Room	1	EA	6	\$3,321	
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 25001 - 35000	Mechanical Room	2	EA	6	\$13,022	
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Roof	2	EA	7	\$0	
	Auxiliaries - 25001 - 35000 cfm	Mechanical Room	2	EA	6	\$13,022	
	Auxiliaries - 4000 - 8000 cfm	Mechanical Room	1	EA	6	\$3,321	
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	Attic	2	EA	6	\$3,714	serve gym/auditorium and office area
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Roof	100	LF	7	\$0	
	Return Duct Work - Masonry and Ducts- Missing or Existing Shaft	Mechanical Room / Entire Building	2	LF	7	\$0	
	Zone Dampers	Mechanical Room	12	EA	6	\$9,996	serves south, Some dampers do not work, and adjusted on manually to control space temps
	Zone Dampers	Mechanical Room	17	EA	6	\$14,162	serves north,

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Zone Dampers	Mechanical Room	4	EA	5	\$7,654	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Non Condensing Steam Boiler - Less than 50 HP	Boiler Room	1	EA	6	\$2,046	One Pipe System serving 3 radiators in Kindergarten Room Flue is in poor condition - Run inside of plumbing pipe; under the floor for location
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 101 - 150 HP	Boiler Room	2	EA	6	\$5,091	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	
	Chemical Feed System	Boiler Room / Mechanical Room	1	EA	6	\$1,078	
	Combustion Dampers	Boiler Room	2	EA	6	\$818	
	Combustion Dampers	Boiler Room	1	EA	6	\$409	
	Condensate Pump	Boiler Room / Mechanical Room	1	EA	6	\$2,021	
	Feed Water Pumps and Tank	Boiler Room / Mechanical Room	1	EA	6	\$2,545	
	Non Condensing- Cast Iron- Force Draft- Steam Boiler - Less than 50 HP	Boiler Room	1	EA	6	\$2,046	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 101 - 150 HP	Boiler Room	2	EA	6	\$5,091	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	50	LF	6	\$94	serves only kindergarden room
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Site	500	LF	6	\$944	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	500	LF	6	\$944	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	50	LF	6	\$94	serves only kindergarden room
	Steam Traps	Boiler Room / Entire Building	20	EA	5	\$26,298	
<b>Gas Booster</b>							
	Gas Booster	Mechanical Room	1	EA	6	\$499	
<b>Heating Devices</b>							
	Radiators - Steam	Kindergarten / 1st Floor	3	EA	5	\$5,026	served by a 50000 btu/hr boiler, under the kindergarden rtoom
	Unit Heater - Electric	Entire Building	11	EA	6	\$3,056	
	Unit Heater - Gas	Entire Building / Boiler Room	1	EA	6	\$278	ceiling mounted
	Unit Heater - Steam	Entire Building / Mechanical Room	1	EA	6	\$278	cylindrical, ceiling mounted
	Wall Heater - Electric	Entire Building	3	EA	7	\$0	
<b>Temperature Control</b>							
	Electric Thermostat	Entire Building / 1st Floor	1	EA	6	\$0	in field house, for furnace
	Hybrid Pneumatic/DDC System	Entire Building	59,563	SF	5	\$205,272	Honeywell, 1999, has some control problems
	Thermostats - Pneumatic	Entire Building	13	EA	4	\$9,584	
	Thermostats - Pneumatic	Entire Building	18	EA	6	\$0	

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Roof / Lower Roof	1	EA	6	\$592	serves gym and auditorium areas
	Roof Mounted Duct Work	Roof / Lower Roof	20	LF	6	\$7,580	

**Mechanical System Subtotal: \$367,516**

**Building: Main**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 150000 - 300000 BTU/HR	Entire Building / Boiler Room	1	EA	6	\$310	Main building
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	59,563	SF	6	\$11,925	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	59,563	SF	6	\$14,480	
	Domestic Piping-Cold Water Risers	Entire Building	59,563	SF	6	\$11,073	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	59,563	SF	6	\$9,369	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	59,563	SF	6	\$11,073	
	Domestic Piping-Hot Water Return Lines	Entire Building	59,563	SF	6	\$8,518	
	Domestic Piping-Hot Water Return Risers	Entire Building	59,563	SF	6	\$8,518	
	Sanitary Piping	Entire Building	59,563	SF	6	\$54,512	
	Storm Piping	Entire Building	59,563	SF	6	\$51,957	
	Vent Piping	Entire Building	59,563	SF	6	\$40,032	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	

**Plumbing System Subtotal: \$223,742**

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #101 (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	24	LF	6	\$606	
	Ceiling - Lay-in	1st Floor	888	SF	6	\$2,667	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #101 (Regular Classroom)</b>							
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	888	SF	6	\$1,943	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,070	SF	6	\$2,953	
<b>Classroom #102 (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	12	LF	6	\$303	
	Ceiling - Lay-in	1st Floor	938	SF	6	\$2,817	
	Doors - Side-lite	1st Floor	14	SF	6	\$234	
	Doors - Transom Window	1st Floor	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,232	SF	6	\$3,400	
<b>Classroom #103 (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	24	LF	6	\$606	
	Ceiling - Lay-in	1st Floor	938	SF	6	\$2,817	
	Chalk Board	1st Floor	10	LF	4	\$918	
	Doors - Transom Window	1st Floor	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	938	SF	6	\$2,052	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,232	SF	6	\$3,400	
	Work Sink	1st Floor	1	EA	6	\$379	
<b>Classroom #104 (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	140	SF	5	\$971	
	Ceiling - Lay-in	1st Floor	794	SF	6	\$2,384	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #104 (Regular Classroom)</b>							
	Floor - Wood	1st Floor	934	SF	6	\$6,585	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,249	SF	6	\$3,447	
<b>Classroom #105 (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Casework	1st Floor	12	LF	6	\$303	
	Ceiling - Lay-in	1st Floor	910	SF	6	\$2,733	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	910	SF	6	\$1,991	
	Lighting - Lay-in	1st Floor	18	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	1	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	1,249	SF	6	\$3,447	
<b>Classroom #109 (Special Program)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Ceiling - Lay-in	1st Floor	329	SF	6	\$988	
	Ceiling - Lay-in	1st Floor	4	SF	5	\$32	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	333	SF	6	\$710	
	Lighting - Pendent/Surface	1st Floor	6	EA	7	\$0	
	Walls - Plaster/Drywall	1st Floor	46	SF	5	\$235	Peeling paint/crack
	Walls - Plaster/Drywall	1st Floor	890	SF	6	\$2,456	
<b>Classroom #110 (Kindergarten)</b>							
	AC Units	1st Floor	1	EA	6	\$496	
	Ceiling - Lay-in	1st Floor	1,300	SF	6	\$3,904	
	Chalk Board	1st Floor	4	LF	4	\$367	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	434	SF	6	\$950	
	Floor - Wood	1st Floor	866	SF	6	\$6,105	
	Lighting - Lay-in	1st Floor	30	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	1	EA	7	\$0	
	Storage/ Closet	1st Floor	20	SF	6	\$145	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #110 (Kindergarten)</b>							
	Walls - Masonry	1st Floor	898	SF	6	\$2,825	
	Walls - Plaster/Drywall	1st Floor	1,426	SF	6	\$3,936	
	Walls - Plaster/Drywall	1st Floor	18	SF	5	\$92	Closet
<b>Classroom #200 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	2nd Floor	415	SF	6	\$1,246	
	Chalk Board	2nd Floor	24	LF	4	\$2,203	
	Doors - Transom Window	2nd Floor	60	SF	6	\$1,016	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	415	SF	6	\$884	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	120	SF	5	\$530	Peeling paint
	Walls - Plaster/Drywall	2nd Floor	730	SF	6	\$2,015	
<b>Classroom #201 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	888	SF	6	\$2,667	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	888	SF	6	\$6,260	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,034	SF	6	\$2,854	
	Walls - Plaster/Drywall	2nd Floor	20	SF	5	\$102	Peeling paint
	Walls - Plaster/Drywall	2nd Floor	5	SF	4	\$74	Drywall damage
<b>Classroom #202 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	903	SF	6	\$2,712	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	903	SF	6	\$6,366	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #202 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	2nd Floor	10	SF	5	\$51	Peeling paint
	Walls - Plaster/Drywall	2nd Floor	1,117	SF	6	\$3,083	
<b>Classroom #203 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	909	SF	6	\$2,730	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	Remove/replace marker board
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	909	SF	6	\$6,408	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,142	SF	6	\$3,152	
	Walls - Plaster/Drywall	2nd Floor	8	SF	5	\$41	cracks
<b>Classroom #204 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	908	SF	6	\$2,727	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	908	SF	6	\$6,401	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,127	SF	6	\$3,110	
	Walls - Plaster/Drywall	2nd Floor	2	SF	6	\$8	Peeling paint
<b>Classroom #205 (Dance Room)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	866	SF	6	\$2,601	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	866	SF	6	\$6,105	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Wall Mirrors	2nd Floor	2	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,687	SF	6	\$4,656	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #205 (Dance Room)</b>							
<b>Classroom #206B (Kindergarten)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	554	SF	6	\$1,664	
	Doors - Side-lite	2nd Floor	14	SF	6	\$234	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	554	SF	6	\$3,906	
	Lighting - Lay-in	2nd Floor	10	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,003	SF	6	\$2,768	
<b>Classroom #207 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	927	SF	6	\$2,784	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	927	SF	6	\$6,535	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	40	SF	5	\$204	Peeling paint
	Walls - Plaster/Drywall	2nd Floor	1,369	SF	6	\$3,778	
<b>Classroom #208 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	881	SF	6	\$2,646	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	881	SF	6	\$6,211	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,512	SF	6	\$4,173	
	Walls - Plaster/Drywall	2nd Floor	12	SF	5	\$61	Peeling paint
	Work Sink	2nd Floor	1	EA	6	\$379	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #209 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	938	SF	6	\$2,817	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,017	SF	6	\$2,807	
<b>Classroom #210 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	6	\$496	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	879	SF	6	\$2,640	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Wood	2nd Floor	879	SF	6	\$6,197	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	16	SF	5	\$82	Peeling paint/minor drywall damage
	Walls - Plaster/Drywall	2nd Floor	1,022	SF	6	\$2,821	
<b>Classroom #300 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	415	SF	6	\$1,246	
	Chalk Board	3rd Floor	20	LF	4	\$1,836	
	Doors - Transom Window	3rd Floor	60	SF	6	\$1,016	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Carpet	3rd Floor	415	SF	6	\$884	
	Lighting - Lay-in	3rd Floor	6	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	850	SF	6	\$2,346	
<b>Classroom #301 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	888	SF	6	\$2,667	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #301 (Regular Classroom)</b>							
	Floor - Wood	3rd Floor	888	SF	6	\$6,260	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,070	SF	6	\$2,953	
<b>Classroom #302 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	15	LF	6	\$379	
	Ceiling - Lay-in	3rd Floor	938	SF	6	\$2,817	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,232	SF	6	\$3,400	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #303 (Science)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	38	LF	6	\$960	
	Ceiling - Lay-in	3rd Floor	909	SF	6	\$2,730	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	909	SF	6	\$6,408	
	Lighting - Lay-in	3rd Floor	21	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,148	SF	6	\$3,168	
	Walls - Plaster/Drywall	3rd Floor	2	SF	5	\$10	Peeling paint
<b>Classroom #304 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	938	SF	6	\$2,817	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #304 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	3rd Floor	1	SF	5	\$5	Peeling paint
	Walls - Plaster/Drywall	3rd Floor	1,231	SF	6	\$3,397	
<b>Classroom #305 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	888	SF	6	\$2,667	
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	888	SF	6	\$6,260	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,150	SF	6	\$3,174	
<b>Classroom #306B (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Ceiling - Lay-in	3rd Floor	602	SF	6	\$1,808	
	Doors - Side-lite	3rd Floor	14	SF	6	\$234	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	602	SF	6	\$4,244	
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	887	SF	6	\$2,448	
<b>Classroom #307 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	3rd Floor	938	SF	6	\$2,817	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Transom Window	3rd Floor	12	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,232	SF	6	\$3,400	
<b>Classroom #308 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #308 (Regular Classroom)</b>							
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	938	SF	6	\$2,817	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	40	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	6	SF	5	\$31	Peeling paint
	Walls - Plaster/Drywall	3rd Floor	1,226	SF	6	\$3,384	
<b>Classroom #309 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	938	SF	6	\$2,817	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	938	SF	6	\$6,613	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1	SF	5	\$5	Peeling paint
	Walls - Plaster/Drywall	3rd Floor	1,231	SF	6	\$3,397	
<b>Classroom #310 (Regular Classroom)</b>							
	AC Units	3rd Floor	2	EA	6	\$991	
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	888	SF	6	\$2,667	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Wood	3rd Floor	888	SF	6	\$6,260	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,138	SF	6	\$3,141	
	Walls - Plaster/Drywall	3rd Floor	12	SF	5	\$61	Peeling paint, minor drywall damage

**Classrooms Subtotal:**

**\$376,189**

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	1st floor NW corner	557	SF	6	\$1,673	
	Doors - Side-lite	1st floor NW corner	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	1st floor NW corner	1	EA	6	\$301	
	Floor - Tile	1st floor NW corner	557	SF	6	\$1,219	
	Lighting - Lay-in	1st floor NW corner	6	EA	7	\$0	
	Lighting - Wall Mounted	1st floor NW corner	1	EA	6	\$124	
	Power Distribution	1st floor NW corner	18	EA	7	\$0	
	Walls - Plaster/Drywall	1st floor NW corner	1,042	SF	6	\$2,876	
	Ceiling - Lay-in	206A at north end of corridor	211	SF	6	\$634	
	Doors - Wood Doors inclu hw	206A at north end of corridor	1	EA	6	\$301	
	Floor - Carpet	206A at north end of corridor	211	SF	6	\$450	
	Lighting - Lay-in	206A at north end of corridor	2	EA	7	\$0	
	Power Distribution	206A at north end of corridor	6	EA	7	\$0	
	Walls - Plaster/Drywall	206A at north end of corridor	646	SF	6	\$1,783	
	Ceiling - Lay-in	306A - Counselor room	360	SF	6	\$1,081	
	Doors - Wood Doors inclu hw	306A - Counselor room	1	EA	6	\$301	
	Floor - Carpet	306A - Counselor room	360	SF	6	\$767	
	Lighting - Lay-in	306A - Counselor room	3	EA	7	\$0	
	Power Distribution	306A - Counselor room	6	EA	7	\$0	
	Walls - Plaster/Drywall	306A - Counselor room	4	SF	5	\$20	Peeling paint
	Walls - Plaster/Drywall	306A - Counselor room	875	SF	6	\$2,415	
	Walls - Plaster/Drywall	306A - Counselor room	5	SF	4	\$74	Drywall damage
	AC Unit	312	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	312	294	SF	6	\$1,017	
	Ceiling - Plaster/Drywall	312	8	SF	5	\$100	Peeling paint
	Doors - Transom Window	312	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	312	1	EA	6	\$301	
	Floor - Wood	312	302	SF	6	\$2,129	
	Lighting - Pendent/Surface	312	4	EA	7	\$0	
	Power Distribution	312	6	EA	7	\$0	
	Walls - Plaster/Drywall	312	722	SF	6	\$1,993	
	AC Unit	313	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	313	26	SF	4	\$566	Water damage/cracks
	Ceiling - Plaster/Drywall	313	276	SF	6	\$955	
	Doors - Transom Window	313	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	313	1	EA	6	\$301	
	Floor - Wood	313	302	SF	6	\$2,129	
	Lighting - Pendent/Surface	313	4	EA	7	\$0	
	Power Distribution	313	6	EA	7	\$0	
	Walls - Plaster/Drywall	313	4	SF	5	\$20	Water damage

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Plaster/Drywall	313	718	SF	6	\$1,982	
	Ceiling - Plaster/Drywall	Dressing room in gymnasium	135	SF	6	\$467	
	Doors - Wood Doors inclu hw	Dressing room in gymnasium	1	EA	6	\$301	
	Floor - Tile	Dressing room in gymnasium	135	SF	6	\$295	
	Lighting - Pendent/Surface	Dressing room in gymnasium	2	EA	7	\$0	
	Power Distribution	Dressing room in gymnasium	2	EA	7	\$0	
	Walls - Plaster/Drywall	Dressing room in gymnasium	368	SF	5	\$2,789	Peeling paint
<b>Gymnasia</b>							
	Ceiling - Plaster/Drywall	1st Floor	6	SF	4	\$202	Water damage in vestibule
	Ceiling - Plaster/Drywall	1st Floor	6,594	SF	6	\$36,398	
	Doors - Transom Window	1st Floor	12	SF	5	\$508	2 broken panes
	Doors - Transom Window	1st Floor	108	SF	6	\$1,829	
	Doors - Wood Doors inclu hw	1st Floor	10	EA	6	\$3,010	
	Floor - Wood	1st Floor	6,022	SF	6	\$42,454	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	28	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	21	EA	7	\$0	
	Main Floor Seating	1st Floor	320	EA	6	\$55,653	
	Scoreboards	1st Floor	1	EA	6	\$2,244	
	Sound System	1st Floor	1	EA	6	\$41,654	
	Stage	1st Floor	578	SF	6	\$3,339	
	Stage Curtain	1st Floor	2	EA	6	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	4	\$287,931	Not working
	Stage-Stairs - Wood	1st Floor	10	LF	6	\$117	
	Storage/ Closet	1st Floor	56	SF	6	\$406	
	Walls - Plaster/Drywall	1st Floor	6,686	SF	6	\$18,453	
<b>MDF_IDF</b>							
	AC Unit	In 206A	1	EA	6	\$496	
	Doors - Steel Doors incl hw	In 206A	1	EA	6	\$301	
	Finishes	In 206A	527	SF	6	\$3,761	
<b>Mechanical/ Service Rooms</b>							
	Boiler Room	Entire Building	1,790	SF	6	\$12,824	
	Coal Room	Entire Building	468	SF	6	\$3,353	
	Janitor's Closet	Entire Building	72	SF	6	\$516	
	Mechanical/ Service Rooms	Entire Building	3,326	SF	6	\$23,828	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	1st floor boys	266	SF	6	\$2,453	
	Ceiling - Plaster/Drywall	1st floor boys	186	SF	6	\$644	
	Ceiling - Plaster/Drywall	1st floor boys	80	SF	4	\$1,406	Water damage
	Doors - Wood Doors inclu hw	1st floor boys	2	EA	6	\$602	
	Floor Drain	1st floor boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor boys	266	SF	6	\$563	
	Lavatory	1st floor boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st floor boys	5	EA	7	\$0	
	Partitions	1st floor boys	3	EA	6	\$891	
	Urinals	1st floor boys	5	EA	6	\$1,680	
	Walls - Plaster/Drywall	1st floor boys	110	SF	5	\$486	Peeling paint
	Walls - Plaster/Drywall	1st floor boys	315	SF	6	\$869	
	Walls - Structural Glazed Tile	1st floor boys	425	SF	6	\$1,337	
	Water Closet	1st floor boys	3	EA	6	\$1,008	
	Accessories	1st floor girls	203	SF	6	\$1,872	
	Ceiling - Plaster/Drywall	1st floor girls	78	SF	4	\$1,371	Drywall damage
	Ceiling - Plaster/Drywall	1st floor girls	125	SF	5	\$1,146	Peeling paint
	Doors - Wood Doors inclu hw	1st floor girls	4	EA	6	\$1,204	
	Floor Drain	1st floor girls	1	EA	6	\$1,059	
	Floor - Tile	1st floor girls	203	SF	6	\$444	
	Lavatory	1st floor girls	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st floor girls	5	EA	7	\$0	
	Partitions	1st floor girls	5	EA	6	\$1,485	
	Walls - Plaster/Drywall	1st floor girls	388	SF	5	\$2,941	Peeling paint
	Walls - Structural Glazed Tile	1st floor girls	388	SF	6	\$1,221	
	Water Closet	1st floor girls	5	EA	6	\$1,680	
	Accessories	1st floor inside office at NW corner	67	SF	6	\$618	
	Ceiling - Plaster/Drywall	1st floor inside office at NW corner	67	SF	6	\$232	
	Doors - Wood Doors inclu hw	1st floor inside office at NW corner	1	EA	6	\$301	
	Floor - Tile	1st floor inside office at NW corner	67	SF	6	\$147	
	Lavatory	1st floor inside office at NW corner	1	EA	6	\$320	
	Lighting - Pendent/Surface	1st floor inside office at NW corner	1	EA	7	\$0	
	Walls - Plaster/Drywall	1st floor inside office at NW corner	307	SF	6	\$847	
	Water Closet	1st floor inside office at NW corner	1	EA	6	\$336	
	Accessories	1st floor next to girls restroom	38	SF	6	\$350	
	Ceiling - Lay-in	1st floor next to girls restroom	38	SF	6	\$114	
	Doors - Wood Doors inclu hw	1st floor next to girls restroom	1	EA	6	\$301	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor - Tile Ceramic/ Porcelain	1st floor next to girls restroom	38	SF	6	\$80	
	Lavatory	1st floor next to girls restroom	1	EA	6	\$320	
	Lighting - Lay-in	1st floor next to girls restroom	1	EA	7	\$0	
	Walls - Plaster/Drywall	1st floor next to girls restroom	165	SF	6	\$455	
	Walls - Structural Glazed Tile	1st floor next to girls restroom	165	SF	6	\$519	
	Water Closet	1st floor next to girls restroom	1	EA	6	\$336	
	Accessories	2nd floor boys	266	SF	6	\$2,453	
	Ceiling - Plaster/Drywall	2nd floor boys	266	SF	6	\$921	
	Doors - Wood Doors inclu hw	2nd floor boys	1	EA	6	\$301	
	Floor Drain	2nd floor boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor boys	266	SF	6	\$563	
	Lavatory	2nd floor boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd floor boys	5	EA	7	\$0	
	Partitions	2nd floor boys	2	EA	6	\$594	
	Urinals	2nd floor boys	4	EA	6	\$1,344	
	Walls - Plaster/Drywall	2nd floor boys	425	SF	6	\$1,173	
	Walls - Structural Glazed Tile	2nd floor boys	425	SF	6	\$1,337	
	Water Closet	2nd floor boys	2	EA	6	\$672	
	Accessories	2nd floor girls	266	SF	6	\$2,453	
	Ceiling - Plaster/Drywall	2nd floor girls	266	SF	6	\$921	
	Doors - Wood Doors inclu hw	2nd floor girls	2	EA	6	\$602	
	Floor Drain	2nd floor girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor girls	266	SF	6	\$563	
	Lavatory	2nd floor girls	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd floor girls	5	EA	7	\$0	
	Partitions	2nd floor girls	4	EA	6	\$1,188	
	Walls - Plaster/Drywall	2nd floor girls	425	SF	6	\$1,173	
	Walls - Structural Glazed Tile	2nd floor girls	425	SF	6	\$1,337	
	Water Closet	2nd floor girls	5	EA	6	\$1,680	
	Accessories	2nd Floor unisex	44	SF	6	\$406	
	Ceiling - Plaster/Drywall	2nd Floor unisex	44	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor unisex	1	EA	6	\$301	
	Floor Drain	2nd Floor unisex	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor unisex	44	SF	6	\$93	
	Lavatory	2nd Floor unisex	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd Floor unisex	1	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor unisex	322	SF	6	\$889	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Walls - Structural Glazed Tile	2nd Floor unisex	46	SF	6	\$145	
	Water Closet	2nd Floor unisex	1	EA	6	\$336	
	Accessories	3rd floor boys	266	SF	6	\$2,453	
	Ceiling - Plaster/Drywall	3rd floor boys	266	SF	6	\$921	
	Doors - Wood Doors inclu hw	3rd floor boys	2	EA	6	\$602	
	Floor Drain	3rd floor boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd floor boys	266	SF	6	\$563	
	Lavatory	3rd floor boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	3rd floor boys	5	EA	7	\$0	
	Partitions	3rd floor boys	3	EA	6	\$891	
	Urinals	3rd floor boys	5	EA	6	\$1,680	
	Walls - Plaster/Drywall	3rd floor boys	420	SF	6	\$1,159	
	Walls - Plaster/Drywall	3rd floor boys	5	SF	5	\$26	Peeling paint
	Walls - Structural Glazed Tile	3rd floor boys	425	SF	6	\$1,337	
	Water Closet	3rd floor boys	3	EA	6	\$1,008	
	Accessories	3rd floor girls	266	SF	6	\$2,453	
	Ceiling - Plaster/Drywall	3rd floor girls	256	SF	6	\$886	
	Ceiling - Plaster/Drywall	3rd floor girls	10	SF	5	\$125	Peeling paint
	Doors - Wood Doors inclu hw	3rd floor girls	2	EA	6	\$602	
	Floor Drain	3rd floor girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd floor girls	266	SF	6	\$563	
	Lavatory	3rd floor girls	3	EA	6	\$959	
	Lighting - Pendent/Surface	3rd floor girls	5	EA	7	\$0	
	Partitions	3rd floor girls	7	EA	6	\$2,078	
	Walls - Plaster/Drywall	3rd floor girls	425	SF	6	\$1,173	
	Walls - Structural Glazed Tile	3rd floor girls	425	SF	6	\$1,337	
	Water Closet	3rd floor girls	7	EA	6	\$2,352	
	Accessories	In 110	44	SF	6	\$406	
	Ceiling - Plaster/Drywall	In 110	44	SF	6	\$152	
	Doors - Wood Doors inclu hw	In 110	1	EA	6	\$301	
	Floor - Tile	In 110	44	SF	6	\$96	
	Lavatory	In 110	1	EA	6	\$320	
	Lighting - Pendent/Surface	In 110	1	EA	7	\$0	
	Walls - Plaster/Drywall	In 110	349	SF	6	\$963	
	Water Closet	In 110	2	EA	6	\$672	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Rooms (Other Than Classrooms) Subtotal:</b>						<b>\$667,392</b>	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	4,157	SF	6	\$12,483	
	Ceiling - Plaster/Drywall	1st Floor	820	SF	6	\$5,077	
	Ceiling - Plaster/Drywall	1st Floor	80	SF	5	\$1,396	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
	Doors - Wood Doors include hw	1st Floor	15	EA	6	\$4,515	
	Drinking Fountains - Double Fountain	1st Floor	1	EA	6	\$336	
	Drinking Fountains - Single Fountain	1st Floor	3	EA	6	\$827	
	Floor - Asphalt Floor	1st Floor	4,745	SF	6	\$7,192	
	Floor - Tile/Sheet	1st Floor	633	SF	6	\$344	
	Lighting - Lay-in	1st Floor	35	EA	7	\$0	
	Lighting - Lay-in	1st Floor	4	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	14	EA	7	\$0	
	Stairs - Concrete Stairs	1st Floor	6	LF	6	\$50	
	Student Lockers - Two Tiers	1st Floor	8	EA	6	\$371	
	Walls - Plaster/Drywall	1st Floor	10,807	SF	6	\$47,907	
	Walls - Structural Glazed Tile	1st Floor	612	SF	6	\$1,925	
	Ceiling - Lay-in	2nd Floor	2,554	SF	6	\$7,670	
	Drinking Fountains - Double Fountain	2nd Floor	1	EA	6	\$336	
	Drinking Fountains - Single Fountain	2nd Floor	3	EA	6	\$827	
	Floor - Asphalt Floor	2nd Floor	2,349	SF	6	\$3,561	
	Floor - Terrazzo	2nd Floor	205	SF	6	\$1,721	
	Lighting - Lay-in	2nd Floor	21	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	4,707	SF	6	\$20,866	
	Ceiling - Lay-in	3rd Floor	2,554	SF	6	\$7,670	
	Drinking Fountains - Double Fountain	3rd Floor	1	EA	6	\$336	
	Drinking Fountains - Single Fountain	3rd Floor	3	EA	6	\$827	
	Floor - Asphalt Floor	3rd Floor	2,349	SF	6	\$3,561	
	Floor - Terrazzo	3rd Floor	205	SF	6	\$1,721	
	Lighting - Lay-in	3rd Floor	27	EA	7	\$0	
	Stairs - Concrete Stairs	3rd Floor	10	LF	6	\$83	
	Student Lockers - One Tier	3rd Floor	18	EA	6	\$1,671	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Student Lockers - Two Tiers	3rd Floor	324	EA	6	\$15,039	
	Walls - Plaster/Drywall	3rd Floor	4,707	SF	6	\$20,866	
<b>Safety</b>							
	Security Cameras	Entire Building	1	EA	6	\$194	
	Security Cameras	Entire Building	1	EA	6	\$194	
<b>Stairs</b>							
	Ceiling - Plaster/Drywall	North stair	40	SF	6	\$293	
	Floor - Asphalt	North stair	150	SF	6	\$1,163	
	Handrails	North stair	162	LF	6	\$1,404	
	Lighting - Lay-in	North stair	3	EA	7	\$0	
	Lighting - Pendent/Surface	North stair	2	EA	7	\$0	
	Stairs - Asphalt	North stair	57	LF	6	\$529	
	Walls - Plaster/Drywall	North stair	2,415	SF	6	\$6,665	
	Ceiling - Plaster/Drywall	South stair	40	SF	6	\$293	
	Floor - Asphalt	South stair	150	SF	6	\$1,163	
	Handrails	South stair	162	LF	6	\$1,404	
	Lighting - Lay-in	South stair	3	EA	7	\$0	
	Lighting - Pendent/Surface	South stair	2	EA	7	\$0	
	Stairs - Asphalt	South stair	57	LF	6	\$529	
	Walls - Plaster/Drywall	South stair	2,415	SF	6	\$6,665	

**Building Interior Subtotal:**

**\$190,577**

**Total Building Cost**

**\$2,933,520**

**Building: Addition**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#3_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#4 S	2	EA	5	\$2,683	
	Exterior Doors - Exterior Steel Door	#4.1_Exit S	1	EA	6	\$481	
	Exterior Doors - Store Front	#2_Exit N	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#5_Exit S	2	EA	6	\$1,092	
	Exterior Doors - Store Front	#6 S	2	EA	6	\$1,092	

## Building: Addition

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Stairs - Concrete	#5_Exit S	45	LF	6	\$3,680	
	Exterior Stairs - Concrete	#6 S	30	LF	6	\$2,453	
	Ramp Handrail - Steel_Ramp Handrail	#5_Exit S	15	LF	6	\$130	
	Ramps - Concrete	#5_Exit S	30	LF	6	\$4,507	
	Stair Handrail - Steel_Stair Handrail	#5_Exit S	15	LF	6	\$130	
	Stair Handrail - Steel_Stair Handrail	#6 S	10	LF	6	\$87	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	835	LF	7	\$0	
	Superstructure - Metal Deck/ Concrete Topping	Entire Building	71,850	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	22	EA	6	\$6,352	
<b>Roof System</b>							
	Chimney - Metal Flue	Roof #1	3	LF	6	\$474	
	Coping - Stone	Roof #1	800	LF	6	\$25,694	
	Coping - Stone	Roof #2	228	LF	6	\$7,323	
	Downspouts - Interior Downspouts	Roof #1	480	LF	6	\$15,952	
	Downspouts - Interior Downspouts	Roof #2	80	LF	6	\$2,659	
	Parapet - 16" - 30" Height	Roof #1	652	LF	6	\$26,050	
	Parapet - 16" - 30" Height	Roof #2	228	LF	6	\$9,110	
	Parapet - Parapet > 30"	Roof #1	148	LF	6	\$9,460	
	Parapet - Parapet > 30"	Roof #1 / North Façade	35	LF	4	\$37,604	Limestone is seperating from building
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof #1	21,310	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof #2	5,743	SF	7	\$0	
	Roof - Modified Bitumen	Roof #1	21,285	SF	6	\$200,279	
	Roof - Modified Bitumen	Roof #1	25	SF	5	\$714	Roof Leaks reported
	Roof - Modified Bitumen	Roof #2	5,693	SF	6	\$53,568	
	Roof - Modified Bitumen	Roof #2	50	SF	5	\$1,428	Roof Leaks reported
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	31,159	SF	6	\$209,420	
	Exterior Walls - Stone-Cast	Entire Building	11,016	SF	6	\$74,039	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building / 1st Floor	1,465	SF	6	\$18,708	
	Lintels - Steel	Entire Building	782	LF	7	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	5,660	SF	6	\$42,250	

**Building: Addition**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Building Exterior Subtotal:</b>						<b>\$759,470</b>	

**Building: Addition**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Mechanical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	13,400	SF	6	\$4,024	
	Emergency A/C Power - Multipurpose Room	Entire Building / 1st Floor	6,280	SF	6	\$2,335	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	20	EA	7	\$0	
	Emergency Battery Packs - Multipurpose Room	Entire Building / 1st Floor	8	EA	7	\$0	
	Emergency Battery Packs - Students Toilets	Entire Building	3	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	20	EA	7	\$0	have battery packs
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	8	EA	7	\$0	
	Security System - CCTV	Entire Building	71,850	SF	6	\$21,577	
	Security System - Intrusion Detection	Entire Building	71,850	SF	6	\$18,494	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Building has an ATS
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	1	EA	6	\$8,662	
	PA System	Entire Building	71,850	SF	6	\$23,631	connected to main building
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	1	EA	7	\$0	Fuses
	Lighting and Power Panels - Above 100 A	Entire Building	13	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Mechanical Room	2	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Mechanical Room	2	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Entire Building / Mechanical Room	2	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building / Boiler Room	1	EA	6	\$1,265	Hot and Excessive hum
	Transformers - 277/480 - 120/208	Entire Building / Mechanical Room	3	EA	6	\$3,795	

**Electrical System Subtotal:**

**\$84,191**

**Building: Addition**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Electrical Room	1	EA	6	\$6,406	

**Building: Addition**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Strobe Lights	Electrical Room / Entire Building	71,850	SF	6	\$25,686	
	Fire Alarm_System	Electrical Room / Entire Building	71,850	SF	7	\$0	
	Fire Pump Controller	Electrical Room / Mechanical Room	1	EA	7	\$0	
<b>Pump Room Assembly</b>							
	Fire Pump - 25-50 hp	Mechanical Room	1	EA	6	\$1,558	
	Jockey Pump	Mechanical Room	1	EA	6	\$758	
<b>Sprinkler System</b>							
	Sprinkler Heads	Entire Building	71,850	SF	7	\$0	
	Sprinkler Piping	Entire Building	71,850	SF	7	\$0	
	Wet Sprinkler System	Entire Building	71,850	SF	7	\$0	

**Safty System Subtotal:**

**\$34,408**

**Building: Addition**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	6	\$606	
	Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons	Roof	2	EA	7	\$0	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	Serves MDF room
	Glycol Feed	Roof / Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Galvanized	Roof / Entire Building	600	LF	6	\$1,133	
	Pressure Fill System	Roof / Mechanical Room	1	EA	6	\$1,405	
<b>Air Handling Systems</b>							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	6	\$3,350	serves 1'st floor area, except kitchen area
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	Mechanical Room	1	EA	6	\$3,350	serves kitchen area
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	6	\$3,350	serves 2'nd and 3'd floors
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	
	Fan Coil Unit- Celing Mounted - Hot Water-Heating	Entire Building	6	EA	6	\$9,625	
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building	13	EA	5	\$20,482	serve AH1
	Fan Power Box - Fan Power Box with Hot Water Coil	Entire Building	13	EA	5	\$20,482	serve AH2

## Building: Addition

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	Mechanical Room	2	EA	6	\$3,714	
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	Mechanical Room	1	EA	6	\$1,857	
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	Mechanical Room	1	EA	6	\$2,433	
	Make Up Air Unit- Indoor Mounted- Hot Water Coils - Less than 6000 cfm	Mechanical Room	1	EA	6	\$3,350	
	VAV Box	Mechanical Room / Entire Building	39	EA	6	\$10,887	
	Zone Dampers	Mechanical Room / 1st Floor	17	EA	6	\$14,162	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Non Condensing Hot Water - 3001 - 4000 MBH	Boiler Room	3	EA	6	\$6,139	
	Chemical Pot Feeder	Boiler Room	1	EA	6	\$725	
	Combustion Dampers	Boiler Room	1	EA	6	\$409	1 Damper for 3 Water Heaters
	Combustion Dampers	Boiler Room	1	EA	5	\$2,552	One Damper for 3 Boilers. Does not open fully
	Glycol Feed System	Boiler Room	1	EA	6	\$539	
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - 3001 - 4000 MBH	Boiler Room	3	EA	6	\$2,994	
	Water Fill System	Boiler Room	1	EA	6	\$1,168	
<b>Gas Booster</b>							
	Gas Booster	Boiler Room	1	EA	6	\$499	1 Booster for 3 Boilers
<b>Heating Devices</b>							
	Radiators - Hot Water	Entire Building	3	EA	6	\$833	
	Unit Heater - Electric	Mechanical Room / Entire Building	2	EA	6	\$556	
	Unit Heater - Hot Water	Mechanical Room / Entire Building	8	EA	6	\$2,233	
<b>Mechanical Plumbing</b>							
	Chilled Water Pump - 10 - 20 HP	Boiler Room	3	EA	6	\$3,727	
	Hot Water Pump - 10 - 20 HP	Boiler Room	2	EA	6	\$2,485	
	Hydronic Supply and Return - Galvanized	Entire Building	1,000	LF	6	\$77,320	
<b>Temperature Control</b>							
	DDC System	Entire Building	71,850	SF	6	\$41,098	
	Thermostats - DDC	Entire Building	56	EA	6	\$0	
<b>Ventilation</b>							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building	4	EA	6	\$2,370	electrical rooms, mechanical rooms
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	6	\$592	Ponding / Standing water on iron duct is rusting. serves kitchen and cafeteria
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	serves kitchen
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	1	EA	6	\$296	

**Building: Addition**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Ventilation</b>							
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	7	\$0	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	2	EA	7	\$0	

**Mechanical System Subtotal:**

**\$269,023**

**Building: Addition**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 300001 - 600000 BTU/HR	3rd Floor / Boiler Room	2	EA	6	\$620	
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	3rd Floor / Boiler Room	1	EA	7	\$0	1999 installation

**Piping**

	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	71,850	SF	6	\$14,384	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	71,850	SF	6	\$17,467	
	Domestic Piping-Cold Water Risers	Entire Building	71,850	SF	6	\$13,357	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	71,850	SF	6	\$11,302	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	71,850	SF	6	\$13,357	
	Domestic Piping-Hot Water Return Lines	Entire Building	71,850	SF	6	\$10,275	
	Domestic Piping-Hot Water Return Risers	Entire Building	71,850	SF	6	\$10,275	
	Sanitary Piping	Entire Building	71,850	SF	6	\$65,757	
	Storm Piping	Entire Building	71,850	SF	6	\$62,675	
	Vent Piping	Entire Building	71,850	SF	6	\$48,290	

**Pumps**

	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	
	Pumps - Sump-Simplex	Mechanical Room / 1st Floor	1	EA	6	\$745	

**Plumbing System Subtotal:**

**\$270,480**

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #121 (Pre School)</b>							
	Casework	1st Floor	66	LF	6	\$1,667	
	Ceiling - Lay-in	1st Floor	1,073	SF	6	\$3,222	
	Chalk Board	1st Floor	12	LF	4	\$1,102	

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #121 (Pre School)</b>							
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,073	SF	6	\$2,348	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Storage/ Closet	1st Floor	43	SF	6	\$312	
	Walls - Concrete Block	1st Floor	504	SF	6	\$1,477	
	Walls - Plaster/Drywall	1st Floor	504	SF	6	\$1,391	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #122 (Pre School)</b>							
	Casework	1st Floor	66	LF	6	\$1,667	
	Ceiling - Lay-in	1st Floor	1,073	SF	6	\$3,222	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,073	SF	6	\$2,348	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Storage/ Closet	1st Floor	43	SF	6	\$312	
	Walls - Concrete Block	1st Floor	616	SF	6	\$1,806	
	Walls - Plaster/Drywall	1st Floor	504	SF	6	\$1,391	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #123 (Pre School)</b>							
	Casework	1st Floor	66	LF	6	\$1,667	
	Ceiling - Lay-in	1st Floor	1,098	SF	6	\$3,297	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,098	SF	6	\$2,402	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Storage/ Closet	1st Floor	43	SF	6	\$312	
	Walls - Concrete Block	1st Floor	876	SF	6	\$2,568	
	Walls - Plaster/Drywall	1st Floor	247	SF	6	\$682	
	Walls - Plaster/Drywall	1st Floor	5	SF	5	\$26	crack
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #126 (Kindergarten)</b>							
	Casework	1st Floor	66	LF	6	\$1,667	
	Ceiling - Lay-in	1st Floor	1,086	SF	6	\$3,261	
	Ceiling - Lay-in	1st Floor	12	SF	5	\$96	water damaged

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #126 (Kindergarten)</b>							
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,098	SF	6	\$2,402	water stains
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Storage/ Closet	1st Floor	43	SF	6	\$312	
	Walls - Concrete Block	1st Floor	876	SF	6	\$2,568	
	Walls - Plaster/Drywall	1st Floor	252	SF	6	\$695	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #128 (Kindergarten)</b>							
	Casework	1st Floor	66	LF	6	\$1,667	
	Ceiling - Lay-in	1st Floor	18	SF	5	\$144	water damaged
	Ceiling - Lay-in	1st Floor	1,080	SF	6	\$3,243	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Side-lite	1st Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,098	SF	6	\$2,402	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Storage/ Closet	1st Floor	43	SF	6	\$312	
	Walls - Concrete Block	1st Floor	8	SF	5	\$113	crack
	Walls - Concrete Block	1st Floor	876	SF	6	\$2,568	
	Walls - Plaster/Drywall	1st Floor	252	SF	6	\$695	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #223 (Regular Classroom)</b>							
	Casework	2nd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	2nd Floor	852	SF	6	\$2,559	
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	852	SF	6	\$1,864	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	673	SF	6	\$1,973	
	Walls - Plaster/Drywall	2nd Floor	504	SF	6	\$1,391	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #224 (Regular Classroom)</b>							
	Casework	2nd Floor	24	LF	6	\$606	

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #224 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	852	SF	6	\$2,559	
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	852	SF	6	\$1,864	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	673	SF	6	\$1,973	
	Walls - Plaster/Drywall	2nd Floor	504	SF	6	\$1,391	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #225 (Regular Classroom)</b>							
	Casework	2nd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	2nd Floor	852	SF	6	\$2,559	
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	852	SF	6	\$1,864	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	901	SF	6	\$2,641	
	Walls - Plaster/Drywall	2nd Floor	252	SF	6	\$695	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #228 (Regular Classroom)</b>							
	Casework	2nd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	2nd Floor	844	SF	6	\$2,535	
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$64	water damaged
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	852	SF	6	\$1,864	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	673	SF	6	\$1,973	
	Walls - Plaster/Drywall	2nd Floor	504	SF	6	\$1,391	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #229 (Computer Lab)</b>							
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	1,013	SF	6	\$3,042	
	Ceiling - Lay-in	2nd Floor	6	SF	5	\$48	water damaged
	Charging Station	2nd Floor	12	EA	6	\$5,816	There are 12 total carts, all were in hall

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #229 (Computer Lab)</b>							
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,019	SF	6	\$2,229	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Storage/ Closet	2nd Floor	24	SF	6	\$174	
	Walls - Concrete Block	2nd Floor	707	SF	6	\$2,073	
	Walls - Plaster/Drywall	2nd Floor	579	SF	6	\$1,598	
	Wireless System	2nd Floor	1	EA	6	\$372	
<b>Classroom #231 (Regular Classroom)</b>							
	Casework	2nd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	2nd Floor	849	SF	6	\$2,550	
	Ceiling - Lay-in	2nd Floor	3	SF	5	\$24	water damaged
	Chalk Board	2nd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	2nd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	852	SF	6	\$1,864	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	1,177	SF	6	\$3,450	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #320 (Regular Classroom)</b>							
	Casework	3rd Floor	51	LF	6	\$1,288	
	Ceiling - Lay-in	3rd Floor	897	SF	6	\$2,694	
	Ceiling - Lay-in	3rd Floor	3	SF	5	\$24	water damage
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	6	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	833	SF	6	\$2,442	
	Walls - Concrete Block	3rd Floor	8	SF	5	\$113	crack
	Walls - Plaster/Drywall	3rd Floor	251	SF	6	\$693	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #321 (Regular Classroom)</b>							
	Casework	3rd Floor	51	LF	6	\$1,288	

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #321 (Regular Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	900	SF	6	\$2,703	
	Chalk Board	3rd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	767	SF	6	\$2,248	
	Walls - Plaster/Drywall	3rd Floor	502	SF	6	\$1,385	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #322 (Regular Classroom)</b>							
	Casework	3rd Floor	51	LF	6	\$1,288	
	Ceiling - Lay-in	3rd Floor	897	SF	6	\$2,694	
	Ceiling - Lay-in	3rd Floor	3	SF	5	\$24	water damaged
	Chalk Board	3rd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	841	SF	6	\$2,465	
	Walls - Plaster/Drywall	3rd Floor	251	SF	6	\$693	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #323 (Regular Classroom)</b>							
	Casework	3rd Floor	51	LF	6	\$1,288	
	Ceiling - Lay-in	3rd Floor	897	SF	6	\$2,694	
	Ceiling - Lay-in	3rd Floor	3	SF	5	\$24	water damaged
	Chalk Board	3rd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	841	SF	6	\$2,465	
	Walls - Plaster/Drywall	3rd Floor	251	SF	6	\$693	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #324 (Regular Classroom)</b>							
	Casework	3rd Floor	51	LF	6	\$1,288	
	Ceiling - Lay-in	3rd Floor	895	SF	6	\$2,688	

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #324 (Regular Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	5	SF	5	\$40	water damaged
	Chalk Board	3rd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	662	SF	6	\$1,941	
	Walls - Plaster/Drywall	3rd Floor	502	SF	6	\$1,385	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #325 (Regular Classroom)</b>							
	Casework	3rd Floor	51	LF	6	\$1,288	
	Ceiling - Lay-in	3rd Floor	888	SF	6	\$2,667	
	Ceiling - Lay-in	3rd Floor	12	SF	5	\$96	water stains
	Chalk Board	3rd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Storage/ Closet	3rd Floor	841	SF	6	\$6,097	
	Walls - Concrete Block	3rd Floor	1,003	SF	6	\$2,940	
	Walls - Concrete Block	3rd Floor	6	SF	5	\$85	crack
	Walls - Plaster/Drywall	3rd Floor	251	SF	6	\$693	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #328 (Art Room)</b>							
	Casework	3rd Floor	56	LF	6	\$1,414	
	Ceiling - Lay-in	3rd Floor	1,052	SF	6	\$3,159	
	Ceiling - Lay-in	3rd Floor	1	SF	5	\$8	water damaged
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,053	SF	6	\$2,304	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Storage/ Closet	3rd Floor	156	SF	6	\$1,131	328A
	Walls - Concrete Block	3rd Floor	767	SF	6	\$2,248	
	Walls - Plaster/Drywall	3rd Floor	502	SF	6	\$1,385	
	Work Sink	3rd Floor	2	EA	6	\$758	

**Building: Addition**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #329 (Science Lab Level 1)</b>							
	Casework	3rd Floor	56	LF	6	\$1,414	
	Ceiling - Lay-in	3rd Floor	1,044	SF	6	\$3,135	
	Doors - Side-lite	3rd Floor	1	SF	6	\$17	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,044	SF	6	\$2,284	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Science Lab Elements	3rd Floor	18	SF	6	\$122	
	Storage/ Closet	3rd Floor	21	SF	6	\$152	
	Walls - Concrete Block	3rd Floor	767	SF	6	\$2,248	
	Walls - Plaster/Drywall	3rd Floor	502	SF	6	\$1,385	
	Work Sink	3rd Floor	3	EA	6	\$1,137	
<b>Classroom #331 (Music Room)</b>							
	Casework	3rd Floor	48	LF	6	\$1,212	
	Ceiling - Lay-in	3rd Floor	848	SF	6	\$2,547	
	Chalk Board	3rd Floor	18	LF	4	\$1,653	
	Doors - Side-lite	3rd Floor	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	848	SF	6	\$1,855	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Walls - Concrete Block	3rd Floor	1,125	SF	6	\$3,298	
	Work Sink	3rd Floor	1	EA	6	\$379	

**Classrooms Subtotal:**

**\$247,468**

**Building: Addition**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Exposed	3rd Flr- engineers office	1,092	SF	6	\$1,624	
	Doors - Steel Doors incl hw	3rd Flr- engineers office	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	3rd Flr- engineers office	1,092	SF	6	\$578	
	Lighting - Pendent/Surface	3rd Flr- engineers office	6	EA	7	\$0	
	Power Distribution	3rd Flr- engineers office	8	EA	7	\$0	
	Walls - Concrete Block	3rd Flr- engineers office	1,618	SF	6	\$4,743	

## Building: Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Plaster/Drywall	3rd Flr- engineers office	1,228	SF	6	\$3,389	
	Work Slnk	3rd Flr- engineers office	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 120- main office	763	SF	6	\$2,291	
	Doors - Side-lite	Rm 120- main office	81	SF	6	\$1,354	
	Doors - Wood Doors inclu hw	Rm 120- main office	2	EA	6	\$602	
	Floor - Carpet	Rm 120- main office	634	SF	6	\$1,351	
	Floor - Terrazzo	Rm 120- main office	129	SF	6	\$282	
	Lighting - Lay-in	Rm 120- main office	17	EA	7	\$0	
	Power Distribution	Rm 120- main office	22	EA	7	\$0	
	Storage/ Closet	Rm 120- main office	28	SF	6	\$203	
	Walls - Concrete Block	Rm 120- main office	1,105	SF	6	\$3,239	
	Walls - Plaster/Drywall	Rm 120- main office	770	SF	6	\$2,125	
	Ceiling - Lay-in	Rm 120A- Asst Principal in main office	1	SF	5	\$8	water damaged
	Ceiling - Lay-in	Rm 120A- Asst Principal in main office	256	SF	6	\$769	
	Doors - Wood Doors inclu hw	Rm 120A- Asst Principal in main office	1	EA	6	\$301	
	Floor - Carpet	Rm 120A- Asst Principal in main office	257	SF	6	\$548	
	Lighting - Lay-in	Rm 120A- Asst Principal in main office	4	EA	7	\$0	
	Power Distribution	Rm 120A- Asst Principal in main office	10	EA	7	\$0	
	Walls - Concrete Block	Rm 120A- Asst Principal in main office	287	SF	6	\$841	
	Walls - Plaster/Drywall	Rm 120A- Asst Principal in main office	458	SF	6	\$1,264	
	Work Slnk	Rm 120A- Asst Principal in main office	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 120B- Principal in main office	413	SF	6	\$1,240	
	Doors - Wood Doors inclu hw	Rm 120B- Principal in main office	1	EA	6	\$301	
	Floor - Carpet	Rm 120B- Principal in main office	340	SF	6	\$724	
	Floor - Tile	Rm 120B- Principal in main office	78	SF	6	\$171	
	Lighting - Lay-in	Rm 120B- Principal in main office	6	EA	7	\$0	
	Power Distribution	Rm 120B- Principal in main office	12	EA	7	\$0	
	Walls - Concrete Block	Rm 120B- Principal in main office	340	SF	6	\$997	
	Walls - Plaster/Drywall	Rm 120B- Principal in main office	662	SF	6	\$1,827	
	Walls - Plaster/Drywall	Rm 120B- Principal in main office	5	SF	5	\$26	water damaged
	Work Slnk	Rm 120B- Principal in main office	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 120C Work Rm in main office	120	SF	6	\$360	
	Doors - Steel Doors incl hw	Rm 120C Work Rm in main office	1	EA	6	\$301	vault door
	Floor - Tile	Rm 120C Work Rm in main office	120	SF	6	\$263	
	Lighting - Lay-in	Rm 120C Work Rm in main office	4	EA	7	\$0	
	Power Distribution	Rm 120C Work Rm in main office	8	EA	7	\$0	
	Walls - Concrete Block	Rm 120C Work Rm in main office	287	SF	6	\$841	

## Building: Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Work Slnk	Rm 120C Work Rm in main office	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 124A- Teacher's Lounge	285	SF	6	\$856	
	Ceiling - Lay-in	Rm 124A- Teacher's Lounge	2	SF	5	\$16	water damage
	Doors - Wood Doors inclu hw	Rm 124A- Teacher's Lounge	1	EA	6	\$301	
	Floor - Tile	Rm 124A- Teacher's Lounge	287	SF	6	\$628	
	Lighting - Lay-in	Rm 124A- Teacher's Lounge	4	EA	7	\$0	
	Power Distribution	Rm 124A- Teacher's Lounge	6	EA	7	\$0	
	Walls - Concrete Block	Rm 124A- Teacher's Lounge	708	SF	6	\$2,076	
	Work Slnk	Rm 124A- Teacher's Lounge	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 125E- Kitchen manager office	73	SF	6	\$219	
	Doors - Side-lite	Rm 125E- Kitchen manager office	91	SF	6	\$1,521	
	Doors - Wood Doors inclu hw	Rm 125E- Kitchen manager office	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Rm 125E- Kitchen manager office	73	SF	6	\$39	
	Lighting - Lay-in	Rm 125E- Kitchen manager office	1	EA	7	\$0	
	Power Distribution	Rm 125E- Kitchen manager office	2	EA	7	\$0	
	Walls - Concrete Block	Rm 125E- Kitchen manager office	320	SF	6	\$938	
	Ceiling - Lay-in	Rm 220A- library workroom/office	200	SF	6	\$601	
	Doors - Side-lite	Rm 220A- library workroom/office	15	SF	6	\$251	
	Doors - Wood Doors inclu hw	Rm 220A- library workroom/office	1	EA	6	\$301	
	Floor - Tile	Rm 220A- library workroom/office	200	SF	6	\$438	
	Lighting - Lay-in	Rm 220A- library workroom/office	2	EA	7	\$0	
	Power Distribution	Rm 220A- library workroom/office	6	EA	7	\$0	
	Storage/ Closet	Rm 220A- library workroom/office	22	SF	6	\$160	
	Walls - Concrete Block	Rm 220A- library workroom/office	100	SF	6	\$293	
	Walls - Plaster/Drywall	Rm 220A- library workroom/office	580	SF	6	\$1,601	
	Work Slnk	Rm 220A- library workroom/office	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 227, teacher resource room	448	SF	6	\$1,345	
	Doors - Side-lite	Rm 227, teacher resource room	6	SF	6	\$100	
	Doors - Wood Doors inclu hw	Rm 227, teacher resource room	1	EA	6	\$301	
	Floor - Tile	Rm 227, teacher resource room	448	SF	6	\$980	
	Lighting - Lay-in	Rm 227, teacher resource room	6	EA	7	\$0	
	Power Distribution	Rm 227, teacher resource room	14	EA	7	\$0	
	Walls - Concrete Block	Rm 227, teacher resource room	630	SF	6	\$1,847	
	Walls - Plaster/Drywall	Rm 227, teacher resource room	310	SF	6	\$856	
	Ceiling - Lay-in	Rm 237- Speech & Language Office	174	SF	6	\$523	
	Doors - Wood Doors inclu hw	Rm 237- Speech & Language Office	1	EA	6	\$301	
	Floor - Tile	Rm 237- Speech & Language Office	174	SF	6	\$381	

## Building: Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Lighting - Lay-in	Rm 237- Speech & Language Office	1	EA	7	\$0	
	Power Distribution	Rm 237- Speech & Language Office	2	EA	7	\$0	
	Walls - Concrete Block	Rm 237- Speech & Language Office	418	SF	6	\$1,225	
	Ceiling - Lay-in	Rm 337- Counseling Office	211	SF	6	\$634	
	Doors - Wood Doors inclu hw	Rm 337- Counseling Office	1	EA	6	\$301	
	Floor - Tile	Rm 337- Counseling Office	211	SF	6	\$462	
	Lighting - Lay-in	Rm 337- Counseling Office	1	EA	7	\$0	
	Power Distribution	Rm 337- Counseling Office	2	EA	7	\$0	
	Walls - Concrete Block	Rm 337- Counseling Office	599	SF	6	\$1,756	
<b>Kitchen</b>							
	Ceiling - Lay-in	1st Floor	817	SF	6	\$2,453	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	1st Floor	817	SF	6	\$432	
	Lighting - Lay-in	1st Floor	10	EA	7	\$0	
	Storage/ Closet	1st Floor	393	SF	6	\$2,849	dry & cold storage
	Walls - Concrete Block	1st Floor	1,442	SF	6	\$4,227	
<b>Library</b>							
	Ceiling - Lay-in	2nd Floor	2,459	SF	6	\$7,384	
	Ceiling - Lay-in	2nd Floor	4	SF	5	\$32	water damaged
	Doors - Side-lite	2nd Floor	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	2,463	SF	6	\$5,248	
	Lighting - Lay-in	2nd Floor	28	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	1,978	SF	6	\$5,799	
	Walls - Plaster/Drywall	2nd Floor	326	SF	6	\$900	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Exposed	Rm 124/125- Cafeteria & Served	5,240	SF	6	\$7,793	
	Ceiling - Lay-in	Rm 124/125- Cafeteria & Served	2	SF	5	\$12	water damage
	Doors - Wood Doors inclu hw	Rm 124/125- Cafeteria & Served	8	EA	6	\$2,408	
	Floor - Tile/Sheet	Rm 124/125- Cafeteria & Served	6,280	SF	6	\$6,286	
	Lighting - Pendant/Surface	Rm 124/125- Cafeteria & Served	12	EA	7	\$0	
	Market Board	Rm 124/125- Cafeteria & Served	12	LF	7	\$0	
	Serving Line	Rm 124/125- Cafeteria & Served	28	LF	6	\$1,666	
	Storage/ Closet	Rm 124/125- Cafeteria & Served	373	SF	6	\$2,704	
	Walls - Concrete Block	Rm 124/125- Cafeteria & Served	10,046	SF	6	\$29,450	includes acoustic material

## Building: Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>MDF_IDF</b>							
	AC Unit	Rm 222	1	EA	4	\$6,086	not working
	Doors - Wood Doors inclu hw	Rm 222	1	EA	6	\$301	
	Finishes	Rm 222	145	SF	6	\$1,035	
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	1st Floor	47	SF	6	\$337	
	Mechanical/ Service Rooms	1st Floor	593	SF	6	\$4,248	water room for RR, pump rm & elec closet
	Storage Room	1st Floor	454	SF	6	\$3,253	129A&B, 132, 137, 127
	Janitor's Closet	2nd Floor	27	SF	6	\$193	
	Mechanical/ Service Rooms	2nd Floor	337	SF	6	\$2,414	Rm 230 elec closet, Rm 238 Elev Mach Rm, water shut off
	Storage Room	2nd Floor	66	SF	6	\$473	
	Boiler Room	3rd Floor	1,891	SF	6	\$13,548	
	Janitor's Closet	3rd Floor	27	SF	6	\$193	
	Mechanical/ Service Rooms	3rd Floor	2,667	SF	6	\$19,107	
	Storage Room	3rd Floor	431	SF	6	\$3,088	Rm 338, 327 & Rm by RR
<b>Prep Room</b>							
	Ceiling - Lay-in	Rm 125A- Dishwashing Rm	157	SF	6	\$471	
	Doors - Wood Doors inclu hw	Rm 125A- Dishwashing Rm	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Rm 125A- Dishwashing Rm	157	SF	6	\$83	
	Lighting - Lay-in	Rm 125A- Dishwashing Rm	3	EA	7	\$0	
	Walls - Concrete Block	Rm 125A- Dishwashing Rm	545	SF	6	\$1,598	
	Work Sink	Rm 125A- Dishwashing Rm	1	EA	6	\$379	
<b>Restroom</b>							
	Accessories	1st Flr- In kitchen	42	SF	6	\$387	
	Ceiling - Lay-in	1st Flr- In kitchen	42	SF	6	\$126	
	Doors - Wood Doors inclu hw	1st Flr- In kitchen	1	EA	6	\$301	
	Floor Drain	1st Flr- In kitchen	1	EA	6	\$1,059	
	Floor - Concrete Epoxy/ Painted	1st Flr- In kitchen	42	SF	6	\$22	
	Lavatory	1st Flr- In kitchen	1	EA	6	\$320	
	Lighting - Lay-in	1st Flr- In kitchen	1	EA	7	\$0	
	Walls - Structural Glazed Tile	1st Flr- In kitchen	208	SF	6	\$654	
	Water Closet	1st Flr- In kitchen	1	EA	6	\$336	
	Accessories	2nd floor- Across from Library	210	SF	6	\$1,937	
	Accessories	2nd floor- Across from Library	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	2nd floor- Across from Library	210	SF	6	\$727	
	Ceiling - Plaster/Drywall	2nd floor- Across from Library	210	SF	6	\$727	

**Building: Addition**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor Drain	2nd floor- Across from Library	1	EA	6	\$1,059	
	Floor Drain	2nd floor- Across from Library	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd floor- Across from Library	210	SF	6	\$459	
	Floor - Terrazzo	2nd floor- Across from Library	210	SF	6	\$459	
	Lavatory	2nd floor- Across from Library	3	EA	6	\$959	
	Lavatory	2nd floor- Across from Library	3	EA	6	\$959	
	Lighting - Lay-in	2nd floor- Across from Library	5	EA	7	\$0	
	Lighting - Lay-in	2nd floor- Across from Library	5	EA	7	\$0	
	Partitions	2nd floor- Across from Library	3	EA	6	\$891	
	Partitions	2nd floor- Across from Library	2	EA	6	\$594	
	Urinals	2nd floor- Across from Library	2	EA	6	\$672	
	Walls - Concrete Block	2nd floor- Across from Library	592	SF	6	\$1,735	
	Walls - Structural Glazed Tile	2nd floor- Across from Library	600	SF	6	\$1,888	
	Water Closet	2nd floor- Across from Library	2	EA	6	\$672	
	Water Closet	2nd floor- Across from Library	4	EA	6	\$1,344	
	Accessories	2nd floor Unisex- Across from Library	45	SF	6	\$415	
	Ceiling - Plaster/Drywall	2nd floor Unisex- Across from Library	45	SF	6	\$156	
	Doors - Wood Doors inclu hw	2nd floor Unisex- Across from Library	1	EA	6	\$301	
	Floor Drain	2nd floor Unisex- Across from Library	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd floor Unisex- Across from Library	45	SF	6	\$98	
	Lavatory	2nd floor Unisex- Across from Library	1	EA	6	\$320	
	Lighting - Lay-in	2nd floor Unisex- Across from Library	1	EA	7	\$0	
	Walls - Concrete Block	2nd floor Unisex- Across from Library	210	SF	6	\$616	
	Water Closet	2nd floor Unisex- Across from Library	1	EA	6	\$336	
	Accessories	3rd floor- Across from 320	210	SF	6	\$1,937	
	Accessories	3rd floor- Across from 320	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	3rd floor- Across from 320	210	SF	6	\$727	
	Ceiling - Plaster/Drywall	3rd floor- Across from 320	210	SF	6	\$727	
	Floor Drain	3rd floor- Across from 320	1	EA	6	\$1,059	
	Floor Drain	3rd floor- Across from 320	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd floor- Across from 320	210	SF	6	\$459	
	Floor - Terrazzo	3rd floor- Across from 320	210	SF	6	\$459	
	Lavatory	3rd floor- Across from 320	3	EA	6	\$959	
	Lavatory	3rd floor- Across from 320	3	EA	6	\$959	
	Lighting - Lay-in	3rd floor- Across from 320	5	EA	7	\$0	
	Lighting - Lay-in	3rd floor- Across from 320	5	EA	7	\$0	
	Partitions	3rd floor- Across from 320	2	EA	6	\$594	

## Building: Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Partitions	3rd floor- Across from 320	3	EA	6	\$891	
	Urinals	3rd floor- Across from 320	2	EA	6	\$672	
	Walls - Concrete Block	3rd floor- Across from 320	592	SF	6	\$1,735	
	Walls - Structural Glazed Tile	3rd floor- Across from 320	600	SF	6	\$1,888	
	Water Closet	3rd floor- Across from 320	4	EA	6	\$1,344	
	Water Closet	3rd floor- Across from 320	2	EA	6	\$672	
	Accessories	3rd floor Unisex- Across from 320	45	SF	6	\$415	
	Ceiling - Plaster/Drywall	3rd floor Unisex- Across from 320	45	SF	6	\$156	
	Doors - Wood Doors inclu hw	3rd floor Unisex- Across from 320	1	EA	6	\$301	
	Floor Drain	3rd floor Unisex- Across from 320	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd floor Unisex- Across from 320	45	SF	6	\$98	
	Lavatory	3rd floor Unisex- Across from 320	1	EA	6	\$320	
	Lighting - Lay-in	3rd floor Unisex- Across from 320	1	EA	7	\$0	
	Walls - Concrete Block	3rd floor Unisex- Across from 320	210	SF	6	\$616	
	Water Closet	3rd floor Unisex- Across from 320	1	EA	6	\$336	
	Accessories	First floor- Across from Main Office	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	First floor- Across from Main Office	210	SF	6	\$727	
	Floor Drain	First floor- Across from Main Office	1	EA	6	\$1,059	
	Floor - Terrazzo	First floor- Across from Main Office	210	SF	6	\$459	
	Lavatory	First floor- Across from Main Office	3	EA	6	\$959	
	Lighting - Lay-in	First floor- Across from Main Office	5	EA	7	\$0	
	Partitions	First floor- Across from Main Office	2	EA	6	\$594	
	Urinals	First floor- Across from Main Office	2	EA	6	\$672	
	Walls - Concrete Block	First floor- Across from Main Office	592	SF	6	\$1,735	
	Water Closet	First floor- Across from Main Office	2	EA	6	\$672	
	Accessories	First floor- Across from Main	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	First floor- Across from Main	210	SF	6	\$727	
	Floor Drain	First floor- Across from Main	1	EA	6	\$1,059	
	Floor - Terrazzo	First floor- Across from Main	210	SF	6	\$459	
	Lavatory	First floor- Across from Main	3	EA	6	\$959	
	Lighting - Lay-in	First floor- Across from Main	5	EA	7	\$0	
	Partitions	First floor- Across from Main	3	EA	6	\$891	
	Walls - Structural Glazed Tile	First floor- Across from Main	592	SF	6	\$1,862	
	Walls - Structural Glazed Tile	First floor- Across from Main	8	SF	5	\$511	grout cracked
	Water Closet	First floor- Across from Main	4	EA	6	\$1,344	
	Accessories	First floor Unisex- Across from Main	45	SF	6	\$415	
	Ceiling - Plaster/Drywall	First floor Unisex- Across from Main	45	SF	6	\$156	

## Building: Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Doors - Wood Doors inclu hw	First floor Unisex- Across from Main	1	EA	6	\$301	
	Floor Drain	First floor Unisex- Across from Main	1	EA	6	\$1,059	
	Floor - Terrazzo	First floor Unisex- Across from Main	45	SF	6	\$98	
	Lavatory	First floor Unisex- Across from Main	1	EA	6	\$320	
	Lighting - Lay-in	First floor Unisex- Across from Main	1	EA	7	\$0	
	Walls - Concrete Block	First floor Unisex- Across from Main	210	SF	6	\$616	
	Water Closet	First floor Unisex- Across from Main	1	EA	6	\$336	
	Accessories	first floor, class 121	38	SF	6	\$350	
	Ceiling - Lay-in	first floor, class 121	38	SF	6	\$114	
	Doors - Wood Doors inclu hw	first floor, class 121	1	EA	6	\$301	
	Floor Drain	first floor, class 121	1	EA	6	\$1,059	
	Floor - Tile	first floor, class 121	38	SF	6	\$83	
	Lavatory	first floor, class 121	1	EA	6	\$320	
	Lighting - Lay-in	first floor, class 121	1	EA	7	\$0	
	Walls - Structural Glazed Tile	first floor, class 121	196	SF	6	\$617	
	Water Closet	first floor, class 121	1	EA	6	\$336	
	Accessories	first floor, class 122	38	SF	6	\$350	
	Ceiling - Lay-in	first floor, class 122	38	SF	6	\$114	
	Doors - Wood Doors inclu hw	first floor, class 122	1	EA	6	\$301	
	Floor Drain	first floor, class 122	1	EA	6	\$1,059	
	Floor - Tile	first floor, class 122	38	SF	6	\$83	
	Lavatory	first floor, class 122	1	EA	6	\$320	
	Lighting - Lay-in	first floor, class 122	1	EA	7	\$0	
	Walls - Structural Glazed Tile	first floor, class 122	196	SF	6	\$617	
	Water Closet	first floor, class 122	1	EA	6	\$336	
	Accessories	first floor, class 123	38	SF	6	\$350	
	Ceiling - Lay-in	first floor, class 123	38	SF	6	\$114	
	Doors - Wood Doors inclu hw	first floor, class 123	1	EA	6	\$301	
	Floor Drain	first floor, class 123	1	EA	6	\$1,059	
	Floor - Tile	first floor, class 123	38	SF	6	\$83	
	Lavatory	first floor, class 123	1	EA	6	\$320	
	Lighting - Lay-in	first floor, class 123	1	EA	7	\$0	
	Walls - Structural Glazed Tile	first floor, class 123	196	SF	6	\$617	
	Water Closet	first floor, class 123	1	EA	6	\$336	
	Accessories	first floor, class 126	38	SF	6	\$350	
	Ceiling - Lay-in	first floor, class 126	38	SF	6	\$114	
	Doors - Wood Doors inclu hw	first floor, class 126	1	EA	6	\$301	

**Building: Addition**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor Drain	first floor, class 126	1	EA	6	\$1,059	
	Floor - Tile	first floor, class 126	38	SF	6	\$83	
	Lavatory	first floor, class 126	1	EA	6	\$320	
	Lighting - Lay-in	first floor, class 126	1	EA	7	\$0	
	Walls - Structural Glazed Tile	first floor, class 126	196	SF	6	\$617	
	Water Closet	first floor, class 126	1	EA	6	\$336	
	Accessories	first floor, class 128	38	SF	6	\$350	
	Ceiling - Lay-in	first floor, class 128	38	SF	6	\$114	
	Doors - Wood Doors inclu hw	first floor, class 128	1	EA	6	\$301	
	Floor Drain	first floor, class 128	1	EA	6	\$1,059	
	Floor - Tile	first floor, class 128	38	SF	6	\$83	
	Lavatory	first floor, class 128	1	EA	6	\$320	
	Lighting - Lay-in	first floor, class 128	1	EA	7	\$0	
	Walls - Structural Glazed Tile	first floor, class 128	196	SF	6	\$617	
	Water Closet	first floor, class 128	1	EA	6	\$336	
	Accessories	Rm 120D, In main office	51	SF	6	\$470	
	Ceiling - Plaster/Drywall	Rm 120D, In main office	51	SF	6	\$176	
	Doors - Wood Doors inclu hw	Rm 120D, In main office	1	EA	6	\$301	
	Floor Drain	Rm 120D, In main office	1	EA	6	\$1,059	
	Floor - Tile	Rm 120D, In main office	51	SF	6	\$112	
	Lavatory	Rm 120D, In main office	1	EA	6	\$320	
	Lighting - Lay-in	Rm 120D, In main office	1	EA	7	\$0	
	Walls - Concrete Block	Rm 120D, In main office	284	SF	6	\$833	
	Water Closet	Rm 120D, In main office	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal:**

**\$282,652**

**Building: Addition**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	4,062	SF	6	\$12,198	
	Ceiling - Lay-in	1st Floor	6	SF	5	\$54	water damaged
	Doors - Steel Doors incl hw	1st Floor	11	EA	6	\$3,311	
	Doors - Wood Doors include hw	1st Floor	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	1st Floor	2	EA	6	\$672	
	Floor - Terrazzo	1st Floor	4,068	SF	6	\$34,147	

## Building: Addition

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Lighting - Lay-in	1st Floor	142	EA	7	\$0	92 are cove & 24 are cans
	Stairs - Concrete Stairs	1st Floor	23	LF	6	\$191	Stairs that go from Multi-Purpose Rm hall, up to Boiler Rm
	Walls - Concrete Block	1st Floor	4,434	SF	6	\$12,998	
	Walls - Masonry	1st Floor	1,304	SF	6	\$4,102	
	Walls - Structural Glazed Tile	1st Floor	1,000	SF	6	\$3,146	
	Ceiling - Lay-in	2nd Floor	3,606	SF	6	\$10,829	
	Ceiling - Lay-in	2nd Floor	10	SF	5	\$89	water damaged
	Ceiling - Plaster/Drywall	2nd Floor	143	SF	6	\$885	
	Doors - Steel Doors incl hw	2nd Floor	4	EA	6	\$1,204	
	Doors - Wood Doors include hw	2nd Floor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	2nd Floor	2	EA	6	\$672	
	Floor - Terrazzo	2nd Floor	4,714	SF	6	\$39,570	
	Lighting - Lay-in	2nd Floor	116	EA	7	\$0	92 are cove at edges
	Walls - Concrete Block	2nd Floor	5,207	SF	6	\$15,264	
	Ceiling - Lay-in	3rd Floor	3,616	SF	6	\$10,859	
	Ceiling - Plaster/Drywall	3rd Floor	143	SF	6	\$885	
	Doors - Steel Doors incl hw	3rd Floor	4	EA	6	\$1,204	
	Doors - Wood Doors include hw	3rd Floor	6	EA	6	\$1,806	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	6	\$551	
	Floor - Terrazzo	3rd Floor	3,616	SF	6	\$30,353	
	Lighting - Lay-in	3rd Floor	116	EA	7	\$0	92 are cove lights at edges
	Walls - Concrete Block	3rd Floor	5,207	SF	6	\$15,264	
<b>Safety</b>							
	Camera Viewing Station	1st Floor	1	EA	6	\$683	Main Office
	Security Cameras	1st Floor / Entire Building	1	EA	5	\$688	southwest corridor- doesn't work
	Security Cameras	1st Floor / Entire Building	5	EA	6	\$970	
<b>Stairs</b>							
	Ceiling - Lay-in	By Door # 6 (SE)	315	SF	6	\$946	
	Floor - Terrazzo	By Door # 6 (SE)	334	SF	7	\$0	
	Handrails	By Door # 6 (SE)	108	LF	6	\$936	
	Lighting - Lay-in	By Door # 6 (SE)	6	EA	7	\$0	
	Lighting - Pendent/Surface	By Door # 6 (SE)	1	EA	7	\$0	
	Stairs - Terrazzo	By Door # 6 (SE)	54	LF	6	\$501	
	Walls - Concrete Block	By Door # 6 (SE)	3,402	SF	6	\$9,973	
	Ceiling - Lay-in	By Door #1 (NE)	315	SF	6	\$946	
	Floor - Terrazzo	By Door #1 (NE)	334	SF	7	\$0	

**Building: Addition**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Handrails	By Door #1 (NE)	108	LF	6	\$936	
	Lighting - Lay-in	By Door #1 (NE)	6	EA	7	\$0	
	Lighting - Pendent/Surface	By Door #1 (NE)	1	EA	7	\$0	
	Stairs - Terrazzo	By Door #1 (NE)	54	LF	6	\$501	
	Walls - Concrete Block	By Door #1 (NE)	3,402	SF	6	\$9,973	
	Ceiling - Lay-in	By Door #5 (SW)	315	SF	6	\$946	
	Floor - Terrazzo	By Door #5 (SW)	334	SF	7	\$0	
	Handrails	By Door #5 (SW)	108	LF	6	\$936	
	Lighting - Lay-in	By Door #5 (SW)	6	EA	7	\$0	
	Lighting - Pendent/Surface	By Door #5 (SW)	1	EA	7	\$0	
	Stairs - Terrazzo	By Door #5 (SW)	54	LF	6	\$501	
	Walls - Concrete Block	By Door #5 (SW)	3,402	SF	6	\$9,973	

**Vertical Conveyance**

	Elevator - Hydraulic Elevator	1st Floor	1	EA	6	\$19,238	
--	-------------------------------	-----------	---	----	---	----------	--

**Building Interior Subtotal:**

**\$261,912**

**Total Building Cost**

**\$2,209,603**

**Building: Field House**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior FRP Door	#1 E	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#2 E	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#3 W	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#4 W	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#5 W	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#6 E	1	EA	6	\$631	
	Exterior Stairs - Concrete	#1 E	8	LF	6	\$654	
	Exterior Stairs - Concrete	#3 W	3	LF	6	\$245	
	Exterior Stairs - Concrete	#3 W	5	LF	6	\$409	
	Exterior Stairs - Concrete	#4 W	8	LF	6	\$654	
	Exterior Stairs - Concrete	#5 W	8	LF	6	\$654	
	Exterior Stairs - Concrete	#6 E	8	LF	6	\$654	
	Ramp Handrail - Steel_Ramp Handrail	#2 E	86	LF	6	\$745	

**Building: Field House**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Ramps - Concrete	#2 E	45	LF	6	\$6,761	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	1,857	LF	7	\$0	
<b>Roof System</b>							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Entire Building	3	LF	6	\$2,864	
	Downspouts - Exterior Downspouts	Entire Building	80	LF	4	\$10,837	Cracked Drain Piping/ deteriorated Metal Gutters
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	1,857	SF	7	\$0	
	Roof - Metal	Entire Building	1,857	SF	6	\$24,882	
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	18,570	SF	6	\$124,809	Open Joints
	Exterior Walls - Stone-Cut	Entire Building	828	SF	6	\$5,565	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building	336	SF	6	\$4,291	
	Lintels - Brick	Entire Building	122	LF	5	\$40,747	Open Joints
	Lintels - Stone	Entire Building	4	LF	6	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	336	SF	6	\$2,508	

**Building Exterior Subtotal: \$231,068**

**Building: Field House**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Main Service</b>							
	Main Electrical Service - 800 A and 120/208/3PH	1st Floor	1	EA	6	\$3,570	service provided by ComEd, mounted at exterior wall
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	1st Floor	1	EA	6	\$299	

**Electrical System Subtotal: \$3,869**

**Building: Field House**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Field House**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm_System	Entire Building	1,825	SF	6	\$887	smoke detector alarm only, in the field house

**Safty System Subtotal: \$887**

**Building: Field House**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Heating Devices</b>							
	Gas/ Natural Draft Furnace - 101 - 200 MBH	1st Floor / 2nd Floor	1	EA	5	\$6,105	residential style furnace
<b>Temperature Control</b>							
	Electric Thermostat	1st Floor	1	EA	6	\$0	
<b>Ventilation</b>							
	Exhaust Fans- Indoor - Less than 500 CFM	Entire Building / 1st Floor	2	EA	6	\$592	bathroom fans
	Roof Mounted Duct Work	Entire Building / 1st Floor	90	LF	6	\$34,112	ducts in attic for furnace air distribution

**Mechanical System Subtotal: \$40,810**

**Building: Field House**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - Less than 150000 BTU/HR	1st Floor	1	EA	5	\$2,249	
<b>Piping</b>							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building / 1st Floor	1,825	SF	6	\$444	1 story small fieldhouse.
	Domestic Piping-Hot Water Horizontal Lines	Entire Building / 1st Floor	1,825	SF	6	\$339	
	Domestic Piping-Hot Water Return Lines	Entire Building / 1st Floor	1,825	SF	6	\$261	
	Sanitary Piping	Entire Building	1,825	SF	6	\$1,670	
	Storm Piping	Entire Building	1,825	SF	6	\$1,592	
	Vent Piping	Entire Building	1,825	SF	6	\$1,227	

**Plumbing System Subtotal: \$7,782**

**Building: Field House**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #North (Play Room)</b>							
	Casework	1st Floor	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	1st Floor	450	SF	6	\$1,557	Wood panel
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	1st Floor	450	SF	5	\$772	
	Lighting - Pendent/Surface	1st Floor	6	EA	7	\$0	
	Walls - Structural Glazed Tile	1st Floor	798	SF	6	\$2,511	
<b>Classroom #South (Play Room)</b>							
	Casework	1st Floor	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	1st Floor	450	SF	6	\$1,557	Wood paneling
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	1st Floor	450	SF	5	\$772	
	Lighting - Pendent/Surface	1st Floor	6	EA	7	\$0	
	Walls - Structural Glazed Tile	1st Floor	798	SF	6	\$2,511	
<b>Classrooms Subtotal:</b>						<b>\$12,302</b>	

## Building: Field House

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Mechanical/ Service Rooms</b>							
	Mechanical/ Service Rooms	1st Floor	95	SF	6	\$681	
<b>Restroom</b>							
	Accessories	In North classroom	45	SF	6	\$415	
	Ceiling - Plaster/Drywall	In North classroom	45	SF	6	\$156	Wood panel
	Doors - Wood Doors inclu hw	In North classroom	1	EA	6	\$301	
	Floor Drain	In North classroom	1	EA	6	\$1,059	
	Floor - Epoxy/ Painted	In North classroom	45	SF	6	\$24	
	Lavatory	In North classroom	1	EA	5	\$1,590	Cracked
	Lighting - Pendent/Surface	In North classroom	1	EA	7	\$0	
	Partitions	In North classroom	1	EA	6	\$297	
	Walls - Structural Glazed Tile	In North classroom	238	SF	6	\$749	
	Water Closet	In North classroom	1	EA	6	\$336	
	Accessories	In South classroom	45	SF	6	\$415	
	Ceiling - Plaster/Drywall	In South classroom	45	SF	6	\$156	Wood panel
	Doors - Wood Doors inclu hw	In South classroom	1	EA	6	\$301	
	Floor Drain	In South classroom	1	EA	6	\$1,059	
	Floor - Epoxy/ Painted	In South classroom	45	SF	5	\$77	
	Lavatory	In South classroom	1	EA	5	\$1,590	Cracked

**Building: Field House**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Pendent/Surface	In South classroom	1	EA	7	\$0	
	Partitions	In South classroom	1	EA	5	\$751	Rusted
	Urinals	In South classroom	2	EA	6	\$672	
	Walls - Structural Glazed Tile	In South classroom	238	SF	6	\$749	
	Water Closet	In South classroom	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal: \$11,712**

**Building: Field House**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Plaster/Drywall	1st Floor	299	SF	6	\$1,851	
	Doors - Wood Doors include hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	1st Floor	299	SF	6	\$145	
	Lighting - Pendent/Surface	1st Floor	4	EA	7	\$0	
	Walls - Structural Glazed Tile	1st Floor	657	SF	6	\$2,067	

**Building Interior Subtotal: \$4,365**

**Total Building Cost \$312,795**

**SITE**

**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Athletic</b>							
	Surface - Asphalt	Central Courtyard	13,613	SF	6	\$32,899	
	Surface - Synthetic including exc & retention	Courtyard Football/Soccer	16,174	SF	7	\$0	
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site	11	EA	6	\$12,032	
	Civil/ Drainage - Site Manhole	Entire Site	10	EA	6	\$14,927	
<b>Fencing</b>							
	Fencing - New Standard Ornamental	Entire Site	1,442	LF	6	\$46,005	

## SITE

### Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Landscape</b>							
	Benches	Entire Site	19	EA	6	\$8,171	
	Irrigation	Entire Site / Playground	29,835	SF	5	\$80,208	Multiple Leaks
	Landscape - Grass	Entire Site	34,607	SF	6	\$28,703	
	Landscape - Hardscape- Concrete	Entire Site	15,479	SF	6	\$79,907	
	Landscape - Hardscape- Concrete	Entire Site	1,879	SF	5	\$20,609	Cracks adjacent to Pre K
	Landscape - Hardscape- Pavers	Entire Site	314	SF	6	\$1,778	
	Parkway trees	Entire Site	32	EA	6	\$21,121	
	Planting Beds/ Area	Entire Site	6,425	SF	6	\$10,566	
	Trash Receptacles	Entire Site	8	EA	6	\$2,498	
<b>Parking Lot</b>							
	Concrete Curbs	East	388	LF	6	\$4,982	
	Lighting - Pole Mounted	East	21	EA	6	\$30,502	
	Surface - Asphalt	East	15,489	SF	6	\$37,432	
	Surface - Concrete	East	1,661	SF	6	\$4,014	
	Trash Compactor	East	1	EA	6	\$0	
	Vehicular Screening	East	304	LF	6	\$23,936	
<b>Playground</b>							
	Equipment - School Age 5-12	Entire Site	3	EA	6	\$10,637	
	Equipment - Swingset	Entire Site	1	EA	6	\$1,182	
	Surface - Poured Surface	Entire Site	6,239	SF	6	\$45,679	
<b>Sidewalks</b>							
	Sidewalks - Internal Walks	Entire Site	594	LF	6	\$7,135	
	Sidewalks - Internal Walks	Entire Site	100	LF	5	\$4,984	Damaged
	Sidewalks - Perimeter Sidewalks	Entire Site	12,342	SF	6	\$24,532	
	Sidewalks - Perimeter Sidewalks	Entire Site	1,000	SF	5	\$9,552	Damaged
<b>Signage</b>							
	Flag Pole - Flag Pole	Entire Site	1	EA	6	\$1,657	
	Marquee - Free Standing Back Lighted	Entire Site	1	EA	6	\$0	
	Monument - Sign	Entire Site	1	EA	6	\$0	

**Site Subtotal: \$565,651**

**Total Site Cost \$565,651**

**Campus Total** <sup>2 3</sup>**\$6,021,569**

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Dance Room	Regular Classroom	2nd Floor	205	205	866	0	2	12	76	40	40	Y	N	N
Kindergarten	Kindergarten	1st Floor	110	Kindergarten	1,300	0	2	20	420	225	40	Y	N	N
Kindergarten	Regular Classroom	2nd Floor	206B	206	554	2	6	30	82	44	40	Y	N	Y
Regular Classroom	Regular Classroom	1st Floor	101	101	888	0	2	12	224	120	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	102	102	938	0	2	12	168	90	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	103	103	938	0	2	12	168	90	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	104	104	934	0	2	12	168	90	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	105	105	910	0	2	12	168	90	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	200	NA	415	0	10	20	84	45	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	201	201	888	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	202	202	903	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	203	203	909	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	204	204	908	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	207	207	927	0	2	15	134	70	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	881	0	2	16	114	59	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	209	209	938	0	2	12	168	90	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	210	210	879	0	2	12	168	90	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	300	NA	415	0	2	6	84	45	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	301	301	888	0	2	12	224	120	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	302	302	938	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	304	304	938	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	305	305	888	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Library	3rd Floor	306B	306	602	0	2	12	168	90	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	307	938	0	2	12	168	90	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	308	308	938	0	2	12	168	90	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	309	309	938	0	2	12	168	90	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	310	310	888	0	2	12	224	120	40	Y	Y	Y
Science	Regular Classroom	3rd Floor	303	303	909	0	2	12	168	90	40	Y	N	Y
Special Program	Faculty Lounge	1st Floor	109	NA - Teacher Rm	333	1	2	4			40	Y	N	N

## Addition

Art Room	Art Room	3rd Floor	328	3-11	1,053	1	8	24	98	42	40	Y	N	Y
Computer Lab	Computer Lab	2nd Floor	229	2-13	1,019	2	40	92	89	45	40	Y	Y	N
Kindergarten	Kindergarten	1st Floor	126	1-21	1,098	1	1	12	164	56	40	Y	N	N
Kindergarten	Kindergarten	1st Floor	128	1-25	1,098	1	1	12	164	56	40	N	N	N
Music Room	Regular Classroom	3rd Floor	331	3-16	848	1	8	22	98	42	40	Y	N	N
Pre School	Kindergarten	1st Floor	121	1-11	1,073	1	1	12	164	56	40	Y	N	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Addition</b>														
Pre School	Kindergarten	1st Floor	122	1-14	1,073	1	1	12	164	56	40	Y	N	N
Pre School	Kindergarten	1st Floor	123	1-17	1,098	1	1	12	164	56	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	223	2-07	852	1	9	18	89	45	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	224	2-08	852	1	9	16	89	45	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	225	2-09	852	1	9	18	113	57	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	228	2-12	852	1	9	18	89	45	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	231	2-17	852	1	9	18	89	45	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	320	3-02	900	1	8	22	155	28	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	321	3-03	900	1	8	22	98	42	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	322	3-04	900	1	8	24	155	28	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	323	3-05	900	1	8	22	155	28	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	324	3-06	900	1	8	22	98	42	40	Y	N	Y
Regular Classroom	Regular Classroom	3rd Floor	325	3-07	900	1	8	22	155	28	40	Y	N	Y
Science Lab Level 1	Regular Classroom	3rd Floor	329	3-12	1,044	1	13	36	98	42	40	Y	Y	Y

## Field House

Play Room	Play Room	1st Floor	North	NA	450	0	0	6	165	83	40	N	N	N
Play Room	Play Room	1st Floor	South	NA	450	0	0	6	165	83	40	N	N	N