

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1972	2	150,700	\$7,065,750
SITE				\$238,827
Campus Total			150,700	\$7,304,577

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Main Entrance	1	EA	7	\$0	
	Exterior Doors - Exterior AMP Door	East Façade	1	EA	6	\$674	
	Exterior Doors - Exterior FRP Door	East Façade / East Entrances	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	South Entrances / South	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	South Façade / South Entrances	1	EA	7	\$0	
	Exterior Doors - Exterior FRP Door	South Façade / South Entrances	1	EA	7	\$0	
	Exterior Doors - Exterior FRP Door	South Façade / South Entrances	1	EA	7	\$0	
	Exterior Doors - Exterior FRP Door	West Façade / West Entrances	2	EA	7	\$0	
	Exterior Doors - Exterior FRP Door	West Façade / West Entrances	1	EA	6	\$631	
	Exterior Doors - Overhead Rolling/ Garage Door	East Façade / East Entrances	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	East Façade	1	EA	6	\$1,433	
	Exterior Doors - Side lite	South Façade / South Entrances	1	EA	7	\$0	
	Exterior Doors - Store Front	East Façade / East Entrances	1	EA	6	\$546	
	Exterior Doors - Store Front	East Façade / East Entrances	1	EA	6	\$546	
	Exterior Doors - Store Front	Main Entrance	4	EA	6	\$2,184	
	Exterior Doors - Store Front	North Façade / North Entrances	4	EA	6	\$2,184	
	Exterior Doors - Store Front	South Façade / South Entrances	2	EA	6	\$1,092	
	Exterior Doors - Store Front	South Façade / South Entrances	2	EA	6	\$1,092	
	Exterior Doors - Store Front	West Façade / West Entrances	1	EA	6	\$546	
	Exterior Doors - Store Front	West Façade / West Entrances	1	EA	6	\$546	
	Exterior Doors - Transom Lite	East Façade	1	EA	4	\$2,007	Plywood, deteriorating

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Stairs - Concrete	South Façade / South Entrances	5	LF	6	\$409	
	Exterior Stairs - Concrete	South Façade / South Entrances	5	LF	6	\$409	
Foundation							
	Foundation - Concrete	Entire Building / Basement	70	LF	7	\$0	
	Foundation - Concrete	Entire Building	1,330	LF	7	\$0	
	Superstructure - Metal Deck/ Concrete Topping	Entire Building	150,700	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	34	EA	7	\$0	
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	1	EA	6	\$537	
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	10	EA	7	\$0	
Roof System							
	Chimney - Metal Flue	Entire Building	31	LF	6	\$4,902	
	Coping - Metal	Entire Building	2,500	LF	5	\$105,677	
	Downspouts - Interior Downspouts	Entire Building	10	LF	2	\$4,672	
	Downspouts - Interior Downspouts	Entire Building	890	LF	6	\$29,578	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	71,800	SF	7	\$0	
	Roof - Metal	Entire Building	1,100	SF	5	\$30,312	
	Roof - Modified Bitumen	Entire Building	69,300	SF	6	\$652,071	
Walls							
	Canopy - Metal	Entire Building / North Entrances	840	SF	7	\$0	
	Exterior Walls - Brick	Entire Building	19,300	SF	6	\$129,715	
	Exterior Walls - Brick	Entire Building / South Façade	1,675	SF	4	\$275,789	Significant bulging
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building / Main Roof	1,585	SF	5	\$12,239	
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building / Main Roof	2,565	SF	6	\$14,562	
Windows							
	Curtain wall - Glazed Double Pane	Entire Building	21,300	SF	6	\$238,799	
	Curtain wall - Insulated Panel	Entire Building	150	SF	5	\$5,618	
	Curtain wall - Insulated Panel	Entire Building / Entire Site	18,420	SF	6	\$206,510	
	Curtain wall - Windows	Entire Building	1,080	SF	5	\$68,788	
	Lintels - Steel	Entire Building	45	LF	7	\$0	
	Skylite - Lexan	Entire Building / Main Roof	1,400	SF	3	\$377,717	Lexan, leaks at ceiling below.
Building Exterior Subtotal:						\$2,175,114	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Basement / Electrical Room	2	EA	7	\$0	Fire alarm room and pump room
	Emergency Generator- Outdoor- Diesel - 60 - 100 KW	Site South	1	EA	6	\$9,865	
	Exit Signs - Auditorium	Entire Building / 1st Floor	4	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	36	EA	7	\$0	
	Exit Signs - Gym	Entire Building / 2nd Floor	4	EA	7	\$0	
	Exit Signs - Pool	Entire Building	2	EA	7	\$0	
	Security System - CCTV	Entire Building	150,700	SF	7	\$0	
	Security System - Intrusion Detection	Entire Building	150,700	SF	7	\$0	
Main Service							
	Independent Electrical Service for emergency power	Basement / Electrical Room	1	EA	7	\$0	
	Main Electrical Service - 2000 A 277/480/3PH	Entire Building / Basement	1	EA	7	\$0	
	Main Electrical Service - 2000 A 277/480/3PH	Entire Building / Penthouse	2	EA	7	\$0	
	PA System	Entire Building	150,700	SF	7	\$0	
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / 2nd Floor	2	EA	2	\$9,699	
	Lighting and Power Panels - 100 A	Entire Building	3	EA	6	\$897	
	Lighting and Power Panels - 100 A	Entire Building	28	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Basement	2	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Penthouse	4	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Entire Building / Basement	1	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Entire Building / Basement	1	EA	7	\$0	
	Transformers - 277/480 - 120/208	Entire Building	12	EA	7	\$0	
Electrical System Subtotal:						\$20,462	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Basement	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Basement / Entire Building	150,700	SF	7	\$0	
	Fire Alarm_System	Basement / Entire Building	150,700	SF	6	\$73,270	
	Fire Pump Controller	Basement	1	EA	5	\$8,100	
Pump Room Assembly							
	Fire Pump - 25-50 hp	Basement	1	EA	5	\$8,163	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pump Room Assembly							
	Jockey Pump	Basement	1	EA	5	\$2,958	
Sprinkler System							
	Sprinkler Heads	Entire Building	150,700	SF	6	\$0	
	Sprinkler Piping	Entire Building	150,700	SF	5	\$105,595	
	Wet Sprinkler System	Entire Building	150,700	SF	5	\$53,875	
Safty System Subtotal:						\$258,368	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	6	EA	7	\$0	Carrier units; Mod#:0613E07744
	Heat Pump- Ceiling Mounted- Electric Heating & DX Cooling- Remote Mounted Compressor - Less than 3 tons	MDF Room	1	EA	7	\$0	
Air Handling Systems							
	Make Up Air Unit- Roof Mounted- Electric Coils - Less than 6000 cfm	Roof	1	EA	5	\$19,234	6000 CFM; 128 KW; No other information available
	Roof Top Unit-Multi Zone-Roof Mounted- Electric and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	17	EA	5	\$544,685	
	Roof Top Unit-Single Zone-Roof Mounted- Electric and DX Cooling with Self Contained Compressor - 11 - 20 tons	Roof	1	EA	5	\$17,658	
	Roof Top Unit-Single Zone-Roof Mounted- Electric and DX Cooling with Self Contained Compressor - 31 - 45 tons	Roof	1	EA	4	\$125,457	Unit is operable, but in poor condition. Sheet metal housing is deteriorating
	Zone Dampers	Roof	116	EA	5	\$221,971	
Heating Devices							
	Cabinet Heaters - With Electric Coil	1st Floor	7	EA	5	\$11,101	
	Fin Tube - Electric	Entire Building / 2nd Floor	60	LF	4	\$6,546	The fin tube is damaged and in poor condition
	Fin Tube - Electric	Entire Building	60	LF	5	\$3,062	
	Fin Tube - Electric	Entire Building	2,176	LF	6	\$20,537	
Mechanical Plumbing							
	Hot Water Pump - Less than 10	Basement	1	EA	5	\$11,495	
	Hot Water Pump - Less than 10	Basement	2	EA	7	\$0	
Temperature Control							
	DDC System	Entire Building	150,700	SF	5	\$247,826	
	Thermostats - DDC	Entire Building	119	EA	6	\$0	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Ventilation							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building	1	EA	7	\$0	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	4	\$6,392	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	7	\$0	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	4	\$6,392	Exhaust fan is more than 15 years of age and is working however fan is rusted
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	3	EA	7	\$0	
	Lab Exhaust Hood	Entire Building / 2nd Floor	1	EA	6	\$1,248	
	Type I Exhaust Hood- Culinary Arts	Entire Building / 1st Floor	2	EA	2	\$52,348	Hood does not have sufficient length
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	6	\$920	

Mechanical System Subtotal: \$1,297,462

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Gas Heater - 150000 - 300000 BTU/HR	Basement	1	EA	6	\$310	
	Gas Heater - Greater than 600000 BTU/HR	Basement	1	EA	4	\$43,134	Heater greater than 15 years of age and shows signs of corrosion
	Hot Water Storage Tank_Gas - Greater than 1000 Gallons	Basement	1	EA	4	\$43,497	Storage tank shows signs of significant corrosion
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	150,700	SF	6	\$30,170	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	150,700	SF	6	\$36,635	
	Domestic Piping-Cold Water Risers	Entire Building	150,700	SF	6	\$28,015	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	150,700	SF	4	\$81,890	Pipes are rusted through and have clamps installed
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	150,700	SF	4	\$193,951	Pipes are rusted through and have clamps installed
	Domestic Piping-Hot Water Return Lines	Entire Building	150,700	SF	4	\$129,301	Pipes are rusted through and have clamps installed
	Domestic Piping-Hot Water Return Risers	Entire Building	150,700	SF	4	\$73,270	Pipes are rusted through and have clamps installed
	Sanitary Piping	Entire Building	150,700	SF	6	\$137,921	
	Storm Piping	Entire Building	150,700	SF	6	\$131,456	
	Vent Piping	Entire Building	150,700	SF	6	\$101,285	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pool Systems							
	Pool Drain Piping	Basement	300	LF	4	\$30,386	Drain piping is in poor condition. Piping is leaking and many pipe clamps are installed
	Pool Filtration System including Pump	Basement	1	EA	5	\$19,025	
	Pool Hot Water Heater - Gas Fired	Basement	1	EA	4	\$44,609	Pool heater is more than 15 years of age and in poor condition
	Pool Supply and Return Piping	Basement	100	LF	4	\$16,604	Piping is in poor condition. Piping is leaking and many pipe clamps are installed
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Basement / Mechanical Room	1	EA	6	\$1,977	
	Pumps - Ejector-Duplex	Basement / Mechanical Room	1	EA	5	\$7,535	
	Pumps - Sump-Duplex	Basement / Mechanical Room	1	EA	5	\$7,535	
	Pumps - Sump-Simplex	Basement / Mechanical Room	1	EA	2	\$11,443	

Plumbing System Subtotal: \$1,169,949

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #109 (Special Program)							
	Ceiling - Lay-in	1st Floor	1,830	SF	7	\$0	
	Doors - Transom Window	1st Floor	9	SF	7	\$0	Glass
	Doors - Transom Window	1st Floor	9	SF	6	\$152	Wood
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,830	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	82	EA	6	\$10,159	T8
	Marker Board	1st Floor	8	LF	6	\$171	
	Walls - Concrete Block	1st Floor	1,950	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	183	SF	6	\$505	
Classroom #110 (Other Instructional Use)							
	Ceiling - Lay-in	1st Floor	775	SF	6	\$2,327	
	Doors - Side-lite	1st Floor	11	SF	5	\$770	missing snap on piece at jamb
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	3	EA	6	\$903	
	Floor - Carpet	1st Floor	775	SF	4	\$7,126	worn and torn carpet. no wall base.
	Lighting - Pendent/Surface	1st Floor	31	EA	6	\$3,841	
	Marker Board	1st Floor	19	LF	6	\$407	
	Walls - Concrete Block	1st Floor	946	SF	6	\$2,773	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #110 (Other Instructional Use)							
	Walls - Metal Panel	1st Floor	146	SF	5	\$4,466	metal panels have large holes and dents.
Classroom #117E (Computer Lab)							
	Ceiling - Lay-in	1st Floor	288	SF	6	\$865	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	288	SF	4	\$2,648	worn + torn. needs to be replaced.
	Lighting - Pendent/Surface	1st Floor	12	EA	6	\$1,487	
	Walls - Concrete Block	1st Floor	342	SF	6	\$1,003	
	Walls - Metal Panel	1st Floor	175	SF	6	\$1,306	60 sf is glazed metal panel wall system.
	Walls - Plaster/Drywall	1st Floor	148	SF	6	\$408	
	Wireless System	1st Floor	1	EA	7	\$0	WAP mounted to the wall.
Classroom #121 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	840	SF	6	\$2,523	
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	840	SF	6	\$1,790	
	Lighting - Pendent/Surface	1st Floor	29	EA	6	\$3,593	T8
	Marker Board	1st Floor	15	LF	6	\$321	
	Walls - Concrete Block	1st Floor	218	SF	6	\$639	
	Walls - Metal Panel	1st Floor	673	SF	6	\$5,024	
Classroom #122 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	977	SF	6	\$2,934	Plaster water damage 5 sf. (at window)
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	Hardware missing closer
	Floor - Carpet	1st Floor	977	SF	6	\$2,082	
	Lighting - Pendent/Surface	1st Floor	31	EA	7	\$0	T8
	Marker Board	1st Floor	15	LF	6	\$321	
	Walls - Concrete Block	1st Floor	218	SF	7	\$0	
	Walls - Metal Panel	1st Floor	740	SF	7	\$0	
Classroom #123 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Chalk Board	1st Floor	12	LF	4	\$1,102	obsolete material
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	795	SF	6	\$1,694	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #123 (Regular Classroom)							
	Lighting - Pendent/Surface	1st Floor	29	EA	6	\$3,593	
	Marker Board	1st Floor	15	LF	6	\$321	
	Walls - Metal Panel	1st Floor	908	SF	6	\$6,778	
Classroom #124 (Special Program)							
	Casework	1st Floor	13	LF	7	\$0	
	Ceiling - Lay-in	1st Floor	650	SF	6	\$1,952	
	Chalk Board	1st Floor	6	LF	4	\$551	obsolete material
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	650	SF	6	\$1,385	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	T8
	Walls - Metal Panel	1st Floor	867	SF	6	\$6,472	
	Work Sink	1st Floor	1	EA	6	\$379	Brown residue on bottom of sink
Classroom #130 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	830	SF	7	\$0	
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	830	SF	6	\$1,768	
	Lighting - Pendent/Surface	1st Floor	29	EA	7	\$0	T8
	Marker Board	1st Floor	15	LF	6	\$321	
	Walls - Concrete Block	1st Floor	470	SF	7	\$0	
	Walls - Metal Panel	1st Floor	467	SF	7	\$0	
Classroom #131 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	786	SF	5	\$4,676	Plaster water damage 10 s.f. (NE corner)
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	786	SF	6	\$1,675	
	Lighting - Pendent/Surface	1st Floor	29	EA	7	\$0	T8
	Marker Board	1st Floor	10	LF	5	\$507	Damaged
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Metal Panel	1st Floor	933	SF	6	\$6,964	
Classroom #132 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	Door Mullion Missing snap in piece

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #132 (Regular Classroom)							
	Floor - Carpet	1st Floor	795	SF	6	\$1,694	
	Lighting - Pendent/Surface	1st Floor	29	EA	6	\$3,593	T8
	Marker Board	1st Floor	15	LF	6	\$321	
	Walls - Metal Panel	1st Floor	910	SF	6	\$6,793	
Classroom #133 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	834	SF	6	\$2,505	
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	834	SF	6	\$1,777	
	Lighting - Pendent/Surface	1st Floor	28	EA	6	\$3,469	T8
	Marker Board	1st Floor	15	LF	7	\$0	
	Walls - Concrete Block	1st Floor	218	SF	6	\$639	
	Walls - Metal Panel	1st Floor	668	SF	6	\$4,986	
Classroom #134 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	839	SF	6	\$2,520	10 sf plaster water damage @ SW corner
	Doors - Side-lite	1st Floor	11	SF	6	\$184	
	Doors - Transom Window	1st Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	839	SF	6	\$1,788	
	Lighting - Pendent/Surface	1st Floor	29	EA	6	\$3,593	T8
	Marker Board	1st Floor	15	LF	6	\$321	
	Walls - Concrete Block	1st Floor	218	SF	6	\$639	
	Walls - Metal Panel	1st Floor	669	SF	6	\$4,994	
Classroom #141 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	811	SF	6	\$2,435	
	Ceiling - Plaster/Drywall	1st Floor	22	SF	5	\$202	
	Doors - Side-lite	1st Floor	11	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	833	SF	6	\$1,775	
	Lighting - Pendent/Surface	1st Floor	29	EA	6	\$3,593	
	Marker Board	1st Floor	16	LF	7	\$0	
	Walls - Concrete Block	1st Floor	220	SF	6	\$645	
	Walls - Metal Panel	1st Floor	227	SF	6	\$1,694	
	Walls - Plaster/Drywall	1st Floor	230	SF	6	\$635	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #142 (Science Lab Level 3)							
	Casework	1st Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	1st Floor	977	SF	7	\$0	
	Doors - Side-lite	1st Floor	11	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Eye Wash Station	1st Floor	1	EA	5	\$844	
	Floor - Tile/Sheet	1st Floor	977	SF	7	\$0	
	Gas Line	1st Floor	2	EA	5	\$7,163	
	Lighting - Pendent/Surface	1st Floor	33	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	230	SF	7	\$0	
	Walls - Metal Panel	1st Floor	320	SF	7	\$0	curtainwall
	Walls - Metal Panel	1st Floor	490	SF	7	\$0	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #143 (Regular Classroom)							
	Ceiling - Lay-in		799	SF	7	\$0	
	Chalk Board		7	LF	4	\$643	obsolete material
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		799	SF	6	\$1,702	
	Lighting - Lay-in		29	EA	6	\$3,450	1 lamp out
	Marker Board		10	LF	7	\$0	
	Walls - Metal Panel		793	SF	6	\$5,919	
Classroom #144 (Regular Classroom)							
	Casework		10	LF	5	\$2,091	
	Ceiling - Lay-in		674	SF	7	\$0	
	Chalk Board		8	LF	4	\$734	obsolete material
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		674	SF	5	\$3,460	
	Lighting - Wall Mounted		24	EA	7	\$0	
	Marker Board		8	LF	7	\$0	
	Walls - Metal Panel		731	SF	6	\$5,457	
	Work Sink		1	EA	6	\$379	
Classroom #147 (Regular Classroom)							
	Casework		9	LF	6	\$227	
	Ceiling - Lay-in		800	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		800	SF	6	\$1,705	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #147 (Regular Classroom)							
	Lighting - Pendent/Surface		28	EA	7	\$0	
	Walls - Concrete Block		350	SF	4	\$12,548	Mortar is failing
	Walls - Metal Panel		547	SF	6	\$4,083	
Classroom #150 (Regular Classroom)							
	Ceiling - Lay-in		831	SF	4	\$8,449	Soffit issues
	Doors - Wood Doors inclu hw		1	EA	5	\$1,174	
	Floor - Carpet		831	SF	6	\$1,771	
	Lighting - Lay-in		28	EA	6	\$3,331	
	Walls - Concrete Block		545	SF	6	\$1,598	
	Walls - Metal Panel		320	SF	6	\$2,389	
Classroom #151 (Regular Classroom)							
	Ceiling - Lay-in		811	SF	7	\$0	
	Chalk Board		6	LF	4	\$551	obsolete material
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		811	SF	5	\$4,163	Bleach stains
	Lighting - Pendent/Surface		28	EA	7	\$0	
	Walls - Metal Panel		768	SF	6	\$5,733	
	Walls - Plaster/Drywall		95	SF	6	\$262	
Classroom #152 (Regular Classroom)							
	Ceiling - Lay-in		811	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	Closer missing
	Floor - Carpet		811	SF	6	\$1,728	
	Lighting - Pendent/Surface		29	EA	7	\$0	
	Marker Board		10	LF	6	\$214	
	Walls - Metal Panel		742	SF	6	\$5,539	
Classroom #153 (Regular Classroom)							
	Ceiling - Lay-in		834	SF	6	\$2,505	Water infiltration
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		834	SF	6	\$1,777	
	Lighting - Lay-in		28	EA	6	\$3,331	4 lamps out
	Walls - Concrete Block		222	SF	6	\$651	
	Walls - Metal Panel		511	SF	6	\$3,814	
Classroom #154 (Regular Classroom)							
	Ceiling - Lay-in		833	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #154 (Regular Classroom)							
	Floor - Carpet		833	SF	6	\$1,775	
	Lighting - Pendent/Surface		29	EA	6	\$3,593	
	Marker Board		15	LF	6	\$321	
	Walls - Concrete Block		223	SF	6	\$654	
	Walls - Metal Panel		460	SF	6	\$3,434	
Classroom #201 (Regular Classroom)							
	Ceiling - Lay-in		918	SF	6	\$2,757	
	Doors - Side-lite		11	SF	6	\$184	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		918	SF	6	\$1,956	
	Lighting - Lay-in		35	EA	6	\$4,164	
	Marker Board		10	LF	6	\$214	
	Walls - Concrete Block		521	SF	6	\$1,527	
	Walls - Metal Panel		791	SF	6	\$5,904	
Classroom #202 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	918	SF	6	\$2,757	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	918	SF	6	\$1,956	
	Lighting - Lay-in	2nd Floor	35	EA	6	\$4,164	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Walls - Metal Panel	2nd Floor	791	SF	6	\$5,904	
Classroom #203 (Regular Classroom)							
	Ceiling - Lay-in		918	SF	6	\$2,757	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		918	SF	6	\$1,956	
	Lighting - Lay-in		35	EA	6	\$4,164	
	Marker Board		10	LF	6	\$214	
	Walls - Concrete Block		521	SF	6	\$1,527	
	Walls - Metal Panel		791	SF	6	\$5,904	
Classroom #204 (Regular Classroom)							
	Ceiling - Lay-in		918	SF	6	\$2,757	
	Doors - Side-lite		11	SF	6	\$184	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		918	SF	6	\$1,956	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #204 (Regular Classroom)							
	Lighting - Lay-in		35	EA	6	\$4,164	
	Marker Board		10	LF	6	\$214	
	Walls - Concrete Block		521	SF	6	\$1,527	
	Walls - Plaster/Drywall		791	SF	6	\$2,183	
Classroom #207 (Computer Lab)							
	Ceiling - Lay-in		971	SF	6	\$2,916	
	Chalk Board		16	LF	4	\$1,469	obsolete material
	Doors - Wood Doors inclu hw		1	EA	5	\$1,174	
	Floor - Carpet		971	SF	5	\$4,985	
	Lighting - Lay-in		35	EA	6	\$4,164	1 not functioning
	Walls - Concrete Block		1,284	SF	6	\$3,764	
	Work Sink		1	EA	6	\$379	
Classroom #208 - Band Room (Other Instructional Use)							
	Ceiling - Lay-in		2,330	SF	6	\$6,997	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		2,230	SF	6	\$2,232	
	Lighting - Lay-in		89	EA	6	\$10,589	
	Marker Board		16	LF	6	\$343	
	Storage/ Closet		50	SF	6	\$363	
	Walls - Concrete Block		2,080	SF	6	\$6,098	
Classroom #209 (Office)							
	Ceiling - Lay-in	2nd Floor	767	SF	6	\$2,303	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	767	SF	6	\$1,634	
	Lighting - Lay-in	2nd Floor	31	EA	6	\$3,688	
	Walls - Concrete Block	2nd Floor	422	SF	7	\$0	
	Walls - Metal Panel	2nd Floor	522	SF	6	\$3,897	
Classroom #210 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	799	SF	6	\$2,399	
	Doors - Side-lite	2nd Floor	11	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	5	\$1,174	
	Floor - Carpet	2nd Floor	799	SF	6	\$1,702	
	Lighting - Lay-in	2nd Floor	31	EA	6	\$3,688	
	Marker Board	2nd Floor	13	LF	6	\$278	
	Walls - Metal Panel	2nd Floor	413	SF	6	\$3,083	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #210 (Regular Classroom)							
	Walls - Plaster/Drywall	2nd Floor	308	SF	6	\$850	
Classroom #211 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	865	SF	6	\$2,598	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	865	SF	6	\$1,843	
	Lighting - Pendent/Surface	2nd Floor	35	EA	6	\$4,336	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Concrete Block	2nd Floor	503	SF	6	\$1,475	
	Walls - Metal Panel	2nd Floor	203	SF	6	\$1,515	
	Walls - Plaster/Drywall	2nd Floor	274	SF	6	\$756	
Classroom #212 (Regular Classroom)							
	Ceiling - Lay-in		730	SF	6	\$2,192	
	Doors - Side-lite		11	SF	6	\$184	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		730	SF	6	\$1,555	
	Lighting - Lay-in		35	EA	6	\$4,164	
	Marker Board		16	LF	6	\$343	
	Walls - Concrete Block		891	SF	6	\$2,612	
	Walls - Metal Panel		276	SF	6	\$2,060	
Classroom #215 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	625	SF	6	\$1,877	
	Ceiling - Plaster/Drywall	2nd Floor	250	SF	6	\$865	
	Doors - Wood Doors inclu hw	2nd Floor	4	EA	6	\$1,204	
	Floor - Tile/Sheet	2nd Floor	875	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	24	EA	6	\$2,973	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	370	SF	7	\$0	
	Walls - Concrete Block	2nd Floor	275	SF	7	\$0	
	Walls - Metal Panel	2nd Floor	510	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	253	SF	7	\$0	
	Wireless System	2nd Floor	1	EA	7	\$0	
Classroom #216 (Regular Classroom)							
	Ceiling - Lay-in		773	SF	6	\$2,321	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #216 (Regular Classroom)							
	Chalk Board		16	LF	6	\$357	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		773	SF	6	\$1,647	
	Lighting - Lay-in		28	EA	6	\$3,331	
	Walls - Concrete Block		1,202	SF	6	\$3,524	
Classroom #217 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	764	SF	6	\$2,294	
	Ceiling - Plaster/Drywall	2nd Floor	200	SF	6	\$692	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	5	\$1,174	
	Floor - Carpet	2nd Floor	964	SF	6	\$2,054	
	Lighting - Pendent/Surface	2nd Floor	31	EA	6	\$3,841	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Concrete Block	2nd Floor	792	SF	6	\$2,322	
	Walls - Metal Panel	2nd Floor	411	SF	6	\$3,068	
Classroom #218 (Regular Classroom)							
	Ceiling - Plaster/Drywall		773	SF	7	\$0	
	Chalk Board		16	LF	4	\$1,469	obsolete material
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Carpet		773	SF	6	\$1,647	
	Lighting - Lay-in		28	EA	6	\$3,331	
	Walls - Concrete Block		1,202	SF	7	\$0	
Classroom #220 (Multi Purpose Room)							
	Ceiling - Lay-in	2nd Floor	1,011	SF	6	\$3,036	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Carpet	2nd Floor	1,011	SF	5	\$5,190	
	Lighting - Lay-in	2nd Floor	37	EA	6	\$4,402	
	Marker Board	2nd Floor	24	LF	6	\$514	
	Walls - Concrete Block	2nd Floor	276	SF	6	\$809	
	Walls - Plaster/Drywall	2nd Floor	832	SF	6	\$2,296	
Classroom #221 (Science Lab Level 1)							
	Casework	2nd Floor	80	LF	6	\$2,020	
	Ceiling - Lay-in	2nd Floor	1,220	SF	6	\$3,664	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #221 (Science Lab Level 1)							
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,220	SF	6	\$1,221	
	Fume Hood	2nd Floor	1	EA	7	\$0	
	Gas Line	2nd Floor	8	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	41	EA	6	\$4,878	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Science Lab Shower	2nd Floor	1	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	220	SF	6	\$645	
	Walls - Plaster/Drywall	2nd Floor	478	SF	6	\$1,319	
	Work Sink	2nd Floor	8	EA	6	\$3,032	
Classroom #222 (Science Classroom)							
	Ceiling - Lay-in	2nd Floor	976	SF	6	\$2,931	
	Ceiling - Plaster/Drywall	2nd Floor	30	SF	5	\$275	paint peeling, appears to have water damage
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	976	SF	6	\$2,080	
	Lighting - Pendent/Surface	2nd Floor	31	EA	6	\$3,841	t8
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Concrete Block	2nd Floor	270	SF	7	\$0	
	Walls - Metal Panel	2nd Floor	488	SF	6	\$3,643	
	Walls - Plaster/Drywall	2nd Floor	20	SF	5	\$152	paint peeling, appears to have water damage
Classroom #223 (Science Lab Level 3)							
	Casework	2nd Floor	12	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	961	SF	6	\$2,886	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	961	SF	6	\$962	
	Gas Line	2nd Floor	2	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	32	EA	6	\$3,965	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	224	SF	6	\$657	
	Walls - Plaster/Drywall	2nd Floor	540	SF	6	\$1,490	
	Work Sink	2nd Floor	2	EA	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #224 (Science Classroom)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	660	SF	6	\$1,982	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	660	SF	6	\$1,406	
	Lighting - Pendent/Surface	2nd Floor	23	EA	6	\$2,850	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Walls - Metal Panel	2nd Floor	623	SF	6	\$4,650	
	Walls - Plaster/Drywall	2nd Floor	65	SF	6	\$179	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #227 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	1,257	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Tile/Sheet	2nd Floor	1,257	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	30	EA	6	\$3,569	
	Marker Board	2nd Floor	20	LF	6	\$428	
	Walls - Concrete Block	2nd Floor	510	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	528	SF	7	\$0	Fiber Reinforced Plastic (FRP) Walls
	Wireless System	2nd Floor	1	EA	7	\$0	
Classroom #230 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	834	SF	7	\$0	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	834	SF	6	\$835	
	Lighting - Pendent/Surface	2nd Floor	29	EA	6	\$3,593	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Concrete Block	2nd Floor	464	SF	7	\$0	
	Walls - Metal Panel	2nd Floor	288	SF	7	\$0	
Classroom #231 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	785	SF	6	\$2,357	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	785	SF	6	\$1,673	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #231 (Regular Classroom)							
	Lighting - Pendent/Surface	2nd Floor	27	EA	6	\$3,345	
	Marker Board	2nd Floor	15	LF	6	\$321	
	Walls - Metal Panel	2nd Floor	658	SF	6	\$4,912	
	Walls - Plaster/Drywall	2nd Floor	110	SF	6	\$304	
Classroom #232 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	794	SF	6	\$2,384	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	794	SF	6	\$795	
	Lighting - Pendent/Surface	2nd Floor	29	EA	6	\$3,593	
	Marker Board	2nd Floor	15	LF	6	\$321	
	Walls - Metal Panel	2nd Floor	666	SF	6	\$4,971	
Classroom #233 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	833	SF	6	\$2,501	
	Ceiling - Plaster/Drywall	2nd Floor	30	SF	5	\$275	north east corner appears to have water damage - plaster and peeling paint
	Doors - Side-lite	2nd Floor	11	SF	5	\$770	missing snap in metal mullion
	Doors - Transom Window	2nd Floor	14	SF	5	\$593	missing snap in metal mullion
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	5	\$1,174	hold open hardware not working
	Floor - Carpet	2nd Floor	833	SF	6	\$1,775	
	Lighting - Pendent/Surface	2nd Floor	28	EA	6	\$3,469	
	Marker Board	2nd Floor	19	LF	6	\$407	
	Walls - Concrete Block	2nd Floor	218	SF	6	\$639	
	Walls - Metal Panel	2nd Floor	458	SF	6	\$3,419	
	Walls - Plaster/Drywall	2nd Floor	20	SF	5	\$152	north east corner appears to have water damage - plaster and peeling paint
Classroom #234 (Regular Classroom)							
	Ceiling - Lay-in		837	SF	6	\$2,514	
	Doors - Wood Doors inclu hw		1	EA	5	\$1,174	closer broken; frame facing panel missing
	Floor - Carpet		837	SF	5	\$4,297	carpet at east wall pulled away from wall
	Lighting - Pendent/Surface		29	EA	6	\$3,593	
	Marker Board		15	LF	6	\$321	
	Walls - Concrete Block		219	SF	6	\$642	
	Walls - Metal Panel		460	SF	6	\$3,434	insulation exposed

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #241 (Science Lab Level 3)							
	Casework	2nd Floor	13	LF	6	\$328	
	Ceiling - Lay-in	2nd Floor	1,215	SF	6	\$3,649	
	Doors - Side-lite	2nd Floor	22	SF	6	\$368	
	Doors - Transom Window	2nd Floor	20	SF	6	\$339	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,215	SF	6	\$1,216	
	Lighting - Pendent/Surface	2nd Floor	38	EA	6	\$4,708	T8
	Marker Board	2nd Floor	10	LF	6	\$214	
	Walls - Concrete Block	2nd Floor	220	SF	6	\$645	
	Walls - Plaster/Drywall	2nd Floor	520	SF	6	\$1,435	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroom #242 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	965	SF	6	\$2,898	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	965	SF	6	\$2,056	
	Lighting - Pendent/Surface	2nd Floor	31	EA	6	\$3,841	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Concrete Block	2nd Floor	235	SF	6	\$689	
	Walls - Metal Panel	2nd Floor	478	SF	6	\$3,568	
Classroom #243 (Science Lab Level 3)							
	Casework	2nd Floor	13	LF	6	\$328	
	Ceiling - Lay-in	2nd Floor	910	SF	6	\$2,733	
	Ceiling - Plaster/Drywall	2nd Floor	55	SF	5	\$504	water damage
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	965	SF	7	\$0	
	Gas Line	2nd Floor	2	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	31	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	1	EA	5	\$183	
	Marker Board	2nd Floor	17	LF	7	\$0	
	Science Lab Elements	2nd Floor	965	SF	6	\$6,541	
	Walls - Concrete Block	2nd Floor	224	SF	6	\$657	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #243 (Science Lab Level 3)							
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroom #244 (Store Room)							
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	658	SF	6	\$1,976	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	658	SF	6	\$1,402	
	Lighting - Pendent/Surface	2nd Floor	23	EA	6	\$2,850	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Walls - Metal Panel	2nd Floor	648	SF	6	\$4,837	
	Work Sink	2nd Floor	1	EA	6	\$379	faucet missing
Classroom #249B (Regular Classroom)							
	Casework	2nd Floor	7	LF	5	\$1,464	
	Ceiling - Lay-in	2nd Floor	924	SF	6	\$2,775	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	924	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	30	EA	6	\$3,717	T8
	Marker Board	2nd Floor	15	LF	6	\$321	
	Walls - Concrete Block	2nd Floor	280	SF	6	\$821	
	Walls - Concrete Block	2nd Floor	10	SF	5	\$141	Crack in SE corner
	Walls - Plaster/Drywall	2nd Floor	620	SF	6	\$1,711	
	Work Sink	2nd Floor	1	EA	5	\$1,508	
Classroom #250 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	833	SF	6	\$2,501	
	Doors - Side-lite	2nd Floor	11	SF	7	\$0	
	Doors - Transom Window	2nd Floor	14	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	833	SF	6	\$1,775	
	Lighting - Pendent/Surface	2nd Floor	29	EA	6	\$3,593	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Concrete Block	2nd Floor	250	SF	4	\$8,963	east wall separating at wall junction; cmu joints cracking
	Walls - Concrete Block	2nd Floor	220	SF	6	\$739	
	Walls - Metal Panel	2nd Floor	306	SF	6	\$2,284	
	Walls - Plaster/Drywall	2nd Floor	50	SF	4	\$503	plaster wall is cracked and peeling
	Wireless System	2nd Floor	1	EA	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #251 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	812	SF	6	\$2,438	
	Doors - Side-lite	2nd Floor	11	SF	7	\$0	
	Doors - Transom Window	2nd Floor	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	812	SF	6	\$1,730	
	Lighting - Lay-in	2nd Floor	27	EA	6	\$3,212	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	698	SF	6	\$5,210	
Classroom #252 (Computer Lab)							
	Ceiling - Lay-in	2nd Floor	800	SF	7	\$0	
	Doors - Side-lite	2nd Floor	11	SF	7	\$0	
	Doors - Transom Window	2nd Floor	14	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	800	SF	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	1	EA	5	\$183	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	395	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	280	SF	7	\$0	
Classroom #253 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	840	SF	6	\$2,523	
	Ceiling - Plaster/Drywall	2nd Floor	33	SF	5	\$302	
	Doors - Side-lite	2nd Floor	11	SF	6	\$184	
	Doors - Transom Window	2nd Floor	14	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	840	SF	6	\$1,790	
	Lighting - Pendent/Surface	2nd Floor	28	EA	6	\$3,469	
	Marker Board	2nd Floor	15	LF	6	\$321	
	Walls - Concrete Block	2nd Floor	220	SF	7	\$0	
	Walls - Metal Panel	2nd Floor	251	SF	6	\$1,874	
	Walls - Plaster/Drywall	2nd Floor	20	SF	4	\$201	Plaster coming off, possible water infiltration at ceiling.
Classroom #254 (Regular Classroom)							
	Ceiling - Lay-in	2nd Floor	830	SF	7	\$0	
	Doors - Side-lite	2nd Floor	10	SF	7	\$0	
	Doors - Transom Window	2nd Floor	14	SF	7	\$0	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #254 (Regular Classroom)							
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	830	SF	6	\$1,768	
	Lighting - Pendent/Surface	2nd Floor	29	EA	6	\$3,593	1 lamp out
	Marker Board	2nd Floor	15	LF	6	\$321	
	Walls - Concrete Block	2nd Floor	270	SF	7	\$0	
	Walls - Metal Panel	2nd Floor	202	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	270	SF	7	\$0	

Classrooms Subtotal:

\$737,498

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	102 Assistant Principal	143	SF	6	\$429	Rust drips at grille
	Doors - Wood Doors inclu hw	102 Assistant Principal	1	EA	6	\$301	
	Floor - Carpet	102 Assistant Principal	143	SF	4	\$1,315	warped, worn, zippering and stained
	Lighting - Pendent/Surface	102 Assistant Principal	4	EA	6	\$496	
	Walls - Concrete Block	102 Assistant Principal	98	SF	7	\$0	
	Walls - Metal Panel	102 Assistant Principal	325	SF	7	\$0	
	Ceiling - Lay-in	125 Security Office	218	SF	6	\$655	
	Doors - Wood Doors inclu hw	125 Security Office	2	EA	6	\$602	
	Floor - Carpet	125 Security Office	218	SF	6	\$464	
	Lighting - Lay-in	125 Security Office	4	EA	6	\$476	T8
	Power Distribution	125 Security Office	6	EA	6	\$12,749	
	Walls - Concrete Block	125 Security Office	25	SF	6	\$73	
	Walls - Metal Panel	125 Security Office	520	SF	6	\$3,882	
	Ceiling - Lay-in	127 Attendants Office	790	SF	6	\$2,372	
	Doors - Side-lite	127 Attendants Office	11	SF	5	\$770	wood panel
	Doors - Transom Window	127 Attendants Office	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	127 Attendants Office	2	EA	6	\$602	
	Floor - Carpet	127 Attendants Office	790	SF	5	\$4,056	
	Lighting - Lay-in	127 Attendants Office	26	EA	6	\$3,093	
	Power Distribution	127 Attendants Office	12	EA	6	\$25,499	
	Walls - Concrete Block	127 Attendants Office	430	SF	6	\$1,261	
	Walls - Metal Panel	127 Attendants Office	515	SF	6	\$3,844	
	Work Slnk	127 Attendants Office	1	EA	6	\$508	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	128 Office (former Counselor)	206	SF	6	\$619	
	Doors - Side-lite	128 Office (former Counselor)	11	SF	6	\$184	
	Doors - Transom Window	128 Office (former Counselor)	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	128 Office (former Counselor)	1	EA	6	\$301	
	Floor - Carpet	128 Office (former Counselor)	162	SF	5	\$832	
	Floor - Tile	128 Office (former Counselor)	44	SF	6	\$96	
	Lighting - Lay-in	128 Office (former Counselor)	7	EA	6	\$833	
	Power Distribution	128 Office (former Counselor)	4	EA	6	\$8,500	
	Walls - Concrete Block	128 Office (former Counselor)	310	SF	6	\$909	
	Walls - Metal Panel	128 Office (former Counselor)	260	SF	6	\$1,941	
	Ceiling - Lay-in	145	214	SF	7	\$0	
	Doors - Wood Doors inclu hw	145	1	EA	7	\$0	
	Floor - Carpet	145	214	SF	6	\$456	
	Lighting - Lay-in	145	6	EA	7	\$0	
	Walls - Metal Panel	145	416	SF	6	\$3,105	
	Ceiling - Lay-in	148 - Office	207	SF	6	\$622	
	Doors - Wood Doors inclu hw	148 - Office	1	EA	7	\$0	
	Floor - Carpet	148 - Office	157	SF	6	\$335	
	Floor - Tile/Sheet	148 - Office	50	SF	6	\$50	
	Lighting - Lay-in	148 - Office	6	EA	6	\$714	
	Walls - Concrete Block	148 - Office	311	SF	6	\$912	
	Walls - Metal Panel	148 - Office	261	SF	6	\$1,948	
	Ceiling - Plaster/Drywall	200 Office (former Classroom)	445	SF	6	\$1,540	Ceiling has damage at light fixture.
	Doors - Wood Doors inclu hw	200 Office (former Classroom)	1	EA	6	\$301	
	Floor - Carpet	200 Office (former Classroom)	445	SF	6	\$948	
	Lighting - Lay-in	200 Office (former Classroom)	3	EA	6	\$357	3 eyeball lights
	Lighting - Pendent/Surface	200 Office (former Classroom)	4	EA	6	\$496	
	Power Distribution	200 Office (former Classroom)	8	EA	6	\$16,999	
	Walls - Concrete Block	200 Office (former Classroom)	424	SF	6	\$1,243	
	Walls - Masonry	200 Office (former Classroom)	132	SF	4	\$8,758	1/2" diagonal crack in masonry 12'-0" long.
	Walls - Plaster/Drywall	200 Office (former Classroom)	144	SF	6	\$397	New low wall used as a partition.
	Ceiling - Lay-in	220A Teachers Resource Center	500	SF	6	\$1,502	
	Ceiling - Plaster/Drywall	220A Teachers Resource Center	48	SF	6	\$166	
	Doors - Side-lite	220A Teachers Resource Center	11	SF	6	\$184	
	Doors - Transom Window	220A Teachers Resource Center	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	220A Teachers Resource Center	1	EA	6	\$301	
	Floor - Carpet	220A Teachers Resource Center	548	SF	6	\$1,168	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	220A Teachers Resource Center	9	EA	6	\$1,071	
	Power Distribution	220A Teachers Resource Center	22	EA	7	\$0	
	Walls - Masonry	220A Teachers Resource Center	98	SF	7	\$0	
	Walls - Plaster/Drywall	220A Teachers Resource Center	386	SF	7	\$0	
	Ceiling - Lay-in	225	207	SF	7	\$0	
	Doors - Wood Doors inclu hw	225	1	EA	7	\$0	
	Floor - Carpet	225	207	SF	7	\$0	
	Lighting - Lay-in	225	10	EA	7	\$0	
	Walls - Concrete Block	225	98	SF	6	\$287	
	Walls - Metal Panel	225	211	SF	7	\$0	
	Walls - Plaster/Drywall	225	310	SF	6	\$856	
	Work Sink	225	1	EA	6	\$508	
	Ceiling - Lay-in	226 Office	206	SF	6	\$619	
	Doors - Side-lite	226 Office	11	SF	5	\$770	Missing mullion cap.
	Doors - Transom Window	226 Office	14	SF	5	\$593	Missing mullion cap.
	Doors - Wood Doors inclu hw	226 Office	1	EA	6	\$301	
	Floor - Tile	226 Office	206	SF	6	\$451	
	Lighting - Lay-in	226 Office	7	EA	6	\$833	
	Power Distribution	226 Office	6	EA	6	\$12,749	
	Walls - Concrete Block	226 Office	300	SF	6	\$879	
	Walls - Metal Panel	226 Office	250	SF	6	\$1,866	
	Ceiling - Lay-in	240 Teachers Resource	500	SF	6	\$1,502	
	Ceiling - Plaster/Drywall	240 Teachers Resource	48	SF	5	\$440	
	Doors - Side-lite	240 Teachers Resource	11	SF	6	\$184	
	Doors - Transom Window	240 Teachers Resource	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	240 Teachers Resource	1	EA	6	\$301	
	Floor - Carpet	240 Teachers Resource	548	SF	6	\$1,168	
	Lighting - Pendent/Surface	240 Teachers Resource	9	EA	6	\$1,115	
	Power Distribution	240 Teachers Resource	22	EA	6	\$46,747	
	Walls - Masonry	240 Teachers Resource	98	SF	7	\$0	
	Walls - Plaster/Drywall	240 Teachers Resource	386	SF	7	\$0	
	Ceiling - Plaster/Drywall	245	209	SF	7	\$0	
	Doors - Wood Doors inclu hw	245	1	EA	6	\$301	
	Floor - Carpet	245	209	SF	6	\$445	
	Lighting - Lay-in	245	8	EA	6	\$952	
	Walls - Plaster/Drywall	245	672	SF	6	\$1,855	
	Ceiling - Lay-in	248 Office	207	SF	6	\$622	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Wood Doors inclu hw	248 Office	1	EA	5	\$1,174	
	Floor - Carpet	248 Office	207	SF	6	\$441	
	Lighting - Pendent/Surface	248 Office	8	EA	7	\$0	
	Walls - Concrete Block	248 Office	311	SF	6	\$912	
	Walls - Metal Panel	248 Office	246	SF	6	\$1,836	
	Ceiling - Lay-in	249A Office	323	SF	7	\$0	
	Doors - Wood Doors inclu hw	249A Office	1	EA	7	\$0	
	Floor - Tile/Sheet	249A Office	323	SF	6	\$323	
	Lighting - Pendent/Surface	249A Office	6	EA	7	\$0	
	Walls - Concrete Block	249A Office	220	SF	7	\$0	
	Walls - Plaster/Drywall	249A Office	335	SF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor VIP Conference Room	458	SF	6	\$1,585	
	Doors - Wood Doors inclu hw	2nd Floor VIP Conference Room	1	EA	6	\$301	
	Floor - Carpet	2nd Floor VIP Conference Room	458	SF	6	\$976	
	Lighting - Lay-in	2nd Floor VIP Conference Room	10	EA	7	\$0	
	Walls - Concrete Block	2nd Floor VIP Conference Room	424	SF	6	\$1,243	
	Walls - Masonry	2nd Floor VIP Conference Room	159	SF	6	\$500	
	Ceiling - Plaster/Drywall	Admin Office I	190	SF	6	\$658	
	Doors - Wood Doors inclu hw	Admin Office I	2	EA	6	\$602	
	Floor - Carpet	Admin Office I	190	SF	4	\$1,747	warped, worn, zippering and stained
	Ceiling - Plaster/Drywall	Admin Office II	141	SF	7	\$0	
	Doors - Wood Doors inclu hw	Admin Office II	2	EA	6	\$602	
	Floor - Carpet	Admin Office II	141	SF	4	\$1,296	warped, worn, zippering, stained
	Lighting - Lay-in	Admin Office II	1	EA	7	\$0	
	Walls - Plaster/Drywall	Admin Office II	76	SF	6	\$210	
	Lighting - Lay-in	Admin Office I	8	EA	6	\$952	
	Walls - Plaster/Drywall	Admin Office I	509	SF	6	\$1,405	
	Ceiling - Lay-in	Conference Room in Main Office	141	SF	6	\$423	
	Doors - Wood Doors inclu hw	Conference Room in Main Office	1	EA	6	\$301	
	Floor - Carpet	Conference Room in Main Office	141	SF	4	\$1,296	warped, worn, zippering and stained
	Lighting - Pendent/Surface	Conference Room in Main Office	6	EA	7	\$0	
	Walls - Concrete Block	Conference Room in Main Office	213	SF	6	\$624	
	Walls - Metal Panel	Conference Room in Main Office	174	SF	6	\$1,299	
	Ceiling - Plaster/Drywall	Copy Room	188	SF	7	\$0	
	Doors - Wood Doors inclu hw	Copy Room	1	EA	6	\$301	
	Floor - Carpet	Copy Room	188	SF	6	\$401	
	Lighting - Lay-in	Copy Room	2	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Plaster/Drywall	Copy Room	637	SF	6	\$1,758	
	Ceiling - Lay-in	Engineer's Office (former Nurse)	424	SF	6	\$1,273	
	Doors - Side-lite	Engineer's Office (former Nurse)	11	SF	6	\$184	covered with paper
	Doors - Transom Window	Engineer's Office (former Nurse)	14	SF	6	\$237	covered with paper
	Doors - Wood Doors inclu hw	Engineer's Office (former Nurse)	2	EA	6	\$602	
	Floor - Carpet	Engineer's Office (former Nurse)	424	SF	6	\$903	Area does not include restroom in Office
	Lighting - Lay-in	Engineer's Office (former Nurse)	17	EA	6	\$2,023	
	Power Distribution	Engineer's Office (former Nurse)	22	EA	6	\$46,747	
	Storage/ Closet	Engineer's Office (former Nurse)	360	SF	6	\$2,610	Receiving area adjacent to Engineer's Office (former Engineer's Office divided in half)
	Walls - Concrete Block	Engineer's Office (former Nurse)	416	SF	6	\$1,220	
	Walls - Metal Panel	Engineer's Office (former Nurse)	438	SF	6	\$3,269	
	Walls - Plaster/Drywall	Engineer's Office (former Nurse)	350	SF	6	\$966	
	Ceiling - Plaster/Drywall	File Room	92	SF	6	\$318	
	Doors - Wood Doors inclu hw	File Room	1	EA	7	\$0	
	Floor - Carpet	File Room	92	SF	5	\$472	
	Lighting - Lay-in	File Room	2	EA	6	\$238	One ballast to be replaced
	Walls - Plaster/Drywall	File Room	94	SF	6	\$259	
	Ceiling - Lay-in	in 117 Library/Media	144	SF	6	\$432	
	Doors - Wood Doors inclu hw	in 117 Library/Media	1	EA	6	\$301	
	Floor - Carpet	in 117 Library/Media	144	SF	5	\$739	
	Lighting - Pendent/Surface	in 117 Library/Media	6	EA	6	\$743	
	Power Distribution	in 117 Library/Media	6	EA	6	\$12,749	
	Walls - Concrete Block	in 117 Library/Media	98	SF	6	\$287	
	Walls - Metal Panel	in 117 Library/Media	370	SF	6	\$2,762	30 sf of metal panel is glazed
	Ceiling - Lay-in	Librarian in 117 Library/Media	215	SF	6	\$646	
	Doors - Wood Doors inclu hw	Librarian in 117 Library/Media	1	EA	6	\$301	
	Floor - Carpet	Librarian in 117 Library/Media	215	SF	5	\$1,104	
	Lighting - Pendent/Surface	Librarian in 117 Library/Media	7	EA	6	\$867	
	Power Distribution	Librarian in 117 Library/Media	8	EA	6	\$16,999	
	Walls - Concrete Block	Librarian in 117 Library/Media	148	SF	6	\$434	
	Walls - Metal Panel	Librarian in 117 Library/Media	420	SF	6	\$3,135	128 sf is glazed metal panel system
	Ceiling - Lay-in	Main Office	583	SF	7	\$0	
	Doors - Wood Doors inclu hw	Main Office	1	EA	6	\$301	
	Floor - Carpet	Main Office	403	SF	4	\$3,706	warped, worn, zippering and stained
	Floor - Tile/Sheet	Main Office	180	SF	7	\$0	
	Lighting - Pendent/Surface	Main Office	22	EA	7	\$0	
	Storage/ Closet	Main Office	26	SF	6	\$189	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Metal Panel	Main Office	448	SF	7	\$0	
	Walls - Plaster/Drywall	Main Office	416	SF	7	\$0	
	Ceiling - Plaster/Drywall	Natatorium Office	96	SF	7	\$0	
	Doors - Steel Doors incl hw	Natatorium Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Natatorium Office	96	SF	6	\$203	
	Lighting - Lay-in	Natatorium Office	4	EA	6	\$476	
	Walls - Concrete Block	Natatorium Office	392	SF	6	\$1,149	
	Ceiling - Plaster/Drywall	Open Office	322	SF	7	\$0	
	Doors - Wood Doors inclu hw	Open Office	3	EA	6	\$903	
	Floor - Carpet	Open Office	322	SF	6	\$686	
	Lighting - Lay-in	Open Office	4	EA	6	\$476	
	Walls - Plaster/Drywall	Open Office	777	SF	6	\$2,144	
	Ceiling - Plaster/Drywall	Phone Room	43	SF	6	\$149	
	Doors - Wood Doors inclu hw	Phone Room	1	EA	6	\$301	
	Floor - Tile	Phone Room	43	SF	6	\$94	VCT
	Lighting - Lay-in	Phone Room	1	EA	6	\$119	
	Walls - Concrete Block	Phone Room	241	SF	6	\$706	
	Ceiling - Lay-in	Principal's Office	211	SF	7	\$0	
	Doors - Wood Doors inclu hw	Principal's Office	4	EA	6	\$1,204	
	Floor - Carpet	Principal's Office	211	SF	6	\$450	
	Lighting - Pendent/Surface	Principal's Office	5	EA	7	\$0	
	Walls - Concrete Block	Principal's Office	470	SF	7	\$0	
	Ceiling - Lay-in	Principals Workroom	139	SF	7	\$0	
	Doors - Wood Doors inclu hw	Principals Workroom	1	EA	7	\$0	
	Floor - Carpet	Principals Workroom	139	SF	6	\$296	
	Lighting - Pendent/Surface	Principals Workroom	2	EA	6	\$248	
	Walls - Plaster/Drywall	Principals Workroom	471	SF	6	\$1,300	
	Ceiling - Lay-in	Radio Room	95	SF	6	\$285	
	Doors - Wood Doors inclu hw	Radio Room	1	EA	6	\$301	
	Floor - Carpet	Radio Room	95	SF	4	\$874	warped, worn, zippering and stained
	Lighting - Pendent/Surface	Radio Room	2	EA	7	\$0	
	Walls - Concrete Block	Radio Room	407	SF	6	\$1,193	
	Work Sink	Radio Room	1	EA	6	\$508	
	Ceiling - Lay-in	School Store (former Engineer's Office divided in half)	350	SF	6	\$1,051	
	Doors - Side-lite	School Store (former Engineer's Office divided in half)	11	SF	6	\$184	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Transom Window	School Store (former Engineer's Office divided in half)	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	School Store (former Engineer's Office divided in half)	1	EA	6	\$301	
	Floor - Carpet	School Store (former Engineer's Office divided in half)	350	SF	6	\$746	
	Lighting - Lay-in	School Store (former Engineer's Office divided in half)	11	EA	6	\$1,309	T8
	Walls - Concrete Block	School Store (former Engineer's Office divided in half)	146	SF	7	\$0	
	Walls - Metal Panel	School Store (former Engineer's Office divided in half)	334	SF	6	\$2,493	
	Walls - Plaster/Drywall	School Store (former Engineer's Office divided in half)	236	SF	7	\$0	new wall between receiving and store
Auditorium & Theater							
	Ceiling - Plaster/Drywall	Activity Center	5,751	SF	7	\$0	
	Doors - Wood Doors inclu hw	Activity Center	3	EA	6	\$903	
	Floor - Carpet	Activity Center	5,751	SF	7	\$0	
	Lighting - Lay-in	Activity Center	53	EA	6	\$6,306	
	Lighting - Pendent/Surface	Activity Center	24	EA	6	\$2,973	
	Main Floor Seating	Activity Center	245	EA	6	\$42,610	
	Sound System	Activity Center	1	EA	6	\$10,721	
	Stage Lighting System	Activity Center	1	EA	6	\$8,077	
	Walls - Concrete Block	Activity Center	2,317	SF	6	\$6,792	
	Walls - Plaster/Drywall	Activity Center	425	SF	6	\$2,024	
Clinic							
	Ceiling - Lay-in	1st Floor between Faculty Dining + School Store	225	SF	6	\$676	
	Doors - Wood Doors inclu hw	1st Floor between Faculty Dining + School Store	2	EA	6	\$602	
	Floor - Carpet	1st Floor between Faculty Dining + School Store	225	SF	4	\$2,069	large stains and torn
	Lighting - Lay-in	1st Floor between Faculty Dining + School Store	7	EA	6	\$833	
	Walls - Concrete Block	1st Floor between Faculty Dining + School Store	98	SF	6	\$287	
	Walls - Metal Panel	1st Floor between Faculty Dining + School Store	680	SF	6	\$5,076	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymnasias							
	Ceiling - Exposed	2nd Floor	5,334	SF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	170	SF	6	\$938	
	Doors - Wood Doors inclu hw	2nd Floor	8	EA	6	\$2,408	
	Floor - Tile/Sheet	2nd Floor	170	SF	6	\$170	
	Floor - Wood	2nd Floor	5,334	SF	6	\$37,604	
	Lighting - Metal Halide/Sodium Vapor	2nd Floor	32	EA	6	\$4,279	
	Scoreboards	2nd Floor	1	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	5,838	SF	6	\$17,114	
Kitchen							
	Ceiling - Lay-in	1st Floor	1,480	SF	5	\$8,804	stained and dirty
	Doors - Steel Doors incl hw	1st Floor	7	EA	6	\$2,107	
	Floor - Tile Ceramic/ Porcelain	1st Floor	1,480	SF	6	\$3,132	
	Lighting - Lay-in	1st Floor	39	EA	6	\$4,640	
	Storage/ Closet	1st Floor	340	SF	6	\$2,465	1 storage room, 1 freezer room, 2 refrigerated rooms.
	Walls - Concrete Block	1st Floor	2,720	SF	6	\$7,974	
Library							
	Casework	117 Library/Media Center	120	LF	6	\$3,030	Wood shelving
	Ceiling - Lay-in	117 Library/Media Center	3,310	SF	6	\$9,940	
	Doors - Transom Window	117 Library/Media Center	18	SF	6	\$305	2 wood transom panels over storage 116 + 116A doors
	Doors - Wood Doors inclu hw	117 Library/Media Center	2	EA	6	\$602	doors to Storage 116 + 116A
	Doors - Wood Doors inclu hw	117 Library/Media Center	3	EA	5	\$3,522	damaged. within glazed metal panel system.
	Floor - Carpet	117 Library/Media Center	3,310	SF	5	\$16,993	worn, stained, infill patches where casework has been removed.
	Lighting - Pendent/Surface	117 Library/Media Center	119	EA	6	\$14,744	
	Storage/ Closet	117 Library/Media Center	140	SF	6	\$1,015	Audio Visual Room - used as storage
	Storage/ Closet	117 Library/Media Center	578	SF	5	\$9,323	116 Video Technology - used as Storage Room. Floors and casework in need of replacement.
	Storage/ Closet	117 Library/Media Center	186	SF	6	\$1,349	116 A Storage in 116 Video Technology
	Walls - Concrete Block	117 Library/Media Center	724	SF	6	\$2,122	
	Walls - Metal Panel	117 Library/Media Center	1,060	SF	6	\$7,912	Glazed metal panel system
	Walls - Metal Panel	117 Library/Media Center	468	SF	6	\$4,236	Solid metal panel system
	Casework	117A Reading Room in Library	45	LF	6	\$1,136	metal shelves
	Ceiling - Lay-in	117A Reading Room in Library	735	SF	6	\$2,207	
	Doors - Wood Doors inclu hw	117A Reading Room in Library	2	EA	6	\$602	
	Floor - Carpet	117A Reading Room in Library	735	SF	5	\$3,773	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Library							
	Lighting - Pendent/Surface	117A Reading Room in Library	32	EA	6	\$3,965	
	Walls - Concrete Block	117A Reading Room in Library	185	SF	6	\$542	
	Walls - Metal Panel	117A Reading Room in Library	946	SF	6	\$7,062	metal panels on south + east sides are partially glazed.
Locker/Shower Room							
	Accessories	1st Floor - Natatorium	270	SF	5	\$2,359	several accessories are rusted
	Benches, ped mounted	1st Floor - Natatorium	12	LF	4	\$5,980	bench bases are rusted and have protruding rusted screws.
	Ceiling - Plaster/ Drywall	1st Floor - Natatorium	1,270	SF	6	\$4,395	Stains on ceiling around light fixtures.
	Doors - Steel Doors incl hw	1st Floor - Natatorium	1	EA	6	\$301	
	Doors - Transom Window	1st Floor - Natatorium	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	1st Floor - Natatorium	1	EA	6	\$301	
	Floor Drain	1st Floor - Natatorium	7	EA	6	\$7,414	
	Floor - Tile Ceramic/ Porcelain	1st Floor - Natatorium	1,270	SF	5	\$20,286	Ceramic tile base missing in several areas and appears in poor condition - should be replaced. Although floor is stable, the appearance is old and has been repaired in several locations and several tiles are chipped.
	Hand Dryer	1st Floor - Natatorium	9	EA	6	\$2,070	
	Lavatory	1st Floor - Natatorium	2	EA	6	\$639	
	Lighting - Lay-in	1st Floor - Natatorium	3	EA	6	\$357	12" x 12" recessed
	Lighting - Lay-in	1st Floor - Natatorium	14	EA	6	\$1,666	12" x 4'-0" Recessed in plaster/drywall
	Lighting - Pendent/Surface	1st Floor - Natatorium	1	EA	6	\$124	
	Partitions	1st Floor - Natatorium	14	EA	4	\$27,810	Changing Area: partitions are damaged, one is missing a bench and door, 8 missing base cap which reveals rusted partitions below. Some cross bars are missing. These partitions have been painted numerous times and should be replaced.
	Partitions	1st Floor - Natatorium	4	EA	6	\$1,188	Toilet partitions
	Showers	1st Floor - Natatorium	11	EA	6	\$3,426	
	Student Lockers - One Tier	1st Floor - Natatorium	52	EA	5	\$7,288	Lockers are pitted and rusted on the inside. They have been painted numerous times on the outside.
	Walls - Concrete Block	1st Floor - Natatorium	2,200	SF	6	\$6,449	
	Water Closet	1st Floor - Natatorium	3	EA	6	\$1,008	
	Accessories	2nd Floor	530	SF	7	\$0	
	Accessories	2nd Floor	519	SF	7	\$0	
	Benches, ped mounted	2nd Floor	18	LF	7	\$0	
	Benches, ped mounted	2nd Floor	15	LF	7	\$0	
	Ceiling - Plaster/ Drywall	2nd Floor	530	SF	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Ceiling - Plaster/ Drywall	2nd Floor	519	SF	6	\$1,796	
	Doors - Steel Doors incl hw	2nd Floor	2	EA	7	\$0	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor Drain	2nd Floor	1	EA	7	\$0	
	Floor Drain	2nd Floor	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	89	SF	6	\$188	
	Floor - Tile/Sheet	2nd Floor	530	SF	7	\$0	
	Floor - Tile/Sheet	2nd Floor	430	SF	6	\$430	
	Hand Dryer	2nd Floor	1	EA	6	\$230	
	Hand Dryer	2nd Floor	1	EA	7	\$0	
	Lavatory	2nd Floor	1	EA	7	\$0	
	Lavatory	2nd Floor	1	EA	6	\$320	
	Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	10	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	2	EA	7	\$0	12" x 12"
	Partitions	2nd Floor	1	EA	6	\$297	
	Partitions	2nd Floor	1	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	33	EA	6	\$3,064	
	Student Lockers - One Tier	2nd Floor	33	EA	7	\$0	
	Urinals	2nd Floor	1	EA	6	\$336	
	Walls - Concrete Block	2nd Floor	1,070	SF	7	\$0	
	Walls - Concrete Block	2nd Floor	1,275	SF	7	\$0	
	Water Closet	2nd Floor	1	EA	7	\$0	
	Water Closet	2nd Floor	1	EA	7	\$0	
Lunch & Multipurpose Room							
	Ceiling - Lay-in	1st Floor East - Commons	1,960	SF	6	\$5,886	
	Ceiling - Plaster/Drywall	1st Floor East - Commons	240	SF	5	\$2,200	
	Floor - Tile	1st Floor East - Commons	120	SF	5	\$692	
	Floor - Tile	1st Floor East - Commons	1,960	SF	6	\$4,288	
	Lighting - Lay-in	1st Floor East - Commons	36	EA	6	\$4,283	
	Serving Line	1st Floor East - Commons	20	LF	6	\$1,190	
	Walls - Concrete Block	1st Floor East - Commons	580	SF	6	\$1,700	
	Ceiling - Lay-in	1st Floor West - Commons	1,960	SF	6	\$5,886	
	Ceiling - Plaster/Drywall	1st Floor West - Commons	240	SF	5	\$2,200	
	Floor - Tile	1st Floor West - Commons	120	SF	4	\$1,556	VCT which runs length of exterior storefront on each side is damaged/missing.
	Floor - Tile	1st Floor West - Commons	1,960	SF	6	\$4,288	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Lighting - Lay-in	1st Floor West - Commons	36	EA	6	\$4,283	
	Serving Line	1st Floor West - Commons	20	LF	6	\$1,190	
	Walls - Concrete Block	1st Floor West - Commons	580	SF	6	\$1,700	
	Ceiling - Lay-in	Clark Cafe	882	SF	6	\$2,649	
	Doors - Wood Doors inclu hw	Clark Cafe	1	EA	6	\$301	
	Floor - Tile/Sheet	Clark Cafe	882	SF	6	\$883	
	Lighting - Pendent/Surface	Clark Cafe	22	EA	6	\$2,726	Needs 1 lamp
	Walls - Concrete Block	Clark Cafe	729	SF	6	\$2,137	
	Walls - Metal Panel	Clark Cafe	480	SF	6	\$3,583	
MDF_IDF							
	AC Unit	186 in Video Technology 116 in Library 117	1	EA	7	\$0	
	Doors - Steel Doors incl hw	186 in Video Technology 116 in Library 117	1	EA	7	\$0	
	Finishes	186 in Video Technology 116 in Library 117	185	SF	6	\$1,320	
	Ventilation and Cooling	186 in Video Technology 116 in Library 117	1	EA	7	\$0	
Mechanical/ Service Rooms							
	Storage Room	110 Engineer's Workroom	752	SF	6	\$5,388	Engineer's Workroom + Storage
	Storage Room	129 Electrical - Football Equipment Storage	305	SF	6	\$2,185	Former Electrical Room being used as football equipment storage. Note: equipment and clothing being stored too close to electrical panels.
	Storage Room	2nd Floor - 206 Storage Room	137	SF	6	\$982	
	Storage Room	2nd Floor Storage Room	139	SF	6	\$996	
	Mechanical/ Service Rooms	2nd Floor	246	SF	6	\$1,762	
	Storage Room	Book Room	308	SF	6	\$2,207	Missing door knob
	Storage Room	Gym Storage	280	SF	6	\$2,006	
	Loading Docks	Loading/Receiving	730	SF	6	\$5,230	
	Storage Room	Outdoor Storage	310	SF	6	\$2,221	2 exterior storage rooms.
	Storage Room	Storage Room Administration Office	187	SF	6	\$1,340	
Pool & Natatorium							
	Accessories	Laundry Room off Natatorium	100	SF	6	\$69	
	Ceiling - Plaster/ Drywall	Laundry Room off Natatorium	100	SF	7	\$0	
	Doors - Steel Doors incl hw	Laundry Room off Natatorium	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Laundry Room off Natatorium	100	SF	6	\$212	
	Lighting - Lay-in	Laundry Room off Natatorium	2	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pool & Natatorium							
	Walls - Concrete Block	Laundry Room off Natatorium	379	SF	6	\$1,111	
	Accessories	Pool	4,226	SF	7	\$0	
	Ceiling - Plaster/ Drywall	Pool	4,226	SF	6	\$23,327	
	Doors - Wood Doors inclu hw	Pool	6	EA	6	\$1,806	
	Floor - Tile Ceramic/ Porcelain	Pool	4,226	SF	7	\$0	
	Lighting - Lay-in	Pool	30	EA	7	\$0	
	Pool Basin	Pool	1,200	SF	7	\$0	
	Pool Deck	Pool	3,026	SF	7	\$0	
	Walls - Concrete Block	Pool	1,727	SF	7	\$0	
Prep Room							
	Casework	2nd flr rm 241A	44	LF	6	\$1,111	
	Ceiling - Lay-in	2nd flr rm 241A	256	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd flr rm 241A	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd flr rm 241A	182	SF	6	\$182	
	Lighting - Lay-in	2nd flr rm 241A	5	EA	6	\$595	T8
	Walls - Plaster/Drywall	2nd flr rm 241A	578	SF	7	\$0	Water damage @ window plaster
Restroom							
	Accessories	1st Floor - south center (Women)	332	SF	6	\$3,062	
	Ceiling - Lay-in	1st Floor - south center (Women)	332	SF	5	\$1,975	12" x 12" lay-in. Large area is missing tiles.
	Doors - Transom Window	1st Floor - south center (Women)	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	1st Floor - south center (Women)	1	EA	6	\$301	
	Floor Drain	1st Floor - south center (Women)	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor - south center (Women)	332	SF	6	\$703	
	Hand Dryer	1st Floor - south center (Women)	1	EA	7	\$0	
	Lavatory	1st Floor - south center (Women)	6	EA	6	\$1,918	
	Lighting - Lay-in	1st Floor - south center (Women)	5	EA	6	\$595	
	Partitions	1st Floor - south center (Women)	7	EA	6	\$2,078	One partition is missing stainless steel shoe. Rusted base exposed.
	Walls - Concrete Block	1st Floor - south center (Women)	850	SF	6	\$2,492	
	Water Closet	1st Floor - south center (Women)	7	EA	6	\$2,352	
	Accessories	1st Floor - south east	206	SF	6	\$1,900	Missing one shelf + mirror
	Ceiling - Plaster/Drywall	1st Floor - south east	206	SF	6	\$713	
	Floor Drain	1st Floor - south east	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Floor - south east	206	SF	6	\$436	
	Hand Dryer	1st Floor - south east	1	EA	7	\$0	
	Lavatory	1st Floor - south east	5	EA	6	\$1,598	One lav is missing - holes + piping still on wall.
	Lighting - Lay-in	1st Floor - south east	3	EA	6	\$357	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Partitions	1st Floor - south east	5	EA	6	\$1,485	
	Walls - Concrete Block	1st Floor - south east	650	SF	6	\$1,905	walls are in need of patching holes and painting.
	Water Closet	1st Floor - south east	5	EA	5	\$6,720	restroom has strong odor. Possibly not venting properly?
	Accessories	1st Floor - south west	206	SF	6	\$1,900	
	Ceiling - Plaster/Drywall	1st Floor - south west	206	SF	7	\$0	
	Floor Drain	1st Floor - south west	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	1st Floor - south west	206	SF	7	\$0	
	Hand Dryer	1st Floor - south west	2	EA	7	\$0	
	Lavatory	1st Floor - south west	4	EA	6	\$1,278	One lavatory is loose from wall and missing drain pipe cover.
	Lighting - Lay-in	1st Floor - south west	3	EA	7	\$0	
	Partitions	1st Floor - south west	5	EA	7	\$0	
	Walls - Concrete Block	1st Floor - south west	650	SF	7	\$0	
	Water Closet	1st Floor - south west	5	EA	7	\$0	
	Accessories	1st Floor Mens Faculty Toilet	186	SF	6	\$1,716	
	Ceiling - Splined	1st Floor Mens Faculty Toilet	186	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor Mens Faculty Toilet	1	EA	6	\$301	
	Floor Drain	1st Floor Mens Faculty Toilet	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	1st Floor Mens Faculty Toilet	186	SF	5	\$2,971	
	Hand Dryer	1st Floor Mens Faculty Toilet	1	EA	6	\$230	
	Lavatory	1st Floor Mens Faculty Toilet	4	EA	6	\$1,278	
	Lighting - Lay-in	1st Floor Mens Faculty Toilet	4	EA	6	\$476	
	Partitions	1st Floor Mens Faculty Toilet	3	EA	6	\$891	
	Urinals	1st Floor Mens Faculty Toilet	4	EA	6	\$1,344	
	Walls - Concrete Block	1st Floor Mens Faculty Toilet	1,047	SF	6	\$3,069	Issue at WC, leak
	Water Closet	1st Floor Mens Faculty Toilet	3	EA	6	\$1,008	
	Accessories	1st Floor SW Boys Toilet Room	337	SF	6	\$3,108	
	Ceiling - Plaster/Drywall	1st Floor SW Boys Toilet Room	337	SF	7	\$0	
	Floor Drain	1st Floor SW Boys Toilet Room	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	1st Floor SW Boys Toilet Room	337	SF	7	\$0	
	Hand Dryer	1st Floor SW Boys Toilet Room	2	EA	7	\$0	
	Lavatory	1st Floor SW Boys Toilet Room	2	EA	6	\$639	
	Lighting - Lay-in	1st Floor SW Boys Toilet Room	2	EA	7	\$0	
	Partitions	1st Floor SW Boys Toilet Room	2	EA	7	\$0	
	Urinals	1st Floor SW Boys Toilet Room	5	EA	7	\$0	
	Walls - Concrete Block	1st Floor SW Boys Toilet Room	468	SF	7	\$0	
	Water Closet	1st Floor SW Boys Toilet Room	2	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Accessories	2nd Floor - SE - Girls Toilet	206	SF	6	\$1,900	
	Ceiling - Plaster/Drywall	2nd Floor - SE - Girls Toilet	206	SF	7	\$0	
	Floor Drain	2nd Floor - SE - Girls Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor - SE - Girls Toilet	206	SF	6	\$436	
	Hand Dryer	2nd Floor - SE - Girls Toilet	1	EA	7	\$0	
	Lavatory	2nd Floor - SE - Girls Toilet	6	EA	6	\$1,918	
	Lighting - Lay-in	2nd Floor - SE - Girls Toilet	3	EA	6	\$357	1 lamp not working
	Partitions	2nd Floor - SE - Girls Toilet	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd Floor - SE - Girls Toilet	650	SF	6	\$1,905	
	Water Closet	2nd Floor - SE - Girls Toilet	5	EA	5	\$6,720	
	Accessories	2nd Floor Men's Faculty (between locker rooms)	132	SF	7	\$0	
	Benches	2nd Floor Men's Faculty (between locker rooms)	4	LF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor Men's Faculty (between locker rooms)	132	SF	7	\$0	
	Doors - Transom Window	2nd Floor Men's Faculty (between locker rooms)	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor Men's Faculty (between locker rooms)	1	EA	6	\$301	
	Floor Drain	2nd Floor Men's Faculty (between locker rooms)	2	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Men's Faculty (between locker rooms)	132	SF	7	\$0	
	Hand Dryer	2nd Floor Men's Faculty (between locker rooms)	1	EA	7	\$0	
	Lavatory	2nd Floor Men's Faculty (between locker rooms)	1	EA	7	\$0	
	Lighting - Lay-in	2nd Floor Men's Faculty (between locker rooms)	2	EA	7	\$0	
	Showers	2nd Floor Men's Faculty (between locker rooms)	1	EA	7	\$0	
	Walls - Concrete Block	2nd Floor Men's Faculty (between locker rooms)	300	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	2nd Floor Men's Faculty (between locker rooms)	124	SF	7	\$0	
	Water Closet	2nd Floor Men's Faculty (between locker rooms)	1	EA	7	\$0	
	Accessories	2nd Floor SE - Boys Toilet	206	SF	6	\$1,900	
	Ceiling - Plaster/Drywall	2nd Floor SE - Boys Toilet	206	SF	6	\$713	
	Floor Drain	2nd Floor SE - Boys Toilet	1	EA	6	\$1,059	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor - Tile Ceramic/ Porcelain	2nd Floor SE - Boys Toilet	206	SF	6	\$436	
	Hand Dryer	2nd Floor SE - Boys Toilet	1	EA	6	\$230	
	Lavatory	2nd Floor SE - Boys Toilet	4	EA	6	\$1,278	
	Lighting - Lay-in	2nd Floor SE - Boys Toilet	3	EA	7	\$0	
	Partitions	2nd Floor SE - Boys Toilet	2	EA	6	\$594	
	Urinals	2nd Floor SE - Boys Toilet	6	EA	6	\$2,016	
	Walls - Concrete Block	2nd Floor SE - Boys Toilet	650	SF	6	\$1,905	
	Water Closet	2nd Floor SE - Boys Toilet	2	EA	6	\$672	
	Accessories	2nd Floor SE Corner Boys Toilet Room	184	SF	6	\$1,697	
	Ceiling - Plaster/Drywall	2nd Floor SE Corner Boys Toilet Room	184	SF	6	\$637	
	Floor Drain	2nd Floor SE Corner Boys Toilet Room	1	EA	6	\$1,059	
	Floor - Tile/Sheet	2nd Floor SE Corner Boys Toilet Room	18	SF	5	\$81	VCT
	Hand Dryer	2nd Floor SE Corner Boys Toilet Room	1	EA	6	\$230	
	Lavatory	2nd Floor SE Corner Boys Toilet Room	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor SE Corner Boys Toilet Room	2	EA	6	\$238	
	Partitions	2nd Floor SE Corner Boys Toilet Room	2	EA	6	\$594	
	Urinals	2nd Floor SE Corner Boys Toilet Room	6	EA	6	\$2,016	
	Walls - Concrete Block	2nd Floor SE Corner Boys Toilet Room	540	SF	6	\$1,583	
	Water Closet	2nd Floor SE Corner Boys Toilet Room	2	EA	6	\$672	
	Accessories	2nd Floor South Center Boys Toilet	230	SF	6	\$2,121	
	Ceiling - Plaster/Drywall	2nd Floor South Center Boys Toilet	230	SF	6	\$796	
	Floor Drain	2nd Floor South Center Boys Toilet	1	EA	6	\$1,059	
	Floor - Tile Quarry	2nd Floor South Center Boys Toilet	230	SF	6	\$487	
	Hand Dryer	2nd Floor South Center Boys Toilet	1	EA	6	\$230	
	Lavatory	2nd Floor South Center Boys Toilet	3	EA	6	\$959	
	Lighting - Lay-in	2nd Floor South Center Boys Toilet	4	EA	6	\$476	
	Partitions	2nd Floor South Center Boys Toilet	2	EA	6	\$594	
	Urinals	2nd Floor South Center Boys Toilet	5	EA	6	\$1,680	
	Walls - Concrete Block	2nd Floor South Center Boys Toilet	742	SF	6	\$2,175	
	Water Closet	2nd Floor South Center Boys Toilet	2	EA	6	\$672	
	Accessories	2nd Floor South Center Girls Toilet Room	228	SF	6	\$2,103	
	Ceiling - Plaster/Drywall	2nd Floor South Center Girls Toilet Room	228	SF	6	\$789	
	Floor Drain	2nd Floor South Center Girls Toilet Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor South Center Girls Toilet Room	228	SF	6	\$483	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Hand Dryer	2nd Floor South Center Girls Toilet Room	1	EA	6	\$230	
	Lavatory	2nd Floor South Center Girls Toilet Room	4	EA	6	\$1,278	
	Lighting - Lay-in	2nd Floor South Center Girls Toilet Room	4	EA	6	\$476	
	Partitions	2nd Floor South Center Girls Toilet Room	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd Floor South Center Girls Toilet Room	993	SF	6	\$2,911	
	Water Closet	2nd Floor South Center Girls Toilet Room	6	EA	6	\$2,016	
	Accessories	2nd Floor SW Boys Toilet Room	337	SF	6	\$3,108	
	Ceiling - Plaster/Drywall	2nd Floor SW Boys Toilet Room	337	SF	7	\$0	
	Floor Drain	2nd Floor SW Boys Toilet Room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor SW Boys Toilet Room	337	SF	7	\$0	
	Hand Dryer	2nd Floor SW Boys Toilet Room	2	EA	6	\$460	
	Lavatory	2nd Floor SW Boys Toilet Room	2	EA	6	\$639	
	Lighting - Lay-in	2nd Floor SW Boys Toilet Room	2	EA	6	\$238	
	Partitions	2nd Floor SW Boys Toilet Room	2	EA	6	\$594	
	Urinals	2nd Floor SW Boys Toilet Room	5	EA	6	\$1,680	
	Walls - Concrete Block	2nd Floor SW Boys Toilet Room	468	SF	7	\$0	
	Water Closet	2nd Floor SW Boys Toilet Room	2	EA	6	\$672	
	Accessories	2nd floor SW Girls Toilet	217	SF	6	\$2,001	
	Ceiling - Plaster/Drywall	2nd floor SW Girls Toilet	217	SF	6	\$751	
	Floor Drain	2nd floor SW Girls Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor SW Girls Toilet	110	SF	7	\$0	
	Floor - Tile Quarry	2nd floor SW Girls Toilet	107	SF	7	\$0	
	Hand Dryer	2nd floor SW Girls Toilet	2	EA	6	\$460	
	Lavatory	2nd floor SW Girls Toilet	4	EA	6	\$1,278	
	Lighting - Lay-in	2nd floor SW Girls Toilet	3	EA	7	\$0	
	Partitions	2nd floor SW Girls Toilet	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd floor SW Girls Toilet	484	SF	7	\$0	
	Water Closet	2nd floor SW Girls Toilet	5	EA	6	\$1,680	
	Accessories	2nd Floor Women's Faculty (between locker rooms)	132	SF	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor Women's Faculty (between locker rooms)	132	SF	7	\$0	
	Doors - Transom Window	2nd Floor Women's Faculty (between locker rooms)	9	SF	6	\$152	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Wood Doors inclu hw	2nd Floor Women's Faculty (between locker rooms)	1	EA	6	\$301	
	Floor Drain	2nd Floor Women's Faculty (between locker rooms)	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	2nd Floor Women's Faculty (between locker rooms)	132	SF	6	\$279	
	Hand Dryer	2nd Floor Women's Faculty (between locker rooms)	1	EA	7	\$0	
	Lavatory	2nd Floor Women's Faculty (between locker rooms)	2	EA	6	\$639	
	Lighting - Lay-in	2nd Floor Women's Faculty (between locker rooms)	2	EA	7	\$0	
	Partitions	2nd Floor Women's Faculty (between locker rooms)	2	EA	7	\$0	
	Walls - Concrete Block	2nd Floor Women's Faculty (between locker rooms)	398	SF	7	\$0	
	Water Closet	2nd Floor Women's Faculty (between locker rooms)	2	EA	7	\$0	
	Accessories	Admin Toilet	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	Admin Toilet	16	SF	7	\$0	
	Doors - Wood Doors inclu hw	Admin Toilet	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Admin Toilet	16	SF	6	\$34	
	Lavatory	Admin Toilet	1	EA	6	\$320	
	Lighting - Pendent/Surface	Admin Toilet	1	EA	6	\$124	Missing cover
	Walls - Plaster/Drywall	Admin Toilet	139	SF	6	\$384	
	Water Closet	Admin Toilet	1	EA	6	\$336	
	Accessories	Gym (next to Gym Office)	25	SF	6	\$231	
	Ceiling - Plaster/Drywall	Gym (next to Gym Office)	25	SF	5	\$229	loose paint around light fixture
	Doors - Steel Doors incl hw	Gym (next to Gym Office)	1	EA	6	\$301	
	Floor - Tile	Gym (next to Gym Office)	25	SF	4	\$215	replace vct behind toilet
	Lavatory	Gym (next to Gym Office)	1	EA	6	\$320	
	Lighting - Pendent/Surface	Gym (next to Gym Office)	1	EA	6	\$124	
	Walls - Concrete Block	Gym (next to Gym Office)	166	SF	6	\$487	
	Water Closet	Gym (next to Gym Office)	1	EA	6	\$336	
	Accessories	in Engineer's Office	50	SF	7	\$0	
	Ceiling - Plaster/Drywall	in Engineer's Office	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	in Engineer's Office	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	in Engineer's Office	50	SF	7	\$0	
	Lavatory	in Engineer's Office	1	EA	7	\$0	
	Lighting - Pendent/Surface	in Engineer's Office	1	EA	7	\$0	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	in Engineer's Office	280	SF	7	\$0	
	Water Closet	in Engineer's Office	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	Principals Washroom	16	SF	7	\$0	
	Doors - Wood Doors inclu hw	Principals Washroom	1	EA	7	\$0	
	Floor Drain	Principals Washroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Principals Washroom	16	SF	7	\$0	
	Lavatory	Principals Washroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Principals Washroom	1	EA	7	\$0	
	Walls - Plaster/Drywall	Principals Washroom	139	SF	7	\$0	
	Water Closet	Principals Washroom	1	EA	7	\$0	

Rooms (Other Than Classrooms) Subtotal:

\$972,043

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor Corridor / 1st Floor	14,951	SF	6	\$44,898	
	Drinking Fountains - Double Water Cooler	1st Floor Corridor / 1st Floor	2	EA	6	\$754	
	Floor - Tile/Sheet	1st Floor Corridor / 1st Floor	14,951	SF	6	\$8,124	
	Lighting - Lay-in	1st Floor Corridor / 1st Floor	294	EA	6	\$34,979	
	Student Lockers - One Tier	1st Floor Corridor / 1st Floor	356	EA	6	\$33,049	
	Walls - Concrete Block	1st Floor Corridor / 1st Floor	5,502	SF	6	\$16,129	
	Walls - Metal Panel	1st Floor Corridor / 1st Floor	10,437	SF	6	\$77,908	
	Ceiling - Lay-in	2nd Floor Corridor / 2nd Floor	12,204	SF	6	\$36,649	
	Drinking Fountains - Double Water Cooler	2nd Floor Corridor / 2nd Floor	2	EA	7	\$0	
	Floor - Tile/Sheet	2nd Floor Corridor / 2nd Floor	12,204	SF	6	\$6,632	
	Lighting - Lay-in	2nd Floor Corridor / 2nd Floor	294	EA	6	\$34,979	
	Walls - Concrete Block	2nd Floor Corridor / 2nd Floor	5,502	SF	6	\$16,129	
	Walls - Metal Panel	2nd Floor Corridor / 2nd Floor	10,437	SF	6	\$77,908	
	Ceiling - Lay-in	Corridor off main office	116	SF	7	\$0	
	Floor - Carpet	Corridor off main office	116	SF	5	\$596	
	Lighting - Pendent/Surface	Corridor off main office	3	EA	7	\$0	
	Walls - Concrete Block	Corridor off main office	150	SF	6	\$440	
	Walls - Metal Panel	Corridor off main office	246	SF	6	\$1,836	
	Ceiling - Lay-in	E/W Admin Office	111	SF	7	\$0	
	Doors - Wood Doors include hw	E/W Admin Office	1	EA	6	\$301	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Floor - Carpet	E/W Admin Office	111	SF	4	\$1,021	worn, warped, stained and zippering at seams
	Lighting - Pendent/Surface	E/W Admin Office	3	EA	7	\$0	
	Walls - Concrete Block	E/W Admin Office	421	SF	7	\$0	
	Ceiling - Plaster/Drywall	Natatorium Corridor	169	SF	7	\$0	
	Floor - Tile/Sheet	Natatorium Corridor	169	SF	6	\$92	
	Lighting - Lay-in	Natatorium Corridor	3	EA	7	\$0	
	Walls - Concrete Block	Natatorium Corridor	658	SF	6	\$1,929	
Stairs							
	Ceiling - Lay-in	100 Auditorium West Stair	240	SF	6	\$721	
	Floor - Tile	100 Auditorium West Stair	240	SF	7	\$0	
	Handrails	100 Auditorium West Stair	28	LF	7	\$0	
	Lighting - Lay-in	100 Auditorium West Stair	6	EA	6	\$714	
	Stairs - Tile	100 Auditorium West Stair	32	LF	6	\$297	Note: ADA Lift in this stair.
	Walls - Concrete Block	100 Auditorium West Stair	920	SF	6	\$2,697	
	Ceiling - Plaster/Drywall	East of gym	132	SF	6	\$966	
	Floor - Tile	East of gym	138	SF	5	\$620	
	Handrails	East of gym	112	LF	6	\$971	
	Lighting - Pendent/Surface	East of gym	5	EA	6	\$619	
	Stairs - Concrete	East of gym	121	LF	6	\$1,004	
	Walls - Concrete Block	East of gym	781	SF	6	\$2,290	
	Walls - Concrete Block	East of gym	303	SF	6	\$1,018	
	Ceiling - Exposed	ST-04 (roof access @ gym)	90	SF	7	\$0	
	Floor - Tile	ST-04 (roof access @ gym)	90	SF	6	\$49	
	Handrails	ST-04 (roof access @ gym)	20	LF	7	\$0	
	Lighting - Wall Mounted	ST-04 (roof access @ gym)	1	EA	6	\$124	
	Stairs - Tile	ST-04 (roof access @ gym)	80	LF	6	\$742	
	Walls - Concrete Block	ST-04 (roof access @ gym)	950	SF	6	\$2,785	some cracks on south wall by storage door.
	Ceiling - Plaster/Drywall	West of gym	195	SF	6	\$1,428	
	Floor - Tile/Sheet	West of gym	195	SF	5	\$876	
	Handrails	West of gym	56	LF	6	\$485	
	Lighting - Pendent/Surface	West of gym	5	EA	6	\$619	
	Stairs - Concrete	West of gym	68	LF	6	\$564	
	Walls - Concrete Block	West of gym	572	SF	6	\$1,677	
Vertical Conveyance							
	Elevator - Hydraulic Elevator		1	EA	6	\$19,238	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Building Interior Subtotal:						\$434,855	

Total Building Cost

\$7,065,750

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Athletic							
	Surface - Asphalt	East / Site - East	32,950	SF	7	\$0	Snow covered
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	9	EA	7	\$0	Snow covered
	Civil/ Drainage - Site Manhole	Entire Site	11	EA	7	\$0	Snow covered
Fencing							
	Fencing - Chain Link	Entire Site	705	LF	7	\$0	
	Fencing - Chain Link	Entire Site / South East	312	LF	4	\$28,643	Leaning posts on west side of tennis court. Bent post at southeast corner or tennis court
	Fencing - New Standard Ornamental	Entire Site	835	LF	7	\$0	
	Fencing - New Standard Ornamental	Entire Site / West	920	LF	6	\$29,351	Corroded caps and base
Landscape							
	Benches	Entire Site / Courtyard	8	EA	6	\$3,440	Wood benches in east and west courtyard
	Irrigation	Entire Site / Site West	93,000	SF	7	\$0	
	Landscape - Grass	Entire Site	117,765	SF	6	\$97,674	
	Landscape - Hardscape- Concrete	Entire Site / Courtyard	370	SF	6	\$2,624	
	Landscape - Hardscape- Concrete	Entire Site	24,660	SF	7	\$0	
	Landscape - Hardscape- Concrete	Entire Site / Main Entrance	32	SF	4	\$681	Ponding at northeast entry curb cut.
	Landscape - Hardscape- Concrete	Entire Site / North West	5	SF	2	\$106	Hole in concrete at catch basin near drinking fountain on northwest of building
	Parkway trees	Entire Site	22	EA	7	\$0	
	Planting Beds/ Area	Entire Site	3,040	SF	7	\$0	
	Retaining Wall - Concrete	Entire Site / South East	180	SF	6	\$4,219	
	Trash Receptacles	Entire Site	5	EA	6	\$1,561	Plastic barrels
Parking Lot							
	Interior Plantings	Parking Lot- East	100	LF	7	\$0	
	Surface - Asphalt	Parking Lot- East	17,640	SF	6	\$42,631	
	Surface - Asphalt	Parking Lot- South	6,115	SF	5	\$27,895	Cracks

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Parking Lot							
	Vehicular Screening	Parking Lot- East	40	LF	7	\$0	
	Vehicular Screening	Parking Lot- South	84	LF	7	\$0	
Sidewalks							
	Sidewalks - Perimeter Sidewalks	Entire Site	22,825	SF	7	\$0	
Signage							
	Flag Pole - Flag Pole	Entire Site / Main Entrance	1	EA	7	\$0	
	Marquee - Building Mounted Back Lighted	Entire Site / North Façade	1	EA	6	\$0	Metal letters
	Monument - Sign-Lighted	Entire Site / North West	1	EA	6	\$0	

Site Subtotal:

\$238,827

Total Site Cost

\$238,827

Campus Total ^{2 3}

\$7,304,577

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Computer Lab	Library	1st Floor	117E		288	1	16	52	0	0	40	N	N	N
Computer Lab	Computer Lab		207	207	971	1	32	82	0	0	40	N	Y	N
Computer Lab	Computer Lab	2nd Floor	215	215	1,245	2	9	68	80	0	40	N	N	N
Computer Lab	Computer Lab	2nd Floor	227	227	1,257	1	41	92	361	14	40	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	230	230	834	2	33	78	228	19	40	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	250	250	833	1	35	72	228	19	40	N	N	N
Computer Lab	Computer Lab	2nd Floor	252	252	800	0	39	75	228	19	40	N	N	N
Multi Purpose Room	Band Room	2nd Floor	220	220	1,011	0	0	8	0	0	40	N	N	N
Office	Regular Classroom	2nd Floor	209	209	767	3	8	22	152	7	40	N	Y	N
Other Instructional Use	Regular Classroom	1st Floor	110	116	775	0	0	12	0	0	40	N	N	N
Other Instructional Use	Other Instructional Use		08 - Band Room	08 - Band Room	2,380	0	1	22	152	7	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	121	121	840	0	2	8	228	19	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	122	122	977	0	16	22	258	19	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	123	123	795	0	1	8	228	19	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	130	130	830	0	1	10	228	19	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	131	131	786	0	9	22	205	19	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	132	132	795	0	1	8	228	19	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	133	133	834	0	2	8	228	19	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	134	134	839	0	1	8	228	19	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	141	141	833	1	2	8	228	18	40	N	Y	Y
Regular Classroom	Regular Classroom		143	143	799	2	8	20	228	15	40	N	Y	N
Regular Classroom	Regular Classroom		144	144	674	1	1	6	176	10	40	N	N	N
Regular Classroom	Regular Classroom		147	147	800	1	2	8	152	16	40	N	Y	N
Regular Classroom	Regular Classroom		150	150	831	1	1	8	228	15	40	N	Y	N
Regular Classroom	Regular Classroom		151	151	811	1	1	8	200	15	40	N	N	N
Regular Classroom	Regular Classroom		152	152	811	2	1	20	228	15	40	N	Y	Y
Regular Classroom	Regular Classroom		153	153	834	1	1	6	228	15	40	N	Y	N
Regular Classroom	Regular Classroom		154	154	833	1	1	6	228	15	40	N	N	N
Regular Classroom	Regular Classroom		201	201	918	1	1	10	76	0	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	918	2	0	3	221	7	40	N	Y	N
Regular Classroom	Regular Classroom		203	203	918	3	8	14	160	0	40	N	N	N
Regular Classroom	Regular Classroom		204	204	918	1	1	22	138	7	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	210	210	799	0	25	20	219	7	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	211	211	865	0	1	66	63	0	40	N	Y	N
Regular Classroom	Regular Classroom		212	212	730	1	1	8	128	0	40	N	N	N
Regular Classroom	Regular Classroom		216	216	773	1	2	8	64	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	217	217	964	0	2	14	0	0	40	N	Y	Y

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom		218	218	773	1	2	30	0	0	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	231	231	785	0	2	8	205	19	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	232	232	794	1	9	10	228	19	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	233	233	833	0	3	8	228	19	40	N	N	Y
Regular Classroom	Regular Classroom		234	234	837	1	1	6	228	14	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	242	242	965	0	8	22	266	29	40	N	Y	N
Regular Classroom	Art Room	2nd Floor	249B	NA	924	0	1	12	266	10	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	251	251	812	0	8	22	220	19	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	253	253	840	0	10	20	228	19	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	254	254	830	0	2	6	228	19	40	N	Y	N
Science Classroom	Regular Classroom	2nd Floor	222	222	976	1	8	20	266	19	40	N	Y	N
Science Classroom	Regular Classroom	2nd Floor	224	224	660	0	1	12	167	19	40	N	N	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	221	221	1,220	0	6	58	342	28	40	N	N	Y
Science Lab Level 3	Science Lab Level 3	1st Floor	142	142	977	0	9	14	243	30	40	N	Y	N
Science Lab Level 3	Science Lab Level 3	2nd Floor	223	223	961	0	5	44	266	28	40	N	N	Y
Science Lab Level 3	Science Lab Level 3	2nd Floor	241	241	1,215	0	8	56	342	29	40	N	Y	N
Science Lab Level 3	Science Lab Level 3	2nd Floor	243	243	965	1	10	50	266	29	40	N	N	N
Special Program	Other Instructional Use	1st Floor	109	109	1,830	1	38	84	0	0	40	N	N	Y
Special Program	Regular Classroom	1st Floor	124	124	650	0	1	12	170	19	40	N	Y	N
Store Room	Regular Classroom	2nd Floor	244	244	658	0	9	28	167	9	40	N	N	N