

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1963	3	69,287	\$2,551,532
SITE				\$265,053
Campus Total			69,287	\$2,816,585

Building: Main

Category: Building Exterior

	Man Tune	Location	Quantity	Linit	Donk	Cost	Comments
-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entran							
	Entrance Control - Audio and Video	#1 N	1	EΑ	6	\$702	
	Entrance Control - Audio and Video	#6 S	1	EA	6	\$702	
	Exterior Doors - Exterior FRP Door	#1 N	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	#5 W	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#6 S	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#7 S	2	EΑ	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#8 Exit E	1	EΑ	6	\$631	
	Exterior Doors - Exterior FRP Door	#9 N	2	EA	6	\$1,263	
	Exterior Doors - Exterior Steel Door	#10 N	1	EΑ	6	\$481	
	Exterior Doors - Exterior Steel Door	#2 W	2	EΑ	6	\$961	
	Exterior Doors - Exterior Steel Door	#3 W	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#4 W	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#6.5 Exit S	2	EA	6	\$961	
	Exterior Doors - Side lite	#1 N	6	EA	6	\$1,880	
	Exterior Doors - Store Front	#11 Courtyard	1	EA	6	\$546	
	Exterior Doors - Store Front	#12 Courtayrd	1	EA	6	\$546	
	Exterior Doors - Store Front	#13 Courtyard	1	EA	6	\$546	
	Exterior Doors - Store Front	#14 Courtyard	1	EA	6	\$546	
	Exterior Doors - Transom Lite	#1 N	5	EA	6	\$1,567	
	Exterior Doors - Transom Lite	#10 N	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#5 W	1	EA	6	\$313	



Category: Building Exterior

_	tom - Type	Location	Quantity	Hoit	Dank	Coct	Comments
-	Item - Type	Location	Quantity	Unit	Rafik	Cost	Comments
Entran		#C C	4	E^	6	Ф040	
	Exterior Doors - Transom Lite	#6 S #7 S	1	EΑ	6	\$313	
	Exterior Doors - Transom Lite	_	1	EA	6	\$313	
	Exterior Stairs - Concrete	#8 Exit E	6	LF	6	\$491	
	Power Door Operator and Controls	#1 N	2	EA	6	\$0	
Founda	ation						
	Foundation - Concrete	Entire Building	890	LF	7	\$0	
	Superstructure - Concrete	Entire Building	69,287	SF	7	\$0	
Lightin	a						
Ligititi	Exterior Lighting - Wall Mounted	Entire Building	12	EA	6	\$3,465	
	Exterior Eighting - Wall Mounted	Littile Building	12	LA	O	φ3,403	
Roof S	ystem						
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Middle Roof	5	LF	5	\$14,258	Need tuck pointing
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Middle Roof	20	LF	6	\$19,094	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Middle Roof	20	LF	6	\$19,094	
	Chimney - Metal Flue	Middle Roof	12	LF	6	\$1,898	
	Coping - Metal	Main Roof	650	LF	6	\$20,877	
	Coping - Metal	Middle Roof	446	LF	6	\$14,325	
	Coping - Metal	NW High Roof	332	LF	6	\$10,663	
	Downspouts - Interior Downspouts	Main Roof	120	LF	6	\$3,988	
	Downspouts - Interior Downspouts	Middle Roof	180	LF	6	\$5,982	
	Downspouts - Interior Downspouts	NW High Roof	60	LF	6	\$1,994	
	Parapet - Parapet < 16" Height	Main Roof	650	LF	6	\$13,850	
	Parapet - Parapet < 16" Height	Middle Roof	446	LF	6	\$9,503	
	Parapet - Parapet < 16" Height	NW High Roof	332	LF	6	\$7,074	
	Roof Structure - Concrete	Main Roof	17,044	SF	7	\$0	
	Roof Structure - Concrete	Middle Roof	10,878	SF	7	\$0	
	Roof Structure - Concrete	NW High Roof	6,893	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Main Roof	4,260	SF	4	\$119,399	Ponding
	Roof - Asphalt Gravel Ballast	Main Roof	12,782	SF	5	\$301,774	
	Roof - Asphalt Gravel Ballast	Middle Roof	10,878	SF	5	\$256,822	
	Roof - Asphalt Gravel Ballast	NW High Roof	6,893	SF	5	\$162,739	
Walls							
TValls	Exterior Walls - Brick	Entire Building	18,360	SF	6	\$123,398	
	Exterior Walls - Brick Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	1,050	SF	6	\$5,961	
	Exterior Walls - Frerabricated Metal Farier Wall Exterior Walls - Stone-Cut	Entire Building Entire Building	600	SF	6	\$4,033	
	LAGIOI WAIS - STOLE-CUL	Entire Building	600	SF	O	φ 4 ,033	



3615 W 16th St Chicago, IL 60623



Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost Comme
Windo	ws					
	Curtain wall - Glazed Double Pane	Entire Building	6,515	SF	6	\$73,041
	Curtain wall - Insulated Panel	Entire Building	8,500	SF	6	\$95,295
	Curtain wall - Louver	Entire Building	160	SF	6	\$1,794
	Curtain wall - Windows	Entire Building	2,400	SF	6	\$26,907
	Lintels - Steel	Entire Building	66	LF	7	\$0
	Skylite - Glass Double-Pane	Entire Building	625	SF	6	\$14,935

Building Exterior Subtotal:

\$1,352,509

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerge	ency System						
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	15,290	SF	6	\$4,592	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	2,350	SF	6	\$874	
	Emergency A/C Power - Multipurpose Room	Entire Building / 1st Floor	4,885	SF	6	\$1,816	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	85	EΑ	6	\$17,213	
	Emergency Battery Packs - Lunchrooms	Entire Building / 1st Floor	9	EΑ	6	\$1,823	
	Emergency Battery Packs - Multipurpose Room	Entire Building / 1st Floor	11	EA	6	\$2,228	
	Emergency Battery Packs - Students Toilets	Entire Building	4	EA	6	\$810	
	Exit Signs - Corridors and Stairs	Entire Building	27	EA	7	\$0	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	3	EΑ	7	\$0	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	5	EΑ	7	\$0	
	Security System - CCTV	Entire Building	69,287	SF	6	\$20,807	
	Security System - Intrusion Detection	Entire Building	69,287	SF	6	\$17,834	
Main S	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	1	EA	6	\$8,232	
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	1	EΑ	6	\$8,662	
	PA System	Entire Building	69,287	SF	6	\$22,788	
Power	Distribution						
	Lighting and Power Panels - 100 A	Entire Building	2	EA	4	\$9,699	Panels are old and significantly deteriorated
	Lighting and Power Panels - 100 A	Entire Building	2	EΑ	7	\$0	
	Lighting and Power Panels - 100 A	Entire Building	2	EΑ	6	\$598	Emergency fuse panel
	Lighting and Power Panels - Above 100 A	Entire Building	16	EA	7	\$0	
D) (OD (D 0 -1 00					A 1 D - 1 AA (00) A



Dvorak Technology Academy

3615 W 16th St Chicago, IL 60623

Building: Main

Category: Electrical System

roup Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ower Distribution						
Lighting and Power Panels - Above 100 A	Entire Building	1	EA	4	\$6,578	Panel is old and significantly deteriorated
Main Distribution Panels - 400 - 600 amp	Entire Building	4	EA	7	\$0	
Main Distribution Panels - 400 - 600 amp	Entire Building	6	EA	7	\$0	Motor Control Center
Main Distribution Panels - Greater than 600 amp	Entire Building	4	EA	7	\$0	
Transformers - 277/480 - 120/208	Entire Building	1	EΑ	6	\$1,265	

Electrical System Subtotal: \$129,146

Building: Main

Category: Safty System


Group	Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Fire Alar	rm					
	Fire Alarm Panel	Entire Building / 1st Floor	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	Entire Building	69,287	SF	6	\$24,770
	Fire Alarm_System	Entire Building	69,287	SF	6	\$33,687

Safty System Subtotal: \$64,863

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Con	ditioning						
	Chemical Pot Feeder	Entire Building / Boiler Room	1	EA	7	\$0	
	Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons	Entire Building / Roof	1	EA	7	\$0	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	
	Glycol Feed	Entire Building / Boiler Room	1	EA	7	\$0	
	Pipes - Chilled Water Pipe- Steel	Entire Building	100	LF	7	\$0	
	Pipes - Dual Temperature Pipe- Steel	Entire Building	1,200	LF	7	\$0	
	Pressure Fill System	Entire Building / Boiler Room	1	EA	7	\$0	
Air Han	dling Systems						
	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils 6000-10000 cfm	Mechanical Room	1	EA	6	\$3,350	AHU-3 serves 1st floor corridor
	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils 6000-10000 cfm	Mechanical Room	1	EA	6	\$3,350	AHU-2 serves gymnasium/auditorium
	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils 6000-10000 cfm	Mechanical Room	1	EA	6	\$3,350	AHU-1 serves cafeteria & kitchen
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	





Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Han	dling Systems						
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / East Façade	1	EA	6	\$5,765	
Boiler S	Systems						
	Boiler Auxiliary- Condensing Hot Water - 1001 - 2000 HP	Boiler Room	2	EA	6	\$6,176	
	Chemical Pot Feeder	Boiler Room	1	EA	6	\$725	
	Condensing- Hot Water Boiler - 1001 - 2000 MBH	Boiler Room	2	EA	6	\$1,996	Direct combustion, no dampers.
	Water Fill System	Boiler Room	1	EA	6	\$1,168	
Heating	Devices						
	Cabinet Heaters - With Hot Water Coil	Entire Building / 1st Floor	1	EA	5	\$1,755	
	Cabinet Heaters - With Hot Water Coil	Entire Building	14	EA	6	\$4,961	
	Cabinet Heaters - With Hot Water Coil	Entire Building	8	EA	7	\$0	
	Fin Tube - Hot Water	Entire Building	5	LF	5	\$407	
	Fin Tube - Hot Water	Entire Building	111	LF	6	\$1,048	
	PTAC - Hot Water Heating and Self Contained Cooling	Entire Building	5	EA	6	\$1,352	
	Unit Heater - Hot Water	Boiler Room	1	EA	6	\$279	
Mechar	nical Plumbing						
	Daul Temperature Pump - 10 - 20 HP	Boiler Room	2	EA	6	\$2,485	
	Hot Water Pump - Less than 10	Mechanical Room	3	EA	6	\$3,334	AHU recirculating pumps
	Hydronic Supply and Return - Steel	Boiler Room	300	LF	7	\$0	
Temper	rature Control						
	DDC System	Entire Building	69,287	SF	6	\$39,632	
	Electric Thermostat	Entire Building	2	EA	6	\$0	Unit heater and split system.
	Thermostats - DDC	Entire Building	44	EA	6	\$0	
Unit Ve	ntilation						
	Unit Ventilators- Floor Mounted- Dual Temperature Coils (Hot/Chilled) Water	Entire Building	40	EA	6	\$49,693	
Ventilat	ion						
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EΑ	6	\$1,185	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	4	EA	7	\$0	
	Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Entire Building / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	20	EA	7	\$0	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EΑ	7	\$0	
	Roof Mounted Duct Work	Entire Building / Roof	15	LF	6	\$5,685	



Dvorak Technology Academy

3615 W 16th St Chicago, IL 60623

Building: Main

Category: Mechanical System

oup Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ntilation						
Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	6	\$1,248	Limited coverage with fire suppression.
Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	7	\$0	

Mechanical System Subtotal: \$157,951

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Wat	ter						
	Gas Heater - 150000 - 300000 BTU/HR	Boiler Room	2	EA	6	\$620	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	69,287	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	69,287	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	69,287	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	69,287	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	69,287	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	69,287	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	69,287	SF	7	\$0	
	Sanitary Piping	Entire Building	69,287	SF	7	\$0	
	Storm Piping	Entire Building	69,287	SF	6	\$60,439	
	Vent Piping	Entire Building	69,287	SF	7	\$0	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room, Elevator pit / Mechanical Room	1	EA	5	\$15,514	Running cont. per Building engineer
	Pumps - Sump-Simplex	Mechanical Room, Elevator pit	1	EA	6	\$745	Elevator pit sump

Plumbing System Subtotal: \$77,318

Building: Main

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Classroom #101 (Pre School)					
Casework	1st Floor	29	LF	6	\$732
Ceiling - Lay-in	1st Floor	1,155	SF	6	\$3,468
Doors - Side-lite	1st Floor	16	SF	6	\$267



	ory: Classrooms					_	_
_	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #101 (Pre School)						
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,155	SF	6	\$1,156	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	16	LF	6	\$343	
	Walls - Concrete Block	1st Floor	1,160	SF	6	\$3,401	
	Work Sink	1st Floor	1	EA	6	\$379	
Classro	oom #102 (Regular Classroom)						
	Casework	1st Floor	29	LF	6	\$732	
	Ceiling - Lay-in	1st Floor	685	SF	6	\$2,057	
	Ceiling - Plaster/Drywall	1st Floor	30	SF	6	\$104	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
Classro	oom #103 (Pre School)						
	Casework	1st Floor	29	LF	6	\$732	
	Ceiling - Lay-in	1st Floor	1,155	SF	6	\$3,468	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,155	SF	6	\$1,156	
	Lighting - Lay-in	1st Floor	17	EA	7	\$0	
	Marker Board	1st Floor	16	LF	6	\$343	
	Walls - Concrete Block	1st Floor	1,160	SF	6	\$3,401	
	Work Sink	1st Floor	1	EA	6	\$379	
Classro	oom #104 (Regular Classroom)						
	Casework	1st Floor	29	LF	6	\$732	
	Ceiling - Lay-in	1st Floor	685	SF	6	\$2,057	
	Ceiling - Plaster/Drywall	1st Floor	30	SF	6	\$104	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	



	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	oom #104 (Regular Classroom)						
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
Classro	oom #105 (Computer Lab)						
	Casework	1st Floor	29	LF	6	\$732	
	Ceiling - Lay-in	1st Floor	715	SF	6	\$2,147	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
Classro	oom #106/108 (Regular Classroom)						
	Casework	1st Floor	44	LF	6	\$1,111	
	Ceiling - Lay-in	1st Floor	1,370	SF	6	\$4,114	
	Ceiling - Plaster/Drywall	1st Floor	60	SF	6	\$208	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,430	SF	6	\$1,431	
	Lighting - Lay-in	1st Floor	24	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Plaster/Drywall	1st Floor	1,550	SF	6	\$4,278	
Classro	oom #107 (Regular Classroom)						
	Casework	1st Floor	29	LF	6	\$732	
	Ceiling - Lay-in	1st Floor	715	SF	6	\$2,147	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
Classro	oom #110 (Regular Classroom)						
	Casework	1st Floor	22	LF	6	\$556	
	Ceiling - Lay-in	1st Floor	685	SF	6	\$2,057	
	Ceiling - Plaster/Drywall	1st Floor	30	SF	6	\$104	



	Item - Type	Location	Quantity	Unit	Rank	Cost	Comme
	om #110 (Regular Classroom)		•				
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EΑ	7	\$0	
	Marker Board	1st Floor	20	LF	6	\$428	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
assro	om #112 (Regular Classroom)						
	Casework	1st Floor	34	LF	6	\$859	
	Ceiling - Lay-in	1st Floor	625	SF	6	\$1,877	
	Ceiling - Plaster/Drywall	1st Floor	90	SF	6	\$311	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
	Work Sink	1st Floor	1	EA	6	\$379	
ssro	om #114 (Regular Classroom)						
	Casework	1st Floor	34	LF	6	\$859	
	Ceiling - Lay-in	1st Floor	715	SF	6	\$2,147	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	715	SF	6	\$716	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	6	\$600	
	Walls - Concrete Block	1st Floor	775	SF	6	\$2,272	
	Work Sink	1st Floor	1	EA	6	\$379	
assro	om #116 (Faculty Lounge)						
	Casework	1st Floor	34	LF	6	\$859	
	Ceiling - Lay-in	1st Floor	715	SF	6	\$2,147	
	Doors - Side-lite	1st Floor	16	SF	6	\$267	
	Doors - Transom Window	1st Floor	6	SF	6	\$102	
(OD 4		D 0 -1 00	_				







tem - Type m #116 (Faculty Lounge) Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Marker Board Valls - Concrete Block Vork Sink m #201 (Regular Classroom) Casework	1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor	Quantity 1 715 12 22 775 1	EA SF EA LF SF EA	6 6 7 6	\$301 \$716 \$0 \$471 \$2,272	
Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Marker Board Valls - Concrete Block Vork Sink m #201 (Regular Classroom) Casework	1st Floor 1st Floor 1st Floor 1st Floor	715 12 22 775	SF EA LF SF	6 7 6	\$716 \$0 \$471	
Lighting - Lay-in Marker Board Walls - Concrete Block Work Sink m #201 (Regular Classroom) Casework	1st Floor 1st Floor 1st Floor 1st Floor	12 22 775	EA LF SF	7	\$0 \$471	
Marker Board Valls - Concrete Block Vork Sink m #201 (Regular Classroom) Casework	1st Floor 1st Floor 1st Floor	22 775	LF SF	6	\$471	
Valls - Concrete Block Vork Sink m #201 (Regular Classroom) Casework	1st Floor 1st Floor	775	SF			
Work Sink m #201 (Regular Classroom) Casework	1st Floor			6	¢2 272	
m #201 (Regular Classroom) Casework		1	FΔ		φ ∠ , ∠ /∠	
Casework				6	\$379	
Datting Lawring	2nd Floor	33	LF	6	\$833	
Ceiling - Lay-in	2nd Floor	890	SF	6	\$2,673	
Doors - Side-lite	2nd Floor	16	SF	6	\$267	
Doors - Transom Window	2nd Floor	6	SF	6	\$102	
Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
Floor - Tile/Sheet	2nd Floor	890	SF	6	\$891	
ighting - Lay-in	2nd Floor	12	EA	7	\$0	
Marker Board	2nd Floor	28	LF	6	\$600	
Valls - Concrete Block	2nd Floor	930	SF	6	\$2,726	
Vork Sink	2nd Floor	1	EA	6	\$379	
n #202 (Regular Classroom)						
Casework	2nd Floor	29	LF	6	\$732	
Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
Doors - Side-lite	2nd Floor	16	SF	6	\$267	
Doors - Transom Window	2nd Floor	6	SF	6	\$102	
Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
ighting - Lay-in	2nd Floor	12	EA	7	\$0	
Marker Board	2nd Floor	28	LF	6	\$600	
Valls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
m #203 (Regular Classroom)						
Casework	2nd Floor	34	LF	6	\$859	
Ceiling - Lay-in	2nd Floor	890	SF	6	\$2,673	
Doors - Side-lite	2nd Floor	16	SF	6	\$267	
Doors - Transom Window	2nd Floor	6	SF	6	\$102	
Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
Floor - Tile/Sheet	2nd Floor	890	SF	6	\$891	
ighting - Lay-in	2nd Floor	12	EA	7	\$0	
Marker Board	2nd Floor	28	LF	6	\$600	
	Doors - Side-life Doors - Transom Window Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Marker Board Walls - Concrete Block Work Sink m #202 (Regular Classroom) Casework Ceiling - Lay-in Doors - Side-lite Doors - Transom Window Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Marker Board Walls - Concrete Block m #203 (Regular Classroom) Casework Ceiling - Lay-in Doors - Side-lite Doors - Transom Window Coors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Doors - Side-lite Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Marker Board	Doors - Transom Window Doors - Wood Doors inclu hw Floor - Tile/Sheet Lighting - Lay-in Marker Board Walls - Concrete Block Work Sink Doors - Side-lite Doors - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor Marker Board Doors - Transom Window Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Side-lite Doors - Side-lite Doors - Transom Window Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Side-lite Doors - Transom Window Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors Inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Side-lite Doors - Transom Window Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Doors Inclu hw Ploor - Tile/Sheet Lighting - Lay-in Doors - Wood Ploor -	Doors - Transom Window 2nd Floor 6 Doors - Wood Doors inclu hw 2nd Floor 1 Floor - Tile/Sheet 2nd Floor 890 Lighting - Lay-in 2nd Floor 28 Walls - Concrete Block 2nd Floor 930 Work Sink 2nd Floor 93 Work Sink 2nd Floor 1 m #202 (Regular Classroom) 2nd Floor 71 Casework 2nd Floor 715 Casework 2nd Floor 715 Coors - Side-lite 2nd Floor 16 Coors - Wood Doors inclu hw 2nd Floor 1 Cloors - Wood Doors inclu hw 2nd Floor 715 Cloors - Tile/Sheet 2nd Floor 715 Lighting - Lay-in 2nd Floor 28 Walls - Concrete Block 2nd Floor 75 m #203 (Regular Classroom) 2nd Floor 89 Caeswork 2nd Floor 89 Coors - Transom Window 2nd Floor 16 Coors - Transom Window 2nd Floor 16 <td>Doors - Transom Window 2nd Floor 6 SF Doors - Wood Doors inclu hw 2nd Floor 1 EA Floor - Tile/Sheet 2nd Floor 890 SF Lighting - Lay-in 2nd Floor 12 EA Walks - Board 2nd Floor 930 SF Walls - Concrete Block 2nd Floor 930 SF Work Sink 2nd Floor 93 SF Work Sink 2nd Floor 29 LF Ceiling - Lay-in 2nd Floor 715 SF Doors - Side-lite 2nd Floor 16 SF Doors - Side-lite 2nd Floor 16 SF Doors - Wood Doors inclu hw 2nd Floor 1 EA Cloor - Tile/Sheet 2nd Floor 715 SF Lighting - Lay-in 2nd Floor 12 EA Marker Board 2nd Floor 28 LF Walls - Concrete Block 2nd Floor 34 LF Doors - Side-lite 2nd Floor 80</td> <td>Doors - Transom Window 2nd Floor 6 SF 6 Doors - Wood Doors inclu hw 2nd Floor 1 EA 6 Floor - Tile/Sheet 2nd Floor 890 SF 6 Lighting - Lay-in 2nd Floor 28 LF 6 Malls - Concrete Block 2nd Floor 930 SF 6 Walls - Concrete Block 2nd Floor 930 SF 6 Walls - Concrete Block 2nd Floor 930 SF 6 Walls - Concrete Block 2nd Floor 1 EA 6 Work Sink 2nd Floor 29 LF 6 Work Sink 2nd Floor 29 LF 6 Eelling - Lay-in 2nd Floor 715 SF 6 Doors - Side-lite 2nd Floor 1 EA 6 Doors - Wood Doors inclu hw 2nd Floor 1 EA 6 Cloors - Tile/Sheet 2nd Floor 12 EA 7 Walls - Concrete Block</td> <td>Doors - Transom Window 2nd Floor 6 SF 6 \$102 Doors - Wood Doors inclu hw 2nd Floor 1 EA 6 \$301 Idoor - Tile/Sheet 2nd Floor 89 SF 6 \$891 Jighting - Lay-in 2nd Floor 12 EA 7 \$0 Marker Board 2nd Floor 28 LF 6 \$600 Walls - Concrete Block 2nd Floor 930 SF 6 \$2,726 Work Sink 2nd Floor 930 SF 6 \$2,726 Work Sink 2nd Floor 930 SF 6 \$2,726 Work Sink 2nd Floor 29 LF 6 \$379 ##202 (Regular Classroom) 2nd Floor 15 SF 6 \$2,147 Doors Side-lite 2nd Floor 16 SF 6 \$2,67 Doors - Wood Doors inclu hw 2nd Floor 15 SF 6 \$102 Coors - Wood Doors inclu hw 2nd Floor</td>	Doors - Transom Window 2nd Floor 6 SF Doors - Wood Doors inclu hw 2nd Floor 1 EA Floor - Tile/Sheet 2nd Floor 890 SF Lighting - Lay-in 2nd Floor 12 EA Walks - Board 2nd Floor 930 SF Walls - Concrete Block 2nd Floor 930 SF Work Sink 2nd Floor 93 SF Work Sink 2nd Floor 29 LF Ceiling - Lay-in 2nd Floor 715 SF Doors - Side-lite 2nd Floor 16 SF Doors - Side-lite 2nd Floor 16 SF Doors - Wood Doors inclu hw 2nd Floor 1 EA Cloor - Tile/Sheet 2nd Floor 715 SF Lighting - Lay-in 2nd Floor 12 EA Marker Board 2nd Floor 28 LF Walls - Concrete Block 2nd Floor 34 LF Doors - Side-lite 2nd Floor 80	Doors - Transom Window 2nd Floor 6 SF 6 Doors - Wood Doors inclu hw 2nd Floor 1 EA 6 Floor - Tile/Sheet 2nd Floor 890 SF 6 Lighting - Lay-in 2nd Floor 28 LF 6 Malls - Concrete Block 2nd Floor 930 SF 6 Walls - Concrete Block 2nd Floor 930 SF 6 Walls - Concrete Block 2nd Floor 930 SF 6 Walls - Concrete Block 2nd Floor 1 EA 6 Work Sink 2nd Floor 29 LF 6 Work Sink 2nd Floor 29 LF 6 Eelling - Lay-in 2nd Floor 715 SF 6 Doors - Side-lite 2nd Floor 1 EA 6 Doors - Wood Doors inclu hw 2nd Floor 1 EA 6 Cloors - Tile/Sheet 2nd Floor 12 EA 7 Walls - Concrete Block	Doors - Transom Window 2nd Floor 6 SF 6 \$102 Doors - Wood Doors inclu hw 2nd Floor 1 EA 6 \$301 Idoor - Tile/Sheet 2nd Floor 89 SF 6 \$891 Jighting - Lay-in 2nd Floor 12 EA 7 \$0 Marker Board 2nd Floor 28 LF 6 \$600 Walls - Concrete Block 2nd Floor 930 SF 6 \$2,726 Work Sink 2nd Floor 930 SF 6 \$2,726 Work Sink 2nd Floor 930 SF 6 \$2,726 Work Sink 2nd Floor 29 LF 6 \$379 ##202 (Regular Classroom) 2nd Floor 15 SF 6 \$2,147 Doors Side-lite 2nd Floor 16 SF 6 \$2,67 Doors - Wood Doors inclu hw 2nd Floor 15 SF 6 \$102 Coors - Wood Doors inclu hw 2nd Floor



oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
assro	om #203 (Regular Classroom)						
	Walls - Concrete Block	2nd Floor	930	SF	6	\$2,726	
	Work Sink	2nd Floor	1	EA	6	\$379	
	#100.4 (Ou '-1 Du)						
assro	om #204 (Special Program)	2 15				# 700	
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
assro	om #205 (Regular Classroom)						
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
		2.10 1 1001	770	0.	Ü	Ψ=,=;=	
ssro	om #206 (Regular Classroom)					^-	
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
assro	om #207 (Regular Classroom)						
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	



	ory: Classrooms				_	_	_
_	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #207 (Regular Classroom)						
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
Classro	oom #208 (Regular Classroom)						
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
Classro	oom #210 (Music Room)						
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EΑ	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
Classro	oom #212 (Regular Classroom)						
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	



Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #212 (Regular Classroom)						
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
Classro	om #214 (Computer Lab)						
0 .u00.0	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
					-	- -,	
Classro	om #216 (Regular Classroom) Casework	2nd Floor	29	LF	6	\$732	
		2nd Floor					
	Ceiling - Lay-in		715	SF	6	\$2,147	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	715	SF	6	\$716	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	6	\$600	
	Walls - Concrete Block	2nd Floor	775	SF	6	\$2,272	
Classro	om #301 (Regular Classroom)						
	Casework	3rd Floor	33	LF	6	\$833	
	Ceiling - Lay-in	3rd Floor	890	SF	6	\$2,673	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	890	SF	6	\$891	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	930	SF	6	\$2,726	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classro	om #302 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	







	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	oom #302 (Regular Classroom)			-			-
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EΑ	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classro	oom #303 (Regular Classroom)						
	Casework	3rd Floor	33	LF	6	\$833	
	Ceiling - Lay-in	3rd Floor	890	SF	6	\$2,673	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	3rd Floor	890	SF	6	\$891	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	930	SF	6	\$2,726	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classro	oom #304 (Regular Classroom)						
	Casework	3rd Floor	22	LF	6	\$556	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classro	oom #305 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
D) (OD (D 44 (00					A 1 D - 1 - 44/00



Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	om #305 (Regular Classroom)						
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classro	om #306 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EΑ	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classro	oom #307 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classro	om #308 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EΑ	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classro	om #310 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	







	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	oom #310 (Regular Classroom)	Location	Quantity	Onit	Nuin	COSI	Comments
Giassi	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Classr	oom #312 (Regular Classroom)	5.4 . 155.		٠.		Ψ=,=:=	
Classic	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$2,147	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	
Class		5.5.100	770	٥.	Ü	Ψ=,=12	
Classro	oom #314 (Regular Classroom)	Ond Floor	00			#700	
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102 \$201	
	Doors - Wood Doors inclu hw	3rd Floor	·	EA SF	6	\$301 \$716	
	Floor - Tile/Sheet	3rd Floor 3rd Floor	715	_	6	\$716	
	Lighting - Lay-in		12	EA	7	\$0 \$600	
	Marker Board Walls - Concrete Block	3rd Floor 3rd Floor	28 775	LF SF	6	\$600 \$2,272	
		314 F1001	115	51	6	\$2,212	
Classro	oom #316 (Regular Classroom)						
	Casework	3rd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	715	SF	6	\$716	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	6	\$600	
	Walls - Concrete Block	3rd Floor	775	SF	6	\$2,272	



Dvorak Technology Academy

3615 W 16th St Chicago, IL 60623

Building: Main

Category: Classrooms

Group Item - Type Location Quantity Unit Rank Cost Comments


Classroom #316 (Regular Classroom)

Classrooms Subtotal: \$268,334

Building: Main

3roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
dmini	strative Suites/Offices						
	Doors - Wood Doors inclu hw	Engineers Office	1	EA	6	\$301	
	Floor - Concrete	Engineers Office	130	SF	6	\$69	
	Lighting - Pendent/Surface	Engineers Office	4	EΑ	7	\$0	
	Power Distribution	Engineers Office	4	EΑ	7	\$0	
	Walls - Plaster/Drywall	Engineers Office	420	SF	6	\$1,159	
	Ceiling - Lay-in	Gym Office	90	SF	6	\$270	
	Doors - Wood Doors inclu hw	Gym Office	1	EΑ	6	\$301	
	Floor - Tile/Sheet	Gym Office	90	SF	6	\$90	
	Lighting - Lay-in	Gym Office	2	EΑ	7	\$0	
	Power Distribution	Gym Office	4	EΑ	7	\$0	
	Walls - Concrete Block	Gym Office	280	SF	6	\$821	
	Ceiling - Plaster/Drywall	Kitchen Office	50	SF	6	\$173	
	Doors - Wood Doors inclu hw	Kitchen Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Kitchen Office	50	SF	6	\$50	
	Lighting - Lay-in	Kitchen Office	1	EΑ	7	\$0	
	Power Distribution	Kitchen Office	2	EA	7	\$0	
	Walls - Concrete Block	Kitchen Office	300	SF	6	\$879	
	Ceiling - Lay-in	Main Office 127	570	SF	6	\$1,712	
	Doors - Side-lite	Main Office 127	50	SF	6	\$836	
	Doors - Store Front	Main Office 127	1	EA	6	\$1,208	
	Doors - Transom Window	Main Office 127	30	SF	6	\$508	
	Floor - Carpet	Main Office 127	470	SF	6	\$1,001	
	Floor - Tile/Sheet	Main Office 127	100	SF	6	\$100	
	Lighting - Lay-in	Main Office 127	11	EA	7	\$0	
	Lighting - Pendent/Surface	Main Office 127	2	EA	7	\$0	
	Power Distribution	Main Office 127	10	EA	7	\$0	
	Walls - Concrete Block	Main Office 127	1,180	SF	6	\$3,459	
	Ceiling - Lay-in	Main Office -B	360	SF	6	\$1,081	
	Doors - Wood Doors inclu hw	Main Office -B	1	EA	6	\$301	
	Floor - Carpet	Main Office -B	360	SF	6	\$767	







oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lminis	strative Suites/Offices						
	Lighting - Lay-in	Main Office -B	6	EA	7	\$0	
	Power Distribution	Main Office -B	10	EA	7	\$0	
	Walls - Concrete Block	Main Office -B	780	SF	6	\$2,287	
	Ceiling - Lay-in	Main Office-A	170	SF	6	\$511	
	Doors - Wood Doors inclu hw	Main Office-A	1	EA	6	\$301	
	Floor - Carpet	Main Office-A	170	SF	6	\$362	
	Lighting - Lay-in	Main Office-A	3	EA	7	\$0	
	Power Distribution	Main Office-A	6	EA	7	\$0	
	Walls - Concrete Block	Main Office-A	520	SF	6	\$1,524	
	Ceiling - Lay-in	Room 134	320	SF	6	\$961	
	Doors - Wood Doors inclu hw	Room 134	1	EA	6	\$301	
	Floor - Tile/Sheet	Room 134	320	SF	6	\$320	
	Lighting - Lay-in	Room 134	5	EA	7	\$0	
	Power Distribution	Room 134	10	EA	7	\$0	
	Walls - Concrete Block	Room 134	700	SF	6	\$2,052	
/mnas	sia						
	Ceiling - Exposed	1st Floor	3,735	SF	6	\$5,555	
	Ceiling - Plaster/Drywall	1st Floor	1,150	SF	6	\$6,348	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Wood	1st Floor	4,885	SF	6	\$34,439	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	20	EA	7	\$0	
	Scoreboards	1st Floor	1	EA	5	\$10,580	Inoperable
	Stage Curtain	1st Floor	12	EA	6	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	6	\$12,369	
	Stage-Stairs - Wood	1st Floor	9	LF	6	\$106	
	Walls - Concrete Block	1st Floor	7,800	SF	6	\$22,866	
tchen							
	Ceiling - Plaster/Drywall	1st Floor	800	SF	6	\$2,768	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Floor	800	SF	6	\$1,693	
	Lighting - Pendent/Surface	1st Floor	12	EA	7	\$0	
	Serving Line	1st Floor	20	LF	6	\$1,190	
	Walls - Tile Ceramic/ Porcelain	1st Floor	1,200	SF	6	\$2,711	
ınch &	& Multipurpose Room						
	Ceiling - Lay-in	1st Floor	2,350	SF	6	\$7,057	




oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ınch (& Multipurpose Room						
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	2,350	SF	6	\$2,352	
	Lighting - Lay-in	1st Floor	26	EA	7	\$0	
	Walls - Concrete Block	1st Floor	2,650	SF	6	\$7,768	
echar	nical/ Service Rooms						
	Boiler Room	1st Floor	2,500	SF	6	\$17,911	
	Janitor's Closet	1st Floor	138	SF	6	\$989	
	Janitor's Closet	2nd Floor	138	SF	6	\$989	
	Janitor's Closet	3rd Floor	138	SF	6	\$989	
estroc	om						
	Accessories	101	28	SF	6	\$258	
	Ceiling - Plaster/Drywall	101	28	SF	6	\$97	
	Doors - Wood Doors inclu hw	101	1	EA	6	\$301	
	Floor Drain	101	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	101	28	SF	6	\$59	
	Lavatory	101	1	EA	6	\$320	
	Lighting - Pendent/Surface	101	1	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	101	170	SF	6	\$384	
	Water Closet	101	1	EA	6	\$336	
	Accessories	103	28	SF	6	\$258	
	Ceiling - Plaster/Drywall	103	28	SF	6	\$97	
	Doors - Wood Doors inclu hw	103	1	EA	6	\$301	
	Floor Drain	103	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	103	28	SF	6	\$59	
	Lavatory	103	1	EA	6	\$320	
	Lighting - Pendent/Surface	103	1	EA	7	\$0	
	Walls - Tile Ceramic/ Porcelain	103	170	SF	6	\$384	
	Water Closet	103	1	EA	6	\$336	
	Accessories	1st FL Men North	90	SF	6	\$830	
	Ceiling - Plaster/Drywall	1st FL Men North	90	SF	6	\$311	
	Doors - Wood Doors inclu hw	1st FL Men North	1	EA	6	\$301	
	Floor Drain	1st FL Men North	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FL Men North	90	SF	6	\$190	
	Hand Dryer	1st FL Men North	1	EA	6	\$230	
	Lavatory	1st FL Men North	2	EA	6	\$639	



Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Partitions	1st FL Men North	1	EA	6	\$297	
	Urinals	1st FL Men North	1	EA	6	\$336	
	Walls - Tile Ceramic/ Porcelain	1st FL Men North	180	SF	6	\$407	
	Water Closet	1st FL Men North	1	EΑ	6	\$336	
	Accessories	1st FL Women North	90	SF	6	\$830	
	Accessories	1st FL Women North	90	SF	6	\$830	
	Ceiling - Plaster/Drywall	1st FL Women North	90	SF	6	\$311	
	Ceiling - Plaster/Drywall	1st FL Women North	90	SF	6	\$311	
	Doors - Wood Doors inclu hw	1st FL Women North	1	EΑ	6	\$301	
	Doors - Wood Doors inclu hw	1st FL Women North	1	EΑ	6	\$301	
	Floor Drain	1st FL Women North	1	EA	6	\$1,059	
	Floor Drain	1st FL Women North	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FL Women North	90	SF	6	\$190	
	Floor - Tile Ceramic/ Porcelain	1st FL Women North	90	SF	6	\$190	
	Hand Dryer	1st FL Women North	1	EA	6	\$230	
	Hand Dryer	1st FL Women North	1	EA	6	\$230	
	Lavatory	1st FL Women North	2	EA	6	\$639	
	Lavatory	1st FL Women North	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st FL Women North	3	EA	7	\$0	
	Lighting - Pendent/Surface	1st FL Women North	3	EA	7	\$0	
	Partitions	1st FL Women North	2	EA	6	\$594	
	Partitions	1st FL Women North	2	EA	6	\$594	
	Walls - Tile Ceramic/ Porcelain	1st FL Women North	180	SF	6	\$407	
	Walls - Tile Ceramic/ Porcelain	1st FL Women North	180	SF	6	\$407	
	Water Closet	1st FL Women North	2	EA	6	\$672	
	Water Closet	1st FL Women North	2	EA	6	\$672	
	Accessories	1st floor boys	235	SF	6	\$2,168	
	Ceiling - Plaster/Drywall	1st floor boys	235	SF	6	\$813	
	Doors - Wood Doors inclu hw	1st floor boys	1	EA	6	\$301	
	Floor Drain	1st floor boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor boys	235	SF	6	\$497	
	Hand Dryer	1st floor boys	2	EA	6	\$460	
	Lavatory	1st floor boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st floor boys	5	EA	7	\$0	
	Partitions	1st floor boys	2	EA	6	\$594	
	Urinals	1st floor boys	1	EA	6	\$336	
	Urinals	1st floor boys	4	EΑ	6	\$1,344	








oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stro	om						
	Walls - Tile Ceramic/ Porcelain	1st floor boys	600	SF	6	\$1,356	
	Water Closet	1st floor boys	2	EA	6	\$672	
	Accessories	1st floor girls	330	SF	6	\$3,044	
	Ceiling - Plaster/Drywall	1st floor girls	240	SF	6	\$831	
	Doors - Wood Doors inclu hw	1st floor girls	1	EA	6	\$301	
	Floor Drain	1st floor girls	1	EA	6	\$1,059	
	Floor - Terrazzo	1st floor girls	15	SF	7	\$0	
	Floor - Tile Ceramic/ Porcelain	1st floor girls	225	SF	6	\$476	
	Hand Dryer	1st floor girls	2	EA	6	\$460	
	Lavatory	1st floor girls	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st floor girls	5	EA	7	\$0	
	Partitions	1st floor girls	5	EA	6	\$1,485	
	Walls - Concrete Block	1st floor girls	10	SF	6	\$29	
	Walls - Tile Ceramic/ Porcelain	1st floor girls	590	SF	6	\$1,333	
	Water Closet	1st floor girls	5	EA	6	\$1,680	
	Ceiling - Plaster/Drywall	1st Floor	135	SF	6	\$467	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Terrazzo	1st Floor	55	SF	6	\$120	
	Floor - Tile Ceramic/ Porcelain	1st Floor	80	SF	6	\$169	
	Hand Dryer	1st Floor	1	EA	6	\$230	
	Lavatory	1st Floor	1	EA	6	\$320	
	Lighting - Lay-in	1st Floor	1	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	1	EA	7	\$0	
	Walls - Concrete Block	1st Floor	480	SF	6	\$1,407	
	Water Closet	1st Floor	1	EA	6	\$336	
	Accessories	2nd floor boys	235	SF	6	\$2,168	
	Ceiling - Plaster/Drywall	2nd floor boys	235	SF	6	\$813	
	Doors - Wood Doors inclu hw	2nd floor boys	1	EA	6	\$301	
	Floor Drain	2nd floor boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor boys	235	SF	6	\$497	
	Hand Dryer	2nd floor boys	2	EA	6	\$460	
	Lavatory	2nd floor boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd floor boys	4	EA	7	\$0	
	Partitions	2nd floor boys	2	EA	6	\$594	
	Urinals	2nd floor boys	5	EA	6	\$1,680	
	Walls - Tile Ceramic/ Porcelain	2nd floor boys	600	SF	6	\$1,356	
	Water Closet	2nd floor boys	2	EΑ	6	\$672	




oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stroc	om						
	Accessories	2nd floor girls	330	SF	6	\$3,044	
	Ceiling - Plaster/Drywall	2nd floor girls	330	SF	6	\$1,142	
	Doors - Wood Doors inclu hw	2nd floor girls	1	EA	6	\$301	
	Floor Drain	2nd floor girls	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd floor girls	20	SF	7	\$0	
	Floor - Tile Ceramic/ Porcelain	2nd floor girls	310	SF	6	\$656	
	Hand Dryer	2nd floor girls	2	EA	6	\$460	
	Lavatory	2nd floor girls	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd floor girls	6	EA	7	\$0	
	Partitions	2nd floor girls	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd floor girls	25	SF	6	\$73	
	Walls - Tile Ceramic/ Porcelain	2nd floor girls	730	SF	6	\$1,649	
	Water Closet	2nd floor girls	5	EA	6	\$1,680	
	Accessories	2nd floor unisex	108	SF	6	\$996	
	Ceiling - Lay-in	2nd floor unisex	108	SF	6	\$324	
	Doors - Wood Doors inclu hw	2nd floor unisex	1	EΑ	6	\$301	
	Floor Drain	2nd floor unisex	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor unisex	51	SF	6	\$108	
	Floor - Tile/Sheet	2nd floor unisex	57	SF	6	\$57	
	Hand Dryer	2nd floor unisex	1	EΑ	6	\$230	
	Lavatory	2nd floor unisex	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd floor unisex	2	EA	7	\$0	
	Walls - Concrete Block	2nd floor unisex	325	SF	6	\$953	
	Walls - Tile Ceramic/ Porcelain	2nd floor unisex	95	SF	6	\$215	
	Water Closet	2nd floor unisex	1	EΑ	6	\$336	
	Accessories	3rd floor boys	235	SF	6	\$2,168	
	Ceiling - Plaster/Drywall	3rd floor boys	235	SF	6	\$813	
	Doors - Wood Doors inclu hw	3rd floor boys	1	EA	6	\$301	
	Floor Drain	3rd floor boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd floor boys	235	SF	6	\$497	
	Hand Dryer	3rd floor boys	2	EA	6	\$460	
	Lavatory	3rd floor boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	3rd floor boys	4	EA	7	\$0	
	Partitions	3rd floor boys	2	EA	6	\$594	
	Urinals	3rd floor boys	5	EA	6	\$1,680	
	Walls - Tile Ceramic/ Porcelain	3rd floor boys	600	SF	6	\$1,356	
	Water Closet	3rd floor boys	2	EA	6	\$672	







auc	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stro	•	2004.0.1	Quantity	O.I.I.C	raint	0001	
	Accessories	3rd floor girls	330	SF	6	\$3,044	
	Ceiling - Plaster/Drywall	3rd floor girls	330	SF	6	\$1,142	
	Doors - Wood Doors inclu hw	3rd floor girls	1	EΑ	6	\$301	
	Floor - Terrazzo	3rd floor girls	20	SF	7	\$0	
	Floor - Tile Ceramic/ Porcelain	3rd floor girls	310	SF	6	\$656	
	Hand Dryer	3rd floor girls	2	EΑ	6	\$460	
	Lavatory	3rd floor girls	3	EΑ	6	\$959	
	Lighting - Pendent/Surface	3rd floor girls	6	EA	7	\$0	
	Partitions	3rd floor girls	5	EΑ	6	\$1,485	
	Walls - Concrete Block	3rd floor girls	25	SF	6	\$73	
	Walls - Tile Ceramic/ Porcelain	3rd floor girls	730	SF	6	\$1,649	
	Water Closet	3rd floor girls	5	EA	6	\$1,680	
	Accessories	3rd floor women's	108	SF	6	\$996	
	Ceiling - Lay-in	3rd floor women's	108	SF	6	\$324	
	Doors - Wood Doors inclu hw	3rd floor women's	1	EA	6	\$301	
	Floor Drain	3rd floor women's	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd floor women's	51	SF	6	\$108	
	Floor - Tile/Sheet	3rd floor women's	57	SF	6	\$57	
	Hand Dryer	3rd floor women's	1	EA	6	\$230	
	Lavatory	3rd floor women's	1	EA	6	\$320	
	Lighting - Pendent/Surface	3rd floor women's	2	EΑ	7	\$0	
	Walls - Concrete Block	3rd floor women's	325	SF	6	\$953	
	Walls - Tile Ceramic/ Porcelain	3rd floor women's	95	SF	6	\$215	
	Water Closet	3rd floor women's	1	EΑ	6	\$336	
	Accessories	Between rooms 106 and 110	90	SF	6	\$830	
	Ceiling - Plaster/Drywall	Between rooms 106 and 110	90	SF	6	\$311	
	Doors - Wood Doors inclu hw	Between rooms 106 and 110	1	EA	6	\$301	
	Floor Drain	Between rooms 106 and 110	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Between rooms 106 and 110	90	SF	6	\$190	
	Hand Dryer	Between rooms 106 and 110	1	EA	6	\$230	
	Lavatory	Between rooms 106 and 110	2	EA	6	\$639	
	Lighting - Pendent/Surface	Between rooms 106 and 110	3	EA	7	\$0	
	Partitions	Between rooms 106 and 110	2	EA	6	\$594	
	Walls - Tile Ceramic/ Porcelain	Between rooms 106 and 110	180	SF	6	\$407	
	Water Closet	Between rooms 106 and 110	2	EA	6	\$672	
	Accessories	Boiler Room	135	SF	6	\$1,245	
	Ceiling - Plaster/Drywall	Boiler Room	135	SF	6	\$467	





Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Doors - Wood Doors inclu hw	Boiler Room	1	EA	6	\$301	
	Floor Drain	Boiler Room	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Boiler Room	40	SF	6	\$85	
	Floor - Tile/Sheet	Boiler Room	100	SF	6	\$100	
	Lavatory	Boiler Room	1	EA	6	\$320	
	Lighting - Pendent/Surface	Boiler Room	3	EA	7	\$0	
	Showers	Boiler Room	1	EA	6	\$311	
	Student Lockers - One Tier	Boiler Room	10	EA	6	\$928	
	Walls - Concrete Block	Boiler Room	1,040	SF	6	\$3,049	
	Walls - Tile	Boiler Room	120	SF	6	\$263	
	Water Closet	Boiler Room	1	EA	6	\$336	
	Accessories	In main office A	90	SF	6	\$830	
	Ceiling - Plaster/Drywall	In main office A	90	SF	6	\$311	
	Doors - Wood Doors inclu hw	In main office A	1	EA	6	\$301	
	Floor Drain	In main office A	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	In main office A	90	SF	6	\$190	
	Hand Dryer	In main office A	1	EA	6	\$230	
	Lavatory	In main office A	2	EA	6	\$639	
	Lighting - Pendent/Surface	In main office A	3	EA	7	\$0	
	Partitions	In main office A	2	EA	6	\$594	
	Walls - Tile Ceramic/ Porcelain	In main office A	180	SF	6	\$407	
	Water Closet	In main office A	2	EA	6	\$672	
	Accessories	Kitchen Office	40	SF	6	\$369	
	Ceiling - Plaster/Drywall	Kitchen Office	40	SF	6	\$138	
	Doors - Wood Doors inclu hw	Kitchen Office	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Kitchen Office	40	SF	6	\$85	
	Lavatory	Kitchen Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	Kitchen Office	1	EA	7	\$0	
	Walls - Concrete Block	Kitchen Office	90	SF	6	\$264	
	Walls - Tile Ceramic/ Porcelain	Kitchen Office	90	SF	6	\$203	
	Water Closet	Kitchen Office	1	EA	6	\$336	
	vvalei Closet	rationism office	'	LA		ψυυ	

Rooms (Other Than Classrooms) Subtotal:

\$293,119

Building: Main

Category: Building Interior

Group Item - Type Location Quantity Unit Rank Cost Comments



Category: Building Interior

up	Item - Type	Location	Quantity	Unit	Rank	Cost	Comm
rido	or .						
	Ceiling - Lay-in	1st Floor	8,990	SF	6	\$26,997	
	Doors - Steel Doors incl hw	1st Floor	10	EA	6	\$3,010	
	Doors - Transom Window	1st Floor	80	EΑ	6	\$1,354	
	Drinking Fountains - Single Fountain	1st Floor	5	EΑ	6	\$1,379	
	Floor - Terrazzo	1st Floor	8,990	SF	7	\$0	
	Lighting - Lay-in	1st Floor	85	EΑ	7	\$0	
	Walls - Concrete Block	1st Floor	5,200	SF	6	\$15,244	
	Walls - Structural Glazed Tile	1st Floor	7,734	SF	6	\$24,331	
	Ceiling - Lay-in	2nd Floor	2,940	SF	6	\$8,829	
	Drinking Fountains - Single Fountain	2nd Floor	2	EΑ	6	\$551	
	Floor - Terrazzo	2nd Floor	2,940	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	36	EA	7	\$0	
	Student Lockers - Two Tiers	2nd Floor	182	EA	6	\$8,448	
	Walls - Concrete Block	2nd Floor	5,860	SF	6	\$17,179	
	Ceiling - Lay-in	3rd Floor	2,940	SF	6	\$8,829	
	Drinking Fountains - Single Fountain	3rd Floor	2	EΑ	6	\$551	
	Floor - Terrazzo	3rd Floor	2,940	SF	6	\$24,679	
	Lighting - Lay-in	3rd Floor	19	EΑ	7	\$0	
	Student Lockers - Two Tiers	3rd Floor	182	EΑ	6	\$8,448	
	Walls - Concrete Block	3rd Floor	5,860	SF	6	\$17,179	
ety							
Ly	Security Cameras	1st Floor / Entire Building	7	EA	6	\$1,358	
	Security Cameras	1st Floor / Entire Building	30	EA	6	\$5,821	
	Coodiny Carneras	Tot Floor / Entire Ballating	00		Ü	ψ0,021	
rs							
	Ceiling - Plaster/Drywall	North Stair	210	SF	6	\$1,538	
	Floor - Terrazzo	North Stair	210	SF	7	\$0	
	Handrails	North Stair	88	LF	6	\$763	
	Lighting - Pendent/Surface	North Stair	4	EA	7	\$0	
	Stairs - Terrazzo	North Stair	44	LF	7	\$0	
	Walls - Plaster/Drywall	North Stair	1,860	SF	6	\$5,133	
	Ceiling - Plaster/Drywall	South Stair	210	SF	6	\$1,538	
	Floor - Terrazzo	South Stair	210	SF	7	\$0	
	Handrails	South Stair	88	LF	6	\$763	
	Lighting - Pendent/Surface	South Stair	4	EA	7	\$0	
	Stairs - Terrazzo	South Stair	44	LF	7	\$0	
	Walls - Plaster/Drywall	South Stair	1,860	SF	6	\$5,133	

Dvorak Technology Academy

3615 W 16th St Chicago, IL 60623

Building: Main

Category: Building Interior

Group Item - Type	Location	Quantity Unit Rank	Cost Comments	
Vertical Conveyance				
Elevator - Hydraulic Elevator	1st Floor	1 EA 6	\$19,238	
Puilding Interior Subtetals		œ.	າດວ າດາ	

Building Interior Subtotal: \$208,292

Total Building Cost \$2,551,532

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Dr	ainage						
	Civil/ Drainage - Catch Basin	Entire Site	3	EA	6	\$3,282	
	Civil/ Drainage - Site Manhole	Entire Site	5	EA	6	\$7,464	
Fencing	3						
	Fencing - Chain Link	Entire Site	166	LF	6	\$3,117	South trash enclosure
	Fencing - New Standard Ornamental	Entire Site	1,358	LF	6	\$43,325	
	Fencing - Wood Fencing w/ Steel Frame	Entire Site	187	LF	6	\$2,452	
Landsc	аре						
	Benches	Entire Site / Courtyard	4	EA	6	\$1,720	
	Landscape - Grass	Entire Site / Site - East	4,300	SF	6	\$3,566	
	Landscape - Hardscape- Concrete	Entire Site	4,170	SF	6	\$21,527	
	Parkway trees	Entire Site	15	EA	6	\$9,901	
	Planting Beds/ Area	Entire Site	1,375	SF	6	\$2,261	
	Play Area - Asphalt/ Hardscape	Entire Site	8,165	SF	6	\$19,732	
	Trash Receptacles	Entire Site	1	EA	6	\$312	South playground
Parking	Lot						
	Surface - Asphalt	West Courtyard	16,300	SF	5	\$74,356	Need seal coating
	Surface - Concrete	West Courtyard	1,200	SF	6	\$2,900	Trash enclosure at south of building
	Trash Enclosure - Chain Links	West Courtyard	1,200	SF	6	\$21,055	
Playgro	ound						
	Equipment - Combo 3-12	Entire Site	1	EA	6	\$7,092	
	Surface - Poured Surface	Entire Site	2,550	SF	6	\$18,670	
Sidewa	lks						
	Sidewalks - Perimeter Sidewalks	Entire Site	11,230	SF	6	\$22,322	



Dvorak Technology Academy

3615 W 16th St Chicago, IL 60623

SITE

Category: Site

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Signage						
Flag Pole - Flag Pole	North Courtyard	1	EA	7	\$0	
Marquee - Free Standing Back lighted w/ LED	North Courtyard	1	EA	6	\$0	
Site Subtotal:				\$	265,053	
Total Site Cost				\$	265,053	

Campus Total ^{2 3}	\$2,816,585
-----------------------------	-------------

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

Definitions

- Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated.
- Unit means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.
- Campus Total also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.



Dvorak Technology Academy 3615 W 16th St Chicago, IL 60623

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main		+				-	-	 				-		
Computer Lab	Regular Classroom	1st Floor	105	105	715	5	3	14	160	20	40	N	Υ	N
Computer Lab	Regular Classroom	2nd Floor	214	214	715	5	3	24	156	17	40	N	Υ	N
Faculty Lounge	Regular Classroom	1st Floor	116	116	715	5	3	14	160	20	40	N	N	N
Music Room	Regular Classroom	2nd Floor	210	210	715	5	3	14	160	20	40	N	Υ	N
Pre School	Kindergarten	1st Floor	101	101	1,155	3	2	10	140	18	40	N	Υ	N
Pre School	Kindergarten	1st Floor	103	103	1,155	3	2	10	140	18	40	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	102	102	715	5	3	14	160	20	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	104	104	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	106/108	106/108	1,430	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	107	107	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	110	110	715	5	3	14	160	20	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	112	112	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	1st Floor	114	114	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	890	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	203	203	890	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	212	212	715	5	3	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	216	216	715	5	3	14	160	20	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	890	3	8	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	302	302	715	3	5	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	303	303	890	3	8	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	304	304	715	3	5	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	305	305	715	3	8	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	306	306	715	5	3	14	160	20	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	307	307	715	3	8	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	308	308	715	5	3	14	160	20	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	310	310	715	5	3	14	160	20	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	312	312	715	3	8	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	314	314	715	3	8	14	160	20	40	N	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	316	316	715	3	5	14	160	20	40	N	N	N
Special Program	Regular Classroom	2nd Floor	204	204	715	5	3	14	160	20	40	N	Υ	N