

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

| Campus Summary | | | | |
|---------------------|------------------|------------------|-----------------------|---------------------|
| Building Name | Year Constructed | Number of Floors | Building Area (Sq Ft) | Assessed Need |
| Main | 1919 | 3 | 305,788 | \$13,481,423 |
| SITE | | | | \$292,451 |
| Campus Total | | | 305,788 | \$13,773,874 |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|--------------------------------------|---|----------|------|------|---------|--|
| Entrance | | | | | | | |
| | Entrance Control - Audio and Video | Entrance 3A-East | 1 | EA | 6 | \$702 | |
| | Entrance Control - Audio and Video | Entrance 9-West | 1 | EA | 6 | \$702 | |
| | Entrance Control - Audio and Video | Main Entrance 3-East | 1 | EA | 6 | \$702 | |
| | Entrance Control - Audio | Entrance 10-North - 146 Mechanical / Boiler | 1 | EA | 6 | \$497 | |
| | Exterior Doors - Exterior Steel Door | Entrance 10-North - 146 Mechanical / Boiler | 1 | EA | 6 | \$481 | Several areas dented and peeling around hardware |
| | Exterior Doors - Exterior Steel Door | Entrance 1-North | 1 | EA | 5 | \$1,341 | Not working properly, hard to open |
| | Exterior Doors - Exterior Steel Door | Entrance 1-North | 1 | EA | 6 | \$481 | |
| | Exterior Doors - Exterior Steel Door | Entrance 2A-East | 1 | EA | 6 | \$481 | |
| | Exterior Doors - Exterior Steel Door | Entrance 3A-East | 1 | EA | 6 | \$481 | |
| | Exterior Doors - Exterior Steel Door | Entrance 5-SE | 2 | EA | 6 | \$961 | |
| | Exterior Doors - Exterior Steel Door | Entrance 6 -SW | 2 | EA | 6 | \$961 | Heavily scraped, peeling at bottom of door |
| | Exterior Doors - Exterior Steel Door | Entrance 8-West | 2 | EA | 6 | \$961 | |
| | Exterior Doors - Exterior Steel Door | Entrance 9-West | 2 | EA | 6 | \$961 | |
| | Exterior Doors - Exterior Steel Door | Exit 2-NE | 3 | EA | 6 | \$1,442 | |
| | Exterior Doors - Exterior Steel Door | Exit 4-SE | 3 | EA | 6 | \$1,442 | |
| | Exterior Doors - Exterior Steel Door | Exit 6A-SW - 161 Storage | 2 | EA | 6 | \$961 | |
| | Exterior Doors - Exterior Steel Door | Exit 7-SW | 2 | EA | 6 | \$961 | |
| | Exterior Doors - Exterior Steel Door | Fire Escape / Roof Access Doors | 6 | EA | 6 | \$2,883 | At 2nd, 4th floors |
| | Exterior Doors - Exterior Steel Door | Main Entrance 3-East | 7 | EA | 6 | \$3,364 | |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|--|---|----------|------|------|-----------|--|
| Entrance | | | | | | | |
| | Exterior Doors - Exterior Steel Door | Main Entrance 3-East | 1 | EA | 5 | \$1,341 | Closer damaged, door slams behind user |
| | Exterior Doors - Exterior Steel Door | North courtyard - Light well | 1 | EA | 6 | \$481 | |
| | Exterior Doors - Overhead Rolling/ Garage Door | Entrance 10A - 147 Storage | 1 | EA | 6 | \$1,433 | 10'x8' - Wood frame cracked, chipped and peeling throughout |
| | Exterior Doors - Overhead Rolling/ Garage Door | Entrance 10B - Loading Dock | 1 | EA | 6 | \$1,433 | 10'x14' - Wood frame cracked, chipped and peeling throughout |
| | Exterior Doors - Side lite | Entrance 10-North - 146 Mechanical / Boiler | 1 | EA | 6 | \$313 | |
| | Exterior Doors - Side lite | Entrance 2A-East | 2 | EA | 6 | \$627 | |
| | Exterior Doors - Side lite | Entrance 3A-East | 2 | EA | 6 | \$627 | |
| | Exterior Doors - Side lite | Entrance 6 -SW | 1 | EA | 6 | \$313 | |
| | Exterior Doors - Transom Lite | Entrance 2A-East | 1 | EA | 6 | \$313 | |
| | Exterior Doors - Transom Lite | Entrance 3A-East | 1 | EA | 6 | \$313 | |
| | Exterior Doors - Transom Lite | Exit 2-NE | 3 | EA | 6 | \$940 | |
| | Exterior Doors - Transom Lite | Main Entrance 3-East | 10 | EA | 6 | \$3,133 | |
| | Exterior Stairs - Concrete | Entrance 1-North | 7 | LF | 6 | \$572 | |
| | Exterior Stairs - Concrete | Entrance 5-SE | 6 | LF | 6 | \$491 | |
| | Exterior Stairs - Concrete | Exit 2-NE | 17 | LF | 6 | \$1,390 | |
| | Exterior Stairs - Concrete | Exit 2-NE | 5 | LF | 5 | \$548 | Area cracked, chipped with missing pieces |
| | Exterior Stairs - Concrete | Exit 4-SE | 20 | LF | 6 | \$1,635 | |
| | Exterior Stairs - Concrete | Exit 7-SW | 6 | LF | 6 | \$491 | |
| | Exterior Stairs - Concrete | Main Entrance 3-East | 575 | LF | 6 | \$47,016 | |
| | Exterior Stairs - Concrete | Main Entrance 3-East | 20 | LF | 5 | \$2,192 | Several cracked, chipped and missing at main entrance 2-east |
| | Exterior Stairs - Concrete | North courtyard - Light well | 3 | LF | 6 | \$245 | |
| | Exterior Stairs - Stone | Exit 6A-SW - 161 Storage | 6 | LF | 6 | \$678 | |
| | Power Door Operator and Controls | Entrance 3A-East | 1 | EA | 5 | \$0 | Not working properly |
| | Power Door Operator and Controls | Entrance 9-West | 1 | EA | 5 | \$0 | Not working properly |
| | Ramp Handrail - Steel_Ramp Handrail | Entrance 2A-East | 160 | LF | 6 | \$1,387 | |
| | Ramp Handrail - Steel_Ramp Handrail | Entrance 3A-East | 160 | LF | 6 | \$1,387 | Rusting, peeling throughout |
| | Ramps - Concrete | Entrance 2A-East | 125 | LF | 6 | \$18,779 | |
| | Ramps - Concrete | Entrance 3A-East | 125 | LF | 6 | \$18,779 | |
| | Stair Handrail - Steel_Stair Handrail | Main Entrance 3-East | 80 | LF | 6 | \$693 | |
| Fire Escape | | | | | | | |
| | Fire Escape | North Courtyard | 175 | LF | 6 | \$110,558 | |
| | Fire Escape | South Courtyard | 175 | LF | 6 | \$110,558 | |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|---|------------------------|----------|------|------|----------|--|
| Foundation | | | | | | | |
| | Foundation - Concrete | Entire Building | 90 | LF | 6 | \$17,480 | Areas cracked, chipped with large gaps at SW corner of parking lot / Evidence of water penetration in storage 142 (old coal room) - flooded with 3 feet of water and below boiler room |
| | Foundation - Masonry | Entire Building | 2,655 | LF | 7 | \$0 | |
| | Superstructure - Heavy Timber | Entire Building | 305,788 | SF | 7 | \$0 | |
| Lighting | | | | | | | |
| | Exterior Lighting - Parapet or Roof Mounted | Entire Building / East | 2 | EA | 6 | \$1,073 | |
| | Exterior Lighting - Parapet or Roof Mounted | Entire Building / East | 2 | EA | 5 | \$4,360 | Not working properly |
| | Exterior Lighting - Wall Mounted | Entire Building | 10 | EA | 5 | \$4,274 | Not working properly - Housing / Cover damaged, cracked, need new bulb |
| | Exterior Lighting - Wall Mounted | Entire Building | 8 | EA | 6 | \$2,310 | Pole mounted spotlights for statues at roof 14 |
| | Exterior Lighting - Wall Mounted | Entire Building | 46 | EA | 6 | \$13,282 | |
| Roof System | | | | | | | |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | Roof 10 | 95 | LF | 6 | \$90,695 | Inside exterior wall - vegetation growing out of top / Adjacent to skylite - missing coping |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | Roof 11 | 45 | LF | 6 | \$42,961 | In exterior wall |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | Roof 13 | 60 | LF | 6 | \$57,281 | 2'x2' |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | Roof 5 | 100 | LF | 6 | \$95,468 | |
| | Chimney - Metal Flue | Roof 13 | 120 | LF | 6 | \$18,977 | |
| | Chimney - Metal Flue | Roof 6, 7 | 25 | LF | 6 | \$3,954 | Rusted at top and bottom |
| | Coping - Clay Tile | Roof 13 | 20 | LF | 5 | \$1,960 | Several pieces cracked, chipped with loose and missing mortar joints throughout |
| | Coping - Clay Tile | Roof 13 | 190 | LF | 6 | \$6,102 | |
| | Coping - Clay Tile | Roof 5 | 35 | LF | 6 | \$1,124 | |
| | Coping - Metal | Roof 14 | 360 | LF | 6 | \$11,562 | |
| | Coping - Metal | Roof 8 | 35 | LF | 6 | \$1,124 | |
| | Coping - Metal | Roofs 4, 12 | 360 | LF | 6 | \$11,562 | |
| | Coping - Stone | Roof 10 | 60 | LF | 6 | \$1,927 | |
| | Coping - Stone | Roof 3 | 10 | LF | 6 | \$321 | Lower roof at adjacent south open court below |
| | Coping - Stone | Roof 6, 7 | 50 | LF | 6 | \$1,606 | Roof 7 |
| | Coping - Terra Cotta | Roof 1 | 310 | LF | 6 | \$9,957 | |
| | Coping - Terra Cotta | Roof 1 | 100 | LF | 5 | \$13,263 | Several pieces cracked, chipped with loose or missing mortar joints throughout |
| | Coping - Terra Cotta | Roof 10 | 100 | LF | 5 | \$13,263 | Several pieces cracked, chipped with loose or missing mortar joints |
| | Coping - Terra Cotta | Roof 10 | 250 | LF | 6 | \$8,029 | |
| | Coping - Terra Cotta | Roof 11 | 410 | LF | 6 | \$13,168 | |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|----------------------------------|-------------|----------|------|------|----------|--|
| Roof System | | | | | | | |
| | Coping - Terra Cotta | Roof 11 | 50 | LF | 5 | \$6,632 | Several pieces cracked, chipped with loose and missing mortar joints throughout / Several areas with old tar patches |
| | Coping - Terra Cotta | Roof 13 | 30 | LF | 5 | \$4,592 | Several pieces cracked, chipped with loose and missing mortar joints throughout |
| | Coping - Terra Cotta | Roof 13 | 545 | LF | 6 | \$17,504 | |
| | Coping - Terra Cotta | Roof 15 | 230 | LF | 6 | \$7,387 | |
| | Coping - Terra Cotta | Roof 2 | 30 | LF | 5 | \$4,592 | Several pieces cracked, chipped with loose and missing mortar joints throughout / Several old tar patches at NE corner |
| | Coping - Terra Cotta | Roof 2 | 350 | LF | 6 | \$11,241 | |
| | Coping - Terra Cotta | Roof 3 | 80 | LF | 6 | \$2,569 | |
| | Coping - Terra Cotta | Roof 5 | 50 | LF | 5 | \$6,632 | Several pieces cracked, chipped with loose and missing mortar joints throughout / Several areas of old tar patches |
| | Coping - Terra Cotta | Roof 5 | 190 | LF | 6 | \$6,102 | |
| | Coping - Terra Cotta | Roof 6, 7 | 30 | LF | 5 | \$3,979 | Roof 6 - Several pieces cracked, chipped with loose and missing mortar joints / Several areas of old tar patches |
| | Coping - Terra Cotta | Roof 6, 7 | 165 | LF | 6 | \$5,299 | Roof 6 |
| | Coping - Terra Cotta | Roof 8 | 200 | LF | 6 | \$6,424 | |
| | Coping - Terra Cotta | Roof 8 | 40 | LF | 5 | \$5,305 | Several pieces cracked, chipped with loose and missing mortar joints throughout |
| | Coping - Terra Cotta | Roof 9 | 325 | LF | 6 | \$10,438 | |
| | Downspouts - Exterior Downspouts | Roof 13 | 35 | LF | 6 | \$1,163 | |
| | Downspouts - Exterior Downspouts | Roof 14 | 420 | LF | 6 | \$13,958 | |
| | Downspouts - Exterior Downspouts | Roof 3 | 70 | LF | 6 | \$2,326 | Lower roof at adjacent south open court below included |
| | Downspouts - Exterior Downspouts | Roof 5 | 3 | LF | 6 | \$100 | |
| | Downspouts - Exterior Downspouts | Roof 8 | 3 | LF | 6 | \$100 | |
| | Downspouts - Exterior Downspouts | Roofs 4, 12 | 20 | LF | 3 | \$2,709 | Cracked, bent, leaking throughout causing staining to adjacent exterior wall |
| | Downspouts - Exterior Downspouts | Roofs 4, 12 | 400 | LF | 6 | \$13,293 | Gutters and downspouts rusted throughout |
| | Downspouts - Interior Downspouts | Roof 1 | 100 | LF | 6 | \$3,323 | |
| | Downspouts - Interior Downspouts | Roof 10 | 100 | LF | 6 | \$3,323 | |
| | Downspouts - Interior Downspouts | Roof 11 | 200 | LF | 6 | \$6,647 | |
| | Downspouts - Interior Downspouts | Roof 13 | 895 | LF | 6 | \$29,744 | |
| | Downspouts - Interior Downspouts | Roof 15 | 180 | LF | 6 | \$5,982 | |
| | Downspouts - Interior Downspouts | Roof 2 | 200 | LF | 6 | \$6,647 | |
| | Downspouts - Interior Downspouts | Roof 3 | 50 | LF | 6 | \$1,662 | |
| | Downspouts - Interior Downspouts | Roof 5 | 200 | LF | 6 | \$6,647 | |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|----------------------------------|-----------|----------|------|------|----------|---|
| Roof System | | | | | | | |
| | Downspouts - Interior Downspouts | Roof 6, 7 | 55 | LF | 6 | \$1,828 | |
| | Downspouts - Interior Downspouts | Roof 8 | 200 | LF | 6 | \$6,647 | |
| | Downspouts - Interior Downspouts | Roof 9 | 80 | LF | 6 | \$2,659 | |
| | Parapet - 16" - 30" Height | Roof 1 | 60 | LF | 6 | \$2,397 | |
| | Parapet - 16" - 30" Height | Roof 11 | 80 | LF | 6 | \$3,196 | |
| | Parapet - 16" - 30" Height | Roof 11 | 40 | LF | 5 | \$8,149 | Areas cracked, chipped, crumbling with loose and missing mortar joints |
| | Parapet - 16" - 30" Height | Roof 13 | 405 | LF | 6 | \$16,181 | |
| | Parapet - 16" - 30" Height | Roof 15 | 115 | LF | 6 | \$4,595 | |
| | Parapet - 16" - 30" Height | Roof 2 | 120 | LF | 6 | \$4,795 | |
| | Parapet - 16" - 30" Height | Roof 3 | 15 | LF | 5 | \$3,056 | Several areas cracked with loose and missing mortar joints throughout |
| | Parapet - 16" - 30" Height | Roof 3 | 25 | LF | 6 | \$999 | |
| | Parapet - 16" - 30" Height | Roof 9 | 155 | LF | 6 | \$6,193 | |
| | Parapet - 16" - 30" Height | Roof 9 | 15 | LF | 5 | \$3,655 | Several areas cracked with loose and missing mortar joints throughout |
| | Parapet - Parapet < 16" Height | Roof 10 | 40 | LF | 6 | \$852 | |
| | Parapet - Parapet < 16" Height | Roof 11 | 290 | LF | 6 | \$6,179 | |
| | Parapet - Parapet < 16" Height | Roof 13 | 190 | LF | 6 | \$4,048 | |
| | Parapet - Parapet < 16" Height | Roof 13 | 20 | LF | 5 | \$2,508 | Areas cracked, chipped, crumbling with loose and missing mortar joints |
| | Parapet - Parapet < 16" Height | Roof 15 | 115 | LF | 6 | \$2,450 | |
| | Parapet - Parapet < 16" Height | Roof 2 | 260 | LF | 6 | \$5,540 | |
| | Parapet - Parapet < 16" Height | Roof 3 | 10 | LF | 6 | \$213 | Lower roof at adjacent south open court below |
| | Parapet - Parapet < 16" Height | Roof 5 | 195 | LF | 6 | \$4,155 | |
| | Parapet - Parapet < 16" Height | Roof 6, 7 | 245 | LF | 6 | \$5,220 | |
| | Parapet - Parapet < 16" Height | Roof 8 | 195 | LF | 6 | \$4,155 | |
| | Parapet - Parapet < 16" Height | Roof 9 | 5 | LF | 5 | \$627 | Areas cracked with loose and missing mortar joints |
| | Parapet - Parapet < 16" Height | Roof 9 | 100 | LF | 6 | \$2,131 | |
| | Parapet - Parapet > 30" | Roof 1 | 330 | LF | 6 | \$21,094 | |
| | Parapet - Parapet > 30" | Roof 1 | 20 | LF | 5 | \$7,594 | Several areas cracking with loose or missing mortar joints throughout |
| | Parapet - Parapet > 30" | Roof 10 | 115 | LF | 5 | \$37,748 | Cracked, chipped with loose and missing mortar joints throughout / Slightly leaning to east |
| | Parapet - Parapet > 30" | Roof 10 | 255 | LF | 6 | \$16,300 | |
| | Parapet - Parapet > 30" | Roof 13 | 140 | LF | 6 | \$8,949 | |
| | Parapet - Parapet > 30" | Roof 3 | 40 | LF | 6 | \$2,557 | |
| | Parapet - Parapet > 30" | Roof 5 | 45 | LF | 6 | \$2,876 | |
| | Parapet - Parapet > 30" | Roof 8 | 35 | LF | 6 | \$2,237 | |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments | |
|--------------------|--|-------------|----------|------|------|-----------|---|---|
| Roof System | | | | | | | | |
| | Parapet - Parapet > 30" | Roof 8 | 10 | LF | 5 | \$3,282 | Areas cracked with loose and missing mortar joints | |
| | Parapet - Parapet > 30" | Roof 9 | 50 | LF | 6 | \$3,196 | | |
| | Roof Structure - Concrete | Roof 3 | 100 | SF | 7 | \$0 | Lower roof at adjacent south open court below | |
| | Roof Structure - Concrete | Roof 6, 7 | 5,190 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 1 | 11,775 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 10 | 11,775 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 11 | 7,175 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 13 | 17,210 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 14 | 7,760 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 15 | 2,660 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 2 | 7,175 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 3 | 1,050 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 5 | 9,900 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 8 | 9,900 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roof 9 | 9,325 | SF | 7 | \$0 | | |
| | Roof Structure - Steel with Clay Tile Arch | Roofs 4, 12 | 4,050 | SF | 7 | \$0 | | |
| | Roof - Asphalt Gravel Ballast | Roof 1 | 8,275 | SF | 6 | \$84,134 | | |
| | Roof - Asphalt Gravel Ballast | Roof 1 | 3,500 | SF | 5 | \$82,633 | | Several areas ripping, blistering, bubbling and worn out throughout / Gaps around majority of pipe penetrations |
| | Roof - Asphalt Gravel Ballast | Roof 10 | 8,775 | SF | 6 | \$89,218 | | |
| | Roof - Asphalt Gravel Ballast | Roof 10 | 3,000 | SF | 5 | \$70,828 | Several areas blistering, cracking, bubbling, worn out throughout / Ripping with small holes around majority of pipe penetrations | |
| | Roof - Asphalt Gravel Ballast | Roof 11 | 5,435 | SF | 6 | \$55,259 | | |
| | Roof - Asphalt Gravel Ballast | Roof 11 | 1,000 | SF | 5 | \$23,609 | Several areas cracking, blistering, bubbling, worn out throughout | |
| | Roof - Asphalt Gravel Ballast | Roof 13 | 5,000 | SF | 3 | \$140,140 | Several areas blistering, cracking, bubbling, worn out throughout / Ripping with small holes around several pipe penetrations / Evidence of water penetration in 404 storage at SE corner | |
| | Roof - Asphalt Gravel Ballast | Roof 13 | 12,210 | SF | 5 | \$288,270 | | |
| | Roof - Asphalt Gravel Ballast | Roof 15 | 2,660 | SF | 5 | \$62,801 | Several areas blistering, bubbling, worn out around and underneath mechanical equipment and roof drains | |
| | Roof - Asphalt Gravel Ballast | Roof 2 | 2,000 | SF | 5 | \$47,219 | Several areas ripping, blistering, bubbling, worn out with open seams throughout / Gaps around majority of pipe penetrations / Ponding occurring at downspout from above / Vegetation growing around downspout around | |
| | Roof - Asphalt Gravel Ballast | Roof 2 | 4,435 | SF | 5 | \$104,707 | | |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|--|-----------------|----------|------|------|-----------|---|
| Roof System | | | | | | | |
| | Roof - Asphalt Gravel Ballast | Roof 3 | 1,050 | SF | 6 | \$10,676 | Vegetation growing along entire south parapet |
| | Roof - Asphalt Gravel Ballast | Roof 3 | 100 | SF | 5 | \$2,696 | Lower roof at adjacent south open court below - Entire roof moist with heavy vegetation |
| | Roof - Asphalt Gravel Ballast | Roof 5 | 6,950 | SF | 6 | \$70,663 | |
| | Roof - Asphalt Gravel Ballast | Roof 5 | 1,500 | SF | 5 | \$35,414 | Several areas blistering, cracking, bubbling, worn out throughout / Heavy vegetation growing at SE corner |
| | Roof - Asphalt Gravel Ballast | Roof 6, 7 | 4,920 | SF | 5 | \$116,158 | |
| | Roof - Asphalt Gravel Ballast | Roof 6, 7 | 270 | SF | 4 | \$14,309 | Roof 6 - South side of roof covered in vegetation along exterior wall / Several areas of blistering, bubbling, worn out throughout |
| | Roof - Asphalt Gravel Ballast | Roof 8 | 8,700 | SF | 3 | \$243,844 | Several areas blistering, cracking, bubbling, worn out throughout / Evidence of water penetration at ceiling of boys gym ceiling throughout |
| | Roof - Asphalt Gravel Ballast | Roof 9 | 500 | SF | 5 | \$15,494 | Several areas blistering, bubbling, worn out throughout |
| | Roof - Asphalt Gravel Ballast | Roof 9 | 8,765 | SF | 6 | \$89,116 | |
| | Roof - Metal | Roof 11 | 740 | SF | 6 | \$9,915 | |
| | Roof - Metal | Roof 14 | 7,760 | SF | 6 | \$103,977 | Rusting throughout |
| | Roof - Metal | Roof 2 | 740 | SF | 6 | \$9,915 | |
| | Roof - Metal | Roof 5 | 250 | SF | 6 | \$3,350 | |
| | Roof - Metal | Roof 5 | 1,200 | SF | 6 | \$16,079 | |
| | Roof - Metal | Roof 8 | 1,200 | SF | 6 | \$16,079 | |
| | Roof - Metal | Roof 8 | 250 | SF | 6 | \$3,350 | |
| | Roof - Metal | Roofs 4, 12 | 4,050 | SF | 5 | \$111,602 | Rusting throughout |
| | Roof - Modified Bitumen | Roof 9 | 60 | SF | 6 | \$565 | Recent patch job |
| Walls | | | | | | | |
| | Canopy - Concrete/ Stucco | Entire Building | 240 | SF | 6 | \$7,942 | Location: Above and adjacent to east entrances 2, 2A, 3A, 4 - Copper roofs with cast stone base |
| | Cheek-Wall - Concrete | Entire Building | 200 | SF | 6 | \$2,051 | N,S ends of steps |
| | Cornice - Cast Stone | Entire Building | 525 | LF | 6 | \$18,206 | NE, SE corners above 3rd floor windows |
| | Cornice - Masonry Projecting Limestone | Entire Building | 4,500 | LF | 6 | \$156,049 | |
| | Cornice - Masonry Projecting Limestone | Entire Building | 100 | LF | 5 | \$18,939 | Several pieces cracked, chipped with gaps and loose and missing mortar joints throughout |
| | Exterior Walls - Brick | Entire Building | 51,810 | SF | 6 | \$348,215 | |
| | Exterior Walls - Brick | Entire Building | 100 | SF | 3 | \$16,465 | Light well at south side of north courtyard - Evidence of water penetration to basement level |

Building: Main

Category: Building Exterior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|------------------------------------|---|-----------------|----------|------|------|--------------------|---|
| Walls | | | | | | | |
| | Exterior Walls - Brick | Entire Building | 1,000 | SF | 6 | \$9,081 | Stepped cracking occurring at upper SW and NE corners of 4th floor exterior walls / Several areas cracked, chipped with loose and missing mortar joints throughout / Light well at south side of north courtyard - Evidence of water penetration to basement level |
| | Exterior Walls - Concrete Block | Entire Building | 960 | SF | 6 | \$6,452 | |
| | Exterior Walls - Prefabricated Metal Panel Wall | Entire Building | 3,680 | SF | 6 | \$20,892 | Location: In between 1st / 2nd floor windows |
| | Exterior Walls - Stone-Cast | Entire Building | 15 | SF | 5 | \$264 | Area cracked, chipped with large gaps and missing pieces |
| | Exterior Walls - Stone-Cast | Entire Building | 15,540 | SF | 6 | \$104,444 | |
| | Exterior Walls - Stone-Cast | Entire Building | 55 | SF | 3 | \$9,989 | Several cracked areas with loose and missing mortar joints throughout / North courtyard - south end, under fire escape - areas , cracked, chipped with vegetation growth at inside corner / Underneath old exterior steel coal door at south side of parking lot - Cracked with large gap - Evidence of water penetration in storage 142 - flooded with 3 feet of water |
| | Exterior Walls - Terra Cotta | Entire Building | 29,340 | SF | 6 | \$197,194 | Continuous banding around perimeter above 1st, 2nd-3rd floor windows |
| Windows | | | | | | | |
| | Guard - Guards perforated | Entire Building | 23,885 | SF | 6 | \$305,009 | |
| | Guard - Guards wire guard | Entire Building | 850 | SF | 6 | \$10,854 | |
| | Lintels - Steel | Entire Building | 2,390 | LF | 6 | \$69,379 | |
| | Skylite - Glass Double-Pane | Entire Building | 1,450 | SF | 6 | \$34,648 | |
| | Windows - Decorative | Entire Building | 15 | SF | 6 | \$112 | |
| | Windows - Louver | Entire Building | 420 | SF | 6 | \$3,135 | |
| | Windows - Sash Aluminum Double-pane | Entire Building | 24,765 | SF | 6 | \$184,861 | |
| Building Exterior Subtotal: | | | | | | \$4,647,295 | |

Building: Main

Category: Electrical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-------------------------|---|-----------------------------|----------|------|------|----------|-----------|
| Emergency System | | | | | | | |
| | Automatic Transfer Switch | Electrical Room | 2 | EA | 6 | \$816 | |
| | Emergency A/C Power - Auditorium and Aisle Lighting | Entire Building / 1st Floor | 11,312 | SF | 6 | \$5,985 | Generator |
| | Emergency A/C Power - Corridors and Stairs | Entire Building | 46,545 | SF | 6 | \$13,977 | |
| | Emergency A/C Power - Gym | Entire Building / 2nd Floor | 15,586 | SF | 6 | \$5,795 | |

Building: Main

Category: Electrical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---------------------------|--|------------------------------|----------|------|------|-----------|------------------------|
| Emergency System | | | | | | | |
| | Emergency A/C Power - Lunchrooms | Entire Building / 4th Floor | 5,245 | SF | 6 | \$1,950 | |
| | Emergency A/C Power - Students Toilets | Entire Building | 3,513 | SF | 6 | \$1,306 | |
| | Emergency Generator- Outdoor- Diesel - 101 - 150 KW | Site North / North Courtyard | 1 | EA | 6 | \$11,529 | install 2005 |
| | Exit Signs - Auditorium | Entire Building / 1st Floor | 19 | EA | 6 | \$2,845 | Generator |
| | Exit Signs - Corridors and Stairs | Entire Building | 97 | EA | 6 | \$14,526 | |
| | Exit Signs - Gym | Entire Building / 2nd Floor | 8 | EA | 6 | \$1,259 | |
| | Exit Signs - Lunchroom | Entire Building / 4th Floor | 4 | EA | 6 | \$599 | |
| | Exit Signs - Pool | Entire Building / 1st Floor | 2 | EA | 6 | \$310 | |
| | Security System - CCTV | Entire Building | 308,788 | SF | 6 | \$92,729 | |
| | Security System - Intrusion Detection | Entire Building | 308,788 | SF | 6 | \$79,482 | |
| Main Service | | | | | | | |
| | Main Electrical Service - 2001 to 3000 A 120/208/3PH | Electrical Room | 3 | EA | 6 | \$32,601 | South electrical room |
| | Main Electrical Service - 2001 to 3000 A 120/240/3PH | Electrical Room | 2 | EA | 6 | \$21,734 | North electrical room |
| | PA System | Entire Building | 308,788 | SF | 6 | \$101,560 | |
| Power Distribution | | | | | | | |
| | Lighting and Power Panels - 100 A | Electrical Room | 15 | EA | 6 | \$4,487 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 1 | EA | 6 | \$497 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 4 | EA | 6 | \$1,988 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 1 | EA | 6 | \$497 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 30 | EA | 6 | \$14,911 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 3 | EA | 6 | \$1,491 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 1 | EA | 6 | \$497 | |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 2 | EA | 6 | \$994 | Emergency breaker type |
| | Lighting and Power Panels - Above 100 A | Electrical Room | 10 | EA | 6 | \$4,970 | |
| | Main Distribution Panels - 400 - 600 amp | Electrical Room | 3 | EA | 6 | \$1,583 | |
| | Main Distribution Panels - 400 - 600 amp | Electrical Room | 2 | EA | 6 | \$1,055 | |
| | Main Distribution Panels - 400 - 600 amp | Electrical Room | 1 | EA | 6 | \$528 | South Emergency |
| | Main Distribution Panels - 400 - 600 amp | Electrical Room | 4 | EA | 6 | \$2,111 | |
| | Main Distribution Panels - Greater than 600 amp | Electrical Room | 2 | EA | 6 | \$1,460 | |
| | Main Distribution Panels - Greater than 600 amp | Electrical Room | 2 | EA | 6 | \$1,460 | |
| | Transformers - 120/240 - 120/208 | Electrical Room | 1 | EA | 6 | \$3,021 | |
| | Transformers - 120/240 - 120/208 | Electrical Room | 1 | EA | 6 | \$3,021 | |
| | Transformers - 277/480 - 120/208 | Electrical Room | 1 | EA | 6 | \$1,265 | |

Electrical System Subtotal:

\$434,842

Building: Main

Category: Safty System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-------------------|--------------------------|-----------------------------------|----------|------|------|-----------|--|
| Fire Alarm | | | | | | | |
| | Fire Alarm Panel | Entire Building / Electrical Room | 2 | EA | 6 | \$12,812 | N/E Electrical room also shuts ALL fans down |
| | Fire Alarm Strobe Lights | Entire Building | 305,788 | SF | 6 | \$109,319 | |
| | Fire Alarm_System | Entire Building | 305,788 | SF | 6 | \$148,674 | updated 2004 |

Safty System Subtotal:

\$270,805

Building: Main

Category: Mechanical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-------------------------|---|------------------------|----------|------|------|---------|----------------------------------|
| Air Conditioning | | | | | | | |
| | Chemical Pot Feeder | Roof / Mechanical Room | 2 | EA | 6 | \$1,213 | |
| | Chiller-Air Cooled-Screw Type-Roof Mounted - 201 - 300 tons | Roof | 2 | EA | 6 | \$8,628 | South |
| | Chiller-Air Cooled-Screw Type-Roof Mounted - 201 - 300 tons | Roof | 2 | EA | 6 | \$8,628 | North |
| | Condensing Unit- Roof Mounted - Less than 5 tons | Roof / Façade- NW | 1 | EA | 6 | \$3,334 | Serves MDF |
| | Condensing Unit- Roof Mounted - Less than 5 tons | Roof | 2 | EA | 6 | \$6,667 | Serves Lunch/Break room Teachers |
| | Condensing Unit- Roof Mounted - Less than 5 tons | Roof | 1 | EA | 6 | \$3,334 | Serves S. Band room |
| | Pipes - Chilled Water Pipe- Galvanized | Roof / Entire Building | 3,500 | LF | 6 | \$6,607 | |
| | Pressure Fill System | Roof / Mechanical Room | 1 | EA | 6 | \$1,405 | |

Air Handling Systems

| | | | | | | | |
|--|---|------------------------|---|----|---|---------|-------------------------|
| | Air Handling Unit- Built Up- Single Zone- Steam Coils and Chilled Water Coils - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | Serves Auditorium |
| | Air Handling Unit- Built Up- Single Zone- Steam Coils and Chilled Water Coils - 8001 - 15000 cfm | Mechanical Room | 1 | EA | 6 | \$4,341 | Serves Lunchroom |
| | Air Handling Unit- Built Up- Single Zone- Steam Coils and Chilled Water Coils - 8001 - 15000 cfm | Mechanical Room | 1 | EA | 6 | \$4,341 | Serves West Building |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils and Chilled Water Coils - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | Serves Central Building |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils and Chilled Water Coils - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | Serves Central Building |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils and Chilled Water Coils - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | Serves S/W building |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils and Chilled Water Coils - 25001 - 35000 cfm | Mechanical Room | 1 | EA | 6 | \$6,511 | Serves N/E building |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils and Chilled Water Coils - 25001 - 35000 cfm | Mechanical Room | 1 | EA | 6 | \$6,511 | Serves S/E Building |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils and Chilled Water Coils - 8001 - 15000 cfm | Mechanical Room | 1 | EA | 6 | \$4,341 | Serves N/W Building |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |

Building: Main

Category: Mechanical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------------------|---|-----------------------------------|----------|------|------|-----------|--------------------|
| Air Handling Systems | | | | | | | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Air Intake | Mechanical Room / Roof | 1 | EA | 7 | \$0 | |
| | Auxiliaries - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | |
| | Auxiliaries - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | |
| | Auxiliaries - 15001 - 25000 cfm | Mechanical Room | 1 | EA | 6 | \$5,788 | |
| | Auxiliaries - 25001 - 35000 cfm | Mechanical Room | 1 | EA | 6 | \$6,511 | |
| | Auxiliaries - 25001 - 35000 cfm | Mechanical Room | 1 | EA | 6 | \$6,511 | |
| | Auxiliaries - 8001 - 15000 cfm | Mechanical Room | 1 | EA | 6 | \$4,341 | |
| | Fan Coil Unit- Floor Mounted - Hot Water and Chilled Water | Entire Building | 148 | EA | 6 | \$226,552 | Chilled water only |
| | Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM | Mechanical Room | 1 | EA | 6 | \$1,857 | Serves AHU9 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM | Mechanical Room | 1 | EA | 6 | \$1,857 | Serves AHU6 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM | Mechanical Room | 1 | EA | 6 | \$1,857 | Serves AHU7 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM | Mechanical Room | 1 | EA | 6 | \$1,857 | Serves AHU8 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM | Mechanical Room | 1 | EA | 6 | \$2,433 | Serves AHU4 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM | Mechanical Room | 1 | EA | 6 | \$2,433 | Serves AHU5 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM | Mechanical Room | 1 | EA | 6 | \$2,433 | Serves AHU3 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM | Mechanical Room / Roof | 1 | EA | 6 | \$2,433 | Serves AHU1 |
| | Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM | Mechanical Room / Roof | 1 | EA | 6 | \$2,433 | Serves AHU2 |
| | Make Up Air Unit- Roof Mounted- Gas Heating and Chilled Water Coils - 10,001 - 20,000 cfm | Roof | 2 | EA | 6 | \$6,700 | Serves Auditorium |
| | Make Up Air Unit- Roof Mounted- Gas Heating and Chilled Water Coils - Less than 6000 cfm | Roof | 2 | EA | 6 | \$6,700 | Serves Boy's Gym |
| | Make Up Air Unit- Roof Mounted- Gas Heating and Chilled Water Coils - Less than 6000 cfm | Roof | 2 | EA | 6 | \$6,700 | Serves Girl's Gym |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 50 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |

Building: Main

Category: Mechanical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------------------|--|-----------------------------------|----------|------|------|----------|-----------------|
| Air Handling Systems | | | | | | | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 100 | LF | 7 | \$0 | |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | Mechanical Room / Entire Building | 50 | LF | 7 | \$0 | |
| | Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 11 - 20 tons | Roof | 1 | EA | 6 | \$2,792 | Serves Room 203 |
| | Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 5 - 10 tons | Roof | 1 | EA | 6 | \$2,051 | Serves Room303 |
| | Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 5 - 10 tons | Roof | 1 | EA | 6 | \$2,051 | Serves Room 323 |
| | Roof Top Unit-Single Zone-Roof Mounted- Gas Heating and DX Cooling Coil - 5 - 10 tons | Roof | 1 | EA | 6 | \$2,051 | Serves Room227 |
| | Zone Dampers | Mechanical Room / Entire Building | 30 | EA | 6 | \$24,991 | |
| | Zone Dampers | Mechanical Room / Entire Building | 38 | EA | 6 | \$31,655 | |
| | Zone Dampers | Mechanical Room / Entire Building | 15 | EA | 6 | \$12,495 | |
| | Zone Dampers | Mechanical Room / Entire Building | 10 | EA | 6 | \$8,330 | |
| | Zone Dampers | Mechanical Room / Entire Building | 16 | EA | 6 | \$13,329 | |
| | Zone Dampers | Mechanical Room / Entire Building | 20 | EA | 6 | \$16,661 | |
| Boiler Systems | | | | | | | |
| | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - Greater than 300 HP | Boiler Room | 1 | EA | 6 | \$998 | |
| | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - Greater than 300 HP | Boiler Room | 2 | EA | 6 | \$1,996 | |
| | Chemical Feed System | Boiler Room | 2 | EA | 6 | \$2,156 | |
| | Chemical Feeder | Boiler Room | 2 | EA | 6 | \$2,156 | |
| | Combustion Dampers | Boiler Room | 3 | EA | 6 | \$1,227 | |
| | Condensate Pump | Boiler Room / Mechanical Room | 9 | EA | 6 | \$18,190 | |
| | Feed Water Pumps and Tank | Boiler Room / Mechanical Room | 1 | EA | 6 | \$2,545 | |
| | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - Greater than 300 HP | Boiler Room | 2 | EA | 6 | \$1,996 | Install 1969 |
| | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - Greater than 300 HP | Boiler Room | 1 | EA | 6 | \$998 | Install 1995 |
| | Piping - Condensate Pipe- Steel | Boiler Room / Entire Building | 900 | LF | 6 | \$1,699 | |
| | Piping - Condensate Pipe- Steel | Boiler Room / Entire Building | 300 | LF | 7 | \$0 | Replaced 2004 |
| | Piping - Steam Pipe- Steel | Boiler Room / Entire Building | 900 | LF | 6 | \$1,699 | |
| | Piping - Steam Pipe- Steel | Boiler Room / Entire Building | 300 | LF | 7 | \$0 | Replaced 2004 |
| | Steam Traps | Boiler Room / Mechanical Room | 2 | EA | 4 | \$5,021 | |
| | Steam Traps | Boiler Room / Mechanical Room | 20 | EA | 6 | \$5,283 | |
| | Vacuum Pump | Boiler Room / Mechanical Room | 1 | EA | 6 | \$2,471 | |

Building: Main

Category: Mechanical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|----------------------------|---|-----------------------------|----------|------|------|-----------|--|
| Gas Booster | | | | | | | |
| | Gas Booster | Boiler Room | 4 | EA | 6 | \$1,996 | |
| Heating Devices | | | | | | | |
| | Fin Tube - Electric | Entire Building | 18 | LF | 6 | \$170 | |
| | Unit Heater - Electric | Electrical Room | 2 | EA | 6 | \$556 | |
| | Unit Heater - Electric | Entire Building | 5 | EA | 5 | \$5,038 | |
| | Unit Heater - Gas | Entire Building | 3 | EA | 6 | \$833 | |
| | Unit Heater - Hot Water | Entire Building | 3 | EA | 6 | \$837 | |
| | Wall Heater - Electric | Entire Building | 10 | EA | 6 | \$1,389 | |
| | Wall Heater - Electric | Entire Building | 4 | EA | 4 | \$4,330 | Do not work |
| Mechanical Plumbing | | | | | | | |
| | Chilled Water Pump - 10 - 20 HP | Mechanical Room | 2 | EA | 6 | \$2,485 | S Mechanical room |
| | Chilled Water Pump - 10 - 20 HP | Mechanical Room | 2 | EA | 6 | \$2,485 | N Mechanical room |
| | Chilled Water Pump - 21 - 50 HP | Mechanical Room | 2 | EA | 6 | \$2,485 | S Mechanical room |
| | Chilled Water Pump - 21 - 50 HP | Mechanical Room | 2 | EA | 6 | \$2,485 | N Mechanical room |
| Temperature Control | | | | | | | |
| | DDC System | Entire Building | 305,788 | SF | 6 | \$174,911 | |
| | Electric Thermostat | Entire Building | 13 | EA | 6 | \$0 | |
| | Thermostats - DDC | Entire Building / 1st Floor | 53 | EA | 6 | \$0 | |
| | Thermostats - DDC | Entire Building / 2nd Floor | 44 | EA | 6 | \$0 | |
| | Thermostats - DDC | Entire Building / 3rd Floor | 46 | EA | 6 | \$0 | |
| | Thermostats - DDC | Entire Building / 4th Floor | 15 | EA | 6 | \$0 | |
| Unit Ventilation | | | | | | | |
| | Unit Ventilators- Floor Mounted- Steam Heating w/ DX Cooling Coil & w/ Self Contained Compressors | 2nd Floor | 3 | EA | 6 | \$3,743 | Serves Band room 244 |
| Ventilation | | | | | | | |
| | Exhaust Fans- Indoor - Less than 500 CFM | Entire Building | 6 | EA | 6 | \$1,777 | |
| | Exhaust Fans- Roof Mounted - 1501 - 8000 CFM | Entire Building / Roof | 9 | EA | 6 | \$5,332 | |
| | Exhaust Fans- Roof Mounted - 500 - 1500 CFM | Entire Building / Roof | 4 | EA | 6 | \$2,370 | |
| | Exhaust Fans- Roof Mounted - Greater than 8000 CFM | Entire Building / Roof | 1 | EA | 6 | \$592 | |
| | Lab Exhaust Hood | Entire Building | 5 | EA | 6 | \$6,239 | |
| | Roof Mounted Duct Work | Entire Building / Roof | 100 | LF | 5 | \$68,224 | Wind damage insulation and sheet metal exposed and not secured |
| | Type I Exhaust Hood- Culinary Arts | Entire Building / 2nd Floor | 2 | EA | 6 | \$2,495 | |
| | Type I Exhaust Hood- Kitchen | Entire Building / 4th Floor | 1 | EA | 6 | \$1,248 | |
| | Type II Exhaust Hood- Warming Kitchen | Entire Building / 4th Floor | 2 | EA | 6 | \$1,840 | |

Building: Main

Category: Mechanical System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|------------------------------------|-------------|----------|----------|------|------|------------------|----------|
| Mechanical System Subtotal: | | | | | | \$848,677 | |

Building: Main

Category: Plumbing System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---------------------|--|-----------------|----------|------|------|-----------|--|
| Hot Water | | | | | | | |
| | Electric Heater - Greater than 50 KW | Mechanical Room | 1 | EA | 6 | \$682 | Serves Kitchen Dishwasher |
| | Gas Heater - 150000 - 300000 BTU/HR | Mechanical Room | 2 | EA | 6 | \$620 | Serves Kitchen |
| | Gas Heater - Greater than 600000 BTU/HR | Mechanical Room | 1 | EA | 5 | \$2,249 | Boiler/hot water for Domestic close to end of life |
| | Hot Water Storage Tank_Gas - 201 - 500 Gallons | Mechanical Room | 1 | EA | 7 | \$0 | Serves Domestic cold water |
| | Hot Water Storage Tank_Gas - 501 - 1000 Gallons | Mechanical Room | 1 | EA | 6 | \$678 | Serves Domestic Hot water |
| Piping | | | | | | | |
| | Domestic Piping-Cold Water from Risers to Fixtures | Entire Building | 305,788 | SF | 6 | \$61,219 | Over service life |
| | Domestic Piping-Cold Water Horizontal Lines | Entire Building | 203,859 | SF | 6 | \$49,558 | Over service life |
| | Domestic Piping-Cold Water Horizontal Lines | Entire Building | 101,929 | SF | 6 | \$24,779 | Replaced 2004 crawl space |
| | Domestic Piping-Cold Water Risers | Entire Building | 305,788 | SF | 6 | \$56,846 | Over service life |
| | Domestic Piping-Hot Water from Risers to Fixtures | Entire Building | 305,788 | SF | 6 | \$48,100 | Over service life |
| | Domestic Piping-Hot Water Horizontal Lines | Entire Building | 203,859 | SF | 6 | \$37,897 | Over service life |
| | Domestic Piping-Hot Water Horizontal Lines | Entire Building | 101,929 | SF | 6 | \$18,949 | Replaced 2004 crawl space |
| | Domestic Piping-Hot Water Return Lines | Entire Building | 203,859 | SF | 6 | \$29,152 | Over service life |
| | Domestic Piping-Hot Water Return Lines | Entire Building | 101,929 | SF | 6 | \$14,576 | Replaced 2004 crawl space |
| | Domestic Piping-Hot Water Return Risers | Entire Building | 305,788 | SF | 6 | \$43,728 | Over service life |
| | Sanitary Piping | Entire Building | 275,788 | SF | 6 | \$252,401 | Over service life |
| | Sanitary Piping | Entire Building | 30,000 | SF | 6 | \$27,456 | Replaced 2004 crawl space |
| | Storm Piping | Entire Building | 305,788 | SF | 6 | \$266,739 | Over service life |
| | Vent Piping | Entire Building | 30,000 | SF | 6 | \$20,163 | Replaced 2004 |
| | Vent Piping | Entire Building | 275,788 | SF | 6 | \$185,357 | Over service life |
| Pool Systems | | | | | | | |
| | Pool Drain Piping | Mechanical Room | 150 | LF | 6 | \$4,294 | |
| | Pool Filtration System including Pump | Mechanical Room | 1 | EA | 5 | \$19,025 | Minor leaks valves and pipes |
| | Pool Hot Water Heater - Gas Fired | Mechanical Room | 1 | EA | 6 | \$310 | |
| | Pool Supply and Return Piping | Mechanical Room | 300 | LF | 6 | \$14,414 | |
| Pumps | | | | | | | |
| | Pumps - Domestic Booster Pump-Duplex | Mechanical Room | 1 | EA | 6 | \$1,977 | |
| | Pumps - Sump-Duplex | Mechanical Room | 1 | EA | 6 | \$1,387 | Serves Elevator pit |

Building: Main

Category: Plumbing System

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|----------------------------------|-------------|----------|----------|------|------|--------------------|----------|
| Plumbing System Subtotal: | | | | | | \$1,182,557 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|----------|----------|
| Classroom #100 (Computer Lab) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 1,571 | SF | 6 | \$5,437 | |
| | Charging Station | 1st Floor | 1 | EA | 6 | \$485 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | 1st Floor | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 2 | EA | 6 | \$602 | |
| | Floor - Wood | 1st Floor | 1,571 | SF | 6 | \$11,075 | |
| | Lighting - Pendent/Surface | 1st Floor | 40 | EA | 6 | \$4,956 | |
| | Marker Board | 1st Floor | 34 | LF | 6 | \$728 | |
| | Walls - Plaster/Drywall | 1st Floor | 2,004 | SF | 6 | \$5,531 | |
| Classroom #104 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 660 | SF | 6 | \$4,653 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 38 | LF | 6 | \$814 | |
| | Storage/ Closet | 1st Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #106 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 660 | SF | 6 | \$4,653 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 38 | LF | 6 | \$814 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #107 (Computer Lab) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| Classroom #107 (Computer Lab) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 815 | SF | 6 | \$2,820 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 815 | SF | 6 | \$5,746 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 36 | LF | 6 | \$771 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,392 | SF | 6 | \$3,842 | |
| Classroom #108 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 660 | SF | 6 | \$4,653 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 38 | LF | 6 | \$814 | |
| | Storage/ Closet | 1st Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #109 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 660 | SF | 6 | \$4,653 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 38 | LF | 6 | \$814 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #110 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 660 | SF | 6 | \$4,653 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 38 | LF | 6 | \$814 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,186 | SF | 6 | \$3,273 | |

Building: Main
Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| Classroom #111 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 660 | SF | 6 | \$4,653 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 38 | LF | 6 | \$814 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #118 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 5 | LF | 6 | \$126 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 700 | SF | 6 | \$2,422 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 700 | SF | 6 | \$4,935 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 20 | LF | 6 | \$428 | |
| | Storage/ Closet | 1st Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,270 | SF | 6 | \$3,505 | |
| Classroom #120 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 5 | LF | 6 | \$126 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 700 | SF | 6 | \$2,422 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 700 | SF | 6 | \$4,935 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 20 | LF | 6 | \$428 | |
| | Storage/ Closet | 1st Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,270 | SF | 6 | \$3,505 | |
| Classroom #122 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 5 | LF | 6 | \$126 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 700 | SF | 6 | \$2,422 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 700 | SF | 6 | \$4,935 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 20 | LF | 6 | \$428 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|---------------|
| Classroom #122 (Regular Classroom) | | | | | | | |
| | Storage/ Closet | 1st Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,270 | SF | 6 | \$3,505 | |
| Classroom #124 (Regular Classroom) | | | | | | | |
| | Casework | 1st Floor | 20 | LF | 6 | \$505 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 711 | SF | 6 | \$2,460 | |
| | Doors - Transom Window | 1st Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 1st Floor | 711 | SF | 6 | \$1,515 | |
| | Lighting - Pendent/Surface | 1st Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 1st Floor | 10 | LF | 6 | \$214 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,398 | SF | 6 | \$3,858 | |
| Classroom #126 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 844 | SF | 6 | \$2,921 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 1st Floor | 844 | SF | 6 | \$1,798 | |
| | Lighting - Pendent/Surface | 1st Floor | 19 | EA | 6 | \$2,354 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,538 | SF | 6 | \$4,245 | |
| Classroom #127 (Science Lab Level 3) | | | | | | | |
| | Casework | 1st Floor | 113 | LF | 6 | \$2,854 | |
| | Ceiling - Lay-in | 1st Floor | 1,277 | SF | 6 | \$3,835 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 1st Floor | 1,277 | SF | 6 | \$1,278 | |
| | Gas Line | 1st Floor | 3 | EA | 6 | \$1,527 | |
| | Lighting - Lay-in | 1st Floor | 20 | EA | 6 | \$2,380 | |
| | Marker Board | 1st Floor | 20 | LF | 6 | \$428 | |
| | Science Lab Elements | 1st Floor | 1,277 | SF | 6 | \$8,656 | |
| | Walls - Plaster/Drywall | 1st Floor | 1,180 | SF | 6 | \$3,257 | |
| | Work Sink | 1st Floor | 3 | EA | 6 | \$1,137 | |
| Classroom #132 (Laboratory/Shop) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 40 | SF | 5 | \$500 | Peeling paint |
| | Ceiling - Plaster/Drywall | 1st Floor | 556 | SF | 6 | \$1,924 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 1st Floor | 596 | SF | 6 | \$1,304 | |
| | Lighting - Pendent/Surface | 1st Floor | 13 | EA | 7 | \$0 | |
| | Walls - Masonry | 1st Floor | 1,014 | SF | 6 | \$3,190 | Brick |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|---------------------------|
| Classroom #132 (Laboratory/Shop) | | | | | | | |
| | Walls - Plaster/Drywall | 1st Floor | 627 | SF | 6 | \$1,730 | |
| Classroom #134 (Art Room) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 851 | SF | 6 | \$2,945 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 1st Floor | 851 | SF | 6 | \$1,862 | |
| | Lighting - Pendent/Surface | 1st Floor | 19 | EA | 7 | \$0 | 3 in storage rooms. |
| | Storage/ Closet | 1st Floor | 71 | SF | 6 | \$515 | Storage rm 1 |
| | Storage/ Closet | 1st Floor | 32 | SF | 6 | \$232 | Storage Rm 2 |
| | Walls - Masonry | 1st Floor | 1,579 | SF | 6 | \$4,968 | Brick |
| | Walls - Plaster/Drywall | 1st Floor | 514 | SF | 6 | \$1,419 | |
| | Work Sink | 1st Floor | 1 | EA | 6 | \$379 | Triple sink w one faucet. |
| Classroom #136 (Art Room) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 837 | SF | 6 | \$2,897 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | 1st Floor | 22 | SF | 6 | \$372 | |
| | Floor - Wood | 1st Floor | 837 | SF | 6 | \$5,901 | |
| | Lighting - Pendent/Surface | 1st Floor | 20 | EA | 7 | \$0 | |
| | Marker Board | 1st Floor | 10 | LF | 6 | \$214 | |
| | Storage/ Closet | 1st Floor | 51 | SF | 6 | \$370 | |
| | Storage/ Closet | 1st Floor | 87 | SF | 6 | \$631 | |
| | Walls - Masonry | 1st Floor | 1,690 | SF | 6 | \$5,317 | |
| | Walls - Plaster/Drywall | 1st Floor | 480 | SF | 6 | \$1,325 | |
| | Work Sink | 1st Floor | 2 | EA | 6 | \$758 | |
| Classroom #136B (Art Room) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 286 | SF | 6 | \$990 | |
| | Doors - Transom Window | 1st Floor | 22 | SF | 6 | \$372 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 1st Floor | 286 | SF | 6 | \$286 | |
| | Kiln | 1st Floor | 1 | EA | 6 | \$2,321 | |
| | Lighting - Pendent/Surface | 1st Floor | 5 | EA | 6 | \$619 | |
| | Walls - Masonry | 1st Floor | 580 | SF | 6 | \$1,825 | Brick |
| | Walls - Plaster/Drywall | 1st Floor | 548 | SF | 6 | \$1,512 | |
| Classroom #137 (Choral Room) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 518 | SF | 6 | \$1,793 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|---------------------------------|-----------|----------|------|------|---------|--------------------------------|
| Classroom #137 (Choral Room) | | | | | | | |
| | Doors - Transom Window | 1st Floor | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 2 | EA | 6 | \$602 | |
| | Floor - Concrete Epoxy/ Painted | 1st Floor | 1,168 | SF | 6 | \$618 | |
| | Lighting - Pendent/Surface | 1st Floor | 33 | EA | 7 | \$0 | |
| | Marker Board | 1st Floor | 10 | LF | 6 | \$214 | |
| | Sound Panels | 1st Floor | 50 | EA | 6 | \$202 | |
| | Walls - Masonry | 1st Floor | 401 | SF | 6 | \$2,007 | Brick |
| | Walls - Masonry | 1st Floor | 914 | SF | 6 | \$2,875 | Brick walls with sound panels |
| | Walls - Plaster/Drywall | 1st Floor | 550 | SF | 6 | \$1,518 | |
| Classroom #138 (Art Room) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 985 | SF | 6 | \$3,409 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | 1st Floor | 22 | SF | 6 | \$372 | |
| | Floor - Wood | 1st Floor | 985 | SF | 6 | \$6,944 | |
| | Lighting - Pendent/Surface | 1st Floor | 20 | EA | 7 | \$0 | |
| | Marker Board | 1st Floor | 4 | LF | 7 | \$0 | |
| | Walls - Masonry | 1st Floor | 1,210 | SF | 6 | \$3,807 | Brick |
| | Walls - Plaster/Drywall | 1st Floor | 960 | SF | 6 | \$2,650 | |
| | Work Sink | 1st Floor | 2 | EA | 6 | \$758 | |
| Classroom #139 (Choral Room) | | | | | | | |
| | Ceiling - Splined | 1st Floor | 925 | SF | 6 | \$754 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Concrete Epoxy/ Painted | 1st Floor | 925 | SF | 6 | \$489 | |
| | Lighting - Pendent/Surface | 1st Floor | 24 | EA | 7 | \$0 | |
| | Marker Board | 1st Floor | 10 | LF | 7 | \$0 | |
| | Risers | 1st Floor | 9 | LF | 6 | \$203 | |
| | Sound Panels | 1st Floor | 46 | EA | 6 | \$185 | |
| | Walls - Masonry | 1st Floor | 907 | SF | 6 | \$2,853 | |
| | Walls - Masonry | 1st Floor | 784 | SF | 6 | \$3,924 | Brick walls with sound panels. |
| | Walls - Plaster/Drywall | 1st Floor | 103 | SF | 6 | \$284 | |
| Classroom #140 (Special Education) | | | | | | | |
| | Casework | 1st Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 1st Floor | 985 | SF | 6 | \$3,409 | |
| | Doors - Steel Doors incl hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | 1st Floor | 22 | SF | 6 | \$372 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|----------|-------------------------------------|
| Classroom #140 (Special Education) | | | | | | | |
| | Doors - Wood Doors inclu hw | 1st Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 1st Floor | 985 | SF | 6 | \$6,944 | |
| | Lighting - Pendent/Surface | 1st Floor | 22 | EA | 7 | \$0 | 2 in storage closet |
| | Marker Board | 1st Floor | 10 | LF | 7 | \$0 | |
| | Storage/ Closet | 1st Floor | 89 | SF | 6 | \$645 | |
| | Walls - Masonry | 1st Floor | 1,730 | SF | 6 | \$5,443 | Brick |
| | Walls - Plaster/Drywall | 1st Floor | 480 | SF | 6 | \$1,325 | |
| | Work Sink | 1st Floor | 2 | EA | 6 | \$758 | |
| Classroom #141 (Other Instructional Use) | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 2,963 | SF | 6 | \$10,254 | |
| | Doors - Steel Doors incl hw | 1st Floor | 2 | EA | 6 | \$602 | |
| | Doors - Wood Doors inclu hw | 1st Floor | 3 | EA | 6 | \$903 | |
| | Floor - Concrete | 1st Floor | 2,963 | SF | 6 | \$1,568 | |
| | Lighting - Pendent/Surface | 1st Floor | 48 | EA | 7 | \$0 | |
| | Walls - Masonry | 1st Floor | 2,580 | SF | 6 | \$8,117 | |
| Classroom #200 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 722 | SF | 6 | \$2,499 | |
| | Doors - Steel Doors incl hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 2nd Floor | 722 | SF | 6 | \$1,580 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 38 | LF | 7 | \$0 | |
| | Storage/ Closet | 2nd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,202 | SF | 6 | \$3,317 | |
| Classroom #200A (Special Education) | | | | | | | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 490 | SF | 6 | \$1,696 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 10 | SF | 5 | \$125 | Water damage,peeling paint/plaster. |
| | Doors - Steel Doors incl hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 500 | SF | 6 | \$3,525 | |
| | Lighting - Pendent/Surface | 2nd Floor | 12 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 16 | LF | 7 | \$0 | |
| | Walls - Plaster/Drywall | 2nd Floor | 970 | SF | 6 | \$2,677 | |
| Classroom #201 (Science Lab Level 3) | | | | | | | |
| | Casework | 2nd Floor | 76 | LF | 6 | \$1,919 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 977 | SF | 6 | \$3,381 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| Classroom #201 (Science Lab Level 3) | | | | | | | |
| | Doors - Steel Doors incl hw | 2nd Floor | 2 | EA | 6 | \$602 | |
| | Eye Wash Station | 2nd Floor | 1 | EA | 6 | \$336 | |
| | Floor - Tile/Sheet | 2nd Floor | 977 | SF | 6 | \$978 | |
| | Gas Line | 2nd Floor | 1 | EA | 6 | \$509 | |
| | Lighting - Pendent/Surface | 2nd Floor | 20 | EA | 6 | \$2,478 | |
| | Marker Board | 2nd Floor | 24 | LF | 6 | \$514 | |
| | Science Lab Shower | 2nd Floor | 1 | EA | 6 | \$379 | |
| | Storage/ Closet | 2nd Floor | 70 | SF | 6 | \$508 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,540 | SF | 6 | \$4,250 | |
| | Work Sink | 2nd Floor | 3 | EA | 6 | \$1,137 | |
| Classroom #203 (Science Lab Level 1) | | | | | | | |
| | Casework | 2nd Floor | 84 | LF | 6 | \$2,121 | |
| | Ceiling - Lay-in | 2nd Floor | 1,340 | SF | 6 | \$4,024 | |
| | Doors - Steel Doors incl hw | 2nd Floor | 2 | EA | 6 | \$602 | |
| | Eye Wash Station | 2nd Floor | 1 | EA | 6 | \$336 | |
| | Floor - Tile/Sheet | 2nd Floor | 1,340 | SF | 6 | \$1,341 | |
| | Gas Line | 2nd Floor | 15 | EA | 6 | \$7,637 | |
| | Lighting - Lay-in | 2nd Floor | 29 | EA | 6 | \$3,450 | |
| | Marker Board | 2nd Floor | 20 | LF | 6 | \$428 | |
| | Science Lab Shower | 2nd Floor | 1 | EA | 6 | \$379 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,912 | SF | 6 | \$5,277 | |
| | Work Sink | 2nd Floor | 10 | EA | 6 | \$3,790 | |
| Classroom #208 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 837 | SF | 6 | \$2,897 | |
| | Doors - Transom Window | 2nd Floor | 24 | SF | 6 | \$406 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 2nd Floor | 837 | SF | 6 | \$1,831 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 36 | LF | 7 | \$0 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,286 | SF | 6 | \$3,549 | |
| Classroom #208A (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 2nd Floor | 660 | SF | 6 | \$1,444 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 7 | \$0 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--|-----------------------------|-----------|----------|------|------|---------|----------|
| Classroom #208A (Regular Classroom) | | | | | | | |
| | Marker Board | 2nd Floor | 20 | LF | 7 | \$0 | |
| | Storage/ Closet | 2nd Floor | 172 | SF | 6 | \$1,247 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #209 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 2nd Floor | 660 | SF | 6 | \$661 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 2nd Floor | 38 | LF | 6 | \$814 | |
| | Storage/ Closet | 2nd Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #210 (Faculty Lounge) | | | | | | | |
| | Casework | 2nd Floor | 42 | LF | 6 | \$1,061 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 849 | SF | 6 | \$2,938 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 849 | SF | 6 | \$5,985 | |
| | Lighting - Pendent/Surface | 2nd Floor | 20 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,528 | SF | 6 | \$4,217 | |
| | Work Sink | 2nd Floor | 1 | EA | 6 | \$379 | |
| Classroom #211 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 660 | SF | 6 | \$2,284 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 2nd Floor | 660 | SF | 6 | \$661 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 2nd Floor | 38 | LF | 6 | \$814 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,186 | SF | 6 | \$3,273 | |
| Classroom #213 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 722 | SF | 6 | \$2,499 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| Classroom #213 (Regular Classroom) | | | | | | | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 2nd Floor | 722 | SF | 6 | \$723 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 2nd Floor | 38 | LF | 6 | \$814 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,202 | SF | 6 | \$3,317 | |
| Classroom #216 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 715 | SF | 6 | \$2,474 | |
| | Doors - Transom Window | 2nd Floor | 24 | SF | 6 | \$406 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 28 | LF | 7 | \$0 | |
| | Storage/ Closet | 2nd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |
| Classroom #218 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 8 | LF | 6 | \$202 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 715 | SF | 6 | \$2,474 | |
| | Doors - Transom Window | 2nd Floor | 24 | SF | 6 | \$406 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 28 | LF | 7 | \$0 | |
| | Storage/ Closet | 2nd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |
| Classroom #219 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 5 | LF | 6 | \$126 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 715 | SF | 6 | \$2,474 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 2nd Floor | 20 | LF | 6 | \$428 | |
| | Storage/ Closet | 2nd Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------|
| Classroom #220 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 8 | LF | 6 | \$202 | |
| | Ceiling - Lay-in | 2nd Floor | 715 | SF | 6 | \$2,147 | |
| | Doors - Transom Window | 2nd Floor | 24 | SF | 6 | \$406 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Lay-in | 2nd Floor | 12 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 28 | LF | 6 | \$600 | |
| | Storage/ Closet | 2nd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |
| Classroom #221 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 5 | LF | 6 | \$126 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 715 | SF | 6 | \$2,474 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 2nd Floor | 20 | LF | 6 | \$428 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |
| Classroom #222 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 8 | LF | 6 | \$202 | |
| | Ceiling - Lay-in | 2nd Floor | 715 | SF | 6 | \$2,147 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Lay-in | 2nd Floor | 12 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 28 | LF | 7 | \$0 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |
| Classroom #224 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 8 | LF | 6 | \$202 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 715 | SF | 6 | \$2,474 | |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 715 | SF | 6 | \$5,041 | |
| | Lighting - Pendent/Surface | 2nd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 28 | LF | 7 | \$0 | |
| | Storage/ Closet | 2nd Floor | 4 | SF | 6 | \$29 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|--------------|
| Classroom #224 (Regular Classroom) | | | | | | | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,260 | SF | 6 | \$3,477 | |
| Classroom #225 (Computer Lab) | | | | | | | |
| | Casework | 2nd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 990 | SF | 6 | \$3,426 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 100 | SF | 5 | \$1,250 | Water Damage |
| | Doors - Transom Window | 2nd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 2nd Floor | 990 | SF | 6 | \$991 | |
| | Lighting - Pendent/Surface | 2nd Floor | 24 | EA | 6 | \$2,973 | |
| | Marker Board | 2nd Floor | 20 | LF | 6 | \$428 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,350 | SF | 6 | \$3,726 | |
| | Walls - Plaster/Drywall | 2nd Floor | 100 | SF | 5 | \$511 | Water Damage |
| Classroom #226 (Regular Classroom) | | | | | | | |
| | Casework | 2nd Floor | 4 | LF | 6 | \$101 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 850 | SF | 6 | \$2,942 | |
| | Doors - Steel Doors incl hw | 2nd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 2nd Floor | 850 | SF | 6 | \$5,992 | |
| | Lighting - Pendent/Surface | 2nd Floor | 20 | EA | 7 | \$0 | |
| | Marker Board | 2nd Floor | 20 | LF | 7 | \$0 | |
| | Storage/ Closet | 2nd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,300 | SF | 6 | \$3,588 | |
| Classroom #227 (Science Lab Level 1) | | | | | | | |
| | Casework | 2nd Floor | 80 | LF | 6 | \$2,020 | |
| | Ceiling - Lay-in | 2nd Floor | 1,340 | SF | 6 | \$4,024 | |
| | Doors - Steel Doors incl hw | 2nd Floor | 2 | EA | 6 | \$602 | |
| | Eye Wash Station | 2nd Floor | 1 | EA | 6 | \$336 | |
| | Floor - Epoxy/ Painted | 2nd Floor | 1,340 | SF | 6 | \$709 | |
| | Fume Hood | 2nd Floor | 1 | EA | 6 | \$816 | |
| | Gas Line | 2nd Floor | 14 | EA | 6 | \$7,128 | |
| | Lighting - Lay-in | 2nd Floor | 20 | EA | 6 | \$2,380 | |
| | Marker Board | 2nd Floor | 20 | LF | 6 | \$428 | |
| | Science Lab Elements | 2nd Floor | 1,340 | SF | 6 | \$9,083 | |
| | Science Lab Shower | 2nd Floor | 1 | EA | 6 | \$379 | |
| | Walls - Plaster/Drywall | 2nd Floor | 1,912 | SF | 6 | \$5,277 | |
| | Work Sink | 2nd Floor | 9 | EA | 6 | \$3,411 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|----------|--------------------|
| Classroom #251 (Band Room) | | | | | | | |
| | Casework | 2nd Floor | 42 | LF | 6 | \$1,061 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 612 | SF | 6 | \$2,118 | |
| | Ceiling - Splined | 2nd Floor | 1,658 | SF | 6 | \$1,351 | |
| | Doors - Wood Doors inclu hw | 2nd Floor | 2 | EA | 6 | \$602 | |
| | Floor - Carpet | 2nd Floor | 2,270 | SF | 6 | \$4,837 | |
| | Instrument Storage Casework | 2nd Floor | 42 | LF | 6 | \$0 | Casework |
| | Lighting - Pendent/Surface | 2nd Floor | 56 | EA | 7 | \$0 | |
| | Sound Panels | 2nd Floor | 88 | EA | 6 | \$355 | |
| | Walls - Plaster/Drywall | 2nd Floor | 2,250 | SF | 6 | \$6,210 | |
| | Work Sink | 2nd Floor | 1 | EA | 6 | \$379 | |
| Classroom #301 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 24 | LF | 6 | \$606 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 1,074 | SF | 6 | \$3,717 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 80 | SF | 5 | \$1,000 | Water Damage |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 3rd Floor | 1,074 | SF | 6 | \$1,075 | |
| | Lighting - Pendent/Surface | 3rd Floor | 20 | EA | 6 | \$2,478 | |
| | Marker Board | 3rd Floor | 16 | LF | 6 | \$343 | |
| | Storage/ Closet | 3rd Floor | 30 | SF | 6 | \$218 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,704 | SF | 6 | \$4,703 | |
| Classroom #302 (Science Lab Level 1) | | | | | | | |
| | Casework | 3rd Floor | 125 | LF | 6 | \$3,157 | |
| | Ceiling - Lay-in | 3rd Floor | 1,557 | SF | 6 | \$4,676 | |
| | Doors - Steel Doors incl hw | 3rd Floor | 2 | EA | 6 | \$602 | |
| | Eye Wash Station | 3rd Floor | 1 | EA | 6 | \$336 | |
| | Floor - Tile/Sheet | 3rd Floor | 1,557 | SF | 6 | \$1,559 | |
| | Fume Hood | 3rd Floor | 1 | EA | 6 | \$816 | |
| | Gas Line | 3rd Floor | 16 | EA | 6 | \$8,146 | |
| | Lighting - Lay-in | 3rd Floor | 30 | EA | 7 | \$0 | |
| | Lighting - Pendent/Surface | 3rd Floor | 2 | EA | 7 | \$0 | In storage closet. |
| | Marker Board | 3rd Floor | 20 | LF | 7 | \$0 | |
| | Science Lab Elements | 3rd Floor | 1,557 | SF | 6 | \$10,554 | |
| | Science Lab Shower | 3rd Floor | 1 | EA | 6 | \$379 | |
| | Storage/ Closet | 3rd Floor | 87 | SF | 6 | \$631 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,912 | SF | 6 | \$5,277 | |
| | Work Sink | 3rd Floor | 10 | EA | 6 | \$3,790 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|-------------------------|
| Classroom #303 (Regular Classroom) | | | | | | | |
| | Ceiling - Lay-in | 3rd Floor | 2,522 | SF | 6 | \$7,574 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 3rd Floor | 2,252 | SF | 6 | \$2,254 | |
| | Lighting - Lay-in | 3rd Floor | 49 | EA | 6 | \$5,830 | |
| | Walls - Plaster/Drywall | 3rd Floor | 2,324 | SF | 6 | \$6,414 | |
| Classroom #304 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 45 | LF | 6 | \$1,136 | |
| | Ceiling - Lay-in | 3rd Floor | 100 | SF | 6 | \$300 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 615 | SF | 6 | \$2,128 | |
| | Doors - Steel Doors incl hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 3rd Floor | 715 | SF | 6 | \$716 | |
| | Lighting - Pendent/Surface | 3rd Floor | 18 | EA | 7 | \$0 | |
| | Marker Board | 3rd Floor | 12 | LF | 7 | \$0 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,310 | SF | 6 | \$3,615 | |
| | Work Sink | 3rd Floor | 1 | EA | 6 | \$379 | |
| Classroom #307 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 1,216 | SF | 6 | \$4,208 | |
| | Doors - Transom Window | 3rd Floor | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 2 | EA | 6 | \$602 | |
| | Floor - Tile/Sheet | 3rd Floor | 1,216 | SF | 6 | \$1,217 | |
| | Lighting - Pendent/Surface | 3rd Floor | 25 | EA | 6 | \$3,097 | |
| | Marker Board | 3rd Floor | 56 | LF | 6 | \$1,200 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,574 | SF | 6 | \$4,344 | |
| Classroom #308 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 2,088 | SF | 6 | \$7,226 | Peeling paint/ plaster. |
| | Doors - Steel Doors incl hw | 3rd Floor | 4 | EA | 6 | \$1,204 | |
| | Doors - Transom Window | 3rd Floor | 32 | SF | 6 | \$542 | |
| | Floor - Tile/Sheet | 3rd Floor | 2,088 | SF | 6 | \$2,090 | |
| | Lighting - Pendent/Surface | 3rd Floor | 54 | EA | 7 | \$0 | |
| | Marker Board | 3rd Floor | 46 | LF | 7 | \$0 | |
| | Walls - Plaster/Drywall | 3rd Floor | 2,324 | SF | 6 | \$6,414 | |
| Classroom #311 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 658 | SF | 6 | \$2,277 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 60 | SF | 5 | \$750 | Water Damage |
| | Doors - Transom Window | 3rd Floor | 8 | SF | 6 | \$135 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|---|
| Classroom #311 (Regular Classroom) | | | | | | | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 3rd Floor | 658 | SF | 6 | \$4,639 | |
| | Lighting - Pendent/Surface | 3rd Floor | 18 | EA | 6 | \$2,230 | |
| | Marker Board | 3rd Floor | 40 | LF | 6 | \$857 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,154 | SF | 6 | \$3,185 | |
| Classroom #313 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 1,091 | SF | 6 | \$3,776 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 60 | SF | 5 | \$750 | Water Damage |
| | Doors - Transom Window | 3rd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 3rd Floor | 1,091 | SF | 6 | \$1,092 | |
| | Lighting - Pendent/Surface | 3rd Floor | 27 | EA | 6 | \$3,345 | |
| | Marker Board | 3rd Floor | 48 | LF | 6 | \$1,028 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,505 | SF | 6 | \$4,154 | |
| Classroom #316 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 685 | SF | 6 | \$2,371 | |
| | Doors - Transom Window | 3rd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 3rd Floor | 685 | SF | 6 | \$4,829 | |
| | Lighting - Pendent/Surface | 3rd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 3rd Floor | 20 | LF | 7 | \$0 | |
| | Storage/ Closet | 3rd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,230 | SF | 6 | \$3,395 | |
| Classroom #318 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 20 | SF | 5 | \$250 | Eflorescence peeling paint/plaster around tops of windows.peeling paint south side of room. |
| | Ceiling - Plaster/Drywall | 3rd Floor | 665 | SF | 6 | \$2,301 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 3rd Floor | 685 | SF | 6 | \$4,829 | |
| | Lighting - Pendent/Surface | 3rd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 3rd Floor | 20 | LF | 7 | \$0 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,230 | SF | 6 | \$3,395 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|-----------------|
| Classroom #319 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 685 | SF | 6 | \$2,371 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 60 | SF | 5 | \$750 | Water Damage |
| | Doors - Transom Window | 3rd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 3rd Floor | 685 | SF | 6 | \$4,829 | |
| | Lighting - Pendent/Surface | 3rd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 3rd Floor | 20 | LF | 6 | \$428 | |
| | Storage/ Closet | 3rd Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,230 | SF | 6 | \$3,395 | |
| Classroom #321 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 10 | LF | 6 | \$253 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 685 | SF | 6 | \$2,371 | |
| | Doors - Transom Window | 3rd Floor | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 3rd Floor | 685 | SF | 6 | \$4,829 | |
| | Lighting - Pendent/Surface | 3rd Floor | 16 | EA | 6 | \$1,982 | |
| | Marker Board | 3rd Floor | 20 | LF | 6 | \$428 | |
| | Storage/ Closet | 3rd Floor | 6 | SF | 6 | \$44 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,230 | SF | 6 | \$3,395 | |
| Classroom #322 (Science Lab Level 1) | | | | | | | |
| | Casework | 3rd Floor | 160 | LF | 6 | \$4,041 | |
| | Ceiling - Lay-in | 3rd Floor | 1,120 | SF | 6 | \$3,363 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Eye Wash Station | 3rd Floor | 1 | EA | 6 | \$336 | |
| | Floor - Tile/Sheet | 3rd Floor | 1,120 | SF | 6 | \$1,121 | |
| | Fume Hood | 3rd Floor | 1 | EA | 6 | \$816 | |
| | Gas Line | 3rd Floor | 16 | EA | 6 | \$8,146 | |
| | Lighting - Lay-in | 3rd Floor | 17 | EA | 7 | \$0 | 2 in storage rm |
| | Marker Board | 3rd Floor | 20 | LF | 7 | \$0 | |
| | Science Lab Elements | 3rd Floor | 1,120 | SF | 6 | \$7,592 | |
| | Science Lab Shower | 3rd Floor | 1 | EA | 6 | \$379 | |
| | Storage/ Closet | 3rd Floor | 77 | SF | 6 | \$558 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,485 | SF | 6 | \$4,098 | |
| | Work Sink | 3rd Floor | 10 | EA | 6 | \$3,790 | |

Building: Main

Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|---------|----------------|
| Classroom #323 (Science Lab Level 1) | | | | | | | |
| | Casework | 3rd Floor | 84 | LF | 6 | \$2,121 | |
| | Ceiling - Lay-in | 3rd Floor | 1,120 | SF | 6 | \$3,363 | |
| | Doors - Steel Doors incl hw | 3rd Floor | 2 | EA | 6 | \$602 | |
| | Eye Wash Station | 3rd Floor | 1 | EA | 6 | \$336 | |
| | Floor - Epoxy/ Painted | 3rd Floor | 1,120 | SF | 6 | \$593 | |
| | Fume Hood | 3rd Floor | 1 | EA | 6 | \$816 | |
| | Gas Line | 3rd Floor | 15 | EA | 6 | \$7,637 | |
| | Lighting - Lay-in | 3rd Floor | 15 | EA | 6 | \$1,785 | |
| | Marker Board | 3rd Floor | 20 | LF | 6 | \$428 | |
| | Science Lab Elements | 3rd Floor | 1,120 | SF | 6 | \$7,592 | |
| | Science Lab Shower | 3rd Floor | 1 | EA | 6 | \$379 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,485 | SF | 6 | \$4,098 | |
| | Work Sink | 3rd Floor | 10 | EA | 6 | \$3,790 | |
| Classroom #324 (Science Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 715 | SF | 6 | \$2,474 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 3rd Floor | 363 | SF | 6 | \$363 | |
| | Floor - Wood | 3rd Floor | 362 | SF | 6 | \$2,552 | |
| | Lighting - Pendent/Surface | 3rd Floor | 16 | EA | 7 | \$0 | |
| | Marker Board | 3rd Floor | 20 | LF | 7 | \$0 | |
| | Risers | 3rd Floor | 16 | LF | 6 | \$360 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,300 | SF | 6 | \$3,588 | |
| | Walls - Plaster/Drywall | 3rd Floor | 24 | SF | 5 | \$123 | Peeling paint. |
| Classroom #325 (Regular Classroom) | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 1,138 | SF | 6 | \$3,938 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Epoxy/ Painted | 3rd Floor | 1,138 | SF | 6 | \$602 | |
| | Lighting - Pendent/Surface | 3rd Floor | 33 | EA | 6 | \$4,089 | |
| | Marker Board | 3rd Floor | 20 | LF | 6 | \$428 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,770 | SF | 6 | \$4,885 | |
| | Walls - Plaster/Drywall | 3rd Floor | 80 | SF | 5 | \$408 | Water Damage |
| Classroom #326 (Regular Classroom) | | | | | | | |
| | Casework | 3rd Floor | 30 | LF | 6 | \$758 | |
| | Ceiling - Lay-in | 3rd Floor | 100 | SF | 6 | \$300 | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 750 | SF | 6 | \$2,595 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |

Building: Main
Category: Classrooms

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---|-----------------------------|-----------|----------|------|------|------------------|----------|
| Classroom #326 (Regular Classroom) | | | | | | | |
| | Floor - Wood | 3rd Floor | 850 | SF | 6 | \$5,992 | |
| | Lighting - Pendent/Surface | 3rd Floor | 20 | EA | 7 | \$0 | |
| | Marker Board | 3rd Floor | 20 | LF | 7 | \$0 | |
| | Storage/ Closet | 3rd Floor | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,404 | SF | 6 | \$3,875 | |
| Classroom #327 (Computer Lab) | | | | | | | |
| | Ceiling - Lay-in | 3rd Floor | 2,130 | SF | 6 | \$6,396 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 3rd Floor | 2,130 | SF | 6 | \$2,132 | |
| | Lighting - Lay-in | 3rd Floor | 42 | EA | 6 | \$4,997 | |
| | Marker Board | 3rd Floor | 10 | LF | 6 | \$214 | |
| | Walls - Plaster/Drywall | 3rd Floor | 1,720 | SF | 6 | \$4,747 | |
| Classroom #Fitness room (Fitness Room) | | | | | | | |
| | Ceiling - Lay-in | 3rd Floor | 2,912 | SF | 6 | \$8,745 | |
| | Doors - Wood Doors inclu hw | 3rd Floor | 2 | EA | 6 | \$602 | |
| | Floor - Tile/Sheet | 3rd Floor | 2,912 | SF | 6 | \$2,915 | |
| | Lighting - Lay-in | 3rd Floor | 38 | EA | 7 | \$0 | |
| | Wall Mirrors | 3rd Floor | 400 | SF | 6 | \$0 | |
| | Walls - Plaster/Drywall | 3rd Floor | 2,912 | SF | 6 | \$8,037 | |
| Classrooms Subtotal: | | | | | | \$981,595 | |

Building: Main
Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-----------------------------|---------------------|----------|------|------|----------|----------|
| Administrative Suites/Offices | | | | | | | |
| | Ceiling - Plaster/Drywall | 020 Conference Room | 1,601 | SF | 6 | \$5,540 | |
| | Doors - Transom Window | 020 Conference Room | 21 | SF | 6 | \$356 | |
| | Doors - Wood Doors inclu hw | 020 Conference Room | 3 | EA | 6 | \$903 | |
| | Floor - Carpet | 020 Conference Room | 1,601 | SF | 6 | \$3,411 | |
| | Lighting - Pendent/Surface | 020 Conference Room | 30 | EA | 6 | \$3,717 | |
| | Power Distribution | 020 Conference Room | 24 | EA | 6 | \$50,997 | |
| | Walls - Plaster/Drywall | 020 Conference Room | 2,524 | SF | 6 | \$6,966 | |
| | Ceiling - Plaster/Drywall | 030 Copy Room | 145 | SF | 6 | \$502 | |
| | Doors - Wood Doors inclu hw | 030 Copy Room | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 030 Copy Room | 145 | SF | 6 | \$1,022 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-----------------------------|---------------|----------|------|------|----------|----------|
| Administrative Suites/Offices | | | | | | | |
| | Lighting - Pendent/Surface | 030 Copy Room | 1 | EA | 6 | \$124 | |
| | Power Distribution | 030 Copy Room | 8 | EA | 6 | \$16,999 | |
| | Walls - Plaster/Drywall | 030 Copy Room | 627 | SF | 6 | \$1,730 | |
| | Ceiling - Lay-in | 101A Office | 120 | SF | 6 | \$360 | |
| | Doors - Wood Doors inclu hw | 101A Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 101A Office | 120 | SF | 6 | \$120 | |
| | Lighting - Pendent/Surface | 101A Office | 3 | EA | 6 | \$372 | |
| | Power Distribution | 101A Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 101A Office | 420 | SF | 6 | \$1,159 | |
| | Ceiling - Lay-in | 101B Office | 145 | SF | 6 | \$435 | |
| | Doors - Wood Doors inclu hw | 101B Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 101B Office | 145 | SF | 6 | \$145 | |
| | Lighting - Pendent/Surface | 101B Office | 3 | EA | 6 | \$372 | |
| | Power Distribution | 101B Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 101B Office | 445 | SF | 6 | \$1,228 | |
| | Ceiling - Lay-in | 103 Office | 245 | SF | 6 | \$736 | |
| | Doors - Wood Doors inclu hw | 103 Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103 Office | 245 | SF | 6 | \$245 | |
| | Lighting - Lay-in | 103 Office | 4 | EA | 6 | \$476 | |
| | Power Distribution | 103 Office | 12 | EA | 6 | \$25,499 | |
| | Walls - Plaster/Drywall | 103 Office | 532 | SF | 6 | \$1,468 | |
| | Ceiling - Lay-in | 103B Office | 152 | SF | 6 | \$456 | |
| | Doors - Wood Doors inclu hw | 103B Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103B Office | 152 | SF | 6 | \$152 | |
| | Lighting - Lay-in | 103B Office | 3 | EA | 6 | \$357 | |
| | Power Distribution | 103B Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 103B Office | 469 | SF | 6 | \$1,294 | |
| | Work Sink | 103B Office | 1 | EA | 6 | \$508 | |
| | Ceiling - Lay-in | 103C Office | 120 | SF | 6 | \$360 | |
| | Doors - Wood Doors inclu hw | 103C Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103C Office | 120 | SF | 6 | \$120 | |
| | Lighting - Lay-in | 103C Office | 3 | EA | 6 | \$357 | |
| | Power Distribution | 103C Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 103C Office | 420 | SF | 6 | \$1,159 | |
| | Work Sink | 103C Office | 1 | EA | 6 | \$508 | |
| | Ceiling - Lay-in | 103D Office | 120 | SF | 6 | \$360 | |
| | Doors - Wood Doors inclu hw | 103D Office | 1 | EA | 6 | \$301 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-----------------------------|-------------------|----------|------|------|----------|----------|
| Administrative Suites/Offices | | | | | | | |
| | Floor - Tile/Sheet | 103D Office | 120 | SF | 6 | \$120 | |
| | Lighting - Lay-in | 103D Office | 3 | EA | 6 | \$357 | |
| | Power Distribution | 103D Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 103D Office | 420 | SF | 6 | \$1,159 | |
| | Work Slnk | 103D Office | 1 | EA | 6 | \$508 | |
| | Ceiling - Lay-in | 103E Office | 120 | SF | 6 | \$360 | |
| | Doors - Wood Doors inclu hw | 103E Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103E Office | 120 | SF | 6 | \$120 | |
| | Lighting - Lay-in | 103E Office | 4 | EA | 6 | \$476 | |
| | Power Distribution | 103E Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 103E Office | 420 | SF | 6 | \$1,159 | |
| | Work Slnk | 103E Office | 1 | EA | 6 | \$508 | |
| | Ceiling - Lay-in | 103F Office | 318 | SF | 6 | \$955 | |
| | Doors - Wood Doors inclu hw | 103F Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103F Office | 318 | SF | 6 | \$318 | |
| | Lighting - Lay-in | 103F Office | 8 | EA | 6 | \$952 | |
| | Power Distribution | 103F Office | 8 | EA | 6 | \$16,999 | |
| | Walls - Plaster/Drywall | 103F Office | 682 | SF | 6 | \$1,882 | |
| | Ceiling - Lay-in | 103G Staff Lounge | 132 | SF | 6 | \$396 | |
| | Doors - Wood Doors inclu hw | 103G Staff Lounge | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103G Staff Lounge | 132 | SF | 6 | \$132 | |
| | Lighting - Lay-in | 103G Staff Lounge | 3 | EA | 6 | \$357 | |
| | Power Distribution | 103G Staff Lounge | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 103G Staff Lounge | 438 | SF | 6 | \$1,209 | |
| | Ceiling - Lay-in | 103H Office | 140 | SF | 6 | \$420 | |
| | Doors - Wood Doors inclu hw | 103H Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 103H Office | 140 | SF | 6 | \$140 | |
| | Lighting - Lay-in | 103H Office | 3 | EA | 6 | \$357 | |
| | Power Distribution | 103H Office | 2 | EA | 6 | \$4,250 | |
| | Walls - Plaster/Drywall | 103H Office | 469 | SF | 6 | \$1,294 | |
| | Ceiling - Lay-in | 105 Office | 491 | SF | 6 | \$1,474 | |
| | Doors - Transom Window | 105 Office | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 105 Office | 2 | EA | 6 | \$602 | |
| | Floor - Tile/Sheet | 105 Office | 491 | SF | 6 | \$491 | |
| | Lighting - Pendent/Surface | 105 Office | 12 | EA | 6 | \$1,487 | |
| | Power Distribution | 105 Office | 12 | EA | 6 | \$25,499 | |
| | Walls - Plaster/Drywall | 105 Office | 1,167 | SF | 6 | \$3,221 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-----------------------------|---------------------------------|----------|------|------|----------|----------|
| Administrative Suites/Offices | | | | | | | |
| | Ceiling - Plaster/Drywall | 113 Main office | 1,015 | SF | 6 | \$3,513 | |
| | Doors - Transom Window | 113 Main office | 21 | SF | 6 | \$356 | |
| | Doors - Wood Doors inclu hw | 113 Main office | 3 | EA | 6 | \$903 | |
| | Floor - Carpet | 113 Main office | 650 | SF | 6 | \$1,385 | |
| | Floor - Tile/Sheet | 113 Main office | 365 | SF | 6 | \$365 | |
| | Lighting - Pendent/Surface | 113 Main office | 24 | EA | 6 | \$2,973 | |
| | Power Distribution | 113 Main office | 20 | EA | 6 | \$42,498 | |
| | Walls - Plaster/Drywall | 113 Main office | 1,640 | SF | 6 | \$4,526 | |
| | Ceiling - Plaster/Drywall | 114 Assistant Principals Office | 212 | SF | 6 | \$734 | |
| | Doors - Transom Window | 114 Assistant Principals Office | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 114 Assistant Principals Office | 2 | EA | 6 | \$602 | |
| | Floor - Carpet | 114 Assistant Principals Office | 212 | SF | 6 | \$452 | |
| | Lighting - Pendent/Surface | 114 Assistant Principals Office | 6 | EA | 6 | \$743 | |
| | Power Distribution | 114 Assistant Principals Office | 6 | EA | 6 | \$12,749 | |
| | Storage/ Closet | 114 Assistant Principals Office | 10 | SF | 6 | \$73 | |
| | Walls - Plaster/Drywall | 114 Assistant Principals Office | 752 | SF | 6 | \$2,075 | |
| | Ceiling - Plaster/Drywall | 115 Conference Room | 259 | SF | 6 | \$896 | |
| | Doors - Wood Doors inclu hw | 115 Conference Room | 2 | EA | 6 | \$602 | |
| | Floor - Carpet | 115 Conference Room | 187 | SF | 6 | \$398 | |
| | Floor - Tile/Sheet | 115 Conference Room | 72 | SF | 6 | \$72 | |
| | Lighting - Pendent/Surface | 115 Conference Room | 7 | EA | 6 | \$867 | |
| | Power Distribution | 115 Conference Room | 8 | EA | 6 | \$16,999 | |
| | Storage/ Closet | 115 Conference Room | 4 | SF | 6 | \$29 | |
| | Walls - Plaster/Drywall | 115 Conference Room | 836 | SF | 6 | \$2,307 | |
| | Ceiling - Plaster/Drywall | 117 Principal's office | 347 | SF | 6 | \$1,201 | |
| | Doors - Transom Window | 117 Principal's office | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 117 Principal's office | 3 | EA | 6 | \$903 | |
| | Floor - Carpet | 117 Principal's office | 347 | SF | 6 | \$739 | |
| | Lighting - Pendent/Surface | 117 Principal's office | 8 | EA | 6 | \$991 | |
| | Power Distribution | 117 Principal's office | 4 | EA | 6 | \$8,500 | |
| | Storage/ Closet | 117 Principal's office | 21 | SF | 6 | \$152 | |
| | Walls - Plaster/Drywall | 117 Principal's office | 1,685 | SF | 6 | \$4,650 | |
| | Ceiling - Lay-in | 119A Office | 116 | SF | 6 | \$348 | |
| | Doors - Wood Doors inclu hw | 119A Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119A Office | 116 | SF | 6 | \$247 | |
| | Lighting - Lay-in | 119A Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119A Office | 4 | EA | 6 | \$8,500 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-----------------------------|-----------------|----------|------|------|----------|----------|
| Administrative Suites/Offices | | | | | | | |
| | Walls - Plaster/Drywall | 119A Office | 477 | SF | 6 | \$1,316 | |
| | Ceiling - Lay-in | 119B Office | 106 | SF | 6 | \$318 | |
| | Doors - Wood Doors inclu hw | 119B Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119B Office | 106 | SF | 6 | \$226 | |
| | Lighting - Lay-in | 119B Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119B Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 119B Office | 460 | SF | 6 | \$1,270 | |
| | Ceiling - Lay-in | 119C & D Office | 479 | SF | 6 | \$1,438 | |
| | Doors - Transom Window | 119C & D Office | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 119C & D Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119C & D Office | 479 | SF | 6 | \$1,021 | |
| | Lighting - Pendent/Surface | 119C & D Office | 8 | EA | 6 | \$991 | |
| | Power Distribution | 119C & D Office | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 119C & D Office | 870 | SF | 6 | \$2,401 | |
| | Ceiling - Plaster/Drywall | 119E Office | 80 | SF | 6 | \$277 | |
| | Doors - Wood Doors inclu hw | 119E Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119E Office | 80 | SF | 6 | \$170 | |
| | Lighting - Lay-in | 119E Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119E Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 119E Office | 365 | SF | 6 | \$1,007 | |
| | Ceiling - Plaster/Drywall | 119G Office | 80 | SF | 6 | \$277 | |
| | Doors - Wood Doors inclu hw | 119G Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119G Office | 80 | SF | 6 | \$170 | |
| | Lighting - Lay-in | 119G Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119G Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 119G Office | 365 | SF | 6 | \$1,007 | |
| | Ceiling - Plaster/Drywall | 119I Office | 80 | SF | 6 | \$277 | |
| | Doors - Wood Doors inclu hw | 119I Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119I Office | 80 | SF | 6 | \$170 | |
| | Lighting - Lay-in | 119I Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119I Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 119I Office | 365 | SF | 6 | \$1,007 | |
| | Ceiling - Plaster/Drywall | 119J Office | 80 | SF | 6 | \$277 | |
| | Doors - Wood Doors inclu hw | 119J Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119J Office | 80 | SF | 6 | \$170 | |
| | Lighting - Lay-in | 119J Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119J Office | 4 | EA | 6 | \$8,500 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|---------------------------------|----------------------------|----------|------|------|----------|-----------|
| Administrative Suites/Offices | | | | | | | |
| | Walls - Plaster/Drywall | 119J Office | 365 | SF | 6 | \$1,007 | |
| | Ceiling - Plaster/Drywall | 119L Office | 80 | SF | 6 | \$277 | |
| | Doors - Wood Doors inclu hw | 119L Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119L Office | 80 | SF | 6 | \$170 | |
| | Lighting - Lay-in | 119L Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119L Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 119L Office | 365 | SF | 6 | \$1,007 | |
| | Ceiling - Plaster/Drywall | 119N Conference Room | 123 | SF | 6 | \$426 | |
| | Doors - Wood Doors inclu hw | 119N Conference Room | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 119N Conference Room | 123 | SF | 6 | \$262 | |
| | Lighting - Lay-in | 119N Conference Room | 2 | EA | 6 | \$238 | |
| | Power Distribution | 119N Conference Room | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 119N Conference Room | 469 | SF | 6 | \$1,294 | |
| | Ceiling - Plaster/Drywall | 126-1 Office | 108 | SF | 6 | \$374 | |
| | Doors - Wood Doors inclu hw | 126-1 Office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | 126-1 Office | 108 | SF | 6 | \$230 | |
| | Lighting - Pendent/Surface | 126-1 Office | 2 | EA | 6 | \$248 | |
| | Power Distribution | 126-1 Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 126-1 Office | 543 | SF | 6 | \$1,499 | |
| | Ceiling - Plaster/Drywall | 127A Office | 235 | SF | 6 | \$813 | |
| | Doors - Wood Doors inclu hw | 127A Office | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 127A Office | 235 | SF | 6 | \$235 | |
| | Lighting - Pendent/Surface | 127A Office | 3 | EA | 6 | \$372 | |
| | Power Distribution | 127A Office | 8 | EA | 6 | \$16,999 | |
| | Storage/ Closet | 127A Office | 20 | SF | 6 | \$145 | 4 Lockers |
| | Walls - Plaster/Drywall | 127A Office | 550 | SF | 6 | \$1,518 | |
| | Ceiling - Plaster/Drywall | 129 Viewing Station Office | 515 | SF | 6 | \$1,782 | |
| | Doors - Wood Doors inclu hw | 129 Viewing Station Office | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 129 Viewing Station Office | 515 | SF | 6 | \$3,631 | |
| | Lighting - Pendent/Surface | 129 Viewing Station Office | 12 | EA | 6 | \$1,487 | |
| | Power Distribution | 129 Viewing Station Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 129 Viewing Station Office | 1,200 | SF | 6 | \$3,312 | |
| | Ceiling - Plaster/Drywall | 139 practice room A | 58 | SF | 6 | \$201 | |
| | Doors - Steel Doors incl hw | 139 practice room A | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | 139 practice room A | 11 | SF | 6 | \$186 | |
| | Floor - Concrete Epoxy/ Painted | 139 practice room A | 58 | SF | 6 | \$31 | |
| | Lighting - Pendent/Surface | 139 practice room A | 1 | EA | 7 | \$0 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|---------------------------------|---------------------|----------|------|------|----------|---|
| Administrative Suites/Offices | | | | | | | |
| | Power Distribution | 139 practice room A | 2 | EA | 6 | \$4,250 | |
| | Walls - Masonry | 139 practice room A | 43 | SF | 6 | \$215 | Brick |
| | Walls - Masonry | 139 practice room A | 94 | SF | 6 | \$296 | Brick covered with sound panels |
| | Walls - Plaster/Drywall | 139 practice room A | 137 | SF | 6 | \$378 | |
| | Ceiling - Plaster/Drywall | 139 practice room C | 59 | SF | 6 | \$204 | |
| | Doors - Steel Doors incl hw | 139 practice room C | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | 139 practice room C | 11 | SF | 6 | \$186 | |
| | Floor - Concrete Epoxy/ Painted | 139 practice room C | 59 | SF | 6 | \$31 | |
| | Lighting - Pendent/Surface | 139 practice room C | 1 | EA | 7 | \$0 | |
| | Power Distribution | 139 practice room C | 2 | EA | 6 | \$4,250 | |
| | Walls - Masonry | 139 practice room C | 92 | SF | 6 | \$289 | Brick |
| | Walls - Plaster/Drywall | 139 practice room C | 95 | SF | 6 | \$262 | Sound panels |
| | Walls - Plaster/Drywall | 139 practice room C | 91 | SF | 6 | \$298 | |
| | Ceiling - Plaster/Drywall | 139 practice roomB | 58 | SF | 6 | \$201 | |
| | Doors - Steel Doors incl hw | 139 practice roomB | 1 | EA | 6 | \$301 | |
| | Floor - Concrete Epoxy/ Painted | 139 practice roomB | 58 | SF | 6 | \$31 | |
| | Lighting - Pendent/Surface | 139 practice roomB | 1 | EA | 7 | \$0 | |
| | Power Distribution | 139 practice roomB | 2 | EA | 6 | \$4,250 | |
| | Walls - Masonry | 139 practice roomB | 95 | SF | 6 | \$299 | Brick covered with sound panels. |
| | Walls - Masonry | 139 practice roomB | 21 | SF | 6 | \$105 | Brick |
| | Walls - Plaster/Drywall | 139 practice roomB | 160 | SF | 6 | \$442 | |
| | Ceiling - Plaster/Drywall | 141A ROTC office | 269 | SF | 6 | \$931 | |
| | Doors - Transom Window | 141A ROTC office | 9 | SF | 6 | \$152 | |
| | Doors - Wood Doors inclu hw | 141A ROTC office | 1 | EA | 6 | \$301 | |
| | Floor - Concrete | 141A ROTC office | 269 | SF | 6 | \$142 | |
| | Lighting - Pendent/Surface | 141A ROTC office | 8 | EA | 7 | \$0 | 2 in storage closets. |
| | Power Distribution | 141A ROTC office | 6 | EA | 6 | \$12,749 | |
| | Storage/ Closet | 141A ROTC office | 95 | SF | 5 | \$1,532 | Water damage missing plaster,peeling paint. |
| | Storage/ Closet | 141A ROTC office | 70 | SF | 6 | \$508 | |
| | Walls - Plaster/Drywall | 141A ROTC office | 672 | SF | 6 | \$1,855 | |
| | Ceiling - Lay-in | 207 Office | 387 | SF | 6 | \$1,162 | |
| | Doors - Transom Window | 207 Office | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 207 Office | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 207 Office | 387 | SF | 6 | \$2,728 | |
| | Lighting - Pendent/Surface | 207 Office | 8 | EA | 6 | \$991 | |
| | Power Distribution | 207 Office | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 207 Office | 1,026 | SF | 6 | \$2,832 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|--|--------------------------|----------|------|------|----------|---------------|
| Administrative Suites/Offices | | | | | | | |
| | Ceiling - Lay-in | 207A Office | 417 | SF | 6 | \$1,252 | |
| | Doors - Transom Window | 207A Office | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 207A Office | 1 | EA | 6 | \$301 | |
| | Floor - Weight/ Fitness Room Floor Matting | 207A Office | 417 | SF | 6 | \$2,182 | |
| | Lighting - Pendent/Surface | 207A Office | 12 | EA | 6 | \$1,487 | |
| | Power Distribution | 207A Office | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 207A Office | 1,026 | SF | 6 | \$2,832 | |
| | Ceiling - Plaster/Drywall | 208A | 173 | SF | 6 | \$599 | |
| | Doors - Wood Doors inclu hw | 208A | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 208A | 173 | SF | 6 | \$379 | |
| | Lighting - Pendent/Surface | 208A | 4 | EA | 7 | \$0 | |
| | Power Distribution | 208A | 2 | EA | 6 | \$4,250 | |
| | Walls - Plaster/Drywall | 208A | 677 | SF | 6 | \$1,868 | |
| | Ceiling - Lay-in | 215 Professional Library | 387 | SF | 6 | \$1,162 | |
| | Doors - Wood Doors inclu hw | 215 Professional Library | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 215 Professional Library | 387 | SF | 6 | \$2,728 | |
| | Lighting - Pendent/Surface | 215 Professional Library | 6 | EA | 6 | \$743 | |
| | Power Distribution | 215 Professional Library | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 215 Professional Library | 1,026 | SF | 6 | \$2,832 | |
| | Walls - Plaster/Drywall | 215 Professional Library | 12 | SF | 6 | \$46 | Wood Casework |
| | Ceiling - Plaster/Drywall | 217A Workroom | 280 | SF | 6 | \$969 | |
| | Doors - Wood Doors inclu hw | 217A Workroom | 2 | EA | 6 | \$602 | |
| | Floor - Wood | 217A Workroom | 280 | SF | 6 | \$1,974 | |
| | Lighting - Pendent/Surface | 217A Workroom | 8 | EA | 6 | \$991 | |
| | Power Distribution | 217A Workroom | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 217A Workroom | 510 | SF | 6 | \$1,408 | |
| | Ceiling - Plaster/Drywall | 217B Office | 190 | SF | 6 | \$658 | |
| | Doors - Wood Doors inclu hw | 217B Office | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 217B Office | 190 | SF | 6 | \$1,339 | |
| | Lighting - Pendent/Surface | 217B Office | 2 | EA | 6 | \$248 | |
| | Power Distribution | 217B Office | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 217B Office | 400 | SF | 6 | \$1,104 | |
| | Ceiling - Lay-in | 223A Office | 435 | SF | 6 | \$1,306 | |
| | Doors - Transom Window | 223A Office | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 223A Office | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 223A Office | 435 | SF | 6 | \$3,067 | |
| | Lighting - Lay-in | 223A Office | 9 | EA | 6 | \$1,071 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|--------------------------------|-----------------------|----------|------|------|----------|-------------------------------------|
| Administrative Suites/Offices | | | | | | | |
| | Power Distribution | 223A Office | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 223A Office | 800 | SF | 6 | \$2,208 | |
| | Ceiling - Lay-in | 223B Office | 375 | SF | 6 | \$1,126 | |
| | Doors - Transom Window | 223B Office | 24 | SF | 6 | \$406 | |
| | Doors - Wood Doors inclu hw | 223B Office | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 223B Office | 375 | SF | 6 | \$2,644 | |
| | Lighting - Lay-in | 223B Office | 6 | EA | 6 | \$714 | |
| | Power Distribution | 223B Office | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 223B Office | 780 | SF | 6 | \$2,153 | |
| | Ceiling - Plaster/Drywall | 229 Teachers Workroom | 265 | SF | 6 | \$917 | |
| | Doors - Wood Doors inclu hw | 229 Teachers Workroom | 1 | EA | 6 | \$301 | |
| | Floor - Wood | 229 Teachers Workroom | 265 | SF | 6 | \$1,868 | |
| | Lighting - Pendent/Surface | 229 Teachers Workroom | 8 | EA | 6 | \$991 | |
| | Power Distribution | 229 Teachers Workroom | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | 229 Teachers Workroom | 750 | SF | 6 | \$2,070 | |
| | Ceiling - Plaster/Drywall | 232A Coach Office | 217 | SF | 6 | \$751 | Isolated areas of cracking plaster. |
| | Doors - Side-lite | 232A Coach Office | 10 | SF | 6 | \$167 | |
| | Doors - Steel Doors incl hw | 232A Coach Office | 2 | EA | 6 | \$602 | |
| | Doors - Transom Window | 232A Coach Office | 34 | SF | 6 | \$576 | |
| | Floor - Wood | 232A Coach Office | 217 | SF | 6 | \$1,530 | |
| | Lighting - Pendent/Surface | 232A Coach Office | 3 | EA | 7 | \$0 | |
| | Power Distribution | 232A Coach Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 232A Coach Office | 359 | SF | 6 | \$991 | |
| | Walls - Structural Glazed Tile | 232A Coach Office | 169 | SF | 6 | \$532 | |
| | Ceiling - Plaster/Drywall | 232B Coach Office | 198 | SF | 6 | \$685 | |
| | Doors - Side-lite | 232B Coach Office | 10 | SF | 6 | \$167 | |
| | Doors - Steel Doors incl hw | 232B Coach Office | 2 | EA | 6 | \$602 | |
| | Doors - Transom Window | 232B Coach Office | 34 | SF | 6 | \$576 | |
| | Floor - Wood | 232B Coach Office | 197 | SF | 6 | \$1,389 | |
| | Lighting - Pendent/Surface | 232B Coach Office | 3 | EA | 7 | \$0 | |
| | Power Distribution | 232B Coach Office | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | 232B Coach Office | 359 | SF | 6 | \$991 | |
| | Walls - Structural Glazed Tile | 232B Coach Office | 169 | SF | 6 | \$532 | |
| | Ceiling - Lay-in | 303A Office | 569 | SF | 6 | \$1,709 | |
| | Doors - Wood Doors inclu hw | 303A Office | 2 | EA | 6 | \$602 | |
| | Floor - Tile/Sheet | 303A Office | 569 | SF | 6 | \$570 | |
| | Lighting - Pendent/Surface | 303A Office | 6 | EA | 6 | \$743 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-----------------------------|-----------------------|----------|------|------|----------|---------------------|
| Administrative Suites/Offices | | | | | | | |
| | Power Distribution | 303A Office | 12 | EA | 6 | \$25,499 | |
| | Walls - Plaster/Drywall | 303A Office | 1,176 | SF | 6 | \$3,246 | |
| | Ceiling - Lay-in | 327A Office | 573 | SF | 6 | \$1,721 | |
| | Doors - Wood Doors inclu hw | 327A Office | 2 | EA | 6 | \$602 | |
| | Floor - Tile/Sheet | 327A Office | 573 | SF | 6 | \$574 | |
| | Lighting - Pendent/Surface | 327A Office | 6 | EA | 6 | \$743 | |
| | Power Distribution | 327A Office | 12 | EA | 6 | \$25,499 | |
| | Walls - Plaster/Drywall | 327A Office | 1,176 | SF | 6 | \$3,246 | |
| | Ceiling - Plaster/Drywall | 352A therapy/ Trainer | 166 | SF | 6 | \$574 | |
| | Doors - Wood Doors inclu hw | 352A therapy/ Trainer | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 352A therapy/ Trainer | 166 | SF | 6 | \$363 | |
| | Lighting - Pendent/Surface | 352A therapy/ Trainer | 2 | EA | 6 | \$248 | Lights not working. |
| | Power Distribution | 352A therapy/ Trainer | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 352A therapy/ Trainer | 586 | SF | 6 | \$1,617 | |
| | Ceiling - Plaster/Drywall | 352E. Therapy/Trainer | 214 | SF | 6 | \$741 | |
| | Doors - Wood Doors inclu hw | 352E. Therapy/Trainer | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 352E. Therapy/Trainer | 214 | SF | 6 | \$468 | |
| | Lighting - Pendent/Surface | 352E. Therapy/Trainer | 2 | EA | 6 | \$248 | |
| | Power Distribution | 352E. Therapy/Trainer | 2 | EA | 6 | \$4,250 | |
| | Walls - Plaster/Drywall | 352E. Therapy/Trainer | 597 | SF | 6 | \$1,648 | |
| | Ceiling - Lay-in | 401-1 Office | 50 | SF | 6 | \$150 | |
| | Doors - Wood Doors inclu hw | 401-1 Office | 1 | EA | 6 | \$301 | |
| | Floor - Epoxy/ Painted | 401-1 Office | 50 | SF | 6 | \$26 | |
| | Lighting - Lay-in | 401-1 Office | 2 | EA | 6 | \$238 | |
| | Power Distribution | 401-1 Office | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | 401-1 Office | 200 | SF | 6 | \$552 | |
| | Ceiling - Lay-in | 406 - staff lounge | 912 | SF | 6 | \$2,739 | |
| | Doors - Wood Doors inclu hw | 406 - staff lounge | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 406 - staff lounge | 912 | SF | 6 | \$913 | |
| | Lighting - Pendent/Surface | 406 - staff lounge | 14 | EA | 6 | \$1,735 | |
| | Power Distribution | 406 - staff lounge | 8 | EA | 6 | \$16,999 | |
| | Walls - Plaster/Drywall | 406 - staff lounge | 2,174 | SF | 6 | \$6,000 | |
| | Ceiling - Plaster/Drywall | Band room 251 office | 97 | SF | 6 | \$336 | |
| | Doors - Steel Doors incl hw | Band room 251 office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | Band room 251 office | 97 | SF | 6 | \$207 | |
| | Lighting - Pendent/Surface | Band room 251 office | 2 | EA | 7 | \$0 | |
| | Power Distribution | Band room 251 office | 6 | EA | 6 | \$12,749 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|---------------------------------|---|----------|------|------|----------|---|
| Administrative Suites/Offices | | | | | | | |
| | Walls - Plaster/Drywall | Band room 251 office | 300 | SF | 6 | \$828 | |
| | Ceiling - Exposed | Engineers office | 264 | SF | 6 | \$393 | Steel ceiling is underside of upper storage area floor. |
| | Doors - Transom Window | Engineers office | 11 | SF | 6 | \$186 | |
| | Doors - Wood Doors inclu hw | Engineers office | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | Engineers office | 264 | SF | 6 | \$563 | |
| | Lighting - Pendent/Surface | Engineers office | 4 | EA | 7 | \$0 | |
| | Power Distribution | Engineers office | 8 | EA | 6 | \$16,999 | |
| | Walls - Masonry | Engineers office | 362 | SF | 6 | \$1,139 | Brick |
| | Walls - Plaster/Drywall | Engineers office | 187 | SF | 6 | \$516 | |
| | Ceiling - Plaster/Drywall | Engineers room. | 1,304 | SF | 6 | \$4,513 | |
| | Doors - Steel Doors incl hw | Engineers room. | 2 | EA | 6 | \$602 | |
| | Floor - Exposed | Engineers room. | 268 | SF | 6 | \$142 | Steel floor in upper storage area. |
| | Floor - Tile | Engineers room. | 1,304 | SF | 6 | \$2,853 | |
| | Lighting - Pendent/Surface | Engineers room. | 13 | EA | 7 | \$0 | |
| | Power Distribution | Engineers room. | 28 | EA | 6 | \$59,497 | |
| | Storage/ Closet | Engineers room. | 45 | SF | 6 | \$326 | |
| | Walls - Masonry | Engineers room. | 2,480 | SF | 6 | \$7,802 | Brick |
| | Walls - Plaster/Drywall | Engineers room. | 175 | SF | 6 | \$483 | |
| | Ceiling - Lay-in | Fine arts office 137A | 215 | SF | 6 | \$646 | |
| | Doors - Transom Window | Fine arts office 137A | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | Fine arts office 137A | 1 | EA | 6 | \$301 | |
| | Floor - Concrete Epoxy/ Painted | Fine arts office 137A | 215 | SF | 6 | \$114 | |
| | Lighting - Lay-in | Fine arts office 137A | 7 | EA | 7 | \$0 | One in storage closet |
| | Power Distribution | Fine arts office 137A | 10 | EA | 6 | \$21,249 | |
| | Storage/ Closet | Fine arts office 137A | 64 | SF | 6 | \$464 | |
| | Walls - Masonry | Fine arts office 137A | 250 | SF | 6 | \$787 | Brick |
| | Walls - Plaster/Drywall | Fine arts office 137A | 250 | SF | 6 | \$690 | |
| | Ceiling - Lay-in | First floor north end nurses office suite | 1,738 | SF | 6 | \$5,219 | |
| | Ceiling - Plaster/Drywall | First floor north end nurses office suite | 306 | SF | 6 | \$1,059 | |
| | Doors - Wood Doors inclu hw | First floor north end nurses office suite | 12 | EA | 6 | \$3,612 | |
| | Floor - Tile/Sheet | First floor north end nurses office suite | 2,044 | SF | 6 | \$2,046 | |
| | Lighting - Lay-in | First floor north end nurses office suite | 32 | EA | 6 | \$3,807 | |
| | Power Distribution | First floor north end nurses office suite | 34 | EA | 6 | \$72,246 | |
| | Storage/ Closet | First floor north end nurses office suite | 50 | SF | 6 | \$363 | |
| | Walls - Plaster/Drywall | First floor north end nurses office suite | 3,972 | SF | 6 | \$10,962 | |
| | Work Slnk | First floor north end nurses office suite | 6 | EA | 6 | \$3,049 | |
| | Ceiling - Plaster/Drywall | First floor room 105 | 492 | SF | 6 | \$1,703 | |

Building: Main
Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|--------------------------------|--|----------|------|------|----------|---------------------|
| Administrative Suites/Offices | | | | | | | |
| | Doors - Wood Doors inclu hw | First floor room 105 | 1 | EA | 6 | \$301 | |
| | Floor - Wood | First floor room 105 | 492 | SF | 6 | \$3,469 | |
| | Lighting - Pendent/Surface | First floor room 105 | 12 | EA | 6 | \$1,487 | |
| | Power Distribution | First floor room 105 | 10 | EA | 6 | \$21,249 | |
| | Walls - Plaster/Drywall | First floor room 105 | 1,164 | SF | 6 | \$3,213 | |
| | AC Unit | In mechanical service room in boiler room. | 1 | EA | 6 | \$496 | |
| | Ceiling - Lay-in | In mechanical service room in boiler room. | 72 | SF | 6 | \$216 | |
| | Doors - Steel Doors incl hw | In mechanical service room in boiler room. | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | In mechanical service room in boiler room. | 72 | SF | 5 | \$370 | Old and stained. |
| | Lighting - Lay-in | In mechanical service room in boiler room. | 2 | EA | 6 | \$238 | |
| | Power Distribution | In mechanical service room in boiler room. | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | In mechanical service room in boiler room. | 303 | SF | 6 | \$836 | Paneling. |
| | Ceiling - Lay-in | Pool office | 160 | SF | 6 | \$480 | |
| | Ceiling - Lay-in | Pool office | 20 | SF | 5 | \$139 | Water stained tiles |
| | Doors - Steel Doors incl hw | Pool office | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | Pool office | 34 | SF | 6 | \$576 | |
| | Floor - Sport Flooring | Pool office | 180 | SF | 6 | \$389 | |
| | Lighting - Lay-in | Pool office | 2 | EA | 6 | \$238 | Can lights. |
| | Power Distribution | Pool office | 4 | EA | 6 | \$8,500 | |
| | Walls - Concrete Block | Pool office | 181 | SF | 6 | \$531 | |
| | Walls - Structural Glazed Tile | Pool office | 447 | SF | 6 | \$1,406 | Brick |
| | Ceiling - Plaster/Drywall | Practice room A, rm 251 | 51 | SF | 6 | \$176 | |
| | Doors - Steel Doors incl hw | Practice room A, rm 251 | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | Practice room A, rm 251 | 10 | SF | 6 | \$169 | |
| | Floor - Carpet | Practice room A, rm 251 | 51 | SF | 6 | \$109 | |
| | Lighting - Pendent/Surface | Practice room A, rm 251 | 1 | EA | 6 | \$124 | |
| | Power Distribution | Practice room A, rm 251 | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | Practice room A, rm 251 | 173 | SF | 6 | \$477 | |
| | Walls - Plaster/Drywall | Practice room A, rm 251 | 87 | SF | 6 | \$285 | Sound panels |
| | Ceiling - Plaster/Drywall | Practice room B,in rm 251 | 51 | SF | 6 | \$176 | |
| | Doors - Steel Doors incl hw | Practice room B,in rm 251 | 1 | EA | 6 | \$301 | |
| | Floor - Carpet | Practice room B,in rm 251 | 51 | SF | 6 | \$109 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|--------------------------------|---------------------------------------|----------|------|------|----------|---------------|
| Administrative Suites/Offices | | | | | | | |
| | Lighting - Pendent/Surface | Practice room B,in rm 251 | 1 | EA | 7 | \$0 | |
| | Power Distribution | Practice room B,in rm 251 | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | Practice room B,in rm 251 | 185 | SF | 6 | \$511 | |
| | Walls - Plaster/Drywall | Practice room B,in rm 251 | 75 | SF | 6 | \$246 | sound panels |
| | Ceiling - Plaster/Drywall | Practice room C, in rm 251. | 51 | SF | 6 | \$176 | |
| | Doors - Steel Doors incl hw | Practice room C, in rm 251. | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | Practice room C, in rm 251. | 10 | SF | 6 | \$169 | |
| | Floor - Carpet | Practice room C, in rm 251. | 6 | SF | 6 | \$13 | |
| | Lighting - Pendent/Surface | Practice room C, in rm 251. | 1 | EA | 7 | \$0 | |
| | Power Distribution | Practice room C, in rm 251. | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | Practice room C, in rm 251. | 184 | SF | 6 | \$508 | |
| | Walls - Plaster/Drywall | Practice room C, in rm 251. | 74 | SF | 6 | \$242 | Sound panels. |
| | Ceiling - Plaster/Drywall | Practice room D, in rm 251. | 63 | SF | 6 | \$218 | |
| | Doors - Steel Doors incl hw | Practice room D, in rm 251. | 1 | EA | 6 | \$301 | |
| | Doors - Transom Window | Practice room D, in rm 251. | 10 | SF | 6 | \$169 | |
| | Floor - Carpet | Practice room D, in rm 251. | 63 | SF | 6 | \$134 | |
| | Lighting - Pendent/Surface | Practice room D, in rm 251. | 1 | EA | 7 | \$0 | |
| | Power Distribution | Practice room D, in rm 251. | 4 | EA | 6 | \$8,500 | |
| | Walls - Plaster/Drywall | Practice room D, in rm 251. | 97 | SF | 6 | \$318 | Sound panels |
| | Walls - Plaster/Drywall | Practice room D, in rm 251. | 193 | SF | 6 | \$533 | |
| | Ceiling - Plaster/Drywall | Second floor boys gym office (north). | 255 | SF | 6 | \$882 | |
| | Doors - Side-lite | Second floor boys gym office (north). | 10 | SF | 6 | \$167 | |
| | Doors - Steel Doors incl hw | Second floor boys gym office (north). | 2 | EA | 6 | \$602 | |
| | Doors - Transom Window | Second floor boys gym office (north). | 34 | SF | 6 | \$576 | |
| | Floor - Wood | Second floor boys gym office (north). | 255 | SF | 6 | \$1,798 | |
| | Lighting - Pendent/Surface | Second floor boys gym office (north). | 2 | EA | 7 | \$0 | |
| | Power Distribution | Second floor boys gym office (north). | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | Second floor boys gym office (north). | 206 | SF | 6 | \$569 | |
| | Walls - Structural Glazed Tile | Second floor boys gym office (north). | 284 | SF | 6 | \$893 | |
| | Ceiling - Plaster/Drywall | Second floor boys gym office (south). | 255 | SF | 6 | \$882 | |
| | Doors - Side-lite | Second floor boys gym office (south). | 10 | SF | 6 | \$167 | |
| | Doors - Steel Doors incl hw | Second floor boys gym office (south). | 2 | EA | 6 | \$602 | |
| | Doors - Transom Window | Second floor boys gym office (south). | 34 | SF | 6 | \$576 | |
| | Floor - Wood | Second floor boys gym office (south). | 255 | SF | 6 | \$1,798 | |
| | Lighting - Pendent/Surface | Second floor boys gym office (south). | 2 | EA | 7 | \$0 | |
| | Power Distribution | Second floor boys gym office (south). | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | Second floor boys gym office (south). | 206 | SF | 6 | \$569 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|-------------------------------------|---------------------------------------|----------|------|------|-----------|-------------------------------------|
| Administrative Suites/Offices | | | | | | | |
| | Walls - Structural Glazed Tile | Second floor boys gym office (south). | 284 | SF | 6 | \$893 | |
| | Ceiling - Plaster/Drywall | Second floor gym office. (North) | 217 | SF | 6 | \$751 | Isolated areas of cracking plaster. |
| | Doors - Side-lite | Second floor gym office. (North) | 10 | SF | 6 | \$167 | |
| | Doors - Steel Doors incl hw | Second floor gym office. (North) | 2 | EA | 6 | \$602 | |
| | Doors - Transom Window | Second floor gym office. (North) | 34 | SF | 6 | \$576 | |
| | Floor - Wood | Second floor gym office. (North) | 217 | SF | 6 | \$1,530 | |
| | Lighting - Pendent/Surface | Second floor gym office. (North) | 3 | EA | 7 | \$0 | |
| | Power Distribution | Second floor gym office. (North) | 6 | EA | 6 | \$12,749 | |
| | Walls - Plaster/Drywall | Second floor gym office. (North) | 359 | SF | 6 | \$991 | |
| | Walls - Structural Glazed Tile | Second floor gym office. (North) | 169 | SF | 6 | \$532 | |
| | Ceiling - Lay-in | Staff lunch room 403 | 1,075 | SF | 6 | \$3,228 | |
| | Doors - Wood Doors inclu hw | Staff lunch room 403 | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | Staff lunch room 403 | 1,075 | SF | 6 | \$1,076 | |
| | Lighting - Pendent/Surface | Staff lunch room 403 | 16 | EA | 6 | \$1,982 | |
| | Power Distribution | Staff lunch room 403 | 10 | EA | 6 | \$21,249 | |
| | Storage/ Closet | Staff lunch room 403 | 300 | SF | 6 | \$2,175 | |
| | Walls - Plaster/Drywall | Staff lunch room 403 | 1,990 | SF | 6 | \$5,492 | |
| Auditorium & Theater | | | | | | | |
| | Balcony Seating | Assembly Hall | 1,003 | EA | 6 | \$174,438 | |
| | Ceiling - Plaster/Drywall | Assembly Hall | 11,312 | SF | 6 | \$94,307 | |
| | Doors - Wood Doors inclu hw | Assembly Hall | 26 | EA | 6 | \$7,826 | |
| | Floor - Carpet | Assembly Hall | 5,835 | SF | 6 | \$12,433 | |
| | Floor - Concrete | Assembly Hall | 5,477 | SF | 6 | \$2,898 | |
| | Lighting - Chandelier, Incandescent | Assembly Hall | 2 | EA | 6 | \$955 | |
| | Lighting - Lay-in | Assembly Hall | 44 | EA | 6 | \$5,235 | |
| | Lighting - Pendent/Surface | Assembly Hall | 72 | EA | 6 | \$8,920 | |
| | Main Floor Seating | Assembly Hall | 580 | EA | 6 | \$100,872 | |
| | Sound System | Assembly Hall | 1 | EA | 6 | \$10,721 | |
| | Stage | Assembly Hall | 1,035 | SF | 6 | \$5,979 | |
| | Stage Curtain | Assembly Hall | 4 | EA | 6 | \$0 | |
| | Stage Lift | Assembly Hall | 1 | EA | 6 | \$6,510 | |
| | Stage Lighting System | Assembly Hall | 1 | EA | 6 | \$8,077 | |
| | Stage-Stairs - Wood | Assembly Hall | 27 | LF | 6 | \$317 | |
| | Stairs - Wood | Assembly Hall | 403 | LF | 6 | \$4,731 | |
| | Storage/ Closet | Assembly Hall | 131 | SF | 6 | \$950 | Stage light control room. |
| | Walls - Plaster/Drywall | Assembly Hall | 19,150 | SF | 6 | \$91,190 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|--------------------------------------|-----------------------|----------|------|------|-----------|---|
| Green House | | | | | | | |
| | Finishes | 125 | 1,285 | SF | 6 | \$7,038 | |
| | Glazing | 125 | 4,085 | SF | 6 | \$101,701 | |
| | Mechanical | 125 | 60 | SF | 6 | \$50 | |
| | Plumbing | 125 | 160 | SF | 6 | \$92 | |
| Gymnasia | | | | | | | |
| | Bleacher Seating | 232 Girl's Gymnasium | 432 | EA | 6 | \$12,503 | |
| | Ceiling - Plaster/Drywall | 232 Girl's Gymnasium | 7,356 | SF | 6 | \$40,604 | |
| | Ceiling - Plaster/Drywall | 232 Girl's Gymnasium | 300 | SF | 5 | \$6,010 | Water Damage |
| | Doors - Steel Doors incl hw | 232 Girl's Gymnasium | 2 | EA | 6 | \$602 | |
| | Floor - Wood | 232 Girl's Gymnasium | 7,356 | SF | 6 | \$51,859 | |
| | Lighting - Metal Halide/Sodium Vapor | 232 Girl's Gymnasium | 24 | EA | 6 | \$3,209 | |
| | Scoreboards | 232 Girl's Gymnasium | 2 | EA | 6 | \$4,489 | |
| | Walls - Plaster/Drywall | 232 Girl's Gymnasium | 4,998 | SF | 6 | \$13,794 | |
| | Walls - Structural Glazed Tile | 232 Girl's Gymnasium | 2,712 | SF | 6 | \$8,532 | |
| | Bleacher Seating | 2nd floor south boy's | 120 | EA | 6 | \$3,473 | |
| | Ceiling - Plaster/Drywall | 2nd floor south boy's | 7,500 | SF | 6 | \$41,399 | |
| | Ceiling - Plaster/Drywall | 2nd floor south boy's | 730 | SF | 4 | \$24,553 | Water damage, crumbling plaster, efflorescence. |
| | Doors - Steel Doors incl hw | 2nd floor south boy's | 7 | EA | 6 | \$2,107 | |
| | Floor - Sport Flooring | 2nd floor south boy's | 2,500 | SF | 6 | \$5,398 | Track |
| | Floor - Wood | 2nd floor south boy's | 8,230 | SF | 6 | \$58,021 | |
| | Lighting - Metal Halide/Sodium Vapor | 2nd floor south boy's | 24 | EA | 7 | \$0 | |
| | Scoreboards | 2nd floor south boy's | 3 | EA | 6 | \$6,733 | |
| | Sound System | 2nd floor south boy's | 1 | EA | 6 | \$41,654 | |
| | Storage/ Closet | 2nd floor south boy's | 211 | SF | 6 | \$1,530 | |
| | Walls - Plaster/Drywall | 2nd floor south boy's | 4,200 | SF | 6 | \$11,592 | |
| | Walls - Structural Glazed Tile | 2nd floor south boy's | 2,530 | SF | 6 | \$7,959 | Glazed brick. |
| Kitchen | | | | | | | |
| | Ceiling - Plaster/Drywall | 025 Kitchen | 193 | SF | 6 | \$668 | |
| | Doors - Transom Window | 025 Kitchen | 8 | SF | 6 | \$135 | |
| | Doors - Wood Doors inclu hw | 025 Kitchen | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 025 Kitchen | 193 | SF | 6 | \$193 | |
| | Lighting - Pendent/Surface | 025 Kitchen | 1 | EA | 6 | \$124 | |
| | Walls - Plaster/Drywall | 025 Kitchen | 713 | SF | 6 | \$1,968 | |
| | Ceiling - Lay-in | 401 Kitchen | 1,100 | SF | 6 | \$3,303 | |
| | Doors - Steel Doors incl hw | 401 Kitchen | 4 | EA | 6 | \$1,204 | |
| | Floor - Tile/Sheet | 401 Kitchen | 1,100 | SF | 6 | \$1,101 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---------------------------|-----------------------------------|-------------------------------|----------|------|------|----------|-------------------------------|
| Kitchen | | | | | | | |
| | Lighting - Lay-in | 401 Kitchen | 24 | EA | 6 | \$2,855 | |
| | Walls - Vinyl Coated Gypsum Panel | 401 Kitchen | 2,300 | SF | 6 | \$6,348 | |
| Library | | | | | | | |
| | Casework | 217 Library | 450 | LF | 6 | \$11,364 | |
| | Ceiling - Plaster/Drywall | 217 Library | 3,192 | SF | 6 | \$11,046 | |
| | Doors - Wood Doors inclu hw | 217 Library | 3 | EA | 6 | \$903 | |
| | Floor - Carpet | 217 Library | 3,192 | SF | 6 | \$6,801 | |
| | Lighting - Pendent/Surface | 217 Library | 92 | EA | 6 | \$11,398 | |
| | Walls - Plaster/Drywall | 217 Library | 3,550 | SF | 6 | \$9,798 | |
| Locker/Shower Room | | | | | | | |
| | Accessories | 244 Girl's Lockers | 2,499 | SF | 6 | \$9,792 | |
| | Benches, ped mounted | 244 Girl's Lockers | 144 | LF | 6 | \$15,679 | |
| | Ceiling - Plaster/ Drywall | 244 Girl's Lockers | 2,499 | SF | 6 | \$8,648 | |
| | Doors - Steel Doors incl hw | 244 Girl's Lockers | 4 | EA | 6 | \$1,204 | |
| | Floor Drain | 244 Girl's Lockers | 9 | EA | 6 | \$9,532 | |
| | Floor - Concrete | 244 Girl's Lockers | 1,910 | SF | 6 | \$1,011 | |
| | Floor - Terrazzo | 244 Girl's Lockers | 589 | SF | 6 | \$1,289 | |
| | Hand Dryer | 244 Girl's Lockers | 7 | EA | 6 | \$1,610 | |
| | Lighting - Pendent/Surface | 244 Girl's Lockers | 34 | EA | 6 | \$4,212 | |
| | Showers | 244 Girl's Lockers | 16 | EA | 6 | \$4,983 | |
| | Student Lockers - Two Tier | 244 Girl's Lockers | 400 | EA | 6 | \$18,567 | Double |
| | Walls - Plaster/Drywall | 244 Girl's Lockers | 3,461 | SF | 6 | \$9,552 | |
| | Walls - Structural Glazed Tile | 244 Girl's Lockers | 1,043 | SF | 6 | \$3,281 | |
| | Walls - Tile Ceramic/ Porcelain | 244 Girl's Lockers | 423 | SF | 6 | \$956 | |
| | Accessories | Boys locker room 2nd flr gym. | 3,308 | SF | 6 | \$12,961 | |
| | Benches, ped mounted | Boys locker room 2nd flr gym. | 80 | LF | 6 | \$8,710 | |
| | Ceiling - Plaster/ Drywall | Boys locker room 2nd flr gym. | 3,208 | SF | 6 | \$11,102 | |
| | Ceiling - Plaster/ Drywall | Boys locker room 2nd flr gym. | 100 | SF | 3 | \$2,176 | Water damage,falling plaster. |
| | Doors - Steel Doors incl hw | Boys locker room 2nd flr gym. | 3 | EA | 6 | \$903 | |
| | Doors - Transom Window | Boys locker room 2nd flr gym. | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | Boys locker room 2nd flr gym. | 2 | EA | 6 | \$602 | |
| | Floor Drain | Boys locker room 2nd flr gym. | 6 | EA | 6 | \$6,355 | |
| | Floor - Concrete | Boys locker room 2nd flr gym. | 2,858 | SF | 6 | \$1,512 | |
| | Floor - Tile Ceramic/ Porcelain | Boys locker room 2nd flr gym. | 450 | SF | 6 | \$952 | |
| | Hand Dryer | Boys locker room 2nd flr gym. | 1 | EA | 5 | \$590 | Wiring not in conduit. |
| | Lavatory | Boys locker room 2nd flr gym. | 2 | EA | 6 | \$639 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------------------------|---------------------------------|-------------------------------|----------|------|------|----------|------------------------------|
| Locker/Shower Room | | | | | | | |
| | Lighting - Pendent/Surface | Boys locker room 2nd flr gym. | 34 | EA | 7 | \$0 | |
| | Partitions | Boys locker room 2nd flr gym. | 8 | EA | 6 | \$2,375 | |
| | Showers | Boys locker room 2nd flr gym. | 12 | EA | 6 | \$3,737 | |
| | Student Lockers - One Tier | Boys locker room 2nd flr gym. | 318 | EA | 6 | \$29,522 | |
| | Urinals | Boys locker room 2nd flr gym. | 1 | EA | 6 | \$336 | |
| | Walls - Plaster/Drywall | Boys locker room 2nd flr gym. | 3,370 | SF | 6 | \$9,301 | |
| | Walls - Structural Glazed Tile | Boys locker room 2nd flr gym. | 900 | SF | 6 | \$2,831 | |
| | Walls - Tile Ceramic/ Porcelain | Boys locker room 2nd flr gym. | 1,070 | SF | 6 | \$2,418 | |
| | Water Closet | Boys locker room 2nd flr gym. | 3 | EA | 6 | \$1,008 | |
| Lunch & Multipurpose Room | | | | | | | |
| | Ceiling - Plaster/Drywall | 317 Multipurpose Room | 3,450 | SF | 6 | \$11,939 | 650 SF of skylight |
| | Ceiling - Plaster/Drywall | 317 Multipurpose Room | 200 | SF | 5 | \$2,500 | Water Damage |
| | Doors - Wood Doors inclu hw | 317 Multipurpose Room | 4 | EA | 6 | \$1,204 | |
| | Floor - Wood | 317 Multipurpose Room | 4,100 | SF | 6 | \$28,905 | |
| | Lighting - Pendent/Surface | 317 Multipurpose Room | 22 | EA | 6 | \$2,726 | |
| | Market Board | 317 Multipurpose Room | 8 | LF | 6 | \$171 | |
| | Stage | 317 Multipurpose Room | 1,058 | SF | 6 | \$6,112 | |
| | Walls - Plaster/Drywall | 317 Multipurpose Room | 5,800 | SF | 6 | \$16,007 | |
| | Ceiling - Lay-in | 400, 402 & 405 - Lunchroom | 3,972 | SF | 6 | \$11,928 | |
| | Floor - Tile/Sheet | 400, 402 & 405 - Lunchroom | 3,972 | SF | 6 | \$3,976 | |
| | Lighting - Pendent/Surface | 400, 402 & 405 - Lunchroom | 84 | EA | 6 | \$10,407 | |
| | Serving Line | 400, 402 & 405 - Lunchroom | 80 | LF | 6 | \$4,761 | |
| | Walls - Plaster/Drywall | 400, 402 & 405 - Lunchroom | 2,917 | SF | 6 | \$8,051 | |
| | Walls - Structural Glazed Tile | 400, 402 & 405 - Lunchroom | 1,092 | SF | 6 | \$3,435 | |
| MDF_IDF | | | | | | | |
| | Doors - Wood Doors inclu hw | 229A MDF Room | 1 | EA | 6 | \$301 | |
| | Finishes | 229A MDF Room | 176 | SF | 6 | \$1,256 | |
| | Ventilation and Cooling | 229A MDF Room | 1 | EA | 6 | \$1,855 | |
| | AC Unit | Rm202 | 1 | EA | 6 | \$496 | |
| | Doors - Wood Doors inclu hw | Rm202 | 1 | EA | 6 | \$301 | |
| | Finishes | Rm202 | 341 | SF | 6 | \$2,433 | |
| | Ventilation and Cooling | Rm202 | 1 | EA | 6 | \$1,855 | |
| Mechanical/ Service Rooms | | | | | | | |
| | Air Intake Plenums | 1st Floor | 250 | SF | 6 | \$1,548 | North plenum. Peeling paint. |
| | Air Intake Plenums | 1st Floor | 158 | SF | 6 | \$978 | |
| | Air Intake Plenums | 1st Floor | 738 | SF | 6 | \$4,570 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|----------------------------------|---------------------------|-----------|----------|------|------|-----------|---|
| Mechanical/ Service Rooms | | | | | | | |
| | Boiler Room | 1st Floor | 3,427 | SF | 6 | \$24,552 | |
| | Crawl Space - Unfinished | 1st Floor | 19,309 | SF | 6 | \$119,559 | Underneath entire 1st floor corridor / Some water penetration, seepage occurring throughout |
| | Interior Stairs | 1st Floor | 126 | LF | 6 | \$1,137 | |
| | Janitor's Closet | 1st Floor | 30 | SF | 6 | \$215 | 105C, Next to girls restroom |
| | Loading Docks | 1st Floor | 1,297 | SF | 6 | \$9,292 | Yard storage/ loading dock. |
| | Mechanical/ Service Rooms | 1st Floor | 676 | SF | 5 | \$10,904 | Air handler 5. Peeling paint,deteriorating brick walls. |
| | Mechanical/ Service Rooms | 1st Floor | 150 | SF | 5 | \$2,420 | Machine rm across from elevator. Peeling paint. |
| | Mechanical/ Service Rooms | 1st Floor | 413 | SF | 6 | \$2,959 | Across from classroom 134 |
| | Mechanical/ Service Rooms | 1st Floor | 170 | SF | 6 | \$1,218 | Electrical rm |
| | Mechanical/ Service Rooms | 1st Floor | 588 | SF | 6 | \$4,213 | 105A, Engineers room. |
| | Mechanical/ Service Rooms | 1st Floor | 780 | SF | 5 | \$12,582 | Boiler room , peeling paint. |
| | Mechanical/ Service Rooms | 1st Floor | 20 | SF | 6 | \$0 | Next to boys restroom |
| | Mechanical/ Service Rooms | 1st Floor | 1,059 | SF | 6 | \$7,587 | Air handlers 3,6 Across from south side of auditorium. |
| | Mechanical/ Service Rooms | 1st Floor | 1,100 | SF | 5 | \$17,743 | Air handler rm 4, peeling paint. |
| | Storage Room | 1st Floor | 90 | SF | 6 | \$645 | Across from assembly hall |
| | Storage Room | 1st Floor | 1,034 | SF | 6 | \$7,408 | 101, 101C, 101C-1, 101D, 102, 105B, 127B All these storage room are adding together. |
| | Storage Room | 1st Floor | 76 | SF | 6 | \$544 | Near door 9 |
| | Storage Room | 1st Floor | 327 | SF | 5 | \$5,275 | Boiler room storage. Standing water. |
| | Storage Room | 1st Floor | 271 | SF | 6 | \$1,942 | Boiler room storage |
| | Storage Room | 1st Floor | 425 | SF | 6 | \$3,045 | Next to loading dock/yard storage. |
| | Storage Room | 1st Floor | 92 | SF | 6 | \$659 | Across from loading dock/ yard storage. |
| | Storage Room | 1st Floor | 70 | SF | 6 | \$502 | Next to engineers office |
| | Storage Room | 1st Floor | 136 | SF | 6 | \$974 | Between 136,138 |
| | Storage Room | 1st Floor | 75 | SF | 6 | \$537 | Next to engineers office |
| | Storage Room | 1st Floor | 46 | SF | 6 | \$330 | Storage rm2 outside rm 138 |
| | Storage Room | 1st Floor | 55 | SF | 6 | \$394 | Storage rm1 outside of rm 138 |
| | Storage Room | 1st Floor | 200 | SF | 6 | \$1,433 | Across from ADA stage access |
| | Storage Room | 1st Floor | 452 | SF | 6 | \$3,238 | Instrument storage. |
| | Storage Room | 1st Floor | 34 | SF | 6 | \$0 | Outside of rm 136 |
| | Storage Room | 1st Floor | 101 | SF | 6 | \$724 | Across from rm 140 |
| | Storage Room | 1st Floor | 1,043 | SF | 6 | \$7,472 | Lower storage rm. Being used as baseball training rm. |
| | Storage Room | 1st Floor | 1,250 | SF | 6 | \$8,955 | Far south |
| | Storage Room | 1st Floor | 1,867 | SF | 6 | \$13,376 | Upper level of storage rm far south. |
| | Janitor's Closet | 2nd Floor | 20 | SF | 6 | \$143 | Next to girls restroom. |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|----------------------------------|--------------------------------|-----------|----------|------|------|----------|---|
| Mechanical/ Service Rooms | | | | | | | |
| | Janitor's Closet | 2nd Floor | 20 | SF | 6 | \$143 | 201A, 225B Janitor Closet |
| | Janitor's Closet | 2nd Floor | 22 | SF | 6 | \$158 | In boys locker room. |
| | Mechanical/ Service Rooms | 2nd Floor | 1,176 | SF | 6 | \$8,425 | Fan room |
| | Mechanical/ Service Rooms | 2nd Floor | 288 | SF | 5 | \$4,646 | Across from girls gym. Efloresence,peeling paint/plaster on ceiling. |
| | Mechanical/ Service Rooms | 2nd Floor | 1,176 | SF | 6 | \$8,425 | Across from North balcony entrance |
| | Storage Room | 2nd Floor | 419 | SF | 6 | \$3,002 | Storage rm 2, across from library |
| | Storage Room | 2nd Floor | 276 | SF | 6 | \$1,977 | Storage rm 1, across from library. |
| | Storage Room | 2nd Floor | 256 | SF | 6 | \$1,834 | Across from south boys gym. |
| | Storage Room | 2nd Floor | 967 | SF | 6 | \$6,928 | 201-1, 203A, 217C, 225A, 227B, 227C, 229A-1, 232C, 232D, 232E Storage |
| | Janitor's Closet | 3rd Floor | 20 | SF | 6 | \$143 | Next to girls restroom |
| | Janitor's Closet | 3rd Floor | 10 | SF | 6 | \$72 | 302A Janitor's Closet |
| | Mechanical/ Service Rooms | 3rd Floor | 125 | SF | 6 | \$896 | 352B |
| | Mechanical/ Service Rooms | 3rd Floor | 166 | SF | 6 | \$1,189 | Control room for auditorium. |
| | Mechanical/ Service Rooms | 3rd Floor | 192 | SF | 6 | \$1,376 | Across fro upper boys gym. |
| | Mechanical/ Service Rooms | 3rd Floor | 230 | SF | 6 | \$1,648 | Across from fitness center |
| | Mechanical/ Service Rooms | 3rd Floor | 127 | SF | 6 | \$910 | In rm 352E |
| | Storage Room | 3rd Floor | 232 | SF | 6 | \$1,662 | 333 |
| | Storage Room | 3rd Floor | 105 | SF | 6 | \$752 | Next to 3rd flr boys rst rm |
| | Storage Room | 3rd Floor | 105 | SF | 6 | \$752 | next to girls restroom |
| | Storage Room | 3rd Floor | 55 | SF | 6 | \$394 | At assembly hall 1st balcony entrance |
| | Storage Room | 3rd Floor | 20 | SF | 6 | \$143 | Next to 3rd flr boys rst rm |
| | Storage Room | 3rd Floor | 55 | SF | 6 | \$394 | Storage rm 2 at assembly hall Lower balcony entrance |
| Pool & Natatorium | | | | | | | |
| | Accessories | 1st Floor | 3,220 | SF | 6 | \$2,210 | |
| | Ceiling - Lay-In | 1st Floor | 3,414 | SF | 6 | \$10,252 | |
| | Ceiling - Plaster/ Drywall | 1st Floor | 260 | SF | 6 | \$1,435 | |
| | Doors - Steel Doors incl hw | 1st Floor | 3 | EA | 6 | \$903 | |
| | Floor - Sport Flooring | 1st Floor | 630 | SF | 6 | \$1,360 | |
| | Lighting - Lay-in | 1st Floor | 15 | EA | 7 | \$0 | Can lights |
| | Lighting - Wall Mounted | 1st Floor | 12 | EA | 7 | \$0 | |
| | Pool Basin | 1st Floor | 1,444 | SF | 6 | \$48,856 | |
| | Pool Deck | 1st Floor | 830 | SF | 6 | \$7,881 | Sport flooring |
| | Pool Deck Drains | 1st Floor | 4 | EA | 6 | \$1,688 | |
| | Walls - Structural Glazed Tile | 1st Floor | 4,342 | SF | 6 | \$13,660 | |

Building: Main
Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|------------------|-----------------------------|-----------------|----------|------|------|---------|----------------------|
| Prep Room | | | | | | | |
| | Casework | 127-1 Prep Room | 20 | LF | 6 | \$505 | |
| | Ceiling - Lay-in | 127-1 Prep Room | 226 | SF | 6 | \$679 | |
| | Doors - Steel Doors incl hw | 127-1 Prep Room | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 127-1 Prep Room | 226 | SF | 6 | \$226 | |
| | Lighting - Lay-in | 127-1 Prep Room | 3 | EA | 6 | \$357 | |
| | Walls - Plaster/Drywall | 127-1 Prep Room | 613 | SF | 6 | \$1,692 | |
| | Work Sink | 127-1 Prep Room | 3 | EA | 6 | \$1,137 | Gas Line |
| | Work Sink | 127-1 Prep Room | 1 | EA | 6 | \$379 | |
| | Casework | 203B Prep Room | 38 | LF | 6 | \$960 | |
| | Ceiling - Lay-in | 203B Prep Room | 565 | SF | 6 | \$1,697 | |
| | Doors - Steel Doors incl hw | 203B Prep Room | 1 | EA | 6 | \$301 | |
| | Floor - Epoxy/ Painted | 203B Prep Room | 565 | SF | 6 | \$299 | |
| | Lighting - Lay-in | 203B Prep Room | 10 | EA | 6 | \$1,190 | |
| | Student Lockers - One Tier | 203B Prep Room | 12 | EA | 6 | \$1,114 | Storage / Closet |
| | Walls - Plaster/Drywall | 203B Prep Room | 986 | SF | 6 | \$2,721 | |
| | Work Sink | 203B Prep Room | 1 | EA | 6 | \$379 | |
| | Casework | 227A Prep Room | 38 | LF | 6 | \$960 | |
| | Ceiling - Lay-in | 227A Prep Room | 565 | SF | 6 | \$1,697 | |
| | Doors - Steel Doors incl hw | 227A Prep Room | 1 | EA | 6 | \$301 | |
| | Floor - Epoxy/ Painted | 227A Prep Room | 565 | SF | 6 | \$299 | |
| | Lighting - Lay-in | 227A Prep Room | 6 | EA | 6 | \$714 | |
| | Walls - Plaster/Drywall | 227A Prep Room | 986 | SF | 6 | \$2,721 | |
| | Work Sink | 227A Prep Room | 1 | EA | 6 | \$379 | |
| | Casework | 302A | 40 | LF | 6 | \$1,010 | |
| | Ceiling - Lay-in | 302A | 40 | SF | 3 | \$453 | Water damaged tiles. |
| | Ceiling - Lay-in | 302A | 275 | SF | 6 | \$826 | |
| | Doors - Steel Doors incl hw | 302A | 1 | EA | 6 | \$301 | |
| | Floor - Tile | 302A | 315 | SF | 6 | \$689 | |
| | Lighting - Lay-in | 302A | 7 | EA | 6 | \$833 | |
| | Walls - Plaster/Drywall | 302A | 732 | SF | 6 | \$2,020 | |
| | Work Sink | 302A | 1 | EA | 6 | \$379 | |
| | Casework | 322B, in rm 322 | 38 | LF | 6 | \$960 | |
| | Ceiling - Lay-in | 322B, in rm 322 | 8 | SF | 3 | \$112 | Water stained tile. |
| | Ceiling - Lay-in | 322B, in rm 322 | 194 | SF | 6 | \$583 | |
| | Doors - Steel Doors incl hw | 322B, in rm 322 | 1 | EA | 6 | \$301 | |
| | Floor - Tile/Sheet | 322B, in rm 322 | 202 | SF | 6 | \$202 | |
| | Lighting - Lay-in | 322B, in rm 322 | 3 | EA | 7 | \$0 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|------------------|---------------------------------|--------------------|----------|------|------|---------|----------|
| Prep Room | | | | | | | |
| | Walls - Plaster/Drywall | 322B, in rm 322 | 586 | SF | 6 | \$1,617 | |
| | Work Sink | 322B, in rm 322 | 1 | EA | 6 | \$379 | |
| | Casework | 323A - Prep Room | 38 | LF | 6 | \$960 | |
| | Ceiling - Lay-in | 323A - Prep Room | 274 | SF | 6 | \$823 | |
| | Doors - Steel Doors incl hw | 323A - Prep Room | 1 | EA | 6 | \$301 | |
| | Floor - Epoxy/ Painted | 323A - Prep Room | 202 | SF | 6 | \$107 | |
| | Lighting - Lay-in | 323A - Prep Room | 3 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | 323A - Prep Room | 586 | SF | 6 | \$1,617 | |
| | Work Sink | 323A - Prep Room | 1 | EA | 6 | \$379 | |
| Restroom | | | | | | | |
| | Accessories | 103A Unisex Toilet | 44 | SF | 6 | \$406 | |
| | Ceiling - Plaster/Drywall | 103A Unisex Toilet | 44 | SF | 6 | \$152 | |
| | Doors - Wood Doors inclu hw | 103A Unisex Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 103A Unisex Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 103A Unisex Toilet | 44 | SF | 6 | \$93 | |
| | Lavatory | 103A Unisex Toilet | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 103A Unisex Toilet | 1 | EA | 6 | \$124 | |
| | Walls - Plaster/Drywall | 103A Unisex Toilet | 68 | SF | 6 | \$188 | |
| | Walls - Tile Ceramic/ Porcelain | 103A Unisex Toilet | 185 | SF | 6 | \$418 | |
| | Water Closet | 103A Unisex Toilet | 1 | EA | 6 | \$336 | |
| | Accessories | 115D Unisex Toilet | 33 | SF | 6 | \$304 | |
| | Ceiling - Plaster/Drywall | 115D Unisex Toilet | 33 | SF | 6 | \$114 | |
| | Doors - Wood Doors inclu hw | 115D Unisex Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 115D Unisex Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 115D Unisex Toilet | 33 | SF | 6 | \$70 | |
| | Lavatory | 115D Unisex Toilet | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 115D Unisex Toilet | 1 | EA | 6 | \$124 | |
| | Walls - Plaster/Drywall | 115D Unisex Toilet | 68 | SF | 6 | \$188 | |
| | Walls - Tile Ceramic/ Porcelain | 115D Unisex Toilet | 185 | SF | 6 | \$418 | |
| | Water Closet | 115D Unisex Toilet | 1 | EA | 6 | \$336 | |
| | Accessories | 116A Mens Toilet | 160 | SF | 6 | \$1,476 | |
| | Ceiling - Plaster/Drywall | 116A Mens Toilet | 160 | SF | 6 | \$554 | |
| | Doors - Wood Doors inclu hw | 116A Mens Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 116A Mens Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 116A Mens Toilet | 160 | SF | 6 | \$339 | |
| | Lavatory | 116A Mens Toilet | 2 | EA | 6 | \$639 | |
| | Lighting - Pendent/Surface | 116A Mens Toilet | 2 | EA | 6 | \$248 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|-------------------------|----------|------|------|---------|----------|
| Restroom | | | | | | | |
| | Partitions | 116A Mens Toilet | 1 | EA | 6 | \$297 | |
| | Urinals | 116A Mens Toilet | 1 | EA | 6 | \$336 | |
| | Walls - Plaster/Drywall | 116A Mens Toilet | 780 | SF | 6 | \$2,153 | |
| | Walls - Tile Ceramic/ Porcelain | 116A Mens Toilet | 460 | SF | 6 | \$1,039 | |
| | Water Closet | 116A Mens Toilet | 1 | EA | 6 | \$336 | |
| | Accessories | 117A Principals Toilet | 44 | SF | 6 | \$406 | |
| | Ceiling - Plaster/Drywall | 117A Principals Toilet | 44 | SF | 6 | \$152 | |
| | Doors - Wood Doors inclu hw | 117A Principals Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 117A Principals Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 117A Principals Toilet | 44 | SF | 6 | \$93 | |
| | Lavatory | 117A Principals Toilet | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 117A Principals Toilet | 1 | EA | 6 | \$124 | |
| | Walls - Plaster/Drywall | 117A Principals Toilet | 68 | SF | 6 | \$188 | |
| | Walls - Tile Ceramic/ Porcelain | 117A Principals Toilet | 185 | SF | 6 | \$418 | |
| | Water Closet | 117A Principals Toilet | 1 | EA | 6 | \$336 | |
| | Accessories | 131 Boys Toilet | 632 | SF | 6 | \$5,829 | |
| | Ceiling - Plaster/Drywall | 131 Boys Toilet | 632 | SF | 6 | \$2,187 | |
| | Doors - Wood Doors inclu hw | 131 Boys Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 131 Boys Toilet | 2 | EA | 6 | \$2,118 | |
| | Floor - Tile Ceramic/ Porcelain | 131 Boys Toilet | 632 | SF | 6 | \$1,338 | |
| | Hand Dryer | 131 Boys Toilet | 2 | EA | 6 | \$460 | |
| | Lavatory | 131 Boys Toilet | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendent/Surface | 131 Boys Toilet | 10 | EA | 6 | \$1,239 | |
| | Partitions | 131 Boys Toilet | 6 | EA | 6 | \$1,782 | |
| | Urinals | 131 Boys Toilet | 11 | EA | 6 | \$3,696 | |
| | Walls - Plaster/Drywall | 131 Boys Toilet | 471 | SF | 6 | \$1,300 | |
| | Walls - Tile Ceramic/ Porcelain | 131 Boys Toilet | 839 | SF | 6 | \$1,896 | Stone |
| | Water Closet | 131 Boys Toilet | 7 | EA | 6 | \$2,352 | |
| | Accessories | 140 Womens Staff Toilet | 151 | SF | 6 | \$1,393 | |
| | Ceiling - Plaster/Drywall | 140 Womens Staff Toilet | 151 | SF | 6 | \$523 | |
| | Doors - Wood Doors inclu hw | 140 Womens Staff Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 140 Womens Staff Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 140 Womens Staff Toilet | 151 | SF | 6 | \$320 | |
| | Lavatory | 140 Womens Staff Toilet | 2 | EA | 6 | \$639 | |
| | Lighting - Pendent/Surface | 140 Womens Staff Toilet | 2 | EA | 6 | \$248 | |
| | Partitions | 140 Womens Staff Toilet | 1 | EA | 6 | \$297 | |
| | Walls - Plaster/Drywall | 140 Womens Staff Toilet | 334 | SF | 6 | \$922 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|------------------------------------|----------|------|------|---------|----------|
| Restroom | | | | | | | |
| | Walls - Tile Ceramic/ Porcelain | 140 Womens Staff Toilet | 438 | SF | 6 | \$990 | |
| | Water Closet | 140 Womens Staff Toilet | 1 | EA | 6 | \$336 | |
| | Accessories | 141A unisex restroom | 103 | SF | 6 | \$950 | |
| | Ceiling - Plaster/Drywall | 141A unisex restroom | 103 | SF | 6 | \$356 | |
| | Doors - Wood Doors inclu hw | 141A unisex restroom | 1 | EA | 6 | \$301 | |
| | Floor Drain | 141A unisex restroom | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 141A unisex restroom | 103 | SF | 6 | \$218 | |
| | Lavatory | 141A unisex restroom | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 141A unisex restroom | 2 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | 141A unisex restroom | 83 | SF | 6 | \$229 | |
| | Walls - Tile Ceramic/ Porcelain | 141A unisex restroom | 285 | SF | 6 | \$644 | |
| | Water Closet | 141A unisex restroom | 1 | EA | 6 | \$336 | |
| | Accessories | 154C Girls Toilet | 621 | SF | 6 | \$5,728 | |
| | Ceiling - Plaster/Drywall | 154C Girls Toilet | 621 | SF | 6 | \$2,149 | |
| | Doors - Wood Doors inclu hw | 154C Girls Toilet | 2 | EA | 6 | \$602 | |
| | Floor Drain | 154C Girls Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 154C Girls Toilet | 621 | SF | 6 | \$1,314 | |
| | Hand Dryer | 154C Girls Toilet | 2 | EA | 6 | \$460 | |
| | Lavatory | 154C Girls Toilet | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendent/Surface | 154C Girls Toilet | 10 | EA | 6 | \$1,239 | |
| | Partitions | 154C Girls Toilet | 16 | EA | 6 | \$4,751 | |
| | Walls - Plaster/Drywall | 154C Girls Toilet | 1,358 | SF | 6 | \$3,748 | |
| | Water Closet | 154C Girls Toilet | 17 | EA | 6 | \$5,712 | |
| | Accessories | 1st flr Staff unisex restroom,131B | 160 | SF | 6 | \$1,476 | |
| | Ceiling - Plaster/Drywall | 1st flr Staff unisex restroom,131B | 160 | SF | 6 | \$554 | |
| | Doors - Wood Doors inclu hw | 1st flr Staff unisex restroom,131B | 1 | EA | 6 | \$301 | |
| | Floor Drain | 1st flr Staff unisex restroom,131B | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 1st flr Staff unisex restroom,131B | 160 | SF | 6 | \$339 | |
| | Lavatory | 1st flr Staff unisex restroom,131B | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 1st flr Staff unisex restroom,131B | 3 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | 1st flr Staff unisex restroom,131B | 780 | SF | 6 | \$2,153 | |
| | Walls - Tile Ceramic/ Porcelain | 1st flr Staff unisex restroom,131B | 460 | SF | 6 | \$1,039 | |
| | Water Closet | 1st flr Staff unisex restroom,131B | 1 | EA | 6 | \$336 | |
| | Accessories | 244B Girl's Toilet | 135 | SF | 6 | \$1,245 | |
| | Ceiling - Plaster/Drywall | 244B Girl's Toilet | 135 | SF | 6 | \$467 | |
| | Floor - Terrazzo | 244B Girl's Toilet | 135 | SF | 6 | \$295 | |
| | Hand Dryer | 244B Girl's Toilet | 1 | EA | 6 | \$230 | |

Building: Main
Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|-------------------------|----------|------|------|---------|----------|
| Restroom | | | | | | | |
| | Lavatory | 244B Girl's Toilet | 2 | EA | 6 | \$639 | |
| | Lighting - Pendant/Surface | 244B Girl's Toilet | 1 | EA | 6 | \$124 | |
| | Partitions | 244B Girl's Toilet | 3 | EA | 6 | \$891 | |
| | Walls - Plaster/Drywall | 244B Girl's Toilet | 616 | SF | 6 | \$1,700 | |
| | Water Closet | 244B Girl's Toilet | 3 | EA | 6 | \$1,008 | |
| | Accessories | 244C Girl's Toilet | 184 | SF | 6 | \$1,697 | |
| | Ceiling - Plaster/Drywall | 244C Girl's Toilet | 184 | SF | 6 | \$637 | |
| | Floor Drain | 244C Girl's Toilet | 2 | EA | 6 | \$2,118 | |
| | Floor - Terrazzo | 244C Girl's Toilet | 184 | SF | 6 | \$403 | |
| | Lavatory | 244C Girl's Toilet | 2 | EA | 6 | \$639 | |
| | Lighting - Pendant/Surface | 244C Girl's Toilet | 4 | EA | 6 | \$496 | |
| | Partitions | 244C Girl's Toilet | 2 | EA | 6 | \$594 | |
| | Showers | 244C Girl's Toilet | 1 | EA | 6 | \$311 | |
| | Walls - Structural Glazed Tile | 244C Girl's Toilet | 508 | SF | 6 | \$1,598 | |
| | Water Closet | 244C Girl's Toilet | 2 | EA | 6 | \$672 | |
| | Accessories | 260 Boy's Toilet | 550 | SF | 6 | \$5,073 | |
| | Ceiling - Plaster/Drywall | 260 Boy's Toilet | 550 | SF | 6 | \$1,903 | |
| | Doors - Wood Doors inclu hw | 260 Boy's Toilet | 1 | EA | 6 | \$301 | |
| | Floor Drain | 260 Boy's Toilet | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 260 Boy's Toilet | 550 | SF | 6 | \$1,164 | |
| | Hand Dryer | 260 Boy's Toilet | 2 | EA | 6 | \$460 | |
| | Lavatory | 260 Boy's Toilet | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendant/Surface | 260 Boy's Toilet | 8 | EA | 6 | \$991 | |
| | Partitions | 260 Boy's Toilet | 6 | EA | 6 | \$1,782 | |
| | Urinals | 260 Boy's Toilet | 11 | EA | 6 | \$3,696 | |
| | Walls - Plaster/Drywall | 260 Boy's Toilet | 1,215 | SF | 6 | \$3,353 | |
| | Walls - Tile Ceramic/ Porcelain | 260 Boy's Toilet | 600 | SF | 6 | \$1,356 | Stone |
| | Water Closet | 260 Boy's Toilet | 7 | EA | 6 | \$2,352 | |
| | Accessories | 2nd floor boys restroom | 550 | SF | 6 | \$5,073 | |
| | Ceiling - Plaster/Drywall | 2nd floor boys restroom | 550 | SF | 6 | \$1,903 | |
| | Doors - Transom Window | 2nd floor boys restroom | 20 | SF | 6 | \$339 | |
| | Doors - Wood Doors inclu hw | 2nd floor boys restroom | 1 | EA | 6 | \$301 | |
| | Floor Drain | 2nd floor boys restroom | 2 | EA | 6 | \$2,118 | |
| | Floor - Tile Ceramic/ Porcelain | 2nd floor boys restroom | 550 | SF | 6 | \$1,164 | |
| | Hand Dryer | 2nd floor boys restroom | 2 | EA | 6 | \$460 | |
| | Lavatory | 2nd floor boys restroom | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendant/Surface | 2nd floor boys restroom | 10 | EA | 7 | \$0 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|--------------------------------|----------|------|------|---------|-------------------------------------|
| Restroom | | | | | | | |
| | Partitions | 2nd floor boys restroom | 6 | EA | 6 | \$1,782 | |
| | Urinals | 2nd floor boys restroom | 11 | EA | 6 | \$3,696 | |
| | Walls - Plaster/Drywall | 2nd floor boys restroom | 1,215 | SF | 6 | \$3,353 | |
| | Walls - Structural Glazed Tile | 2nd floor boys restroom | 82 | SF | 6 | \$258 | |
| | Walls - Tile Ceramic/ Porcelain | 2nd floor boys restroom | 600 | SF | 6 | \$1,356 | Stone |
| | Water Closet | 2nd floor boys restroom | 6 | EA | 6 | \$2,016 | |
| | Accessories | 2nd flr girls restroom. | 621 | SF | 6 | \$5,728 | |
| | Ceiling - Plaster/Drywall | 2nd flr girls restroom. | 621 | SF | 6 | \$2,149 | |
| | Doors - Transom Window | 2nd flr girls restroom. | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 2nd flr girls restroom. | 1 | EA | 6 | \$301 | |
| | Floor Drain | 2nd flr girls restroom. | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 2nd flr girls restroom. | 621 | SF | 6 | \$1,314 | |
| | Hand Dryer | 2nd flr girls restroom. | 2 | EA | 6 | \$460 | |
| | Lavatory | 2nd flr girls restroom. | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendent/Surface | 2nd flr girls restroom. | 10 | EA | 7 | \$0 | |
| | Partitions | 2nd flr girls restroom. | 1 | EA | 5 | \$751 | ADA Stall missing door |
| | Partitions | 2nd flr girls restroom. | 10 | EA | 6 | \$2,969 | |
| | Walls - Plaster/Drywall | 2nd flr girls restroom. | 1,358 | SF | 6 | \$3,748 | |
| | Water Closet | 2nd flr girls restroom. | 6 | EA | 6 | \$2,016 | |
| | Accessories | 2nd flr men's staff restroom. | 160 | SF | 6 | \$1,476 | |
| | Ceiling - Plaster/Drywall | 2nd flr men's staff restroom. | 140 | SF | 6 | \$484 | |
| | Ceiling - Plaster/Drywall | 2nd flr men's staff restroom. | 20 | SF | 5 | \$215 | Eflorescence,peeling paint/plaster. |
| | Doors - Wood Doors inclu hw | 2nd flr men's staff restroom. | 1 | EA | 6 | \$301 | |
| | Floor Drain | 2nd flr men's staff restroom. | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 2nd flr men's staff restroom. | 160 | SF | 6 | \$339 | |
| | Lavatory | 2nd flr men's staff restroom. | 2 | EA | 6 | \$639 | |
| | Lighting - Pendent/Surface | 2nd flr men's staff restroom. | 2 | EA | 7 | \$0 | |
| | Partitions | 2nd flr men's staff restroom. | 1 | EA | 6 | \$297 | |
| | Urinals | 2nd flr men's staff restroom. | 1 | EA | 6 | \$336 | |
| | Walls - Plaster/Drywall | 2nd flr men's staff restroom. | 780 | SF | 6 | \$2,153 | |
| | Walls - Tile Ceramic/ Porcelain | 2nd flr men's staff restroom. | 460 | SF | 6 | \$1,039 | |
| | Water Closet | 2nd flr men's staff restroom. | 1 | EA | 6 | \$336 | |
| | Accessories | 2nd flr Womens staff restroom. | 152 | SF | 6 | \$1,402 | |
| | Ceiling - Plaster/Drywall | 2nd flr Womens staff restroom. | 152 | SF | 6 | \$526 | |
| | Doors - Wood Doors inclu hw | 2nd flr Womens staff restroom. | 1 | EA | 6 | \$301 | |
| | Floor Drain | 2nd flr Womens staff restroom. | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 2nd flr Womens staff restroom. | 152 | SF | 6 | \$322 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|--------------------------------|----------|------|------|---------|--|
| Restroom | | | | | | | |
| | Lavatory | 2nd flr Womens staff restroom. | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 2nd flr Womens staff restroom. | 2 | EA | 7 | \$0 | |
| | Partitions | 2nd flr Womens staff restroom. | 1 | EA | 6 | \$297 | |
| | Walls - Plaster/Drywall | 2nd flr Womens staff restroom. | 330 | SF | 6 | \$911 | |
| | Walls - Tile Ceramic/ Porcelain | 2nd flr Womens staff restroom. | 443 | SF | 6 | \$1,001 | |
| | Water Closet | 2nd flr Womens staff restroom. | 1 | EA | 6 | \$336 | |
| | Accessories | 352C fitness center | 72 | SF | 6 | \$664 | |
| | Ceiling - Plaster/Drywall | 352C fitness center | 72 | SF | 6 | \$249 | |
| | Doors - Wood Doors inclu hw | 352C fitness center | 1 | EA | 6 | \$301 | |
| | Floor Drain | 352C fitness center | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 352C fitness center | 72 | SF | 6 | \$152 | |
| | Lavatory | 352C fitness center | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 352C fitness center | 1 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | 352C fitness center | 166 | SF | 6 | \$458 | |
| | Walls - Tile Ceramic/ Porcelain | 352C fitness center | 257 | SF | 6 | \$581 | |
| | Water Closet | 352C fitness center | 1 | EA | 6 | \$336 | |
| | Accessories | 352D fitness center | 72 | SF | 6 | \$664 | |
| | Ceiling - Plaster/Drywall | 352D fitness center | 72 | SF | 6 | \$249 | |
| | Doors - Wood Doors inclu hw | 352D fitness center | 1 | EA | 6 | \$301 | |
| | Floor Drain | 352D fitness center | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 352D fitness center | 72 | SF | 6 | \$152 | |
| | Lavatory | 352D fitness center | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | 352D fitness center | 1 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | 352D fitness center | 48 | SF | 6 | \$132 | |
| | Walls - Tile Ceramic/ Porcelain | 352D fitness center | 256 | SF | 6 | \$578 | |
| | Water Closet | 352D fitness center | 1 | EA | 6 | \$336 | |
| | Accessories | 3rd floor boys restroom | 550 | SF | 6 | \$5,073 | |
| | Ceiling - Lay-in | 3rd floor boys restroom | 100 | SF | 6 | \$300 | |
| | Ceiling - Plaster/Drywall | 3rd floor boys restroom | 450 | SF | 6 | \$1,557 | Small amount of eflorescence at window. |
| | Doors - Transom Window | 3rd floor boys restroom | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 3rd floor boys restroom | 1 | EA | 6 | \$301 | |
| | Floor Drain | 3rd floor boys restroom | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 3rd floor boys restroom | 550 | SF | 6 | \$1,164 | Small amount of tile missing around floor drain. |
| | Hand Dryer | 3rd floor boys restroom | 2 | EA | 6 | \$460 | |
| | Lavatory | 3rd floor boys restroom | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendent/Surface | 3rd floor boys restroom | 10 | EA | 7 | \$0 | |
| | Partitions | 3rd floor boys restroom | 6 | EA | 6 | \$1,782 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|--------------------------------|----------|------|------|---------|-------------------------------------|
| Restroom | | | | | | | |
| | Urinals | 3rd floor boys restroom | 11 | EA | 6 | \$3,696 | |
| | Walls - Masonry | 3rd floor boys restroom | 600 | SF | 6 | \$1,888 | Stone |
| | Walls - Plaster/Drywall | 3rd floor boys restroom | 1,215 | SF | 6 | \$3,353 | Peeling paint at window. |
| | Walls - Structural Glazed Tile | 3rd floor boys restroom | 80 | SF | 6 | \$252 | |
| | Water Closet | 3rd floor boys restroom | 6 | EA | 6 | \$2,016 | |
| | Accessories | 3rd flr girls restroom. | 650 | SF | 6 | \$5,995 | |
| | Ceiling - Lay-in | 3rd flr girls restroom. | 100 | SF | 6 | \$300 | |
| | Ceiling - Plaster/Drywall | 3rd flr girls restroom. | 500 | SF | 6 | \$1,730 | |
| | Ceiling - Plaster/Drywall | 3rd flr girls restroom. | 50 | SF | 5 | \$625 | Water damage,peeling paint/plaster. |
| | Doors - Transom Window | 3rd flr girls restroom. | 16 | SF | 6 | \$271 | |
| | Doors - Wood Doors inclu hw | 3rd flr girls restroom. | 1 | EA | 6 | \$301 | |
| | Floor Drain | 3rd flr girls restroom. | 1 | EA | 5 | \$2,094 | Standing water over drain. |
| | Floor - Tile Ceramic/ Porcelain | 3rd flr girls restroom. | 650 | SF | 6 | \$1,376 | |
| | Hand Dryer | 3rd flr girls restroom. | 2 | EA | 6 | \$460 | |
| | Lavatory | 3rd flr girls restroom. | 5 | EA | 6 | \$1,598 | |
| | Lighting - Pendant/Surface | 3rd flr girls restroom. | 10 | EA | 6 | \$1,239 | |
| | Partitions | 3rd flr girls restroom. | 16 | EA | 6 | \$4,751 | |
| | Walls - Masonry | 3rd flr girls restroom. | 707 | SF | 6 | \$2,224 | |
| | Walls - Plaster/Drywall | 3rd flr girls restroom. | 834 | SF | 6 | \$2,302 | |
| | Water Closet | 3rd flr girls restroom. | 17 | EA | 6 | \$5,712 | |
| | Accessories | 3rd flr Womens staff restroom. | 162 | SF | 6 | \$1,494 | |
| | Ceiling - Plaster/Drywall | 3rd flr Womens staff restroom. | 162 | SF | 6 | \$561 | |
| | Doors - Wood Doors inclu hw | 3rd flr Womens staff restroom. | 1 | EA | 6 | \$301 | |
| | Floor Drain | 3rd flr Womens staff restroom. | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | 3rd flr Womens staff restroom. | 162 | SF | 6 | \$343 | |
| | Lavatory | 3rd flr Womens staff restroom. | 2 | EA | 6 | \$639 | |
| | Lighting - Pendant/Surface | 3rd flr Womens staff restroom. | 2 | EA | 7 | \$0 | |
| | Partitions | 3rd flr Womens staff restroom. | 1 | EA | 6 | \$297 | |
| | Walls - Plaster/Drywall | 3rd flr Womens staff restroom. | 332 | SF | 6 | \$916 | |
| | Walls - Tile Ceramic/ Porcelain | 3rd flr Womens staff restroom. | 453 | SF | 6 | \$1,024 | |
| | Water Closet | 3rd flr Womens staff restroom. | 1 | EA | 6 | \$336 | |
| | Accessories | Boiler Room | 229 | SF | 6 | \$2,112 | |
| | Ceiling - Plaster/Drywall | Boiler Room | 229 | SF | 6 | \$792 | |
| | Doors - Steel Doors incl hw | Boiler Room | 1 | EA | 6 | \$301 | |
| | Floor Drain | Boiler Room | 1 | EA | 6 | \$1,059 | Shower drain |
| | Floor - Tile | Boiler Room | 229 | SF | 6 | \$501 | |
| | Lavatory | Boiler Room | 1 | EA | 6 | \$320 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|----------------------------|----------|------|------|---------|-----------|
| Restroom | | | | | | | |
| | Lighting - Pendent/Surface | Boiler Room | 2 | EA | 7 | \$0 | |
| | Partitions | Boiler Room | 1 | EA | 6 | \$297 | |
| | Showers | Boiler Room | 1 | EA | 6 | \$311 | |
| | Student Lockers - One Tier | Boiler Room | 20 | EA | 6 | \$1,857 | |
| | Urinals | Boiler Room | 1 | EA | 6 | \$336 | |
| | Walls - Plaster/Drywall | Boiler Room | 430 | SF | 6 | \$1,187 | |
| | Walls - Structural Glazed Tile | Boiler Room | 87 | SF | 6 | \$274 | |
| | Water Closet | Boiler Room | 1 | EA | 6 | \$336 | |
| | Accessories | Fourth floor men's staff | 120 | SF | 6 | \$1,107 | |
| | Ceiling - Plaster/Drywall | Fourth floor men's staff | 120 | SF | 6 | \$415 | |
| | Doors - Wood Doors inclu hw | Fourth floor men's staff | 1 | EA | 6 | \$301 | |
| | Floor Drain | Fourth floor men's staff | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | Fourth floor men's staff | 120 | SF | 6 | \$254 | |
| | Lavatory | Fourth floor men's staff | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | Fourth floor men's staff | 1 | EA | 6 | \$124 | |
| | Partitions | Fourth floor men's staff | 1 | EA | 6 | \$297 | |
| | Walls - Plaster/Drywall | Fourth floor men's staff | 578 | SF | 6 | \$1,595 | |
| | Water Closet | Fourth floor men's staff | 1 | EA | 6 | \$336 | |
| | Accessories | Fourth floor women's staff | 120 | SF | 6 | \$1,107 | |
| | Ceiling - Plaster/Drywall | Fourth floor women's staff | 145 | SF | 6 | \$502 | |
| | Floor Drain | Fourth floor women's staff | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | Fourth floor women's staff | 145 | SF | 6 | \$307 | |
| | Lavatory | Fourth floor women's staff | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | Fourth floor women's staff | 1 | EA | 6 | \$124 | |
| | Walls - Plaster/Drywall | Fourth floor women's staff | 578 | SF | 6 | \$1,595 | |
| | Water Closet | Fourth floor women's staff | 1 | EA | 6 | \$336 | |
| | Accessories | In engineers office 2 | 58 | SF | 6 | \$535 | |
| | Ceiling - Lay-in | In engineers office 2 | 58 | SF | 6 | \$174 | |
| | Doors - Wood Doors inclu hw | In engineers office 2 | 1 | EA | 6 | \$301 | |
| | Floor - Tile | In engineers office 2 | 58 | SF | 6 | \$127 | |
| | Lavatory | In engineers office 2 | 1 | EA | 6 | \$320 | |
| | Lighting - Lay-in | In engineers office 2 | 1 | EA | 7 | \$0 | |
| | Partitions | In engineers office 2 | 1 | EA | 6 | \$297 | |
| | Walls - Plaster/Drywall | In engineers office 2 | 248 | SF | 6 | \$684 | Paneling. |
| | Water Closet | In engineers office 2 | 1 | EA | 6 | \$336 | |
| | Accessories | Men's Staff rstrm,320 | 160 | SF | 6 | \$1,476 | |
| | Ceiling - Plaster/Drywall | Men's Staff rstrm,320 | 130 | SF | 6 | \$450 | |

Building: Main
Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|---------------------------------|---|----------|------|------|---------|--|
| Restroom | | | | | | | |
| | Ceiling - Plaster/Drywall | Men's Staff rstrm,320 | 30 | SF | 5 | \$323 | Eflorescence,peeling paint/plaster above window. |
| | Doors - Wood Doors inclu hw | Men's Staff rstrm,320 | 1 | EA | 6 | \$301 | |
| | Floor Drain | Men's Staff rstrm,320 | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | Men's Staff rstrm,320 | 160 | SF | 6 | \$339 | |
| | Lavatory | Men's Staff rstrm,320 | 2 | EA | 6 | \$639 | |
| | Lighting - Pendent/Surface | Men's Staff rstrm,320 | 2 | EA | 7 | \$0 | |
| | Partitions | Men's Staff rstrm,320 | 1 | EA | 6 | \$297 | |
| | Urinals | Men's Staff rstrm,320 | 1 | EA | 6 | \$336 | |
| | Walls - Plaster/Drywall | Men's Staff rstrm,320 | 780 | SF | 6 | \$2,153 | |
| | Walls - Tile Ceramic/ Porcelain | Men's Staff rstrm,320 | 460 | SF | 6 | \$1,039 | |
| | Water Closet | Men's Staff rstrm,320 | 1 | EA | 6 | \$336 | |
| | Accessories | Unisex staff restroom across from rm 140 | 105 | SF | 6 | \$968 | |
| | Ceiling - Plaster/Drywall | Unisex staff restroom across from rm 140 | 105 | SF | 6 | \$363 | |
| | Doors - Wood Doors inclu hw | Unisex staff restroom across from rm 140 | 1 | EA | 6 | \$301 | |
| | Floor Drain | Unisex staff restroom across from rm 140 | 1 | EA | 6 | \$1,059 | |
| | Floor - Tile Ceramic/ Porcelain | Unisex staff restroom across from rm 140 | 105 | SF | 6 | \$222 | |
| | Lavatory | Unisex staff restroom across from rm 140 | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | Unisex staff restroom across from rm 140 | 2 | EA | 7 | \$0 | |
| | Walls - Plaster/Drywall | Unisex staff restroom across from rm 140 | 83 | SF | 6 | \$229 | |
| | Walls - Tile Ceramic/ Porcelain | Unisex staff restroom across from rm 140 | 3 | SF | 5 | \$63 | Broken/missing tiles. |
| | Walls - Tile Ceramic/ Porcelain | Unisex staff restroom across from rm 140 | 308 | SF | 6 | \$696 | |
| | Water Closet | Unisex staff restroom across from rm 140 | 1 | EA | 6 | \$336 | |
| | Accessories | Upper level restroom in mech serv rm, in boiler rm. | 151 | SF | 6 | \$1,393 | |
| | Ceiling - Plaster/Drywall | Upper level restroom in mech serv rm, in boiler rm. | 20 | SF | 5 | \$215 | Cracking/splitting plaster. |
| | Ceiling - Plaster/Drywall | Upper level restroom in mech serv rm, in boiler rm. | 131 | SF | 6 | \$453 | |
| | Doors - Steel Doors incl hw | Upper level restroom in mech serv rm, in boiler rm. | 1 | EA | 6 | \$301 | |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|----------------------------|---|----------|------|------|----------|------------------------------------|
| Restroom | | | | | | | |
| | Floor - Tile | Upper level restroom in mech serv rm, in boiler rm. | 151 | SF | 6 | \$330 | |
| | Lavatory | Upper level restroom in mech serv rm, in boiler rm. | 1 | EA | 6 | \$320 | |
| | Lighting - Pendent/Surface | Upper level restroom in mech serv rm, in boiler rm. | 2 | EA | 7 | \$0 | |
| | Showers | Upper level restroom in mech serv rm, in boiler rm. | 1 | EA | 6 | \$311 | |
| | Walls - Masonry | Upper level restroom in mech serv rm, in boiler rm. | 538 | SF | 5 | \$22,234 | Brick. Eflorescence,peeling paint. |
| | Walls - Plaster/Drywall | Upper level restroom in mech serv rm, in boiler rm. | 76 | SF | 6 | \$210 | |
| | Water Closet | Upper level restroom in mech serv rm, in boiler rm. | 1 | EA | 6 | \$336 | |

Rooms (Other Than Classrooms) Subtotal:

\$3,577,684

Building: Main

Category: Building Interior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|--|-----------|----------|------|------|-----------|----------|
| Corridor | | | | | | | |
| | Ceiling - Plaster/Drywall | 1st Floor | 19,309 | SF | 6 | \$119,559 | |
| | Doors - Steel Doors incl hw | 1st Floor | 20 | EA | 6 | \$6,020 | |
| | Drinking Fountains - Double Water Cooler | 1st Floor | 4 | EA | 6 | \$1,508 | |
| | Floor - Terrazzo | 1st Floor | 19,309 | SF | 6 | \$162,082 | |
| | Lighting - Chandelier, Incandescent | 1st Floor | 70 | EA | 6 | \$33,429 | |
| | Lighting - Pendent/Surface | 1st Floor | 158 | EA | 6 | \$19,575 | |
| | Student Lockers - One Tier | 1st Floor | 498 | EA | 6 | \$46,232 | |
| | Walls - Plaster/Drywall | 1st Floor | 31,458 | SF | 6 | \$139,453 | |
| | Walls - Tile Ceramic/ Porcelain | 1st Floor | 2,105 | SF | 6 | \$6,622 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 15,543 | SF | 6 | \$96,241 | |
| | Ceiling - Plaster/Drywall | 2nd Floor | 8 | SF | 5 | \$140 | |
| | Doors - Steel Doors incl hw | 2nd Floor | 20 | EA | 6 | \$6,020 | |
| | Drinking Fountains - Double Fountain | 2nd Floor | 5 | EA | 6 | \$1,680 | |
| | Floor - Terrazzo | 2nd Floor | 15,543 | SF | 6 | \$130,469 | |
| | Lighting - Pendent/Surface | 2nd Floor | 178 | EA | 6 | \$22,053 | |
| | Student Lockers - One Tier | 2nd Floor | 462 | EA | 6 | \$42,890 | |
| | Walls - Plaster/Drywall | 2nd Floor | 27,895 | SF | 6 | \$123,659 | |
| | Walls - Tile Ceramic/ Porcelain | 2nd Floor | 1,798 | SF | 6 | \$5,657 | |

Building: Main

Category: Building Interior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------|--|-----------------------------|----------|------|------|-----------|--|
| Corridor | | | | | | | |
| | Ceiling - Plaster/Drywall | 3rd Floor | 13,807 | SF | 6 | \$85,492 | |
| | Doors - Steel Doors incl hw | 3rd Floor | 16 | EA | 6 | \$4,816 | |
| | Drinking Fountains - Double Water Cooler | 3rd Floor | 4 | EA | 6 | \$1,508 | |
| | Floor - Terrazzo | 3rd Floor | 13,807 | SF | 6 | \$115,897 | |
| | Lighting - Pendent/Surface | 3rd Floor | 166 | EA | 6 | \$20,567 | |
| | Student Lockers - One Tier | 3rd Floor | 368 | EA | 6 | \$34,164 | |
| | Walls - Plaster/Drywall | 3rd Floor | 21,882 | SF | 6 | \$97,003 | |
| | Walls - Tile Ceramic/ Porcelain | 3rd Floor | 1,559 | SF | 6 | \$4,905 | |
| | Ceiling - Lay-in | 4th Floor | 3,796 | SF | 6 | \$11,399 | |
| | Doors - Steel Doors incl hw | 4th Floor | 6 | EA | 6 | \$1,806 | |
| | Drinking Fountains - Double Fountain | 4th Floor | 1 | EA | 6 | \$336 | |
| | Floor - Epoxy/ Painted | 4th Floor | 3,796 | SF | 6 | \$2,008 | |
| | Lighting - Pendent/Surface | 4th Floor | 60 | EA | 6 | \$7,434 | |
| | Stairs - Concrete Stairs | 4th Floor | 20 | LF | 6 | \$166 | |
| | Walls - Concrete Block | 4th Floor | 5,646 | SF | 6 | \$16,551 | |
| | Walls - Structural Glazed Tile | 4th Floor | 2,299 | SF | 6 | \$7,233 | |
| Safety | | | | | | | |
| | Camera Viewing Station | Entire Building / 1st Floor | 5 | EA | 6 | \$3,413 | Main entrance #3, principal office, assistant principal office, engineers office, security office. |
| | Metal Dedector | Entire Building / 1st Floor | 2 | EA | 6 | \$1,761 | |
| | Security Cameras | Entire Building | 37 | EA | 6 | \$7,179 | |
| | Security Cameras | Entire Building | 1 | EA | 5 | \$688 | East courtyard |
| | Security Cameras | Entire Building | 14 | EA | 6 | \$2,717 | |
| | Security Cameras | Entire Building | 1 | EA | 5 | \$688 | At cafeteria |
| Stairs | | | | | | | |
| | Ceiling - Plaster/Drywall | Stairwell #10 | 96 | SF | 6 | \$703 | |
| | Floor - Rubber Floor | Stairwell #10 | 635 | SF | 6 | \$1,371 | |
| | Handrails | Stairwell #10 | 120 | LF | 6 | \$1,040 | |
| | Lighting - Pendent/Surface | Stairwell #10 | 4 | EA | 6 | \$496 | |
| | Stairs - Rubber | Stairwell #10 | 60 | LF | 6 | \$645 | |
| | Walls - Plaster/Drywall | Stairwell #10 | 1,160 | SF | 6 | \$3,201 | |
| | Ceiling - Plaster/Drywall | Stairwell #1 | 272 | SF | 6 | \$1,991 | |
| | Floor - Rubber Floor | Stairwell #1 | 684 | SF | 6 | \$1,477 | |
| | Handrails | Stairwell #1 | 120 | LF | 6 | \$1,040 | |
| | Lighting - Pendent/Surface | Stairwell #1 | 4 | EA | 6 | \$496 | |
| | Stairs - Rubber | Stairwell #1 | 60 | LF | 6 | \$645 | |
| | Walls - Plaster/Drywall | Stairwell #1 | 1,664 | SF | 6 | \$4,592 | |

Building: Main

Category: Building Interior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---------------|----------------------------|--------------|----------|------|------|---------|----------|
| Stairs | | | | | | | |
| | Ceiling - Plaster/Drywall | Stairwell #2 | 650 | SF | 6 | \$4,759 | |
| | Floor - Rubber Floor | Stairwell #2 | 1,584 | SF | 6 | \$3,420 | |
| | Handrails | Stairwell #2 | 240 | LF | 6 | \$2,080 | |
| | Lighting - Pendant/Surface | Stairwell #2 | 8 | EA | 6 | \$991 | |
| | Stairs - Rubber | Stairwell #2 | 60 | LF | 6 | \$645 | |
| | Walls - Plaster/Drywall | Stairwell #2 | 2,650 | SF | 6 | \$7,314 | |
| | Ceiling - Plaster/Drywall | Stairwell #3 | 272 | SF | 6 | \$1,991 | |
| | Floor - Rubber Floor | Stairwell #3 | 684 | SF | 6 | \$1,477 | |
| | Handrails | Stairwell #3 | 120 | LF | 6 | \$1,040 | |
| | Lighting - Pendant/Surface | Stairwell #3 | 4 | EA | 6 | \$496 | |
| | Stairs - Rubber | Stairwell #3 | 60 | LF | 6 | \$645 | |
| | Walls - Plaster/Drywall | Stairwell #3 | 1,664 | SF | 6 | \$4,592 | |
| | Ceiling - Plaster/Drywall | Stairwell #4 | 650 | SF | 6 | \$4,759 | |
| | Floor - Rubber Floor | Stairwell #4 | 1,584 | SF | 6 | \$3,420 | |
| | Handrails | Stairwell #4 | 240 | LF | 6 | \$2,080 | |
| | Lighting - Pendant/Surface | Stairwell #4 | 8 | EA | 6 | \$991 | |
| | Stairs - Rubber | Stairwell #4 | 60 | LF | 6 | \$645 | |
| | Walls - Plaster/Drywall | Stairwell #4 | 2,650 | SF | 6 | \$7,314 | |
| | Ceiling - Plaster/Drywall | Stairwell #5 | 265 | SF | 6 | \$1,940 | |
| | Floor - Rubber Floor | Stairwell #5 | 1,244 | SF | 6 | \$2,686 | |
| | Handrails | Stairwell #5 | 180 | LF | 6 | \$1,560 | |
| | Lighting - Pendant/Surface | Stairwell #5 | 6 | EA | 6 | \$743 | |
| | Stairs - Rubber | Stairwell #5 | 90 | LF | 6 | \$968 | |
| | Walls - Plaster/Drywall | Stairwell #5 | 2,146 | SF | 6 | \$5,923 | |
| | Ceiling - Plaster/Drywall | Stairwell #6 | 265 | SF | 6 | \$1,940 | |
| | Floor - Rubber Floor | Stairwell #6 | 1,244 | SF | 6 | \$2,686 | |
| | Handrails | Stairwell #6 | 180 | LF | 6 | \$1,560 | |
| | Lighting - Pendant/Surface | Stairwell #6 | 6 | EA | 6 | \$743 | |
| | Stairs - Rubber | Stairwell #6 | 90 | LF | 6 | \$968 | |
| | Walls - Plaster/Drywall | Stairwell #6 | 2,146 | SF | 6 | \$5,923 | |
| | Ceiling - Plaster/Drywall | Stairwell #7 | 254 | SF | 6 | \$1,860 | |
| | Floor - Rubber Floor | Stairwell #7 | 1,056 | SF | 6 | \$2,280 | |
| | Handrails | Stairwell #7 | 180 | LF | 6 | \$1,560 | |
| | Lighting - Pendant/Surface | Stairwell #7 | 6 | EA | 6 | \$743 | |
| | Stairs - Rubber | Stairwell #7 | 90 | LF | 6 | \$968 | |
| | Walls - Plaster/Drywall | Stairwell #7 | 1,200 | SF | 6 | \$3,312 | |
| | Ceiling - Plaster/Drywall | Stairwell #8 | 254 | SF | 6 | \$1,860 | |

Building: Main

Category: Building Interior

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|---------------|----------------------------|--------------|----------|------|------|---------|----------|
| Stairs | | | | | | | |
| | Floor - Rubber Floor | Stairwell #8 | 1,056 | SF | 6 | \$2,280 | |
| | Handrails | Stairwell #8 | 180 | LF | 6 | \$1,560 | |
| | Lighting - Pendent/Surface | Stairwell #8 | 6 | EA | 6 | \$743 | |
| | Stairs - Rubber | Stairwell #8 | 90 | LF | 6 | \$968 | |
| | Walls - Plaster/Drywall | Stairwell #8 | 1,200 | SF | 6 | \$3,312 | |
| | Ceiling - Plaster/Drywall | Stairwell #9 | 283 | SF | 6 | \$2,072 | |
| | Floor - Rubber Floor | Stairwell #9 | 352 | SF | 6 | \$760 | |
| | Handrails | Stairwell #9 | 60 | LF | 6 | \$520 | |
| | Lighting - Pendent/Surface | Stairwell #9 | 2 | EA | 6 | \$248 | |
| | Stairs - Rubber | Stairwell #9 | 30 | LF | 6 | \$323 | |
| | Walls - Plaster/Drywall | Stairwell #9 | 600 | SF | 6 | \$1,656 | |

Vertical Conveyance

| | | | | | | | |
|--|---------------------------------|-----------------|---|----|---|----------|--|
| | Wheelchair Lift - Platform Lift | 1st Floor | 1 | EA | 6 | \$6,690 | |
| | Elevator - Hydraulic Elevator | Entire Building | 1 | EA | 6 | \$19,238 | |

Building Interior Subtotal:

\$1,537,967

Total Building Cost

\$13,481,423

SITE

Category: Site

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------------|--------------------------------|-------------|----------|------|------|---------|----------|
| Civil/Drainage | | | | | | | |
| | Civil/ Drainage - Catch Basin | Entire Site | 3 | EA | 6 | \$3,282 | |
| | Civil/ Drainage - Site Manhole | Entire Site | 5 | EA | 6 | \$7,464 | |

Fencing

| | | | | | | | |
|--|-----------------------------------|-------------|-------|----|---|----------|---|
| | Fencing - Chain Link | Entire Site | 80 | LF | 6 | \$1,502 | Location: N, S Courtyards are fire escapes |
| | Fencing - New Standard Ornamental | Entire Site | 1,120 | LF | 6 | \$35,732 | SE - Tree shrubbery, vines growing on 40ft section of fencing adjacent to greenhouse building |

Landscape

| | | | | | | | |
|--|--------------------------------|-------------|--------|----|---|----------|---|
| | Irrigation | Entire Site | 14,400 | SF | 6 | \$16,268 | Location: East grass areas N-S of Main Entrance 3 |
| | Landscape - Grass | Entire Site | 20,555 | SF | 6 | \$17,048 | |
| | Landscape - Hardscape- Asphalt | Entire Site | 3,640 | SF | 6 | \$8,797 | North courtyard - south of parking lot with trash compactor |

SITE

Category: Site

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|--------------------|---|-----------------------|----------|------|------|----------|---|
| Landscape | | | | | | | |
| | Landscape - Hardscape- Asphalt | Entire Site | 500 | SF | 5 | \$2,281 | Several areas cracked, chipped with holes throughout / Area around catch basin cover in poor condition - holes with loose pieces |
| | Landscape - Hardscape- Concrete | Entire Site | 8,400 | SF | 6 | \$43,363 | |
| | Landscape - Hardscape- Concrete | Entire Site | 260 | SF | 5 | \$3,316 | Raised curb / walk at east side of parking lot cracked, chipped with pieces missing and vegetation growth throughout / Open court south of roof 3 below - Areas cracked with holes underneath downspout from lower roof / Bottom of light well, south side of north courtyard - flooded with heavy vegetation due to no floor drain |
| | Landscape - Hardscape- Pavers | Entire Site | 1,345 | SF | 6 | \$7,616 | East - Garden, sitting area north of main entrance 3 |
| | Parkway trees | Entire Site | 50 | EA | 6 | \$33,002 | |
| | Planting Beds/ Area | Entire Site | 5,060 | SF | 6 | \$8,321 | Location: N, E, S |
| | Retaining Wall - Concrete | Entire Site | 1,750 | SF | 6 | \$41,016 | |
| | Retaining Wall - Masonry | Entire Site | 400 | SF | 6 | \$5,840 | North side of parking lot / Brick Piers |
| Parking Lot | | | | | | | |
| | Concrete Curbs | NW | 30 | LF | 6 | \$385 | South side |
| | Surface - Asphalt | NW | 7,100 | SF | 6 | \$17,159 | |
| | Surface - Asphalt | NW | 200 | SF | 5 | \$1,181 | Several cracks throughout |
| | Trash Compactor | NW | 1 | EA | 6 | \$0 | At north asphalt courtyard across overhead doors 10A-B |
| Sidewalks | | | | | | | |
| | Sidewalks - Internal Walks | Entire Site | 70 | LF | 6 | \$841 | |
| | Sidewalks - Perimeter Sidewalks | Entire Site | 15,310 | SF | 6 | \$30,432 | Concrete |
| | Sidewalks - Perimeter Sidewalks | Entire Site | 350 | SF | 4 | \$5,631 | Asphalt - NW parking lot entry driveway cracked, uneven with holes throughout, ponding occurring |
| | Sidewalks - Perimeter Sidewalks | Entire Site | 120 | SF | 5 | \$1,146 | Concrete - East - Main entrance 3 drop off area - Large cracks, uneven with areas of upheaving and sinking / North - Entrance 1 - Area cracked, sinking adjacent to curb, curb raised above sidewalk causing trip hazard to street / SW corner of site at exit 6A - Cracked with large gap adjacent to street edge |
| Signage | | | | | | | |
| | Flag Pole - Building Mounted Flag Pole | East / East Façade | 1 | EA | 6 | \$828 | Above Main Entrance 3-East |
| | Marquee - Free Standing Back lighted w/ LED | East / East Courtyard | 1 | EA | 6 | \$0 | |

SITE

Category: Site

| Group | Item - Type | Location | Quantity | Unit | Rank | Cost | Comments |
|-----------------------|-------------|----------|----------|------|------|------------------|----------|
| Site Subtotal: | | | | | | \$292,451 | |

Total Site Cost

\$292,451

Campus Total ^{2 3}

\$13,773,874

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

| Current Usage | Intended Usage | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|-------------------------|-------------------------|---------------|--------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| Main | | | | | | | | | | | | | | |
| Art Room | Art Room | 1st Floor | 134 | 134 | 851 | 0 | 1 | 10 | 200 | 100 | 40 | N | Y | Y |
| Art Room | Art Room | 1st Floor | 136 | 136 | 837 | 1 | 7 | 20 | 190 | 95 | 40 | N | Y | N |
| Art Room | Art Room | 1st Floor | 136B | 136 | 286 | 0 | 0 | 4 | 0 | 0 | 40 | N | Y | N |
| Art Room | Art Room | 1st Floor | 138 | 138 | 985 | 1 | 7 | 20 | 190 | 95 | 40 | N | Y | N |
| Band Room | Band Room | 2nd Floor | 251 | 251 | 2,270 | 1 | 7 | 30 | 494 | 247 | 40 | N | Y | N |
| Choral Room | Choral Room | 1st Floor | 137 | 137 | 1,168 | 1 | 7 | 30 | 210 | 105 | 40 | N | Y | N |
| Choral Room | Choral Room | 1st Floor | 139 | 139 | 925 | 1 | 7 | 30 | 210 | 105 | 40 | N | Y | N |
| Computer Lab | Computer Lab | 1st Floor | 100 | 100 | 1,571 | 1 | 7 | 28 | 360 | 180 | 40 | N | N | Y |
| Computer Lab | Regular Classroom | 1st Floor | 107 | 107 | 815 | 1 | 4 | 14 | 180 | 90 | 40 | N | Y | N |
| Computer Lab | Computer Lab | 2nd Floor | 225 | 225 | 990 | 1 | 30 | 60 | 120 | 60 | 40 | N | Y | N |
| Computer Lab | Computer Lab | 3rd Floor | 327 | 327 | 2,130 | 1 | 30 | 70 | 272 | 136 | 40 | N | Y | N |
| Faculty Lounge | Regular Classroom | 2nd Floor | 210 | 210 | 849 | 1 | 9 | 25 | 160 | 80 | 40 | N | N | N |
| Fitness Room | Fitness Room | 3rd Floor | Fitness room | Fitness room | 2,912 | 0 | 0 | 18 | 540 | 270 | 40 | N | N | N |
| Laboratory/Shop | Other Instructional Use | 1st Floor | 132 | 132 | 596 | 0 | 1 | 8 | 80 | 40 | 40 | N | Y | N |
| Other Instructional Use | Other Instructional Use | 1st Floor | 141 | 141 | 2,963 | 1 | 7 | 30 | 380 | 190 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 104 | 104 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 106 | 106 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 108 | 108 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 109 | 109 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 1st Floor | 110 | 110 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 111 | 111 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 118 | 118 | 700 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 120 | 120 | 700 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 122 | 122 | 700 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 1st Floor | 124 | 124 | 711 | 1 | 8 | 20 | 136 | 68 | 40 | N | N | Y |
| Regular Classroom | Regular Classroom | 1st Floor | 126 | 126 | 844 | 1 | 8 | 14 | 204 | 102 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 200 | 200 | 722 | 1 | 1 | 24 | 180 | 90 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 208 | 208 | 837 | 0 | 0 | 8 | 225 | 112 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 208A | 208A | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 209 | 209 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 211 | 211 | 660 | 1 | 7 | 22 | 180 | 90 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 213 | 213 | 722 | 1 | 1 | 12 | 180 | 90 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 216 | 216 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 218 | 218 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 219 | 219 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 220 | 220 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 221 | 221 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |

Classroom Summary

| Current Usage | Intended Usage | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|---------------------|---------------------|---------------|-------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| Main | | | | | | | | | | | | | | |
| Regular Classroom | Regular Classroom | 2nd Floor | 222 | 222 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 224 | 224 | 715 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 226 | 226 | 850 | 1 | 7 | 20 | 240 | 120 | 40 | N | Y | N |
| Regular Classroom | Computer Lab | 3rd Floor | 301 | 301 | 1,074 | 1 | 5 | 16 | 90 | 45 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 303 | 303 | 2,252 | 1 | 22 | 48 | 320 | 160 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 304 | 304 | 715 | 1 | 3 | 8 | 80 | 40 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 307 | 307 | 1,216 | 1 | 5 | 14 | 360 | 180 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 308 | 308 | 2,088 | 1 | 5 | 32 | 540 | 270 | 40 | N | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 311 | 311 | 658 | 1 | 5 | 18 | 180 | 90 | 40 | N | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 313 | 313 | 1,091 | 1 | 1 | 12 | 270 | 135 | 40 | N | N | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 316 | 316 | 685 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 318 | 318 | 685 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 319 | 319 | 685 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 321 | 321 | 685 | 1 | 7 | 20 | 120 | 60 | 40 | N | Y | Y |
| Regular Classroom | Computer Lab | 3rd Floor | 325 | 325 | 1,138 | 1 | 2 | 20 | 68 | 34 | 40 | N | Y | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 326 | 326 | 850 | 4 | 6 | 16 | 132 | 66 | 40 | N | Y | Y |
| Science Classroom | Choral Room | 3rd Floor | 324 | 324 | 725 | 1 | 2 | 12 | 66 | 33 | 40 | N | Y | N |
| Science Lab Level 1 | Science Lab Level 1 | 2nd Floor | 203 | 203 | 1,340 | 1 | 2 | 70 | 300 | 150 | 40 | N | N | N |
| Science Lab Level 1 | Science Lab Level 1 | 2nd Floor | 227 | 227 | 1,340 | 1 | 2 | 70 | 300 | 150 | 40 | N | N | N |
| Science Lab Level 1 | Science Lab Level 1 | 3rd Floor | 302 | 302 | 1,557 | 1 | 5 | 74 | 90 | 45 | 40 | N | N | N |
| Science Lab Level 1 | Science Lab Level 1 | 3rd Floor | 322 | 322 | 1,120 | 1 | 30 | 90 | 120 | 60 | 40 | N | Y | N |
| Science Lab Level 1 | Science Lab Level 1 | 3rd Floor | 323 | 323 | 1,120 | 1 | 30 | 90 | 120 | 60 | 40 | N | Y | N |
| Science Lab Level 3 | Science Lab Level 3 | 1st Floor | 127 | 127 | 1,277 | 1 | 7 | 40 | 300 | 150 | 40 | N | N | N |
| Science Lab Level 3 | Science Lab Level 3 | 2nd Floor | 201 | 201 | 977 | 1 | 1 | 12 | 180 | 90 | 40 | N | N | N |
| Special Education | Art Room | 1st Floor | 140 | 140 | 985 | 1 | 7 | 20 | 152 | 76 | 40 | N | Y | Y |
| Special Education | Special Education | 2nd Floor | 200A | 200A | 500 | 1 | 1 | 12 | 200 | 110 | 40 | N | Y | N |