

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	2010	3	213,710	\$4,629,366
SITE				\$317,632
<b>Campus Total</b>			<b>213,710</b>	<b>\$4,946,998</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio and Video	Entrance 4-W - Basement level	1	EA	6	\$702	
	Entrance Control - Audio and Video	Entrance 6-West	1	EA	6	\$702	
	Entrance Control - Audio and Video	Entrance 7B-N - 129 Loading Dock	1	EA	6	\$702	
	Entrance Control - Audio and Video	Entrance 9-East	2	EA	6	\$1,403	
	Entrance Control - Audio and Video	Main Entrance 1-South	2	EA	6	\$1,403	
	Exterior Doors - Exterior Steel Door	Entrance 11-SE	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 2-S	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 3-SW	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 5-W	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	Entrance 7B-N - 129 Loading Dock	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Entrance 7-W - Pool	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	Entrance 8A-N - 130 Outside yard storage	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Entrance 8-N	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	Roof access doors	2	EA	6	\$961	
	Exterior Doors - Overhead Rolling/ Garage Door	Entrance 7A-N - Overhead door at 129 Loading Dock	1	EA	6	\$1,433	
	Exterior Doors - Side lite	Entrance 10-East	2	EA	7	\$0	
	Exterior Doors - Side lite	Entrance 8A-N - 130 Outside yard storage	1	EA	6	\$313	
	Exterior Doors - Store Front	Entrance 10-East	3	EA	6	\$1,638	
	Exterior Doors - Store Front	Entrance 4-W - Basement level	4	EA	6	\$2,184	

**Building: Main**
**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Store Front	Entrance 6-West	1	EA	6	\$546	
	Exterior Doors - Store Front	Entrance 9-East	5	EA	6	\$2,730	
	Exterior Doors - Store Front	Main Entrance 1-South	6	EA	6	\$3,276	
	Exterior Doors - Transom Lite	Entrance 10-East	3	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 7B-N - 129 Loading Dock	10	EA	7	\$0	
	Exterior Stairs - Concrete	Entrance 4-W - Basement level	325	LF	6	\$26,574	
	Exterior Stairs - Concrete	Entrance 7-W - Pool	10	LF	7	\$0	
	Exterior Stairs - Concrete	Main Entrance 1-South	1,565	LF	7	\$0	
	Exterior Stairs - Concrete	Main Entrance 1-South	10	LF	6	\$818	Several areas cracked, chipped at outside corners
	Power Door Operator and Controls	Entrance 10-East	1	EA	6	\$0	
	Power Door Operator and Controls	Entrance 6-West	1	EA	6	\$0	
	Power Door Operator and Controls	Entrance 9-East	1	EA	6	\$0	
	Ramp Handrail	Entrance 9-East	260	LF	6	\$0	
	Ramp Handrail - Steel_Ramp Handrail	Main Entrance 1-South	300	LF	6	\$2,600	
	Ramps - Concrete	Main Entrance 1-South	150	LF	7	\$0	
	Stair Handrail - Steel_Stair Handrail	Entrance 4-W - Basement level	105	LF	6	\$910	
	Stair Handrail - Steel_Stair Handrail	Main Entrance 1-South	160	LF	6	\$1,387	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	1,770	LF	7	\$0	
	Superstructure - Concrete	Entire Building	213,710	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	41	EA	6	\$11,839	
	Exterior Lighting - Wall Mounted	Entire Building	21	EA	6	\$6,064	
	Exterior Lighting - Wall Mounted	Entire Building	22	EA	6	\$6,352	
	Exterior Lighting - Wall Mounted	Entire Building	8	EA	6	\$2,310	At south elevation at ramp and sloped walkway
	Exterior Lighting - Wall Mounted	Entire Building	16	EA	5	\$6,838	At entrances 1, 4 concrete steps - Majority of lights rusted, bent, not working properly
<b>Roof System</b>							
	Chimney - Metal Flue	Roof 1	420	LF	6	\$66,420	
	Chimney - Metal Flue	Roof 3	55	LF	6	\$8,698	Cap bent and falling off at base of flue above roof membrane
	Coping - Metal	Roof 1	265	LF	7	\$0	
	Coping - Metal	Roof 10	560	LF	7	\$0	
	Coping - Metal	Roof 2 - Outside chiller	125	LF	6	\$4,015	
	Coping - Metal	Roof 3	1,140	LF	7	\$0	
	Coping - Metal	Roof 4	26	LF	7	\$0	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
	Coping - Metal	Roof 8 - Green Roof	260	LF	7	\$0	
	Coping - Metal	Roofs 5, 9 - E, W Cantilevers	335	LF	7	\$0	
	Coping - Metal	Roofs 6, 7 - Green Roofs	760	LF	7	\$0	
	Downspouts - Interior Downspouts	Roof 1	240	LF	6	\$7,976	
	Downspouts - Interior Downspouts	Roof 10	580	LF	6	\$19,275	
	Downspouts - Interior Downspouts	Roof 2 - Outside chiller	100	LF	6	\$3,323	
	Downspouts - Interior Downspouts	Roof 3	1,450	LF	6	\$48,188	
	Downspouts - Interior Downspouts	Roof 4	100	LF	6	\$3,323	
	Downspouts - Interior Downspouts	Roof 8 - Green Roof	200	LF	6	\$6,647	
	Downspouts - Interior Downspouts	Roofs 5, 9 - E, W Cantilevers	300	LF	6	\$9,970	
	Downspouts - Interior Downspouts	Roofs 6, 7 - Green Roofs	525	LF	6	\$17,447	
	Parapet - 16" - 30" Height	Roofs 6, 7 - Green Roofs	325	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 1	265	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 10	560	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 2 - Outside chiller	125	LF	6	\$2,663	
	Parapet - Parapet < 16" Height	Roof 3	1,140	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roof 4	26	LF	7	\$0	
	Parapet - Parapet < 16" Height	Roofs 5, 9 - E, W Cantilevers	335	LF	7	\$0	
	Parapet - Parapet > 30"	Roof 8 - Green Roof	260	LF	7	\$0	
	Parapet - Parapet > 30"	Roofs 6, 7 - Green Roofs	435	LF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 1	4,340	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 10	5,550	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 2 - Outside chiller	1,880	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 3	26,705	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 4	60	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 8 - Green Roof	10,000	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roofs 5, 9 - E, W Cantilevers	2,950	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roofs 6, 7 - Green Roofs	31,800	SF	7	\$0	
	Roof - Modified Bitumen	Roof 1	4,340	SF	7	\$0	
	Roof - Modified Bitumen	Roof 10	5,550	SF	6	\$52,222	
	Roof - Modified Bitumen	Roof 2 - Outside chiller	1,880	SF	6	\$17,690	Worn out with staining and bubbling throughout
	Roof - Modified Bitumen	Roof 3	26,205	SF	7	\$0	
	Roof - Modified Bitumen	Roof 3	500	SF	6	\$9,710	Areas bubbling and splitting at south side / Ponding, worn out areas at west side under mechanical units
	Roof - Modified Bitumen	Roof 4	60	SF	6	\$565	
	Roof - Modified Bitumen	Roof 8 - Green Roof	8,500	SF	6	\$79,980	Vegetation areas
	Roof - Modified Bitumen	Roof 8 - Green Roof	1,500	SF	6	\$20,699	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
	Roof - Modified Bitumen	Roofs 5, 9 - E, W Cantilevers	2,950	SF	6	\$27,758	
	Roof - Modified Bitumen	Roofs 6, 7 - Green Roofs	28,620	SF	6	\$269,297	Vegetation areas
	Roof - Modified Bitumen	Roofs 6, 7 - Green Roofs	3,180	SF	6	\$43,882	
<b>Walls</b>							
	Canopy - Concrete/ Stucco	Entire Building	300	SF	6	\$9,927	
	Canopy - Metal	Entire Building	3,030	SF	7	\$0	
	Exterior Walls - Brick	Entire Building	47,115	SF	7	\$0	
	Exterior Walls - Concrete Block	Entire Building	3,150	SF	7	\$0	Above entrance 10-E - Library / North exterior wall of pool
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	11,205	SF	7	\$0	
	Exterior Walls - Stone-Cut	Entire Building	130	SF	7	\$0	
<b>Windows</b>							
	Clerestory - Glass Double-Pane	Entire Building	1,710	SF	7	\$0	
	Curtain wall - Glazed Double Pane	Entire Building	10,930	SF	7	\$0	
	Curtain wall - Windows	Entire Building	5,775	SF	7	\$0	
	Guard - Guards perforated	Entire Building	1,815	SF	7	\$0	
	Lintels - Steel	Entire Building	1,030	LF	7	\$0	
	Windows - Louver	Entire Building	165	SF	7	\$0	

**Building Exterior Subtotal:**

**\$821,532**

**Building: Main**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	4	EA	7	\$0	
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	5,600	SF	6	\$2,963	
	Emergency A/C Power - Corridors and Stairs	Entire Building	12,000	SF	6	\$3,604	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	1,350	SF	6	\$502	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	1,250	SF	6	\$465	
	Emergency A/C Power - Students Toilets	Entire Building	4,000	SF	6	\$1,487	
	Emergency Generator- Indoor- Natural Gas - Above 250 KW	Mechanical Room	1	EA	6	\$20,340	
	Exit Signs - Auditorium	Entire Building / 1st Floor	16	EA	6	\$2,396	Generator
	Exit Signs - Corridors and Stairs	Entire Building	68	EA	6	\$10,183	Generator
	Exit Signs - Gym	Entire Building / 1st Floor	6	EA	6	\$945	Generator
	Exit Signs - Lunchroom	Entire Building / 1st Floor	8	EA	6	\$1,198	Generator

**Building: Main**
**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Exit Signs - Pool	Entire Building / 1st Floor	6	EA	6	\$930	Generator
	Security System - CCTV	Entire Building	213,710	SF	7	\$0	
	Security System - Intrusion Detection	Entire Building	213,710	SF	7	\$0	
<b>Main Service</b>							
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	6	EA	7	\$0	
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	3	EA	7	\$0	
	PA System	Entire Building	213,710	SF	6	\$70,289	
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Electrical Room	4	EA	7	\$0	
	Lighting and Power Panels - 100 A	Electrical Room	6	EA	7	\$0	Emergency panel
	Lighting and Power Panels - 100 A	Electrical Room	31	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	1	EA	7	\$0	Emergency panel
	Lighting and Power Panels - Above 100 A	Electrical Room	5	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	3	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	15	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	4	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Electrical Room	3	EA	7	\$0	Generator panel
	Transformers - 277/480 - 120/208	Electrical Room	1	EA	7	\$0	
	Transformers - 277/480 - 120/208	Electrical Room	2	EA	7	\$0	
	Transformers - 277/480 - 120/208	Electrical Room	2	EA	7	\$0	
	Transformers - 277/480 - 120/208	Electrical Room	2	EA	7	\$0	In Elevator equipment room
	Transformers - 277/480 - 120/208	Electrical Room	1	EA	7	\$0	

**Electrical System Subtotal:**
**\$115,301**
**Building: Main**
**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Entire Building / Main Entrance	1	EA	6	\$6,406	Has a Trouble alarm that is being fixed
	Fire Alarm Strobe Lights	Entire Building	213,710	SF	7	\$0	

**Building: Main**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm_System	Entire Building	213,710	SF	6	\$103,906	
	Fire Pump Controller	Entire Building / Mechanical Room	1	EA	6	\$1,823	
<b>Pump Room Assembly</b>							
	Fire Pump - 51-75hp	Mechanical Room	1	EA	6	\$1,558	
	Jockey Pump	Mechanical Room	1	EA	6	\$758	
<b>Sprinkler System</b>							
	Dry Sprinkler System	Entire Building	1,000	SF	7	\$0	Serves Dock Area only.
	Sprinkler Heads	Entire Building	213,710	SF	7	\$0	
	Sprinkler Piping	Entire Building	213,710	SF	7	\$0	
	Wet Sprinkler System	Entire Building	213,710	SF	7	\$0	

**Safty System Subtotal:**

**\$114,450**

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	7	\$0	
	Chiller-Air Cooled-Screw Type-Roof Mounted - Greater than 400 tons	Roof	1	EA	6	\$4,969	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	3	EA	6	\$10,001	
	Glycol Feed	Roof / Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Galvanized	Roof / Mechanical Room	1,500	LF	7	\$0	
	Pressure Fill System	Roof / Mechanical Room	1	EA	7	\$0	
<b>Air Handling Systems</b>							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mech Room AHU-3/4 / Mechanical Room	2	EA	7	\$0	serves gym and stage area
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mech Room AHU-5 / Mechanical Room	1	EA	7	\$0	serves pool with ERU
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mech Room AHU-6 / Mechanical Room	1	EA	7	\$0	serves locker room
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	mech room AHU-1 / Mechanical Room	1	EA	7	\$0	Serves floors 1,2,3 East side
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mech Room AHU-2 / Mechanical Room	1	EA	7	\$0	serves west side
	Air Intake	mech room AHU-1 / Mechanical Room	1	EA	7	\$0	
	Air Intake	Mech Room AHU-2 / Façade- NW	1	EA	7	\$0	

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Intake	Mech Room AHU-3/4 / East Façade	2	EA	7	\$0	
	Air Intake	Mech Room AHU-5 / Façade- SE	1	EA	7	\$0	
	Air Intake	Mech Room AHU-6 / Façade- NE	1	EA	7	\$0	
	Energy Recovery Unit	Mech Room AHU-5 / Mechanical Room	1	EA	7	\$0	
	Energy Recovery Unit	Mech Room AHU-6 / Mechanical Room	1	EA	7	\$0	
	Fan Coil Unit- Ceiling Mounted - Electric	Entire Building / Electrical Room	3	EA	6	\$2,461	
	Indoor Return Fans- Centrifugal Squirrel Cage - 10001 - 20000 CFM	Penthouse / Mechanical Room	2	EA	6	\$3,714	Energy recovery wheel is attached to return fans for AHU1,2
	VAV Box	mech room AHU-1 / East	72	EA	7	\$0	AHU1 1,2,3 floors
	VAV Box	Mech Room AHU-2 / West	72	EA	7	\$0	
	VAV Box	Mech Room AHU-3/4 / Entire Building	3	EA	7	\$0	AHU-3
	VAV Box	Mech Room AHU-3/4 / Entire Building	2	EA	7	\$0	AHU-4
	VAV Box	Mech Room AHU-5 / 1st Floor	6	EA	7	\$0	
	VAV Box	Mech Room AHU-6 / 1st Floor	6	EA	7	\$0	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Condensing Hot Water - 2001 - 3000 HP	Boiler Room	3	EA	6	\$9,215	
	Chemical Pot Feeder	Boiler Room	1	EA	7	\$0	
	Condensing- Hot Water Boiler - 2001 - 3000 MBH	Boiler Room	3	EA	6	\$2,994	
	Glycol Feed System	Boiler Room	1	EA	6	\$539	
	Hot Water Pump	Boiler Room	3	EA	6	\$1,123	
<b>Heating Devices</b>							
	Cabinet Heaters - With Hot Water Coil	Entire Building	14	EA	7	\$0	
	Fin Tube - Hot Water	Entire Building	1,500	LF	7	\$0	Self contained thermostats
	Unit Heater - Electric	Mechanical Room	2	EA	6	\$556	
	Unit Heater - Hot Water	Mechanical Room	11	EA	7	\$0	
<b>Mechanical Plumbing</b>							
	Chilled Water Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - 21 - 50 HP	Boiler Room	2	EA	6	\$2,485	
	Hydronic Supply and Return - Copper	Entire Building	1,500	LF	7	\$0	Hot water to heating devices
<b>Temperature Control</b>							
	DDC System	Entire Building	213,710	SF	7	\$0	
	Electric Thermostat	Entire Building	2	EA	6	\$0	
	Thermostats - DDC	Entire Building	122	EA	6	\$0	
<b>Ventilation</b>							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / Mechanical Room	4	EA	7	\$0	

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	5	EA	6	\$2,962	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	
	Lab Exhaust Hood	Entire Building / 1st Floor	2	EA	7	\$0	
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	7	\$0	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	7	\$0	
<b>Mechanical System Subtotal:</b>						<b>\$48,512</b>	

**Building: Main**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 300001 - 600000 BTU/HR	Mechanical Room	3	EA	6	\$930	
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	213,710	SF	7	\$0	
	Sanitary Piping	Entire Building / Electrical Room	213,710	SF	7	\$0	
	Storm Piping	Entire Building / Electrical Room	213,710	SF	7	\$0	
	Vent Piping	Entire Building	213,710	SF	7	\$0	
<b>Pool Systems</b>							
	Pool Drain Piping	Mechanical Room	100	LF	7	\$0	
	Pool Filtration System including Pump	Mechanical Room	1	EA	6	\$12,330	
	Pool Hot Water Heater - Gas Fired	Mechanical Room	1	EA	6	\$310	
	Pool Supply and Return Piping	Mechanical Room	300	LF	7	\$0	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	7	\$0	
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	7	\$0	
	Pumps - Ejector-Duplex	Mechanical Room	2	EA	7	\$0	
	Pumps - Sump-Duplex	Mechanical Room	5	EA	7	\$0	



**Building: Main**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Plumbing System Subtotal:</b>						<b>\$13,570</b>	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #010 (Regular Classroom)</b>							
	Ceiling - Exposed	Basement	1,410	SF	6	\$2,097	
	Doors - Steel Doors incl hw	Basement	2	EA	6	\$602	
	Floor - Concrete	Basement	1,410	SF	6	\$746	
	Lighting - Pendent/Surface	Basement	17	EA	6	\$2,106	
	Walls - Concrete Block	Basement	1,185	SF	6	\$3,474	Concrete Wall
<b>Classroom #100 - C (Computer Lab)</b>							
	Ceiling - Lay-in	1st Floor	1,410	SF	6	\$4,234	
	Doors - Side-lite	1st Floor	224	SF	6	\$3,745	Windows
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Transom Window	1st Floor	20	SF	6	\$339	
	Floor - Carpet	1st Floor	1,410	SF	6	\$3,004	
	Lighting - Chandelier, Incandescent	1st Floor	29	EA	6	\$13,849	Recessed Fixtures with Incandescent bulbs
	Marker Board	1st Floor	6	LF	6	\$129	
	Walls - Masonry	1st Floor	720	SF	6	\$2,265	
	Walls - Plaster/Drywall	1st Floor	370	SF	6	\$1,021	
<b>Classroom #117 (Computer Lab)</b>							
	Ceiling - Lay-in	1st Floor	770	SF	6	\$2,312	
	Doors - Side-lite	1st Floor	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	770	SF	6	\$1,641	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Storage/ Closet	1st Floor	65	SF	6	\$471	
	Walls - Concrete Block	1st Floor	230	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	910	SF	6	\$2,512	
	Wireless System	1st Floor	1	EA	7	\$0	
<b>Classroom #126 (Regular Classroom)</b>							
	Ceiling - Lay-in	1st Floor	702	SF	6	\$2,108	
	Doors - Hardware	1st Floor	40	EA	6	\$8,464	Overhead metal door.
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #126 (Regular Classroom)</b>							
	Floor - Tile/Sheet	1st Floor	702	SF	6	\$703	
	Lighting - Lay-in	1st Floor	8	EA	6	\$952	
	Marker Board	1st Floor	30	LF	6	\$643	
	Walls - Concrete Block	1st Floor	196	SF	6	\$575	
	Walls - Plaster/Drywall	1st Floor	274	SF	6	\$756	
<b>Classroom #180 B (Language Lab)</b>							
	Ceiling - Lay-in	1st Floor	437	SF	6	\$1,312	
	Ceiling - Plaster/Drywall	1st Floor	184	SF	6	\$637	
	Doors - Store Front	1st Floor	1	EA	6	\$1,208	
	Floor - Carpet	1st Floor	184	SF	6	\$392	
	Floor - Terrazzo	1st Floor	437	SF	6	\$956	
	Lighting - Chandelier, Incandescent	1st Floor	15	EA	6	\$7,163	
	Lighting - Pendent/Surface	1st Floor	3	EA	6	\$372	
	Marker Board	1st Floor	20	LF	6	\$428	
	Walls - Concrete Block	1st Floor	251	SF	6	\$736	
	Walls - Metal Panel	1st Floor	178	SF	6	\$1,329	
<b>Classroom #180A (Language Lab)</b>							
	Ceiling - Plaster/Drywall	1st Floor	719	SF	6	\$2,488	
	Doors - Store Front	1st Floor	1	EA	6	\$1,208	
	Floor - Carpet	1st Floor	719	SF	6	\$1,532	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Concrete Block	1st Floor	419	SF	6	\$1,228	
	Walls - Plaster/Drywall	1st Floor	636	SF	6	\$1,755	
<b>Classroom #200B (Art Room)</b>							
	Casework	2nd Floor	47	LF	6	\$1,187	
	Ceiling - Lay-in	2nd Floor	1,220	SF	6	\$3,664	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,220	SF	6	\$1,221	
	Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	30	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	220	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,255	SF	6	\$3,464	
	Work Sink	2nd Floor	2	EA	6	\$758	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #200B (Art Room)</b>							
<b>Classroom #200D (Art Room)</b>							
	Casework	2nd Floor	47	LF	6	\$1,187	
	Ceiling - Lay-in	2nd Floor	1,220	SF	6	\$3,664	
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,220	SF	6	\$2,669	
	Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	30	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	220	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,255	SF	6	\$3,464	
	Work Sink	2nd Floor	2	EA	6	\$758	
<b>Classroom #200F (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	1,255	SF	6	\$3,769	
	Doors - Side-lite	2nd Floor	1	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,255	SF	6	\$2,746	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Sound Panels	2nd Floor	8	EA	7	\$0	
	Sound System	2nd Floor	1	EA	6	\$1,442	
	Walls - Plaster/Drywall	2nd Floor	1,360	SF	6	\$3,753	
<b>Classroom #200H (Choral Room)</b>							
	Ceiling - Lay-in	2nd Floor	1,755	SF	6	\$5,270	
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Carpet	2nd Floor	1,755	SF	6	\$3,739	
	Instrument Storage Casework	2nd Floor	257	LF	6	\$0	200H-2
	Lighting - Lay-in	2nd Floor	28	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	25	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Risers	2nd Floor	156	LF	6	\$3,511	
	Sound Panels	2nd Floor	11	EA	6	\$44	
	Sound System	2nd Floor	1	EA	6	\$1,442	
	Storage/ Closet	2nd Floor	115	SF	6	\$834	200H-4

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #200H (Choral Room)</b>							
	Walls - Masonry	2nd Floor	90	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,195	SF	6	\$3,298	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #212 (Special Education)</b>							
	Ceiling - Lay-in	2nd Floor	690	SF	6	\$2,072	
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	38	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	690	SF	6	\$1,510	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	510	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	510	SF	6	\$1,408	
<b>Classroom #215 (Regular Classroom)</b>							
	Casework	2nd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #216 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	859	SF	6	\$1,879	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	recessed incandescents
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #216 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #217 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #218 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #219 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #219 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #220 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #221 (Computer Lab)</b>							
	Ceiling - Lay-in	2nd Floor	1,350	SF	6	\$4,054	ncludes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Transom Window	2nd Floor	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,350	SF	6	\$2,954	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	24	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	385	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,205	SF	6	\$3,326	
<b>Classroom #222 (Computer Lab)</b>							
	Ceiling - Lay-in	2nd Floor	1,260	SF	6	\$3,784	includes exposed concrete section with glued ACT
	Charging Station	2nd Floor	5	EA	6	\$2,423	
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Transom Window	2nd Floor	43	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,260	SF	6	\$2,757	
	Lighting - Pendent/Surface	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	225	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	950	SF	6	\$2,622	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #223 (Science Lab Level 2)</b>							
	Casework	2nd Floor	107	LF	6	\$2,702	
	Ceiling - Lay-in	2nd Floor	1,240	SF	6	\$3,724	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Transom Window	2nd Floor	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Concrete Epoxy/ Painted	2nd Floor	1,240	SF	6	\$656	
	Gas Line	2nd Floor	4	EA	6	\$2,036	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	7	\$0	
	Science Lab Elements	2nd Floor	1,240	SF	6	\$8,405	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	390	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,065	SF	6	\$2,939	
	Walls - Structural Glazed Tile	2nd Floor	95	SF	7	\$0	
	Work Sink	2nd Floor	4	EA	6	\$1,516	
<b>Classroom #224 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #226 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	ecessed incandescents

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #226 (Regular Classroom)</b>							
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #227 (Science Lab Level 2)</b>							
	Casework	2nd Floor	107	LF	6	\$2,702	
	Ceiling - Lay-in	2nd Floor	1,240	SF	6	\$3,724	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Transom Window	2nd Floor	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Concrete Epoxy/ Painted	2nd Floor	1,240	SF	6	\$656	
	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	7	\$0	
	Science Lab Elements	2nd Floor	1,240	SF	6	\$8,405	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	390	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,065	SF	6	\$2,939	
	Walls - Structural Glazed Tile	2nd Floor	95	SF	7	\$0	
	Work Sink	2nd Floor	8	EA	6	\$3,032	
<b>Classroom #228 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #230 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT



**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #230 (Regular Classroom)</b>							
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #231 (Science Lab Level 1)</b>							
	Casework	2nd Floor	107	LF	6	\$2,702	
	Ceiling - Lay-in	2nd Floor	1,240	SF	6	\$3,724	ncludes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	16	SF	7	\$0	
	Doors - Transom Window	2nd Floor	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Concrete Epoxy/ Painted	2nd Floor	1,240	SF	6	\$656	
	Fume Hood	2nd Floor	1	EA	6	\$816	
	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	36	LF	7	\$0	
	Science Lab Elements	2nd Floor	1,240	SF	6	\$8,405	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	390	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,065	SF	6	\$2,939	
	Walls - Structural Glazed Tile	2nd Floor	95	SF	7	\$0	
	Work Sink	2nd Floor	8	EA	6	\$3,032	
<b>Classroom #232 (Regular Classroom)</b>							
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	35	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #232 (Regular Classroom)</b>							
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	205	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	975	SF	6	\$2,691	
<b>Classroom #234 (Regular Classroom)</b>							
	Casework	2nd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	ncludes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	410	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	775	SF	6	\$2,139	
<b>Classroom #235 (Regular Classroom)</b>							
	Casework	2nd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	2nd Floor	800	SF	6	\$2,402	includes exposed concrete section with glued ACT
	Doors - Side-lite	2nd Floor	8	SF	7	\$0	
	Doors - Transom Window	2nd Floor	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	800	SF	6	\$1,750	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	30	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	410	SF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	775	SF	6	\$2,139	
<b>Classroom #301 (Regular Classroom)</b>							
	Casework	3rd Floor	10	LF	6	\$253	
	Ceiling - Exposed	3rd Floor	431	SF	6	\$641	
	Ceiling - Lay-in	3rd Floor	431	SF	6	\$1,294	
	Doors - Side-lite	3rd Floor	15	SF	6	\$251	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Doors - Transom Window	3rd Floor	100	SF	6	\$1,693	
	Floor - Terrazzo	3rd Floor	862	SF	6	\$1,886	
	Lighting - Pendent/Surface	3rd Floor	15	EA	6	\$1,858	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #301 (Regular Classroom)</b>							
	Marker Board	3rd Floor	14	LF	6	\$300	
	Walls - Concrete Block	3rd Floor	369	SF	6	\$1,082	
	Walls - Plaster/Drywall	3rd Floor	309	SF	6	\$853	
	Walls - Structural Glazed Tile	3rd Floor	60	SF	6	\$189	
<b>Classroom #312 (Special Education)</b>							
	Ceiling - Lay-in	3rd Floor	690	SF	6	\$2,072	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	100	SF	6	\$1,693	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	690	SF	6	\$691	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	30	LF	6	\$643	
	Student Lockers - One Tier	3rd Floor	24	EA	6	\$2,228	
	Walls - Concrete Block	3rd Floor	510	SF	6	\$1,495	
	Walls - Plaster/Drywall	3rd Floor	510	SF	6	\$1,408	
<b>Classroom #315 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	18	LF	6	\$386	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #316 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #316 (Regular Classroom)</b>							
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #317 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #318 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #319 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #319 (Regular Classroom)</b>							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #320 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
<b>Classroom #321 (Regular Classroom)</b>							
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	1,350	SF	6	\$4,054	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	1,350	SF	6	\$1,351	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	13	EA	6	\$1,611	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	325	SF	6	\$953	
	Walls - Plaster/Drywall	3rd Floor	1,005	SF	6	\$2,774	
	Walls - Structural Glazed Tile	3rd Floor	42	SF	6	\$132	
<b>Classroom #321A (Regular Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	435	SF	6	\$1,306	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #321A (Regular Classroom)</b>							
	Doors - Transom Window	3rd Floor	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	435	SF	6	\$435	
	Lighting - Pendent/Surface	3rd Floor	8	EA	6	\$991	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Concrete Block	3rd Floor	147	SF	6	\$431	
	Walls - Plaster/Drywall	3rd Floor	686	SF	6	\$1,893	
	Walls - Structural Glazed Tile	3rd Floor	10	SF	6	\$31	
<b>Classroom #322 (Computer Lab)</b>							
	Ceiling - Lay-in	3rd Floor	1,260	SF	6	\$3,784	
	Charging Station	3rd Floor	1	EA	6	\$485	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Side-lite	3rd Floor	16	SF	6	\$267	
	Floor - Tile/Sheet	3rd Floor	1,260	SF	6	\$1,261	
	Floor - Transom Window	3rd Floor	40	SF	6	\$677	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	17	EA	6	\$2,106	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	225	SF	6	\$660	
	Walls - Plaster/Drywall	3rd Floor	950	SF	6	\$2,622	
	Walls - Structural Glazed Tile	3rd Floor	42	SF	6	\$132	
<b>Classroom #323 (Science Lab Level 2)</b>							
	Casework	3rd Floor	107	LF	6	\$2,702	
	Ceiling - Lay-in	3rd Floor	1,240	SF	6	\$3,724	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,240	SF	6	\$1,241	
	Gas Line	3rd Floor	6	EA	6	\$3,055	
	Lighting - Pendent/Surface	3rd Floor	28	EA	6	\$3,469	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Concrete Block	3rd Floor	390	SF	6	\$1,143	
	Walls - Plaster/Drywall	3rd Floor	1,065	SF	6	\$2,939	
	Walls - Structural Glazed Tile	3rd Floor	95	SF	6	\$299	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #323 (Science Lab Level 2)</b>							
	Work Sink	3rd Floor	4	EA	6	\$1,516	
<b>Classroom #324 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #326 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #327 (Science Lab Level 2)</b>							
	Casework	3rd Floor	107	LF	6	\$2,702	
	Ceiling - Lay-in	3rd Floor	1,240	SF	6	\$3,724	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	60	SF	6	\$1,016	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Concrete Epoxy/ Painted	3rd Floor	1,240	SF	6	\$656	
	Gas Line	3rd Floor	8	EA	6	\$4,073	
	Lighting - Pendent/Surface	3rd Floor	28	EA	6	\$3,469	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #327 (Science Lab Level 2)</b>							
	Marker Board	3rd Floor	16	LF	6	\$343	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Concrete Block	3rd Floor	390	SF	6	\$1,143	
	Walls - Plaster/Drywall	3rd Floor	1,065	SF	6	\$2,939	
	Walls - Structural Glazed Tile	3rd Floor	95	SF	6	\$299	
	Work Sink	3rd Floor	8	EA	6	\$3,032	
<b>Classroom #328 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Lay-in	3rd Floor	3	EA	6	\$357	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Masonry	3rd Floor	170	SF	6	\$535	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #330 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #331 (Science Lab Level 2)</b>							
	Casework	3rd Floor	107	LF	6	\$2,702	
	Ceiling - Lay-in	3rd Floor	1,240	SF	6	\$3,724	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	



**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #331 (Science Lab Level 2)</b>							
	Doors - Transom Window	3rd Floor	70	SF	6	\$1,185	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,240	SF	6	\$1,241	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	8	EA	6	\$4,073	
	Lighting - Pendent/Surface	3rd Floor	28	EA	6	\$3,469	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Concrete Block	3rd Floor	390	SF	6	\$1,143	
	Walls - Plaster/Drywall	3rd Floor	1,065	SF	6	\$2,939	
	Walls - Structural Glazed Tile	3rd Floor	95	SF	6	\$299	
	Work Sink	3rd Floor	8	EA	6	\$3,032	
<b>Classroom #332 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #334 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #334 (Regular Classroom)</b>							
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	
<b>Classroom #335 (Regular Classroom)</b>							
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	800	SF	6	\$2,402	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	800	SF	6	\$801	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	10	EA	6	\$1,239	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	21	SF	6	\$66	

**Classrooms Subtotal:**

**\$611,894**

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Exposed	000 Scene Shop	810	SF	6	\$1,205	
	Doors - Steel Doors incl hw	000 Scene Shop	2	EA	6	\$602	
	Floor - Concrete Epoxy/ Painted	000 Scene Shop	810	SF	6	\$429	
	Lighting - Pendent/Surface	000 Scene Shop	15	EA	6	\$1,858	
	Power Distribution	000 Scene Shop	6	EA	6	\$12,749	
	Storage/ Closet	000 Scene Shop	100	SF	6	\$725	
	Walls	000 Scene Shop	960		6	\$0	Concrete Walls
	Ceiling - Lay-in	003 E- Park District Check-in	120	SF	6	\$360	
	Doors - Steel Doors incl hw	003 E- Park District Check-in	1	EA	6	\$301	
	Floor - Terrazzo	003 E- Park District Check-in	120	SF	7	\$0	
	Lighting - Pendent/Surface	003 E- Park District Check-in	2	EA	7	\$0	
	Power Distribution	003 E- Park District Check-in	8	EA	6	\$16,999	
	Walls - Concrete Block	003 E- Park District Check-in	350	SF	7	\$0	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	003A concessions	130	SF	6	\$390	
	Doors - Steel Doors incl hw	003A concessions	1	EA	6	\$301	
	Floor - Tile	003A concessions	130	SF	6	\$284	
	Lighting - Lay-in	003A concessions	1	EA	6	\$119	
	Power Distribution	003A concessions	4	EA	6	\$8,500	
	Walls - Concrete Block	003A concessions	397	SF	7	\$0	
	Ceiling - Lay-in	003D park district office	102	SF	6	\$306	
	Doors - Side-lite	003D park district office	8	SF	7	\$0	
	Doors - Steel Doors incl hw	003D park district office	1	EA	6	\$301	
	Floor - Terrazzo	003D park district office	102	SF	7	\$0	
	Lighting - Lay-in	003D park district office	2	EA	7	\$0	
	Power Distribution	003D park district office	8	EA	6	\$16,999	
	Walls - Concrete Block	003D park district office	349	SF	7	\$0	
	Ceiling - Lay-in	004 F - Trainer	90	SF	6	\$270	
	Doors - Steel Doors incl hw	004 F - Trainer	1	EA	6	\$301	
	Floor - Terrazzo	004 F - Trainer	90	SF	6	\$197	
	Lighting - Lay-in	004 F - Trainer	1	EA	6	\$119	
	Power Distribution	004 F - Trainer	4	EA	6	\$8,500	
	Walls - Concrete Block	004 F - Trainer	342	SF	6	\$1,003	
	Work Slnk	004 F - Trainer	1	EA	6	\$508	
	Ceiling - Lay-in	004 G - Men's Coach Office	100	SF	6	\$300	
	Doors - Steel Doors incl hw	004 G - Men's Coach Office	1	EA	6	\$301	
	Floor - Terrazzo	004 G - Men's Coach Office	100	SF	6	\$219	
	Lighting - Lay-in	004 G - Men's Coach Office	2	EA	6	\$238	
	Power Distribution	004 G - Men's Coach Office	4	EA	6	\$8,500	
	Walls - Concrete Block	004 G - Men's Coach Office	350	SF	6	\$1,026	
	Ceiling - Lay-in	006F Trainer	90	SF	6	\$270	
	Doors - Steel Doors incl hw	006F Trainer	1	EA	6	\$301	
	Floor - Terrazzo	006F Trainer	90	SF	6	\$197	
	Lighting - Lay-in	006F Trainer	1	EA	6	\$119	
	Power Distribution	006F Trainer	4	EA	6	\$8,500	
	Walls - Concrete Block	006F Trainer	342	SF	6	\$1,003	
	Ceiling - Lay-in	006G - Women's Coach Office	100	SF	6	\$300	
	Doors - Steel Doors incl hw	006G - Women's Coach Office	1	EA	6	\$301	
	Floor - Terrazzo	006G - Women's Coach Office	100	SF	6	\$219	
	Lighting - Lay-in	006G - Women's Coach Office	2	EA	6	\$238	
	Power Distribution	006G - Women's Coach Office	4	EA	6	\$8,500	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Concrete Block	006G - Women's Coach Office	350	SF	6	\$1,026	
	Ceiling - Plaster/Drywall	007A -Men's Pool Coach	115	SF	6	\$398	
	Doors - Steel Doors incl hw	007A -Men's Pool Coach	1	EA	6	\$301	
	Doors - Transom Window	007A -Men's Pool Coach	24	SF	7	\$0	
	Floor - Terrazzo	007A -Men's Pool Coach	115	SF	7	\$0	
	Lighting - Lay-in	007A -Men's Pool Coach	3	EA	7	\$0	
	Power Distribution	007A -Men's Pool Coach	6	EA	6	\$12,749	
	Walls - Concrete Block	007A -Men's Pool Coach	380	SF	7	\$0	
	Ceiling - Plaster/Drywall	007B - Women's Pool Coach	115	SF	6	\$398	
	Doors - Steel Doors incl hw	007B - Women's Pool Coach	1	EA	6	\$301	
	Doors - Transom Window	007B - Women's Pool Coach	24	SF	7	\$0	
	Floor - Terrazzo	007B - Women's Pool Coach	115	SF	7	\$0	
	Lighting - Lay-in	007B - Women's Pool Coach	3	EA	7	\$0	
	Power Distribution	007B - Women's Pool Coach	6	EA	6	\$12,749	
	Walls - Concrete Block	007B - Women's Pool Coach	380	SF	7	\$0	
	Ceiling - Lay-in	100 B - Work Room	175	SF	6	\$526	
	Doors - Steel Doors incl hw	100 B - Work Room	1	EA	6	\$301	
	Doors - Transom Window	100 B - Work Room	60	SF	6	\$1,016	Including 50 sq.ft. Windows
	Floor - Terrazzo	100 B - Work Room	175	SF	6	\$383	
	Lighting - Chandelier, Incandescent	100 B - Work Room	6	EA	6	\$2,865	Recessed Fixtures with Incandescent bulbs
	Power Distribution	100 B - Work Room	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	100 B - Work Room	490	SF	6	\$1,352	
	Ceiling - Lay-in	100 F - Workroom	417	SF	6	\$1,252	
	Doors - Side-lite	100 F - Workroom	210	SF	6	\$3,511	Windows
	Doors - Transom Window	100 F - Workroom	20	SF	6	\$339	
	Doors - Transom Window	100 F - Workroom	2	SF	6	\$34	
	Floor - Terrazzo	100 F - Workroom	417	SF	6	\$912	
	Lighting - Lay-in	100 F - Workroom	8	EA	6	\$952	Recessed Fixtures with Incandescent bulbs
	Power Distribution	100 F - Workroom	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	100 F - Workroom	615	SF	6	\$1,697	
	Work Slnk	100 F - Workroom	1	EA	6	\$508	
	Ceiling - Lay-in	100A Office	329	SF	6	\$988	
	Doors - Steel Doors incl hw	100A Office	1	EA	6	\$301	
	Doors - Transom Window	100A Office	100	SF	6	\$1,693	Including 100 sq.ft. windows
	Floor - Terrazzo	100A Office	329	SF	6	\$720	
	Lighting - Chandelier, Incandescent	100A Office	8	EA	6	\$3,821	
	Power Distribution	100A Office	12	EA	6	\$25,499	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Plaster/Drywall	100A Office	722	SF	6	\$1,993	
	Ceiling - Lay-in	103B Auditorium lighting control.	167	SF	6	\$502	
	Doors - Transom Window	103B Auditorium lighting control.	46	SF	7	\$0	
	Doors - Wood Doors inclu hw	103B Auditorium lighting control.	1	EA	6	\$301	
	Floor - Carpet	103B Auditorium lighting control.	167	SF	6	\$356	
	Lighting - Lay-in	103B Auditorium lighting control.	2	EA	7	\$0	
	Lighting - Pendent/Surface	103B Auditorium lighting control.	3	EA	6	\$372	Incandescent track lighting.
	Power Distribution	103B Auditorium lighting control.	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	103B Auditorium lighting control.	412	SF	6	\$1,137	
	Ceiling - Lay-in	103B-1 Sound projection	129	SF	6	\$387	
	Doors - Transom Window	103B-1 Sound projection	48	SF	6	\$813	
	Doors - Wood Doors inclu hw	103B-1 Sound projection	1	EA	6	\$301	
	Floor - Carpet	103B-1 Sound projection	129	SF	6	\$275	
	Lighting - Lay-in	103B-1 Sound projection	2	EA	7	\$0	
	Lighting - Pendent/Surface	103B-1 Sound projection	3	EA	6	\$372	Incandescent track lighting.
	Power Distribution	103B-1 Sound projection	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	103B-1 Sound projection	367	SF	6	\$1,013	
	Ceiling - Lay-in	103B-1A follow spot	108	SF	6	\$324	
	Doors - Transom Window	103B-1A follow spot	25	SF	7	\$0	
	Doors - Wood Doors inclu hw	103B-1A follow spot	1	EA	6	\$301	
	Floor - Carpet	103B-1A follow spot	108	SF	6	\$230	
	Lighting - Lay-in	103B-1A follow spot	1	EA	7	\$0	
	Lighting - Pendent/Surface	103B-1A follow spot	2	EA	6	\$248	Incandescent track lighting.
	Power Distribution	103B-1A follow spot	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	103B-1A follow spot	336	SF	6	\$927	
	Ceiling - Lay-in	106 - Campus Manager	128	SF	6	\$384	
	Doors - Wood Doors inclu hw	106 - Campus Manager	1	EA	6	\$301	
	Floor - Tile/Sheet	106 - Campus Manager	128	SF	6	\$128	
	Lighting - Lay-in	106 - Campus Manager	2	EA	6	\$238	
	Power Distribution	106 - Campus Manager	4	EA	6	\$8,500	
	Walls - Concrete Block	106 - Campus Manager	230	SF	6	\$674	
	Walls - Plaster/Drywall	106 - Campus Manager	230	SF	6	\$635	
	Ceiling - Lay-in	111 - Security	100	SF	6	\$300	
	Doors - Wood Doors inclu hw	111 - Security	1	EA	6	\$301	
	Floor - Tile	111 - Security	100	SF	6	\$219	
	Lighting - Lay-in	111 - Security	2	EA	7	\$0	
	Power Distribution	111 - Security	4	EA	6	\$8,500	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Concrete Block	111 - Security	360	SF	7	\$0	
	Ceiling - Lay-in	116 - Office of Development	325	SF	6	\$976	
	Doors - Wood Doors inclu hw	116 - Office of Development	1	EA	6	\$301	
	Floor - Carpet	116 - Office of Development	325	SF	6	\$692	
	Lighting - Lay-in	116 - Office of Development	4	EA	6	\$476	
	Power Distribution	116 - Office of Development	4	EA	6	\$8,500	
	Walls - Concrete Block	116 - Office of Development	152	SF	6	\$446	
	Walls - Plaster/Drywall	116 - Office of Development	517	SF	6	\$1,427	
	Ceiling - Lay-in	116 A - Office	100	SF	6	\$300	
	Doors - Wood Doors inclu hw	116 A - Office	1	EA	6	\$301	
	Floor - Carpet	116 A - Office	100	SF	6	\$213	
	Lighting - Lay-in	116 A - Office	2	EA	6	\$238	
	Power Distribution	116 A - Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	116 A - Office	360	SF	6	\$994	
	Ceiling - Lay-in	118 - South Work Room / Mailbox	390	SF	6	\$1,171	
	Doors - Wood Doors inclu hw	118 - South Work Room / Mailbox	2	EA	6	\$602	
	Floor - Terrazzo	118 - South Work Room / Mailbox	390	SF	6	\$853	
	Lighting - Lay-in	118 - South Work Room / Mailbox	8	EA	6	\$952	
	Power Distribution	118 - South Work Room / Mailbox	10	EA	6	\$21,249	
	Walls - Concrete Block	118 - South Work Room / Mailbox	130	SF	6	\$381	
	Walls - Plaster/Drywall	118 - South Work Room / Mailbox	730	SF	6	\$2,015	
	Work Slnk	118 - South Work Room / Mailbox	1	EA	6	\$508	
	Ceiling - Lay-in	120 A - Conference	225	SF	6	\$676	
	Doors - Wood Doors inclu hw	120 A - Conference	1	EA	6	\$301	
	Floor - Carpet	120 A - Conference	225	SF	6	\$479	
	Lighting - Lay-in	120 A - Conference	6	EA	6	\$714	
	Power Distribution	120 A - Conference	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	120 A - Conference	585	SF	6	\$1,615	
	Ceiling - Lay-in	120 B - Assistant Principal	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	120 B - Assistant Principal	1	EA	6	\$301	
	Floor - Carpet	120 B - Assistant Principal	160	SF	6	\$341	
	Lighting - Lay-in	120 B - Assistant Principal	2	EA	6	\$238	
	Power Distribution	120 B - Assistant Principal	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	120 B - Assistant Principal	468	SF	6	\$1,292	
	Ceiling - Lay-in	120 C - Assistant Principal	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	120 C - Assistant Principal	1	EA	6	\$301	
	Floor - Carpet	120 C - Assistant Principal	160	SF	6	\$341	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Lighting - Lay-in	120 C - Assistant Principal	2	EA	6	\$238	
	Power Distribution	120 C - Assistant Principal	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	120 C - Assistant Principal	468	SF	6	\$1,292	
	Ceiling - Lay-in	120 D - Dean	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	120 D - Dean	1	EA	6	\$301	
	Floor - Carpet	120 D - Dean	160	SF	6	\$341	
	Lighting - Lay-in	120 D - Dean	2	EA	6	\$238	
	Power Distribution	120 D - Dean	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	120 D - Dean	468	SF	6	\$1,292	
	Ceiling - Lay-in	120 E - Principal	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	120 E - Principal	1	EA	6	\$301	
	Floor - Carpet	120 E - Principal	208	SF	6	\$443	
	Lighting - Lay-in	120 E - Principal	4	EA	6	\$476	
	Power Distribution	120 E - Principal	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	120 E - Principal	600	SF	6	\$1,656	
	Ceiling - Lay-in	120-Main Office South	762	SF	6	\$2,288	
	Doors - Side-lite	120-Main Office South	8	SF	6	\$134	
	Doors - Transom Window	120-Main Office South	60	SF	6	\$1,016	
	Doors - Wood Doors inclu hw	120-Main Office South	1	EA	6	\$301	
	Floor - Carpet	120-Main Office South	762	SF	6	\$1,624	
	Lighting - Chandelier, Incandescent	120-Main Office South	6	EA	6	\$2,865	
	Lighting - Lay-in	120-Main Office South	8	EA	6	\$952	
	Power Distribution	120-Main Office South	12	EA	6	\$25,499	
	Walls - Concrete Block	120-Main Office South	378	SF	6	\$1,108	
	Walls - Plaster/Drywall	120-Main Office South	1,035	SF	6	\$2,856	
	Ceiling - Lay-in	122 A - Conference Room	230	SF	6	\$691	
	Doors - Wood Doors inclu hw	122 A - Conference Room	1	EA	6	\$301	
	Floor - Carpet	122 A - Conference Room	230	SF	6	\$490	
	Lighting - Lay-in	122 A - Conference Room	6	EA	6	\$714	
	Power Distribution	122 A - Conference Room	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	122 A - Conference Room	600	SF	6	\$1,656	
	Ceiling - Lay-in	122 B - Counselor	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	122 B - Counselor	1	EA	6	\$301	
	Floor - Carpet	122 B - Counselor	160	SF	6	\$341	
	Lighting - Lay-in	122 B - Counselor	2	EA	6	\$238	
	Power Distribution	122 B - Counselor	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	122 B - Counselor	468	SF	6	\$1,292	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	122 C - Counselor	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	122 C - Counselor	1	EA	6	\$301	
	Floor - Carpet	122 C - Counselor	160	SF	6	\$341	
	Lighting - Lay-in	122 C - Counselor	2	EA	6	\$238	
	Power Distribution	122 C - Counselor	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	122 C - Counselor	468	SF	6	\$1,292	
	Ceiling - Lay-in	122 D - Counselor	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	122 D - Counselor	1	EA	6	\$301	
	Floor - Carpet	122 D - Counselor	160	SF	6	\$341	
	Lighting - Lay-in	122 D - Counselor	2	EA	6	\$238	
	Power Distribution	122 D - Counselor	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	122 D - Counselor	468	SF	6	\$1,292	
	Ceiling - Lay-in	122 E - Case Manager	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	122 E - Case Manager	1	EA	6	\$301	
	Floor - Carpet	122 E - Case Manager	208	SF	6	\$443	
	Lighting - Lay-in	122 E - Case Manager	4	EA	6	\$476	
	Power Distribution	122 E - Case Manager	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	122 E - Case Manager	600	SF	6	\$1,656	
	Ceiling - Lay-in	122-Main Office North	762	SF	6	\$2,288	
	Doors - Side-lite	122-Main Office North	8	SF	6	\$134	
	Doors - Transom Window	122-Main Office North	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	122-Main Office North	1	EA	6	\$301	
	Floor - Carpet	122-Main Office North	762	SF	6	\$1,624	
	Lighting - Chandelier, Incandescent	122-Main Office North	6	EA	6	\$2,865	
	Lighting - Lay-in	122-Main Office North	7	EA	6	\$833	Includes eight (8) recessed fixtures with incandescent bulbs
	Power Distribution	122-Main Office North	12	EA	6	\$25,499	
	Walls - Concrete Block	122-Main Office North	378	SF	6	\$1,108	
	Walls - Plaster/Drywall	122-Main Office North	1,035	SF	6	\$2,856	
	Ceiling - Lay-in	124 - North Work Room / Mailbox	390	SF	6	\$1,171	
	Doors - Wood Doors inclu hw	124 - North Work Room / Mailbox	2	EA	6	\$602	
	Floor - Terrazzo	124 - North Work Room / Mailbox	390	SF	6	\$853	
	Lighting - Lay-in	124 - North Work Room / Mailbox	8	EA	6	\$952	
	Power Distribution	124 - North Work Room / Mailbox	10	EA	6	\$21,249	
	Walls - Concrete Block	124 - North Work Room / Mailbox	130	SF	6	\$381	
	Walls - Plaster/Drywall	124 - North Work Room / Mailbox	730	SF	6	\$2,015	
	Work Slnk	124 - North Work Room / Mailbox	1	EA	6	\$508	
	Ceiling - Lay-in	125 E-Kitchen Office	160	SF	6	\$480	



**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Doors - Steel Doors incl hw	125 E-Kitchen Office	2	EA	6	\$602	
	Floor - Tile/Sheet	125 E-Kitchen Office	160	SF	6	\$160	
	Lighting - Lay-in	125 E-Kitchen Office	2	EA	6	\$238	
	Power Distribution	125 E-Kitchen Office	6	EA	6	\$12,749	
	Walls - Concrete Block	125 E-Kitchen Office	500	SF	6	\$1,466	
	Ceiling - Lay-in	127 - Engineer's Office	175	SF	6	\$526	
	Doors - Steel Doors incl hw	127 - Engineer's Office	1	EA	6	\$301	
	Doors - Transom Window	127 - Engineer's Office	35	SF	7	\$0	
	Floor - Concrete	127 - Engineer's Office	175	SF	6	\$93	
	Lighting - Lay-in	127 - Engineer's Office	2	EA	7	\$0	
	Power Distribution	127 - Engineer's Office	4	EA	6	\$8,500	
	Walls - Concrete Block	127 - Engineer's Office	490	SF	7	\$0	
	Ceiling - Lay-in	128 A - Counselor	100	SF	6	\$300	
	Doors - Wood Doors inclu hw	128 A - Counselor	1	EA	6	\$301	
	Floor - Carpet	128 A - Counselor	100	SF	6	\$213	
	Lighting - Lay-in	128 A - Counselor	2	EA	6	\$238	
	Power Distribution	128 A - Counselor	4	EA	6	\$8,500	
	Walls - Concrete Block	128 A - Counselor	360	SF	6	\$1,055	
	Ceiling - Lay-in	128 B - Social Worker	100	SF	6	\$300	
	Doors - Wood Doors inclu hw	128 B - Social Worker	1	EA	6	\$301	
	Floor - Carpet	128 B - Social Worker	100	SF	6	\$213	
	Lighting - Lay-in	128 B - Social Worker	2	EA	6	\$238	
	Power Distribution	128 B - Social Worker	4	EA	6	\$8,500	
	Walls - Concrete Block	128 B - Social Worker	360	SF	6	\$1,055	
	Ceiling - Lay-in	128 C - Counselor	100	SF	6	\$300	
	Ceiling - Lay-in	128 C - Counselor	118	SF	6	\$354	
	Doors - Wood Doors inclu hw	128 C - Counselor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	128 C - Counselor	1	EA	6	\$301	
	Floor - Carpet	128 C - Counselor	118	SF	6	\$251	
	Floor - Carpet	128 C - Counselor	100	SF	6	\$213	
	Lighting - Lay-in	128 C - Counselor	2	EA	6	\$238	
	Lighting - Lay-in	128 C - Counselor	2	EA	6	\$238	
	Power Distribution	128 C - Counselor	4	EA	6	\$8,500	
	Power Distribution	128 C - Counselor	4	EA	6	\$8,500	
	Walls - Concrete Block	128 C - Counselor	360	SF	6	\$1,055	
	Walls - Plaster/Drywall	128 C - Counselor	360	SF	6	\$994	
	Ceiling - Lay-in	128 D - Workroom Lab	75	SF	6	\$225	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Doors - Wood Doors inclu hw	128 D - Workroom Lab	1	EA	6	\$301	
	Floor - Tile/Sheet	128 D - Workroom Lab	75	SF	6	\$75	
	Lighting - Lay-in	128 D - Workroom Lab	1	EA	6	\$119	
	Power Distribution	128 D - Workroom Lab	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	128 D - Workroom Lab	324	SF	6	\$894	
	Work Sink	128 D - Workroom Lab	1	EA	6	\$508	
	Ceiling - Lay-in	128 E - Exam Room	135	SF	6	\$405	
	Doors - Wood Doors inclu hw	128 E - Exam Room	1	EA	6	\$301	
	Floor - Tile/Sheet	128 E - Exam Room	135	SF	6	\$135	
	Lighting - Lay-in	128 E - Exam Room	2	EA	6	\$238	
	Power Distribution	128 E - Exam Room	4	EA	6	\$8,500	
	Walls - Concrete Block	128 E - Exam Room	90	SF	6	\$264	
	Walls - Plaster/Drywall	128 E - Exam Room	335	SF	6	\$925	
	Work Sink	128 E - Exam Room	1	EA	6	\$508	
	Ceiling - Lay-in	128 F - Exam Room	135	SF	6	\$405	
	Doors - Wood Doors inclu hw	128 F - Exam Room	1	EA	6	\$301	
	Floor - Tile/Sheet	128 F - Exam Room	135	SF	6	\$135	
	Lighting - Lay-in	128 F - Exam Room	2	EA	6	\$238	
	Power Distribution	128 F - Exam Room	4	EA	6	\$8,500	
	Walls - Concrete Block	128 F - Exam Room	90	SF	6	\$264	
	Walls - Plaster/Drywall	128 F - Exam Room	335	SF	6	\$925	
	Work Sink	128 F - Exam Room	1	EA	6	\$508	
	Ceiling - Lay-in	128 G - Cot Room	180	SF	6	\$541	
	Doors - Wood Doors inclu hw	128 G - Cot Room	1	EA	6	\$301	
	Floor - Tile/Sheet	128 G - Cot Room	180	SF	6	\$180	
	Lighting - Lay-in	128 G - Cot Room	3	EA	6	\$357	
	Power Distribution	128 G - Cot Room	6	EA	6	\$12,749	
	Walls - Concrete Block	128 G - Cot Room	180	SF	6	\$528	
	Walls - Plaster/Drywall	128 G - Cot Room	324	SF	6	\$894	
	Work Sink	128 G - Cot Room	1	EA	6	\$508	
	Ceiling - Lay-in	128-Nurse Suite	950	SF	6	\$2,853	
	Doors - Side-lite	128-Nurse Suite	36	SF	6	\$602	
	Doors - Steel Doors incl hw	128-Nurse Suite	2	EA	6	\$602	
	Floor - Terrazzo	128-Nurse Suite	950	SF	6	\$2,079	
	Lighting - Lay-in	128-Nurse Suite	17	EA	6	\$2,023	Includes eight (8) recessed fixtures with incandescent bulbs
	Power Distribution	128-Nurse Suite	22	EA	6	\$46,747	
	Walls - Concrete Block	128-Nurse Suite	387	SF	6	\$1,134	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Plaster/Drywall	128-Nurse Suite	1,750	SF	6	\$4,830	
	Ceiling - Lay-in	1st floor - 125A - Kitchen Manager Office	155	SF	6	\$465	
	Doors - Side-lite	1st floor - 125A - Kitchen Manager Office	55	SF	7	\$0	
	Doors - Steel Doors incl hw	1st floor - 125A - Kitchen Manager Office	1	EA	6	\$301	
	Floor - Tile	1st floor - 125A - Kitchen Manager Office	155	SF	6	\$339	
	Lighting - Lay-in	1st floor - 125A - Kitchen Manager Office	2	EA	7	\$0	
	Power Distribution	1st floor - 125A - Kitchen Manager Office	6	EA	6	\$12,749	
	Walls - Concrete Block	1st floor - 125A - Kitchen Manager Office	375	SF	7	\$0	
	Ceiling - Lay-in	200A Department Office	375	SF	6	\$1,126	
	Doors - Side-lite	200A Department Office	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	200A Department Office	1	EA	6	\$301	
	Floor - Tile	200A Department Office	375	SF	6	\$820	
	Lighting - Lay-in	200A Department Office	6	EA	7	\$0	
	Power Distribution	200A Department Office	10	EA	6	\$21,249	
	Storage/ Closet	200A Department Office	275	SF	6	\$1,994	200A-1
	Walls - Concrete Block	200A Department Office	390	SF	7	\$0	
	Walls - Plaster/Drywall	200A Department Office	395	SF	7	\$0	
	Ceiling - Exposed	200C area of rescue assistance	28	SF	6	\$42	
	Doors - Wood Doors inclu hw	200C area of rescue assistance	1	EA	6	\$301	
	Floor - Terrazzo	200C area of rescue assistance	28	SF	6	\$61	
	Lighting - Pendent/Surface	200C area of rescue assistance	1	EA	7	\$0	
	Power Distribution	200C area of rescue assistance	2	EA	6	\$4,250	
	Walls - Concrete Block	200C area of rescue assistance	355	SF	6	\$1,041	
	Ceiling - Lay-in	200F office	90	SF	6	\$270	
	Doors - Side-lite	200F office	16	SF	7	\$0	
	Doors - Wood Doors inclu hw	200F office	1	EA	6	\$301	
	Floor - Carpet	200F office	90	SF	6	\$192	
	Lighting - Lay-in	200F office	3	EA	7	\$0	
	Power Distribution	200F office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	200F office	260	SF	6	\$718	
	Ceiling - Exposed	200G area of rescue assistance	28	SF	6	\$42	
	Doors - Wood Doors inclu hw	200G area of rescue assistance	1	EA	6	\$301	
	Floor - Terrazzo	200G area of rescue assistance	28	SF	6	\$61	
	Lighting - Pendent/Surface	200G area of rescue assistance	1	EA	7	\$0	
	Power Distribution	200G area of rescue assistance	2	EA	6	\$4,250	
	Walls - Concrete Block	200G area of rescue assistance	355	SF	6	\$1,041	
	Ceiling - Lay-in	200H - 5 practice room	142	SF	6	\$426	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Doors - Side-lite	200H - 5 practice room	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	200H - 5 practice room	1	EA	6	\$301	
	Floor - Tile	200H - 5 practice room	142	SF	6	\$311	
	Lighting - Lay-in	200H - 5 practice room	2	EA	7	\$0	
	Power Distribution	200H - 5 practice room	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	200H - 5 practice room	420	SF	6	\$1,159	
	Ceiling - Lay-in	200H - 6 practice room	101	SF	6	\$303	
	Doors - Side-lite	200H - 6 practice room	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	200H - 6 practice room	1	EA	6	\$301	
	Floor - Tile	200H - 6 practice room	101	SF	6	\$221	
	Lighting - Lay-in	200H - 6 practice room	2	EA	7	\$0	
	Power Distribution	200H - 6 practice room	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	200H - 6 practice room	295	SF	6	\$814	
	Ceiling - Lay-in	200H-3	92	SF	6	\$276	
	Doors - Side-lite	200H-3	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	200H-3	1	EA	6	\$301	
	Floor - Carpet	200H-3	92	SF	6	\$196	
	Lighting - Lay-in	200H-3	3	EA	7	\$0	
	Power Distribution	200H-3	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	200H-3	276	SF	6	\$762	
	Ceiling - Lay-in	200H-7 practice room	101	SF	6	\$303	
	Doors - Side-lite	200H-7 practice room	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	200H-7 practice room	1	EA	6	\$301	
	Floor - Tile	200H-7 practice room	101	SF	6	\$221	
	Lighting - Lay-in	200H-7 practice room	2	EA	7	\$0	
	Power Distribution	200H-7 practice room	6	EA	6	\$12,749	
	Walls - Concrete Block	200H-7 practice room	53	SF	7	\$0	
	Walls - Plaster/Drywall	200H-7 practice room	326	SF	6	\$900	
	Ceiling - Exposed	225 science prep Rm	390	SF	6	\$580	
	Doors - Side-lite	225 science prep Rm	8	SF	7	\$0	
	Doors - Transom Window	225 science prep Rm	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	225 science prep Rm	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	225 science prep Rm	390	SF	6	\$206	
	Lighting - Pendent/Surface	225 science prep Rm	4	EA	7	\$0	
	Power Distribution	225 science prep Rm	8	EA	6	\$16,999	
	Storage/ Closet	225 science prep Rm	23	SF	6	\$167	Electrical closet
	Walls - Concrete Block	225 science prep Rm	130	SF	7	\$0	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Plaster/Drywall	225 science prep Rm	795	SF	6	\$2,194	
	Work Slnk	225 science prep Rm	1	EA	6	\$508	
	Ceiling - Exposed	229 science prep	390	SF	6	\$580	
	Doors - Side-lite	229 science prep	8	SF	7	\$0	
	Doors - Transom Window	229 science prep	8	SF	7	\$0	
	Doors - Wood Doors inclu hw	229 science prep	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	229 science prep	390	SF	6	\$206	
	Lighting - Pendent/Surface	229 science prep	4	EA	7	\$0	
	Power Distribution	229 science prep	8	EA	6	\$16,999	
	Walls - Concrete Block	229 science prep	130	SF	7	\$0	
	Walls - Plaster/Drywall	229 science prep	795	SF	6	\$2,194	
	Ceiling - Exposed	311C area of rescue assistance	28	SF	6	\$42	
	Doors - Wood Doors inclu hw	311C area of rescue assistance	1	EA	6	\$301	
	Floor - Terrazzo	311C area of rescue assistance	28	SF	6	\$61	
	Lighting - Pendent/Surface	311C area of rescue assistance	1	EA	6	\$124	
	Power Distribution	311C area of rescue assistance	2	EA	6	\$4,250	
	Walls - Concrete Block	311C area of rescue assistance	355	SF	6	\$1,041	
	Ceiling - Lay-in	313 Office	210	SF	6	\$631	
	Doors - Side-lite	313 Office	8	SF	6	\$134	
	Doors - Transom Window	313 Office	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	313 Office	1	EA	6	\$301	
	Floor - Tile/Sheet	313 Office	210	SF	6	\$210	
	Lighting - Lay-in	313 Office	4	EA	6	\$476	
	Power Distribution	313 Office	6	EA	6	\$12,749	
	Walls - Concrete Block	313 Office	250	SF	6	\$733	
	Walls - Plaster/Drywall	313 Office	250	SF	6	\$690	
	Ceiling - Lay-in	325 science prep	390	SF	6	\$1,171	
	Doors - Wood Doors inclu hw	325 science prep	3	EA	6	\$903	
	Floor - Tile/Sheet	325 science prep	390	SF	6	\$390	
	Lighting - Pendent/Surface	325 science prep	4	EA	6	\$496	
	Power Distribution	325 science prep	8	EA	6	\$16,999	
	Walls - Concrete Block	325 science prep	110	SF	6	\$322	
	Walls - Plaster/Drywall	325 science prep	665	SF	6	\$1,835	
<b>Gymnasia</b>							
	Balcony Seating	Basement	2	EA	6	\$348	Gym Observation deck 340sq'
	Bleacher Seating	Basement	1,186	EA	6	\$34,327	
	Ceiling - Exposed	Basement	12,000	SF	7	\$0	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Gymnasia</b>							
	Doors - Steel Doors incl hw	Basement	20	EA	6	\$6,020	
	Floor - Wood	Basement	12,000	SF	6	\$84,599	
	Lighting - Metal Halide/Sodium Vapor	Basement	60	EA	7	\$0	
	Lighting - Pendent/Surface	Basement	60	EA	7	\$0	
	Scoreboards	Basement	3	EA	6	\$6,733	2 scoreboards in gym, 1 in pool area.
	Sound System	Basement	1	EA	6	\$41,654	
	Stage	Basement	2,870	SF	6	\$16,581	
	Stage Curtain	Basement	4	EA	6	\$0	
	Stage Lift	Basement	1	EA	6	\$6,510	
	Stage Lighting System	Basement	1	EA	6	\$12,369	
	Stage-Stairs - Wood	Basement	5	LF	6	\$59	
	Storage/ Closet	Basement	75	SF	6	\$544	
	Walls - Concrete Block	Basement	7,500	SF	7	\$0	Brick
	Walls - Metal Panel	Basement	5,900	SF	6	\$44,041	
	Walls - Plaster/Drywall	Basement	1,530	SF	6	\$4,223	
	Walls - Structural Glazed Tile	Basement	5,440	SF	7	\$0	
<b>Kitchen</b>							
	Ceiling - Lay-in	125 - Kitchen	1,215	SF	6	\$3,649	
	Doors - Steel Doors incl hw	125 - Kitchen	3	EA	6	\$903	1-Double door
	Floor - Tile/Sheet	125 - Kitchen	1,215	SF	6	\$1,216	
	Lighting - Lay-in	125 - Kitchen	16	EA	7	\$0	
	Storage/ Closet	125 - Kitchen	285	SF	6	\$2,066	125D - Storage
	Storage/ Closet	125 - Kitchen	146	SF	6	\$1,059	Corner walk-in coolers
	Walls - Structural Glazed Tile	125 - Kitchen	1,100	SF	7	\$0	
<b>Library</b>							
	Casework	100 - Library	275	LF	6	\$6,945	
	Ceiling - Lay-in	100 - Library	365	SF	6	\$1,096	Includes Exposed Concrete with Sections of Splined Panels
	Ceiling - Splined	100 - Library	5,555	SF	6	\$4,528	
	Doors - Side-lite	100 - Library	30	SF	6	\$502	
	Doors - Steel Doors incl hw	100 - Library	2	EA	6	\$602	
	Doors - Transom Window	100 - Library	40	SF	6	\$677	
	Floor - Carpet	100 - Library	5,325	SF	6	\$11,346	
	Floor - Terrazzo	100 - Library	2,300	SF	6	\$5,032	
	Lighting - Chandelier, Incandescent	100 - Library	30	EA	6	\$14,327	Recessed Fixtures with Incandescent bulbs
	Lighting - Pendent/Surface	100 - Library	88	EA	6	\$10,903	
	Walls - Masonry	100 - Library	1,790	SF	6	\$5,631	Brick

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Library</b>	Walls - Plaster/Drywall	100 - Library	1,790	SF	6	\$4,940	
<b>Locker/Shower Room</b>	Accessories	005 Men's Pool Locker Rm	900	SF	6	\$3,526	
	Benches, ped mounted	005 Men's Pool Locker Rm	72	LF	6	\$7,839	
	Ceiling - Plaster/ Drywall	005 Men's Pool Locker Rm	900	SF	6	\$3,115	
	Doors - Steel Doors incl hw	005 Men's Pool Locker Rm	2	EA	6	\$602	
	Floor Drain	005 Men's Pool Locker Rm	10	EA	6	\$10,592	
	Floor - Concrete Epoxy/ Painted	005 Men's Pool Locker Rm	900	SF	6	\$476	
	Hand Dryer	005 Men's Pool Locker Rm	2	EA	6	\$460	
	Lavatory	005 Men's Pool Locker Rm	3	EA	6	\$959	
	Lighting - Lay-in	005 Men's Pool Locker Rm	12	EA	7	\$0	
	Partitions	005 Men's Pool Locker Rm	2	EA	6	\$594	
	Showers	005 Men's Pool Locker Rm	5	EA	6	\$1,557	
	Student Lockers - One Tier	005 Men's Pool Locker Rm	90	EA	6	\$8,355	
	Student Lockers - Two Tier	005 Men's Pool Locker Rm	40	EA	6	\$1,857	
	Urinals	005 Men's Pool Locker Rm	1	EA	6	\$336	
	Walls - Concrete Block	005 Men's Pool Locker Rm	2,100	SF	6	\$6,156	
	Walls - Tile Ceramic/ Porcelain	005 Men's Pool Locker Rm	360	SF	6	\$813	
	Water Closet	005 Men's Pool Locker Rm	2	EA	6	\$672	
	Accessories	006E Women's Team Lockers	570	SF	6	\$2,233	
	Benches, ped mounted	006E Women's Team Lockers	120	LF	6	\$13,066	
	Ceiling - Plaster/ Drywall	006E Women's Team Lockers	570	SF	6	\$1,973	
	Doors - Wood Doors inclu hw	006E Women's Team Lockers	2	EA	6	\$602	
	Floor Drain	006E Women's Team Lockers	7	EA	6	\$7,414	
	Floor - Epoxy/ Painted	006E Women's Team Lockers	570	SF	6	\$302	
	Lighting - Lay-in	006E Women's Team Lockers	11	EA	6	\$1,309	
	Student Lockers - One Tier	006E Women's Team Lockers	199	EA	6	\$18,474	
	Walls - Concrete Block	006E Women's Team Lockers	1,410	SF	6	\$4,133	
	Accessories	013 Womens Pool Locker Rm	900	SF	6	\$3,526	
	Benches, ped mounted	013 Womens Pool Locker Rm	75	LF	7	\$0	
	Ceiling - Plaster/ Drywall	013 Womens Pool Locker Rm	900	SF	6	\$3,115	
	Doors - Steel Doors incl hw	013 Womens Pool Locker Rm	3	EA	6	\$903	
	Floor Drain	013 Womens Pool Locker Rm	9	EA	6	\$9,532	
	Floor - Concrete Epoxy/ Painted	013 Womens Pool Locker Rm	900	SF	6	\$476	
	Hand Dryer	013 Womens Pool Locker Rm	2	EA	6	\$460	
	Lavatory	013 Womens Pool Locker Rm	3	EA	6	\$959	
	Lighting - Lay-in	013 Womens Pool Locker Rm	11	EA	7	\$0	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Locker/Shower Room</b>							
	Partitions	013 Womens Pool Locker Rm	2	EA	6	\$594	
	Showers	013 Womens Pool Locker Rm	5	EA	6	\$1,557	
	Student Lockers - One Tier	013 Womens Pool Locker Rm	90	EA	6	\$8,355	
	Student Lockers - Two Tier	013 Womens Pool Locker Rm	38	EA	6	\$1,764	
	Walls - Concrete Block	013 Womens Pool Locker Rm	2,100	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	013 Womens Pool Locker Rm	360	SF	6	\$813	
	Water Closet	013 Womens Pool Locker Rm	3	EA	6	\$1,008	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Lay-in	002 - Green Room	375	SF	6	\$1,126	
	Chalk Board	002 - Green Room	50	LF	6	\$1,115	
	Doors - Steel Doors incl hw	002 - Green Room	1	EA	6	\$301	
	Floor - Terrazzo	002 - Green Room	375	SF	6	\$820	Terrazzo Floor
	Lighting - Lay-in	002 - Green Room	8	EA	6	\$952	
	Walls - Concrete Block	002 - Green Room	675	SF	6	\$1,979	
	Ceiling - Lay-in	003 A - Concession	130	SF	6	\$390	
	Doors - Steel Doors incl hw	003 A - Concession	1	EA	6	\$301	
	Floor - Tile/Sheet	003 A - Concession	130	SF	6	\$130	
	Lighting - Lay-in	003 A - Concession	1	EA	7	\$0	
	Walls - Concrete Block	003 A - Concession	390	SF	6	\$1,143	
	Ceiling - Lay-in	008 - Fitness	1,325	SF	6	\$3,979	
	Doors - Side-lite	008 - Fitness	10	SF	6	\$167	
	Doors - Steel Doors incl hw	008 - Fitness	1	EA	6	\$301	
	Doors - Transom Window	008 - Fitness	6	SF	6	\$102	
	Floor - Weight/ Fitness Room Floor Matting	008 - Fitness	1,325	SF	6	\$6,935	
	Lighting - Lay-in	008 - Fitness	16	EA	6	\$1,904	
	Walls - Concrete Block	008 - Fitness	1,350	SF	6	\$3,958	
	Ceiling - Exposed	012 - Laundry Room	205	SF	6	\$305	
	Doors - Steel Doors incl hw	012 - Laundry Room	1	EA	6	\$301	
	Floor - Concrete	012 - Laundry Room	205	SF	6	\$108	Concrete
	Lighting - Pendent/Surface	012 - Laundry Room	2	EA	6	\$248	
	Walls - Concrete Block	012 - Laundry Room	900	SF	6	\$2,638	
	Ceiling - Lay-in	121 A - Faculty Dining	315	SF	6	\$946	
	Doors - Side-lite	121 A - Faculty Dining	50	SF	7	\$0	
	Doors - Wood Doors inclu hw	121 A - Faculty Dining	2	EA	6	\$602	1-Double door
	Floor - Terrazzo	121 A - Faculty Dining	315	SF	7	\$0	Terrazzo
	Lighting - Lay-in	121 A - Faculty Dining	6	EA	7	\$0	Recessed Fixtures with Incandescent bulbs
	Walls - Structural Glazed Tile	121 A - Faculty Dining	485	SF	7	\$0	



**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Exposed	1st Floor - 121 Lunchroom / Tray Drop-Off	2,435	SF	7	\$0	Areas of exposed concrete with attached spined panels
	Ceiling - Plaster/Drywall	1st Floor - 121 Lunchroom / Tray Drop-Off	1,345	SF	6	\$4,655	
	Ceiling - Splined	1st Floor - 121 Lunchroom / Tray Drop-Off	1,115	SF	6	\$909	
	Doors - Steel Doors incl hw	1st Floor - 121 Lunchroom / Tray Drop-Off	8	EA	6	\$2,408	
	Floor - Terrazzo	1st Floor - 121 Lunchroom / Tray Drop-Off	4,950	SF	7	\$0	
	Lighting - Lay-in	1st Floor - 121 Lunchroom / Tray Drop-Off	28	EA	7	\$0	Recessed cans
	Lighting - Pendent/Surface	1st Floor - 121 Lunchroom / Tray Drop-Off	51	EA	7	\$0	
	Storage/ Closet	1st Floor - 121 Lunchroom / Tray Drop-Off	5	SF	6	\$36	
	Student Lockers - One Tier	1st Floor - 121 Lunchroom / Tray Drop-Off	2	EA	6	\$186	
	Walls - Masonry	1st Floor - 121 Lunchroom / Tray Drop-Off	720	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor - 121 Lunchroom / Tray Drop-Off	565	SF	6	\$1,850	
	Walls - Plaster/Drywall	1st Floor - 121 Lunchroom / Tray Drop-Off	915	SF	7	\$0	Glazed curtain wall at east side
	Walls - Structural Glazed Tile	1st Floor - 121 Lunchroom / Tray Drop-Off	575	SF	7	\$0	
	Walls - Vinyl Coated Gypsum Panel	1st Floor - 121 Lunchroom / Tray Drop-Off	565	SF	6	\$1,559	Above east glazed curtain wall
	Ceiling - Lay-in	1st Floor - 121B Dishwashing Room	295	SF	6	\$886	
	Doors - Steel Doors incl hw	1st Floor - 121B Dishwashing Room	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	1st Floor - 121B Dishwashing Room	295	SF	6	\$156	
	Lighting - Lay-in	1st Floor - 121B Dishwashing Room	4	EA	7	\$0	
	Walls - Structural Glazed Tile	1st Floor - 121B Dishwashing Room	490	SF	7	\$0	
	Ceiling - Lay-in	1st Floor - 123 Servery	985	SF	6	\$2,958	
	Doors - Side-lite	1st Floor - 123 Servery	70	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor - 123 Servery	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	1st Floor - 123 Servery	4	EA	6	\$1,204	2-Double doors
	Floor - Tile/Sheet	1st Floor - 123 Servery	985	SF	6	\$986	
	Lighting - Lay-in	1st Floor - 123 Servery	16	EA	7	\$0	
	Serving Line	1st Floor - 123 Servery	48	LF	6	\$2,857	
	Storage/ Closet	1st Floor - 123 Servery	50	SF	6	\$363	Electrical closets at east side

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Lunch &amp; Multipurpose Room</b>							
	Walls - Structural Glazed Tile	1st Floor - 123 Servery	1,050	SF	7	\$0	
<b>MDF_IDF</b>							
	Doors - Wood Doors inclu hw	101 MDF Room	1	EA	6	\$301	
	Finishes	101 MDF Room	129	SF	6	\$921	
	Ventilation and Cooling	101 MDF Room	1	EA	6	\$1,855	
	Doors - Wood Doors inclu hw	110 - MDF Room	1	EA	6	\$301	
	Finishes	110 - MDF Room	297	SF	6	\$2,119	
	Ventilation and Cooling	110 - MDF Room	1	EA	6	\$1,855	
<b>Mechanical/ Service Rooms</b>							
	Interior Stairs	1st Floor	6	LF	7	\$0	Steel stairs into mech rm 237
	Interior Stairs	1st Floor	7	LF	6	\$63	Concrete stairs in loading dock area.
	Janitor's Closet	1st Floor	47	SF	6	\$337	115B Janitors closet
	Janitor's Closet	1st Floor	43	SF	6	\$308	125C janitors closet.
	Loading Docks	1st Floor	1,297	SF	6	\$9,292	
	Mechanical/ Service Rooms	1st Floor	46	SF	6	\$330	In rm 127(engineers office).
	Mechanical/ Service Rooms	1st Floor	77	SF	6	\$552	111A electrical room.
	Mechanical/ Service Rooms	1st Floor	800	SF	6	\$5,731	237 Mech rm at upper level of stage/ catwalk
	Mechanical/ Service Rooms	1st Floor	185	SF	6	\$1,325	129A Recycling.
	Mechanical/ Service Rooms	1st Floor	800	SF	6	\$5,731	236 mechanical rm at upper level of stage off of cat walk.
	Storage Room	1st Floor	177	SF	6	\$1,268	103A storage. gym balcony.
	Storage Room	1st Floor	330	SF	6	\$2,364	100F-2, 122F & 128I Storage
	Storage Room	1st Floor	100	SF	6	\$716	Rm112 storage.
	Interior Stairs	2nd Floor	2	LF	7	\$0	Stairs in rm 200H
	Janitor's Closet	2nd Floor	35	SF	6	\$251	200E
	Janitor's Closet	2nd Floor	46	SF	6	\$330	233B
	Mechanical/ Service Rooms	2nd Floor	28	SF	7	\$0	200C Area of rescue assistance.
	Mechanical/ Service Rooms	2nd Floor	12	SF	7	\$0	234A
	Mechanical/ Service Rooms	2nd Floor	40	SF	6	\$287	214B electrical rm
	Storage Room	2nd Floor	89	SF	6	\$638	200B-2(Kiln)
	Storage Room	2nd Floor	167	SF	6	\$1,196	200D-1
	Storage Room	2nd Floor	155	SF	6	\$1,110	200B-1
	Storage Room	2nd Floor	65	SF	6	\$466	200H-1
	Storage Room	2nd Floor	79	SF	6	\$566	200F-1
	Janitor's Closet	3rd Floor	45	SF	6	\$322	333B Janitor's Closet
	Storage Room	3rd Floor	23	SF	6	\$165	325A Storage / Electrical
	Storage Room	3rd Floor	15	SF	6	\$107	334A Storage / Electrical

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Mechanical/ Service Rooms</b>							
	Storage Room	3rd Floor	70	SF	6	\$502	311 Storage
	Storage Room	3rd Floor	60	SF	6	\$430	313A, 314B Storage / Electrical
	Mechanical/ Service Rooms	4th Floor	3,990	SF	6	\$28,586	4th floor mechanical penthouse
	Interior Stairs	Basement	24	LF	5	\$427	Spiral staircase on stage. Very rickety, hardware literally falling off while walking up.
	Loading Docks	Basement	1,340	SF	6	\$9,600	129 Loading Dock
	Mechanical/ Service Rooms	Basement	172	SF	6	\$1,232	007D pool mech rm.
	Mechanical/ Service Rooms	Basement	128	SF	6	\$917	003B-1
	Mechanical/ Service Rooms	Basement	613	SF	6	\$4,392	NW end of pool area
	Storage Room	Basement	157	SF	6	\$1,125	003B
	Storage Room	Basement	405	SF	6	\$2,902	130-Outside Yard Storage
	Storage Room	Basement	1,033	SF	6	\$7,401	000, 000A, 000B, 000C, 004G-1, 010 Storage
	Storage Room	Basement	199	SF	6	\$1,426	003C park district storage
<b>Pool &amp; Natatorium</b>							
	Accessories	Basement	9,244	SF	6	\$6,345	
	Bleachers Seating/Plank Seating	Basement	18	EA	6	\$521	
	Ceiling - Exposed	Basement	9,244	SF	6	\$13,748	
	Doors - Steel Doors incl hw	Basement	8	EA	6	\$2,408	
	Floor - Tile Ceramic/ Porcelain	Basement	2,011	SF	6	\$4,256	
	Lighting - Lay-in	Basement	5	EA	7	\$0	
	Lighting - Pendent/Surface	Basement	33	EA	7	\$0	
	Lighting - Wall Mounted	Basement	4	EA	7	\$0	
	Pool Basin	Basement	3,600	SF	6	\$121,802	
	Pool Deck	Basement	1,521	SF	6	\$14,442	
	Pool Deck Drains	Basement	5	EA	6	\$2,110	
	Storage/ Closet	Basement	489	SF	6	\$3,545	Pool storage rooms 007C,G,E.(Combined)
	Walls - Concrete Block	Basement	1,977	SF	7	\$0	
	Walls - Metal Panel	Basement	550	SF	6	\$4,106	
	Walls - Plaster/Drywall	Basement	3,000	SF	6	\$9,309	
	Walls - Structural Glazed Tile	Basement	4,965	SF	7	\$0	
<b>Prep Room</b>							
	Casework	325 Prep Between 323 & 327	38	LF	6	\$960	
	Ceiling - Lay-in	325 Prep Between 323 & 327	448	SF	6	\$1,345	
	Doors - Side-lite	325 Prep Between 323 & 327	8	SF	6	\$134	
	Doors - Transom Window	325 Prep Between 323 & 327	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	325 Prep Between 323 & 327	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	325 Prep Between 323 & 327	448	SF	6	\$237	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Prep Room</b>							
	Lighting - Pendent/Surface	325 Prep Between 323 & 327	4	EA	6	\$496	
	Walls - Concrete Block	325 Prep Between 323 & 327	154	SF	6	\$451	
	Walls - Plaster/Drywall	325 Prep Between 323 & 327	537	SF	6	\$1,482	
	Work Sink	325 Prep Between 323 & 327	1	EA	6	\$379	
	Casework	329 Prep Between 327 & 331	40	LF	6	\$1,010	
	Ceiling - Lay-in	329 Prep Between 327 & 331	442	SF	6	\$1,327	
	Doors - Side-lite	329 Prep Between 327 & 331	8	SF	6	\$134	
	Doors - Transom Window	329 Prep Between 327 & 331	10	SF	6	\$169	
	Doors - Wood Doors inclu hw	329 Prep Between 327 & 331	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	329 Prep Between 327 & 331	442	SF	6	\$234	
	Lighting - Pendent/Surface	329 Prep Between 327 & 331	4	EA	6	\$496	
	Walls - Concrete Block	329 Prep Between 327 & 331	153	SF	6	\$449	
	Walls - Plaster/Drywall	329 Prep Between 327 & 331	724	SF	6	\$1,998	
	Work Sink	329 Prep Between 327 & 331	1	EA	6	\$379	
<b>Restroom</b>							
	Accessories	004A - Men's Restroom	160	SF	6	\$1,476	
	Ceiling - Plaster/Drywall	004A - Men's Restroom	160	SF	6	\$554	
	Floor Drain	004A - Men's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	004A - Men's Restroom	160	SF	6	\$350	
	Hand Dryer	004A - Men's Restroom	1	EA	6	\$230	
	Lavatory	004A - Men's Restroom	2	EA	6	\$639	
	Lighting - Lay-in	004A - Men's Restroom	3	EA	6	\$357	Recessed Fixtures with Incandescent bulbs
	Partitions	004A - Men's Restroom	3	EA	6	\$891	
	Urinals	004A - Men's Restroom	2	EA	6	\$672	
	Walls - Concrete Block	004A - Men's Restroom	486	SF	6	\$1,425	
	Water Closet	004A - Men's Restroom	2	EA	6	\$672	
	Accessories	004B-Men's Restroom	480	SF	6	\$4,427	
	Ceiling - Plaster/Drywall	004B-Men's Restroom	480	SF	6	\$1,661	
	Floor Drain	004B-Men's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	004B-Men's Restroom	480	SF	6	\$1,050	
	Hand Dryer	004B-Men's Restroom	1	EA	6	\$230	
	Lavatory	004B-Men's Restroom	3	EA	6	\$959	
	Lighting - Lay-in	004B-Men's Restroom	5	EA	6	\$595	Includes three (3) recessed fixtures with incandescent bulbs
	Partitions	004B-Men's Restroom	2	EA	6	\$594	
	Urinals	004B-Men's Restroom	1	EA	6	\$336	
	Walls - Concrete Block	004B-Men's Restroom	875	SF	6	\$2,565	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Water Closet	004B-Men's Restroom	2	EA	6	\$672	
	Accessories	004C- Men's Locker Room	900	SF	6	\$8,301	
	Benches	004C- Men's Locker Room	120	LF	6	\$1,737	
	Ceiling - Plaster/Drywall	004C- Men's Locker Room	900	SF	6	\$3,115	
	Doors - Steel Doors incl hw	004C- Men's Locker Room	2	EA	6	\$602	
	Floor Drain	004C- Men's Locker Room	2	EA	6	\$2,118	
	Floor - Concrete Epoxy/ Painted	004C- Men's Locker Room	900	SF	6	\$476	
	Lighting - Lay-in	004C- Men's Locker Room	8	EA	7	\$0	
	Student Lockers - One Tier	004C- Men's Locker Room	200	EA	6	\$18,567	
	Walls - Concrete Block	004C- Men's Locker Room	1,410	SF	6	\$4,133	
	Accessories	004E-Men's Team/PE Locker Room	1,675	SF	6	\$15,449	
	Benches	004E-Men's Team/PE Locker Room	232	LF	6	\$3,357	
	Ceiling - Plaster/Drywall	004E-Men's Team/PE Locker Room	1,675	SF	6	\$5,797	
	Doors - Steel Doors incl hw	004E-Men's Team/PE Locker Room	2	EA	6	\$602	
	Floor Drain	004E-Men's Team/PE Locker Room	9	EA	6	\$9,532	
	Floor - Concrete Epoxy/ Painted	004E-Men's Team/PE Locker Room	1,500	SF	6	\$794	Epoxy Covered Concrete Floor
	Floor - Tile Ceramic/ Porcelain	004E-Men's Team/PE Locker Room	180	SF	6	\$381	
	Lighting - Lay-in	004E-Men's Team/PE Locker Room	23	EA	6	\$2,736	Includes one (1) Recessed Fixture with Incandescent bulb
	Student Lockers - One Tier	004E-Men's Team/PE Locker Room	270	EA	6	\$25,066	
	Walls - Concrete Block	004E-Men's Team/PE Locker Room	2,500	SF	6	\$7,329	
	Walls - Tile Ceramic/ Porcelain	004E-Men's Team/PE Locker Room	270	SF	6	\$610	
	Accessories	004G - 1 Coach Locker Room	162	SF	6	\$1,494	
	Benches	004G - 1 Coach Locker Room	9	LF	6	\$130	
	Ceiling - Plaster/Drywall	004G - 1 Coach Locker Room	162	SF	6	\$561	
	Doors - Wood Doors inclu hw	004G - 1 Coach Locker Room	1	EA	6	\$301	
	Floor Drain	004G - 1 Coach Locker Room	2	EA	6	\$2,118	
	Floor - Terrazzo	004G - 1 Coach Locker Room	81	SF	6	\$177	
	Floor - Tile Ceramic/ Porcelain	004G - 1 Coach Locker Room	81	SF	6	\$171	
	Lavatory	004G - 1 Coach Locker Room	1	EA	6	\$320	
	Lighting - Lay-in	004G - 1 Coach Locker Room	3	EA	6	\$357	Includes one (1) recessed fixture with incandescent bulb
	Showers	004G - 1 Coach Locker Room	1	EA	6	\$311	
	Student Lockers - One Tier	004G - 1 Coach Locker Room	8	EA	6	\$743	
	Walls - Concrete Block	004G - 1 Coach Locker Room	486	SF	6	\$1,425	
	Walls - Tile Ceramic/ Porcelain	004G - 1 Coach Locker Room	81	SF	6	\$183	
	Water Closet	004G - 1 Coach Locker Room	1	EA	6	\$336	
	Accessories	006 B- Women's Restroom	480	SF	6	\$4,427	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Ceiling - Plaster/Drywall	006 B- Women's Restroom	480	SF	6	\$1,661	
	Floor Drain	006 B- Women's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	006 B- Women's Restroom	480	SF	6	\$1,050	
	Hand Dryer	006 B- Women's Restroom	1	EA	6	\$230	
	Lavatory	006 B- Women's Restroom	3	EA	6	\$959	
	Lighting - Lay-in	006 B- Women's Restroom	5	EA	6	\$595	Includes three (3) recessed fixtures with incandescent bulbs
	Partitions	006 B- Women's Restroom	3	EA	6	\$891	
	Walls - Concrete Block	006 B- Women's Restroom	875	SF	6	\$2,565	
	Water Closet	006 B- Women's Restroom	3	EA	6	\$1,008	
	Accessories	006A - Women's Restroom	160	SF	6	\$1,476	
	Ceiling - Plaster/Drywall	006A - Women's Restroom	160	SF	6	\$554	
	Doors - Steel Doors incl hw	006A - Women's Restroom	1	EA	6	\$301	
	Floor Drain	006A - Women's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	006A - Women's Restroom	160	SF	6	\$350	
	Hand Dryer	006A - Women's Restroom	1	EA	6	\$230	
	Lavatory	006A - Women's Restroom	2	EA	6	\$639	
	Lighting - Chandelier, Incandescent	006A - Women's Restroom	3	EA	6	\$1,433	Recessed Fixtures with Incandescent bulbs
	Lighting - Lay-in	006A - Women's Restroom	1	EA	6	\$119	
	Partitions	006A - Women's Restroom	3	EA	6	\$891	
	Walls - Concrete Block	006A - Women's Restroom	486	SF	6	\$1,425	
	Water Closet	006A - Women's Restroom	3	EA	6	\$1,008	
	Accessories	006G - 1 Coach Locker Room	162	SF	6	\$1,494	
	Benches	006G - 1 Coach Locker Room	9	LF	6	\$130	
	Ceiling - Plaster/Drywall	006G - 1 Coach Locker Room	162	SF	6	\$561	
	Doors - Wood Doors inclu hw	006G - 1 Coach Locker Room	1	EA	6	\$301	
	Floor Drain	006G - 1 Coach Locker Room	2	EA	6	\$2,118	
	Floor - Terrazzo	006G - 1 Coach Locker Room	81	SF	6	\$177	
	Floor - Tile Ceramic/ Porcelain	006G - 1 Coach Locker Room	81	SF	6	\$171	
	Lavatory	006G - 1 Coach Locker Room	1	EA	6	\$320	
	Lighting - Lay-in	006G - 1 Coach Locker Room	3	EA	6	\$357	Includes one (1) recessed fixture with incandescent bulb
	Showers	006G - 1 Coach Locker Room	1	EA	6	\$311	
	Student Lockers - One Tier	006G - 1 Coach Locker Room	8	EA	6	\$743	
	Walls - Concrete Block	006G - 1 Coach Locker Room	486	SF	6	\$1,425	
	Walls - Tile Ceramic/ Porcelain	006G - 1 Coach Locker Room	81	SF	6	\$183	
	Water Closet	006G - 1 Coach Locker Room	1	EA	6	\$336	
	Accessories	007A-1 Coach's Pool Locker Room	127	SF	6	\$1,171	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Ceiling - Plaster/Drywall	007A-1 Coach's Pool Locker Room	127	SF	6	\$439	
	Doors - Steel Doors incl hw	007A-1 Coach's Pool Locker Room	1	EA	6	\$301	
	Floor Drain	007A-1 Coach's Pool Locker Room	2	EA	6	\$2,118	
	Floor - Concrete Epoxy/ Painted	007A-1 Coach's Pool Locker Room	127	SF	6	\$67	oncrete with Epoxy Covering
	Floor - Tile Ceramic/ Porcelain	007A-1 Coach's Pool Locker Room	10	SF	6	\$21	Shower floor
	Hand Dryer	007A-1 Coach's Pool Locker Room	1	EA	6	\$230	
	Lavatory	007A-1 Coach's Pool Locker Room	1	EA	6	\$320	
	Lighting - Lay-in	007A-1 Coach's Pool Locker Room	3	EA	7	\$0	
	Partitions	007A-1 Coach's Pool Locker Room	1	EA	6	\$297	
	Showers	007A-1 Coach's Pool Locker Room	1	EA	6	\$311	
	Student Lockers - One Tier	007A-1 Coach's Pool Locker Room	2	EA	6	\$186	
	Walls - Concrete Block	007A-1 Coach's Pool Locker Room	350	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	007A-1 Coach's Pool Locker Room	81	SF	6	\$183	
	Water Closet	007A-1 Coach's Pool Locker Room	1	EA	6	\$336	
	Accessories	007B - 1 Coach's Pool Locker Room	145	SF	6	\$1,337	
	Ceiling - Plaster/Drywall	007B - 1 Coach's Pool Locker Room	145	SF	6	\$502	
	Doors - Steel Doors incl hw	007B - 1 Coach's Pool Locker Room	1	EA	6	\$301	
	Floor Drain	007B - 1 Coach's Pool Locker Room	2	EA	6	\$2,118	
	Floor - Concrete Epoxy/ Painted	007B - 1 Coach's Pool Locker Room	145	SF	6	\$77	oncrete with Epoxy Covering
	Floor - Tile Ceramic/ Porcelain	007B - 1 Coach's Pool Locker Room	10	SF	6	\$21	Shower floor.
	Hand Dryer	007B - 1 Coach's Pool Locker Room	1	EA	6	\$230	
	Lavatory	007B - 1 Coach's Pool Locker Room	1	EA	6	\$320	
	Lighting - Lay-in	007B - 1 Coach's Pool Locker Room	3	EA	7	\$0	Includes one(1) recessed incandescent fixture
	Partitions	007B - 1 Coach's Pool Locker Room	1	EA	6	\$297	
	Showers	007B - 1 Coach's Pool Locker Room	1	EA	6	\$311	
	Student Lockers - One Tier	007B - 1 Coach's Pool Locker Room	2	EA	6	\$186	
	Walls - Concrete Block	007B - 1 Coach's Pool Locker Room	480	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	007B - 1 Coach's Pool Locker Room	81	SF	6	\$183	
	Water Closet	007B - 1 Coach's Pool Locker Room	1	EA	6	\$336	
	Accessories	009-Men's Restroom	200	SF	6	\$1,845	
	Ceiling - Plaster/Drywall	009-Men's Restroom	200	SF	6	\$692	
	Doors - Steel Doors incl hw	009-Men's Restroom	1	EA	6	\$301	
	Floor Drain	009-Men's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	009-Men's Restroom	200	SF	7	\$0	
	Hand Dryer	009-Men's Restroom	1	EA	6	\$230	
	Lavatory	009-Men's Restroom	3	EA	6	\$959	
	Lighting - Lay-in	009-Men's Restroom	7	EA	7	\$0	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Partitions	009-Men's Restroom	3	EA	6	\$891	
	Urinals	009-Men's Restroom	2	EA	6	\$672	
	Walls - Concrete Block	009-Men's Restroom	540	SF	7	\$0	
	Water Closet	009-Men's Restroom	2	EA	6	\$672	
	Accessories	011-Women's Restroom	200	SF	6	\$1,845	
	Ceiling - Plaster/Drywall	011-Women's Restroom	200	SF	6	\$692	
	Doors - Steel Doors incl hw	011-Women's Restroom	1	EA	6	\$301	
	Floor Drain	011-Women's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	011-Women's Restroom	200	SF	7	\$0	
	Hand Dryer	011-Women's Restroom	1	EA	6	\$230	
	Lavatory	011-Women's Restroom	3	EA	6	\$959	
	Lighting - Lay-in	011-Women's Restroom	7	EA	7	\$0	
	Partitions	011-Women's Restroom	3	EA	6	\$891	
	Walls - Concrete Block	011-Women's Restroom	540	SF	7	\$0	
	Water Closet	011-Women's Restroom	4	EA	6	\$1,344	
	Accessories	013-Women's Locker Room	900	SF	6	\$8,301	
	Benches	013-Women's Locker Room	75	LF	7	\$0	
	Ceiling - Plaster/Drywall	013-Women's Locker Room	900	SF	6	\$3,115	
	Doors - Steel Doors incl hw	013-Women's Locker Room	3	EA	6	\$903	
	Floor Drain	013-Women's Locker Room	9	EA	6	\$9,532	
	Floor - Concrete Epoxy/ Painted	013-Women's Locker Room	900	SF	6	\$476	
	Hand Dryer	013-Women's Locker Room	2	EA	6	\$460	
	Lavatory	013-Women's Locker Room	3	EA	6	\$959	
	Lighting - Lay-in	013-Women's Locker Room	11	EA	7	\$0	
	Partitions	013-Women's Locker Room	2	EA	6	\$594	
	Showers	013-Women's Locker Room	5	EA	6	\$1,557	
	Student Lockers - One Tier	013-Women's Locker Room	90	EA	6	\$8,355	
	Student Lockers - Two Tiers	013-Women's Locker Room	38	EA	6	\$1,764	
	Walls - Concrete Block	013-Women's Locker Room	2,100	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	013-Women's Locker Room	360	SF	6	\$813	
	Water Closet	013-Women's Locker Room	3	EA	6	\$1,008	
	Accessories	100 E-Women's Restroom	67	SF	6	\$618	
	Ceiling - Lay-in	100 E-Women's Restroom	67	SF	6	\$201	
	Doors - Wood Doors inclu hw	100 E-Women's Restroom	1	EA	6	\$301	
	Floor Drain	100 E-Women's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	100 E-Women's Restroom	67	SF	6	\$147	
	Hand Dryer	100 E-Women's Restroom	1	EA	6	\$230	



**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lavatory	100 E-Women's Restroom	1	EA	6	\$320	
	Lighting - Lay-in	100 E-Women's Restroom	1	EA	6	\$119	
	Walls - Concrete Block	100 E-Women's Restroom	250	SF	6	\$733	
	Water Closet	100 E-Women's Restroom	1	EA	6	\$336	
	Accessories	100D - Men's Toilet	67	SF	6	\$618	
	Ceiling - Lay-in	100D - Men's Toilet	67	SF	6	\$201	
	Doors - Wood Doors inclu hw	100D - Men's Toilet	1	EA	6	\$301	
	Floor Drain	100D - Men's Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	100D - Men's Toilet	67	SF	6	\$142	
	Hand Dryer	100D - Men's Toilet	1	EA	6	\$230	
	Lavatory	100D - Men's Toilet	1	EA	6	\$320	
	Lighting - Lay-in	100D - Men's Toilet	1	EA	6	\$119	
	Walls - Concrete Block	100D - Men's Toilet	342	SF	6	\$1,003	
	Water Closet	100D - Men's Toilet	1	EA	6	\$336	
	Accessories	114 A - Women's Restroom	830	SF	6	\$7,656	
	Ceiling - Plaster/Drywall	114 A - Women's Restroom	830	SF	6	\$2,872	
	Floor Drain	114 A - Women's Restroom	2	EA	6	\$2,118	
	Floor - Terrazzo	114 A - Women's Restroom	830	SF	7	\$0	
	Hand Dryer	114 A - Women's Restroom	5	EA	6	\$1,150	
	Lavatory	114 A - Women's Restroom	9	EA	6	\$2,876	
	Lighting - Lay-in	114 A - Women's Restroom	23	EA	7	\$0	
	Partitions	114 A - Women's Restroom	16	EA	6	\$4,751	
	Walls - Structural Glazed Tile	114 A - Women's Restroom	2,050	SF	7	\$0	
	Water Closet	114 A - Women's Restroom	17	EA	6	\$5,712	
	Accessories	114B - Staff Toilet	45	SF	6	\$415	
	Ceiling - Lay-in	114B - Staff Toilet	45	SF	6	\$135	
	Doors - Wood Doors inclu hw	114B - Staff Toilet	1	EA	6	\$301	
	Floor Drain	114B - Staff Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	114B - Staff Toilet	45	SF	6	\$98	
	Lavatory	114B - Staff Toilet	1	EA	6	\$320	
	Lighting - Lay-in	114B - Staff Toilet	1	EA	6	\$119	
	Walls - Concrete Block	114B - Staff Toilet	225	SF	6	\$660	
	Water Closet	114B - Staff Toilet	1	EA	6	\$336	
	Accessories	115 A - Men's Restroom	830	SF	6	\$7,656	
	Ceiling - Lay-in	115 A - Men's Restroom	830	SF	6	\$2,492	
	Floor Drain	115 A - Men's Restroom	2	EA	6	\$2,118	
	Floor - Terrazzo	115 A - Men's Restroom	830	SF	6	\$1,816	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Hand Dryer	115 A - Men's Restroom	5	EA	6	\$1,150	
	Lavatory	115 A - Men's Restroom	9	EA	6	\$2,876	
	Lighting - Lay-in	115 A - Men's Restroom	3	EA	6	\$357	Recessed Fixtures with Incandescent Bulbs
	Lighting - Lay-in	115 A - Men's Restroom	18	EA	6	\$2,142	
	Partitions	115 A - Men's Restroom	10	EA	6	\$2,969	
	Urinals	115 A - Men's Restroom	6	EA	6	\$2,016	
	Walls - Structural Glazed Tile	115 A - Men's Restroom	2,050	SF	6	\$6,449	
	Water Closet	115 A - Men's Restroom	10	EA	6	\$3,360	
	Accessories	120G-Unisex Restroom	67	SF	6	\$618	
	Ceiling - Lay-in	120G-Unisex Restroom	67	SF	6	\$201	
	Doors - Wood Doors inclu hw	120G-Unisex Restroom	1	EA	6	\$301	
	Floor Drain	120G-Unisex Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	120G-Unisex Restroom	67	SF	6	\$147	
	Lavatory	120G-Unisex Restroom	1	EA	6	\$320	
	Lighting - Lay-in	120G-Unisex Restroom	1	EA	6	\$119	
	Walls - Concrete Block	120G-Unisex Restroom	250	SF	6	\$733	
	Water Closet	120G-Unisex Restroom	1	EA	6	\$336	
	Accessories	122G - Staff Toilet	67	SF	6	\$618	
	Ceiling - Lay-in	122G - Staff Toilet	67	SF	6	\$201	
	Doors - Wood Doors inclu hw	122G - Staff Toilet	1	EA	6	\$301	
	Floor Drain	122G - Staff Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	122G - Staff Toilet	67	SF	6	\$147	
	Lavatory	122G - Staff Toilet	1	EA	6	\$320	
	Lighting - Lay-in	122G - Staff Toilet	1	EA	6	\$119	
	Walls - Concrete Block	122G - Staff Toilet	250	SF	6	\$733	
	Water Closet	122G - Staff Toilet	1	EA	6	\$336	
	Accessories	125A- Women's Restroom loading dock area.	67	SF	6	\$618	
	Ceiling - Lay-in	125A- Women's Restroom loading dock area.	67	SF	6	\$201	
	Doors - Steel Doors incl hw	125A- Women's Restroom loading dock area.	1	EA	6	\$301	
	Floor Drain	125A- Women's Restroom loading dock area.	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	125A- Women's Restroom loading dock area.	67	SF	7	\$0	
	Lavatory	125A- Women's Restroom loading dock area.	1	EA	6	\$320	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Lay-in	125A- Women's Restroom loading dock area.	1	EA	7	\$0	
	Walls - Concrete Block	125A- Women's Restroom loading dock area.	250	SF	7	\$0	
	Water Closet	125A- Women's Restroom loading dock area.	1	EA	6	\$336	
	Accessories	125B- men's rm at loading dock area.	45	SF	6	\$415	
	Ceiling - Lay-in	125B- men's rm at loading dock area.	45	SF	6	\$135	
	Doors - Steel Doors incl hw	125B- men's rm at loading dock area.	1	EA	6	\$301	
	Floor Drain	125B- men's rm at loading dock area.	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	125B- men's rm at loading dock area.	45	SF	6	\$95	
	Lavatory	125B- men's rm at loading dock area.	1	EA	6	\$320	
	Lighting - Lay-in	125B- men's rm at loading dock area.	1	EA	7	\$0	
	Walls - Concrete Block	125B- men's rm at loading dock area.	225	SF	7	\$0	
	Water Closet	125B- men's rm at loading dock area.	1	EA	6	\$336	
	Accessories	128 H - Unisex Restroom	125	SF	6	\$1,153	
	Ceiling - Lay-in	128 H - Unisex Restroom	125	SF	6	\$375	
	Doors - Wood Doors inclu hw	128 H - Unisex Restroom	1	EA	6	\$301	
	Floor Drain	128 H - Unisex Restroom	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	128 H - Unisex Restroom	125	SF	6	\$265	
	Lavatory	128 H - Unisex Restroom	1	EA	6	\$320	
	Lighting - Lay-in	128 H - Unisex Restroom	2	EA	6	\$238	
	Showers	128 H - Unisex Restroom	1	EA	6	\$311	
	Walls - Tile Ceramic/ Porcelain	128 H - Unisex Restroom	432	SF	6	\$976	
	Water Closet	128 H - Unisex Restroom	1	EA	6	\$336	
	Accessories	214A women's restroom south	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	214A women's restroom south	285	SF	6	\$986	
	Floor Drain	214A women's restroom south	1	EA	6	\$1,059	
	Floor - Terrazzo	214A women's restroom south	285	SF	7	\$0	
	Hand Dryer	214A women's restroom south	3	EA	6	\$690	
	Lavatory	214A women's restroom south	5	EA	6	\$1,598	
	Lighting - Lay-in	214A women's restroom south	1	EA	7	\$0	
	Lighting - Pendent/Surface	214A women's restroom south	10	EA	7	\$0	
	Partitions	214A women's restroom south	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	214A women's restroom south	723	SF	7	\$0	
	Water Closet	214A women's restroom south	6	EA	6	\$2,016	
	Accessories	214C Men's restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	214C Men's restroom	285	SF	6	\$986	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor Drain	214C Men's restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	214C Men's restroom	285	SF	7	\$0	
	Hand Dryer	214C Men's restroom	3	EA	6	\$690	
	Lavatory	214C Men's restroom	5	EA	6	\$1,598	
	Lighting - Lay-in	214C Men's restroom	1	EA	7	\$0	recessed incandescent
	Lighting - Pendent/Surface	214C Men's restroom	8	EA	7	\$0	
	Partitions	214C Men's restroom	4	EA	6	\$1,188	
	Urinals	214C Men's restroom	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	214C Men's restroom	780	SF	7	\$0	
	Water Closet	214C Men's restroom	3	EA	6	\$1,008	
	Accessories	214D unisex	45	SF	6	\$415	
	Ceiling - Lay-in	214D unisex	45	SF	6	\$135	
	Doors - Wood Doors inclu hw	214D unisex	1	EA	6	\$301	
	Floor Drain	214D unisex	1	EA	6	\$1,059	
	Floor - Terrazzo	214D unisex	45	SF	7	\$0	
	Lavatory	214D unisex	1	EA	6	\$320	
	Lighting - Lay-in	214D unisex	1	EA	7	\$0	
	Walls - Concrete Block	214D unisex	225	SF	7	\$0	
	Water Closet	214D unisex	1	EA	6	\$336	
	Accessories	233A Womens restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	233A Womens restroom	285	SF	6	\$986	
	Floor Drain	233A Womens restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	233A Womens restroom	285	SF	7	\$0	
	Hand Dryer	233A Womens restroom	3	EA	6	\$690	
	Lavatory	233A Womens restroom	5	EA	6	\$1,598	
	Lighting - Lay-in	233A Womens restroom	1	EA	7	\$0	
	Lighting - Lay-in	233A Womens restroom	10	EA	7	\$0	
	Partitions	233A Womens restroom	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	233A Womens restroom	780	SF	7	\$0	
	Water Closet	233A Womens restroom	5	EA	6	\$1,680	
	Accessories	233C men's restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	233C men's restroom	285	SF	6	\$986	
	Floor Drain	233C men's restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	233C men's restroom	285	SF	7	\$0	
	Hand Dryer	233C men's restroom	3	EA	6	\$690	
	Lavatory	233C men's restroom	5	EA	6	\$1,598	
	Lighting - Lay-in	233C men's restroom	2	EA	7	\$0	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Lay-in	233C men's restroom	8	EA	7	\$0	
	Partitions	233C men's restroom	4	EA	6	\$1,188	
	Urinals	233C men's restroom	2	EA	6	\$672	
	Walls - Structural Glazed Tile	233C men's restroom	780	SF	7	\$0	
	Water Closet	233C men's restroom	4	EA	6	\$1,344	
	Accessories	233D unisex	67	SF	6	\$618	
	Ceiling - Lay-in	233D unisex	67	SF	7	\$0	
	Doors - Wood Doors inclu hw	233D unisex	1	EA	6	\$301	
	Floor Drain	233D unisex	1	EA	6	\$1,059	
	Floor - Terrazzo	233D unisex	67	SF	7	\$0	
	Lavatory	233D unisex	1	EA	6	\$320	
	Lighting - Lay-in	233D unisex	2	EA	7	\$0	
	Walls - Concrete Block	233D unisex	250	SF	7	\$0	
	Water Closet	233D unisex	1	EA	6	\$336	
	Accessories	314A Women's Toilet	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	314A Women's Toilet	285	SF	6	\$986	
	Floor Drain	314A Women's Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	314A Women's Toilet	285	SF	6	\$624	
	Hand Dryer	314A Women's Toilet	3	EA	6	\$690	
	Lavatory	314A Women's Toilet	5	EA	6	\$1,598	
	Lighting - Lay-in	314A Women's Toilet	8	EA	6	\$952	
	Lighting - Lay-in	314A Women's Toilet	1	EA	6	\$119	recessed incandescent
	Partitions	314A Women's Toilet	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	314A Women's Toilet	780	SF	6	\$2,454	
	Water Closet	314A Women's Toilet	6	EA	6	\$2,016	
	Accessories	314C Men's Toilet	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	314C Men's Toilet	285	SF	6	\$986	
	Floor Drain	314C Men's Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	314C Men's Toilet	285	SF	6	\$624	
	Hand Dryer	314C Men's Toilet	3	EA	6	\$690	
	Lavatory	314C Men's Toilet	5	EA	6	\$1,598	
	Lighting - Lay-in	314C Men's Toilet	1	EA	6	\$119	recessed incandescent
	Lighting - Lay-in	314C Men's Toilet	8	EA	6	\$952	
	Partitions	314C Men's Toilet	3	EA	6	\$891	
	Urinals	314C Men's Toilet	3	EA	6	\$1,008	
	Walls - Structural Glazed Tile	314C Men's Toilet	780	SF	6	\$2,454	
	Water Closet	314C Men's Toilet	3	EA	6	\$1,008	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Accessories	314D Staff Toilet	45	SF	6	\$415	
	Ceiling - Lay-in	314D Staff Toilet	45	SF	6	\$135	
	Doors - Wood Doors inclu hw	314D Staff Toilet	1	EA	6	\$301	
	Floor Drain	314D Staff Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	314D Staff Toilet	45	SF	6	\$98	
	Lavatory	314D Staff Toilet	1	EA	6	\$320	
	Lighting - Lay-in	314D Staff Toilet	1	EA	6	\$119	
	Walls - Concrete Block	314D Staff Toilet	216	SF	6	\$633	
	Water Closet	314D Staff Toilet	1	EA	6	\$336	
	Accessories	333A Womens restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	333A Womens restroom	285	SF	6	\$986	
	Floor Drain	333A Womens restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	333A Womens restroom	285	SF	7	\$0	
	Hand Dryer	333A Womens restroom	3	EA	6	\$690	
	Lavatory	333A Womens restroom	5	EA	6	\$1,598	
	Lighting - Lay-in	333A Womens restroom	10	EA	7	\$0	
	Lighting - Lay-in	333A Womens restroom	1	EA	7	\$0	
	Partitions	333A Womens restroom	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	333A Womens restroom	780	SF	7	\$0	
	Water Closet	333A Womens restroom	5	EA	6	\$1,680	
	Accessories	333C Men's Restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	333C Men's Restroom	285	SF	6	\$986	
	Floor Drain	333C Men's Restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	333C Men's Restroom	285	SF	7	\$0	
	Hand Dryer	333C Men's Restroom	3	EA	6	\$690	
	Lavatory	333C Men's Restroom	4	EA	6	\$1,278	
	Lighting - Lay-in	333C Men's Restroom	8	EA	6	\$952	
	Partitions	333C Men's Restroom	4	EA	6	\$1,188	
	Urinals	333C Men's Restroom	3	EA	5	\$4,032	
	Walls - Structural Glazed Tile	333C Men's Restroom	780	SF	6	\$2,454	
	Water Closet	333C Men's Restroom	3	EA	6	\$1,008	
	Accessories	333D Staff Toilet	67	SF	6	\$618	
	Ceiling - Lay-in	333D Staff Toilet	67	SF	6	\$201	
	Doors - Wood Doors inclu hw	333D Staff Toilet	1	EA	6	\$301	
	Floor Drain	333D Staff Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	333D Staff Toilet	67	SF	6	\$147	
	Lavatory	333D Staff Toilet	1	EA	6	\$320	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Lay-in	333D Staff Toilet	2	EA	6	\$238	
	Walls - Concrete Block	333D Staff Toilet	250	SF	6	\$733	
	Water Closet	333D Staff Toilet	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal: \$2,206,867**

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Exposed	1st Floor	5,188	SF	7	\$0	
	Ceiling - Plaster/Drywall	1st Floor	2,323	SF	6	\$14,384	
	Ceiling - Plaster/Drywall	1st Floor	340	SF	7	\$0	At Main Entrance 1 vestibule
	Ceiling - Splined	1st Floor	20	SF	5	\$193	Areas in between entrance 9 and lunchroom stained
	Ceiling - Splined	1st Floor	8,300	SF	6	\$23,975	
	Doors - Side-lite	1st Floor	70	EA	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Store Front	1st Floor	9	EA	6	\$10,874	
	Doors - Transom Window	1st Floor	15	EA	7	\$0	
	Doors - Wood Doors include hw	1st Floor	3	EA	6	\$903	
	Drinking Fountains - Single Fountain	1st Floor	4	EA	6	\$1,103	
	Floor - Concrete Epoxy/ Painted	1st Floor	535	SF	7	\$0	
	Floor - Terrazzo	1st Floor	9,870	SF	7	\$0	
	Floor - Terrazzo	1st Floor	30	SF	5	\$1,570	At Main Entrance 1 vestibule - Section loose and not stable
	Floor - Terrazzo	1st Floor	700	SF	6	\$8,148	At entrances 1, 9 vestibules
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	6-floor lights at main entrance 1 vestibule
	Lighting - Pendent/Surface	1st Floor	173	EA	7	\$0	
	Lighting - Wall Mounted	1st Floor	11	EA	7	\$0	
	Walls - Concrete Block	1st Floor	2,055	SF	7	\$0	
	Walls - Masonry	1st Floor	3,935	SF	7	\$0	
	Walls - Metal Panel	1st Floor	1,280	SF	7	\$0	
	Walls - Plaster/Drywall	1st Floor	635	SF	6	\$3,342	
	Walls - Plaster/Drywall	1st Floor	2,230	SF	7	\$0	At entrance 1,9 vestibules / Pool balcony south wall
	Walls - Plaster/Drywall	1st Floor	760	SF	6	\$3,999	
	Walls - Structural Glazed Tile	1st Floor	6,810	SF	7	\$0	

**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Walls - Tile Ceramic/ Porcelain	1st Floor	1,122	SF	7	\$0	At Main Entrance 1 vestibule
	Ceiling - Exposed	2nd Floor	12,580	SF	6	\$18,709	ncludes portions of glued on ACT
	Drinking Fountains - Single Fountain	2nd Floor	6	EA	6	\$1,654	
	Floor - Terrazzo	2nd Floor	12,580	SF	6	\$105,598	
	Lighting - Lay-in	2nd Floor	40	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	128	EA	7	\$0	
	Lighting - Wall Mounted	2nd Floor	40	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	595	EA	6	\$55,237	
	Walls - Masonry	2nd Floor	1,925	SF	6	\$6,056	Masonry
	Walls - Plaster/Drywall	2nd Floor	3,700	SF	6	\$16,402	
	Walls - Structural Glazed Tile	2nd Floor	6,344	SF	6	\$19,958	
	Ceiling - Exposed	3rd Floor	3,280	SF	6	\$4,878	Includes portions of glued on ACT
	Ceiling - Plaster/Drywall	3rd Floor	6,735	SF	6	\$41,702	
	Doors - Wood Doors include hw	3rd Floor	1	EA	6	\$301	At stair up to 4th floor mechanical penthouse
	Drinking Fountains - Single Water Cooler	3rd Floor	4	EA	6	\$1,267	
	Floor - Concrete	3rd Floor	45	SF	7	\$0	
	Floor - Terrazzo	3rd Floor	10,015	SF	6	\$84,067	
	Lighting - Chandelier, Incandescent	3rd Floor	3	EA	6	\$1,433	
	Lighting - Pendent/Surface	3rd Floor	22	EA	6	\$2,726	
	Lighting - Wall Mounted	3rd Floor	80	EA	7	\$0	At bottom of stairs up to 4th floor mechanical penthouse
	Student Lockers - One Tier	3rd Floor	595	EA	6	\$55,237	
	Walls - Masonry	3rd Floor	650	SF	6	\$2,045	Masonry
	Walls - Metal Panel	3rd Floor	980	SF	6	\$7,315	Glass
	Walls - Plaster/Drywall	3rd Floor	3,700	SF	6	\$16,402	
	Walls - Structural Glazed Tile	3rd Floor	3,672	SF	6	\$11,552	
	Ceiling - Exposed	Basement	170	SF	7	\$0	At stair L bottom landing
	Ceiling - Plaster/Drywall	Basement	460	SF	6	\$2,848	
	Doors - Steel Doors incl hw	Basement	2	EA	6	\$602	
	Drinking Fountains - Double Fountain	Basement	2	EA	6	\$672	In pool area
	Drinking Fountains - Single Fountain	Basement	4	EA	6	\$1,103	
	Floor - Concrete Epoxy/ Painted	Basement	145	SF	7	\$0	
	Floor - Terrazzo	Basement	365	SF	7	\$0	
	Floor - Terrazzo	Basement	30	SF	6	\$349	At entrance 8
	Lighting - Lay-in	Basement	3	EA	7	\$0	
	Lighting - Pendent/Surface	Basement	20	EA	6	\$2,478	
	Lighting - Wall Mounted	Basement	6	EA	7	\$0	At stairs G, L bottom landings
	Walls - Concrete Block	Basement	685	SF	7	\$0	



**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Walls - Masonry	Basement	100	SF	7	\$0	At stair L bottom landing around pool steel doors
	Walls - Structural Glazed Tile	Basement	1,452	SF	7	\$0	
<b>Safety</b>							
	Camera Viewing Station	Entire Building / 1st Floor	4	EA	6	\$2,730	Main Entrance, Principals office, MDF
	Metal Dedector	Entire Building / 1st Floor	3	EA	6	\$2,642	2-main entrance 1 / 1-entrance 9
	Security Cameras	Entire Building	14	EA	6	\$2,717	
	Security Cameras	Entire Building	85	EA	6	\$16,493	
<b>Stairs</b>							
	Ceiling - Exposed	4th floor mechanical penthouse	255	SF	6	\$379	
	Floor - Concrete	4th floor mechanical penthouse	100	SF	7	\$0	
	Handrails	4th floor mechanical penthouse	65	LF	6	\$563	
	Lighting - Pendant/Surface	4th floor mechanical penthouse	1	EA	6	\$124	Above top landing - not working properly
	Lighting - Wall Mounted	4th floor mechanical penthouse	2	EA	7	\$0	
	Stairs - Concrete	4th floor mechanical penthouse	26	LF	7	\$0	
	Walls - Concrete Block	4th floor mechanical penthouse	1,400	SF	7	\$0	
	Walls - Plaster/Drywall	4th floor mechanical penthouse	225	SF	6	\$621	Unfinished drywall
	Ceiling - Plaster/Drywall	Stair A-NW	205	SF	6	\$1,501	
	Floor - Terrazzo	Stair A-NW	1,488	SF	6	\$12,490	
	Floor - Terrazzo	Stair A-NW	768	SF	6	\$7,622	Landing
	Handrails	Stair A-NW	270	LF	6	\$2,340	
	Lighting - Chandelier, Incandescent	Stair A-NW	15	EA	6	\$7,163	
	Stairs - Terrazzo	Stair A-NW	90	LF	6	\$835	
	Walls - Structural Glazed Tile	Stair A-NW	1,235	SF	6	\$3,885	
	Ceiling - Plaster/Drywall	Stair B	280	SF	6	\$2,050	
	Floor - Terrazzo	Stair B	220	SF	6	\$2,183	Stair Landing
	Floor - Terrazzo	Stair B	480	SF	6	\$4,029	
	Handrails	Stair B	120	LF	6	\$1,040	
	Lighting - Wall Mounted	Stair B	4	EA	6	\$496	
	Stairs - Terrazzo	Stair B	60	LF	6	\$557	
	Walls - Structural Glazed Tile	Stair B	840	SF	6	\$2,643	
	Ceiling - Plaster/Drywall	Stair C	325	SF	6	\$2,380	
	Floor - Terrazzo	Stair C	236	SF	6	\$2,342	Landing
	Floor - Terrazzo	Stair C	850	SF	6	\$7,135	
	Handrails	Stair C	140	LF	6	\$1,213	
	Lighting - Wall Mounted	Stair C	12	EA	6	\$1,487	
	Stairs - Terrazzo	Stair C	70	LF	6	\$650	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Walls - Structural Glazed Tile	Stair C	840	SF	6	\$2,643	
	Ceiling - Exposed	Stair D 1st. Floor to Basement	157	SF	6	\$233	
	Floor - Concrete	Stair D 1st. Floor to Basement	544	SF	6	\$288	
	Handrails	Stair D 1st. Floor to Basement	60	LF	6	\$520	
	Lighting - Wall Mounted	Stair D 1st. Floor to Basement	4	EA	6	\$496	
	Stairs - Concrete	Stair D 1st. Floor to Basement	30	LF	6	\$249	
	Walls - Concrete Block	Stair D 1st. Floor to Basement	120	SF	6	\$352	
	Walls - Masonry	Stair D 1st. Floor to Basement	160	SF	6	\$503	
	Ceiling - Exposed	Stair D 1st. To 2nd.	70	SF	6	\$104	
	Ceiling - Lay-in	Stair D 1st. To 2nd.	143	SF	6	\$429	
	Floor - Terrazzo	Stair D 1st. To 2nd.	205	SF	6	\$2,034	Landing
	Floor - Terrazzo	Stair D 1st. To 2nd.	415	SF	6	\$3,484	
	Handrails	Stair D 1st. To 2nd.	60	LF	6	\$520	
	Lighting - Wall Mounted	Stair D 1st. To 2nd.	8	EA	6	\$991	
	Stairs - Terrazzo	Stair D 1st. To 2nd.	30	LF	6	\$278	
	Walls - Concrete Block	Stair D 1st. To 2nd.	270	SF	6	\$792	
	Walls - Structural Glazed Tile	Stair D 1st. To 2nd.	360	SF	6	\$1,133	
	Ceiling - Exposed	Stair E 1st Floor to 2nd. Floor	70	SF	6	\$104	
	Ceiling - Lay-in	Stair E 1st Floor to 2nd. Floor	143	SF	6	\$429	
	Floor - Terrazzo	Stair E 1st Floor to 2nd. Floor	30	SF	6	\$349	Landing
	Floor - Terrazzo	Stair E 1st Floor to 2nd. Floor	415	SF	6	\$3,484	
	Handrails	Stair E 1st Floor to 2nd. Floor	60	LF	6	\$520	
	Lighting - Pendent/Surface	Stair E 1st Floor to 2nd. Floor	4	EA	6	\$496	
	Lighting - Wall Mounted	Stair E 1st Floor to 2nd. Floor	2	EA	6	\$248	
	Stairs - Terrazzo	Stair E 1st Floor to 2nd. Floor	30	LF	6	\$278	
	Walls - Concrete Block	Stair E 1st Floor to 2nd. Floor	240	SF	6	\$704	
	Walls - Structural Glazed Tile	Stair E 1st Floor to 2nd. Floor	240	SF	6	\$755	
	Ceiling - Exposed	Stair E 1st. Floor to Basement	70	SF	6	\$104	
	Ceiling - Lay-in	Stair E 1st. Floor to Basement	140	SF	6	\$420	
	Floor - Concrete	Stair E 1st. Floor to Basement	420	SF	6	\$222	
	Floor - Concrete	Stair E 1st. Floor to Basement	205	SF	6	\$126	Landing
	Handrails	Stair E 1st. Floor to Basement	60	LF	6	\$520	
	Lighting - Wall Mounted	Stair E 1st. Floor to Basement	4	EA	6	\$496	
	Stairs - Concrete	Stair E 1st. Floor to Basement	30	LF	6	\$249	
	Walls - Concrete Block	Stair E 1st. Floor to Basement	120	SF	6	\$352	
	Walls - Masonry	Stair E 1st. Floor to Basement	160	SF	6	\$503	
	Ceiling - Exposed	Stair F-SE - Entrance 2	205	SF	7	\$0	Above stairs

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Ceiling - Plaster/Drywall	Stair F-SE - Entrance 2	110	SF	6	\$805	
	Ceiling - Plaster/Drywall	Stair F-SE - Entrance 2	5	SF	5	\$102	Hole above stair landing with staining, peeling around area
	Floor - Concrete Epoxy/ Painted	Stair F-SE - Entrance 2	115	SF	6	\$56	
	Handrails	Stair F-SE - Entrance 2	60	LF	6	\$520	
	Lighting - Wall Mounted	Stair F-SE - Entrance 2	2	EA	7	\$0	
	Stairs - Concrete	Stair F-SE - Entrance 2	28	LF	7	\$0	
	Walls - Concrete Block	Stair F-SE - Entrance 2	1,010	SF	7	\$0	
	Walls - Plaster/Drywall	Stair F-SE - Entrance 2	160	SF	6	\$442	
	Ceiling - Exposed	Stair G - SW of gym / West of stage	90	SF	6	\$134	
	Ceiling - Plaster/Drywall	Stair G - SW of gym / West of stage	275	SF	6	\$2,013	
	Floor - Concrete Epoxy/ Painted	Stair G - SW of gym / West of stage	190	SF	7	\$0	
	Handrails	Stair G - SW of gym / West of stage	55	LF	6	\$477	
	Lighting - Lay-in	Stair G - SW of gym / West of stage	1	EA	7	\$0	At top landing
	Lighting - Wall Mounted	Stair G - SW of gym / West of stage	5	EA	7	\$0	
	Stairs - Concrete	Stair G - SW of gym / West of stage	25	LF	7	\$0	
	Walls - Concrete Block	Stair G - SW of gym / West of stage	2,240	SF	7	\$0	
	Handrails	Stair K at Entrance 5-W	27	LF	7	\$0	
	Lighting - Wall Mounted	Stair K at Entrance 5-W	2	EA	7	\$0	
	Stairs - Concrete	Stair K at Entrance 5-W	9	LF	7	\$0	
	Ceiling - Plaster/Drywall	Stair L- W of pool	290	SF	6	\$2,123	
	Floor - Concrete Epoxy/ Painted	Stair L- W of pool	170	SF	7	\$0	
	Handrails	Stair L- W of pool	55	LF	7	\$0	
	Lighting - Wall Mounted	Stair L- W of pool	6	EA	7	\$0	
	Stairs - Concrete	Stair L- W of pool	22	LF	7	\$0	
	Walls - Concrete Block	Stair L- W of pool	1,000	SF	7	\$0	
<b>Vertical Conveyance</b>							
	Elevator - Hydraulic Elevator	Basement	1	EA	6	\$19,238	Basement to first floor and practice field level only.
	Wheelchair Lift - Platform Lift	Basement	1	EA	6	\$6,690	S/W corner of Gym.
	Elevator - Hydraulic Elevator	Main Entrance	1	EA	6	\$19,238	

**Building Interior Subtotal: \$697,240**

**Total Building Cost \$4,629,366**

**SITE**

## Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Athletic</b>							
	Lighting	West	4	EA	6	\$14,417	
	Metal Bleachers	North	50	LF	6	\$2,231	At south side
	Metal Bleachers	West	780	LF	7	\$0	
	Surface - Asphalt	North	26,910	SF	7	\$0	
	Surface - Asphalt	North	300	SF	5	\$1,772	Several areas worn out, cracking, bulging with gaps throughout
	Surface - Concrete	NW	60	SF	6	\$0	Shot putt pad - north of football field
	Surface - Concrete	NW	985	SF	6	\$0	Long jump running surface
	Surface - Natural	NW	165	SF	6	\$137	Long jump sand pit
	Surface - Synthetic including exc & retention	West	74,250	SF	7	\$0	
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site	18	EA	6	\$19,689	
	Civil/ Drainage - Site Drain	Entire Site	8	EA	6	\$2,482	
	Civil/ Drainage - Site Manhole	Entire Site	8	EA	6	\$11,942	
<b>Fencing</b>							
	Fencing - Chain Link	Entire Site	1,820	LF	7	\$0	
	Fencing - New Standard Ornamental	Entire Site	945	LF	7	\$0	
<b>Landscape</b>							
	Benches	Entire Site	5	EA	6	\$2,150	At tennis court
	Landscape - Grass	Entire Site	147,985	SF	6	\$122,739	
	Landscape - Hardscape- Concrete	Entire Site	16,765	SF	7	\$0	
	Landscape - Hardscape- Pavers	Entire Site	30,210	SF	7	\$0	
	Lighting - Pole Mounted	Entire Site	7	EA	6	\$7,586	Recessed site lighting at flag poles and throughout
	Lighting - Pole Mounted	Entire Site	12	EA	6	\$13,005	
	Lighting - Pole Mounted	Entire Site	2	EA	5	\$4,070	Recessed site lighting at flag poles - Not working properly
	Parkway trees	Entire Site	40	EA	6	\$26,402	
	Planting Beds/ Area	Entire Site	27,685	SF	6	\$45,528	
	Retaining Wall - Concrete	Entire Site	1,750	SF	7	\$0	At west elevation basement entrance 4
	Retaining Wall - Masonry	Entire Site	4,450	SF	7	\$0	At NE elevation around planting, garden area
	Retaining Wall - Masonry	Entire Site	160	SF	7	\$0	Granite slabs at south ramp / planters
	Trash Receptacles	Entire Site	12	EA	6	\$3,748	
	Walking Path - Crushed Stone	Entire Site	6,715	SF	6	\$14,212	Underneath E,W 1st floor cantilevers / North side of parking at bike racks / Underneath metal bleachers at football field
<b>Parking Lot</b>							
	Concrete Curbs	West	1,535	LF	7	\$0	

**SITE**

**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Parking Lot</b>							
	Concrete Curbs	West	1,255	LF	7	\$0	At paver, concrete driveway around tennis court on north side of property
	Interior Plantings	West	210	LF	6	\$8,934	
	Lighting - Pole Mounted	West	8	EA	6	\$11,620	
	Surface - Asphalt	West	36,985	SF	7	\$0	
	Trash Compactor	West	1	EA	6	\$0	Inside service garage
<b>Sidewalks</b>							
	Sidewalks - Internal Walks	Entire Site	2,560	LF	7	\$0	Concrete
	Sidewalks - Internal Walks	Entire Site	30	LF	7	\$0	Pavers
	Sidewalks - Perimeter Sidewalks	Entire Site	13,300	SF	7	\$0	
<b>Signage</b>							
	Flag Pole - Flag Pole	Entire Site	3	EA	6	\$4,971	
	Monument - Sign	Entire Site	1	EA	6	\$0	Location: SW corner of building at planter retaining wall

**Site Subtotal:** **\$317,632**

**Total Site Cost** **\$317,632**

**Campus Total <sup>2 3</sup>** **\$4,946,998**

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

**Definitions**

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").

- 
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Art Room	2nd Floor	200B	200B	1,220	1	8	28	520	0	40	N	N	N
Art Room	Art Room	2nd Floor	200D	200D	1,220	1	8	28	520	0	40	N	N	N
Choral Room	Choral Room	2nd Floor	200H	200H	1,755	1	4	24	85	0	40	N	N	N
Computer Lab	Computer Lab	1st Floor	100 - C	100 - C	1,270	1	1	4	120	0	40	N	N	N
Computer Lab	Computer Lab	1st Floor	117	117	770	1	2	8	0	0	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	221	221	1,350	2	36	80	102	12	40	N	Y	N
Computer Lab	Computer Lab	2nd Floor	222	222	1,260	1	38	80	115	4	40	N	N	N
Computer Lab	Computer Lab	3rd Floor	322	322	1,260	1	38	80	115	4	40	N	N	N
Language Lab	Language Lab	1st Floor	180 B	180 B	630	1	7	12	169	0	40	N	N	N
Language Lab	Language Lab	1st Floor	180A	180A	719	1	7	12	96	0	40	N	N	N
Regular Classroom	Store Room	Basement	010	010	1,410	1	1	4	0	0	40	N	N	N
Regular Classroom	Other Instructional Use	1st Floor	126	126	702	2	4	18	48	0	40	N	N	N
Regular Classroom	Choral Room	2nd Floor	200F	200F	1,255	1	4	30	380	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	215	215	800	2	9	26	84	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	216	216	859	2	8	26	28	0	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	217	217	800	2	9	26	76	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	218	218	800	2	9	26	91	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	219	219	800	2	9	26	86	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	220	220	800	2	9	26	93	4	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	224	224	800	2	9	26	86	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	226	226	800	2	9	26	86	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	228	228	800	2	9	26	75	8	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	230	230	800	2	9	26	85	6	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	232	232	800	2	9	26	85	6	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	234	234	800	2	9	26	98	6	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	235	235	800	2	9	26	98	8	40	N	Y	N
Regular Classroom	Office	3rd Floor	301	301	862	1	6	14	267	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	315	800	2	9	26	71	4	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	316	316	800	2	9	26	71	4	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	317	317	800	2	9	26	71	4	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	318	318	800	2	9	26	77	4	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	319	319	800	2	9	26	95	4	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	320	320	800	2	9	26	75	4	40	N	Y	N
Regular Classroom	Computer Lab	3rd Floor	321	321	1,350	1	4	20	104	8	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	321A	321A	435	1	9	22	50	8	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	324	324	800	2	9	26	77	7	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	326	326	800	2	9	26	78	6	40	N	Y	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Regular Classroom	Regular Classroom	3rd Floor	328	328	800	2	9	26	78	6	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	330	330	800	2	9	26	78	6	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	332	332	800	2	9	26	78	6	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	334	334	800	2	9	26	98	6	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	335	335	800	2	9	26	98	6	40	N	Y	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	231	231	1,240	2	10	44	98	0	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	2nd Floor	223	223	1,240	2	10	44	98	0	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	2nd Floor	227	227	1,240	2	10	44	98	0	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	323	323	1,240	2	10	44	98	0	40	N	N	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	327	327	1,240	2	10	44	98	0	40	N	N	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	331	331	1,240	2	10	44	98	0	40	N	N	N
Special Education	Regular Classroom	2nd Floor	212	212	690	2	8	26	0	0	40	N	N	N
Special Education	Regular Classroom	3rd Floor	312	312	690	2	7	24	35	4	40	N	N	N