1955 E 75th St Chicago, IL 60649

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	2011	3	213,710	\$4,806,450
SITE				\$168,832
Campus Total			213,710	\$4,975,282

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entran		Location	Qualitity	Oill	IVALIK	Cost	Comments
Entran							
	Entrance Control - Audio and Video	Entrance 4-West / Basement	1	EA	6	\$702	
	Entrance Control - Audio and Video	Entrance 6-West / Elevator vestibule	1	EΑ	6	\$702	
	Entrance Control - Audio and Video	Entrance 9-East	2	EA	6	\$1,403	
	Entrance Control - Audio and Video	Main Entrance 1-North	2	EA	6	\$1,403	
	Exterior Doors - Exterior Steel Door	Entrance 11-North	2	EΑ	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 2-North	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 3-NW	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 5-West	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	Entrance 7-West	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	Entrance 8A-South / Outside Yard Storage	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Entrance 8-South	3	EA	6	\$1,442	
	Exterior Doors - Side lite	Entrance 10-East / Library	2	EΑ	6	\$627	
	Exterior Doors - Side lite	Entrance 6-West / Elevator vestibule	8	EΑ	6	\$2,507	
	Exterior Doors - Side lite	Entrance 8A-South / Outside Yard Storage	1	EA	6	\$313	Metal panel
	Exterior Doors - Side lite	Entrance 9-East	9	EA	6	\$2,820	
	Exterior Doors - Side lite	Main Entrance 1-North	8	EΑ	6	\$2,507	
	Exterior Doors - Store Front	Entrance 10-East / Library	3	EΑ	6	\$1,638	
	Exterior Doors - Store Front	Entrance 4-West / Basement	4	EΑ	6	\$2,184	
	Exterior Doors - Store Front	Entrance 6-West / Elevator vestibule	1	EA	6	\$546	



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrand	ce						
	Exterior Doors - Store Front	Entrance 9-East	5	EA	6	\$2,730	
	Exterior Doors - Store Front	Main Entrance 1-North	6	EA	6	\$3,276	
	Exterior Doors - Transom Lite	Entrance 10-East / Library	3	EA	6	\$940	
	Exterior Doors - Transom Lite	Entrance 6-West / Elevator vestibule	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Entrance 9-East	14	EA	6	\$4,386	
	Exterior Doors - Transom Lite	Main Entrance 1-North	9	EA	6	\$2,820	
	Exterior Stairs - Concrete	Entrance 4-West / Basement	275	LF	6	\$22,486	
	Exterior Stairs - Concrete	Main Entrance 1-North	1,830	LF	6	\$149,634	
	Power Door Operator and Controls	Entrance 10-East / Library	1	EA	6	\$0	
	Power Door Operator and Controls	Entrance 6-West / Elevator vestibule	1	EA	6	\$0	
	Power Door Operator and Controls	Entrance 9-East	1	EA	6	\$0	
	Ramp Handrail - Steel_Ramp Handrail	Entrance 9-East	260	LF	6	\$2,253	Sloped walkway
	Ramp Handrail - Steel_Ramp Handrail	Main Entrance 1-North	120	LF	6	\$1,040	
	Ramps - Concrete	Main Entrance 1-North	60	LF	6	\$9,014	
	Stair Handrail - Steel_Stair Handrail	Entrance 4-West / Basement	110	LF	6	\$953	
	Stair Handrail - Steel_Stair Handrail	Main Entrance 1-North	200	LF	6	\$1,733	
Founda	ation						
	Foundation - Concrete	Entire Building	1,776	LF	7	\$0	
	Superstructure - Concrete	Entire Building	213,710	SF	7	\$0	
Lighting	g						
	Exterior Lighting - Wall Mounted	Entire Building	49	EA	6	\$14,149	
	Exterior Lighting - Wall Mounted	Entire Building	14	EA	6	\$4,042	
	Exterior Lighting - Wall Mounted	Entire Building	78	EA	6	\$22,522	Concrete steps
Roof Sy	ystem						
	Chimney - Metal Flue	Roof 1	55	LF	6	\$8,698	
	Chimney - Metal Flue	Roof 3	180	LF	6	\$28,466	3-boiler / 3-H.W.H
	Coping - Metal	Roof 1	1,165	LF	6	\$37,417	
	Coping - Metal	Roof 2	560	LF	6	\$17,986	
	Coping - Metal	Roof 3	265	LF	6	\$8,511	
	Coping - Metal	Roof 4 - Outside Chiller	125	LF	6	\$4,015	
	Coping - Metal	Roof 5 - E,W cantilevers	335	LF	6	\$10,759	
	Coping - Metal	Roof 6	260	LF	6	\$8,351	
	Coping - Metal	Roof 7	760	LF	6	\$24,410	
	Downspouts - Interior Downspouts	Roof 1	1,550	LF	6	\$51,511	
	Downspouts - Interior Downspouts	Roof 2	580	LF	6	\$19,275	
	Downspouts - Interior Downspouts	Roof 3	240	LF	6	\$7,976	

1955 E 75th St Chicago, IL 60649

Building: Main

Category: Building Exterior

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof Sy			•				
	Downspouts - Interior Downspouts	Roof 4 - Outside Chiller	100	LF	6	\$3,323	
	Downspouts - Interior Downspouts	Roof 5 - E,W cantilevers	300	LF	6	\$9,970	
	Downspouts - Interior Downspouts	Roof 6	200	LF	6	\$6,647	
	Downspouts - Interior Downspouts	Roof 7	525	LF	6	\$17,447	
	Parapet - 16" - 30" Height	Roof 7	325	LF	6	\$12,985	
	Parapet - Parapet < 16" Height	Roof 1	1,165	LF	6	\$24,823	
	Parapet - Parapet < 16" Height	Roof 2	560	LF	6	\$11,932	
	Parapet - Parapet < 16" Height	Roof 3	265	LF	6	\$5,646	
	Parapet - Parapet < 16" Height	Roof 4 - Outside Chiller	125	LF	6	\$2,663	
	Parapet - Parapet < 16" Height	Roof 5 - E,W cantilevers	335	LF	6	\$7,138	
	Parapet - Parapet > 30"	Roof 6	260	LF	6	\$16,619	
	Parapet - Parapet > 30"	Roof 7	435	LF	6	\$27,806	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 1	26,765	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 2	5,550	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 3	4,340	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 4 - Outside Chiller	1,800	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 5 - E,W cantilevers	2,950	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 6	10,000	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Roof 7	31,800	SF	7	\$0	
	Roof - Modified Bitumen	Roof 1	26,765	SF	6	\$251,843	
	Roof - Modified Bitumen	Roof 2	5,550	SF	6	\$52,222	
	Roof - Modified Bitumen	Roof 3	4,340	SF	6	\$40,837	
	Roof - Modified Bitumen	Roof 4 - Outside Chiller	1,880	SF	6	\$17,690	
	Roof - Modified Bitumen	Roof 5 - E,W cantilevers	2,950	SF	6	\$27,758	
	Roof - Modified Bitumen	Roof 6	8,500	SF	6	\$79,980	Vegetation areas
	Roof - Modified Bitumen	Roof 6	1,500	SF	6	\$20,699	
	Roof - Modified Bitumen	Roof 7	3,180	SF	6	\$43,882	
	Roof - Modified Bitumen	Roof 7	28,620	SF	6	\$269,297	Vegetation areas
Walls							
	Canopy - Concrete/ Stucco	Entire Building	300	SF	6	\$9,927	
	Canopy - Metal	Entire Building	3,030	SF	6	\$65,080	
	Exterior Walls - Brick	Entire Building	47,115	SF	7	\$0	
	Exterior Walls - Concrete Block	Entire Building	3,150	SF	6	\$21,171	
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	11,205	SF	7	\$0	
	Exterior Walls - Stone-Cut	Entire Building	130	SF	6	\$874	Granite slab



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Building Exterior

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Windov	/s						
	Clerestory - Glass Double-Pane	Entire Building	1,710	SF	6	\$16,017	
	Curtain wall - Glazed Double Pane	Entire Building	10,930	SF	6	\$122,538	
	Curtain wall - Windows	Entire Building	5,775	SF	6	\$64,745	
	Guard - Guards perforated	Entire Building / 1st Floor	1,815	SF	6	\$23,177	
	Lintels - Steel	Entire Building	1,030	LF	7	\$0	
	Windows - Louver	Entire Building	165	SF	6	\$1,232	

Building Exterior Subtotal:

\$1,770,677

Building: Main

Category: Electrical System

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	ency System	Location	Qualitity	Offic	INGIIN	0031	Commonto
Linery	Automatic Transfer Switch	Electrical Room	4	EA	6	\$1,632	
			•		0		
	Emergency A/C Power - Corridors and Stairs	Basement, 1st floor, Entire Building / Entire Building	46,450	SF	7	\$0	
	Emergency A/C Power - Gym	Basement, 1st floor, Entire Building / 1st Floor	12,000	SF	7	\$0	
	Emergency A/C Power - Lunchrooms	Basement, 1st floor, Entire Building / 1st Floor	5,610	SF	7	\$0	
	Emergency A/C Power - Pool	Basement, 1st floor, Entire Building / Basement	6,690	SF	7	\$0	
	Emergency A/C Power - Students Toilets	Basement, 1st floor, Entire Building / Entire Building	3,890	SF	7	\$0	
	Emergency Generator- Indoor- Natural Gas - Above 250 KW	Mechanical Room	1	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	63	EA	7	\$0	
	Exit Signs - Gym	Entire Building / 1st Floor	5	EA	7	\$0	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	3	EA	7	\$0	
	Exit Signs - Pool	Entire Building / Basement	7	EA	7	\$0	
	Security System - CCTV	Entire Building	213,710	SF	7	\$0	
	Security System - Intrusion Detection	Entire Building	213,710	SF	7	\$0	
Main S	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	An extra feed from ComEd
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	2	EA	7	\$0	
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	7	\$0	
	PA System	Entire Building / 1st Floor	213,710	SF	6	\$70,289	



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power	Distribution						
	Lighting and Power Panels - 100 A	Electrical Room	26	EA	7	\$0	
	Lighting and Power Panels - 100 A	Electrical Room	6	EA	7	\$0	Emergency lights
	Lighting and Power Panels - 100 A	Electrical Room	1	EA	7	\$0	Serves Snow Melt panel
	Lighting and Power Panels - 100 A	Electrical Room	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	14	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	1	EA	7	\$0	Emergency Panel
	Lighting and Power Panels - Above 100 A	Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	2	EA	7	\$0	Emergency Panel
	Main Distribution Panels - 400 - 600 amp	Electrical Room	3	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	2	EA	7	\$0	Emergency Distribution
	Transformers - 277/480 - 120/208	Electrical Room	2	EA	6	\$2,530	Emergency Transformer
	Transformers - 277/480 - 120/208	Electrical Room	2	EA	6	\$2,530	
	Transformers - 277/480 - 120/208	Electrical Room	3	EA	6	\$3,795	
	Transformers - 277/480 - 120/208	Electrical Room	1	EA	6	\$1,265	
Flerin	inal Contama Collegatale					COO 044	

Electrical System Subtotal:

\$82,041

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Ala	arm						
	Fire Alarm Panel	Main Entrance	1	EA	7	\$0	
	Fire Alarm Strobe Lights	Main Entrance / Entire Building	213,710	SF	7	\$0	
	Fire Alarm_System	Main Entrance / Entire Building	213,710	SF	6	\$103,906	
	Fire Pump Controller	Main Entrance / Entire Building	1	EA	7	\$0	
Pump I	Room Assembly						
	Fire Pump - 25-50 hp	Mechanical Room	1	EA	7	\$0	
	Jockey Pump	Mechanical Room	1	EA	7	\$0	
Sprink	ler System						
	Dry Sprinkler System	Entire Building	1,000	SF	7	\$0	Dry System only serves the Dock area



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Safty System

roup Item - Type	Location	Quantity Unit Rank	Cost Comments
prinkler System			
Sprinkler Heads	Entire Building	213,710 SF 7	\$0
Sprinkler Piping	Entire Building	213,710 SF 7	\$0
Wet Sprinkler System	Entire Building	213,710 SF 7	\$0

Safty System Subtotal: \$103,906

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Con	ditioning						
	Chemical Pot Feeder	Roof / Mechanical Room	1	EA	7	\$0	
	Chiller-Air Cooled-Screw Type-Roof Mounted - Greater than 400 tons	Roof	1	EA	6	\$4,969	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	3	EA	6	\$10,001	
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	1	EA	6	\$3,334	
	Pipes - Chilled Water Pipe- Galvanized	Roof / Entire Building	500	LF	6	\$944	
	Pressure Fill System	Roof / Mechanical Room	1	EA	6	\$1,405	
Air Han	dling Systems						
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	Mechanical Room	1	EA	7	\$0	Serves Gym
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 8001-12000 cfm	Mechanical Room	1	EA	7	\$0	Serves Stage
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	7	\$0	serves floors 1,2,3 east
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	7	\$0	Serves pool
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	7	\$0	serves floor 1,2,3, central area
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	Mechanical Room	1	EA	7	\$0	serve floors 1,2,3, west
	Air Intake	Mechanical Room / Façade- SE	1	EA	7	\$0	
	Air Intake	Mechanical Room / Façade- SE	1	EA	7	\$0	
	Air Intake	Mechanical Room / Façade- SW	1	EA	7	\$0	
	Air Intake	Mechanical Room / Roof	1	EA	7	\$0	Extra Large
	Energy Recovery Unit	Mechanical Room	2	EA	5	\$0	Attached to AH - 5,6 - Energy wheel
	Energy Recovery Unit	Mechanical Room / Penthouse	2	EA	5	\$0	Serves AH - 1,2 - Energy wheel
	Indoor Return Fans- Centrifugal Squirrel Cage - 10001 - 20000 CFM	Penthouse	2	EA	7	\$0	
	VAV Box	Mechanical Room / Entire Building	52	EA	6	\$14,517	serve AH2, west side
	VAV Box	Mechanical Room / Entire Building	28	EA	6	\$7,817	serve AH3, central area



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Mechanical System

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lling Systems						
VAV Box	Mechanical Room / Entire Building	60	EA	6	\$16,750	floors 1,2,3, east area
Zone Dampers	Mechanical Room / Entire Building	60	EA	6	\$49,982	1 per VAV
Zone Dampers	Mechanical Room / Entire Building	52	EA	6	\$43,318	
Zone Dampers	Mechanical Room / Entire Building	28	EA	6	\$23,325	1 per VAV
ystems						
Boiler Auxiliary- Condensing Hot Water - 2001 - 3000 HP	Boiler Room	3	EA	7	\$0	
Condensing- Hot Water Boiler - 2001 - 3000 MBH	Boiler Room	3	EA	6	\$2,994	
Glycol Feed System	Boiler Room	1	EA	6	\$539	
Hot Water Pump	Boiler Room / Mechanical Room	2	EA	6	\$748	
Devices						
Cabinet Heaters - With Hot Water Coil	Entire Building	14	EA	7	\$0	
Fin Tube - Hot Water	Entire Building	275	LF	7	\$0	
Radiator Panels - Hot Water	Entire Building	90	EA	7	\$0	Self contained Temperature control
Unit Heater - Hot Water	Entire Building	11	EΑ	7	\$0	
Wall Heater - Electric	Electrical Room	2	EA	7	\$0	
cal Plumbing						
Chilled Water Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
Hydronic Supply and Return - Copper	Entire Building	1,000	LF	7	\$0	Hot water heat
Hydronic Supply and Return - Copper	Entire Building	1,000	LF	7	\$0	Chilled water
Hydronic Supply and Return - Steel	Entire Building / Mechanical Room	1,000	LF	7	\$0	Chilled water
Hydronic Supply and Return - Steel	Entire Building / Mechanical Room	1,000	LF	7	\$0	Hot water heat
iture Control						
DDC System	Entire Building	213,710	SF	7	\$0	
Electric Thermostat	Entire Building / 2nd Floor	4	EA	7	\$0	Serves Split System / CU's
Thermostats - DDC	Entire Building	150	EA	7	\$0	
on						
Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	7	\$0	Serves Labs
Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	3	EA	7	\$0	
Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Entire Building / Roof	1	EA	7	\$0	Serves Kitchen
Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Lower Roof	2	EA	7	\$0	
Lab Exhaust Hood	Entire Building / 3rd Floor	2	EA	7	\$0	
T 151 (11 170)		2	EA	7	\$0	
Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	_	$\vdash \land$,	ΨΟ	
	Iling Systems VAV Box Zone Dampers Zone Dampers Zone Dampers Zone Dampers Zone Dampers Stems Boiler Auxiliary- Condensing Hot Water - 2001 - 3000 HP Condensing- Hot Water Boiler - 2001 - 3000 MBH Glycol Feed System Hot Water Pump Devices Cabinet Heaters - With Hot Water Coil Fin Tube - Hot Water Radiator Panels - Hot Water Unit Heater - Hot Water Wall Heater - Electric cal Plumbing Chilled Water Pump - 21 - 50 HP Hydronic Supply and Return - Copper Hydronic Supply and Return - Steel ture Control DDC System Electric Thermostat Thermostats - DDC on Exhaust Fans- Roof Mounted - 500 - 1500 CFM Exhaust Fans- Roof Mounted - Greater than 8000 CFM Exhaust Fans- Roof Mounted - Greater than 8000 CFM Exhaust Fans- Roof Mounted - Less than 500 CFM	Iling Systems VAV Box Zone Dampers Zone Dampers Zone Dampers Alechanical Room / Entire Building Mechanical Room / Entire Building Sistems Boiler Auxiliary- Condensing Hot Water - 2001 - 3000 HP Condensing- Hot Water Boiler - 2001 - 3000 MBH Boiler Room Glycol Feed System Boiler Room Boiler Room Boiler Room Mechanical Room Boiler Room Boiler Room Mechanical Room Devices Cabinet Heaters - With Hot Water Coil Entire Building Fin Tube - Hot Water Cabinet Heaters - Hot Water Entire Building Radiator Panels - Hot Water Unit Heater - Hot Water Entire Building Wall Heater - Electric Electrical Room Cal Plumbing Chilled Water Pump - 21 - 50 HP Hydronic Supply and Return - Copper Hydronic Supply and Return - Copper Hydronic Supply and Return - Steel Hydronic Supply and Return - Steel Hydronic Supply and Return - Steel Entire Building / Mechanical Room Hydronic Supply and Return - Steel Entire Building / Mechanical Room ture Control DDC System Entire Building / Mechanical Room ture Control DDC System Entire Building / Poof Entire Building / Roof Exhaust Fans- Roof Mounted - 500 - 1500 CFM Exhaust Fans- Roof Mounted - Greater than 8000 CFM Exhaust Fans- Roof Mounted - Greater than 8000 CFM Exhaust Fans- Roof Mounted - Less than 500 CFM Entire Building / Lower Roof	Ing Systems VAV Box And Box	Ing Systems	Inign Systems	Initial Systems



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Mechanical System

Group Item - Type Location Quantity Unit Rank Cost Comments

Mechanical System Subtotal: \$183,126

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Wa	ter						
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	3	EA	7	\$0	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Cold Water Risers	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water Return Lines	Entire Building	213,710	SF	7	\$0	
	Domestic Piping-Hot Water Return Risers	Entire Building	213,710	SF	7	\$0	
	Sanitary Piping	Entire Building	213,710	SF	7	\$0	
	Storm Piping	Entire Building	213,710	SF	7	\$0	
	Vent Piping	Entire Building	213,710	SF	7	\$0	
Pool Sy	stems						
	Pool Drain Piping	Mechanical Room	100	LF	7	\$0	
	Pool Filtration System including Pump	Mechanical Room	1	EA	7	\$0	
	Pool Hot Water Heater - Gas Fired	Mechanical Room	1	EA	6	\$310	
	Pool Supply and Return Piping	Mechanical Room	100	LF	7	\$0	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	
	Pumps - Ejector-Duplex	Mechanical Room	2	EA	6	\$2,774	
	Pumps - Sump-Duplex	Mechanical Room	2	EA	6	\$2,774	
	Pumps - Sump-Simplex	Mechanical Room	1	EA	6	\$745	

Plumbing System Subtotal:

\$8,579

Building: Main

Category: Classrooms

Group Item - Type Location Quantity Unit Rank Cost Comments



1955 E 75th St Chicago, IL 60649

Building: Main

	Item - Type	Location	Quantity	l Ini4	Dank	Cost	Comments
•	oom #008 (Fitness Room)	Location	Quantity	Jiiit	Kalik	Cost	Comments
CidSSfC	Ceiling - Lay-in	Basement	1,317	SF	6	\$3,955	
	Doors - Side-lite	Basement	1,317	SF	6	\$267	
	Doors - Steel Doors incl hw	Basement	2	EA	6	\$602	
	Doors - Transom Window	Basement	16	SF	6	\$271	
	Floor - Sport Flooring	Basement	1,317	SF	6	\$2,844	
	Lighting - Lay-in	Basement	1,317	EA	7	\$2,044	
	Storage/ Closet	Basement	100	SF	6	\$725	
	Wall Mirrors	Basement	1,205	SF	6	\$0	
	Walls - Concrete Block	Basement	•	SF	6		
	Walls - Concrete block	Basement	3,292	SF	0	\$9,650	
Classro	om #117 (Computer Lab)						
	Ceiling - Lay-in	1st Floor	770	SF	6	\$2,312	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	770	SF	6	\$1,641	
	Lighting - Pendent/Surface	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Concrete Block	1st Floor	230	SF	6	\$674	
	Walls - Plaster/Drywall	1st Floor	910	SF	6	\$2,512	
Classro	oom #200B (Art Room)						
	Casework	2nd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	2nd Floor	1,220	SF	6	\$3,664	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,220	SF	6	\$2,669	
	Lighting - Lay-in	2nd Floor	8	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	23	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	8	EA	6	\$991	Incandescent fixtures
	Marker Board	2nd Floor	16	LF	7	\$0	
	Storage/ Closet	2nd Floor	6	SF	6	\$44	
	Walls - Concrete Block	2nd Floor	248	SF	6	\$727	
	Walls - Masonry	2nd Floor	66	SF	6	\$208	
	Walls - Plaster/Drywall	2nd Floor	915	SF	6	\$2,525	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classro	oom #200B-2 (Art Room)						
	Ceiling - Lay-in	2nd Floor	91	SF	6	\$273	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Concrete	2nd Floor	91	SF	6	\$48	
	OLIODE INTL. LIO	D 0 . (FF					A 1 D - 1 - 0/00/45



1955 E 75th St Chicago, IL 60649

Building: Main

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	oom #200B-2 (Art Room)						
	Kiln	2nd Floor	1	EA	6	\$2,321	
	Lighting - Lay-in	2nd Floor	2	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	106	SF	6	\$311	
	Walls - Plaster/Drywall	2nd Floor	244	SF	6	\$673	
Classro	oom #200D (Art Room)						
	Casework	2nd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	2nd Floor	1,220	SF	6	\$3,664	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	1,220	SF	6	\$2,669	
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	23	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	8	EA	6	\$991	Incandescent fixture
	Marker Board	2nd Floor	16	LF	7	\$0	
	Storage/ Closet	2nd Floor	6	SF	6	\$44	
	Walls - Concrete Block	2nd Floor	248	SF	6	\$727	
	Walls - Masonry	2nd Floor	66	SF	6	\$208	
	Walls - Plaster/Drywall	2nd Floor	915	SF	6	\$2,525	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classro	oom #200F (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	1,570	SF	7	\$0	
	Doors - Side-lite	2nd Floor	24	SF	6	\$401	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Tile	2nd Floor	1,570	SF	6	\$3,435	
	Lighting - Lay-in	2nd Floor	11	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	23	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Risers	2nd Floor	120	LF	6	\$2,701	
	Sound Panels	2nd Floor	8	EA	6	\$32	
	Sound System	2nd Floor	1	EA	6	\$1,442	
	Walls - Masonry	2nd Floor	66	SF	6	\$208	
	Walls - Plaster/Drywall	2nd Floor	1,145	SF	6	\$3,160	
Classro	oom #200H (Band Room)						
	Ceiling - Lay-in	2nd Floor	1,570	SF	6	\$4,715	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	Broken door closer hardware
	LOUGDE INTL. LIG	D 40 -/ 5					A 1 D - 1 - 0/000



1955 E 75th St Chicago, IL 60649

Building: Main

oup Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
assroom #200H (Band Room)						
Floor - Carpet	2nd Floor	1,570	SF	6	\$3,345	
Instrument Storage Casework	2nd Floor	284	LF	6	\$0	200H-2 storage
Lighting - Lay-in	2nd Floor	16	EA	7	\$0	Can lights
Lighting - Pendent/Surface	2nd Floor	25	EA	7	\$0	
Marker Board	2nd Floor	16	LF	7	\$0	
Risers	2nd Floor	14	LF	6	\$315	
Sound Panels	2nd Floor	12	EA	6	\$48	
Sound System	2nd Floor	1	EA	6	\$1,442	
Walls - Concrete Block	2nd Floor	100	SF	6	\$293	
Walls - Plaster/Drywall	2nd Floor	1,650	SF	6	\$4,554	
Work Sink	2nd Floor	1	EA	6	\$379	
assroom #212 (Office)						
Casework	2nd Floor	70	LF	6	\$1,768	
Ceiling - Lay-in	2nd Floor	690	SF	6	\$2,072	
Doors - Side-lite	2nd Floor	8	SF	6	\$134	
Doors - Transom Window	2nd Floor	32	SF	6	\$542	
Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
Marker Board	2nd Floor	16	LF	7	\$0	
Walls - Concrete Block	2nd Floor	398	SF	6	\$1,167	
Walls - Plaster/Drywall	2nd Floor	1,050	SF	6	\$2,898	
Walls - Structural Glazed Tile	2nd Floor	16	SF	6	\$50	
assroom #215 (Regular Classroom)						
Casework	2nd Floor	15	LF	6	\$379	
Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
Doors - Side-lite	2nd Floor	8	SF	6	\$134	
Doors - Transom Window	2nd Floor	40	SF	6	\$677	
Doors - Wood Doors inclu hw	2nd Floor	1	EΑ	6	\$301	
Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
Marker Board	2nd Floor	16	LF	7	\$0	
Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #216 (Regular Classroom)						
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	42	SF	6	\$711	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	590	SF	6	\$1,628	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
Classro	oom #217 (Regular Classroom)						
	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	590	SF	6	\$1,628	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
Classro	oom #218 (Regular Classroom)						
	Casework	2nd Floor	14	LF	6	\$354	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	32	SF	6	\$542	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	



1955 E 75th St Chicago, IL 60649

Building: Main

Froup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lassro	om #218 (Regular Classroom)						
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
lassro	om #219 (Regular Classroom)						
	Casework	2nd Floor	15	LF	6	\$379	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EΑ	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
lassro	om #220 (Regular Classroom)						
.000.0	Casework	2nd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
lassro	om #221 (Health)						
	Casework	2nd Floor	52	LF	6	\$1,313	
	Ceiling - Lay-in	2nd Floor	975	SF	6	\$2,928	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	975	SF	6	\$976	
	Lighting - Lay-in	2nd Floor	7	EA	7		Can lights
	CHOPE INTLINE	Para 40 of				**	Assessment Pote



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	oom #221 (Health)						
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	10	LF	7	\$0	
	Storage/ Closet	2nd Floor	15	SF	6	\$109	
	Walls - Concrete Block	2nd Floor	234	SF	6	\$686	
	Walls - Plaster/Drywall	2nd Floor	1,160	SF	6	\$3,201	
	Walls - Structural Glazed Tile	2nd Floor	66	SF	6	\$208	
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classro	oom #222 (Computer Lab)						
	Ceiling - Lay-in	2nd Floor	1,260	SF	6	\$3,784	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	2nd Floor	2	EΑ	6	\$602	
	Floor - Tile/Sheet	2nd Floor	1,260	SF	6	\$1,261	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	20	EΑ	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	225	SF	6	\$660	
	Walls - Plaster/Drywall	2nd Floor	950	SF	6	\$2,622	
	Walls - Structural Glazed Tile	2nd Floor	30	SF	6	\$94	
	Wireless System	2nd Floor	1	EA	6	\$372	
Classro	oom #223 (Science Lab Level 2)						
	Casework	2nd Floor	92	LF	6	\$2,323	
	Ceiling - Lay-in	2nd Floor	1,290	SF	6	\$3,874	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,290	SF	6	\$1,291	
	Gas Line	2nd Floor	4	EA	6	\$2,036	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Science Lab Elements	2nd Floor	1,290	SF	6	\$8,744	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	200	SF	6	\$586	
	Walls - Plaster/Drywall	2nd Floor	890	SF	6	\$2,456	
	Walls - Structural Glazed Tile	2nd Floor	176	SF	6	\$554	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	om #223 (Science Lab Level 2)		•				
	Work Sink	2nd Floor	4	EA	6	\$1,516	
Classro	om #224 (Regular Classroom)						
0100010	Casework	2nd Floor	17	LF	6	\$429	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	3
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
Classro	om #226 (Regular Classroom)						
Ciassio	Casework	2nd Floor	16	LF	6	\$404	
		2nd Floor	795	SF	6 6	\$2,387	
	Ceiling - Lay-in	2nd Floor		SF			
	Doors - Side-lite Doors - Transom Window	2nd Floor	8	SF	6 6	\$134 \$677	
	Doors - Wood Doors inclu hw	2nd Floor	40	EA		\$301	
	Floor - Tile/Sheet	2nd Floor	1 795	SF	6 6	\$796	
		2nd Floor	795	EA	7		Can lighta
	Lighting - Lay-in	2nd Floor		EA	7	\$0 \$0	Can lights
	Lighting - Pendent/Surface Marker Board	2nd Floor	16 16	LF	7 7	\$0 \$0	
		2nd Floor	170	SF	6		
	Walls - Concrete Block Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$498 \$2,249	
	Walls - Flaster/Drywall Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
		2110 1 1001	44	SI	O	φ130	
Classro	om #227 (Science Lab Level 2)						
	Casework	2nd Floor	92	LF	6	\$2,323	
	Ceiling - Lay-in	2nd Floor	1,290	SF	6	\$3,874	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,290	SF	6	\$1,291	
	Fume Hood	2nd Floor	1	EA	6	\$816	



1955 E 75th St Chicago, IL 60649

Building: Main

J. Jup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #227 (Science Lab Level 2)	Location	Quantity	Jint	Marin	0031	
G iacoi G	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Science Lab Elements	2nd Floor	1,290	SF	6	\$8,744	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	200	SF	6	\$586	
	Walls - Plaster/Drywall	2nd Floor	890	SF	6	\$2,456	
	Walls - Structural Glazed Tile	2nd Floor	160	SF	6	\$503	
Classra	oom #228 (Regular Classroom)					•	
Ciassio	Casework	2nd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	793 8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Lay-III Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
		2110 1 1001	77	OI	O	ψ100	
Classro	oom #230 (Regular Classroom)						
	Casework	2nd Floor	15	LF	6	\$379	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
Classro	oom #231 (Science Lab Level 1)						
	Casework	2nd Floor	92	LF	6	\$2,323	



1955 E 75th St Chicago, IL 60649

Building: Main

up	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	oom #231 (Science Lab Level 1)		•				
	Ceiling - Lay-in	2nd Floor	1,290	SF	6	\$3,874	
	Doors - Side-lite	2nd Floor	16	SF	6	\$267	
	Doors - Transom Window	2nd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	2nd Floor	2	EΑ	6	\$602	
	Eye Wash Station	2nd Floor	1	EΑ	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,290	SF	6	\$1,291	
	Fume Hood	2nd Floor	1	EΑ	6	\$816	
	Gas Line	2nd Floor	9	EΑ	6	\$4,582	
	Lighting - Pendent/Surface	2nd Floor	28	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Science Lab Elements	2nd Floor	1,290	SF	6	\$8,744	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	200	SF	6	\$586	
	Walls - Plaster/Drywall	2nd Floor	890	SF	6	\$2,456	
	Walls - Structural Glazed Tile	2nd Floor	176	SF	6	\$554	
	Work Sink	2nd Floor	9	EA	6	\$3,411	
sro	oom #232 (Regular Classroom)						
	Casework	2nd Floor	15	LF	6	\$379	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	-
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
sro	om #234 (Regular Classroom)						
	Casework	2nd Floor	12	LF	6	\$303	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	775	SF	6	\$776	



1955 E 75th St Chicago, IL 60649

Building: Main

	ory: Classrooms	Landton	0		D'		0
-	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	pom #234 (Regular Classroom)	- 1-					5
	Floor - Tile/Sheet	2nd Floor	20	SF	4	\$296	Broken/missing tiles
	Lighting - Lay-in	2nd Floor	2	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	2nd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
Classro	oom #235 (Regular Classroom)						
	Casework	2nd Floor	19	LF	6	\$480	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Side-lite	2nd Floor	8	SF	6	\$134	
	Doors - Transom Window	2nd Floor	8	SF	6	\$135	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Plaster/Drywall	2nd Floor	170	SF	6	\$469	
	Walls - Structural Glazed Tile	2nd Floor	44	SF	6	\$138	
Classro	oom #312 (Office)						
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	24	EA	6	\$2,228	
	Walls - Concrete Block	3rd Floor	400	SF	6	\$1,173	
	Walls - Plaster/Drywall	3rd Floor	1,011	SF	6	\$2,790	
Classro	oom #315 (Regular Classroom)						
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	



1955 E 75th St Chicago, IL 60649

Building: Main

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	oom #315 (Regular Classroom)						
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7		Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	S
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #316 (Regular Classroom)						
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	-
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #317 (Regular Classroom)						
	Casework	3rd Floor	18	LF	6	\$455	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	770	SF	6	\$771	
	Floor - Tile/Sheet	3rd Floor	25	SF	4	\$370	Broken/missing floor tiles
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$571	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$571	
	Walls - Plaster/Drywall	3rd Floor	590	SF	6	\$1,628	
Classro	oom #318 (Regular Classroom)						
	Casework	3rd Floor	14	LF	6	\$354	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #318 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	790	SF	6	\$791	
	Floor - Tile/Sheet	3rd Floor	5	SF	4	\$74	Missing/broken floor tiles
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #319 (Regular Classroom)						
	Casework	3rd Floor	14	LF	6	\$354	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #320 (Regular Classroom)						
	Casework	3rd Floor	17	LF	6	\$429	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	



1955 E 75th St Chicago, IL 60649

Building: Main

•	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #320 (Regular Classroom)						
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #321 (Computer Lab)						
	Ceiling - Lay-in	3rd Floor	1,290	SF	6	\$3,874	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,290	SF	6	\$1,291	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	24	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	200	SF	6	\$586	
	Walls - Plaster/Drywall	3rd Floor	890	SF	6	\$2,456	
	Walls - Structural Glazed Tile	3rd Floor	176	SF	6	\$554	
	Wireless System	3rd Floor	1	EA	6	\$372	
lassro	oom #322 (Computer Lab)						
	Ceiling - Lay-in	3rd Floor	1,260	SF	6	\$3,784	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,260	SF	6	\$1,261	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	20	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	225	SF	6	\$660	
	Walls - Plaster/Drywall	3rd Floor	950	SF	6	\$2,622	
	Wireless System	3rd Floor	1	EA	6	\$372	
lassro	oom #323 (Science Lab Level 2)						
	Casework		92	LF	6	\$2,323	
	Ceiling - Lay-in		1,290	SF	6	\$3,874	
	Doors - Side-lite		16	SF	6	\$267	
	Doors - Transom Window		50	SF	6	\$847	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Eye Wash Station		1	EA	6	\$336	
	Floor - Tile/Sheet		1,290	SF	6	\$1,291	
	Gas Line		4	EA	6	\$2,036	
	LOUODE MITLUO	Davis 04 at					A 1 D - 1 - 0/0



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	oom #323 (Science Lab Level 2)						
	Lighting - Pendent/Surface		28	EA	7	\$0	
	Marker Board		16	LF	7	\$0	
	Science Lab Elements		1,290	SF	6	\$8,744	
	Science Lab Shower		1	EA	6	\$379	
	Walls - Concrete Block		200	SF	6	\$586	
	Walls - Plaster/Drywall		890	SF	6	\$2,456	
	Walls - Structural Glazed Tile		176	SF	6	\$554	
	Work Sink		4	EA	6	\$1,516	
Classro	oom #324 (Regular Classroom)						
	Casework	3rd Floor	17	LF	6	\$429	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #326 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #327 (Science Lab Level 2)						
	Casework	3rd Floor	92	LF	6	\$2,323	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #327 (Science Lab Level 2)						
	Ceiling - Lay-in	3rd Floor	1,290	SF	6	\$3,874	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,290	SF	6	\$1,291	
	Gas Line	3rd Floor	8	EA	6	\$4,073	
	Lighting - Pendent/Surface	3rd Floor	28	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Elements	3rd Floor	1,290	SF	6	\$8,744	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Concrete Block	3rd Floor	200	SF	6	\$586	
	Walls - Plaster/Drywall	3rd Floor	890	SF	6	\$2,456	
	Walls - Structural Glazed Tile	3rd Floor	176	SF	6	\$554	
	Work Sink	3rd Floor	8	EA	6	\$3,032	
Classro	oom #328 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	oom #330 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	



1955 E 75th St Chicago, IL 60649

Building: Main

•	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lassro	om #330 (Regular Classroom)						
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	om #331 (Science Lab Level 1)						
	Casework	3rd Floor	92	LF	6	\$2,323	
	Ceiling - Lay-in	3rd Floor	1,290	SF	6	\$3,874	
	Doors - Side-lite	3rd Floor	16	SF	6	\$267	
	Doors - Transom Window	3rd Floor	50	SF	6	\$847	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,290	SF	6	\$1,291	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	8	EΑ	6	\$4,073	
	Lighting - Pendent/Surface	3rd Floor	28	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Science Lab Elements	3rd Floor	1,290	SF	6	\$8,744	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Concrete Block	3rd Floor	200	SF	6	\$586	
	Walls - Plaster/Drywall	3rd Floor	890	SF	6	\$2,456	
	Walls - Structural Glazed Tile	3rd Floor	176	SF	6	\$554	
	Work Sink	3rd Floor	8	EA	6	\$3,032	
lassro	om #332 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	40	SF	6	\$677	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	795	SF	6	\$796	
	Lighting - Lay-in	3rd Floor	3	EA	6	\$357	Can light
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	170	SF	6	\$498	
	Walls - Plaster/Drywall	3rd Floor	815	SF	6	\$2,249	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	om #334 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	om #334 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	5	SF	4	\$65	Missing/broken floor tile
	Floor - Tile	3rd Floor	790	SF	6	\$1,728	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	815	SF	6	\$2,389	
	Walls - Plaster/Drywall	3rd Floor	170	SF	6	\$469	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	
Classro	om #335 (Regular Classroom)						
	Casework	3rd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	3rd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	3rd Floor	8	SF	6	\$134	
	Doors - Transom Window	3rd Floor	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	16	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	815	SF	6	\$2,389	
	Walls - Plaster/Drywall	3rd Floor	170	SF	6	\$469	
	Walls - Structural Glazed Tile	3rd Floor	44	SF	6	\$138	

Classrooms Subtotal: \$513,778

Building: Main

Group Item - Type	Location	Quantity	Unit	Rank	Cost Commer
Administrative Suites/Offices					
Ceiling - Lay-in	002 Green Room	372	SF	6	\$1,117
Doors - Steel Doors incl hw	002 Green Room	1	EA	6	\$301
Floor - Terrazzo	002 Green Room	372	SF	6	\$814
Lighting - Lay-in	002 Green Room	6	EA	6	\$714



1955 E 75th St Chicago, IL 60649

Building: Main

Group Item - Type	Location	Quantity	Unit	Rank	Cost	(
dministrative Suites/Offices						
Power Distribution	002 Green Room	47	EA	7	\$0	
Walls - Concrete Block	002 Green Room	711	SF	6	\$2,084	
Work SInk	002 Green Room	1	EA	6	\$508	
Ceiling - Lay-in	003D Park District Office	100	SF	6	\$300	
Doors - Steel Doors incl hw	003D Park District Office	1	EA	6	\$301	
Floor - Terrazzo	003D Park District Office	100	SF	6	\$219	
Lighting - Lay-in	003D Park District Office	2	EA	6	\$238	
Power Distribution	003D Park District Office	6	EA	7	\$0	
Walls - Concrete Block	003D Park District Office	360	SF	6	\$1,055	
Ceiling - Lay-in	004G Men's Coach Office	91	SF	6	\$273	
Doors - Steel Doors incl hw	004G Men's Coach Office	1	EA	6	\$301	
Floor - Tile/Sheet	004G Men's Coach Office	91	SF	6	\$91	
Lighting - Lay-in	004G Men's Coach Office	2	EΑ	6	\$238	
Power Distribution	004G Men's Coach Office	12	EA	7	\$0	
Walls - Concrete Block	004G Men's Coach Office	330	SF	6	\$967	
Ceiling - Plaster/Drywall	007A Men's Pool Coach	193	SF	6	\$668	
Doors - Wood Doors inclu hw	007A Men's Pool Coach	3	EΑ	6	\$903	
Floor - Terrazzo	007A Men's Pool Coach	193	SF	6	\$422	
Lighting - Lay-in	007A Men's Pool Coach	3	EΑ	6	\$357	
Power Distribution	007A Men's Pool Coach	10	EA	7	\$0	
Walls - Concrete Block	007A Men's Pool Coach	495	SF	6	\$1,451	
Ceiling - Plaster/Drywall	007B Women's Pool Coach	193	SF	6	\$668	
Doors - Wood Doors inclu hw	007B Women's Pool Coach	3	EA	6	\$903	
Floor - Terrazzo	007B Women's Pool Coach	193	SF	6	\$422	
Lighting - Lay-in	007B Women's Pool Coach	3	EA	6	\$357	
Power Distribution	007B Women's Pool Coach	10	EA	7	\$0	
Walls - Concrete Block	007B Women's Pool Coach	495	SF	6	\$1,451	
Ceiling - Lay-in	100A Professional Library	327	SF	6	\$982	
Doors - Store Front	100A Professional Library	1	EA	6	\$1,208	
Floor - Terrazzo	100A Professional Library	327	SF	6	\$715	
Lighting - Chandelier, Incandescent	100A Professional Library	6	EA	6	\$2,865	
Power Distribution	100A Professional Library	10	EA	7	\$0	
Walls - Plaster/Drywall	100A Professional Library	820	SF	6	\$2,263	
Ceiling - Lay-in	100B Workroom	175	SF	6	\$526	
Doors - Store Front	100B Workroom	1	EA	6	\$1,208	
Floor - Terrazzo	100B Workroom	175	SF	6	\$383	
Lighting - Chandelier, Incandescent	100B Workroom	6	EA	6	\$2,865	



1955 E 75th St Chicago, IL 60649

Building: Main

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lmini	strative Suites/Offices						
	Power Distribution	100B Workroom	4	EA	7	\$0	
	Walls - Plaster/Drywall	100B Workroom	490	SF	6	\$1,352	
	Ceiling - Lay-in	100C Distance Learning	827	SF	6	\$2,483	
	Doors - Store Front	100C Distance Learning	2	EA	6	\$2,416	
	Floor - Carpet	100C Distance Learning	827	SF	6	\$1,762	
	Lighting - Chandelier, Incandescent	100C Distance Learning	22	EA	6	\$10,506	
	Power Distribution	100C Distance Learning	8	EA	7	\$0	
	Walls - Masonry	100C Distance Learning	1,033	SF	6	\$3,250	Brick Face
	Walls - Metal Panel	100C Distance Learning	520	SF	6	\$3,882	Glass Wall
	Walls - Plaster/Drywall	100C Distance Learning	520	SF	6	\$1,435	
	Ceiling - Lay-in	100F Workroom	417	SF	6	\$1,252	
	Doors - Store Front	100F Workroom	2	EA	6	\$2,416	
	Floor - Terrazzo	100F Workroom	417	SF	6	\$912	
	Lighting - Lay-in	100F Workroom	8	EA	6	\$952	
	Power Distribution	100F Workroom	10	EA	7	\$0	
	Walls - Plaster/Drywall	100F Workroom	615	SF	6	\$1,697	
	Ceiling - Lay-in	103B Auditorium Lighting Control	153	SF	6	\$459	
	Doors - Wood Doors inclu hw	103B Auditorium Lighting Control	1	EA	6	\$301	
	Floor - Carpet	103B Auditorium Lighting Control	153	SF	6	\$326	
	Lighting - Lay-in	103B Auditorium Lighting Control	2	EA	6	\$238	
	Lighting - Pendent/Surface	103B Auditorium Lighting Control	1	EA	6	\$124	
	Power Distribution	103B Auditorium Lighting Control	4	EA	7	\$0	
	Walls - Plaster/Drywall	103B Auditorium Lighting Control	398	SF	6	\$1,098	
	Ceiling - Lay-in	103B-1 Sound Projection	124	SF	6	\$372	
	Doors - Wood Doors inclu hw	103B-1 Sound Projection	1	EA	6	\$301	
	Floor - Carpet	103B-1 Sound Projection	124	SF	6	\$264	
	Lighting - Lay-in	103B-1 Sound Projection	2	EA	6	\$238	
	Lighting - Pendent/Surface	103B-1 Sound Projection	1	EA	6	\$124	
	Power Distribution	103B-1 Sound Projection	8	EA	7	\$0	
	Walls - Plaster/Drywall	103B-1 Sound Projection	398	SF	6	\$1,098	
	Ceiling - Lay-in	106 Campus Manager	128	SF	6	\$384	
	Doors - Wood Doors inclu hw	106 Campus Manager	1	EA	6	\$301	
	Floor - Tile/Sheet	106 Campus Manager	128	SF	6	\$128	
	Lighting - Lay-in	106 Campus Manager	2	EA	6	\$238	
	Power Distribution	106 Campus Manager	8	EA	7	\$0	
	Walls - Concrete Block	106 Campus Manager	230	SF	6	\$674	
	Walls - Plaster/Drywall	106 Campus Manager	230	SF	6	\$635	



1955 E 75th St Chicago, IL 60649

Building: Main

oup Item	- Туре	Location	Quantity	Unit	Rank	Cost	Comments
ministrative	e Suites/Offices						
Ceilin	ng - Lay-in	111 Security	100	SF	6	\$300	
Doors	s - Wood Doors inclu hw	111 Security	1	EΑ	6	\$301	
Floor	- Terrazzo	111 Security	100	SF	7	\$0	
Lighti	ing - Lay-in	111 Security	2	EA	6	\$238	
Powe	er Distribution	111 Security	2	EA	7	\$0	
Walls	s - Concrete Block	111 Security	360	SF	6	\$1,055	
Ceilin	ng - Lay-in	113 Police	100	SF	6	\$300	
Doors	s - Wood Doors inclu hw	113 Police	1	EΑ	6	\$301	
Floor	- Terrazzo	113 Police	100	SF	7	\$0	
Lighti	ing - Lay-in	113 Police	2	EΑ	6	\$238	
Powe	er Distribution	113 Police	6	EA	7	\$0	
Walls	s - Concrete Block	113 Police	270	SF	6	\$792	
Walls	s - Plaster/Drywall	113 Police	90	SF	6	\$248	
Ceilin	ng - Lay-in	116 College Resources	323	SF	6	\$970	
Doors	s - Wood Doors inclu hw	116 College Resources	1	EA	6	\$301	
Floor	- Carpet	116 College Resources	323	SF	6	\$688	
Lighti	ing - Lay-in	116 College Resources	4	EA	6	\$476	
Powe	er Distribution	116 College Resources	12	EA	7	\$0	
Walls	s - Concrete Block	116 College Resources	201	SF	6	\$589	
Walls	s - Plaster/Drywall	116 College Resources	807	SF	6	\$2,227	
Ceilin	ng - Lay-in	116A Office of Development	100	SF	6	\$300	
Doors	s - Wood Doors inclu hw	116A Office of Development	1	EA	6	\$301	
Floor	- Tile/Sheet	116A Office of Development	100	SF	6	\$100	
Lighti	ing - Lay-in	116A Office of Development	2	EA	6	\$238	
Powe	er Distribution	116A Office of Development	8	EA	7	\$0	
Walls	s - Concrete Block	116A Office of Development	360	SF	6	\$1,055	
	ng - Lay-in	118 Mail Room	435	SF	6	\$1,306	
Doors	s - Wood Doors inclu hw	118 Mail Room	3	EA	6	\$903	
Floor	- Exposed	118 Mail Room	435	SF	6	\$230	
Lighti	ing - Lay-in	118 Mail Room	8	EA	6	\$952	
Powe	er Distribution	118 Mail Room	18	EA	7	\$0	
Walls	s - Concrete Block	118 Mail Room	120	SF	6	\$352	
Walls	s - Plaster/Drywall	118 Mail Room	970	SF	6	\$2,677	
Work	SInk	118 Mail Room	1	EA	6	\$508	
Ceilin	ng - Lay-in	120 Main Office North	762	SF	6	\$2,288	
Doors	s - Side-lite	120 Main Office North	8	SF	6	\$134	
Doors	s - Wood Doors inclu hw	120 Main Office North	1	EA	6	\$301	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	Floor - Carpet	120 Main Office North	762	SF	6	\$1,624	
	Lighting - Lay-in	120 Main Office North	8	EA	6	\$952	
	Lighting - Lay-in	120 Main Office North	8	EA	6	\$952	Can lights (recessed)
	Power Distribution	120 Main Office North	40	EA	7	\$0	
	Walls - Concrete Block	120 Main Office North	378	SF	6	\$1,108	
	Walls - Plaster/Drywall	120 Main Office North	1,035	SF	6	\$2,856	
	Ceiling - Lay-in	120A Conference Room	226	SF	6	\$679	
	Doors - Wood Doors inclu hw	120A Conference Room	1	EA	6	\$301	
	Floor - Carpet	120A Conference Room	226	SF	6	\$482	
	Lighting - Lay-in	120A Conference Room	6	EA	6	\$714	
	Power Distribution	120A Conference Room	6	EA	7	\$0	
	Walls - Plaster/Drywall	120A Conference Room	790	SF	6	\$2,180	
	Ceiling - Lay-in	120B Assistant Principals	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	120B Assistant Principals	1	EA	6	\$301	
	Floor - Carpet	120B Assistant Principals	160	SF	6	\$341	
	Lighting - Lay-in	120B Assistant Principals	2	EA	6	\$238	
	Power Distribution	120B Assistant Principals	6	EA	7	\$0	
	Walls - Plaster/Drywall	120B Assistant Principals	468	SF	6	\$1,292	
	Ceiling - Lay-in	120C Counselor Office	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	120C Counselor Office	1	EA	6	\$301	
	Floor - Carpet	120C Counselor Office	160	SF	6	\$341	
	Lighting - Lay-in	120C Counselor Office	2	EA	6	\$238	
	Power Distribution	120C Counselor Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	120C Counselor Office	468	SF	6	\$1,292	
	Ceiling - Lay-in	120D Counselor Office	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	120D Counselor Office	1	EA	6	\$301	
	Floor - Carpet	120D Counselor Office	160	SF	6	\$341	
	Lighting - Lay-in	120D Counselor Office	2	EA	6	\$238	
	Power Distribution	120D Counselor Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	120D Counselor Office	430	SF	6	\$1,187	
	Ceiling - Lay-in	120E Principal Office	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	120E Principal Office	1	EA	6	\$301	
	Floor - Carpet	120E Principal Office	208	SF	6	\$443	
	Lighting - Lay-in	120E Principal Office	4	EA	6	\$476	
	Power Distribution	120E Principal Office	8	EA	7	\$0	
	Walls - Plaster/Drywall	120E Principal Office	600	SF	6	\$1,656	
	Ceiling - Lay-in	121A Faculty Cafeteria	307	SF	6	\$922	



1955 E 75th St Chicago, IL 60649

Building: Main

up Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ninistrative Suites/Offices						
Doors - Side-lite	121A Faculty Cafeteria	14	SF	6	\$234	
Doors - Wood Doors inclu hw	121A Faculty Cafeteria	2	EA	6	\$602	
Floor - Terrazzo	121A Faculty Cafeteria	307	SF	6	\$672	
Lighting - Lay-in	121A Faculty Cafeteria	4	EA	6	\$476	
Power Distribution	121A Faculty Cafeteria	18	EA	7	\$0	
Walls - Structural Glazed Tile	121A Faculty Cafeteria	767	SF	6	\$2,413	
Work SInk	121A Faculty Cafeteria	1	EA	6	\$508	
Ceiling - Lay-in	121B Dishwashing Room	286	SF	6	\$859	
Doors - Steel Doors incl hw	121B Dishwashing Room	1	EA	6	\$301	
Floor - Epoxy/ Painted	121B Dishwashing Room	286	SF	6	\$151	
Lighting - Lay-in	121B Dishwashing Room	4	EA	6	\$476	
Walls - Concrete Block	121B Dishwashing Room	715	SF	6	\$2,096	
Work SInk	121B Dishwashing Room	3	EΑ	6	\$1,524	
Ceiling - Lay-in	122 Main Office South	762	SF	6	\$2,288	
Doors - Side-lite	122 Main Office South	8	SF	6	\$134	
Doors - Wood Doors inclu hw	122 Main Office South	1	EA	6	\$301	
Floor - Carpet	122 Main Office South	762	SF	6	\$1,624	
Lighting - Lay-in	122 Main Office South	8	EA	6	\$952	
Lighting - Lay-in	122 Main Office South	8	EA	6	\$952	Can lights (recessed)
Power Distribution	122 Main Office South	54	EA	7	\$0	
Walls - Concrete Block	122 Main Office South	378	SF	6	\$1,108	
Walls - Plaster/Drywall	122 Main Office South	1,035	SF	6	\$2,856	
Ceiling - Lay-in	122A Conference Office	226	SF	6	\$679	
Doors - Wood Doors inclu hw	122A Conference Office	1	EA	6	\$301	
Floor - Carpet	122A Conference Office	226	SF	6	\$482	
Lighting - Lay-in	122A Conference Office	6	EA	6	\$714	
Power Distribution	122A Conference Office	6	EA	7	\$0	
Walls - Plaster/Drywall	122A Conference Office	790	SF	6	\$2,180	
Ceiling - Lay-in	122B Counselor Office	160	SF	6	\$480	
Doors - Wood Doors inclu hw	122B Counselor Office	1	EA	6	\$301	
Floor - Carpet	122B Counselor Office	160	SF	6	\$341	
Lighting - Lay-in	122B Counselor Office	2	EA	6	\$238	
Power Distribution	122B Counselor Office	14	EA	7	\$0	
Walls - Plaster/Drywall	122B Counselor Office	468	SF	6	\$1,292	
Ceiling - Lay-in	122C Counselor Office	160	SF	6	\$480	
Doors - Wood Doors inclu hw	122C Counselor Office	1	EA	6	\$301	
Floor - Carpet	122C Counselor Office	160	SF	6	\$341	



1955 E 75th St Chicago, IL 60649

Building: Main

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Lighting - Lay-in	122C Counselor Office	2	EA	6	\$238	
	Power Distribution	122C Counselor Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	122C Counselor Office	468	SF	6	\$1,292	
	Ceiling - Lay-in	122D Assistant Principal	160	SF	6	\$480	
	Doors - Wood Doors inclu hw	122D Assistant Principal	1	EA	6	\$301	
	Floor - Carpet	122D Assistant Principal	160	SF	6	\$341	
	Lighting - Lay-in	122D Assistant Principal	8	EΑ	6	\$952	
	Power Distribution	122D Assistant Principal	6	EΑ	7	\$0	
	Walls - Plaster/Drywall	122D Assistant Principal	445	SF	6	\$1,228	
	Ceiling - Lay-in	122E Case Manager	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	122E Case Manager	1	EΑ	6	\$301	
	Floor - Carpet	122E Case Manager	208	SF	6	\$443	
	Lighting - Lay-in	122E Case Manager	4	EΑ	6	\$476	
	Power Distribution	122E Case Manager	8	EA	7	\$0	
	Walls - Plaster/Drywall	122E Case Manager	600	SF	6	\$1,656	
	Ceiling - Lay-in	124 Mail Room	435	SF	6	\$1,306	
	Doors - Wood Doors inclu hw	124 Mail Room	3	EΑ	6	\$903	
	Floor - Exposed	124 Mail Room	435	SF	6	\$230	
	Lighting - Lay-in	124 Mail Room	8	EA	6	\$952	
	Power Distribution	124 Mail Room	18	EΑ	7	\$0	
	Walls - Concrete Block	124 Mail Room	120	SF	6	\$352	
	Walls - Plaster/Drywall	124 Mail Room	970	SF	6	\$2,677	
	Work Slnk	124 Mail Room	1	EA	6	\$508	
	Ceiling - Lay-in	125E Kitchen Office	160	SF	6	\$480	
	Doors - Store Front	125E Kitchen Office	1	EΑ	6	\$1,208	
	Floor - Tile/Sheet	125E Kitchen Office	160	SF	6	\$160	
	Lighting - Lay-in	125E Kitchen Office	2	EA	6	\$238	
	Power Distribution	125E Kitchen Office	8	EA	7	\$0	
	Walls - Concrete Block	125E Kitchen Office	500	SF	6	\$1,466	
	Ceiling - Lay-in	127 Engineers Office	175	SF	6	\$526	
	Doors - Steel Doors incl hw	127 Engineers Office	1	EA	6	\$301	
	Floor - Concrete	127 Engineers Office	175	SF	6	\$93	
	Lighting - Lay-in	127 Engineers Office	2	EA	6	\$238	
	Power Distribution	127 Engineers Office	12	EA	7	\$0	
	Walls - Concrete Block	127 Engineers Office	470	SF	6	\$1,378	
	Ceiling - Lay-in	128 Nurse Suite	950	SF	6	\$2,853	
	Doors - Side-lite	128 Nurse Suite	24	SF	6	\$401	



1955 E 75th St Chicago, IL 60649

Building: Main

Location	Quantity	Unit	Rank	Cost	Comments
128 Nurse Suite	2	EA	6	\$2,416	
128 Nurse Suite	950	SF	6	\$2,079	
128 Nurse Suite	10	EA	6	\$4,776	
128 Nurse Suite	9	EA	6	\$1,071	
128 Nurse Suite	10	EA	7	\$0	
128 Nurse Suite	387	SF	6	\$1,134	
128 Nurse Suite	1,750	SF	6	\$4,830	
128A Counselor Office	100	SF	6	\$300	
128A Counselor Office	1	EA	6	\$301	
128A Counselor Office	100	SF	6	\$100	
128A Counselor Office	2	EA	6	\$238	
128A Counselor Office	8	EA	7	\$0	
128A Counselor Office	209	SF	6	\$613	
128A Counselor Office	209	SF	6	\$577	
128B Social Worker	100	SF	6	\$300	
128B Social Worker	1	EA	6	\$301	
128B Social Worker	100	SF	6	\$100	
128B Social Worker	2	EA	6	\$238	
128B Social Worker	8	EA	7	\$0	
128B Social Worker	360	SF	6	\$1,055	
128C Counselor Office	100	SF	6	\$300	
128C Counselor Office	1	EA	6	\$301	
128C Counselor Office	100	SF	6	\$100	
128C Counselor Office	2	EA	6	\$238	
128C Counselor Office	8	EA	7	\$0	
128C Counselor Office	360	SF	6	\$1,055	
128D Workroom / Lab	73	SF	6	\$219	
128D Workroom / Lab	1	EA	6	\$301	
128D Workroom / Lab	73	SF	6	\$73	
128D Workroom / Lab	1	EA	6	\$119	
128D Workroom / Lab	8	EA	7	\$0	
128D Workroom / Lab	335	SF	6	\$925	
128D Workroom / Lab	1	EA	6	\$508	
128E Exam Room	135	SF	6	\$405	
128E Exam Room	1	EA	6	\$301	
128E Exam Room	135	SF	6	\$135	
128E Exam Room	2	EA	6	\$238	
	128 Nurse Suite 128A Counselor Office 128B Social Worker 128C Counselor Office 128D Workroom / Lab	128 Nurse Suite 950 128 Nurse Suite 950 128 Nurse Suite 10 128 Nurse Suite 9 128 Nurse Suite 9 128 Nurse Suite 10 128 Nurse Suite 10 128 Nurse Suite 17,750 128 Nurse Suite 17,750 128 Counselor Office 100 128A Counselor Office 100 128A Counselor Office 100 128A Counselor Office 20 128A Counselor Office 8 128A Counselor Office 20 128A Counselor Office 20 128B Social Worker 100 128B Social Worker 100 128B Social Worker 100 128B Social Worker 128B Social Worker 128B Social Worker 128B Social Worker 100 128C Counselor Office 100 128D Workroom / Lab 73 128D Workroom / Lab 1	128 Nurse Suite 2 EA 128 Nurse Suite 950 SF 128 Nurse Suite 10 EA 128 Nurse Suite 9 EA 128 Nurse Suite 10 EA 128 Nurse Suite 1750 SF 128 Nurse Suite 1,750 SF 128 Nurse Suite 1,750 SF 128 Counselor Office 100 SF 128A Counselor Office 100 SF 128A Counselor Office 2 EA 128A Counselor Office 2 EA 128A Counselor Office 209 SF 128A Counselor Office 209 SF 128A Counselor Office 209 SF 128B Social Worker 100 SF 128B Social Worker 1 EA 128B Social Worker 2 EA 128B Social Worker 360 SF 128C Counselor Office 100 SF 128C Counselor Office 1 EA 128C Counselor O	128 Nurse Suite 2 EA 6 128 Nurse Suite 950 SF 6 128 Nurse Suite 10 EA 6 128 Nurse Suite 9 EA 6 128 Nurse Suite 10 EA 7 128 Nurse Suite 387 SF 6 128 Nurse Suite 1,750 SF 6 128A Counselor Office 100 SF 6 128A Counselor Office 1 EA 6 128A Counselor Office 2 EA 6 128A Counselor Office 2 EA 6 128A Counselor Office 20 SF 6 128A Counselor Office 209 SF 6 128A Counselor Office 209 SF 6 128A Counselor Office 209 SF 6 128B Social Worker 100 SF 6 128B Social Worker 100 SF 6 128B Social Worker 1 EA 6 128B Social Worker 2 EA 6 128B Social Worker 360 SF 6 128B Counselor Office 100 SF 6 <	128 Nurse Suite 2 EA 6 \$2,416 128 Nurse Suite 950 SF 6 \$2,079 128 Nurse Suite 10 EA 6 \$4,776 128 Nurse Suite 10 EA 6 \$1,071 128 Nurse Suite 10 EA 7 \$0 128 Nurse Suite 17,50 SF 6 \$1,134 128 Nurse Suite 1,750 SF 6 \$4,830 128A Counselor Office 100 SF 6 \$300 128A Counselor Office 100 SF 6 \$300 128A Counselor Office 2 EA 6 \$238 128A Counselor Office 2 EA 6 \$238 128A Counselor Office 209 SF 6 \$613 128A Counselor Office 209 SF 6 \$613 128B Social Worker 100 SF 6 \$300 128B Social Worker 100 SF 6 \$10



1955 E 75th St Chicago, IL 60649

Building: Main

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	Administrative Suites/Offices						
	Power Distribution	128E Exam Room	8	EA	7	\$0	
	Walls - Concrete Block	128E Exam Room	90	SF	6	\$264	
	Walls - Plaster/Drywall	128E Exam Room	335	SF	6	\$925	
	Work Sink	128E Exam Room	1	EA	6	\$508	
	Ceiling - Lay-in	128F Exam Room	135	SF	6	\$405	
	Doors - Wood Doors inclu hw	128F Exam Room	1	EA	6	\$301	
	Floor - Tile/Sheet	128F Exam Room	135	SF	6	\$135	
	Lighting - Lay-in	128F Exam Room	2	EA	6	\$238	
	Power Distribution	128F Exam Room	8	EA	7	\$0	
	Walls - Concrete Block	128F Exam Room	90	SF	6	\$264	
	Walls - Plaster/Drywall	128F Exam Room	135	SF	6	\$373	
	Work Sink	128F Exam Room	1	EA	6	\$508	
	Ceiling - Lay-in	128G Cot Room	194	SF	6	\$583	
	Doors - Wood Doors inclu hw	128G Cot Room	1	EA	6	\$301	
	Floor - Tile/Sheet	128G Cot Room	194	SF	6	\$194	
	Lighting - Lay-in	128G Cot Room	3	EA	6	\$357	
	Power Distribution	128G Cot Room	10	EA	7	\$0	
	Walls - Concrete Block	128G Cot Room	314	SF	6	\$920	
	Walls - Plaster/Drywall	128G Cot Room	290	SF	6	\$800	
	Work SInk	128G Cot Room	1	EA	6	\$508	
	Ceiling - Lay-in	200A department office	392	SF	6	\$1,177	
	Doors - Side-lite	200A department office	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	200A department office	1	EA	6	\$301	
	Floor - Tile	200A department office	392	SF	6	\$858	
	Lighting - Lay-in	200A department office	8	EA	7	\$0	
	Power Distribution	200A department office	24	EA	7	\$0	
	Storage/ Closet	200A department office	140	SF	6		200A-1
	Walls - Concrete Block	200A department office	405	SF	6	\$1,187	
	Walls - Plaster/Drywall	200A department office	405	SF	6	\$1,118	
	Ceiling - Lay-in	200F-2	92	SF	6	\$276	
	Doors - Side-lite	200F-2	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	200F-2	1	EA	6	\$301	
	Floor - Carpet	200F-2	92	SF	6	\$196	
	Lighting - Lay-in	200F-2	3	EA	7	\$0	Can lights
	Power Distribution	200F-2	8	EA	7	\$0	
	Walls - Plaster/Drywall	200F-2	279	SF	6	\$770	
	Ceiling - Lay-in	200H- 5 Practice Room	142	SF	6	\$426	



1955 E 75th St Chicago, IL 60649

Building: Main

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
dmini	istrative Suites/Offices						
	Doors - Side-lite	200H- 5 Practice Room	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	200H- 5 Practice Room	1	EA	6	\$301	
	Floor - Tile/Sheet	200H- 5 Practice Room	142	SF	6	\$142	
	Lighting - Lay-in	200H- 5 Practice Room	2	EA	7	\$0	
	Power Distribution	200H- 5 Practice Room	6	EA	7	\$0	
	Walls - Plaster/Drywall	200H- 5 Practice Room	420	SF	6	\$1,159	
	Ceiling - Lay-in	200H 6 Practice Room	98	SF	6	\$294	
	Doors - Side-lite	200H 6 Practice Room	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	200H 6 Practice Room	1	EA	6	\$301	
	Floor - Tile/Sheet	200H 6 Practice Room	98	SF	6	\$98	
	Lighting - Lay-in	200H 6 Practice Room	2	EA	7	\$0	
	Power Distribution	200H 6 Practice Room	6	EA	7	\$0	
	Walls - Plaster/Drywall	200H 6 Practice Room	382	SF	6	\$1,054	
	Ceiling - Lay-in	200H -7 Practice Room	102	SF	6	\$306	
	Doors - Side-lite	200H -7 Practice Room	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	200H -7 Practice Room	1	EΑ	6	\$301	
	Floor - Tile/Sheet	200H -7 Practice Room	102	SF	6	\$102	
	Lighting - Lay-in	200H -7 Practice Room	2	EA	7	\$0	
	Power Distribution	200H -7 Practice Room	6	EA	7	\$0	
	Walls - Plaster/Drywall	200H -7 Practice Room	385	SF	6	\$1,063	
	Ceiling - Lay-in	200H-3 office	91	SF	6	\$273	
	Doors - Side-lite	200H-3 office	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	200H-3 office	1	EA	6	\$301	
	Floor - Carpet	200H-3 office	91	SF	6	\$194	
	Lighting - Lay-in	200H-3 office	3	EA	7	\$0	Can lights
	Power Distribution	200H-3 office	6	EA	7	\$0	
	Walls - Plaster/Drywall	200H-3 office	274	SF	6	\$756	
	Ceiling - Lay-in	213	210	SF	6	\$631	
	Doors - Side-lite	213	8	SF	6	\$134	
	Doors - Transom Window	213	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	213	1	EA	6	\$301	
	Floor - Tile/Sheet	213	210	SF	6	\$210	
	Lighting - Lay-in	213	4	EA	7	\$0	
	Power Distribution	213	12	EA	7	\$0	
	Walls - Concrete Block	213	250	SF	6	\$733	
	Walls - Plaster/Drywall	213	250	SF	6	\$690	
	Ceiling - Lay-in	221A office	150	SF	6	\$450	



1955 E 75th St Chicago, IL 60649

Building: Main

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments	
Adminis	Administrative Suites/Offices							
	Doors - Side-lite	221A office	8	SF	6	\$134		
	Doors - Transom Window	221A office	40	SF	6	\$677		
	Doors - Wood Doors inclu hw	221A office	1	EA	6	\$301		
	Floor - Tile	221A office	150	SF	6	\$328		
	Lighting - Lay-in	221A office	8	EA	6	\$952		
	Power Distribution	221A office	16	EA	6	\$33,998		
	Storage/ Closet	221A office	66	SF	6	\$479	221B storage	
	Walls - Plaster/Drywall	221A office	510	SF	6	\$1,408		
	Ceiling - Lay-in	313	210	SF	6	\$631		
	Doors - Side-lite	313	8	SF	6	\$134		
	Doors - Transom Window	313	8	SF	6	\$135		
	Doors - Wood Doors inclu hw	313	1	EA	6	\$301		
	Floor - Tile/Sheet	313	210	SF	6	\$210		
	Lighting - Lay-in	313	4	EA	7	\$0		
	Power Distribution	313	10	EA	6	\$21,249		
	Walls - Concrete Block	313	250	SF	6	\$733		
	Walls - Plaster/Drywall	313	250	SF	6	\$690		
	Ceiling - Lay-in	325 Science Prep	390	SF	6	\$1,171		
	Doors - Side-lite	325 Science Prep	8	SF	6	\$134		
	Doors - Transom Window	325 Science Prep	8	SF	6	\$135		
	Doors - Wood Doors inclu hw	325 Science Prep	1	EA	6	\$301		
	Floor - Tile/Sheet	325 Science Prep	390	SF	6	\$390		
	Lighting - Pendent/Surface	325 Science Prep	4	EA	7	\$0		
	Power Distribution	325 Science Prep	12	EA	7	\$0		
	Storage/ Closet	325 Science Prep	21	SF	6	\$152	Electrical closet in room	
	Walls - Concrete Block	325 Science Prep	110	SF	6	\$322		
	Walls - Plaster/Drywall	325 Science Prep	665	SF	6	\$1,835		
	Work Slnk	325 Science Prep	1	EA	6	\$508		
	Ceiling - Lay-in	329 Science Prep	390	SF	6	\$1,171		
	Doors - Side-lite	329 Science Prep	8	SF	6	\$134		
	Doors - Transom Window	329 Science Prep	8	SF	6	\$135		
	Doors - Wood Doors inclu hw	329 Science Prep	1	EA	6	\$301		
	Floor - Tile/Sheet	329 Science Prep	390	SF	6	\$390		
	Lighting - Pendent/Surface	329 Science Prep	4	EA	7	\$0		
	Power Distribution	329 Science Prep	16	EA	7	\$0		
	Storage/ Closet	329 Science Prep	15	SF	6	\$109		
	Walls - Concrete Block	329 Science Prep	141	SF	6	\$413		



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments	
Admini	Administrative Suites/Offices							
	Walls - Plaster/Drywall	329 Science Prep	725	SF	6	\$2,001		
	Work Slnk	329 Science Prep	1	EA	6	\$508		
Gymna	sia							
	Bleacher Seating	034 Gymnasia	50	EA	6	\$1,447		
	Ceiling - Exposed	034 Gymnasia	12,000	SF	6	\$17,846		
	Doors - Steel Doors incl hw	034 Gymnasia	8	EA	6	\$2,408		
	Floor - Wood	034 Gymnasia	12,000	SF	6	\$84,599		
	Lighting - Metal Halide/Sodium Vapor	034 Gymnasia	60	EA	6	\$8,023		
	Scoreboards	034 Gymnasia	2	EA	6	\$4,489		
	Sound System	034 Gymnasia	1	EA	6	\$41,654		
	Stage	034 Gymnasia	2,847	SF	6	\$16,448		
	Stage Curtain	034 Gymnasia	14	EA	6	\$0		
	Stage Lift	034 Gymnasia	1	EA	6	\$6,510		
	Stage Lighting System	034 Gymnasia	1	EA	6	\$12,369		
	Stage-Stairs - Terrazzo	034 Gymnasia	12	LF	7	\$0		
	Walls - Concrete Block	034 Gymnasia	5,440	SF	6	\$15,947		
	Walls - Metal Panel	034 Gymnasia	7,240	SF	6	\$54,044		
	Walls - Plaster/Drywall	034 Gymnasia	1,530	SF	6	\$4,223		
Kitcher	1							
	Ceiling - Lay-in	123 Servery Line	1,017	SF	6	\$3,054		
	Doors - Steel Doors incl hw	123 Servery Line	2	EA	6	\$602		
	Doors - Wood Doors inclu hw	123 Servery Line	4	EA	6	\$1,204		
	Floor - Epoxy/ Painted	123 Servery Line	1,017	SF	6	\$538		
	Lighting - Lay-in	123 Servery Line	16	EA	6	\$1,904		
	Serving Line	123 Servery Line	60	LF	6	\$3,571		
	Walls - Structural Glazed Tile	123 Servery Line	1,195	SF	6	\$3,759		
	Ceiling - Lay-in	125 Kitchen	1,209	SF	6	\$3,631		
	Doors - Steel Doors incl hw	125 Kitchen	3	EA	6	\$903		
	Floor - Terrazzo	125 Kitchen	1,209	SF	6	\$2,645		
	Lighting - Lay-in	125 Kitchen	16	EA	6	\$1,904		
	Walls - Concrete Block	125 Kitchen	3,022	SF	6	\$8,859		
Library			•			•		
	Casework	100 Library	275	LF	6	\$6,945		
	Ceiling - Lay-in	100 Library	365	SF	6	\$1,096		
	Ceiling - Splined	100 Library	5,555	SF	6	\$4,528		
	Doors - Side-lite	100 Library	5,353	SF	6	\$903		
	Doord Glacillo	100 Library	54	01	J	ψουσ		



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Library							
	Doors - Store Front	100 Library	6	EA	6	\$7,249	
	Doors - Transom Window	100 Library	12	SF	6	\$203	
	Floor - Carpet	100 Library	3,255	SF	6	\$6,935	
	Floor - Terrazzo	100 Library	2,300	SF	6	\$5,032	
	Lighting - Chandelier, Incandescent	100 Library	30	EΑ	6	\$14,327	
	Lighting - Pendent/Surface	100 Library	88	EΑ	6	\$10,903	
	Walls - Masonry	100 Library	1,790	SF	6	\$5,631	
	Walls - Plaster/Drywall	100 Library	1,790	SF	6	\$4,940	
Locker	Shower Room						
	Accessories	004C Boy's Locker Room	1,680	SF	6	\$6,583	
	Benches, ped mounted	004C Boy's Locker Room	160	LF	6	\$17,421	
	Ceiling - Plaster/ Drywall	004C Boy's Locker Room	2,310	SF	6	\$7,994	
	Doors - Steel Doors incl hw	004C Boy's Locker Room	2	EA	6	\$602	
	Floor Drain	004C Boy's Locker Room	6	EA	6	\$6,355	
	Floor - Concrete Epoxy/ Painted	004C Boy's Locker Room	2,130	SF	6	\$1,127	
	Floor - Tile Ceramic/ Porcelain	004C Boy's Locker Room	180	SF	6	\$381	
	Lighting - Lay-in	004C Boy's Locker Room	25	EΑ	6	\$2,974	
	Student Lockers - Two Tier	004C Boy's Locker Room	332	EΑ	6	\$15,411	
	Walls - Concrete Block	004C Boy's Locker Room	5,480	SF	6	\$16,065	
	Walls - Tile Ceramic/ Porcelain	004C Boy's Locker Room	310	SF	6	\$700	
	Accessories	004G-1 Men's Coach Locker	58	SF	6	\$227	
	Benches, ped mounted	004G-1 Men's Coach Locker	9	LF	6	\$980	
	Ceiling - Lay-In	004G-1 Men's Coach Locker	58	SF	6	\$174	
	Doors - Steel Doors incl hw	004G-1 Men's Coach Locker	1	EΑ	6	\$301	
	Floor Drain	004G-1 Men's Coach Locker	1	EΑ	6	\$1,059	
	Floor - Terrazzo	004G-1 Men's Coach Locker	58	SF	6	\$127	
	Lighting - Lay-in	004G-1 Men's Coach Locker	1	EA	6	\$119	
	Student Lockers - One Tier	004G-1 Men's Coach Locker	9	EA	6	\$836	
	Walls - Concrete Block	004G-1 Men's Coach Locker	145	SF	6	\$425	
	Accessories	007 Girl's Locker Room	900	SF	6	\$3,526	
	Benches, ped mounted	007 Girl's Locker Room	72	LF	6	\$7,839	
	Ceiling - Plaster/ Drywall	007 Girl's Locker Room	900	SF	6	\$3,115	
	Doors - Steel Doors incl hw	007 Girl's Locker Room	2	EA	6	\$602	
	Floor Drain	007 Girl's Locker Room	9	EA	6	\$9,532	
	Floor - Epoxy/ Painted	007 Girl's Locker Room	900	SF	6	\$476	
	Hand Dryer	007 Girl's Locker Room	2	EA	6	\$460	
	Lavatory	007 Girl's Locker Room	3	EΑ	6	\$959	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker	/Shower Room						
	Lighting - Lay-in	007 Girl's Locker Room	11	EA	6	\$1,309	
	Partitions	007 Girl's Locker Room	2	EA	6	\$594	
	Showers	007 Girl's Locker Room	5	EA	6	\$1,557	
	Student Lockers - Two Tier	007 Girl's Locker Room	128	EA	6	\$5,941	
	Walls - Concrete Block	007 Girl's Locker Room	2,100	SF	6	\$6,156	
	Walls - Tile Ceramic/ Porcelain	007 Girl's Locker Room	360	SF	6	\$813	
	Water Closet	007 Girl's Locker Room	3	EA	6	\$1,008	
	Accessories	009 Boy's Locker Room	900	SF	6	\$3,526	
	Benches, ped mounted	009 Boy's Locker Room	72	LF	6	\$7,839	
	Ceiling - Plaster/ Drywall	009 Boy's Locker Room	900	SF	6	\$3,115	
	Doors - Steel Doors incl hw	009 Boy's Locker Room	2	EA	6	\$602	
	Floor Drain	009 Boy's Locker Room	10	EA	6	\$10,592	
	Floor - Terrazzo	009 Boy's Locker Room	900	SF	6	\$1,969	
	Hand Dryer	009 Boy's Locker Room	2	EA	6	\$460	
	Lavatory	009 Boy's Locker Room	1	EA	6	\$320	basin
	Lighting - Lay-in	009 Boy's Locker Room	11	EA	6	\$1,309	
	Lighting - Lay-in	009 Boy's Locker Room	4	EA	6	\$476	can lights (recerssed)
	Partitions	009 Boy's Locker Room	2	EA	6	\$594	
	Showers	009 Boy's Locker Room	5	EA	6	\$1,557	
	Student Lockers - One Tier	009 Boy's Locker Room	130	EA	6	\$12,069	
	Urinals	009 Boy's Locker Room	1	EA	6	\$336	
	Walls - Concrete Block	009 Boy's Locker Room	2,100	SF	6	\$6,156	
	Walls - Tile Ceramic/ Porcelain	009 Boy's Locker Room	360	SF	6	\$813	
	Water Closet	009 Boy's Locker Room	2	EA	6	\$672	
Lunch	& Multipurpose Room						
	Ceiling - Exposed	121 Cafeteria	1,990	SF	6	\$2,960	
	Ceiling - Lay-in	121 Cafeteria	749	SF	6	\$2,249	
	Ceiling - Plaster/Drywall	121 Cafeteria	1,663	SF	6	\$5,755	
	Doors - Side-lite	121 Cafeteria	64	SF	6	\$1,070	
	Doors - Steel Doors incl hw	121 Cafeteria	4	EA	6	\$1,204	
	Doors - Transom Window	121 Cafeteria	24	SF	6	\$406	
	Floor - Terrazzo	121 Cafeteria	5,610	SF	6	\$12,274	
	Lighting - Chandelier, Incandescent	121 Cafeteria	26	EA	6	\$12,417	
	Lighting - Pendent/Surface	121 Cafeteria	46	EA	6	\$5,699	
	Walls - Plaster/Drywall	121 Cafeteria	8,400	SF	6	\$23,183	
	Walls - Structural Glazed Tile	121 Cafeteria	450	SF	6	\$1,416	
	Ceiling - Lay-in	121 Tray Drop-Off	373	SF	6	\$1,120	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch 8	& Multipurpose Room						
	Floor - Terrazzo	121 Tray Drop-Off	373	SF	7	\$0	
	Lighting - Pendent/Surface	121 Tray Drop-Off	5	EA	6	\$619	
	Walls - Structural Glazed Tile	121 Tray Drop-Off	820	SF	6	\$2,580	
MDF_ID	DF .						
	Doors - Wood Doors inclu hw	110 MDF_IDF	1	EA	6	\$301	
	Finishes	110 MDF_IDF	300	SF	6	\$2,141	
	Ventilation and Cooling	110 MDF_IDF	1	EA	6	\$1,855	
Mechar	nical/ Service Rooms						
	Janitor's Closet	1st Floor	94	SF	6	\$673	115B, 125C Janitor Closet
	Storage Room	1st Floor	1,408	SF	6	\$10,087	100C-1, 100F-2,103A, 125D, 126, 126A, 128 Storage
	Vaults	1st Floor	160	SF	6	\$1,146	122F Vault
	Interior Stairs	2nd Floor	3	LF	6	\$27	In rm 200H
	Janitor's Closet	2nd Floor	48	SF	6	\$344	233B janitor closet
	Mechanical/ Service Rooms	2nd Floor	30	SF	6	\$215	Electrical closet in rm 213
	Mechanical/ Service Rooms	2nd Floor	20	SF	6	\$143	Electrical closet in room 234
	Mechanical/ Service Rooms	2nd Floor	21	SF	6	\$150	Electrical closet in prep rm 225
	Mechanical/ Service Rooms	2nd Floor	40	SF	6	\$287	Electrical closet at girls restroom 214A
	Storage Room	2nd Floor	167	SF	6	\$1,196	200B-1
	Storage Room	2nd Floor	110	SF	6	\$788	200H-4
	Storage Room	2nd Floor	80	SF	6	\$573	200F-1 Insturment storage
	Storage Room	2nd Floor	80	SF	6	\$573	
	Storage Room	2nd Floor	28	SF	6	\$201	200E
	Storage Room	2nd Floor	28	SF	6	\$201	Next to 200B
	Storage Room	2nd Floor	75	SF	6	\$537	Storage rm at stairwell behind elevator
	Storage Room	2nd Floor	33	SF	6	\$236	Next to 200H
	Storage Room	2nd Floor	167	SF	6	\$1,196	200D-1
	Janitor's Closet	3rd Floor	48	SF	6	\$344	Rm 333B
	Mechanical/ Service Rooms	3rd Floor	26	SF	6	\$186	In rm 334
	Mechanical/ Service Rooms	3rd Floor	29	SF	6	\$208	Electrical closet in prep rm 325
	Mechanical/ Service Rooms	3rd Floor	29	SF	6	\$208	Rm313A (electrical closet)
	Mechanical/ Service Rooms	3rd Floor	40	SF	6	\$287	Rm 314B (electrical closet)
	Storage Room	3rd Floor	75	SF	6	\$537	Next to stairs to penthouse, back side of elevator
	Mechanical/ Service Rooms	4th Floor	3,990	SF	6	\$28,586	
	Loading Docks	Basement	1,340	SF	6	\$9,600	South
	Mechanical/ Service Rooms	Basement	6,819	SF	6	\$48,853	Mechanical Room, Pool Equipment
	Storage Room	Basement	5,944	SF	6	\$42,585	000, 000A, 000C, 003B, 003C, 004E, 012 Storage



1955 E 75th St Chicago, IL 60649

Building: Main

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
lechan	nical/ Service Rooms						
	Storage Room	Basement	395	SF	6	\$2,830	Outside yard storage
	Vaults	Basement	129	SF	6	\$924	003A, Vaults
	Interior Stairs	Penthouse	30	LF	6	\$271	
	Mechanical/ Service Rooms	Penthouse	800	SF	6	\$5,731	
ool & l	Natatorium						
	Accessories	007 Pool Basement 109 Pool Observation Deck 1st floor	6,690	SF	6	\$4,592	
	Bleachers Seating/Plank Seating	007 Pool Basement 109 Pool Observation Deck 1st floor	18	EA	6	\$521	
	Ceiling - Exposed	007 Pool Basement 109 Pool Observation Deck 1st floor	6,690	SF	6	\$9,949	
	Doors - Steel Doors incl hw	007 Pool Basement 109 Pool Observation Deck 1st floor	3	EA	6	\$903	
	Floor - Concrete Epoxy/ Painted	007 Pool Basement 109 Pool Observation Deck 1st floor	500	SF	7	\$0	Pool Observation deck
	Floor - Tile Ceramic/ Porcelain	007 Pool Basement 109 Pool Observation Deck 1st floor	6,190	SF	6	\$13,101	
	Lighting - Pendent/Surface	007 Pool Basement 109 Pool Observation Deck 1st floor	29	EA	6	\$3,593	
	Pool Basin	007 Pool Basement 109 Pool Observation Deck 1st floor	4,099	SF	6	\$138,685	
	Pool Deck	007 Pool Basement 109 Pool Observation Deck 1st floor	1,212	SF	6	\$11,508	
	Pool Deck Drains	007 Pool Basement 109 Pool Observation Deck 1st floor	12	EA	6	\$5,065	
	Walls - Concrete Block	007 Pool Basement 109 Pool Observation Deck 1st floor	2,257	SF	6	\$6,616	
rep Ro	oom						
	Casework	225 prep room, in rm 225	40	LF	6	\$1,010	
	Ceiling - Exposed	225 prep room, in rm 225	422	SF	6	\$628	
	Doors - Side-lite	225 prep room, in rm 225	8	SF	6	\$134	
	Doors - Transom Window	225 prep room, in rm 225	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	225 prep room, in rm 225	1	EA	6	\$301	
	Floor - Tile/Sheet	225 prep room, in rm 225	422	SF	6	\$422	
	Lighting - Pendent/Surface	225 prep room, in rm 225	4	EA	7	\$0	
	Walls - Concrete Block	225 prep room, in rm 225	165	SF	6	\$484	
	Walls - Plaster/Drywall	225 prep room, in rm 225	912	SF	6	\$2,517	
	Walls - Structural Glazed Tile	225 prep room, in rm 225	30	SF	6	\$94	
	Work Sink	225 prep room, in rm 225	1	EΑ	6	\$379	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Prep R	oom						
	Casework	229 prep room, in rm 229	42	LF	6	\$1,061	
	Ceiling - Exposed	229 prep room, in rm 229	413	SF	6	\$614	
	Doors - Side-lite	229 prep room, in rm 229	8	SF	6	\$134	
	Doors - Transom Window	229 prep room, in rm 229	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	229 prep room, in rm 229	1	EA	6	\$301	
	Floor - Tile/Sheet	229 prep room, in rm 229	413	SF	6	\$413	
	Lighting - Pendent/Surface	229 prep room, in rm 229	4	EA	7	\$0	
	Walls - Concrete Block	229 prep room, in rm 229	160	SF	6	\$469	
	Walls - Plaster/Drywall	229 prep room, in rm 229	917	SF	6	\$2,531	
	Walls - Structural Glazed Tile	229 prep room, in rm 229	30	SF	6	\$94	
	Work Sink	229 prep room, in rm 229	1	EA	6	\$379	
	Casework	325 prep room, in rm 325	40	LF	6	\$1,010	
	Ceiling - Exposed	325 prep room, in rm 325	422	SF	6	\$628	
	Doors - Side-lite	325 prep room, in rm 325	8	SF	6	\$134	
	Doors - Transom Window	325 prep room, in rm 325	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	325 prep room, in rm 325	1	EA	6	\$301	
	Floor - Tile/Sheet	325 prep room, in rm 325	422	SF	6	\$422	
	Lighting - Pendent/Surface	325 prep room, in rm 325	4	EA	7	\$0	
	Walls - Concrete Block	325 prep room, in rm 325	165	SF	6	\$484	
	Walls - Plaster/Drywall	325 prep room, in rm 325	912	SF	6	\$2,517	
	Walls - Structural Glazed Tile	325 prep room, in rm 325	30	SF	6	\$94	
	Work Sink	325 prep room, in rm 325	1	EA	6	\$379	
	Casework	329 prep room, in rm 329	42	LF	6	\$1,061	
	Ceiling - Exposed	329 prep room, in rm 329	413	SF	6	\$614	
	Doors - Side-lite	329 prep room, in rm 329	8	SF	6	\$134	
	Doors - Transom Window	329 prep room, in rm 329	8	SF	6	\$135	
	Doors - Wood Doors inclu hw	329 prep room, in rm 329	1	EA	6	\$301	
	Floor - Tile/Sheet	329 prep room, in rm 329	413	SF	6	\$413	
	Lighting - Pendent/Surface	329 prep room, in rm 329	4	EA	7	\$0	
	Walls - Concrete Block	329 prep room, in rm 329	160	SF	6	\$469	
	Walls - Plaster/Drywall	329 prep room, in rm 329	917	SF	6	\$2,531	
	Walls - Structural Glazed Tile	329 prep room, in rm 329	30	SF	6	\$94	
	Work Sink	329 prep room, in rm 329	1	EA	6	\$379	
Restro	om						
	Accessories	004A Boy's Toilet	163	SF	6	\$1,503	
	Ceiling - Plaster/Drywall	004A Boy's Toilet	163	SF	6	\$564	
	Doors - Steel Doors incl hw	004A Boy's Toilet	1	EA	6	\$301	



1955 E 75th St Chicago, IL 60649

Building: Main

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Floor Drain	004A Boy's Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	004A Boy's Toilet	163	SF	7	\$0	
	Hand Dryer	004A Boy's Toilet	1	EA	6	\$230	
	Lavatory	004A Boy's Toilet	1	EA	6	\$320	Basin
	Lighting - Chandelier, Incandescent	004A Boy's Toilet	3	EA	6	\$1,433	
	Lighting - Lay-in	004A Boy's Toilet	5	EA	6	\$595	
	Partitions	004A Boy's Toilet	2	EA	6	\$594	
	Urinals	004A Boy's Toilet	1	EA	6	\$336	
	Walls - Structural Glazed Tile	004A Boy's Toilet	473	SF	6	\$1,488	
	Water Closet	004A Boy's Toilet	2	EA	6	\$672	
	Accessories	004B Boy's Toilet	200	SF	6	\$1,845	
	Ceiling - Plaster/Drywall	004B Boy's Toilet	200	SF	6	\$692	
	Floor Drain	004B Boy's Toilet	1	EA	6	\$1,059	
	Floor - Terrazzo	004B Boy's Toilet	200	SF	7	\$0	
	Hand Dryer	004B Boy's Toilet	1	EA	6	\$230	
	Lavatory	004B Boy's Toilet	1	EA	6	\$320	Basin
	Lighting - Lay-in	004B Boy's Toilet	2	EA	6	\$238	
	Partitions	004B Boy's Toilet	2	EA	6	\$594	
	Urinals	004B Boy's Toilet	2	EA	6	\$672	
	Walls - Structural Glazed Tile	004B Boy's Toilet	540	SF	6	\$1,699	
	Water Closet	004B Boy's Toilet	2	EA	6	\$672	
	Accessories	004G-1A Men's Coach Shower	68	SF	6	\$627	
	Ceiling - Lay-in	004G-1A Men's Coach Shower	68	SF	6	\$204	
	Doors - Steel Doors incl hw	004G-1A Men's Coach Shower	1	EA	6	\$301	
	Floor Drain	004G-1A Men's Coach Shower	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	004G-1A Men's Coach Shower	68	SF	6	\$144	
	Lighting - Pendent/Surface	004G-1A Men's Coach Shower	1	EA	6	\$124	
	Showers	004G-1A Men's Coach Shower	1	EA	6	\$311	
	Walls - Concrete Block	004G-1A Men's Coach Shower	289	SF	6	\$847	
	Water Closet	004G-1A Men's Coach Shower	1	EA	6	\$336	
	Accessories	100D Men's Toilet	67	SF	6	\$618	
	Ceiling - Plaster/Drywall	100D Men's Toilet	67	SF	6	\$232	
	Doors - Wood Doors inclu hw	100D Men's Toilet	1	EA	6	\$301	
	Floor Drain	100D Men's Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	100D Men's Toilet	67	SF	6	\$142	
	Lavatory	100D Men's Toilet	1	EA	6	\$320	
	Lighting - Lay-in	100D Men's Toilet	1	EA	6	\$119	



1955 E 75th St Chicago, IL 60649

Building: Main

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
estro	om						
	Walls - Structural Glazed Tile	100D Men's Toilet	250	SF	6	\$787	
	Water Closet	100D Men's Toilet	1	EA	6	\$336	
	Accessories	100E Women's Toilet	67	SF	6	\$618	
	Ceiling - Plaster/Drywall	100E Women's Toilet	67	SF	6	\$232	
	Doors - Wood Doors inclu hw	100E Women's Toilet	1	EA	6	\$301	
	Floor Drain	100E Women's Toilet	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	100E Women's Toilet	67	SF	6	\$142	
	Lavatory	100E Women's Toilet	1	EΑ	6	\$320	
	Lighting - Lay-in	100E Women's Toilet	1	EΑ	6	\$119	
	Walls - Concrete Block	100E Women's Toilet	250	SF	6	\$733	
	Water Closet	100E Women's Toilet	1	EA	6	\$336	
	Accessories	114A Girl's Toilet	830	SF	6	\$7,656	
	Ceiling - Lay-in	114A Girl's Toilet	830	SF	6	\$2,492	
	Floor Drain	114A Girl's Toilet	2	EΑ	6	\$2,118	
	Floor - Terrazzo	114A Girl's Toilet	830	SF	6	\$1,816	
	Hand Dryer	114A Girl's Toilet	5	EΑ	6	\$1,150	
	Lavatory	114A Girl's Toilet	1	EA	6	\$320	Basin
	Lighting - Lay-in	114A Girl's Toilet	13	EA	6	\$1,547	
	Partitions	114A Girl's Toilet	17	EA	6	\$5,048	
	Walls - Structural Glazed Tile	114A Girl's Toilet	2,050	SF	6	\$6,449	
	Water Closet	114A Girl's Toilet	17	EA	6	\$5,712	
	Accessories	114B Unisex Toilet	45	SF	6	\$415	
	Ceiling - Lay-in	114B Unisex Toilet	45	SF	6	\$135	
	Doors - Wood Doors inclu hw	114B Unisex Toilet	1	EA	6	\$301	
	Floor Drain	114B Unisex Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	114B Unisex Toilet	45	SF	6	\$95	
	Lavatory	114B Unisex Toilet	1	EA	6	\$320	
	Lighting - Lay-in	114B Unisex Toilet	1	EA	6	\$119	
	Walls - Concrete Block	114B Unisex Toilet	225	SF	6	\$660	
	Water Closet	114B Unisex Toilet	1	EA	6	\$336	
	Accessories	115A Boy's Toilet	830	SF	6	\$7,656	
	Ceiling - Lay-in	115A Boy's Toilet	830	SF	6	\$2,492	
	Floor Drain	115A Boy's Toilet	2	EA	6	\$2,118	
	Floor - Terrazzo	115A Boy's Toilet	830	SF	7	\$0	
	Hand Dryer	115A Boy's Toilet	5	EA	6	\$1,150	
	Lavatory	115A Boy's Toilet	1	EA	6	\$320	Basin
	Lighting - Lay-in	115A Boy's Toilet	13	EΑ	6	\$1,547	



1955 E 75th St Chicago, IL 60649

Building: Main

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom						
Partitions	115A Boy's Toilet	10	EA	6	\$2,969	
Urinals	115A Boy's Toilet	6	EA	6	\$2,016	
Walls - Structural Glazed Tile	115A Boy's Toilet	2,050	SF	6	\$6,449	
Water Closet	115A Boy's Toilet	10	EA	6	\$3,360	
Accessories	120G Unisex Toilet	67	SF	6	\$618	
Ceiling - Lay-in	120G Unisex Toilet	67	SF	6	\$201	
Doors - Wood Doors inclu hw	120G Unisex Toilet	1	EA	6	\$301	
Floor Drain	120G Unisex Toilet	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	120G Unisex Toilet	67	SF	6	\$142	
Lavatory	120G Unisex Toilet	1	EA	6	\$320	
Lighting - Lay-in	120G Unisex Toilet	1	EA	6	\$119	
Walls - Concrete Block	120G Unisex Toilet	250	SF	6	\$733	
Water Closet	120G Unisex Toilet	1	EA	6	\$336	
Accessories	125B Unisex Toilet	45	SF	6	\$415	
Ceiling - Lay-in	125B Unisex Toilet	45	SF	6	\$135	
Doors - Steel Doors incl hw	125B Unisex Toilet	1	EA	6	\$301	
Floor Drain	125B Unisex Toilet	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	125B Unisex Toilet	45	SF	6	\$95	
Lavatory	125B Unisex Toilet	1	EA	6	\$320	
Lighting - Lay-in	125B Unisex Toilet	1	EA	6	\$119	
Walls - Concrete Block	125B Unisex Toilet	225	SF	6	\$660	
Water Closet	125B Unisex Toilet	1	EA	6	\$336	
Accessories	128H Unisex Toilet	125	SF	6	\$1,153	
Ceiling - Plaster/Drywall	128H Unisex Toilet	125	SF	6	\$433	
Doors - Wood Doors inclu hw	128H Unisex Toilet	1	EA	6	\$301	
Floor Drain	128H Unisex Toilet	2	EA	6	\$2,118	
Floor - Tile Ceramic/ Porcelain	128H Unisex Toilet	125	SF	6	\$265	
Lavatory	128H Unisex Toilet	1	EA	6	\$320	
Lighting - Lay-in	128H Unisex Toilet	2	EA	6	\$238	
Showers	128H Unisex Toilet	1	EA	6	\$311	
Walls - Tile Ceramic/ Porcelain	128H Unisex Toilet	432	SF	6	\$976	
Water Closet	128H Unisex Toilet	1	EA	6	\$336	
Accessories	214A Girls restroom	285	SF	6	\$2,629	
Ceiling - Plaster/Drywall	214A Girls restroom	285	SF	6	\$986	
Floor Drain	214A Girls restroom	1	EA	6	\$1,059	
Floor - Terrazzo	214A Girls restroom	285	SF	7	\$0	
Hand Dryer	214A Girls restroom	3	EA	6	\$690	



1955 E 75th St Chicago, IL 60649

Building: Main

Restriction Lighting - Lay-in 214A Gilfs restroom 10 EA 7 S0 Can light		Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lighting - Lay-in 214A Girls mastroom 10 EA 7 \$0	-			•				
Lighting - Lay-in 214A Girls restroom 1 EA 7 \$ \$ 0 Can light		Lavatory	214A Girls restroom	1	EA	6	\$320	Basin
Lighting - Lay-in 214A Girls mestroom 1 EA 7 \$ 0 Can light		Lighting - Lay-in	214A Girls restroom	10	EA	7	\$0	
Partitions			214A Girls restroom	1	EA	7	\$0	Can light
Water Closet 214A Cirits restroom 6 EA 6 \$2,016 Accessories 214C Boys restroom 285 SF 6 \$2,629 Celling - Plaster/Drywell 214C Boys restroom 285 SF 6 \$3,986 Floor Dear 214C Boys restroom 1 EA 6 \$1,059 Hand Dryer 214C Boys restroom 3 EA 6 \$600 Lavatory 214C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 214C Boys restroom 10 EA 7 \$0 Partitions 214C Boys restroom 10 EA 7 \$0 Waller - Structural Glazed Tile 214C Boys restroom 10 EA 7 \$0 Water Closet 214C Boys restroom 30 EA 6 \$1,008 Water Closet 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214C Boys restroom 780 SF 6 \$1,008 <			214A Girls restroom	6	EA	6	\$1,782	
Accessories 214C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 214C Boys restroom 285 SF 6 \$3986 Floor Drain 214C Boys restroom 285 SF 6 \$3986 Floor - Terrazzo 214C Boys restroom 285 SF 7 \$0 Hand Dryer 214C Boys restroom 3 EA 6 \$500 Lavatory 214C Boys restroom 3 EA 6 \$500 Lavatory 214C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 214C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 214C Boys restroom 1 EA 7 \$0 Partitions 214C Boys restroom 3 EA 6 \$1,188 Urinals 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 3 EA 6 \$1,008 Accessories 214D Staff 45 SF 6 \$415 Ceiling - Lay-in 214D Staff 1 EA 6 \$301 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor Drain 214D Staff 1 EA 6 \$305 Floor - Tile Ceramic/ Porcelain 214D Staff 1 EA 6 \$305 Lavatory 214D Staff 1 EA 6 \$306 Water Closet 214D Staff 1 EA 6 \$306 Water		Walls - Structural Glazed Tile	214A Girls restroom	780	SF	6	\$2,454	
Celling - Plaster/Drywall 214C Boys restroom 285 SF 6 \$9,868 Floor Tarin 214C Boys restroom 285 SF 7 \$0 Hand Dryer 214C Boys restroom 285 SF 7 \$0 Lavetory 214C Boys restroom 1 EA 6 \$890 Lighting - Lay-in 214C Boys restroom 1 EA 6 \$30 Basin Urinals 214C Boys restroom 1 EA 6 \$10 Basin Urinals 214C Boys restroom 1 EA 6 \$1,08 \$1 Urinals 214C Boys restroom 3 EA 6 \$1,08 \$1 Walls - Structural Glazed Tile 214C Boys restroom 38 EA 6 \$1,008 \$1 Water Closet 214C Boys restroom 38 EA 6 \$1,008 \$1 \$6 \$1,008 \$1,008 \$1,008 \$1,008 \$1,008 \$1,008 \$1,008 \$1,008 \$1,008 \$1,008		Water Closet	214A Girls restroom	6	EA	6	\$2,016	
Floor Drain		Accessories	214C Boys restroom	285	SF	6	\$2,629	
Floor - Terrazzo		Ceiling - Plaster/Drywall	214C Boys restroom	285	SF	6	\$986	
Hand Dryer		Floor Drain	214C Boys restroom	1	EΑ	6	\$1,059	
Lavatory 214C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 214C Boys restroom 1 EA 7 \$0 Can light Lighting - Lay-in 214C Boys restroom 1 EA 7 \$0 Can light Lighting - Lay-in 214C Boys restroom 1 EA 7 \$0 Partitions 214C Boys restroom 4 EA 6 \$1,188 Urinals 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214C Boys restroom 3 EA 6 \$1,008 Accessories 214D Staff 45 SF 6 \$415 Celling - Lay-in 214D Staff 45 SF 6 \$415 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$310 Floor Train 214D Staff 1 EA 6 \$310 Floor Trile Ceramic/ Porcelain 214D Staff 1 EA 6 \$30 Layatory 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 6 \$320 Celling - Plaster/Drywall 233A Giffs restroom 285 SF 6 \$2,629 Celling - Plaster/Drywall 233A Giffs restroom 285 SF 7 \$0 Hand Dryer 233A Giffs restroom 3 EA 6 \$990 Layatory 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lay-in 233A Giffs restroom 1 EA 7 \$0 Lay-in 233A Giffs restroom 1 EA 7 \$0 Lay-in 233A Giffs restroom 1 EA 6 \$320 Celling - Plaster/Drywall 233A Giffs restroom 1 EA 7 \$0 Lay-in 233A Giffs restroom 1 EA 6 \$990 Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 7 \$0 Lighting - Lay-in 233A Giffs restroom 1 EA 6 \$1,782		Floor - Terrazzo	214C Boys restroom	285	SF	7	\$0	
Lighting - Lay-in 214C Boys restroom 1 EA 7 \$0 Can light Lighting - Lay-in 214C Boys restroom 10 EA 7 \$0 Partitions 214C Boys restroom 4 EA 6 \$1,108 Urinals 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 780 SF 6 \$2,464 Water Closet 214D Staff 45 SF 6 \$1,008 Accessories 214D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$1,059 Floor - Tile Ceramic/ Porcelain 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Waler Closet 214D Staff 1 EA 7 \$0 W		Hand Dryer	214C Boys restroom	3	EA	6	\$690	
Lighting - Lay-in 214C Boys restroom 10 EA 7 \$0 Partitions 214C Boys restroom 4 EA 6 \$1,188 Urinals 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214D Staff 45 SF 6 \$1,008 Accessories 214D Staff 45 SF 6 \$135 Celling - Lay-in 214D Staff 1 EA 6 \$301 Floor - Tile Ceramic/ Porcelain 214D Staff 1 EA 6 \$301 Floor - Tile Ceramic/ Porcelain 214D Staff 1 EA 6 \$320 Layatory 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 7 \$0 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Gir		Lavatory	214C Boys restroom	1	EA	6	\$320	Basin
Partitions 214C Boys restroom 4 EA 6 \$1,188 Urinals 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214C Boys restroom 3 EA 6 \$1,008 Accessories 214D Staff 45 SF 6 \$415 Ceiling - Lay-in 214D Staff 45 SF 6 \$331 Floor Drain 214D Staff 1 EA 6 \$1,059 Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$320 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 6 \$320 Walls - Closet 214D Staff 1 EA 6 \$320 Walls - Closet 214D Staff 1 EA 6 \$320 Water Closet 214D Staff <		Lighting - Lay-in	214C Boys restroom	1	EA	7	\$0	Can light
Urinals 214C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214D Staff 45 SF 6 \$415 Ceiling - Lay-in 214D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor - Tile Ceramic/ Porcelain 214D Staff 1 EA 6 \$320 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 7 \$0 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$960 Floor - Terrazzo 233A		Lighting - Lay-in	214C Boys restroom	10	EA	7	\$0	
Walls - Structural Glazed Tile 214C Boys restroom 780 SF 6 \$2,454 Water Closet 214C Boys restroom 3 EAA 6 \$1,008 Accessories 214D Staff 45 SF 6 \$415 Ceiling - Lay-in 214D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$350 Floor Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 6 \$320 Water Closet 214D Staff 25 SF 6 \$60 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$986 Floor Terrazzo		Partitions	214C Boys restroom	4	EA	6	\$1,188	
Water Closet 214C Bøys restroom 3 EA 6 \$1,008 Accessories 214D Staff 45 SF 6 \$415 Ceiling - Lay-in 214D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor - Tile Ceramic/ Porcelain 214D Staff 1 EA 6 \$1,059 Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 6 \$320 Walls - Concrete Block 214D Staff 25 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$660 Celling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 285 SF 7 \$0 Lay-in 233A Girls restroom 1 EA 6 \$320 Lay-in 233A Girls restro		Urinals	214C Boys restroom	3	EA	6	\$1,008	
Accessories 214D Staff 45 SF 6 \$415 Ceiling - Lay-in 214D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor Drain 214D Staff 1 EA 6 \$10,59 Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 6 \$336 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$320 Basin Ligh		Walls - Structural Glazed Tile	214C Boys restroom	780	SF	6	\$2,454	
Ceiling - Lay-in 214D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor Drain 214D Staff 1 EA 6 \$1,059 Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$330 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 1 EA 6 \$330 Water Closet 214D Staff 1 EA 6 \$360 Water Closet 214D Staff 1 EA 6 \$360 Accessories 233A Girls restroom 285 SF 6 \$260 Geiling - Plaster/Drywall 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 3 EA 6 \$60 Hand Dryer 233A Girls restr		Water Closet	214C Boys restroom	3	EA	6	\$1,008	
Doors - Wood Doors inclu hw 214D Staff 1 EA 6 \$301 Floor Drain 214D Staff 1 EA 6 \$1,059 Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 225 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$320 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting		Accessories	214D Staff	45	SF	6	\$415	
Floor Drain 214D Staff 1 EA 6 \$1,059 Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 225 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 234A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 285 SF 7 \$0 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$990 Lavatory 233A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Layatory 233A Girls restroom 233A Gi		Ceiling - Lay-in	214D Staff	45	SF	6	\$135	
Floor - Tile Ceramic/ Porcelain 214D Staff 45 SF 6 \$95 Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Water Closet 214D Staff 225 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 285 SF 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Layatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Can light <		Doors - Wood Doors inclu hw	214D Staff	1	EA	6	\$301	
Lavatory 214D Staff 1 EA 6 \$320 Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 225 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 6 EA 6 \$1,782 <td></td> <td>Floor Drain</td> <td>214D Staff</td> <td>1</td> <td>EA</td> <td>6</td> <td>\$1,059</td> <td></td>		Floor Drain	214D Staff	1	EA	6	\$1,059	
Lighting - Lay-in 214D Staff 1 EA 7 \$0 Walls - Concrete Block 214D Staff 225 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Partitions 233A Girls restroom 6 EA 6 \$1,782		Floor - Tile Ceramic/ Porcelain	214D Staff	45	SF	6	\$95	
Walls - Concrete Block 214D Staff 225 SF 6 \$660 Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782 \$0		Lavatory	214D Staff	1	EA	6	\$320	
Water Closet 214D Staff 1 EA 6 \$336 Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Lighting - Lay-in	214D Staff	1	EA	7	\$0	
Accessories 233A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Walls - Concrete Block	214D Staff	225	SF	6	\$660	
Ceiling - Plaster/Drywall 233A Girls restroom 285 SF 6 \$986 Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Water Closet	214D Staff	1	EA	6	\$336	
Floor Drain 233A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Accessories	233A Girls restroom	285	SF	6	\$2,629	
Floor - Terrazzo 233A Girls restroom 285 SF 7 \$0 Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Ceiling - Plaster/Drywall	233A Girls restroom	285	SF	6	\$986	
Hand Dryer 233A Girls restroom 3 EA 6 \$690 Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Floor Drain	233A Girls restroom	1	EA	6	\$1,059	
Lavatory 233A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 233A Girls restroom 10 EA 7 \$0 Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Floor - Terrazzo	233A Girls restroom	285	SF	7	\$0	
Lighting - Lay-in233A Girls restroom10 EA 7\$0Lighting - Lay-in233A Girls restroom1 EA 7\$0 Can lightPartitions233A Girls restroom6 EA 6\$1,782		Hand Dryer	233A Girls restroom	3	EA	6	\$690	
Lighting - Lay-in 233A Girls restroom 1 EA 7 \$0 Can light Partitions 233A Girls restroom 6 EA 6 \$1,782		Lavatory	233A Girls restroom	1	EA	6	\$320	Basin
Partitions 233A Girls restroom 6 EA 6 \$1,782		Lighting - Lay-in	233A Girls restroom	10	EA	7	\$0	
• •		Lighting - Lay-in	233A Girls restroom	1	EA	7	\$0	Can light
Walls - Structural Glazed Tile 233A Girls restroom 780 SF 6 \$2,454		Partitions	233A Girls restroom	6	EA	6	\$1,782	
		Walls - Structural Glazed Tile	233A Girls restroom	780	SF	6	\$2,454	



1955 E 75th St Chicago, IL 60649

Building: Main

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
estroor							
	Water Closet	233A Girls restroom	6	EA	6	\$2,016	
	Accessories	233C Boys restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	233C Boys restroom	285	SF	6	\$986	
	Floor Drain	233C Boys restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	233C Boys restroom	285	SF	7	\$0	
	Hand Dryer	233C Boys restroom	3	EA	6	\$690	
	Lavatory	233C Boys restroom	1	EA	6	\$320	Basin
	Lighting - Lay-in	233C Boys restroom	10	EA	7	\$0	
	Lighting - Lay-in	233C Boys restroom	1	EA	7	\$0	Can light
	Partitions	233C Boys restroom	4	EA	6	\$1,188	
	Walls - Structural Glazed Tile	233C Boys restroom	780	SF	6	\$2,454	
	Water Closet	233C Boys restroom	3	EA	6	\$1,008	
	Accessories	233D Staff	45	SF	6	\$415	
	Ceiling - Lay-in	233D Staff	45	SF	6	\$135	
	Doors - Wood Doors inclu hw	233D Staff	1	EA	6	\$301	
	Floor Drain	233D Staff	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	233D Staff	45	SF	6	\$95	
	Lavatory	233D Staff	1	EA	6	\$320	
	Lighting - Lay-in	233D Staff	1	EA	7	\$0	
	Walls - Concrete Block	233D Staff	225	SF	6	\$660	
	Water Closet	233D Staff	1	EA	6	\$336	
	Accessories	314A Girls restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	314A Girls restroom	285	SF	6	\$986	
	Floor Drain	314A Girls restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	314A Girls restroom	285	SF	7	\$0	
	Hand Dryer	314A Girls restroom	3	EA	6	\$690	
	Lavatory	314A Girls restroom	1	EA	6	\$320	Basin
	Lighting - Lay-in	314A Girls restroom	1	EA	7	\$0	Can light
	Lighting - Lay-in	314A Girls restroom	10	EA	7	\$0	
	Partitions	314A Girls restroom	6	EA	6	\$1,782	
	Walls - Structural Glazed Tile	314A Girls restroom	780	SF	6	\$2,454	
	Water Closet	314A Girls restroom	6	EA	6	\$2,016	
	Accessories	314C Boys restroom	285	SF	6	\$2,629	
	Ceiling - Plaster/Drywall	314C Boys restroom	285	SF	6	\$986	
	Floor Drain	314C Boys restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	314C Boys restroom	285	SF	7	\$0	



1955 E 75th St Chicago, IL 60649

Building: Main

Lavatory	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments		
Lighting - Lay-in 314C Boys restroom 10 EA 7 \$0 Can light Lighting - Lay-in 314C Boys restroom 1 EA 7 \$0 Can light Partitions 314C Boys restroom 4 EA 6 \$1,108 Can light Partitions 314C Boys restroom 780 SE 6 \$1,008 Can light Can light	m								
Lighting - Lay-in 314C Boys restroom 4 EA 7 \$0 Can light Partitions 314C Boys restroom 48 6 \$1,108 Walls - Structural Glazed Tile 314C Boys restroom 780 \$F 6 \$2,454 Waler Closet 314C Boys restroom 780 \$F 6 \$2,454 Waler Closet 314D Staff 45 \$F 6 \$1,008 Accessorius 314D Staff 45 \$F 6 \$1,009 Ploor Train 314D Staff 45 \$F 6 \$301 Floor Tille Ceranic/ Porcelain 314D Staff 45 \$F 6 \$302 Floor Tille Ceranic/ Porcelain 314D Staff 45 \$F 6 \$302 Valler Closet 314D Staff 45 \$F 6 \$302 Walls - Concrete Block 314D Staff 15 \$F 6 \$302 Waller Closet 314D Staff 25 \$F 6 \$560 Waler Closet	Lavatory	314C Boys restroom	1	EA	6	\$320	Basin		
Partitions 314C Boys restroom 4 EA 6 \$1,108 Urinals 314C Boys restroom 3 EA 6 \$1,008 Walls - Structural Glazed Tile 314C Boys restroom 780 SF 6 \$2,464 Water Closet 314D Staff 45 SF 6 \$1,008 Accessories 314D Staff 45 SF 6 \$13,05 Doors - Wood Doors inclu hw 314D Staff 1 EA 6 \$3,05 Floor Train 314D Staff 1 EA 6 \$3,05 Floor Drain 314D Staff 1 EA 6 \$3,05 Floor Drain 314D Staff 1 EA 6 \$3,05 Lavatory 314D Staff 1 EA 6 \$3,30 Walls - Concrete Block 314D Staff 1 EA 6 \$3,30 Walls - Concrete Block 314D Staff 1 EA 6 \$3,30 Walls - Custor 334D Staff	Lighting - Lay-in	314C Boys restroom	10	EA	7	\$0			
Urinals 314C Boys restroom 38 EA 6 \$1,008 Walls - Structural Glazed Tile 314C Boys restroom 78 5F 6 \$2,454 Walls - Structural Glazed Tile 314C Boys restroom 3 EA 6 \$1,008 Accessories 314D Staff 45 SF 6 \$415 Ceiling - Lay-in 314D Staff 15 SF 6 \$301 Floor - Tille Ceramic/ Porcelain 314D Staff 1 EA 6 \$95 Floor - Tille Ceramic/ Porcelain 314D Staff 1 EA 6 \$95 Lighting - Lay-in 314D Staff 1 EA 6 \$95 Lighting - Concrete Block 314D Staff 25 SF 6 \$60 Walls - Concrete Block 314D Staff 225 SF 6 \$60 Walls - Concrete Block 314D Staff 225 SF 6 \$60 Walls - Concrete Block 314D Staff 225 SF 6 \$60	Lighting - Lay-in	314C Boys restroom	1	EA	7	\$0	Can light		
Walls - Structural Glazed Tile 314C Boys restroom 780 SF 6 \$2,454 Water Closet 314C Boys restroom 3 EA 6 \$1,008 Accessories 314D Staff 45 SF 6 \$415 Ceiling - Lay-in 314D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 314D Staff 1 EA 6 \$301 Floor - Tile Ceramic/ Porcelain 314D Staff 45 SF 6 \$320 Lavatory 314D Staff 1 EA 6 \$320 Lavatory 314D Staff 1 EA 6 \$320 Walls - Concrete Block 314D Staff 25 SF 6 \$660 Water Closet 314D Staff 25 SF 6 \$660 Water Closet 314D Staff 28 SF 6 \$2629 Ceiling - Plaster/Dywall 333A Girls restroom 285 SF 6 \$860 Floor Drain 3	Partitions	314C Boys restroom	4	EA	6	\$1,188			
Walls - Structural Glazed Tile 314C Boys restroom 780 SF 6 \$2,454 Water Closet 314D Staff 45 \$F 6 \$1,008 Accessories 314D Staff 45 \$F 6 \$415 Celling - Lay-in 314D Staff 45 \$F 6 \$135 Doors - Wood Doors inclu hw 314D Staff 1 EA 6 \$1,059 Floor Tille Ceramic/ Porcelain 314D Staff 45 \$F 6 \$95 Lavatory 314D Staff 45 \$F 6 \$95 Lavatory 314D Staff 1 EA 6 \$32 Walls - Concrete Block 314D Staff 25 \$F 6 \$66 Water Closet 314D Staff 25 \$F 6 \$660 Water Closet 314D Staff 25 \$F 6 \$660 Water Closet 333A Girls restroom 285 \$F 6 \$2,629 Celing - Plaster/Drywall 333A Gir	Urinals	314C Boys restroom	3	EA	6	\$1,008			
Accessories 314D Staff 45 SF 6 \$415 Ceiling - Lay-in 314D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 314D Staff 1 EA 6 \$31.05 Floor - Tile Ceramic/ Porcelain 314D Staff 45 SF 6 \$95 Lavatory 314D Staff 45 SF 6 \$95 Lavatory 314D Staff 1 EA 6 \$320 Waller - Concrete Block 314D Staff 1 EA 6 \$320 Waller - Closet 314D Staff 1 EA 6 \$320 Waller - Closet 314D Staff 1 EA 6 \$320 Waller - Closet 314D Staff 1 EA 6 \$320 Waller - Closet 314D Staff 1 EA 6 \$320 Ceiling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333A Girls res	Walls - Structural Glazed Tile	314C Boys restroom	780	SF	6	\$2,454			
Celling - Lay-in 314D Staff 45 SF 6 \$135 Doors - Wood Doors inclu hw 314D Staff 1 EA 6 \$301 Floor Drain 314D Staff 1 EA 6 \$105 Floor - Tile Ceramic/ Porcelain 314D Staff 45 SF 6 \$95 Lavatory 314D Staff 1 EA 6 \$320 Lighting - Lay-in 314D Staff 1 EA 6 \$320 Walter Closet 314D Staff 225 SF 6 \$660 Water Closet 314D Staff 225 SF 6 \$660 Accessories 333A Girls restroom 285 SF 6 \$3262 Celing - Plaster/Drywall 333A Girls restroom 285 SF 6 \$966 Floor - Terrazzo 333A Girls restroom 3 EA 6 \$11,05 Lavatory 333A Girls restroom 1 EA 6 \$320 Layling - Lay-in 333A Gi	Water Closet	314C Boys restroom	3	EA	6	\$1,008			
Doors - Wood Doors inclu hw 314D Staff 1 EA 6 \$3.01 Floor Drain 314D Staff 1 EA 6 \$1.059 Floor - Tile Ceramic/ Porcelain 314D Staff 45 SF 6 \$93.2 Layatory 314D Staff 1 EA 6 \$32.2 Lighting - Lay-in 314D Staff 1 EA 7 \$0 Walls - Concrete Block 314D Staff 1 EA 6 \$33.6 Water Closet 314D Staff 1 EA 6 \$36.6 Water Closet 314D Staff 1 EA 6 \$36.6 Accessories 333A Girls restroom 285 SF 6 \$96.6 Celling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$9.96 Floor T-ferazzo 333A Girls restroom 1 EA 6 \$1.09 Hand Dryer 333A Girls restroom 1 EA 6 \$3.20 Layatory 333A	Accessories	314D Staff	45	SF	6	\$415			
Floor Drain 314D Staff 14	Ceiling - Lay-in	314D Staff	45	SF	6	\$135			
Floor - Tile Ceramic/ Porcelain 314D Staff 45	Doors - Wood Doors inclu hw	314D Staff	1	EA	6	\$301			
Layatory 314D Staff 1 EA 6 \$320 Lighting - Lay-in 314D Staff 1 EA 7 \$0 Walls - Concrete Block 314D Staff 25 SF 6 \$60 Water Closet 314D Staff 1 EA 6 \$336 Accessories 333A Girls restroom 285 SF 6 \$2,629 Celling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$986 Floor Drain 333A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 333A Girls restroom 3 EA 6 \$900 Lay-in 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Parittions 333A Girls restroom 6 EA 6 \$1,782 Walls - \$1,782 Walls - \$1,782 \$1,782 \$2,454 \$1,782 \$2,454 \$2,454	Floor Drain	314D Staff	1	EA	6	\$1,059			
Lavatory 314D Staff 1 EA 6 \$320 Lighting - Lay-in 314D Staff 1 EA 7 \$0 Walls - Concrete Block 314D Staff 225 SF 6 \$60 Water Closet 314D Staff 1 EA 6 \$336 Accessories 333A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$986 Floor Drain 333A Girls restroom 285 SF 7 \$00 Floor - Terrazzo 333A Girls restroom 285 SF 7 \$00 Lavatory 333A Girls restroom 3 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 7 \$0 Can light Water Closet 333A Girls restroom 780 SF 6 \$	Floor - Tile Ceramic/ Porcelain	314D Staff	45	SF	6	\$95			
Walls - Concrete Block 314D Staff 225 SF 6 \$660 Water Closet 314D Staff 1 EA 6 \$336 Accessories 333A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$986 Floor Drain 333A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 333A Girls restroom 3 EA 6 \$600 Hand Dryer 333A Girls restroom 1 EA 6 \$600 Lavatory 333A Girls restroom 1 EA 6 \$600 Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Partitions 333A Girls restroom 6 EA 6 \$1,782 Waller Closet 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333C Boys restroom 285 SF 6 \$2,616 Water Clo	Lavatory	314D Staff	1	EA	6	\$320			
Water Closet 314D Staff 1 EA 6 \$336 Accessories 333A Girls restroom 285 SF 6 \$2,629 Celling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$986 Floor Drain 333A Girls restroom 1 EA 6 \$1,059 Floor Terrazzo 333A Girls restroom 285 SF 7 \$50 Hand Dryer 333A Girls restroom 1 EA 6 \$690 Lavatory 333A Girls restroom 1 EA 6 \$890 Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 \$1 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 285 SF 6 \$2,016 Accessories 333C Boys restroom 285 SF 6	Lighting - Lay-in	314D Staff	1	EA	7	\$0			
Accessories 333A Girls restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$986 Floor Drain 333A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 333A Girls restroom 285 SF 7 \$0 Hand Dryer 333A Girls restroom 1 EA 6 \$320 Basin Lavatory 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 780 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom<			225	SF	6	\$660			
Ceiling - Plaster/Drywall 333A Girls restroom 285 SF 6 \$986 Floor Drain 333A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 333A Girls restroom 285 SF 7 \$0 Hand Dryer 333A Girls restroom 3 EA 6 \$690 Lavatory 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 10 EA 7 \$0 Can light Partitions 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 285 SF 6 \$2,629 Valley - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 28	Water Closet	314D Staff	1	EA	6	\$336			
Floor Drain 333A Girls restroom 1 EA 6 \$1,059 Floor - Terrazzo 333A Girls restroom 285 SF 7 \$0 Hand Dryer 333A Girls restroom 3 EA 6 \$690 Lavatory 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 Can light Partitions 333A Girls restroom 780 SF 6 \$1,782 Can light Partitions 333A Girls restroom 780 SF 6 \$2,454 Can light Walls - Structural Glazed Tile 333A Girls restroom 6 EA 6 \$2,454 Can light Water Closet 333C Boys restroom 285 SF 6 \$2,629 Can light Accessories 333C Boys restroom 285 SF 6 \$9,629	Accessories	333A Girls restroom	285	SF	6	\$2,629			
Floor - Terrazzo 333A Girls restroom 285 SF 7 \$0 Hand Dryer 333A Girls restroom 3 EA 6 \$690 Lavatory 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 10 EA 7 \$0 Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 285 SF 6 \$2,016 Accessories 333C Boys restroom 285 SF 6 \$3,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Ceiling - Plaster/Drywall	333A Girls restroom	285	SF	6	\$986			
Hand Dryer 333A Girls restroom 3 EA 6 \$690 Lavatory 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 10 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 6 EA 6 \$2,016 Accessories 333C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 285 SF 7 \$0 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 E	Floor Drain	333A Girls restroom	1	EA	6	\$1,059			
Lavatory 333A Girls restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333A Girls restroom 10 EA 7 \$0 Can light Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 For light Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 For light Water Closet 333A Girls restroom 6 EA 6 \$2,016 For light \$2,016 <	Floor - Terrazzo	333A Girls restroom	285	SF	7	\$0			
Lighting - Lay-in 333A Girls restroom 10 EA 7 \$0 Can light Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 \$F 6 \$2,454 Water Closet 333A Girls restroom 6 EA 6 \$2,016 Accessories 333C Boys restroom 285 \$F 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 \$F 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 \$F 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Hand Dryer	333A Girls restroom	3	EA	6	\$690			
Lighting - Lay-in 333A Girls restroom 1 EA 7 \$0 Can light Partitions 333A Girls restroom 6 EA 6 \$1,782 \$1,7	Lavatory	333A Girls restroom	1	EA	6	\$320	Basin		
Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 6 EA 6 \$2,016 Accessories 333C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 10 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0	Lighting - Lay-in	333A Girls restroom	10	EA	7	\$0			
Partitions 333A Girls restroom 6 EA 6 \$1,782 Walls - Structural Glazed Tile 333A Girls restroom 780 SF 6 \$2,454 Water Closet 333A Girls restroom 6 EA 6 \$2,016 Accessories 333C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$600 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0	Lighting - Lay-in	333A Girls restroom	1	EA	7	\$0	Can light		
Water Closet 333A Girls restroom 6 EA 6 \$2,016 Accessories 333C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0		333A Girls restroom	6	EA	6	\$1,782			
Water Closet 333A Girls restroom 6 EA 6 \$2,016 Accessories 333C Boys restroom 285 SF 6 \$2,629 Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0	Walls - Structural Glazed Tile	333A Girls restroom	780	SF	6	\$2,454			
Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Water Closet	333A Girls restroom	6	EA	6	\$2,016			
Ceiling - Plaster/Drywall 333C Boys restroom 285 SF 6 \$986 Floor Drain 333C Boys restroom 1 EA 6 \$1,059 Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Accessories	333C Boys restroom	285	SF	6	\$2,629			
Floor - Terrazzo 333C Boys restroom 285 SF 7 \$0 Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 10 EA 7 \$0 Can light Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Ceiling - Plaster/Drywall	333C Boys restroom	285	SF	6	\$986			
Hand Dryer 333C Boys restroom 3 EA 6 \$690 Lavatory 333C Boys restroom 1 EA 6 \$320 Basin Lighting - Lay-in 333C Boys restroom 10 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Floor Drain	333C Boys restroom	1	EA	6	\$1,059			
Lavatory333C Boys restroom1EA6\$320 BasinLighting - Lay-in333C Boys restroom10EA7\$0Lighting - Lay-in333C Boys restroom1EA7\$0Can light	Floor - Terrazzo	333C Boys restroom	285	SF	7	\$0			
Lighting - Lay-in 333C Boys restroom 10 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Hand Dryer		3	EA	6	\$690			
Lighting - Lay-in 333C Boys restroom 10 EA 7 \$0 Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Lavatory	333C Boys restroom	1	EA	6	\$320	Basin		
Lighting - Lay-in 333C Boys restroom 1 EA 7 \$0 Can light	Lighting - Lay-in		10	EA	7	\$0			
		333C Boys restroom	1	EA	7	\$0	Can light		
Partitions 333C Boys restroom 4 EA 6 \$1,188	Partitions	333C Boys restroom	4	EA	6	\$1,188			
Urinals 333C Boys restroom 3 EA 6 \$1,008	Urinals	333C Boys restroom	3	EA	6	\$1,008			

1955 E 75th St Chicago, IL 60649

Building: Main

Category: Rooms (Other Than Classrooms)

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Walls - Structural Glazed Tile	333C Boys restroom	780	SF	6	\$2,454	
	Water Closet	333C Boys restroom	3	EA	6	\$1,008	
	Accessories	333D Staff	45	SF	6	\$415	
	Ceiling - Lay-in	333D Staff	45	SF	6	\$135	
	Doors - Wood Doors inclu hw	333D Staff	1	EA	6	\$301	
	Floor Drain	333D Staff	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	333D Staff	45	SF	6	\$95	
	Lavatory	333D Staff	1	EA	6	\$320	
	Lighting - Lay-in	333D Staff	1	EA	7	\$0	
	Walls - Concrete Block	333D Staff	225	SF	6	\$660	
	Water Closet	333D Staff	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$1,526,854

Building: Main

Category: Building Interior

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
or .						
Ceiling - Exposed	1st Floor	710	SF	6	\$1,056	
Ceiling - Lay-in	1st Floor	11,674	SF	6	\$35,057	
Ceiling - Plaster/Drywall	1st Floor	3,330	SF	6	\$20,619	
Doors - Store Front	1st Floor	5	EΑ	6	\$6,041	
Drinking Fountains - Single Fountain	1st Floor	4	EA	6	\$1,103	
Floor - Terrazzo	1st Floor	15,004	SF	7	\$0	
Lighting - Pendent/Surface	1st Floor	162	EΑ	7	\$0	
Walls - Concrete Block	1st Floor	9,588	SF	6	\$28,107	
Walls - Metal Panel	1st Floor	540	SF	6	\$4,031	Glass Wall
Walls - Structural Glazed Tile	1st Floor	7,055	SF	6	\$22,195	
Ceiling - Exposed	2nd Floor	10,145	SF	6	\$15,088	
Ceiling - Splined	2nd Floor	2,160	SF	6	\$6,239	
Doors - Steel Doors incl hw	2nd Floor	4	EA	6	\$1,204	
Doors - Transom Window	2nd Floor	215	EA	6	\$3,640	
Doors - Wood Doors include hw	2nd Floor	3	EA	6	\$903	
Drinking Fountains - Double Water Cooler	2nd Floor	3	EA	6	\$1,131	
Floor - Terrazzo	2nd Floor	12,305	SF	7	\$0	
Lighting - Lay-in	2nd Floor	60	EA	7	\$0	Can lights
Lighting - Pendent/Surface	2nd Floor	95	EΑ	7	\$0	



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Building Interior

_	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido		Location	Quantity	Jint	Marin	0031	
3011100	Lighting - Wall Mounted	2nd Floor	131	EA	7	\$0	
	Stairs - Concrete Stairs	2nd Floor	3	LF	6	\$25	
	Student Lockers - One Tier	2nd Floor	610	EA	6	\$56,630	
	Walls - Concrete Block	2nd Floor	3,065	SF	6	\$8,985	
	Walls - Plaster/Drywall	2nd Floor	4,100	SF	6	\$18,175	
	Walls - Structural Glazed Tile	2nd Floor	5,795	SF	6	\$18,231	
	Walls - Tile Ceramic/ Porcelain	2nd Floor	900	SF	6	\$2,831	
	Ceiling - Exposed	3rd Floor	3,280	SF	6	\$4,878	
	Ceiling - Plaster/Drywall	3rd Floor	6,735	SF	6	\$41,702	
	Doors - Steel Doors incl hw	3rd Floor	6	EA	6	\$1,806	
	Doors - Transom Window	3rd Floor	920	EA	6	\$15,577	
	Doors - Wood Doors include hw	3rd Floor	1	EA	6	\$301	
	Drinking Fountains - Double Fountain	3rd Floor	2	EA	6	\$672	
	Floor - Terrazzo	3rd Floor	10,015	SF	7	\$0	
	Lighting - Lay-in	3rd Floor	38	EA	7	\$0	Can lights
	Lighting - Pendent/Surface	3rd Floor	40	EA	7	\$0	Carrigins
	Lighting - Wall Mounted	3rd Floor	128	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	609	EA	6	\$56,537	
	Walls - Concrete Block	3rd Floor	1,050	SF	6	\$3,078	
	Walls - Plaster/Drywall	3rd Floor	3,700	SF	6	\$16,402	
	Walls - Structural Glazed Tile	3rd Floor	3,672	SF	6	\$10,402	
	Walls - Tile Ceramic/ Porcelain	3rd Floor	905	SF	6	\$2,847	
	Ceiling - Lay-in	Basement	3,600	SF	6	\$10,811	
	Doors - Hardware	Basement	3,000	EA	6	\$1,693	
	Drinking Fountains - Double Fountain	Basement	1	EA	6	\$336	
	Floor - Terrazzo	Basement	3,600	SF	7	\$0	
	Lighting - Pendent/Surface	Basement	36	EA	6	\$4,460	
	Walls - Concrete Block	Basement	5,280	SF	6	\$15,478	
	Walls - Masonry	Basement	2,380	SF	6	\$7,487	
	Walls - Structural Glazed Tile	Basement	3,480	SF	6	\$10,948	
	Walls Structural Glazed Tile	Daschicht	3,400	Oi	O	Ψ10,540	
Safety							
	Camera Viewing Station	1st Floor	4	EA	6	\$2,730	Main entrance #1, room 313, Principals office, asst principals office
	Metal Dedector	1st Floor	2	EA	6	\$1,761	Main entrance #1
	Security Cameras	1st Floor / Entire Building	175	EA	6	\$33,956	
	Security Cameras	1st Floor / Entire Building	29	EA	6	\$5,627	



1955 E 75th St Chicago, IL 60649

Building: Main

Category: Building Interior

Carling - Plaster/Drywall Stairwell # A 1,362 SF 6 \$3,361 Stairwell # A 1,148 SF 6 \$3,361 Stairwell # B 4,20 SF 7 \$0 ST 5 SF 6 \$3,361 Stairwell # B 4,20 SF 7 \$0 ST 5 ST
Ceiling - Exposed 4th floor mechanical penthouse 255 SF 6 \$379 Floor - Concrete 4th floor mechanical penthouse 100 SF 7 \$0 Handrails 4th floor mechanical penthouse 65 LF 7 \$0 Lighting - Pealent/Surface 4th floor mechanical penthouse 1 EA 7 \$0 Lighting - Wall Mounted 4th floor mechanical penthouse 2 EA 7 \$0 Stairs - Concrete 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Concrete Block 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Plaster/Drywall 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Plaster/Drywall 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Plaster/Drywall 4th floor mechanical penthouse 26 LF 7 \$0 Handrails Stairwell # A 1,40 SF 6 \$3,807 Floor - Terrazzo
Floor - Concrete
Handrails
Lighting - Pendent/Surface 4th floor mechanical penthouse 1 EA 7 \$0 Lighting - Wall Mounted 4th floor mechanical penthouse 2 EA 7 \$0 Stairs - Concrete 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Concrete Block 4th floor mechanical penthouse 1,400 \$F 6 \$4,104 Walls - Plaster/Drywall 4th floor mechanical penthouse 225 \$F 6 \$4,104 Walls - Plaster/Drywall 5tairwell # A 520 \$F 6 \$3,807 Floor - Terrazzo Stairwell # A 1,362 \$F 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 \$F 6 \$3,612 Walls - Structural Glazed Tile Stairwell # B 42,00 \$F 7 \$0 Ceiling - Plaster/Drywall Stairw
Lighting - Wall Mounted 4th floor mechanical penthouse 2 EA 7 \$0 Stairs - Concrete 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Concrete Block 4th floor mechanical penthouse 1,400 SF 6 \$4,104 Walls - Plaster/Drywall 4th floor mechanical penthouse 225 SF 6 \$621 Celling - Plaster/Drywall Stairwell # A 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # A 1,362 SF 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 24 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 82 LF 7 \$0 Walls - Terrazzo Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # B 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwel
Stairs - Concrete 4th floor mechanical penthouse 26 LF 7 \$0 Walls - Concrete Block 4th floor mechanical penthouse 1,400 SF 6 \$4,104 Walls - Plaster/Drywall 4th floor mechanical penthouse 225 SF 6 \$621 Ceiling - Plaster/Drywall Stairwell # A 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # A 1,362 SF 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # B 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 11,20
Walls - Concrete Block 4th floor mechanical penthouse 1,400 SF 6 \$4,104 Walls - Plaster/Drywall 4th floor mechanical penthouse 225 SF 6 \$621 Ceiling - Plaster/Drywall Stairwell # A 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # A 1,362 SF 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 1,148 SF 6 \$3,612 Walls - Masonry Stairwell # A 1,200 SF 7 \$0 Walls - Structural Glazed Tile Stairwell # B 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6
Walls - Plaster/Drywall 4th floor mechanical penthouse 225 SF 6 \$621 Ceiling - Plaster/Drywall Stairwell # A 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # A 1,362 SF 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 <t< td=""></t<>
Ceiling - Plaster/Drywall Stairwell # A 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # A 1,362 SF 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 1,150 SF 7 \$0 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo
Floor - Terrazzo Stairwell # A 1,362 SF 7 \$0 Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807
Handrails Stairwell # A 246 LF 6 \$2,132 Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Lighting - Chandelier, Incandescent Stairwell # A 16 EA 6 \$7,641 Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Stairs - Terrazzo Stairwell # A 82 LF 7 \$0 Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Walls - Masonry Stairwell # A 1,148 SF 6 \$3,612 Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Walls - Structural Glazed Tile Stairwell # A 1,200 SF 7 \$0 Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Ceiling - Plaster/Drywall Stairwell # B 420 SF 6 \$3,075 Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Floor - Terrazzo Stairwell # B 1,150 SF 7 \$0 Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Handrails Stairwell # B 112 LF 6 \$971 Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Lighting - Wall Mounted Stairwell # B 6 EA 7 \$0 Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Stairs - Terrazzo Stairwell # B 56 LF 7 \$0 Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Walls - Concrete Block Stairwell # B 1,360 SF 6 \$3,987 Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Ceiling - Plaster/Drywall Stairwell # C 520 SF 6 \$3,807 Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Floor - Terrazzo Stairwell # C 1,289 SF 7 \$0
Handrails Stairwell # C 260 LF 6 \$2.253
Lighting - Pendent/Surface Stairwell # C 8 EA 7 \$0
Stairs - Terrazzo Stairwell # C 65 LF 7 \$0
Walls - Concrete Block Stairwell # C 1,420 SF 6 \$4,163
Ceiling - Plaster/Drywall Stairwell # D 350 SF 6 \$2,563
Floor - Terrazzo Stairwell # D 1,150 SF 7 \$0
Handrails Stairwell # D 164 LF 6 \$1,421
Lighting - Pendent/Surface Stairwell # D 2 EA 7 \$0
Lighting - Wall Mounted Stairwell # D 6 EA 7 \$0
Stairs - Concrete Stairwell # D 26 LF 6 \$216
Stairs - Terrazzo Stairwell # D 56 LF 7 \$0
Walls - Concrete Block Stairwell # D 3,620 SF 6 \$10,612
Ceiling - Exposed Stairwell #F 205 SF 7 \$0 Above sta
Ceiling - Plaster/Drywall Stairwell #F 115 SF 6 \$842

\$4,806,450

1955 E 75th St Chicago, IL 60649

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Floor - Concrete Epoxy/ Painted	Stairwell #F	115	SF	7	\$0	
	Handrails	Stairwell #F	60	LF	7	\$0	
	Lighting - Wall Mounted	Stairwell #F	7	EA	7	\$0	
	Stairs - Concrete	Stairwell #F	28	LF	7	\$0	
	Walls - Concrete Block	Stairwell #F	1,010	SF	7	\$0	
	Walls - Plaster/Drywall	Stairwell #F	160	SF	6	\$442	
	Ceiling - Exposed	Stairwell #G	90	SF	7	\$0	
	Ceiling - Plaster/Drywall	Stairwell #G	275	SF	6	\$2,013	
	Floor - Concrete Epoxy/ Painted	Stairwell #G	190	SF	7	\$0	
	Handrails	Stairwell #G	55	LF	6	\$477	
	Lighting - Lay-in	Stairwell #G	1	EA	7	\$0	
	Lighting - Wall Mounted	Stairwell #G	5	EΑ	7	\$0	
	Stairs - Concrete	Stairwell #G	25	LF	7	\$0	
	Walls - Concrete Block	Stairwell #G	2,240	SF	6	\$6,567	
	Handrails	Stairwell #K	17	LF	7	\$0	
	Lighting - Wall Mounted	Stairwell #K	2	EΑ	6	\$248	
	Stairs - Concrete	Stairwell #K	9	LF	7	\$0	
	Ceiling - Plaster/Drywall	Stairwell #L - W of pool	290	SF	6	\$2,123	
	Floor - Concrete Epoxy/ Painted	Stairwell #L - W of pool	170	SF	7	\$0	
	Handrails	Stairwell #L - W of pool	55	LF	6	\$477	
	Lighting - Wall Mounted	Stairwell #L - W of pool	6	EΑ	7	\$0	
	Stairs - Concrete	Stairwell #L - W of pool	22	LF	7	\$0	
	Walls - Concrete Block	Stairwell #L - W of pool	1,000	SF	6	\$2,932	
Vertica	I Conveyance						
	Elevator - Hydraulic Elevator	1st Floor	2	EA	6	\$38,476	Locations: Entrances 1, 6 / Entrance 6 elevator only 1st grade level down to basement level
	Wheelchair Lift - Chair Lift		1	EA	6	\$5,597	
Build	ing Interior Subtotal:					\$617,488	

Total Building Cost

SITE

Category: Site

Group Item - Type Location Quantity Unit Rank Cost Comments



1955 E 75th St Chicago, IL 60649

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/D	rainage						
	Civil/ Drainage - Catch Basin	Entire Site	6	EA	6	\$6,563	
	Civil/ Drainage - Site Drain	Entire Site	4	EA	6	\$1,241	
	Civil/ Drainage - Site Manhole	Entire Site	3	EA	6	\$4,478	
Fencin	g						
	Fencing - New Standard Ornamental	Entire Site	70	LF	6	\$2,233	Location: SW parking lot entry driveway with gate
Lands	cape						
	Landscape - Grass	Entire Site	15,260	SF	6	\$12,657	
	Landscape - Hardscape- Concrete	Entire Site	13,835	SF	7	\$0	
	Landscape - Hardscape- Pavers	Entire Site	1,600	SF	7	\$0	West - Sitting/Garden area
	Landscape - Hardscape- Pavers	Entire Site	11,510	SF	7	\$0	
	Lighting - Pole Mounted	Entire Site	12	EΑ	6	\$13,005	3-Recessed at flagpoles / 9-spot lights at trees
	Lighting - Pole Mounted	Entire Site	3	EA	6	\$3,251	2-lights damaged at west internal sidewalk / 1-not working at main entrance 1 plaza
	Lighting - Pole Mounted	Entire Site	17	EA	6	\$18,424	
	Parkway trees	Entire Site	14	EA	6	\$9,241	Location: S, E
	Planting Beds/ Area	Entire Site	12,905	SF	6	\$21,222	
	Retaining Wall - Concrete	Entire Site	1,090	SF	7	\$0	West - Basement Entrance 4
	Retaining Wall - Masonry	Entire Site	4,550	SF	7	\$0	Location: North main entrance 1 plaza ramp - Granite
	Retaining Wall - Masonry	Entire Site	4,450	SF	7	\$0	At SE elevation around raised planting, garden area
	Trash Receptacles	Entire Site	2	EA	6	\$625	
	Walking Path - Crushed Stone	Entire Site	8,675	SF	6	\$18,360	SE corner of parking lot - Bike racks / Underneath cantilever / Raised sitting, garden area adjacent to entrances 9,10
Parkin	g Lot						
	Concrete Curbs	SW staff only	620	LF	6	\$7,962	
	Lighting - Pole Mounted	SW staff only	6	EΑ	6	\$8,715	
	Pavers	SW staff only	19,400	SF	7	\$0	
	Trash Compactor	SW staff only	1	EA	6	\$0	In Loading Dock
Sidewa	alks						
	Sidewalks - Internal Walks	Entire Site	1,380	LF	6	\$16,577	
	Sidewalks - Perimeter Sidewalks	Entire Site	12,215	SF	6	\$24,280	
Signag	ge						
	Flag Pole - Flag Pole	Entire Site	3	EA	7	\$0	NE
	Monument - Building Mounted Cut Letter Sign	Entire Site	1	EA	7	\$0	N. Facade
	LOUIODE INTLUIO	D 50					A D - 1 - 0/00/45



1955 E 75th St Chicago, IL 60649

SITE

Category: Site

Group Item - Type	Location	Quantity Unit Rank Cost Comments
Signage		
Site Subtotal:		\$168,832
Total Site Cost		\$168,832

Campus Total ^{2 3} \$4,975,282

Definitions

- Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated.
- Unit means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.
- Campus Total also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding: these are viewed as separate capital needs.

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.



1955 E 75th St Chicago, IL 60649

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main		-												1
Art Room	Art Room	2nd Floor	200B	200B	1,220	1	4	20	350	0	40	N	Υ	N
Art Room	Store Room	2nd Floor	200B-2	200B-2	91	0	0	2	0	0	40	N	N	N
Art Room	Art Room	2nd Floor	200D	200D	1,220	1	4	20	350	0	40	N	Υ	N
Band Room	Band Room	2nd Floor	200H	200H	1,570	1	10	36	375	0	40	N	N	N
Computer Lab	Computer Lab	1st Floor	117	117	770	1	2	8	0	0	40	N	N	N
Computer Lab	Computer Lab	2nd Floor	222	222	1,260	1	38	80	115	4	40	Υ	Υ	Y
Computer Lab	Computer Lab	3rd Floor	321	321	1,290	2	22	82	104	8	40	Υ	N	N
Computer Lab	Computer Lab	3rd Floor	322	322	1,260	1	22	82	115	4	40	Υ	N	N
Fitness Room	Fitness Room	Basement	800	800	1,317	1	4	12	0	0	40	N	N	N
Health	Other Instructional Use	2nd Floor	221	221	975	1	1	50	90	8	40	Υ	N	N
Office	Regular Classroom	2nd Floor	212	212	795	9	14	46	35	4	40	Υ	N	N
Office	Regular Classroom	3rd Floor	312	312	795	2	14	38	35	4	40	Υ	N	N
Regular Classroom	Choral Room	2nd Floor	200F	200F	1,255	1	4	30	380	0	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	215	215	795	1	10	26	83	7	40	Υ	N	N
Regular Classroom	Regular Classroom	2nd Floor	216	216	795	1	10	246	90	5	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	217	217	795	1	10	26	83	7	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	218	218	795	1	7	24	90	5	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	219	219	795	1	7	24	57	5	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	220	220	795	1	10	26	75	8	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	224	224	795	1	10	26	75	8	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	226	226	795	1	10	26	84	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	228	228	795	2	10	26	90	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	230	230	795	1	7	24	90	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	232	232	795	1	10	26	69	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	234	234	795	1	10	26	97	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	235	235	795	1	10	26	115	12	40	Υ	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	315	795	1	10	26	83	7	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	316	316	795	1	10	26	90	5	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	317	317	795	1	6	16	83	7	40	Υ	N	N
Regular Classroom	Regular Classroom	3rd Floor	318	318	795	1	6	16	90	5	40	Υ	N	N
Regular Classroom	Regular Classroom	3rd Floor	319	319	795	1	10	26	57	5	40	Υ	N	N
Regular Classroom	Regular Classroom	3rd Floor	320	320	795	1	6	16	75	8	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	324	324	795	1	10	24	75	8	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	326	326	795	1	10	26	84	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	328	328	795	1	10	26	90	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	330	330	795	1	6	24	90	10	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	332	332	795	1	6	16	69	10	40	Υ	Υ	N



1955 E 75th St Chicago, IL 60649

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main														
Regular Classroom	Regular Classroom	3rd Floor	334	334	795	1	6	16	115	17	40	Υ	Υ	N
Regular Classroom	Regular Classroom	3rd Floor	335	335	795	1	10	26	115	7	40	Υ	Υ	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	231	231	1,290	1	7	30	97	6	40	Υ	Υ	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	331	331	1,290	1	10	46	97	6	40	Υ	N	N
Science Lab Level 2	Science Lab Level 2	2nd Floor	223	223	1,290	1	10	42	130	6	40	Υ	Υ	N
Science Lab Level 2	Science Lab Level 2	2nd Floor	227	227	1,290	2	13	42	130	6	40	Υ	N	N
Science Lab Level 2	Science Lab Level 2		323	323	1,290	1	11	30	130	6	40	Υ	N	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	327	327	1,290	2	12	42	130	6	40	Υ	N	N