

Facility Assessment Summary

This report summarizes the findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility feature and system by visual observation only; they do not test operability or perform destructive testing inside walls, ceilings or floors. The rankings below reflect the assessors' visual evaluations of the property condition as of that date. For additional information, you may review the detailed assessment report linked on this school's profile page and visit the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx.

Condition Rankings and Descriptions

- Rank 7:** The item/system is new or in good condition and no work is required.
- Rank 6:** The item/system requires general cleaning and/or routine maintenance.
- Rank 5:** The item/system requires repairs and has not reached the end of its serviceable life.
- Rank 4:** The item/system has reached its expected useful life, but is still fully operational. CPS will maintain until replacement occurs.
- Rank 3:** The item/system has surpassed its expected useful life and has limited operability. CPS will maintain until replacement occurs.
- Rank 2:** The item/system has surpassed its expected useful life and has low operability. CPS will maintain until replacement occurs.
- Rank 1:** The item's/system's failure leads to an immediate life safety condition for occupants or to the potential of an uninhabitable facility.¹

Definitions

Total Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated. Within that Total Quantity, different portions may have different rankings.

Unit means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").

Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.

For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.

Total Campus Need also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

EXTERIOR

CHIMNEY

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Brick Chimney - Concrete/ Mortar Liner | 5 | | | | | 19 | | | 19 | LF | \$33,963 |
| | | | | | | | | | | | \$33,963 |

DOORS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Exterior Steel Door | 7 | | | | | | | 6 | 6 | EA | \$0 |
| | | | | | | | | | | | \$0 |

ENTRANCE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-------------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Concrete Exterior Stairs | 6 | | | | | | 173 | 120 | 293 | LF | \$18,554 |
| Concrete Ramp | 7 | | | | | | | 173 | 173 | LF | \$0 |
| Entrance Controls - Audio | 4 | | | | 1 | | | | 1 | EA | \$2,288 |
| Entrance Controls - Audio and Video | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Power Door Operator and Controls | 6 | | | | 1 | | 1 | 1 | 3 | EA | \$4,908 |
| Ramp Handrails | 6 | | | | | | 190 | 156 | 346 | LF | \$0 |
| Stair Handrails | 6 | | | | | | 72 | 72 | 144 | LF | \$0 |
| | | | | | | | | | | | \$25,750 |

FOUNDATION

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------------|
| Concrete Foundation | 6 | | | | | | 929 | 188 | 1,117 | LF | \$144,670 |
| | | | | | | | | | | | \$144,670 |

LIGHTING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Exterior Lights - Parapet or Roof Mounted | 6 | | | | | | 9 | | 9 | EA | \$4,505 |
| Exterior Lights - Wall Mounted | 6 | | | | | | 15 | | 15 | EA | \$3,218 |
| | | | | | | | | | | | \$7,722 |

LINTELS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Lintels - Brick | 7 | | | | | | | 259 | 259 | LF | \$0 |
| Lintels - Steel | 7 | | | | | | | 927 | 927 | LF | \$0 |
| | | | | | | | | | | | \$0 |

PARAPET

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|----------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------|
| Coping - Stone | 6 | | | | | | 1,034 | 355 | 1,389 | LF | \$0 |
| Parapet < 16" Height | 6 | | | | | | 745 | | 745 | LF | \$116,017 |

| | | | | | | | | | | | | | |
|---------------------------|---|--|--|--|--|--|--|--|--|-----|-----|------------------|-----------|
| Parapet > 30" Height | 6 | | | | | | | | | 123 | 123 | LF | \$31,924 |
| Parapet 16" to 30" Height | 6 | | | | | | | | | 571 | 571 | LF | \$118,560 |
| | | | | | | | | | | | | \$266,501 | |

ROOF SYSTEM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------------|
| EPDM/ Synthetic Rubber Roof | 5 | | | | | 21,099 | 13,327 | | 34,426 | SF | \$247,731 |
| Interior Downspouts | 6 | | | | | | 303 | | 303 | LF | \$0 |
| Roof Structure: Concrete | 7 | | | | | | | 27,385 | 27,385 | SF | \$0 |
| Roof Structure: Steel with Clay Tile Arch | 7 | | | | | | | 7,041 | 7,041 | SF | \$0 |
| | | | | | | | | | | | \$247,731 |

SUPERSTRUCTURE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Concrete | 7 | | | | | | | 48,200 | 48,200 | SF | \$0 |
| Steel with Clay Tile Arch | 7 | | | | | | | 17,900 | 17,900 | SF | \$0 |
| | | | | | | | | | | | \$0 |

WALLS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------------|
| Brick | 6 | | | | | | 33,873 | | 33,873 | SF | \$223,785 |
| Stone - Cast | 6 | | | | | | 1,222 | | 1,222 | SF | \$17,475 |
| | | | | | | | | | | | \$241,260 |

WINDOWS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------|
| Window - Guards perforated | 7 | | | | | | | 4,397 | 4,397 | SF | \$0 |
| Windows - Casement Aluminum Double-pane | 7 | | | | | | | 9,580 | 9,580 | SF | \$0 |
| Windows - Decorative | 6 | | | | | | 81 | | 81 | SF | \$463 |
| | | | | | | | | | | | \$463 |

| | | | | | | | | | | | | |
|-----------------------|--|--|--|--|--|--|--|--|--|--|--|------------------|
| EXTERIOR Total | | | | | | | | | | | | \$968,060 |
|-----------------------|--|--|--|--|--|--|--|--|--|--|--|------------------|

ELECTRICAL

EMERGENCY SYSTEM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Emergency A/C power - Corridors and Stairs | 7 | | | | | | | 15,188 | 15,188 | SF | \$0 |
| Emergency A/C power - Gym and Lunch rooms | 7 | | | | | | | 6,502 | 6,502 | SF | \$0 |
| Emergency A/C power - Students Toilets | 7 | | | | | | | 1,738 | 1,738 | SF | \$0 |
| Emergency Battery Packs - Corridors and Stairs | 7 | | | | | | | 25 | 25 | EA | \$0 |
| Emergency Battery Packs - Lunchroom and Gym | 7 | | | | | | | 13 | 13 | EA | \$0 |
| Emergency Battery Packs - Toilets | 7 | | | | | | | 8 | 8 | EA | \$0 |
| Exit Signs - Auditorium | 7 | | | | | | | 6 | 6 | EA | \$0 |
| Exit Signs - Corridors and Stairs | 7 | | | | | | | 20 | 20 | EA | \$0 |
| Exit Signs - Lunchroom - Gym - multipurpose rooms | 7 | | | | | | | 8 | 8 | EA | \$0 |
| Public Announcement System | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Security System - Intrusion detection | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| | | | | | | | | | | | \$0 |

MAIN SERVICE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Main Electrical service - Live Front - 2000 A 120/240/3PH | 5 | | | | | 1 | | | 1 | EA | \$33,462 |
| Main Electrical service 1200 A 277/480/3PH | 7 | | | | | | | 1 | 1 | EA | \$0 |
| | | | | | | | | | | | \$33,462 |

POWER DISTRIBUTION

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Lighting and power panels | 7 | | | | | | | 17 | 17 | EA | \$0 |
| Main distribution panels 400-600 amp | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Main distribution panels above 600 amp | 6 | | | | | | 3 | | 3 | EA | \$6,435 |
| Main distribution panels less than 400 amp | 6 | | | | | | 1 | 2 | 3 | EA | \$1,216 |
| Transformers 120/240-120/208 | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Transformers 277/480-120/208 | 7 | | | | | | | 1 | 1 | EA | \$0 |
| | | | | | | | | | | | \$7,651 |

ELECTRICAL Total \$41,113

FIRE PROTECTION

FIRE ALARM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Fire Alarm Strobe Lights | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Fire Alarm System | 7 | | | | | | | 36,740 | 36,740 | SF | \$0 |
| | | | | | | | | | | | \$0 |

FIRE PROTECTION Total \$0

MECHANICAL

AIR CONDITIONING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------|
| Chillers - Air Cooled - Rotary/Screw type - Roof Mounted 100 to 200 tons | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Condensing Unit - Roof Mounted less than 5 tons | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Window A/C Unit | 6 | | | | | | 1 | | 1 | EA | \$215 |
| | | | | | | | | | | | \$215 |

AIR HANDLING SYSTEMS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|---------|
| Air Handling Unit Package - Single Zone - Hot Water 12,001 to 20,000 cfm | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Air Handling Unit Package - Single Zone - Hot Water less than 4,000 cfm | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Air Intake - Built Up Air Handling Unit | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Air intake for all Air Handling Units except built up AHU | 6 | | | | | | 2 | 24 | 26 | EA | \$2,860 |
| Make Up Air Unit - Roof Mounted - Gas-Heating less than 6,000 cfm | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Multi Zone Built Up Air Handling Unit - Hot Water or Dual Temperature Water 15,001 to 25,000 cfm | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Multi Zone Built Up Air Handling Unit Auxiliaries - Hot Water 15,000 to 25,000 cfm | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Return Duct Work - Masonry and Ducts - Existing or Missing Exterior Shaft | 7 | | | | | | | 40 | 40 | LF | \$0 |
| Return Fans - Indoor 10,001 to 20,000 CFM | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Return Fans - Indoor 5,000 to 10,000 CFM | 7 | | | | | | | 1 | 1 | EA | \$0 |

| | | | | | | | | | | | | | |
|--|---|--|--|--|--|--|--|--|--|---|---|----|----------------|
| Return Fans - Indoor greater than 20,000 CFM | 7 | | | | | | | | | 1 | 1 | EA | \$0 |
| | | | | | | | | | | | | | \$2,860 |

BOILER SYSTEMS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Boiler Assembly - Condensing Hot Water Boiler 2,001MBH-3,000 MBH | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Boiler Auxiliary - Condensing Hot Water Boiler 2,001MBH-3,000 MBH | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Chemical Pot Feeder - Hot Water | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Glycol Feed System | 7 | | | | | | | 1 | 1 | EA | \$0 |
| | | | | | | | | | | | \$0 |

HEATING DEVICES

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--------------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Cabinet Heaters With Hot Water Coils | 7 | | | | | | | 9 | 9 | EA | \$0 |
| Radiators - Hot Water | 7 | | | | | | | 10 | 10 | EA | \$0 |
| Wall Heater - Electric | 6 | | | | 1 | | | 10 | 11 | EA | \$1,030 |
| | | | | | | | | | | | \$1,030 |

MECHANICAL PLUMBING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Piping - Hydronic Supply and Return - Steel or Galvanized | 7 | | | | | | | 1,700 | 1,700 | LF | \$0 |
| Piping - Steam - Steel or Galvanized | 7 | | | | | | | 2,000 | 2,000 | LF | \$0 |
| Pumps - Dual Temperature Water 11 to 20 HP | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Pumps - Hot Water 11 to 20 HP | 6 | | | | | | 5 | 2 | 7 | EA | \$12,870 |
| | | | | | | | | | | | \$12,870 |

TEMPERATURE CONTROL

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Direct Digital Control (DDC) System | 7 | | | | | | | 29,360 | 29,360 | SF | \$0 |
| Thermostats - Direct Digital Control (DDC) | 7 | | | | | | | 32 | 32 | EA | \$0 |
| Zone Dampers | 7 | | | | | | | 31 | 31 | EA | \$0 |
| | | | | | | | | | | | \$0 |

UNIT VENTILATION

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Unit Ventilators - Hot Water and Chilled Water | 7 | | | | | | | 25 | 25 | EA | \$0 |
| | | | | | | | | | | | \$0 |

VENTILATION

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------|
| Exhaust Fan - Indoor | 6 | | | | | | 1 | | 1 | EA | \$501 |
| Exhaust Fans - Roof Mounted 1,501 to 8,000 cfm | 7 | | | | | | | 5 | 5 | EA | \$0 |
| Exhaust Fans - Roof Mounted 500 to 1,500 cfm | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Exhaust Fans - Roof mounted less than 500 CFM | 7 | | | | | | | 2 | 2 | EA | \$0 |
| | | | | | | | | | | | \$501 |

MECHANICAL Total \$17,475

PLUMBING

HOT WATER

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Hot Water Heater - Gas 150,000 -300,000 BTU/HR | 7 | | | | | | | 2 | 2 | EA | \$0 |
| | | | | | | | | | | | \$0 |

PIPING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------|
| Domestic Piping - Cold Water from Risers to Fixtures | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Domestic Piping - Cold Water Risers | 5 | | | | | 66,100 | | | 66,100 | SF | \$21,740 |
| Domestic Piping - Hot Water from Riser to fixtures | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Domestic Piping - Hot Water Return Risers | 5 | | | | | 66,100 | | | 66,100 | SF | \$14,178 |
| Domestic Piping - Hot Water Risers | 5 | | | | | 66,100 | | | 66,100 | SF | \$17,014 |
| Domestic Piping Cold Water Horizontal lines | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Domestic Piping Hot Water Horizontal lines | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Domestic Piping Hot Water Return Lines | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |
| Sanitary Piping | 7 | | | | | | | 66,100 | 66,100 | SF | \$0 |

| | | | | | | |
|--------------|---|--------|--------|--------|----|-----------------|
| Storm Piping | 5 | 66,100 | | 66,100 | SF | \$31,193 |
| Vent Piping | 6 | 36,740 | 29,360 | 66,100 | SF | \$13,135 |
| | | | | | | \$97,260 |

PUMPS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Domestic Booster Pump duplex | 7 | | | | | | | 1 | 1 | EA | \$0 |
| Sump Pump | 6 | | | 1 | | | | 4 | 5 | EA | \$11,869 |
| | | | | | | | | | | | \$11,869 |

PLUMBING Total \$109,129

INTERIOR

ADMINISTRATIVE SUITES

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|----------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Ceiling - Plaster/Drywall | 6 | | | | | | 4,553 | | 4,553 | SF | \$12,891 |
| Flooring - Tile/Sheet | 6 | | | | | | 4,553 | | 4,553 | SF | \$6,511 |
| Lighting - Pendant/Surface | 6 | | | | 6 | | 82 | | 88 | SF | \$98 |
| Walls - Concrete Block | 6 | | | | | | 1,068 | | 1,068 | SF | \$3,054 |
| Walls - Plaster/Drywall | 6 | | | | | | 6,828 | | 6,828 | SF | \$16,111 |
| | | | | | | | | | | | \$38,665 |

CORRIDOR

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------|
| Ceiling - Lay-In | 6 | | | | | | 1,883 | | 1,883 | SF | \$4,039 |
| Ceiling - Plaster/Drywall | 6 | | | | | | 13,305 | | 13,305 | SF | \$37,672 |
| Flooring Concrete | 6 | | | | | | 990 | | 990 | SF | \$4,672 |
| Flooring Terrazzo | 7 | | | | | | | 3,374 | 3,374 | SF | \$0 |
| Flooring Tile/ Sheet | 6 | | | | | | 10,824 | | 10,824 | SF | \$15,478 |
| Lighting - Pendant/ Surface | 6 | | | | | | 15,188 | | 15,188 | SF | \$10,859 |
| Stair Handrails | 6 | | | | | | 288 | | 288 | LF | \$0 |
| Stairs - Terrazzo | 7 | | | | | | | 120 | 120 | LF | \$0 |
| Stairs - Tile | 6 | | | | | | 24 | 24 | 48 | LF | \$181 |

| | | | | | | | | | | | | | | | |
|--------------------------------|---|--|--|--|--|--|--|--|--|-----|--------|--------|-------|------------------|----------|
| Student Lockers | 5 | | | | | | | | | 597 | | 597 | EA | \$106,714 | |
| Walls - Concrete Block | 6 | | | | | | | | | | 1,720 | 1,720 | SF | \$4,919 | |
| Walls - Plaster/Drywall | 6 | | | | | | | | | | 12,864 | 12,864 | SF | \$30,353 | |
| Walls - Structural Glazed Tile | 6 | | | | | | | | | 50 | 7,029 | 1,635 | 8,714 | SF | \$52,617 |
| | | | | | | | | | | | | | | \$267,504 | |

DOORS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Interior Steel Doors incl hw | 6 | | | | | | 9 | | 9 | EA | \$2,548 |
| Interior Wood Doors incl hw | 6 | | | | | 4 | 119 | | 123 | EA | \$35,581 |
| | | | | | | | | | | | \$38,130 |

DRINKING FOUNTAINS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Double Fountain | 6 | | | | | | 6 | | 6 | EA | \$3,947 |
| Single Fountain | 6 | | | | | | 4 | | 4 | EA | \$1,544 |
| | | | | | | | | | | | \$5,491 |

GYMNASIUM / AUDITORIUM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--------------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------------|
| Ceiling - Plaster/Drywall | 6 | | | | | | 4,500 | | 4,500 | SF | \$38,481 |
| Flooring - Wood | 6 | | | | | | 4,500 | | 4,500 | SF | \$33,977 |
| Lighting - Metal Halide/Sodium Vapor | 6 | | | | | | 15 | | 15 | EA | \$2,681 |
| Scoreboards | 6 | | | | | | 1 | | 1 | EA | \$2,076 |
| Sound System | 6 | | | | | | 1 | | 1 | EA | \$5,005 |
| Stage Curtain | 6 | | | | | | 2 | | 2 | EA | \$18,876 |
| Stage Platform | 6 | | | | | | 890 | | 890 | SF | \$3,780 |
| Walls - Concrete Block | 6 | | | | | | 3,144 | | 3,144 | SF | \$26,976 |
| Walls - Structural Glazed Tile | 6 | | | | | | 2,096 | | 2,096 | SF | \$14,986 |
| | | | | | | | | | | | \$146,839 |

KITCHEN

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Ceiling - Plaster/Drywall | 6 | | | | | | 1,143 | | 1,143 | SF | \$4,315 |
| Flooring - Tile Ceramic/Porcelain | 6 | | | | | | 1,143 | | 1,143 | SF | \$2,909 |
| Lighting - Pendant/Surface | 6 | | | | | | 16 | | 16 | SF | \$11 |
| Wall - Plaster/Drywall | 6 | | | | | | 1,343 | | 1,343 | SF | \$3,169 |
| | | | | | | | | | | | \$10,405 |

LIBRARY

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Flooring Carpet | 6 | | | | | | 903 | | 903 | SF | \$1,291 |
| Lighting - Pendant/ Surface | 6 | | | | | | 15 | | 15 | SF | \$11 |
| | | | | | | | | | | | \$1,302 |

LOCKER/SHOWER ROOM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Benches | 7 | | | | | | | 15 | 15 | LF | \$0 |
| Lockers | 6 | | | | | | 44 | | 44 | EA | \$2,159 |
| Showers | 6 | | | | | | 7 | | 7 | EA | \$1,702 |
| | | | | | | | | | | | \$3,861 |

LUNCHROOM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|----------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Ceiling - Plaster/Drywall | 6 | | | | | | 2,022 | | 2,022 | SF | \$5,725 |
| Flooring - Tile/Sheet | 6 | | | | | | 2,022 | | 2,022 | SF | \$2,891 |
| Lighting - Pendant/Surface | 6 | | | | | | 24 | | 24 | SF | \$17 |
| Serving Line | 6 | | | | | | 24 | | 24 | LF | \$1,030 |
| Wall - Plaster/Drywall | 6 | | | | | | 1,545 | | 1,545 | SF | \$3,645 |
| | | | | | | | | | | | \$13,309 |

MDF/IDF

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Finishes | 6 | | | | | | 172 | | 172 | SF | \$585 |
| Ventilation and Cooling | 6 | | | | | | 1 | | 1 | EA | \$1,401 |
| | | | | | | | | | | | \$1,987 |

MECHANICAL/SERVICE ROOMS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Boiler Room | 6 | | | | | | 1,680 | | 1,680 | SF | \$7,928 |
| Crawl Space - Unfinished | 6 | | | | | | 18,480 | | 18,480 | SF | \$34,883 |
| Janitor's Closet | 6 | | | | | | 4 | | 4 | SF | \$19 |
| Mechanical/Service Rooms | 6 | | | | | | 5,463 | | 5,463 | SF | \$25,780 |
| Storage Room | 6 | | | | | 375 | 2,694 | | 3,069 | SF | \$16,960 |
| Vaults | 6 | | | | | | 520 | | 520 | SF | \$2,454 |
| | | | | | | | | | | | \$88,024 |

PHYSICAL EDUCATION ROOMS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|------------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Wall Mirrors | 7 | | | | | | | 138 | 138 | SF | \$0 |
| Weight/ Fitness Room Floor Matting | 7 | | | | | | | 684 | 684 | SF | \$0 |
| | | | | | | | | | | | \$0 |

STAFF RESTROOM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------|
| Accessories | 6 | | | | | | 3,767 | | 3,767 | SF | \$29,089 |
| Ceiling - Plaster/Drywall | 6 | | | | | | 3,707 | | 3,707 | SF | \$10,496 |
| Floor Drain | 6 | | | | | | 16 | | 16 | EA | \$4,805 |
| Flooring - Tile Ceramic/Porcelain | 6 | | | | | | 2,966 | | 2,966 | SF | \$7,550 |
| Flooring - Tile/Sheet | 6 | | | | | | 801 | | 801 | SF | \$1,145 |
| Hand Dryer | 6 | | | | | | 17 | | 17 | EA | \$3,690 |
| Lavatory | 6 | | | | | 4 | 31 | | 35 | EA | \$18,962 |
| Lighting - Lay-In | 5 | | | | | 4 | | | 4 | SF | \$6 |

| | | | | | | | | | | | | | |
|--------------------------------|---|--|--|--|--|--|--|--|---|-------|-------|----|------------------|
| Lighting - Pendant/ Surface | 6 | | | | | | | | | 47 | 47 | SF | \$34 |
| Partitions | 6 | | | | | | | | | 33 | 33 | EA | \$5,918 |
| Urinals | 6 | | | | | | | | | 8 | 8 | EA | \$2,974 |
| Wall - Concrete Block | 6 | | | | | | | | | 2,735 | 2,735 | SF | \$7,822 |
| Wall - Plaster/Drywall | 6 | | | | | | | | | 2,393 | 2,393 | SF | \$5,646 |
| Wall - Structural Glazed Tile | 6 | | | | | | | | | 2,078 | 2,078 | SF | \$14,858 |
| Wall - Tile Ceramic/ Porcelain | 6 | | | | | | | | | 4,903 | 4,903 | SF | \$12,480 |
| Water Closet | 6 | | | | | | | | 4 | 39 | 43 | EA | \$21,936 |
| | | | | | | | | | | | | | \$147,410 |

VERTICAL CONVEYANCE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-------------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Elevator - Roped Holeless Hydraulic | 6 | | | | | | 1 | | 1 | EA | \$17,160 |
| Stage Lift | 7 | | | | | | | 1 | 1 | EA | \$0 |
| | | | | | | | | | | | \$17,160 |

VOCATIONAL SHOP

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Work Sink | 6 | | | | | | 16 | 3 | 19 | EA | \$6,178 |
| | | | | | | | | | | | \$6,178 |

INTERIOR Total \$786,264

ROOM

CASEWORK

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Casework | 6 | | | | | | 165 | | 165 | LF | \$5,899 |
| | | | | | | | | | | | \$5,899 |

CEILING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------|
| Lay-In/Drop | 7 | | | | | | | 2,126 | 2,126 | SF | \$0 |
| Plaster/Drywall | 6 | | | | | | 15,558 | 5,114 | 20,672 | SF | \$44,051 |

\$44,051

CLASSROOM

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|----------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Eye Wash Station | 7 | | | | | | | 2 | 2 | EA | \$0 |
| Science Lab Elements | 7 | | | | | | | 1,442 | 1,442 | SF | \$0 |
| Science Lab Shower | 7 | | | | | | | 2 | 2 | EA | \$0 |
| | | | | | | | | | | | \$0 |

FLOOR

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Tile/Sheet | 6 | | | | | | 12,287 | 10,511 | 22,798 | SF | \$17,570 |
| | | | | | | | | | | | \$17,570 |

LIBRARY CEILING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Plaster/Drywall | 6 | | | | | | 903 | | 903 | SF | \$2,557 |
| | | | | | | | | | | | \$2,557 |

LIBRARY WALL

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|----------------|
| Plaster/Drywall | 6 | | | | | | 1,550 | | 1,550 | | \$3,657 |
| | | | | | | | | | | | \$3,657 |

LIGHTING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Pendant/Surface | 6 | | | | | | 157 | 249 | 406 | EA | \$11,226 |
| | | | | | | | | | | | \$11,226 |

MARKER BOARD

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Marker Board | 7 | | | | | | | 627 | 627 | LF | \$0 |
| | | | | | | | | | | | \$0 |

RESTROOM CEILING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------|
| Restroom Ceiling | 6 | | | | | | 60 | | 60 | SF | \$170 |
| | | | | | | | | | | | \$170 |

RESTROOM LIGHT

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------|
| Restroom Lighting | 6 | | | | | | 6 | | 6 | EA | \$172 |
| | | | | | | | | | | | \$172 |

WALL

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Plaster/Drywall | 6 | | | | | | 34,352 | | 34,352 | SF | \$81,054 |
| | | | | | | | | | | | \$81,054 |

| | | | | | | | | | | | |
|-------------------|--|--|--|--|--|--|--|--|--|--|------------------|
| ROOM Total | | | | | | | | | | | \$166,355 |
|-------------------|--|--|--|--|--|--|--|--|--|--|------------------|

SITE

CIVIL/DRAINAGE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------|
| Catch Basin | 6 | | | | | | 1 | | 1 | EA | \$543 |
| Site Drain | 6 | | | | | | 2 | | 2 | EA | \$223 |
| Site Manhole | 7 | | | | | | | 1 | 1 | EA | \$0 |
| | | | | | | | | | | | \$766 |

FENCING

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Chain Link | 5 | | | | 72 | | 134 | | 206 | LF | \$9,644 |
| Ornamental Iron | 6 | | | | | | 894 | | 894 | LF | \$16,875 |
| | | | | | | | | | | | \$26,519 |

LANDSCAPE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|----------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|--------------------|
| Grass | 6 | | | | | | 5,434 | | 5,434 | SF | \$2,176 |
| Hardscape - Concrete | 5 | | | | 321 | | | 138 | 459 | SF | \$6,059 |
| Parkway trees | 6 | | | | | | 12,804 | | 12,804 | EA | \$3,661,944 |
| Trash Receptacles | 7 | | | | | | | 2 | 2 | EA | \$0 |
| | | | | | | | | | | | \$3,670,179 |

PARKING LOT

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|-----------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------------|
| Asphalt | 4 | | | | 41,321 | 5,139 | | | 46,460 | SF | \$369,085 |
| Concrete | 7 | | | | | | | 1,130 | 1,130 | SF | \$0 |
| Concrete Curbs | 5 | | | | | 192 | | | 192 | LF | \$3,827 |
| Trash Enclosure | 7 | | | | | | | 672 | 672 | SF | \$0 |
| | | | | | | | | | | | \$372,912 |

SIDEWALKS

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|---------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|-----------------|
| Perimeter Sidewalks | 6 | | | | | | 12,804 | | 12,804 | SF | \$24,169 |
| | | | | | | | | | | | \$24,169 |

SIGNAGE

| Assessed Item | Composite Rank | Rank 1 Qty | Rank 2 Qty | Rank 3 Qty | Rank 4 Qty | Rank 5 Qty | Rank 6 Qty | Rank 7 Qty | Total Quantity | Unit | Cost |
|--------------------------------------|----------------|------------|------------|------------|------------|------------|------------|------------|----------------|------|------------|
| Flag Pole | 6 | | | | | | 1 | | 1 | EA | \$0 |
| Marquee - Free Standing Back Lighted | 6 | | | | | | 1 | | 1 | EA | \$0 |
| | | | | | | | | | | | \$0 |

| | | | | | | | | | | | |
|-------------------|--|--|--|--|--|--|--|--|--|--|--------------------|
| SITE Total | | | | | | | | | | | \$4,094,545 |
|-------------------|--|--|--|--|--|--|--|--|--|--|--------------------|

Total Campus Need ^{2 3}

\$6,182,940

¹ It is very rare for an assessor to find a feature in this condition. If they do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in summary reports; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.