

## Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Kennedy	1965	3	233,791	\$8,414,916
Kinzie	1954	2	111,615	\$4,403,405
SITE				\$395,598
<b>Campus Total</b>			<b>345,406</b>	<b>\$13,213,919</b>

### Building: Kennedy

#### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	3	EA	7	\$0
	Exterior Doors - Exterior FRP Door	6	EA	6	\$3,788
	Exterior Doors - Exterior FRP Door	5	EA	7	\$0
	Exterior Doors - Exterior Steel Door	1	EA	4	\$3,823
	Exterior Doors - Exterior Steel Door	7	EA	5	\$9,389
	Exterior Doors - Exterior Steel Door	3	EA	6	\$1,442
	Exterior Doors - Overhead Rolling/ Garage Door	1	EA	5	\$3,942
	Exterior Doors - Side lite	4	EA	7	\$0
	Exterior Doors - Store Front	15	EA	7	\$0
	Exterior Doors - Transom Lite	2	EA	6	\$627
	Exterior Doors - Transom Lite	20	EA	7	\$0
	Exterior Stairs - Concrete	2	LF	4	\$327
	Exterior Stairs - Concrete	182	LF	6	\$14,882
	Exterior Stairs - Concrete	427	LF	7	\$0
	Power Door Operator and Controls	3	EA	7	\$0
	Ramp Handrail - Steel_Ramp Handrail	120	LF	5	\$1,272
	Ramp Handrail - Steel_Ramp Handrail	470	LF	6	\$4,073
	Ramp Handrail - Steel_Ramp Handrail	96	LF	7	\$0

## Building: Kennedy

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Ramps - Concrete	114	LF	6	\$17,127
	Ramps - Concrete	220	LF	7	\$0
	Stair Handrail - Steel_Stair Handrail	25	LF	5	\$287
	Stair Handrail - Steel_Stair Handrail	136	LF	6	\$1,179
	Stair Handrail - Steel_Stair Handrail	42	LF	7	\$0
<b>Foundation</b>					
	Foundation - Concrete	1,615	LF	7	\$0
	Superstructure - Concrete	237,191	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	19	EA	7	\$0
	Exterior Lighting - Wall Mounted	1	EA	4	\$1,030
	Exterior Lighting - Wall Mounted	11	EA	6	\$3,176
	Exterior Lighting - Wall Mounted	2	EA	7	\$0
<b>Roof System</b>					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	50	LF	6	\$47,734
	Coping - Metal	2,389	LF	6	\$76,729
	Coping - Metal	50	LF	7	\$0
	Downspouts - Interior Downspouts	22	LF	6	\$731
	Downspouts - Interior Downspouts	968	LF	7	\$0
	Roof - Asphalt Gravel Ballast	120	SF	5	\$3,719
	Roof - Asphalt Gravel Ballast	78,100	SF	6	\$794,066
	Roof - EPDM/ Synthetic Rubber	3,400	SF	6	\$28,783
	Roof - Modified Bitumen	1,596	SF	6	\$15,017
	Roof - Modified Bitumen	150	SF	7	\$0
	Roof Structure - Concrete	83,396	SF	7	\$0
<b>Walls</b>					
	Canopy - Concrete/ Stucco	300	SF	5	\$30,223
	Canopy - Concrete/ Stucco	222	SF	6	\$8,136
	Canopy - Metal	24	SF	5	\$1,763
	Canopy - Metal	320	SF	6	\$7,871
	Canopy - Metal	692	SF	7	\$0
	Cheek-Wall - Concrete	94	SF	6	\$964
	Cheek-Wall - Concrete	500	SF	7	\$0
	Exterior Walls - Brick	40	SF	4	\$6,586
	Exterior Walls - Brick	2,405	SF	5	\$57,262

## Building: Kennedy

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Walls</b>					
	Exterior Walls - Brick	21,440	SF	6	\$144,098
	Exterior Walls - Brick	520	SF	7	\$0
	Exterior Walls - Prefabricated Metal Panel Wall	2,700	SF	7	\$0
	Exterior Walls - Stone-Cut	5,250	SF	6	\$35,285
<b>Windows</b>					
	Guard - Guards perforated	588	SF	7	\$0
	Guard - Guards wire guard	200	SF	6	\$2,554
	Lintels - Concrete	45	LF	7	\$0
	Lintels - Steel	6	LF	4	\$2,717
	Lintels - Steel	721	LF	5	\$243,674
	Lintels - Steel	21	LF	7	\$0
	Lintels - Stone	128	LF	7	\$0
	Windows - Insulated Panel	1,185	SF	5	\$37,348
	Windows - Insulated Panel	10,000	SF	6	\$74,646
	Windows - Sash Aluminum Double-pane	17,335	SF	7	\$0

### Building Exterior Subtotal:

**\$1,686,269**

## Building: Kennedy

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	2	EA	7	\$0
	Emergency A/C Power - Auditorium and Aisle Lighting	7,260	SF	6	\$3,841
	Emergency A/C Power - Corridors and Stairs	31,543	SF	6	\$9,472
	Emergency A/C Power - Gym	13,083	SF	6	\$4,864
	Emergency A/C Power - Students Toilets	4,341	SF	6	\$1,614
	Emergency Battery Packs - Lunchrooms	1	EA	4	\$579
	Emergency Generator- Outdoor- Diesel - 101 - 150 KW	1	EA	6	\$11,529
	Exit Signs - Auditorium	12	EA	6	\$1,797
	Exit Signs - Corridors and Stairs	64	EA	6	\$9,584
	Exit Signs - Gym	1	EA	2	\$578
	Exit Signs - Gym	5	EA	6	\$787
	Exit Signs - Lunchroom	4	EA	6	\$599
	Exit Signs - Pool	4	EA	6	\$620
	Security System - CCTV	233,791	SF	6	\$70,207

## Building: Kennedy

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Security System - Intrusion Detection	233,791	SF	6	\$60,178
<b>Main Service</b>					
	Independent Electrical Service for emergency power	1	EA	7	\$0
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	1	EA	7	\$0
	Main Electrical Service - Greater than 3000 A 120/208/3PH	1	EA	6	\$16,381
	PA System	233,791	SF	6	\$76,894
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	6	EA	4	\$29,096
	Lighting and Power Panels - 100 A	4	EA	6	\$1,196
	Lighting and Power Panels - 100 A	28	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	2	EA	4	\$42,209
	Main Distribution Panels - Less than 400 amp	2	EA	7	\$0
	Transformers - 277/480 - 120/208	3	EA	7	\$0
<b>Electrical System Subtotal:</b>					<b>\$342,027</b>

## Building: Kennedy

### Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	7	\$0
	Fire Alarm Strobe Lights	233,791	SF	6	\$83,580
	Fire Alarm_System	233,791	SF	6	\$113,669
<b>Safty System Subtotal:</b>					<b>\$197,249</b>

## Building: Kennedy

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Chemical Pot Feeder	1	EA	6	\$606
	Chiller-Air Cooled-Screw Type-Roof Mounted - 201 - 300 tons	2	EA	6	\$8,628
	Condensing Unit- Ground Mounted - Less than 5 tons	3	EA	7	\$0

**Building: Kennedy**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Handling Systems</b>					
	Air Handling Unit- Built Up- Single Zone- Steam Coils and Chilled Water Coils - 8001 - 15000 cfm	1	EA	6	\$4,341
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils and Chilled Water Coils - 25001 - 35000 cfm	2	EA	6	\$13,022
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils and Chilled Water Coils - Less than 8000 cfm	1	EA	6	\$3,321
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 8001-12000 cfm	4	EA	5	\$136,700
	Air Intake	2	EA	6	\$11,529
	Air Intake	2	EA	7	\$0
	Auxiliaries - 25001 - 35000 cfm	2	EA	6	\$13,022
	Auxiliaries - 8001 - 15000 cfm	1	EA	7	\$0
	Auxiliaries - 8001-12000 cfm	4	EA	5	\$0
	Auxiliaries - Less than 8000 cfm	1	EA	6	\$3,321
	Fan Coil Unit- Ceiling Mounted - Hot Water and Chilled Water	11	EA	6	\$17,645
	Fan Coil Unit- Ceiling Mounted - Steam	2	EA	7	\$0
	Fan Coil Unit- Floor Mounted - Steam	38	EA	6	\$58,169
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	1	EA	6	\$2,433
	Outdoor Return Fans- Air Handling Unit Type - 10001 - 20000 CFM	3	EA	6	\$4,772
	Reheat Boxes	6	EA	7	\$0
	Reheat Boxes - Reheat Boxes with Steam Coil	13	EA	7	\$0
	Return Duct Work	300	LF	6	\$0
	Zone Dampers	47	EA	7	\$0
<b>Boiler Systems</b>					
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 201 - 300 HP	3	EA	5	\$83,390
	Chemical Feed System	1	EA	6	\$1,078
	Combustion Dampers	3	EA	3	\$19,660
	Condensate Pump	1	EA	4	\$44,329
	Condensate Pump	2	EA	5	\$36,392
	Feed Water Pumps and Tank	1	EA	6	\$2,545
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 201 - 300 HP	3	EA	5	\$83,390
	Piping - Steam Pipe- Steel	1,000	LF	4	\$294,208
	Steam Traps	70	EA	5	\$92,043
<b>Heat Exchangers</b>					
	Heat Exchanger - Steam to Hot Water Shell Type	2	EA	7	\$0
<b>Heating Devices</b>					
	Cabinet Heaters - With Hot Water Coil	3	EA	4	\$11,516
	Cabinet Heaters - With Hot Water Coil	3	EA	5	\$5,264

**Building: Kennedy**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Heating Devices</b>					
	Cabinet Heaters - With Hot Water Coil	4	EA	6	\$1,417
	Cabinet Heaters - With Hot Water Coil	9	EA	7	\$0
	Fin Tube - Steam	255	LF	6	\$2,407
	Unit Heater - Electric	2	EA	6	\$556
	Unit Heater - Steam	1	EA	4	\$1,755
	Wall Heater - Electric	1	EA	6	\$139
	Wall Heater - Electric	2	EA	7	\$0
<b>Mechanical Plumbing</b>					
	Chilled Water Pump - 10 - 20 HP	5	EA	6	\$6,212
	Condensate-Steel or Galvanized	1,800	LF	4	\$586,949
	Hot Water Pump - Less than 10	2	EA	6	\$2,222
	Hydronic Supply and Return - Steel	1,800	LF	6	\$138,198
<b>Temperature Control</b>					
	DDC System	251,526	SF	6	\$143,873
	Electric Thermostat	13	EA	6	\$0
	Thermostats - DDC	65	EA	6	\$0
<b>Ventilation</b>					
	Exhaust Fans- Indoor - 1501 - 8000 CFM	1	EA	3	\$6,392
	Exhaust Fans- Indoor - 500 - 1500 CFM	1	EA	7	\$0
	Exhaust Fans- Indoor - Greater than 8000 CFM	5	EA	4	\$56,951
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	4	EA	3	\$25,568
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	1	EA	6	\$592
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	5	EA	7	\$0
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	1	EA	3	\$4,245
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	3	EA	6	\$1,777
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	2	EA	7	\$0
	Exhaust Fans- Roof Mounted - Less than 500 CFM	1	EA	3	\$1,942
	Exhaust Fans- Roof Mounted - Less than 500 CFM	1	EA	7	\$0
	Lab Exhaust Hood	1	EA	7	\$0
	Type I Exhaust Hood- Kitchen	3	EA	7	\$0

**Mechanical System Subtotal:** **\$1,932,520**

**Building: Kennedy**
**Category: Plumbing System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - Greater than 600000 BTU/HR	1	EA	7	\$0
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	2	EA	4	\$26,540
	Steam Heat Exchanger	2	EA	7	\$0
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	233,791	SF	4	\$167,161
	Domestic Piping-Cold Water Horizontal Lines	233,791	SF	4	\$337,664
	Domestic Piping-Cold Water Risers	233,791	SF	4	\$187,220
	Domestic Piping-Hot Water from Risers to Fixtures	233,791	SF	4	\$127,042
	Domestic Piping-Hot Water Horizontal Lines	233,791	SF	4	\$300,889
	Domestic Piping-Hot Water Return Lines	233,791	SF	4	\$200,593
	Domestic Piping-Hot Water Return Risers	233,791	SF	4	\$113,669
	Sanitary Piping	233,791	SF	6	\$213,966
	Storm Piping	233,791	SF	6	\$203,936
	Vent Piping	233,791	SF	6	\$157,131
<b>Pool Systems</b>					
	Pool Drain Piping	50	LF	7	\$0
	Pool Filtration System including Pump	1	EA	7	\$0
	Pool Hot Water Heater - Gas Fired	1	EA	7	\$0
	Pool Supply and Return Piping	400	LF	7	\$0
<b>Pumps</b>					
	Pumps - Domestic Booster Pump-Duplex	1	EA	7	\$0
	Pumps - Ejector-Duplex	2	EA	6	\$2,774
	Pumps - Sump-Simplex	1	EA	4	\$11,443
<b>Plumbing System Subtotal:</b>					<b>\$2,050,028</b>

## Building: Kennedy

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (2 rooms)</b>					
	Casework	24	LF	5	\$5,018
	Casework	61	LF	7	\$0
	Ceiling - Lay-in	1,569	SF	7	\$0
	Ceiling - Splined	909	SF	7	\$0
	Chalk Board	10	LF	4	\$918
	Doors - Steel Doors incl hw	1	EA	7	\$0
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Floor - Concrete	1,569	SF	6	\$830

## Building: Kennedy

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (2 rooms)</b>					
	Floor - Tile/Sheet	909	SF	6	\$910
	Lighting - Pendent/Surface	38	EA	6	\$4,708
	Lighting - Pendent/Surface	18	EA	7	\$0
	Lighting - Wall Mounted	3	EA	5	\$508
	Marker Board	8	LF	7	\$0
	Walls - Concrete Block	2,428	SF	6	\$7,118
	Work Sink	3	EA	6	\$1,137
<b>Computer Lab (6 rooms)</b>					
	Casework	115	LF	6	\$2,904
	Casework	49	LF	7	\$0
	Ceiling - Splined	369	SF	6	\$301
	Ceiling - Splined	4,788	SF	7	\$0
	Chalk Board	42	LF	4	\$3,856
	Doors - Side-lite	24	SF	7	\$0
	Doors - Wood Doors inclu hw	10	EA	7	\$0
	Floor - Carpet	2,949	SF	6	\$6,283
	Floor - Tile/Sheet	1,110	SF	5	\$4,984
	Floor - Tile/Sheet	1,098	SF	6	\$1,099
	Lighting - Pendent/Surface	92	EA	7	\$0
	Marker Board	20	LF	6	\$428
	Marker Board	40	LF	7	\$0
	Walls - Concrete Block	5,046	SF	7	\$0
	Walls - Plaster/Drywall	648	SF	7	\$0
	Wireless System	3	EA	7	\$0
	Work Sink	3	EA	6	\$1,137
	Work Sink	1	EA	7	\$0
<b>Fitness Room (1 room)</b>					
	Ceiling - Exposed	1,086	SF	6	\$1,615
	Doors - Wood Doors inclu hw	1	EA	7	\$0
	Floor - Weight/ Fitness Room Floor Matting	26	SF	6	\$183
	Floor - Weight/ Fitness Room Floor Matting	1,060	SF	7	\$0
	Lighting - Pendent/Surface	20	EA	7	\$0
	Storage/ Closet	200	SF	6	\$1,450
	Walls - Concrete Block	1,670	SF	7	\$0
<b>Music Room (2 rooms)</b>					
	Casework	8	LF	6	\$202



## Building: Kennedy

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Music Room (2 rooms)</b>					
	Casework	8	LF	7	\$0
	Ceiling - Lay-in	1,303	SF	7	\$0
	Ceiling - Splined	1,387	SF	7	\$0
	Chalk Board	40	LF	4	\$3,672
	Doors - Steel Doors incl hw	3	EA	7	\$0
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Floor - Carpet	2,162	SF	7	\$0
	Floor - Tile/Sheet	528	SF	6	\$529
	Instrument Storage Casework	28	LF	7	\$0
	Lighting - Lay-in	15	EA	6	\$1,785
	Lighting - Pendent/Surface	32	EA	7	\$0
	Risers	89	LF	7	\$0
	Storage/ Closet	455	SF	7	\$0
	Walls - Concrete Block	2,764	SF	7	\$0
<b>Other Instructional Use (1 room)</b>					
	Casework	35	LF	6	\$884
	Ceiling - Splined	1,110	SF	7	\$0
	Chalk Board	8	LF	4	\$734
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Floor - Carpet	1,110	SF	6	\$2,365
	Lighting - Pendent/Surface	24	EA	4	\$12,975
	Marker Board	3	LF	7	\$0
	Walls - Concrete Block	1,102	SF	6	\$3,231
	Work Sink	1	EA	5	\$1,508
<b>Regular Classroom (32 rooms)</b>					
	Casework	381	LF	6	\$9,622
	Ceiling - Plaster/Drywall	116	SF	5	\$1,450
	Ceiling - Plaster/Drywall	3,272	SF	6	\$11,323
	Ceiling - Splined	42	SF	4	\$590
	Ceiling - Splined	2,275	SF	5	\$16,201
	Ceiling - Splined	5,434	SF	6	\$4,429
	Ceiling - Splined	11,127	SF	7	\$0
	Chalk Board	76	LF	4	\$6,977
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Wood Doors inclu hw	2	EA	6	\$602

## Building: Kennedy

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Regular Classroom (32 rooms)</b>					
	Doors - Wood Doors inclu hw	29	EA	7	\$0
	Floor - Tile	2,019	SF	6	\$4,417
	Floor - Tile/Sheet	557	SF	5	\$2,501
	Floor - Tile/Sheet	8,670	SF	6	\$8,679
	Floor - Tile/Sheet	11,020	SF	7	\$0
	Lighting - Pendent/Surface	212	EA	4	\$114,616
	Lighting - Pendent/Surface	8	EA	5	\$1,461
	Lighting - Pendent/Surface	37	EA	6	\$4,584
	Lighting - Pendent/Surface	220	EA	7	\$0
	Marker Board	20	LF	4	\$1,786
	Marker Board	73	LF	6	\$1,564
	Marker Board	486	LF	7	\$0
	Walls - Concrete Block	4,719	SF	6	\$13,834
	Walls - Concrete Block	17,303	SF	7	\$0
	Walls - Metal Panel	502	SF	6	\$3,747
	Walls - Plaster/Drywall	966	SF	5	\$7,321
	Walls - Plaster/Drywall	3,286	SF	6	\$9,069
	Walls - Plaster/Drywall	348	SF	7	\$0
	Walls - Structural Glazed Tile	1,137	SF	6	\$3,577
	Work Sink	3	EA	5	\$4,523
	Work Sink	4	EA	6	\$1,516
	Work Sink	2	EA	7	\$0
<b>Science Classroom (4 rooms)</b>					
	Casework	382	LF	6	\$9,647
	Casework	324	LF	7	\$0
	Ceiling - Lay-in	2,850	SF	6	\$8,559
	Ceiling - Splined	2,188	SF	7	\$0
	Doors - Wood Doors inclu hw	7	EA	7	\$0
	Floor - Tile/Sheet	5,038	SF	7	\$0
	Lighting - Lay-in	52	EA	7	\$0
	Lighting - Pendent/Surface	28	EA	6	\$3,469
	Lighting - Pendent/Surface	28	EA	7	\$0
	Lighting - Wall Mounted	2	EA	6	\$248
	Marker Board	36	LF	7	\$0
	Storage/ Closet	240	SF	7	\$0
	Walls - Concrete Block	741	SF	6	\$2,172
	Walls - Concrete Block	2,578	SF	7	\$0

## Building: Kennedy

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Science Classroom (4 rooms)</b>					
	Walls - Plaster/Drywall	762	SF	7	\$0
	Work Sink	1	EA	5	\$1,508
	Work Sink	7	EA	6	\$2,653
<b>Science Lab Level 1 (1 room)</b>					
	Casework	157	LF	7	\$0
	Ceiling - Lay-in	1,402	SF	6	\$4,210
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Eye Wash Station	1	EA	7	\$0
	Floor - Tile/Sheet	1,402	SF	7	\$0
	Fume Hood	1	EA	7	\$0
	Gas Line	8	EA	7	\$0
	Lighting - Lay-in	23	EA	7	\$0
	Marker Board	9	LF	7	\$0
	Science Lab Shower	1	EA	7	\$0
	Walls - Concrete Block	792	SF	7	\$0
	Walls - Plaster/Drywall	298	SF	7	\$0
	Work Sink	1	EA	6	\$379
	Work Sink	10	EA	7	\$0
<b>Science Lab Level 2 (1 room)</b>					
	Casework	89	LF	7	\$0
	Ceiling - Lay-in	1,242	SF	7	\$0
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Eye Wash Station	1	EA	7	\$0
	Floor - Tile/Sheet	1,242	SF	7	\$0
	Gas Line	7	EA	7	\$0
	Lighting - Lay-in	24	EA	7	\$0
	Marker Board	12	LF	6	\$257
	Science Lab Shower	1	EA	7	\$0
	Walls - Concrete Block	1,007	SF	7	\$0
	Walls - Plaster/Drywall	178	SF	7	\$0
	Work Sink	7	EA	7	\$0
<b>Special Education (1 room)</b>					
	Casework	7	LF	7	\$0
	Ceiling - Splined	388	SF	5	\$2,763
	Doors - Wood Doors inclu hw	1	EA	7	\$0
	Floor - Tile/Sheet	388	SF	6	\$388

## Building: Kennedy

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Special Education (1 room)</b>					
	Lighting - Pendent/Surface	9	EA	7	\$0
	Marker Board	6	LF	7	\$0
	Walls - Concrete Block	500	SF	7	\$0
	Walls - Plaster/Drywall	26	SF	6	\$72
<b>Special Program (6 rooms)</b>					
	AC Units	1	EA	4	\$6,086
	Casework	66	LF	6	\$1,667
	Casework	16	LF	7	\$0
	Ceiling - Plaster/Drywall	417	SF	6	\$1,443
	Ceiling - Splined	1,231	SF	6	\$1,003
	Ceiling - Splined	769	SF	7	\$0
	Chalk Board	6	LF	5	\$314
	Doors - Wood Doors inclu hw	7	EA	7	\$0
	Floor - Carpet	369	SF	6	\$786
	Floor - Tile/Sheet	400	SF	4	\$3,867
	Floor - Tile/Sheet	1,648	SF	6	\$1,650
	Lighting - Pendent/Surface	19	EA	4	\$10,272
	Lighting - Pendent/Surface	16	EA	6	\$1,982
	Lighting - Pendent/Surface	8	EA	7	\$0
	Marker Board	67	LF	7	\$0
	Storage/ Closet	116	SF	7	\$0
	Walls - Concrete Block	1,484	SF	6	\$4,350
	Walls - Concrete Block	1,807	SF	7	\$0
	Walls - Plaster/Drywall	990	SF	6	\$2,732
	Walls - Plaster/Drywall	216	SF	7	\$0
	Work Sink	1	EA	6	\$379

**Classrooms Subtotal:**

**\$381,422**

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Ceiling - Lay-in	89	SF	5	\$529
	Ceiling - Lay-in	94	SF	7	\$0
	Ceiling - Plaster/Drywall	103	SF	4	\$1,839

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Ceiling - Plaster/Drywall	376	SF	5	\$3,847
	Ceiling - Plaster/Drywall	5,932	SF	6	\$20,543
	Ceiling - Plaster/Drywall	1,407	SF	7	\$0
	Ceiling - Splined	172	SF	5	\$1,322
	Ceiling - Splined	697	SF	6	\$568
	Ceiling - Splined	538	SF	7	\$0
	Doors - Side-lite	42	SF	7	\$0
	Doors - Steel Doors incl hw	3	EA	5	\$3,522
	Doors - Steel Doors incl hw	15	EA	6	\$4,515
	Doors - Steel Doors incl hw	2	EA	7	\$0
	Doors - Store Front	1	EA	7	\$0
	Doors - Wood Doors inclu hw	19	EA	6	\$5,719
	Doors - Wood Doors inclu hw	33	EA	7	\$0
	Floor - Carpet	722	SF	6	\$1,538
	Floor - Carpet	663	SF	7	\$0
	Floor - Tile	1,525	SF	5	\$6,848
	Floor - Tile	3,898	SF	6	\$8,528
	Floor - Tile Ceramic/ Porcelain	330	SF	6	\$698
	Floor - Tile Quarry	80	SF	6	\$169
	Floor - Tile/Sheet	546	SF	6	\$547
	Floor - Tile/Sheet	1,903	SF	7	\$0
	Floor - Wood	96	SF	7	\$0
	Lighting - Lay-in	3	EA	5	\$487
	Lighting - Lay-in	18	EA	6	\$2,142
	Lighting - Lay-in	12	EA	7	\$0
	Lighting - Pendent/Surface	1	EA	5	\$183
	Lighting - Pendent/Surface	13	EA	6	\$1,611
	Lighting - Pendent/Surface	128	EA	7	\$0
	Lighting - Wall Mounted	2	EA	7	\$0
	Power Distribution	28	EA	6	\$59,497
	Power Distribution	229	EA	7	\$0
	Storage/ Closet	22	SF	5	\$355
	Storage/ Closet	107	SF	6	\$776
	Storage/ Closet	49	SF	7	\$0
	Walls - Concrete Block	6,464	SF	6	\$18,949
	Walls - Concrete Block	7,460	SF	7	\$0
	Walls - Metal Panel	3,281	SF	6	\$24,491

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Walls - Metal Panel	349	SF	7	\$0
	Walls - Plaster/Drywall	218	SF	4	\$2,195
	Walls - Plaster/Drywall	155	SF	5	\$685
	Walls - Plaster/Drywall	2,771	SF	6	\$7,648
	Walls - Plaster/Drywall	1,334	SF	7	\$0
	Walls - Structural Glazed Tile	775	SF	7	\$0
	Work Sink	1	EA	5	\$1,508
	Work Sink	4	EA	6	\$2,033
<b>Auditorium &amp; Theater</b>					
	Ceiling - Plaster/Drywall	8,600	SF	6	\$73,318
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Wood Doors inclu hw	8	EA	7	\$0
	Floor - Carpet	3,900	SF	7	\$0
	Floor - Concrete Epoxy/ Painted	3,300	SF	6	\$1,746
	Floor - Terrazzo	60	SF	7	\$0
	Lighting - Pendent/Surface	78	EA	7	\$0
	Lighting - Wall Mounted	12	EA	5	\$2,034
	Main Floor Seating	72	EA	5	\$27,399
	Main Floor Seating	646	EA	6	\$112,350
	Sound System	1	EA	7	\$0
	Stage	1,430	SF	6	\$8,261
	Stage Curtain	3	EA	7	\$0
	Stage Lighting System	1	EA	7	\$0
	Stage-Stairs - Terrazzo	67	LF	7	\$0
	Storage/ Closet	320	SF	5	\$5,162
	Storage/ Closet	44	SF	7	\$0
	Walls - Plaster/Drywall	1,800	SF	6	\$8,571
	Walls - Sound Panel	200	SF	6	\$807
	Walls - Sound Panel	2,300	SF	7	\$0
	Walls - Structural Glazed Tile	2,840	SF	7	\$0
	Walls - Tile Ceramic/ Porcelain	600	SF	7	\$0
<b>Gymnasia</b>					
	Bleacher Seating	119	EA	7	\$0
	Ceiling - Lay-in	11,660	SF	6	\$35,015
	Ceiling - Plaster/Drywall	1,254	SF	6	\$6,922
	Ceiling - Splined	169	SF	6	\$138

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Gymnasias</b>					
	Doors - Steel Doors incl hw	4	EA	4	\$14,144
	Doors - Steel Doors incl hw	14	EA	5	\$16,437
	Doors - Steel Doors incl hw	3	EA	6	\$903
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Floor - Carpet	1,254	SF	6	\$2,672
	Floor - Tile	169	SF	5	\$759
	Floor - Wood	11,660	SF	7	\$0
	Lighting - Lay-in	36	EA	7	\$0
	Lighting - Pendent/Surface	18	EA	7	\$0
	Scoreboards	1	EA	7	\$0
	Storage/ Closet	630	SF	4	\$17,559
	Storage/ Closet	70	SF	5	\$1,129
	Storage/ Closet	150	SF	7	\$0
	Walls - Concrete Block	500	SF	4	\$26,226
	Walls - Concrete Block	335	SF	5	\$4,719
	Walls - Concrete Block	28,396	SF	6	\$83,243
	Walls - Plaster/Drywall	468	SF	6	\$1,292
	Walls - Structural Glazed Tile	70	SF	5	\$4,467
	Walls - Structural Glazed Tile	1,900	SF	6	\$5,977
	Walls - Structural Glazed Tile	2,598	SF	7	\$0
<b>Kitchen</b>					
	Ceiling - Plaster/Drywall	1,534	SF	7	\$0
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile Quarry	1,534	SF	7	\$0
	Lighting - Pendent/Surface	32	EA	7	\$0
	Storage/ Closet	100	SF	6	\$725
	Walls - Structural Glazed Tile	1,240	SF	6	\$3,901
<b>Library</b>					
	Casework	125	LF	6	\$3,157
	Casework	298	LF	7	\$0
	Ceiling - Plaster/Drywall	3,537	SF	7	\$0
	Ceiling - Splined	2,050	SF	7	\$0
	Doors - Wood Doors inclu hw	7	EA	7	\$0
	Floor - Tile/Sheet	5,588	SF	7	\$0
	Lighting - Pendent/Surface	150	EA	7	\$0

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Library</b>					
	Walls - Concrete Block	1,624	SF	7	\$0
	Walls - Plaster/Drywall	2,174	SF	7	\$0
<b>Locker/Shower Room</b>					
	Accessories	1,551	SF	6	\$6,077
	Accessories	3,128	SF	7	\$0
	Benches, ped mounted	125	LF	6	\$13,610
	Benches, ped mounted	68	LF	7	\$0
	Ceiling - Plaster/ Drywall	80	SF	5	\$1,044
	Ceiling - Plaster/ Drywall	3,740	SF	6	\$13,144
	Ceiling - Plaster/ Drywall	2,673	SF	7	\$0
	Doors - Steel Doors incl hw	1	EA	5	\$1,174
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Doors - Steel Doors incl hw	2	EA	7	\$0
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	5	EA	7	\$0
	Floor - Concrete	890	SF	6	\$471
	Floor - Concrete	2,356	SF	7	\$0
	Floor - Concrete Epoxy/ Painted	787	SF	6	\$416
	Floor - Tile Ceramic/ Porcelain	1,890	SF	6	\$4,000
	Floor - Tile Ceramic/ Porcelain	543	SF	7	\$0
	Floor Drain	1	EA	5	\$2,094
	Floor Drain	25	EA	6	\$26,479
	Floor Drain	6	EA	7	\$0
	Hand Dryer	9	EA	5	\$5,314
	Hand Dryer	20	EA	7	\$0
	Lavatory	1	EA	6	\$320
	Lavatory	10	EA	7	\$0
	Lighting - Lay-in	7	EA	6	\$833
	Lighting - Lay-in	55	EA	7	\$0
	Lighting - Pendent/Surface	28	EA	6	\$3,469
	Partitions	1	EA	6	\$297
	Partitions	24	EA	7	\$0
	Showers	6	EA	5	\$16,287
	Showers	33	EA	6	\$10,277
	Showers	21	EA	7	\$0
	Storage/ Closet	44	SF	6	\$319
	Student Lockers - One Tier	147	EA	6	\$13,647



## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Locker/Shower Room</b>					
	Student Lockers - One Tier	16	EA	7	\$0
	Student Lockers - Two Tier	58	EA	5	\$5,437
	Student Lockers - Two Tier	224	EA	7	\$0
	Urinals	5	EA	7	\$0
	Walls - Concrete Block	225	SF	5	\$2,716
	Walls - Concrete Block	1,706	SF	6	\$5,001
	Walls - Concrete Block	520	SF	7	\$0
	Walls - Structural Glazed Tile	8,660	SF	7	\$0
	Walls - Tile Ceramic/ Porcelain	200	SF	7	\$0
	Water Closet	12	EA	7	\$0
<b>Lunch &amp; Multipurpose Room</b>					
	Ceiling - Plaster/Drywall	400	SF	4	\$8,706
	Ceiling - Plaster/Drywall	6,281	SF	6	\$21,736
	Doors - Side-lite	7	SF	7	\$0
	Doors - Store Front	1	EA	7	\$0
	Doors - Transom Window	12	SF	7	\$0
	Doors - Wood Doors inclu hw	5	EA	7	\$0
	Floor - Tile	6,681	SF	6	\$14,617
	Lighting - Lay-in	15	EA	6	\$1,785
	Lighting - Pendent/Surface	76	EA	7	\$0
	Serving Line	98	LF	7	\$0
	Walls - Concrete Block	200	SF	6	\$586
	Walls - Structural Glazed Tile	3,702	SF	7	\$0
<b>MDF_IDF</b>					
	Doors - Wood Doors inclu hw	1	EA	7	\$0
	Finishes	794	SF	6	\$5,666
	Ventilation and Cooling	1	EA	6	\$1,855
<b>Mechanical/ Service Rooms</b>					
	Air Tunnel	3,500	SF	5	\$46,597
	Air Tunnel	1,500	SF	6	\$9,288
	Air Tunnel	2,300	SF	7	\$0
	Boiler Room	6,500	SF	5	\$104,848
	Crawl Space - Unfinished	28,000	SF	6	\$173,373
	Interior Stairs	344	LF	6	\$3,104
	Janitor's Closet	260	SF	5	\$4,194
	Janitor's Closet	140	SF	6	\$1,003

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Mechanical/ Service Rooms</b>					
	Mechanical/ Service Rooms	10,920	SF	5	\$176,144
	Mechanical/ Service Rooms	4,525	SF	6	\$32,418
	Mechanical/ Service Rooms	5,550	SF	7	\$0
	Storage Room	1,011	SF	5	\$16,308
	Storage Room	2,270	SF	6	\$16,263
	Storage Room	375	SF	7	\$0
	Vaults	120	SF	6	\$860
<b>Pool &amp; Natatorium</b>					
	Bleachers Seating/Plank Seating	72	EA	6	\$2,084
	Ceiling - Exposed	3,210	SF	7	\$0
	Ceiling - Plaster/ Drywall	3,952	SF	7	\$0
	Doors - Steel Doors incl hw	4	EA	7	\$0
	Floor - Tile Ceramic/ Porcelain	3,952	SF	7	\$0
	Lighting - Pendent/Surface	30	EA	6	\$3,717
	Pool Basin	3,210	SF	7	\$0
	Pool Deck	3,952	SF	7	\$0
	Pool Deck Drains	28	EA	7	\$0
	Walls - Structural Glazed Tile	5,880	SF	7	\$0
<b>Prep Room</b>					
	Casework	122	LF	7	\$0
	Ceiling - Lay-in	264	SF	5	\$1,570
	Ceiling - Lay-in	330	SF	7	\$0
	Ceiling - Splined	100	SF	7	\$0
	Doors - Side-lite	40	SF	7	\$0
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	40	SF	7	\$0
	Doors - Wood Doors inclu hw	3	EA	7	\$0
	Floor - Tile/Sheet	694	SF	7	\$0
	Lighting - Lay-in	6	EA	6	\$714
	Lighting - Lay-in	6	EA	7	\$0
	Lighting - Pendent/Surface	2	EA	7	\$0
	Walls - Concrete Block	913	SF	7	\$0
	Walls - Plaster/Drywall	378	SF	7	\$0
	Work Sink	1	EA	6	\$379
	Work Sink	2	EA	7	\$0

## Building: Kennedy

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Restroom</b>					
	Accessories	3,769	SF	6	\$34,763
	Accessories	837	SF	7	\$0
	Benches	4	LF	7	\$0
	Ceiling - Plaster/Drywall	214	SF	4	\$3,222
	Ceiling - Plaster/Drywall	382	SF	5	\$3,573
	Ceiling - Plaster/Drywall	2,530	SF	6	\$8,783
	Ceiling - Plaster/Drywall	1,444	SF	7	\$0
	Ceiling - Splined	77	SF	6	\$63
	Ceiling - Splined	77	SF	7	\$0
	Doors - Side-lite	180	SF	6	\$3,009
	Doors - Side-lite	252	SF	7	\$0
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Steel Doors incl hw	2	EA	7	\$0
	Doors - Transom Window	1	SF	6	\$17
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Doors - Wood Doors inclu hw	9	EA	7	\$0
	Floor - Tile	118	SF	5	\$530
	Floor - Tile	27	SF	6	\$59
	Floor - Tile Ceramic/ Porcelain	26	SF	5	\$543
	Floor - Tile Ceramic/ Porcelain	3,208	SF	6	\$6,789
	Floor - Tile Ceramic/ Porcelain	785	SF	7	\$0
	Floor - Tile/Sheet	118	SF	4	\$1,141
	Floor - Tile/Sheet	50	SF	5	\$226
	Floor - Tile/Sheet	214	SF	6	\$230
	Floor - Tile/Sheet	153	SF	7	\$0
	Floor Drain	5	EA	6	\$5,296
	Floor Drain	12	EA	7	\$0
	Hand Dryer	9	EA	5	\$5,314
	Hand Dryer	9	EA	6	\$2,070
	Hand Dryer	17	EA	7	\$0
	Lavatory	14	EA	5	\$22,255
	Lavatory	40	EA	6	\$12,784
	Lavatory	16	EA	7	\$0
	Lighting - Lay-in	1	EA	4	\$336
	Lighting - Lay-in	2	EA	5	\$324
	Lighting - Lay-in	6	EA	6	\$714

**Building: Kennedy**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Restroom</b>					
	Lighting - Lay-in	2	EA	7	\$0
	Lighting - Pendent/Surface	1	EA	4	\$541
	Lighting - Pendent/Surface	6	EA	5	\$1,095
	Lighting - Pendent/Surface	4	EA	6	\$496
	Lighting - Pendent/Surface	57	EA	7	\$0
	Lighting - Wall Mounted	1	EA	4	\$393
	Lighting - Wall Mounted	1	EA	5	\$169
	Lighting - Wall Mounted	5	EA	6	\$619
	Lighting - Wall Mounted	5	EA	7	\$0
	Partitions	2	EA	5	\$1,502
	Partitions	35	EA	6	\$10,392
	Partitions	22	EA	7	\$0
	Showers	1	EA	4	\$4,720
	Showers	1	EA	5	\$1,172
	Showers	2	EA	6	\$623
	Student Lockers - One Tier	6	EA	7	\$0
	Urinals	2	EA	6	\$672
	Urinals	16	EA	7	\$0
	Walls - Concrete Block	630	SF	6	\$1,847
	Walls - Concrete Block	404	SF	7	\$0
	Walls - Plaster/Drywall	90	SF	5	\$682
	Walls - Plaster/Drywall	24	SF	7	\$0
	Walls - Structural Glazed Tile	6,982	SF	6	\$21,965
	Walls - Structural Glazed Tile	4,388	SF	7	\$0
	Walls - Tile Ceramic/ Porcelain	326	SF	6	\$737
	Water Closet	4	EA	5	\$5,376
	Water Closet	24	EA	6	\$8,063
	Water Closet	39	EA	7	\$0

**Rooms (Other Than Classrooms) Subtotal:**
**\$1,614,036**
**Building: Kennedy**
**Category: Building Interior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Exposed	478	SF	7	\$0
	Ceiling - Lay-in	8,817	SF	7	\$0

## Building: Kennedy

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Plaster/Drywall	10	SF	5	\$174
	Ceiling - Plaster/Drywall	2,863	SF	6	\$18,538
	Ceiling - Plaster/Drywall	19,079	SF	7	\$0
	Ceiling - Splined	196	SF	6	\$566
	Doors - Steel Doors incl hw	15	EA	7	\$0
	Doors - Store Front	4	EA	7	\$0
	Doors - Wood Doors include hw	8	EA	6	\$2,408
	Doors - Wood Doors include hw	14	EA	7	\$0
	Drinking Fountains - Single Fountain	1	EA	5	\$1,180
	Drinking Fountains - Single Water Cooler	16	EA	7	\$0
	Floor - Carpet	210	SF	7	\$0
	Floor - Concrete	270	SF	6	\$143
	Floor - Concrete Epoxy/ Painted	350	SF	7	\$0
	Floor - Terrazzo	580	SF	6	\$4,869
	Floor - Terrazzo	796	SF	7	\$0
	Floor - Tile Ceramic/ Porcelain	8	SF	5	\$167
	Floor - Tile Ceramic/ Porcelain	272	SF	6	\$758
	Floor - Tile Ceramic/ Porcelain	336	SF	7	\$0
	Floor - Tile/Sheet	4	SF	5	\$23
	Floor - Tile/Sheet	3,377	SF	6	\$1,835
	Floor - Tile/Sheet	25,340	SF	7	\$0
	Lighting - Lay-in	4	EA	5	\$649
	Lighting - Lay-in	40	EA	6	\$4,759
	Lighting - Lay-in	375	EA	7	\$0
	Lighting - Pendent/Surface	7	EA	5	\$1,278
	Lighting - Pendent/Surface	3	EA	6	\$372
	Lighting - Pendent/Surface	11	EA	7	\$0
	Stairs - Concrete Stairs	86	LF	5	\$8,521
	Student Lockers - One Tier	1,459	EA	7	\$0
	Walls - Concrete Block	1,800	SF	6	\$5,277
	Walls - Concrete Block	8,250	SF	7	\$0
	Walls - Metal Panel	1,330	SF	6	\$9,928
	Walls - Plaster/Drywall	632	SF	6	\$2,802
	Walls - Plaster/Drywall	6,054	SF	7	\$0
	Walls - Structural Glazed Tile	1,785	SF	6	\$5,616
	Walls - Structural Glazed Tile	15,953	SF	7	\$0

## Building: Kennedy

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Safety</b>					
	Security Cameras	1	EA	4	\$1,326
	Security Cameras	15	EA	7	\$0
<b>Stairs</b>					
	Ceiling - Plaster/Drywall	330	SF	5	\$4,851
	Ceiling - Plaster/Drywall	150	SF	6	\$1,098
	Ceiling - Plaster/Drywall	4,914	SF	7	\$0
	Floor - Terrazzo	242	SF	6	\$2,681
	Floor - Terrazzo	3,445	SF	7	\$0
	Floor - Tile	238	SF	5	\$1,069
	Floor - Tile	50	SF	6	\$27
	Floor - Tile Ceramic/ Porcelain	128	SF	6	\$858
	Handrails	4	LF	5	\$46
	Handrails	86	LF	6	\$745
	Handrails	732	LF	7	\$0
	Lighting - Lay-in	1	EA	5	\$162
	Lighting - Lay-in	2	EA	6	\$238
	Lighting - Lay-in	34	EA	7	\$0
	Lighting - Pendent/Surface	5	EA	5	\$913
	Lighting - Pendent/Surface	12	EA	7	\$0
	Stairs - Terrazzo	205	LF	6	\$1,903
	Stairs - Terrazzo	1,615	LF	7	\$0
	Walls - Structural Glazed Tile	2,459	SF	5	\$125,587
	Walls - Structural Glazed Tile	9,035	SF	7	\$0
<b>Vertical Conveyance</b>					
	Elevator - Elevator- Roped Holeless Hydraulic	2	EA	7	\$0

**Building Interior Subtotal: \$211,366**

**Total Building Cost \$8,414,916**

## Building: Kinzie

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	1	EA	7	\$0

## Building: Kinzie

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Exterior Doors - Exterior Steel Door	7	EA	5	\$9,389
	Exterior Doors - Exterior Steel Door	4	EA	6	\$1,922
	Exterior Doors - Side lite	4	EA	5	\$1,904
	Exterior Doors - Store Front	10	EA	5	\$18,362
	Exterior Doors - Transom Lite	4	EA	5	\$3,287
	Exterior Stairs - Concrete	10	LF	3	\$1,636
	Exterior Stairs - Concrete	140	LF	5	\$15,341
	Exterior Stairs - Concrete	375	LF	6	\$30,663
	Exterior Stairs - Stone	10	LF	6	\$1,130
	Power Door Operator and Controls	1	EA	7	\$0
	Ramp Handrail - Steel_Ramp Handrail	50	LF	5	\$530
	Ramps - Concrete	25	LF	6	\$3,756
	Stair Handrail - Steel_Stair Handrail	7	LF	5	\$80
	Stair Handrail - Steel_Stair Handrail	171	LF	6	\$1,482
<b>Foundation</b>					
	Foundation - Concrete	1,635	LF	7	\$0
	Superstructure - Concrete	111,615	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	18	EA	7	\$0
	Exterior Lighting - Wall Mounted	4	EA	4	\$4,120
	Exterior Lighting - Wall Mounted	5	EA	6	\$1,444
	Exterior Lighting - Wall Mounted	3	EA	7	\$0
<b>Roof System</b>					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	8	LF	4	\$45,056
	Chimney - Brick Chimney- Concrete/ Mortar Liner	35	LF	6	\$33,414
	Coping - Stone	1	LF	4	\$363
	Coping - Stone	1,669	LF	6	\$53,605
	Downspouts - Interior Downspouts	13	LF	4	\$6,073
	Downspouts - Interior Downspouts	50	LF	5	\$11,065
	Downspouts - Interior Downspouts	300	LF	6	\$9,970
	Parapet - 16" - 30" Height	1,626	LF	6	\$64,966
	Parapet - Parapet < 16" Height	44	LF	6	\$938
	Roof - Asphalt Gravel Ballast	150	SF	5	\$4,648
	Roof - Asphalt Gravel Ballast	48,619	SF	6	\$494,324
	Roof Structure - Concrete	48,769	SF	7	\$0

## Building: Kinzie

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Walls</b>					
	Canopy - Metal	240	SF	5	\$12,849
	Exterior Walls - Brick	23,950	SF	6	\$160,968
	Exterior Walls - Stone-Cast	3	SF	4	\$545
	Exterior Walls - Stone-Cast	128	SF	5	\$2,255
	Exterior Walls - Stone-Cast	1,214	SF	6	\$8,159
<b>Windows</b>					
	Lintels - Steel	1,639	LF	6	\$47,579
	Windows - Decorative	2	SF	4	\$653
	Windows - Decorative	238	SF	6	\$1,777
	Windows - Louver	232	SF	5	\$19,866
	Windows - Sash Aluminum Double-pane	7,884	SF	6	\$58,851
<b>Building Exterior Subtotal:</b>					<b>\$1,132,970</b>

## Building: Kinzie

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Corridors and Stairs	11,343	SF	6	\$3,406
	Emergency A/C Power - Gym	19,754	SF	6	\$7,345
	Emergency A/C Power - Students Toilets	4,341	SF	6	\$1,614
	Emergency Battery Packs - Corridors and Stairs	4	EA	6	\$810
	Exit Signs - Corridors and Stairs	28	EA	2	\$15,274
	Exit Signs - Gym	5	EA	2	\$2,891
	Exit Signs - Multipurpose Room	4	EA	2	\$2,182
	Security System - CCTV	111,615	SF	6	\$33,518
	Security System - Intrusion Detection	111,615	SF	6	\$28,730
<b>Main Service</b>					
	Independent Electrical Service for emergency power	1	EA	7	\$0
	Main Electrical Service - 1600 A 277/480/3PH	1	EA	7	\$0
	PA System	111,615	SF	6	\$36,710
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	3	EA	4	\$14,548
	Lighting and Power Panels - 100 A	21	EA	6	\$6,281



**Building: Kinzie**
**Category: Electrical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	3	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	1	EA	7	\$0
	Transformers - 277/480 - 120/208	2	EA	7	\$0

**Electrical System Subtotal:**
**\$153,717**
**Building: Kinzie**
**Category: Safty System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	111,615	SF	6	\$39,902
	Fire Alarm_System	111,615	SF	6	\$54,267

**Safty System Subtotal:**
**\$100,575**
**Building: Kinzie**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Chemical Pot Feeder	1	EA	5	\$1,685
	Chiller-Air Cooled- Recipricating-Roof Mounted - 201 - 300 tons	2	EA	5	\$140,540
	Condensing Unit- Roof Mounted - Less than 5 tons	1	EA	6	\$3,334
	Glycol Feed	1	EA	6	\$490
	Pressure Fill System	1	EA	6	\$1,405
<b>Air Handling Systems</b>					
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 4000-8000 cfm	1	EA	5	\$26,442
	Fan Coil Unit- Floor Mounted - Hot Water and Chilled Water	1	EA	7	\$0
	Indoor Return Fans- Centrifugal Squirrel Cage - 5000 - 10000 CFM	1	EA	5	\$9,732
<b>Boiler Systems</b>					
	Boiler Auxiliary- Steam Boiler - Greater than 200 HP	2	EA	6	\$4,093
	Combustion Dampers	2	EA	6	\$818
	Condensate Pump	2	EA	6	\$4,042
	Feed Water Pumps and Tank	1	EA	6	\$2,545

## Building: Kinzie

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Boiler Systems</b>					
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Steam Boiler - Greater than 200 HP	2	EA	6	\$4,093
	Piping - Condensate Pipe- Steel	100	LF	6	\$189
	Piping - Steam Pipe- Steel	100	LF	6	\$189
	Steam Traps	70	EA	6	\$18,490
<b>Heat Exchangers</b>					
	Heat Exchanger - Steam to Hot Water Shell Type	1	EA	7	\$0
<b>Heating Devices</b>					
	Cabinet Heaters - With Hot Water Coil	18	EA	6	\$6,378
	Fin Tube - Hot Water	87	LF	6	\$821
	Radiators - Hot Water	4	EA	6	\$1,111
	Unit Heater - Hot Water	1	EA	7	\$0
	Unit Heater - Steam	3	EA	4	\$5,266
	Wall Heater - Electric	4	EA	6	\$556
<b>Mechanical Plumbing</b>					
	Chilled Water Pump - 21 - 50 HP	2	EA	6	\$2,485
	Hot Water Pump - 21 - 50 HP	2	EA	6	\$2,485
	Hydronic Supply and Return - Steel	800	LF	6	\$61,421
<b>Temperature Control</b>					
	Pneumatic System	106,838	SF	4	\$556,113
	Thermostats - Pneumatic	94	EA	4	\$69,300
<b>Unit Ventilation</b>					
	Unit Ventilators- Floor Mounted- Dual Temperature Coils (Hot/Chilled) Water	59	EA	6	\$73,296
<b>Ventilation</b>					
	Exhaust Fans- Indoor - 500 - 1500 CFM	1	EA	6	\$592
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	4	EA	4	\$25,568
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	1	EA	7	\$0
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	6	EA	4	\$25,467
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	2	EA	6	\$1,185
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	3	EA	7	\$0
	Type I Exhaust Hood- Kitchen	1	EA	3	\$28,265
	Type I Exhaust Hood- Kitchen	1	EA	6	\$1,248

## Building: Kinzie

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Mechanical System Subtotal:</b>					<b>\$1,079,644</b>

## Building: Kinzie

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - 150000 - 300000 BTU/HR	2	EA	7	\$0
	Hot Water Storage Tank_Gas - Less than 200 Gallons	2	EA	7	\$0
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	111,615	SF	5	\$0
	Domestic Piping-Cold Water Horizontal Lines	111,615	SF	5	\$0
	Domestic Piping-Cold Water Risers	111,615	SF	5	\$0
	Domestic Piping-Hot Water from Risers to Fixtures	111,615	SF	5	\$0
	Domestic Piping-Hot Water Horizontal Lines	111,615	SF	5	\$0
	Domestic Piping-Hot Water Return Lines	111,615	SF	5	\$0
	Domestic Piping-Hot Water Return Risers	111,615	SF	5	\$0
	Sanitary Piping	111,615	SF	6	\$102,150
	Storm Piping	111,615	SF	6	\$97,362
	Vent Piping	111,615	SF	6	\$75,016
<b>Pumps</b>					
	Pumps - Sump-Duplex	1	EA	5	\$7,535
<b>Plumbing System Subtotal:</b>					<b>\$282,063</b>

## Building: Kinzie

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (1 room)</b>					
	Casework	100	LF	6	\$2,525
	Ceiling - Plaster/Drywall	1,361	SF	6	\$4,710
	Chalk Board	10	LF	4	\$918
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,361	SF	6	\$2,978
	Lighting - Pendent/Surface	28	EA	6	\$3,469
	Walls - Concrete Block	1,153	SF	6	\$3,380
	Work Sink	2	EA	6	\$758

## Building: Kinzie

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (1 room)</b>					
<b>Computer Lab (2 rooms)</b>					
	Casework	40	LF	6	\$1,010
	Ceiling - Lay-in	725	SF	6	\$2,177
	Ceiling - Splined	725	SF	6	\$591
	Chalk Board	61	LF	4	\$5,600
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,450	SF	6	\$3,172
	Lighting - Lay-in	12	EA	7	\$0
	Lighting - Pendent/Surface	20	EA	6	\$2,478
	Marker Board	20	LF	7	\$0
	Walls - Concrete Block	50	SF	5	\$704
	Walls - Concrete Block	1,450	SF	6	\$4,251
<b>Faculty Lounge (1 room)</b>					
	Casework	70	LF	6	\$1,768
	Ceiling - Lay-in	135	SF	6	\$405
	Ceiling - Plaster/Drywall	1,040	SF	6	\$3,599
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Carpet	1,175	SF	5	\$6,032
	Lighting - Lay-in	4	EA	7	\$0
	Lighting - Pendent/Surface	18	EA	6	\$2,230
	Walls - Concrete Block	1,054	SF	7	\$0
	Work Sink	2	EA	6	\$758
<b>Kindergarten (4 rooms)</b>					
	Casework	114	LF	6	\$2,879
	Ceiling - Lay-in	25	SF	5	\$199
	Ceiling - Lay-in	2,775	SF	6	\$8,333
	Ceiling - Plaster/Drywall	1,080	SF	6	\$3,737
	Chalk Board	41	LF	4	\$3,764
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Floor - Carpet	725	SF	5	\$3,722
	Floor - Carpet	725	SF	6	\$1,545
	Floor - Tile	2,484	SF	6	\$5,435
	Lighting - Lay-in	17	EA	6	\$2,023
	Lighting - Lay-in	30	EA	7	\$0
	Lighting - Pendent/Surface	16	EA	6	\$1,982
	Marker Board	64	LF	7	\$0

## Building: Kinzie

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Kindergarten (4 rooms)</b>					
	Storage/ Closet	109	SF	6	\$790
	Walls - Concrete Block	61	SF	4	\$2,565
	Walls - Concrete Block	50	SF	5	\$704
	Walls - Concrete Block	1,100	SF	6	\$3,225
	Walls - Concrete Block	1,848	SF	7	\$0
	Work Sink	3	EA	6	\$1,137
<b>Other Instructional Use (3 rooms)</b>					
	Casework	65	LF	6	\$1,641
	Ceiling - Lay-in	90	SF	6	\$270
	Ceiling - Lay-in	95	SF	7	\$0
	Ceiling - Plaster/Drywall	1,233	SF	7	\$0
	Chalk Board	20	LF	4	\$1,836
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	221	SF	5	\$1,135
	Floor - Concrete Epoxy/ Painted	422	SF	6	\$223
	Floor - Tile	725	SF	7	\$0
	Lighting - Lay-in	4	EA	6	\$476
	Lighting - Lay-in	3	EA	7	\$0
	Lighting - Pendent/Surface	15	EA	6	\$1,858
	Lighting - Pendent/Surface	4	EA	7	\$0
	Marker Board	23	LF	7	\$0
	Storage/ Closet	6	SF	6	\$44
	Walls - Concrete Block	856	SF	6	\$2,509
	Walls - Concrete Block	750	SF	7	\$0
	Work Sink	1	EA	5	\$1,508
<b>Pre School (1 room)</b>					
	Casework	20	LF	6	\$505
	Ceiling - Lay-in	811	SF	6	\$2,435
	Chalk Board	24	LF	4	\$2,203
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	811	SF	5	\$4,163
	Lighting - Lay-in	12	EA	7	\$0
	Marker Board	10	LF	7	\$0
	Walls - Concrete Block	813	SF	6	\$2,383
	Work Sink	1	EA	6	\$379

**Building: Kinzie**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Regular Classroom (32 rooms)</b>					
	Casework	18	LF	5	\$3,763
	Casework	574	LF	6	\$14,496
	Casework	40	LF	7	\$0
	Ceiling - Lay-in	8	SF	4	\$112
	Ceiling - Lay-in	25	SF	5	\$173
	Ceiling - Lay-in	10,789	SF	6	\$32,399
	Ceiling - Plaster/Drywall	725	SF	5	\$6,646
	Ceiling - Plaster/Drywall	5,710	SF	6	\$19,760
	Ceiling - Plaster/Drywall	4,730	SF	7	\$0
	Ceiling - Splined	25	SF	4	\$351
	Ceiling - Splined	1,425	SF	6	\$1,162
	Chalk Board	406	LF	4	\$37,273
	Doors - Wood Doors inclu hw	31	EA	6	\$9,331
	Doors - Wood Doors inclu hw	1	EA	7	\$0
	Floor - Carpet	12,420	SF	5	\$63,761
	Floor - Carpet	6,540	SF	6	\$13,935
	Floor - Tile	2,212	SF	6	\$4,840
	Floor - Tile	725	SF	7	\$0
	Floor - Tile/Sheet	725	SF	6	\$726
	Floor - Tile/Sheet	725	SF	7	\$0
	Lighting - Lay-in	57	EA	6	\$6,782
	Lighting - Lay-in	129	EA	7	\$0
	Lighting - Pendent/Surface	152	EA	6	\$18,832
	Lighting - Pendent/Surface	116	EA	7	\$0
	Marker Board	21	LF	6	\$450
	Marker Board	797	LF	7	\$0
	Walls - Concrete Block	50	SF	4	\$2,623
	Walls - Concrete Block	555	SF	5	\$7,817
	Walls - Concrete Block	19,506	SF	6	\$57,182
	Walls - Concrete Block	3,000	SF	7	\$0
	Walls - Plaster/Drywall	250	SF	6	\$690
	Work Sink	2	EA	5	\$3,016
	Work Sink	8	EA	6	\$3,032
<b>Science (1 room)</b>					
	Casework	65	LF	6	\$1,641
	Ceiling - Plaster/Drywall	872	SF	6	\$3,018
	Doors - Wood Doors inclu hw	1	EA	6	\$301

## Building: Kinzie

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Science (1 room)</b>					
	Floor - Tile	872	SF	6	\$1,908
	Lighting - Pendent/Surface	16	EA	6	\$1,982
	Walls - Concrete Block	679	SF	6	\$1,990
	Walls - Plaster/Drywall	260	SF	7	\$0
	Work Sink	1	EA	5	\$1,508
<b>Science Lab Level 3 (1 room)</b>					
	Casework	112	LF	5	\$23,417
	Ceiling - Lay-in	135	SF	6	\$405
	Ceiling - Plaster/Drywall	995	SF	6	\$3,443
	Chalk Board	8	LF	4	\$734
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,130	SF	6	\$2,472
	Lighting - Lay-in	7	EA	6	\$833
	Lighting - Pendent/Surface	18	EA	6	\$2,230
	Storage/ Closet	4	SF	6	\$29
	Walls - Concrete Block	918	SF	6	\$2,691
	Work Sink	4	EA	6	\$1,516
<b>Special Program (2 rooms)</b>					
	Casework	20	LF	6	\$505
	Ceiling - Plaster/Drywall	725	SF	6	\$2,509
	Ceiling - Plaster/Drywall	392	SF	7	\$0
	Chalk Board	20	LF	4	\$1,836
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Concrete Epoxy/ Painted	392	SF	6	\$207
	Floor - Tile	725	SF	6	\$1,586
	Lighting - Pendent/Surface	19	EA	7	\$0
	Marker Board	20	LF	7	\$0
	Storage/ Closet	64	SF	6	\$464
	Walls - Concrete Block	750	SF	6	\$2,199
	Walls - Concrete Block	678	SF	7	\$0
	Work Sink	5	EA	6	\$1,895
<b>Store Room (1 room)</b>					
	Casework	19	LF	6	\$480
	Ceiling - Lay-in	15	SF	5	\$120
	Ceiling - Lay-in	710	SF	6	\$2,132

## Building: Kinzie

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Store Room (1 room)</b>					
	Chalk Board	20	LF	4	\$1,836
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Carpet	725	SF	5	\$3,722
	Lighting - Lay-in	12	EA	7	\$0
	Marker Board	20	LF	7	\$0
	Walls - Concrete Block	751	SF	6	\$2,202
	Work Sink	1	EA	6	\$379

### Classrooms Subtotal:

**\$507,089**

## Building: Kinzie

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Ceiling - Lay-in	2,049	SF	6	\$6,153
	Ceiling - Lay-in	104	SF	7	\$0
	Ceiling - Plaster/Drywall	199	SF	5	\$1,824
	Ceiling - Plaster/Drywall	1,391	SF	6	\$4,814
	Ceiling - Plaster/Drywall	1,596	SF	7	\$0
	Doors - Side-lite	22	SF	5	\$1,540
	Doors - Steel Doors incl hw	2	EA	5	\$2,348
	Doors - Wood Doors inclu hw	7	EA	5	\$8,219
	Doors - Wood Doors inclu hw	13	EA	6	\$3,913
	Floor - Carpet	1,801	SF	6	\$3,837
	Floor - Concrete Epoxy/ Painted	122	SF	6	\$65
	Floor - Terrazzo	136	SF	7	\$0
	Floor - Tile	360	SF	5	\$1,616
	Floor - Tile	2,540	SF	6	\$5,557
	Floor - Tile	320	SF	7	\$0
	Lighting - Lay-in	37	EA	6	\$4,402
	Lighting - Lay-in	6	EA	7	\$0
	Lighting - Pendent/Surface	20	EA	6	\$2,478
	Lighting - Pendent/Surface	36	EA	7	\$0
	Power Distribution	6	EA	6	\$12,749
	Power Distribution	177	EA	7	\$0
	Storage/ Closet	48	SF	5	\$774
	Walls - Concrete Block	522	SF	5	\$5,360



## Building: Kinzie

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Walls - Concrete Block	3,974	SF	6	\$11,650
	Walls - Concrete Block	3,539	SF	7	\$0
	Walls - Plaster/Drywall	216	SF	7	\$0
	Work Sink	1	EA	5	\$1,508
	Work Sink	4	EA	6	\$2,033
<b>Gymnasias</b>					
	Ceiling - Exposed	500	SF	5	\$1,938
	Ceiling - Exposed	6,223	SF	6	\$9,255
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Floor - Wood	6,723	SF	6	\$47,396
	Lighting - Metal Halide/ High Pressure Sodium	24	EA	6	\$3,209
	Storage/ Closet	327	SF	5	\$5,275
	Storage/ Closet	404	SF	6	\$2,929
	Walls - Concrete Block	420	SF	5	\$5,069
	Walls - Concrete Block	3,250	SF	6	\$9,527
	Walls - Structural Glazed Tile	250	SF	4	\$26,348
	Walls - Structural Glazed Tile	1,857	SF	6	\$5,842
<b>Kitchen</b>					
	Ceiling - Lay-in	100	SF	7	\$0
	Ceiling - Plaster/Drywall	142	SF	7	\$0
	Ceiling - Splined	800	SF	6	\$652
	Doors - Wood Doors inclu hw	3	EA	5	\$3,522
	Floor - Tile	1,042	SF	6	\$2,280
	Lighting - Lay-in	2	EA	6	\$238
	Lighting - Pendent/Surface	13	EA	6	\$1,611
	Serving Line	20	LF	7	\$0
	Storage/ Closet	60	SF	5	\$968
	Walls - Concrete Block	676	SF	6	\$1,982
	Walls - Structural Glazed Tile	235	SF	7	\$0
<b>Library</b>					
	Casework	336	LF	7	\$0
	Ceiling - Splined	1,096	SF	6	\$893
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	1,096	SF	6	\$2,335
	Lighting - Pendent/Surface	30	EA	6	\$3,717
	Walls - Concrete Block	1,286	SF	6	\$3,770

## Building: Kinzie

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Library					
Locker/Shower Room					
	Accessories	2,115	SF	5	\$18,479
	Accessories	2,214	SF	6	\$8,675
	Benches, ped mounted	16	LF	5	\$4,396
	Ceiling - Lay-In	2,115	SF	4	\$21,504
	Ceiling - Plaster/ Drywall	2,214	SF	4	\$33,338
	Doors - Steel Doors incl hw	2	EA	5	\$2,348
	Doors - Wood Doors inclu hw	2	EA	5	\$2,348
	Floor - Concrete	2,214	SF	4	\$7,219
	Floor - Concrete Epoxy/ Painted	1,715	SF	5	\$2,943
	Floor - Tile Ceramic/ Porcelain	400	SF	5	\$6,389
	Floor Drain	14	EA	5	\$29,315
	Hand Dryer	1	EA	5	\$590
	Lavatory	1	EA	5	\$3,763
	Lavatory	2	EA	6	\$639
	Lighting - Lay-in	29	EA	4	\$9,740
	Lighting - Pendent/Surface	26	EA	4	\$14,057
	Partitions	9	EA	6	\$2,672
	Showers	14	EA	4	\$66,086
	Showers	12	EA	5	\$32,574
	Urinals	2	EA	4	\$15,339
	Walls - Concrete Block	1,650	SF	5	\$16,941
	Walls - Concrete Block	1,724	SF	6	\$5,054
	Walls - Structural Glazed Tile	664	SF	5	\$33,736
	Walls - Structural Glazed Tile	775	SF	6	\$2,438
	Water Closet	1	EA	4	\$7,669
	Water Closet	4	EA	5	\$15,576
Lunch & Multipurpose Room					
	Ceiling - Exposed	447	SF	5	\$1,227
	Ceiling - Lay-in	3,496	SF	6	\$10,498
	Ceiling - Plaster/Drywall	2,000	SF	5	\$18,333
	Chalk Board	10	LF	4	\$918
	Doors - Steel Doors incl hw	3	EA	6	\$903
	Doors - Wood Doors inclu hw	5	EA	5	\$5,870
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Concrete	447	SF	5	\$767

## Building: Kinzie

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Lunch &amp; Multipurpose Room</b>					
	Floor - Concrete Epoxy/ Painted	2,000	SF	5	\$3,432
	Floor - Tile	3,496	SF	5	\$15,698
	Lighting - Lay-in	18	EA	6	\$2,142
	Lighting - Metal Halide/ High Pressure Sodium	15	EA	6	\$2,006
	Lighting - Pendent/Surface	9	EA	5	\$1,643
	Serving Line	6	LF	5	\$3,113
	Stage	619	SF	6	\$3,576
	Storage/ Closet	25	SF	5	\$403
	Walls - Concrete Block	7,638	SF	6	\$22,391
	Walls - Structural Glazed Tile	1,120	SF	7	\$0
<b>MDF_IDF</b>					
	Doors - Steel Doors incl hw	1	EA	7	\$0
	Finishes	250	SF	5	\$4,036
	Ventilation and Cooling	1	EA	7	\$0
<b>Mechanical/ Service Rooms</b>					
	Auditorium Plenums	110	SF	6	\$681
	Boiler Room	4,011	SF	5	\$64,699
	Janitor's Closet	61	SF	5	\$984
	Janitor's Closet	81	SF	6	\$580
	Mechanical/ Service Rooms	762	SF	6	\$5,459
	Storage Room	61	SF	5	\$984
	Storage Room	494	SF	6	\$3,539
	Storage Room	56	SF	7	\$0
	Vaults	66	SF	6	\$473
<b>Restroom</b>					
	Accessories	30	SF	5	\$594
	Accessories	1,408	SF	6	\$12,987
	Accessories	1,158	SF	7	\$0
	Ceiling - Lay-in	104	SF	6	\$312
	Ceiling - Lay-in	132	SF	7	\$0
	Ceiling - Plaster/Drywall	80	SF	4	\$1,330
	Ceiling - Plaster/Drywall	27	SF	5	\$247
	Ceiling - Plaster/Drywall	1,985	SF	6	\$6,869
	Ceiling - Plaster/Drywall	268	SF	7	\$0
	Doors - Hardware	1	EA	6	\$212
	Doors - Steel Doors incl hw	8	EA	6	\$2,408

## Building: Kinzie

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Restroom</b>					
	Doors - Steel Doors incl hw	1	EA	7	\$0
	Doors - Wood Doors inclu hw	3	EA	5	\$3,522
	Doors - Wood Doors inclu hw	22	EA	6	\$6,622
	Floor - Concrete	30	SF	5	\$51
	Floor - Tile	35	SF	4	\$357
	Floor - Tile	655	SF	5	\$2,945
	Floor - Tile	319	SF	6	\$698
	Floor - Tile Ceramic/ Porcelain	91	SF	5	\$1,676
	Floor - Tile Ceramic/ Porcelain	953	SF	6	\$2,017
	Floor - Tile Ceramic/ Porcelain	513	SF	7	\$0
	Floor Drain	7	EA	6	\$7,414
	Floor Drain	1	EA	7	\$0
	Hand Dryer	8	EA	7	\$0
	Lavatory	1	EA	5	\$1,590
	Lavatory	23	EA	6	\$7,351
	Lavatory	7	EA	7	\$0
	Lighting - Lay-in	5	EA	6	\$595
	Lighting - Pendent/Surface	1	EA	4	\$541
	Lighting - Pendent/Surface	5	EA	6	\$619
	Lighting - Pendent/Surface	26	EA	7	\$0
	Lighting - Wall Mounted	3	EA	5	\$508
	Lighting - Wall Mounted	1	EA	6	\$124
	Partitions	2	EA	5	\$1,502
	Partitions	18	EA	6	\$5,345
	Partitions	23	EA	7	\$0
	Showers	2	EA	5	\$2,344
	Student Lockers	15	EA	6	\$0
	Urinals	1	EA	5	\$1,344
	Urinals	15	EA	6	\$5,040
	Urinals	4	EA	7	\$0
	Walls - Concrete Block	175	SF	5	\$1,797
	Walls - Concrete Block	2,730	SF	6	\$8,003
	Walls - Concrete Block	1,505	SF	7	\$0
	Walls - Plaster/Drywall	260	SF	6	\$718
	Walls - Structural Glazed Tile	448	SF	5	\$22,762
	Walls - Structural Glazed Tile	2,337	SF	6	\$7,352
	Walls - Structural Glazed Tile	1,078	SF	7	\$0

## Building: Kinzie

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Restroom	Water Closet	1	EA	4	\$7,669
	Water Closet	1	EA	5	\$1,344
	Water Closet	38	EA	6	\$12,767
	Water Closet	8	EA	7	\$0

### Rooms (Other Than Classrooms) Subtotal:

**\$900,667**

## Building: Kinzie

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor	Ceiling - Plaster/Drywall	3,308	SF	5	\$41,675
	Ceiling - Plaster/Drywall	2,112	SF	6	\$13,077
	Ceiling - Plaster/Drywall	3,179	SF	7	\$0
	Ceiling - Splined	1,062	SF	5	\$7,563
	Ceiling - Splined	1,688	SF	6	\$4,876
	Doors - Steel Doors incl hw	5	EA	5	\$6,894
	Doors - Steel Doors incl hw	8	EA	6	\$2,408
	Doors - Steel Doors incl hw	2	EA	7	\$0
	Doors - Wood Doors include hw	10	EA	5	\$11,741
	Doors - Wood Doors include hw	5	EA	6	\$1,505
	Drinking Fountains - Double Fountain	2	EA	6	\$672
	Drinking Fountains - Single Fountain	2	EA	6	\$551
	Drinking Fountains - Single Water Cooler	9	EA	7	\$0
	Floor - Concrete Epoxy/ Painted	1,077	SF	5	\$1,848
	Floor - Terrazzo	859	SF	6	\$7,211
	Floor - Terrazzo	744	SF	7	\$0
	Floor - Tile/Sheet	322	SF	5	\$1,446
	Floor - Tile/Sheet	8,288	SF	6	\$4,504
	Floor - Tile/Sheet	59	SF	7	\$0
	Lighting - Pendent/Surface	180	EA	6	\$22,301
	Lighting - Pendent/Surface	22	EA	7	\$0
	Student Lockers - One Tier	273	EA	5	\$38,262
	Student Lockers - One Tier	348	EA	6	\$32,307
	Student Lockers - One Tier	75	EA	7	\$0
	Walls - Concrete Block	5	SF	4	\$262
	Walls - Concrete Block	2,159	SF	6	\$6,329

## Building: Kinzie

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Walls - Concrete Block	1,639	SF	7	\$0
	Walls - Plaster/Drywall	2,946	SF	6	\$13,060
	Walls - Plaster/Drywall	4,579	SF	7	\$0
	Walls - Structural Glazed Tile	3,729	SF	6	\$11,731
	Walls - Structural Glazed Tile	6,249	SF	7	\$0
<b>Stairs</b>					
	Ceiling - Lay-in	318	SF	6	\$955
	Ceiling - Plaster/Drywall	890	SF	7	\$0
	Ceiling - Splined	389	SF	5	\$2,770
	Floor - Terrazzo	803	SF	6	\$6,740
	Floor - Tile	484	SF	6	\$263
	Floor - Tile Ceramic/ Porcelain	74	SF	5	\$1,182
	Floor - Tile Ceramic/ Porcelain	79	SF	6	\$530
	Handrails	144	LF	6	\$1,248
	Handrails	52	LF	7	\$0
	Lighting - Pendent/Surface	7	EA	6	\$867
	Lighting - Pendent/Surface	6	EA	7	\$0
	Lighting - Wall Mounted	2	EA	5	\$339
	Stairs - Terrazzo	100	LF	6	\$928
	Stairs - Terrazzo	200	LF	7	\$0
	Walls - Concrete Block	216	SF	6	\$633
	Walls - Concrete Block	675	SF	7	\$0
	Walls - Structural Glazed Tile	1,782	SF	7	\$0
<b>Vertical Conveyance</b>					
	Elevator - Hydraulic Elevator	1	EA	7	\$0

**Building Interior Subtotal:** **\$246,679**

**Total Building Cost** **\$4,403,405**

## SITE

### Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Civil/Drainage</b>					
	Civil/ Drainage - Catch Basin	16	EA	7	\$0

**SITE**
**Category: Site**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Civil/Drainage</b>					
	Civil/ Drainage - Site Drain	4	EA	5	\$5,517
	Civil/ Drainage - Site Manhole	18	EA	7	\$0
<b>Fencing</b>					
	Fencing - Chain Link	1,168	LF	6	\$21,930
	Fencing - Guard Rail	1,075	LF	7	\$0
	Fencing - New Standard Ornamental	405	LF	6	\$12,921
<b>Landscape</b>					
	Landscape - Grass	12,332	SF	7	\$0
	Landscape - Hardscape- Concrete	2,576	SF	5	\$28,254
	Landscape - Hardscape- Concrete	15,710	SF	7	\$0
	Parkway trees	25	EA	7	\$0
	Planting Beds/ Area	2,000	SF	7	\$0
	Play Area - Asphalt/ Hardscape	336	SF	4	\$3,560
	Play Area - Asphalt/ Hardscape	5,814	SF	6	\$14,051
	Retaining Wall - Concrete	1,225	SF	6	\$28,711
	Retaining Wall - Concrete	900	SF	7	\$0
	Trash Receptacles	7	EA	6	\$2,186
<b>Parking Lot</b>					
	Surface - Asphalt	45,756	SF	5	\$208,725
	Surface - Asphalt	9,375	SF	6	\$26,142
	Trash Enclosure - Chain Links	700	SF	7	\$0
<b>Sidewalks</b>					
	Sidewalks - Perimeter Sidewalks	14,453	SF	7	\$0
<b>Signage</b>					
	Flag Pole - Flag Pole	1	EA	7	\$0
	Marquee - Free Standing Back lighted w/ LED	1	EA	4	\$43,600
	Monument - Building Mounted Cut Letter Sign	2	EA	7	\$0
<b>Site Subtotal:</b>					<b>\$395,598</b>
<b>Total Site Cost</b>					<b>\$395,598</b>
<b>Campus Total <sup>2 3</sup></b>					<b>\$13,213,919</b>

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked “1” in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

---

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
  - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement “EA” for “each.” Other items, like chimneys, are measured in terms of linear feet (“LF”). Still other items, like flooring, are generally measured in square feet (“SF”).
  - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-



## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Kennedy</b>														
Art Room	Regular Classroom	1st Floor	110	109	909	1	0	6	246	60	40	N	Y	N
Art Room	Art Room		118	118	1,569	1	5	14	315	157	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	300	301 (partial)	369	0	8	16	96	24	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	302	301 (partial)	729	0	12	42	192	48	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	304	303	1,110	0	2	78	288	72	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	306	305 (partial)	729	0	33	68	192	48	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	308	306	1,110	1	2	112	288	72	40	N	N	N
Computer Lab	Computer Lab	3rd Floor	311	308	1,110	1	23	98	288	72	40	N	Y	N
Fitness Room	Fitness Room	Basement	Bsmt Wrestling	B100	1,086	0	0	12	0	0	40	N	N	N
Music Room	Music Room	1st Floor	111	110	1,595	0	0	10	0	0	40	N	Y	N
Music Room	Choral Room	2nd Floor	212	212	1,550	0	1	8	0	0	40	N	N	N
Other Instructional Use	Computer Lab	3rd Floor	310	307	1,110	1	2	98	288	72	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	108	105	729	1	0	6	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	112	112	729	0	2	10	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	113	113 (partial)	545	0	1	8	144	36	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	114	113 (partial)	545	0	1	4	144	36	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	115	114	729	0	1	8	192	48	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	116	115 (partial)	545	1	1	6	144	36	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	117	115 (partial)	545	0	1	6	144	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	729	0	1	6	192	49	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	729	0	1	4	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	203	203	729	0	1	4	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	204	204	729	0	1	6	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	729	0	2	10	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	729	0	1	6	192	48	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	207	207	729	0	2	8	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	208	208	729	0	1	6	192	48	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	209	209	729	0	1	6	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	210	210	729	0	2	8	192	48	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	211	211	729	0	1	6	192	48	40	N	Y	N
Regular Classroom	Special Program	2nd Floor	213	213 (partial)	714	2	3	18	148	40		N	N	N
Regular Classroom	Regular Classroom	2nd Floor	214	213 (partial)	814	0	1	10	200	56	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	217	217	729	0	1	6	192	48	40	N	Y	N
Regular Classroom	Regular Classroom		220A	n/a	741	0	1	4	221	110	40	Y	Y	Y
Regular Classroom	Regular Classroom		220B	n/a	836	0	1	6	336	168	50	Y	N	N
Regular Classroom	Office		222	n/a	442	0	1	4	72	0	40	N	Y	N
Regular Classroom	Regular Classroom		309B	NA	697	0	2	6	174	48	40	N	Y	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Kennedy</b>														
Regular Classroom	Regular Classroom	3rd Floor	312B	309 (partial)	759	0	2	8	192	48	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	313B	310 (partial)	759	0	1	6	192	48	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	312 (partial)	668	0	2	18	148	40	40	N	Y	N
Regular Classroom	Regular Classroom		317	312 (partial)	878	1	0	8	200	56	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	319A	NA	557	0	0	4	200	56	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	319B	NA	557	0	0	10	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	321	315	729	0	1	6	192	48	40	N	Y	N
Science Classroom	Science Classroom	1st Floor	109	108	1,004	1	2	82	273	66	40	N	Y	N
Science Classroom	Science Classroom		215	214	1,485	1	2	34	384	96	40	N	Y	N
Science Classroom	Science Classroom	2nd Floor	216	215	1,485	1	2	80	384	96	40	N	Y	N
Science Classroom	Science Lab Level 3	3rd Floor	320	314	1,304	1	3	78	285	72	40	N	Y	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	314	311	1,402	0	12	72	225	54	40	N	Y	N
Science Lab Level 2	Science Lab Level 2	3rd Floor	318	313	1,242	1	5	36	315	78	40	N	N	N
Special Education	Regular Classroom	3rd Floor	301	302 (partial)	388	0	1	2	72	16	40	N	Y	N
Special Program	Library	1st Floor	111A	111	609	0	1	8	0	0	40	N	Y	N
Special Program	Special Program	3rd Floor	306A	305 (partial)	369	1	3	32	96	24	40	N	Y	N
Special Program	Store Room	3rd Floor	307	NA	400	0	1	30	72	16	40	N	Y	N
Special Program	Special Program	3rd Floor	309A	NA	417	1	0	16	0	0	40	N	Y	N
Special Program	Special Program	3rd Floor	312A	309 (partial)	369	1	0	8	96	24	40	N	Y	N
Special Program	Special Program	3rd Floor	313A	310 (partial)	369	1	0	8	96	24	40	N	N	N

## Kinzie

Art Room	Regular Classroom		224	NA	1,361	0	0	11	345	172	53	Y	Y	Y
Computer Lab	Regular Classroom		217	NA	725	0	34	101	210	105	53	N	Y	Y
Computer Lab	Regular Classroom		235	NA	725	1	32	70	168	66	53	N	Y	Y
Faculty Lounge	Other Instructional Use		117	NA	1,175	2	7	35	345	99	40	Y	Y	N
Kindergarten	Kindergarten		120	NA	1,270	0	0	8	345	172	53	N	Y	Y
Kindergarten	Regular Classroom		121	NA	725	0	0	4	210	105	53	N	Y	Y
Kindergarten	Kindergarten		122	NA	1,269	1	1	4	345	172	53	Y	Y	Y
Kindergarten	Regular Classroom		227	NA	725	0	1	8	200	100	53	Y	Y	Y
Other Instructional Use	Regular Classroom		104	NA	725	0	1	4	210	105	53	N	N	N
Other Instructional Use	Other Instructional Use		Bsmt Speech		428	0	0	4	0	0	40	N	N	N
Other Instructional Use	Other Instructional Use		In Room 119		221	0	0	8	115	33	40	Y	N	N
Pre School	Pre School		119	NA	811	1	1	10	168	66	40	Y	Y	Y
Regular Classroom	Regular Classroom		102	NA	725	0	0	6	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		112	NA	725	0	0	6	210	105	53	N	N	Y
Regular Classroom	Regular Classroom		113	NA	740	1	2	7	230	66	40	Y	Y	Y

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Kinzie</b>														
Regular Classroom	Regular Classroom		114	NA	725	0	0	8	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		116	NA	725	0	1	4	210	105	53	N	N	Y
Regular Classroom	Regular Classroom		118	NA	725	0	0	6	210	105	53	N	N	Y
Regular Classroom	Regular Classroom		123	NA	725	0	0	6	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		124	NA	730	1	0	6	115	66	40	Y	N	N
Regular Classroom	Regular Classroom		125	NA	725	0	1	8	210	105	53	N	N	Y
Regular Classroom	Regular Classroom		126	NA	725	0	0	6	200	100	53	N	Y	N
Regular Classroom	Regular Classroom		127	NA	878	0	0	4	210	105	53	Y	N	Y
Regular Classroom	Regular Classroom		129	NA	617	0	0	6	156	78	40	N	N	Y
Regular Classroom	Regular Classroom		133	NA	762	0	1	6	200	100	40	N	N	Y
Regular Classroom	Regular Classroom		200	NA	725	0	8	26	168	66	53	N	N	N
Regular Classroom	Regular Classroom		202	NA	725	1	8	20	210	105	53	N	N	Y
Regular Classroom	Regular Classroom		203	NA	725	0	1	12	210	105	53	N	N	N
Regular Classroom	Regular Classroom		204	NA	725	1	11	30	210	105	53	N	Y	N
Regular Classroom	Regular Classroom		205	NA	725	0	0	14	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		206	NA	725	0	9	10	168	66	53	N	Y	Y
Regular Classroom	Regular Classroom		207	NA	725	0	7	20	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		209	NA	725	0	9	22	210		53	N	N	N
Regular Classroom	Regular Classroom		211	NA	725	0	10	22	210	105	53	N	Y	N
Regular Classroom	Regular Classroom		212	NA	725	0	7	20	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		213	NA	725	0	0	6	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		214	NA	725	0	8	20	210	105	53	N	N	N
Regular Classroom	Regular Classroom		215	NA	725	0	0	8	210	105	53	N	Y	N
Regular Classroom	Regular Classroom		216	NA	725	0	8	22	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		218	NA	725	0	11	22	210	105	53	N	Y	N
Regular Classroom	Regular Classroom		219	NA	725	1	9	22	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		221	NA	878	0	4	14	210	105	53	N	Y	Y
Regular Classroom	Regular Classroom		223	NA	617	0	0	6	156	78	53	Y	Y	Y
Regular Classroom	Regular Classroom		225	NA	725	0	2	4	210	105	53	N	Y	Y
Science	Science Classroom		220	NA	872	0	8	16	230	115	40	Y	Y	Y
Science Lab Level 3	Science Lab Level 3		115	103	1,134	0	7	36	315	157	53	N	Y	Y
Special Program	Regular Classroom		222	222	725	0	7	20	210	105	40	N	Y	N
Special Program		Basement	Basmt Audio Booth		456	0	0	2	0	0	40	N	N	N
Store Room	Regular Classroom		131	NA	725	0	1	6	200	100	40	Y	N	N