

Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1928	3	213,820	\$11,812,917
SITE				\$482,866
Campus Total			213,820	\$12,295,783

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Entrance Control - Audio and Video	3	EA	6	\$2,105
	Exterior Doors - Exterior Steel Door	8	EA	6	\$3,844
	Exterior Doors - Exterior Wood Door	22	EA	6	\$10,572
	Exterior Doors - Transom Lite	14	EA	6	\$4,386
	Exterior Stairs - Concrete	224	LF	5	\$24,546
	Exterior Stairs - Concrete	309	LF	6	\$25,266
	Exterior Stairs - Stone	332	LF	5	\$90,029
	Exterior Stairs - Stone	403	LF	6	\$45,533
	Exterior Stairs - Wood	54	LF	5	\$388
	Power Door Operator and Controls	2	EA	6	\$0
	Ramp Handrail - Steel_Ramp Handrail	160	LF	5	\$1,695
	Ramp Handrail - Steel_Ramp Handrail	280	LF	6	\$2,426
	Ramps - Concrete	335	LF	6	\$50,329
	Stair Handrail - Steel_Stair Handrail	52	LF	6	\$451
	Stair Handrail - Wood_Stair Handrail	8	LF	6	\$69
Foundation					
	Foundation - Concrete	25	LF	6	\$4,856
	Foundation - Concrete	1,855	LF	7	\$0
	Superstructure - Concrete	213,820	SF	7	\$0

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Foundation					
	Superstructure - Steel with Clay Tile Arch	20,014	SF	7	\$0
Lighting					
	Exterior Lighting - Parapet or Roof Mounted	13	EA	6	\$6,975
	Exterior Lighting - Wall Mounted	5	EA	6	\$1,444
Roof System					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	30	LF	5	\$85,547
	Chimney - Brick Chimney- Concrete/ Mortar Liner	55	LF	6	\$52,508
	Chimney - Metal Flue	10	LF	6	\$1,581
	Coping - Terra Cotta	2,160	LF	6	\$69,374
	Downspouts - Exterior Downspouts	35	LF	6	\$1,163
	Downspouts - Interior Downspouts	1,177	LF	6	\$39,115
	Parapet - 16" - 30" Height	134	LF	5	\$23,184
	Parapet - Parapet < 16" Height	210	LF	6	\$4,474
	Parapet - Parapet > 30"	1,816	LF	5	\$448,040
	Roof - Asphalt Shingle	1,000	SF	6	\$4,590
	Roof - Modified Bitumen	77,393	SF	5	\$1,627,985
	Roof Structure - Concrete	65,036	SF	7	\$0
	Roof Structure - Steel with Clay Tile Arch	12,357	SF	7	\$0
Walls					
	Cheek-Wall - Concrete	340	SF	5	\$8,017
	Cornice - Terra Cotta	120	LF	6	\$4,161
	Exterior Walls - Brick	566	SF	5	\$13,476
	Exterior Walls - Brick	66,272	SF	6	\$445,414
	Exterior Walls - Prefabricated Metal Panel Wall	420	SF	6	\$2,384
	Exterior Walls - Terra Cotta	4	SF	5	\$62
	Exterior Walls - Terra Cotta	3,972	SF	6	\$26,696
Windows					
	Guard - Guards wire guard	125	SF	5	\$1,916
	Guard - Guards wire guard	10,476	SF	6	\$133,777
	Lintels - Steel	1,136	LF	4	\$514,343
	Lintels - Steel	565	LF	5	\$190,951
	Lintels - Terra Cotta	4	LF	4	\$1,787
	Lintels - Terra Cotta	10	LF	5	\$2,728
	Lintels - Terra Cotta	1,119	LF	6	\$0
	Skylite - Lexan	224	SF	6	\$5,353

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Windows					
	Windows - Casement Aluminum Double-pane	2,442	SF	6	\$18,229
	Windows - Casement Steel	18	SF	5	\$1,472
	Windows - Decorative	48	SF	6	\$358
	Windows - Sash Aluminum Double-pane	1,249	SF	5	\$67,281
	Windows - Sash Aluminum Double-pane	23,728	SF	6	\$177,120
	Windows - Sash Lexan	12	SF	6	\$90

Building Exterior Subtotal:

\$4,248,093

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
	Automatic Transfer Switch	2	EA	6	\$816
	Emergency A/C Power - Auditorium and Aisle Lighting	4,878	SF	6	\$2,581
	Emergency A/C Power - Corridors and Stairs	34,145	SF	6	\$10,254
	Emergency A/C Power - Gym	11,948	SF	6	\$4,442
	Emergency A/C Power - Lunchrooms	6,083	SF	6	\$2,262
	Emergency A/C Power - Pool	3,589	SF	6	\$1,334
	Emergency A/C Power - Students Toilets	3,898	SF	6	\$1,449
	Emergency Battery Packs - Auditorium and Aisle Lighting	10	EA	6	\$2,025
	Emergency Battery Packs - Corridors and Stairs	28	EA	6	\$5,670
	Emergency Battery Packs - Gym	6	EA	6	\$1,215
	Emergency Battery Packs - Lunchrooms	3	EA	6	\$608
	Emergency Battery Packs - Pool	5	EA	6	\$1,013
	Emergency Battery Packs - Students Toilets	3	EA	6	\$608
	Emergency Generator- Outdoor- Natural Gas - 101 - 150 KW	1	EA	7	\$0
	Exit Signs - Auditorium	10	EA	7	\$0
	Exit Signs - Corridors and Stairs	28	EA	7	\$0
	Exit Signs - Gym	6	EA	7	\$0
	Exit Signs - Lunchroom	3	EA	7	\$0
	Exit Signs - Pool	4	EA	7	\$0
	Security System - CCTV	213,820	SF	6	\$64,210
	Security System - Intrusion Detection	213,820	SF	6	\$55,037
	UPS - Less than 30 KW	1	EA	6	\$7,886

Building: Main
Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Main Service					
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	1	EA	7	\$0
	PA System	213,820	SF	6	\$70,325
Power Distribution					
	Lighting and Power Panels - 100 A	23	EA	6	\$6,880
	Lighting and Power Panels - Above 100 A	25	EA	7	\$0
	Main Distribution Panels - 400 - 600 amp	3	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	2	EA	7	\$0
	Main Distribution Panels - Less than 400 amp	2	EA	6	\$1,006
Electrical System Subtotal:					\$239,621

Building: Main
Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	213,820	SF	6	\$76,441
	Fire Alarm_System	213,820	SF	6	\$103,959
Safty System Subtotal:					\$186,806

Building: Main
Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Conditioning					
	Condensing Unit- Ground Mounted - Less than 5 tons	2	EA	6	\$6,667
	Condensing Unit- Roof Mounted - Less than 5 tons	3	EA	6	\$10,001
Air Handling Systems					
	Air Handling Unit- Built Up- Single Zone- Steam Coils - 15001 - 25000 cfm	1	EA	6	\$5,788
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 15001 - 25000 cfm	2	EA	5	\$88,525
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Steam Coils - 25001 - 35000 cfm	1	EA	5	\$55,649
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 25001 - 35000 cfm	1	EA	5	\$78,608
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 8001 - 15000 cfm	3	EA	5	\$150,010
	Air Intake	5	EA	5	\$37,353
	Air Intake	2	EA	6	\$11,529

Building: Main
Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Handling Systems					
	Air Intake	1	EA	7	\$0
	Auxiliaries - 15001 - 25000 cfm	2	EA	5	\$29,798
	Auxiliaries - 15001 - 25000 cfm	1	EA	6	\$5,788
	Auxiliaries - 25001 - 35000 cfm	2	EA	5	\$33,155
	Auxiliaries - 8001 - 15000 cfm	3	EA	5	\$38,723
	Fan Power Box - Fan Power Box with Electric Coil	1	EA	6	\$558
	Reheat Boxes - Reheat Boxes with Steam Coil	20	EA	6	\$21,022
	Return Duct Work - Indoor- Vertical Shaft and Ducts	800	LF	7	\$0
	Zone Dampers	114	EA	6	\$94,966
Boiler Systems					
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - Greater than 300 HP	2	EA	5	\$51,050
	Chemical Feeder	1	EA	6	\$1,078
	Combustion Dampers	2	EA	5	\$5,104
	Condensate Pump	5	EA	5	\$90,980
	Feed Water Pumps and Tank	1	EA	6	\$2,545
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - Greater than 300 HP	2	EA	5	\$51,050
	Piping - Condensate Pipe- Steel	2,000	LF	6	\$3,775
	Piping - Steam Pipe- Steel	2,000	LF	6	\$3,775
	Steam Traps	213	EA	5	\$280,074
Heating Devices					
	Cabinet Heaters - With Steam Coil	2	EA	5	\$3,526
	Fin Tube - Steam	100	LF	5	\$8,142
	Fin Tube - Steam	200	LF	6	\$1,888
	Radiators - Steam	10	EA	4	\$36,571
	Radiators - Steam	47	EA	5	\$78,740
	Unit Heater - Steam	2	EA	5	\$1,819
	Wall Heater - Electric	12	EA	6	\$1,667
Temperature Control					
	Electric Thermostat	2	EA	6	\$0
	Pneumatic System	213,820	SF	4	\$1,112,976
	Thermostats - Pneumatic	25	EA	4	\$18,431
	Thermostats - Pneumatic	50	EA	6	\$0
Ventilation					
	Exhaust Fans- Indoor - Less than 500 CFM	3	EA	6	\$889

Building: Main
Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Ventilation					
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	7	EA	6	\$4,147
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	3	EA	6	\$1,777
	Exhaust Fans- Roof Mounted - Less than 500 CFM	2	EA	6	\$592
	Lab Exhaust Hood	2	EA	6	\$2,495
	Roof Mounted Duct Work	40	LF	6	\$15,161
	Type I Exhaust Hood- Culinary Arts	4	EA	6	\$4,991
	Type I Exhaust Hood- Kitchen	2	EA	6	\$2,495
	Type II Exhaust Hood- Warming Kitchen	1	EA	6	\$920

Mechanical System Subtotal:
\$2,454,798
Building: Main
Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Hot Water					
	Gas Heater - 300001 - 600000 BTU/HR	2	EA	5	\$4,498
	Hot Water Storage Tank_Gas - 501 - 1000 Gallons	1	EA	6	\$678
Piping					
	Domestic Piping-Cold Water from Risers to Fixtures	213,828	SF	6	\$42,808
	Domestic Piping-Cold Water Horizontal Lines	213,828	SF	6	\$51,982
	Domestic Piping-Cold Water Risers	213,828	SF	6	\$39,751
	Domestic Piping-Hot Water from Risers to Fixtures	213,828	SF	6	\$33,635
	Domestic Piping-Hot Water Horizontal Lines	213,828	SF	6	\$39,751
	Domestic Piping-Hot Water Return Lines	213,828	SF	6	\$30,577
	Domestic Piping-Hot Water Return Risers	213,828	SF	6	\$30,577
	Sanitary Piping	213,828	SF	6	\$195,695
	Storm Piping	213,828	SF	6	\$186,522
	Vent Piping	213,828	SF	6	\$143,714
Pool Systems					
	Pool Drain Piping	100	LF	4	\$10,129
	Pool Filtration System including Pump	1	EA	6	\$12,330
	Pool Hot Water Heater - Gas Fired	1	EA	6	\$310
	Pool Supply and Return Piping	100	LF	6	\$4,805
Pumps					
	Pumps - Domestic Booster Pump-Simplex	2	EA	6	\$2,891

Building: Main
Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Pumps					
	Pumps - Ejector-Simplex	2	EA	6	\$1,490
	Pumps - Sump-Simplex	5	EA	6	\$3,725

Plumbing System Subtotal:
\$835,870
Building: Main
Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Carpentry (1 room)					
	Casework	52	LF	6	\$1,313
	Ceiling - Splined	4	SF	5	\$39
	Ceiling - Splined	2,696	SF	6	\$2,198
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	2	EA	5	\$2,348
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	2,700	SF	5	\$12,124
	Lighting - Pendent/Surface	3	EA	4	\$1,622
	Lighting - Pendent/Surface	30	EA	6	\$3,717
	Lighting - Pendent/Surface	21	EA	7	\$0
	Walls - Plaster/Drywall	1,469	SF	6	\$4,054
	Walls - Structural Glazed Tile	1,469	SF	6	\$4,621
	Wood Shop Equipment	20	EA	6	\$80,547
	Work Sink	3	EA	6	\$1,137

Computer Lab (7 rooms)

AC Units	9	EA	5	\$16,432
Casework	64	LF	6	\$1,616
Ceiling - Plaster/Drywall	6,084	SF	6	\$21,054
Chalk Board	18	LF	4	\$1,653
Doors - Transom Window	9	SF	5	\$381
Doors - Transom Window	90	SF	6	\$1,524
Doors - Wood Doors inclu hw	16	EA	6	\$4,816
Floor - Carpet	1,053	SF	5	\$5,406
Floor - Carpet	1,900	SF	6	\$4,048
Floor - Tile/Sheet	822	SF	6	\$823
Floor - Wood	2,309	SF	6	\$16,278
Lighting - Pendent/Surface	20	EA	6	\$2,478

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Computer Lab (7 rooms)					
	Lighting - Pendent/Surface	76	EA	7	\$0
	Marker Board	67	LF	7	\$0
	Storage/ Closet	104	SF	6	\$754
	Walls - Plaster/Drywall	30	SF	5	\$153
	Walls - Plaster/Drywall	8,761	SF	6	\$24,179
	Wireless System	1	EA	6	\$372
	Wireless System	3	EA	7	\$0
	Work Sink	6	EA	6	\$2,274
Culinary (2 rooms)					
	AC Units	2	EA	5	\$3,652
	Casework	30	LF	6	\$758
	Ceiling - Lay-in	2,318	SF	6	\$6,961
	Chalk Board	14	LF	4	\$1,285
	Culinary Kitchen Equipment	1	EA	6	\$4,027
	Doors - Transom Window	18	SF	5	\$762
	Doors - Transom Window	18	SF	6	\$305
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Tile Ceramic/ Porcelain	1,686	SF	6	\$3,568
	Floor - Tile/Sheet	632	SF	6	\$633
	Lighting - Lay-in	35	EA	7	\$0
	Marker Board	12	LF	7	\$0
	Walls - Plaster/Drywall	3,653	SF	6	\$10,082
	Work Sink	1	EA	6	\$379
Health (2 rooms)					
	Casework	39	LF	6	\$985
	Ceiling - Plaster/Drywall	1,189	SF	6	\$4,115
	Doors - Transom Window	18	SF	6	\$305
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Tile/Sheet	1,189	SF	6	\$1,190
	Lighting - Pendent/Surface	15	EA	7	\$0
	Walls - Plaster/Drywall	12	SF	4	\$176
	Walls - Plaster/Drywall	1,450	SF	5	\$10,990
	Walls - Plaster/Drywall	1,024	SF	6	\$2,826
	Work Sink	3	EA	6	\$1,137
Laboratory/Shop (1 room)					
	Ceiling - Splined	2	SF	5	\$19

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Laboratory/Shop (1 room)					
	Ceiling - Splined	453	SF	6	\$369
	Chalk Board	6	LF	4	\$551
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	2	EA	5	\$2,348
	Floor - Tile	455	SF	6	\$995
	Lighting - Pendent/Surface	8	EA	7	\$0
	Marker Board	18	LF	7	\$0
	Walls - Plaster/Drywall	408	SF	6	\$1,126
	Walls - Structural Glazed Tile	446	SF	5	\$22,660
Music Room (1 room)					
	Ceiling - Plaster/Drywall	1,702	SF	6	\$5,890
	Chalk Board	30	LF	4	\$2,754
	Doors - Transom Window	18	SF	6	\$305
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Wood	1,702	SF	5	\$24,898
	Lighting - Pendent/Surface	19	EA	7	\$0
	Storage/ Closet	12	SF	6	\$87
	Walls - Plaster/Drywall	2,030	SF	6	\$5,603
Office (1 room)					
	AC Units	1	EA	5	\$1,826
	Casework	2	LF	5	\$418
	Casework	4	LF	6	\$101
	Ceiling - Plaster/Drywall	508	SF	6	\$1,758
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	508	SF	6	\$3,581
	Lighting - Pendent/Surface	8	EA	7	\$0
	Marker Board	6	LF	7	\$0
	Walls - Plaster/Drywall	1,035	SF	6	\$2,856
Other Instructional Use (1 room)					
	AC Units	1	EA	5	\$1,826
	Ceiling - Plaster/Drywall	508	SF	6	\$1,758
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Carpet	508	SF	6	\$1,082
	Lighting - Pendent/Surface	8	EA	7	\$0

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Other Instructional Use (1 room)					
	Storage/ Closet	50	SF	6	\$363
	Walls - Plaster/Drywall	10	SF	5	\$51
	Walls - Plaster/Drywall	1,025	SF	6	\$2,829
Regular Classroom (37 rooms)					
	AC Units	7	EA	5	\$12,781
	Casework	20	LF	5	\$4,182
	Casework	386	LF	6	\$9,748
	Ceiling - Exposed	800	SF	6	\$1,190
	Ceiling - Lay-in	40	SF	5	\$319
	Ceiling - Lay-in	2,940	SF	6	\$8,829
	Ceiling - Plaster/Drywall	23	SF	5	\$287
	Ceiling - Plaster/Drywall	24,721	SF	6	\$85,549
	Ceiling - Splined	6	SF	4	\$84
	Ceiling - Splined	12	SF	5	\$116
	Ceiling - Splined	884	SF	6	\$721
	Chalk Board	554	LF	4	\$50,861
	Chalk Board	25	LF	6	\$558
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	54	SF	4	\$4,128
	Doors - Transom Window	18	SF	5	\$762
	Doors - Transom Window	460	SF	6	\$7,788
	Doors - Wood Doors inclu hw	4	EA	5	\$4,696
	Doors - Wood Doors inclu hw	62	EA	6	\$18,661
	Floor - Tile	1,702	SF	6	\$3,724
	Floor - Tile/Sheet	724	SF	6	\$725
	Floor - Wood	9,796	SF	5	\$143,305
	Floor - Wood	17,204	SF	6	\$121,286
	Lighting - Lay-in	48	EA	7	\$0
	Lighting - Pendent/Surface	21	EA	6	\$2,602
	Lighting - Pendent/Surface	381	EA	7	\$0
	Marker Board	409	LF	7	\$0
	Storage/ Closet	135	SF	6	\$979
	Walls - Plaster/Drywall	8	SF	4	\$118
	Walls - Plaster/Drywall	44	SF	5	\$225
	Walls - Plaster/Drywall	44,486	SF	6	\$122,777
	Walls - Tile	6	SF	5	\$137
	Walls - Tile	806	SF	6	\$1,763

Building: Main
Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Regular Classroom (37 rooms)					
	Wireless System	1	EA	6	\$372
	Work Sink	4	EA	6	\$1,516
Science Lab Level 1 (2 rooms)					
	AC Units	2	EA	5	\$3,652
	Casework	155	LF	6	\$3,914
	Ceiling - Plaster/Drywall	2,508	SF	6	\$8,679
	Doors - Transom Window	36	SF	6	\$610
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Eye Wash Station	2	EA	6	\$672
	Floor - Tile/Sheet	2,508	SF	6	\$2,511
	Fume Hood	2	EA	6	\$1,631
	Gas Line	47	EA	6	\$23,929
	Lighting - Pendent/Surface	44	EA	7	\$0
	Marker Board	5	LF	7	\$0
	Science Lab Shower	2	EA	6	\$758
	Walls - Plaster/Drywall	3,566	SF	6	\$9,842
	Work Sink	18	EA	6	\$6,822
Science Lab Level 2 (2 rooms)					
	AC Units	2	EA	5	\$3,652
	Casework	100	LF	6	\$2,525
	Ceiling - Plaster/Drywall	2,382	SF	6	\$8,243
	Doors - Transom Window	27	SF	6	\$457
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile/Sheet	2,382	SF	6	\$2,384
	Gas Line	14	EA	6	\$7,128
	Lighting - Pendent/Surface	42	EA	7	\$0
	Marker Board	28	LF	7	\$0
	Walls - Plaster/Drywall	6	SF	4	\$88
	Walls - Plaster/Drywall	3,404	SF	6	\$9,395
	Work Sink	14	EA	6	\$5,306
Vacant (2 rooms)					
	Doors - Wood Doors inclu hw	2	EA	6	\$602

Classrooms Subtotal:
\$1,079,272
Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	AC Unit	8	EA	5	\$14,607
	AC Unit	12	EA	6	\$5,947
	Ceiling - Lay-in	4	SF	5	\$32
	Ceiling - Lay-in	5,786	SF	6	\$17,375
	Ceiling - Plaster/Drywall	32	SF	4	\$696
	Ceiling - Plaster/Drywall	384	SF	5	\$3,600
	Ceiling - Plaster/Drywall	9,147	SF	6	\$31,654
	Doors - Side-lite	250	SF	6	\$4,179
	Doors - Side-lite	56	SF	7	\$0
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	9	SF	4	\$688
	Doors - Transom Window	312	SF	6	\$5,283
	Doors - Wood Doors inclu hw	18	EA	5	\$21,133
	Doors - Wood Doors inclu hw	33	EA	6	\$9,933
	Doors - Wood Doors inclu hw	10	EA	7	\$0
	Floor - Carpet	1,850	SF	4	\$17,011
	Floor - Carpet	742	SF	5	\$3,809
	Floor - Carpet	841	SF	6	\$1,792
	Floor - Carpet	4,049	SF	7	\$0
	Floor - Concrete	56	SF	6	\$30
	Floor - Terrazzo	572	SF	6	\$1,251
	Floor - Tile	84	SF	4	\$858
	Floor - Tile	2,056	SF	5	\$9,232
	Floor - Tile	1,999	SF	6	\$4,374
	Floor - Tile	336	SF	7	\$0
	Floor - Tile/Sheet	1,214	SF	6	\$1,215
	Floor - Wood	365	SF	5	\$5,340
	Floor - Wood	1,235	SF	6	\$8,707
	Lighting - Lay-in	74	EA	7	\$0
	Lighting - Pendent/Surface	9	EA	6	\$1,115
	Lighting - Pendent/Surface	139	EA	7	\$0
	Power Distribution	10	EA	5	\$38,516
	Power Distribution	92	EA	6	\$195,489
	Power Distribution	200	EA	7	\$0
	Storage/ Closet	50	SF	5	\$807
	Storage/ Closet	478	SF	6	\$3,466
	Storage/ Closet	280	SF	7	\$0
	Walls - Metal Panel	536	SF	6	\$4,001
	Walls - Plaster/Drywall	22	SF	4	\$323

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Walls - Plaster/Drywall	10	SF	5	\$51
	Walls - Plaster/Drywall	27,500	SF	6	\$75,897
	Walls - Structural Glazed Tile	328	SF	6	\$1,032
	Work Sink	1	EA	4	\$7,669
	Work Sink	3	EA	6	\$1,524
Auditorium & Theater					
	Balcony Seating	8	EA	4	\$5,980
	Balcony Seating	254	EA	6	\$44,175
	Ceiling - Plaster/Drywall	1,951	SF	6	\$16,265
	Ceiling - Splined	2,927	SF	6	\$2,386
	Doors - Wood Doors inclu hw	20	EA	5	\$23,481
	Floor - Concrete Epoxy/ Painted	1,920	SF	6	\$1,016
	Floor - Tile Quarry	60	SF	4	\$3,296
	Floor - Tile Quarry	4,006	SF	5	\$92,860
	Lighting - Pendent/Surface	1	EA	6	\$124
	Lighting - Pendent/Surface	24	EA	7	\$0
	Main Floor Seating	448	EA	6	\$77,915
	Sound System	1	EA	6	\$10,721
	Stage	812	SF	6	\$4,691
	Stage Curtain	2	EA	6	\$0
	Stage Lighting System	1	EA	6	\$8,077
	Stage-Stairs - Wood	6	LF	6	\$70
	Walls	2		5	\$0
	Walls	460		6	\$0
	Walls - Plaster/Drywall	6,158	SF	6	\$29,324
Gymnasia					
	Bleacher Seating	26	EA	6	\$753
	Ceiling - Plaster/Drywall	16	SF	4	\$538
	Ceiling - Plaster/Drywall	100	SF	5	\$2,003
	Ceiling - Plaster/Drywall	11,936	SF	6	\$65,884
	Doors - Transom Window	36	SF	6	\$610
	Doors - Wood Doors inclu hw	5	EA	5	\$5,870
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Floor - Wood	11,948	SF	6	\$84,232
	Lighting - Pendent/Surface	36	EA	7	\$0
	Lighting - Wall Mounted	4	EA	7	\$0

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Gymnasias					
	Scoreboards	2	EA	6	\$4,489
	Storage/ Closet	128	SF	6	\$928
	Walls - Structural Glazed Tile	16,560	SF	6	\$52,098
Kitchen					
	Ceiling - Exposed	140	SF	6	\$208
	Ceiling - Splined	10	SF	5	\$97
	Ceiling - Splined	751	SF	6	\$612
	Doors - Transom Window	27	SF	6	\$457
	Doors - Wood Doors inclu hw	3	EA	5	\$3,522
	Floor - Terrazzo	901	SF	5	\$33,911
	Lighting - Pendent/Surface	6	EA	7	\$0
	Walls - Masonry	1,123	SF	6	\$3,533
	Walls - Plaster/Drywall	6	SF	4	\$88
	Walls - Plaster/Drywall	369	SF	6	\$1,018
Library					
	AC Unit	3	EA	5	\$5,477
	Casework	120	LF	6	\$3,030
	Ceiling - Plaster/Drywall	80	SF	5	\$1,000
	Ceiling - Plaster/Drywall	1,781	SF	6	\$6,163
	Doors - Transom Window	27	SF	6	\$457
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Carpet	1,861	SF	4	\$17,112
	Lighting - Pendent/Surface	14	EA	7	\$0
	Walls - Plaster/Drywall	1,783	SF	6	\$4,921
Lunch & Multipurpose Room					
	Ceiling - Lay-in	8	SF	5	\$64
	Ceiling - Lay-in	7,743	SF	6	\$23,252
	Ceiling - Plaster/Drywall	6	SF	5	\$75
	Ceiling - Plaster/Drywall	2,052	SF	6	\$7,101
	Doors - Transom Window	198	SF	6	\$3,352
	Doors - Wood Doors inclu hw	24	EA	5	\$28,178
	Floor - Terrazzo	50	SF	5	\$2,616
	Floor - Terrazzo	8,387	SF	6	\$18,350
	Floor - Tile Ceramic/ Porcelain	4	SF	4	\$154
	Floor - Tile Ceramic/ Porcelain	1,364	SF	5	\$21,787

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Lunch & Multipurpose Room					
	Lighting - Lay-in	62	EA	7	\$0
	Lighting - Pendent/Surface	10	EA	6	\$1,239
	Lighting - Pendent/Surface	14	EA	7	\$0
	Serving Line	140	LF	6	\$8,332
	Storage/ Closet	464	SF	6	\$3,364
	Student Lockers - Two Tier	82	EA	6	\$3,806
	Walls - Plaster/Drywall	11	SF	4	\$162
	Walls - Plaster/Drywall	10	SF	5	\$51
	Walls - Plaster/Drywall	4,852	SF	6	\$13,391
	Walls - Structural Glazed Tile	3,637	SF	6	\$11,442
MDF_IDF					
	AC Unit	2	EA	5	\$3,652
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Finishes	434	SF	5	\$7,007
Mechanical/ Service Rooms					
	Boiler Room	3,036	SF	5	\$48,972
	Interior Stairs	42	LF	6	\$379
	Janitor's Closet	446	SF	6	\$3,195
	Mechanical/ Service Rooms	5,863	SF	5	\$94,573
	Storage Room	4,184	SF	6	\$29,975
Pool & Natatorium					
	Accessories	3,589	SF	6	\$2,463
	Bleachers Seating/Plank Seating	45	EA	6	\$1,302
	Ceiling - Plaster/ Drywall	3,589	SF	6	\$19,811
	Doors - Steel Doors incl hw	4	EA	6	\$1,204
	Doors - Transom Window	168	SF	6	\$2,844
	Lighting - Pendent/Surface	18	EA	6	\$2,230
	Lighting - Pendent/Surface	42	EA	7	\$0
	Lighting - Wall Mounted	6	EA	6	\$743
	Lighting - Wall Mounted	7	EA	7	\$0
	Pool Basin	1,500	SF	6	\$50,751
	Pool Deck	2,069	SF	6	\$19,646
	Pool Deck Drains	6	EA	6	\$2,532
	Walls - Structural Glazed Tile	3,276	SF	5	\$166,447

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Prep Room					
	Casework	40	LF	6	\$1,010
	Ceiling - Plaster/Drywall	440	SF	6	\$1,523
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile/Sheet	440	SF	6	\$440
	Lighting - Pendent/Surface	1	EA	6	\$124
	Lighting - Pendent/Surface	4	EA	7	\$0
	Walls - Plaster/Drywall	1,572	SF	6	\$4,339
	Work Sink	2	EA	5	\$3,016
	Work Sink	8	EA	6	\$3,032
Restroom					
	Accessories	5,511	SF	6	\$50,831
	Ceiling - Lay-in	348	SF	6	\$1,045
	Ceiling - Plaster/Drywall	26	SF	4	\$566
	Ceiling - Plaster/Drywall	6	SF	5	\$75
	Ceiling - Plaster/Drywall	5,168	SF	6	\$17,884
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	36	SF	6	\$610
	Doors - Wood Doors inclu hw	2	EA	5	\$2,348
	Doors - Wood Doors inclu hw	29	EA	6	\$8,729
	Floor - Tile	187	SF	6	\$409
	Floor - Tile Ceramic/ Porcelain	109	SF	5	\$1,756
	Floor - Tile Ceramic/ Porcelain	5,215	SF	6	\$11,037
	Floor - Tile/Sheet	37	SF	6	\$37
	Floor Drain	15	EA	6	\$15,887
	Hand Dryer	1	EA	5	\$590
	Hand Dryer	11	EA	6	\$2,530
	Lavatory	14	EA	5	\$22,255
	Lavatory	28	EA	6	\$8,949
	Lighting - Lay-in	5	EA	7	\$0
	Lighting - Pendent/Surface	8	EA	6	\$991
	Lighting - Pendent/Surface	85	EA	7	\$0
	Partitions	53	EA	6	\$15,737
	Showers	2	EA	6	\$623
	Student Lockers - One Tier	9	EA	6	\$836
	Urinals	1	EA	4	\$7,669
	Urinals	1	EA	5	\$1,344
	Urinals	22	EA	6	\$7,392

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Restroom					
	Walls	18		6	\$0
	Walls - Metal Panel	97	SF	6	\$724
	Walls - Plaster/Drywall	29	SF	4	\$426
	Walls - Plaster/Drywall	15	SF	5	\$77
	Walls - Plaster/Drywall	6,629	SF	6	\$18,295
	Walls - Structural Glazed Tile	2	SF	4	\$245
	Walls - Structural Glazed Tile	19	SF	5	\$1,213
	Walls - Structural Glazed Tile	8,493	SF	6	\$26,719
	Walls - Tile	1	SF	5	\$23
	Walls - Tile	3,282	SF	6	\$7,181
	Walls - Tile Ceramic/ Porcelain	173	SF	6	\$391
	Water Closet	68	EA	6	\$22,847

Rooms (Other Than Classrooms) Subtotal:
\$2,000,216
Building: Main
Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					
	Ceiling - Plaster/Drywall	6	SF	5	\$105
	Ceiling - Plaster/Drywall	29,264	SF	6	\$181,200
	Doors - Wood Doors include hw	16	EA	6	\$4,816
	Drinking Fountains - Single Fountain	1	EA	6	\$276
	Drinking Fountains - Single Water Cooler	1	EA	5	\$3,007
	Drinking Fountains - Single Water Cooler	18	EA	6	\$5,700
	Floor - Terrazzo	70	SF	5	\$3,663
	Floor - Terrazzo	3,420	SF	6	\$28,708
	Floor - Tile/Sheet	26,334	SF	6	\$14,310
	Lighting - Lay-in	1	EA	7	\$0
	Lighting - Pendent/Surface	306	EA	7	\$0
	Stairs - Terrazzo	6	LF	6	\$56
	Student Lockers - One Tier	1,678	EA	6	\$155,778
	Walls - Plaster/Drywall	2	SF	5	\$20
	Walls - Plaster/Drywall	22,783	SF	6	\$100,997
	Walls - Structural Glazed Tile	31,471	SF	6	\$99,008

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Safety					
	Camera Viewing Station	1	EA	6	\$683
	Metal Dedector	1	EA	6	\$881
	Security Cameras	60	EA	6	\$11,642
Stairs					
	Ceiling - Plaster/Drywall	8	SF	4	\$283
	Ceiling - Plaster/Drywall	6	SF	5	\$123
	Ceiling - Plaster/Drywall	5,037	SF	6	\$36,879
	Floor - Terrazzo	4,321	SF	6	\$36,271
	Handrails	636	LF	6	\$5,511
	Lighting - Pendent/Surface	4	EA	4	\$2,163
	Lighting - Pendent/Surface	10	EA	6	\$1,239
	Lighting - Pendent/Surface	33	EA	7	\$0
	Stairs - Terrazzo	355	LF	6	\$3,295
	Walls - Concrete Block	24	SF	6	\$70
	Walls - Plaster/Drywall	12	SF	4	\$176
	Walls - Plaster/Drywall	804	SF	5	\$4,303
	Walls - Plaster/Drywall	11,501	SF	6	\$31,742
	Walls - Structural Glazed Tile	5,118	SF	6	\$16,101
Vertical Conveyance					
	Elevator - Hydraulic Elevator	1	EA	6	\$19,238

Building Interior Subtotal: **\$768,242**

Total Building Cost **\$11,812,917**

SITE

Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Civil/Drainage					
	Civil/ Drainage - Catch Basin	6	EA	6	\$6,563
	Civil/ Drainage - Site Drain	1	EA	6	\$310
	Civil/ Drainage - Site Manhole	5	EA	5	\$18,487
	Civil/ Drainage - Site Manhole	21	EA	6	\$31,348
Fencing					
	Fencing - Chain Link	109	LF	5	\$6,648

SITE
Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Fencing					
	Fencing - Chain Link	164	LF	6	\$3,079
	Fencing - Guard Rail	688	LF	6	\$7,949
	Fencing - New Standard Ornamental	1,183	LF	6	\$37,742
Landscape					
	Benches	4	EA	6	\$1,720
	Landscape - Grass	17,680	SF	6	\$14,664
	Landscape - Hardscape- Concrete	450	SF	5	\$4,936
	Landscape - Hardscape- Concrete	2,586	SF	6	\$13,350
	Parkway trees	22	EA	5	\$30,844
	Planting Beds/ Area	1,600	SF	6	\$2,631
	Retaining Wall - Concrete	10	SF	5	\$735
	Retaining Wall - Concrete	1,587	SF	6	\$37,196
	Retaining Wall - Masonry	5	SF	5	\$292
	Retaining Wall - Masonry	109	SF	6	\$1,591
	Trash Receptacles	1	EA	6	\$312
Parking Lot					
	Concrete Curbs	105	LF	6	\$1,348
	Surface - Asphalt	32,295	SF	5	\$147,320
	Surface - Asphalt	20,159	SF	6	\$48,718
	Trash Compactor	1	EA	6	\$0
	Trash Enclosure	252	SF	6	\$0
Sidewalks					
	Sidewalks - Internal Walks	20	LF	4	\$1,944
	Sidewalks - Internal Walks	200	LF	6	\$2,402
	Sidewalks - Perimeter Sidewalks	100	SF	5	\$955
	Sidewalks - Perimeter Sidewalks	29,242	SF	6	\$58,124
Signage					
	Flag Pole - Flag Pole	1	EA	6	\$1,657
	Marquee - Free Standing Back Lighted	1	EA	6	\$0
Site Subtotal:					\$482,866
Total Site Cost					\$482,866

Campus Total ^{2 3}**\$12,295,783**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Carpentry	Laboratory/Shop	1st Floor	114	114	2,700			50			40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	200	200	861	1	8	80	192	72	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	201	201	1,176	2	35	80	150	60	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	204	204	724	1	8	80	192	72	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	208	208	724	1	8	80	192	72	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	212	212	724	1	20	60	192	72	40	N	N	N
Computer Lab	Computer Lab	2nd Floor	213	213	1,053	2	35	60	150	60	40	N	N	N
Computer Lab	Art Room	3rd Floor	304	304	822	1	11	32	192	72	40	N	N	N
Culinary	Culinary	2nd Floor	207	207	1,416	1	0				40	N	N	N
Culinary	Culinary	2nd Floor	215	215	902	1	0				40	N	N	N
Health	Other Instructional Use	3rd Floor	302B	302B	367	1	2	6	128	48	40	N	N	N
Health	Art Room	3rd Floor	308	308	822	1	11	32	192	72	40	N	N	N
Laboratory/Shop	Laboratory/Shop	1st Floor	112	112	455	1	5	20	38	18	40	N	N	N
Music Room	Music Room	3rd Floor	319	319	1,702	1	10	20	90	45	40	N	N	N
Office	Regular Classroom	2nd Floor	209A	209	508	1	6	24	75	30	40	N	N	N
Other Instructional Use	Regular Classroom	2nd Floor	209B	209B	508	1	6	16	75	30	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	111	111	720						40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	113	113	840	1	0				40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	125	125	720						40	N	N	N
Regular Classroom	Computer Lab	2nd Floor	202	202	808	1	8	40	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	724	1	8	20	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	210	210	724	1	8	20	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	214	214	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	216	216	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	218	218	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	220	220	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	222	222	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	223	223	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	227	227	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	229	229	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	231	231	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	233	233	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	235	235	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	237	237	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	300	300	822	1	11	32	192	72	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	301	301	822	1	6	16	192	72	40	N	N	Y
Regular Classroom	Regular Classroom	1st Floor	305	305	822	1	6	16	192	72	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	3rd Floor	312	312	822	1	6	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	313	313	822	1	6	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	316	316	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	317	ROTC 317	1,702	1	10	20	130	45	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	318	318	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	320	320	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	321	ROTC 321	1,702	1	10	20	90	45	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	322	322	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	323	323	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	325	325	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	327	327	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	329	329	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	331	331	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	333	333	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	335	335	724	1	8	16	192	72	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	337	337	724	1	8	16	192	72	40	N	N	N
Science Lab Level 1	Science	3rd Floor	310	310	1,254	1	16	28	320	120	40	N	N	N
Science Lab Level 1	Science	3rd Floor	315	315	1,254	1	16	28	320	120	40	N	N	N
Science Lab Level 2	Science	3rd Floor	302	302	1,128	1	1	38	320	120	40	N	N	N
Science Lab Level 2	Science	3rd Floor	307	307	1,254	1	16	28	320	120	40	N	N	N
Vacant	Regular Classroom	3rd Floor	309	309	822	1	6	16	192	72	40	N	N	N
Vacant	Music Room	3rd Floor	324	324								N	N	N