

## Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1961	2	42,620	\$3,005,100
SITE				\$229,452
Campus Total			42,620	\$3,234,552

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	1	EA	7	\$0
	Exterior Doors - Exterior Steel Door	3	EA	6	\$1,442
	Exterior Doors - Store Front	9	EA	6	\$4,915
	Exterior Doors - Transom Lite	2	EA	6	\$627
	Exterior Stairs - Concrete	71	LF	6	\$5,805
	Exterior Stairs - Stone	20	LF	6	\$2,260
<b>Foundation</b>					
	Foundation - Concrete	1	LF	5	\$0
	Foundation - Concrete	745	LF	7	\$0
	Superstructure - Concrete	38,705	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	11	EA	6	\$5,902
	Exterior Lighting - Wall Mounted	9	EA	6	\$2,599
<b>Roof System</b>					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	15	LF	5	\$42,773
	Chimney - Brick Chimney- Concrete/ Mortar Liner	26	LF	6	\$24,822
	Coping - Stone	2	LF	4	\$727
	Coping - Stone	790	LF	6	\$25,373

## Building: Main

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Roof System</b>					
	Downspouts - Interior Downspouts	117	LF	6	\$3,888
	Parapet - 16" - 30" Height	230	LF	5	\$46,855
	Parapet - 16" - 30" Height	562	LF	6	\$22,454
	Roof - Modified Bitumen	21,168	SF	4	\$580,281
	Roof - Modified Bitumen	561	SF	6	\$5,279
	Roof Structure - Concrete	21,729	SF	7	\$0
<b>Walls</b>					
	Canopy - Concrete/ Stucco	234	SF	5	\$23,574
	Exterior Walls - Brick	300	SF	5	\$7,143
	Exterior Walls - Brick	18,376	SF	6	\$123,505
	Exterior Walls - Stone-Cast	720	SF	6	\$4,839
<b>Windows</b>					
	Curtain wall - Glazed Double Pane	366	SF	6	\$4,103
	Curtain wall - Louver	46	SF	6	\$516
	Guard - Guards perforated	5,157	SF	6	\$65,854
	Lintels - Steel	741	LF	6	\$21,510
	Lintels - Stone	38	LF	6	\$0
	Windows - Sash Aluminum	4,626	SF	6	\$34,531

### Building Exterior Subtotal:

**\$1,061,577**

## Building: Main

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Corridors and Stairs	6,402	SF	6	\$1,923
	Emergency A/C Power - Gym	3,424	SF	6	\$1,273
	Emergency A/C Power - Students Toilets	1,210	SF	6	\$450
	Emergency Battery Packs - Corridors and Stairs	7	EA	6	\$1,418
	Emergency Battery Packs - Gym	2	EA	6	\$405
	Exit Signs - Corridors and Stairs	9	EA	2	\$4,909
	Exit Signs - Lunchroom	4	EA	2	\$2,182
	Security System - CCTV	42,620	SF	6	\$12,799
	Security System - Intrusion Detection	42,620	SF	6	\$10,970

**Building: Main**
**Category: Electrical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Main Service</b>					
	Independent Electrical Service for emergency power	1	EA	6	\$2,921
	Main Electrical Service - 1600 A 120/208/3PH	1	EA	6	\$5,641
	PA System	42,620	SF	6	\$14,018
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	1	EA	4	\$4,849
	Lighting and Power Panels - 100 A	1	EA	6	\$299
	Lighting and Power Panels - Above 100 A	10	EA	6	\$4,970
	Main Distribution Panels - 400 - 600 amp	1	EA	6	\$528
	Main Distribution Panels - Greater than 600 amp	1	EA	6	\$730
	Main Distribution Panels - Less than 400 amp	1	EA	6	\$503
<b>Electrical System Subtotal:</b>					<b>\$71,196</b>

**Building: Main**
**Category: Safty System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	42,620	SF	4	\$57,899
	Fire Alarm_System	42,620	SF	4	\$84,716
<b>Safty System Subtotal:</b>					<b>\$149,021</b>

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Handling Systems</b>					
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 4000-8000 cfm	2	EA	5	\$52,885
	Air Intake	2	EA	5	\$14,941
	Auxiliaries - 4000-8000 cfm	2	EA	5	\$0
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	2	EA	5	\$19,463
<b>Boiler Systems</b>					
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 76 - 100 HP	2	EA	6	\$5,091
	Chemical Feed System	1	EA	6	\$1,078
	Chemical Feeder	1	EA	6	\$1,078

## Building: Main

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Boiler Systems</b>					
	Combustion Dampers	2	EA	6	\$818
	Condensate Pump	2	EA	5	\$36,392
	Feed Water Pumps and Tank	1	EA	6	\$2,545
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 76 - 100 HP	2	EA	6	\$5,091
	Piping - Condensate Pipe- Steel	300	LF	5	\$3,659
	Piping - Steam Pipe- Steel	300	LF	5	\$4,226
	Steam Traps	12	EA	6	\$3,170
	Vacuum Pump	2	EA	5	\$28,812
<b>Gas Booster</b>					
	Gas Booster	3	EA	6	\$1,497
<b>Heating Devices</b>					
	Cabinet Heaters - With Steam Coil	12	EA	6	\$4,279
	Fin Tube - Steam	80	LF	6	\$755
	Wall Heater - Electric	6	EA	5	\$3,220
<b>Temperature Control</b>					
	Hybrid Pneumatic/DDC System	42,620	SF	5	\$146,881
	Thermostats - Pneumatic	25	EA	6	\$0
<b>Unit Ventilation</b>					
	Unit Ventilators- Floor Mounted- Steam Heating Coils Only	24	EA	5	\$228,926
<b>Ventilation</b>					
	Exhaust Fans- Indoor - Less than 500 CFM	1	EA	4	\$1,278
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	1	EA	4	\$6,392
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	4	EA	4	\$16,978
	Type I Exhaust Hood- Kitchen	1	EA	4	\$28,265
<b>Mechanical System Subtotal:</b>					<b>\$617,719</b>

## Building: Main

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - 150000 - 300000 BTU/HR	1	EA	6	\$310
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	42,620	SF	6	\$8,533

## Building: Main

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Piping					
	Domestic Piping-Cold Water Horizontal Lines	42,620	SF	6	\$10,361
	Domestic Piping-Cold Water Risers	42,620	SF	6	\$7,923
	Domestic Piping-Hot Water from Risers to Fixtures	42,620	SF	6	\$6,704
	Domestic Piping-Hot Water Horizontal Lines	42,620	SF	6	\$7,923
	Domestic Piping-Hot Water Return Lines	42,620	SF	6	\$6,095
	Domestic Piping-Hot Water Return Risers	42,620	SF	6	\$6,095
	Sanitary Piping	42,620	SF	6	\$39,006
	Storm Piping	42,620	SF	6	\$37,177
	Vent Piping	42,620	SF	6	\$28,645

### Plumbing System Subtotal:

**\$158,771**

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Computer Lab (1 room)					
	AC Units	2	EA	6	\$991
	Casework	20	LF	6	\$505
	Ceiling - Plaster/Drywall	653	SF	6	\$2,260
	Chalk Board	34	LF	4	\$3,121
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile/Sheet	653	SF	5	\$2,932
	Lighting - Pendent/Surface	12	EA	6	\$1,487
	Walls - Concrete Block	934	SF	6	\$2,738
	Wireless System	1	EA	6	\$372
Kindergarten (1 room)					
	AC Units	1	EA	6	\$496
	Casework	24	LF	6	\$606
	Ceiling - Plaster/Drywall	813	SF	6	\$2,813
	Chalk Board	36	LF	4	\$3,305
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	813	SF	6	\$1,779
	Lighting - Pendent/Surface	16	EA	6	\$1,982
	Storage/ Closet	14	SF	6	\$102
	Walls - Concrete Block	1,160	SF	6	\$3,401

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Library (1 room)</b>					
	AC Units	1	EA	6	\$496
	Casework	85	LF	6	\$2,147
	Ceiling - Plaster/Drywall	1,121	SF	6	\$3,879
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Carpet	1,121	SF	6	\$2,389
	Lighting - Pendent/Surface	22	EA	6	\$2,726
	Walls - Concrete Block	1,411	SF	6	\$4,136
	Work Sink	1	EA	6	\$379
<b>Office (1 room)</b>					
	AC Units	1	EA	6	\$496
	Casework	42	LF	6	\$1,061
	Ceiling - Plaster/Drywall	787	SF	6	\$2,723
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile/Sheet	787	SF	6	\$788
	Lighting - Pendent/Surface	16	EA	6	\$1,982
	Walls - Concrete Block	894	SF	6	\$2,621
	Work Sink	1	EA	6	\$379
<b>Pre School (1 room)</b>					
	AC Units	2	EA	6	\$991
	Casework	40	LF	6	\$1,010
	Ceiling - Plaster/Drywall	10	SF	5	\$125
	Ceiling - Plaster/Drywall	1,070	SF	6	\$3,703
	Chalk Board	16	LF	4	\$1,469
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,080	SF	6	\$2,363
	Lighting - Pendent/Surface	22	EA	6	\$2,726
	Storage/ Closet	18	SF	6	\$131
	Walls - Concrete Block	5	SF	5	\$51
	Walls - Plaster/Drywall	1,445	SF	6	\$3,988
	Work Sink	1	EA	6	\$379
<b>Regular Classroom (14 rooms)</b>					
	AC Units	13	EA	6	\$6,443
	Casework	456	LF	6	\$11,516
	Ceiling - Plaster/Drywall	813	SF	5	\$7,452
	Ceiling - Plaster/Drywall	10,309	SF	6	\$35,675
	Chalk Board	224	LF	4	\$20,565

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Regular Classroom (14 rooms)</b>					
	Doors - Wood Doors inclu hw	14	EA	6	\$4,214
	Floor - Tile	813	SF	5	\$3,651
	Floor - Tile	3,226	SF	6	\$7,058
	Floor - Tile/Sheet	7,083	SF	6	\$7,090
	Lighting - Pendent/Surface	224	EA	6	\$27,753
	Marker Board	48	LF	6	\$1,028
	Storage/ Closet	70	SF	6	\$508
	Walls - Concrete Block	13,397	SF	6	\$39,273
	Work Sink	3	EA	6	\$1,137
<b>Store Room (1 room)</b>					
	AC Units	1	EA	6	\$496
	Casework	24	LF	6	\$606
	Ceiling - Plaster/Drywall	813	SF	6	\$2,813
	Chalk Board	36	LF	4	\$3,305
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	813	SF	6	\$1,779
	Lighting - Pendent/Surface	16	EA	6	\$1,982
	Storage/ Closet	14	SF	6	\$102
	Walls - Concrete Block	1,160	SF	6	\$3,401
<b>Classrooms Subtotal:</b>					<b>\$262,579</b>

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	AC Unit	4	EA	6	\$1,982
	Ceiling - Plaster/Drywall	1,586	SF	6	\$5,489
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Carpet	473	SF	6	\$1,008
	Floor - Tile	798	SF	6	\$1,746
	Floor - Tile/Sheet	315	SF	6	\$315
	Lighting - Pendent/Surface	6	EA	4	\$3,244
	Lighting - Pendent/Surface	10	EA	6	\$1,239
	Lighting - Pendent/Surface	8	EA	7	\$0
	Power Distribution	29	EA	6	\$61,622

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Storage/ Closet	50	SF	6	\$363
	Walls - Concrete Block	1,670	SF	6	\$4,896
	Walls - Plaster/Drywall	1,796	SF	6	\$4,957
	Work Slnk	1	EA	6	\$508
<b>Gymnasia</b>					
	Ceiling - Plaster/Drywall	3,424	SF	6	\$18,900
	Doors - Steel Doors incl hw	4	EA	6	\$1,204
	Floor - Tile	3,424	SF	6	\$7,491
	Lighting - Metal Halide/Sodium Vapor	12	EA	7	\$0
	Sound System	1	EA	7	\$0
	Stage	710	SF	6	\$4,102
	Stage Curtain	8	EA	6	\$0
	Stage Lift	1	EA	6	\$6,510
	Stage Lighting System	1	EA	6	\$12,369
	Storage/ Closet	95	SF	6	\$689
	Walls - Concrete Block	2,295	SF	6	\$6,728
	Walls - Structural Glazed Tile	2,295	SF	6	\$7,220
<b>Kitchen</b>					
	Ceiling - Plaster/Drywall	657	SF	6	\$2,274
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Floor - Tile	657	SF	6	\$1,437
	Lighting - Pendent/Surface	12	EA	6	\$1,487
	Serving Line	18	LF	6	\$1,071
	Storage/ Closet	38	SF	6	\$276
	Walls - Concrete Block	317	SF	6	\$929
	Walls - Structural Glazed Tile	739	SF	6	\$2,325
<b>MDF_IDF</b>					
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Finishes	147	SF	6	\$1,049
	Ventilation and Cooling	1	EA	4	\$16,431
<b>Mechanical/ Service Rooms</b>					
	Boiler Room	942	SF	6	\$6,749
	Crawl Space - Unfinished	42,300	SF	6	\$261,917
	Janitor's Closet	86	SF	6	\$616
	Mechanical/ Service Rooms	330	SF	6	\$2,364



## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Mechanical/ Service Rooms</b>					
	Storage Room	116	SF	6	\$831
	Vaults	82	SF	6	\$587
<b>Restroom</b>					
	Accessories	1,496	SF	6	\$13,798
	Ceiling - Plaster/Drywall	266	SF	5	\$2,438
	Ceiling - Plaster/Drywall	1,230	SF	6	\$4,257
	Doors - Wood Doors inclu hw	22	EA	6	\$6,622
	Floor - Tile	219	SF	6	\$479
	Floor - Tile Ceramic/ Porcelain	1,210	SF	6	\$2,561
	Floor - Tile/Sheet	67	SF	6	\$67
	Floor Drain	4	EA	6	\$4,237
	Lavatory	18	EA	6	\$5,753
	Lavatory	1	EA	7	\$0
	Lighting - Lay-in	8	EA	6	\$952
	Lighting - Pendent/Surface	6	EA	6	\$743
	Lighting - Wall Mounted	4	EA	6	\$496
	Partitions	20	EA	6	\$5,939
	Student Lockers	3	EA	6	\$0
	Urinals	11	EA	6	\$3,696
	Walls - Concrete Block	196	SF	5	\$2,012
	Walls - Concrete Block	1,677	SF	6	\$4,916
	Walls - Masonry	170	SF	6	\$535
	Walls - Structural Glazed Tile	1,966	SF	6	\$6,185
	Water Closet	25	EA	6	\$8,399

**Rooms (Other Than Classrooms) Subtotal: \$530,318**

## Building: Main

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Plaster/Drywall	4,356	SF	6	\$26,972
	Ceiling - Splined	748	SF	6	\$2,161
	Doors - Wood Doors include hw	7	EA	6	\$2,107
	Drinking Fountains - Double Fountain	4	EA	6	\$1,344
	Floor - Terrazzo	748	SF	6	\$6,279

## Building: Main

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Floor - Tile/Sheet	4,356	SF	6	\$2,367
	Lighting - Lay-in	8	EA	6	\$952
	Lighting - Pendent/Surface	63	EA	6	\$7,805
	Student Lockers - One Tier	355	EA	6	\$32,957
	Walls - Plaster/Drywall	2,155	SF	6	\$9,553
	Walls - Structural Glazed Tile	5,317	SF	6	\$16,727
<b>Safety</b>					
	Camera Viewing Station	1	EA	6	\$683
	Security Cameras	8	EA	6	\$1,552
<b>Stairs</b>					
	Ceiling - Plaster/Drywall	1,502	SF	6	\$10,997
	Floor - Terrazzo	1,348	SF	6	\$11,315
	Handrails	256	LF	6	\$2,218
	Lighting - Lay-in	1	EA	6	\$119
	Lighting - Pendent/Surface	10	EA	6	\$1,239
	Stairs - Terrazzo	120	LF	6	\$1,114
	Walls - Concrete Block	1,534	SF	6	\$4,497
	Walls - Structural Glazed Tile	3,484	SF	6	\$10,961

**Building Interior Subtotal:** **\$153,918**

**Total Building Cost** **\$3,005,100**

## SITE

### Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Athletic</b>					
	Surface - Asphalt	6,532	SF	6	\$15,786
<b>Civil/Drainage</b>					
	Civil/ Drainage - Catch Basin	6	EA	6	\$6,563
<b>Fencing</b>					
	Fencing - Chain Link	20	LF	5	\$1,220
	Fencing - Chain Link	1,344	LF	6	\$25,235

## SITE

### Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Landscape</b>					
	Landscape - Grass	5,445	SF	6	\$4,516
	Parkway trees	13	EA	7	\$0
	Planting Beds/ Area	2,511	SF	6	\$4,129
	Play Area - Asphalt/ Hardscape	500	SF	4	\$5,298
	Play Area - Asphalt/ Hardscape	20,012	SF	5	\$91,289
<b>Parking Lot</b>					
	Surface - Asphalt	15,326	SF	6	\$37,038
<b>Playground</b>					
	Equipment - School Age 5-12	1	EA	6	\$3,546
	Surface - Poured Surface	2,298	SF	6	\$16,825
<b>Sidewalks</b>					
	Sidewalks - Internal Walks	66	LF	4	\$4,475
	Sidewalks - Internal Walks	41	LF	6	\$569
	Sidewalks - Perimeter Sidewalks	5,688	SF	6	\$11,306
<b>Signage</b>					
	Flag Pole - Flag Pole	1	EA	6	\$1,657
	Marquee - Free Standing Back Lighted	1	EA	6	\$0
	Monument - Building Mounted Cut Letter Sign	3	EA	6	\$0
<b>Site Subtotal:</b>					<b>\$229,452</b>
<b>Total Site Cost</b>					<b>\$229,452</b>

<b>Campus Total <sup>2 3</sup></b>	<b>\$3,234,552</b>
------------------------------------	--------------------

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
  - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
  - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Computer Lab	Computer Lab	2nd Floor	208	208	653	1	2	25	210	72	40	Y	Y	N
Kindergarten	Regular Classroom	1st Floor	103	103	813	1		6	136	37	40	N	Y	Y
Library	Kindergarten	1st Floor	108	108	1,121	1	2	6	315	108	40	Y	Y	N
Office	Regular Classroom	1st Floor	106	106	787	1	2	6	210	72	40	N	Y	N
Pre School	Kindergarten	1st Floor	110	110	1,080	1	2	6	175	56	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	100	100	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	101	101	787	1		6	136	37	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	102	102	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	104	104	787	1	2	6	210	72	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	200	200	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	201	201	813	1		6	136	37	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	202	202	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	204	204	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	206	206	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	207	207	787	1		6	136	37	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	209	209	813	1		6	136	37	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	210	210	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	212	212	787	1	2	6	210	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	214	214	787	1	2	6	136	37	40	N	Y	Y
Store Room	Regular Classroom	2nd Floor	203	203	813	1	2	6	136	37	40	N	Y	Y