

## Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1923	4	77,725	\$3,396,931
Branch	1960	3	38,925	\$1,567,089
SITE				\$438,241
<b>Campus Total</b>			<b>116,650</b>	<b>\$5,402,261</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	2	EA	6	\$1,403
	Exterior Doors - Exterior FRP Door	12	EA	6	\$7,577
	Exterior Doors - Exterior Steel Door	1	EA	4	\$3,823
	Exterior Doors - Exterior Steel Door	10	EA	6	\$4,806
	Exterior Doors - Exterior Wood Door	1	EA	5	\$1,341
	Exterior Doors - Transom Lite	21	EA	6	\$6,580
	Exterior Stairs - Concrete	12	LF	5	\$1,315
	Exterior Stairs - Concrete	88	LF	6	\$7,196
	Exterior Stairs - Steel or Aluminum	124	LF	6	\$477
	Stair Handrail - Steel_Stair Handrail	124	LF	6	\$1,075
<b>Fire Escape</b>					
	Fire Escape	100	LF	6	\$63,176
<b>Foundation</b>					
	Foundation - Concrete	56	LF	6	\$10,876
	Foundation - Concrete	650	LF	7	\$0
	Superstructure - Steel with Clay Tile Arch	77,725	SF	7	\$0

## Building: Main

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	14	EA	6	\$7,512
	Exterior Lighting - Wall Mounted	15	EA	6	\$4,331
<b>Roof System</b>					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	67	LF	6	\$63,964
	Coping - Metal	20	LF	6	\$642
	Coping - Stone	680	LF	6	\$21,840
	Coping - Terra Cotta	717	LF	6	\$23,028
	Downspouts - Exterior Downspouts	38	LF	6	\$1,263
	Downspouts - Interior Downspouts	994	LF	6	\$33,034
	Parapet - 16" - 30" Height	785	LF	6	\$31,364
	Parapet - Parapet < 16" Height	199	LF	6	\$4,240
	Parapet - Parapet > 30"	413	LF	6	\$26,399
	Roof - Modified Bitumen	12	SF	5	\$343
	Roof - Modified Bitumen	23,729	SF	6	\$223,276
	Roof Structure - Steel / Metal Deck/ Concrete Topping	169	SF	7	\$0
	Roof Structure - Steel with Clay Tile Arch	23,560	SF	7	\$0
<b>Walls</b>					
	Cornice - Masonry Projecting Limestone	468	LF	6	\$16,229
	Exterior Walls - Brick	43,255	SF	6	\$290,717
	Exterior Walls - Prefabricated Metal Panel Wall	1,045	SF	6	\$5,933
	Exterior Walls - Stone-Cast	2,850	SF	6	\$19,155
	Exterior Walls - Terra Cotta	60	SF	6	\$403
<b>Windows</b>					
	Clerestory - Glass Double-Pane	240	SF	6	\$2,248
	Guard - Guards perforated	2,100	SF	6	\$26,817
	Lintels - Brick	17	LF	6	\$0
	Lintels - Concrete	216	LF	6	\$0
	Lintels - Steel	224	LF	6	\$6,502
	Lintels - Stone	175	LF	6	\$0
	Windows - Sash Aluminum Double-pane	1,578	SF	5	\$85,004
	Windows - Sash Aluminum Double-pane	2,368	SF	6	\$17,676

**Building Exterior Subtotal:**

**\$1,021,564**

## Building: Main

## Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	2	EA	6	\$816
	Emergency A/C Power - Auditorium and Aisle Lighting	4,351	SF	6	\$2,302
	Emergency A/C Power - Corridors and Stairs	9,026	SF	6	\$2,711
	Emergency A/C Power - Gym	4,001	SF	6	\$1,488
	Emergency A/C Power - Students Toilets	840	SF	6	\$312
	Emergency Battery Packs - Auditorium and Aisle Lighting	6	EA	6	\$1,215
	Emergency Battery Packs - Corridors and Stairs	16	EA	6	\$3,240
	Emergency Battery Packs - Gym	5	EA	6	\$1,013
	Emergency Battery Packs - Pool	2	EA	6	\$405
	Emergency Generator- Outdoor- Natural Gas - Below 60 KW	1	EA	7	\$0
	Exit Signs - Auditorium	14	EA	6	\$2,096
	Exit Signs - Corridors and Stairs	22	EA	6	\$3,294
	Exit Signs - Gym	5	EA	6	\$787
	Exit Signs - Pool	3	EA	6	\$465
	Security System - CCTV	77,725	SF	6	\$23,341
	Security System - Intrusion Detection	77,725	SF	6	\$20,006
<b>Main Service</b>					
	Independent Electrical Service for emergency power	1	EA	7	\$0
	Main Electrical Service - 2000 A 120/208/3PH	1	EA	7	\$0
	PA System	77,725	SF	6	\$25,564
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	1	EA	7	\$0
	Lighting and Power Panels - Above 100 A	12	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	1	EA	7	\$0
	Main Distribution Panels - Less than 400 amp	1	EA	7	\$0

**Electrical System Subtotal:**
**\$89,055**

## Building: Main

### Category: Safety System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	77,725	SF	5	\$60,019
	Fire Alarm_System	77,725	SF	5	\$86,694

## Building: Main

### Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Safty System Subtotal:</b>					<b>\$153,119</b>

## Building: Main

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Handling Systems</b>					
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 15001-20000 cfm	1	EA	7	\$0
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 6000-10000 cfm	1	EA	7	\$0
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 12001-20000 cfm	1	EA	7	\$0
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 8001-12000 cfm	2	EA	7	\$0
	Air Intake	5	EA	7	\$0
	Auxiliaries - 12001-20000 cfm	1	EA	7	\$0
	Auxiliaries - 15001-20000 cfm	1	EA	7	\$0
	Auxiliaries - 6000-10000 cfm	1	EA	7	\$0
	Auxiliaries - 8001-12000 cfm	2	EA	7	\$0
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	3	EA	6	\$5,571
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	2	EA	6	\$3,714
	Zone Dampers	30	EA	6	\$24,991
<b>Boiler Systems</b>					
	Boiler Auxiliary- Steam Boiler - 50 - 75 HP	2	EA	6	\$4,093
	Chemical Feed System	1	EA	6	\$1,078
	Combustion Dampers	2	EA	6	\$818
	Condensate Pump	3	EA	6	\$6,063
	Feed Water Pumps and Tank	1	EA	6	\$2,545
	Non Condensing- Water Tube- Flexible Tube- Atmospheric- Steam Boiler - 50 - 75 HP	2	EA	6	\$1,996
	Piping - Condensate Pipe- Steel	400	LF	5	\$4,942
	Piping - Steam Pipe- Steel	400	LF	5	\$5,634
	Steam Traps	140	EA	5	\$184,086
<b>Heating Devices</b>					
	Cabinet Heaters - With Steam Coil	1	EA	6	\$357
	Fin Tube - Steam	20	LF	5	\$1,628
	Fin Tube - Steam	134	LF	6	\$1,265
	Radiators - Steam	1	EA	5	\$1,675
	Radiators - Steam	106	EA	6	\$29,447
	Unit Heater - Electric	4	EA	5	\$4,031
	Unit Heater - Steam	2	EA	6	\$556

## Building: Main

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Temperature Control</b>					
	DDC System	77,725	SF	6	\$44,459
	Thermostats - DDC	55	EA	6	\$0
<b>Unit Ventilation</b>					
	Unit Ventilators- Ceiling Mounted- Electric Heating & DX Cooling Coil W/ Self Contained Compressor	1	EA	6	\$1,248
<b>Ventilation</b>					
	Exhaust Fans- Indoor - 1501 - 8000 CFM	1	EA	6	\$592
	Exhaust Fans- Indoor - 500 - 1500 CFM	1	EA	4	\$4,245
	Exhaust Fans- Indoor - Less than 500 CFM	1	EA	6	\$296
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	1	EA	6	\$592
	Exhaust Fans- Roof Mounted - Less than 500 CFM	3	EA	6	\$889
	Roof Mounted Duct Work	30	LF	6	\$11,371
<b>Mechanical System Subtotal:</b>					<b>\$348,182</b>

## Building: Main

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - 300001 - 600000 BTU/HR	2	EA	6	\$620
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	77,725	SF	6	\$15,561
	Domestic Piping-Cold Water Horizontal Lines	77,725	SF	6	\$18,895
	Domestic Piping-Cold Water Risers	77,725	SF	6	\$14,449
	Domestic Piping-Hot Water from Risers to Fixtures	77,725	SF	6	\$12,226
	Domestic Piping-Hot Water Horizontal Lines	77,725	SF	6	\$14,449
	Domestic Piping-Hot Water Return Lines	77,725	SF	6	\$11,115
	Domestic Piping-Hot Water Return Risers	77,725	SF	6	\$11,115
	Sanitary Piping	77,725	SF	4	\$270,087
	Storm Piping	77,725	SF	4	\$268,975
	Vent Piping	77,725	SF	4	\$190,061
<b>Pumps</b>					
	Pumps - Ejector-Simplex	1	EA	6	\$745
	Pumps - Sump-Duplex	1	EA	6	\$1,387
	Pumps - Sump-Simplex	1	EA	5	\$5,627

## Building: Main

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Pumps</b>					
<b>Plumbing System Subtotal:</b>					<b>\$835,310</b>

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (1 room)</b>					
	Ceiling - Plaster/Drywall	350	SF	6	\$1,211
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	350	SF	4	\$3,008
	Lighting - Lay-in	7	EA	7	\$0
	Storage/ Closet	60	SF	6	\$435
	Walls - Plaster/Drywall	700	SF	6	\$1,932
<b>Carpentry (1 room)</b>					
	Ceiling - Plaster/Drywall	754	SF	6	\$2,609
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Floor - Tile	754	SF	6	\$1,650
	Lighting - Lay-in	6	EA	7	\$0
	Storage/ Closet	42	SF	6	\$305
	Walls - Plaster/Drywall	1,508	SF	6	\$4,162
<b>Computer Lab (1 room)</b>					
	AC Units	2	EA	6	\$991
	Ceiling - Lay-in	648	SF	6	\$1,946
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Floor - Tile	648	SF	6	\$1,418
	Lighting - Lay-in	8	EA	7	\$0
	Walls - Plaster/Drywall	1,080	SF	6	\$2,981
<b>Library (1 room)</b>					
	Ceiling - Plaster/Drywall	1,058	SF	6	\$3,661
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,058	SF	6	\$2,315
	Lighting - Lay-in	15	EA	7	\$0
	Storage/ Closet	72	SF	6	\$522
	Walls - Plaster/Drywall	1,986	SF	6	\$5,481

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Music Room (2 rooms)</b>					
	AC Units	1	EA	6	\$496
	Ceiling - Splined	1,687	SF	6	\$1,375
	Chalk Board	12	LF	4	\$1,102
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Carpet	1,687	SF	6	\$3,594
	Lighting - Pendent/Surface	22	EA	7	\$0
	Walls - Plaster/Drywall	2,024	SF	6	\$5,586
	Walls - Tile	247	SF	6	\$540
	Work Sink	1	EA	6	\$379
<b>Office (3 rooms)</b>					
	AC Units	1	EA	6	\$496
	Ceiling - Plaster/Drywall	1,343	SF	6	\$4,648
	Chalk Board	38	LF	4	\$3,489
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Tile	1,343	SF	6	\$2,938
	Lighting - Pendent/Surface	26	EA	7	\$0
	Marker Board	42	LF	6	\$900
	Walls - Plaster/Drywall	1,843	SF	6	\$5,086
<b>Regular Classroom (18 rooms)</b>					
	AC Units	13	EA	6	\$6,443
	AC Units	1	EA	7	\$0
	Casework	78	LF	6	\$1,970
	Ceiling - Lay-in	1,216	SF	6	\$3,652
	Ceiling - Plaster/Drywall	627	SF	5	\$5,747
	Ceiling - Plaster/Drywall	11,753	SF	6	\$40,672
	Chalk Board	33	LF	4	\$3,030
	Chalk Board	12	LF	6	\$268
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Doors - Wood Doors inclu hw	1	EA	4	\$3,413
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	10	EA	6	\$3,010
	Floor - Tile	824	SF	3	\$7,082
	Floor - Tile	1,473	SF	5	\$6,614
	Floor - Tile	10,467	SF	6	\$22,901
	Floor - Tile/Sheet	832	SF	6	\$833
	Lighting - Lay-in	12	EA	6	\$1,428

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Regular Classroom (18 rooms)</b>					
	Lighting - Lay-in	59	EA	7	\$0
	Lighting - Pendent/Surface	143	EA	7	\$0
	Marker Board	185	LF	6	\$3,963
	Storage/ Closet	285	SF	6	\$2,066
	Walls - Plaster/Drywall	1,272	SF	5	\$9,640
	Walls - Plaster/Drywall	19,981	SF	6	\$55,146
	Work Sink	7	EA	6	\$2,653
	Work Sink	1	EA	7	\$0
<b>Store Room (1 room)</b>					
	Ceiling - Plaster/Drywall	355	SF	6	\$1,229
	Chalk Board	3	LF	4	\$275
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	355	SF	6	\$777
	Lighting - Pendent/Surface	8	EA	7	\$0
	Marker Board	6	LF	6	\$129
	Storage/ Closet	70	SF	6	\$508
	Walls - Plaster/Drywall	410	SF	6	\$1,132
<b>Classrooms Subtotal:</b>					<b>\$257,026</b>

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	AC Unit	4	EA	6	\$1,982
	Ceiling - Plaster/Drywall	1,817	SF	5	\$16,655
	Ceiling - Plaster/Drywall	1,283	SF	6	\$4,440
	Doors - Steel Doors incl hw	3	EA	6	\$903
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Tile	864	SF	5	\$3,880
	Floor - Tile	2,236	SF	6	\$4,892
	Lighting - Lay-in	4	EA	7	\$0
	Lighting - Pendent/Surface	5	EA	6	\$619
	Lighting - Pendent/Surface	27	EA	7	\$0
	Power Distribution	24	EA	6	\$50,997
	Walls - Plaster/Drywall	370	SF	5	\$2,804



## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Walls - Plaster/Drywall	3,506	SF	6	\$9,676
	Work Sink	1	EA	6	\$508
<b>Auditorium &amp; Theater</b>					
	Balcony Seating	150	EA	6	\$26,087
	Ceiling - Plaster/Drywall	4,351	SF	6	\$36,274
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Concrete	2,176	SF	6	\$1,151
	Floor - Tile	2,176	SF	6	\$4,761
	Lighting - Chandelier, Incandescent	1	EA	7	\$0
	Lighting - Pendent/Surface	9	EA	6	\$1,115
	Main Floor Seating	434	EA	6	\$75,480
	Sound System	1	EA	6	\$10,721
	Stage	806	SF	6	\$4,656
	Stage Curtain	8	EA	6	\$0
	Stage Lighting System	1	EA	6	\$8,077
	Stage-Stairs - Wood	8	LF	6	\$94
	Stairs - Wood	6	LF	6	\$70
	Walls - Plaster/Drywall	5,004	SF	6	\$24,884
<b>Gymnasia</b>					
	Ceiling - Plaster/Drywall	4,001	SF	6	\$22,085
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Floor - Wood	4,001	SF	6	\$28,207
	Lighting - Metal Halide/ High Pressure Sodium	15	EA	7	\$0
	Scoreboards	1	EA	5	\$10,580
	Walls - Structural Glazed Tile	4,601	SF	6	\$14,475
<b>MDF_IDF</b>					
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Finishes	203	SF	5	\$3,277
<b>Mechanical/ Service Rooms</b>					
	Air Tunnel	1,355	SF	6	\$8,390
	Boiler Room	1,440	SF	6	\$10,317
	Janitor's Closet	172	SF	6	\$1,232
	Mechanical/ Service Rooms	2,707	SF	6	\$19,394
	Storage Room	3,632	SF	6	\$26,021

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Restroom</b>					
	Accessories	1,315	SF	6	\$12,129
	Ceiling - Lay-in	420	SF	6	\$1,261
	Ceiling - Plaster/Drywall	255	SF	5	\$2,337
	Ceiling - Plaster/Drywall	640	SF	6	\$2,215
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Tile Ceramic/ Porcelain	220	SF	4	\$6,154
	Floor - Tile Ceramic/ Porcelain	255	SF	5	\$4,073
	Floor - Tile Ceramic/ Porcelain	840	SF	6	\$1,778
	Hand Dryer	6	EA	6	\$1,380
	Lavatory	25	EA	6	\$7,990
	Lighting - Lay-in	3	EA	6	\$357
	Lighting - Pendent/Surface	5	EA	6	\$619
	Lighting - Pendent/Surface	4	EA	7	\$0
	Partitions	19	EA	6	\$5,642
	Urinals	2	EA	5	\$2,688
	Urinals	11	EA	6	\$3,696
	Walls - Plaster/Drywall	1,512	SF	6	\$4,367
	Water Closet	19	EA	6	\$6,384

### Rooms (Other Than Classrooms) Subtotal:

**\$506,202**

## Building: Main

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Lay-in	4,528	SF	6	\$13,598
	Ceiling - Plaster/Drywall	14	SF	3	\$424
	Ceiling - Plaster/Drywall	2,942	SF	6	\$18,217
	Drinking Fountains - Single Fountain	12	EA	6	\$3,309
	Floor - Terrazzo	7,206	SF	6	\$60,488
	Lighting - Lay-in	4	EA	7	\$0
	Lighting - Pendent/Surface	85	EA	7	\$0
	Stairs - Concrete Stairs	18	LF	6	\$149
	Walls - Plaster/Drywall	8,231	SF	6	\$36,488
<b>Safety</b>					
	Camera Viewing Station	3	EA	6	\$2,048

## Building: Main

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Safety</b>					
	Security Cameras	23	EA	6	\$4,463
<b>Stairs</b>					
	Ceiling - Plaster/Drywall	2,365	SF	6	\$17,316
	Floor - Terrazzo	2,365	SF	6	\$19,852
	Handrails	424	LF	6	\$3,674
	Lighting - Pendent/Surface	18	EA	7	\$0
	Stairs - Terrazzo	238	LF	6	\$2,209
	Walls - Plaster/Drywall	1,536	SF	6	\$4,239

**Building Interior Subtotal: \$186,473**

**Total Building Cost \$3,396,931**

## Building: Branch

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	1	EA	6	\$702
	Exterior Doors - Exterior Steel Door	14	EA	6	\$6,728
	Exterior Doors - Side lite	7	EA	6	\$2,193
	Exterior Doors - Transom Lite	1	EA	4	\$2,007
	Exterior Doors - Transom Lite	10	EA	6	\$3,133
	Exterior Stairs - Concrete	48	LF	6	\$3,925
	Ramp Handrail - Steel_Ramp Handrail	36	LF	6	\$312
	Ramps - Concrete	18	LF	6	\$2,704
<b>Foundation</b>					
	Foundation - Concrete	610	LF	7	\$0
	Superstructure - Concrete	38,925	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	2	EA	6	\$1,073
	Exterior Lighting - Wall Mounted	6	EA	6	\$1,732
<b>Roof System</b>					
	Chimney - Metal Flue	14	LF	6	\$2,214
	Coping - Metal	713	LF	6	\$22,900

## Building: Branch

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Roof System</b>					
	Coping - Stone	36	LF	6	\$1,156
	Downspouts - Interior Downspouts	122	LF	6	\$4,054
	Parapet - 16" - 30" Height	36	LF	6	\$1,438
	Parapet - Parapet < 16" Height	681	LF	6	\$14,510
	Roof - Modified Bitumen	11,002	SF	5	\$231,430
	Roof - Modified Bitumen	6,052	SF	6	\$56,946
	Roof Structure - Concrete	17,054	SF	7	\$0
<b>Walls</b>					
	Canopy - Metal	32	SF	6	\$687
	Exterior Walls - Brick	13,250	SF	6	\$89,053
<b>Windows</b>					
	Curtain wall - Glazed Double Pane	4,850	SF	6	\$54,374
	Curtain wall - Insulated Panel	2,012	SF	6	\$22,557
	Guard - Guards perforated	2,240	SF	6	\$28,605
	Lintels - Steel	988	LF	6	\$28,681
	Windows - Sash Aluminum Double-pane	36	SF	5	\$1,939
	Windows - Sash Aluminum Double-pane	684	SF	6	\$5,106

### Building Exterior Subtotal:

**\$590,160**

## Building: Branch

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Corridors and Stairs	9,044	SF	6	\$2,716
	Emergency A/C Power - Lunchrooms	2,536	SF	6	\$943
	Emergency A/C Power - Students Toilets	1,227	SF	6	\$456
	Emergency Battery Packs - Corridors and Stairs	18	EA	6	\$3,645
	Emergency Battery Packs - Lunchrooms	4	EA	6	\$810
	Emergency Battery Packs - Students Toilets	7	EA	6	\$1,418
	Exit Signs - Corridors and Stairs	10	EA	7	\$0
	Exit Signs - Lunchroom	2	EA	7	\$0
	Security System - CCTV	38,925	SF	6	\$11,689
	Security System - Intrusion Detection	38,925	SF	6	\$10,019

## Building: Branch

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Main Service</b>					
	Independent Electrical Service for emergency power	1	EA	7	\$0
	Main Electrical Service - 1600 A 120/208/3PH	1	EA	7	\$0
	PA System	38,925	SF	6	\$12,802
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	3	EA	7	\$0
	Lighting and Power Panels - Above 100 A	10	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	1	EA	7	\$0

### Electrical System Subtotal:

**\$44,907**

## Building: Branch

### Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	4	\$49,477
	Fire Alarm Strobe Lights	38,925	SF	4	\$52,880
	Fire Alarm_System	38,925	SF	4	\$77,371

### Safty System Subtotal:

**\$179,727**

## Building: Branch

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Heat Pump- Floor Mounted- Electric Heating & DX Cooling- Self Contained Air Cooled Compressor - Less than 3 tons	1	EA	6	\$1,405
<b>Boiler Systems</b>					
	Boiler Auxiliary- Steam Boiler - Less than 50 HP	2	EA	6	\$4,093
	Chemical Feeder	1	EA	6	\$1,078
	Combustion Dampers	2	EA	6	\$818
	Condensate Pump	2	EA	6	\$4,042
	Feed Water Pumps and Tank	1	EA	6	\$2,545
	Non Condensing- Water Tube- Flexible Tube- Atmospheric- Steam Boiler - Less than 50 HP	2	EA	6	\$1,996
	Piping - Condensate Pipe- Steel	100	LF	6	\$189
	Piping - Steam Pipe- Steel	200	LF	6	\$378

## Building: Branch

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Boiler Systems</b>					
	Steam Traps	150	EA	6	\$39,622
	Vacuum Pump	1	EA	6	\$2,471
<b>Heating Devices</b>					
	Cabinet Heaters - With Steam Coil	7	EA	4	\$26,959
	Fin Tube - Steam	750	LF	6	\$7,079
	Unit Heater - Electric	1	EA	6	\$278
	Wall Heater - Electric	1	EA	6	\$139
<b>Temperature Control</b>					
	DDC System	77,725	SF	6	\$44,459
	Thermostats - DDC	1	EA	4	\$819
	Thermostats - DDC	23	EA	6	\$0
<b>Unit Ventilation</b>					
	Unit Ventilators- Floor Mounted- Steam Heating Coils Only	2	EA	4	\$39,985
	Unit Ventilators- Floor Mounted- Steam Heating Coils Only	25	EA	6	\$31,193
<b>Ventilation</b>					
	Exhaust Fans- Indoor - Less than 500 CFM	2	EA	6	\$592
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	3	EA	6	\$1,777
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	1	EA	6	\$592
	Exhaust Fans- Roof Mounted - Less than 500 CFM	1	EA	6	\$296
	Type I Exhaust Hood- Kitchen	1	EA	6	\$1,248
<b>Mechanical System Subtotal:</b>					<b>\$214,053</b>

## Building: Branch

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - 150000 - 300000 BTU/HR	1	EA	6	\$310
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	38,925	SF	6	\$7,793
	Domestic Piping-Cold Water Horizontal Lines	38,925	SF	6	\$9,463
	Domestic Piping-Cold Water Risers	38,925	SF	6	\$7,236
	Domestic Piping-Hot Water from Risers to Fixtures	38,925	SF	6	\$6,123
	Domestic Piping-Hot Water Horizontal Lines	38,925	SF	6	\$7,236

## Building: Branch

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Piping					
	Domestic Piping-Hot Water Return Lines	38,925	SF	6	\$5,566
	Domestic Piping-Hot Water Return Risers	38,925	SF	6	\$5,566
	Sanitary Piping	38,925	SF	6	\$35,624
	Storm Piping	38,925	SF	6	\$33,954
	Vent Piping	38,925	SF	6	\$26,161
<b>Plumbing System Subtotal:</b>					<b>\$145,033</b>

## Building: Branch

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Computer Lab (1 room)					
	AC Units	1	EA	6	\$496
	Ceiling - Splined	775	SF	6	\$632
	Chalk Board	12	LF	6	\$268
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	16	SF	6	\$271
	Floor - Tile	775	SF	6	\$1,696
	Lighting - Pendent/Surface	20	EA	7	\$0
	Marker Board	12	LF	6	\$257
	Storage/ Closet	36	SF	6	\$261
	Walls - Concrete Block	670	SF	6	\$1,964
Kindergarten (3 rooms)					
	AC Units	2	EA	6	\$991
	AC Units	2	EA	7	\$0
	Ceiling - Splined	2,720	SF	6	\$2,217
	Chalk Board	12	LF	4	\$1,102
	Chalk Board	16	LF	6	\$357
	Doors - Side-lite	14	SF	6	\$234
	Doors - Transom Window	16	SF	6	\$271
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile	2,720	SF	6	\$5,951
	Lighting - Pendent/Surface	64	EA	7	\$0
	Marker Board	48	LF	6	\$1,028
	Storage/ Closet	40	SF	6	\$290
	Walls - Concrete Block	2,685	SF	6	\$7,871

## Building: Branch

## Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Pre School (1 room)</b>					
	AC Units	2	EA	6	\$991
	Ceiling - Splined	1,417	SF	6	\$1,155
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	1,417	SF	6	\$3,100
	Lighting - Pendent/Surface	34	EA	7	\$0
	Marker Board	22	LF	6	\$471
	Storage/ Closet	48	SF	6	\$348
	Walls - Concrete Block	1,518	SF	6	\$4,450
<b>Regular Classroom (13 rooms)</b>					
	AC Units	11	EA	6	\$5,451
	AC Units	2	EA	7	\$0
	Casework	32	LF	6	\$808
	Ceiling - Splined	10,075	SF	6	\$8,212
	Chalk Board	48	LF	4	\$4,407
	Chalk Board	14	LF	6	\$312
	Doors - Side-lite	140	SF	6	\$2,340
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Doors - Transom Window	207	SF	6	\$3,505
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Floor - Tile	10,075	SF	6	\$22,043
	Lighting - Pendent/Surface	260	EA	7	\$0
	Marker Board	200	LF	6	\$4,284
	Storage/ Closet	236	SF	6	\$1,711
	Walls - Concrete Block	9,255	SF	6	\$27,131
	Walls - Structural Glazed Tile	670	SF	6	\$2,108
<b>Store Room (2 rooms)</b>					
	AC Units	2	EA	6	\$991
	Casework	6	LF	6	\$152
	Ceiling - Splined	1,550	SF	6	\$1,263
	Chalk Board	12	LF	4	\$1,102
	Chalk Board	12	LF	6	\$268
	Doors - Side-lite	14	SF	6	\$234
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	32	SF	6	\$542
	Doors - Wood Doors inclu hw	1	EA	6	\$301



## Building: Branch

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Store Room (2 rooms)</b>					
	Floor - Tile	1,550	SF	6	\$3,391
	Lighting - Pendent/Surface	40	EA	7	\$0
	Marker Board	28	LF	6	\$600
	Storage/ Closet	40	SF	6	\$290
	Walls - Concrete Block	1,561	SF	6	\$4,576

### Classrooms Subtotal:

**\$138,565**

## Building: Branch

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	AC Unit	1	EA	6	\$496
	Ceiling - Exposed	142	SF	6	\$211
	Ceiling - Lay-in	1,470	SF	6	\$4,414
	Ceiling - Splined	183	SF	6	\$149
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile	1,795	SF	6	\$3,927
	Lighting - Lay-in	30	EA	7	\$0
	Lighting - Pendent/Surface	6	EA	7	\$0
	Power Distribution	8	EA	6	\$16,999
	Storage/ Closet	352	SF	6	\$2,552
	Walls - Concrete Block	2,436	SF	6	\$7,141

### Kitchen

	Ceiling - Splined	576	SF	6	\$469
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	576	SF	6	\$1,260
	Lighting - Pendent/Surface	15	EA	7	\$0
	Storage/ Closet	423	SF	6	\$3,067
	Walls - Structural Glazed Tile	662	SF	6	\$2,083

### Lunch & Multipurpose Room

	Ceiling - Plaster/Drywall	257	SF	6	\$889
	Ceiling - Splined	3,355	SF	6	\$2,735
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Tile	3,612	SF	6	\$7,903
	Lighting - Pendent/Surface	34	EA	7	\$0

## Building: Branch

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Lunch &amp; Multipurpose Room</b>					
	Serving Line	44	LF	6	\$2,619
	Storage/ Closet	175	SF	6	\$1,269
	Walls - Concrete Block	2,187	SF	6	\$6,411
	Walls - Structural Glazed Tile	2,002	SF	6	\$6,298
<b>MDF_IDF</b>					
	AC Unit	1	EA	6	\$496
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Finishes	143	SF	6	\$1,020
<b>Mechanical/ Service Rooms</b>					
	Boiler Room	425	SF	6	\$3,045
	Janitor's Closet	127	SF	6	\$910
	Mechanical/ Service Rooms	80	SF	6	\$573
<b>Restroom</b>					
	Accessories	1,462	SF	6	\$13,485
	Ceiling - Lay-in	1,303	SF	6	\$3,913
	Ceiling - Splined	159	SF	6	\$130
	Doors - Wood Doors inclu hw	11	EA	6	\$3,311
	Floor - Tile Ceramic/ Porcelain	1,462	SF	6	\$3,094
	Floor Drain	1	EA	6	\$1,059
	Lavatory	16	EA	6	\$5,114
	Lighting - Lay-in	12	EA	7	\$0
	Lighting - Pendent/Surface	3	EA	6	\$372
	Lighting - Pendent/Surface	2	EA	7	\$0
	Lighting - Wall Mounted	1	EA	6	\$124
	Partitions	26	EA	6	\$7,720
	Student Lockers - One Tier	11	EA	6	\$1,021
	Urinals	7	EA	6	\$2,352
	Walls - Structural Glazed Tile	1,682	SF	6	\$5,292
	Water Closet	28	EA	6	\$9,407
<b>Rooms (Other Than Classrooms) Subtotal:</b>					<b>\$136,339</b>

## Building: Branch

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
-------	-------------	----------	------	------	------

## Building: Branch

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Splined	7,466	SF	6	\$21,566
	Doors - Wood Doors include hw	10	EA	6	\$3,010
	Drinking Fountains - Single Fountain	6	EA	6	\$1,654
	Floor - Tile/Sheet	7,466	SF	6	\$4,057
	Lighting - Pendent/Surface	19	EA	6	\$2,354
	Lighting - Pendent/Surface	40	EA	7	\$0
	Student Lockers - One Tier	258	EA	6	\$23,952
	Walls - Structural Glazed Tile	8,586	SF	6	\$27,012
<b>Safety</b>					
	Camera Viewing Station	1	EA	6	\$683
	Security Cameras	18	EA	6	\$3,493
<b>Stairs</b>					
	Ceiling - Splined	1,578	SF	6	\$4,558
	Floor - Terrazzo	1,578	SF	6	\$13,246
	Handrails	360	LF	6	\$3,120
	Lighting - Pendent/Surface	36	EA	7	\$0
	Stairs - Terrazzo	168	LF	6	\$1,559
	Walls - Masonry	1,278	SF	6	\$4,021
	Walls - Tile Ceramic/ Porcelain	1,278	SF	6	\$4,021
<b>Building Interior Subtotal:</b>					<b>\$118,304</b>

## Total Building Cost

**\$1,567,089**

## SITE

### Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Civil/Drainage</b>					
	Civil/ Drainage - Catch Basin	5	EA	6	\$5,469
	Civil/ Drainage - Site Drain	2	EA	6	\$621
	Civil/ Drainage - Site Manhole	17	EA	6	\$25,377
<b>Fencing</b>					
	Fencing - Chain Link	131	LF	6	\$2,460
	Fencing - New Standard Ornamental	906	LF	6	\$28,904
	Fencing - Wood Fencing w/ Steel Frame	666	LF	5	\$52,714

**SITE**
**Category: Site**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fencing</b>					
<b>Landscape</b>					
	Benches	15	EA	6	\$6,451
	Landscape - Grass	16,606	SF	6	\$13,773
	Landscape - Hardscape- Concrete	3,550	SF	6	\$18,326
	Parkway trees	28	EA	6	\$18,481
	Planting Beds/ Area	15,355	SF	6	\$25,251
	Play Area - Asphalt/ Hardscape	9,800	SF	6	\$23,684
	Retaining Wall - Concrete	530	SF	6	\$12,422
<b>Parking Lot</b>					
	Concrete Curbs	566	LF	6	\$7,268
	Surface - Asphalt	17,404	SF	6	\$42,060
	Trash Enclosure - Wood	601	SF	6	\$13,768
<b>Playground</b>					
	Equipment - Combo 3-12	1	EA	6	\$7,092
	Surface - Poured Surface	906	SF	6	\$6,633
<b>Sidewalks</b>					
	Sidewalks - Internal Walks	265	LF	6	\$3,183
	Sidewalks - Perimeter Sidewalks	17,550	SF	5	\$123,475
<b>Signage</b>					
	Flag Pole - Building Mounted Flag Pole	1	EA	6	\$828
	Marquee - Free Standing Back Lighted	1	EA	6	\$0
	Monument - Building Mounted Cut Letter Sign	1	EA	6	\$0
<b>Site Subtotal:</b>					<b>\$438,241</b>
<b>Total Site Cost</b>					<b>\$438,241</b>

<b>Campus Total <sup>2 3</sup></b>	<b>\$5,402,261</b>
------------------------------------	--------------------

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Art Room	Basement	01	01	350	0	5	8	0	0	40	N	N	N
Carpentry	Regular Classroom	Basement	02	02	754	0	0	0	0	0	40	N	N	N
Computer Lab	Regular Classroom	4th Floor	422	402	648	1	1	20	18	18	40	N	N	N
Library	Regular Classroom	1st Floor	122	102	1,058	4	12	20	120	50	40	N	N	N
Music Room	Regular Classroom	3rd Floor	327	307	827	1	0	8	129	64	40	N	N	N
Music Room	Music Room	3rd Floor	Music Room	NA	860	0	1	4	0	0	40	N	N	N
Office	Regular Classroom	2nd Floor	229	208	484	0	0	4	96	12	40	N	Y	N
Office	Regular Classroom	3rd Floor	324	304	375	1	1	7	18	3	40	N	Y	N
Office	Regular Classroom	3rd Floor	329	309	484	0	0	4	96	12	40	N	Y	N
Regular Classroom	Regular Classroom	Basement	03	03	1,188	0	0	0	0	0	40	N	N	N
Regular Classroom	Regular Classroom	Basement	04	04	824				188			N	N	N
Regular Classroom	Regular Classroom	1st Floor	121	101	905	0	0	4	72	36	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	123	103	964	1	0	4	72	36	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	221	201	832	0	0	38	132	66	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	222	202	780	1	2	15	84	12	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	223	203	768	1	1	12	84	12	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	224	204	774	1	1	7	54	3	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	225	205	488	5	1	10	117	12	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	226	206	545	0	0	10	144	18	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	227	207	790	1	1	6	72	9	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	321	301	627	1	1	13	84	6	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	322	302	768	0	0	4	174	6	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	323	303	763	1	2	4	72	9	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	325	305	761	5	1	10	18	12	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	326	306	568	1	2	10	69	6	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	330	310	603	1	2	8	56	9	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	421	401	648	1	1	20	18	18	40	N	N	N
Store Room	Regular Classroom	3rd Floor	328	308	355	1	0	8	20	10	40	N	N	N

## Branch

Computer Lab	Regular Classroom	3rd Floor	318	318	775	1	1	38	110	103	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	117	117	1,170	0	0	8	210	105	40	N	Y	N
Kindergarten	Regular Classroom	1st Floor	118	118	775	1	1	38	110	103	40	N	Y	N
Kindergarten	Kindergarten	2nd Floor	212	212	775	1	1	8	110	103	40	N	Y	N
Pre School	Pre School	1st Floor	112	112	1,417	0	0	0	94	47	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	116	116	775	1	1	38	110	103	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	214	214	775	1	1	38	110	103	40	N	Y	Y

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Branch</b>														
Regular Classroom	Regular Classroom	2nd Floor	215	215	775	1	1	8	207	103	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	216	216	775	1	1	8	110	103	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	217	217	775	1	1	8	207	103	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	218	218	775	1	1	8	110	103	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	220	220	775	1	1	8	110	103	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	312	312	775	1	1	8	110	103	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	314	314	775	1	1	8	110	103	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	315	315	775	1	1	8	207	103	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	316	316	775	1	1	76	110	103	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	317	317	775	1	1	8	207	103	40	N	Y	N
Regular Classroom	Special Program	3rd Floor	319	319	775	1	1	8	207	103	40	N	Y	N
Store Room	Regular Classroom	2nd Floor	219	219	775	1	1	8	207	103	40	N	Y	N
Store Room	Regular Classroom	3rd Floor	320	320	775	1	1	8	110	103	40	N	Y	N