

## Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1926	2	63,800	\$2,775,294
Addition	1998	3	65,153	\$2,488,642
SITE				\$608,798
<b>Campus Total</b>			<b>128,953</b>	<b>\$5,872,734</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Exterior Doors - Exterior Steel Door	15	EA	6	\$7,208
	Exterior Doors - Transom Lite	11	EA	6	\$3,446
	Exterior Stairs - Concrete	60	LF	5	\$6,575
	Exterior Stairs - Concrete	106	LF	6	\$8,667
	Exterior Stairs - Stone	72	LF	5	\$19,524
	Exterior Stairs - Stone	60	LF	6	\$6,779
	Ramp Handrail - Steel_Ramp Handrail	100	LF	6	\$867
	Ramps - Concrete	50	LF	6	\$7,512
	Stair Handrail - Steel_Stair Handrail	120	LF	6	\$1,040
<b>Foundation</b>					
	Foundation - Concrete	1,370	LF	7	\$0
	Superstructure - Steel with Clay Tile Arch	63,800	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	16	EA	6	\$8,585
	Exterior Lighting - Wall Mounted	18	EA	6	\$5,197
<b>Roof System</b>					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	55	LF	6	\$52,508

**Building: Main**
**Category: Building Exterior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Roof System</b>					
	Coping - Terra Cotta	1,179	LF	6	\$37,867
	Downspouts - Interior Downspouts	356	LF	6	\$11,831
	Parapet - 16" - 30" Height	697	LF	6	\$27,848
	Parapet - Parapet > 30"	482	LF	6	\$30,810
	Roof - Metal	520	SF	5	\$14,329
	Roof - Modified Bitumen	31,974	SF	6	\$300,856
	Roof Structure - Steel with Clay Tile Arch	31,974	SF	7	\$0
<b>Walls</b>					
	Cheek-Wall - Concrete	65	SF	5	\$1,533
	Exterior Walls - Brick	38,908	SF	6	\$261,501
	Exterior Walls - Terra Cotta	4,500	SF	6	\$30,245
<b>Windows</b>					
	Guard - Guards perforated	4,266	SF	6	\$54,476
	Lintels - Steel	1,044	LF	6	\$30,306
	Windows - Sash Aluminum Double-pane	427	SF	5	\$23,002
	Windows - Sash Aluminum Double-pane	8,532	SF	6	\$63,688

**Building Exterior Subtotal:**
**\$1,016,200**
**Building: Main**
**Category: Electrical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	3	EA	7	\$0
	Emergency A/C Power - Auditorium and Aisle Lighting	2,319	SF	6	\$1,227
	Emergency A/C Power - Corridors and Stairs	11,260	SF	6	\$3,381
	Emergency A/C Power - Gym	2,776	SF	6	\$1,032
	Emergency A/C Power - Students Toilets	2,445	SF	6	\$909
	Emergency Battery Packs - Auditorium and Aisle Lighting	4	EA	6	\$810
	Emergency Battery Packs - Corridors and Stairs	3	EA	6	\$608
	Emergency Battery Packs - Gym	3	EA	6	\$608
	Emergency Generator- Outdoor- Natural Gas - 101 - 150 KW	1	EA	7	\$0
	Exit Signs - Auditorium	9	EA	7	\$0
	Exit Signs - Corridors and Stairs	20	EA	7	\$0
	Exit Signs - Gym	2	EA	7	\$0
	Security System - Intrusion Detection	63,800	SF	6	\$16,422

**Building: Main**
**Category: Electrical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
<b>Main Service</b>					
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	1	EA	6	\$10,867
	PA System	63,800	SF	6	\$20,984
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	4	EA	4	\$19,397
	Lighting and Power Panels - 100 A	1	EA	6	\$299
	Lighting and Power Panels - 100 A	3	EA	7	\$0
	Lighting and Power Panels - Above 100 A	5	EA	4	\$32,889
	Lighting and Power Panels - Above 100 A	2	EA	6	\$994
	Lighting and Power Panels - Above 100 A	11	EA	7	\$0
	Main Distribution Panels - 400 - 600 amp	3	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	2	EA	7	\$0
	Main Distribution Panels - Less than 400 amp	1	EA	7	\$0
	Transformers - 277/480 - 120/208	1	EA	7	\$0
<b>Electrical System Subtotal:</b>					<b>\$110,427</b>

**Building: Main**
**Category: Safty System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	63,800	SF	6	\$22,809
	Fire Alarm_System	63,800	SF	6	\$31,020
<b>Safty System Subtotal:</b>					<b>\$60,234</b>

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Chemical Pot Feeder	1	EA	6	\$725
	Chiller-Air Cooled-Scroll Type-Roof Mounted - 101 - 150 tons	1	EA	6	\$4,314
	Glycol Feed	1	EA	6	\$490
	Pipes - Chilled Water Pipe- Galvanized	150	LF	7	\$0

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Pipes - Dual Temperature Pipe- Galvanized	1,200	LF	7	\$0
	Pressure Fill System	1	EA	6	\$1,405
<b>Air Handling Systems</b>					
	Air Handling Unit- Built Up- Single Zone- Daul Temperature Coils - 4000 - 8000 cfm	2	EA	6	\$6,642
	Air Handling Unit- Built Up- Single Zone w/ Air Tunnel- Daul Temperature Coils - 15001 - 25000 cfm	2	EA	6	\$11,575
	Air Intake	4	EA	6	\$23,059
	Auxiliaries - 15001 - 25000 cfm	2	EA	6	\$11,575
	Auxiliaries - 4000 - 8000 cfm	2	EA	6	\$6,642
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	2	EA	6	\$3,714
	Outdoor Return Fans- inline Centrifugal - 10001 - 20000 CFM	2	EA	6	\$3,181
	Reheat Boxes - Reheat Boxes with Hot Water Coil	13	EA	7	\$0
	Return Duct Work - Indoor- Vertical Shaft and Ducts	280	LF	7	\$0
	Zone Dampers	32	EA	6	\$26,657
<b>Boiler Systems</b>					
	Boiler Auxiliary- Condensing Hot Water - 1001 - 2000 HP	2	EA	7	\$0
	Chemical Pot Feeder	1	EA	7	\$0
	Combustion Dampers	2	EA	7	\$0
	Condensing- Hot Water Boiler - 1001 - 2000 MBH	2	EA	7	\$0
	Glycol Feed System	1	EA	7	\$0
	Water Fill System	1	EA	7	\$0
<b>Heating Devices</b>					
	Cabinet Heaters - With Hot Water Coil	5	EA	6	\$1,772
	Fin Tube - Hot Water	63	LF	6	\$595
	Unit Heater - Electric	1	EA	5	\$1,008
	Unit Heater - Electric	9	EA	6	\$2,500
	Unit Heater - Hot Water	1	EA	6	\$279
	Wall Heater - Electric	5	EA	6	\$695
<b>Mechanical Plumbing</b>					
	Daul Temperature Pump - 10 - 20 HP	2	EA	6	\$2,485
	Hot Water Pump - Less than 10	4	EA	6	\$4,445
	Hydronic Supply and Return - Galvanized	150	LF	7	\$0
<b>Temperature Control</b>					
	DDC System	63,800	SF	5	\$104,919
	Thermostats - DDC	48	EA	6	\$0

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Temperature Control</b>					
<b>Ventilation</b>					
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	2	EA	7	\$0
	Exhaust Fans- Roof Mounted - Less than 500 CFM	1	EA	7	\$0
	Roof Mounted Duct Work	100	LF	7	\$0

**Mechanical System Subtotal:** **\$218,676**

**Building: Main**
**Category: Plumbing System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - 150000 - 300000 BTU/HR	2	EA	7	\$0
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	63,800	SF	6	\$12,773
	Domestic Piping-Cold Water Horizontal Lines	63,800	SF	6	\$15,510
	Domestic Piping-Cold Water Risers	63,800	SF	6	\$11,860
	Domestic Piping-Hot Water from Risers to Fixtures	63,800	SF	6	\$10,036
	Domestic Piping-Hot Water Horizontal Lines	63,800	SF	6	\$11,860
	Domestic Piping-Hot Water Return Lines	63,800	SF	6	\$9,123
	Domestic Piping-Hot Water Return Risers	63,800	SF	6	\$9,123
	Sanitary Piping	63,800	SF	6	\$58,390
	Storm Piping	63,800	SF	6	\$55,653
	Vent Piping	63,800	SF	6	\$42,880

<b>Pumps</b>					
	Pumps - Sump-Duplex	1	EA	6	\$1,387

**Plumbing System Subtotal:** **\$238,595**

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Computer Lab (1 room)</b>					
	AC Units	2	EA	5	\$3,652
	Casework	14	LF	6	\$354
	Ceiling - Plaster/Drywall	724	SF	6	\$2,505

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Computer Lab (1 room)</b>					
	Chalk Board	25	LF	4	\$2,295
	Doors - Transom Window	8	SF	6	\$135
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	724	SF	6	\$5,104
	Lighting - Pendent/Surface	12	EA	7	\$0
	Marker Board	24	LF	6	\$514
	Walls - Plaster/Drywall	1,229	SF	6	\$3,392
<b>Regular Classroom (19 rooms)</b>					
	AC Units	2	EA	5	\$3,652
	Casework	281	LF	6	\$7,096
	Ceiling - Lay-in	724	SF	6	\$2,174
	Ceiling - Plaster/Drywall	13,705	SF	6	\$47,428
	Chalk Board	85	LF	4	\$7,804
	Doors - Transom Window	164	SF	6	\$2,777
	Doors - Wood Doors inclu hw	18	EA	6	\$5,418
	Floor - Tile/Sheet	750	SF	6	\$751
	Floor - Wood	13,679	SF	6	\$96,436
	Lighting - Metal Halide/Sodium Vapor	12	EA	6	\$1,605
	Lighting - Pendent/Surface	48	EA	6	\$5,947
	Lighting - Pendent/Surface	172	EA	7	\$0
	Marker Board	390	LF	6	\$8,354
	Walls - Metal Panel	366	SF	6	\$2,732
	Walls - Plaster/Drywall	21,619	SF	6	\$59,666
	Walls - Side-lite	64	SF	6	\$1,070
	Walls - Structural Glazed Tile	1	SF	5	\$51
	Walls - Structural Glazed Tile	3,687	SF	6	\$11,599
	Work Sink	1	EA	6	\$379
<b>Vacant (1 room)</b>					
	Ceiling - Plaster/Drywall	1	SF	5	\$12
	Ceiling - Plaster/Drywall	698	SF	6	\$2,415
	Chalk Board	20	LF	4	\$1,836
	Doors - Transom Window	1	SF	6	\$17
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Wood	699	SF	6	\$4,928
	Lighting - Pendent/Surface	12	EA	7	\$0
	Marker Board	16	LF	6	\$343

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Vacant (1 room)</b>					
	Walls - Plaster/Drywall	1,210	SF	6	\$3,528

**Classrooms Subtotal:** **\$298,677**

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	AC Unit	2	EA	5	\$3,652
	Ceiling - Plaster/Drywall	4,796	SF	6	\$16,597
	Doors - Transom Window	48	SF	6	\$813
	Doors - Wood Doors inclu hw	9	EA	6	\$2,709
	Floor - Concrete	544	SF	6	\$288
	Floor - Terrazzo	104	SF	6	\$228
	Floor - Tile Ceramic/ Porcelain	434	SF	5	\$6,932
	Floor - Tile/Sheet	2,241	SF	6	\$2,243
	Floor - Weight/ Fitness Room Floor Matting	1,004	SF	6	\$5,255
	Floor - Wood	573	SF	6	\$4,040
	Lighting - Pendent/Surface	7	EA	6	\$867
	Lighting - Pendent/Surface	41	EA	7	\$0
	Power Distribution	44	EA	7	\$0
	Storage/ Closet	67	SF	6	\$486
	Walls - Masonry	565	SF	6	\$1,777
	Walls - Plaster/Drywall	5	SF	5	\$26
	Walls - Plaster/Drywall	9,388	SF	6	\$26,075
	Work Sink	1	EA	6	\$508
<b>Auditorium &amp; Theater</b>					
	Balcony Seating	95	EA	6	\$16,522
	Ceiling - Plaster/Drywall	4,050	SF	6	\$33,764
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile/Sheet	2,319	SF	6	\$2,321
	Lighting - Pendent/Surface	19	EA	6	\$2,354
	Lighting - Wall Mounted	9	EA	6	\$1,115
	Main Floor Seating	288	EA	6	\$50,088
	Sound System	1	EA	6	\$10,721
	Stage	550	SF	6	\$3,177

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Auditorium &amp; Theater</b>					
	Stage Curtain	4	EA	6	\$0
	Stage Lighting System	1	EA	6	\$8,077
	Stage-Stairs - Wood	8	LF	6	\$94
	Walls - Plaster/Drywall	10,240	SF	6	\$48,762
<b>Gymnasia</b>					
	Ceiling - Plaster/Drywall	2,776	SF	6	\$15,323
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Wood	2,776	SF	6	\$19,571
	Lighting - Pendent/Surface	10	EA	7	\$0
	Scoreboards	1	EA	5	\$10,580
	Walls - Masonry	1,509	SF	6	\$4,747
	Walls - Plaster/Drywall	4,249	SF	6	\$11,727
<b>Mechanical/ Service Rooms</b>					
	Air Intake Plenums	204	SF	6	\$1,263
	Air Tunnel	4,032	SF	6	\$24,966
	Boiler Room	2,126	SF	6	\$15,231
	Crawl Space - Unfinished	8,436	SF	6	\$52,235
	Interior Stairs	16	LF	6	\$144
	Janitor's Closet	142	SF	6	\$1,017
	Mechanical/ Service Rooms	4,252	SF	6	\$30,463
	Storage Room	1,208	SF	6	\$8,654
<b>Restroom</b>					
	Accessories	2,729	SF	6	\$25,171
	Ceiling - Plaster/Drywall	2,764	SF	6	\$9,565
	Doors - Transom Window	4	SF	6	\$68
	Doors - Wood Doors inclu hw	2	EA	5	\$2,348
	Doors - Wood Doors inclu hw	10	EA	6	\$3,010
	Floor - Concrete	14	SF	6	\$7
	Floor - Tile Ceramic/ Porcelain	2,750	SF	6	\$5,820
	Floor Drain	13	EA	6	\$13,769
	Lavatory	23	EA	6	\$7,351
	Lighting - Pendent/Surface	3	EA	6	\$372
	Lighting - Pendent/Surface	41	EA	7	\$0
	Partitions	26	EA	6	\$7,720
	Urinals	16	EA	6	\$5,376
	Walls - Masonry	3,100	SF	6	\$9,753



**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Restroom</b>					
	Walls - Plaster/Drywall	5,986	SF	6	\$16,521
	Walls - Structural Glazed Tile	1,555	SF	6	\$4,892
	Water Closet	27	EA	6	\$9,071

**Rooms (Other Than Classrooms) Subtotal: \$567,430**

**Building: Main**
**Category: Building Interior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Plaster/Drywall	9,900	SF	6	\$61,300
	Drinking Fountains - Double Water Cooler	4	EA	6	\$1,508
	Floor - Terrazzo	2,396	SF	6	\$20,112
	Floor - Tile/Sheet	7,504	SF	6	\$4,078
	Lighting - Pendent/Surface	79	EA	7	\$0
	Student Lockers - One Tier	418	EA	6	\$38,805
	Walls - Plaster/Drywall	19,978	SF	6	\$88,562
<b>Stairs</b>					
	Ceiling - Plaster/Drywall	1,360	SF	6	\$9,957
	Floor - Terrazzo	1,360	SF	6	\$11,416
	Handrails	232	LF	6	\$2,010
	Lighting - Pendent/Surface	12	EA	7	\$0
	Stairs - Terrazzo	116	LF	6	\$1,077
	Walls - Plaster/Drywall	9,504	SF	6	\$26,230

**Building Interior Subtotal: \$265,056**

**Total Building Cost \$2,775,294**

**Building: Addition**
**Category: Building Exterior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	1	EA	6	\$702
	Exterior Doors - Exterior FRP Door	2	EA	6	\$1,263

## Building: Addition

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Exterior Doors - Exterior Steel Door	6	EA	5	\$8,048
	Exterior Doors - Exterior Steel Door	6	EA	6	\$2,883
	Exterior Doors - Side lite	4	EA	6	\$1,253
	Exterior Doors - Transom Lite	2	EA	6	\$627
	Exterior Stairs - Concrete	12	LF	6	\$981
	Power Door Operator and Controls	2	EA	6	\$0
	Ramp Handrail - Steel_Ramp Handrail	26	LF	6	\$225
	Ramps - Concrete	13	LF	6	\$1,953
<b>Foundation</b>					
	Foundation - Concrete	805	LF	7	\$0
	Superstructure - Steel	65,153	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Wall Mounted	26	EA	6	\$7,507
<b>Roof System</b>					
	Chimney - Metal Flue	6	LF	6	\$949
	Coping - Stone	990	LF	6	\$31,797
	Downspouts - Interior Downspouts	220	LF	6	\$7,311
	Downspouts - Interior Downspouts	96	LF	7	\$0
	Parapet - 16" - 30" Height	666	LF	6	\$26,609
	Parapet - Parapet > 30"	324	LF	6	\$20,710
	Roof - Modified Bitumen	27,097	SF	6	\$254,967
	Roof Structure - Steel / Metal Deck/ Concrete Topping	27,097	SF	7	\$0
<b>Walls</b>					
	Exterior Walls - Brick	34,616	SF	6	\$232,654
	Exterior Walls - Stone-Cast	1,862	SF	6	\$12,515
<b>Windows</b>					
	Guard - Guards perforated	2,449	SF	6	\$31,273
	Lintels - Steel	766	LF	6	\$22,236
	Windows - Sash Aluminum Double-pane	340	SF	5	\$18,315
	Windows - Sash Aluminum Double-pane	6,449	SF	6	\$48,139

**Building Exterior Subtotal:** **\$732,918**

## Building: Addition

## Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Corridors and Stairs	16,826	SF	6	\$5,053
	Emergency A/C Power - Multipurpose Room	4,741	SF	6	\$1,763
	Emergency A/C Power - Students Toilets	1,608	SF	6	\$598
	Emergency Battery Packs - Corridors and Stairs	35	EA	6	\$7,088
	Emergency Battery Packs - Multipurpose Room	3	EA	6	\$608
	Emergency Battery Packs - Students Toilets	6	EA	6	\$1,215
	Exit Signs - Corridors and Stairs	26	EA	7	\$0
	Exit Signs - Multipurpose Room	3	EA	7	\$0
	Security System - Intrusion Detection	65,153	SF	6	\$16,770
<b>Main Service</b>					
	Independent Electrical Service for emergency power	2	EA	6	\$5,841
	Main Electrical Service - 1200 A 277/480/3PH	1	EA	6	\$5,346
	Main Electrical Service - 1600 A 120/208/3PH	1	EA	6	\$5,641
	PA System	65,153	SF	6	\$21,429
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	7	EA	7	\$0
	Lighting and Power Panels - Above 100 A	11	EA	7	\$0
	Main Distribution Panels - Greater than 600 amp	3	EA	7	\$0

**Electrical System Subtotal: \$71,760**

## Building: Addition

### Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Strobe Lights	65,153	SF	6	\$23,292
	Fire Alarm_System	65,153	SF	6	\$31,677
	Fire Pump Controller	1	EA	7	\$0
<b>Pump Room Assembly</b>					
	Fire Pump - 25-50 hp	1	EA	6	\$1,558
	Jockey Pump	1	EA	6	\$758
<b>Sprinkler System</b>					
	Sprinkler Heads	65,153	SF	7	\$0
	Sprinkler Piping	65,153	SF	7	\$0
	Wet Sprinkler System	65,153	SF	7	\$0

**Building: Addition**
**Category: Safty System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Sprinkler System</b>					
<b>Safty System Subtotal:</b>					<b>\$57,285</b>

**Building: Addition**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Chemical Pot Feeder	1	EA	6	\$606
	Chiller-Air Cooled- Recipricating-Roof Mounted - 201 - 300 tons	1	EA	5	\$70,270
	Glycol Feed	1	EA	6	\$490
	Pipes - Chilled Water Pipe- Steel	500	LF	6	\$944
	Pressure Fill System	1	EA	6	\$1,405
<b>Air Handling Systems</b>					
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	1	EA	6	\$3,350
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 8001-12000 cfm	1	EA	6	\$3,350
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm	1	EA	6	\$3,350
	Air Intake	3	EA	6	\$17,294
	Fan Power Box - Fan Power Box with No Coil	41	EA	5	\$60,971
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	1	EA	6	\$1,857
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	1	EA	6	\$1,857
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	1	EA	6	\$2,433
	Make Up Air Unit- Roof Mounted- Gas Heating - 6000 - 10,000 cfm	1	EA	6	\$3,350
	Return Duct Work - Indoor- Vertical Shaft and Ducts	400	LF	6	\$0
	VAV Box	16	EA	6	\$4,467
<b>Boiler Systems</b>					
	Boiler Auxiliary- Condensing Hot Water - 1001 - 2000 HP	3	EA	5	\$45,343
	Chemical Pot Feeder	1	EA	6	\$725
	Condensing- Hot Water Boiler - 1001 - 2000 MBH	3	EA	5	\$140,098
	Water Fill System	1	EA	6	\$1,168
<b>Gas Booster</b>					
	Gas Booster	1	EA	6	\$499

## Building: Addition

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Heating Devices</b>					
	Cabinet Heaters - With Hot Water Coil	3	EA	6	\$1,063
<b>Mechanical Plumbing</b>					
	Chilled Water Pump - 10 - 20 HP	2	EA	6	\$2,485
	Hot Water Pump - 10 - 20 HP	2	EA	6	\$2,485
	Hot Water Pump - Less than 10	3	EA	6	\$3,334
	Hydronic Supply and Return - Steel	900	LF	6	\$69,099
<b>Temperature Control</b>					
	DDC System	65,153	SF	5	\$107,144
	Thermostats - DDC	57	EA	6	\$0
<b>Ventilation</b>					
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	2	EA	6	\$1,185
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	1	EA	4	\$4,245
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	3	EA	6	\$1,777
	Type I Exhaust Hood- Kitchen	1	EA	7	\$0
	Type II Exhaust Hood- Warming Kitchen	1	EA	7	\$0
<b>Mechanical System Subtotal:</b>					<b>\$556,641</b>

## Building: Addition

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - 150000 - 300000 BTU/HR	2	EA	7	\$0
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	65,153	SF	6	\$13,044
	Domestic Piping-Cold Water Horizontal Lines	65,153	SF	6	\$15,839
	Domestic Piping-Cold Water Risers	65,153	SF	6	\$12,112
	Domestic Piping-Hot Water from Risers to Fixtures	65,153	SF	6	\$10,249
	Domestic Piping-Hot Water Horizontal Lines	65,153	SF	6	\$12,112
	Domestic Piping-Hot Water Return Lines	65,153	SF	6	\$9,317
	Domestic Piping-Hot Water Return Risers	65,153	SF	6	\$9,317
	Sanitary Piping	65,153	SF	6	\$59,628
	Storm Piping	65,153	SF	6	\$56,833
	Vent Piping	65,153	SF	6	\$43,789

**Building: Addition**
**Category: Plumbing System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Pumps</b>					
	Pumps - Domestic Booster Pump-Duplex	1	EA	6	\$1,977

**Plumbing System Subtotal:**
**\$244,216**
**Building: Addition**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Computer Lab (1 room)</b>					
	Ceiling - Lay-in	935	SF	6	\$2,808
	Chalk Board	24	LF	4	\$2,203
	Doors - Side-lite	8	SF	6	\$134
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile/Sheet	935	SF	6	\$936
	Lighting - Lay-in	12	EA	7	\$0
	Walls - Concrete Block	670	SF	6	\$1,964
	Walls - Plaster/Drywall	500	SF	6	\$1,380

**Kindergarten (1 room)**

Casework	12	LF	6	\$303
Ceiling - Lay-in	1,307	SF	6	\$3,925
Doors - Side-lite	8	SF	6	\$134
Doors - Wood Doors inclu hw	1	EA	6	\$301
Floor - Tile/Sheet	1,307	SF	6	\$1,308
Lighting - Lay-in	15	EA	7	\$0
Marker Board	12	LF	6	\$257
Storage/ Closet	46	SF	6	\$334
Walls - Concrete Block	1,201	SF	6	\$3,521
Walls - Plaster/Drywall	400	SF	6	\$1,104
Work Sink	2	EA	6	\$758

**Office (1 room)**

Casework	20	LF	6	\$505
Ceiling - Lay-in	492	SF	6	\$1,477
Chalk Board	16	LF	4	\$1,469
Doors - Wood Doors inclu hw	1	EA	6	\$301
Floor - Tile/Sheet	492	SF	6	\$492
Lighting - Lay-in	6	EA	7	\$0
Walls - Concrete Block	711	SF	6	\$2,084

## Building: Addition

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Office (1 room)</b>					
	Walls - Plaster/Drywall	239	SF	6	\$660
	Work Sink	1	EA	6	\$379
<b>Pre School (2 rooms)</b>					
	Casework	72	LF	6	\$1,818
	Ceiling - Lay-in	2,715	SF	6	\$8,153
	Chalk Board	10	LF	4	\$918
	Doors - Side-lite	16	SF	6	\$267
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile/Sheet	2,715	SF	6	\$2,718
	Lighting - Lay-in	18	EA	6	\$2,142
	Lighting - Lay-in	15	EA	7	\$0
	Marker Board	12	LF	6	\$257
	Storage/ Closet	92	SF	6	\$667
	Walls - Concrete Block	2,281	SF	6	\$6,687
	Walls - Plaster/Drywall	1,060	SF	6	\$2,925
	Work Sink	4	EA	6	\$1,516
<b>Regular Classroom (17 rooms)</b>					
	Casework	775	LF	6	\$19,572
	Ceiling - Lay-in	15,830	SF	6	\$47,537
	Chalk Board	312	LF	4	\$28,643
	Doors - Side-lite	136	SF	6	\$2,273
	Doors - Wood Doors inclu hw	17	EA	6	\$5,117
	Floor - Tile/Sheet	15,830	SF	6	\$15,846
	Lighting - Lay-in	204	EA	7	\$0
	Marker Board	12	LF	6	\$257
	Storage/ Closet	4	SF	6	\$29
	Walls - Concrete Block	12,390	SF	6	\$36,321
	Walls - Plaster/Drywall	7,250	SF	6	\$20,009
	Work Sink	17	EA	6	\$6,443
<b>Science Lab Level 3 (1 room)</b>					
	Casework	50	LF	6	\$1,263
	Ceiling - Lay-in	935	SF	6	\$2,808
	Chalk Board	24	LF	4	\$2,203
	Doors - Side-lite	8	SF	6	\$134
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile/Sheet	935	SF	6	\$936

**Building: Addition**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Science Lab Level 3 (1 room)</b>					
	Lighting - Lay-in	12	EA	7	\$0
	Walls - Concrete Block	670	SF	6	\$1,964
	Walls - Plaster/Drywall	500	SF	6	\$1,380
	Work Sink	3	EA	6	\$1,137
<b>Special Education (3 rooms)</b>					
	Casework	60	LF	6	\$1,515
	Ceiling - Lay-in	1,476	SF	6	\$4,432
	Chalk Board	48	LF	4	\$4,407
	Doors - Side-lite	24	SF	6	\$401
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile/Sheet	1,476	SF	6	\$1,477
	Lighting - Lay-in	18	EA	7	\$0
	Walls - Concrete Block	2,133	SF	6	\$6,253
	Walls - Plaster/Drywall	717	SF	6	\$1,979
	Work Sink	3	EA	6	\$1,137
<b>Store Room (3 rooms)</b>					
	Casework	112	LF	6	\$2,828
	Ceiling - Lay-in	3,167	SF	6	\$9,511
	Chalk Board	24	LF	4	\$2,203
	Doors - Side-lite	24	SF	6	\$401
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile/Sheet	3,167	SF	6	\$3,170
	Lighting - Lay-in	39	EA	7	\$0
	Marker Board	36	LF	6	\$771
	Storage/ Closet	54	SF	6	\$392
	Walls - Concrete Block	2,791	SF	6	\$8,182
	Walls - Plaster/Drywall	1,150	SF	6	\$3,174
	Work Sink	4	EA	6	\$1,516

**Classrooms Subtotal:**
**\$307,740**
**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Ceiling - Lay-in	2,068	SF	6	\$6,210



**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Doors - Side-lite	12	SF	6	\$201
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Transom Window	2	SF	6	\$34
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Carpet	1,466	SF	6	\$3,124
	Floor - Concrete Epoxy/ Painted	72	SF	6	\$38
	Floor - Terrazzo	175	SF	6	\$383
	Floor - Tile/Sheet	355	SF	6	\$355
	Lighting - Lay-in	1	EA	6	\$119
	Lighting - Lay-in	26	EA	7	\$0
	Power Distribution	50	EA	7	\$0
	Storage/ Closet	143	SF	6	\$1,037
	Walls - Concrete Block	2,880	SF	6	\$8,443
	Walls - Plaster/Drywall	1,970	SF	6	\$5,437
	Work Sink	2	EA	6	\$1,016
<b>Gymnasia</b>					
	Ceiling - Exposed	4,741	SF	6	\$7,051
	Doors - Steel Doors incl hw	4	EA	6	\$1,204
	Floor - Tile/Sheet	4,741	SF	6	\$4,746
	Lighting - Metal Halide/Sodium Vapor	12	EA	7	\$0
	Storage/ Closet	120	SF	6	\$870
	Walls - Concrete Block	9,004	SF	6	\$26,395
<b>Kitchen</b>					
	Ceiling - Lay-in	1,832	SF	6	\$5,501
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Floor - Concrete Epoxy/ Painted	155	SF	6	\$82
	Floor - Tile/Sheet	1,677	SF	6	\$1,679
	Lighting - Lay-in	30	EA	7	\$0
	Serving Line	24	LF	6	\$1,428
	Storage/ Closet	156	SF	6	\$1,131
	Walls - Concrete Block	2,832	SF	6	\$8,302
<b>Library</b>					
	Ceiling - Lay-in	2,495	SF	6	\$7,492
	Doors - Side-lite	16	SF	6	\$267
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	2,495	SF	6	\$5,316

**Building: Addition**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Library</b>					
	Lighting - Lay-in	27	EA	7	\$0
	Walls - Concrete Block	1,300	SF	6	\$3,811
	Walls - Plaster/Drywall	850	SF	6	\$2,346
<b>MDF_IDF</b>					
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Finishes	140	SF	6	\$999
	Ventilation and Cooling	1	EA	6	\$1,855
<b>Mechanical/ Service Rooms</b>					
	Janitor's Closet	180	SF	6	\$1,290
	Mechanical/ Service Rooms	3,065	SF	6	\$21,959
	Storage Room	271	SF	6	\$1,942
<b>Restroom</b>					
	Accessories	1,822	SF	6	\$16,805
	Ceiling - Lay-in	943	SF	6	\$2,832
	Ceiling - Plaster/Drywall	879	SF	6	\$3,042
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Terrazzo	1,767	SF	6	\$3,866
	Floor - Tile/Sheet	55	SF	6	\$55
	Floor Drain	12	EA	6	\$12,710
	Hand Dryer	1	EA	6	\$230
	Lavatory	26	EA	6	\$8,310
	Lighting - Lay-in	38	EA	7	\$0
	Partitions	18	EA	6	\$5,345
	Urinals	9	EA	6	\$3,024
	Walls - Concrete Block	220	SF	6	\$645
	Walls - Structural Glazed Tile	3,798	SF	6	\$11,949
	Walls - Tile Ceramic/ Porcelain	1,160	SF	6	\$2,621
	Water Closet	29	EA	6	\$9,743
<b>Rooms (Other Than Classrooms) Subtotal:</b>					<b>\$218,355</b>

**Building: Addition**
**Category: Building Interior**

Group	Item - Type	Quantity	Unit	Rank	Cost
-------	-------------	----------	------	------	------

**Building: Addition**
**Category: Building Interior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Lay-in	15,776	SF	6	\$47,375
	Drinking Fountains - Double Water Cooler	2	EA	6	\$754
	Drinking Fountains - Single Fountain	1	EA	6	\$276
	Floor - Terrazzo	15,776	SF	6	\$132,425
	Lighting - Lay-in	326	EA	7	\$0
	Stairs - Terrazzo	8	LF	7	\$0
	Walls - Structural Glazed Tile	16,434	SF	6	\$51,701
	Walls - Structural Glazed Tile	8,242	SF	7	\$0
<b>Stairs</b>					
	Ceiling - Plaster/Drywall	1,050	SF	6	\$7,688
	Floor - Terrazzo	1,050	SF	6	\$8,814
	Handrails	348	LF	6	\$3,016
	Lighting - Pendent/Surface	36	EA	7	\$0
	Stairs - Terrazzo	174	LF	6	\$1,615
	Walls - Plaster/Drywall	9,720	SF	6	\$26,826
<b>Vertical Conveyance</b>					
	Elevator - Hydraulic Elevator	1	EA	6	\$19,238

**Building Interior Subtotal:** **\$299,728**

**Total Building Cost** **\$2,488,642**

**SITE**
**Category: Site**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Civil/Drainage</b>					
	Civil/ Drainage - Catch Basin	6	EA	6	\$6,563
	Civil/ Drainage - Site Manhole	3	EA	6	\$4,478
<b>Fencing</b>					
	Fencing - New Standard Ornamental	1,981	LF	6	\$63,200
<b>Landscape</b>					
	Benches	2	EA	6	\$860
	Irrigation	48,135	SF	4	\$216,824
	Landscape - Grass	48,135	SF	6	\$39,923

**SITE**
**Category: Site**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Landscape</b>					
	Parkway trees	55	EA	6	\$36,302
	Planting Beds/ Area	6,766	SF	6	\$11,127
	Play Area - Asphalt/ Hardscape	8,209	SF	6	\$19,839
	Retaining Wall - Masonry	15	SF	6	\$219
	Walking Path - Crushed Stone	1,980	SF	6	\$4,190
<b>Parking Lot</b>					
	Concrete Curbs	405	LF	6	\$5,201
	Interior Plantings	75	LF	6	\$3,191
	Lighting - Pole Mounted	9	EA	6	\$13,072
	Surface - Asphalt	28,109	SF	6	\$67,931
	Surface - Concrete	6,485	SF	6	\$15,672
	Trash Compactor	1	EA	6	\$0
	Trash Enclosure	681	SF	6	\$0
	Vehicular Screening	255	LF	6	\$20,078
<b>Playground</b>					
	Equipment - School Age 5-12	2	EA	6	\$7,092
	Surface - Poured Surface	4,777	SF	6	\$34,975
<b>Sidewalks</b>					
	Sidewalks - Internal Walks	232	LF	6	\$2,787
	Sidewalks - Perimeter Sidewalks	16,912	SF	6	\$33,616
<b>Signage</b>					
	Flag Pole - Flag Pole	1	EA	6	\$1,657
	Marquee - Free Standing Back Lighted	1	EA	6	\$0
	Monument - Sign	1	EA	6	\$0
<b>Site Subtotal:</b>					<b>\$608,798</b>
<b>Total Site Cost</b>					<b>\$608,798</b>
<b>Campus Total <sup>2 3</sup></b>					<b>\$5,872,734</b>

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

---

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
  - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
  - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

**Classroom Summary**

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Computer Lab	Computer Lab	2nd Floor	224	214	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Library	1st Floor	123	113	750	1	2	8	165	85	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	124	114	724	1	2	8	165	85	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	125	111	724	1	2	6	165	85	85	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	126	112	699	1	2	6	165	85	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	127	109	724	1	2	6	165	85	40	N	Y	N
Regular Classroom	Pre School	1st Floor	130	108	770	1	1	8	165	85	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	131	105	724	1	2	6	165	85	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	133	103	724	1	2	6	165	85	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	221	215	1,350	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	223	213	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	225	211	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	226	212	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	227	209	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	228	210	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	229	207	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	230	208	724	1	2	6	165	85	85	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	231	205	724	1	2	6	165	85	85	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	232	206	724	1	2	6	165	85	85	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	233	203	724	1	2	6	165	85	85	N	N	N
Vacant	Regular Classroom	1st Floor	128	110	699	1	1	6	165	85	40	N	Y	N

**Addition**

Computer Lab	Computer Lab	2nd Floor	215	2-11	935	1	36	40	132	66	40	N	Y	N
Kindergarten	Pre School	1st Floor	119	1-13	1,307	1	2	12	176	88	40	N	N	N
Office	Regular Classroom	2nd Floor	218A	2-08	492	1	4	10	66	33	40	N	Y	N
Pre School	Pre School	1st Floor	107	1-22	1,408	1	2	12	198	99	40	N	Y	N
Pre School	Pre School	1st Floor	122	1-10	1,307	1	2	12	176	88	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	110	1-21	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	206	2-18	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	207	2-17	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	208	2-16	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	209	2-15	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	216	2-10	935	1	6	16	132	66	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	217	2-09	935	1	6	16	132	66	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	218	2-08	935	1	6	16	132	66	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	300	3-21	930	1	8	20	132	66	40	N	Y	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Addition</b>														
Regular Classroom	Regular Classroom	3rd Floor	301	3-20	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	302	3-19	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	303	3-18	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	304	3-17	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	305	3-16	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	306	3-15	930	1	8	20	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	313	3-10	935	1	6	16	132	66	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	314	3-11	930	1	6	18	132	66	40	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	312	3-09	935	1	8	20	132	66	40	N	N	N
Special Education	Regular Classroom	2nd Floor	211	2-14	492	1	4	10	66	33	40	N	Y	N
Special Education	Regular Classroom	3rd Floor	308	3-08	492	1	4	10	66	33	40	N	Y	N
Special Education	Regular Classroom	3rd Floor	316	3-14	492	1	4	10	66	33	40	N	Y	N
Store Room	Regular Classroom	1st Floor	111	1-20	930	1	8	20	132	66	40	N	N	N
Store Room	Regular Classroom	1st Floor	112	1-19	930	1	8	20	132	66	40	N	N	N
Store Room	Pre School	1st Floor	116	1-16	1,307	1	2	12	176	88	40	N	N	N