

Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1920	3	79,926	\$3,371,910
SITE				\$174,098
Campus Total			79,926	\$3,546,009

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Entrance Control - Audio	1	EA	6	\$497
	Exterior Doors - Exterior Steel Door	17	EA	6	\$8,169
	Exterior Doors - Exterior Wood Door	3	EA	5	\$4,024
	Exterior Doors - Exterior Wood Door	4	EA	6	\$1,922
	Exterior Doors - Side lite	6	EA	6	\$1,880
	Exterior Doors - Transom Lite	1	EA	5	\$822
	Exterior Doors - Transom Lite	15	EA	6	\$4,700
	Exterior Stairs - Concrete	360	LF	6	\$29,436
	Exterior Stairs - Stone	23	LF	6	\$2,599
	Stair Handrail - Steel_Stair Handrail	24	LF	6	\$208
Foundation					
	Foundation - Concrete	30	LF	5	\$16,558
	Foundation - Concrete	50	LF	6	\$9,711
	Foundation - Concrete	1,264	LF	7	\$0
	Superstructure - Concrete	200	SF	5	\$8,366
	Superstructure - Concrete	3,800	SF	7	\$0
	Superstructure - Heavy Timber	46,316	SF	7	\$0
	Superstructure - Steel with Clay Tile Arch	29,610	SF	7	\$0

Building: Main
Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Lighting					
	Exterior Lighting - Wall Mounted	11	EA	6	\$3,176
Roof System					
	Cell Tower	1	EA	6	\$736
	Chimney - Brick Chimney- Concrete/ Mortar Liner	75	LF	5	\$213,867
	Coping - Clay Tile	785	LF	6	\$25,212
	Coping - Terra Cotta	563	LF	6	\$18,082
	Downspouts - Exterior Downspouts	338	LF	6	\$11,233
	Parapet - 16" - 30" Height	523	LF	6	\$20,896
	Parapet - Parapet < 16" Height	380	LF	6	\$8,097
	Parapet - Parapet > 30"	445	LF	6	\$28,445
	Roof - Asphalt Gravel Ballast	16,275	SF	6	\$165,473
	Roof - Asphalt Shingle	90	SF	6	\$413
	Roof - Modified Bitumen	9,795	SF	6	\$92,165
	Roof Structure - Heavy Timber	14,552	SF	7	\$0
	Roof Structure - Steel with Clay Tile Arch	11,608	SF	7	\$0
Walls					
	Cheek-Wall - Stone	20	SF	5	\$476
	Cheek-Wall - Stone	80	SF	6	\$820
	Cornice - Masonry Projecting Limestone	2,688	LF	6	\$93,213
	Exterior Walls - Brick	50,126	SF	6	\$336,968
	Exterior Walls - Stone-Cast	556	SF	6	\$3,737
	Exterior Walls - Terra Cotta	1,290	SF	6	\$8,670
Windows					
	Curtain wall - Insulated Panel	2,803	SF	6	\$31,425
	Guard - Guards wire guard	2,264	SF	6	\$28,911
	Lintels - Steel	1,262	LF	6	\$36,635
	Skylite - Glass Single-Pane	12	SF	4	\$3,238
	Skylite - Glass Single-Pane	179	SF	6	\$4,277
	Storefront Windows	48	SF	6	\$538
	Windows - Decorative	741	SF	6	\$5,531
	Windows - Sash Aluminum Double-pane	5,386	SF	6	\$40,204
	Windows - Wood- Single-pane	689	SF	4	\$90,438
	Windows - Wood- Single-pane	545	SF	6	\$4,068

Building Exterior Subtotal:
\$1,365,836

Building: Main
Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
	Automatic Transfer Switch	1	EA	6	\$408
	Exit Signs - Corridors and Stairs	25	EA	2	\$13,637
	Exit Signs - Lunchroom	3	EA	2	\$1,636
	Exit Signs - Multipurpose Room	7	EA	2	\$3,818
	Security System - CCTV	79,926	SF	7	\$0
	Security System - Intrusion Detection	79,926	SF	7	\$0
Main Service					
	Independent Electrical Service for emergency power	1	EA	6	\$2,921
	Main Electrical Service - 1600 A 120/240/3PH	1	EA	7	\$0
	PA System	79,926	SF	6	\$26,288
Power Distribution					
	Lighting and Power Panels - 100 A	2	EA	6	\$598
	Lighting and Power Panels - Above 100 A	4	EA	6	\$1,988
	Main Distribution Panels - 400 - 600 amp	3	EA	6	\$1,583
Electrical System Subtotal:					\$52,878

Building: Main
Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Alarm Panel	1	EA	3	\$49,477
Pump Room Assembly					
	Fire Pump - Less than 25hp	1	EA	6	\$1,558
Sprinkler System					
	Dry Sprinkler System	29,610	SF	4	\$40,225
	Sprinkler Heads	29,610	SF	4	\$15,243
	Sprinkler Piping	29,610	SF	4	\$42,766
Safty System Subtotal:					\$149,268

Building: Main
Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
-------	-------------	----------	------	------	------

Building: Main
Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Conditioning					
	Condensing Unit- Roof Mounted - Less than 5 tons	2	EA	6	\$6,667
	Condensing Unit- Roof Mounted - Less than 5 tons	1	EA	7	\$0
Boiler Systems					
	Piping - Condensate Pipe- Steel	800	LF	6	\$1,510
	Piping - Steam Pipe- Steel	800	LF	6	\$1,510
	Steam Traps	25	EA	4	\$62,758
	Steam Traps	100	EA	5	\$131,490
Heating Devices					
	Radiators - Steam	125	EA	6	\$34,726
Ventilation					
	Exhaust Fans- Indoor - 500 - 1500 CFM	3	EA	4	\$12,734
Mechanical System Subtotal:					\$251,395

Building: Main
Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Hot Water					
	Gas Heater - 300001 - 600000 BTU/HR	1	EA	7	\$0
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	1	EA	6	\$678
Piping					
	Domestic Piping-Cold Water from Risers to Fixtures	79,926	SF	6	\$16,001
	Domestic Piping-Cold Water Horizontal Lines	79,926	SF	6	\$19,430
	Domestic Piping-Cold Water Risers	79,926	SF	6	\$14,858
	Domestic Piping-Hot Water from Risers to Fixtures	79,926	SF	6	\$12,572
	Domestic Piping-Hot Water Horizontal Lines	79,926	SF	6	\$14,858
	Domestic Piping-Hot Water Return Lines	79,926	SF	6	\$11,429
	Domestic Piping-Hot Water Return Risers	79,926	SF	6	\$11,429
	Sanitary Piping	79,926	SF	6	\$73,148
	Storm Piping	79,926	SF	6	\$69,719
	Vent Piping	79,926	SF	6	\$53,718
Pumps					
	Pumps - Sump-Duplex	1	EA	5	\$7,535

Building: Main
Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Plumbing System Subtotal:					\$305,378

Building: Main
Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Computer Lab (1 room)					
	Casework	5	LF	6	\$126
	Ceiling - Plaster/Drywall	853	SF	6	\$2,952
	Doors - Transom Window	72	SF	6	\$1,219
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Wood	853	SF	6	\$6,014
	Lighting - Lay-in	13	EA	7	\$0
	Walls - Plaster/Drywall	1,935	SF	6	\$5,340
Music Room (1 room)					
	AC Units	1	EA	7	\$0
	Ceiling - Plaster/Drywall	770	SF	6	\$2,665
	Doors - Transom Window	21	SF	6	\$356
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	770	SF	6	\$5,428
	Lighting - Pendent/Surface	12	EA	7	\$0
	Marker Board	18	LF	7	\$0
	Storage/ Closet	115	SF	6	\$834
	Walls - Plaster/Drywall	30	SF	5	\$153
	Walls - Plaster/Drywall	1,165	SF	6	\$3,215
Office (3 rooms)					
	AC Units	3	EA	7	\$0
	Casework	11	LF	6	\$278
	Ceiling - Plaster/Drywall	10	SF	5	\$125
	Ceiling - Plaster/Drywall	2,420	SF	6	\$8,375
	Doors - Transom Window	162	SF	6	\$2,743
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Wood	2,420	SF	6	\$17,061
	Lighting - Pendent/Surface	37	EA	7	\$0
	Marker Board	49	LF	7	\$0
	Storage/ Closet	230	SF	6	\$1,668
	Walls - Plaster/Drywall	10	SF	5	\$51

Building: Main
Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Office (3 rooms)					
	Walls - Plaster/Drywall	4,618	SF	6	\$12,745
Regular Classroom (24 rooms)					
	AC Units	23	EA	7	\$0
	Casework	254	LF	6	\$6,414
	Ceiling - Plaster/Drywall	61	SF	5	\$762
	Ceiling - Plaster/Drywall	19,987	SF	6	\$69,180
	Chalk Board	64	LF	4	\$5,876
	Doors - Transom Window	1,464	SF	6	\$24,787
	Doors - Wood Doors inclu hw	44	EA	6	\$13,243
	Floor - Wood	20,012	SF	6	\$141,083
	Lighting - Pendent/Surface	303	EA	7	\$0
	Marker Board	403	LF	7	\$0
	Storage/ Closet	2,603	SF	6	\$18,872
	Walls - Plaster/Drywall	160	SF	5	\$817
	Walls - Plaster/Drywall	43,550	SF	6	\$120,194
Special Program (1 room)					
	AC Units	1	EA	7	\$0
	Ceiling - Plaster/Drywall	376	SF	6	\$1,301
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile/Sheet	371	SF	6	\$371
	Lighting - Pendent/Surface	2	EA	7	\$0
	Marker Board	1	LF	7	\$0
	Storage/ Closet	24	SF	6	\$174
	Walls - Plaster/Drywall	1,038	SF	6	\$2,865
Classrooms Subtotal:					\$480,449

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	AC Unit	2	EA	7	\$0
	Ceiling - Plaster/Drywall	487	SF	5	\$4,464
	Ceiling - Plaster/Drywall	2,663	SF	6	\$9,216
	Doors - Transom Window	207	SF	6	\$3,505

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Doors - Wood Doors inclu hw	9	EA	6	\$2,709
	Floor - Concrete	1,024	SF	6	\$542
	Floor - Tile	1,442	SF	6	\$2,452
	Floor - Tile	756	SF	7	\$0
	Floor - Wood	383	SF	6	\$2,700
	Lighting - Pendent/Surface	2	EA	4	\$1,081
	Lighting - Pendent/Surface	23	EA	7	\$0
	Power Distribution	42	EA	7	\$0
	Storage/ Closet	746	SF	6	\$5,409
	Walls - Concrete Block	615	SF	6	\$1,803
	Walls - Plaster/Drywall	10	SF	5	\$51
	Walls - Plaster/Drywall	7,795	SF	6	\$21,513
Gymnasias					
	Ceiling - Plaster/Drywall	10	SF	5	\$200
	Ceiling - Plaster/Drywall	6,825	SF	6	\$37,673
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Floor - Wood	6,835	SF	6	\$48,186
	Lighting - Pendent/Surface	18	EA	7	\$0
	Sound System	1	EA	6	\$41,654
	Stage	144	SF	6	\$832
	Stage Curtain	4	EA	6	\$0
	Stage Lighting System	1	EA	7	\$0
	Walls - Plaster/Drywall	40	SF	5	\$204
	Walls - Plaster/Drywall	4,690	SF	6	\$12,944
Kitchen					
	Ceiling - Plaster/Drywall	1,624	SF	6	\$5,620
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	20	SF	5	\$115
	Floor - Tile	1,604	SF	6	\$3,509
	Lighting - Pendent/Surface	20	EA	7	\$0
	Serving Line	22	LF	6	\$1,309
	Walls - Metal Panel	1,113	SF	6	\$8,308
	Walls - Plaster/Drywall	1,112	SF	6	\$3,069
Lunch & Multipurpose Room					
	Ceiling - Plaster/Drywall	2,159	SF	6	\$7,471
	Floor - Tile/Sheet	2,159	SF	6	\$2,161

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Lunch & Multipurpose Room					
	Lighting - Pendent/Surface	24	EA	7	\$0
	Walls - Plaster/Drywall	2,308	SF	6	\$7,558
MDF_IDF					
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Finishes	98	SF	6	\$699
	Ventilation and Cooling	1	EA	6	\$1,855
Mechanical/ Service Rooms					
	Coal Room	403	SF	5	\$6,501
	Crawl Space - Unfinished	1,328	SF	6	\$8,223
	Janitor's Closet	75	SF	6	\$537
	Mechanical/ Service Rooms	2,112	SF	6	\$15,131
	Storage Room	1,185	SF	6	\$8,490
Restroom					
	Accessories	1,997	SF	6	\$18,419
	Ceiling - Exposed	21	SF	6	\$31
	Ceiling - Plaster/Drywall	1,997	SF	6	\$6,911
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Concrete	21	SF	6	\$11
	Floor - Tile	1,727	SF	6	\$3,779
	Floor - Tile Ceramic/ Porcelain	270	SF	6	\$571
	Floor Drain	2	EA	6	\$2,118
	Hand Dryer	1	EA	6	\$230
	Lavatory	15	EA	6	\$4,794
	Lighting - Pendent/Surface	13	EA	7	\$0
	Lighting - Wall Mounted	1	EA	7	\$0
	Partitions	29	EA	6	\$8,611
	Urinals	37	EA	6	\$12,431
	Walls - Concrete Block	38	SF	6	\$111
	Walls - Plaster/Drywall	1,689	SF	5	\$12,801
	Walls - Plaster/Drywall	554	SF	6	\$1,529
	Walls - Structural Glazed Tile	347	SF	5	\$17,630
	Walls - Structural Glazed Tile	1,342	SF	6	\$4,222
	Walls - Tile Ceramic/ Porcelain	276	SF	5	\$4,420
	Walls - Tile Ceramic/ Porcelain	138	SF	6	\$312
	Water Closet	5	EA	5	\$6,720
	Water Closet	27	EA	6	\$9,071

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Restroom					

Rooms (Other Than Classrooms) Subtotal:
\$396,030
Building: Main
Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					

Ceiling - Plaster/Drywall	80	SF	5	\$1,396
Ceiling - Plaster/Drywall	11,731	SF	6	\$72,637
Doors - Wood Doors include hw	2	EA	6	\$602
Drinking Fountains - Double Water Cooler	4	EA	6	\$1,508
Floor - Concrete Epoxy/ Painted	1,381	SF	6	\$671
Floor - Tile/Sheet	10,390	SF	5	\$46,653
Lighting - Pendent/Surface	5	EA	6	\$619
Lighting - Pendent/Surface	114	EA	7	\$0
Lighting - Wall Mounted	8	EA	6	\$991
Lighting - Wall Mounted	29	EA	7	\$0
Walls - Plaster/Drywall	40	SF	5	\$402
Walls - Plaster/Drywall	34,227	SF	6	\$151,728
Walls - Vinyl Coated Gypsum Panel	1,704	SF	6	\$4,703

Safety

Camera Viewing Station	1	EA	6	\$683
Security Cameras	24	EA	6	\$4,657

Stairs

Ceiling - Plaster/Drywall	10	SF	5	\$205
Ceiling - Plaster/Drywall	1,179	SF	6	\$8,632
Floor - Terrazzo	714	SF	6	\$5,993
Floor - Tile Ceramic/ Porcelain	501	SF	6	\$3,360
Handrails	846	LF	6	\$7,331
Lighting - Wall Mounted	44	EA	7	\$0
Stairs - Terrazzo	213	LF	6	\$1,977
Stairs - Tile	222	LF	6	\$2,060
Walls - Plaster/Drywall	2,233	SF	5	\$10,285
Walls - Plaster/Drywall	15,791	SF	6	\$43,582

Building: Main
Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Building Interior Subtotal:					\$370,675

Total Building Cost
\$3,371,910
SITE
Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Civil/Drainage					
	Civil/ Drainage - Catch Basin	4	EA	6	\$4,375
	Civil/ Drainage - Site Drain	1	EA	6	\$310
	Civil/ Drainage - Site Manhole	4	EA	6	\$5,971
Fencing					
	Fencing - Guard Rail	96	LF	6	\$1,109
	Fencing - Old Standard Ornamental	269	LF	6	\$13,925
Landscape					
	Landscape - Hardscape- Concrete	177	SF	6	\$914
	Play Area - Asphalt/ Hardscape	1,350	SF	6	\$3,263
Parking Lot					
	Surface - Asphalt	1,399	SF	4	\$14,824
	Surface - Asphalt	27,000	SF	5	\$123,166
Sidewalks					
	Sidewalks - Perimeter Sidewalks	250	SF	4	\$3,268
	Sidewalks - Perimeter Sidewalks	1,496	SF	6	\$2,974
Signage					
	Flag Pole - Building Mounted Flag Pole	1	EA	7	\$0
	Marquee - Free Standing Back Lighted	2	EA	6	\$0
Site Subtotal:					\$174,098

Total Site Cost
\$174,098
Campus Total ^{2 3}
\$3,546,009

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
 - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Computer Lab	Regular Classroom	3rd Floor	305	305	853	6	1	76	93	45	40	N	Y	Y
Music Room	Regular Classroom		210	210	770	1	0	8	40	30	40	N	N	Y
Office	Regular Classroom	2nd Floor	202	202	870	1	0	8	100	60	40	N	Y	Y
Office	Regular Classroom		209	209	756	1	0	8	61	45	40	N	Y	Y
Office	Regular Classroom	2nd Floor	216	216	794	1	0	10	40	30	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	101	101	870	1	0	8	100	60	40	N	Y	Y
Regular Classroom	Regular Classroom		102	102	870	1	0	8	100	60	40	N	N	Y
Regular Classroom	Regular Classroom	1st Floor	103	103	870	1	0	8	100	60	40	N	Y	Y
Regular Classroom	Regular Classroom		104	104	870	1	0	8	100	60	40	N	N	Y
Regular Classroom	Regular Classroom	1st Floor	105	105	870	1	0	8	100	60	40	N	Y	N
Regular Classroom	Regular Classroom		106	106	870	1	0	8	100	60	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	107	107	870	1	0	8	100	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	203	203	739	1	0	6	61	45	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	204	204	870	1	0	8	100	60	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	205	205	756	1	0	8	61	45	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	206	206	870	1	0	8	100	60	40	N	N	Y
Regular Classroom	Regular Classroom		207	207	756	1	0	8	61	45	40	N	Y	Y
Regular Classroom	Regular Classroom		208	208	870	1	0	8	100	60	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	211	211	785	1	0	8	40	30	40	N	N	Y
Regular Classroom	Art Room		212	212	794	1	0	8	40	30	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	213	213	785	1	0	8	40	30	40	N	N	Y
Regular Classroom	Regular Classroom		214	214	794	1	0	10	40	30	40	N	N	Y
Regular Classroom	Regular Classroom	2nd Floor	215	215	785	1	0	8	40	30	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	302	302	853	1	0	6	93	45	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	303	303	853	1	0	6	93	45	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	304	304	853	1	0	6	93	45	40	N	Y	Y
Regular Classroom	Regular Classroom		306	306	853	1	0	6	93	45	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	307	307	853	1	0	6	93	45	40	N	Y	Y
Regular Classroom	Regular Classroom		308	308	853	1	0	6	93	45	40	N	Y	Y
Special Program	Regular Classroom	3rd Floor	300	300	376	1	2	6	47	22	40	N	Y	Y