

## Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1911	3	56,765	\$4,128,738
Linked Addition	1996	2	35,600	\$1,904,743
SITE				\$295,619
<b>Campus Total</b>			<b>92,365</b>	<b>\$6,329,099</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	1	EA	6	\$702
	Exterior Doors - Exterior FRP Door	14	EA	6	\$8,840
	Exterior Doors - Side lite	6	EA	6	\$1,880
	Exterior Doors - Transom Lite	20	EA	6	\$6,266
	Exterior Stairs - Concrete	15	LF	5	\$1,644
	Exterior Stairs - Concrete	12	LF	6	\$981
<b>Foundation</b>					
	Foundation - Masonry	798	LF	7	\$0
	Superstructure - Heavy Timber	56,765	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Parapet or Roof Mounted	9	EA	5	\$19,620
	Exterior Lighting - Wall Mounted	7	EA	6	\$2,021
<b>Roof System</b>					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	108	LF	6	\$103,106
	Chimney - Metal Flue	49	LF	6	\$7,749
	Coping - Metal	250	LF	6	\$8,029
	Coping - Stone	1,134	LF	6	\$36,422

## Building: Main

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Roof System</b>					
	Downspouts - Exterior Downspouts	58	LF	6	\$1,928
	Downspouts - Interior Downspouts	434	LF	6	\$14,423
	Parapet - 16" - 30" Height	300	LF	5	\$51,905
	Parapet - 16" - 30" Height	267	LF	6	\$12,779
	Parapet - Parapet > 30"	50	LF	5	\$18,984
	Parapet - Parapet > 30"	517	LF	6	\$33,047
	Roof - Asphalt Gravel Ballast	25,421	SF	6	\$258,463
	Roof Structure - Steel with Clay Tile Arch	25,421	SF	7	\$0
<b>Walls</b>					
	Cheek-Wall - Stone	5	SF	5	\$119
	Cornice - Masonry Projecting Limestone	3	LF	4	\$2,273
	Cornice - Masonry Projecting Limestone	1,474	LF	6	\$51,115
	Cornice - Metal Projecting	10	LF	5	\$1,505
	Exterior Walls - Brick	60	SF	5	\$1,429
	Exterior Walls - Brick	42,667	SF	6	\$286,765
	Exterior Walls - Prefabricated Metal Panel Wall	1,000	SF	6	\$5,677
	Exterior Walls - Stone-Cast	4,788	SF	6	\$32,180
<b>Windows</b>					
	Guard - Guards perforated	2,146	SF	6	\$27,404
	Lintels - Steel	12	LF	4	\$5,433
	Lintels - Steel	873	LF	6	\$25,342
	Lintels - Stone	606	LF	6	\$0
	Skylite - Glass Single-Pane	140	SF	6	\$3,345
	Windows - Sash Aluminum	111	SF	6	\$829
	Windows - Sash Aluminum Double-pane	7,881	SF	6	\$58,829
<b>Building Exterior Subtotal:</b>					<b>\$1,091,032</b>

## Building: Main

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	1	EA	4	\$8,200
	Emergency A/C Power - Corridors and Stairs	10,288	SF	6	\$3,089
	Emergency A/C Power - Gym	5,672	SF	6	\$2,109
	Emergency A/C Power - Lunchrooms	1,691	SF	6	\$629

## Building: Main

### Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Emergency A/C Power - Students Toilets	1,719	SF	6	\$639
	Emergency Battery Packs - Auditorium and Aisle Lighting	2	EA	6	\$405
	Emergency Battery Packs - Corridors and Stairs	10	EA	6	\$2,025
	Exit Signs - Auditorium	6	EA	6	\$898
	Exit Signs - Corridors and Stairs	17	EA	6	\$2,546
	Security System - CCTV	56,765	SF	5	\$44,646
	Security System - Intrusion Detection	56,765	SF	5	\$56,822
	UPS - Less than 30 KW	1	EA	5	\$33,979
<b>Main Service</b>					
	Main Electrical Service - 2000 A 277/480/3PH	1	EA	6	\$8,662
	PA System	56,765	SF	6	\$18,670
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	2	EA	4	\$9,699
	Lighting and Power Panels - 100 A	2	EA	6	\$598
	Lighting and Power Panels - Above 100 A	7	EA	6	\$3,479
	Main Distribution Panels - 400 - 600 amp	2	EA	6	\$1,055
	Main Distribution Panels - Greater than 600 amp	2	EA	6	\$1,460
	Transformers - 120/240 - 120/208	1	EA	6	\$3,021
	Transformers - 277/480 - 120/208	1	EA	6	\$1,265

### Electrical System Subtotal:

**\$203,897**

## Building: Main

### Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	4	\$49,477
	Fire Alarm Strobe Lights	56,765	SF	5	\$43,834
	Fire Alarm_System	56,765	SF	5	\$63,316
<b>Pump Room Assembly</b>					
	Fire Pump - 25-50 hp	1	EA	5	\$8,163
	Jockey Pump	1	EA	6	\$758
<b>Sprinkler System</b>					
	Sprinkler Heads	56,765	SF	6	\$0
	Sprinkler Piping	56,765	SF	6	\$10,553

**Building: Main**
**Category: Safty System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Sprinkler System</b>					
	Wet Sprinkler System	56,765	SF	6	\$14,611

**Safty System Subtotal:**
**\$190,711**
**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Handling Systems</b>					
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000 cfm	3	EA	5	\$199,314
	Air Intake	3	EA	5	\$22,412
	Auxiliaries - 15001 - 25000 cfm	3	EA	6	\$17,363
	Return Duct Work - Indoor- Vertical Shaft and Ducts	300	LF	5	\$288,593
	Zone Dampers	31	EA	5	\$59,320
<b>Boiler Systems</b>					
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 76 - 100 HP	2	EA	6	\$5,091
	Chemical Feed System	1	EA	5	\$3,075
	Combustion Dampers	2	EA	5	\$5,104
	Feed Water Pumps and Tank	1	EA	5	\$36,450
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 76 - 100 HP	2	EA	5	\$19,066
	Piping - Condensate Pipe- Steel	400	LF	6	\$755
	Piping - Steam Pipe- Steel	400	LF	6	\$755
	Steam Traps	60	EA	5	\$78,894
<b>Heating Devices</b>					
	Cabinet Heaters - With Electric Coil	25	EA	4	\$83,996
	Cabinet Heaters - With Electric Coil	3	EA	6	\$1,070
	Radiators - Steam	3	EA	4	\$10,971
<b>Mechanical Plumbing</b>					
	Condenser Pump - Less than 10	3	EA	5	\$34,484
<b>Temperature Control</b>					
	Pneumatic System	56,765	SF	4	\$295,473
	Thermostats - Pneumatic	31	EA	4	\$22,854
<b>Ventilation</b>					
	Exhaust Fans- Indoor - 500 - 1500 CFM	1	EA	6	\$592
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	1	EA	6	\$592

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Mechanical System Subtotal:</b>					<b>\$1,186,225</b>

**Building: Main**
**Category: Plumbing System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Electric Heater - 20 - 50 KW	1	EA	5	\$2,504
	Gas Heater - 150000 - 300000 BTU/HR	1	EA	6	\$310
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	56,765	SF	4	\$40,587
	Domestic Piping-Cold Water Horizontal Lines	56,765	SF	4	\$81,986
	Domestic Piping-Cold Water Risers	56,765	SF	4	\$45,457
	Domestic Piping-Hot Water from Risers to Fixtures	56,765	SF	4	\$30,846
	Domestic Piping-Hot Water Horizontal Lines	56,765	SF	4	\$73,057
	Domestic Piping-Hot Water Return Lines	56,765	SF	4	\$48,704
	Domestic Piping-Hot Water Return Risers	56,765	SF	4	\$27,599
	Sanitary Piping	56,765	SF	6	\$51,951
	Storm Piping	56,765	SF	6	\$49,516
	Vent Piping	56,765	SF	6	\$38,152
<b>Pumps</b>					
	Pumps - Domestic Booster Pump-Simplex	1	EA	5	\$8,937
<b>Plumbing System Subtotal:</b>					<b>\$499,606</b>

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (1 room)</b>					
	AC Units	2	EA	6	\$991
	Casework	10	LF	6	\$253
	Ceiling - Plaster/Drywall	5	SF	5	\$62
	Ceiling - Plaster/Drywall	839	SF	6	\$2,903
	Chalk Board	36	LF	4	\$3,305
	Doors - Transom Window	12	SF	6	\$203
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	839	SF	6	\$1,836

## Building: Main

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Art Room (1 room)</b>					
	Lighting - Pendent/Surface	10	EA	7	\$0
	Marker Board	10	LF	7	\$0
	Storage/ Closet	54	SF	6	\$392
	Walls - Plaster/Drywall	5	SF	5	\$26
	Walls - Plaster/Drywall	1,510	SF	6	\$4,167
<b>Kindergarten (1 room)</b>					
	AC Units	1	EA	6	\$496
	Casework	34	LF	6	\$859
	Ceiling - Plaster/Drywall	912	SF	6	\$3,156
	Chalk Board	13	LF	4	\$1,193
	Doors - Transom Window	12	SF	6	\$203
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	10	SF	5	\$58
	Floor - Tile	902	SF	6	\$1,973
	Lighting - Pendent/Surface	14	EA	7	\$0
	Marker Board	8	LF	7	\$0
	Storage/ Closet	35	SF	6	\$254
	Walls - Plaster/Drywall	1,583	SF	6	\$4,369
<b>Music Room (1 room)</b>					
	AC Units	1	EA	6	\$496
	Casework	7	LF	6	\$177
	Ceiling - Plaster/Drywall	812	SF	6	\$2,810
	Chalk Board	41	LF	4	\$3,764
	Doors - Side-lite	12	SF	6	\$201
	Doors - Transom Window	12	SF	6	\$203
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	812	SF	6	\$5,725
	Lighting - Pendent/Surface	14	EA	7	\$0
	Marker Board	6	LF	7	\$0
	Storage/ Closet	63	SF	6	\$457
	Walls - Plaster/Drywall	1,494	SF	6	\$4,123
<b>Regular Classroom (23 rooms)</b>					
	AC Units	29	EA	6	\$14,372
	Casework	213	LF	6	\$5,379
	Ceiling - Plaster/Drywall	35	SF	5	\$437
	Ceiling - Plaster/Drywall	17,727	SF	6	\$61,346

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Regular Classroom (23 rooms)</b>					
	Chalk Board	422	LF	4	\$38,742
	Chalk Board	56	LF	6	\$1,249
	Doors - Side-lite	28	SF	6	\$468
	Doors - Transom Window	293	SF	6	\$4,961
	Doors - Wood Doors inclu hw	24	EA	6	\$7,224
	Floor - Tile	4,000	SF	6	\$8,752
	Floor - Wood	10	SF	5	\$197
	Floor - Wood	13,752	SF	6	\$96,950
	Lighting - Pendent/Surface	308	EA	7	\$0
	Marker Board	168	LF	7	\$0
	Storage/ Closet	947	SF	6	\$6,866
	Walls - Plaster/Drywall	160	SF	5	\$817
	Walls - Plaster/Drywall	33,703	SF	6	\$93,017
	Work Sink	1	EA	6	\$379

**Classrooms Subtotal:**
**\$386,712**
**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	AC Unit	2	EA	6	\$991
	Ceiling - Plaster/Drywall	1,425	SF	6	\$4,931
	Doors - Side-lite	58	SF	6	\$970
	Doors - Transom Window	28	SF	6	\$474
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Tile	5	SF	5	\$29
	Floor - Tile	1,256	SF	6	\$2,748
	Floor - Wood	164	SF	6	\$1,156
	Lighting - Pendent/Surface	26	EA	7	\$0
	Power Distribution	40	EA	6	\$84,995
	Storage/ Closet	68	SF	6	\$493
	Walls - Plaster/Drywall	4,335	SF	6	\$11,964
	Work Sink	2	EA	6	\$1,016

**Gymnasia**

Ceiling - Plaster/Drywall	5,672	SF	6	\$31,308
---------------------------	-------	----	---	----------

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Gymnasias</b>					
	Doors - Transom Window	98	SF	6	\$1,659
	Doors - Wood Doors inclu hw	12	EA	6	\$3,612
	Floor - Concrete	1,852	SF	6	\$980
	Floor - Tile	408	SF	6	\$893
	Floor - Wood	3,412	SF	6	\$24,054
	Lighting - Metal Halide/ High Pressure Sodium	20	EA	7	\$0
	Lighting - Wall Mounted	4	EA	7	\$0
	Stage	721	SF	6	\$4,165
	Stage Curtain	2	EA	6	\$0
	Stage Lighting System	107	EA	7	\$0
	Stage-Stairs - Wood	8	LF	6	\$94
	Storage/ Closet	817	SF	6	\$5,923
	Walls - Masonry	1,373	SF	6	\$4,319
	Walls - Plaster/Drywall	5,211	SF	6	\$14,382
<b>Kitchen</b>					
	Ceiling - Plaster/Drywall	920	SF	6	\$3,184
	Doors - Transom Window	12	SF	6	\$203
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	920	SF	6	\$2,013
	Lighting - Pendent/Surface	13	EA	7	\$0
	Storage/ Closet	203	SF	6	\$1,472
	Walls - Plaster/Drywall	1,691	SF	6	\$4,667
<b>Lunch &amp; Multipurpose Room</b>					
	Ceiling - Plaster/Drywall	1,691	SF	6	\$5,852
	Chalk Board	69	LF	4	\$6,335
	Doors - Side-lite	8	SF	6	\$134
	Doors - Transom Window	23	SF	6	\$389
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,691	SF	6	\$3,700
	Lighting - Pendent/Surface	28	EA	7	\$0
	Storage/ Closet	64	SF	6	\$464
	Walls - Plaster/Drywall	5	SF	5	\$26
	Walls - Plaster/Drywall	2,622	SF	6	\$7,236
<b>MDF_IDF</b>					
	AC Unit	1	EA	6	\$496
	Doors - Wood Doors inclu hw	1	EA	6	\$301



**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>MDF_IDF</b>					
	Finishes	414	SF	6	\$2,954
	Ventilation and Cooling	1	EA	5	\$7,815
<b>Mechanical/ Service Rooms</b>					
	Air Intake Plenums	586	SF	6	\$3,628
	Boiler Room	1,469	SF	6	\$10,524
	Coal Room	468	SF	6	\$3,353
	Interior Stairs	14	LF	6	\$126
	Janitor's Closet	33	SF	6	\$236
	Mechanical/ Service Rooms	2,163	SF	6	\$15,496
	Storage Room	394	SF	6	\$2,823
<b>Restroom</b>					
	Accessories	2,117	SF	6	\$19,526
	Ceiling - Exposed	23	SF	6	\$34
	Ceiling - Plaster/Drywall	20	SF	5	\$250
	Ceiling - Plaster/Drywall	2,074	SF	6	\$7,177
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	5	EA	6	\$1,505
	Floor - Concrete Epoxy/ Painted	68	SF	6	\$36
	Floor - Tile	153	SF	6	\$335
	Floor - Tile Ceramic/ Porcelain	1,896	SF	6	\$4,013
	Floor Drain	6	EA	6	\$6,355
	Hand Dryer	12	EA	6	\$2,761
	Lavatory	17	EA	6	\$5,433
	Lighting - Pendent/Surface	35	EA	7	\$0
	Lighting - Wall Mounted	1	EA	5	\$169
	Lighting - Wall Mounted	1	EA	6	\$124
	Partitions	21	EA	6	\$6,235
	Urinals	15	EA	6	\$5,040
	Walls - Concrete Block	2,202	SF	6	\$6,455
	Walls - Masonry	513	SF	6	\$1,614
	Walls - Plaster/Drywall	25	SF	5	\$121
	Walls - Plaster/Drywall	5,183	SF	6	\$14,358
	Water Closet	28	EA	6	\$9,407
<b>Rooms (Other Than Classrooms) Subtotal:</b>					<b>\$379,116</b>

**Building: Main**
**Category: Building Interior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Plaster/Drywall	9,958	SF	6	\$61,659
	Doors - Transom Window	120	EA	6	\$2,032
	Doors - Wood Doors include hw	12	EA	6	\$3,612
	Drinking Fountains - Double Fountain	2	EA	6	\$672
	Drinking Fountains - Single Fountain	8	EA	6	\$2,206
	Floor - Asphalt Floor	9,958	SF	6	\$15,094
	Lighting - Pendent/Surface	107	EA	7	\$0
	Lighting - Wall Mounted	4	EA	7	\$0
	Stairs - Concrete Stairs	23	LF	6	\$191
	Walls - Masonry	450	SF	6	\$1,416
	Walls - Plaster/Drywall	18,089	SF	6	\$80,189
	Walls - Structural Glazed Tile	527	SF	6	\$1,658
<b>Safety</b>					
	Camera Viewing Station	3	EA	6	\$2,048
	Security Cameras	1	EA	5	\$688
	Security Cameras	3	EA	6	\$582
<b>Stairs</b>					
	Ceiling - Plaster/Drywall	650	SF	6	\$4,759
	Floor - Asphalt	330	SF	6	\$2,558
	Handrails	318	LF	6	\$2,756
	Lighting - Pendent/Surface	6	EA	7	\$0
	Lighting - Wall Mounted	4	EA	7	\$0
	Stairs - Asphalt	112	LF	6	\$1,039
	Walls - Plaster/Drywall	10	SF	5	\$62
	Walls - Plaster/Drywall	2,978	SF	6	\$8,219
<b>Building Interior Subtotal:</b>					<b>\$191,438</b>

**Total Building Cost**
**\$4,128,738**
**Building: Linked Addition**
**Category: Building Exterior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Entrance Control - Audio and Video	1	EA	6	\$702

## Building: Linked Addition

### Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Entrance</b>					
	Exterior Doors - Exterior Steel Door	2	EA	4	\$7,645
	Exterior Doors - Exterior Steel Door	2	EA	6	\$961
	Exterior Doors - Side lite	14	EA	6	\$4,386
	Exterior Doors - Store Front	2	EA	5	\$3,672
	Exterior Doors - Store Front	18	EA	6	\$9,829
	Exterior Doors - Transom Lite	9	EA	6	\$2,820
	Exterior Stairs - Concrete	30	LF	5	\$3,287
	Power Door Operator and Controls	1	EA	6	\$0
<b>Foundation</b>					
	Foundation - Concrete	390	LF	7	\$0
	Superstructure - Steel	35,600	SF	7	\$0
<b>Lighting</b>					
	Exterior Lighting - Wall Mounted	15	EA	6	\$4,331
<b>Roof System</b>					
	Chimney - Metal Flue	40	LF	6	\$6,326
	Coping - Stone	640	LF	6	\$20,555
	Downspouts - Interior Downspouts	405	LF	5	\$89,629
	Parapet - 16" - 30" Height	18	LF	4	\$15,731
	Parapet - 16" - 30" Height	622	LF	6	\$24,852
	Roof - Modified Bitumen	16,477	SF	5	\$346,599
	Roof - Modified Bitumen	1,332	SF	6	\$18,381
	Roof Structure - Steel with Clay Tile Arch	17,809	SF	7	\$0
<b>Walls</b>					
	Exterior Walls - Brick	8	SF	5	\$190
	Exterior Walls - Brick	18,722	SF	6	\$125,831
	Exterior Walls - Prefabricated Metal Panel Wall	378	SF	6	\$2,146
	Exterior Walls - Stone-Cast	672	SF	6	\$4,517
<b>Windows</b>					
	Curtain wall - Louver	378	SF	6	\$4,238
	Guard - Guards perforated	2,268	SF	6	\$28,962
	Lintels - Steel	672	LF	6	\$19,507
	Windows - Casement Steel Double-pane	5,103	SF	6	\$38,092

**Building Exterior Subtotal:**

**\$783,190**

**Building: Linked Addition**
**Category: Electrical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Emergency System</b>					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Corridors and Stairs	7,272	SF	6	\$2,184
	Emergency A/C Power - Lunchrooms	1,245	SF	6	\$463
	Emergency A/C Power - Multipurpose Room	1,909	SF	6	\$710
	Emergency A/C Power - Students Toilets	744	SF	6	\$277
	Emergency Battery Packs - Corridors and Stairs	6	EA	6	\$1,215
	Emergency Battery Packs - Lunchrooms	2	EA	6	\$405
	Emergency Battery Packs - Multipurpose Room	2	EA	6	\$405
	Exit Signs - Corridors and Stairs	16	EA	6	\$2,396
	Exit Signs - Lunchroom	4	EA	6	\$599
	Exit Signs - Multipurpose Room	7	EA	6	\$1,048
	Security System - CCTV	35,600	SF	6	\$10,691
	Security System - Intrusion Detection	35,600	SF	6	\$9,163
<b>Main Service</b>					
	Independent Electrical Service for emergency power	1	EA	6	\$2,921
	Main Electrical Service - 1200 A 277/480/3PH	1	EA	6	\$5,346
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	1	EA	6	\$10,867
	PA System	35,600	SF	6	\$11,709
<b>Power Distribution</b>					
	Lighting and Power Panels - 100 A	2	EA	6	\$598
	Lighting and Power Panels - Above 100 A	8	EA	6	\$3,976
	Main Distribution Panels - Greater than 600 amp	1	EA	6	\$730
<b>Electrical System Subtotal:</b>					<b>\$66,111</b>

**Building: Linked Addition**
**Category: Safty System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Fire Alarm</b>					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	35,600	SF	6	\$12,727
	Fire Alarm_System	35,600	SF	6	\$17,309
	Fire Pump Controller	1	EA	6	\$1,823
<b>Pump Room Assembly</b>					
	Fire Pump - 51-75hp	1	EA	6	\$1,558

## Building: Linked Addition

### Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Pump Room Assembly</b>					
	Jockey Pump	1	EA	6	\$758
<b>Sprinkler System</b>					
	Sprinkler Heads	35,600	SF	7	\$0
	Sprinkler Piping	35,600	SF	6	\$6,618
	Wet Sprinkler System	35,600	SF	6	\$9,163
<b>Safty System Subtotal:</b>					<b>\$56,362</b>

## Building: Linked Addition

### Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Air Conditioning</b>					
	Chemical Pot Feeder	1	EA	6	\$606
	Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons	1	EA	5	\$63,450
	Glycol Feed	1	EA	6	\$490
	Pipes - Chilled Water Pipe- Steel	200	LF	6	\$378
	Pressure Fill System	1	EA	6	\$1,405
<b>Air Handling Systems</b>					
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	1	EA	6	\$3,350
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 8001-12000 cfm	2	EA	6	\$6,700
	Air Intake	3	EA	6	\$17,294
	Fan Power Box - Fan Power Box with Hot Water Coil	26	EA	6	\$12,813
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	1	EA	6	\$1,857
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	2	EA	6	\$3,714
<b>Boiler Systems</b>					
	Boiler Auxiliary- Non Condensing Hot Water - 500 - 1000 MBH	2	EA	6	\$4,093
	Chemical Pot Feeder	1	EA	5	\$1,685
	Combustion Dampers	2	EA	6	\$818
	Glycol Feed System	1	EA	5	\$1,724
	Hot Water Pump	2	EA	5	\$9,407
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - 500 - 1000 MBH	2	EA	6	\$1,996
	Water Fill System	1	EA	6	\$1,168

**Building: Linked Addition**
**Category: Mechanical System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Heating Devices</b>					
	Cabinet Heaters - With Hot Water Coil	5	EA	6	\$1,772
	Fin Tube - Hot Water	50	LF	6	\$472
<b>Mechanical Plumbing</b>					
	Chilled Water Pump - Less than 10	2	EA	6	\$2,222
	Hot Water Pump - Less than 10	6	EA	5	\$68,969
	Hydronic Supply and Return - Steel	600	LF	6	\$46,066
<b>Temperature Control</b>					
	DDC System	35,600	SF	5	\$58,544
	Thermostats - DDC	26	EA	6	\$0
<b>Ventilation</b>					
	Exhaust Fans- Indoor - 500 - 1500 CFM	1	EA	4	\$4,245
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	3	EA	6	\$1,777

**Mechanical System Subtotal:**
**\$317,014**
**Building: Linked Addition**
**Category: Plumbing System**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Hot Water</b>					
	Gas Heater - Less than 150000 BTU/HR	2	EA	5	\$4,498
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	1	EA	6	\$678
<b>Piping</b>					
	Domestic Piping-Cold Water from Risers to Fixtures	35,600	SF	6	\$7,127
	Domestic Piping-Cold Water Horizontal Lines	35,600	SF	6	\$8,654
	Domestic Piping-Cold Water Risers	35,600	SF	6	\$6,618
	Domestic Piping-Hot Water from Risers to Fixtures	35,600	SF	6	\$5,600
	Domestic Piping-Hot Water Horizontal Lines	35,600	SF	6	\$6,618
	Domestic Piping-Hot Water Return Lines	35,600	SF	6	\$5,091
	Domestic Piping-Hot Water Return Risers	35,600	SF	6	\$5,091
	Sanitary Piping	35,600	SF	6	\$32,581
	Storm Piping	35,600	SF	6	\$31,054
	Vent Piping	35,600	SF	6	\$23,927
<b>Pumps</b>					
	Pumps - Domestic Booster Pump-Duplex	1	EA	5	\$15,514

## Building: Linked Addition

### Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Pumps	Pumps - Sump-Simplex	1	EA	6	\$745

### Plumbing System Subtotal:

**\$153,797**

## Building: Linked Addition

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Computer Lab (1 room)</b>					
	Ceiling - Lay-in	8	SF	5	\$48
	Doors - Side-lite	12	SF	6	\$201
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	1,120	SF	6	\$2,450
	Lighting - Lay-in	12	EA	7	\$0
	Walls - Concrete Block	336	SF	6	\$985
	Walls - Plaster/Drywall	537	SF	6	\$1,482
	Wireless System	1	EA	6	\$372

### Kindergarten (3 rooms)

Casework	134	LF	6	\$3,384
Ceiling - Lay-in	3,390	SF	6	\$10,180
Chalk Board	60	LF	4	\$5,508
Doors - Side-lite	36	SF	6	\$602
Doors - Wood Doors inclu hw	3	EA	6	\$903
Floor - Tile	3,390	SF	6	\$7,417
Lighting - Lay-in	48	EA	7	\$0
Walls - Concrete Block	2,357	SF	6	\$6,910
Walls - Plaster/Drywall	1,032	SF	6	\$2,848
Work Sink	2	EA	5	\$3,016
Work Sink	4	EA	6	\$1,516

### Other Instructional Use (1 room)

Ceiling - Lay-in	336	SF	6	\$1,009
Doors - Side-lite	12	SF	6	\$201
Doors - Wood Doors inclu hw	1	EA	6	\$301
Floor - Tile	336	SF	6	\$735
Lighting - Lay-in	4	EA	7	\$0
Marker Board	10	LF	6	\$214
Walls - Concrete Block	690	SF	6	\$2,023

## Building: Linked Addition

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Other Instructional Use (1 room)</b>					
<b>Pre School (2 rooms)</b>					
	Casework	68	LF	6	\$1,717
	Ceiling - Lay-in	16	SF	5	\$128
	Ceiling - Lay-in	1,719	SF	6	\$5,162
	Chalk Board	30	LF	4	\$2,754
	Doors - Side-lite	24	SF	6	\$401
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,735	SF	6	\$3,796
	Lighting - Lay-in	1	EA	6	\$119
	Lighting - Lay-in	12	EA	7	\$0
	Walls - Concrete Block	1,396	SF	6	\$4,092
	Walls - Plaster/Drywall	660	SF	6	\$1,822
	Work Sink	4	EA	6	\$1,516
<b>Regular Classroom (6 rooms)</b>					
	Casework	264	LF	6	\$6,667
	Ceiling - Lay-in	24	SF	5	\$192
	Ceiling - Lay-in	5,876	SF	6	\$17,646
	Chalk Board	130	LF	4	\$11,935
	Doors - Side-lite	72	SF	6	\$1,204
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Floor - Tile	5,900	SF	6	\$12,909
	Lighting - Lay-in	80	EA	7	\$0
	Marker Board	30	LF	7	\$0
	Walls - Concrete Block	2,949	SF	6	\$8,645
	Walls - Plaster/Drywall	2,896	SF	6	\$7,993
	Work Sink	1	EA	6	\$379
<b>Special Education (2 rooms)</b>					
	Casework	46	LF	6	\$1,162
	Ceiling - Lay-in	18	SF	5	\$144
	Ceiling - Lay-in	962	SF	6	\$2,889
	Doors - Side-lite	24	SF	6	\$401
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	980	SF	6	\$2,144
	Lighting - Lay-in	12	EA	7	\$0
	Marker Board	5	LF	7	\$0
	Walls - Concrete Block	540	SF	6	\$1,583



## Building: Linked Addition

### Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Special Education (2 rooms)</b>					
	Walls - Plaster/Drywall	900	SF	6	\$2,484

### Classrooms Subtotal:

**\$155,797**

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Administrative Suites/Offices</b>					
	Ceiling - Lay-in	8	SF	5	\$64
	Ceiling - Lay-in	2,011	SF	6	\$6,039
	Doors - Side-lite	12	SF	6	\$201
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Carpet	1,449	SF	6	\$3,087
	Floor - Tile	570	SF	6	\$1,247
	Lighting - Lay-in	28	EA	7	\$0
	Power Distribution	48	EA	6	\$101,994
	Walls - Concrete Block	1,835	SF	6	\$5,379
	Walls - Plaster/Drywall	2,979	SF	6	\$8,222
	Work Sink	1	EA	5	\$1,508
	Work Sink	2	EA	6	\$1,016
<b>Kitchen</b>					
	Ceiling - Plaster/Drywall	1,194	SF	6	\$4,132
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Concrete Epoxy/ Painted	1,194	SF	6	\$632
	Lighting - Lay-in	12	EA	7	\$0
	Serving Line	14	LF	6	\$833
	Storage/ Closet	133	SF	6	\$964
	Walls - Concrete Block	1,402	SF	6	\$4,110
<b>Library</b>					
	Casework	155	LF	6	\$3,914
	Ceiling - Lay-in	36	SF	5	\$287
	Ceiling - Lay-in	2,106	SF	6	\$6,324
	Doors - Transom Window	88	SF	6	\$1,490
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	2,142	SF	6	\$4,564

## Building: Linked Addition

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Library</b>					
	Lighting - Lay-in	29	EA	7	\$0
	Walls - Concrete Block	1,450	SF	6	\$4,251
	Walls - Plaster/Drywall	508	SF	6	\$1,402
<b>Locker/Shower Room</b>					
	Accessories	34	SF	6	\$133
	Ceiling - Plaster/ Drywall	34	SF	6	\$118
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Floor - Concrete Epoxy/ Painted	34	SF	6	\$18
	Floor Drain	1	EA	6	\$1,059
	Lavatory	1	EA	6	\$320
	Lighting - Lay-in	1	EA	7	\$0
	Student Lockers - Two Tier	8	EA	6	\$371
	Walls - Concrete Block	202	SF	6	\$592
<b>Lunch &amp; Multipurpose Room</b>					
	Ceiling - Exposed	1,909	SF	6	\$2,839
	Ceiling - Lay-in	1,245	SF	6	\$3,739
	Doors - Side-lite	24	SF	6	\$401
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Tile	3,154	SF	6	\$6,901
	Lighting - Lay-in	16	EA	7	\$0
	Lighting - Pendent/Surface	24	EA	7	\$0
	Walls - Concrete Block	3,522	SF	6	\$10,444
<b>MDF_IDF</b>					
	AC Unit	1	EA	6	\$496
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Finishes	491	SF	6	\$3,504
<b>Mechanical/ Service Rooms</b>					
	Janitor's Closet	120	SF	6	\$860
	Mechanical/ Service Rooms	2,262	SF	6	\$16,206
<b>Restroom</b>					
	Accessories	973	SF	6	\$8,974
	Ceiling - Plaster/Drywall	973	SF	6	\$3,367
	Doors - Wood Doors inclu hw	10	EA	6	\$3,010
	Floor - Tile Ceramic/ Porcelain	973	SF	6	\$2,059
	Floor Drain	9	EA	6	\$9,532

**Building: Linked Addition**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Restroom</b>					
	Hand Dryer	4	EA	6	\$920
	Lavatory	14	EA	6	\$4,474
	Lighting - Lay-in	9	EA	7	\$0
	Lighting - Pendent/Surface	9	EA	7	\$0
	Partitions	10	EA	6	\$2,969
	Urinals	6	EA	6	\$2,016
	Walls - Tile Ceramic/ Porcelain	3,387	SF	6	\$7,653
	Water Closet	16	EA	6	\$5,376

**Rooms (Other Than Classrooms) Subtotal:**
**\$266,603**
**Building: Linked Addition**
**Category: Building Interior**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Corridor</b>					
	Ceiling - Lay-in	15	SF	5	\$134
	Ceiling - Lay-in	7,248	SF	6	\$21,766
	Ceiling - Plaster/Drywall	264	SF	6	\$1,635
	Doors - Side-lite	90	EA	6	\$1,505
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Doors - Store Front	8	EA	6	\$9,666
	Doors - Transom Window	64	EA	6	\$1,084
	Doors - Wood Doors include hw	3	EA	6	\$903
	Drinking Fountains - Single Fountain	4	EA	6	\$1,103
	Floor - Tile Ceramic/ Porcelain	1,699	SF	6	\$4,738
	Floor - Tile/Sheet	5,573	SF	6	\$3,028
	Lighting - Lay-in	99	EA	7	\$0
	Walls - Concrete Block	1,839	SF	6	\$5,391
	Walls - Masonry	300	SF	6	\$944
	Walls - Structural Glazed Tile	8,558	SF	6	\$26,923
<b>Safety</b>					
	Security Cameras	2	EA	5	\$1,375
	Security Cameras	1	EA	6	\$194
<b>Stairs</b>					
	Floor - Rubber Floor	46	SF	6	\$99
	Handrails	186	LF	6	\$1,612

## Building: Linked Addition

### Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Stairs</b>					
	Stairs - Rubber	78	LF	6	\$839
	Walls - Structural Glazed Tile	600	SF	6	\$1,888
<b>Vertical Conveyance</b>					
	Elevator - Elevator- Roped Holeless Hydraulic	1	EA	6	\$19,238

**Building Interior Subtotal:** **\$105,869**

**Total Building Cost** **\$1,904,743**

## SITE

### Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Civil/Drainage</b>					
	Civil/ Drainage - Catch Basin	10	EA	6	\$10,938
	Civil/ Drainage - Site Manhole	4	EA	6	\$5,971
<b>Fencing</b>					
	Fencing - New Standard Ornamental	1,210	LF	6	\$38,603
<b>Landscape</b>					
	Benches	7	EA	6	\$3,010
	Irrigation	2,800	SF	6	\$3,163
	Landscape - Hardscape- Concrete	5,397	SF	6	\$27,861
	Landscape - Hardscape- Pavers	3,085	SF	6	\$17,470
	Parkway trees	26	EA	6	\$17,161
	Planting Beds/ Area	6	SF	6	\$10
	Trash Receptacles	2	EA	6	\$625
<b>Parking Lot</b>					
	Concrete Curbs	570	LF	6	\$7,320
	Interior Plantings	20	LF	6	\$851
	Surface - Asphalt	13,387	SF	6	\$32,352
	Surface - Concrete	2,085	SF	4	\$30,770
	Trash Compactor	1	EA	6	\$0
	Trash Enclosure - Chain Links	536	SF	5	\$16,978
	Trash Enclosure - Chain Links	778	SF	6	\$13,651
	Vehicular Screening	39	LF	6	\$3,071

**SITE**
**Category: Site**

Group	Item - Type	Quantity	Unit	Rank	Cost
<b>Playground</b>					
	Equipment - Pre K 3-5	1	EA	6	\$3,546
	Equipment - School Age 5-12	1	EA	6	\$3,546
	Surface - Poured Surface	3,302	SF	6	\$24,176
<b>Sidewalks</b>					
	Sidewalks - Internal Walks	35	LF	5	\$1,744
	Sidewalks - Internal Walks	200	LF	6	\$2,402
	Sidewalks - Perimeter Sidewalks	300	SF	4	\$3,921
	Sidewalks - Perimeter Sidewalks	600	SF	6	\$1,193
<b>Signage</b>					
	Flag Pole - Building Mounted Flag Pole	1	EA	6	\$828
	Marquee - Free Standing Back lighted w/ LED	1	EA	5	\$24,459
	Monument - Building Mounted Cut Letter Sign	1	EA	6	\$0
<b>Site Subtotal:</b>					<b>\$295,619</b>
<b>Total Site Cost</b>					<b>\$295,619</b>

<b>Campus Total <sup>2 3</sup></b>	<b>\$6,329,099</b>
------------------------------------	--------------------

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

**Definitions**

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").

- 
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Regular Classroom	1st Floor	105	105	844	0	11	7	120	60	40	N	N	N
Kindergarten	Regular Classroom	1st Floor	106	106	912	0	4	12	156	78	40	N	N	N
Music Room	Regular Classroom	1st Floor	104	104	812	1	10	24	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	200	NA	355	2	5	9	84	42	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	882	0	0	7	120	60	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	203	204	812	1	8	17	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	204	203	810	0	9	16	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	205	810	0	6	23	98	49	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	206	206	800	1	7	14	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	207	208	812	0	6	17	120	60	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	208	207	796	1	7	14	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	209	209	804	1	11	8	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	210	210	810	0	3	16	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	211	NA	327	1	1	6	84	42	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	300	NA	371	0	3	18	84	42	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	301	301	817	0	5	17	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	302	302	808	0	6	17	120	60	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	303	304	813	0	4	15	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	304	303	812	0	7	23	120	60	40	N	N	N
Regular Classroom	Art Room	3rd Floor	305	305	812	1	5	18	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	306	306	806	0	4	15	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	305	821	0	3	12	120	60	40	N	Y	N
Regular Classroom	Laboratory/Shop	3rd Floor	308	307	814	0	9	27	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	309	309	811	0	1	18	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	310	310	806	3	7	22	120	60	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	311	311	371	0	2	8	84	42	40	N	N	N

## Linked Addition

Computer Lab	Computer Lab	2nd Floor	508	209	1,120	1	21	42	240	56	40	N	N	Y
Kindergarten	Kindergarten	2nd Floor	401	136	1,130	3	2	24	360	84	40	N	N	N
Kindergarten	Kindergarten	1st Floor	402	134	1,130	3	2	28	180	42	40	N	N	N
Kindergarten	Kindergarten	1st Floor	403	135	1,130	3	3	20	180	42	40	N	N	N
Other Instructional Use	Other Instructional Use	2nd Floor	501	218	336	0	0	6	80	18	40	Y	Y	N
Pre School	Pre School	1st Floor	404	124	845	2	2	20	120	28	40	N	N	N
Pre School	Pre School	1st Floor	405	123	890	1	1	28	300	70	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	500	202	890	2	2	24	180	42	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	502	217	880	2	2	24	180	42	40	N	N	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Linked Addition</b>														
Regular Classroom	Regular Classroom	2nd Floor	503	216	880	2	2	24	180	42	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	504	215	1,180	2	2	34	240	84	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	505	214	1,180	2	2	34	240	84	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	506	211	890	2	2	24	180	42	40	N	N	N
Special Education	Special Education	2nd Floor	510	204	490	2	2	24	120	128	40	N	N	N
Special Education	Special Education	2nd Floor	511	203	490	2	2	24	120	28	40	N	N	N