

Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

| Campus Summary | | | | |
|---------------------|------------------|------------------|-----------------------|--------------------|
| Building Name | Year Constructed | Number of Floors | Building Area (Sq Ft) | Assessed Need |
| Main | 1915 | 3 | 59,563 | \$2,933,520 |
| Addition | 1999 | 2 | 71,850 | \$2,209,603 |
| Field House | 0 | 1 | 1,825 | \$312,795 |
| SITE | | | | \$565,651 |
| Campus Total | | | 133,238 | \$6,021,569 |

Building: Main

Category: Building Exterior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------|---|----------|------|------|----------|
| Entrance | | | | | |
| | Entrance Control - Audio | 1 | EA | 6 | \$497 |
| | Exterior Doors - Exterior Steel Door | 9 | EA | 6 | \$4,325 |
| | Exterior Doors - Side lite | 6 | EA | 6 | \$1,880 |
| | Exterior Doors - Store Front | 22 | EA | 6 | \$12,014 |
| | Exterior Doors - Transom Lite | 18 | EA | 6 | \$5,640 |
| | Exterior Stairs - Concrete | 211 | LF | 6 | \$17,253 |
| | Stair Handrail - Steel_Stair Handrail | 50 | LF | 6 | \$433 |
| Foundation | | | | | |
| | Foundation - Masonry | 29,016 | LF | 7 | \$0 |
| | Superstructure - Steel with Clay Tile Arch | 59,563 | SF | 7 | \$0 |
| Lighting | | | | | |
| | Exterior Lighting - Parapet or Roof Mounted | 11 | EA | 6 | \$5,902 |
| | Exterior Lighting - Wall Mounted | 11 | EA | 6 | \$3,176 |
| Roof System | | | | | |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | 5 | LF | 5 | \$14,258 |

Building: Main

Category: Building Exterior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------|---|----------|------|------|-----------|
| Roof System | | | | | |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | 80 | LF | 6 | \$76,375 |
| | Chimney - Metal Flue | 7 | LF | 4 | \$11,617 |
| | Coping - Stone | 308 | LF | 6 | \$9,892 |
| | Coping - Terra Cotta | 764 | LF | 6 | \$24,538 |
| | Downspouts - Exterior Downspouts | 12 | LF | 6 | \$399 |
| | Downspouts - Interior Downspouts | 680 | LF | 6 | \$22,599 |
| | Parapet - 16" - 30" Height | 379 | LF | 6 | \$15,143 |
| | Parapet - Parapet < 16" Height | 465 | LF | 6 | \$9,908 |
| | Parapet - Parapet > 30" | 300 | LF | 6 | \$19,176 |
| | Roof - Modified Bitumen | 1,900 | SF | 5 | \$39,967 |
| | Roof - Modified Bitumen | 27,053 | SF | 6 | \$254,552 |
| | Roof Structure - Steel with Clay Tile Arch | 28,953 | SF | 7 | \$0 |
| Walls | | | | | |
| | Cheek-Wall - Concrete | 122 | SF | 6 | \$1,251 |
| | Cornice - Metal Projecting | 607 | LF | 6 | \$21,049 |
| | Exterior Walls - Brick | 33,738 | SF | 6 | \$226,753 |
| | Exterior Walls - Prefabricated Metal Panel Wall | 768 | SF | 6 | \$4,360 |
| | Exterior Walls - Stone-Cast | 7,125 | SF | 6 | \$47,887 |
| Windows | | | | | |
| | Guard - Guards perforated | 3,921 | SF | 6 | \$50,071 |
| | Lintels - Steel | 936 | LF | 6 | \$27,171 |
| | Skylite - Glass Single-Pane | 26 | SF | 6 | \$621 |
| | Windows - Sash Aluminum Double-pane | 7,853 | SF | 6 | \$58,620 |

Building Exterior Subtotal:

\$987,325

Building: Main

Category: Electrical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------|---|----------|------|------|---------|
| Emergency System | | | | | |
| | Automatic Transfer Switch | 1 | EA | 6 | \$408 |
| | Emergency A/C Power - Auditorium and Aisle Lighting | 6,620 | SF | 6 | \$3,503 |
| | Emergency A/C Power - Corridors and Stairs | 10,786 | SF | 6 | \$3,239 |
| | Emergency Battery Packs - Auditorium and Aisle Lighting | 3 | EA | 6 | \$608 |
| | Emergency Battery Packs - Corridors and Stairs | 24 | EA | 6 | \$4,860 |
| | Emergency Battery Packs - Gym | 6 | EA | 6 | \$1,215 |

Building: Main

Category: Electrical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------------------|---|----------|------|------|-----------------|
| Emergency System | | | | | |
| | Exit Signs - Auditorium | 4 | EA | 7 | \$0 |
| | Exit Signs - Corridors and Stairs | 24 | EA | 7 | \$0 |
| | Exit Signs - Gym | 3 | EA | 7 | \$0 |
| | Security System - CCTV | 59,563 | SF | 6 | \$17,887 |
| | Security System - Intrusion Detection | 59,563 | SF | 6 | \$15,332 |
| Main Service | | | | | |
| | Main Electrical Service - 2000 A 120/208/3PH | 1 | EA | 6 | \$8,232 |
| | PA System | 59,563 | SF | 6 | \$19,590 |
| Power Distribution | | | | | |
| | Lighting and Power Panels - 100 A | 3 | EA | 4 | \$14,548 |
| | Lighting and Power Panels - 100 A | 8 | EA | 6 | \$2,393 |
| | Lighting and Power Panels - Above 100 A | 9 | EA | 7 | \$0 |
| | Main Distribution Panels - 400 - 600 amp | 2 | EA | 7 | \$0 |
| | Main Distribution Panels - Greater than 600 amp | 1 | EA | 7 | \$0 |
| | Transformers - 277/480 - 120/208 | 1 | EA | 6 | \$1,265 |
| Electrical System Subtotal: | | | | | \$93,078 |

Building: Main

Category: Safty System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------------|--------------------------|----------|------|------|-----------------|
| Fire Alarm | | | | | |
| | Fire Alarm Panel | 1 | EA | 6 | \$6,406 |
| | Fire Alarm Strobe Lights | 59,563 | SF | 6 | \$21,294 |
| | Fire Alarm_System | 59,563 | SF | 7 | \$0 |
| Safty System Subtotal: | | | | | \$27,700 |

Building: Main

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------------------|---|----------|------|------|---------|
| Air Conditioning | | | | | |
| | Condensing Unit- Roof Mounted - 5-10 tons | 1 | EA | 5 | \$9,590 |
| Air Handling Systems | | | | | |
| | Air Handling Unit- Built Up- Single Zone- Steam Coils - 4000 - 8000 cfm | 1 | EA | 6 | \$3,321 |

Building: Main

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------------------|---|----------|------|------|-----------|
| Air Handling Systems | | | | | |
| | Air Handling Unit- Built Up-Multi Zone- Steam Coils - 25001 - 35000 cfm | 2 | EA | 6 | \$13,022 |
| | Air Intake | 1 | EA | 6 | \$5,765 |
| | Air Intake | 2 | EA | 7 | \$0 |
| | Auxiliaries - 25001 - 35000 cfm | 2 | EA | 6 | \$13,022 |
| | Auxiliaries - 4000 - 8000 cfm | 1 | EA | 6 | \$3,321 |
| | Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM | 2 | EA | 6 | \$3,714 |
| | Return Duct Work - Indoor- Vertical Shaft and Ducts | 100 | LF | 7 | \$0 |
| | Return Duct Work - Masonry and Ducts- Missing or Existing Shaft | 2 | LF | 7 | \$0 |
| | Zone Dampers | 4 | EA | 5 | \$7,654 |
| | Zone Dampers | 29 | EA | 6 | \$24,158 |
| Boiler Systems | | | | | |
| | Boiler Auxiliary- Non Condensing Steam Boiler - Less than 50 HP | 1 | EA | 6 | \$2,046 |
| | Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 101 - 150 HP | 2 | EA | 6 | \$5,091 |
| | Chemical Feed System | 2 | EA | 6 | \$2,156 |
| | Combustion Dampers | 3 | EA | 6 | \$1,227 |
| | Condensate Pump | 1 | EA | 6 | \$2,021 |
| | Feed Water Pumps and Tank | 1 | EA | 6 | \$2,545 |
| | Non Condensing- Cast Iron- Force Draft- Steam Boiler - Less than 50 HP | 1 | EA | 6 | \$2,046 |
| | Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 101 - 150 HP | 2 | EA | 6 | \$5,091 |
| | Piping - Condensate Pipe- Steel | 550 | LF | 6 | \$1,038 |
| | Piping - Steam Pipe- Steel | 550 | LF | 6 | \$1,038 |
| | Steam Traps | 20 | EA | 5 | \$26,298 |
| Gas Booster | | | | | |
| | Gas Booster | 1 | EA | 6 | \$499 |
| Heating Devices | | | | | |
| | Radiators - Steam | 3 | EA | 5 | \$5,026 |
| | Unit Heater - Electric | 11 | EA | 6 | \$3,056 |
| | Unit Heater - Gas | 1 | EA | 6 | \$278 |
| | Unit Heater - Steam | 1 | EA | 6 | \$278 |
| | Wall Heater - Electric | 3 | EA | 7 | \$0 |
| Temperature Control | | | | | |
| | Electric Thermostat | 1 | EA | 6 | \$0 |
| | Hybrid Pneumatic/DDC System | 59,563 | SF | 5 | \$205,272 |
| | Thermostats - Pneumatic | 13 | EA | 4 | \$9,584 |
| | Thermostats - Pneumatic | 18 | EA | 6 | \$0 |

Building: Main

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------|--|----------|------|------|---------|
| Ventilation | | | | | |
| | Exhaust Fans- Roof Mounted - 1501 - 8000 CFM | 2 | EA | 6 | \$1,185 |
| | Exhaust Fans- Roof Mounted - Greater than 8000 CFM | 1 | EA | 6 | \$592 |
| | Roof Mounted Duct Work | 20 | LF | 6 | \$7,580 |

Mechanical System Subtotal: **\$367,516**

Building: Main

Category: Plumbing System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------|--|----------|------|------|----------|
| Hot Water | | | | | |
| | Gas Heater - 150000 - 300000 BTU/HR | 1 | EA | 6 | \$310 |
| Piping | | | | | |
| | Domestic Piping-Cold Water from Risers to Fixtures | 59,563 | SF | 6 | \$11,925 |
| | Domestic Piping-Cold Water Horizontal Lines | 59,563 | SF | 6 | \$14,480 |
| | Domestic Piping-Cold Water Risers | 59,563 | SF | 6 | \$11,073 |
| | Domestic Piping-Hot Water from Risers to Fixtures | 59,563 | SF | 6 | \$9,369 |
| | Domestic Piping-Hot Water Horizontal Lines | 59,563 | SF | 6 | \$11,073 |
| | Domestic Piping-Hot Water Return Lines | 59,563 | SF | 6 | \$8,518 |
| | Domestic Piping-Hot Water Return Risers | 59,563 | SF | 6 | \$8,518 |
| | Sanitary Piping | 59,563 | SF | 6 | \$54,512 |
| | Storm Piping | 59,563 | SF | 6 | \$51,957 |
| | Vent Piping | 59,563 | SF | 6 | \$40,032 |
| Pumps | | | | | |
| | Pumps - Domestic Booster Pump-Duplex | 1 | EA | 6 | \$1,977 |

Plumbing System Subtotal: **\$223,742**

Building: Main

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|----------------------------|------------------------|----------|------|------|---------|
| Dance Room (1 room) | | | | | |
| | AC Units | 1 | EA | 6 | \$496 |
| | Casework | 9 | LF | 6 | \$227 |
| | Ceiling - Lay-in | 866 | SF | 6 | \$2,601 |
| | Doors - Transom Window | 12 | SF | 6 | \$203 |

Building: Main

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------------------|-----------------------------|----------|------|------|-----------|
| Dance Room (1 room) | | | | | |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Wood | 866 | SF | 6 | \$6,105 |
| | Lighting - Lay-in | 14 | EA | 7 | \$0 |
| | Marker Board | 24 | LF | 7 | \$0 |
| | Wall Mirrors | 2 | EA | 7 | \$0 |
| | Walls - Plaster/Drywall | 1,687 | SF | 6 | \$4,656 |
| Kindergarten (2 rooms) | | | | | |
| | AC Units | 2 | EA | 6 | \$991 |
| | Casework | 9 | LF | 6 | \$227 |
| | Ceiling - Lay-in | 1,854 | SF | 6 | \$5,568 |
| | Chalk Board | 4 | LF | 4 | \$367 |
| | Doors - Side-lite | 14 | SF | 6 | \$234 |
| | Doors - Transom Window | 9 | SF | 6 | \$152 |
| | Doors - Wood Doors inclu hw | 2 | EA | 6 | \$602 |
| | Floor - Tile | 434 | SF | 6 | \$950 |
| | Floor - Wood | 1,420 | SF | 6 | \$10,011 |
| | Lighting - Lay-in | 40 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 1 | EA | 7 | \$0 |
| | Marker Board | 16 | LF | 7 | \$0 |
| | Storage/ Closet | 20 | SF | 6 | \$145 |
| | Walls - Masonry | 898 | SF | 6 | \$2,825 |
| | Walls - Plaster/Drywall | 18 | SF | 5 | \$92 |
| | Walls - Plaster/Drywall | 2,429 | SF | 6 | \$6,704 |
| Regular Classroom (24 rooms) | | | | | |
| | AC Units | 25 | EA | 6 | \$12,390 |
| | Casework | 236 | LF | 6 | \$5,960 |
| | Ceiling - Lay-in | 140 | SF | 5 | \$971 |
| | Ceiling - Lay-in | 20,487 | SF | 6 | \$61,522 |
| | Chalk Board | 134 | LF | 4 | \$12,302 |
| | Doors - Side-lite | 28 | SF | 6 | \$468 |
| | Doors - Transom Window | 357 | SF | 6 | \$6,044 |
| | Doors - Transom Window | 12 | SF | 7 | \$0 |
| | Doors - Wood Doors inclu hw | 25 | EA | 6 | \$7,525 |
| | Floor - Carpet | 830 | SF | 6 | \$1,768 |
| | Floor - Tile | 2,736 | SF | 6 | \$5,986 |
| | Floor - Wood | 17,061 | SF | 6 | \$120,278 |

Building: Main

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------------------|-----------------------------|----------|------|------|----------|
| Regular Classroom (24 rooms) | | | | | |
| | Lighting - Lay-in | 345 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 1 | EA | 7 | \$0 |
| | Marker Board | 476 | LF | 7 | \$0 |
| | Walls - Plaster/Drywall | 5 | SF | 4 | \$74 |
| | Walls - Plaster/Drywall | 246 | SF | 5 | \$1,173 |
| | Walls - Plaster/Drywall | 27,351 | SF | 6 | \$75,488 |
| | Work Sink | 3 | EA | 6 | \$1,137 |
| Science (1 room) | | | | | |
| | AC Units | 1 | EA | 6 | \$496 |
| | Casework | 38 | LF | 6 | \$960 |
| | Ceiling - Lay-in | 909 | SF | 6 | \$2,730 |
| | Doors - Transom Window | 12 | SF | 6 | \$203 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Wood | 909 | SF | 6 | \$6,408 |
| | Lighting - Lay-in | 21 | EA | 7 | \$0 |
| | Marker Board | 24 | LF | 7 | \$0 |
| | Walls - Plaster/Drywall | 2 | SF | 5 | \$10 |
| | Walls - Plaster/Drywall | 1,148 | SF | 6 | \$3,168 |
| Special Program (1 room) | | | | | |
| | AC Units | 1 | EA | 6 | \$496 |
| | Ceiling - Lay-in | 4 | SF | 5 | \$32 |
| | Ceiling - Lay-in | 329 | SF | 6 | \$988 |
| | Doors - Transom Window | 9 | SF | 6 | \$152 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Carpet | 333 | SF | 6 | \$710 |
| | Lighting - Pendent/Surface | 6 | EA | 7 | \$0 |
| | Walls - Plaster/Drywall | 46 | SF | 5 | \$235 |
| | Walls - Plaster/Drywall | 890 | SF | 6 | \$2,456 |

Classrooms Subtotal: **\$376,189**

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------------------------|-------------|----------|------|------|-------|
| Administrative Suites/Offices | | | | | |
| | AC Unit | 2 | EA | 6 | \$991 |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------------------------|--------------------------------------|----------|------|------|-----------|
| Administrative Suites/Offices | | | | | |
| | Ceiling - Lay-in | 1,128 | SF | 6 | \$3,387 |
| | Ceiling - Plaster/Drywall | 26 | SF | 4 | \$566 |
| | Ceiling - Plaster/Drywall | 8 | SF | 5 | \$100 |
| | Ceiling - Plaster/Drywall | 705 | SF | 6 | \$2,440 |
| | Doors - Side-lite | 10 | SF | 6 | \$167 |
| | Doors - Transom Window | 18 | SF | 6 | \$305 |
| | Doors - Wood Doors inclu hw | 6 | EA | 6 | \$1,806 |
| | Floor - Carpet | 571 | SF | 6 | \$1,217 |
| | Floor - Tile | 692 | SF | 6 | \$1,514 |
| | Floor - Wood | 604 | SF | 6 | \$4,258 |
| | Lighting - Lay-in | 11 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 10 | EA | 7 | \$0 |
| | Lighting - Wall Mounted | 1 | EA | 6 | \$124 |
| | Power Distribution | 44 | EA | 7 | \$0 |
| | Walls - Plaster/Drywall | 5 | SF | 4 | \$74 |
| | Walls - Plaster/Drywall | 376 | SF | 5 | \$2,830 |
| | Walls - Plaster/Drywall | 4,003 | SF | 6 | \$11,048 |
| Gymnasia | | | | | |
| | Ceiling - Plaster/Drywall | 6 | SF | 4 | \$202 |
| | Ceiling - Plaster/Drywall | 6,594 | SF | 6 | \$36,398 |
| | Doors - Transom Window | 12 | SF | 5 | \$508 |
| | Doors - Transom Window | 108 | SF | 6 | \$1,829 |
| | Doors - Wood Doors inclu hw | 10 | EA | 6 | \$3,010 |
| | Floor - Wood | 6,022 | SF | 6 | \$42,454 |
| | Lighting - Metal Halide/Sodium Vapor | 28 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 21 | EA | 7 | \$0 |
| | Main Floor Seating | 320 | EA | 6 | \$55,653 |
| | Scoreboards | 1 | EA | 6 | \$2,244 |
| | Sound System | 1 | EA | 6 | \$41,654 |
| | Stage | 578 | SF | 6 | \$3,339 |
| | Stage Curtain | 2 | EA | 6 | \$0 |
| | Stage Lift | 1 | EA | 6 | \$6,510 |
| | Stage Lighting System | 1 | EA | 4 | \$287,931 |
| | Stage-Stairs - Wood | 10 | LF | 6 | \$117 |
| | Storage/ Closet | 56 | SF | 6 | \$406 |
| | Walls - Plaster/Drywall | 6,686 | SF | 6 | \$18,453 |

Building: Main

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|----------------------------------|---------------------------------|----------|------|------|----------|
| MDF_IDF | | | | | |
| | AC Unit | 1 | EA | 6 | \$496 |
| | Doors - Steel Doors incl hw | 1 | EA | 6 | \$301 |
| | Finishes | 527 | SF | 6 | \$3,761 |
| Mechanical/ Service Rooms | | | | | |
| | Boiler Room | 1,790 | SF | 6 | \$12,824 |
| | Coal Room | 468 | SF | 6 | \$3,353 |
| | Janitor's Closet | 72 | SF | 6 | \$516 |
| | Mechanical/ Service Rooms | 3,326 | SF | 6 | \$23,828 |
| Restroom | | | | | |
| | Accessories | 1,726 | SF | 6 | \$15,920 |
| | Ceiling - Lay-in | 38 | SF | 6 | \$114 |
| | Ceiling - Plaster/Drywall | 158 | SF | 4 | \$2,777 |
| | Ceiling - Plaster/Drywall | 135 | SF | 5 | \$1,271 |
| | Ceiling - Plaster/Drywall | 1,395 | SF | 6 | \$4,828 |
| | Doors - Wood Doors inclu hw | 17 | EA | 6 | \$5,117 |
| | Floor - Tile | 314 | SF | 6 | \$687 |
| | Floor - Tile Ceramic/ Porcelain | 1,412 | SF | 6 | \$2,988 |
| | Floor Drain | 7 | EA | 6 | \$7,414 |
| | Lavatory | 22 | EA | 6 | \$7,031 |
| | Lighting - Lay-in | 1 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 33 | EA | 7 | \$0 |
| | Partitions | 24 | EA | 6 | \$7,126 |
| | Urinals | 14 | EA | 6 | \$4,704 |
| | Walls - Plaster/Drywall | 503 | SF | 5 | \$3,452 |
| | Walls - Plaster/Drywall | 3,153 | SF | 6 | \$8,702 |
| | Walls - Structural Glazed Tile | 2,724 | SF | 6 | \$8,570 |
| | Water Closet | 30 | EA | 6 | \$10,079 |

Rooms (Other Than Classrooms) Subtotal: \$667,392

Building: Main

Category: Building Interior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------|---------------------------|----------|------|------|----------|
| Corridor | | | | | |
| | Ceiling - Lay-in | 9,265 | SF | 6 | \$27,823 |
| | Ceiling - Plaster/Drywall | 80 | SF | 5 | \$1,396 |

Building: Main

Category: Building Interior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------------------|--------------------------------------|----------|------|------|------------------|
| Corridor | | | | | |
| | Ceiling - Plaster/Drywall | 820 | SF | 6 | \$5,077 |
| | Doors - Steel Doors incl hw | 3 | EA | 6 | \$903 |
| | Doors - Wood Doors include hw | 15 | EA | 6 | \$4,515 |
| | Drinking Fountains - Double Fountain | 3 | EA | 6 | \$1,008 |
| | Drinking Fountains - Single Fountain | 9 | EA | 6 | \$2,482 |
| | Floor - Asphalt Floor | 9,443 | SF | 6 | \$14,314 |
| | Floor - Terrazzo | 410 | SF | 6 | \$3,442 |
| | Floor - Tile/Sheet | 633 | SF | 6 | \$344 |
| | Lighting - Lay-in | 87 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 14 | EA | 7 | \$0 |
| | Stairs - Concrete Stairs | 16 | LF | 6 | \$133 |
| | Student Lockers - One Tier | 18 | EA | 6 | \$1,671 |
| | Student Lockers - Two Tiers | 332 | EA | 6 | \$15,411 |
| | Walls - Plaster/Drywall | 20,221 | SF | 6 | \$89,640 |
| | Walls - Structural Glazed Tile | 612 | SF | 6 | \$1,925 |
| Safety | | | | | |
| | Security Cameras | 2 | EA | 6 | \$388 |
| Stairs | | | | | |
| | Ceiling - Plaster/Drywall | 80 | SF | 6 | \$586 |
| | Floor - Asphalt | 300 | SF | 6 | \$2,325 |
| | Handrails | 324 | LF | 6 | \$2,808 |
| | Lighting - Lay-in | 6 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 4 | EA | 7 | \$0 |
| | Stairs - Asphalt | 114 | LF | 6 | \$1,058 |
| | Walls - Plaster/Drywall | 4,830 | SF | 6 | \$13,330 |
| Building Interior Subtotal: | | | | | \$190,577 |

Total Building Cost

\$2,933,520

Building: Addition

Category: Building Exterior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------|--------------------------------------|----------|------|------|---------|
| Entrance | | | | | |
| | Exterior Doors - Exterior Steel Door | 2 | EA | 5 | \$2,683 |

Building: Addition

Category: Building Exterior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------|---|----------|------|------|-----------|
| Entrance | | | | | |
| | Exterior Doors - Exterior Steel Door | 3 | EA | 6 | \$1,442 |
| | Exterior Doors - Store Front | 6 | EA | 6 | \$3,276 |
| | Exterior Stairs - Concrete | 75 | LF | 6 | \$6,133 |
| | Ramp Handrail - Steel_Ramp Handrail | 15 | LF | 6 | \$130 |
| | Ramps - Concrete | 30 | LF | 6 | \$4,507 |
| | Stair Handrail - Steel_Stair Handrail | 25 | LF | 6 | \$217 |
| Foundation | | | | | |
| | Foundation - Concrete | 835 | LF | 7 | \$0 |
| | Superstructure - Metal Deck/ Concrete Topping | 71,850 | SF | 7 | \$0 |
| Lighting | | | | | |
| | Exterior Lighting - Wall Mounted | 22 | EA | 6 | \$6,352 |
| Roof System | | | | | |
| | Chimney - Metal Flue | 3 | LF | 6 | \$474 |
| | Coping - Stone | 1,028 | LF | 6 | \$33,017 |
| | Downspouts - Interior Downspouts | 560 | LF | 6 | \$18,611 |
| | Parapet - 16" - 30" Height | 880 | LF | 6 | \$35,160 |
| | Parapet - Parapet > 30" | 35 | LF | 4 | \$37,604 |
| | Parapet - Parapet > 30" | 148 | LF | 6 | \$9,460 |
| | Roof - Modified Bitumen | 75 | SF | 5 | \$2,142 |
| | Roof - Modified Bitumen | 26,978 | SF | 6 | \$253,847 |
| | Roof Structure - Steel / Metal Deck/ Concrete Topping | 27,053 | SF | 7 | \$0 |
| Walls | | | | | |
| | Exterior Walls - Brick | 31,159 | SF | 6 | \$209,420 |
| | Exterior Walls - Stone-Cast | 11,016 | SF | 6 | \$74,039 |
| Windows | | | | | |
| | Guard - Guards perforated | 1,465 | SF | 6 | \$18,708 |
| | Lintels - Steel | 782 | LF | 7 | \$0 |
| | Windows - Sash Aluminum Double-pane | 5,660 | SF | 6 | \$42,250 |

Building Exterior Subtotal: \$759,470

Building: Addition

Category: Electrical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------|-------------|----------|------|------|------|
|-------|-------------|----------|------|------|------|

Building: Addition

Category: Electrical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------------------|--|----------|------|------|-----------------|
| Emergency System | | | | | |
| | Automatic Transfer Switch | 1 | EA | 6 | \$408 |
| | Emergency A/C Power - Corridors and Stairs | 13,400 | SF | 6 | \$4,024 |
| | Emergency A/C Power - Multipurpose Room | 6,280 | SF | 6 | \$2,335 |
| | Emergency Battery Packs - Corridors and Stairs | 20 | EA | 7 | \$0 |
| | Emergency Battery Packs - Multipurpose Room | 8 | EA | 7 | \$0 |
| | Emergency Battery Packs - Students Toilets | 3 | EA | 7 | \$0 |
| | Exit Signs - Corridors and Stairs | 20 | EA | 7 | \$0 |
| | Exit Signs - Multipurpose Room | 8 | EA | 7 | \$0 |
| | Security System - CCTV | 71,850 | SF | 6 | \$21,577 |
| | Security System - Intrusion Detection | 71,850 | SF | 6 | \$18,494 |
| Main Service | | | | | |
| | Independent Electrical Service for emergency power | 1 | EA | 7 | \$0 |
| | Main Electrical Service - 2000 A 277/480/3PH | 1 | EA | 6 | \$8,662 |
| | PA System | 71,850 | SF | 6 | \$23,631 |
| Power Distribution | | | | | |
| | Lighting and Power Panels - 100 A | 1 | EA | 7 | \$0 |
| | Lighting and Power Panels - Above 100 A | 13 | EA | 7 | \$0 |
| | Main Distribution Panels - 400 - 600 amp | 2 | EA | 7 | \$0 |
| | Main Distribution Panels - Greater than 600 amp | 2 | EA | 7 | \$0 |
| | Main Distribution Panels - Less than 400 amp | 2 | EA | 7 | \$0 |
| | Transformers - 277/480 - 120/208 | 4 | EA | 6 | \$5,060 |
| Electrical System Subtotal: | | | | | \$84,191 |

Building: Addition

Category: Safty System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|---------------------------|--------------------------|----------|------|------|----------|
| Fire Alarm | | | | | |
| | Fire Alarm Panel | 1 | EA | 6 | \$6,406 |
| | Fire Alarm Strobe Lights | 71,850 | SF | 6 | \$25,686 |
| | Fire Alarm_System | 71,850 | SF | 7 | \$0 |
| | Fire Pump Controller | 1 | EA | 7 | \$0 |
| Pump Room Assembly | | | | | |
| | Fire Pump - 25-50 hp | 1 | EA | 6 | \$1,558 |
| | Jockey Pump | 1 | EA | 6 | \$758 |

Building: Addition

Category: Safty System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------|----------------------|----------|------|------|------|
| Sprinkler System | | | | | |
| | Sprinkler Heads | 71,850 | SF | 7 | \$0 |
| | Sprinkler Piping | 71,850 | SF | 7 | \$0 |
| | Wet Sprinkler System | 71,850 | SF | 7 | \$0 |

Safty System Subtotal:

\$34,408

Building: Addition

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------|---|----------|------|------|---------|
| Air Conditioning | | | | | |
| | Chemical Pot Feeder | 1 | EA | 6 | \$606 |
| | Chiller-Air Cooled-Screw Type-Roof Mounted - 101 - 200 tons | 2 | EA | 7 | \$0 |
| | Condensing Unit- Roof Mounted - Less than 5 tons | 1 | EA | 6 | \$3,334 |
| | Glycol Feed | 1 | EA | 6 | \$490 |
| | Pipes - Chilled Water Pipe- Galvanized | 600 | LF | 6 | \$1,133 |
| | Pressure Fill System | 1 | EA | 6 | \$1,405 |

Air Handling Systems

| | | | | |
|--|----|----|---|----------|
| Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm | 1 | EA | 6 | \$3,350 |
| Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm | 1 | EA | 6 | \$3,350 |
| Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Greater than 30,000 cfm | 1 | EA | 6 | \$3,350 |
| Air Intake | 3 | EA | 6 | \$17,294 |
| Fan Coil Unit- Celing Mounted - Hot Water-Heating | 6 | EA | 6 | \$9,625 |
| Fan Power Box - Fan Power Box with Hot Water Coil | 26 | EA | 5 | \$40,965 |
| Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM | 2 | EA | 6 | \$3,714 |
| Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM | 1 | EA | 6 | \$1,857 |
| Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM | 1 | EA | 6 | \$2,433 |
| Make Up Air Unit- Indoor Mounted- Hot Water Coils - Less than 6000 cfm | 1 | EA | 6 | \$3,350 |
| VAV Box | 39 | EA | 6 | \$10,887 |
| Zone Dampers | 17 | EA | 6 | \$14,162 |

Boiler Systems

| | | | | |
|--|---|----|---|---------|
| Boiler Auxiliary- Non Condensing Hot Water - 3001 - 4000 MBH | 3 | EA | 6 | \$6,139 |
| Chemical Pot Feeder | 1 | EA | 6 | \$725 |
| Combustion Dampers | 1 | EA | 5 | \$2,552 |
| Combustion Dampers | 1 | EA | 6 | \$409 |

Building: Addition

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------------------|--|----------|------|------|------------------|
| Boiler Systems | | | | | |
| | Glycol Feed System | 1 | EA | 6 | \$539 |
| | Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - 3001 - 4000 MBH | 3 | EA | 6 | \$2,994 |
| | Water Fill System | 1 | EA | 6 | \$1,168 |
| Gas Booster | | | | | |
| | Gas Booster | 1 | EA | 6 | \$499 |
| Heating Devices | | | | | |
| | Radiators - Hot Water | 3 | EA | 6 | \$833 |
| | Unit Heater - Electric | 2 | EA | 6 | \$556 |
| | Unit Heater - Hot Water | 8 | EA | 6 | \$2,233 |
| Mechanical Plumbing | | | | | |
| | Chilled Water Pump - 10 - 20 HP | 3 | EA | 6 | \$3,727 |
| | Hot Water Pump - 10 - 20 HP | 2 | EA | 6 | \$2,485 |
| | Hydronic Supply and Return - Galvanized | 1,000 | LF | 6 | \$77,320 |
| Temperature Control | | | | | |
| | DDC System | 71,850 | SF | 6 | \$41,098 |
| | Thermostats - DDC | 56 | EA | 6 | \$0 |
| Ventilation | | | | | |
| | Exhaust Fans- Indoor - 500 - 1500 CFM | 4 | EA | 6 | \$2,370 |
| | Exhaust Fans- Roof Mounted - 1501 - 8000 CFM | 1 | EA | 6 | \$592 |
| | Exhaust Fans- Roof Mounted - 500 - 1500 CFM | 2 | EA | 6 | \$1,185 |
| | Exhaust Fans- Roof Mounted - Less than 500 CFM | 1 | EA | 6 | \$296 |
| | Type I Exhaust Hood- Kitchen | 1 | EA | 7 | \$0 |
| | Type II Exhaust Hood- Warming Kitchen | 2 | EA | 7 | \$0 |
| Mechanical System Subtotal: | | | | | \$269,023 |

Building: Addition

Category: Plumbing System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------|--|----------|------|------|-------|
| Hot Water | | | | | |
| | Gas Heater - 300001 - 600000 BTU/HR | 2 | EA | 6 | \$620 |
| | Hot Water Storage Tank_Gas - 201 - 500 Gallons | 1 | EA | 7 | \$0 |

Building: Addition

Category: Plumbing System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|---------------|--|----------|------|------|----------|
| Piping | | | | | |
| | Domestic Piping-Cold Water from Risers to Fixtures | 71,850 | SF | 6 | \$14,384 |
| | Domestic Piping-Cold Water Horizontal Lines | 71,850 | SF | 6 | \$17,467 |
| | Domestic Piping-Cold Water Risers | 71,850 | SF | 6 | \$13,357 |
| | Domestic Piping-Hot Water from Risers to Fixtures | 71,850 | SF | 6 | \$11,302 |
| | Domestic Piping-Hot Water Horizontal Lines | 71,850 | SF | 6 | \$13,357 |
| | Domestic Piping-Hot Water Return Lines | 71,850 | SF | 6 | \$10,275 |
| | Domestic Piping-Hot Water Return Risers | 71,850 | SF | 6 | \$10,275 |
| | Sanitary Piping | 71,850 | SF | 6 | \$65,757 |
| | Storm Piping | 71,850 | SF | 6 | \$62,675 |
| | Vent Piping | 71,850 | SF | 6 | \$48,290 |
| Pumps | | | | | |
| | Pumps - Domestic Booster Pump-Duplex | 1 | EA | 6 | \$1,977 |
| | Pumps - Sump-Simplex | 1 | EA | 6 | \$745 |

Plumbing System Subtotal:

\$270,480

Building: Addition

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------------|-----------------------------|----------|------|------|---------|
| Art Room (1 room) | | | | | |
| | Casework | 56 | LF | 6 | \$1,414 |
| | Ceiling - Lay-in | 1 | SF | 5 | \$8 |
| | Ceiling - Lay-in | 1,052 | SF | 6 | \$3,159 |
| | Doors - Side-lite | 6 | SF | 6 | \$100 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Tile | 1,053 | SF | 6 | \$2,304 |
| | Lighting - Lay-in | 12 | EA | 7 | \$0 |
| | Marker Board | 18 | LF | 7 | \$0 |
| | Storage/ Closet | 156 | SF | 6 | \$1,131 |
| | Walls - Concrete Block | 767 | SF | 6 | \$2,248 |
| | Walls - Plaster/Drywall | 502 | SF | 6 | \$1,385 |
| | Work Sink | 2 | EA | 6 | \$758 |
| Computer Lab (1 room) | | | | | |
| | Casework | 6 | LF | 6 | \$152 |
| | Ceiling - Lay-in | 6 | SF | 5 | \$48 |
| | Ceiling - Lay-in | 1,013 | SF | 6 | \$3,042 |

Building: Addition

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------------|-----------------------------|----------|------|------|---------|
| Computer Lab (1 room) | | | | | |
| | Charging Station | 12 | EA | 6 | \$5,816 |
| | Doors - Side-lite | 6 | SF | 6 | \$100 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Tile | 1,019 | SF | 6 | \$2,229 |
| | Lighting - Lay-in | 12 | EA | 7 | \$0 |
| | Marker Board | 24 | LF | 7 | \$0 |
| | Storage/ Closet | 24 | SF | 6 | \$174 |
| | Walls - Concrete Block | 707 | SF | 6 | \$2,073 |
| | Walls - Plaster/Drywall | 579 | SF | 6 | \$1,598 |
| | Wireless System | 1 | EA | 6 | \$372 |
| Kindergarten (2 rooms) | | | | | |
| | Casework | 132 | LF | 6 | \$3,334 |
| | Ceiling - Lay-in | 30 | SF | 5 | \$239 |
| | Ceiling - Lay-in | 2,166 | SF | 6 | \$6,504 |
| | Chalk Board | 24 | LF | 4 | \$2,203 |
| | Doors - Side-lite | 12 | SF | 6 | \$201 |
| | Doors - Wood Doors inclu hw | 2 | EA | 6 | \$602 |
| | Floor - Tile | 2,196 | SF | 6 | \$4,805 |
| | Lighting - Lay-in | 34 | EA | 7 | \$0 |
| | Storage/ Closet | 86 | SF | 6 | \$624 |
| | Walls - Concrete Block | 8 | SF | 5 | \$113 |
| | Walls - Concrete Block | 1,752 | SF | 6 | \$5,136 |
| | Walls - Plaster/Drywall | 504 | SF | 6 | \$1,391 |
| | Work Sink | 4 | EA | 6 | \$1,516 |
| Music Room (1 room) | | | | | |
| | Casework | 48 | LF | 6 | \$1,212 |
| | Ceiling - Lay-in | 848 | SF | 6 | \$2,547 |
| | Chalk Board | 18 | LF | 4 | \$1,653 |
| | Doors - Side-lite | 6 | SF | 6 | \$100 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Tile | 848 | SF | 6 | \$1,855 |
| | Lighting - Lay-in | 12 | EA | 7 | \$0 |
| | Walls - Concrete Block | 1,125 | SF | 6 | \$3,298 |
| | Work Sink | 1 | EA | 6 | \$379 |
| Pre School (3 rooms) | | | | | |
| | Casework | 198 | LF | 6 | \$5,000 |

Building: Addition

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------------------|-----------------------------|----------|------|------|----------|
| Pre School (3 rooms) | | | | | |
| | Ceiling - Lay-in | 3,244 | SF | 6 | \$9,742 |
| | Chalk Board | 24 | LF | 4 | \$2,203 |
| | Doors - Side-lite | 18 | SF | 6 | \$301 |
| | Doors - Wood Doors inclu hw | 3 | EA | 6 | \$903 |
| | Floor - Tile | 3,244 | SF | 6 | \$7,098 |
| | Lighting - Lay-in | 51 | EA | 7 | \$0 |
| | Storage/ Closet | 129 | SF | 6 | \$935 |
| | Walls - Concrete Block | 1,996 | SF | 6 | \$5,851 |
| | Walls - Plaster/Drywall | 5 | SF | 5 | \$26 |
| | Walls - Plaster/Drywall | 1,255 | SF | 6 | \$3,464 |
| | Work Sink | 6 | EA | 6 | \$2,274 |
| Regular Classroom (11 rooms) | | | | | |
| | Casework | 426 | LF | 6 | \$10,758 |
| | Ceiling - Lay-in | 37 | SF | 5 | \$295 |
| | Ceiling - Lay-in | 9,623 | SF | 6 | \$28,898 |
| | Chalk Board | 192 | LF | 4 | \$17,627 |
| | Doors - Side-lite | 60 | SF | 6 | \$1,003 |
| | Doors - Wood Doors inclu hw | 11 | EA | 6 | \$3,311 |
| | Floor - Tile | 9,660 | SF | 6 | \$21,135 |
| | Lighting - Lay-in | 132 | EA | 7 | \$0 |
| | Marker Board | 6 | LF | 7 | \$0 |
| | Storage/ Closet | 841 | SF | 6 | \$6,097 |
| | Walls - Concrete Block | 14 | SF | 5 | \$197 |
| | Walls - Concrete Block | 9,044 | SF | 6 | \$26,512 |
| | Walls - Plaster/Drywall | 3,772 | SF | 6 | \$10,410 |
| | Work Sink | 11 | EA | 6 | \$4,169 |
| Science Lab Level 1 (1 room) | | | | | |
| | Casework | 56 | LF | 6 | \$1,414 |
| | Ceiling - Lay-in | 1,044 | SF | 6 | \$3,135 |
| | Doors - Side-lite | 1 | SF | 6 | \$17 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Eye Wash Station | 1 | EA | 6 | \$336 |
| | Floor - Tile | 1,044 | SF | 6 | \$2,284 |
| | Lighting - Lay-in | 12 | EA | 7 | \$0 |
| | Marker Board | 12 | LF | 7 | \$0 |
| | Science Lab Elements | 18 | SF | 6 | \$122 |

Building: Addition

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------------------------|-------------------------|----------|------|------|---------|
| Science Lab Level 1 (1 room) | | | | | |
| | Storage/ Closet | 21 | SF | 6 | \$152 |
| | Walls - Concrete Block | 767 | SF | 6 | \$2,248 |
| | Walls - Plaster/Drywall | 502 | SF | 6 | \$1,385 |
| | Work Sink | 3 | EA | 6 | \$1,137 |

Classrooms Subtotal:

\$247,468

Building: Addition

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------------------------|---------------------------------|----------|------|------|----------|
| Administrative Suites/Offices | | | | | |
| | Ceiling - Exposed | 1,092 | SF | 6 | \$1,624 |
| | Ceiling - Lay-in | 3 | SF | 5 | \$24 |
| | Ceiling - Lay-in | 2,943 | SF | 6 | \$8,838 |
| | Doors - Side-lite | 193 | SF | 6 | \$3,226 |
| | Doors - Steel Doors incl hw | 2 | EA | 6 | \$602 |
| | Doors - Wood Doors inclu hw | 10 | EA | 6 | \$3,010 |
| | Floor - Carpet | 1,231 | SF | 6 | \$2,623 |
| | Floor - Concrete Epoxy/ Painted | 1,165 | SF | 6 | \$616 |
| | Floor - Terrazzo | 129 | SF | 6 | \$282 |
| | Floor - Tile | 1,518 | SF | 6 | \$3,321 |
| | Lighting - Lay-in | 46 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 6 | EA | 7 | \$0 |
| | Power Distribution | 92 | EA | 7 | \$0 |
| | Storage/ Closet | 50 | SF | 6 | \$363 |
| | Walls - Concrete Block | 6,412 | SF | 6 | \$18,797 |
| | Walls - Plaster/Drywall | 5 | SF | 5 | \$26 |
| | Walls - Plaster/Drywall | 4,008 | SF | 6 | \$11,062 |
| | Work Sink | 6 | EA | 6 | \$3,049 |
| Kitchen | | | | | |
| | Ceiling - Lay-in | 817 | SF | 6 | \$2,453 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Concrete Epoxy/ Painted | 817 | SF | 6 | \$432 |
| | Lighting - Lay-in | 10 | EA | 7 | \$0 |
| | Storage/ Closet | 393 | SF | 6 | \$2,849 |
| | Walls - Concrete Block | 1,442 | SF | 6 | \$4,227 |

Building: Addition

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------------------------|---------------------------------|----------|------|------|----------|
| Library | | | | | |
| | Ceiling - Lay-in | 4 | SF | 5 | \$32 |
| | Ceiling - Lay-in | 2,459 | SF | 6 | \$7,384 |
| | Doors - Side-lite | 12 | SF | 6 | \$201 |
| | Doors - Wood Doors inclu hw | 2 | EA | 6 | \$602 |
| | Floor - Carpet | 2,463 | SF | 6 | \$5,248 |
| | Lighting - Lay-in | 28 | EA | 7 | \$0 |
| | Walls - Concrete Block | 1,978 | SF | 6 | \$5,799 |
| | Walls - Plaster/Drywall | 326 | SF | 6 | \$900 |
| Lunch & Multipurpose Room | | | | | |
| | Ceiling - Exposed | 5,240 | SF | 6 | \$7,793 |
| | Ceiling - Lay-in | 2 | SF | 5 | \$12 |
| | Doors - Wood Doors inclu hw | 8 | EA | 6 | \$2,408 |
| | Floor - Tile/Sheet | 6,280 | SF | 6 | \$6,286 |
| | Lighting - Pendent/Surface | 12 | EA | 7 | \$0 |
| | Market Board | 12 | LF | 7 | \$0 |
| | Serving Line | 28 | LF | 6 | \$1,666 |
| | Storage/ Closet | 373 | SF | 6 | \$2,704 |
| | Walls - Concrete Block | 10,046 | SF | 6 | \$29,450 |
| MDF_IDF | | | | | |
| | AC Unit | 1 | EA | 4 | \$6,086 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Finishes | 145 | SF | 6 | \$1,035 |
| Mechanical/ Service Rooms | | | | | |
| | Boiler Room | 1,891 | SF | 6 | \$13,548 |
| | Janitor's Closet | 101 | SF | 6 | \$724 |
| | Mechanical/ Service Rooms | 3,597 | SF | 6 | \$25,770 |
| | Storage Room | 951 | SF | 6 | \$6,813 |
| Prep Room | | | | | |
| | Ceiling - Lay-in | 157 | SF | 6 | \$471 |
| | Doors - Wood Doors inclu hw | 1 | EA | 6 | \$301 |
| | Floor - Concrete Epoxy/ Painted | 157 | SF | 6 | \$83 |
| | Lighting - Lay-in | 3 | EA | 7 | \$0 |
| | Walls - Concrete Block | 545 | SF | 6 | \$1,598 |
| | Work Sink | 1 | EA | 6 | \$379 |

Building: Addition

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------|---------------------------------|----------|------|------|----------|
| Restroom | | | | | |
| | Accessories | 1,678 | SF | 6 | \$15,477 |
| | Ceiling - Lay-in | 232 | SF | 6 | \$697 |
| | Ceiling - Plaster/Drywall | 1,446 | SF | 6 | \$5,004 |
| | Doors - Wood Doors inclu hw | 10 | EA | 6 | \$3,010 |
| | Floor - Concrete Epoxy/ Painted | 42 | SF | 6 | \$22 |
| | Floor - Terrazzo | 1,395 | SF | 6 | \$3,052 |
| | Floor - Tile | 241 | SF | 6 | \$527 |
| | Floor Drain | 16 | EA | 6 | \$16,947 |
| | Lavatory | 28 | EA | 6 | \$8,949 |
| | Lighting - Lay-in | 40 | EA | 7 | \$0 |
| | Partitions | 15 | EA | 6 | \$4,454 |
| | Urinals | 6 | EA | 6 | \$2,016 |
| | Walls - Concrete Block | 2,690 | SF | 6 | \$7,886 |
| | Walls - Structural Glazed Tile | 8 | SF | 5 | \$511 |
| | Walls - Structural Glazed Tile | 2,980 | SF | 6 | \$9,375 |
| | Water Closet | 28 | EA | 6 | \$9,407 |

Rooms (Other Than Classrooms) Subtotal: \$282,652

Building: Addition

Category: Building Interior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------|--------------------------------------|----------|------|------|-----------|
| Corridor | | | | | |
| | Ceiling - Lay-in | 16 | SF | 5 | \$143 |
| | Ceiling - Lay-in | 11,284 | SF | 6 | \$33,886 |
| | Ceiling - Plaster/Drywall | 286 | SF | 6 | \$1,771 |
| | Doors - Steel Doors incl hw | 19 | EA | 6 | \$5,719 |
| | Doors - Wood Doors include hw | 16 | EA | 6 | \$4,816 |
| | Drinking Fountains - Double Fountain | 4 | EA | 6 | \$1,344 |
| | Drinking Fountains - Single Fountain | 2 | EA | 6 | \$551 |
| | Floor - Terrazzo | 12,398 | SF | 6 | \$104,070 |
| | Lighting - Lay-in | 374 | EA | 7 | \$0 |
| | Stairs - Concrete Stairs | 23 | LF | 6 | \$191 |
| | Walls - Concrete Block | 14,848 | SF | 6 | \$43,527 |
| | Walls - Masonry | 1,304 | SF | 6 | \$4,102 |
| | Walls - Structural Glazed Tile | 1,000 | SF | 6 | \$3,146 |

Building: Addition

Category: Building Interior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|----------------------------|-------------------------------|----------|------|------|----------|
| Safety | | | | | |
| | Camera Viewing Station | 1 | EA | 6 | \$683 |
| | Security Cameras | 1 | EA | 5 | \$688 |
| | Security Cameras | 5 | EA | 6 | \$970 |
| Stairs | | | | | |
| | Ceiling - Lay-in | 945 | SF | 6 | \$2,838 |
| | Floor - Terrazzo | 1,002 | SF | 7 | \$0 |
| | Handrails | 324 | LF | 6 | \$2,808 |
| | Lighting - Lay-in | 18 | EA | 7 | \$0 |
| | Lighting - Pendent/Surface | 3 | EA | 7 | \$0 |
| | Stairs - Terrazzo | 162 | LF | 6 | \$1,503 |
| | Walls - Concrete Block | 10,206 | SF | 6 | \$29,919 |
| Vertical Conveyance | | | | | |
| | Elevator - Hydraulic Elevator | 1 | EA | 6 | \$19,238 |

Building Interior Subtotal: \$261,912

Total Building Cost \$2,209,603

Building: Field House

Category: Building Exterior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|--------------------|---|----------|------|------|----------|
| Entrance | | | | | |
| | Exterior Doors - Exterior FRP Door | 6 | EA | 6 | \$3,788 |
| | Exterior Stairs - Concrete | 40 | LF | 6 | \$3,271 |
| | Ramp Handrail - Steel_Ramp Handrail | 86 | LF | 6 | \$745 |
| | Ramps - Concrete | 45 | LF | 6 | \$6,761 |
| Foundation | | | | | |
| | Foundation - Concrete | 1,857 | LF | 7 | \$0 |
| Roof System | | | | | |
| | Chimney - Brick Chimney- Concrete/ Mortar Liner | 3 | LF | 6 | \$2,864 |
| | Downspouts - Exterior Downspouts | 80 | LF | 4 | \$10,837 |
| | Roof - Metal | 1,857 | SF | 6 | \$24,882 |
| | Roof Structure - Steel / Metal Deck/ Concrete Topping | 1,857 | SF | 7 | \$0 |

Building: Field House

Category: Building Exterior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|----------------|-------------------------------------|----------|------|------|-----------|
| Walls | | | | | |
| | Exterior Walls - Brick | 18,570 | SF | 6 | \$124,809 |
| | Exterior Walls - Stone-Cut | 828 | SF | 6 | \$5,565 |
| Windows | | | | | |
| | Guard - Guards perforated | 336 | SF | 6 | \$4,291 |
| | Lintels - Brick | 122 | LF | 5 | \$40,747 |
| | Lintels - Stone | 4 | LF | 6 | \$0 |
| | Windows - Sash Aluminum Double-pane | 336 | SF | 6 | \$2,508 |

Building Exterior Subtotal:

\$231,068

Building: Field House

Category: Electrical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|---------------------------|---|----------|------|------|---------|
| Main Service | | | | | |
| | Main Electrical Service - 800 A and 120/208/3PH | 1 | EA | 6 | \$3,570 |
| Power Distribution | | | | | |
| | Lighting and Power Panels - 100 A | 1 | EA | 6 | \$299 |

Electrical System Subtotal:

\$3,869

Building: Field House

Category: Safty System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------------------|-------------------|----------|------|------|-------|
| Fire Alarm | | | | | |
| | Fire Alarm_System | 1,825 | SF | 6 | \$887 |

Safty System Subtotal:

\$887

Building: Field House

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------|--|----------|------|------|---------|
| Heating Devices | | | | | |
| | Gas/ Natural Draft Furnace - 101 - 200 MBH | 1 | EA | 5 | \$6,105 |

Building: Field House

Category: Mechanical System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|------------------------------------|--|----------|------|------|-----------------|
| Temperature Control | | | | | |
| | Electric Thermostat | 1 | EA | 6 | \$0 |
| Ventilation | | | | | |
| | Exhaust Fans- Indoor - Less than 500 CFM | 2 | EA | 6 | \$592 |
| | Roof Mounted Duct Work | 90 | LF | 6 | \$34,112 |
| Mechanical System Subtotal: | | | | | \$40,810 |

Building: Field House

Category: Plumbing System

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|----------------------------------|---|----------|------|------|----------------|
| Hot Water | | | | | |
| | Gas Heater - Less than 150000 BTU/HR | 1 | EA | 5 | \$2,249 |
| Piping | | | | | |
| | Domestic Piping-Cold Water Horizontal Lines | 1,825 | SF | 6 | \$444 |
| | Domestic Piping-Hot Water Horizontal Lines | 1,825 | SF | 6 | \$339 |
| | Domestic Piping-Hot Water Return Lines | 1,825 | SF | 6 | \$261 |
| | Sanitary Piping | 1,825 | SF | 6 | \$1,670 |
| | Storm Piping | 1,825 | SF | 6 | \$1,592 |
| | Vent Piping | 1,825 | SF | 6 | \$1,227 |
| Plumbing System Subtotal: | | | | | \$7,782 |

Building: Field House

Category: Classrooms

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------------------|---------------------------------|----------|------|------|-----------------|
| Play Room (2 rooms) | | | | | |
| | Casework | 80 | LF | 6 | \$2,020 |
| | Ceiling - Plaster/Drywall | 900 | SF | 6 | \$3,115 |
| | Doors - Wood Doors inclu hw | 2 | EA | 6 | \$602 |
| | Floor - Concrete Epoxy/ Painted | 900 | SF | 5 | \$1,544 |
| | Lighting - Pendent/Surface | 12 | EA | 7 | \$0 |
| | Walls - Structural Glazed Tile | 1,596 | SF | 6 | \$5,021 |
| Classrooms Subtotal: | | | | | \$12,302 |

Building: Field House

Category: Rooms (Other Than Classrooms)

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|----------------------------------|--------------------------------|----------|------|------|---------|
| Mechanical/ Service Rooms | | | | | |
| | Mechanical/ Service Rooms | 95 | SF | 6 | \$681 |
| Restroom | | | | | |
| | Accessories | 90 | SF | 6 | \$830 |
| | Ceiling - Plaster/Drywall | 90 | SF | 6 | \$311 |
| | Doors - Wood Doors inclu hw | 2 | EA | 6 | \$602 |
| | Floor - Epoxy/ Painted | 45 | SF | 5 | \$77 |
| | Floor - Epoxy/ Painted | 45 | SF | 6 | \$24 |
| | Floor Drain | 2 | EA | 6 | \$2,118 |
| | Lavatory | 2 | EA | 5 | \$3,179 |
| | Lighting - Pendent/Surface | 2 | EA | 7 | \$0 |
| | Partitions | 1 | EA | 5 | \$751 |
| | Partitions | 1 | EA | 6 | \$297 |
| | Urinals | 2 | EA | 6 | \$672 |
| | Walls - Structural Glazed Tile | 476 | SF | 6 | \$1,497 |
| | Water Closet | 2 | EA | 6 | \$672 |

Rooms (Other Than Classrooms) Subtotal: \$11,712

Building: Field House

Category: Building Interior

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------|---------------------------------|----------|------|------|---------|
| Corridor | | | | | |
| | Ceiling - Plaster/Drywall | 299 | SF | 6 | \$1,851 |
| | Doors - Wood Doors include hw | 1 | EA | 6 | \$301 |
| | Floor - Concrete Epoxy/ Painted | 299 | SF | 6 | \$145 |
| | Lighting - Pendent/Surface | 4 | EA | 7 | \$0 |
| | Walls - Structural Glazed Tile | 657 | SF | 6 | \$2,067 |

Building Interior Subtotal: \$4,365

Total Building Cost \$312,795

SITE

Category: Site

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-------|-------------|----------|------|------|------|
|-------|-------------|----------|------|------|------|

SITE

Category: Site

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|-----------------------|---|----------|------|------|----------|
| Athletic | | | | | |
| | Surface - Asphalt | 13,613 | SF | 6 | \$32,899 |
| | Surface - Synthetic including exc & retention | 16,174 | SF | 7 | \$0 |
| Civil/Drainage | | | | | |
| | Civil/ Drainage - Catch Basin | 11 | EA | 6 | \$12,032 |
| | Civil/ Drainage - Site Manhole | 10 | EA | 6 | \$14,927 |
| Fencing | | | | | |
| | Fencing - New Standard Ornamental | 1,442 | LF | 6 | \$46,005 |
| Landscape | | | | | |
| | Benches | 19 | EA | 6 | \$8,171 |
| | Irrigation | 29,835 | SF | 5 | \$80,208 |
| | Landscape - Grass | 34,607 | SF | 6 | \$28,703 |
| | Landscape - Hardscape- Concrete | 1,879 | SF | 5 | \$20,609 |
| | Landscape - Hardscape- Concrete | 15,479 | SF | 6 | \$79,907 |
| | Landscape - Hardscape- Pavers | 314 | SF | 6 | \$1,778 |
| | Parkway trees | 32 | EA | 6 | \$21,121 |
| | Planting Beds/ Area | 6,425 | SF | 6 | \$10,566 |
| | Trash Receptacles | 8 | EA | 6 | \$2,498 |
| Parking Lot | | | | | |
| | Concrete Curbs | 388 | LF | 6 | \$4,982 |
| | Lighting - Pole Mounted | 21 | EA | 6 | \$30,502 |
| | Surface - Asphalt | 15,489 | SF | 6 | \$37,432 |
| | Surface - Concrete | 1,661 | SF | 6 | \$4,014 |
| | Trash Compactor | 1 | EA | 6 | \$0 |
| | Vehicular Screening | 304 | LF | 6 | \$23,936 |
| Playground | | | | | |
| | Equipment - School Age 5-12 | 3 | EA | 6 | \$10,637 |
| | Equipment - Swingset | 1 | EA | 6 | \$1,182 |
| | Surface - Poured Surface | 6,239 | SF | 6 | \$45,679 |
| Sidewalks | | | | | |
| | Sidewalks - Internal Walks | 100 | LF | 5 | \$4,984 |
| | Sidewalks - Internal Walks | 594 | LF | 6 | \$7,135 |
| | Sidewalks - Perimeter Sidewalks | 1,000 | SF | 5 | \$9,552 |
| | Sidewalks - Perimeter Sidewalks | 12,342 | SF | 6 | \$24,532 |

SITE

Category: Site

| Group | Item - Type | Quantity | Unit | Rank | Cost |
|---------|--------------------------------------|----------|------|------|---------|
| Signage | Flag Pole - Flag Pole | 1 | EA | 6 | \$1,657 |
| | Marquee - Free Standing Back Lighted | 1 | EA | 6 | \$0 |
| | Monument - Sign | 1 | EA | 6 | \$0 |

Site Subtotal: **\$565,651**

Total Site Cost **\$565,651**

Campus Total ^{2 3} **\$6,021,569**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

| Current Usage | Intended Usage | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|-------------------|-------------------|---------------|-------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| Main | | | | | | | | | | | | | | |
| Dance Room | Regular Classroom | 2nd Floor | 205 | 205 | 866 | 0 | 2 | 12 | 76 | 40 | 40 | Y | N | N |
| Kindergarten | Kindergarten | 1st Floor | 110 | Kindergarten | 1,300 | 0 | 2 | 20 | 420 | 225 | 40 | Y | N | N |
| Kindergarten | Regular Classroom | 2nd Floor | 206B | 206 | 554 | 2 | 6 | 30 | 82 | 44 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 1st Floor | 101 | 101 | 888 | 0 | 2 | 12 | 224 | 120 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 1st Floor | 102 | 102 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 1st Floor | 103 | 103 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 1st Floor | 104 | 104 | 934 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 1st Floor | 105 | 105 | 910 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 200 | NA | 415 | 0 | 10 | 20 | 84 | 45 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 201 | 201 | 888 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 202 | 202 | 903 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 203 | 203 | 909 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 204 | 204 | 908 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 207 | 207 | 927 | 0 | 2 | 15 | 134 | 70 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 208 | 208 | 881 | 0 | 2 | 16 | 114 | 59 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 209 | 209 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | Y | Y |
| Regular Classroom | Regular Classroom | 2nd Floor | 210 | 210 | 879 | 0 | 2 | 12 | 168 | 90 | 40 | Y | Y | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 300 | NA | 415 | 0 | 2 | 6 | 84 | 45 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 301 | 301 | 888 | 0 | 2 | 12 | 224 | 120 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 302 | 302 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 304 | 304 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 305 | 305 | 888 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Library | 3rd Floor | 306B | 306 | 602 | 0 | 2 | 12 | 168 | 90 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 307 | 307 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | Y | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 308 | 308 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 309 | 309 | 938 | 0 | 2 | 12 | 168 | 90 | 40 | Y | Y | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 310 | 310 | 888 | 0 | 2 | 12 | 224 | 120 | 40 | Y | Y | Y |
| Science | Regular Classroom | 3rd Floor | 303 | 303 | 909 | 0 | 2 | 12 | 168 | 90 | 40 | Y | N | Y |
| Special Program | Faculty Lounge | 1st Floor | 109 | NA - Teacher Rm | 333 | 1 | 2 | 4 | | | 40 | Y | N | N |

Addition

| | | | | | | | | | | | | | | |
|--------------|-------------------|-----------|-----|------|-------|---|----|----|-----|----|----|---|---|---|
| Art Room | Art Room | 3rd Floor | 328 | 3-11 | 1,053 | 1 | 8 | 24 | 98 | 42 | 40 | Y | N | Y |
| Computer Lab | Computer Lab | 2nd Floor | 229 | 2-13 | 1,019 | 2 | 40 | 92 | 89 | 45 | 40 | Y | Y | N |
| Kindergarten | Kindergarten | 1st Floor | 126 | 1-21 | 1,098 | 1 | 1 | 12 | 164 | 56 | 40 | Y | N | N |
| Kindergarten | Kindergarten | 1st Floor | 128 | 1-25 | 1,098 | 1 | 1 | 12 | 164 | 56 | 40 | N | N | N |
| Music Room | Regular Classroom | 3rd Floor | 331 | 3-16 | 848 | 1 | 8 | 22 | 98 | 42 | 40 | Y | N | N |
| Pre School | Kindergarten | 1st Floor | 121 | 1-11 | 1,073 | 1 | 1 | 12 | 164 | 56 | 40 | Y | N | N |

Classroom Summary

| Current Usage | Intended Usage | Room Location | Room Number | Floor Plan Room Number | Area (SF) | Voice Outlets | Data Outlets | Elect. Outlets | Glazed Window Area | Operable Window Area | Noise Level | Window Stop | Power Strip | Smart-Board |
|---------------------|-------------------|---------------|-------------|------------------------|-----------|---------------|--------------|----------------|--------------------|----------------------|-------------|-------------|-------------|-------------|
| Addition | | | | | | | | | | | | | | |
| Pre School | Kindergarten | 1st Floor | 122 | 1-14 | 1,073 | 1 | 1 | 12 | 164 | 56 | 40 | Y | N | N |
| Pre School | Kindergarten | 1st Floor | 123 | 1-17 | 1,098 | 1 | 1 | 12 | 164 | 56 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 223 | 2-07 | 852 | 1 | 9 | 18 | 89 | 45 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 224 | 2-08 | 852 | 1 | 9 | 16 | 89 | 45 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 225 | 2-09 | 852 | 1 | 9 | 18 | 113 | 57 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 228 | 2-12 | 852 | 1 | 9 | 18 | 89 | 45 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 2nd Floor | 231 | 2-17 | 852 | 1 | 9 | 18 | 89 | 45 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 320 | 3-02 | 900 | 1 | 8 | 22 | 155 | 28 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 321 | 3-03 | 900 | 1 | 8 | 22 | 98 | 42 | 40 | Y | N | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 322 | 3-04 | 900 | 1 | 8 | 24 | 155 | 28 | 40 | Y | Y | N |
| Regular Classroom | Regular Classroom | 3rd Floor | 323 | 3-05 | 900 | 1 | 8 | 22 | 155 | 28 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 324 | 3-06 | 900 | 1 | 8 | 22 | 98 | 42 | 40 | Y | N | Y |
| Regular Classroom | Regular Classroom | 3rd Floor | 325 | 3-07 | 900 | 1 | 8 | 22 | 155 | 28 | 40 | Y | N | Y |
| Science Lab Level 1 | Regular Classroom | 3rd Floor | 329 | 3-12 | 1,044 | 1 | 13 | 36 | 98 | 42 | 40 | Y | Y | Y |

Field House

| | | | | | | | | | | | | | | |
|-----------|-----------|-----------|-------|----|-----|---|---|---|-----|----|----|---|---|---|
| Play Room | Play Room | 1st Floor | North | NA | 450 | 0 | 0 | 6 | 165 | 83 | 40 | N | N | N |
| Play Room | Play Room | 1st Floor | South | NA | 450 | 0 | 0 | 6 | 165 | 83 | 40 | N | N | N |