

Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	2005	2	290,134	\$10,185,687
SITE				\$1,410,123
Campus Total			290,134	\$11,595,811

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Entrance Control - Audio	4	EA	6	\$1,988
	Entrance Control - Audio and Video	2	EA	7	\$0
	Exterior Doors - Exterior Stainless Steel Door	1	EA	7	\$0
	Exterior Doors - Exterior Steel Door	37	EA	6	\$17,780
	Exterior Doors - Overhead Rolling/ Garage Door	1	EA	6	\$1,433
	Exterior Doors - Side lite	8	EA	7	\$0
	Exterior Doors - Store Front	37	EA	6	\$20,205
	Exterior Stairs - Concrete	21	LF	6	\$1,717
	Exterior Stairs - Concrete	150	LF	7	\$0
	Power Door Operator and Controls	5	EA	6	\$0
	Ramp Handrail - Steel_Ramp Handrail	120	LF	7	\$0
	Ramps - Concrete	60	LF	6	\$9,014
	Stair Handrail - Steel_Stair Handrail	20	LF	6	\$173
	Stair Handrail - Steel_Stair Handrail	24	LF	7	\$0
Foundation					
	Foundation - Concrete	5	LF	6	\$0
	Foundation - Concrete	1,925	LF	7	\$0
	Superstructure - Steel	290,134	SF	7	\$0

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Lighting					
	Exterior Lighting - Parapet or Roof Mounted	4	EA	6	\$2,146
	Exterior Lighting - Wall Mounted	2	EA	5	\$855
	Exterior Lighting - Wall Mounted	153	EA	6	\$44,178
Roof System					
	Chimney - Metal Flue	24	LF	6	\$3,795
	Coping - Metal	5,600	LF	6	\$179,860
	Coping - Metal	612	LF	7	\$0
	Downspouts - Exterior Downspouts	30	LF	7	\$0
	Downspouts - Interior Downspouts	480	LF	5	\$106,227
	Downspouts - Interior Downspouts	800	LF	6	\$26,587
	Downspouts - Interior Downspouts	5,280	LF	7	\$0
	Parapet - 16" - 30" Height	1,543	LF	6	\$61,649
	Parapet - 16" - 30" Height	315	LF	7	\$0
	Parapet - Parapet < 16" Height	286	LF	6	\$6,094
	Parapet - Parapet > 30"	1,946	LF	6	\$124,390
	Parapet - Parapet > 30"	1,103	LF	7	\$0
	Roof - Asphalt Gravel Ballast	930	SF	5	\$25,069
	Roof - Asphalt Gravel Ballast	55,720	SF	6	\$566,522
	Roof - EPDM/ Synthetic Rubber	1,328	SF	6	\$11,242
	Roof - Metal	1,126	SF	5	\$31,028
	Roof - Modified Bitumen	114,823	SF	6	\$1,080,416
	Roof Structure - Steel / Metal Deck/ Concrete Topping	298,841	SF	7	\$0
Walls					
	Canopy - Concrete/ Stucco	192	SF	7	\$0
	Canopy - Metal	1,765	SF	7	\$0
	Exterior Walls - Brick	111,179	SF	6	\$747,234
	Exterior Walls - Prefabricated Metal Panel Wall	28,401	SF	6	\$161,235
	Exterior Walls - Stone-Cast	415	SF	6	\$2,789
Windows					
	Curtain wall - Glazed Double Pane	18,373	SF	7	\$0
	Curtain wall - Louver	1,860	SF	6	\$20,853
	Guard - Guards perforated	2,232	SF	6	\$28,502
	Lintels - Steel	1,875	LF	7	\$0
	Skylite - Glass Double-Pane	27	SF	7	\$0
	Windows - Decorative	2,339	SF	7	\$0
	Windows - Sash Aluminum Double-pane	8,988	SF	6	\$67,092

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Windows					

Building Exterior Subtotal:

\$3,350,075

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					

Automatic Transfer Switch	3	EA	6	\$1,224
Emergency A/C Power - Auditorium and Aisle Lighting	2,829	SF	6	\$1,497
Emergency A/C Power - Corridors and Stairs	53,710	SF	6	\$16,129
Emergency A/C Power - Gym	17,008	SF	6	\$6,324
Emergency A/C Power - Lunchrooms	6,920	SF	6	\$2,573
Emergency A/C Power - Pool	8,749	SF	6	\$3,253
Emergency Generator- Indoor- Diesel - 201 - 250 KW	1	EA	6	\$12,554
Exit Signs - Auditorium	10	EA	6	\$1,497
Exit Signs - Corridors and Stairs	107	EA	6	\$16,023
Exit Signs - Gym	12	EA	6	\$1,889
Exit Signs - Lunchroom	4	EA	6	\$599
Exit Signs - Pool	4	EA	6	\$620
Security System - CCTV	290,134	SF	6	\$87,127
Security System - Intrusion Detection	290,134	SF	6	\$74,680
UPS - Less than 30 KW	1	EA	7	\$0

Main Service

Independent Electrical Service for emergency power	2	EA	6	\$5,841
Main Electrical Service - 1200 A 120/208/3PH	1	EA	6	\$5,078
Main Electrical Service - 2001 to 3000 A 120/208/3PH	1	EA	6	\$10,867
Main Electrical Service - Greater than 3000 A 277/480/3PH	1	EA	6	\$17,930
PA System	290,134	SF	6	\$95,425

Power Distribution

Lighting and Power Panels - 100 A	2	EA	7	\$0
Lighting and Power Panels - Above 100 A	67	EA	7	\$0
Main Distribution Panels - 400 - 600 amp	11	EA	7	\$0
Main Distribution Panels - Greater than 600 amp	7	EA	7	\$0
Transformers - 277/480 - 120/208	3	EA	6	\$3,795

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Electrical System Subtotal:					\$364,925

Building: Main

Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	290,134	SF	6	\$103,723
	Fire Alarm_System	290,134	SF	6	\$141,063
	Fire Pump Controller	1	EA	6	\$1,823
Pump Room Assembly					
	Fire Pump - 51-75hp	1	EA	6	\$1,558
	Jockey Pump	1	EA	6	\$758
Sprinkler System					
	Sprinkler Heads	290,134	SF	7	\$0
	Sprinkler Piping	290,134	SF	6	\$53,936
	Wet Sprinkler System	290,134	SF	6	\$74,680
Safty System Subtotal:					\$383,947

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Conditioning					
	Chemical Pot Feeder	1	EA	7	\$0
	Chiller-Air Cooled-Screw Type-Roof Mounted - 201 - 300 tons	3	EA	6	\$12,942
	Condensing Unit- Roof Mounted - 31-50 tons	1	EA	6	\$4,120
	Condensing Unit- Roof Mounted - Less than 5 tons	3	EA	6	\$10,001
	Glycol Feed	1	EA	6	\$490
	Pipes - Chilled Water Pipe- Copper	600	LF	7	\$0
Air Handling Systems					
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	5	EA	6	\$16,750
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	6	EA	6	\$20,100

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Handling Systems					
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	1	EA	6	\$3,350
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 8001-12000 cfm	1	EA	6	\$3,350
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - Less than 4000 cfm	2	EA	6	\$6,700
	Air Intake	15	EA	6	\$86,470
	Dehumidification Unit- Indoor- Hot Water Heating- DX Cooling with Remote Mounted Compressor - Greater than 8000 cfm	1	EA	6	\$3,350
	Fan Coil Unit- Ceiling Mounted - Hot Water and Chilled Water	4	EA	6	\$6,417
	Fan Power Box - Fan Power Box with Hot Water Coil	154	EA	6	\$75,890
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	5	EA	6	\$9,286
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	2	EA	6	\$3,714
	Indoor Return Fans- Centrifugal Inline - Greater than 20000 CFM	1	EA	6	\$2,433
	Indoor Return Fans- Centrifugal Squirrel Cage - Greater than 20000 CFM	4	EA	6	\$9,730
	Make Up Air Unit- Indoor Mounted- Hot Water Coils - Less than 6000 cfm	1	EA	6	\$3,350
	VAV Box	57	EA	6	\$15,912
Boiler Systems					
	Boiler Auxiliary- Non Condensing Hot Water - Greater than 4000 MBH	2	EA	6	\$4,093
	Chemical Pot Feeder	1	EA	6	\$725
	Glycol Feed System	1	EA	6	\$539
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - Greater than 4000 MBH	2	EA	6	\$1,996
Heating Devices					
	Cabinet Heaters - With Hot Water Coil	28	EA	6	\$9,921
	Duct Heater - Electric	5		6	\$2,136
	Radiator Panels - Hot Water	18	EA	6	\$5,001
	Unit Heater - Electric	6	EA	6	\$1,667
	Unit Heater - Hot Water	15	EA	6	\$4,187
Mechanical Plumbing					
	Chilled Water Pump - 10 - 20 HP	3	EA	6	\$3,727
	Chilled Water Pump - 21 - 50 HP	2	EA	6	\$2,485
	Hot Water Pump - 10 - 20 HP	4	EA	6	\$4,969
	Hydronic Supply and Return - Copper	2,000	LF	6	\$104,933
	Hydronic Supply and Return - Galvanized	500	LF	6	\$38,660
Temperature Control					
	DDC System	290,134	SF	6	\$165,957

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Temperature Control					
	Electric Thermostat	32	EA	6	\$0
	Thermostats - DDC	221	EA	6	\$0
Ventilation					
	Exhaust Fans- Indoor - 500 - 1500 CFM	2	EA	6	\$1,185
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	22	EA	6	\$13,033
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	15	EA	6	\$8,886
	Exhaust Fans- Roof Mounted - Less than 500 CFM	10	EA	6	\$2,962
	Lab Exhaust Hood	8	EA	6	\$9,982
	Type I Exhaust Hood- Kitchen	2	EA	6	\$2,495
	Type II Exhaust Hood- Warming Kitchen	1	EA	6	\$920
Mechanical System Subtotal:					\$684,811

Building: Main

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Hot Water					
	Electric Heater - 20 - 50 KW	1	EA	6	\$682
	Gas Heater - 300001 - 600000 BTU/HR	4	EA	6	\$1,240
Piping					
	Domestic Piping-Cold Water from Risers to Fixtures	290,134	SF	6	\$58,085
	Domestic Piping-Cold Water Horizontal Lines	290,134	SF	6	\$70,532
	Domestic Piping-Cold Water Risers	290,134	SF	6	\$53,936
	Domestic Piping-Hot Water from Risers to Fixtures	290,134	SF	6	\$45,638
	Domestic Piping-Hot Water Horizontal Lines	290,134	SF	6	\$53,936
	Domestic Piping-Hot Water Return Lines	290,134	SF	6	\$41,489
	Domestic Piping-Hot Water Return Risers	290,134	SF	6	\$41,489
	Sanitary Piping	290,134	SF	6	\$265,531
	Storm Piping	290,134	SF	6	\$253,084
	Vent Piping	290,134	SF	6	\$194,999
Pool Systems					
	Pool Drain Piping	50	LF	6	\$1,431
	Pool Filtration System including Pump	1	EA	6	\$12,330
	Pool Hot Water Heater - Gas Fired	1	EA	6	\$310
	Pool Supply and Return Piping	150	LF	6	\$7,207

Building: Main

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Pumps					
	Pumps - Domestic Booster Pump-Duplex	1	EA	6	\$1,977
	Pumps - Ejector-Duplex	1	EA	6	\$1,387
	Pumps - Sump-Simplex	2	EA	6	\$1,490

Plumbing System Subtotal:

\$1,106,773

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Art Room (1 room)					
	Ceiling - Lay-in	1,132	SF	6	\$3,399
	Doors - Side-lite	15	SF	6	\$251
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile/Sheet	1,132	SF	6	\$1,133
	Lighting - Lay-in	21	EA	7	\$0
	Storage/ Closet	80	SF	6	\$580
	Walls - Concrete Block	1,404	SF	6	\$4,116

Computer Lab (4 rooms)

Casework	89	LF	6	\$2,248
Ceiling - Lay-in	18	SF	5	\$144
Ceiling - Lay-in	4,546	SF	6	\$13,652
Doors - Side-lite	26	SF	6	\$435
Doors - Side-lite	65	SF	7	\$0
Doors - Transom Window	26	SF	6	\$440
Doors - Transom Window	65	SF	7	\$0
Doors - Wood Doors inclu hw	8	EA	6	\$2,408
Floor - Tile	1,097	SF	6	\$2,400
Floor - Tile/Sheet	3,467	SF	6	\$3,470
Lighting - Lay-in	32	EA	6	\$3,807
Lighting - Lay-in	32	EA	7	\$0
Marker Board	64	LF	7	\$0
Storage/ Closet	40	SF	6	\$290
Walls - Concrete Block	4,603	SF	6	\$13,494
Walls - Plaster/Drywall	674	SF	6	\$1,860
Wireless System	2	EA	6	\$743

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Dance Room (1 room)					
	Ceiling - Lay-in	1,406	SF	6	\$4,222
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Floor - Wood	1,406	SF	6	\$9,912
	Lighting - Lay-in	15	EA	6	\$1,785
	Marker Board	12	LF	6	\$257
	Wall Mirrors	4	EA	6	\$0
	Walls - Concrete Block	1,468	SF	6	\$4,303
Fitness Room (1 room)					
	Ceiling - Lay-in	1,576	SF	7	\$0
	Doors - Side-lite	24	SF	7	\$0
	Doors - Steel Doors incl hw	1	EA	7	\$0
	Floor - Weight/ Fitness Room Floor Matting	1,576	SF	7	\$0
	Lighting - Lay-in	18	EA	7	\$0
	Marker Board	16	LF	7	\$0
	Storage/ Closet	205	SF	7	\$0
	Wall Mirrors	245	SF	6	\$0
	Walls - Concrete Block	2,683	SF	7	\$0
Music Room (3 rooms)					
	Casework	6	LF	6	\$152
	Ceiling - Lay-in	8	SF	5	\$64
	Ceiling - Lay-in	2,868	SF	6	\$8,613
	Ceiling - Lay-in	1,652	SF	7	\$0
	Doors - Side-lite	39	SF	6	\$652
	Doors - Side-lite	24	SF	7	\$0
	Doors - Transom Window	24	SF	6	\$406
	Doors - Transom Window	24	SF	7	\$0
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Doors - Wood Doors inclu hw	2	EA	7	\$0
	Floor - Tile	1,660	SF	6	\$3,632
	Floor - Tile	1,660	SF	7	\$0
	Floor - Tile/Sheet	1,208	SF	6	\$1,209
	Lighting - Lay-in	17	EA	7	\$0
	Lighting - Pendent/Surface	20	EA	6	\$2,478
	Lighting - Pendent/Surface	20	EA	7	\$0
	Marker Board	20	LF	6	\$428
	Marker Board	24	LF	7	\$0

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Music Room (3 rooms)					
	Sound Panels	20	EA	6	\$81
	Sound Panels	35	EA	7	\$0
	Sound System	1	EA	6	\$1,442
	Sound System	1	EA	7	\$0
	Storage/ Closet	30	SF	6	\$218
	Storage/ Closet	314	SF	7	\$0
	Student Lockers - Three Tiers	72	EA	6	\$2,228
	Walls - Concrete Block	3,234	SF	5	\$33,205
	Walls - Concrete Block	1,464	SF	6	\$4,292
	Walls - Concrete Block	3,636	SF	7	\$0
Office (2 rooms)					
	Ceiling - Lay-in	1,164	SF	6	\$3,495
	Doors - Side-lite	26	SF	7	\$0
	Doors - Transom Window	26	SF	7	\$0
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	582	SF	6	\$1,273
	Floor - Tile/Sheet	582	SF	6	\$583
	Lighting - Lay-in	12	EA	7	\$0
	Marker Board	32	LF	7	\$0
	Walls - Concrete Block	1,164	SF	6	\$3,412
	Walls - Plaster/Drywall	388	SF	6	\$1,071
Regular Classroom (44 rooms)					
	Casework	628	LF	6	\$15,859
	Casework	176	LF	7	\$0
	Ceiling - Lay-in	98	SF	5	\$782
	Ceiling - Lay-in	30,003	SF	6	\$90,099
	Ceiling - Lay-in	8,921	SF	7	\$0
	Doors - Side-lite	70	SF	6	\$1,170
	Doors - Side-lite	435	SF	7	\$0
	Doors - Transom Window	70	SF	6	\$1,185
	Doors - Transom Window	435	SF	7	\$0
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	34	EA	6	\$10,234
	Doors - Wood Doors inclu hw	8	EA	7	\$0
	Floor - Tile	20,320	SF	6	\$44,458
	Floor - Tile	7,120	SF	7	\$0

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Regular Classroom (44 rooms)					
	Floor - Tile/Sheet	11,564	SF	6	\$11,576
	Lighting - Lay-in	41	EA	6	\$4,878
	Lighting - Lay-in	527	EA	7	\$0
	Marker Board	16	LF	6	\$343
	Marker Board	644	LF	7	\$0
	Walls - Concrete Block	25,870	SF	6	\$75,838
	Walls - Concrete Block	5,196	SF	7	\$0
	Walls - Plaster/Drywall	194	SF	5	\$1,470
	Walls - Plaster/Drywall	8,402	SF	6	\$23,189
	Walls - Plaster/Drywall	866	SF	7	\$0
	Walls - Tile	4	SF	6	\$9
Science Lab Level 1 (4 rooms)					
	Casework	278	LF	6	\$7,021
	Ceiling - Lay-in	2,422	SF	6	\$7,273
	Ceiling - Lay-in	2,422	SF	7	\$0
	Doors - Side-lite	67	SF	6	\$1,120
	Doors - Side-lite	13	SF	7	\$0
	Doors - Transom Window	67	SF	6	\$1,134
	Doors - Transom Window	13	SF	7	\$0
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Eye Wash Station	4	EA	6	\$1,344
	Floor - Tile/Sheet	4,844	SF	6	\$4,849
	Fume Hood	4	EA	6	\$3,262
	Lighting - Lay-in	60	EA	6	\$7,139
	Marker Board	16	LF	6	\$343
	Marker Board	48	LF	7	\$0
	Science Lab Elements	4,844	SF	6	\$32,834
	Science Lab Shower	4	EA	6	\$1,516
	Walls - Concrete Block	4,060	SF	6	\$11,902
	Walls - Plaster/Drywall	1,400	SF	6	\$3,864
	Work Sink	30	EA	6	\$11,371
Science Lab Level 3 (4 rooms)					
	Casework	260	LF	6	\$6,566
	Ceiling - Lay-in	4,740	SF	6	\$14,234
	Doors - Side-lite	78	SF	7	\$0
	Doors - Transom Window	78	SF	7	\$0

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Science Lab Level 3 (4 rooms)					
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Eye Wash Station	1	EA	6	\$336
	Floor - Tile	3,555	SF	6	\$7,778
	Floor - Tile	1,185	SF	7	\$0
	Fume Hood	4	EA	6	\$3,262
	Gas Line	52	EA	6	\$26,474
	Lighting - Lay-in	60	EA	7	\$0
	Marker Board	48	LF	7	\$0
	Science Lab Elements	4,740	SF	6	\$32,129
	Science Lab Shower	4	EA	6	\$1,516
	Walls - Concrete Block	3,536	SF	6	\$10,366
	Walls - Plaster/Drywall	1,180	SF	6	\$3,257
	Work Sink	32	EA	6	\$12,129
Classrooms Subtotal:					\$646,786

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Ceiling - Exposed	978	SF	6	\$1,454
	Ceiling - Lay-in	22	SF	5	\$176
	Ceiling - Lay-in	21,594	SF	6	\$64,847
	Ceiling - Lay-in	552	SF	7	\$0
	Ceiling - Plaster/Drywall	946	SF	6	\$3,274
	Doors - Side-lite	102	SF	6	\$1,705
	Doors - Side-lite	154	SF	7	\$0
	Doors - Steel Doors incl hw	12	EA	6	\$3,612
	Doors - Steel Doors incl hw	1	EA	7	\$0
	Doors - Transom Window	84	SF	6	\$1,422
	Doors - Transom Window	134	SF	7	\$0
	Doors - Wood Doors inclu hw	33	EA	6	\$9,933
	Doors - Wood Doors inclu hw	8	EA	7	\$0
	Floor - Carpet	17,585	SF	6	\$37,468
	Floor - Concrete	978	SF	6	\$517
	Floor - Tile	840	SF	6	\$1,838
	Floor - Tile	1,378	SF	7	\$0

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Floor - Tile/Sheet	3,289	SF	6	\$3,292
	Lighting - Lay-in	2	EA	6	\$238
	Lighting - Lay-in	378	EA	7	\$0
	Lighting - Pendent/Surface	18	EA	6	\$2,230
	Lighting - Wall Mounted	35	EA	7	\$0
	Power Distribution	286	EA	6	\$607,716
	Power Distribution	304	EA	7	\$0
	Storage/ Closet	580	SF	6	\$4,205
	Walls - Concrete Block	31,354	SF	6	\$91,914
	Walls - Concrete Block	1,595	SF	7	\$0
	Walls - Plaster/Drywall	19,746	SF	6	\$54,497
	Walls - Plaster/Drywall	2,245	SF	7	\$0
	Walls - Structural Glazed Tile	252	SF	7	\$0
	Work Sink	2	EA	6	\$1,016
	Work Sink	1	EA	7	\$0
Auditorium & Theater					
	Ceiling - Exposed	2,829	SF	6	\$4,207
	Doors - Steel Doors incl hw	6	EA	6	\$1,806
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Carpet	1,414	SF	6	\$3,013
	Floor - Concrete	707	SF	6	\$374
	Floor - Tile/Sheet	707	SF	6	\$708
	Lighting - Lay-in	18	EA	7	\$0
	Main Floor Seating	475	EA	6	\$82,610
	Sound System	1	EA	6	\$10,721
	Stage	3,248	SF	6	\$18,764
	Stage Curtain	8	EA	6	\$0
	Stage Lighting System	1	EA	6	\$8,077
	Walls - Concrete Block	2,644	SF	6	\$7,751
	Walls - Structural Glazed Tile	2,644	SF	6	\$8,318
Gymnasia					
	Bleacher Seating	910	EA	6	\$26,338
	Ceiling - Exposed	17,008	SF	6	\$25,294
	Doors - Steel Doors incl hw	8	EA	6	\$2,408
	Floor - Wood	17,008	SF	6	\$119,905
	Lighting - Metal Halide/Sodium Vapor	56	EA	7	\$0

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Gymnasias					
	Scoreboards	1	EA	6	\$2,244
	Scoreboards	2	EA	7	\$0
	Sound System	2	EA	6	\$83,308
	Walls - Concrete Block	21,547	SF	6	\$63,165
	Walls - Plaster/Drywall	3,807	SF	6	\$10,507
Kitchen					
	Ceiling - Lay-in	2,014	SF	6	\$6,048
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Floor - Tile Ceramic/ Porcelain	2,014	SF	6	\$4,262
	Lighting - Lay-in	18	EA	7	\$0
	Storage/ Closet	287	SF	6	\$2,081
	Walls - Concrete Block	2,375	SF	6	\$6,962
Library					
	Casework	325	LF	7	\$0
	Ceiling - Lay-in	5,646	SF	7	\$0
	Doors - Side-lite	224	SF	7	\$0
	Doors - Transom Window	12	SF	7	\$0
	Doors - Wood Doors inclu hw	4	EA	7	\$0
	Floor - Carpet	5,646	SF	5	\$28,985
	Lighting - Lay-in	30	EA	7	\$0
	Lighting - Pendent/Surface	78	EA	7	\$0
	Storage/ Closet	428	SF	7	\$0
	Walls - Plaster/Drywall	2,312	SF	7	\$0
	Walls - Structural Glazed Tile	4,325	SF	7	\$0
Locker/Shower Room					
	Accessories	3,385	SF	6	\$13,263
	Benches, ped mounted	583	LF	6	\$63,477
	Ceiling - Lay-In	1,140	SF	6	\$3,423
	Ceiling - Plaster/ Drywall	5,935	SF	6	\$20,539
	Doors - Steel Doors incl hw	12	EA	6	\$3,612
	Floor - Concrete	6,751	SF	6	\$3,572
	Floor - Tile Ceramic/ Porcelain	234	SF	6	\$495
	Floor Drain	42	EA	6	\$44,485
	Hand Dryer	9	EA	6	\$2,070
	Lavatory	4	EA	6	\$1,278
	Lighting - Lay-in	90	EA	7	\$0

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Locker/Shower Room					
	Partitions	10	EA	6	\$2,969
	Showers	15	EA	6	\$4,671
	Student Lockers - One Tier	196	EA	6	\$18,196
	Student Lockers - One Tier	126	EA	7	\$0
	Student Lockers - Three Tiers	770	EA	6	\$23,828
	Student Lockers - Three Tiers	770	EA	7	\$0
	Urinals	2	EA	6	\$672
	Walls - Concrete Block	10,860	SF	6	\$31,836
	Walls - Tile Ceramic/ Porcelain	394	SF	6	\$890
	Water Closet	10	EA	6	\$3,360
Lunch & Multipurpose Room					
	Ceiling - Lay-in	6,920	SF	6	\$20,781
	Doors - Steel Doors incl hw	8	EA	6	\$2,408
	Floor - Tile/Sheet	1,478	SF	6	\$1,479
	Lighting - Lay-in	28	EA	6	\$3,331
	Lighting - Pendent/Surface	100	EA	7	\$0
	Serving Line	100	LF	6	\$5,952
	Walls - Concrete Block	4,666	SF	6	\$13,678
	Walls - Plaster/Drywall	6,316	SF	6	\$17,432
MDF_IDF					
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Finishes	128	SF	6	\$913
Mechanical/ Service Rooms					
	Boiler Room	1,235	SF	6	\$8,848
	Janitor's Closet	498	SF	6	\$3,568
	Janitor's Closet	55	SF	7	\$0
	Mechanical/ Service Rooms	4,246	SF	6	\$29,574
	Mechanical/ Service Rooms	9,686	SF	7	\$0
	Storage Room	765	SF	6	\$5,481
	Vaults	1,006	SF	6	\$7,207
Pool & Natatorium					
	Accessories	8,749	SF	6	\$6,005
	Bleachers Seating/Plank Seating	72	EA	6	\$2,084
	Ceiling - Exposed	8,749	SF	6	\$13,012
	Doors - Steel Doors incl hw	4	EA	6	\$1,204

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Pool & Natatorium					
	Floor - Concrete	1,011	SF	6	\$535
	Lighting - Pendent/Surface	22	EA	7	\$0
	Lighting - Wall Mounted	30	EA	6	\$3,717
	Pool Basin	4,143	SF	6	\$140,173
	Pool Deck	2,926	SF	6	\$27,783
	Pool Deck Drains	3	EA	6	\$1,266
	Walls - Concrete Block	9,183	SF	6	\$26,920
	Walls - Plaster/Drywall	3,935	SF	6	\$12,211
Prep Room					
	Casework	120	LF	6	\$3,030
	Ceiling - Lay-in	4	SF	5	\$32
	Ceiling - Lay-in	688	SF	6	\$2,066
	Ceiling - Lay-in	690	SF	7	\$0
	Doors - Side-lite	26	SF	7	\$0
	Doors - Transom Window	38	SF	7	\$0
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Tile	688	SF	6	\$1,505
	Floor - Tile/Sheet	690	SF	6	\$691
	Lighting - Lay-in	8	EA	6	\$952
	Lighting - Lay-in	4	EA	7	\$0
	Walls - Concrete Block	640	SF	6	\$1,876
	Walls - Plaster/Drywall	900	SF	6	\$2,484
	Work Sink	8	EA	6	\$3,032
Restroom					
	Accessories	4,780	SF	6	\$44,088
	Accessories	921	SF	7	\$0
	Benches	12	LF	6	\$174
	Ceiling - Lay-in	8	SF	5	\$60
	Ceiling - Lay-in	1,151	SF	6	\$3,456
	Ceiling - Lay-in	310	SF	7	\$0
	Ceiling - Plaster/Drywall	3,812	SF	6	\$13,192
	Ceiling - Plaster/Drywall	304	SF	7	\$0
	Doors - Steel Doors incl hw	9	EA	6	\$2,709
	Doors - Transom Window	2	SF	7	\$0
	Doors - Wood Doors inclu hw	16	EA	6	\$4,816
	Doors - Wood Doors inclu hw	3	EA	7	\$0

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Restroom					
	Floor - Tile Ceramic/ Porcelain	5,230	SF	6	\$11,206
	Floor - Tile Ceramic/ Porcelain	614	SF	7	\$0
	Floor - Tile/Sheet	204	SF	6	\$204
	Floor Drain	39	EA	6	\$41,307
	Floor Drain	7	EA	7	\$0
	Hand Dryer	14	EA	6	\$3,221
	Hand Dryer	2	EA	7	\$0
	Lavatory	45	EA	6	\$14,382
	Lavatory	7	EA	7	\$0
	Lighting - Lay-in	38	EA	6	\$4,521
	Lighting - Lay-in	136	EA	7	\$0
	Partitions	47	EA	6	\$13,955
	Partitions	3	EA	7	\$0
	Showers	4	EA	6	\$1,246
	Student Lockers - One Tier	27	EA	6	\$2,507
	Urinals	19	EA	6	\$6,384
	Urinals	5	EA	7	\$0
	Walls - Concrete Block	4,548	SF	6	\$13,332
	Walls - Plaster/Drywall	986	SF	6	\$2,721
	Walls - Structural Glazed Tile	8,216	SF	6	\$25,848
	Walls - Structural Glazed Tile	1,852	SF	7	\$0
	Walls - Tile Ceramic/ Porcelain	132	SF	6	\$298
	Water Closet	1	EA	5	\$1,344
	Water Closet	71	EA	6	\$23,854
	Water Closet	7	EA	7	\$0

Rooms (Other Than Classrooms) Subtotal:

\$2,270,913

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					
	Ceiling - Lay-in	10	SF	5	\$89
	Ceiling - Lay-in	48,226	SF	6	\$144,823
	Ceiling - Plaster/Drywall	4	SF	5	\$70
	Ceiling - Plaster/Drywall	8,515	SF	6	\$52,724
	Doors - Side-lite	12	EA	6	\$201

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					
	Doors - Steel Doors incl hw	78	EA	6	\$23,477
	Doors - Store Front	14	EA	6	\$16,915
	Doors - Transom Window	295	EA	6	\$4,995
	Drinking Fountains - Double Fountain	11	EA	6	\$3,696
	Drinking Fountains - Triple Fountain	1	EA	6	\$444
	Floor - Terrazzo	56,106	SF	6	\$470,959
	Floor - Tile/Sheet	135	SF	6	\$73
	Lighting - Lay-in	782	EA	6	\$93,039
	Lighting - Pendent/Surface	39	EA	6	\$4,832
	Lighting - Wall Mounted	10	EA	6	\$1,239
	Student Lockers - One Tier	1,344	EA	6	\$124,771
	Walls - Concrete Block	456	SF	6	\$1,337
	Walls - Masonry	26,296	SF	6	\$82,727
	Walls - Plaster/Drywall	25	SF	5	\$251
	Walls - Plaster/Drywall	3,135	SF	6	\$13,897
	Walls - Structural Glazed Tile	4	SF	5	\$255
	Walls - Structural Glazed Tile	45,275	SF	6	\$142,435
Safety					
	Camera Viewing Station	5	EA	6	\$3,413
	Metal Dedector	3	EA	6	\$2,642
	Security Cameras	146	EA	6	\$28,329
Stairs					
	Ceiling - Lay-in	22	SF	5	\$196
	Ceiling - Lay-in	5,270	SF	6	\$15,826
	Ceiling - Plaster/Drywall	1,070	SF	6	\$7,834
	Floor - Terrazzo	4,870	SF	6	\$40,879
	Handrails	684	LF	6	\$5,927
	Lighting - Lay-in	77	EA	6	\$9,161
	Lighting - Pendent/Surface	8	EA	6	\$991
	Stairs - Terrazzo	260	LF	6	\$2,413
	Walls - Masonry	1,110	SF	6	\$3,492
	Walls - Structural Glazed Tile	17,122	SF	6	\$53,866
Vertical Conveyance					
	Elevator	1	EA	6	\$0
	Elevator - Hydraulic Elevator	1	EA	6	\$19,238

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Building Interior Subtotal:					\$1,377,457

Total Building Cost

\$10,185,687

SITE

Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Athletic					
	Lighting	10	EA	6	\$36,043
	Metal Bleachers	150	LF	6	\$6,692
	Surface - Asphalt	25,736	SF	6	\$62,196
	Surface - Natural	239,051	SF	6	\$198,269
Civil/Drainage					
	Civil/ Drainage - Bioswale	20,091	SF	6	\$120,667
	Civil/ Drainage - Catch Basin	17	EA	7	\$0
	Civil/ Drainage - Site Drain	19	EA	7	\$0
	Civil/ Drainage - Site Manhole	15	EA	7	\$0
Fencing					
	Fencing - Chain Link	848	LF	6	\$15,922
	Fencing - New Standard Ornamental	3,450	LF	6	\$110,066
Landscape					
	Benches	1	EA	4	\$2,826
	Benches	22	EA	6	\$9,461
	Irrigation	327,199	SF	6	\$369,637
	Landscape - Grass	88,148	SF	6	\$73,110
	Landscape - Hardscape- Concrete	100	SF	5	\$1,276
	Landscape - Hardscape- Concrete	22,341	SF	6	\$115,331
	Parkway trees	41	EA	7	\$0
	Planting Beds/ Area	26,358	SF	6	\$43,346
	Retaining Wall - Masonry	586	SF	7	\$0
	Trash Receptacles	10	EA	7	\$0
Parking Lot					
	Concrete Curbs	2,481	LF	7	\$0
	Interior Plantings	378	LF	7	\$0
	Lighting - Lighting	1	EA	5	\$881

SITE

Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Parking Lot					
	Lighting - Lighting	27	EA	6	\$12,563
	Lighting - Pole Mounted	16	EA	6	\$23,240
	Surface - Asphalt	43,383	SF	6	\$104,844
	Surface - Concrete	1,986	SF	6	\$4,800
	Trash Compactor	1	EA	6	\$0
	Vehicular Screening	615	LF	7	\$0
Playground					
	Surface - Poured Surface	1,473	SF	6	\$10,785
Sidewalks					
	Sidewalks - Internal Walks	3,533	LF	6	\$42,438
	Sidewalks - Perimeter Sidewalks	20	SF	5	\$191
	Sidewalks - Perimeter Sidewalks	22,912	SF	6	\$45,542
Signage					
	Flag Pole - Flag Pole	3	EA	7	\$0
	Monument - Building Mounted Cut Letter Sign	1	EA	7	\$0
	Monument - Sign-Lighted	1	EA	7	\$0
Site Subtotal:					\$1,410,123
Total Site Cost					\$1,410,123
Campus Total ^{2 3}					\$11,595,811

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.

- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-



Infinity Math Science and Technology High School

3120 S Kostner Ave Chicago, IL 60623

Co-locating on this campus are WORLD LANGUAGE HS, INFINITY HS, SOCIAL JUSTICE HS and MULTICULTURAL HS

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Regular Classroom	1st Floor	2-102	A.8.1	1,132	1	4	30	152	24	40	Y	Y	N
Computer Lab	Computer Lab	1st Floor	1-101	B150	1,180	1	2	30	152	24	40	Y	N	N
Computer Lab	Computer Lab	1st Floor	2-101	B180	1,097	1	2	30	152	24	40	Y	N	N
Computer Lab	Computer Lab	1st Floor	3-102	D132	1,185	1	20	40	112	16	40	Y	Y	N
Computer Lab	Computer Lab	1st Floor	4-102	D161	1,185	1	20	40	112	16	40	Y	Y	Y
Dance Room	Dance Room	2nd Floor	Dance Studio	D203	1,406	1	6	16	140		40	N	Y	N
Fitness Room	Fitness Room	2nd Floor	Weight Room	C203	1,576	1	6	16	140	0	40	N	Y	N
Music Room	Regular Classroom	1st Floor	1-102	A101	1,208	1	2	14	152	24	10	N	Y	N
Music Room	Music Room	2nd Floor	4-200	A230	1,660	2	6	22	240	0	40	N	Y	N
Music Room	Music Room	2nd Floor	4-201	A235	1,660	2	6	22	60	0	40	N	Y	N
Office	Regular Classroom	1st Floor	1-104	B133	582	1	2	10	76	12	40	Y	Y	N
Office	Regular Classroom	1st Floor	2-104	B161	582	1	2	10	76	12	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	1-103	B151	890	1	2	12	152	24	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	1-104	B131	890	1	2	12	152	24	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	1-105	B152	890	1	2	12	152	24	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	1-106	B132	890	1	2	12	152	24	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	1-107	B153	890	1	2	12	152	24	40	Y	N	N
Regular Classroom	Regular Classroom	1st Floor	1-108		890	14	6	2	144	32	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	1-202	B213	890	1	2	12	114	18	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	1-204	B212	890	1	2	12	114	18	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	1-206	B211	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	1-207	B219	890	1	2	12	114	18	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	1-208	B210	890	1	2	12	114	18	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	2-103	B179	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	2-105	B180	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	2-106	B160	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	2-107	B181	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	2-108	B160	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	2-202	B224	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	2-204	B223	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	2-205	B229	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	2-206	B222	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	2-208	B221	890	1	2	12	114	18	40	Y	Y	Y
Regular Classroom	Regular Classroom		3-104	D131	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	3-105	D149	534	1	4	12	56	8	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	3-106	D130	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	3-107	D150	875	1	6	16	84	12	40	Y	Y	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	1st Floor	3-108	D129	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	3-109	D151	913	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	3-203	D217	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	3-205	D218	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	3-207	D219	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	3-208	D212	875	1	6	16	84	12	40	Y	N	Y
Regular Classroom	Regular Classroom	2nd Floor	3-209	D220	913	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom		4-104	D160	875	1	6	16	84	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	4-105	D178	534	1	4	12	56	8	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	4-106	D159	875	1	6	16	84	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	4th Floor	4-107	D179	875	1	6	16	84	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	4-108	D158	875	1	6	16	84	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	4th Floor	4-109	D180	913	1	6	16	84	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	4-203	D231	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	4-205	D232	875	1	6	16	84	12	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	4-207	D233	875	1	6	16	84	12	40	Y	N	N
Regular Classroom	Regular Classroom	2nd Floor	4-208	D226	875	1	6	16	84	12	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	4-209	D234	913	1	6	16	84	12	40	Y	N	Y
Regular Classroom	Faculty Lounge	1st Floor	N/A	C102	722	1	4	8	0	0	40	N	Y	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	1-201	B216	1,211	1	12	40	152	24	40	Y	N	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	1-205	B218	1,211	1	12	40	152	24	40	Y	N	N
Science Lab Level 1	Science Lab Level 1	2nd Floor	2-201	B226	1,211	1	12	40	152	24	40	Y	Y	Y
Science Lab Level 1	Science Lab Level 1	2nd Floor	2-203	B228	1,211	1	12	40	152	24	40	Y	Y	Y
Science Lab Level 3	Science Lab Level 3	2nd Floor	3-202	D215	1,185	1	12	34	112	16	40	Y	N	Y
Science Lab Level 3	Science Lab Level 3	2nd Floor	3-206	D213	1,185	1	12	34	112	16	40	Y	N	Y
Science Lab Level 3	Science Lab Level 3	2nd Floor	4-202	D229	1,185	1	12	34	112	16	40	Y	N	Y
Science Lab Level 3	Science Lab Level 3	2nd Floor	4-206	D227	1,185	1	12	34	112	16	40	Y	Y	Y