

Facility Assessment Detail

This report contains the findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility feature and system by visual observation only; they do not test operability or perform destructive testing inside walls, ceilings or floors. The rankings below reflect the assessors' visual evaluations of the property condition as of that date. For additional information, you may visit the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx.

Condition Rankings and Descriptions

- Rank 7:** The item/system is new or in good condition and no work is required.
- Rank 6:** The item/system requires general cleaning and/or routine maintenance.
- Rank 5:** The item/system requires repairs and has not reached the end of its serviceable life.
- Rank 4:** The item/system has reached its expected useful life, but is still fully operational. CPS will maintain until replacement occurs.
- Rank 3:** The item/system has surpassed its expected useful life and has limited operability. CPS will maintain until replacement occurs.
- Rank 2:** The item/system has surpassed its expected useful life and has low operability. CPS will maintain until replacement occurs.
- Rank 1:** The item's/system's failure leads to an immediate life safety condition for occupants or to the potential of an uninhabitable facility.¹

Definitions

- Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- Total Campus Need** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Building: Main Category: EXTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Chimney		Brick Chimney - Concrete/ Mortar Liner	Boiler Room	5	16	LF	\$28,600	
Chimney		Metal Flue	Boiler Room	6	92	LF	\$5,920	
Cornice		Cornice - Cast Stone	Entire Building	6	346	LF	\$18,614	
Cornice		Cornice - Metal Projecting	Entire Building	5	369	LF	\$109,180	
Doors		Exterior Steel Door	Entire Building	5	19	EA	\$20,712	
Entrance		Concrete Exterior Stairs	Entire Building	6	118	LF	\$12,656	
Entrance		Concrete Ramp	West Entrances	6	22	LF	\$3,067	
Entrance		Entrance Controls - Audio and Video	Main, east entrances	7	2	EA	\$0	
Entrance		Ramp Handrails	West Entrances	6	46	LF	\$0	
Entrance		Stair Handrails	Southeast, east entrances	6	11	LF	\$0	
Foundation		Masonry Foundation	Entire Building	7	21,426	SF	\$0	
Lighting		Exterior Lights - Parapet or Roof Mounted	Roof	6	5	EA	\$2,503	
Lighting		Exterior Lights - Wall Mounted	Entire Building	6	11	EA	\$2,360	
Lintels		Lintels - Steel	Entire Building	6	531	LF	\$20,046	

Building: Main
Category: EXTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Parapet		Coping - Clay Tile	Roof	6	591	LF	\$0	
Parapet		Coping - Terra Cotta	Roof	6	478	LF	\$0	
Parapet		Parapet < 16" Height	Roof	6	314	LF	\$48,898	
Parapet		Parapet > 30" Height	Roof	6	332	LF	\$86,169	
Parapet		Parapet 16" to 30" Height	Roof	6	307	LF	\$63,744	
Parapet		Parapet 16" to 30" Height	Auditorium roof - north parapet	5	116	LF	\$37,223	
Roof System		Asphalt Gravel Ballast Roof	Roof	5	21,426	SF	\$272,995	
Roof System		Exterior Downspouts	Roof	6	162	LF	\$3,012	
Roof System		Roof Structure: Steel with Clay Tile Arch	Roof	7	21,426	SF	\$0	
Superstructure		Heavy Timber	Entire Building	7	39,036	SF	\$0	
Walls		Brick	Entire Building	6	26,179	SF	\$172,954	
Walls		Brick	Southeast - low roof area	5	2,064	SF	\$46,752	
Walls		Stone - Cast	Entire Building	6	2,284	SF	\$32,661	
Windows		Window - Guards perforated	1st Floor	6	2,043	SF	\$0	
Windows		Windows - Sash Aluminum Double-pane	Entire Building	6	4,572	SF	\$39,228	
EXTERIOR Sub Total							\$1,027,294	

Building: Main
Category: ELECTRICAL

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Emergency System		Automatic Transfer switch	Electrical Room	4	1	EA	\$8,866	
Emergency System		Emergency Battery Packs - Lunchroom and Gym	Lunch Room	6	1	EA	\$107	
Emergency System		Exit Signs - Corridors and Stairs	Corridors and Stairs	2	15	EA	\$13,943	School does not have an emergency generator or UPS and the existing signs are not provided with the battery backup or the exit sign is more than 20 years of age and not working or not provided in all areas
Emergency System		Exit Signs - Lunchroom - Gym - multipurpose rooms Gym		2	2	EA	\$1,859	School does not have an emergency generator or UPS and the existing signs are not provided with the battery backup or the exit sign is more than 20 years of age and not working or not provided in all areas

Building: Main
Category: ELECTRICAL

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Emergency System		Exit Signs - Lunchroom - Gym - multipurpose rooms	Lunch Room	2	4	EA	\$3,718	School does not have an emergency generator or UPS and the existing signs are not provided with the battery backup or the exit sign is more than 20 years of age and not working or not provided in all areas
Emergency System		Independent Electrical Service for emergency power	Electrical Room	4	1	EA	\$17,160	
Emergency System		Public Announcement System	Entire Building	5	39,036	SF	\$55,821	
Emergency System		Security System - CCTV	Entire Building	6	39,036	SF	\$55,821	
Emergency System		Security System - Intrusion detection	Mechanical Room	6	39,036	SF	\$36,284	
Main Service		Main Electrical service - Live Front - 1000 A and below 120/208/3PH	Electrical Room	4	1	EA	\$96,096	
Power Distribution		Lighting and power panels	Entire Building	6	5	EA	\$3,575	
Power Distribution		Lighting and power panels	Entire Building	4	5	EA	\$27,170	
Power Distribution		Main distribution panels 400-600 amp	Electrical Room	3	2	EA	\$24,310	Distribution Panels are live fronts
Power Distribution		Main distribution panels above 600 amp	Electrical Room	4	1	EA	\$18,590	
Power Distribution		Main distribution panels less than 400 amp	Electrical Room	3	1	EA	\$6,578	Distribution Panel is a Live Front
Power Distribution		Main distribution panels less than 400 amp	Electrical Room	4	1	EA	\$6,578	
Power Distribution		Main distribution panels less than 400 amp	Electrical Room	6	1	EA	\$1,216	
Power Distribution		Transformers 120/240-120/208	Electrical Room	4	1	EA	\$15,730	Excessive Hum and running Hot - Very Old
ELECTRICAL Sub Total							\$393,422	

Building: Main
Category: FIRE PROTECTION

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Fire Alarm		Fire Alarm System	Boiler Room	4	39,036	SF	\$137,879	
FIRE PROTECTION Sub Total							\$137,879	

Building: Main
Category: MECHANICAL

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Air Conditioning		Window A/C Unit	Entire Building	5	9	EA	\$9,653	
Air Handling Systems		Air Intake - Built Up Air Handling Unit	Exterior Facades	5	2	EA	\$32,032	

Building: Main
Category: MECHANICAL

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Air Handling Systems		Multi Zone Built Up Air Handling Unit - Steam 15,001 to 25,000 cfm	Mechanical Room	4	1	EA	\$92,950	
Air Handling Systems		Multi Zone Built Up Air Handling Unit - Steam 8,000 to 15,000 cfm	Mechanical Room	4	1	EA	\$57,200	
Air Handling Systems		Multi Zone Built Up Air Handling Unit - Steam 8,000 to 15,000 cfm	Mechanical Room	4	1	EA	\$57,200	
Air Handling Systems		Multi Zone Built Up Air Handling Unit Auxiliaries - Hot Water 15,000 to 25,000 cfm	Mechanical Room	4	1	EA	\$32,890	
Air Handling Systems		Return Duct Work - Sheet Metal - Exterior Vertical Shaft and Ducts	Entire Building	4	200	LF	\$125,840	
Boiler Systems		Boiler Assembly - Steam - Low Pressure Scotch Marine Boiler 76-100 HP	Boiler Room	4	2	EA	\$237,380	
Boiler Systems		Boiler Auxiliary - Steam Boiler 76-100 HP	Boiler Room	4	2	EA	\$40,040	
Boiler Systems		Chemical Feeder - Steam Boiler	Boiler Room	6	3	EA	\$901	
Boiler Systems		Combustion Dampers	Boiler Room	5	2	EA	\$3,146	
Boiler Systems		Feed Water Pumps and Tank - Steam Boilers	Boiler Room	3	1	EA	\$31,460	Tank has failed and leaking on floor - High Chemical Usage
Heating Devices		Unit Heater - Electric	Entire Building	5	6	EA	\$15,444	
Heating Devices		Unit Heater - Hot Water	Mechanical Room	6	1	EA	\$1,430	
Mechanical Plumbing		Condensate Assembly - Pumps and Tank	Mechanical Room	5	1	EA	\$9,438	
Mechanical Plumbing		Piping - Condensate - Steel or Galvanized	Entire Building	5	250	LF	\$8,133	
Mechanical Plumbing		Piping - Steam - Steel or Galvanized	Entire Building	5	250	LF	\$12,370	
Temperature Control		Pneumatic System	Entire Building	3	39,036	SF	\$279,107	Controls are more than 30 years of age and only few of the controls work (most damper and valve actuators are not working, not all sensors are responding, most dampers and valves are operating in manual mode, temperatures are not maintained).
Temperature Control		Thermostats - Pneumatic	Entire Building	4	19	EA	\$12,498	
Temperature Control		Zone Dampers	Plenum	3	19	EA	\$16,030	Dampers opened manually by wood blocks, controls do not work
Ventilation		Exhaust Fan - Indoor	Attic	4	1	EA	\$5,577	
Ventilation		Exhaust Fans - Roof Mounted 500 to 1,500 cfm	Low Roof and East Facade	3	2	EA	\$4,576	Fans are inoperative - Cover off Roof Fan
MECHANICAL Sub Total							\$1,085,295	

Building: Main
Category: PLUMBING

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Building: Main								
Category: PLUMBING								
Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Hot Water		Hot Water Heater - Gas 150,000 -300,000 BTU/HR	Boiler Room	4	2	EA	\$45,760	
Piping		Domestic Piping - Cold Water from Risers to Fixtures	Entire Building	4	39,036	SF	\$12,839	
Piping		Domestic Piping - Cold Water Risers	Entire Building	4	39,036	SF	\$25,120	
Piping		Domestic Piping - Hot Water from Riser to fixtures	Entire Building	4	39,036	SF	\$8,373	
Piping		Domestic Piping - Hot Water Return Risers	Entire Building	4	39,036	SF	\$17,863	
Piping		Domestic Piping - Hot Water Risers	Entire Building	4	39,036	SF	\$21,212	
Piping		Domestic Piping Cold Water Horizontal lines	Entire Building	4	39,036	SF	\$93,222	
Piping		Domestic Piping Hot Water Horizontal lines	Entire Building	4	39,036	SF	\$77,034	
Piping		Domestic Piping Hot Water Return Lines	Entire Building	4	39,036	SF	\$44,657	
Piping		Sanitary Piping	Entire Building	5	39,036	SF	\$24,003	
Piping		Vent Piping	Entire Building	5	39,036	SF	\$13,955	
Pumps		Domestic Booster Pump simplex	Mechanical Room	5	1	EA	\$8,580	Pump Runs, but Pressure Reducing valve is inoperative and valved off. Notified CPS of issue.
PLUMBING Sub Total							\$392,618	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Administrative Suites	Administrative Suites/Offices	Ceiling - Plaster/Drywall	1st floor, Main Office & Principal's Office	6	615	SF	\$1,741	
Administrative Suites	Administrative Suites/Offices	Ceiling - Plaster/Drywall	1st floor, former store room next to engine room	6	57	SF	\$161	
Administrative Suites	Administrative Suites/Offices	Ceiling - Plaster/Drywall	1st floor east, In Fan Room (engine room)	6	780	SF	\$2,208	
Administrative Suites	Administrative Suites/Offices	Ceiling - Plaster/Drywall	1st floor east, Engineer's Office	6	140	SF	\$396	
Administrative Suites	Administrative Suites/Offices	Ceiling - Plaster/Drywall	Second floor, teacher lounge	6	276	SF	\$781	
Administrative Suites	Administrative Suites/Offices	Ceiling - Plaster/Drywall	1st floor east, former engineer's office	6	110	SF	\$311	
Administrative Suites	Administrative Suites/Offices	Flooring - Concrete	1st floor east, In Fan Room (engine room)	5	780	SF	\$3,681	
Administrative Suites	Administrative Suites/Offices	Flooring - Tile Ceramic/Porcelain	1st floor east, Engineer's Office	5	140	SF	\$2,202	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Administrative Suites	Administrative Suites/Offices	Flooring - Tile/Sheet	Second floor, teacher lounge	6	276	SF	\$395	
Administrative Suites	Administrative Suites/Offices	Flooring - Tile/Sheet	1st floor, Main Office & Principal's Office	6	615	SF	\$879	
Administrative Suites	Administrative Suites/Offices	Flooring - Tile/Sheet	1st floor, former store room next to engine room	6	57	SF	\$82	
Administrative Suites	Administrative Suites/Offices	Flooring - Tile/Sheet	1st floor east, former engineer's office	6	110	SF	\$157	
Administrative Suites	Administrative Suites/Offices	Lighting - Pendant/Surface	1st floor east, former engineer's office	6	4	SF	\$3	
Administrative Suites	Administrative Suites/Offices	Lighting - Pendant/Surface	1st floor, Main Office & Principal's Office	7	9	SF	\$0	
Administrative Suites	Administrative Suites/Offices	Lighting - Pendant/Surface	1st floor, former store room next to engine room	6	1	SF	\$1	
Administrative Suites	Administrative Suites/Offices	Lighting - Pendant/Surface	1st floor east, Engineer's Office	4	2	SF	\$13	
Administrative Suites	Administrative Suites/Offices	Lighting - Pendant/Surface	Second floor, teacher lounge	7	4	SF	\$0	
Administrative Suites	Administrative Suites/Offices	Lighting - Pendant/Surface	1st floor east, In Fan Room (engine room)	6	8	SF	\$6	
Administrative Suites	Administrative Suites/Offices	Walls - Concrete Block	1st floor east, former engineer's office	6	210	SF	\$601	
Administrative Suites	Administrative Suites/Offices	Walls - Concrete Block	1st floor east, Engineer's Office	5	90	SF	\$680	
Administrative Suites	Administrative Suites/Offices	Walls - Concrete Block	1st floor east, Engineer's Office	6	460	SF	\$1,316	
Administrative Suites	Administrative Suites/Offices	Walls - Concrete Block	1st floor east, In Fan Room (engine room)	6	1,020	SF	\$2,917	
Administrative Suites	Administrative Suites/Offices	Walls - Concrete Block	1st floor east, former engineer's office	6	210	SF	\$601	
Administrative Suites	Administrative Suites/Offices	Walls - Concrete Block	1st floor, former store room next to engine room	6	150	SF	\$429	
Administrative Suites	Administrative Suites/Offices	Walls - Plaster/Drywall	1st floor, former store room next to engine room	6	150	SF	\$354	
Administrative Suites	Administrative Suites/Offices	Walls - Plaster/Drywall	1st floor, Main Office & Principal's Office	6	1,380	SF	\$3,256	
Administrative Suites	Administrative Suites/Offices	Walls - Plaster/Drywall	Second floor, teacher lounge	6	1,040	SF	\$2,454	
Doors		Interior Steel Doors incl hw	Entire Building	6	1	EA	\$283	
Doors		Interior Wood Doors incl hw	Entire Building	4	10	EA	\$32,089	
Doors		Interior Wood Doors incl hw	Entire Building	6	45	EA	\$12,741	
Doors		Transom Window	Entire Building	6	124	SF	\$2,305	
Drinking Fountains	Corridors	Single Fountain	1st Floor	6	1	EA	\$386	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Drinking Fountains	Corridors	Single Fountain	2nd Floor	6	1	EA	\$386	
Drinking Fountains	Corridors	Single Fountain	3rd Floor	6	1	EA	\$386	
Gymnasium / Auditorium	Gymnasium.Auditorium	Ceiling - Lay-In	1st floor, former Assembly Hall seating area	6	2,400	SF	\$18,876	
Gymnasium / Auditorium	Gymnasium.Auditorium	Ceiling - Splined	1st floor, former Assembly Hall seating area	6	670	SF	\$6,228	
Gymnasium / Auditorium	Gymnasium.Auditorium	Flooring - Tile/Sheet	1st floor, former Assembly Hall seating area	6	3,070	SF	\$4,390	
Gymnasium / Auditorium	Gymnasium.Auditorium	Lighting - Lay-In	1st floor, former Assembly Hall seating area	6	32	SF	\$23	
Gymnasium / Auditorium	Gymnasium.Auditorium	Sound System	1st floor, former Assembly Hall seating area	6	1	EA	\$5,005	
Gymnasium / Auditorium	Gymnasium.Auditorium	Stage Curtain	1st floor, former Assembly Hall seating area	6	2	EA	\$18,876	
Gymnasium / Auditorium	Gymnasium.Auditorium	Walls - Concrete Block	1st floor, former Assembly Hall seating area	6	1,535	SF	\$13,170	
Gymnasium / Auditorium	Gymnasium.Auditorium	Walls - Plaster/Drywall	1st floor, former Assembly Hall seating area	6	1,535	SF	\$13,170	
Gymnasium / Auditorium	Gymnasium.Auditorium	Walls - Structural Glazed Tile	1st floor, former Assembly Hall seating area	6	856	SF	\$6,120	
Kitchen	Warming Kitchen	Ceiling - Plaster/Drywall	1st floor, Kitchen Prep Room (former Men Teacher's Rest Room)	6	225	SF	\$849	
Kitchen	Warming Kitchen	Flooring - Tile/Sheet	1st floor, Kitchen Prep Room (former Men Teacher's Rest Room)	6	225	SF	\$322	
Kitchen	Warming Kitchen	Lighting - Pendant/Surface	1st floor, Kitchen Prep Room (former Men Teacher's Rest Room)	6	4	SF	\$3	
Kitchen	Warming Kitchen	Wall - Plaster/Drywall	1st floor, Kitchen Prep Room (former Men Teacher's Rest Room)	6	710	SF	\$1,675	
Library	Library	Casework	Second floor, room 204	6	8	LF	\$245	
Library	Library	Flooring Tile/ Sheet	Second floor, room 204	6	885	SF	\$1,266	
Library	Library	Lighting - Pendant/ Surface	Second floor, room 204	6	14	SF	\$10	
Lunchroom	Lunchroom	Ceiling - Lay-In	1st floor, former Assembly Hall seating area	6	2,510	SF	\$5,384	
Lunchroom	Lunchroom	Flooring - Tile/Sheet	1st floor, former Assembly Hall seating area	6	2,510	SF	\$3,589	
Lunchroom	Lunchroom	Lighting - Lay-In	1st floor, former Assembly Hall seating area	6	24	SF	\$17	
Lunchroom	Lunchroom	Serving Line	1st floor, former Assembly Hall seating area	7	20	LF	\$0	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Lunchroom	Lunchroom	Wall - Concrete Block	1st floor, former Assembly Hall seating area	6	1,158	SF	\$3,312	
Lunchroom	Lunchroom	Wall - Plaster/Drywall	1st floor, former Assembly Hall seating area	6	1,148	SF	\$2,709	
Lunchroom	Lunchroom	Wall - Structural Glazed Tile	1st floor, former Assembly Hall seating area	6	856	SF	\$6,120	
MDF/IDF		Finishes	Third floor, inside room 306	6	96	SF	\$327	
MDF/IDF		Ventilation and Cooling	Third floor, inside room 306	4	1	EA	\$14,014	
Mechanical/Service Rooms		Air Handling/ Mechanical Room	1st floor east, Fan Room (engine room)	6	780	SF	\$3,681	
Mechanical/Service Rooms		Air Handling/ Mechanical Room	1st floor center, Fan Room (engine room)	6	500	SF	\$2,360	
Mechanical/Service Rooms		Boiler Room	Boiler Room	5	1,280	SF	\$14,497	
Mechanical/Service Rooms		Janitor's Closet	Entire Building	6	4	SF	\$19	
Mechanical/Service Rooms		Mechanical/Service Rooms	Pump Room	5	490	SF	\$5,550	
Mechanical/Service Rooms		Storage Room	Second floor, next to room 205	6	91	SF	\$429	
Mechanical/Service Rooms		Storage Room	1st floor, Store Room next to Engine Room	6	120	SF	\$566	
Mechanical/Service Rooms		Storage Room	Former Coal Room	5	370	SF	\$4,190	
Staff Restroom	Early Childhood Student Restroom	Accessories	In Kindergarten Room 101	6	66	SF	\$510	
Staff Restroom	Staff Restroom	Accessories	1st floor, Men's	6	25	SF	\$193	
Staff Restroom	Staff Restroom	Accessories	1st floor, Kitchen	6	63	SF	\$486	
Staff Restroom	Staff Restroom	Accessories	1st floor east, former engineer's toilet	6	30	SF	\$232	
Staff Restroom	Locker/Shower Room	Accessories	Second floor, inside teacher lounge	6	73	SF	\$564	
Staff Restroom	Children's Standard Student Restroom	Accessories	1st floor, Girls'	6	256	SF	\$1,977	
Staff Restroom	Children's Standard Student Restroom	Accessories	Second floor, boys	6	233	SF	\$1,799	
Staff Restroom	Children's Standard Student Restroom	Accessories	Third floor, girls	6	256	SF	\$1,977	
Staff Restroom	Staff Restroom	Accessories	1st floor, Engineer's Office	6	30	SF	\$232	
Staff Restroom	Children's Standard Student Restroom	Ceiling - Plaster/Drywall	Third floor, girls	6	256	SF	\$725	
Staff Restroom	Children's Standard Student Restroom	Ceiling - Plaster/Drywall	Second floor, boys	6	233	SF	\$660	
Staff Restroom	Early Childhood Student Restroom	Ceiling - Plaster/Drywall	In Kindergarten Room 101	6	66	SF	\$187	
Staff Restroom	Staff Restroom	Ceiling - Plaster/Drywall	1st floor, Men's	6	25	SF	\$71	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Staff Restroom	Staff Restroom	Ceiling - Plaster/Drywall	1st floor, Kitchen	6	63	SF	\$178	
Staff Restroom	Staff Restroom	Ceiling - Plaster/Drywall	1st floor, Engineer's Office	6	30	SF	\$85	
Staff Restroom	Staff Restroom	Ceiling - Plaster/Drywall	1st floor east, former engineer's toilet	6	30	SF	\$85	
Staff Restroom	Locker/Shower Room	Ceiling - Plaster/Drywall	Second floor, inside teacher lounge	7	73	SF	\$0	
Staff Restroom	Children's Standard Student Restroom	Ceiling - Plaster/Drywall	1st floor, Girls'	6	256	SF	\$725	
Staff Restroom	Early Childhood Student Restroom	Floor Drain	In Kindergarten Room 101	7	1	EA	\$0	
Staff Restroom	Children's Standard Student Restroom	Floor Drain	1st floor, Girls'	6	1	EA	\$300	
Staff Restroom	Children's Standard Student Restroom	Floor Drain	Third floor, girls	6	1	EA	\$300	
Staff Restroom	Children's Standard Student Restroom	Floor Drain	Second floor, boys	6	1	EA	\$300	
Staff Restroom	Staff Restroom	Flooring - Tile Ceramic/Porcelain	1st floor, Engineer's Office	6	30	SF	\$76	
Staff Restroom	Children's Standard Student Restroom	Flooring - Tile Ceramic/Porcelain	1st floor, Girls'	6	256	SF	\$652	
Staff Restroom	Children's Standard Student Restroom	Flooring - Tile Ceramic/Porcelain	Second floor, boys	6	233	SF	\$593	
Staff Restroom	Staff Restroom	Flooring - Tile Ceramic/Porcelain	1st floor east, former engineer's toilet	6	30	SF	\$76	
Staff Restroom	Locker/Shower Room	Flooring - Tile Ceramic/Porcelain	Second floor, inside teacher lounge	6	73	SF	\$186	
Staff Restroom	Children's Standard Student Restroom	Flooring - Tile Ceramic/Porcelain	Third floor, girls	6	256	SF	\$652	
Staff Restroom	Staff Restroom	Flooring - Tile/Sheet	1st floor, Kitchen	6	63	SF	\$90	
Staff Restroom	Early Childhood Student Restroom	Flooring - Tile/Sheet	In Kindergarten Room 101	6	66	SF	\$94	
Staff Restroom	Staff Restroom	Flooring - Tile/Sheet	1st floor, Men's	6	25	SF	\$36	
Staff Restroom	Staff Restroom	Lavatory	1st floor east, former engineer's toilet	6	1	EA	\$372	
Staff Restroom	Staff Restroom	Lavatory	1st floor, Engineer's Office	6	1	EA	\$372	
Staff Restroom	Staff Restroom	Lavatory	1st floor, Kitchen	6	1	EA	\$372	
Staff Restroom	Staff Restroom	Lavatory	1st floor, Men's	6	1	EA	\$372	
Staff Restroom	Children's Standard Student Restroom	Lavatory	1st floor, Girls'	6	2	EA	\$744	
Staff Restroom	Locker/Shower Room	Lavatory	Second floor, inside teacher lounge	6	1	EA	\$372	
Staff Restroom	Children's Standard Student Restroom	Lavatory	Second floor, boys	6	4	EA	\$1,487	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Staff Restroom	Children's Standard Student Restroom	Lavatory	Third floor, girls	6	2	EA	\$744	
Staff Restroom	Early Childhood Student Restroom	Lavatory	In Kindergarten Room 101	6	1	EA	\$372	
Staff Restroom	Children's Standard Student Restroom	Lighting - Pendant/ Surface	Third floor, girls	6	4	SF	\$3	
Staff Restroom	Early Childhood Student Restroom	Lighting - Pendant/ Surface	In Kindergarten Room 101	6	1	SF	\$1	
Staff Restroom	Children's Standard Student Restroom	Lighting - Pendant/ Surface	1st floor, Girls'	6	5	SF	\$4	
Staff Restroom	Staff Restroom	Lighting - Pendant/ Surface	1st floor, Kitchen	4	1	SF	\$4	
Staff Restroom	Staff Restroom	Lighting - Pendant/ Surface	1st floor, Engineer's Office	4	1	SF	\$4	
Staff Restroom	Staff Restroom	Lighting - Pendant/ Surface	1st floor east, former engineer's toilet	4	1	SF	\$4	
Staff Restroom	Children's Standard Student Restroom	Lighting - Pendant/ Surface	Second floor, boys	6	4	SF	\$3	
Staff Restroom	Locker/Shower Room	Lighting - Pendant/ Surface	Second floor, inside teacher lounge	7	1	SF	\$0	
Staff Restroom	Locker/Shower Room	Lighting - Wall Mounted	Second floor, inside teacher lounge	6	1	EA	\$29	
Staff Restroom	Staff Restroom	Lighting - Wall Mounted	1st floor, Men's	4	1	EA	\$322	
Staff Restroom	Staff Restroom	Lighting - Wall Mounted	1st floor, Kitchen	4	1	EA	\$322	
Staff Restroom	Children's Standard Student Restroom	Partitions	Second floor, boys	6	2	EA	\$359	
Staff Restroom	Children's Standard Student Restroom	Partitions	1st floor, Girls'	6	4	EA	\$717	
Staff Restroom	Children's Standard Student Restroom	Partitions	Third floor, girls	6	5	EA	\$897	
Staff Restroom	Locker/Shower Room	Partitions	Second floor, inside teacher lounge	6	2	EA	\$359	
Staff Restroom	Staff Restroom	Partitions	1st floor, Kitchen	6	1	EA	\$179	
Staff Restroom	Children's Standard Student Restroom	Urinals	Second floor, boys	6	9	EA	\$3,346	
Staff Restroom	Children's Standard Student Restroom	Wall - Concrete Block	Second floor, boys	6	469	SF	\$1,341	
Staff Restroom	Staff Restroom	Wall - Concrete Block	1st floor east, former engineer's toilet	5	108	SF	\$815	
Staff Restroom	Children's Standard Student Restroom	Wall - Concrete Block	1st floor, Girls'	6	175	SF	\$501	
Staff Restroom	Staff Restroom	Wall - Concrete Block	1st floor, Engineer's Office	6	108	SF	\$309	
Staff Restroom	Children's Standard Student Restroom	Wall - Concrete Block	Third floor, girls	6	286	SF	\$818	

Building: Main
Category: INTERIOR

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Staff Restroom	Early Childhood Student Restroom	Wall - Plaster/Drywall	In Kindergarten Room 101	6	480	SF	\$1,133	
Staff Restroom	Locker/Shower Room	Wall - Plaster/Drywall	Second floor, inside teacher lounge	6	94	SF	\$222	
Staff Restroom	Children's Standard Student Restroom	Wall - Plaster/Drywall	Third floor, girls	6	106	SF	\$250	
Staff Restroom	Staff Restroom	Wall - Plaster/Drywall	1st floor, Kitchen	6	480	SF	\$1,133	
Staff Restroom	Staff Restroom	Wall - Structural Glazed Tile	1st floor east, former engineer's toilet	5	108	SF	\$5,097	
Staff Restroom	Staff Restroom	Wall - Structural Glazed Tile	1st floor, Engineer's Office	5	108	SF	\$5,097	
Staff Restroom	Children's Standard Student Restroom	Wall - Tile Ceramic/ Porcelain	Third floor, girls	6	195	SF	\$496	
Staff Restroom	Children's Standard Student Restroom	Wall - Tile Ceramic/ Porcelain	Second floor, boys	6	115	SF	\$293	
Staff Restroom	Children's Standard Student Restroom	Wall - Tile Ceramic/ Porcelain	1st floor, Girls'	6	435	SF	\$1,107	
Staff Restroom	Locker/Shower Room	Wall - Tile Ceramic/ Porcelain	Second floor, inside teacher lounge	6	208	SF	\$529	
Staff Restroom	Staff Restroom	Wall - Tile Ceramic/ Porcelain	1st floor, Men's	6	175	SF	\$445	
Staff Restroom	Children's Standard Student Restroom	Water Closet	Second floor, boys	6	2	EA	\$744	
Staff Restroom	Staff Restroom	Water Closet	1st floor east, former engineer's toilet	6	1	EA	\$372	
Staff Restroom	Staff Restroom	Water Closet	1st floor, Engineer's Office	6	1	EA	\$372	
Staff Restroom	Staff Restroom	Water Closet	1st floor, Kitchen	6	1	EA	\$372	
Staff Restroom	Staff Restroom	Water Closet	1st floor, Men's	6	1	EA	\$372	
Staff Restroom	Early Childhood Student Restroom	Water Closet	In Kindergarten Room 101	6	1	EA	\$372	
Staff Restroom	Locker/Shower Room	Water Closet	Second floor, inside teacher lounge	6	2	EA	\$744	
Staff Restroom	Children's Standard Student Restroom	Water Closet	1st floor, Girls'	6	4	EA	\$1,487	
Staff Restroom	Children's Standard Student Restroom	Water Closet	Third floor, girls	6	5	EA	\$1,859	
Vocational Shop	Classroom	Work Sink		7	1	EA	\$0	
INTERIOR Sub Total							\$283,270	

Building: Main
Category: ROOM

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Casework	Classroom	Casework		6	6	LF	\$215	

Building: Main
Category: ROOM

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	16	LF	\$572	
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	40	LF	\$1,430	
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	7	LF	\$250	
Casework	Classroom	Casework		6	40	LF	\$1,430	
Ceiling	Classroom	Plaster/Drywall		6	880	SF	\$2,492	
Ceiling	Classroom	Plaster/Drywall		6	895	SF	\$2,534	
Ceiling	Classroom	Plaster/Drywall		6	895	SF	\$2,534	
Ceiling	Classroom	Plaster/Drywall		6	885	SF	\$2,506	
Ceiling	Classroom	Plaster/Drywall		6	880	SF	\$2,492	
Ceiling	Classroom	Plaster/Drywall		6	900	SF	\$2,548	
Ceiling	Classroom	Plaster/Drywall		6	880	SF	\$2,492	
Ceiling	Classroom	Plaster/Drywall		6	900	SF	\$2,548	
Ceiling	Classroom	Plaster/Drywall		6	885	SF	\$2,506	
Ceiling	Classroom	Plaster/Drywall		6	340	SF	\$963	
Ceiling	Classroom	Plaster/Drywall		6	115	SF	\$326	
Ceiling	Classroom	Plaster/Drywall		6	895	SF	\$2,534	
Chalk Board	Classroom	Chalk Board		4	30	LF	\$3,647	
Chalk Board	Classroom	Chalk Board		4	4	LF	\$486	
Chalk Board	Classroom	Chalk Board		4	12	LF	\$1,459	
Chalk Board	Classroom	Chalk Board		4	12	LF	\$1,459	
Chalk Board	Classroom	Chalk Board		4	30	LF	\$3,647	
Chalk Board	Classroom	Chalk Board		4	10	LF	\$1,216	
Chalk Board	Classroom	Chalk Board		4	4	LF	\$486	
Chalk Board	Classroom	Chalk Board		4		LF		
Chalk Board	Classroom	Chalk Board		4	8	LF	\$972	
Corridors	Corridors	Concrete Epoxy/Painted	1st Floor	5	622	SF	\$2,935	
Corridors	Corridors	Pendant/Surface	1st Floor	6	2,003	EA	\$1,432	
Corridors	Corridors	Pendant/Surface	3rd Floor	6	1,273	EA	\$910	
Corridors	Corridors	Pendant/Surface	2nd Floor	6	1,317	EA	\$942	
Corridors	Corridors	Pendant/Surface	Stairs, entire building	6	690	EA	\$493	
Corridors	Corridors	Plaster/Drywall	1st Floor	6	3,425	SF	\$8,081	

Building: Main
Category: ROOM

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Corridors	Corridors	Plaster/Drywall	3rd Floor	6	2,668	SF	\$6,295	
Corridors	Corridors	Plaster/Drywall	2nd Floor	6	2,800	SF	\$6,607	
Corridors	Corridors	Plaster/Drywall	Stairs, entire building	6	5,616	SF	\$13,251	
Corridors	Corridors	Single Water Cooler	2nd Floor	6	1	EA	\$615	
Corridors	Corridors	Single Water Cooler	1st Floor	6	1	EA	\$615	
Corridors	Corridors	Single Water Cooler	3rd Floor	6	1	EA	\$615	
Corridors	Corridors	Stair Handrails	Stairs, entire building	6	264	LF	\$0	
Corridors	Corridors	Structural Glazed Tile	1st Floor	6	1,000	SF	\$7,150	
Corridors	Corridors	Student Lockers	3rd Floor	7	60	EA	\$0	
Corridors	Corridors	Tile/Sheet Flooring	Stairs, entire building	6	456	SF	\$652	
Corridors	Corridors	Tile/Sheet Flooring	2nd Floor	6	1,317	SF	\$1,883	
Corridors	Corridors	Tile/Sheet Flooring	3rd Floor	6	1,273	SF	\$1,820	
Corridors	Corridors	Tile/Sheet Flooring	1st Floor	6	1,381	SF	\$1,975	
Corridors Ceiling	Corridors	Plaster/Drywall	2nd Floor	6	1,317	SF	\$3,729	
Corridors Ceiling	Corridors	Plaster/Drywall	3rd Floor	6	1,273	SF	\$3,604	
Corridors Ceiling	Corridors	Plaster/Drywall	Stairs, entire building	6	690	SF	\$1,954	
Corridors Ceiling	Corridors	Plaster/Drywall	1st Floor	6	2,003	SF	\$5,671	
Stairs	Corridors	Asphalt	Stairs, entire building	6	112	SF	\$801	
Floor	Classroom	Tile/Sheet		6	895	SF	\$1,280	
Floor	Classroom	Tile/Sheet		6	895	SF	\$1,280	
Floor	Classroom	Tile/Sheet		6	900	SF	\$1,287	
Floor	Classroom	Tile/Sheet		6	895	SF	\$1,280	
Floor	Classroom	Tile/Sheet		6	880	SF	\$1,258	
Floor	Classroom	Tile/Sheet		6	900	SF	\$1,287	
Floor	Classroom	Tile/Sheet		6	880	SF	\$1,258	
Floor	Classroom	Tile/Sheet		6	340	SF	\$486	
Floor	Classroom	Tile/Sheet		6	880	SF	\$1,258	
Floor	Classroom	Tile/Sheet		6	885	SF	\$1,266	
Floor	Classroom	Tile/Sheet		6	115	SF	\$164	
Floor	Classroom	Tile/Sheet		6	885	SF	\$1,266	
LIBRARY_CEILING	Library	Plaster/Drywall	Second floor, room 204	6	885	SF	\$2,506	
LIBRARY_WALL	Library	Plaster/Drywall	Second floor, room 204	6	1,682		\$3,969	
Lighting	Classroom	Pendant/Surface		7	4	EA	\$0	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	

Building: Main
Category: ROOM

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Lighting	Classroom	Pendant/Surface		7	14	EA	\$0	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Lighting	Classroom	Pendant/Surface		7	14	EA	\$0	
Lighting	Classroom	Pendant/Surface		7	2	EA	\$0	
Lighting	Classroom	Pendant/Surface		6	14	EA	\$1,001	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	10	LF	\$0	
Marker Board	Classroom	Marker Board		7	10	LF	\$0	
Marker Board	Classroom	Marker Board		7	17	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	16	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	8	LF	\$0	
Marker Board	Classroom	Marker Board		7	4	LF	\$0	
Wall	Classroom	Plaster/Drywall		6	1,500	SF	\$3,539	
Wall	Classroom	Plaster/Drywall		6	1,455	SF	\$3,433	
Wall	Classroom	Plaster/Drywall		6	910	SF	\$2,147	
Wall	Classroom	Plaster/Drywall		6	592	SF	\$1,397	
Wall	Classroom	Plaster/Drywall		6	1,466	SF	\$3,459	
Wall	Classroom	Plaster/Drywall		6	1,466	SF	\$3,459	
Wall	Classroom	Plaster/Drywall		6	1,466	SF	\$3,459	
Wall	Classroom	Plaster/Drywall		6	1,455	SF	\$3,433	
Wall	Classroom	Plaster/Drywall		6	1,455	SF	\$3,433	
Wall	Classroom	Plaster/Drywall		6	1,500	SF	\$3,539	
Wall	Classroom	Plaster/Drywall		6	1,455	SF	\$3,433	
Wall	Classroom	Plaster/Drywall		6	1,455	SF	\$3,433	
ROOM Sub Total							\$183,291	
Building Main Sub Total							\$3,503,069	

Building: SITE
Category: SITE

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
-------	-----------	------	----------	------	----------	------	------	--------

Building: SITE
Category: SITE

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Civil/Drainage		Catch Basin	Entire Site	6	5	EA	\$2,717	
Civil/Drainage		Site Manhole	East Entrances	7	1	EA	\$0	
Fencing		Chain Link	Parking Lot	6	228	LF	\$3,270	
Fencing		Ornamental Iron	Main Entrance	6	231	LF	\$4,360	
Fencing		Ornamental Iron	Playground north and south, parking lot	7	572	LF	\$0	
Fencing		Wood Fencing w/ Steel Frame	Site - East	6	124	LF	\$1,521	
Landscape		Asphalt Play Area/Hardscape	Playground	6	7,456	SF	\$6,397	
Landscape		Benches	Entire Site	6	16	EA	\$3,775	
Landscape		Grass	Entire Site	6	5,260	SF	\$2,106	
Landscape		Hardscape - Concrete	Main Entrance	6	997	SF	\$1,882	
Landscape		Parkway trees	Entire Site	6	19	EA	\$5,434	
Landscape		Planting Beds/ Areas	Entire Site	6	3,547	SF	\$0	
Landscape		Synthetic Turf Play Field	Playground	6	8,915	SF	\$22,310	
Landscape		Trash Receptacles	Playground	6	4	EA	\$831	
Parking Lot		Asphalt	Parking Lot	6	12,905	SF	\$11,072	
Parking Lot		Concrete	Alley	6	1,102	SF	\$0	
Parking Lot		Lights, Pole Mounted	Playground	6	6	EA	\$6,864	
Parking Lot		Trash Compactor	Alley	6	1	EA	\$3,575	
Parking Lot		Trash Enclosure	Alley	6	512	SF	\$5,491	
Playground		Playground Equipment - School Age 5-12	Playground	7	2	EA	\$0	
Playground		Playground Surfacing - Poured Surface	Playground	7	8,915	SF	\$0	
Sidewalks		Internal Walks	Playground	6	358	LF	\$3,379	
Sidewalks		Perimeter Sidewalks	Entire Site	6	8,759	SF	\$16,533	
Signage		Flag Pole	Main Entrance	6	1	EA	\$0	
Signage		Marquee - Free Standing Back Lighted	Playground	6	1	EA	\$0	

SITE Sub Total \$101,519

SITE Sub Total \$101,519

Building: SITE

Category: SITE

Group	Sub Group	Item	Location	Rank	Quantity	Unit	Cost	Reason
Total Campus Need ^{2 3}							\$3,604,588	

¹ It is very rare for an assessor to find a feature in this condition. If they do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in summary reports; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Room Summary

Room Number	Room Size	Voice Outlet	Data Outlet	Elect Outlet	Noise Level	Glaze Window Area	Operable Window Area	No. of Window AC	Window Stop	Smart Board	Power Strip	Room Type	Room Sub Type	Location
Building: Main														
101	900	0	1	10	40	180	90	0	N	N	Y	Classroom		
102	900	0	1	10	40	180	90	1	N	N	Y	Classroom		
201	895	1	0	10	40	132	66	1	N	N	N	Classroom		
202	895	1	0	10	40	132	66	1	N	N	N	Classroom		
203	880	1	0	10	40	132	66		N	N	N	Classroom		
205	885	1	0	10	40	132	66		N	N	N	Classroom		
300	340	1	0	16	40	44	22	1	N	N	N	Classroom		
302	895	1	0	12	40	132	66		N	N	Y	Classroom		
303	880	1	0	10	40	132	66		N	N	N	Classroom		
304	880	1	0	10	40	132	66		N	N	N	Classroom		
305	885	1	0	12	40	132	66		N	N	N	Classroom		
306	115	0	0	2	40	0	0		N	N	N	Classroom		
Other	690								N	N	N	Corridors		Stairs, entire building
Other	73								N	N	N	Restroom	Locker/Shower Room	Second floor, inside teacher lounge
Other	276			6					N	N	N	Administrative Suites/Offices		Second floor, teacher lounge
Other	885								N	N	N	Library		Second floor, room 204
Other	256								N	N	N	Restroom	Children's Standard Student Restroom	Third floor, girls
Other	233								N	N	N	Restroom	Children's Standard Student Restroom	Second floor, boys
Other	615			12					N	N	Y	Administrative Suites/Offices		1st floor, Main Office & Principal's Office
Other	110			4					N	N	Y	Administrative Suites/Offices		1st floor east, former engineer's office
Other	30								N	N	N	Restroom	Staff Restroom	1st floor east, former engineer's toilet
Other	30								N	N	N	Restroom	Staff Restroom	1st floor, Engineer's Office
Other	140			4					N	N	Y	Administrative Suites/Offices		1st floor east, Engineer's Office
Other	780			4					N	N	Y	Administrative Suites/Offices		1st floor east, In Fan Room (engine room)
Other	57			2					N	N	N	Administrative Suites/Offices		1st floor, former store room next to engine room
Other	1273								N	N	N	Corridors		3rd Floor
Other	2510								N	N	N	Lunch & Multipurpose Room	Lunchroom	1st floor, former Assembly Hall seating area
Other	1317								N	N	N	Corridors		2nd Floor
Other	63								N	N	N	Restroom	Staff Restroom	1st floor, Kitchen
Other	225								N	N	N	Kitchen	Warming Kitchen	1st floor, Kitchen Prep Room (former Men Teacher's Rest Room)

Room Summary

Room Number	Room Size	Voice Outlet	Data Outlet	Elect Outlet	Noise Level	Glaze Window Area	Operable Window Area	No. of Window AC	Window Stop	Smart Board	Power Strip	Room Type	Room Sub Type	Location
Other	25								N	N	N	Restroom	Staff Restroom	1st floor, Men's
Other	256								N	N	N	Restroom	Children's Standard Student Restroom	1st floor, Girls'
Other	66								N	N	N	Restroom	Early Childhood Student Restroom	In Kindergarten Room 101
Other	2003								N	N	N	Corridors		1st Floor
Other	3070								N	N	N	Gymnasia	Gymnasium.Auditorium	1st Floor