

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1956	4	169,086	\$5,872,980
SITE				\$322,689
<b>Campus Total</b>			<b>169,086</b>	<b>\$6,195,669</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio and Video	#1- Main Accessible- SE	1	EA	6	\$702	
	Exterior Doors - Exterior AMP Door	#1- Main Accessible- SE	3	EA	6	\$2,022	
	Exterior Doors - Exterior AMP Door	#2- S	6	EA	6	\$4,044	
	Exterior Doors - Exterior AMP Door	#27- SE	2	EA	6	\$1,348	
	Exterior Doors - Exterior AMP Door	#3- SW	3	EA	6	\$2,022	
	Exterior Doors - Exterior FRP Door	#11- SW	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#14- SW	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#17- SE	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#18- SE	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#19- SE	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#20- SE	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#6- NW	1	EA	6	\$631	
	Exterior Doors - Exterior FRP Door	#8- NW	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#9- NW	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	Roof Access - Roof #8	6	EA	6	\$3,788	
	Exterior Doors - Exterior Steel Door	#12- SW	1	EA	5	\$1,341	Paint peeling
	Exterior Doors - Exterior Steel Door	#13- SW	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#15- SW	2	EA	4	\$7,645	deteriorated
	Exterior Doors - Exterior Steel Door	#16.5- Incinerator Room- NE	2	EA	5	\$2,683	Repair door mullion
	Exterior Doors - Exterior Steel Door	#20- SE	1	EA	5	\$1,341	Worn
	Exterior Doors - Exterior Steel Door	#21- NE	1	EA	6	\$481	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#22- NE	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#23- NE	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#24- NE	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#26A- NE	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#4- SW	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#5- W	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Roof Access - Roof #8	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	#10- W	1	EA	4	\$3,823	Deterioration
	Exterior Doors - Exterior Wood Door	#16- SW	1	EA	4	\$3,823	Deteriorating
	Exterior Doors - Exterior Wood Door	#16.2- SW	1	EA	4	\$3,823	Deteriorating
	Exterior Doors - Exterior Wood Door	#16.3- Mechanical room- NW	1	EA	4	\$3,823	Deteriorating
	Exterior Doors - Exterior Wood Door	#22- NE	1	EA	4	\$3,823	Deteriorating
	Exterior Doors - Exterior Wood Door	#7- NW	1	EA	6	\$481	
	Exterior Doors - Overhead Rolling/ Garage Door	#16.1- SW	2	EA	6	\$2,867	
	Exterior Doors - Overhead Rolling/ Garage Door	#16.4- NE	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	#16.6- NE	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	#7.5- NW	1	EA	6	\$1,433	
	Exterior Doors - Side lite	#6- NW	2	EA	6	\$627	
	Exterior Doors - Side lite	Roof Access - Roof #8	1	EA	6	\$313	
	Exterior Doors - Store Front	#26- E	6	EA	5	\$11,017	Gaps between doors
	Exterior Doors - Transom Lite	#1- Main Accessible- SE	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#2- S	9	EA	6	\$2,820	
	Exterior Doors - Transom Lite	#26- E	6	EA	6	\$1,880	
	Exterior Doors - Transom Lite	#3- SW	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#5- W	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#6- NW	1	EA	6	\$313	
	Exterior Stairs - Concrete	#10- W	27	LF	6	\$2,208	
	Exterior Stairs - Concrete	#11- SW	6	LF	6	\$491	
	Exterior Stairs - Concrete	#20- SE	3	LF	6	\$245	
	Exterior Stairs - Concrete	#22- NE	20	LF	5	\$2,192	Spalling
	Exterior Stairs - Concrete	#26- E	90	LF	6	\$7,359	
	Exterior Stairs - Concrete	#3- SW	10	LF	5	\$1,096	Cracks & spalling
	Exterior Stairs - Concrete	#4- SW	18	LF	6	\$1,472	
	Exterior Stairs - Concrete	#6- NW	5	LF	5	\$548	spalling
	Exterior Stairs - Concrete	#7- NW	3	LF	6	\$245	
	Exterior Stairs - Concrete	#9- NW	24	LF	6	\$1,962	
	Exterior Stairs - Steel or Aluminum	#5- W	30	LF	6	\$115	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Stairs - Stone	#20- SE	3	LF	6	\$339	
	Exterior Stairs - Stone	#22- NE	3	LF	6	\$339	
	Exterior Stairs - Stone	#5- W	3	LF	6	\$339	
	Power Door Operator and Controls	#1- Main Accessible- SE	1	EA	6	\$0	
	Stair Handrail - Steel_Stair Handrail	#10- W	18	LF	6	\$156	
	Stair Handrail - Steel_Stair Handrail	#10- W	10	LF	4	\$1,502	Missing
	Stair Handrail - Steel_Stair Handrail	#22- NE	16	LF	6	\$139	
	Stair Handrail - Steel_Stair Handrail	#23- NE	15	LF	6	\$130	
	Stair Handrail - Steel_Stair Handrail	#26- E	32	LF	6	\$277	
	Stair Handrail - Steel_Stair Handrail	#4- SW	20	LF	6	\$173	
	Stair Handrail - Steel_Stair Handrail	#5- W	24	LF	6	\$208	
	Stair Handrail - Steel_Stair Handrail	#9- NW	25	LF	6	\$217	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	1,931	LF	7	\$0	
	Foundation - Concrete	Entire Building	30	LF	5	\$16,558	seepage
	Superstructure - Concrete	Entire Building	169,086	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	8	EA	6	\$4,292	
	Exterior Lighting - Wall Mounted	Entire Building	22	EA	6	\$6,352	
<b>Roof System</b>							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof #13	63	LF	6	\$60,145	no liner; has straps
	Coping - Metal	Roof #12	60	LF	6	\$1,927	
	Coping - Metal	Roof #15	52	LF	6	\$1,670	
	Coping - Metal	Roof #16	12	LF	6	\$385	
	Coping - Stone	Roof #1	212	LF	6	\$6,809	
	Coping - Stone	Roof #10	164	LF	6	\$5,267	open joints
	Coping - Stone	Roof #11	48	LF	6	\$1,542	open joints
	Coping - Stone	Roof #13	328	LF	6	\$10,535	
	Coping - Stone	Roof #14	57	LF	6	\$1,831	
	Coping - Stone	Roof #1A	54	LF	6	\$1,734	
	Coping - Stone	Roof #2	32	LF	6	\$1,028	
	Coping - Stone	Roof #3	235	LF	6	\$7,548	
	Coping - Stone	Roof #4	253	LF	6	\$8,126	
	Coping - Stone	Roof #5	593	LF	6	\$19,046	
	Coping - Stone	Roof #6	12	LF	6	\$385	
	Coping - Stone	Roof #7	553	LF	6	\$17,761	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
	Coping - Stone	Roof #8	38	LF	6	\$1,220	
	Coping - Stone	Roof #9	46	LF	6	\$1,477	
	Downspouts - Exterior Downspouts	Roof #1	8	LF	6	\$266	
	Downspouts - Exterior Downspouts	Roof #10	34	LF	6	\$1,130	
	Downspouts - Exterior Downspouts	Roof #11	13	LF	6	\$432	
	Downspouts - Exterior Downspouts	Roof #12	7	LF	6	\$233	
	Downspouts - Exterior Downspouts	Roof #13	189	LF	6	\$6,281	
	Downspouts - Exterior Downspouts	Roof #14	3	LF	6	\$100	
	Downspouts - Exterior Downspouts	Roof #15	6	LF	6	\$199	clean out gutter
	Downspouts - Exterior Downspouts	Roof #16	10	LF	6	\$332	
	Downspouts - Exterior Downspouts	Roof #1A	30	LF	6	\$997	
	Downspouts - Exterior Downspouts	Roof #2	34	LF	6	\$1,130	
	Downspouts - Exterior Downspouts	Roof #3	222	LF	6	\$7,378	
	Downspouts - Exterior Downspouts	Roof #4	300	LF	6	\$9,970	
	Downspouts - Exterior Downspouts	Roof #5	220	LF	6	\$7,311	
	Downspouts - Exterior Downspouts	Roof #6	15	LF	6	\$498	
	Downspouts - Exterior Downspouts	Roof #7	405	LF	6	\$13,459	
	Downspouts - Exterior Downspouts	Roof #8	17	LF	6	\$565	
	Downspouts - Exterior Downspouts	Roof #9	26	LF	6	\$864	
	Parapet - 16" - 30" Height	Roof #1	212	LF	6	\$8,470	
	Parapet - 16" - 30" Height	Roof #11	48	LF	6	\$1,918	
	Parapet - 16" - 30" Height	Roof #13	328	LF	6	\$13,105	
	Parapet - 16" - 30" Height	Roof #14	57	LF	6	\$2,277	
	Parapet - 16" - 30" Height	Roof #1A	54	LF	6	\$2,158	
	Parapet - 16" - 30" Height	Roof #2	32	LF	6	\$1,279	
	Parapet - 16" - 30" Height	Roof #3	211	LF	6	\$8,430	
	Parapet - 16" - 30" Height	Roof #4	253	LF	6	\$10,108	
	Parapet - 16" - 30" Height	Roof #5	180	LF	6	\$7,192	
	Parapet - 16" - 30" Height	Roof #6	12	LF	6	\$479	
	Parapet - 16" - 30" Height	Roof #7	553	LF	6	\$22,095	
	Parapet - 16" - 30" Height	Roof #9	46	LF	6	\$1,838	
	Parapet - Parapet > 30"	Roof #10	164	LF	6	\$10,483	
	Parapet - Parapet > 30"	Roof #3	24	LF	6	\$1,534	
	Parapet - Parapet > 30"	Roof #5	40	LF	6	\$2,557	
	Parapet - Parapet > 30"	Roof #8	38	LF	6	\$2,429	
	Roof Structure - Concrete	Roof #1	2,296	SF	7	\$0	
	Roof Structure - Concrete	Roof #10	1,619	SF	7	\$0	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
	Roof Structure - Concrete	Roof #11	304	SF	7	\$0	
	Roof Structure - Concrete	Roof #12	532	SF	7	\$0	
	Roof Structure - Concrete	Roof #13	6,189	SF	7	\$0	
	Roof Structure - Concrete	Roof #14	565	SF	7	\$0	
	Roof Structure - Concrete	Roof #16	10	SF	7	\$0	
	Roof Structure - Concrete	Roof #1A	266	SF	7	\$0	
	Roof Structure - Concrete	Roof #2	111	SF	7	\$0	
	Roof Structure - Concrete	Roof #3	8,223	SF	7	\$0	
	Roof Structure - Concrete	Roof #4	4,688	SF	7	\$0	
	Roof Structure - Concrete	Roof #5	12,677	SF	7	\$0	
	Roof Structure - Concrete	Roof #6	84	SF	7	\$0	
	Roof Structure - Concrete	Roof #7	7,237	SF	7	\$0	
	Roof Structure - Concrete	Roof #8	998	SF	7	\$0	
	Roof Structure - Concrete	Roof #9	280	SF	7	\$0	
	Roof Structure - Heavy Timber	Roof #15	290	SF	7	\$0	
	Roof - Asphalt Shingle	Roof #15	377	SF	6	\$1,731	
	Roof - Modified Bitumen	Roof #1	2,296	SF	6	\$21,604	
	Roof - Modified Bitumen	Roof #10	1,619	SF	6	\$15,234	
	Roof - Modified Bitumen	Roof #11	304	SF	6	\$2,860	not accessible
	Roof - Modified Bitumen	Roof #12	532	SF	6	\$5,006	not accessible
	Roof - Modified Bitumen	Roof #13	6,189	SF	6	\$58,235	
	Roof - Modified Bitumen	Roof #14	565	SF	5	\$11,885	surface wear, water ponding
	Roof - Modified Bitumen	Roof #16	22	SF	6	\$207	
	Roof - Modified Bitumen	Roof #1A	266	SF	6	\$2,503	
	Roof - Modified Bitumen	Roof #2	111	SF	6	\$1,044	
	Roof - Modified Bitumen	Roof #3	8,223	SF	6	\$77,373	some water ponding and bubbles
	Roof - Modified Bitumen	Roof #4	4,688	SF	5	\$98,613	water ponding, bubbles
	Roof - Modified Bitumen	Roof #5	12,677	SF	6	\$119,283	some minor water ponding, some bubbles
	Roof - Modified Bitumen	Roof #6	84	SF	6	\$790	not accessible
	Roof - Modified Bitumen	Roof #7	7,237	SF	6	\$68,096	some bubbles
	Roof - Modified Bitumen	Roof #8	998	SF	6	\$9,391	
	Roof - Modified Bitumen	Roof #9	280	SF	6	\$2,635	
<b>Walls</b>							
	Canopy - Metal	Entire Building	18	SF	6	\$387	
	Cheek-Wall - Stone	Entire Building	80	SF	6	\$820	
	Cornice - Masonry Projecting Limestone	Entire Building	360	LF	6	\$12,484	
	Exterior Walls - Brick	Entire Building	67,739	SF	6	\$455,274	

## Building: Main

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Walls</b>							
	Exterior Walls - Stone-Cast	Entire Building	10	SF	5	\$176	efflorescence
	Exterior Walls - Stone-Cast	Entire Building	8,513	SF	6	\$57,216	
	Exterior Walls - Wood Siding	Entire Building	252	SF	5	\$1,834	stain/seal
<b>Windows</b>							
	Curtain wall - Glazed Double Pane	Entire Building	2,373	SF	6	\$26,604	
	Curtain wall - Louver	Entire Building	228	SF	6	\$2,556	
	Guard - Guards perforated	Entire Building	3,898	SF	6	\$49,777	Basement and 1st Floor
	Lintels - Steel	Entire Building	2,345	LF	6	\$68,073	
	Lintels - Stone	Entire Building	190	LF	6	\$0	
	Windows - Casement Aluminum Double-pane	Entire Building	300	SF	6	\$2,239	
	Windows - Decorative	Entire Building	12	SF	6	\$90	
	Windows - Sash Aluminum Double-pane	Entire Building	10,336	SF	6	\$77,154	
	Windows - Sash Aluminum Double-pane	Entire Building	1,602	SF	5	\$86,297	poor balances
	Windows - Sash Aluminum	Entire Building	52	SF	5	\$1,867	

### Building Exterior Subtotal:

**\$1,772,327**

## Building: Main

### Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	for 2'd independent feed
	Automatic Transfer Switch	Electrical Room	2	EA	6	\$816	for diesel ac generator
	Emergency A/C Power - Corridors and Stairs	Entire Building	13,838	SF	6	\$4,156	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	5,961	SF	6	\$2,216	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	4,470	SF	6	\$1,662	convent building
	Emergency A/C Power - Multipurpose Room	Entire Building / Basement	2,228	SF	6	\$828	
	Emergency A/C Power - Students Toilets	Entire Building	1,386	SF	6	\$515	
	Emergency Battery Packs - Auditorium and Aisle Lighting	1st Floor	2	EA	6	\$405	
	Emergency Battery Packs - Gym	1st Floor	2	EA	6	\$405	
	Emergency Generator- Outdoor- Diesel - 101 - 150 KW	Site North	1	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	2	EA	4	\$1,091	deteriorated, older, in convent area
	Exit Signs - Corridors and Stairs	Entire Building	50	EA	6	\$7,487	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	5	EA	6	\$749	
	Exit Signs - Multipurpose Room	Entire Building / 1st Floor	18	EA	6	\$2,695	gym and auditorium
	Exit Signs - Multipurpose Room	Entire Building / Basement	2	EA	6	\$299	

**Building: Main**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Security System - CCTV	Entire Building	169,086	SF	6	\$50,777	
	Security System - Intrusion Detection	Entire Building	169,086	SF	6	\$43,523	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	ComEd second feed
	Main Electrical Service- Live Front - 1600 A 120/240/3PH	Electrical Room	1	EA	4	\$55,430	
	Main Electrical Service - 1600 A 277/480/3PH	Electrical Room	1	EA	6	\$5,977	confirmed
	PA System	Entire Building	169,086	SF	6	\$55,612	
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building	12	EA	6	\$3,589	
	Lighting and Power Panels - 100 A	Entire Building	4	EA	6	\$1,196	convert building
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	1	EA	4	\$4,849	old fuse panel
	Lighting and Power Panels - 100 A	Entire Building / Site North	2	EA	6	\$598	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	5	EA	6	\$2,485	convert building
	Lighting and Power Panels - Above 100 A	Entire Building	15	EA	6	\$7,455	
	Lighting and Power Panels - Above 100 A	Entire Building	10	EA	6	\$4,970	
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	1	EA	6	\$528	Stage in auditorium
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	CPDP
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	
	Transformers - 277/480 - 120/240	Entire Building / Electrical Room	1	EA	6	\$1,019	

**Electrical System Subtotal:**

**\$266,789**

**Building: Main**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Electrical Room	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Electrical Room / Entire Building	169,086	SF	6	\$60,448	
	Fire Alarm_System	Electrical Room / Entire Building	169,086	SF	6	\$82,210	
<b>Sprinkler System</b>							
	Sprinkler Heads	1st Floor	4,470	SF	7	\$0	in auditorium only

**Building: Main**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Sprinkler System</b>							
	Sprinkler Piping	1st Floor	4,470	SF	6	\$831	in auditorium only
	Wet Sprinkler System	1st Floor	4,470	SF	6	\$1,151	in auditorium only

**Safty System Subtotal:**

**\$151,045**

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Chemical Pot Feeder	Site North / Mechanical Room	2	EA	6	\$1,213	first floor
	Chiller-Air Cooled-Screw Type-Ground Mounted - 101 - 200 tons	Site North	2	EA	6	\$8,628	
	Glycol Feed	Site North / Mechanical Room	2	EA	6	\$980	first floor
	Pipes - Chilled Water Pipe- Galvanized	Site North / Entire Building	750	LF	6	\$1,416	
	Pressure Fill System	Site North / Mechanical Room	1	EA	6	\$1,405	first floor

**Air Handling Systems**

	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils- - 10001-15000 cfm	Mechanical Room	1	EA	6	\$3,350	serves music room, next to cafeteria
	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils- - 10001-15000 cfm	Mechanical Room	1	EA	6	\$3,350	serves cafeteria, in convent building
	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils- - 10001-15000 cfm	Mechanical Room	1	EA	6	\$3,350	serves auditorium
	Air Handling Unit- Package Single Zone- Indoor- Daul Temperature Coils- - 15001-20000 cfm	Mechanical Room	1	EA	6	\$3,350	serves gym, largest air handler
	Air Intake	Mechanical Room / 1st Floor	1	EA	6	\$5,765	from side
	Air Intake	Mechanical Room / 1st Floor	1	EA	6	\$5,765	from side wall
	Air Intake	Mechanical Room / 1st Floor	1	EA	6	\$5,765	side wall
	Air Intake	Mechanical Room / 1st Floor	1	EA	6	\$5,765	from side wall

**Boiler Systems**

	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 151 - 200 HP	Boiler Room	2	EA	6	\$5,091	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	glycol not being used because of leak.
	Combustion Dampers	Boiler Room	2	EA	6	\$818	fan powered, Greenheck
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 151 - 200 HP	Boiler Room	2	EA	5	\$34,033	Fire tube , not flexible tube, leaks
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	750	LF	6	\$1,416	requires frequent maintenance.
	Steam Traps	Boiler Room / Entire Building	20	EA	5	\$26,298	school uses mostly hot water heating, no traps



## Building: Main

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Gas Booster</b>							
	Gas Booster	Mechanical Room	2	EA	6	\$998	dark blue
<b>Heat Exchangers</b>							
	Heat Exchanger - Steam to Hot Water Shell Type	Boiler Room / Mechanical Room	1	EA	6	\$0	ceiling mounted,
<b>Heating Devices</b>							
	Cabinet Heaters - With Hot Water Coil	Entire Building	53	EA	6	\$18,779	
	Cabinet Heaters - With Hot Water Coil	Entire Building	10	EA	5	\$17,548	deteriorated
	Cabinet Heaters - With Steam Coil	Entire Building	10	EA	6	\$3,566	
	Cabinet Heaters - With Steam Coil	Entire Building	2	EA	5	\$3,526	deteriorated
	Fin Tube - Hot Water	Entire Building	50	LF	5	\$4,071	deteriorated
	Fin Tube - Hot Water	Entire Building	500	LF	6	\$4,719	
	Radiators - Hot Water	Mechanical Room	1	EA	5	\$1,622	
	Radiators - Steam	Entire Building	10	EA	6	\$2,778	in the 2nd, 3d & 4th floor convent area, near gym and boiler room
	Radiators - Steam	Entire Building	2	EA	5	\$3,351	deteriorated
	Unit Heater - Electric	Entire Building	3	EA	6	\$833	
	Unit Heater - Electric	Loading Dock, Gym	3	EA	5	\$3,023	with steam trap
	Unit Heater - Hot Water	Entire Building	9	EA	6	\$2,512	
<b>Mechanical Plumbing</b>							
	Daul Temperature Pump - 21 - 50 HP	Outside Mech. room by/Chillers, Mechanical Room / Mechanical Room	2	EA	5	\$42,885	from heat exchanger, remote convent building and from mechanical room
	Daul Temperature Pump - Less than 10	Outside Mech. room by/Chillers, Mechanical Room	2	EA	6	\$2,222	
<b>Temperature Control</b>							
	DDC System	Entire Building	169,086	SF	6	\$96,717	
	Thermostats - DDC	Entire Building	6	EA	4	\$4,915	deteriorated, older
	Thermostats - DDC	Entire Building	100	EA	6	\$0	
<b>Unit Ventilation</b>							
	Unit Ventilators- Floor Mounted- Hot Water & Chilled Water Coils	Entire Building	50	EA	6	\$62,386	2 pipe system, changed over seasonally.
	Unit Ventilators- Floor Mounted- Hot Water & Chilled Water Coils	Entire Building	7	EA	4	\$155,439	per engineer's comment, 1/8 need repair or replacement
<b>Ventilation</b>							
	Exhaust Fans- Indoor - 1501 - 8000 CFM	Entire Building / 1st Floor	4	EA	6	\$2,370	side wall mounted, from AHUs
	Exhaust Fans- Indoor - 1501 - 8000 CFM	Entire Building / Penthouse	1	EA	6	\$592	
	Exhaust Fans- Indoor - Less than 500 CFM	Entire Building / Loading Dock	6	EA	6	\$1,777	32 inch near ceiling at loading dock, auditorium
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	4	EA	6	\$1,185	bathroom fans

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Ventilation</b>							
	Lab Exhaust Hood	Entire Building / 3rd Floor	4	EA	6	\$4,991	Room 302, 308, 313, 315
	Roof Mounted Duct Work	Entire Building / Roofs	60	LF	6	\$22,741	
	Type I Exhaust Hood- Culinary Arts	Entire Building / 2nd Floor	1	EA	6	\$1,248	Art Room 209
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	6	\$1,248	Cooking Kitchen
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	6	\$920	above reheat equipment
<b>Mechanical System Subtotal:</b>						<b>\$590,341</b>	

**Building: Main**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 150000 - 300000 BTU/HR	Boiler Room	1	EA	5	\$2,249	315000 BTU/hr input, deteriorated, rusted, exposed wires
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	Boiler Room	1	EA	5	\$2,249	500 gallon
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	169,086	SF	6	\$33,851	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	169,086	SF	6	\$41,105	more than 50 years old, some 2006 plumbing upgrade near boilers
	Domestic Piping-Cold Water Risers	Entire Building	169,086	SF	6	\$31,433	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	169,086	SF	6	\$26,597	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	169,086	SF	6	\$31,433	
	Domestic Piping-Hot Water Return Lines	Entire Building	169,086	SF	6	\$24,179	
	Domestic Piping-Hot Water Return Risers	Entire Building	169,086	SF	6	\$24,179	
	Sanitary Piping	Entire Building	169,086	SF	6	\$154,748	more than 50 years old, functional
	Storm Piping	Entire Building	169,086	SF	6	\$147,494	more than 50 years old
	Vent Piping	Entire Building	169,086	SF	6	\$113,643	more than 50 years old
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	convent building
	Pumps - Ejector-Duplex	Mechanical Room	1	EA	6	\$1,387	gym area
	Pumps - Ejector-Simplex	Mechanical Room	1	EA	6	\$745	convent building
	Pumps - Sump-Duplex	Mechanical Room	2	EA	6	\$2,774	boiler area
	Pumps - Sump-Simplex	Mechanical Room / 1st Floor	2	EA	6	\$1,490	at pit under 2 hydraulic elevators
<b>Plumbing System Subtotal:</b>						<b>\$641,533</b>	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #014 (Music Room)</b>							
	Casework	Basement	20	LF	6	\$505	
	Ceiling - Plaster/Drywall	Basement	953	SF	6	\$3,298	
	Doors - Wood Doors inclu hw	Basement	2	EA	6	\$602	
	Floor - Tile	Basement	953	SF	6	\$2,085	
	Lighting - Pendant/Surface	Basement	30	EA	4	\$16,219	T12
	Storage/ Closet	Basement	6	SF	6	\$44	
	Walls - Plaster/Drywall	Basement	1,095	SF	6	\$3,022	
<b>Classroom #101 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	682	SF	6	\$2,360	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	682	SF	6	\$1,492	
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Marker Board	1st Floor	40	LF	6	\$857	
	Storage/ Closet	1st Floor	8	SF	6	\$58	
	Walls - Plaster/Drywall	1st Floor	1,058	SF	6	\$2,920	
<b>Classroom #102 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	682	SF	6	\$2,360	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	682	SF	6	\$1,492	
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Marker Board	1st Floor	40	LF	6	\$857	
	Storage/ Closet	1st Floor	8	SF	6	\$58	
	Walls - Plaster/Drywall	1st Floor	1,058	SF	6	\$2,920	
<b>Classroom #103 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	682	SF	6	\$2,360	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	682	SF	6	\$1,492	
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Marker Board	1st Floor	40	LF	6	\$857	
	Storage/ Closet	1st Floor	8	SF	6	\$58	
	Walls - Plaster/Drywall	1st Floor	1,058	SF	6	\$2,920	
<b>Classroom #104 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	1st Floor	682	SF	6	\$2,360	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	682	SF	6	\$1,492	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #104 (Regular Classroom)</b>							
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Marker Board	1st Floor	40	LF	6	\$857	
	Storage/ Closet	1st Floor	8	SF	6	\$58	
	Walls - Plaster/Drywall	1st Floor	1,058	SF	6	\$2,920	
<b>Classroom #121 (Computer Lab)</b>							
	Ceiling - Plaster/Drywall	1st Floor	928	SF	6	\$3,211	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	928	SF	6	\$2,030	
	Lighting - Pendent/Surface	1st Floor	10	EA	7	\$0	
	Marker Board	1st Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	1st Floor	1,417	SF	6	\$3,911	
	Wireless System	1st Floor	1	EA	6	\$372	
<b>Classroom #201 (Office)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	900	SF	5	\$8,250	Peeling paint throughout
	Doors - Transom Window	2nd Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	900	SF	6	\$1,969	
	Lighting - Pendent/Surface	2nd Floor	8	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,422	SF	6	\$3,925	
<b>Classroom #203 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	615	SF	6	\$2,128	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	615	SF	6	\$1,346	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	60	LF	6	\$1,285	
	Walls - Plaster/Drywall	2nd Floor	1,235	SF	6	\$3,408	
<b>Classroom #204 (Computer Lab)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	615	SF	6	\$2,128	
	Charging Station	2nd Floor	2	EA	6	\$969	
	Doors - Transom Window	2nd Floor	30	SF	6	\$508	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	615	SF	6	\$1,346	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	40	LF	6	\$857	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #204 (Computer Lab)</b>							
	Walls - Plaster/Drywall	2nd Floor	1,180	SF	6	\$3,257	
	Wireless System	2nd Floor	1	EA	6	\$372	
<b>Classroom #205 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	500	SF	6	\$1,502	
	Doors - Transom Window	2nd Floor	30	SF	6	\$508	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	500	SF	6	\$1,094	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	2nd Floor	981	SF	6	\$2,707	
<b>Classroom #207 (Art Room)</b>							
	Casework	2nd Floor	134	LF	6	\$3,384	
	Ceiling - Lay-in	2nd Floor	1,045	SF	6	\$3,138	
	Chalk Board	2nd Floor	6	LF	4	\$551	
	Doors - Transom Window	2nd Floor	30	SF	6	\$508	
	Doors - Wood Doors inclu hw	2nd Floor	4	EA	6	\$1,204	
	Floor - Tile	2nd Floor	1,045	SF	6	\$2,286	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,503	SF	6	\$4,148	
	Work Sink	2nd Floor	2	EA	6	\$758	
<b>Classroom #208 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	615	SF	6	\$2,128	
	Chalk Board	2nd Floor	20	LF	4	\$1,836	
	Doors - Transom Window	2nd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	615	SF	6	\$1,346	
	Lighting - Pendent/Surface	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	2nd Floor	1,180	SF	6	\$3,257	
<b>Classroom #209 (Art Room)</b>							
	Casework	2nd Floor	16	LF	6	\$404	
	Ceiling - Lay-in	2nd Floor	1,213	SF	6	\$3,643	
	Doors - Transom Window	2nd Floor	30	SF	6	\$508	
	Doors - Wood Doors inclu hw	2nd Floor	4	EA	6	\$1,204	
	Floor - Tile	2nd Floor	1,213	SF	6	\$2,654	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #209 (Art Room)</b>							
	Kiln	2nd Floor	1	EA	6	\$2,321	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	2nd Floor	1,685	SF	6	\$4,650	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #210 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	590	SF	6	\$2,042	
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Transom Window	2nd Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	2nd Floor	3	EA	6	\$903	
	Floor - Tile	2nd Floor	590	SF	6	\$1,291	
	Lighting - Pendent/Surface	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	2nd Floor	1,215	SF	6	\$3,353	
<b>Classroom #211 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	2nd Floor	745	SF	6	\$2,578	
	Doors - Transom Window	2nd Floor	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	625	SF	6	\$1,367	
	Floor - Tile	2nd Floor	120	SF	4	\$1,225	Damaged
	Lighting - Pendent/Surface	2nd Floor	8	EA	7	\$0	
	Marker Board	2nd Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	2nd Floor	1,417	SF	6	\$3,911	
<b>Classroom #301 (Regular Classroom)</b>							
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Plaster/Drywall	3rd Floor	715	SF	6	\$2,474	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	715	SF	6	\$1,564	
	Lighting - Lay-in	3rd Floor	9	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Plaster/Drywall	3rd Floor	821	SF	5	\$6,222	scraped and peeling
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #302 (Science Lab Level 1)</b>							
	Casework	3rd Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	3rd Floor	1,090	SF	6	\$3,273	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #302 (Science Lab Level 1)</b>							
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,090	SF	6	\$2,385	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	8	EA	6	\$4,073	
	Lighting - Lay-in	3rd Floor	24	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	6	\$214	
	Science Lab Elements	3rd Floor	1,090	SF	6	\$7,388	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,235	SF	6	\$3,408	
	Work Sink	3rd Floor	7	EA	6	\$2,653	
<b>Classroom #303 (Regular Classroom)</b>							
	Casework	3rd Floor	14	LF	6	\$354	
	Ceiling - Plaster/Drywall	3rd Floor	715	SF	5	\$6,554	peeling badly
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	715	SF	6	\$1,564	
	Lighting - Lay-in	3rd Floor	9	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Plaster/Drywall	3rd Floor	715	SF	6	\$1,973	
<b>Classroom #306 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	615	SF	6	\$2,128	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Terrazzo	3rd Floor	8	SF	4	\$487	damaged and missing pieces
	Floor - Tile	3rd Floor	607	SF	6	\$1,328	
	Lighting - Pendent/Surface	3rd Floor	2	EA	7	\$0	
	Marker Board	3rd Floor	30	LF	6	\$643	
	Walls - Plaster/Drywall	3rd Floor	684	SF	6	\$1,888	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #307 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	900	SF	6	\$3,115	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	900	SF	6	\$1,969	
	Lighting - Pendent/Surface	3rd Floor	11	EA	7	\$0	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #307 (Regular Classroom)</b>							
	Marker Board	3rd Floor	20	LF	6	\$428	
	Walls - Plaster/Drywall	3rd Floor	1,002	SF	6	\$2,765	
<b>Classroom #308 (Science Classroom)</b>							
	Ceiling - Lay-in	3rd Floor	825	SF	6	\$2,477	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	825	SF	6	\$1,805	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	6	\$171	
	Science Lab Elements	3rd Floor	825	SF	6	\$5,592	
	Walls - Plaster/Drywall	3rd Floor	1,007	SF	6	\$2,779	
	Work Sink	3rd Floor	2	EA	6	\$758	
<b>Classroom #310 (Special Program)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	2,414	SF	6	\$8,354	
	Doors - Transom Window	3rd Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Carpet	3rd Floor	1,207	SF	6	\$2,572	
	Floor - Tile	3rd Floor	1,207	SF	6	\$2,641	
	Lighting - Lay-in	3rd Floor	16	EA	6	\$1,904	can lights
	Lighting - Pendent/Surface	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	6	LF	6	\$129	
	Storage/ Closet	3rd Floor	46	SF	6	\$334	
	Walls - Plaster/Drywall	3rd Floor	1,388	SF	6	\$4,545	wood paneling wainscot
	Walls - Plaster/Drywall	3rd Floor	1,388	SF	6	\$4,545	
<b>Classroom #311 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	645	SF	6	\$2,232	
	Doors - Transom Window	3rd Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	645	SF	6	\$1,411	
	Lighting - Pendent/Surface	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	3rd Floor	754	SF	6	\$2,081	
<b>Classroom #313 (Science Lab Level 3)</b>							
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Lay-in	3rd Floor	1,073	SF	6	\$3,222	



**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #313 (Science Lab Level 3)</b>							
	Doors - Side-lite	3rd Floor	12	SF	6	\$201	
	Doors - Transom Window	3rd Floor	27	SF	6	\$457	
	Doors - Wood Doors inclu hw	3rd Floor	3	EA	6	\$903	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,073	SF	6	\$2,348	
	Gas Line	3rd Floor	1	EA	6	\$509	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	6	\$214	
	Science Lab Elements	3rd Floor	1,073	SF	6	\$7,273	
	Walls - Plaster/Drywall	3rd Floor	1,233	SF	6	\$3,403	
	Work Sink	3rd Floor	2	EA	6	\$758	
<b>Classroom #315 (Science Lab Level 3)</b>							
	Casework	3rd Floor	30	LF	6	\$758	
	Ceiling - Plaster/Drywall	3rd Floor	1,150	SF	6	\$3,980	
	Doors - Side-lite	3rd Floor	24	SF	6	\$401	
	Doors - Transom Window	3rd Floor	15	SF	6	\$254	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	1,150	SF	6	\$2,516	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	6	\$214	
	Science Lab Elements	3rd Floor	1,150	SF	6	\$7,795	
	Walls - Plaster/Drywall	3rd Floor	1,233	SF	6	\$3,403	
<b>Classroom #317 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	3rd Floor	945	SF	6	\$3,270	
	Doors - Transom Window	3rd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	945	SF	6	\$2,068	
	Lighting - Pendent/Surface	3rd Floor	10	EA	7	\$0	
	Marker Board	3rd Floor	30	LF	6	\$643	
	Walls - Plaster/Drywall	3rd Floor	1,086	SF	6	\$2,997	
<b>Classroom #400 (Regular Classroom)</b>							
	Casework	4th Floor	30	LF	6	\$758	
	Ceiling - Plaster/Drywall	4th Floor	670	SF	6	\$2,319	
	Chalk Board	4th Floor	14	LF	4	\$1,285	
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #400 (Regular Classroom)</b>							
	Floor - Tile	4th Floor	670	SF	6	\$1,466	
	Lighting - Lay-in	4th Floor	9	EA	7	\$0	
	Marker Board	4th Floor	16	LF	6	\$343	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	776	SF	6	\$2,142	
<b>Classroom #401 (Regular Classroom)</b>							
	Casework	4th Floor	32	LF	6	\$808	
	Ceiling - Plaster/Drywall	4th Floor	935	SF	5	\$8,570	water damage
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	935	SF	6	\$2,046	
	Lighting - Lay-in	4th Floor	20	EA	7	\$0	
	Marker Board	4th Floor	10	LF	6	\$214	
	Walls - Plaster/Drywall	4th Floor	1,055	SF	5	\$7,996	water damage and cracked
	Work Sink	4th Floor	1	EA	6	\$379	
<b>Classroom #402 (Regular Classroom)</b>							
	Casework	4th Floor	16	LF	6	\$404	
	Ceiling - Plaster/Drywall	4th Floor	615	SF	6	\$2,128	
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	615	SF	6	\$1,346	
	Lighting - Lay-in	4th Floor	8	EA	7	\$0	
	Marker Board	4th Floor	16	LF	6	\$343	
	Storage/ Closet	4th Floor	24	SF	6	\$174	
	Walls - Plaster/Drywall	4th Floor	738	SF	6	\$2,037	
<b>Classroom #403 (Regular Classroom)</b>							
	Casework	4th Floor	30	LF	6	\$758	
	Ceiling - Plaster/Drywall	4th Floor	825	SF	5	\$7,562	possible water damage and cracking
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	825	SF	6	\$1,805	
	Lighting - Lay-in	4th Floor	15	EA	7	\$0	
	Marker Board	4th Floor	22	LF	6	\$471	
	Walls - Plaster/Drywall	4th Floor	1,002	SF	6	\$2,765	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #409 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	900	SF	6	\$3,115	
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	892	SF	6	\$1,952	
	Floor - Tile	4th Floor	8	SF	5	\$46	damaged and missing pieces
	Lighting - Pendent/Surface	4th Floor	12	EA	7	\$0	
	Marker Board	4th Floor	22	LF	6	\$471	
	Walls - Plaster/Drywall	4th Floor	1,015	SF	6	\$2,801	
	Work Sink	4th Floor	2	EA	6	\$758	
<b>Classroom #411 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	695	SF	6	\$2,405	peeling paint
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile	4th Floor	687	SF	6	\$1,503	
	Floor - Tile	4th Floor	8	SF	4	\$104	damaged and missing pieces
	Lighting - Pendent/Surface	4th Floor	12	EA	7	\$0	
	Marker Board	4th Floor	22	LF	6	\$471	
	Walls - Plaster/Drywall	4th Floor	810	SF	6	\$2,236	
<b>Classroom #412 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	645	SF	6	\$2,232	
	Chalk Board	4th Floor	2	LF	4	\$184	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile	4th Floor	6	SF	6	\$13	
	Lighting - Pendent/Surface	4th Floor	12	EA	7	\$0	
	Marker Board	4th Floor	26	LF	6	\$557	
	Walls - Plaster/Drywall	4th Floor	736	SF	5	\$5,578	water damage and chipping
<b>Classroom #413 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	1,009	SF	5	\$9,249	peeling
	Chalk Board	4th Floor	4	LF	6	\$89	
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Transom Window	4th Floor	27	SF	6	\$457	
	Doors - Wood Doors inclu hw	4th Floor	3	EA	6	\$903	
	Floor - Tile	4th Floor	1,009	SF	6	\$2,208	
	Lighting - Pendent/Surface	4th Floor	16	EA	7	\$0	
	Marker Board	4th Floor	14	LF	6	\$300	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #413 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	4th Floor	870	SF	5	\$6,594	water damage
	Walls - Plaster/Drywall	4th Floor	290	SF	6	\$950	wood panel
<b>Classroom #414 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	445	SF	6	\$1,540	
	Doors - Transom Window	4th Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	445	SF	6	\$974	
	Lighting - Pendent/Surface	4th Floor	6	EA	7	\$0	
	Marker Board	4th Floor	22	LF	6	\$471	
	Walls - Plaster/Drywall	4th Floor	502	SF	5	\$3,805	water damage and holes in the plaster
<b>Classroom #415 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	745	SF	6	\$2,578	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile	4th Floor	745	SF	6	\$1,630	
	Lighting - Pendent/Surface	4th Floor	8	EA	7	\$0	
	Marker Board	4th Floor	30	LF	6	\$643	
	Walls - Plaster/Drywall	4th Floor	640	SF	6	\$1,766	
	Walls - Plaster/Drywall	4th Floor	213	SF	6	\$698	wood paneling
<b>Classroom #416 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	745	SF	6	\$2,578	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile	4th Floor	745	SF	6	\$1,630	
	Lighting - Pendent/Surface	4th Floor	12	EA	7	\$0	
	Marker Board	4th Floor	30	LF	6	\$643	
	Walls - Plaster/Drywall	4th Floor	844	SF	6	\$2,329	
<b>Classroom #417 (Computer Lab)</b>							
	Ceiling - Plaster/Drywall	4th Floor	441	SF	6	\$1,526	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile	4th Floor	441	SF	6	\$965	
	Lighting - Pendent/Surface	4th Floor	6	EA	7	\$0	
	Marker Board	4th Floor	20	LF	6	\$428	
	Walls - Plaster/Drywall	4th Floor	507	SF	6	\$1,399	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #417 (Computer Lab)</b>							
	Wireless System	4th Floor	1	EA	7	\$0	
<b>Classroom #419 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall	4th Floor	695	SF	6	\$2,405	
	Doors - Transom Window	4th Floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile	4th Floor	695	SF	6	\$1,521	
	Lighting - Pendent/Surface	4th Floor	12	EA	7	\$0	
	Marker Board	4th Floor	26	LF	6	\$557	
	Walls - Plaster/Drywall	4th Floor	800	SF	6	\$2,208	

**Classrooms Subtotal: \$470,494**

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Plaster/Drywall	1st flr #105	222	SF	6	\$768	
	Doors - Wood Doors inclu hw	1st flr #105	1	EA	6	\$301	
	Floor - Terrazzo	1st flr #105	222	SF	6	\$486	
	Lighting - Pendent/Surface	1st flr #105	2	EA	4	\$1,081	T-12
	Power Distribution	1st flr #105	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st flr #105	540	SF	6	\$1,490	
	Ceiling - Plaster/Drywall	1st flr #110	577	SF	6	\$1,997	
	Doors - Wood Doors inclu hw	1st flr #110	1	EA	5	\$1,174	Damaged @ bottom
	Floor - Tile	1st flr #110	577	SF	6	\$1,262	
	Lighting - Pendent/Surface	1st flr #110	5	EA	7	\$0	
	Power Distribution	1st flr #110	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	1st flr #110	786	SF	6	\$2,169	
	Ceiling - Plaster/Drywall	1st flr #113 Security office	213	SF	6	\$737	
	Doors - Wood Doors inclu hw	1st flr #113 Security office	1	EA	6	\$301	
	Floor - Carpet	1st flr #113 Security office	213	SF	6	\$454	
	Lighting - Pendent/Surface	1st flr #113 Security office	2	EA	7	\$0	
	Power Distribution	1st flr #113 Security office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st flr #113 Security office	576	SF	6	\$1,590	
	Ceiling - Plaster/Drywall	1st flr #115 Janitor's office	150	SF	6	\$519	
	Doors - Wood Doors inclu hw	1st flr #115 Janitor's office	1	EA	6	\$301	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Floor - Tile	1st flr #115 Janitor's office	150	SF	6	\$328	
	Lighting - Pendent/Surface	1st flr #115 Janitor's office	2	EA	7	\$0	
	Power Distribution	1st flr #115 Janitor's office	4	EA	6	\$8,500	
	Walls - Masonry	1st flr #115 Janitor's office	193	SF	6	\$607	Wainscot
	Walls - Plaster/Drywall	1st flr #115 Janitor's office	193	SF	6	\$533	
	Ceiling - Splined	1st flr #119 Counseling office	878	SF	6	\$716	
	Doors - Wood Doors inclu hw	1st flr #119 Counseling office	1	EA	6	\$301	
	Floor - Tile	1st flr #119 Counseling office	878	SF	6	\$1,921	
	Lighting - Pendent/Surface	1st flr #119 Counseling office	12	EA	7	\$0	
	Power Distribution	1st flr #119 Counseling office	12	EA	6	\$25,499	
	Walls - Structural Glazed Tile	1st flr #119 Counseling office	1,395	SF	6	\$4,389	
	Ceiling - Plaster/Drywall	1st flr kitchen office	168	SF	6	\$581	
	Doors - Wood Doors inclu hw	1st flr kitchen office	1	EA	6	\$301	
	Floor - Concrete	1st flr kitchen office	168	SF	6	\$89	
	Lighting - Pendent/Surface	1st flr kitchen office	2	EA	7	\$0	
	Power Distribution	1st flr kitchen office	4	EA	6	\$8,500	
	Walls - Structural Glazed Tile	1st flr kitchen office	522	SF	6	\$1,642	
	AC Unit	1st flr NE of gym	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	1st flr NE of gym	158	SF	6	\$547	
	Doors - Wood Doors inclu hw	1st flr NE of gym	1	EA	6	\$301	
	Floor - Tile	1st flr NE of gym	158	SF	6	\$346	
	Lighting - Pendent/Surface	1st flr NE of gym	2	EA	7	\$0	
	Power Distribution	1st flr NE of gym	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st flr NE of gym	468	SF	6	\$1,292	
	Ceiling - Plaster/Drywall	1st flr North of classroom #101	212	SF	6	\$734	
	Doors - Wood Doors inclu hw	1st flr North of classroom #101	1	EA	6	\$301	
	Floor - Tile	1st flr North of classroom #101	212	SF	6	\$464	
	Lighting - Pendent/Surface	1st flr North of classroom #101	2	EA	7	\$0	
	Power Distribution	1st flr North of classroom #101	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st flr North of classroom #101	558	SF	6	\$1,540	
	Ceiling - Plaster/Drywall	1st flr NW corner	1,352	SF	6	\$4,679	
	Doors - Wood Doors inclu hw	1st flr NW corner	1	EA	6	\$301	
	Floor - Tile	1st flr NW corner	1,352	SF	6	\$2,958	
	Lighting - Pendent/Surface	1st flr NW corner	12	EA	7	\$0	
	Power Distribution	1st flr NW corner	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	1st flr NW corner	2,128	SF	6	\$5,873	
	Work Sink	1st flr NW corner	1	EA	6	\$508	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Plaster/Drywall	1st flr NW of gym former Storage	158	SF	6	\$547	
	Doors - Wood Doors inclu hw	1st flr NW of gym former Storage	1	EA	6	\$301	
	Floor - Tile	1st flr NW of gym former Storage	158	SF	6	\$346	
	Lighting - Pendent/Surface	1st flr NW of gym former Storage	2	EA	7	\$0	
	Power Distribution	1st flr NW of gym former Storage	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	1st flr NW of gym former Storage	468	SF	6	\$1,292	
	Ceiling - Plaster/Drywall	1st flr SE main office suite	1,505	SF	6	\$5,208	
	Doors - Side-lite	1st flr SE main office suite	10	SF	6	\$167	At entry door
	Doors - Transom Window	1st flr SE main office suite	9	SF	6	\$152	At entry door
	Doors - Wood Doors inclu hw	1st flr SE main office suite	9	EA	6	\$2,709	
	Floor - Carpet	1st flr SE main office suite	1,300	SF	6	\$2,770	
	Floor - Terrazzo	1st flr SE main office suite	205	SF	6	\$449	
	Lighting - Pendent/Surface	1st flr SE main office suite	19	EA	7	\$0	
	Power Distribution	1st flr SE main office suite	24	EA	6	\$50,997	
	Storage/ Closet	1st flr SE main office suite	64	SF	6	\$464	
	Walls - Plaster/Drywall	1st flr SE main office suite	2,754	SF	6	\$7,601	
	Ceiling - Splined	Case Manager's Office, Room 305	152	SF	6	\$124	
	Doors - Wood Doors inclu hw	Case Manager's Office, Room 305	1	EA	6	\$301	
	Floor - Tile	Case Manager's Office, Room 305	152	SF	6	\$333	
	Lighting - Pendent/Surface	Case Manager's Office, Room 305	2	EA	7	\$0	T-8
	Power Distribution	Case Manager's Office, Room 305	6	EA	6	\$12,749	
	Storage/ Closet	Case Manager's Office, Room 305	55	SF	6	\$399	
	Walls - Plaster/Drywall	Case Manager's Office, Room 305	174	SF	6	\$480	
	Ceiling - Plaster/Drywall	Counselor's Office, Room 407	86	SF	5	\$788	cracked and water damage
	Doors - Wood Doors inclu hw	Counselor's Office, Room 407	1	EA	6	\$301	
	Floor - Tile	Counselor's Office, Room 407	86	SF	6	\$188	
	Lighting - Pendent/Surface	Counselor's Office, Room 407	1	EA	7	\$0	
	Power Distribution	Counselor's Office, Room 407	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Counselor's Office, Room 407	102	SF	5	\$773	water damage and cracks
	Ceiling - Plaster/Drywall	Counselor's Office, Room 420B	180	SF	6	\$623	
	Doors - Transom Window	Counselor's Office, Room 420B	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Counselor's Office, Room 420B	1	EA	6	\$301	
	Floor - Tile	Counselor's Office, Room 420B	180	SF	6	\$394	
	Lighting - Pendent/Surface	Counselor's Office, Room 420B	1	EA	7	\$0	
	Power Distribution	Counselor's Office, Room 420B	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Counselor's Office, Room 420B	207	SF	6	\$571	5' Marker Board "6", 5' Chalk Board "4"
	Ceiling - Plaster/Drywall	Counselor's Office, Room 420C	180	SF	6	\$623	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Doors - Transom Window	Counselor's Office, Room 420C	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Counselor's Office, Room 420C	1	EA	6	\$301	
	Floor - Tile	Counselor's Office, Room 420C	180	SF	6	\$394	
	Lighting - Pendant/Surface	Counselor's Office, Room 420C	1	EA	7	\$0	
	Power Distribution	Counselor's Office, Room 420C	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Counselor's Office, Room 420C	207	SF	6	\$571	5' Marker Board "6"
	Ceiling - Plaster/Drywall	Guidance Specialist, Room 423	136	SF	6	\$471	
	Doors - Transom Window	Guidance Specialist, Room 423	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Guidance Specialist, Room 423	1	EA	6	\$301	
	Floor - Tile	Guidance Specialist, Room 423	136	SF	6	\$298	
	Lighting - Pendant/Surface	Guidance Specialist, Room 423	1	EA	7	\$0	
	Power Distribution	Guidance Specialist, Room 423	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Guidance Specialist, Room 423	156	SF	6	\$431	
	Ceiling - Plaster/Drywall	Nurse's Office, Room 422A	124	SF	6	\$429	
	Doors - Transom Window	Nurse's Office, Room 422A	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Nurse's Office, Room 422A	1	EA	6	\$301	
	Floor - Tile	Nurse's Office, Room 422A	124	SF	6	\$271	
	Lighting - Pendant/Surface	Nurse's Office, Room 422A	1	EA	7	\$0	
	Power Distribution	Nurse's Office, Room 422A	6	EA	6	\$12,749	
	Walls - Structural Glazed Tile	Nurse's Office, Room 422A	142	SF	6	\$447	
	Ceiling - Plaster/Drywall	Office in Room 405	126	SF	5	\$1,155	peeling
	Doors - Wood Doors inclu hw	Office in Room 405	1	EA	6	\$301	
	Floor - Tile	Office in Room 405	126	SF	6	\$276	
	Lighting - Pendant/Surface	Office in Room 405	1	EA	7	\$0	
	Power Distribution	Office in Room 405	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Office in Room 405	144	SF	6	\$397	
	Ceiling - Plaster/Drywall	Office Room 426	95	SF	6	\$329	
	Doors - Transom Window	Office Room 426	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Office Room 426	1	EA	6	\$301	
	Floor - Tile	Office Room 426	95	SF	6	\$208	
	Lighting - Pendant/Surface	Office Room 426	1	EA	7	\$0	
	Power Distribution	Office Room 426	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Office Room 426	131	SF	6	\$362	
	Ceiling - Plaster/Drywall	Office, Room 421	195	SF	6	\$675	
	Doors - Wood Doors inclu hw	Office, Room 421	1	EA	6	\$301	
	Floor - Tile	Office, Room 421	195	SF	6	\$427	
	Lighting - Pendant/Surface	Office, Room 421	1	EA	7	\$0	



## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Power Distribution	Office, Room 421	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	Office, Room 421	224	SF	6	\$618	
	Ceiling - Lay-in	Office, Room 422B	244	SF	6	\$733	
	Doors - Store Front	Office, Room 422B	9	EA	6	\$10,874	
	Doors - Wood Doors inclu hw	Office, Room 422B	1	EA	5	\$1,174	Damaged @ bottom
	Floor - Tile	Office, Room 422B	244	SF	6	\$534	
	Lighting - Lay-in	Office, Room 422B	3	EA	7	\$0	
	Power Distribution	Office, Room 422B	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	Office, Room 422B	280	SF	5	\$2,122	water damage, cracking, peeling
	Ceiling - Plaster/Drywall	Office, Room 424	112	SF	6	\$388	
	Doors - Store Front	Office, Room 424	9	EA	6	\$10,874	
	Doors - Wood Doors inclu hw	Office, Room 424	1	EA	6	\$301	
	Floor - Tile	Office, Room 424	1	SF	6	\$2	
	Lighting - Pendent/Surface	Office, Room 424	1	EA	7	\$0	
	Power Distribution	Office, Room 424	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Office, Room 424	132	SF	5	\$1,000	cracked
	Ceiling - Plaster/Drywall	Office, Room 425	95	SF	6	\$329	
	Doors - Transom Window	Office, Room 425	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Office, Room 425	1	EA	6	\$301	
	Floor - Tile	Office, Room 425	95	SF	6	\$208	
	Lighting - Pendent/Surface	Office, Room 425	1	EA	6	\$124	
	Power Distribution	Office, Room 425	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Office, Room 425	126	SF	6	\$348	
	Ceiling - Plaster/Drywall	Social Worker's Office, Room 420A	137	SF	6	\$474	
	Doors - Wood Doors inclu hw	Social Worker's Office, Room 420A	1	EA	6	\$301	
	Floor - Tile	Social Worker's Office, Room 420A	137	SF	6	\$300	
	Lighting - Pendent/Surface	Social Worker's Office, Room 420A	2	EA	7	\$0	
	Power Distribution	Social Worker's Office, Room 420A	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	Social Worker's Office, Room 420A	157	SF	6	\$433	
	Ceiling - Plaster/Drywall	Teacher's Lounge, Room 418	315	SF	6	\$1,090	
	Doors - Wood Doors inclu hw	Teacher's Lounge, Room 418	1	EA	6	\$301	
	Floor - Terrazzo	Teacher's Lounge, Room 418	315	SF	6	\$689	
	Lighting - Pendent/Surface	Teacher's Lounge, Room 418	2	EA	7	\$0	
	Power Distribution	Teacher's Lounge, Room 418	12	EA	6	\$25,499	
	Walls - Plaster/Drywall	Teacher's Lounge, Room 418	362	SF	6	\$999	6' marker board "6"
<b>Auditorium &amp; Theater</b>							
	Balcony Seating	1st Floor	305	EA	6	\$53,045	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Auditorium &amp; Theater</b>							
	Ceiling - Plaster/Drywall	1st Floor	12,536	SF	6	\$104,511	
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Doors - Store Front	1st Floor	6	EA	6	\$7,249	
	Doors - Transom Window	1st Floor	36	SF	6	\$610	
	Floor - Tile	1st Floor	10,028	SF	6	\$21,940	
	Floor - Wood	1st Floor	2,507	SF	6	\$17,674	
	Lighting - Lay-in	1st Floor	62	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	4	EA	7	\$0	
	Main Floor Seating	1st Floor	720	EA	6	\$125,220	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	2,507	SF	6	\$14,483	
	Stage Curtain	1st Floor	2	EA	6	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor	12	LF	6	\$141	
	Stairs - Terrazzo	1st Floor	90	LF	6	\$689	
	Storage/ Closet	1st Floor	240	SF	6	\$1,740	
	Walls - Plaster/Drywall	1st Floor	14,687	SF	6	\$69,938	
<b>Gymnasia</b>							
	Bleacher Seating	1st Floor	150	EA	6	\$4,341	
	Ceiling - Plaster/Drywall	1st Floor	5,961	SF	6	\$32,904	
	Doors - Steel Doors incl hw	1st Floor	14	EA	6	\$4,214	
	Floor - Wood	1st Floor	5,961	SF	6	\$42,024	
	Lighting - Metal Halide/ High Pressure Sodium	1st Floor	10	EA	6	\$1,337	
	Scoreboards	1st Floor	1	EA	6	\$2,244	
	Sound System	1st Floor	1	EA	6	\$41,654	
	Stage	1st Floor	780	SF	6	\$4,506	
	Stage Curtain	1st Floor	2	EA	6	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	6	\$12,369	
	Stage-Stairs - Wood	1st Floor	12	LF	6	\$141	
	Storage/ Closet	1st Floor	760	SF	6	\$5,510	
	Walls - Plaster/Drywall	1st Floor	4,568	SF	6	\$12,607	
	Walls - Structural Glazed Tile	1st Floor	2,284	SF	6	\$7,185	
<b>Kitchen</b>							
	Ceiling - Plaster/Drywall	1st Floor	1,093	SF	6	\$3,782	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Kitchen</b>							
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Floor - Tile	1st Floor	1,093	SF	6	\$2,391	
	Lighting - Pendent/Surface	1st Floor	18	EA	7	\$0	
	Storage/ Closet	1st Floor	1,605	SF	6	\$11,636	North end of kitchen
	Walls - Structural Glazed Tile	1st Floor	1,555	SF	6	\$4,892	
<b>Library</b>							
	Casework	2nd flr east, #200	240	LF	6	\$6,061	
	Ceiling - Lay-in	2nd flr east, #200	4,094	SF	6	\$12,294	
	Doors - Wood Doors inclu hw	2nd flr east, #200	2	EA	6	\$602	
	Floor - Tile	2nd flr east, #200	4,094	SF	6	\$8,957	
	Lighting - Lay-in	2nd flr east, #200	36	EA	7	\$0	
	Storage/ Closet	2nd flr east, #200	1,680	SF	6	\$12,180	
	Walls - Plaster/Drywall	2nd flr east, #200	2,376	SF	6	\$6,558	
<b>Locker/Shower Room</b>							
	Accessories	1st flr east of gym	580	SF	6	\$2,273	
	Ceiling - Plaster/ Drywall	1st flr east of gym	580	SF	6	\$2,007	
	Doors - Wood Doors inclu hw	1st flr east of gym	1	EA	5	\$1,174	Damaged @door hardware
	Floor Drain	1st flr east of gym	2	EA	6	\$2,118	
	Floor - Terrazzo	1st flr east of gym	580	SF	6	\$1,269	
	Lavatory	1st flr east of gym	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st flr east of gym	9	EA	7	\$0	
	Partitions	1st flr east of gym	5	EA	6	\$1,485	
	Showers	1st flr east of gym	3	EA	6	\$934	
	Student Lockers - Two Tier	1st flr east of gym	66	EA	6	\$3,064	
	Walls - Plaster/Drywall	1st flr east of gym	220	SF	6	\$607	
	Walls - Structural Glazed Tile	1st flr east of gym	960	SF	6	\$3,020	
	Water Closet	1st flr east of gym	2	EA	6	\$672	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Plaster/Drywall	1st Floor	4,470	SF	6	\$15,469	
	Floor - Tile	1st Floor	4,470	SF	6	\$9,780	
	Lighting - Lay-in	1st Floor	8	EA	6	\$952	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	
	Serving Line	1st Floor	50	LF	6	\$2,976	
	Walls - Plaster/Drywall	1st Floor	1,068	SF	6	\$2,948	
	Walls - Structural Glazed Tile	1st Floor	1,068	SF	6	\$3,360	
	Ceiling - Plaster/Drywall	Basement	2,228	SF	6	\$7,710	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Lunch &amp; Multipurpose Room</b>							
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Basement	4	EA	6	\$1,204	
	Floor - Tile/Sheet	Basement	2,228	SF	6	\$2,230	
	Lighting - Pendant/Surface	Basement	20	EA	7	\$0	T8
	Market Board	Basement	12	LF	6	\$257	
	Storage/ Closet	Basement	97	SF	6	\$703	
	Walls - Plaster/Drywall	Basement	2,562	SF	6	\$7,071	
<b>MDF_IDF</b>							
	AC Unit	2nd flr #202	1	EA	4	\$6,086	Not working
	Doors - Wood Doors inclu hw	2nd flr #202	1	EA	6	\$301	
	Finishes	2nd flr #202	194	SF	6	\$1,384	
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	1st Floor	86	SF	6	\$616	
	Loading Docks	1st Floor	50	SF	6	\$358	
	Mechanical/ Service Rooms	1st Floor	356	SF	6	\$2,550	
	Storage Room	1st Floor	2,697	SF	6	\$19,322	
	Janitor's Closet	2nd Floor	6	SF	6	\$43	
	Storage Room	2nd Floor	1,656	SF	6	\$11,864	
	Janitor's Closet	3rd Floor	36	SF	6	\$258	
	Storage Room	3rd Floor	36	SF	6	\$258	
	Janitor's Closet	4th Floor	36	SF	6	\$258	2 @ 18 sf each
	Janitor's Closet	4th Floor	18	SF	6	\$129	2 @ 9 sf each
	Mechanical/ Service Rooms	4th Floor	22	SF	6	\$158	Room 422
	Storage Room	4th Floor	140	SF	6	\$1,003	2 @ 70 sf each
	Storage Room	4th Floor	36	SF	6	\$258	
	Air Tunnel	Basement	1,428	SF	6	\$8,842	
	Boiler Room	Basement	1,407	SF	6	\$10,080	
	Janitor's Closet	Basement	49	SF	6	\$351	
	Mechanical/ Service Rooms	Basement	650	SF	6	\$4,657	
	Storage Room	Basement	2,339	SF	6	\$16,757	
<b>Prep Room</b>							
	Casework	Room 308	30	LF	6	\$758	
	Ceiling - Lay-in	Room 308	237	SF	6	\$712	
	Doors - Wood Doors inclu hw	Room 308	1	EA	6	\$301	
	Floor - Tile	Room 308	237	SF	6	\$519	
	Lighting - Lay-in	Room 308	4	EA	7	\$0	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Prep Room</b>							
	Walls - Plaster/Drywall	Room 308	272	SF	6	\$751	
	Work Sink	Room 308	1	EA	6	\$379	
	Casework	Room 313	30	LF	6	\$758	
	Ceiling - Lay-in	Room 313	237	SF	6	\$712	
	Doors - Wood Doors inclu hw	Room 313	1	EA	6	\$301	
	Floor - Tile	Room 313	237	SF	6	\$519	
	Lighting - Lay-in	Room 313	4	EA	7	\$0	
	Walls - Plaster/Drywall	Room 313	272	SF	6	\$751	
	Work Sink	Room 313	1	EA	6	\$379	
	Casework	Room 315	30	LF	6	\$758	
	Ceiling - Lay-in	Room 315	237	SF	6	\$712	
	Doors - Wood Doors inclu hw	Room 315	1	EA	6	\$301	
	Floor - Tile	Room 315	237	SF	6	\$519	
	Lighting - Lay-in	Room 315	4	EA	7	\$0	
	Walls - Plaster/Drywall	Room 315	272	SF	6	\$751	
	Work Sink	Room 315	1	EA	6	\$379	
<b>Restroom</b>							
	Accessories	1st Floor	173	SF	6	\$1,596	
	Accessories	1st Floor	173	SF	6	\$1,596	
	Ceiling - Plaster/Drywall	1st Floor	173	SF	6	\$599	
	Ceiling - Plaster/Drywall	1st Floor	173	SF	6	\$599	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor Drain	1st Floor	1	EA	6	\$1,059	
	Floor - Terrazzo	1st Floor	173	SF	6	\$379	
	Floor - Terrazzo	1st Floor	173	SF	6	\$379	
	Lavatory	1st Floor	2	EA	6	\$639	
	Lavatory	1st Floor	2	EA	6	\$639	
	Lighting - Lay-in	1st Floor	2	EA	7	\$0	
	Lighting - Lay-in	1st Floor	3	EA	7	\$0	
	Partitions	1st Floor	1	EA	6	\$297	
	Partitions	1st Floor	3	EA	6	\$891	
	Urinals	1st Floor	2	EA	6	\$672	
	Walls - Plaster/Drywall	1st Floor	188	SF	6	\$519	
	Walls - Plaster/Drywall	1st Floor	188	SF	6	\$519	
	Walls - Structural Glazed Tile	1st Floor	188	SF	6	\$591	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Walls - Structural Glazed Tile	1st Floor	188	SF	6	\$591	
	Water Closet	1st Floor	3	EA	6	\$1,008	
	Water Closet	1st Floor	1	EA	6	\$336	
	Accessories	1st flr men's west of auditorium lobby	106	SF	6	\$978	
	Ceiling - Plaster/Drywall	1st flr men's west of auditorium lobby	106	SF	6	\$367	
	Doors - Wood Doors inclu hw	1st flr men's west of auditorium lobby	1	EA	6	\$301	
	Floor Drain	1st flr men's west of auditorium lobby	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr men's west of auditorium lobby	106	SF	6	\$224	
	Lavatory	1st flr men's west of auditorium lobby	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st flr men's west of auditorium lobby	2	EA	7	\$0	
	Partitions	1st flr men's west of auditorium lobby	1	EA	6	\$297	
	Urinals	1st flr men's west of auditorium lobby	2	EA	6	\$672	
	Walls - Tile Ceramic/ Porcelain	1st flr men's west of auditorium lobby	360	SF	6	\$813	
	Water Closet	1st flr men's west of auditorium lobby	1	EA	6	\$336	
	Accessories	1st flr women's north of main office suite	209	SF	6	\$1,928	
	Ceiling - Plaster/Drywall	1st flr women's north of main office suite	209	SF	6	\$723	
	Doors - Wood Doors inclu hw	1st flr women's north of main office suite	1	EA	6	\$301	
	Floor Drain	1st flr women's north of main office suite	1	EA	6	\$1,059	
	Floor - Terrazzo	1st flr women's north of main office suite	209	SF	6	\$457	
	Lavatory	1st flr women's north of main office suite	2	EA	6	\$639	
	Lighting - Lay-in	1st flr women's north of main office suite	2	EA	7	\$0	
	Partitions	1st flr women's north of main office suite	5	EA	6	\$1,485	
	Walls - Plaster/Drywall	1st flr women's north of main office suite	310	SF	6	\$856	
	Walls - Structural Glazed Tile	1st flr women's north of main office suite	310	SF	6	\$975	
	Water Closet	1st flr women's north of main office suite	5	EA	6	\$1,680	
	Accessories	1st flr women's west of auditorium lobby	106	SF	6	\$978	
	Ceiling - Plaster/Drywall	1st flr women's west of auditorium lobby	106	SF	6	\$367	
	Doors - Wood Doors inclu hw	1st flr women's west of auditorium lobby	1	EA	6	\$301	
	Floor Drain	1st flr women's west of auditorium lobby	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr women's west of auditorium lobby	106	SF	6	\$224	
	Lavatory	1st flr women's west of auditorium lobby	2	EA	6	\$639	
	Lighting - Pendent/Surface	1st flr women's west of auditorium lobby	2	EA	7	\$0	
	Partitions	1st flr women's west of auditorium lobby	2	EA	6	\$594	
	Walls - Tile Ceramic/ Porcelain	1st flr women's west of auditorium lobby	360	SF	6	\$813	
	Water Closet	1st flr women's west of auditorium lobby	2	EA	6	\$672	
	Accessories	2nd Floor	124	SF	6	\$1,144	
	Accessories	2nd Floor	124	SF	6	\$1,144	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Ceiling - Plaster/Drywall	2nd Floor	124	SF	6	\$429	
	Ceiling - Plaster/Drywall	2nd Floor	124	SF	6	\$429	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor - Terrazzo	2nd Floor	124	SF	6	\$271	
	Floor - Terrazzo	2nd Floor	124	SF	6	\$271	
	Lavatory	2nd Floor	2	EA	6	\$639	
	Lavatory	2nd Floor	2	EA	6	\$639	
	Lighting - Lay-in	2nd Floor	3	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	2	EA	7	\$0	
	Partitions	2nd Floor	5	EA	6	\$1,485	
	Partitions	2nd Floor	1	EA	6	\$297	
	Urinals	2nd Floor	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	2nd Floor	188	SF	6	\$519	
	Walls - Plaster/Drywall	2nd Floor	188	SF	6	\$519	
	Walls - Structural Glazed Tile	2nd Floor	188	SF	6	\$591	
	Walls - Structural Glazed Tile	2nd Floor	188	SF	6	\$591	
	Water Closet	2nd Floor	1	EA	6	\$336	
	Water Closet	2nd Floor	5	EA	6	\$1,680	
	Accessories	3rd Floor	198	SF	6	\$1,826	
	Accessories	3rd Floor	225	SF	6	\$2,075	
	Ceiling - Plaster/Drywall	3rd Floor	198	SF	6	\$685	
	Ceiling - Plaster/Drywall	3rd Floor	225	SF	6	\$779	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor Drain	3rd Floor	1	EA	6	\$1,059	
	Floor Drain	3rd Floor	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd Floor	225	SF	6	\$492	
	Floor - Terrazzo	3rd Floor	198	SF	6	\$433	
	Lavatory	3rd Floor	2	EA	6	\$639	
	Lavatory	3rd Floor	2	EA	6	\$639	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	
	Partitions	3rd Floor	4	EA	6	\$1,188	
	Partitions	3rd Floor	1	EA	6	\$297	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Urinals	3rd Floor	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	3rd Floor	129	SF	6	\$356	
	Walls - Plaster/Drywall	3rd Floor	114	SF	6	\$315	
	Walls - Structural Glazed Tile	3rd Floor	129	SF	6	\$406	
	Walls - Structural Glazed Tile	3rd Floor	114	SF	6	\$359	
	Water Closet	3rd Floor	5	EA	6	\$1,680	
	Water Closet	3rd Floor	1	EA	6	\$336	
	Accessories	4th Floor	198	SF	6	\$1,826	
	Accessories	4th Floor	225	SF	6	\$2,075	
	Ceiling - Plaster/Drywall	4th Floor	225	SF	6	\$779	
	Ceiling - Plaster/Drywall	4th Floor	198	SF	6	\$685	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor Drain	4th Floor	1	EA	6	\$1,059	
	Floor Drain	4th Floor	1	EA	6	\$1,059	
	Floor - Terrazzo	4th Floor	225	SF	6	\$492	
	Floor - Terrazzo	4th Floor	198	SF	6	\$433	
	Lavatory	4th Floor	2	EA	6	\$639	
	Lavatory	4th Floor	2	EA	6	\$639	
	Lighting - Lay-in	4th Floor	3	EA	7	\$0	
	Lighting - Lay-in	4th Floor	3	EA	7	\$0	
	Partitions	4th Floor	4	EA	6	\$1,188	
	Partitions	4th Floor	1	EA	6	\$297	
	Urinals	4th Floor	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	4th Floor	129	SF	5	\$978	holes, cracks and water damage
	Walls - Plaster/Drywall	4th Floor	114	SF	6	\$315	
	Walls - Structural Glazed Tile	4th Floor	114	SF	6	\$359	
	Walls - Structural Glazed Tile	4th Floor	129	SF	6	\$406	
	Water Closet	4th Floor	1	EA	6	\$336	
	Water Closet	4th Floor	5	EA	6	\$1,680	
	Accessories	Basement	69	SF	6	\$636	
	Ceiling - Plaster/Drywall	Basement	69	SF	6	\$239	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Basement	69	SF	6	\$146	
	Lavatory	Basement	2	EA	6	\$639	
	Lighting - Pendent/Surface	Basement	1	EA	4	\$541	T12
	Lighting - Wall Mounted	Basement	1	EA	6	\$124	



**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Partitions	Basement	2	EA	6	\$594	
	Walls - Plaster/Drywall	Basement	46	SF	6	\$127	
	Walls - Structural Glazed Tile	Basement	46	SF	6	\$145	
	Water Closet	Basement	3	EA	6	\$1,008	
	Accessories	Unisex Room, 1st flr inside NW corner office	47	SF	6	\$434	1 Bathtub ranked a 6
	Ceiling - Lay-in	Unisex Room, 1st flr inside NW corner office	47	SF	6	\$141	
	Doors - Wood Doors inclu hw	Unisex Room, 1st flr inside NW corner office	1	EA	6	\$301	
	Floor Drain	Unisex Room, 1st flr inside NW corner office	1	EA	6	\$1,059	
	Floor - Tile	Unisex Room, 1st flr inside NW corner office	47	SF	6	\$103	
	Lavatory	Unisex Room, 1st flr inside NW corner office	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 1st flr inside NW corner office	1	EA	7	\$0	
	Showers	Unisex Room, 1st flr inside NW corner office	1	EA	6	\$311	
	Walls - Plaster/Drywall	Unisex Room, 1st flr inside NW corner office	252	SF	6	\$695	
	Water Closet	Unisex Room, 1st flr inside NW corner office	1	EA	6	\$336	
	Accessories	Unisex Room, 1st flr north end of kitchen storage	47	SF	6	\$434	
	Ceiling - Plaster/Drywall	Unisex Room, 1st flr north end of kitchen storage	47	SF	4	\$708	Peeling paint and damage w/hole
	Doors - Wood Doors inclu hw	Unisex Room, 1st flr north end of kitchen storage	1	EA	6	\$301	
	Floor Drain	Unisex Room, 1st flr north end of kitchen storage	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Unisex Room, 1st flr north end of kitchen storage	47	SF	6	\$99	
	Lavatory	Unisex Room, 1st flr north end of kitchen storage	1	EA	6	\$320	
	Lighting - Pendent/Surface	Unisex Room, 1st flr north end of kitchen storage	1	EA	7	\$0	
	Partitions	Unisex Room, 1st flr north end of kitchen storage	1	EA	6	\$297	
	Walls - Structural Glazed Tile	Unisex Room, 1st flr north end of kitchen storage	252	SF	6	\$793	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Water Closet	Unisex Room, 1st flr north end of kitchen storage	1	EA	6	\$336	
	Accessories	Unisex Room, 1st flr south of classroom #104	70	SF	6	\$646	
	Ceiling - Plaster/Drywall	Unisex Room, 1st flr south of classroom #104	70	SF	6	\$242	
	Doors - Wood Doors inclu hw	Unisex Room, 1st flr south of classroom #104	1	EA	6	\$301	
	Floor Drain	Unisex Room, 1st flr south of classroom #104	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Unisex Room, 1st flr south of classroom #104	70	SF	6	\$148	
	Hand Dryer	Unisex Room, 1st flr south of classroom #104	1	EA	6	\$230	
	Lavatory	Unisex Room, 1st flr south of classroom #104	1	EA	6	\$320	
	Lighting - Pendent/Surface	Unisex Room, 1st flr south of classroom #104	1	EA	7	\$0	
	Partitions	Unisex Room, 1st flr south of classroom #104	3	EA	6	\$891	
	Walls - Plaster/Drywall	Unisex Room, 1st flr south of classroom #104	146	SF	6	\$403	
	Walls - Structural Glazed Tile	Unisex Room, 1st flr south of classroom #104	291	SF	6	\$915	
	Water Closet	Unisex Room, 1st flr south of classroom #104	3	EA	6	\$1,008	
	Accessories	Unisex Room, 1st flr west of kitchen	77	SF	6	\$710	
	Ceiling - Lay-in	Unisex Room, 1st flr west of kitchen	77	SF	6	\$231	
	Doors - Wood Doors inclu hw	Unisex Room, 1st flr west of kitchen	1	EA	6	\$301	
	Floor Drain	Unisex Room, 1st flr west of kitchen	1	EA	6	\$1,059	
	Floor - Tile	Unisex Room, 1st flr west of kitchen	77	SF	6	\$168	
	Lavatory	Unisex Room, 1st flr west of kitchen	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 1st flr west of kitchen	1	EA	7	\$0	
	Partitions	Unisex Room, 1st flr west of kitchen	1	EA	6	\$297	
	Student Lockers - One Tier	Unisex Room, 1st flr west of kitchen	3	EA	6	\$279	
	Walls - Plaster/Drywall	Unisex Room, 1st flr west of kitchen	146	SF	6	\$403	
	Walls - Tile Ceramic/ Porcelain	Unisex Room, 1st flr west of kitchen	291	SF	6	\$657	
	Water Closet	Unisex Room, 1st flr west of kitchen	1	EA	6	\$336	
	Accessories	Unisex Room, 2nd flr NE of gym	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	Unisex Room, 2nd flr NE of gym	16	SF	6	\$55	
	Doors - Wood Doors inclu hw	Unisex Room, 2nd flr NE of gym	1	EA	6	\$301	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor - Tile	Unisex Room, 2nd flr NE of gym	16	SF	4	\$138	Damage
	Lighting - Pendent/Surface	Unisex Room, 2nd flr NE of gym	1	EA	6	\$124	
	Walls - Plaster/Drywall	Unisex Room, 2nd flr NE of gym	153	SF	6	\$422	
	Water Closet	Unisex Room, 2nd flr NE of gym	1	EA	6	\$336	
	Accessories	Unisex Room, 2nd flr NW of gym	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	Unisex Room, 2nd flr NW of gym	16	SF	6	\$55	
	Doors - Wood Doors inclu hw	Unisex Room, 2nd flr NW of gym	1	EA	6	\$301	
	Floor - Tile	Unisex Room, 2nd flr NW of gym	16	SF	5	\$72	Broken pieces
	Lighting - Pendent/Surface	Unisex Room, 2nd flr NW of gym	1	EA	6	\$124	
	Walls - Plaster/Drywall	Unisex Room, 2nd flr NW of gym	153	SF	6	\$422	
	Water Closet	Unisex Room, 2nd flr NW of gym	1	EA	6	\$336	
	Accessories	Unisex Room, 2nd flr south of library	70	SF	6	\$646	
	Ceiling - Lay-in	Unisex Room, 2nd flr south of library	70	SF	6	\$210	
	Doors - Wood Doors inclu hw	Unisex Room, 2nd flr south of library	1	EA	6	\$301	
	Floor Drain	Unisex Room, 2nd flr south of library	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Unisex Room, 2nd flr south of library	70	SF	6	\$148	
	Hand Dryer	Unisex Room, 2nd flr south of library	1	EA	6	\$230	
	Lavatory	Unisex Room, 2nd flr south of library	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 2nd flr south of library	1	EA	7	\$0	
	Partitions	Unisex Room, 2nd flr south of library	3	EA	6	\$891	
	Walls - Plaster/Drywall	Unisex Room, 2nd flr south of library	146	SF	6	\$403	
	Walls - Tile Ceramic/ Porcelain	Unisex Room, 2nd flr south of library	291	SF	6	\$657	
	Water Closet	Unisex Room, 2nd flr south of library	3	EA	6	\$1,008	
	Accessories	Unisex Room, 3rd Floor	63	SF	6	\$581	
	Ceiling - Lay-in	Unisex Room, 3rd Floor	63	SF	6	\$189	
	Doors - Wood Doors inclu hw	Unisex Room, 3rd Floor	1	EA	6	\$301	
	Floor Drain	Unisex Room, 3rd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Unisex Room, 3rd Floor	63	SF	6	\$133	
	Hand Dryer	Unisex Room, 3rd Floor	1	EA	6	\$230	
	Lavatory	Unisex Room, 3rd Floor	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Room, 3rd Floor	1	EA	7	\$0	
	Walls - Plaster/Drywall	Unisex Room, 3rd Floor	23	SF	6	\$63	
	Walls - Tile Ceramic/ Porcelain	Unisex Room, 3rd Floor	69	SF	6	\$156	
	Water Closet	Unisex Room, 3rd Floor	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal:**

**\$1,490,735**

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	1,542	SF	6	\$4,631	
	Ceiling - Plaster/Drywall	1st Floor	450	SF	6	\$2,786	
	Ceiling - Splined	1st Floor	664	SF	6	\$1,918	
	Doors - Wood Doors include hw	1st Floor	10	EA	6	\$3,010	
	Drinking Fountains - Double Water Cooler	1st Floor	2	EA	6	\$754	
	Floor - Terrazzo	1st Floor	1,839	SF	6	\$15,437	
	Floor - Tile/Sheet	1st Floor	817	SF	6	\$444	
	Lighting - Lay-in	1st Floor	28	EA	6	\$3,331	
	Lighting - Pendent/Surface	1st Floor	14	EA	6	\$1,735	
	Stairs - Terrazzo	1st Floor	6	LF	6	\$56	
	Student Lockers - One Tier	1st Floor	75	EA	6	\$6,963	
	Student Lockers - Two Tiers	1st Floor	24	EA	6	\$1,114	
	Walls - Plaster/Drywall	1st Floor	1,753	SF	6	\$7,771	
	Walls - Structural Glazed Tile	1st Floor	3,506	SF	6	\$11,030	
	Ceiling - Lay-in	2nd Floor	1,748	SF	6	\$5,249	
	Doors - Wood Doors include hw	2nd Floor	7	EA	6	\$2,107	
	Drinking Fountains - Double Water Cooler	2nd Floor	2	EA	6	\$754	
	Floor - Terrazzo	2nd Floor	1,748	SF	6	\$14,673	
	Lighting - Lay-in	2nd Floor	25	EA	6	\$2,974	
	Stairs - Terrazzo	2nd Floor	6	LF	6	\$56	
	Student Lockers - One Tier	2nd Floor	80	EA	6	\$7,427	
	Student Lockers - Two Tiers	2nd Floor	36	EA	6	\$1,671	
	Walls - Plaster/Drywall	2nd Floor	1,980	SF	6	\$8,777	
	Walls - Structural Glazed Tile	2nd Floor	1,980	SF	6	\$6,229	
	Ceiling - Plaster/Drywall	3rd Floor	2,455	SF	6	\$15,201	
	Drinking Fountains - Single Water Cooler	3rd Floor	4	EA	6	\$1,267	
	Floor - Tile Quarry	3rd Floor	2,455	SF	6	\$6,846	
	Lighting - Pendent/Surface	3rd Floor	53	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	210	EA	6	\$19,495	
	Student Lockers - Three Tiers	3rd Floor	64	EA	6	\$1,980	
	Walls - Plaster/Drywall	3rd Floor	1,498	SF	6	\$6,641	
	Walls - Structural Glazed Tile	3rd Floor	1,498	SF	6	\$4,713	
	Ceiling - Plaster/Drywall	4th Floor	2,805	SF	6	\$17,368	
	Drinking Fountains - Single Water Cooler	4th Floor	4	EA	6	\$1,267	
	Floor - Tile/Sheet	4th Floor	2,805	SF	6	\$1,524	
	Lighting - Pendent/Surface	4th Floor	7	EA	7	\$0	
	Student Lockers - One Tier	4th Floor	180	EA	6	\$16,710	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Student Lockers - Two Tiers	4th Floor	30	EA	6	\$1,393	
	Walls - Plaster/Drywall	4th Floor	2,566	SF	6	\$11,375	
	Walls - Structural Glazed Tile	4th Floor	855	SF	6	\$2,690	
	Ceiling - Plaster/Drywall	Basement	742	SF	6	\$4,594	
	Floor - Tile/Sheet	Basement	742	SF	6	\$403	
	Lighting - Pendant/Surface	Basement	6	EA	4	\$3,244	
	Student Lockers - One Tier	Basement	35	EA	6	\$3,249	
	Walls - Plaster/Drywall	Basement	456	SF	6	\$2,021	
	Walls - Structural Glazed Tile	Basement	456	SF	6	\$1,435	
<b>Safety</b>							
	Camera Viewing Station	1st Floor	2	EA	6	\$1,365	
	Metal Dedector	1st Floor	2	EA	6	\$1,761	
	Security Cameras	1st Floor / Entire Building	20	EA	6	\$3,881	
	Security Cameras	1st Floor / Entire Building	2	EA	6	\$388	
<b>Stairs</b>							
	Ceiling - Plaster/Drywall	East	440	SF	6	\$3,222	
	Floor - Tile	East	305	SF	6	\$166	
	Handrails	East	248	LF	6	\$2,149	
	Lighting - Pendant/Surface	East	9	EA	6	\$1,115	
	Stairs - Tile	East	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	East	4,030	SF	6	\$11,122	
	Ceiling - Plaster/Drywall	NE of Gym	240	SF	6	\$1,757	
	Floor - Terrazzo	NE of Gym	228	SF	6	\$1,914	
	Handrails	NE of Gym	168	LF	6	\$1,456	
	Lighting - Pendant/Surface	NE of Gym	6	EA	6	\$743	
	Stairs - Terrazzo	NE of Gym	86	LF	6	\$798	
	Walls - Plaster/Drywall	NE of Gym	2,150	SF	6	\$5,934	
	Walls - Structural Glazed Tile	NE of Gym	2,150	SF	6	\$6,764	
	Ceiling - Plaster/Drywall	North East	440	SF	6	\$3,222	
	Floor - Tile	North East	305	SF	6	\$166	
	Handrails	North East	248	LF	6	\$2,149	
	Lighting - Pendant/Surface	North East	9	EA	6	\$1,115	
	Stairs - Tile	North East	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	North East	4,030	SF	6	\$11,122	
	Ceiling - Plaster/Drywall	North West	440	SF	6	\$3,222	
	Floor - Tile	North West	305	SF	6	\$166	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Handrails	North West	248	LF	6	\$2,149	
	Lighting - Pendant/Surface	North West	9	EA	6	\$1,115	
	Stairs - Tile	North West	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	North West	4,030	SF	6	\$11,122	
	Ceiling - Plaster/Drywall	NW of Gym	240	SF	6	\$1,757	
	Floor - Terrazzo	NW of Gym	228	SF	6	\$1,914	
	Handrails	NW of Gym	168	LF	6	\$1,456	
	Lighting - Pendant/Surface	NW of Gym	6	EA	6	\$743	
	Stairs - Terrazzo	NW of Gym	86	LF	6	\$798	
	Walls - Plaster/Drywall	NW of Gym	2,150	SF	6	\$5,934	
	Walls - Structural Glazed Tile	NW of Gym	2,150	SF	6	\$6,764	
	Ceiling - Plaster/Drywall	SE of gym	240	SF	6	\$1,757	
	Floor - Terrazzo	SE of gym	228	SF	6	\$1,914	
	Handrails	SE of gym	168	LF	6	\$1,456	
	Lighting - Pendant/Surface	SE of gym	6	EA	6	\$743	
	Stairs - Terrazzo	SE of gym	86	LF	6	\$798	
	Walls - Plaster/Drywall	SE of gym	2,150	SF	6	\$5,934	
	Walls - Structural Glazed Tile	SE of gym	2,150	SF	6	\$6,764	
	Ceiling - Plaster/Drywall	South East	738	SF	6	\$5,403	
	Floor - Terrazzo	South East	650	SF	6	\$5,456	
	Handrails	South East	252	LF	6	\$2,184	
	Lighting - Pendant/Surface	South East	10	EA	6	\$1,239	
	Stairs - Terrazzo	South East	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	South East	2,178	SF	6	\$6,011	
	Walls - Structural Glazed Tile	South East	2,178	SF	6	\$6,852	
	Ceiling - Plaster/Drywall	South West	738	SF	6	\$5,403	
	Floor - Terrazzo	South West	650	SF	6	\$5,456	
	Handrails	South West	252	LF	6	\$2,184	
	Lighting - Pendant/Surface	South West	10	EA	6	\$1,239	
	Stairs - Terrazzo	South West	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	South West	2,178	SF	6	\$6,011	
	Walls - Structural Glazed Tile	South West	2,178	SF	6	\$6,852	
	Ceiling - Plaster/Drywall	SW of gym	240	SF	6	\$1,757	
	Floor - Terrazzo	SW of gym	228	SF	6	\$1,914	
	Handrails	SW of gym	168	LF	6	\$1,456	
	Lighting - Pendant/Surface	SW of gym	6	EA	6	\$743	
	Stairs - Terrazzo	SW of gym	86	LF	6	\$798	

## Building: Main

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Walls - Plaster/Drywall	SW of gym	2,150	SF	6	\$5,934	
	Walls - Structural Glazed Tile	SW of gym	2,150	SF	6	\$6,764	
	Ceiling - Plaster/Drywall	West	440	SF	6	\$3,222	
	Floor - Tile	West	305	SF	6	\$166	
	Handrails	West	248	LF	6	\$2,149	
	Lighting - Pendant/Surface	West	9	EA	6	\$1,115	
	Stairs - Tile	West	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	West	4,030	SF	6	\$11,122	
<b>Vertical Conveyance</b>							
	Elevator - Elevator- Roped Holeless Hydraulic	1st Floor	1	EA	6	\$19,238	
	Elevator - Freight Elevator	Basement	1	EA	6	\$19,238	

### Building Interior Subtotal:

**\$489,716**

### Total Building Cost

**\$5,872,980**

## SITE

### Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site	8	EA	6	\$8,751	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	5	\$1,379	Location: outside boiler room door clogged
	Civil/ Drainage - Site Drain	Entire Site	1	EA	5	\$1,379	Location: door 7 clogged
	Civil/ Drainage - Site Manhole	Entire Site	11	EA	6	\$16,420	
<b>Fencing</b>							
	Fencing - Chain Link	North	740	LF	6	\$13,894	
	Fencing - New Standard Ornamental	North	262	LF	6	\$8,359	
<b>Landscape</b>							
	Benches	Entire Site	18	EA	6	\$7,741	
	Benches	Entire Site / Site North	2	EA	4	\$5,652	broken
	Landscape - Grass	Entire Site	65,217	SF	6	\$54,091	
	Landscape - Hardscape- Asphalt	Entire Site / Courtyard	3,337	SF	6	\$8,065	
	Landscape - Hardscape- Concrete	Entire Site / Site South	2,922	SF	5	\$27,327	cracks
	Landscape - Hardscape- Concrete	Entire Site / South West	371	SF	6	\$2,255	
	Parkway trees	Entire Site	46	EA	6	\$30,362	

## SITE

### Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Landscape</b>							
	Planting Beds/ Area	Entire Site	11,508	SF	6	\$18,925	
	Retaining Wall - Concrete	Entire Site	200	SF	6	\$4,688	Location: at basement wells
	Trash Receptacles	Entire Site	3	EA	6	\$937	
<b>Parking Lot</b>							
	Concrete Curbs	Parking Lot- North	252	LF	6	\$3,236	
	Surface - Asphalt	Parking Lot- North	13,113	SF	6	\$31,690	
	Surface - Concrete	Parking Lot- North / West	300	SF	6	\$725	
	Trash Compactor	Parking Lot- North	1	EA	6	\$0	
	Trash Enclosure - Masonry	Parking Lot- North	530	SF	6	\$20,910	
	Vehicular Screening	Parking Lot- North	222	LF	6	\$17,479	
<b>Service Garage</b>							
	Service Garage - Built-in	North / North Façade	3	SF	6	\$28	
	Service Garage - Free-Standing	North / Site North	1	SF	5	\$17	Wood panel walls worn
<b>Sidewalks</b>							
	Sidewalks - Internal Walks	Entire Site	5	LF	5	\$289	Location: door 6 - movement
	Sidewalks - Internal Walks	Entire Site	196	LF	6	\$2,354	
	Sidewalks - Internal Walks	Entire Site	10	LF	5	\$578	Location: door 3 - deterioration
	Sidewalks - Internal Walks	Entire Site	15	LF	5	\$867	Location: Door 27
	Sidewalks - Perimeter Sidewalks	Entire Site	13,847	SF	6	\$27,524	
	Sidewalks - Perimeter Sidewalks	Entire Site / Site - East	10	SF	5	\$96	cracks
	Sidewalks - Perimeter Sidewalks	Entire Site / Site North	200	SF	4	\$3,218	cracks, pitting
	Sidewalks - Perimeter Sidewalks	Entire Site / Site West	275	SF	5	\$2,627	cracks
<b>Signage</b>							
	Flag Pole - Building Mounted Flag Pole	South / South Façade	1	EA	6	\$828	
	Monument - Sign	South	2	EA	6	\$0	Locations: entrances 1 & 3
<b>Site Subtotal:</b>						<b>\$322,689</b>	
<b>Total Site Cost</b>						<b>\$322,689</b>	
<b>Campus Total <sup>2 3</sup></b>						<b>\$6,195,669</b>	



<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

---

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
  - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
  - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Science	2nd Floor	207	NA	1,045	1	2	30	168	56	40	N	Y	N
Art Room	Science	2nd Floor	209	NA	1,213	1	2	40	210	70	40	N	Y	N
Computer Lab	Regular Classroom	1st Floor	121	A103	928	1	34	80	147	49	40	N	Y	N
Computer Lab	Regular Classroom	2nd Floor	204	NA	615	1	25	50	105	35	40	N	Y	N
Computer Lab	Regular Classroom	4th Floor	417	NA	441	1	1	8	42	14	40	N	Y	N
Music Room	Music Room	Basement	014	NA	953	0	2	10	42	18	40	N	Y	N
Office	Regular Classroom	2nd Floor	201	NA	900	1	5	20	147	49	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	101	C106	682	2	4	4	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	102	C105	682	2	4	4	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	103	C104	682	2	4	4	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	104	C102	682	2	4	4	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	203	NA	615	1	2	6	126	42	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	205	NA	500	1	2	6	84	28	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	208	NA	615	1	2	6	92	46	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	210	NA	590	1	2	40	42	14	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	211	NA	745	1	2	12	147	49	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	301	NA	715	1	1	6	110	55	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	303	NA	715	1	1	6	132	66	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	306	NA	615	1	1	6	105	53	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	NA	900	1	1	24	147	49	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	311	NA	645	1	1	8	126	63	40	N	Y	N
Regular Classroom	Science Classroom	3rd Floor	317	NA	945	1	1	24	147	49	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	400	NA	670	1	1	6	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	401	NA	935	1	1	22	77	39	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	402	NA	615	1	1	6	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	403	NA	825	1	1	16	66	33	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	409	NA	900	1	1	14	126	42	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	411	NA	695	1	1	8	84	28	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	412	NA	645	1	1	8	52	18	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	413	NA	1,009	1	1	8	105	35	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	414	NA	445	1	1	6	42	14	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	415	NA	745	1	1	8	105	35	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	416	NA	745	1	1	8	63	21	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	419	NA	695	1	1	8	63	21	40	N	Y	N
Science Classroom	Science Lab Level 1	3rd Floor	308	NA	825	1	1	16	84	28	40	N	Y	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	302	NA	1,090	1	1	30	220	110	40	N	Y	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	313	NA	1,073	1	1	30	189	63	40	N	Y	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Science Lab Level 3	Science Lab Level 3	3rd Floor	315	NA	1,150	1	1	40	210	70	40	N	Y	N
Special Program	Other Instructional Use	3rd Floor	310	NA	2,414	1	1	10	169	85	40	N	Y	N