

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1905	3	328,514	\$27,138,737
SITE				\$143,924
Campus Total			328,514	\$27,282,661

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Entrance 5,6 - West	1	EA	6	\$702	
	Entrance Control - Audio	Entrance 10-East	1	EA	6	\$497	
	Exterior Doors	Exit 9-NE	3	EA	7	\$0	
	Exterior Doors - Exterior FRP Door	Entrance 5,6 - West	9	EA	6	\$5,683	
	Exterior Doors - Exterior FRP Door	Entrance 7-NW	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Entrance 9A-East - Storage	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	Exit 1-NE	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Exit 2-NE	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Exit 3-South	6	EA	6	\$3,788	
	Exterior Doors - Exterior FRP Door	Exit 4-SW	4	EA	6	\$2,526	
	Exterior Doors - Exterior FRP Door	Exit 8-North	3	EA	6	\$1,894	
	Exterior Doors - Exterior FRP Door	Exit 9-NE	3	EA	5	\$5,509	Door closers not working properly - all doors slam
	Exterior Doors - Exterior Steel Door	Entrance 10-East	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Fire Escape Doors	4	EA	6	\$1,922	
	Exterior Doors - Overhead Rolling/ Garage Door	Entrance 11-South - Auto shop	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	Entrance 12-South	1	EA	6	\$1,433	
	Exterior Doors - Overhead Rolling/ Garage Door	Entrance 1A-NE - Mechanical Room	1	EA	6	\$1,433	
	Exterior Doors - Side lite	Entrance 5,6 - West	12	EA	6	\$3,760	
	Exterior Doors - Side lite	Exit 1-NE	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 10-East	1	EA	6	\$313	
	Exterior Doors - Transom Lite	Entrance 5,6 - West	15	EA	6	\$4,700	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Transom Lite	Entrance 7-NW	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 9A-East - Storage	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Exit 1-NE	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Exit 2-NE	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Exit 3-South	6	EA	6	\$1,880	
	Exterior Doors - Transom Lite	Exit 4-SW	4	EA	7	\$0	
	Exterior Doors - Transom Lite	Exit 8-North	3	EA	7	\$0	
	Exterior Doors - Transom Lite	Fire Escape Doors	4	EA	7	\$0	
	Exterior Stairs - Concrete	Entrance 10-East	80	LF	6	\$6,541	
	Exterior Stairs - Concrete	Entrance 10-East	15	LF	5	\$1,644	Several cracked areas
	Exterior Stairs - Concrete	Entrance 12-South	10	LF	6	\$818	
	Exterior Stairs - Concrete	Entrance 5,6 - West	25	LF	6	\$2,044	
	Exterior Stairs - Concrete	Entrance 7-NW	3	LF	5	\$329	Bottom step cracked with gap
	Exterior Stairs - Concrete	Entrance 7-NW	22	LF	6	\$1,799	
	Exterior Stairs - Concrete	Entrance 9A-East - Storage	6	LF	6	\$491	
	Exterior Stairs - Concrete	Exit 1-NE	20	LF	4	\$3,272	Cracked, chipped, uneven with missing and sinking areas throughout
	Exterior Stairs - Concrete	Exit 2-NE	15	LF	6	\$1,227	
	Exterior Stairs - Concrete	Exit 3-South	21	LF	6	\$1,717	
	Exterior Stairs - Concrete	Exit 4-SW	32	LF	6	\$2,617	
	Exterior Stairs - Concrete	Exit 8-North	36	LF	6	\$2,944	
	Exterior Stairs - Concrete	Exit 9-NE	11	LF	4	\$1,799	Cracked, spalling, uneven entire length of step
	Ramp Handrail - Steel_Ramp Handrail	Entrance 5,6 - West	30	LF	6	\$260	
	Ramps - Concrete	Entrance 5,6 - West	10	LF	6	\$1,502	
Fire Escape							
	Fire Escape	East Façade	120	LF	6	\$75,811	
Foundation							
	Foundation - Masonry	Entire Building	1,870	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	20	SF	5	\$0	Areas of basement concrete slab upheaving throughout corridor
	Superstructure - Steel with Clay Tile Arch	Entire Building	328,494	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	12	EA	6	\$6,438	
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	2	EA	5	\$4,360	Damaged, not working and supported properly
	Exterior Lighting - Wall Mounted	Entire Building	7	EA	6	\$2,021	
	Exterior Lighting - Wall Mounted	Entire Building	1	EA	5	\$427	Damaged housing with no bulb, not working properly

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lighting							
Roof System							
	Cell Tower	Roof 8	1	EA	7	\$0	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 5	5	LF	5	\$14,258	Several areas of loose and missing mortar joints at brick and coping
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 8	60	LF	7	\$0	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 8	20	LF	6	\$19,094	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 8	60	LF	7	\$0	
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 8	45	LF	6	\$42,961	
	Chimney - Metal Flue	Roof 4	70	LF	7	\$0	
	Coping - Clay Tile	Roof 1	55	LF	5	\$3,253	Currently being stabilized
	Coping - Clay Tile	Roof 2	430	LF	5	\$25,432	Currently being stabilized
	Coping - Clay Tile	Roof 3	33	LF	7	\$0	Currently being stabilized
	Coping - Clay Tile	Roof 4	305	LF	5	\$18,039	Currently being stabilized
	Coping - Clay Tile	Roof 5	910	LF	5	\$53,822	Currently being stabilized
	Coping - Metal	Roof 1	65	LF	5	\$2,748	Currently being stabilized
	Coping - Stone	Roof 13	95	LF	5	\$10,403	Currently being stabilized
	Coping - Stone	Roof 2	110	LF	5	\$12,046	Currently being stabilized
	Coping - Stone	Roof 3	213	LF	7	\$0	Currently being stabilized
	Coping - Stone	Roof 4	350	LF	5	\$38,328	Currently being stabilized
	Coping - Stone	Roof 6	95	LF	5	\$10,403	Currently being stabilized
	Coping - Stone	Roof 7	80	LF	7	\$0	Renovation in progress - Removing or repairing parapets and copings
	Coping - Stone	Roof 8	335	LF	5	\$36,686	Currently being stabilized
	Coping - Stone	Roofs 9-12, 14	390	LF	5	\$42,709	Currently being stabilized
	Downspouts - Exterior Downspouts	Roof 4	100	LF	6	\$3,323	
	Downspouts - Exterior Downspouts	Roof 7	40	LF	6	\$1,329	
	Downspouts - Interior Downspouts	Roof 1	150	LF	6	\$4,985	
	Downspouts - Interior Downspouts	Roof 13	90	LF	6	\$2,991	
	Downspouts - Interior Downspouts	Roof 2	450	LF	6	\$14,955	
	Downspouts - Interior Downspouts	Roof 3	150	LF	6	\$4,985	
	Downspouts - Interior Downspouts	Roof 4	260	LF	6	\$8,641	
	Downspouts - Interior Downspouts	Roof 5	520	LF	6	\$17,281	
	Downspouts - Interior Downspouts	Roof 6	100	LF	6	\$3,323	
	Downspouts - Interior Downspouts	Roof 7	15	LF	6	\$498	
	Downspouts - Interior Downspouts	Roof 8	150	LF	6	\$4,985	
	Downspouts - Interior Downspouts	Roofs 9-12, 14	75	LF	6	\$2,492	Roof 9, 11 - Roof drains surrounded by debris at east side
	Parapet - 16" - 30" Height	Roof 1	100	LF	5	\$17,302	Currently being stabilized

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Parapet - 16" - 30" Height	Roof 1	20	LF	4	\$13,513	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 2	30	LF	4	\$26,218	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 2	460	LF	5	\$79,587	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 3	25	LF	4	\$16,891	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 3	75	LF	7	\$0	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 4	45	LF	4	\$30,404	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 4	135	LF	5	\$23,357	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 5	415	LF	5	\$71,802	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 5	55	LF	4	\$37,161	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 6	60	LF	5	\$10,381	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 6	35	LF	4	\$23,648	Currently being stabilized
	Parapet - 16" - 30" Height	Roof 7	80	LF	7	\$0	Renovation in progress - Removing or repairing parapets and copings
	Parapet - Parapet < 16" Height	Roof 2	50	LF	4	\$24,488	Currently being stabilized
	Parapet - Parapet < 16" Height	Roof 4	85	LF	4	\$49,399	Currently being stabilized
	Parapet - Parapet < 16" Height	Roof 4	390	LF	5	\$36,078	Currently being stabilized
	Parapet - Parapet < 16" Height	Roof 5	40	LF	5	\$3,700	Currently being stabilized
	Parapet - Parapet < 16" Height	Roofs 9-12, 14	45	LF	4	\$26,152	Currently being stabilized
	Parapet - Parapet < 16" Height	Roofs 9-12, 14	240	LF	5	\$22,202	Currently being stabilized
	Parapet - Parapet > 30"	Roof 13	20	LF	4	\$21,488	Currently being stabilized
	Parapet - Parapet > 30"	Roof 13	75	LF	5	\$18,504	Currently being stabilized
	Parapet - Parapet > 30"	Roof 3	104	LF	7	\$0	Currently being stabilized
	Parapet - Parapet > 30"	Roof 3	42	LF	4	\$45,125	Currently being stabilized
	Parapet - Parapet > 30"	Roof 5	40	LF	4	\$54,945	Currently being stabilized
	Parapet - Parapet > 30"	Roof 5	360	LF	5	\$88,818	Currently being stabilized
	Parapet - Parapet > 30"	Roof 8	300	LF	5	\$74,015	Currently being stabilized
	Parapet - Parapet > 30"	Roof 8	36	LF	4	\$38,678	Currently being stabilized
	Roof Structure - Concrete	Roof 7	420	SF	7	\$0	
	Roof Structure - Concrete	Roofs 9-12, 14	880	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 1	5,330	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 13	350	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 2	14,855	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 3	5,330	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 4	18,450	SF	7	\$0	Roof below at recessed court included
	Roof Structure - Steel with Clay Tile Arch	Roof 5	35,150	SF	7	\$0	Roof below at recessed court included
	Roof Structure - Steel with Clay Tile Arch	Roof 6	2,115	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 7	4,460	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof 8	6,882	SF	7	\$0	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Roof - Asphalt Gravel Ballast	Roof 1	5,330	SF	5	\$125,838	Several areas blistering, bubbling, worn out throughout
	Roof - Asphalt Gravel Ballast	Roof 2	13,855	SF	6	\$140,868	
	Roof - Asphalt Gravel Ballast	Roof 2	1,000	SF	5	\$26,956	Several areas blistering, cracking, worn out, bubbling throughout
	Roof - Asphalt Gravel Ballast	Roof 3	600	SF	3	\$21,175	Several areas blistering, ripping, cracking, worn out, bubbling throughout / Evidence of water damage below at gym 400 ceiling and walls
	Roof - Asphalt Gravel Ballast	Roof 3	4,730	SF	6	\$48,091	
	Roof - Asphalt Gravel Ballast	Roof 4	15,950	SF	6	\$162,168	
	Roof - Asphalt Gravel Ballast	Roof 4	1,500	SF	6	\$22,501	Moist with vegetation growing throughout
	Roof - Asphalt Gravel Ballast	Roof 4	1,000	SF	5	\$30,988	Several areas blistering, bubbling, worn out throughout
	Roof - Asphalt Gravel Ballast	Roof 5	2,000	SF	5	\$53,911	Several areas blistering, bubbling, worn out throughout
	Roof - Asphalt Gravel Ballast	Roof 5	33,150	SF	6	\$337,046	Moist with vegetation growing in some areas
	Roof - Asphalt Gravel Ballast	Roof 6	2,115	SF	6	\$21,504	
	Roof - Asphalt Gravel Ballast	Roof 7	4,335	SF	6	\$44,075	
	Roof - Asphalt Gravel Ballast	Roof 8	500	SF	5	\$13,478	Several areas blistering, bubbling, worn out throughout / Cracking with holes occurring around roof penetrations
	Roof - Asphalt Gravel Ballast	Roof 8	6,382	SF	6	\$64,888	
	Roof - Metal	Roof 4	225	SF	6	\$3,015	
	Roof - Metal	Roof 5	225	SF	6	\$3,015	
	Roof - Metal	Roof 7	125	SF	6	\$1,675	
	Roof - Modified Bitumen	Roof 13	350	SF	6	\$3,293	
	Roof - Modified Bitumen	Roof 7	420	SF	6	\$3,952	
	Roof - Modified Bitumen	Roofs 9-12, 14	5	SF	3	\$257	Roof 10 - Evidence of water penetration at storage B10 B-1 below
	Roof - Modified Bitumen	Roofs 9-12, 14	875	SF	6	\$8,233	
Walls							
	Cornice - Masonry Projecting Limestone	Entire Building	1,760	LF	6	\$61,032	
	Exterior Walls - Brick	Entire Building	83,960	SF	4	\$6,775,144	Currently being stabilized - Several areas cracked, chipped with loose and missing mortar joints throughout / Above exit 1- loose and missing pieces / Stepped cracking occurring at majority of outside corners at upper 4th floor exterior walls
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	115	SF	5	\$747	Above exits 1, 3 in between windows
	Exterior Walls - Stone-Cast	Entire Building	21,415	SF	4	\$3,011,204	Currently being stabilized Several areas cracked, chipped with loose and missing mortar joints throughout

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls							
Windows							
	Guard - Guards wire guard	Entire Building	3,530	SF	5	\$54,113	Majority bent, cracked, peeling, loose with holes throughout / Door frame screwed over window at SW corner due to window guard wire being vandalized
	Lintels - Brick	Entire Building	55	LF	7	\$0	
	Lintels - Steel	Entire Building	2,205	LF	6	\$64,009	stained, rusted, peeling throughout
	Lintels - Stone	Entire Building	1,600	LF	4	\$417,491	Currently being stabilized.
	Windows - Decorative	Entire Building	635	SF	6	\$4,740	Above main entrance 5/6, 9, 3
	Windows - Decorative	Entire Building	100	SF	5	\$12,255	Above main entrance 5/6 - Areas cracked with old bullet holes, majority of weatherstripping falling out of frames
	Windows - Louver	Entire Building	140	SF	7	\$0	
	Windows - Sash Lexan	Entire Building	27,780	SF	4	\$3,646,394	Damaged, screwed shut, not working properly
	Windows - Sash Lexan	Entire Building	6,945	SF	6	\$51,842	

Building Exterior Subtotal:

\$16,654,579

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	1	EA	4	\$8,200	install 1970
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	9,705	SF	6	\$5,135	Independent service
	Emergency A/C Power - Corridors and Stairs	Entire Building	59,354	SF	6	\$17,824	Independent service
	Emergency A/C Power - Lunchrooms	Entire Building / 4th Floor	33,192	SF	6	\$12,341	Independent service
	Emergency A/C Power - Students Toilets	Entire Building	4,272	SF	6	\$1,588	Independent service
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	2	EA	6	\$405	
	Emergency Battery Packs - Lunchrooms	Entire Building / 4th Floor	8	EA	6	\$1,620	
	Exit Signs - Auditorium	Entire Building / 1st Floor	20	EA	4	\$10,910	Independent service
	Exit Signs - Auditorium	Entire Building / 1st Floor	10	EA	4	\$5,455	Independent service
	Exit Signs - Corridors and Stairs	Entire Building	50	EA	4	\$27,274	Independent service
	Exit Signs - Gym	Entire Building / 3rd Floor	4	EA	4	\$2,313	Independent service
	Exit Signs - Lunchroom	Entire Building / 4th Floor	6	EA	4	\$3,273	Independent service
	Security System - CCTV	Entire Building	328,529	SF	6	\$98,657	
	Security System - Intrusion Detection	Entire Building	328,529	SF	6	\$84,563	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	4	\$18,799	Live
	Main Electrical Service - 1200 A 120/208/3PH	Electrical Room	1	EA	6	\$5,078	Motor Control - Distribution
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	2	EA	6	\$21,734	
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	6	\$11,555	
	Main Electrical Service - Greater than 3000 A 120/208/3PH	Electrical Room	1	EA	6	\$16,381	
	PA System	Entire Building	328,529	SF	5	\$225,502	
Power Distribution							
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	9	EA	4	\$43,644	Fuse type live
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	42	EA	6	\$12,563	Breaker type
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	9	EA	4	\$59,200	Fuse type live
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	16	EA	6	\$7,952	Breaker type
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	5	EA	4	\$32,889	Fuse type live
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	16	EA	6	\$7,952	Breaker type
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	6	EA	6	\$2,982	Breaker type
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	4	\$6,578	Fuse type live
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	2	EA	4	\$13,156	Fuse type live
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	16	EA	4	\$105,244	Fuse type live
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	4	EA	6	\$1,988	Motor control
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	4	EA	6	\$1,988	Breaker type
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	4	EA	6	\$1,988	Emergency lights
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	2	EA	6	\$994	Motor control
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	2	EA	6	\$994	Breaker type
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	2	EA	4	\$27,388	Fuse type live
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	4	EA	6	\$2,111	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	3	EA	6	\$2,191	
	Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	6	\$3,021	
	Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	6	\$3,021	
	Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	6	\$3,021	Emergency transformer
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	2	EA	6	\$2,530	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	3	EA	6	\$3,795	

Electrical System Subtotal: \$927,064

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Entire Building / 1st Floor	1	EA	4	\$49,477	Parts are obsolete
	Fire Alarm_System	Entire Building	56,976	SF	4	\$113,251	No sight only sound annunciators in corridors
Safety System Subtotal:						\$162,728	

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Condensing Unit- Roof Mounted - 5-10 tons	Roof	1	EA	6	\$3,334	Serves MAU1 for room 403// this MAU1 does not have adequate airflow for this size C/U
Air Handling Systems							
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 20001-30000 cfm	Mechanical Room AH2 / Mechanical Room	1	EA	6	\$3,350	serves south central
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 20001-30000 cfm	Mechanical room for AH3 / Mechanical Room	1	EA	6	\$3,350	serves southwest
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 20001-30000 cfm	mechanical room AH1 / Mechanical Room	1	EA	6	\$3,350	serves south east
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 20001-30000 cfm	Mechanical room for AH5 / Mechanical Room	1	EA	6	\$3,350	serves cafe
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - Greater than 30,000 cfm	Mechanical room AH4 / Mechanical Room	1	EA	6	\$3,350	serves northeast
	Air Intake	Mechanical Room AH2 / Façade- SE	1	EA	7	\$0	
	Air Intake	Mechanical room for AH3 / North Façade	1	EA	7	\$0	
	Air Intake	mechanical room AH1 / Façade- SE	1	EA	7	\$0	
	Air Intake	Mechanical room AH4 / Façade- SE	1	EA	7	\$0	
	Air Intake	Mechanical room for AH5 / Façade- SE	1	EA	7	\$0	
	Auxiliaries - 20001-30000 cfm	mechanical room AH1 / Mechanical Room	1	EA	6	\$0	
	Make Up Air Unit- Roof Mounted- Gas Heating - 10,001 - 20,000 cfm	Roof	1	EA	6	\$3,350	
	Make Up Air Unit- Roof Mounted- Gas Heating - 6000 - 10,000 cfm	Roof	1	EA	6	\$3,350	
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating & DX Cooling w/ Remote Mounted Compressor - Less than 5 tons	Roof	1	EA	6	\$1,265	MAU1 serves room 403/See Air conditioning for C/U
	Zone Dampers	Mechanical Room AH2 / Entire Building	28	EA	6	\$23,325	serves south central
	Zone Dampers	Mechanical room for AH3 / Entire Building	32	EA	6	\$26,657	serves southwest
	Zone Dampers	mechanical room AH1 / Entire Building	22	EA	6	\$18,327	serves south east
	Zone Dampers	Mechanical room AH4 / Façade- SE	50	EA	6	\$41,652	serves northeast
	Zone Dampers	Mechanical room for AH5 / Entire Building	33	EA	6	\$27,490	serves cafe, gym, library

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Boiler Systems							
	Boiler Auxiliary- Scotch Marine- Steam High Pressure Boiler - 150 - 300 HP	Boiler Room	1	EA	6	\$998	
	Boiler Auxiliary- Scotch Marine- Steam High Pressure Boiler - 150 - 300 HP	Boiler Room	1	EA	6	\$998	
	Boiler Auxiliary- Scotch Marine- Steam High Pressure Boiler - 150 - 300 HP	Boiler Room	1	EA	6	\$998	
	Chemical Feeder	Boiler Room	1	EA	7	\$0	
	Combustion Dampers	Boiler Room	3	EA	7	\$0	
	Condensate Pump	Boiler Room / Mechanical Room	3	EA	6	\$6,063	
	Feed Water Pumps and Tank	Boiler Room	2	EA	6	\$5,091	
	Feed Water Pumps and Tank	Boiler Room / Mechanical Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- High Pressure Boiler - 150 - 300 HP	Boiler Room	1	EA	6	\$998	
	Non Condensing- Fire Tube- Scotch Marine- Steam- High Pressure Boiler - 150 - 300 HP	Boiler Room	1	EA	6	\$998	
	Non Condensing- Fire Tube- Scotch Marine- Steam- High Pressure Boiler - 150 - 300 HP	Boiler Room	1	EA	6	\$998	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	1,000	LF	6	\$1,888	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	1,000	LF	6	\$1,888	
	Steam Traps	Boiler Room / Mechanical Room	82	EA	5	\$107,822	
	Vacuum Pump	Boiler Room / Mechanical Room	1	EA	6	\$2,471	
Gas Booster							
	Gas Booster	Boiler Room	1	EA	6	\$499	
	Gas Booster	Boiler Room	2	EA	6	\$998	
Heating Devices							
	Cabinet Heaters - With Steam Coil	1st Floor	1	EA	6	\$357	
	Fin Tube - Steam	Entire Building	50	LF	6	\$472	
	Radiators - Steam	Entire Building	43	EA	5	\$72,039	
	Unit Heater - Electric	Entire Building / Mechanical Room	2	EA	4	\$4,002	broken
	Unit Heater - Electric	Entire Building / Mechanical Room	5	EA	6	\$1,389	
	Unit Heater - Hot Water	Entire Building / Mechanical Room	3	EA	6	\$837	
	Wall Heater - Electric	Entire Building	16	EA	6	\$2,223	
	Wall Heater - Electric	Entire Building	4	EA	4	\$4,330	broken
Temperature Control							
	Pneumatic System	Entire Building	328,529	SF	5	\$1,132,209	
	Thermostats - Pneumatic	Entire Building	10	EA	4	\$7,372	Broken
	Thermostats - Pneumatic	Entire Building	33	EA	6	\$0	N/W Gym's,Cafe,Library

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Temperature Control							
	Thermostats - Pneumatic	Entire Building	50	EA	6	\$0	Serves N/E floors 1,2,3,4
	Thermostats - Pneumatic	Entire Building	28	EA	6	\$0	Serves S/C floors 1,2,3,4
	Thermostats - Pneumatic	Entire Building	32	EA	6	\$0	Serves S/W floors 1,2,3,4
	Thermostats - Pneumatic	Entire Building	22	EA	6	\$0	Serves S/E floors 1,2,3,4
Ventilation							
	Exhaust Fans- Indoor - 1501 - 8000 CFM	Entire Building / Attic	1	EA	6	\$592	Kitchen
	Exhaust Fans- Indoor - 1501 - 8000 CFM	Entire Building / Attic	5	EA	6	\$2,962	Building
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	6	EA	6	\$3,554	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	2	EA	4	\$12,784	Broken not working
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	5	EA	6	\$2,962	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	1	EA	6	\$296	
	Lab Exhaust Hood	Entire Building / 3rd Floor	1	EA	6	\$1,248	
	Lab Exhaust Hood	Entire Building / North	1	EA	5	\$2,950	Serves closed Wood Shop room
	Roof Mounted Duct Work	Entire Building / North	50	LF	6	\$18,951	Serves Wood Shop
	Roof Mounted Duct Work	Entire Building / Roof	70	LF	6	\$26,532	Serves MAU1,2,3
	Roof Mounted Duct Work	Entire Building / Roof	10	LF	7	\$0	
	Type I Exhaust Hood- Kitchen	Entire Building / 3rd Floor	1	EA	6	\$1,248	
	Type I Exhaust Hood- Kitchen	Entire Building / 4th Floor	1	EA	6	\$1,248	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 3rd Floor	1	EA	5	\$2,606	Needs cleaning and testing
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 4th Floor	2	EA	5	\$5,212	Needs cleaning and testing
Mechanical System Subtotal:						\$1,612,680	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Electric Heater - Less than 20 KW	Kitchen / 1st Floor	1	EA	6	\$682	
	Electric Heater - Less than 20 KW	Kitchen / 4th Floor	1	EA	6	\$682	
	Gas Heater - 300001 - 600000 BTU/HR	Entire Building / 1st Floor	1	EA	6	\$310	
	Gas Heater - 300001 - 600000 BTU/HR	Entire Building / 4th Floor	1	EA	6	\$310	Serves Dishwashing area
	Gas Heater - Less than 150000 BTU/HR	Entire Building / 1st Floor	1	EA	6	\$310	Serves Kitchen
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	328,529	SF	6	\$65,772	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	328,529	SF	6	\$79,865	

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water Risers	Entire Building	328,529	SF	6	\$61,074	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	328,529	SF	6	\$51,678	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	328,529	SF	6	\$61,074	
	Domestic Piping-Hot Water Return Lines	Entire Building	328,529	SF	6	\$46,980	
	Domestic Piping-Hot Water Return Risers	Entire Building	328,529	SF	6	\$46,980	
	Sanitary Piping	Entire Building	328,529	SF	6	\$300,670	
	Storm Piping	Entire Building	328,529	SF	6	\$286,576	
	Vent Piping	Entire Building	328,529	SF	6	\$220,804	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	
	Pumps - Sump-Duplex	Mechanical Room	6	EA	5	\$45,209	

Plumbing System Subtotal:

\$1,270,951

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #101 (Regular Classroom)							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Plaster/Drywall	1st Floor	2,239	SF	5	\$20,523	Peeling paint
	Chalk Board	1st Floor	10	LF	4	\$918	
	Doors - Transom Window	1st Floor	120	SF	6	\$2,032	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	2,239	SF	5	\$10,054	Broken/missing tiles
	Lighting - Pendant/Surface	1st Floor	54	EA	4	\$29,195	T12 lighting
	Storage/ Closet	1st Floor	60	SF	6	\$435	
	Walls - Masonry	1st Floor	1,587	SF	6	\$4,993	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #102 (Store Room)							
	Casework	1st Floor	75	LF	6	\$1,894	
	Ceiling - Plaster/Drywall	1st Floor	1,908	SF	6	\$6,603	
	Chalk Board	1st Floor	20	LF	6	\$446	
	Doors - Transom Window	1st Floor	20	SF	6	\$339	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	1,880	SF	6	\$4,113	
	Lighting - Pendant/Surface	1st Floor	56	EA	4	\$30,276	T12 lighting

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #102 (Store Room)							
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	495	SF	6	\$3,589	102B
	Walls - Concrete Block	1st Floor	624	SF	6	\$1,829	
	Walls - Masonry	1st Floor	1,427	SF	6	\$4,489	
	Walls - Masonry	1st Floor	50	SF	6	\$242	
Classroom #103 (Office)							
	Ceiling - Lay-in	1st Floor	571	SF	6	\$1,715	
	Doors - Transom Window	1st Floor	19	SF	6	\$322	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	571	SF	6	\$1,249	
	Lighting - Lay-in	1st Floor	10	EA	7	\$0	
	Risers	1st Floor	16	LF	6	\$360	
	Walls - Plaster/Drywall	1st Floor	1,192	SF	6	\$3,290	
Classroom #105 (Store Room)							
	Casework	1st Floor	29	LF	6	\$732	
	Ceiling - Plaster/Drywall	1st Floor	1,706	SF	6	\$5,904	
	Chalk Board	1st Floor	5	LF	4	\$459	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Concrete	1st Floor	1,706	SF	6	\$903	
	Lighting - Pendent/Surface	1st Floor	51	EA	4	\$27,573	T12 lighting
	Storage/ Closet	1st Floor	210	SF	6	\$1,523	
	Walls - Masonry	1st Floor	2,490	SF	6	\$7,834	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #107 (Store Room)							
	Ceiling - Plaster/Drywall	1st Floor	1,257	SF	6	\$4,350	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	5	\$1,174	Not working, missing hardware.
	Floor - Concrete	1st Floor	1,257	SF	6	\$665	
	Lighting - Pendent/Surface	1st Floor	33	EA	7	\$0	
	Marker Board	1st Floor	5	LF	7	\$0	
	Storage/ Closet	1st Floor	124	SF	6	\$899	
	Walls - Masonry	1st Floor	2,049	SF	6	\$6,446	
	Work Sink	1st Floor	1	EA	6	\$379	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #109 (Autoshop)							
	Auto Repair Lifts	1st Floor	3	EA	6	\$2,805	
	Casework	1st Floor	60	LF	6	\$1,515	
	Ceiling - Exposed	1st Floor	2,925	SF	6	\$4,350	
	Doors - Wood Doors inclu hw	1st Floor	3	EA	6	\$903	
	Floor - Concrete	1st Floor	2,925	SF	6	\$1,548	
	Lighting - Pendent/Surface	1st Floor	40	EA	7	\$0	
	Student Lockers - One Tier	1st Floor	5	EA	6	\$464	
	Walls - Masonry	1st Floor	3,590	SF	6	\$11,294	Brick
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #112 (Carpentry)							
	Ceiling - Plaster/Drywall	1st Floor	2,761	SF	6	\$9,555	
	Doors - Wood Doors inclu hw	1st Floor	4	EA	6	\$1,204	
	Floor - Concrete	1st Floor	2,761	SF	6	\$1,461	
	Lighting - Pendent/Surface	1st Floor	54	EA	6	\$6,690	
	Student Lockers - Three Tiers	1st Floor	108	EA	6	\$3,342	
	Walls - Masonry	1st Floor	3,964	SF	6	\$12,471	
	Wood Shop Equipment	1st Floor	9	EA	6	\$36,246	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #112A (Regular Classroom)							
	Ceiling - Plaster/Drywall	1st Floor	583	SF	6	\$2,018	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	583	SF	6	\$308	
	Lighting - Pendent/Surface	1st Floor	9	EA	6	\$1,115	
	Walls - Masonry	1st Floor	1,218	SF	6	\$3,832	
Classroom #112B (Art Room)							
	Ceiling - Plaster/Drywall	1st Floor	215	SF	6	\$744	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	215	SF	6	\$114	
	Lighting - Pendent/Surface	1st Floor	3	EA	6	\$372	
	Walls - Masonry	1st Floor	1,056	SF	6	\$3,322	
Classroom #112C (Computer Lab)							
	Ceiling - Plaster/Drywall	1st Floor	657	SF	6	\$2,274	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	657	SF	6	\$348	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #112C (Computer Lab)							
	Lighting - Pendent/Surface	1st Floor	9	EA	6	\$1,115	
	Marker Board	1st Floor	14	LF	6	\$300	
	Walls - Concrete Block	1st Floor	573	SF	6	\$1,680	
	Walls - Masonry	1st Floor	240	SF	6	\$755	
Classroom #113 (Laboratory/Shop)							
	Ceiling - Plaster/Drywall	1st Floor	857	SF	6	\$2,966	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	857	SF	6	\$858	
	Lighting - Pendent/Surface	1st Floor	18	EA	6	\$2,230	
	Marker Board	1st Floor	18	LF	6	\$386	
	Walls - Plaster/Drywall	1st Floor	1,323	SF	6	\$3,651	
Classroom #115 (Regular Classroom)							
	Ceiling - Plaster/Drywall	1st Floor	857	SF	6	\$2,966	
	Chalk Board	1st Floor	6	LF	4	\$551	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	857	SF	6	\$858	
	Lighting - Pendent/Surface	1st Floor	18	EA	6	\$2,230	
	Marker Board	1st Floor	6	LF	6	\$129	
	Walls - Plaster/Drywall	1st Floor	1,323	SF	6	\$3,651	
Classroom #117 (Regular Classroom)							
	Ceiling - Plaster/Drywall	1st Floor	594	SF	6	\$2,056	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	594	SF	6	\$595	
	Lighting - Pendent/Surface	1st Floor	8	EA	6	\$991	
	Walls - Plaster/Drywall	1st Floor	448	SF	6	\$1,236	
	Walls - Vinyl Coated Gypsum Panel	1st Floor	673	SF	6	\$1,857	
Classroom #119 (Regular Classroom)							
	Ceiling - Plaster/Drywall	1st Floor	547	SF	6	\$1,893	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	547	SF	6	\$548	
	Lighting - Pendent/Surface	1st Floor	8	EA	6	\$991	
	Marker Board	1st Floor	10	LF	6	\$214	
	Walls - Plaster/Drywall	1st Floor	463	SF	6	\$1,278	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #119 (Regular Classroom)							
	Walls - Vinyl Coated Gypsum Panel	1st Floor	657	SF	6	\$1,813	Vinyl Panel
Classroom #120 (Weight)							
	Ceiling - Plaster/Drywall	1st Floor	1,449	SF	6	\$5,014	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
	Floor - Concrete	1st Floor	1,449	SF	6	\$767	Some rubber mat areas over concrete
	Lighting - Pendent/Surface	1st Floor	10	EA	6	\$1,239	
	Walls - Concrete Block	1st Floor	301	SF	6	\$882	
	Walls - Structural Glazed Tile	1st Floor	1,840	SF	6	\$5,789	
Classroom #121 (Regular Classroom)							
	AC Units	1st Floor	1	EA	5	\$1,826	Not supported properly
	Casework	1st Floor	8	LF	6	\$202	
	Ceiling - Lay-in	1st Floor	475	SF	6	\$1,426	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	475	SF	6	\$475	
	Lighting - Lay-in	1st Floor	8	EA	6	\$952	
	Marker Board	1st Floor	21	LF	6	\$450	
	Walls - Plaster/Drywall	1st Floor	852	SF	6	\$2,351	
	Work Sink	1st Floor	1	EA	6	\$379	
Classroom #203 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	54	LF	6	\$1,157	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #205 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #205 (Regular Classroom)							
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #207 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	680	SF	6	\$2,042	
	Chalk Board	2nd Floor	8	LF	6	\$178	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	20	SF	5	\$115	missing VCT
	Floor - Tile/Sheet	2nd Floor	680	SF	6	\$681	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	1,092	SF	6	\$3,014	
Classroom #209 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #211 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #213 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #213 (Regular Classroom)							
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #214 (Computer Lab)							
	AC Units	2nd Floor	2	EA	5	\$3,652	Not supported properly
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	761	SF	6	\$2,285	
	Chalk Board	2nd Floor	14	LF	4	\$1,285	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	761	SF	6	\$1,665	
	Lighting - Lay-in	2nd Floor	13	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	961	SF	6	\$2,652	
	Wireless System	2nd Floor	1	EA	6	\$372	
Classroom #215 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	686	SF	6	\$2,374	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Pendent/Surface	2nd Floor	12	EA	6	\$1,487	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #217 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #218 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #219 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Side-lite	2nd Floor	14	SF	6	\$234	
	Doors - Transom Window	2nd Floor	20	SF	6	\$339	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	42	LF	6	\$900	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #220 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #221 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Marker Board	2nd Floor	65	LF	6	\$1,392	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #221 (Regular Classroom)							
	Walls - Plaster/Drywall	2nd Floor	947	SF	6	\$2,614	
Classroom #222 (Office)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	445	SF	6	\$1,336	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	445	SF	6	\$445	
	Lighting - Lay-in	2nd Floor	8	EA	6	\$952	
	Marker Board	2nd Floor	21	LF	6	\$450	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	824	SF	6	\$2,274	
Classroom #223 (Store Room)							
	Ceiling - Lay-in	2nd Floor	686	SF	6	\$2,060	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	686	SF	6	\$687	
	Lighting - Lay-in	2nd Floor	19	EA	6	\$2,261	
	Marker Board	2nd Floor	10	LF	6	\$214	
	Walls - Plaster/Drywall	2nd Floor	1,490	SF	6	\$4,112	
Classroom #224 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	2nd Floor	498	SF	6	\$1,495	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	498	SF	6	\$498	
	Lighting - Lay-in	2nd Floor	8	EA	6	\$952	
	Marker Board	2nd Floor	24	LF	6	\$514	
	Walls - Plaster/Drywall	2nd Floor	985	SF	6	\$2,719	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #225 (Regular Classroom)							
	Casework	2nd Floor	5	LF	6	\$126	
	Ceiling - Lay-in	2nd Floor	515	SF	6	\$1,547	
	Chalk Board	2nd Floor	20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	515	SF	6	\$516	
	Lighting - Lay-in	2nd Floor	15	EA	6	\$1,785	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	2nd Floor	869	SF	6	\$2,398	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #225 (Regular Classroom)							
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #226 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	441	SF	6	\$1,526	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	441	SF	6	\$441	
	Lighting - Pendent/Surface	2nd Floor	8	EA	6	\$991	
	Marker Board	2nd Floor	24	LF	6	\$514	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	920	SF	6	\$2,539	
Classroom #227 (Regular Classroom)							
	AC Units	2nd Floor	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	2nd Floor	515	SF	6	\$1,547	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	515	SF	6	\$516	
	Lighting - Lay-in	2nd Floor	15	EA	6	\$1,785	
	Marker Board	2nd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	2nd Floor	869	SF	6	\$2,398	
Classroom #228 (Regular Classroom)							
	Casework	2nd Floor	8	LF	6	\$202	
	Ceiling - Plaster/Drywall	2nd Floor	532	SF	6	\$1,841	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	532	SF	6	\$533	
	Lighting - Lay-in	2nd Floor	10	EA	6	\$1,190	
	Marker Board	2nd Floor	24	LF	6	\$514	
	Walls - Plaster/Drywall	2nd Floor	1,008	SF	6	\$2,782	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classroom #230 (Office)							
	Casework	2nd Floor	4	LF	6	\$101	
	Ceiling - Lay-in	2nd Floor	763	SF	6	\$2,291	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	763	SF	6	\$764	
	Lighting - Lay-in	2nd Floor	12	EA	6	\$1,428	
	Walls - Plaster/Drywall	2nd Floor	1,153	SF	6	\$3,182	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #231 (Other Instructional Use)							
	AC Units	2nd Floor	3	EA	5	\$5,477	Not supported properly
	Casework	2nd Floor	14	LF	6	\$354	
	Ceiling - Lay-in	2nd Floor	1,618	SF	6	\$4,859	
	Chalk Board	2nd Floor	10	LF	4	\$918	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	1,618	SF	6	\$3,447	
	Lighting - Lay-in	2nd Floor	30	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	1	EA	4	\$541	T12 lighting.
	Marker Board	2nd Floor	60	LF	7	\$0	
	Storage/ Closet	2nd Floor	54	SF	6	\$392	
	Walls - Plaster/Drywall	2nd Floor	2,358	SF	6	\$6,508	
Classroom #235 (Other Instructional Use)							
	AC Units	2nd Floor	1	EA	5	\$1,826	Not supported properly
	Casework	2nd Floor	9	LF	6	\$227	
	Ceiling - Lay-in	2nd Floor	844	SF	6	\$2,535	
	Ceiling - Lay-in	2nd Floor	20	SF	5	\$160	Water Stained tiles.
	Chalk Board	2nd Floor	14	LF	4	\$1,285	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	834	SF	6	\$1,825	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	7	\$0	
	Storage/ Closet	2nd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	2nd Floor	968	SF	6	\$2,672	
Classroom #301 (Science)							
	Casework	3rd Floor	166	LF	6	\$4,192	
	Ceiling - Lay-in	3rd Floor	1,142	SF	6	\$3,429	
	Chalk Board	3rd Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,142	SF	6	\$1,143	
	Gas Line	3rd Floor	5	EA	6	\$2,546	
	Lighting - Lay-in	3rd Floor	29	EA	6	\$3,450	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Walls - Plaster/Drywall	3rd Floor	1,188	SF	6	\$3,279	
	Work Sink	3rd Floor	6	EA	6	\$2,274	
Classroom #303 (Science)							
	Casework	3rd Floor	166	LF	6	\$4,192	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #303 (Science)							
	Ceiling - Lay-in	3rd Floor	1,142	SF	6	\$3,429	
	Chalk Board	3rd Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,142	SF	6	\$1,143	
	Gas Line	3rd Floor	4	EA	6	\$2,036	
	Lighting - Lay-in	3rd Floor	29	EA	6	\$3,450	
	Marker Board	3rd Floor	16	LF	6	\$343	
	Storage/ Closet	3rd Floor	10	SF	6	\$73	
	Walls - Plaster/Drywall	3rd Floor	1,188	SF	6	\$3,279	
	Work Sink	3rd Floor	3	EA	6	\$1,137	
Classroom #304 (Regular Classroom)							
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	916	SF	6	\$2,751	
	Chalk Board	3rd Floor	6	LF	4	\$551	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	916	SF	6	\$2,004	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	6	\$257	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	1,270	SF	6	\$3,505	
Classroom #305 (Science)							
	Ceiling - Lay-in	3rd Floor	1,142	SF	6	\$3,429	
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	1,142	SF	6	\$1,143	
	Lighting - Lay-in	3rd Floor	29	EA	6	\$3,450	
	Marker Board	3rd Floor	36	LF	6	\$771	
	Walls - Plaster/Drywall	3rd Floor	1,191	SF	6	\$3,287	
Classroom #306 (Auditorium)							
	AC Units	3rd Floor	3	EA	6	\$1,487	
	Ceiling - Lay-in	3rd Floor	1,802	SF	6	\$5,411	
	Ceiling - Plaster/Drywall	3rd Floor	843	SF	6	\$2,917	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	2,632	SF	6	\$2,635	
	Lighting - Lay-in	3rd Floor	30	EA	6	\$3,569	
	Lighting - Pendent/Surface	3rd Floor	12	EA	6	\$1,487	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #306 (Auditorium)							
	Storage/ Closet	3rd Floor	230	SF	6	\$1,668	
	Walls - Plaster/Drywall	3rd Floor	3,029	SF	6	\$8,360	
Classroom #307 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	913	SF	6	\$2,742	
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	913	SF	6	\$914	
	Lighting - Lay-in	3rd Floor	24	EA	6	\$2,855	
	Marker Board	3rd Floor	38	LF	6	\$814	
	Walls - Plaster/Drywall	3rd Floor	1,321	SF	6	\$3,646	
Classroom #309 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	38	LF	6	\$814	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #311 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	58	LF	6	\$1,242	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #313 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #313 (Regular Classroom)							
	Marker Board	3rd Floor	70	LF	6	\$1,499	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #314 (Computer Lab)							
	AC Units	3rd Floor	2	EA	5	\$3,652	Not supported properly
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	980	SF	6	\$2,943	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Wood	3rd Floor	980	SF	6	\$6,909	
	Lighting - Lay-in	3rd Floor	18	EA	6	\$2,142	
	Marker Board	3rd Floor	36	LF	6	\$771	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	1,152	SF	6	\$3,179	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #315 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	70	LF	6	\$1,499	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #316 (Computer Lab)							
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	980	SF	6	\$2,943	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	980	SF	6	\$981	
	Lighting - Lay-in	3rd Floor	18	EA	6	\$2,142	
	Marker Board	3rd Floor	36	LF	6	\$771	
	Walls - Plaster/Drywall	3rd Floor	1,152	SF	6	\$3,179	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #317 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #317 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	54	LF	6	\$1,157	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #318 (Computer Lab)							
	AC Units	3rd Floor	1	EA	5	\$1,826	Not supported properly
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	980	SF	6	\$2,943	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	3rd Floor	980	SF	6	\$981	
	Lighting - Lay-in	3rd Floor	18	EA	6	\$2,142	
	Marker Board	3rd Floor	36	LF	6	\$771	
	Storage/ Closet	3rd Floor	40	SF	6	\$290	
	Walls - Plaster/Drywall	3rd Floor	1,152	SF	6	\$3,179	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #319 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	5	\$1,826	Not supported properly
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	40	LF	6	\$857	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #320 (Computer Lab)							
	AC Units	3rd Floor	1	EA	7	\$0	
	AC Units	3rd Floor	2	EA	5	\$3,652	Not supported properly
	Casework	3rd Floor	8	LF	6	\$202	
	Ceiling - Lay-in	3rd Floor	2,799	SF	6	\$8,405	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Carpet	3rd Floor	2,799	SF	6	\$5,964	
	Lighting - Lay-in	3rd Floor	40	EA	6	\$4,759	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #320 (Computer Lab)							
	Marker Board	3rd Floor	14	LF	6	\$300	
	Walls - Plaster/Drywall	3rd Floor	1,911	SF	6	\$5,274	
Classroom #321 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	6	\$1,428	
	Marker Board	3rd Floor	70	LF	6	\$1,499	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	994	SF	6	\$2,743	
Classroom #323 (Regular Classroom)							
	AC Units	3rd Floor	2	EA	7	\$0	
	AC Units	3rd Floor	1	EA	5	\$1,826	Not supported properly
	Casework	3rd Floor	14	LF	6	\$354	
	Ceiling - Lay-in	3rd Floor	1,546	SF	6	\$4,643	
	Doors - Wood Doors inclu hw	3rd Floor	3	EA	6	\$903	
	Floor - Carpet	3rd Floor	1,546	SF	6	\$3,294	
	Lighting - Lay-in	3rd Floor	21	EA	6	\$2,498	
	Marker Board	3rd Floor	18	LF	6	\$386	
	Walls - Plaster/Drywall	3rd Floor	12,776	SF	6	\$35,260	
Classroom #325 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	4	\$6,086	Not operational.
	Casework	3rd Floor	21	LF	6	\$530	
	Ceiling - Lay-in	3rd Floor	906	SF	6	\$2,721	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	906	SF	6	\$1,982	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	32	LF	7	\$0	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	1,094	SF	6	\$3,019	
Classroom #327 (Regular Classroom)							
	AC Units	3rd Floor	1	EA	6	\$496	
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	868	SF	6	\$2,607	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #327 (Regular Classroom)							
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	868	SF	6	\$1,899	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Storage/ Closet	3rd Floor	2	SF	6	\$15	
	Walls - Plaster/Drywall	3rd Floor	1,000	SF	6	\$2,760	
	Walls - Plaster/Drywall	3rd Floor	130	SF	5	\$574	Peeling paint, cracked plaster.
Classroom #329 (Regular Classroom)							
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	868	SF	6	\$2,607	
	Doors - Steel Doors incl hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	868	SF	5	\$3,897	missing tiles
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	28	LF	7	\$0	
	Storage/ Closet	3rd Floor	14	SF	6	\$102	
	Walls - Plaster/Drywall	3rd Floor	1,130	SF	6	\$3,119	
Classroom #330 (Regular Classroom)							
	Casework	3rd Floor	7	LF	6	\$177	
	Ceiling - Lay-in	3rd Floor	913	SF	6	\$2,742	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	23	SF	5	\$133	Broken/ missing tiles.
	Floor - Tile	3rd Floor	886	SF	6	\$1,938	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	31	LF	6	\$664	
	Storage/ Closet	3rd Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	3rd Floor	1,173	SF	6	\$3,237	
Classroom #331 (Special Program)							
	Casework	3rd Floor	24	LF	6	\$606	
	Ceiling - Lay-in	3rd Floor	1,445	SF	6	\$4,339	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Floor - Tile	3rd Floor	1,445	SF	6	\$3,162	
	Lighting - Lay-in	3rd Floor	33	EA	7	\$0	
	Marker Board	3rd Floor	30	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,434	SF	6	\$3,958	
	Work Sink	3rd Floor	2	EA	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #332 (Regular Classroom)							
	AC Units	3rd Floor	2	EA	5	\$3,652	Not supported properly
	Ceiling - Lay-in	3rd Floor	1,462	SF	6	\$4,390	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,462	SF	6	\$3,199	
	Lighting - Lay-in	3rd Floor	33	EA	7	\$0	
	Marker Board	3rd Floor	40	LF	7	\$0	
	Storage/ Closet	3rd Floor	28	SF	6	\$203	
	Walls - Plaster/Drywall	3rd Floor	1,494	SF	6	\$4,123	
Classroom #333 (Art Room)							
	Ceiling - Lay-in	3rd Floor	1,015	SF	6	\$3,048	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,015	SF	6	\$2,221	
	Lighting - Lay-in	3rd Floor	29	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	2	EA	4	\$1,081	T12 lighting, in storage closet.
	Marker Board	3rd Floor	5	LF	7	\$0	
	Storage/ Closet	3rd Floor	348	SF	6	\$2,523	Rm 333 storage
	Storage/ Closet	3rd Floor	160	SF	6	\$1,160	
	Walls - Plaster/Drywall	3rd Floor	1,140	SF	6	\$3,146	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #334 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	906	SF	6	\$2,721	
	Ceiling - Plaster/Drywall	3rd Floor	300	SF	6	\$1,038	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	1,206	SF	6	\$2,639	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	4	EA	7	\$0	
	Marker Board	3rd Floor	6	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,198	SF	6	\$3,306	
Classroom #401 (Regular Classroom)							
	Casework	4th Floor	10	LF	6	\$253	
	Ceiling - Lay-in	4th Floor	474	SF	6	\$1,423	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	474	SF	6	\$474	
	Lighting - Lay-in	4th Floor	7	EA	6	\$833	
	Marker Board	4th Floor	16	LF	6	\$343	
	Storage/ Closet	4th Floor	20	SF	6	\$145	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #401 (Regular Classroom)							
	Walls - Plaster/Drywall	4th Floor	726	SF	6	\$2,004	
	Work Sink	4th Floor	1	EA	6	\$379	
Classroom #403 (Science)							
	Casework	4th Floor	110	LF	6	\$2,778	
	Ceiling - Lay-in	4th Floor	988	SF	6	\$2,967	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Eye Wash Station	4th Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	4th Floor	988	SF	6	\$989	
	Fume Hood	4th Floor	1	EA	6	\$816	
	Gas Line	4th Floor	15	EA	6	\$7,637	
	Lighting - Lay-in	4th Floor	16	EA	6	\$1,904	
	Marker Board	4th Floor	24	LF	6	\$514	
	Science Lab Shower	4th Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	4th Floor	1,142	SF	6	\$3,152	
	Work Sink	4th Floor	8	EA	6	\$3,032	
Classroom #405 (Science)							
	AC Units	4th Floor	1	EA	6	\$496	
	Casework	4th Floor	110	LF	6	\$2,778	
	Ceiling - Lay-in	4th Floor	988	SF	6	\$2,967	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Eye Wash Station	4th Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	4th Floor	988	SF	6	\$989	
	Lighting - Lay-in	4th Floor	27	EA	6	\$3,212	
	Marker Board	4th Floor	24	LF	6	\$514	
	Science Lab Shower	4th Floor	1	EA	6	\$379	
	Storage/ Closet	4th Floor	20	SF	6	\$145	
	Walls - Plaster/Drywall	4th Floor	1,142	SF	6	\$3,152	
	Work Sink	4th Floor	3	EA	6	\$1,137	
Classroom #407 (Science)							
	Casework	4th Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	4th Floor	879	SF	6	\$2,640	
	Chalk Board	4th Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	879	SF	6	\$880	
	Gas Line	4th Floor	1	EA	6	\$509	
	Lighting - Pendent/Surface	4th Floor	24	EA	6	\$2,973	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #407 (Science)							
	Marker Board	4th Floor	18	LF	6	\$386	
	Walls - Plaster/Drywall	4th Floor	1,090	SF	6	\$3,008	
	Work Sink	4th Floor	2	EA	6	\$758	
Classroom #408 (Computer Lab)							
	AC Units	4th Floor	2	EA	4	\$12,173	Not supported properly
	Casework	4th Floor	32	LF	6	\$808	
	Ceiling - Lay-in	4th Floor	1,573	SF	6	\$4,724	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	1,573	SF	6	\$1,575	
	Lighting - Lay-in	4th Floor	21	EA	6	\$2,498	
	Marker Board	4th Floor	24	LF	6	\$514	
	Walls - Plaster/Drywall	4th Floor	1,470	SF	6	\$4,057	
Classroom #409 (Science)							
	Casework	4th Floor	50	LF	6	\$1,263	
	Ceiling - Lay-in	4th Floor	879	SF	6	\$2,640	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	879	SF	6	\$880	
	Gas Line	4th Floor	3	EA	6	\$1,527	
	Lighting - Pendent/Surface	4th Floor	24	EA	6	\$2,973	
	Marker Board	4th Floor	40	LF	6	\$857	
	Walls - Plaster/Drywall	4th Floor	1,090	SF	6	\$3,008	
	Work Sink	4th Floor	2	EA	6	\$758	
Classroom #410 (Store Room)							
	Ceiling - Lay-in	4th Floor	781	SF	6	\$2,345	
	Chalk Board	4th Floor	48	LF	4	\$4,407	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Wood	4th Floor	781	SF	6	\$5,506	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	24	LF	6	\$514	
	Walls - Plaster/Drywall	4th Floor	687	SF	6	\$1,896	
Classroom #411 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Floor - Wood	4th Floor	702	SF	6	\$4,949	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #411 (Regular Classroom)							
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	
Classroom #413 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	702	SF	6	\$703	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	
Classroom #415 (Regular Classroom)							
	AC Units	4th Floor	2	EA	5	\$3,652	Not supported properly
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	702	SF	6	\$703	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	
Classroom #416 (Regular Classroom)							
	Casework	4th Floor	20	LF	6	\$505	
	Ceiling - Lay-in	4th Floor	1,053	SF	6	\$3,162	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	1,053	SF	6	\$1,054	
	Lighting - Lay-in	4th Floor	27	EA	6	\$3,212	
	Marker Board	4th Floor	30	LF	6	\$643	
	Walls - Plaster/Drywall	4th Floor	1,458	SF	6	\$4,024	
Classroom #417 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Wood	4th Floor	702	SF	6	\$4,949	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #418 (Regular Classroom)							
	Casework	4th Floor	20	LF	6	\$505	
	Ceiling - Lay-in	4th Floor	980	SF	6	\$2,943	
	Chalk Board	4th Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	980	SF	6	\$981	
	Lighting - Lay-in	4th Floor	18	EA	6	\$2,142	
	Marker Board	4th Floor	32	LF	6	\$685	
	Walls - Plaster/Drywall	4th Floor	1,152	SF	6	\$3,179	
Classroom #419 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Wood	4th Floor	702	SF	6	\$4,949	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	
Classroom #420 (Regular Classroom)							
	Casework	4th Floor	20	LF	6	\$505	
	Ceiling - Lay-in	4th Floor	980	SF	6	\$2,943	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	980	SF	6	\$981	
	Lighting - Lay-in	4th Floor	18	EA	6	\$2,142	
	Marker Board	4th Floor	36	LF	6	\$771	
	Walls - Plaster/Drywall	4th Floor	1,152	SF	6	\$3,179	
	Work Sink	4th Floor	1	EA	6	\$379	
Classroom #421 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Chalk Board	4th Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	702	SF	6	\$703	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #423 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	702	SF	6	\$2,108	
	Chalk Board	4th Floor	16	LF	4	\$1,469	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	4th Floor	702	SF	6	\$703	
	Lighting - Lay-in	4th Floor	12	EA	6	\$1,428	
	Marker Board	4th Floor	56	LF	6	\$1,200	
	Walls - Plaster/Drywall	4th Floor	994	SF	6	\$2,743	
Classroom #424 (Band Room)							
	Casework	4th Floor	12	LF	6	\$303	
	Ceiling - Lay-in	4th Floor	2,798	SF	6	\$8,402	
	Doors - Wood Doors inclu hw	4th Floor	3	EA	6	\$903	
	Floor - Tile/Sheet	4th Floor	2,798	SF	6	\$2,801	
	Lighting - Lay-in	4th Floor	21	EA	6	\$2,498	
	Marker Board	4th Floor	14	LF	6	\$300	
	Storage/ Closet	4th Floor	20	SF	6	\$145	
	Walls - Plaster/Drywall	4th Floor	2,798	SF	6	\$7,722	
Classroom #425 (Music Room)							
	Casework	4th Floor	70	LF	6	\$1,768	
	Ceiling - Lay-in	4th Floor	2,259	SF	6	\$6,784	
	Doors - Wood Doors inclu hw	4th Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	4th Floor	2,259	SF	6	\$2,261	
	Lighting - Lay-in	4th Floor	36	EA	6	\$4,283	
	Walls - Plaster/Drywall	4th Floor	3,094	SF	6	\$8,539	
Classroom #429 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	806	SF	6	\$2,420	
	Ceiling - Plaster/Drywall	4th Floor	100	SF	5	\$917	Peeling paint, falling/broken plaster.
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	906	SF	6	\$1,982	
	Lighting - Lay-in	4th Floor	13	EA	7	\$0	
	Marker Board	4th Floor	32	LF	7	\$0	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	1,094	SF	6	\$3,019	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #431 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	800	SF	6	\$2,402	
	Ceiling - Lay-in	4th Floor	16	SF	5	\$128	Water stained tiles
	Ceiling - Plaster/Drywall	4th Floor	68	SF	5	\$623	Peeling paint, falling plaster
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	868	SF	6	\$1,899	
	Lighting - Lay-in	4th Floor	18	EA	7	\$0	
	Marker Board	4th Floor	50	LF	7	\$0	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	1,130	SF	6	\$3,119	
Classroom #433 (Regular Classroom)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	824	SF	6	\$2,474	
	Ceiling - Plaster/Drywall	4th Floor	44	SF	5	\$403	Peeling paint
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	868	SF	6	\$1,899	
	Lighting - Lay-in	4th Floor	18	EA	7	\$0	
	Marker Board	4th Floor	50	LF	7	\$0	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	1,130	SF	6	\$3,119	
Classroom #436 (Computer Lab)							
	Casework	4th Floor	6	LF	6	\$152	
	Ceiling - Lay-in	4th Floor	896	SF	6	\$2,691	
	Chalk Board	4th Floor	13	LF	4	\$1,193	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	896	SF	6	\$1,960	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	32	LF	7	\$0	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	1,004	SF	6	\$2,771	
Classroom #438 (Computer Lab)							
	Casework	4th Floor	7	LF	6	\$177	
	Ceiling - Lay-in	4th Floor	896	SF	6	\$2,691	
	Chalk Board	4th Floor	24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Tile	4th Floor	896	SF	6	\$1,960	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #438 (Computer Lab)							
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	42	LF	7	\$0	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	1,004	SF	6	\$2,771	
Classroom #440 (Computer Lab)							
	AC Units	4th Floor	1	EA	4	\$6,086	Not working.
	Casework	4th Floor	4	LF	6	\$101	
	Ceiling - Lay-in	4th Floor	896	SF	6	\$2,691	
	Doors - Wood Doors inclu hw	4th Floor	1	EA	6	\$301	
	Floor - Wood	4th Floor	896	SF	6	\$6,317	
	Lighting - Lay-in	4th Floor	14	EA	7	\$0	
	Marker Board	4th Floor	34	LF	7	\$0	
	Storage/ Closet	4th Floor	4	SF	6	\$29	
	Walls - Plaster/Drywall	4th Floor	1,004	SF	6	\$2,771	

Classrooms Subtotal:

\$1,325,099

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	109-1 Coach Office - Not use	159	SF	6	\$477	
	Doors - Wood Doors inclu hw	109-1 Coach Office - Not use	1	EA	6	\$301	
	Floor - Concrete	109-1 Coach Office - Not use	159	SF	6	\$84	
	Power Distribution	109-1 Coach Office - Not use	4	EA	6	\$8,500	
	Walls - Concrete Block	109-1 Coach Office - Not use	257	SF	6	\$753	
	Walls - Plaster/Drywall	109-1 Coach Office - Not use	257	SF	6	\$709	
	Ceiling - Plaster/Drywall	109A Autosshop Office	143	SF	5	\$1,311	Peeling paint
	Doors - Wood Doors inclu hw	109A Autosshop Office	1	EA	6	\$301	
	Floor - Concrete	109A Autosshop Office	143	SF	6	\$76	
	Lighting - Pendent/Surface	109A Autosshop Office	2	EA	7	\$0	
	Walls - Masonry	109A Autosshop Office	721	SF	6	\$2,268	Brick
	Ceiling - Plaster/Drywall	109B auto shop tool room	201	SF	5	\$1,842	Peeling paint
	Floor - Concrete	109B auto shop tool room	201	SF	6	\$106	
	Lighting - Pendent/Surface	109B auto shop tool room	1	EA	4	\$541	T12 lighting
	Walls - Masonry	109B auto shop tool room	60	SF	5	\$3,431	Eflorescence on west wall

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Walls - Masonry	109B auto shop tool room	600	SF	6	\$1,888	Brick
	Walls - Structural Glazed Tile	109B auto shop tool room	75	SF	6	\$236	
	Ceiling - Plaster/Drywall	121 A Discipline Office	1,072	SF	6	\$3,710	
	Doors - Steel Doors incl hw	121 A Discipline Office	2	EA	6	\$602	
	Floor - Tile/Sheet	121 A Discipline Office	1,072	SF	6	\$1,073	
	Lighting - Pendent/Surface	121 A Discipline Office	25	EA	6	\$3,097	
	Power Distribution	121 A Discipline Office	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	121 A Discipline Office	1,666	SF	6	\$4,598	
	Ceiling - Plaster/Drywall	121A Discipline Office	570	SF	6	\$1,973	
	Doors - Wood Doors inclu hw	121A Discipline Office	1	EA	6	\$301	
	Floor - Tile/Sheet	121A Discipline Office	570	SF	6	\$571	
	Lighting - Pendent/Surface	121A Discipline Office	12	EA	6	\$1,487	
	Power Distribution	121A Discipline Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	121A Discipline Office	1,129	SF	6	\$3,116	
	Ceiling - Lay-in	127A PE Office - Not Used	111	SF	6	\$333	
	Doors - Wood Doors inclu hw	127A PE Office - Not Used	1	EA	6	\$301	
	Floor - Concrete	127A PE Office - Not Used	111	SF	6	\$59	
	Lighting - Lay-in	127A PE Office - Not Used	1	EA	6	\$119	
	Power Distribution	127A PE Office - Not Used	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	127A PE Office - Not Used	388	SF	6	\$1,071	
	Ceiling - Lay-in	200 Main Office	1,383	SF	6	\$4,153	
	Doors - Wood Doors inclu hw	200 Main Office	2	EA	6	\$602	
	Floor - Tile/Sheet	200 Main Office	644	SF	6	\$645	
	Floor - Wood	200 Main Office	746	SF	6	\$5,259	
	Lighting - Lay-in	200 Main Office	24	EA	6	\$2,855	
	Lighting - Pendent/Surface	200 Main Office	3	EA	6	\$372	
	Power Distribution	200 Main Office	20	EA	6	\$42,498	
	Storage/ Closet	200 Main Office	6	SF	6	\$44	
	Walls - Plaster/Drywall	200 Main Office	1,847	SF	6	\$5,098	
	AC Unit	200A Office	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	200A Office	449	SF	6	\$1,348	
	Doors - Wood Doors inclu hw	200A Office	1	EA	6	\$301	
	Floor - Tile/Sheet	200A Office	449	SF	6	\$449	
	Lighting - Lay-in	200A Office	9	EA	6	\$1,071	
	Power Distribution	200A Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	200A Office	954	SF	6	\$2,633	
	AC Unit	200C Office	1	EA	5	\$1,826	Not supported properly

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	200C Office	188	SF	6	\$565	
	Doors - Wood Doors inclu hw	200C Office	1	EA	6	\$301	
	Floor - Wood	200C Office	188	SF	6	\$1,325	
	Lighting - Lay-in	200C Office	4	EA	7	\$0	
	Power Distribution	200C Office	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	200C Office	563	SF	6	\$1,554	
	AC Unit	200D Office	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	200D Office	165	SF	6	\$495	
	Doors - Wood Doors inclu hw	200D Office	1	EA	6	\$301	
	Floor - Tile/Sheet	200D Office	165	SF	6	\$165	
	Lighting - Lay-in	200D Office	2	EA	6	\$238	
	Power Distribution	200D Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	200D Office	638	SF	6	\$1,761	
	AC Unit	200E Office	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	200E Office	188	SF	6	\$565	
	Doors - Wood Doors inclu hw	200E Office	1	EA	6	\$301	
	Floor - Wood	200E Office	144	SF	6	\$1,015	
	Lighting - Lay-in	200E Office	2	EA	7	\$0	
	Power Distribution	200E Office	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	200E Office	363	SF	6	\$1,002	
	AC Unit	200F Office	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	200F Office	411	SF	6	\$1,234	
	Doors - Wood Doors inclu hw	200F Office	1	EA	6	\$301	
	Floor - Tile/Sheet	200F Office	411	SF	6	\$411	
	Lighting - Lay-in	200F Office	8	EA	6	\$952	
	Power Distribution	200F Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	200F Office	885	SF	6	\$2,443	
	AC Unit	200I Principals Office	1	EA	6	\$496	
	Ceiling - Lay-in	200I Principals Office	385	SF	6	\$1,156	
	Doors - Wood Doors inclu hw	200I Principals Office	2	EA	6	\$602	
	Floor - Wood	200I Principals Office	385	SF	6	\$2,714	
	Lighting - Lay-in	200I Principals Office	8	EA	6	\$952	
	Power Distribution	200I Principals Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	200I Principals Office	560	SF	6	\$1,546	
	Ceiling - Lay-in	201 Office	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	201 Office	1	EA	6	\$301	
	Floor - Tile/Sheet	201 Office	208	SF	6	\$208	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	201 Office	3	EA	6	\$357	
	Power Distribution	201 Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	201 Office	587	SF	6	\$1,620	
	Ceiling - Lay-in	201A Office	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	201A Office	1	EA	6	\$301	
	Floor - Tile/Sheet	201A Office	124,208	SF	6	\$124,332	
	Lighting - Lay-in	201A Office	3	EA	6	\$357	
	Power Distribution	201A Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	201A Office	470	SF	6	\$1,297	
	Ceiling - Lay-in	201B Office	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	201B Office	1	EA	6	\$301	
	Floor - Tile/Sheet	201B Office	208	SF	6	\$208	
	Lighting - Lay-in	201B Office	3	EA	6	\$357	
	Power Distribution	201B Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	201B Office	587	SF	6	\$1,620	
	Ceiling - Lay-in	201C Office	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	201C Office	1	EA	6	\$301	
	Floor - Tile/Sheet	201C Office	124,208	SF	6	\$124,332	
	Lighting - Lay-in	201C Office	3	EA	6	\$357	
	Power Distribution	201C Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	201C Office	470	SF	6	\$1,297	
	Ceiling - Lay-in	202 Office	511	SF	6	\$1,535	
	Doors - Wood Doors inclu hw	202 Office	1	EA	6	\$301	
	Floor - Wood	202 Office	511	SF	6	\$3,602	
	Lighting - Lay-in	202 Office	12	EA	6	\$1,428	
	Power Distribution	202 Office	28	EA	6	\$59,497	
	Walls - Plaster/Drywall	202 Office	1,038	SF	6	\$2,865	
	Ceiling - Plaster/Drywall	208. Custodian locker room.	235	SF	5	\$2,154	Peeling paint
	Doors - Wood Doors inclu hw	208. Custodian locker room.	1	EA	6	\$301	
	Floor - Terrazzo	208. Custodian locker room.	235	SF	6	\$514	
	Lighting - Pendant/Surface	208. Custodian locker room.	2	EA	4	\$1,081	T-12 lighting
	Power Distribution	208. Custodian locker room.	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	208. Custodian locker room.	10	SF	4	\$147	Broken/missing plaster.
	Walls - Plaster/Drywall	208. Custodian locker room.	945	SF	5	\$7,162	Peeling paint
	Ceiling - Lay-in	223B Office	258	SF	6	\$775	
	Doors - Wood Doors inclu hw	223B Office	1	EA	6	\$301	
	Floor - Tile/Sheet	223B Office	258	SF	6	\$258	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	223B Office	6	EA	6	\$714	
	Power Distribution	223B Office	10	EA	6	\$21,249	
	Walls - Plaster/Drywall	223B Office	645	SF	6	\$1,780	
	Ceiling - Lay-in	234	551	SF	6	\$1,655	
	Doors - Wood Doors inclu hw	234	1	EA	6	\$301	
	Floor - Tile	234	545	SF	6	\$1,192	
	Floor - Tile	234	6	SF	5	\$35	Damaged/missing tiles throughout room.
	Lighting - Lay-in	234	12	EA	7	\$0	
	Power Distribution	234	9	EA	6	\$19,124	
	Walls - Plaster/Drywall	234	846	SF	6	\$2,335	
	Walls - Plaster/Drywall	234	30	SF	5	\$153	Peeling paint/plaster.
	AC Unit	236 office/Confrence rm.	1	EA	6	\$496	
	Ceiling - Lay-in	236 office/Confrence rm.	378	SF	6	\$1,135	
	Doors - Wood Doors inclu hw	236 office/Confrence rm.	1	EA	6	\$301	
	Floor - Tile	236 office/Confrence rm.	378	SF	6	\$827	
	Lighting - Lay-in	236 office/Confrence rm.	6	EA	7	\$0	
	Power Distribution	236 office/Confrence rm.	17	EA	6	\$36,123	
	Walls - Plaster/Drywall	236 office/Confrence rm.	168	SF	6	\$550	
	Walls - Plaster/Drywall	236 office/Confrence rm.	687	SF	6	\$1,896	Wood paneling
	AC Unit	236A Case Manager	1	EA	4	\$6,086	No working
	Ceiling - Lay-in	236A Case Manager	386	SF	6	\$1,159	
	Doors - Wood Doors inclu hw	236A Case Manager	1	EA	6	\$301	
	Floor - Tile	236A Case Manager	386	SF	5	\$1,733	Broken/missing tiles throughout.
	Lighting - Lay-in	236A Case Manager	6	EA	7	\$0	
	Power Distribution	236A Case Manager	13	EA	6	\$27,623	
	Walls - Plaster/Drywall	236A Case Manager	712	SF	6	\$1,965	Wood paneling
	Walls - Plaster/Drywall	236A Case Manager	178	SF	6	\$583	
	Ceiling - Lay-in	237	356	SF	6	\$1,069	
	Ceiling - Lay-in	237	12	SF	5	\$96	Water stained tiles
	Doors - Wood Doors inclu hw	237	4	EA	6	\$1,204	
	Floor - Tile	237	368	SF	6	\$805	
	Lighting - Lay-in	237	8	EA	7	\$0	
	Power Distribution	237	17	EA	6	\$36,123	
	Storage/ Closet	237	89	SF	6	\$645	
	Walls - Plaster/Drywall	237	1,132	SF	6	\$3,124	
	Work Slnk	237	1	EA	6	\$508	
	AC Unit	238 Nurses Office	2	EA	5	\$3,652	Not supported properly

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	238 Nurses Office	530	SF	6	\$1,592	
	Doors - Wood Doors inclu hw	238 Nurses Office	1	EA	6	\$301	
	Floor - Tile	238 Nurses Office	530	SF	6	\$1,160	
	Lighting - Lay-in	238 Nurses Office	24	EA	7	\$0	
	Lighting - Pendent/Surface	238 Nurses Office	1	EA	6	\$124	
	Power Distribution	238 Nurses Office	15	EA	6	\$31,873	
	Storage/ Closet	238 Nurses Office	188	SF	6	\$1,363	
	Walls - Plaster/Drywall	238 Nurses Office	1,751	SF	6	\$4,833	
	Doors - Wood Doors inclu hw	238A	1	EA	6	\$301	
	Floor - Tile	238A	117	SF	6	\$256	
	Power Distribution	238A	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	238A	224	SF	6	\$618	
	Doors - Wood Doors inclu hw	238B	1	EA	6	\$301	
	Floor - Tile	238B	141	SF	6	\$308	
	Power Distribution	238B	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	238B	254	SF	6	\$701	
	Doors - Wood Doors inclu hw	238C	1	EA	6	\$301	
	Floor - Tile	238C	503	SF	6	\$1,101	
	Power Distribution	238C	17	EA	6	\$36,123	
	Walls - Plaster/Drywall	238C	186	SF	6	\$513	
	Doors - Wood Doors inclu hw	238D	1	EA	6	\$301	
	Floor - Tile	238D	75	SF	6	\$164	
	Power Distribution	238D	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	238D	201	SF	6	\$555	
	AC Unit	239A-2	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	239A-2	533	SF	6	\$1,601	
	Doors - Wood Doors inclu hw	239A-2	1	EA	6	\$301	
	Floor - Wood	239A-2	533	SF	6	\$3,758	
	Lighting - Lay-in	239A-2	10	EA	7	\$0	
	Power Distribution	239A-2	16	EA	6	\$33,998	
	Walls - Plaster/Drywall	239A-2	1,010	SF	6	\$2,787	
	AC Unit	239A	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	239A	730	SF	6	\$2,192	
	Doors - Wood Doors inclu hw	239A	2	EA	6	\$602	
	Floor - Wood	239A	730	SF	6	\$5,146	
	Lighting - Lay-in	239A	14	EA	7	\$0	
	Lighting - Pendent/Surface	239A	1	EA	4	\$541	T12 lighting

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Power Distribution	239A	13	EA	6	\$27,623	
	Storage/ Closet	239A	115	SF	6	\$834	
	Walls - Plaster/Drywall	239A	1,206	SF	6	\$3,328	
	Work Slnk	239A	1	EA	6	\$508	
	Doors - Wood Doors inclu hw	239B-1	1	EA	6	\$301	
	Floor - Wood	239B-1	98	SF	6	\$691	
	Power Distribution	239B-1	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	239B-1	140	SF	6	\$386	
	Doors - Wood Doors inclu hw	239B-2	1	EA	6	\$301	
	Floor - Wood	239B-2	84	SF	6	\$592	
	Power Distribution	239B-2	3	EA	6	\$6,375	
	Walls - Plaster/Drywall	239B-2	209	SF	6	\$577	
	Doors - Wood Doors inclu hw	239B-3	1	EA	6	\$301	
	Floor - Wood	239B-3	172	SF	6	\$1,213	
	Power Distribution	239B-3	5	EA	6	\$10,624	
	Walls - Plaster/Drywall	239B-3	264	SF	6	\$729	
	AC Unit	239B	1	EA	5	\$1,826	Not supported properly
	Ceiling - Lay-in	239B	768	SF	6	\$2,306	
	Doors - Wood Doors inclu hw	239B	1	EA	6	\$301	
	Floor - Wood	239B	417	SF	6	\$2,940	
	Lighting - Lay-in	239B	12	EA	7	\$0	
	Power Distribution	239B	2	EA	6	\$4,250	
	Storage/ Closet	239B	70	SF	6	\$508	
	Walls - Plaster/Drywall	239B	774	SF	6	\$2,136	
	AC Unit	300B Office	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	300B Office	102	SF	6	\$353	
	Doors - Wood Doors inclu hw	300B Office	1	EA	6	\$301	
	Floor - Tile/Sheet	300B Office	102	SF	6	\$102	
	Lighting - Pendent/Surface	300B Office	1	EA	6	\$124	
	Power Distribution	300B Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	300B Office	427	SF	6	\$1,178	
	Ceiling - Plaster/Drywall	400E PE Office	281	SF	6	\$972	
	Doors - Wood Doors inclu hw	400E PE Office	1	EA	6	\$301	
	Floor - Tile/Sheet	400E PE Office	281	SF	6	\$281	
	Lighting - Lay-in	400E PE Office	7	EA	6	\$833	
	Power Distribution	400E PE Office	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	400E PE Office	627	SF	6	\$1,730	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	AC Unit	426 ROTC	2	EA	6	\$991	
	Ceiling - Lay-in	426 ROTC	1,061	SF	6	\$3,186	
	Doors - Wood Doors inclu hw	426 ROTC	2	EA	6	\$602	
	Floor - Tile/Sheet	426 ROTC	1,061	SF	6	\$1,062	
	Lighting - Lay-in	426 ROTC	20	EA	6	\$2,380	
	Power Distribution	426 ROTC	6	EA	6	\$12,749	
	Storage/ Closet	426 ROTC	50	SF	6	\$363	
	Walls - Plaster/Drywall	426 ROTC	2,272	SF	6	\$6,270	
	Ceiling - Lay-in	Career Resource 2nd Floor	898	SF	6	\$2,697	
	Doors - Wood Doors inclu hw	Career Resource 2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	Career Resource 2nd Floor	898	SF	6	\$899	
	Lighting - Lay-in	Career Resource 2nd Floor	18	EA	6	\$2,142	
	Power Distribution	Career Resource 2nd Floor	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	Career Resource 2nd Floor	930	SF	6	\$2,567	
	AC Unit	Engineers Office	2	EA	5	\$3,652	Not supported properly
	Ceiling - Lay-in	Engineers Office	452	SF	6	\$1,357	
	Doors - Wood Doors inclu hw	Engineers Office	1	EA	6	\$301	
	Floor - Tile	Engineers Office	452	SF	6	\$989	
	Lighting - Lay-in	Engineers Office	8	EA	4	\$2,687	T12
	Power Distribution	Engineers Office	24	EA	6	\$50,997	
	Walls - Plaster/Drywall	Engineers Office	408	SF	6	\$1,126	Wood paneling
	Walls - Plaster/Drywall	Engineers Office	112	SF	6	\$367	
	AC Unit	Janitors locker/break rm	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	Janitors locker/break rm	236	SF	6	\$817	
	Doors - Wood Doors inclu hw	Janitors locker/break rm	1	EA	6	\$301	
	Floor - Terrazzo	Janitors locker/break rm	236	SF	6	\$516	
	Lighting - Pendent/Surface	Janitors locker/break rm	2	EA	6	\$248	
	Power Distribution	Janitors locker/break rm	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Janitors locker/break rm	601	SF	6	\$1,659	
	Ceiling - Lay-in	Main Gym Office	400	SF	6	\$1,201	
	Doors - Wood Doors inclu hw	Main Gym Office	2	EA	6	\$602	
	Floor - Tile	Main Gym Office	400	SF	6	\$875	
	Lighting - Lay-in	Main Gym Office	8	EA	7	\$0	
	Power Distribution	Main Gym Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Main Gym Office	680	SF	6	\$1,877	
	Ceiling - Lay-in	Police Office 50	208	SF	6	\$625	
	Doors - Wood Doors inclu hw	Police Office 50	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Terrazzo	Police Office 50	208	SF	6	\$455	
	Lighting - Pendent/Surface	Police Office 50	3	EA	7	\$0	
	Power Distribution	Police Office 50	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Police Office 50	909	SF	6	\$2,509	
	Work Slnk	Police Office 50	1	EA	6	\$508	
Auditorium & Theater							
	Balcony Seating	1st Floor	662	EA	6	\$115,133	
	Ceiling - Plaster/Drywall	1st Floor	9,705	SF	6	\$80,910	
	Doors - Steel Doors incl hw	1st Floor	22	EA	6	\$6,622	
	Doors - Wood Doors inclu hw	1st Floor	8	EA	6	\$2,408	
	Floor - Carpet	1st Floor	1,951	SF	6	\$4,157	
	Floor - Concrete	1st Floor	5,833	SF	6	\$3,086	
	Floor - Terrazzo	1st Floor	440	SF	6	\$963	
	Lighting - Chandelier, Incandescent	1st Floor	17	EA	6	\$8,119	
	Lighting - Pendent/Surface	1st Floor	3	EA	6	\$372	
	Lighting - Wall Mounted	1st Floor	32	EA	6	\$3,965	
	Main Floor Seating	1st Floor	902	EA	6	\$156,873	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	2,034	SF	6	\$11,751	
	Stage Curtain	1st Floor	3	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Terrazzo	1st Floor	10	LF	6	\$77	
	Stage-Stairs - Wood	1st Floor	16	LF	6	\$188	
	Stairs - Asphalt	1st Floor	180	LF	6	\$1,671	Concrete
	Stairs - Terrazzo	1st Floor	10	LF	6	\$77	
	Walls - Plaster/Drywall	1st Floor	13,134	SF	6	\$62,543	
	Walls - Plaster/Drywall	1st Floor	175	SF	5	\$1,974	Peeling paint
Gymnasia							
	Ceiling - Plaster/Drywall	400 Gymnasia	4,120	SF	6	\$22,742	
	Ceiling - Plaster/Drywall	400 Gymnasia	200	SF	5	\$4,007	Water Damage
	Doors - Steel Doors incl hw	400 Gymnasia	2	EA	6	\$602	
	Floor - Wood	400 Gymnasia	4,120	SF	6	\$29,046	
	Lighting - Metal Halide/Sodium Vapor	400 Gymnasia	36	EA	6	\$4,814	
	Walls - Plaster/Drywall	400 Gymnasia	5,588	SF	6	\$15,422	
	Walls - Plaster/Drywall	400 Gymnasia	200	SF	5	\$1,021	Water Damage
	Balcony Seating	4th Floor Main Gym 406	440	EA	6	\$76,523	44, 20' benches.

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymnasia							
	Ceiling - Plaster/Drywall	4th Floor Main Gym 406	12,197	SF	5	\$175,638	Peeling paint
	Doors - Steel Doors incl hw	4th Floor Main Gym 406	6	EA	6	\$1,806	
	Floor - Wood	4th Floor Main Gym 406	9,592	SF	6	\$67,623	
	Lighting - Pendent/Surface	4th Floor Main Gym 406	36	EA	4	\$19,463	T12 lighting
	Scoreboards	4th Floor Main Gym 406	3	EA	6	\$6,733	
	Sound System	4th Floor Main Gym 406	1	EA	6	\$41,654	
	Storage/ Closet	4th Floor Main Gym 406	34	SF	6	\$247	Under stairs to balcony.
	Walls - Plaster/Drywall	4th Floor Main Gym 406	7,644	SF	6	\$21,097	
	Walls - Structural Glazed Tile	4th Floor Main Gym 406	3,000	SF	6	\$9,438	
	Ceiling - Plaster/Drywall	Girls gym. Rm 427	3,620	SF	6	\$19,982	
	Ceiling - Plaster/Drywall	Girls gym. Rm 427	500	SF	5	\$8,516	Peeling paint /plaster.
	Doors - Steel Doors incl hw	Girls gym. Rm 427	2	EA	6	\$602	
	Floor - Wood	Girls gym. Rm 427	4,120	SF	6	\$29,046	
	Lighting - Pendent/Surface	Girls gym. Rm 427	36	EA	7	\$0	
	Sound System	Girls gym. Rm 427	1	EA	6	\$41,654	
	Storage/ Closet	Girls gym. Rm 427	104	SF	5	\$1,678	Peeling paint/plaster.
	Walls - Plaster/Drywall	Girls gym. Rm 427	5,588	SF	5	\$42,351	Peeling paint, cracking plaster.
Kitchen							
	Ceiling - Plaster/Drywall	300A Kitchen	678	SF	6	\$2,346	
	Doors - Wood Doors inclu hw	300A Kitchen	2	EA	6	\$602	
	Floor - Tile/Sheet	300A Kitchen	678	SF	6	\$679	
	Lighting - Pendent/Surface	300A Kitchen	10	EA	6	\$1,239	
	Walls - Plaster/Drywall	300A Kitchen	1,785	SF	6	\$4,926	
	Ceiling - Splined	300E Kitchen	1,903	SF	6	\$1,551	
	Doors - Wood Doors inclu hw	300E Kitchen	2	EA	6	\$602	
	Floor - Concrete	300E Kitchen	1,903	SF	6	\$1,007	
	Lighting - Pendent/Surface	300E Kitchen	32	EA	6	\$3,965	
	Walls - Plaster/Drywall	300E Kitchen	2,029	SF	6	\$5,600	
	AC Unit	437/439 Culinary Training Kitchen	2	EA	6	\$991	
	Ceiling - Lay-in	437/439 Culinary Training Kitchen	1,700	SF	6	\$5,105	
	Doors - Wood Doors inclu hw	437/439 Culinary Training Kitchen	3	EA	6	\$903	
	Floor - Tile	437/439 Culinary Training Kitchen	1,700	SF	6	\$3,719	
	Lighting - Lay-in	437/439 Culinary Training Kitchen	35	EA	7	\$0	
	Storage/ Closet	437/439 Culinary Training Kitchen	261	SF	6	\$1,892	
	Walls - Plaster/Drywall	437/439 Culinary Training Kitchen	1,423	SF	6	\$3,927	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Library							
	AC Unit	229 Library	2	EA	7	\$0	
	AC Unit	229 Library	2	EA	5	\$3,652	Not supported properly
	Casework	229 Library	256	LF	6	\$6,465	
	Ceiling - Plaster/Drywall	229 Library	4,269	SF	6	\$14,773	
	Doors - Wood Doors inclu hw	229 Library	2	EA	6	\$602	
	Floor - Carpet	229 Library	4,269	SF	6	\$9,096	
	Floor - Wood	229 Library	533	SF	6	\$3,758	
	Lighting - Pendent/Surface	229 Library	27	EA	6	\$3,345	
	Walls - Plaster/Drywall	229 Library	2,342	SF	6	\$6,464	
Locker/Shower Room							
	Accessories	109 Girls Locker Room - Not in Use	2,789	SF	5	\$24,368	
	Benches, ped mounted	109 Girls Locker Room - Not in Use	35	LF	5	\$9,616	
	Ceiling - Exposed	109 Girls Locker Room - Not in Use	2,789	SF	6	\$4,148	
	Doors - Wood Doors inclu hw	109 Girls Locker Room - Not in Use	2	EA	6	\$602	
	Floor Drain	109 Girls Locker Room - Not in Use	5	EA	6	\$5,296	
	Floor - Concrete	109 Girls Locker Room - Not in Use	2,789	SF	6	\$1,476	
	Hand Dryer	109 Girls Locker Room - Not in Use	11	EA	6	\$2,530	
	Lavatory	109 Girls Locker Room - Not in Use	3	EA	6	\$959	
	Lavatory	109 Girls Locker Room - Not in Use	1	EA	5	\$3,763	Missing one Lav.
	Lighting - Pendent/Surface	109 Girls Locker Room - Not in Use	38	EA	6	\$4,708	
	Showers	109 Girls Locker Room - Not in Use	17	EA	6	\$5,294	
	Student Lockers - Two Tier	109 Girls Locker Room - Not in Use	100	EA	6	\$4,642	
	Walls - Masonry	109 Girls Locker Room - Not in Use	2,224	SF	6	\$6,997	
	Walls - Plaster/Drywall	109 Girls Locker Room - Not in Use	677	SF	6	\$1,868	
	Walls - Structural Glazed Tile	109 Girls Locker Room - Not in Use	988	SF	6	\$3,108	
	Walls - Tile Ceramic/ Porcelain	109 Girls Locker Room - Not in Use	512	SF	6	\$1,157	
	Water Closet	109 Girls Locker Room - Not in Use	4	EA	6	\$1,344	
	Accessories	127 Boys Locker - Not in Use	1,288	SF	6	\$5,047	
	Ceiling - Plaster/ Drywall	127 Boys Locker - Not in Use	1,288	SF	6	\$4,457	
	Doors - Wood Doors inclu hw	127 Boys Locker - Not in Use	2	EA	6	\$602	
	Floor - Concrete	127 Boys Locker - Not in Use	1,288	SF	6	\$681	
	Lighting - Pendent/Surface	127 Boys Locker - Not in Use	16	EA	6	\$1,982	
	Walls - Concrete Block	127 Boys Locker - Not in Use	330	SF	6	\$967	
	Walls - Plaster/Drywall	127 Boys Locker - Not in Use	354	SF	6	\$977	
	Walls - Structural Glazed Tile	127 Boys Locker - Not in Use	1,118	SF	6	\$3,517	
	Accessories	400A Girls Locker Room	4,211	SF	5	\$36,793	
	Benches, ped mounted	400A Girls Locker Room	35	LF	5	\$9,616	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/Shower Room							
	Ceiling - Plaster/ Drywall	400A Girls Locker Room	4,211	SF	6	\$14,573	
	Doors - Wood Doors inclu hw	400A Girls Locker Room	4	EA	6	\$1,204	
	Floor Drain	400A Girls Locker Room	2	EA	6	\$2,118	
	Floor - Concrete	400A Girls Locker Room	4,211	SF	6	\$2,228	
	Hand Dryer	400A Girls Locker Room	14	EA	6	\$3,221	
	Lavatory	400A Girls Locker Room	3	EA	6	\$959	
	Lighting - Pendent/Surface	400A Girls Locker Room	46	EA	6	\$5,699	
	Showers	400A Girls Locker Room	10	EA	6	\$3,114	
	Student Lockers - Two Tier	400A Girls Locker Room	723	EA	6	\$33,560	
	Walls - Masonry	400A Girls Locker Room	2,224	SF	6	\$6,997	
	Walls - Plaster/Drywall	400A Girls Locker Room	677	SF	6	\$1,868	
	Walls - Structural Glazed Tile	400A Girls Locker Room	988	SF	6	\$3,108	
	Walls - Tile Ceramic/ Porcelain	400A Girls Locker Room	512	SF	6	\$1,157	
	Water Closet	400A Girls Locker Room	3	EA	6	\$1,008	
	Accessories	Boys Locker Room	1,794	SF	6	\$7,029	
	Ceiling - Plaster/ Drywall	Boys Locker Room	1,794	SF	6	\$6,208	
	Doors - Transom Window	Boys Locker Room	25	SF	6	\$423	
	Doors - Wood Doors inclu hw	Boys Locker Room	3	EA	6	\$903	
	Floor Drain	Boys Locker Room	3	EA	6	\$3,177	
	Floor - Terrazzo	Boys Locker Room	224	SF	6	\$490	
	Floor - Tile Ceramic/ Porcelain	Boys Locker Room	370	SF	6	\$783	
	Floor - Tile/Sheet	Boys Locker Room	1,092	SF	6	\$1,093	
	Lighting - Pendent/Surface	Boys Locker Room	22	EA	4	\$11,894	T12 Lighting
	Partitions	Boys Locker Room	2	EA	6	\$594	
	Showers	Boys Locker Room	17	EA	6	\$5,294	
	Student Lockers - Two Tier	Boys Locker Room	125	EA	6	\$5,802	
	Urinals	Boys Locker Room	3	EA	6	\$1,008	
	Walls - Concrete Block	Boys Locker Room	80	SF	6	\$235	
	Walls - Plaster/Drywall	Boys Locker Room	2,118	SF	6	\$5,845	
	Walls - Structural Glazed Tile	Boys Locker Room	511	SF	6	\$1,608	
	Water Closet	Boys Locker Room	2	EA	6	\$672	
Lunch & Multipurpose Room							
	AC Unit	300 Lunch	8	EA	6	\$3,965	
	Ceiling - Lay-in	300 Lunch	10,667	SF	6	\$32,033	
	Doors - Wood Doors inclu hw	300 Lunch	2	EA	6	\$602	
	Floor - Tile/Sheet	300 Lunch	10,667	SF	6	\$10,678	
	Lighting - Lay-in	300 Lunch	85	EA	6	\$10,113	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Serving Line	300 Lunch	132	LF	6	\$7,856	
	Walls - Plaster/Drywall	300 Lunch	4,545	SF	6	\$12,544	
	AC Unit	300C Serving Line	1	EA	6	\$496	
	Ceiling - Lay-in	300C Serving Line	2,291	SF	6	\$6,880	
	Doors - Wood Doors inclu hw	300C Serving Line	4	EA	6	\$1,204	
	Floor - Tile/Sheet	300C Serving Line	2,291	SF	6	\$2,293	
	Lighting - Lay-in	300C Serving Line	24	EA	6	\$2,855	
	Serving Line	300C Serving Line	60	LF	6	\$3,571	
	Walls - Plaster/Drywall	300C Serving Line	1,900	SF	6	\$5,244	
	AC Unit	300D Teachers Faculty Lunchroom	1	EA	6	\$496	
	Ceiling - Lay-in	300D Teachers Faculty Lunchroom	639	SF	6	\$1,919	
	Doors - Wood Doors inclu hw	300D Teachers Faculty Lunchroom	1	EA	6	\$301	
	Floor - Tile/Sheet	300D Teachers Faculty Lunchroom	639	SF	6	\$640	
	Lighting - Lay-in	300D Teachers Faculty Lunchroom	8	EA	6	\$952	
	Walls - Plaster/Drywall	300D Teachers Faculty Lunchroom	1,252	SF	6	\$3,455	
	AC Unit	306 Band Room	3	EA	6	\$1,487	
	Ceiling - Lay-in	306 Band Room	1,830	SF	6	\$5,495	
	Doors - Wood Doors inclu hw	306 Band Room	2	EA	6	\$602	
	Floor - Tile/Sheet	306 Band Room	2,681	SF	6	\$2,684	
	Lighting - Lay-in	306 Band Room	21	EA	6	\$2,498	
	Lighting - Pendent/Surface	306 Band Room	12	EA	6	\$1,487	
	Stage	306 Band Room	790	SF	6	\$4,564	
	Walls - Plaster/Drywall	306 Band Room	2,928	SF	6	\$8,081	
MDF_IDF							
	AC Unit	308 MDF Room	1	EA	4	\$6,086	Not supported properly
	Doors - Wood Doors inclu hw	308 MDF Room	1	EA	6	\$301	
	Finishes	308 MDF Room	588	SF	6	\$4,196	
Mechanical/ Service Rooms							
	Air Intake Plenums	1st Floor	749	SF	6	\$4,638	Rm111. Peeling paint.
	Air Intake Plenums	1st Floor	349	SF	6	\$2,161	118A
	Air Intake Plenums	1st Floor	295	SF	6	\$1,827	106A
	Air Intake Plenums	1st Floor	295	SF	6	\$1,827	In 106
	Air Intake Plenums	1st Floor	270	SF	6	\$1,672	In rm 118
	Air Tunnel	1st Floor	441	SF	6	\$2,731	In rm 118
	Air Tunnel	1st Floor	450	SF	6	\$2,786	In rm 106
	Boiler Room	1st Floor	2,067	SF	5	\$33,342	Peeling paint

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Crawl Space - Unfinished	1st Floor	1,887	SF	6	\$11,684	Unfinished
	Mechanical/ Service Rooms	1st Floor	1,032	SF	6	\$7,394	Rm118
	Mechanical/ Service Rooms	1st Floor	1,027	SF	6	\$7,358	Rm106
	Mechanical/ Service Rooms	1st Floor	2,400	SF	5	\$38,713	Peeling paint. Room in boiler room.
	Storage Room	1st Floor	81	SF	3	\$2,258	B10B-1 Ceiling falling in, floor crumbling.
	Storage Room	1st Floor	6,873	SF	6	\$49,240	130, 130A, 111C, 110C, 125A, 113A, 112D, 102D, E, F, G, 103B, 202B, 214C, 301B, 303B, 305A, 323A, 400A, D, 403B, 405B, 425A, B, C, D, E, F Storage room are adding together.
	Storage Room	1st Floor	1,013	SF	5	\$16,340	Peeling paint
	Storage Room	1st Floor	465	SF	5	\$7,501	Peeling paint. Boiler room office
	Storage Room	1st Floor	30	SF	6	\$0	In boiler rm.
	Air Tunnel	2nd Floor	236	SF	5	\$3,142	Peeling paint. In storage rm.
	Janitor's Closet	2nd Floor	95	SF	6	\$681	
	Janitor's Closet	2nd Floor	35	SF	6	\$251	Next to boys restroom.
	Mechanical/ Service Rooms	2nd Floor	122	SF	6	\$874	Next to 214
	Mechanical/ Service Rooms	2nd Floor	80	SF	6	\$573	Next to balcony.
	Storage Room	2nd Floor	123	SF	6	\$881	Next to balcony
	Storage Room	2nd Floor	1,011	SF	6	\$7,243	Across from engineers office.
	Storage Room	2nd Floor	253	SF	5	\$4,081	Peeling paint
	Storage Room	2nd Floor	25	SF	6	\$179	Next to boys restroom.
	Storage Room	2nd Floor	125	SF	5	\$2,016	Damaged plaster. Next to balcony.
	Storage Room	2nd Floor	780	SF	6	\$5,588	Next to janitor locker/break rm.
	Storage Room	3rd Floor	40	SF	6	\$287	South side auditorium balcony. No keys no entry.
	Janitor's Closet	4th Floor	50	SF	6	\$358	Next to boys restroom
	Mechanical/ Service Rooms	4th Floor	20	SF	6	\$143	In room 437
	Storage Room	4th Floor	350	SF	6	\$2,508	Main gym storage
	Storage Room	4th Floor	20	SF	6	\$143	Next to boys restroom
	Storage Room	4th Floor	72	SF	6	\$516	Main gym storage
Pool & Natatorium							
	Accessories	108 Pool - Not use	3,409	SF	6	\$2,340	
	Bleachers Seating/Plank Seating	108 Pool - Not use	7	EA	6	\$203	
	Ceiling - Lay-In	108 Pool - Not use	3,409	SF	6	\$10,237	
	Doors - Steel Doors incl hw	108 Pool - Not use	3	EA	6	\$903	
	Floor - Concrete	108 Pool - Not use	1,466	SF	6	\$776	
	Lighting - Lay-in	108 Pool - Not use	51	EA	6	\$6,068	
	Pool Basin	108 Pool - Not use	2,482	SF	6	\$83,975	
	Pool Deck	108 Pool - Not use	1,466	SF	6	\$13,920	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Pool & Natatorium							
	Pool Deck Drains	108 Pool - Not use	1	EA	6	\$422	
	Walls - Masonry	108 Pool - Not use	5,131	SF	6	\$16,142	
Prep Room							
	Casework	301A Prep Room	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	301A Prep Room	207	SF	6	\$716	
	Doors - Wood Doors inclu hw	301A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	301A Prep Room	207	SF	6	\$207	
	Lighting - Pendent/Surface	301A Prep Room	2	EA	6	\$248	
	Walls - Plaster/Drywall	301A Prep Room	751	SF	6	\$2,073	
	Work Sink	301A Prep Room	2	EA	6	\$758	
	Casework	303A Prep Room	40	LF	6	\$1,010	
	Ceiling - Plaster/Drywall	303A Prep Room	207	SF	6	\$716	
	Doors - Wood Doors inclu hw	303A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	303A Prep Room	207	SF	6	\$207	
	Lighting - Pendent/Surface	303A Prep Room	2	EA	6	\$248	
	Walls - Plaster/Drywall	303A Prep Room	751	SF	6	\$2,073	
	Work Sink	303A Prep Room	2	EA	6	\$758	
	Casework	403A Prep Room	20	LF	6	\$505	
	Ceiling - Plaster/Drywall	403A Prep Room	207	SF	6	\$716	
	Doors - Wood Doors inclu hw	403A Prep Room	1	EA	6	\$301	
	Floor - Tile/Sheet	403A Prep Room	207	SF	6	\$207	
	Lighting - Pendent/Surface	403A Prep Room	6	EA	6	\$743	
	Walls - Plaster/Drywall	403A Prep Room	751	SF	6	\$2,073	
	Work Sink	403A Prep Room	1	EA	6	\$379	
Restroom							
	Accessories	102A restroom	130	SF	5	\$2,573	Restroom out of service
	Ceiling - Plaster/Drywall	102A restroom	130	SF	6	\$450	
	Doors - Wood Doors inclu hw	102A restroom	1	EA	5	\$1,174	Missing hardware
	Floor Drain	102A restroom	1	EA	6	\$1,059	
	Floor - Terrazzo	102A restroom	130	SF	6	\$284	
	Lighting - Pendent/Surface	102A restroom	1	EA	4	\$541	Not working T12
	Partitions	102A restroom	1	EA	6	\$297	
	Urinals	102A restroom	2	EA	5	\$2,688	Out of service
	Walls - Plaster/Drywall	102A restroom	600	SF	5	\$4,547	Efloresence, peeling paint, cracked/broken plaster.
	Water Closet	102A restroom	1	EA	5	\$1,344	Out of service
	Accessories	105A restroom	216	SF	6	\$1,992	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Ceiling - Plaster/Drywall	105A restroom	216	SF	6	\$747	
	Doors - Wood Doors inclu hw	105A restroom	1	EA	6	\$301	
	Floor - Concrete	105A restroom	216	SF	6	\$114	
	Lighting - Pendent/Surface	105A restroom	1	EA	6	\$124	
	Partitions	105A restroom	1	EA	6	\$297	Structural glazed tile
	Urinals	105A restroom	1	EA	6	\$336	
	Walls - Masonry	105A restroom	711	SF	6	\$2,237	
	Walls - Masonry	105A restroom	186	SF	6	\$931	Painted taracotta
	Walls - Plaster/Drywall	105A restroom	67	SF	6	\$185	
	Walls - Structural Glazed Tile	105A restroom	129	SF	6	\$406	
	Water Closet	105A restroom	1	EA	6	\$336	
	Accessories	109B Boys Toilet - Not Used	629	SF	6	\$5,802	
	Ceiling - Plaster/Drywall	109B Boys Toilet - Not Used	629	SF	6	\$2,177	
	Doors - Wood Doors inclu hw	109B Boys Toilet - Not Used	2	EA	6	\$602	
	Floor Drain	109B Boys Toilet - Not Used	2	EA	6	\$2,118	
	Floor - Terrazzo	109B Boys Toilet - Not Used	629	SF	6	\$1,376	
	Lavatory	109B Boys Toilet - Not Used	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	109B Boys Toilet - Not Used	9	EA	6	\$1,115	
	Partitions	109B Boys Toilet - Not Used	2	EA	6	\$594	
	Urinals	109B Boys Toilet - Not Used	9	EA	6	\$3,024	
	Walls - Plaster/Drywall	109B Boys Toilet - Not Used	1,351	SF	6	\$3,729	
	Water Closet	109B Boys Toilet - Not Used	2	EA	6	\$672	
	Accessories	127 Boys Toilet - Not Used	653	SF	6	\$6,023	
	Ceiling - Plaster/Drywall	127 Boys Toilet - Not Used	653	SF	6	\$2,260	
	Doors - Wood Doors inclu hw	127 Boys Toilet - Not Used	1	EA	6	\$301	
	Floor Drain	127 Boys Toilet - Not Used	2	EA	6	\$2,118	
	Floor - Terrazzo	127 Boys Toilet - Not Used	653	SF	6	\$1,429	
	Hand Dryer	127 Boys Toilet - Not Used	4	EA	6	\$920	
	Lavatory	127 Boys Toilet - Not Used	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	127 Boys Toilet - Not Used	9	EA	6	\$1,115	
	Partitions	127 Boys Toilet - Not Used	2	EA	6	\$594	
	Urinals	127 Boys Toilet - Not Used	7	EA	6	\$2,352	
	Walls - Plaster/Drywall	127 Boys Toilet - Not Used	569	SF	6	\$1,570	
	Walls - Tile Ceramic/ Porcelain	127 Boys Toilet - Not Used	854	SF	6	\$1,930	
	Water Closet	127 Boys Toilet - Not Used	2	EA	6	\$672	
	Accessories	1st floor girls restroom	653	SF	6	\$6,023	
	Ceiling - Plaster/Drywall	1st floor girls restroom	653	SF	6	\$2,260	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Steel Doors incl hw	1st floor girls restroom	2	EA	6	\$602	
	Floor Drain	1st floor girls restroom	2	EA	6	\$2,118	
	Floor - Terrazzo	1st floor girls restroom	653	SF	6	\$1,429	
	Hand Dryer	1st floor girls restroom	4	EA	6	\$920	
	Lavatory	1st floor girls restroom	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	1st floor girls restroom	9	EA	7	\$0	
	Partitions	1st floor girls restroom	9	EA	6	\$2,672	
	Walls - Plaster/Drywall	1st floor girls restroom	569	SF	6	\$1,570	
	Walls - Tile Ceramic/ Porcelain	1st floor girls restroom	854	SF	6	\$1,930	
	Water Closet	1st floor girls restroom	11	EA	6	\$3,696	
	Accessories	208A. Custodian locker room restroom.	53	SF	6	\$489	
	Ceiling - Plaster/Drywall	208A. Custodian locker room restroom.	53	SF	6	\$183	
	Doors - Wood Doors inclu hw	208A. Custodian locker room restroom.	1	EA	6	\$301	
	Floor - Terrazzo	208A. Custodian locker room restroom.	53	SF	6	\$116	
	Hand Dryer	208A. Custodian locker room restroom.	1	EA	4	\$1,079	Not operational.
	Lavatory	208A. Custodian locker room restroom.	1	EA	6	\$320	
	Lighting - Pendent/Surface	208A. Custodian locker room restroom.	1	EA	4	\$541	Incandescent fixture.
	Partitions	208A. Custodian locker room restroom.	1	EA	6	\$297	
	Urinals	208A. Custodian locker room restroom.	1	EA	5	\$1,344	Not operational.
	Walls - Plaster/Drywall	208A. Custodian locker room restroom.	380	SF	5	\$2,880	Eflorescence, peeling paint.
	Water Closet	208A. Custodian locker room restroom.	1	EA	6	\$336	
	Accessories	230A Unisex Toilet	134	SF	6	\$1,236	
	Ceiling - Plaster/Drywall	230A Unisex Toilet	134	SF	6	\$464	
	Doors - Wood Doors inclu hw	230A Unisex Toilet	1	EA	6	\$301	
	Floor - Terrazzo	230A Unisex Toilet	134	SF	6	\$293	
	Hand Dryer	230A Unisex Toilet	1	EA	6	\$230	
	Lavatory	230A Unisex Toilet	2	EA	6	\$639	
	Lighting - Pendent/Surface	230A Unisex Toilet	2	EA	6	\$248	
	Partitions	230A Unisex Toilet	3	EA	6	\$891	
	Walls - Structural Glazed Tile	230A Unisex Toilet	314	SF	6	\$988	
	Water Closet	230A Unisex Toilet	3	EA	6	\$1,008	
	Accessories	231B Boys Toilet	629	SF	6	\$5,802	
	Ceiling - Plaster/Drywall	231B Boys Toilet	629	SF	6	\$2,177	
	Doors - Wood Doors inclu hw	231B Boys Toilet	2	EA	6	\$602	
	Floor Drain	231B Boys Toilet	2	EA	6	\$2,118	
	Floor - Terrazzo	231B Boys Toilet	629	SF	6	\$1,376	
	Hand Dryer	231B Boys Toilet	4	EA	6	\$920	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	231B Boys Toilet	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	231B Boys Toilet	6	EA	6	\$743	
	Partitions	231B Boys Toilet	2	EA	6	\$594	
	Urinals	231B Boys Toilet	9	EA	6	\$3,024	
	Walls - Plaster/Drywall	231B Boys Toilet	1,158	SF	6	\$3,196	
	Walls - Tile Ceramic/ Porcelain	231B Boys Toilet	1,273	SF	6	\$2,876	
	Water Closet	231B Boys Toilet	2	EA	6	\$672	
	Ceiling - Plaster/Drywall	232A restroom	38	SF	5	\$348	Peeling paint
	Doors - Wood Doors inclu hw	232A restroom	1	EA	6	\$301	
	Floor - Terrazzo	232A restroom	38	SF	6	\$83	
	Hand Dryer	232A restroom	1	EA	4	\$1,079	Not operational
	Lighting - Pendent/Surface	232A restroom	1	EA	4	\$541	Incandescent fixture
	Partitions	232A restroom	1	EA	6	\$297	
	Walls - Plaster/Drywall	232A restroom	332	SF	5	\$2,516	Peeling paint
	Accessories	236A restroom.	46	SF	6	\$424	
	Ceiling - Lay-in	236A restroom.	46	SF	6	\$138	
	Doors - Wood Doors inclu hw	236A restroom.	1	EA	6	\$301	
	Floor - Tile	236A restroom.	46	SF	6	\$101	
	Lavatory	236A restroom.	1	EA	6	\$320	
	Lighting - Lay-in	236A restroom.	1	EA	7	\$0	
	Walls - Plaster/Drywall	236A restroom.	25	SF	6	\$82	
	Walls - Plaster/Drywall	236A restroom.	145	SF	6	\$400	Paneling.
	Water Closet	236A restroom.	1	EA	6	\$336	
	Accessories	334 restroom	32	SF	6	\$295	
	Ceiling - Plaster/Drywall	334 restroom	32	SF	6	\$111	
	Doors - Wood Doors inclu hw	334 restroom	1	EA	6	\$301	
	Floor - Tile	334 restroom	32	SF	6	\$70	
	Lavatory	334 restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	334 restroom	1	EA	4	\$541	Incandescent fixture
	Walls - Plaster/Drywall	334 restroom	229	SF	6	\$632	
	Accessories	3rd Floor Girls	653	SF	6	\$6,023	
	Ceiling - Plaster/Drywall	3rd Floor Girls	653	SF	6	\$2,260	
	Doors - Wood Doors inclu hw	3rd Floor Girls	1	EA	6	\$301	
	Floor Drain	3rd Floor Girls	2	EA	6	\$2,118	
	Floor - Terrazzo	3rd Floor Girls	653	SF	6	\$1,429	
	Hand Dryer	3rd Floor Girls	4	EA	6	\$920	
	Lavatory	3rd Floor Girls	4	EA	6	\$1,278	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Pendent/Surface	3rd Floor Girls	9	EA	6	\$1,115	
	Partitions	3rd Floor Girls	12	EA	6	\$3,563	
	Walls - Plaster/Drywall	3rd Floor Girls	569	SF	6	\$1,570	
	Walls - Tile Ceramic/ Porcelain	3rd Floor Girls	854	SF	6	\$1,930	
	Water Closet	3rd Floor Girls	12	EA	6	\$4,032	
	Accessories	3rd Floor Women	412	SF	6	\$3,800	
	Ceiling - Lay-in	3rd Floor Women	412	SF	6	\$1,237	
	Doors - Wood Doors inclu hw	3rd Floor Women	1	EA	6	\$301	
	Floor Drain	3rd Floor Women	1	EA	6	\$1,059	
	Floor - Terrazzo	3rd Floor Women	412	SF	6	\$901	
	Lavatory	3rd Floor Women	2	EA	6	\$639	
	Lighting - Lay-in	3rd Floor Women	6	EA	6	\$714	
	Partitions	3rd Floor Women	3	EA	6	\$891	
	Walls - Plaster/Drywall	3rd Floor Women	792	SF	6	\$2,186	
	Water Closet	3rd Floor Women	3	EA	6	\$1,008	
	Accessories	4th Floor Boys	653	SF	6	\$6,023	
	Ceiling - Plaster/Drywall	4th Floor Boys	653	SF	6	\$2,260	
	Doors - Wood Doors inclu hw	4th Floor Boys	1	EA	6	\$301	
	Floor Drain	4th Floor Boys	2	EA	6	\$2,118	
	Floor - Terrazzo	4th Floor Boys	653	SF	6	\$1,429	
	Hand Dryer	4th Floor Boys	4	EA	6	\$920	
	Lavatory	4th Floor Boys	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	4th Floor Boys	9	EA	7	\$0	
	Partitions	4th Floor Boys	2	EA	6	\$594	
	Urinals	4th Floor Boys	7	EA	6	\$2,352	
	Walls - Plaster/Drywall	4th Floor Boys	569	SF	6	\$1,570	
	Walls - Tile Ceramic/ Porcelain	4th Floor Boys	854	SF	6	\$1,930	
	Water Closet	4th Floor Boys	2	EA	6	\$672	
	Accessories	4th Floor Girls	653	SF	6	\$6,023	
	Ceiling - Plaster/Drywall	4th Floor Girls	653	SF	6	\$2,260	
	Doors - Wood Doors inclu hw	4th Floor Girls	1	EA	6	\$301	
	Floor Drain	4th Floor Girls	2	EA	6	\$2,118	
	Floor - Terrazzo	4th Floor Girls	653	SF	6	\$1,429	
	Hand Dryer	4th Floor Girls	4	EA	6	\$920	
	Lavatory	4th Floor Girls	4	EA	6	\$1,278	
	Lighting - Pendent/Surface	4th Floor Girls	9	EA	6	\$1,115	
	Partitions	4th Floor Girls	12	EA	6	\$3,563	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	4th Floor Girls	569	SF	6	\$1,570	
	Walls - Tile Ceramic/ Porcelain	4th Floor Girls	854	SF	6	\$1,930	
	Water Closet	4th Floor Girls	12	EA	6	\$4,032	
	Accessories	Engineers Office	71	SF	6	\$655	
	Ceiling - Lay-in	Engineers Office	56	SF	6	\$199	
	Ceiling - Lay-in	Engineers Office	56	SF	6	\$199	
	Doors - Wood Doors inclu hw	Engineers Office	1	EA	6	\$301	
	Floor - Terrazzo	Engineers Office	71	SF	6	\$155	
	Lavatory	Engineers Office	1	EA	6	\$320	
	Lighting - Lay-in	Engineers Office	1	EA	4	\$336	T12 lighting
	Partitions	Engineers Office	1	EA	6	\$297	
	Walls - Plaster/Drywall	Engineers Office	317	SF	6	\$875	
	Water Closet	Engineers Office	1	EA	6	\$336	
	Accessories	Janitor locker/break rm restroom	100	SF	6	\$922	
	Ceiling - Plaster/Drywall	Janitor locker/break rm restroom	100	SF	6	\$346	
	Doors - Transom Window	Janitor locker/break rm restroom	14	SF	6	\$237	
	Doors - Wood Doors inclu hw	Janitor locker/break rm restroom	1	EA	6	\$301	
	Floor - Terrazzo	Janitor locker/break rm restroom	100	SF	6	\$219	
	Lavatory	Janitor locker/break rm restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Janitor locker/break rm restroom	1	EA	4	\$541	T12 lighting
	Partitions	Janitor locker/break rm restroom	2	EA	6	\$594	
	Showers	Janitor locker/break rm restroom	1	EA	6	\$311	
	Student Lockers - One Tier	Janitor locker/break rm restroom	7	EA	6	\$650	
	Walls - Plaster/Drywall	Janitor locker/break rm restroom	512	SF	6	\$1,413	
	Water Closet	Janitor locker/break rm restroom	1	EA	6	\$336	
	Accessories	Main Gym Office Restroom	147	SF	6	\$1,356	
	Ceiling - Plaster/Drywall	Main Gym Office Restroom	147	SF	6	\$509	
	Doors - Wood Doors inclu hw	Main Gym Office Restroom	1	EA	6	\$301	
	Floor - Tile	Main Gym Office Restroom	147	SF	6	\$322	
	Lavatory	Main Gym Office Restroom	1	EA	6	\$320	
	Lighting - Pendent/Surface	Main Gym Office Restroom	2	EA	6	\$248	
	Partitions	Main Gym Office Restroom	2	EA	6	\$594	
	Showers	Main Gym Office Restroom	1	EA	6	\$311	
	Student Lockers - One Tier	Main Gym Office Restroom	6	EA	6	\$557	
	Urinals	Main Gym Office Restroom	1	EA	6	\$336	
	Walls - Plaster/Drywall	Main Gym Office Restroom	600	SF	6	\$1,656	
	Walls - Plaster/Drywall	Main Gym Office Restroom	30	SF	5	\$153	Peeling paint

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	Main Gym Office Restroom	1	EA	5	\$1,344	Not working
	Accessories	Men's restroom (staff) 1st floor	99	SF	6	\$913	
	Ceiling - Plaster/Drywall	Men's restroom (staff) 1st floor	99	SF	5	\$907	Peeling paint.
	Doors - Wood Doors inclu hw	Men's restroom (staff) 1st floor	1	EA	6	\$301	
	Floor - Terrazzo	Men's restroom (staff) 1st floor	99	SF	6	\$217	
	Lavatory	Men's restroom (staff) 1st floor	1	EA	6	\$320	
	Lighting - Chandelier, Incandescent	Men's restroom (staff) 1st floor	1	EA	4	\$1,057	Incandescent light. Exposed wires.
	Partitions	Men's restroom (staff) 1st floor	3	EA	6	\$891	
	Urinals	Men's restroom (staff) 1st floor	1	EA	6	\$336	
	Walls - Masonry	Men's restroom (staff) 1st floor	309	SF	6	\$972	
	Walls - Plaster/Drywall	Men's restroom (staff) 1st floor	110	SF	5	\$834	Peeling paint.
	Water Closet	Men's restroom (staff) 1st floor	1	EA	6	\$336	
	Accessories	Police Office	83	SF	6	\$766	
	Ceiling - Plaster/Drywall	Police Office	83	SF	6	\$287	
	Doors - Wood Doors inclu hw	Police Office	1	EA	6	\$301	
	Floor Drain	Police Office	2	EA	6	\$2,118	
	Floor - Terrazzo	Police Office	83	SF	6	\$182	
	Lavatory	Police Office	1	EA	6	\$320	
	Lighting - Pendent/Surface	Police Office	1	EA	6	\$124	
	Partitions	Police Office	2	EA	6	\$594	
	Showers	Police Office	1	EA	5	\$1,172	Water supply's capped off, not functioning.
	Urinals	Police Office	1	EA	5	\$1,344	Appears to no longer be in use.
	Walls - Plaster/Drywall	Police Office	40	SF	5	\$204	Eflorescence,damaged plaster.
	Walls - Plaster/Drywall	Police Office	521	SF	6	\$1,438	
	Water Closet	Police Office	1	EA	6	\$336	
	Accessories	Womens restroom (staff) 1st floor	109	SF	6	\$1,005	
	Ceiling - Plaster/Drywall	Womens restroom (staff) 1st floor	109	SF	6	\$377	
	Doors - Wood Doors inclu hw	Womens restroom (staff) 1st floor	1	EA	6	\$301	
	Floor Drain	Womens restroom (staff) 1st floor	1	EA	6	\$1,059	
	Floor - Terrazzo	Womens restroom (staff) 1st floor	109	SF	6	\$238	
	Hand Dryer	Womens restroom (staff) 1st floor	1	EA	4	\$1,079	Not operational.
	Lavatory	Womens restroom (staff) 1st floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	Womens restroom (staff) 1st floor	1	EA	6	\$124	
	Partitions	Womens restroom (staff) 1st floor	3	EA	6	\$891	
	Walls - Masonry	Womens restroom (staff) 1st floor	311	SF	6	\$978	Stone
	Walls - Plaster/Drywall	Womens restroom (staff) 1st floor	85	SF	6	\$235	
	Water Closet	Womens restroom (staff) 1st floor	2	EA	6	\$672	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Rooms (Other Than Classrooms) Subtotal:						\$3,530,000	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Plaster/Drywall	1st fl Maintenance Dept	452	SF	6	\$2,799	
	Doors - Steel Doors incl hw	1st fl Maintenance Dept	1	EA	6	\$301	
	Floor - Terrazzo	1st fl Maintenance Dept	452	SF	6	\$3,794	
	Lighting - Pendent/Surface	1st fl Maintenance Dept	6	EA	4	\$3,244	
	Walls - Plaster/Drywall	1st fl Maintenance Dept	1,957	SF	6	\$8,675	
	Ceiling - Lay-in	1st Floor	16,751	SF	6	\$50,303	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Drinking Fountains - Double Fountain	1st Floor	5	EA	6	\$1,680	
	Floor - Terrazzo	1st Floor	16,751	SF	6	\$140,610	
	Lighting - Lay-in	1st Floor	90	EA	6	\$10,708	
	Student Lockers - One Tier	1st Floor	517	EA	6	\$47,996	
	Walls - Plaster/Drywall	1st Floor	42,078	SF	6	\$186,532	
	Ceiling - Lay-in	2nd Floor	16,751	SF	6	\$50,303	
	Drinking Fountains - Double Fountain	2nd Floor	4	EA	6	\$1,344	
	Drinking Fountains - Single Fountain	2nd Floor	1	EA	6	\$276	
	Floor - Terrazzo	2nd Floor	16,751	SF	6	\$140,610	
	Lighting - Lay-in	2nd Floor	90	EA	6	\$10,708	
	Walls - Plaster/Drywall	2nd Floor	42,078	SF	6	\$186,532	
	Ceiling - Lay-in	3rd Floor	13,238	SF	6	\$39,754	
	Drinking Fountains - Double Fountain	3rd Floor	5	EA	6	\$1,680	
	Floor - Terrazzo	3rd Floor	5,886	SF	6	\$49,408	
	Floor - Tile/Sheet	3rd Floor	8,352	SF	6	\$4,538	
	Lighting - Lay-in	3rd Floor	60	EA	6	\$7,139	
	Student Lockers - One Tier	3rd Floor	504	EA	6	\$46,789	
	Walls - Plaster/Drywall	3rd Floor	33,296	SF	6	\$147,601	
	Ceiling - Plaster/Drywall	Basement	16,171	SF	6	\$100,129	
	Doors - Steel Doors incl hw	Basement	10	EA	6	\$3,010	
	Floor - Terrazzo	Basement	16,171	SF	6	\$135,741	
	Lighting - Pendent/Surface	Basement	90	EA	6	\$11,151	
	Walls - Plaster/Drywall	Basement	42,078	SF	6	\$186,532	
	Ceiling - Plaster/Drywall	Small 4th floor corridor leading to main gym and gym storage rooms	126	SF	6	\$780	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Doors - Wood Doors include hw	Small 4th floor corridor leading to main gym and gym storage rooms	1	EA	5	\$1,174	Large hole in door
	Doors - Wood Doors include hw	Small 4th floor corridor leading to main gym and gym storage rooms	1	EA	6	\$301	
	Floor - Wood	Small 4th floor corridor leading to main gym and gym storage rooms	126	SF	6	\$888	
	Lighting - Chandelier, Incandescent	Small 4th floor corridor leading to main gym and gym storage rooms	2	EA	4	\$2,113	Incandescent fixture
	Walls - Plaster/Drywall	Small 4th floor corridor leading to main gym and gym storage rooms	819	SF	6	\$3,631	
Safety							
	Camera Viewing Station	Entire Building / 1st Floor	4	EA	6	\$2,730	Main entrance, principal office, rm304, MDF/IDF rm
	Security Cameras	Entire Building	31	EA	6	\$6,015	
	Security Cameras	Entire Building	2	EA	5	\$1,375	Old generation - Not working properly
	Security Cameras	Entire Building	7	EA	6	\$1,358	
Stairs							
	Ceiling - Plaster/Drywall	Door 9	286	SF	6	\$2,094	
	Floor - Concrete	Door 9	226	SF	6	\$120	
	Handrails	Door 9	152	LF	6	\$1,317	
	Lighting - Pendent/Surface	Door 9	6	EA	4	\$3,244	T12 lighting
	Stairs - Concrete	Door 9	76	LF	6	\$630	
	Walls - Plaster/Drywall	Door 9	1,656	SF	6	\$4,570	
	Ceiling - Plaster/Drywall	Stairwell in maintenance corridor	118	SF	6	\$864	
	Floor - Terrazzo	Stairwell in maintenance corridor	20	SF	6	\$168	
	Handrails	Stairwell in maintenance corridor	40	LF	6	\$347	
	Lighting - Lay-in	Stairwell in maintenance corridor	2	EA	7	\$0	
	Stairs - Concrete	Stairwell in maintenance corridor	19	LF	6	\$158	
	Walls - Plaster/Drywall	Stairwell in maintenance corridor	1,013	SF	6	\$2,796	
Vertical Conveyance							
	Elevator - Freight Elevator	1st Floor	1	EA	6	\$19,238	
	Elevator - Hydraulic Elevator	Entire Building	1	EA	6	\$19,238	

Building Interior Subtotal: \$1,655,636

Total Building Cost \$27,138,737

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	4	EA	6	\$4,375	
	Civil/ Drainage - Site Manhole	Entire Site	28	EA	6	\$41,797	2-Wood Covers
Fencing							
	Fencing - New Standard Ornamental	Entire Site	1,100	LF	7	\$0	
	Fencing - New Standard Ornamental	Entire Site	25	LF	5	\$3,560	Sections of fence leaning at north side of parking lot
Landscape							
	Benches	Entire Site	2	EA	6	\$860	
	Landscape - Grass	Entire Site	10,790	SF	7	\$0	
	Landscape - Hardscape- Concrete	Entire Site	3,020	SF	5	\$33,124	Main Entrance 3 - Majority of concrete cracked, chipped with missing and sinking areas throughout / Vegetation growing throughout / SE corner of site around steel coal door - Cracked with missing pieces
	Landscape - Hardscape- Concrete	Entire Site	4,025	SF	7	\$0	
	Parkway trees	Entire Site	46	EA	6	\$30,362	
	Retaining Wall - Concrete	Entire Site	95	SF	5	\$5,081	East adjacent to perimeter sidewalk - Majority of wall cracked, chipped with large gaps throughout
	Retaining Wall - Concrete	Entire Site	16	SF	7	\$0	Entrance 11-South
Parking Lot							
	Surface - Asphalt	NE	1,000	SF	5	\$5,906	Several areas cracking, chipped with a hole around catch basin cover plate / Missing and loose pieces at entry driveway / Vegetation growing throughout
	Surface - Asphalt	NE	32,180	SF	7	\$0	
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	85	LF	5	\$4,911	Main Entrance 5/6, 9 - Several areas cracked, chipped with missing and sinking areas
	Sidewalks - Internal Walks	Entire Site	830	LF	7	\$0	
	Sidewalks - Perimeter Sidewalks	Entire Site	14,365	SF	7	\$0	
	Sidewalks - Perimeter Sidewalks	Entire Site	1,200	SF	5	\$11,463	Entrances 4, 5/6, 7 - Areas cracked, chipped with missing and sinking pieces, vegetation / SE corner of site - Cracked, chipped with missing and loose pieces
Signage							
	Flag Pole - Building Mounted Flag Pole	Entire Site	1	EA	6	\$828	Location: Main Entrance 3-West
	Flag Pole - Flag Pole	Entire Site	1	EA	6	\$1,657	Location: Main Entrance 3-West
	Marquee - Free Standing Back Lighted	Entire Site	1	EA	6	\$0	Location: Main Entrance 3-West

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	Signage						
	Monument - Building Mounted Cut Letter Sign	Entire Site	2	EA	6	\$0	Location: main entrance 5/6 and entrance 3

Site Subtotal:

\$143,924

Total Site Cost

\$143,924

Campus Total ^{2 3}

\$27,282,661

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Art Room	1st Floor	112B	B12B	215	0	0	0	40	20	40	N	N	N
Art Room	Art Room	3rd Floor	333	233	1,015	0	1	12	228	60	40	Y	N	N
Auditorium	Auditorium	3rd Floor	306	206	2,632	0	0	10	480	240	40	N	N	N
Autoshop	Autoshop	1st Floor	109	B11	2,925	0	0	34	310	68	40	Y	Y	N
Band Room	Band Room	4th Floor	424	324	2,798	0	0	8	114	30	40	N	Y	N
Carpentry	Carpentry	1st Floor	112	B12	2,761	0	0	50	136	78	40	N	N	N
Computer Lab	Computer Lab	1st Floor	112C	B12C	657	0	23	46	136	78	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	214	114	761	0	32	130	132	40	40	Y	N	N
Computer Lab	Regular Classroom	3rd Floor	314	214	980	1	10	30	228	60	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	316	216	980	1	10	30	228	60	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	318	218	980	1	10	30	228	60	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	320	220	2,799	1	30	120	520	260	40	N	N	N
Computer Lab	Computer Lab	4th Floor	408	308	1,573	8	27	70	228	60	40	N	N	Y
Computer Lab	Regular Classroom	4th Floor	436	336	896	2	10	27	266	70	40	Y	Y	N
Computer Lab	Regular Classroom	4th Floor	438	338	896	2	10	27	266	70	40	Y	Y	N
Computer Lab	Regular Classroom	4th Floor	440	340	896	2	10	27	266	70	40	Y	Y	N
Laboratory/Shop	Laboratory/Shop	1st Floor	113	B13	857	0	1	8	48	15	40	N	N	N
Music Room	Music Room	4th Floor	425	325	2,259	0	0	12	432	90	40	N	Y	N
Office	Choral Room	1st Floor	103	B03	571	0	6	13	81	18	40	Y	Y	N
Office	Regular Classroom	2nd Floor	222	122	445	0	5	15	81	24	40	N	N	N
Office	Regular Classroom	2nd Floor	230	130	763	1	1	8	54	18	40	N	Y	N
Other Instructional Use	Regular Classroom	2nd Floor	231	131	1,618	3	16	43	260	60	40	Y	Y	Y
Other Instructional Use	Regular Classroom	2nd Floor	235	135	854	3	0	13	81	24	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	101	B01	2,239	0	0	24	392	126	40	Y	Y	N
Regular Classroom	Carpentry	1st Floor	112A	B12A	583	0	1	8	136	78	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	115	B15	857	1	1	8	48	15	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	117	B17	594	0	1	8	48	15	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	119	B19	547	0	0	8	48	15	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	121	224	475	1	6	8	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	203	103	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	205	105	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	207	107	680	0	6	12	160	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	209	109	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	211	111	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	213	113	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	215	115	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	217	117	686	1	5	20	135	40	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	2nd Floor	218	118	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	219	119	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	220	120	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	221	121	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	224	124	498	0	4	20	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	225	125	515	0	7	18	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	226	126	441	0	4	20	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	227	127	515	0	7	18	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	228	128	532	1	4	20	81	24	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	304	204	916	6	7	26	64	16	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	207	913	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	309	209	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	311	211	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	313	213	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	215	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	317	217	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	319	219	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	321	221	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	323	223	1,546	1	12	38	380	100	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	325	225	906	0	0	8	228	60	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	327	227	868	1	1	12	138	35	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	329	229	868	1	1	12	138	35	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	330	230	913	0	0	14	81	21	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	332	232	1,462	0	0	18	228	60	40	Y	N	Y
Regular Classroom	Multi Purpose Room	3rd Floor	334	234	1,206	0	0	14	304	80	40	Y	N	N
Regular Classroom	Science	4th Floor	401	301	474	0	0	5	114	30	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	411	310	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	413	313	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	415	315	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	416	316	1,053	0	1	10	280	140	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	417	317	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	418	318	980	0	0	10	228	60	40	N	Y	Y
Regular Classroom	Regular Classroom	4th Floor	419	319	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	420	320	980	0	1	10	228	60	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	421	321	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	423	323	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	429	337	906	0	0	8	228	60	40	Y	Y	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	4th Floor	431	331	868	1	1	12	138	35	40	Y	Y	N
Regular Classroom	Regular Classroom	4th Floor	433	333	868	1	1	12	138	35	40	Y	Y	N
Science	Science	3rd Floor	301	201	1,155	0	0	72	266	70	40	N	N	N
Science	Science	3rd Floor	303	205	1,155	0	0	72	266	70	40	N	N	N
Science	Regular Classroom	3rd Floor	305	205	1,142	1	1	26	266	70	40	N	N	N
Science	Science	4th Floor	403	303	988	1	16	36	228	60	40	N	Y	N
Science	Science	4th Floor	405	305	988	1	6	66	228	60	40	N	Y	N
Science	Science	4th Floor	407	307	879	0	0	12	190	50	40	N	N	N
Science	Science	4th Floor	409	309	879	0	0	12	190	50	40	N	N	N
Special Program	Art Room	3rd Floor	331	233	1,445	0	0	14	266	70	40	Y	N	N
Store Room	Art Room	1st Floor	102	B02	1,908	0	0	28	270	40	40	Y	N	N
Store Room	Laboratory/Shop	1st Floor	105	B05	1,706	0	4	24	316	96	40	Y	N	N
Store Room	Regular Classroom	1st Floor	107		1,257	0	16	48	221	67	40	Y	N	N
Store Room	Regular Classroom	2nd Floor	223	123	686	0	0	16	107	32	40	N	N	N
Store Room	Regular Classroom	4th Floor	410	310	781	0	0	10	152	40	40	N	N	N
Weight	Multi Purpose Room	1st Floor	120	228	1,449	1	0	15	0	0	40	N	N	N