

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Linked Addition-Arts Building C	1975	2	85,174	\$3,887,427
Linked Addition-Athletic Building B	1975	2	93,727	\$3,481,033
Main - Building A	1975	3	251,542	\$8,414,742
SITE				\$2,306,215
Campus Total			430,443	\$18,089,417

Building: Linked Addition-Arts Building C

Category: Building Exterior

oup Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
trance						
Entrance Control - Audio and Video	#1a N	1	EA	5	\$1,567	
Exterior Doors - Exterior FRP Door	#1a N	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#1b_Exit N	2	EΑ	6	\$1,263	
Exterior Doors - Exterior FRP Door	#1c_Exit N	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#2.1_Exit W	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#2.2_Exit W	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#2.3_Exit W	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#2a_Exit S	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#2b S	2	EA	6	\$1,263	
Exterior Doors - Exterior FRP Door	#2c_Exit S	2	EA	6	\$1,263	
Exterior Doors - Exterior Steel Door	#3 Roof	2	EA	6	\$961	
Exterior Doors - Side lite	#1a N	2	EA	6	\$627	
Exterior Doors - Side lite	#1b_Exit N	2	EA	6	\$627	
Exterior Doors - Side lite	#1c_Exit N	2	EA	6	\$627	
Exterior Doors - Side lite	#2a_Exit S	2	EA	6	\$627	
Exterior Doors - Side lite	#2b S	2	EA	6	\$627	
Exterior Doors - Side lite	#2c_Exit S	2	EA	6	\$627	
Exterior Doors - Transom Lite	#1a N	2	EΑ	6	\$627	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entran	ce						
	Exterior Doors - Transom Lite	#1b_Exit N	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#1c_Exit N	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#2a_Exit S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#2b S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#2c_Exit S	2	EA	6	\$627	
Founda	ation						
	Foundation - Concrete	Entire Building	968	LF	7	\$0	Reported seepage adjcent to pump rm. LL2 (8 LF)
	Superstructure - Steel	Entire Building	85,174	SF	7	\$0	
Lightin	g						
	Exterior Lighting - Wall Mounted	Entire Building	24	EA	6	\$6,930	
Roof S	ystem						
	Chimney - Metal Flue	Entire Building	207	LF	6	\$32,736	
	Coping - Metal	Entire Building / Bridge	246	LF	6	\$7,901	
	Downspouts - Interior Downspouts	Entire Building	735	LF	6	\$24,426	
	Downspouts - Interior Downspouts	Entire Building / Bridge	40	LF	6	\$1,329	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	44,508	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Entire Building	44,508	SF	5	\$1,050,803	blisters and bubbles
	Roof - Asphalt Gravel Ballast	Entire Building / Bridge	3,658	SF	5	\$98,603	blisters and bubbles
Walls							
	Exterior Walls - Brick	Entire Building	4,214	SF	6	\$28,322	loose mortar/ Open joints
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building / Penthouse	6,144	SF	5	\$39,888	rusting
Windo	ws						
	Clerestory - Glass Single-Pane	Entire Building	4,220	SF	5	\$179,228	Sealant/ Gaskets
	Curtain wall - Glazed Single Pane	Entire Building	6,838	SF	5	\$304,595	Sealant/ Gaskets
	Windows - Casement Aluminum	Entire Building	702	SF	5	\$25,207	Sealant/ Gaskets/ weather stripping

Building Exterior Subtotal:

\$1,821,382

Building: Linked Addition-Arts Building C

Category: Electrical System

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Emergency System					
Automatic Transfer Switch	Electrical Room	2	EA	6	\$816
Emergency A/C Power - Auditoium and Aisle Lighting	Entire Building / 1st Floor	9,875	SF	6	\$5,225

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerger	ncy System						
	Emergency A/C Power - Corridors and Stairs	Entire Building	17,125	SF	6	\$5,143	
	Emergency A/C Power - Students Toilets	Entire Building	2,250	SF	6	\$837	
	Emergency Battery Packs - Auditoium and Aisle Lighting	Basement	4	EA	6	\$810	
	Emergency Generator- Outdoor- Natural Gas - 201 - 250 KW	Site West	1	EA	6	\$21,488	
	Exit Signs - Auditoium	Entire Building / 1st Floor	11	EA	6	\$1,647	
	Exit Signs - Corridors and Stairs	Entire Building	19	EA	6	\$2,845	
	Security System - CCTV	Entire Building	85,175	SF	6	\$25,578	
	Security System - Intrusion Detection	Entire Building	85,175	SF	6	\$21,924	
ain Sei	rvice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	2	EA	6	\$17,323	
	PA System	Entire Building	85,174	SF	6	\$28,014	
ower D	istribution						
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	Emergency fuse pamel
	Lighting and Power Panels - Above 100 A	Entire Building	7	EA	6	\$3,479	
	Lighting and Power Panels - Above 100 A	Entire Building	8	EA	6	\$3,976	
	Lighting and Power Panels - Above 100 A	Entire Building / Mechanical Room	1	EA	4	\$6,578	
	Main Distribution Panels - 400 - 600 amp	Entire Building	3	EA	6	\$1,583	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	3	EA	6	\$2,191	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	4	EA	6	\$5,060	
						_	

Electrical System Subtotal:

\$157,737

Building: Linked Addition-Arts Building C

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire A	arm						
	Fire Alarm Panel	Entire Building / Electrical Room	1	EA	6	\$6,406	
	Fire Alarm Strobe Lights	Entire Building	85,174	SF	6	\$30,450	
	Fire Alarm_System	Entire Building	85,174	SF	6	\$41,412	
	Fire Pump Controller	Entire Building / Mechanical Room	1	EA	6	\$1,823	
Pump	Room Assembly						
	Fire Pump - 25-50 hp	Mechanical Room	1	EA	6	\$1,558	
	Jockey Pump	Mechanical Room	1	EA	6	\$758	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Safty System

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments	
Sprinkler System						
Sprinkler Heads	Entire Building	85,174	SF	7	\$0	
Sprinkler Piping	Entire Building	85,174	SF	6	\$15,834	
Wet Sprinkler System	Entire Building	85,174	SF	6	\$21,924	

Safty System Subtotal: \$120,163

Building: Linked Addition-Arts Building C

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Han	dling Systems						
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	serves auditorium
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating & DX Cooling w/ Remote Mounted Compressor - 11 - 20 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating & DX Cooling w/ Remote Mounted Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating & DX Cooling w/ Remote Mounted Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	
Heating	Devices						
	Fin Tube - Electric	Entire Building	80	LF	6	\$755	
	Unit Heater - Electric	Mechanical Room	1	EA	6	\$278	
Temper	rature Control						
	DDC System	Entire Building	85,174	SF	6	\$48,720	control software is located in main building
	Thermostats - DDC	Entire Building	48	EA	6	\$0	
	Thermostats - DDC	Entire Building	2	EA	4	\$1,638	
Ventilat	tion						
	Exhaust Fans- Indoor - Greater than 8000 CFM	Roof / 1st Floor	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	9	EA	6	\$5,332	
YOUNG	S HS	Page 4 of 102					Assessment Date: 9/14/15



211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Mechanical System

Group Item - Type	Location	Quantity Unit Rank Cost Comments	
Ventilation			
Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	9 EA 6 \$5,332	

Mechanical System Subtotal: \$87,771

Building: Linked Addition-Arts Building C

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Wa	ter						
	Electric Heater - Less than 20 KW	Mechanical Room	1	EA	6	\$682	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	85,174	SF	6	\$17,052	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	85,174	SF	6	\$20,706	
	Domestic Piping-Cold Water Risers	Entire Building	85,174	SF	6	\$15,834	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	85,174	SF	6	\$13,398	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	85,174	SF	6	\$15,834	
	Domestic Piping-Hot Water Return Lines	Entire Building	85,174	SF	6	\$12,180	
	Domestic Piping-Hot Water Return Risers	Entire Building	85,174	SF	6	\$12,180	
	Sanitary Piping	Entire Building	85,174	SF	6	\$77,951	
	Storm Piping	Entire Building	85,174	SF	6	\$74,297	
	Vent Piping	Entire Building	85,174	SF	6	\$57,245	
Pumps							
	Pumps - Domestic Booster Pump-Simplex	Entire Building / Mechanical Room	1	EA	6	\$1,446	
	Pumps - Sump-Simplex	Entire Building / 1st Floor	1	EA	6	\$745	
	Pumps - Sump-Simplex	Entire Building / Mechanical Room	1	EA	6	\$745	

Plumbing System Subtotal: \$320,295

Building: Linked Addition-Arts Building C

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #175 (Art Room)						
Casework	1st Floor	60	LF	6	\$1,515	
Ceiling - Lay-in	1st Floor	856	SF	6	\$2,571	
Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
Floor - Tile	1st Floor	6	SF	5	\$27	missing tiles

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

_	ory. Classicollis	Lasation	0	Heli	Daw!	01	Commonto
	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #175 (Art Room)						
	Floor - Tile/Sheet	1st Floor	851	SF	6	\$852	
	Lighting - Lay-in	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Storage/ Closet	1st Floor	87	SF	6	\$631	
	Walls - Concrete Block	1st Floor	773	SF	6	\$2,266	
	Walls - Metal Panel	1st Floor	258	SF	6	\$1,926	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classro	oom #177 (Art Room)						
	Casework	1st Floor	100	LF	6	\$2,525	
	Ceiling - Lay-in	1st Floor	1,322	SF	6	\$3,970	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Wood	1st Floor	1,322	SF	6	\$9,320	
	Instructional Surface	1st Floor	12	LF	6	\$404	
	Lighting - Lay-in	1st Floor	23	EA	7	\$0	
	Lighting - Lay-in	1st Floor	1	EA	6	\$119	cover missing
	Marker Board	1st Floor	12	LF	7	\$0	, and the second
	Storage/ Closet	1st Floor	227	SF	6		177A- shared with Rm 178
	Walls - Concrete Block	1st Floor	677	SF	6	\$1,985	
	Walls - Metal Panel	1st Floor	677	SF	6	\$5,054	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classro	oom #178 (Computer Lab)						
	Ceiling - Lay-in	1st Floor	1,466	SF	6	\$4,402	
	Chalk Board	1st Floor	4	LF	4	\$367	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,466	SF	6	\$3,207	
	Lighting - Lay-in	1st Floor	30	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	743	SF	6	\$2,178	
	Walls - Metal Panel	1st Floor	743	SF	6	\$5,546	
Classro	oom #179 (Art Room)						
	Casework	1st Floor	35	LF	6	\$884	
	Ceiling - Lay-in	1st Floor	1,300	SF	6	\$3,904	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,300	SF	6	\$1,301	
	Instructional Surface	1st Floor	12	LF	6	\$404	
	Kiln	1st Floor	2	EA	6	\$4,642	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	pom #179 (Art Room)	Location	Qualitity	Ullit	ivalik	CUSI	Comments
CIASSIC	Lighting - Lay-in	1st Floor	27	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Concrete Block	1st Floor	450	SF	6	\$1,319	
	Walls - Metal Panel	1st Floor	580	SF	6	\$4,329	
	Work Sink	1st Floor	2	EA	6	\$758	
		13111001	2	LA	O	Ψ130	
Classro	oom #181 (Art Room)						
	Casework	1st Floor	40	LF	6	\$1,010	
	Ceiling - Lay-in	1st Floor	1,420	SF	6	\$4,264	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,419	SF	6	\$3,105	
	Floor - Tile	1st Floor	1	SF	5	\$6	damaged
	Instructional Surface	1st Floor	12	LF	6	\$404	
	Lighting - Lay-in	1st Floor	18	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Storage/ Closet	1st Floor	86	SF	6	\$624	
	Walls - Concrete Block	1st Floor	450	SF	6	\$1,319	
	Walls - Metal Panel	1st Floor	580	SF	6	\$4,329	
	Work Sink	1st Floor	3	EA	6	\$1,137	
Classro	oom #184 (Dance Room)						
	Ceiling - Lay-in	1st Floor	2,114	SF	6	\$6,348	
	Ceiling - Lay-in	1st Floor	6	SF	6	\$25	water damaged
	Doors - Steel Doors incl hw	1st Floor	2	EΑ	6	\$602	
	Floor - Terrazzo	1st Floor	36	SF	6	\$79	
	Floor - Wood	1st Floor	36	SF	6	\$254	
	Lighting - Lay-in	1st Floor	23	EΑ	7	\$0	
	Lighting - Lay-in	1st Floor	2	EΑ	6	\$238	covers missing
	Marker Board	1st Floor	16	LF	7	\$0	
	Storage/ Closet	1st Floor	188	SF	6	\$1,363	
	Wall Mirrors	1st Floor	10	EΑ	6	\$0	
	Walls - Concrete Block	1st Floor	1,540	SF	6	\$4,515	
	Weight/ Fitness Room Floor Matting	1st Floor	2,098	SF	6	\$7,260	
	Work Sink	1st Floor	1	EA	6	\$379	
Classro	oom #188 (Music Room)						
	Ceiling - Exposed	1st Floor	1,073	SF	6	\$1,596	
	Doors - Side-lite	1st Floor	80	SF	6	\$1,337	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
						-	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Classroom #188 (Music Room) Floor - Tile		Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Floor - Tile	_						- 2.56	
Lighting - Pendent/Surface		· · · · · · · · · · · · · · · · · · ·	1st Floor	1,073	SF	5	\$4,818	old
Marker Board 1st Floor		Lighting - Pendent/Surface						
Ceiling - Lay-in			1st Floor		LF	7	\$0	
Ceiling - Lay-in		Walls - Concrete Block		1,243	SF	6	\$3,644	
Ceiling - Lay-in	Classro	oom #190 (Music Room)						
Doors - Steel Doors incl hw 1st Floor			1st Floor	1,490	SF	6	\$4,474	Room sq footage includes the 2 practice booths 190C & 190D (Office 190E recorded separately)
Floor - Tile		Ceiling - Lay-in	1st Floor	8	SF	5	\$64	missing tiles
Lighting - Lay-in		Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
Sound Panels		Floor - Tile	1st Floor	1,498	SF	6	\$3,277	
Sound System		Lighting - Lay-in	1st Floor	22	EA	7	\$0	
Storage Closet 1st Floor 450 5F 6 \$3,263 190A, 190B, 190F Walls - Concrete Block 1st Floor 1st Floor 7 5F 5 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418 \$4,418		Sound Panels	1st Floor	6	EA	6	\$24	acoustic curtains
Walls - Concrete Block 1st Floor 1,507 SF 6 \$4,418 Classroom #191 (Music Room) Ceiling - Lay-in 1st Floor 7 SF 5 \$56 water damaged Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048 Chalk Board 1st Floor 4 LF 4 \$367 Doors - Steel Doors incl hw 1st Floor 689 SF 6 \$301 Floor - Tile/Sheet 1st Floor 689 SF 6 \$600 Lighting - Lay-in 1st Floor 17 EA 7 \$0 Walls - Concrete Block 1st Floor 1,160 SF 6 \$3,301 Cliging - Lay-in 1st Floor 1,109 SF 6 \$3,330 Colling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Marker Board 1st Floor 1,109 SF 6 \$3,330 Lighting - Lay-in 1st Floor 2 EA 6 \$2		Sound System	1st Floor	1	EA	6	\$1,442	
Caling - Lay-in		Storage/ Closet	1st Floor	450	SF	6	\$3,263	190A, 190B, 190F
Ceiling - Lay-in 1st Floor 7 SF 5 \$56 water damaged Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048 Chalk Board 1st Floor 4 LF 4 \$367 Doors - Steel Doors incl hw 1st Floor 1 EA 6 \$301 Floor - Tile/Sheet 1st Floor 17 EA 7 \$0 Lighting - Lay-in 1st Floor 12 LF 7 \$0 Marker Board 1st Floor 12 LF 7 \$0 Walls - Concrete Block 1st Floor 1,160 SF 6 \$3,301 Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 1,109 SF 6 \$3,330 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 2 EA 7 \$0 Marker Board		Walls - Concrete Block	1st Floor	1,507	SF	6	\$4,418	
Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048 Chalk Board 1st Floor 4 LF 4 \$367 Doors - Steel Doors incl hw 1st Floor 1 EA 6 \$301 Floor - Tile/Sheet 1st Floor 689 SF 6 \$301 Lighting - Lay-in 1st Floor 17 EA 7 \$0 Marker Board 1st Floor 1,160 SF 6 \$3,401 Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 1,109 SF 6 \$602 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 1,28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor	Classro	oom #191 (Music Room)						
Chalk Board 1st Floor 4 LF 4 \$367 Doors - Steel Doors incl hw 1st Floor 1 EA 6 \$301 Floor - Tile/Sheet 1st Floor 689 SF 6 \$690 Lighting - Lay-in 1st Floor 17 EA 7 \$0 Marker Board 1st Floor 1,160 SF 6 \$3,401 Classroom #196 (Choral Room) Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 1,109 SF 6 \$2,426 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 2 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579		Ceiling - Lay-in	1st Floor	7	SF	5	\$56	water damaged
Doors - Steel Doors incl hw		Ceiling - Lay-in	1st Floor	682	SF	6	\$2,048	
Floor - Tile/Sheet 1st Floor 689 SF 6 \$690 Lighting - Lay-in 1st Floor 17 EA 7 \$0 Marker Board 1st Floor 12 LF 7 \$0 Walls - Concrete Block 1st Floor 1,160 \$F 6 \$3,401 Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Floor - Tile 1st Floor 1,109 SF 6 \$3,330 Lighting - Lay-in 1st Floor 2 EA 6 \$602 Marker Board 1st Floor 28 EA 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Ceiling - Lay-in 1st Floor 682 SF 6 \$5,579		Chalk Board	1st Floor	4	LF	4	\$367	
Lighting - Lay-in 1st Floor 17 EA 7 \$0 Marker Board 1st Floor 12 LF 7 \$0 Walls - Concrete Block 1st Floor 1,160 SF 6 \$3,401 Celling - Lay-in Ploor - Tile 1st Floor 1,109 SF 6 \$3,330 Floor - Tile 1st Floor 2 EA 6 \$602 Lighting - Lay-in 1st Floor 1,109 SF 6 \$2,426 Lighting - Board 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 84 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
Marker Board 1st Floor 12 LF 7 \$0 Walls - Concrete Block 1st Floor 1,160 SF 6 \$3,401 Calisasroom #196 (Choral Room) Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Floor - Tile/Sheet	1st Floor	689	SF	6	\$690	
Walls - Concrete Block 1st Floor 1,160 SF 6 \$3,401 Classroom #196 (Choral Room) Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Lighting - Lay-in	1st Floor	17	EA	7	\$0	
Classroom #196 (Choral Room) Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) 5 6 \$2,048		Marker Board	1st Floor	12	LF	7	\$0	
Ceiling - Lay-in 1st Floor 1,109 SF 6 \$3,330 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Walls - Concrete Block	1st Floor	1,160	SF	6	\$3,401	
Doors - Steel Doors incl hw	Classro	oom #196 (Choral Room)						
Floor - Tile 1st Floor 1,109 SF 6 \$2,426 Lighting - Lay-in 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Ceiling - Lay-in	1st Floor	1,109	SF	6	\$3,330	
Lighting - Lay-in 1st Floor 28 EA 7 \$0 Marker Board 1st Floor 6 LF 7 \$0 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
Marker Board 1st Floor 6 LF 7 90 Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Floor - Tile	1st Floor	1,109	SF	6	\$2,426	
Risers 1st Floor 84 LF 6 \$1,891 Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Lighting - Lay-in	1st Floor	28	EA	7	\$0	
Walls - Concrete Block 1st Floor 1,903 SF 6 \$5,579 Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Marker Board	1st Floor	6	LF	7	\$0	
Classroom #197 (Music Room) Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Risers	1st Floor	84	LF	6	\$1,891	
Ceiling - Lay-in 1st Floor 682 SF 6 \$2,048		Walls - Concrete Block	1st Floor	1,903	SF	6	\$5,579	
	Classro	oom #197 (Music Room)						
Doors - Steel Doors incl hw 1st Floor 1 EA 6 \$301		Ceiling - Lay-in	1st Floor	682	SF	6	\$2,048	
		Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

m - Type #197 (Music Room) or - Tile hting - Lay-in rker Board alls - Concrete Block #198 (Band Room) ling - Lay-in ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor	Quantity 682 17 6 1,492 2,441 4 2,441 48 48	SF EA LF SF SF EA SF	6 7 7 6	\$1,492 \$0 \$0 \$4,374 \$7,330 \$1,204	
or - Tile hting - Lay-in rker Board ills - Concrete Block #198 (Band Room) ling - Lay-in ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor	17 6 1,492 2,441 4 2,441 48	EA LF SF SF EA	7 7 6 6	\$0 \$0 \$4,374 \$7,330	
rker Board #198 (Band Room) ling - Lay-in ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor	2,441 4 2,441 48	LF SF SF EA	7 6 6 6	\$0 \$4,374 \$7,330	
#198 (Band Room) ling - Lay-in ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework inting - Lay-in rker Board ers	1st Floor 1st Floor 1st Floor 1st Floor 1st Floor 1st Floor	2,441 4 2,441 48	SF SF EA	6 6	\$4,374 \$7,330	
#198 (Band Room) ling - Lay-in ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor 1st Floor 1st Floor 1st Floor 1st Floor	2,441 4 2,441 48	SF EA	6	\$7,330	
ling - Lay-in ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor 1st Floor 1st Floor 1st Floor	4 2,441 48	EA	6		
ors - Steel Doors incl hw or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor 1st Floor 1st Floor 1st Floor	4 2,441 48	EA	6		
or - Tile/Sheet trument Storage Casework hting - Lay-in rker Board ers	1st Floor 1st Floor 1st Floor	2,441 48			\$1,204	
trument Storage Casework hting - Lay-in rker Board ers	1st Floor 1st Floor	48	SF			
nting - Lay-in rker Board ers	1st Floor			6	\$2,443	
rker Board ers		10	LF	6	\$0	inside the storage closet
ers	1st Floor	40	EA	7	\$0	
		6	LF	7	\$0	
mana/ Olasat	1st Floor	69	LF	6	\$1,553	
rage/ Closet	1st Floor	118	SF	6	\$856	2' of water stains
dent Lockers - Two Tiers	1st Floor	6	EΑ	6	\$279	
ills - Concrete Block	1st Floor	2,814	SF	6	\$8,249	
ork Sink	1st Floor	1	EA	6	\$379	
#275 (Regular Classroom)						
sework	2nd Floor	6	LF	6	\$152	
ling - Lay-in	2nd Floor	879	SF	6	\$2,640	
ors - Steel Doors incl hw	2nd Floor	1	EΑ	6	\$301	
or - Tile	2nd Floor	879	SF	6	\$1,923	
hting - Lay-in	2nd Floor	18	EΑ	7	\$0	
rker Board	2nd Floor	24	LF	7	\$0	
ills - Metal Panel	2nd Floor	594	SF	6	\$4,434	
#277 (Computer Lab)						
sework	2nd Floor	6	LF	6	\$152	
ling - Lay-in	2nd Floor	1,032	SF	6	\$3,099	
ors - Steel Doors incl hw	2nd Floor	1	EΑ	6	\$301	
or - Tile/Sheet	2nd Floor	1,032	SF	6	\$1,033	
hting - Lay-in	2nd Floor	21	EA	7	\$0	
rker Board	2nd Floor	16	LF	7	\$0	
ills - Metal Panel	2nd Floor	944	SF	6	\$7,047	
#278 (Other Instructional Use)						
sework	2nd Floor	6	LF	6	\$152	
ling - Lay-in	2nd Floor	1,335	SF	6	\$4,009	
all or ### seli on on his seli on his selli on his seli on his sel	Is - Concrete Block It k Sink 275 (Regular Classroom) ework ing - Lay-in rs - Steel Doors incl hw or - Tile ting - Lay-in ker Board Is - Metal Panel 277 (Computer Lab) ework ing - Lay-in rs - Steel Doors incl hw or - Tile/Sheet ting - Lay-in ker Board Is - Metal Panel 278 (Other Instructional Use)	Is - Concrete Block It k Sink Ist Floor 275 (Regular Classroom) ework Ing - Lay-in Irs - Steel Doors incl hw Irr - Tile	Is - Concrete Block 1st Floor 2,814 Is k Sink 1st Floor 1 275 (Regular Classroom) Eework 2nd Floor 6 ing - Lay-in 2nd Floor 879 irs - Steel Doors incl hw 2nd Floor 1 ir - Tile 2nd Floor 879 iting - Lay-in 2nd Floor 24 is - Metal Panel 2nd Floor 594 277 (Computer Lab) Eework 2nd Floor 6 ing - Lay-in 2nd Floor 1 irs - Steel Doors incl hw 2nd Floor 1 ir - Tile/Sheet 2nd Floor 1 irg - Lay-in 2nd Floor 1 ier - Steel Doors incl hw 2nd Floor 1 ir - Tile/Sheet 2nd Floor 1 is - Metal Panel 2nd Floor 94 ker Board 2nd Floor 94 is - Metal Panel 2nd Floor 6 6 (Metal Panel) 2nd Floor 6 6 (Metal Panel) 2nd Floor 6 6 (Metal Panel) 2nd Floor 6	Is - Concrete Block 1st Floor 2,814 SF It k Sink 1st Floor 1 EA 275 (Regular Classroom) V ework 2nd Floor 6 LF ing - Lay-in 2nd Floor 879 SF rs - Steel Doors incl hw 2nd Floor 879 SF ting - Lay-in 2nd Floor 18 EA ker Board 2nd Floor 24 LF Is - Metal Panel 2nd Floor 594 SF 277 (Computer Lab) 2nd Floor 6 LF ework 2nd Floor 6 LF ing - Lay-in 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF rs - Steel Doors incl hw 2nd Floor 1,032 SF right - Steel Doors incl hw 2nd Floor 1,032 SF	S - Concrete Block	Is - Concrete Block 1st Floor 2,814 SF 6 \$8,249 Is K Sink 1st Floor 1 EA 6 \$379 275 (Regular Classroom) SF 6 \$152 ework 2nd Floor 879 SF 6 \$2,640 ing - Lay-in 2nd Floor 1 EA 6 \$301 ir - Tile 2nd Floor 879 SF 6 \$1,923 string - Lay-in 2nd Floor 18 EA 7 \$0 ser Board 2nd Floor 18 EA 7 \$0 ser Heal Panel 2nd Floor 18 EA 7 \$0 ser Board 2nd Floor 594 SF 6 \$1,434 277 (Computer Lab) 2nd Floor 1,032 SF 6 \$3,099 ing - Lay-in 2nd Floor 1,032 SF 6 \$3,009 is - Steel Doors incl hw 2nd Floor 1,032 SF 6 \$3,009 <tr< td=""></tr<>

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

	ltem Time	Location	Ouant!te	l lmit	Donk	Cost	Comments
•	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classre	pom #278 (Other Instructional Use)	O. J. Flans		Ε.Δ		#004	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,335	SF	6	\$1,336	
	Lighting - Lay-in	2nd Floor	27	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	7	\$0	
	Storage/ Closet	2nd Floor	65	SF	6		display window
	Walls - Concrete Block	2nd Floor	448	SF	6	\$1,313	
	Walls - Metal Panel	2nd Floor	596	SF	6	\$4,449	
Classr	oom #279 (Computer Lab)						
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	1,167	SF	6	\$3,505	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,167	SF	6	\$2,553	
	Lighting - Lay-in	2nd Floor	24	EA	7	\$0	
	Marker Board	2nd Floor	18	LF	7	\$0	
	Storage/ Closet	2nd Floor	130	SF	6	\$943	
	Walls - Concrete Block	2nd Floor	398	SF	6	\$1,167	
	Walls - Metal Panel	2nd Floor	596	SF	6	\$4,449	
	Wireless System	2nd Floor	1	EA	6	\$372	
Classr	oom #281 (Store Room)						
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	879	SF	6	\$2,640	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	879	SF	6	\$1,923	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	594	SF	6	\$4,434	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classr	oom #282 (Regular Classroom)						
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	879	SF	6	\$2,640	
	Ceiling - Lay-in	2nd Floor	1	SF	5	\$8	water stains on tile
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	879	SF	6	\$880	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	247	LF	7	\$0	
	Storage/ Closet	2nd Floor	137	SF	6	\$993	vault

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	oom #282 (Regular Classroom)	200 0000	quantity	J	·······	- 0000	
J.4001	Walls - Metal Panel	2nd Floor	594	SF	6	\$4,434	
	Work Sink	2nd Floor	1	EA	6	\$379	
					-	****	
Classro	oom #290 (Physical Education Room)						
	Ceiling - Lay-in	2nd Floor	2,176	SF	6	\$6,535	
	Ceiling - Lay-in	2nd Floor	10	SF	5		water damaged
	Doors - Steel Doors incl hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	2,186	SF	6	\$4,783	
	Lighting - Lay-in	2nd Floor	30	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	460	SF	6	\$1,348	
	Walls - Metal Panel	2nd Floor	475	SF	6	\$3,546	
Classro	oom #291 (Regular Classroom)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	1,388	SF	6	\$4,168	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	1,388	SF	6	\$3,037	
	Lighting - Lay-in	2nd Floor	27	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Storage/ Closet	2nd Floor	405	SF	6	\$2,936	Rm 291A
	Student Lockers - One Tier	2nd Floor	12	EA	6	\$1,114	
	Walls - Concrete Block	2nd Floor	298	SF	6	\$874	
	Walls - Metal Panel	2nd Floor	980	SF	6	\$7,315	
	Work Sink	2nd Floor	3	EA	6	\$1,137	
Classro	oom #292 (Regular Classroom)						
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	879	SF	6	\$2,640	
	Chalk Board	2nd Floor	6	LF	4	\$551	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	879	SF	6	\$880	
	Lighting - Lay-in	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	1,279	SF	6	\$9,547	
Classro	oom #293 (Regular Classroom)						
	Casework	2nd Floor	5	LF	6	\$126	
	Ceiling - Lay-in	2nd Floor	569	SF	6	\$1,709	
	Ceiling - Lay-in	2nd Floor	569	SF	6	\$1,709	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

_	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	oom #293 (Regular Classroom)						
	Chalk Board	2nd Floor	16	LF	4	\$1,469	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	569	SF	6	\$1,245	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	498	SF	6	\$1,460	
	Walls - Metal Panel	2nd Floor	894	SF	6	\$6,673	
Classro	oom #294 (Regular Classroom)						
	Casework	2nd Floor	48	LF	6	\$1,212	
	Ceiling - Lay-in	2nd Floor	1,218	SF	6	\$3,658	
	Ceiling - Lay-in	2nd Floor	5	SF	5	\$40	water damaged
	Chalk Board	2nd Floor	8	LF	4	\$734	•
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,218	SF	6	\$1,219	
	Lighting - Lay-in	2nd Floor	24	EΑ	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	743	SF	6	\$2,178	
	Walls - Metal Panel	2nd Floor	498	SF	6	\$3,717	
	Work Sink	2nd Floor	1	EA	6	\$379	
Classro	oom #295 (Regular Classroom)						
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	1,436	SF	6	\$4,312	
	Doors - Steel Doors incl hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile	2nd Floor	1,436	SF	6	\$3,142	
	Lighting - Lay-in	2nd Floor	22	EA	7	\$0	
	Marker Board	2nd Floor	32	LF	7	\$0	
	Storage/ Closet	2nd Floor	127	SF	5	\$2,049	Rm 295A- 3' crack in CMU & 2' stain on ceiling tiles
	Walls - Concrete Block	2nd Floor	1,221	SF	6	\$3,579	
Classro	oom #297 (Regular Classroom)						
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	730	SF	6	\$2,192	
	Ceiling - Lay-in	2nd Floor	3	SF	5	\$24	water stains
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	733	SF	6	\$734	
	Lighting - Lay-in	2nd Floor	16	EA	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #297 (Regular Classroom)						
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	296	SF	6	\$868	
	Walls - Metal Panel	2nd Floor	248	SF	6	\$1,851	
Classro	oom #298 (Regular Classroom)						
	Casework	2nd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	2nd Floor	604	SF	6	\$1,814	
	Ceiling - Lay-in	2nd Floor	4	SF	5	\$32	water damage
	Doors - Steel Doors incl hw	2nd Floor	1	EΑ	6	\$301	
	Floor - Tile	2nd Floor	604	SF	6	\$1,321	
	Lighting - Lay-in	2nd Floor	13	EΑ	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	492	SF	6	\$1,442	
	Walls - Metal Panel	2nd Floor	248	SF	6	\$1,851	

Classrooms Subtotal: \$361,810

Building: Linked Addition-Arts Building C

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
nistrative Suites/Offices						
Ceiling - Lay-in	1st Flr- Copy Rm (behind Stage)	54	SF	6	\$162	
Doors - Side-lite	1st FIr- Copy Rm (behind Stage)	10	SF	6	\$167	
Doors - Steel Doors incl hw	1st FIr- Copy Rm (behind Stage)	1	EA	6	\$301	
Floor - Terrazzo	1st FIr- Copy Rm (behind Stage)	54	SF	6	\$118	
Lighting - Lay-in	1st FIr- Copy Rm (behind Stage)	2	EA	7	\$0	cans
Lighting - Pendent/Surface	1st FIr- Copy Rm (behind Stage)	1	EA	7	\$0	
Power Distribution	1st FIr- Copy Rm (behind Stage)	4	EA	6	\$8,500	
Walls - Concrete Block	1st FIr- Copy Rm (behind Stage)	240	SF	6	\$704	
Ceiling - Plaster/Drywall	Rm 176- Ticket Booth	72	SF	6	\$249	
Doors - Steel Doors incl hw	Rm 176- Ticket Booth	1	EA	6	\$301	
Floor - Tile	Rm 176- Ticket Booth	72	SF	6	\$158	
Lighting - Lay-in	Rm 176- Ticket Booth	2	EA	7	\$0	
Power Distribution	Rm 176- Ticket Booth	2	EA	6	\$4,250	
Walls - Plaster/Drywall	Rm 176- Ticket Booth	72	SF	6	\$199	
Ceiling - Lay-in	Rm 179B- Office	283	SF	6	\$850	
Doors - Side-lite	Rm 179B- Office	20	SF	6	\$334	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

3roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Doors - Steel Doors incl hw	Rm 179B- Office	1	EA	6	\$301	
	Doors - Transom Window	Rm 179B- Office	9	SF	6	\$152	
	Floor - Concrete Epoxy/ Painted	Rm 179B- Office	283	SF	6	\$150	
	Lighting - Lay-in	Rm 179B- Office	6	EA	7	\$0	
	Power Distribution	Rm 179B- Office	6	EA	6	\$12,749	
	Walls - Concrete Block	Rm 179B- Office	384	SF	6	\$1,126	
	Walls - Metal Panel	Rm 179B- Office	385	SF	6	\$2,874	
	Ceiling - Lay-in	Rm 186A- Music Office	153	SF	6	\$459	
	Doors - Steel Doors incl hw	Rm 186A- Music Office	1	EA	6	\$301	
	Floor - Tile	Rm 186A- Music Office	153	SF	6	\$335	
	Lighting - Lay-in	Rm 186A- Music Office	2	EA	6	\$238	
	Power Distribution	Rm 186A- Music Office	8	EA	6	\$16,999	
	Walls - Concrete Block	Rm 186A- Music Office	404	SF	6	\$1,184	
	Ceiling - Lay-in	Rm 186A- Theater Director Office	138	SF	6	\$414	
	Doors - Side-lite	Rm 186A- Theater Director Office	132	SF	6	\$2,207	
	Doors - Steel Doors incl hw	Rm 186A- Theater Director Office	1	EA	6	\$301	
	Floor - Tile	Rm 186A- Theater Director Office	138	SF	6	\$302	
	Lighting - Pendent/Surface	Rm 186A- Theater Director Office	2	EA	7	\$0	
	Power Distribution	Rm 186A- Theater Director Office	6	EA	6	\$12,749	
	Walls - Concrete Block	Rm 186A- Theater Director Office	385	SF	6	\$1,129	
	Ceiling - Lay-in	Rm 190E- Guitar Office	89	SF	6	\$267	
	Doors - Side-lite	Rm 190E- Guitar Office	6	SF	6	\$100	
	Doors - Steel Doors incl hw	Rm 190E- Guitar Office	1	EA	6	\$301	
	Floor - Carpet	Rm 190E- Guitar Office	89	SF	6	\$190	
	Lighting - Lay-in	Rm 190E- Guitar Office	2	EA	7	\$0	
	Power Distribution	Rm 190E- Guitar Office	2	EA	6	\$4,250	
	Walls - Concrete Block	Rm 190E- Guitar Office	300	SF	6	\$879	
	Ceiling - Lay-in	Rm 192- Piano Teacher Office	255	SF	6	\$766	
	Doors - Steel Doors incl hw	Rm 192- Piano Teacher Office	1	EA	6	\$301	
	Floor - Carpet	Rm 192- Piano Teacher Office	255	SF	6	\$543	
	Lighting - Lay-in	Rm 192- Piano Teacher Office	6	EA	7	\$0	
	Power Distribution	Rm 192- Piano Teacher Office	6	EA	6	\$12,749	
	Walls - Concrete Block	Rm 192- Piano Teacher Office	750	SF	6	\$2,199	
	Ceiling - Lay-in	Rm 198B- Music Teacher Office	127	SF	6	\$381	
	Doors - Side-lite	Rm 198B- Music Teacher Office	4	SF	6	\$67	
	Doors - Steel Doors incl hw	Rm 198B- Music Teacher Office	1	EA	6	\$301	
	Floor - Carpet	Rm 198B- Music Teacher Office	127	SF	5	\$652	old & worn

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	Lighting - Lay-in	Rm 198B- Music Teacher Office	4	EA	6	\$476	
	Power Distribution	Rm 198B- Music Teacher Office	4	EA	6	\$8,500	
	Walls - Metal Panel	Rm 198B- Music Teacher Office	368	SF	6	\$2,747	
	Ceiling - Lay-in	Rm 276- Asst Principal	492	SF	6	\$1,477	
	Doors - Steel Doors incl hw	Rm 276- Asst Principal	2	EA	6	\$602	
	Floor - Tile	Rm 276- Asst Principal	492	SF	6	\$1,076	
	Lighting - Lay-in	Rm 276- Asst Principal	10	EA	7	\$0	
	Power Distribution	Rm 276- Asst Principal	14	EA	7	\$0	
	Walls - Concrete Block	Rm 276- Asst Principal	792	SF	6	\$2,322	
	Ceiling - Lay-in	Rm 279A- Copy Room/Business Dept Office	137	SF	6	\$411	
	Doors - Side-lite	Rm 279A- Copy Room/Business Dept Office	36	SF	6	\$602	
	Doors - Steel Doors incl hw	Rm 279A- Copy Room/Business Dept Office	2	EA	6	\$602	
	Floor - Tile/Sheet	Rm 279A- Copy Room/Business Dept Office	137	SF	6	\$137	
	Lighting - Lay-in	Rm 279A- Copy Room/Business Dept Office	2	EA	7	\$0	
	Power Distribution	Rm 279A- Copy Room/Business Dept Office	10	EA	6	\$21,249	
	Walls - Concrete Block	Rm 279A- Copy Room/Business Dept Office	479	SF	6	\$1,404	
	Ceiling - Lay-in	Rm 280- Counselor Office	1	SF	5	\$8	water stain
	Ceiling - Lay-in	Rm 280- Counselor Office	241	SF	6	\$724	
	Doors - Steel Doors incl hw	Rm 280- Counselor Office	1	EA	6	\$301	
	Floor - Tile	Rm 280- Counselor Office	241	SF	6	\$527	
	Lighting - Lay-in	Rm 280- Counselor Office	6	EA	7	\$0	
	Power Distribution	Rm 280- Counselor Office	14	EA	6	\$29,748	
	Walls - Concrete Block	Rm 280- Counselor Office	562	SF	6	\$1,648	
	Ceiling - Lay-in	Rm 281A- Office inside the storage vault	2	SF	5	\$16	water damage
	Ceiling - Lay-in	Rm 281A- Office inside the storage vault	137	SF	6	\$411	
	Doors - Steel Doors incl hw	Rm 281A- Office inside the storage vault	1	EA	6	\$301	Vault door
	Floor - Carpet	Rm 281A- Office inside the storage vault	137	SF	6	\$292	
	Lighting - Lay-in	Rm 281A- Office inside the storage vault	2	EA	7	\$0	
	Power Distribution	Rm 281A- Office inside the storage vault	6	EA	6	\$12,749	
	Walls - Concrete Block	Rm 281A- Office inside the storage vault	477	SF	6	\$1,398	
	Ceiling - Lay-in	Rm 284- Theater Control Room	576	SF	6	\$1,730	
	Doors - Steel Doors incl hw	Rm 284- Theater Control Room	2	EA	6	\$602	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Floor - Tile	Rm 284- Theater Control Room	25	SF	5	\$144	needs subfloor & tile replaced
	Floor - Tile	Rm 284- Theater Control Room	551	SF	6	\$1,206	
	Lighting - Lay-in	Rm 284- Theater Control Room	4	EA	7	\$0	
	Power Distribution	Rm 284- Theater Control Room	12	EA	6	\$25,499	
	Walls - Concrete Block	Rm 284- Theater Control Room	880	SF	6	\$2,580	
	Ceiling - Lay-in	Rm 288- Math office	1	SF	5	\$8	water stains
	Ceiling - Lay-in	Rm 288- Math office	732	SF	6	\$2,198	
	Doors - Side-lite	Rm 288- Math office	99	SF	6	\$1,655	
	Doors - Steel Doors incl hw	Rm 288- Math office	1	EA	6	\$301	
	Floor - Tile	Rm 288- Math office	732	SF	6	\$1,602	
	Lighting - Lay-in	Rm 288- Math office	13	EA	7	\$0	
	Power Distribution	Rm 288- Math office	12	EA	6	\$25,499	
	Walls - Concrete Block	Rm 288- Math office	873	SF	6	\$2,559	
Auditor	ium & Theater						
	Ceiling - Exposed	Rm 199, First floor	8,717	SF	6	\$12,964	ceiling was black & there was not enough light to see if any issues were present
	Doors - Steel Doors incl hw	Rm 199, First floor	20	EA	6	\$6,020	
	Floor - Carpet	Rm 199, First floor	6,156	SF	6	\$13,117	
	Floor - Terrazzo	Rm 199, First floor	2,561	SF	6	\$5,603	
	Lighting - Pendent/Surface	Rm 199, First floor	30	EA	7	\$0	spot lights (very dark in auditorium due to type of lights)
	Main Floor Seating	Rm 199, First floor	1,085	EA	6	\$188,700	g
	Sound System	Rm 199, First floor	1	EA	6	\$10,721	
	Stage	Rm 199, First floor	1,879	SF	6	\$10,855	
	Stage Curtain	Rm 199, First floor	10	EA	6	\$0	
	Stage Lift	Rm 199, First floor	1	EA	7	\$0	new unit being installed that day
	Stage Lighting System	Rm 199, First floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	Rm 199, First floor	20	LF	6	\$235	
	Storage/ Closet	Rm 199, First floor	30	SF	6	\$218	
	Walls - Masonry	Rm 199, First floor	13,966	SF	6	\$43,937	
Locker/	Shower Room						
	Accessories	Men's dressing room next to theater	318	SF	6	\$1,246	
	Ceiling - Lay-In	Men's dressing room next to theater	318	SF	6	\$955	
	Doors - Steel Doors incl hw	Men's dressing room next to theater	2	EA	6	\$602	
	Floor Drain	Men's dressing room next to theater	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's dressing room next to theater	76	SF	6	\$161	
	Floor - Tile/Sheet	Men's dressing room next to theater	242	SF	6	\$242	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Locker/	Shower Room						
	Lavatory	Men's dressing room next to theater	1	EA	6	\$320	
	Lighting - Lay-in	Men's dressing room next to theater	9	EA	7	\$0	
	Lighting - Wall Mounted	Men's dressing room next to theater	1	EA	5	\$169	open clock box, exposed wires
	Partitions	Men's dressing room next to theater	1	EA	6	\$297	
	Showers	Men's dressing room next to theater	1	EA	6	\$311	
	Walls - Concrete Block	Men's dressing room next to theater	514	SF	6	\$1,507	
	Water Closet	Men's dressing room next to theater	1	EA	6	\$336	
	Ceiling - Plaster/ Drywall	Rm 184A- Dance Locker Rm	218	SF	6	\$754	
	Doors - Steel Doors incl hw	Rm 184A- Dance Locker Rm	1	EA	6	\$301	
	Floor - Tile/Sheet	Rm 184A- Dance Locker Rm	218	SF	6	\$218	
	Lighting - Pendent/Surface	Rm 184A- Dance Locker Rm	3	EA	7	\$0	
	Student Lockers - Two Tier	Rm 184A- Dance Locker Rm	36	EA	6	\$1,671	
	Walls - Concrete Block	Rm 184A- Dance Locker Rm	720	SF	6	\$2,111	
	Benches, ped mounted	Rm 290A- Boys Yoga Locker Rm	6	LF	6	\$653	
	Ceiling - Lay-In	Rm 290A- Boys Yoga Locker Rm	98	SF	6	\$294	
	Doors - Steel Doors incl hw	Rm 290A- Boys Yoga Locker Rm	2	EA	6	\$602	
	Floor - Tile/Sheet	Rm 290A- Boys Yoga Locker Rm	98	SF	6	\$98	
	Lighting - Lay-in	Rm 290A- Boys Yoga Locker Rm	2	EA	7	\$0	
	Student Lockers - Two Tier	Rm 290A- Boys Yoga Locker Rm	12	EA	6	\$557	
	Walls - Plaster/Drywall	Rm 290A- Boys Yoga Locker Rm	420	SF	6	\$1,159	
	Benches, ped mounted	Rm 290B- Girls Yoga Locker Rm	6	LF	6	\$653	
	Ceiling - Lay-In	Rm 290B- Girls Yoga Locker Rm	170	SF	6	\$511	
	Doors - Steel Doors incl hw	Rm 290B- Girls Yoga Locker Rm	1	EΑ	6	\$301	
	Floor - Tile/Sheet	Rm 290B- Girls Yoga Locker Rm	170	SF	6	\$170	
	Lighting - Lay-in	Rm 290B- Girls Yoga Locker Rm	4	EΑ	7	\$0	
	Student Lockers - Two Tier	Rm 290B- Girls Yoga Locker Rm	42	EΑ	6	\$1,950	
	Walls - Plaster/Drywall	Rm 290B- Girls Yoga Locker Rm	720	SF	6	\$1,987	
	Accessories	Women's dressing room next to theater	318	SF	6	\$1,246	
	Ceiling - Lay-In	Women's dressing room next to theater	318	SF	6	\$955	
	Doors - Steel Doors incl hw	Women's dressing room next to theater	2	EA	6	\$602	
	Floor Drain	Women's dressing room next to theater	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's dressing room next to theater	76	SF	6	\$161	
	Floor - Tile/Sheet	Women's dressing room next to theater	242	SF	6	\$242	
	Lavatory	Women's dressing room next to theater	1	EA	6	\$320	
	Lighting - Lay-in	Women's dressing room next to theater	12	EA	7	\$0	cans
	Partitions	Women's dressing room next to theater	1	EA	6	\$297	
	Showers	Women's dressing room next to theater	1	EA	6	\$311	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

	Location	Quantity	Unit	Rank	Cost	Comments
Drywall	Women's dressing room next to theater	514	SF	6	\$1,419	
	Women's dressing room next to theater	1	EA	6	\$336	
Room						
ed	Rm 186- Stage Prop Creation Rm	1,177	SF	6	\$1,750	
	Rm 186- Stage Prop Creation Rm	3	SF	5	\$24	Water damage
	Rm 186- Stage Prop Creation Rm	145	SF	6	\$435	
ors incl hw	Rm 186- Stage Prop Creation Rm	1	EA	6	\$301	
et .	Rm 186- Stage Prop Creation Rm	1,325	SF	4	\$12,809	missing tile
l .	Rm 186- Stage Prop Creation Rm	3	EA	6	\$357	
ent/Surface	Rm 186- Stage Prop Creation Rm	27	EA	6	\$3,345	No lens covers
	Rm 186- Stage Prop Creation Rm	107	SF	6	\$776	
e Block	Rm 186- Stage Prop Creation Rm	3,766	SF	6	\$11,040	
oms						
	1st Floor	40	SF	6	\$287	
vice Rooms	1st Floor	150	SF	6	\$1,075	elec closets
	1st Floor	45	SF	6	\$322	
vice Rooms	2nd Floor	293	SF	6	\$2,099	Rm 288A- At&T IBT Rm, 279C, Elec Closet
vice Rooms	2nd Floor	19	SF	5	\$306	Rm 278D- water damage
	2nd Floor	115	SF	6	\$824	Rm 296
	2nd Floor	480	SF	6	\$3,439	storage vault by Rm 282
ums	Basement	1,879	SF	6	\$11,635	under stage
vice Rooms	Basement	704	SF	6	\$5,044	-
	Basement	904	SF	6	\$6,477	
vice Rooms	Sub- Basement (below basement)	119	SF	5	\$1,920	There was either a pipe that was rusting out, or the wall was leaking.
vice Rooms	Sub- Basement (below basement)	607	SF	6	\$4,349	Ç
	Sub- Basement (below basement)	55	SF	6	\$394	
	2nd Flr-Theater Make-up Area	6	SF	5	\$48	water damaged
	2nd FIr-Theater Make-up Area	182	SF	6	\$547	
ors incl hw	2nd Flr-Theater Make-up Area	1	EA	6	\$301	
	2nd FIr-Theater Make-up Area	188	SF	6	\$411	
l.	2nd FIr-Theater Make-up Area	4	EA	7	\$0	
Mounted	2nd FIr-Theater Make-up Area	5	EA	7	\$0	
e Block	2nd FIr-Theater Make-up Area	550	SF	6	\$1,612	
	2nd Flr-Theater Make-up Area	2	EA	6	\$758	
	Drywall Room ed pors incl hw et ent/Surface e Block poms vice Rooms vice Booms vice Rooms vice Rooms vice Rooms vice Rooms vice Rooms vice Rooms	Drywall Women's dressing room next to theater Women's dressing room next to theater Women's dressing room next to theater Room and Rm 186- Stage Prop Creation Rm Rm 186- Stage Prop Cre	Drywall Women's dressing room next to theater 514	Drywall Women's dressing room next to theater 514 SF Women's dressing room next to theater 1 EA	Drywall Women's dressing room next to theater 514 SF 6	Drywall Women's dressing room next to theater 514 SF 6 \$1,419

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

_	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Prep Ro						- 0001	
	Ceiling - Lay-in	Rm 180B- Photo Booth	72	SF	6	\$216	
	Doors - Steel Doors incl hw	Rm 180B- Photo Booth	1	EA	6	\$301	
	Floor - Tile	Rm 180B- Photo Booth	72	SF	6	\$158	
	Lighting - Lay-in	Rm 180B- Photo Booth	2	EA	6	\$238	
	Walls - Concrete Block	Rm 180B- Photo Booth	132	SF	6	\$387	
	Ceiling - Lay-in	Rm 188B- Music Practice room	75	SF	6	\$225	
	Doors - Side-lite	Rm 188B- Music Practice room	40	SF	6	\$669	
	Doors - Steel Doors incl hw	Rm 188B- Music Practice room	1	EA	6	\$301	
	Floor - Tile	Rm 188B- Music Practice room	75	SF	5	\$337	old
	Lighting - Lay-in	Rm 188B- Music Practice room	4	EA	7	\$0	cans
	Walls - Concrete Block	Rm 188B- Music Practice room	788	SF	6	\$2,310	
	Ceiling - Lay-in	Rm 193- Piano practice room	304	SF	6	\$913	
	Ceiling - Lay-in	Rm 193- Piano practice room	12	SF	5	\$96	water damaged
	Doors - Steel Doors incl hw	Rm 193- Piano practice room	1	EA	6	\$301	nate: damaged
	Floor - Carpet	Rm 193- Piano practice room	316	SF	5	\$1,622	old
	Lighting - Lay-in	Rm 193- Piano practice room	6	EA	7	\$0	
	Walls - Concrete Block	Rm 193- Piano practice room	788	SF	6	\$2,310	
	Ceiling - Lay-in	Rm 196A -Choral Practice Room	356	SF	6	\$1,069	
	Doors - Side-lite	Rm 196A -Choral Practice Room	184	SF	6	\$3,076	
	Doors - Steel Doors incl hw	Rm 196A -Choral Practice Room	5	EΑ	6	\$1,505	
	Floor - Tile	Rm 196A -Choral Practice Room	356	SF	6	\$779	
	Lighting - Lay-in	Rm 196A -Choral Practice Room	4	EΑ	7	\$0	
	Lighting - Lay-in	Rm 196A -Choral Practice Room	6	EΑ	6		no covers
	Walls - Metal Panel	Rm 196A -Choral Practice Room	729	SF	6	\$5,442	
	Ceiling - Lay-in	Rm 198A -Instrument Practice Room	356	SF	6	\$1,069	
	Doors - Side-lite	Rm 198A -Instrument Practice Room	184	SF	6	\$3,076	
	Doors - Steel Doors incl hw	Rm 198A -Instrument Practice Room	5	EA	6	\$1,505	
	Floor - Tile	Rm 198A -Instrument Practice Room	356	SF	6	\$779	
	Lighting - Lay-in	Rm 198A -Instrument Practice Room	10	EA	7	\$0	
	Walls - Metal Panel	Rm 198A -Instrument Practice Room	729	SF	6	\$5,442	
Restro	om						
	Accessories	1st flr Men's- next to 179	37	SF	6	\$341	
	Ceiling - Plaster/Drywall	1st flr Men's- next to 179	37	SF	6	\$128	
	Doors - Steel Doors incl hw	1st flr Men's- next to 179	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st flr Men's- next to 179	37	SF	6	\$78	
	Hand Dryer	1st flr Men's- next to 179	1	EA	6	\$230	
	Lavatory	1st flr Men's- next to 179	1	EA	6	\$320	
	,		•		-	+0	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Lighting - Wall Mounted	1st flr Men's- next to 179	1	EA	7	\$0	
	Walls - Concrete Block	1st flr Men's- next to 179	192	SF	6	\$563	
	Water Closet	1st flr Men's- next to 179	1	EA	6	\$336	
	Accessories	1st flr- Next to 178	280	SF	6	\$2,583	
	Ceiling - Plaster/Drywall	1st flr- Next to 178	280	SF	6	\$969	
	Floor Drain	1st flr- Next to 178	2	EA	6	\$2,118	
	Floor - Tile	1st flr- Next to 178	86	SF	6	\$188	
	Floor - Tile Ceramic/ Porcelain	1st flr- Next to 178	239	SF	6	\$506	
	Hand Dryer	1st flr- Next to 178	2	EA	6	\$460	
	Lavatory	1st flr- Next to 178	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st flr- Next to 178	5	EA	7	\$0	
	Partitions	1st flr- Next to 178	3	EA	6	\$891	
	Urinals	1st flr- Next to 178	3	EA	6	\$1,008	
	Walls - Concrete Block	1st flr- Next to 178	620	SF	6	\$1,818	
	Water Closet	1st flr- Next to 178	3	EΑ	6	\$1,008	
	Accessories	1st flr- Next to 196	280	SF	6	\$2,583	
	Ceiling - Plaster/Drywall	1st flr- Next to 196	280	SF	6	\$969	
	Floor Drain	1st flr- Next to 196	2	EA	6	\$2,118	
	Floor - Tile	1st flr- Next to 196	70	SF	6	\$153	
	Floor - Tile Ceramic/ Porcelain	1st flr- Next to 196	210	SF	6	\$444	
	Hand Dryer	1st flr- Next to 196	2	EA	6	\$460	
	Lavatory	1st flr- Next to 196	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st flr- Next to 196	5	EA	7	\$0	
	Partitions	1st flr- Next to 196	6	EΑ	6	\$1,782	
	Walls - Concrete Block	1st flr- Next to 196	620	SF	6	\$1,818	
	Water Closet	1st flr- Next to 196	6	EΑ	6	\$2,016	
	Accessories	1st Flr Women's -next to 196	28	SF	6	\$258	
	Ceiling - Plaster/Drywall	1st Flr Women's -next to 196	28	SF	6	\$97	
	Doors - Steel Doors incl hw	1st Flr Women's -next to 196	1	EA	5	\$1,174	rusting
	Floor - Tile Ceramic/ Porcelain	1st Flr Women's -next to 196	28	SF	6	\$59	
	Hand Dryer	1st Flr Women's -next to 196	1	EA	6	\$230	
	Lavatory	1st Flr Women's -next to 196	1	EA	6	\$320	
	Lighting - Wall Mounted	1st Flr Women's -next to 196	1	EA	6	\$124	
	Walls - Concrete Block	1st Flr Women's -next to 196	179	SF	6	\$525	
	Water Closet	1st Flr Women's -next to 196	1	EA	6	\$336	
	Accessories	2nd floor Women's- next to 294	28	SF	6	\$258	Tumbler was missing, so room was not accessible. Rankings are assumed based on surrounding restroom conditions.

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stroo	m						
	Ceiling - Plaster/Drywall	2nd floor Women's- next to 294	28	SF	6	\$97	
	Doors - Steel Doors incl hw	2nd floor Women's- next to 294	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd floor Women's- next to 294	28	SF	6	\$59	
	Lavatory	2nd floor Women's- next to 294	1	EA	6	\$320	
	Lighting - Wall Mounted	2nd floor Women's- next to 294	1	EA	7	\$0	
	Walls - Concrete Block	2nd floor Women's- next to 294	179	SF	6	\$525	
	Water Closet	2nd floor Women's- next to 294	1	EA	6	\$336	
	Accessories	2nd flr Men's- next to 279	152	SF	6	\$1,402	
	Ceiling - Plaster/Drywall	2nd flr Men's- next to 279	148	SF	6	\$512	
	Ceiling - Plaster/Drywall	2nd flr Men's- next to 279	4	SF	5	\$50	efflorescence
	Doors - Steel Doors incl hw	2nd flr Men's- next to 279	2	EA	6	\$602	
	Floor Drain	2nd flr Men's- next to 279	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd flr Men's- next to 279	152	SF	6	\$322	
	Hand Dryer	2nd flr Men's- next to 279	1	EA	6	\$230	
	Lavatory	2nd flr Men's- next to 279	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd flr Men's- next to 279	1	EA	7	\$0	
	Lighting - Wall Mounted	2nd flr Men's- next to 279	1	EA	7	\$0	
	Showers	2nd flr Men's- next to 279	1	EA	6	\$311	
	Walls - Concrete Block	2nd flr Men's- next to 279	400	SF	6	\$1,173	
	Water Closet	2nd flr Men's- next to 279	1	EA	6	\$336	
	Accessories	2nd flr- Next to 278	280	SF	6	\$2,583	
	Ceiling - Plaster/Drywall	2nd flr- Next to 278	280	SF	6	\$969	
	Floor Drain	2nd flr- Next to 278	2	EA	6	\$2,118	
	Floor - Tile	2nd flr- Next to 278	86	SF	6	\$188	
	Floor - Tile Ceramic/ Porcelain	2nd flr- Next to 278	239	SF	6	\$506	
	Hand Dryer	2nd flr- Next to 278	2	EA	6	\$460	
	Lavatory	2nd flr- Next to 278	3	EA	6	\$959	
	Lighting - Lay-in	2nd flr- Next to 278	5	EA	7	\$0	
	Lighting - Lay-in	2nd flr- Next to 278	3	EA	7	\$0	can lights
	Partitions	2nd flr- Next to 278	2	EA	6	\$594	
	Urinals	2nd flr- Next to 278	3	EA	6	\$1,008	
	Walls - Concrete Block	2nd flr- Next to 278	620	SF	6	\$1,818	
	Water Closet	2nd flr- Next to 278	2	EA	6	\$672	
	Accessories	2nd flr- Next to 294	280	SF	6	\$2,583	
	Ceiling - Plaster/Drywall	2nd flr- Next to 294	280	SF	6	\$969	
	Floor Drain	2nd flr- Next to 294	2	EA	6	\$2,118	
	Floor - Tile	2nd flr- Next to 294	5	SF	5	\$29	damaged

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Restro	om					
	Floor - Tile	2nd flr- Next to 294	70	SF	6	\$153
	Floor - Tile Ceramic/ Porcelain	2nd flr- Next to 294	205	SF	6	\$434
	Hand Dryer	2nd flr- Next to 294	2	EA	6	\$460
	Lavatory	2nd flr- Next to 294	3	EA	6	\$959
	Lighting - Lay-in	2nd flr- Next to 294	5	EA	7	\$0
	Partitions	2nd flr- Next to 294	5	EA	6	\$1,485
	Walls - Concrete Block	2nd flr- Next to 294	620	SF	6	\$1,818
	Water Closet	2nd flr- Next to 294	5	EA	6	\$1,680

Rooms (Other Than Classrooms) Subtotal:

\$749,630

Building: Linked Addition-Arts Building C

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor	•						
	Ceiling - Lay-in	1st Floor	6	SF	5	\$54	water damage
	Ceiling - Lay-in	1st Floor	10,617	SF	6	\$31,883	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	
	Drinking Fountains - Single Water Cooler	1st Floor	1	EA	6	\$317	
	Floor - Terrazzo	1st Floor	8,250	SF	6	\$69,251	
	Floor - Tile/Sheet	1st Floor	2,367	SF	6	\$1,286	
	Lighting - Lay-in	1st Floor	171	EA	7	\$0	
	Walls - Concrete Block	1st Floor	11,256	SF	6	\$32,997	
	Walls - Masonry	1st Floor	2,900	SF	6	\$9,123	
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$71	water damaged
	Ceiling - Lay-in	2nd Floor	7,615	SF	6	\$22,868	
	Doors - Steel Doors incl hw	2nd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	2nd Floor	1	EA	6	\$276	
	Drinking Fountains - Single Water Cooler	2nd Floor	2	EA	6	\$633	
	Floor - Tile/Sheet	2nd Floor	50	SF	5	\$288	damaged tiles
	Floor - Tile/Sheet	2nd Floor	7,573	SF	6	\$4,115	
	Lighting - Lay-in	2nd Floor	171	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	11,256	SF	6	\$32,997	
	Walls - Masonry	2nd Floor	2,900	SF	6	\$9,123	
	Ceiling - Exposed	Basement	404	SF	6	\$601	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Floor - Concrete	Basement	404	SF	6	\$214	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Building Interior

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido							
	Lighting - Pendent/Surface	Basement	7	EA	7	\$0	
	Stairs - Concrete Stairs	Basement	7	LF	6	\$58	steps at wood storage room
	Walls - Concrete Block	Basement	1,208	SF	6	\$3,541	
	Ceiling - Exposed	Sub-Basement (area outside of elevator)	150	SF	6	\$223	
	Doors - Steel Doors incl hw	Sub-Basement (area outside of elevator)	1	EA	6	\$301	
	Floor - Concrete	Sub-Basement (area outside of elevator)	150	SF	6	\$79	
	Lighting - Pendent/Surface	Sub-Basement (area outside of elevator)	2	EA	6	\$248	
	Walls - Concrete Block	Sub-Basement (area outside of elevator)	350	SF	6	\$1,026	
Safety							
	Metal Dedector		1	EA	6	\$881	
Stairs							
	Ceiling - Lay-in	North East Stairs (near link)	172	SF	6	\$517	
	Floor - Terrazzo	North East Stairs (near link)	44	SF	6	\$369	
	Handrails	North East Stairs (near link)	64	LF	6	\$555	
	Stairs - Terrazzo	North East Stairs (near link)	26	LF	6	\$241	
	Walls - Masonry	North East Stairs (near link)	520	SF	6	\$1,636	
	Ceiling - Lay-in	North West Stairs	172	SF	6	\$517	
	Floor - Terrazzo	North West Stairs	44	SF	6	\$369	landing
	Handrails	North West Stairs	64	LF	6	\$555	
	Stairs - Terrazzo	North West Stairs	26	LF	6	\$241	
	Walls - Masonry	North West Stairs	520	SF	6	\$1,636	
	Ceiling - Lay-in	South East Stairs	172	SF	6	\$517	
	Floor - Terrazzo	South East Stairs	44	SF	6	\$369	
	Handrails	South East Stairs	64	LF	6	\$555	
	Stairs - Terrazzo	South East Stairs	24	LF	6	\$223	
	Stairs - Terrazzo	South East Stairs	2	LF	5	\$108	damaged
	Walls - Masonry	South East Stairs	520	SF	6	\$1,636	
	Ceiling - Lay-in	South West Stairs	172	SF	6	\$517	
	Floor - Terrazzo	South West Stairs	44	SF	6	\$369	
	Handrails	South West Stairs	64	LF	6	\$555	
	Stairs - Terrazzo	South West Stairs	5	LF	5	\$271	damaged
	Stairs - Terrazzo	South West Stairs	21	LF	6	\$195	
	Walls - Masonry	South West Stairs	520	SF	6	\$1,636	
	Ceiling - Exposed	To basement & sub-basement	150	SF	6	\$223	
	Floor - Concrete	To basement & sub-basement	40	SF	6	\$21	
	Handrails	To basement & sub-basement	36	LF	6	\$312	
	Floor - Concrete	To basement & sub-basement	40	SF	6	\$21	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Arts Building C

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Stairs							
	Lighting - Pendent/Surface	To basement & sub-basement	4	EA	7	\$0	
	Stairs - Concrete	To basement & sub-basement	30	LF	6	\$249	
	Walls - Concrete Block	To basement & sub-basement	1,300	SF	6	\$3,811	
Vertica	al Conveyance						
	Elevator - Hydraulic Elevator		1	EA	6	\$19,238	
	Wheelchair Lift - Platform Lift		1	EA	6	\$6,690	inside Rm 198
	Wheelchair Lift - Platform Lift		1	EA	7	\$0	Brand new unit being installed while I was there

Building Interior Subtotal: \$268,640

Total Building Cost \$3,887,427

Building: Linked Addition-Athletic Building B

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entran	ce						
	Entrance Control - Audio and Video	#1 W	1	EA	5	\$1,567	
	Exterior Doors - Exterior FRP Door	#1 W	6	EA	6	\$3,788	
	Exterior Doors - Exterior FRP Door	#2 E	6	EA	6	\$3,788	
	Exterior Doors - Exterior Stainless Steel Door	#1.1 S	2	EA	6	\$1,092	
	Exterior Doors - Exterior Steel Door	#1.2_Exit S	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.1_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.2_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.3_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.4_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.5_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#2.6_Exit N	2	EA	6	\$961	
	Exterior Doors - Transom Lite	#1 W	6	EA	6	\$1,880	
	Exterior Doors - Transom Lite	#2 E	6	EA	6	\$1,880	
	Power Door Operator and Controls	#1 W	1	EA	6	\$0	
Founda	ation						
	Foundation - Concrete	Entire Building	968	LF	7	\$0	
	Superstructure - Steel	Entire Building	93,727	SF	7	\$0	
Lightin	g						
	Exterior Lighting - Wall Mounted	Entire Building	12	EA	6	\$3,465	
VOLINI	2.110	D 04 -1	(100				A D - 1 - 0/4 4/45

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Building Exterior

Group Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
ighting_							
Roof System							
Chimney - M	Metal Flue	Entire Building	45	LF	6	\$7,116	
Chimney - M	Metal Flue	Entire Building	120	LF	7	\$0	
Coping - Me	etal	Entire Building	970	LF	6	\$31,154	
Coping - Me	etal	Entire Building / Bridge	110	LF	6	\$4,766	
Downspouts	- Interior Downspouts	Entire Building	792	LF	6	\$26,321	
Downspouts	- Interior Downspouts	Entire Building / Bridge	30	LF	6	\$997	
Roof Structu	ire - Steel / Metal Deck/ Concrete Topping	Entire Building	58,564	SF	7	\$0	
Roof Structu	re - Steel / Metal Deck/ Concrete Topping	Entire Building / Bridge	1,824	SF	7	\$0	
Roof - Aspha	alt Gravel Ballast	Entire Building / Bridge	1,824	SF	5	\$43,063	blisters
Roof - Modifi	ied Bitumen	Entire Building	58,564	SF	6	\$551,052	
/alls							
Exterior Wall	ls - Brick	Entire Building	23,300	SF	6	\$156,599	Missing mortar/ Open Joints
Exterior Wall	ls - Prefabricated Metal Panel Wall	Entire Building	5,115	SF	6	\$29,038	
/indows							
Clerestory - 0	Glass Single-Pane	Entire Building	2,660	SF	5	\$112,973	Gaskets
Curtain wall	- Glazed Single Pane	Entire Building	1,086	SF	6	\$12,175	
Lintels - Ste	eel	Entire Building	36	LF	6	\$1,045	
Lintels - Ste	eel	Entire Building / South Entrances	12	LF	5	\$4,056	Rusted/ Warped
'						4 004 545	

Building Exterior Subtotal:

\$1,004,545

Building: Linked Addition-Athletic Building B

Category: Electrical System

Automatic Transfer Switch Electrical Room 2 EA 6 \$816 Emergency A/C Power - Corridors and Stairs Entire Building 7,500 SF 6 \$2,252 Emergency A/C Power - Gym Entire Building 24,816 SF 6 \$9,227 Emergency A/C Power - Students Toilets Entire Building / Entire Site 840 SF 6 \$312 Emergency Battery Packs - Corridors and Stairs Electrical Room / Entire Building 3 EA 6 \$608 Emergency Battery Packs - Pool Electrical Room / Entire Building 4 EA 6 \$810 Exit Signs - Corridors and Stairs Entire Building 18 EA 6 \$2,695	Froup Item	ı - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency A/C Power - Corridors and Stairs Entire Building 7,500 SF 6 \$2,252 Emergency A/C Power - Gym Entire Building 24,816 SF 6 \$9,227 Emergency A/C Power - Students Toilets Entire Building / Entire Site 840 SF 6 \$312 Emergency Battery Packs - Corridors and Stairs Electrical Room / Entire Building 3 EA 6 \$608 Emergency Battery Packs - Pool Exit Signs - Corridors and Stairs Entire Building 18 EA 6 \$2,252	mergency S	System						
Emergency A/C Power - Gym Entire Building 24,816 SF 6 \$9,227 Emergency A/C Power - Students Toilets Entire Building / Entire Site 840 SF 6 \$312 Emergency Battery Packs - Corridors and Stairs Electrical Room / Entire Building 3 EA 6 \$608 Emergency Battery Packs - Pool Exit Signs - Corridors and Stairs Entire Building 18 EA 6 \$2,695	Auto	omatic Transfer Switch	Electrical Room	2	EA	6	\$816	
Emergency A/C Power - Students Toilets Entire Building / Entire Site 840 SF 6 \$312 Emergency Battery Packs - Corridors and Stairs Electrical Room / Entire Building 3 EA 6 \$608 Emergency Battery Packs - Pool Exit Signs - Corridors and Stairs Entire Building 18 EA 6 \$2,695	Eme	ergency A/C Power - Corridors and Stairs	Entire Building	7,500	SF	6	\$2,252	
Emergency Battery Packs - Corridors and Stairs Electrical Room / Entire Building 3 EA 6 \$608 Emergency Battery Packs - Pool Exit Signs - Corridors and Stairs Electrical Room / Entire Building 4 EA 6 \$810 Entire Building 18 EA 6 \$2,695	Eme	ergency A/C Power - Gym	Entire Building	24,816	SF	6	\$9,227	
Emergency Battery Packs - Pool Electrical Room / Entire Building 4 EA 6 \$810 Exit Signs - Corridors and Stairs Entire Building 18 EA 6 \$2,695	Eme	ergency A/C Power - Students Toilets	Entire Building / Entire Site	840	SF	6	\$312	
Exit Signs - Corridors and Stairs Entire Building 18 EA 6 \$2,695	Eme	ergency Battery Packs - Corridors and Stairs	Electrical Room / Entire Building	3	EA	6	\$608	
	Eme	ergency Battery Packs - Pool	Electrical Room / Entire Building	4	EA	6	\$810	
	Exit S	Signs - Corridors and Stairs	Entire Building	18	EA	6	\$2,695	
Exit Signs - Gym Entire Building 8 EA 6 \$1,259	Exit S	Signs - Gym	Entire Building	8	EA	6	\$1,259	
Security System - CCTV Entire Building 93,727 SF 6 \$28,146	Secu	urity System - CCTV	Entire Building	93,727	SF	6	\$28,146	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergen	ncy System						
	Security System - Intrusion Detection	Entire Building	93,727	SF	6	\$24,125	
Main Ser	rvice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	1	EA	6	\$8,662	
	PA System	Entire Building	93,727	SF	6	\$30,827	
Power Di	istribution						
	Lighting and Power Panels - 100 A	1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Electrical Room	1	EA	6	\$299	Emergency fuse poanel
	Lighting and Power Panels - Above 100 A	Entire Building	5	EΑ	6	\$2,485	
	Lighting and Power Panels - Above 100 A	Entire Building	6	EΑ	6	\$2,982	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	1	EA	6	\$528	
	Main Distribution Panels - 400 - 600 amp	Entire Building	2	EA	6	\$1,055	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	2	EA	6	\$1,460	
	Main Distribution Panels - Less than 400 amp	1st Floor	1	EA	6	\$503	
	Transformers - 277/480 - 120/208	Electrical Room	3	EA	6	\$3,795	
	10 4 0 14 4 1					A 400 000	

Electrical System Subtotal:

\$126,068

Building: Linked Addition-Athletic Building B

Category: Safty System

	4 5		.	
	4 [•	*	
	1 EA	6	\$6,406	
Entire Building 93,72	,727 SF	6	\$33,507	
Entire Building 93,72	,727 SF	6	\$45,570	
		•	•	7

Safty System Subtotal: \$85,483

Building: Linked Addition-Athletic Building B

Category: Mechanical System

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems						
Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 10 - 20 tons	Roof	1	EA	5	\$17,658	serves gym area
Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 10 - 20 tons	Roof	1	EA	5	\$17,658	serves pool area

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Mechanical System

Group Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
Roof Top Unit-Multi Zone-Roof Mounted- Gas He w/ Self Contained Compressor - 31 - 45 tons	eating and DX Cooling	Roof	1	EA	5	\$32,040	serves gym area
Roof Top Unit-Multi Zone-Roof Mounted- Gas He w/ Self Contained Compressor - 31 - 45 tons	eating and DX Cooling	Roof	1	EA	5	\$32,040	serves pool area
Roof Top Unit-Multi Zone-Roof Mounted- Gas He w/ Self Contained Compressor - 46 - 60 tons	eating and DX Cooling	Roof	1	EA	5	\$39,774	serves gym area
Roof Top Unit-Single Zone-Roof Mounted- DX Co Contained Compressor - 31 - 45 tons	ooling Only with Self	Roof	1	EA	5	\$32,040	serves gym area
Roof Top Unit-Single Zone-Roof Mounted- DX Co Contained Compressor - 31 - 45 tons	ooling Only with Self	Roof	1	EA	6	\$2,792	serves pool area, provides also dehumidification
Roof Top Unit-Single Zone-Roof Mounted- Gas Hoons	leating Coil - 31 - 45	Roof	1	EA	6	\$2,792	serve gym
Roof Top Unit-Single Zone-Roof Mounted- Gas H tons	leating Coil - 31 - 45	Roof	1	EA	6	\$2,792	serve gym
Heating Devices							
Cabinet Heaters - With Electric Coil		1st Floor	3	EA	5	\$4,758	
Fin Tube - Electric		Entire Building	120	LF	6	\$1,133	
Unit Heater - Electric		Mechanical Room	2	EA	6	\$556	
Temperature Control							
DDC System		Entire Building	93,727	SF	6	\$53,612	control panel is in main building
Thermostats - DDC		Entire Building	1	EA	4	\$819	
Thermostats - DDC		Entire Building	16	EA	6	\$0	
Ventilation							
Exhaust Fans- Roof Mounted - 1501 - 8000 CFM		Entire Building / Roof	3	EA	6	\$1,777	
Exhaust Fans- Roof Mounted - 500 - 1500 CFM		Entire Building / Roof	2	EA	6	\$1,185	
Exhaust Fans- Roof Mounted - Greater than 8000) CFM	Entire Building / Roof	2	EA	6	\$1,185	
Exhaust Fans- Roof Mounted - Less than 500 CF	FM .	Entire Building / Roof	2	EA	6	\$592	
Machanical System Subtatal						\$245 204	_

Mechanical System Subtotal:

\$245,201

Building: Linked Addition-Athletic Building B

Category: Plumbing System

Group Item - Type	Location	Quantity	Unit	Rank	Cost Comments
Hot Water					
Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	2	EA	6	\$620
Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	1	EA	6	\$310

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	93,727	SF	6	\$18,764	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	93,727	SF	6	\$22,785	
	Domestic Piping-Cold Water Risers	Entire Building	93,727	SF	6	\$17,424	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	93,727	SF	6	\$14,743	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	93,727	SF	6	\$17,424	
	Domestic Piping-Hot Water Return Lines	Entire Building	93,727	SF	6	\$13,403	
	Domestic Piping-Hot Water Return Risers	Entire Building	93,727	SF	6	\$13,403	
	Sanitary Piping	Entire Building	93,727	SF	6	\$85,779	
	Storm Piping	Entire Building	93,727	SF	6	\$81,758	
	Vent Piping	Entire Building	93,727	SF	6	\$62,994	
Pool Sy	rstems						
	Pool Drain Piping	1st Floor / Basement	100	LF	6	\$2,863	
	Pool Filtration System including Pump	1st Floor / Mechanical Room	1	EΑ	6	\$12,330	
	Pool Hot Water Heater - Gas Fired	1st Floor / Roof	1	EΑ	6	\$310	
	Pool Supply and Return Piping	1st Floor / Entire Building	100	LF	6	\$4,805	
Pumps							
	Pumps - Sump-Simplex	Mechanical Room	1	EA	6	\$745	
<u> </u>	-in a Occatana Occhetatala					£070 400	

Plumbing System Subtotal:

\$370,460

Building: Linked Addition-Athletic Building B

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comme
Classro	om #154 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	6	SF	4	\$84	water damag
	Ceiling - Lay-in	1st Floor	658	SF	6	\$1,976	Clean
	Doors - Side-lite	1st Floor	215	SF	6	\$3,594	Window wall
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	664	SF	6	\$1,453	
	Lighting - Lay-in	1st Floor	1	EA	5	\$162	Relamp
	Lighting - Lay-in	1st Floor	13	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Walls - Concrete Block	1st Floor	9	SF	5	\$127	Large crack
	Walls - Concrete Block	1st Floor	852	SF	6	\$2,498	Clean

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	om #156 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	664	SF	6	\$1,994	Clean
	Doors - Side-lite	1st Floor	215	SF	6	\$3,594	Window wall
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Floor - Tile	1st Floor	3	SF	5	\$17	
	Floor - Tile	1st Floor	661	SF	6	\$1,446	
	Lighting - Lay-in	1st Floor	4	EA	6	\$476	Relamp
	Lighting - Lay-in	1st Floor	10	EA	7	\$0	
	Marker Board	1st Floor	10	LF	7	\$0	
	Walls - Concrete Block	1st Floor	861	SF	6	\$2,524	

Classrooms Subtotal: \$20,848

Building: Linked Addition-Athletic Building B

oup Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ministrative Suites/Offices						
Ceiling - Lay-in	152 - Coach office	282	SF	6	\$847	
Doors - Steel Doors incl hw	152 - Coach office	2	EΑ	6	\$602	
Floor - Tile	152 - Coach office	282	SF	6	\$617	
Lighting - Lay-in	152 - Coach office	4	EΑ	6	\$476	
Power Distribution	152 - Coach office	4	EΑ	6	\$8,500	
Walls - Concrete Block	152 - Coach office	780	SF	6	\$2,287	
Ceiling - Lay-in	153 - office	204	SF	6	\$613	
Doors - Side-lite	153 - office	46	SF	7	\$0	
Doors - Steel Doors incl hw	153 - office	1	EΑ	6	\$301	
Doors - Store Front	153 - office	1	EΑ	7	\$0	
Floor - Tile Ceramic/ Porcelain	153 - office	204	SF	6	\$432	
Lighting - Lay-in	153 - office	5	EΑ	7	\$0	
Power Distribution	153 - office	6	EΑ	7	\$0	
Walls - Concrete Block	153 - office	463	SF	6	\$1,357	
Ceiling - Lay-in	157 - office	204	SF	6	\$613	
Doors - Side-lite	157 - office	46	SF	7	\$0	
Doors - Steel Doors incl hw	157 - office	1	EΑ	6	\$301	
Doors - Store Front	157 - office	1	EΑ	7	\$0	
Floor - Tile Ceramic/ Porcelain	157 - office	204	SF	6	\$432	
Lighting - Lay-in	157 - office	5	EA	7	\$0	
Power Distribution	157 - office	6	EΑ	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Walls-Concrete Block 157 - office 463 SF 6 \$1,357 Calling - Layvin 158 - Gym office 282 SF 6 \$847 Doors - Steel Doors incl hw 158 - Gym office 22 SF 6 \$807 Ploor - Tille 158 - Gym office 28 SF 6 \$917 Lighting - Layvin 158 - Gym office 4 EA 7 \$0 Power Distribution 158 - Gym office 4 EA 7 \$0 Walls - Concrete Block 158 - Gym office 204 SF 6 \$2287 Celling - Layvin 159 - Aquatics office 40 SF 7 \$0 Doors - Steel Boors incl hw 159 - Aquatics office 46 SF 7 \$0 Doors - Steel Doors incl hw 159 - Aquatics office 46 SF 7 \$0 Floor - Tille Coramic/Porcelain 159 - Aquatics office 5 EA 7 \$0 Floor - Tille Coramic/Porcelain 159 - Aquatics office 6 EA<	Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Calling - Lay-in 158 - Gym office 282 SF 6 \$947 Doors - Steel Doors incl hw 158 - Gym office 2 EA 6 \$6002 Floor - Tile 158 - Gym office 282 SF 6 \$617 Lighting - Lay-in 158 - Gym office 4 EA 7 \$0 Power Distribution 158 - Gym office 780 SF 6 \$2,287 Calling - Lay-in 159 - Agualics office 204 SF 6 \$2,287 Calling - Lay-in 159 - Agualics office 204 SF 6 \$513 Doors - Side-Blue 159 - Agualics office 1 EA 6 \$301 Doors - Stoel Florat 159 - Agualics office 1 EA 7 \$0 Doors - Stoel Florat 159 - Agualics office 1 EA 7 \$0 Floor - Tile Ceramic/ Porcelain 159 - Agualics office 4 EA 7 \$0 Floor - Tille Ceramic/ Porcelain 159 - Agualics office 5 EA 7 \$0 Power Distribution 159 - Agualics office 6 EA 7 \$0 Walls - Concrete Block 159 - Agualics office 6 EA 7 \$0	Adminis	strative Suites/Offices						
Doors - Steel Doors incl hw		Walls - Concrete Block	157 - office	463	SF	6	\$1,357	
Floor - Tile		Ceiling - Lay-in	158 - Gym office	282	SF	6	\$847	
Lighting - Lay-in 158 - Gym office 4 EA 7 \$0 Power Distribution 158 - Gym office 780 SF 6 \$2.287 Celling - Lay-in 159 - Aquatics office 204 SF 6 \$6.32 Doors - Side-Ilte 159 - Aquatics office 204 SF 6 \$6.33 Doors - Steel Doors incl hw 159 - Aquatics office 1 EA 6 \$301 Doors - Steel Doors incl hw 159 - Aquatics office 1 EA 6 \$301 Doors - Steel Doors incl hw 159 - Aquatics office 1 EA 7 \$0 Power Distribution 159 - Aquatics office 5 EA 7 \$0 Power Distribution 159 - Aquatics office 463 SF 6 \$1.357 Calling - Lay-in 171 - Ticket office 463 SF 6 \$2.24 Doors - Steel Doors incl hw 171 - Ticket office 4 EA 6 \$2.34 Poor - Tille 171 - Ticket office 4		Doors - Steel Doors incl hw	158 - Gym office	2	EA	6	\$602	
Power Distribution		Floor - Tile	158 - Gym office	282	SF	6	\$617	
Walls - Concrete Block 158 - Gym office 780 SF 6 \$2,287 Celling - Lay-in 159 - Aquatics office 204 SF 6 \$613 Doors - Side-life 159 - Aquatics office 46 SF 7 \$0 Doors - Side-life 159 - Aquatics office 1 EA 6 \$301 Doors - Side Froit 159 - Aquatics office 1 EA 7 \$0 Floor - Tille Ceramic/ Porcelain 159 - Aquatics office 5 EA 7 \$0 Power Distribution 159 - Aquatics office 6 EA 7 \$0 Power Distribution 159 - Aquatics office 6 EA 7 \$0 Power Distribution 159 - Aquatics office 6 EA 7 \$0 Power Distribution 159 - Aquatics office 6 EA 7 \$0 Vallar - Concrete Block 159 - Aquatics office 6 EA 35 SF 6 \$1,357 Celling - Lay-in 171 - Ticket office 19 EA 6 \$301 Power Distribution 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office		Lighting - Lay-in	158 - Gym office	4	EA	7	\$0	
Ceiling - Lay-in 159 - Aquatics office 204 SF 6 \$613 Doors - Side-Hors 159 - Aquatics office 1 EA 6 \$301 Doors - Steel Doors incl hw 159 - Aquatics office 1 EA 6 \$301 Doors - Store Front 159 - Aquatics office 1 EA 7 \$0 Floor - Tile Ceramic/ Porcelain 159 - Aquatics office 5 EA 7 \$0 Power Distribution 159 - Aquatics office 5 EA 7 \$0 Power Distribution 159 - Aquatics office 463 SF 6 \$1357 Ceiling - Lay-in 171 - Ticket office 463 SF 6 \$1357 Ceiling - Lay-in 171 - Ticket office 98 SF 6 \$234 Doors - Steel Doors incl hw 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 173 - PE Office 215 SF 6 \$360 Power Distribution 173 - PE Office 215 SF 6 \$648		Power Distribution	158 - Gym office	4	EA	7	\$0	
Doors - Side-lite		Walls - Concrete Block	158 - Gym office	780	SF	6	\$2,287	
Doors - Steel Doors incl hw 159 - Aquatics office 1 EA 7 50		Ceiling - Lay-in	159 - Aquatics office	204	SF	6	\$613	
Doors - Store Front 159 - Aquatics office 1 EA 7 \$0		Doors - Side-lite	159 - Aquatics office	46	SF	7	\$0	
Floor - Tile Ceramic/ Porcelain 159 - Aquatics office 204 SF 6 \$432 Lighting - Lay-in 159 - Aquatics office 5 EA 7 \$0 Power Distribution 159 - Aquatics office 6 EA 7 \$0 Power Distribution 159 - Aquatics office 463 SF 6 \$1,357 Ceiling - Lay-in 171 - Ticket office 98 SF 6 \$294 Doors - Steel Doors incl hw 171 - Ticket office 98 SF 6 \$294 Doors - Steel Doors incl hw 171 - Ticket office 98 SF 6 \$294 Lighting - Lay-in 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office 4 EA 6 \$8,500 Walls - Concrete Block 171 - Ticket office 4 EA 6 \$8,500 Walls - Concrete Block 171 - Ticket office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 20 SF 6 \$415 Lighting - Lay-in 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 425 SF 6 \$1,135 Valls - Concrete Block 173 - PE Office 425 SF 6 \$1,135 Ceiling - Lay-in 15t floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 5 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$476 Power Distri		Doors - Steel Doors incl hw	159 - Aquatics office	1	EA	6	\$301	
Lighting - Lay-in 159 - Aquatics office 5 EA 7 \$0 Power Distribution 159 - Aquatics office 6 EA 7 \$0 Walls - Concrete Block 159 - Aquatics office 463 SF 6 \$1,357 Ceiling - Lay-in 171 - Ticket office 98 SF 6 \$2,94 Doors - Steel Doors incl hw 171 - Ticket office 98 SF 6 \$2,94 Lighting - Lay-in 171 - Ticket office 98 SF 6 \$2,94 Lighting - Lay-in 171 - Ticket office 98 SF 6 \$2,94 Lighting - Lay-in 171 - Ticket office 98 SF 6 \$2,14 Lighting - Lay-in 171 - Ticket office 98 SF 6 \$2,14 Lighting - Lay-in 171 - Ticket office 1 EA 6 \$1,19 Power Distribution 171 - Ticket office 4 EA 6 \$8,500 Walls - Concrete Block 171 - Ticket office 388 SF 6 \$1,137 Ceiling - Lay-in 173 - PE Office 2 EA 6 \$8,500 Floor - Carpet 173 - PE Office 2 EA 6 \$6,602 Floor - Carpet 173 - PE Office 2 EA 6 \$6,002 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Tile 173 - PE Office 2 EA 6 \$430 Floor - Tile 173 - PE Office 2 EA 6 \$430 Floor - Tile 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Carpet 173 - PE Office 2 EA 6 \$430 Floor - Tile 173 - PE Office 2 EA 6 \$25,499 Storage/ Closet 173 - PE Office 2 EA 6 \$25,499 Storage/ Closet 173 - PE Office 2 EA 6 \$802 Floor - Tile Sheet 181 floor large office at east 2 EA 6 \$802 Floor - Tile Sheet 181 floor large office at east 2 EA 6 \$802 Floor - Tile Sheet 181 floor large office at east 2 EA 6 \$802 Floor - Tile Sheet 181 floor large office at east 2 EA 6 \$802 Floor - Tile Sheet 181 floor large office at east 2 EA 6 \$802 Floor - Tile Sheet 181 floor large office at east 2 EA 6 \$802		Doors - Store Front	159 - Aquatics office	1	EA	7	\$0	
Power Distribution 159 - Aquatics office 6 EA 7 \$0 Walls - Concrete Block 159 - Aquatics office 483 SF 6 \$1,357 Ceiling - Lay-in 171 - Ticket office 98 SF 6 \$294 Doors - Steel Doors incl hw 171 - Ticket office 1 EA 6 \$301 Floor - Tile 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office 4 EA 6 \$8,500 Walls - Concrete Block 171 - Ticket office 388 SF 6 \$1,137 Ceiling - Lay-in 173 - PE Office 215 SF 6 \$662 Doors - Steel Doors incl hw 173 - PE Office 25 SF 6 \$602 Floor - Carpet 173 - PE Office 20 SF 5 \$40 Paint stain Floor - Tile 173 - PE Office 7 SF 5 \$31 SI Lighting - Lay-in 173 - PE Office 3 EA 7 SO SO Power Distribution 173 - PE Office 20 SF 6 \$145 \$145		Floor - Tile Ceramic/ Porcelain	159 - Aquatics office	204	SF	6	\$432	
Walls - Concrete Block 159 - Aquatics office 463 SF 6 \$1,357 Ceiling - Lay-in 171 - Ticket office 98 SF 6 \$294 Doors - Steel Doors incl hw 171 - Ticket office 1 EA 6 \$301 Floor - Tile 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office 38 SF 6 \$5100 Walls - Concrete Block 171 - Ticket office 38 SF 6 \$8,500 Walls - Concrete Block 171 - Ticket office 38 SF 6 \$8,500 Walls - Concrete Block 171 - Ticket office 38 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 20 SF 5 \$40 Floor - Tille 173 - PE Office 17 SO		Lighting - Lay-in	159 - Aquatics office	5	EA	7	\$0	
Ceiling - Lay-in 171 - Ticket office 98 SF 6 \$294 Doors - Steel Doors incl hw 171 - Ticket office 1 EA 6 \$301 Floor - Tile 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office 4 EA 6 \$8,500 Walls - Concrete Block 171 - Ticket office 388 SF 6 \$1,137 Ceiling - Lay-in 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 2 EA 6 \$602 Floor - Tile 173 - PE Office 7 SF 5 \$40 Floor - Tile 173 - PE Office 3 EA 7 \$0 Floor - Tile 173 - PE Office 3 EA 7 \$0		Power Distribution	159 - Aquatics office	6	EA	7	\$0	
Doors - Steel Doors incl hw 171 - Ticket office 1 EA 6 \$301 Floor - Tile 171 - Ticket office 98 SF 6 \$214 Lighting - Lay-in 171 - Ticket office 1 EA 6 \$119 Power Distribution 171 - Ticket office 1 EA 6 \$85.00 Walls - Concrete Block 171 - Ticket office 388 SF 6 \$\$1,137 Ceiling - Lay-in 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 20 SF 6 \$430 Paint stain Floor - Tile 173 - PE Office 7 SF 5 \$31 Paint stain Floor - Tile 173 - PE Office 3 EA 7 \$0 Paint stain Floor - Tile 173 - PE Office 3 EA 7 \$0 Paint stain Floor - Tile 173 - PE Office 3 EA 7 \$0 Paint stain Floor - Tile 173 - PE Office 3 EA 7 \$0 POWED ISTRIBUTION 173 - PE Office 3 EA 7 \$0 POWED ISTRIBUTION \$15 ON TILE SEA 6 \$145 \$145 ON TILE SEA 6 \$145 \$145 ON TILE SEA 6 \$145 \$145 ON TI		Walls - Concrete Block	159 - Aquatics office	463	SF	6	\$1,357	
Floor - Tile		Ceiling - Lay-in	171 - Ticket office	98	SF	6	\$294	
Lighting - Lay-in 171 - Ticket office 1 EA 6 \$ \$119 Power Distribution 171 - Ticket office 4 EA 6 \$ \$8,500 Walls - Concrete Block 171 - Ticket office 388 SF 6 \$ \$1,137 Ceiling - Lay-in 173 - PE Office 215 SF 6 \$ \$66 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$ \$602 Floor - Carpet 173 - PE Office 2 SF 6 \$ \$40 Pioor - Carpet 173 - PE Office 20 SF 6 \$ \$430 Floor - Tile 173 - PE Office 7 SF 5 \$ \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$ \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$145 Walls - Concrete Block 173 - PE Office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$282 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 4 EA 6 \$476		Doors - Steel Doors incl hw	171 - Ticket office	1	EA	6	\$301	
Power Distribution 171 - Ticket office 4 EA 6 \$8,500 Walls - Concrete Block 171 - Ticket office 388 SF 6 \$1,137 Ceiling - Lay-in 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 6 SF 5 \$40 Paint stain Floor - Tile 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$145 Walls - Lay-in 1st floor large office at east 282 SF 6		Floor - Tile	171 - Ticket office	98	SF	6	\$214	
Walls - Concrete Block 171 - Ticket office 388 SF 6 \$1,137 Ceiling - Lay-in 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 6 SF 5 \$40 Paint stain Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$145 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east		Lighting - Lay-in	171 - Ticket office	1	EA	6	\$119	
Ceiling - Lay-in 173 - PE Office 215 SF 6 \$646 Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 6 SF 5 \$40 Paint stain Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4EA <td< td=""><td></td><td>Power Distribution</td><td>171 - Ticket office</td><td>4</td><td>EA</td><td>6</td><td>\$8,500</td><td></td></td<>		Power Distribution	171 - Ticket office	4	EA	6	\$8,500	
Doors - Steel Doors incl hw 173 - PE Office 2 EA 6 \$602 Floor - Carpet 173 - PE Office 6 SF 5 \$40 Paint stain Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$8282 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4<		Walls - Concrete Block	171 - Ticket office	388	SF	6	\$1,137	
Floor - Carpet 173 - PE Office 6 SF 5 5 \$40 Paint stain Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$602 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Ceiling - Lay-in	173 - PE Office	215	SF	6	\$646	
Floor - Carpet 173 - PE Office 202 SF 6 \$430 Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 282 SF 6 \$602 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Doors - Steel Doors incl hw	173 - PE Office	2	EA	6	\$602	
Floor - Tile 173 - PE Office 7 SF 5 \$31 Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 2 EA 6 \$602 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Floor - Carpet	173 - PE Office	6	SF	5	\$40	Paint stain
Lighting - Lay-in 173 - PE Office 3 EA 7 \$0 Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 2 EA 6 \$602 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Floor - Carpet	173 - PE Office	202	SF	6	\$430	
Power Distribution 173 - PE Office 12 EA 6 \$25,499 Storage/ Closet 173 - PE Office 20 SF 6 \$145 Walls - Concrete Block 173 - PE Office 452 SF 6 \$1,325 Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 2 EA 6 \$602 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Floor - Tile	173 - PE Office	7	SF	5	\$31	
Storage/ Closet173 - PE Office20SF6\$145Walls - Concrete Block173 - PE Office452SF6\$1,325Ceiling - Lay-in1st floor large office at east282SF6\$847Doors - Steel Doors incl hw1st floor large office at east2EA6\$602Floor - Tile/Sheet1st floor large office at east282SF6\$282Lighting - Lay-in1st floor large office at east4EA6\$476Power Distribution1st floor large office at east6EA6\$12,749		Lighting - Lay-in	173 - PE Office	3	EA	7	\$0	
Walls - Concrete Block Ceiling - Lay-in 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 2 EA 6 \$602 Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$847 Doors - Steel Doors incl hw 1st floor large office at east 2 EA 6 \$602 Floor - Tile/Sheet 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Power Distribution	173 - PE Office	12	EA	6	\$25,499	
Ceiling - Lay-in1st floor large office at east282SF6\$847Doors - Steel Doors incl hw1st floor large office at east2EA6\$602Floor - Tile/Sheet1st floor large office at east282SF6\$282Lighting - Lay-in1st floor large office at east4EA6\$476Power Distribution1st floor large office at east6EA6\$12,749		Storage/ Closet	173 - PE Office	20	SF	6	\$145	
Doors - Steel Doors incl hw1st floor large office at east2EA6\$602Floor - Tile/Sheet1st floor large office at east282SF6\$282Lighting - Lay-in1st floor large office at east4EA6\$476Power Distribution1st floor large office at east6EA6\$12,749		Walls - Concrete Block	173 - PE Office	452	SF	6	\$1,325	
Floor - Tile/Sheet 1st floor large office at east 282 SF 6 \$282 Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Ceiling - Lay-in	1st floor large office at east	282	SF	6	\$847	
Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Doors - Steel Doors incl hw	1st floor large office at east	2	EA	6	\$602	
Lighting - Lay-in 1st floor large office at east 4 EA 6 \$476 Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Floor - Tile/Sheet	_	282	SF	6	\$282	
Power Distribution 1st floor large office at east 6 EA 6 \$12,749		Lighting - Lay-in	_	4	EA	6		
			_	6		6		
		Walls - Concrete Block	_	780	SF	6		
Ceiling - Lay-in Rm 050-L Basement Coaches Office 192 SF 6 \$577		Ceiling - Lay-in	_	192	SF	6		

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Doors - Side-lite	Rm 050-L Basement Coaches Office	54	SF	6	\$903	
	Doors - Steel Doors incl hw	Rm 050-L Basement Coaches Office	2	EA	6	\$602	
	Floor - Tile	Rm 050-L Basement Coaches Office	192	SF	6	\$420	
	Lighting - Lay-in	Rm 050-L Basement Coaches Office	4	EA	7	\$0	
	Power Distribution	Rm 050-L Basement Coaches Office	8	EA	6	\$16,999	
	Walls - Concrete Block	Rm 050-L Basement Coaches Office	472	SF	6	\$1,384	
	Ceiling - Lay-in	West gym office	98	SF	6	\$294	
	Doors - Steel Doors incl hw	West gym office	2	EA	6	\$602	
	Floor - Tile	West gym office	98	SF	6	\$214	
	Lighting - Lay-in	West gym office	1	EA	6	\$119	Relamp
	Lighting - Lay-in	West gym office	3	EΑ	7	\$0	
	Power Distribution	West gym office	6	EA	6	\$12,749	
	Walls - Concrete Block	West gym office	388	SF	6	\$1,137	
Clinic							
	Ceiling - Lay-in	Rm 053- Basement Physical Therapy Rm	634	SF	6	\$1,904	
	Ceiling - Lay-in	Rm 053- Basement Physical Therapy Rm	4	SF	5	\$32	water damaged
	Doors - Steel Doors incl hw	Rm 053- Basement Physical Therapy Rm	2	EA	6	\$602	
	Floor - Tile/Sheet	Rm 053- Basement Physical Therapy Rm	638	SF	6	\$639	
	Lighting - Lay-in	Rm 053- Basement Physical Therapy Rm	15	EA	7	\$0	
	Storage/ Closet	Rm 053- Basement Physical Therapy Rm	47	SF	6	\$341	
	Walls - Concrete Block	Rm 053- Basement Physical Therapy Rm	859	SF	6	\$2,518	
€ymna	sia						
	Bleacher Seating	150 - Gym A	550	EA	6	\$15,919	
	Ceiling - Exposed	150 - Gym A	10,980	SF	6	\$16,329	
	Doors - Steel Doors incl hw	150 - Gym A	8	EA	6	\$2,408	
	Floor - Wood	150 - Gym A	10,980	SF	6	\$77,408	
	Lighting - Metal Halide/Sodium Vapor	150 - Gym A	45	EA	6	\$6,017	
	Scoreboards	150 - Gym A	2	EA	6	\$4,489	
	Sound System	150 - Gym A	1	EA	6	\$41,654	
	Storage/ Closet	150 - Gym A	210	SF	6	\$1,523	
	Walls - Concrete Block	150 - Gym A	14,746	SF	6	\$43,228	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymna	sia						
	Bleacher Seating	160 - Gym B	400	EA	6	\$11,577	
	Ceiling - Exposed	160 - Gym B	10,270	SF	6	\$15,274	
	Doors - Steel Doors incl hw	160 - Gym B	8	EA	6	\$2,408	
	Floor - Wood	160 - Gym B	10,270	SF	6	\$72,402	
	Lighting - Metal Halide/Sodium Vapor	160 - Gym B	30	EA	7	\$0	
	Scoreboards	160 - Gym B	2	EA	6	\$4,489	
	Sound System	160 - Gym B	1	EA	6	\$41,654	
	Storage/ Closet	160 - Gym B	186	SF	6	\$1,349	
	Walls - Concrete Block	160 - Gym B	12,986	SF	6	\$38,068	
	Balcony Seating	165 - Gym C	20	EA	6	\$3,478	
	Ceiling - Exposed	165 - Gym C	6,566	SF	6	\$9,765	
	Doors - Steel Doors incl hw	165 - Gym C	8	EA	6	\$2,408	
	Floor - Wood	165 - Gym C	6,566	SF	6	\$46,290	
	Lighting - Metal Halide/Sodium Vapor	165 - Gym C	63	EA	7	\$0	
	Scoreboards	165 - Gym C	2	EA	6	\$4,489	
	Walls - Concrete Block	165 - Gym C	8,140	SF	6	\$23,862	
	Ceiling - Lay-in	Basement- Rm 050 Weight Room	1,655	SF	6	\$4,970	
	Ceiling - Lay-in	Basement- Rm 050 Weight Room	4	SF	5	\$32	water damaged
	Doors - Steel Doors incl hw	Basement- Rm 050 Weight Room	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Basement- Rm 050 Weight Room	265	SF	6	\$140	
	Floor - Weight/ Fitness Room Floor Matting	Basement- Rm 050 Weight Room	1,394	SF	6	\$7,296	
	Lighting - Lay-in	Basement- Rm 050 Weight Room	32	EA	7	\$0	
	Walls - Concrete Block	Basement- Rm 050 Weight Room	1,744	SF	6	\$5,113	
	Walls - Concrete Block	Basement- Rm 050 Weight Room	6	SF	5	\$85	crack in cmu
Locker/	Shower Room						
	Accessories	151 - Boy's pool locker	937	SF	6	\$3,671	
	Benches, ped mounted	151 - Boy's pool locker	30	LF	6	\$3,266	
	Ceiling - Plaster/ Drywall	151 - Boy's pool locker	937	SF	6	\$3,243	
	Doors - Steel Doors incl hw	151 - Boy's pool locker	3	EA	6	\$903	
	Floor Drain	151 - Boy's pool locker	8	EA	6	\$8,473	
	Floor - Tile Ceramic/ Porcelain	151 - Boy's pool locker	937	SF	6	\$1,983	
	Hand Dryer	151 - Boy's pool locker	6	EA	6	\$1,380	
	Lavatory	151 - Boy's pool locker	1	EA	6	\$320	
	Lighting - Lay-in	151 - Boy's pool locker	26	EA	7	\$0	
	Partitions	151 - Boy's pool locker	2	EA	6	\$594	
	Showers	151 - Boy's pool locker	15	EA	6	\$4,671	
	Storage/ Closet	151 - Boy's pool locker	24	SF	6	\$174	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Group Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
ocker/Shower Room							
Student Lockers	- One Tier	151 - Boy's pool locker	56	EA	6	\$5,199	
Urinals		151 - Boy's pool locker	3	EΑ	6	\$1,008	
Walls - Concrete	e Block	151 - Boy's pool locker	953	SF	6	\$2,794	
Walls - Structura	al Glazed Tile	151 - Boy's pool locker	318	SF	6	\$1,000	
Water Closet		151 - Boy's pool locker	2	EA	6	\$672	
Accessories		161 - Girl's pool locker	1,130	SF	6	\$4,428	
Benches, ped mo	punted	161 - Girl's pool locker	42	LF	6	\$4,573	
Ceiling - Plaster/	Drywall	161 - Girl's pool locker	1,130	SF	6	\$3,910	
Doors - Steel Doo	ors incl hw	161 - Girl's pool locker	3	EΑ	7	\$0	
Floor Drain		161 - Girl's pool locker	10	EΑ	6	\$10,592	
Floor - Tile Ceran	nic/ Porcelain	161 - Girl's pool locker	1,130	SF	6	\$2,392	
Hand Dryer		161 - Girl's pool locker	6	EA	6	\$1,380	
Lavatory		161 - Girl's pool locker	1	EA	6	\$320	
Lighting - Lay-in		161 - Girl's pool locker	1	EA	6	\$119	Relamp
Lighting - Lay-in		161 - Girl's pool locker	26	EA	7	\$0	
Partitions		161 - Girl's pool locker	4	EA	6	\$1,188	
Showers		161 - Girl's pool locker	15	EA	6	\$4,671	
Storage/ Closet		161 - Girl's pool locker	24	SF	6	\$174	
Student Lockers	- One Tier	161 - Girl's pool locker	75	EA	6	\$6,963	
Walls - Concrete	e Block	161 - Girl's pool locker	1,440	SF	6	\$4,221	
Water Closet		161 - Girl's pool locker	3	EA	6	\$1,008	
Accessories		255A - Boy's gym locker	3,171	SF	6	\$12,425	
Benches, ped mo	punted	255A - Boy's gym locker	115	LF	6	\$12,521	
Ceiling - Plaster/	Drywall	255A - Boy's gym locker	3,171	SF	6	\$10,974	
Doors - Steel Doo	ors incl hw	255A - Boy's gym locker	2	EΑ	6	\$602	
Floor Drain		255A - Boy's gym locker	5	EΑ	6	\$5,296	
Floor - Tile Ceran	nic/ Porcelain	255A - Boy's gym locker	3,171	SF	6	\$6,711	
Hand Dryer		255A - Boy's gym locker	10	EΑ	6	\$2,300	
Lavatory		255A - Boy's gym locker	2	EΑ	6	\$639	
Lighting - Lay-in		255A - Boy's gym locker	58	EA	7	\$0	
Partitions		255A - Boy's gym locker	1	EΑ	6	\$297	
Showers		255A - Boy's gym locker	41	EA	6	\$12,768	
Student Lockers	- One Tier	255A - Boy's gym locker	27	EA	7	\$0	
Urinals		255A - Boy's gym locker	3	EA	6	\$1,008	
Walls - Concrete	e Block	255A - Boy's gym locker	2,825	SF	6	\$8,281	
Walls - Structura	al Glazed Tile	255A - Boy's gym locker	1,412	SF	6	\$4,442	
Water Closet		255A - Boy's gym locker	1	EA	6	\$336	



Building: Linked Addition-Athletic Building B

up Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ker/Shower Room			•		0001	
Accessories	255E - Girl's gym locker	3,171	SF	6	\$12,425	
Benches, ped mounted	255E - Girl's gym locker	260	LF	6	\$28,309	
Ceiling - Plaster/ Drywall	255E - Girl's gym locker	3,171	SF	6	\$10,974	
Doors - Steel Doors incl hw	255E - Girl's gym locker	2	EA	6	\$602	
Floor Drain	255E - Girl's gym locker	5	EA	6	\$5,296	
Floor - Tile Ceramic/ Porcelain	255E - Girl's gym locker	3,171	SF	6	\$6,711	
Hand Dryer	255E - Girl's gym locker	11	EA	6	\$2,530	
Lavatory	255E - Girl's gym locker	3	EA	6	\$959	
Lighting - Lay-in	255E - Girl's gym locker	43	EA	7	\$0	
Partitions	255E - Girl's gym locker	3	EA	6	\$891	
Showers	255E - Girl's gym locker	31	EA	6	\$9,654	
Walls - Concrete Block	255E - Girl's gym locker	28,825	SF	6	\$84,500	
Walls - Structural Glazed Tile	255E - Girl's gym locker	1,412	SF	6	\$4,442	
Water Closet	255E - Girl's gym locker	3	EA	6	\$1,008	
Accessories	Rm 050A- Basement visiting team locker room	700	SF	6	\$2,743	
Ceiling - Plaster/ Drywall	Rm 050A- Basement visiting team locker room	700	SF	6	\$2,422	
Doors - Steel Doors incl hw	Rm 050A- Basement visiting team locker room	1	EA	6	\$301	
Floor Drain	Rm 050A- Basement visiting team locker room	6	EA	6	\$6,355	
Floor - Tile Ceramic/ Porcelain	Rm 050A- Basement visiting team locker room	700	SF	6	\$1,481	
Hand Dryer	Rm 050A- Basement visiting team locker room	2	EA	6	\$460	
Lavatory	Rm 050A- Basement visiting team locker room	1	EA	6	\$320	
Lighting - Lay-in	Rm 050A- Basement visiting team locker room	17	EA	7	\$0	
Partitions	Rm 050A- Basement visiting team locker room	1	EA	6	\$297	
Showers	Rm 050A- Basement visiting team locker room	13	EA	6	\$4,048	
Urinals	Rm 050A- Basement visiting team locker room	1	EA	6	\$336	
Walls - Concrete Block	Rm 050A- Basement visiting team locker room	943	SF	6	\$2,764	
Walls - Structural Glazed Tile	Rm 050A- Basement visiting team locker room	472	SF	6	\$1,485	in shower

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments	
Locker/	Locker/Shower Room							
	Water Closet	Rm 050A- Basement visiting team locker room	1	EA	6	\$336		
	Accessories	Rm 050E -Basement home team locker room #	1,336	SF	6	\$5,235		
	Benches, ped mounted	Rm 050E -Basement home team locker room #	60	LF	5	\$16,485		
	Ceiling - Plaster/ Drywall	Rm 050E -Basement home team locker room #	30	SF	4	\$653	water damage & mildew	
	Ceiling - Plaster/ Drywall	Rm 050E -Basement home team locker room #	1,306	SF	6	\$4,520		
	Doors - Steel Doors incl hw	Rm 050E -Basement home team locker room #	2	EA	6	\$602		
	Floor Drain	Rm 050E -Basement home team locker room #	6	EA	6	\$6,355		
	Floor - Tile Ceramic/ Porcelain	Rm 050E -Basement home team locker room #	1,336	SF	6	\$2,828		
	Hand Dryer	Rm 050E -Basement home team locker room #	1	EA	6	\$230		
	Lavatory	Rm 050E -Basement home team locker room #	2	EA	6	\$639		
	Lighting - Lay-in	Rm 050E -Basement home team locker room #	5	EA	6	\$595	missing covers	
	Lighting - Lay-in	Rm 050E -Basement home team locker room #	30	EA	6	\$3,569		
	Partitions	Rm 050E -Basement home team locker room #	1	EA	6	\$297		
	Showers	Rm 050E -Basement home team locker room #	1	EA	5	\$2,714	ADA shower is leaking a lot, plus it is missing the handheld shower head	
	Showers	Rm 050E -Basement home team locker room #	24	EA	6	\$7,474		
	Storage/ Closet	Rm 050E -Basement home team locker room #	152	SF	4	\$4,236	ceiling is water damaged	
	Urinals	Rm 050E -Basement home team locker room #	3	EA	6	\$1,008		
	Walls - Concrete Block	Rm 050E -Basement home team locker room #	1,825	SF	6	\$5,350		
	Walls - Structural Glazed Tile	Rm 050E -Basement home team locker room #	563	SF	6	\$1,771		
	Water Closet	Rm 050E -Basement home team locker room #	1	EA	6	\$336		
Mechan	Mechanical/ Service Rooms							
	Mechanical/ Service Rooms	1st Floor	48	SF	5	\$774	167 - Laundry/storage	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechar	nical/ Service Rooms						
	Storage Room	1st Floor	860	SF	6	\$6,161	169
	Janitor's Closet	Basement	32	SF	6	\$229	
	Mechanical/ Service Rooms	Basement	5,144	SF	6	\$36,853	
	Storage Room	Basement	432	SF	5	\$6,968	Uniform storage room has water damage on ceiling & on some walls
	Storage Room	Basement	94	SF	6	\$673	
Pool &	Natatorium						
	Accessories	1st Floor	12,306	SF	6	\$8,447	
	Bleachers Seating/Plank Seating	1st Floor	25	EA	6	\$724	Fixed wood/concrete seating
	Ceiling - Exposed	1st Floor	12,306	SF	6	\$18,301	
	Doors - Steel Doors incl hw	1st Floor	6	EΑ	6	\$1,806	Balcony doors
	Floor - Tile Ceramic/ Porcelain	1st Floor	7,326	SF	6	\$15,505	
	Lighting - Metal Halide/ High Pressure Sodium	1st Floor	27	EΑ	7	\$0	
	Lighting - Metal Halide/Sodium Vapor	1st Floor	90	EΑ	7	\$0	
	Lighting - Wall Mounted	1st Floor	10	EΑ	7	\$0	
	Pool Basin	1st Floor	4,980	SF	6	\$168,492	
	Pool Deck Drains	1st Floor	28	EΑ	6	\$11,818	
	Storage/ Closet	1st Floor	223	SF	6	\$1,617	
	Walls - Concrete Block	1st Floor	8,680	SF	6	\$25,445	
Restroc	om						
	Accessories	1st floor East - Men's	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	1st floor East - Men's	210	SF	6	\$727	
	Doors - Steel Doors incl hw	1st floor East - Men's	1	EΑ	6	\$301	
	Floor Drain	1st floor East - Men's	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor East - Men's	210	SF	6	\$444	
	Hand Dryer	1st floor East - Men's	1	EA	6	\$230	
	Lavatory	1st floor East - Men's	4	EA	6	\$1,278	
	Lighting - Lay-in	1st floor East - Men's	1	EA	6	\$119	Relamp
	Lighting - Lay-in	1st floor East - Men's	2	EΑ	7	\$0	
	Partitions	1st floor East - Men's	1	EA	6	\$297	
	Urinals	1st floor East - Men's	4	EA	6	\$1,344	
	Walls - Concrete Block	1st floor East - Men's	477	SF	6	\$1,398	
	Water Closet	1st floor East - Men's	1	EA	6	\$336	
	Accessories	1st floor East - Women's	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	1st floor East - Women's	210	SF	7	\$0	
	Doors - Steel Doors incl hw	1st floor East - Women's	1	EA	6	\$301	
	Floor Drain	1st floor East - Women's	1	EA	6	\$1,059	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	om						
	Floor - Tile Ceramic/ Porcelain	1st floor East - Women's	210	SF	6	\$444	Paint
	Hand Dryer	1st floor East - Women's	1	EA	6	\$230	
	Lavatory	1st floor East - Women's	4	EA	6	\$1,278	
	Lighting - Lay-in	1st floor East - Women's	3	EA	7	\$0	
	Partitions	1st floor East - Women's	3	EA	6	\$891	
	Walls - Concrete Block	1st floor East - Women's	477	SF	6	\$1,398	
	Water Closet	1st floor East - Women's	4	EA	6	\$1,344	
	Accessories	1st floor West - Men's	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	1st floor West - Men's	210	SF	7	\$0	
	Doors - Steel Doors incl hw	1st floor West - Men's	1	EA	6	\$301	
	Floor Drain	1st floor West - Men's	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor West - Men's	210	SF	6	\$444	
	Hand Dryer	1st floor West - Men's	1	EA	6	\$230	
	Lavatory	1st floor West - Men's	4	EA	6	\$1,278	
	Lighting - Lay-in	1st floor West - Men's	3	EA	7	\$0	
	Partitions	1st floor West - Men's	2	EA	6	\$594	
	Urinals	1st floor West - Men's	2	EA	6	\$672	
	Walls - Concrete Block	1st floor West - Men's	477	SF	6	\$1,398	
	Water Closet	1st floor West - Men's	2	EA	6	\$672	
	Accessories	1st floor West - Women's	210	SF	6	\$1,937	
	Ceiling - Plaster/Drywall	1st floor West - Women's	210	SF	6	\$727	
	Doors - Steel Doors incl hw	1st floor West - Women's	1	EA	6	\$301	
	Floor Drain	1st floor West - Women's	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st floor West - Women's	210	SF	6	\$444	
	Hand Dryer	1st floor West - Women's	1	EA	6	\$230	
	Lavatory	1st floor West - Women's	3	EA	6	\$959	
	Lighting - Lay-in	1st floor West - Women's	3	EA	7	\$0	
	Partitions	1st floor West - Women's	3	EA	6	\$891	
	Walls - Concrete Block	1st floor West - Women's	477	SF	6	\$1,398	
	Water Closet	1st floor West - Women's	2	EA	6	\$672	
	Water Closet	1st floor West - Women's	2	EA	5	\$2,688	Replace seats in 2 south stalls
	Accessories	Basement- Men's by 053	20	SF	6	\$184	
	Ceiling - Plaster/Drywall	Basement- Men's by 053	20	SF	6	\$69	
	Doors - Steel Doors incl hw	Basement- Men's by 053	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Basement- Men's by 053	20	SF	6	\$42	
	Lavatory	Basement- Men's by 053	1	EA	6	\$320	
	Lighting - Pendent/Surface	Basement- Men's by 053	1	EA	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

up	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
troor	m						
	Walls - Concrete Block	Basement- Men's by 053	160	SF	6	\$469	
	Water Closet	Basement- Men's by 053	1	EA	6	\$336	
	Accessories	Basement- Women's by 053	20	SF	6	\$184	
	Ceiling - Plaster/Drywall	Basement- Women's by 053	20	SF	6	\$69	
	Doors - Steel Doors incl hw	Basement- Women's by 053	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	Basement- Women's by 053	20	SF	6	\$42	
	Lavatory	Basement- Women's by 053	1	EA	6	\$320	
	Lighting - Pendent/Surface	Basement- Women's by 053	1	EA	7	\$0	
	Walls - Concrete Block	Basement- Women's by 053	160	SF	6	\$469	
	Water Closet	Basement- Women's by 053	1	EA	6	\$336	
	Accessories	In office 152	33	SF	6	\$304	
	Ceiling - Plaster/Drywall	In office 152	33	SF	6	\$114	
	Doors - Steel Doors incl hw	In office 152	1	EA	6	\$301	
	Floor - Tile	In office 152	17	SF	6	\$37	
	Floor - Tile Ceramic/ Porcelain	In office 152	16	SF	6	\$34	
	Lavatory	In office 152	1	EA	6	\$320	
	Lighting - Lay-in	In office 152	2	EA	7	\$0	
	Partitions	In office 152	1	EA	6	\$297	
	Student Lockers - One Tier	In office 152	4	EA	6	\$371	Staff
	Walls - Concrete Block	In office 152	193	SF	6	\$566	
	Water Closet	In office 152	1	EA	6	\$336	
	Accessories	In office 153	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	In office 153	38	SF	6	\$132	
	Doors - Steel Doors incl hw	In office 153	1	EA	6	\$301	
	Floor Drain	In office 153	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	In office 153	38	SF	6	\$80	
	Lavatory	In office 153	1	EA	6	\$320	
	Lighting - Lay-in	In office 153	1	EA	7	\$0	
	Partitions	In office 153	1	EA	6	\$297	
	Showers	In office 153	1	EA	6	\$311	
	Walls - Concrete Block	In office 153	184	SF	6	\$539	
	Water Closet	In office 153	1	EA	6	\$336	
	Accessories	In office 157	38	SF	6	\$350	
	Ceiling - Plaster/Drywall	In office 157	38	SF	6	\$132	
	Doors - Steel Doors incl hw	In office 157	1	EA	6	\$301	
	Floor Drain	In office 157	2	EA	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	In office 157	38	SF	6	\$80	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Restroom Lavatory In office 157 1 EA 6 \$320 Lighting - Lay-in In office 157 1 EA 7 \$0 Recessed incandescent Partitions In office 157 1 EA 6 \$297 Showers In office 157 1 EA 6 \$311	
Lighting - Lay-in In office 157 1 EA 7 \$0 Recessed incandescent Partitions In office 157 1 EA 6 \$297	
Partitions In office 157 1 EA 6 \$297	
Showers In office 157 1 EA 6 \$311	
ποποστοί	
Walls - Concrete Block In office 157 184 SF 6 \$539	
Water Closet In office 157 1 EA 6 \$336	
Accessories In office 158 33 SF 6 \$304	
Ceiling - Plaster/Drywall In office 158 33 SF 6 \$114	
Doors - Steel Doors incl hw In office 158 1 EA 6 \$301	
Floor - Tile In office 158 17 SF 6 \$37	
Floor - Tile Ceramic/ Porcelain In office 158 16 SF 6 \$34	
Lavatory In office 158 1 EA 6 \$320	
Lighting - Lay-in In office 158 2 EA 7 \$0	
Partitions In office 158 1 EA 6 \$297	
Student Lockers - One Tier In office 158 4 EA 6 \$371 Staff	
Walls - Concrete Block In office 158 193 SF 6 \$566	
Water Closet	
Accessories In office 159 38 SF 6 \$350	
Ceiling - Plaster/Drywall In office 159 38 SF 6 \$132	
Doors - Steel Doors incl hw In office 159 1 EA 6 \$301	
Floor Drain In office 159 2 EA 6 \$2,118	
Floor - Tile Ceramic/ Porcelain In office 159 38 SF 6 \$80	
Lavatory In office 159 1 EA 6 \$320	
Lighting - Lay-in In office 159 1 EA 7 \$0 Recessed incandescent	
Partitions In office 159 1 EA 6 \$297	
Showers In office 159 1 EA 6 \$311	
Walls - Concrete Block In office 159 184 SF 6 \$539	
Water Closet In office 159 1 EA 6 \$336	
Accessories In room 150 33 SF 6 \$304	
Ceiling - Plaster/Drywall In room 150 33 SF 6 \$114	
Doors - Wood Doors inclu hw In room 150 1 EA 6 \$301	
Floor - Tile/Sheet In room 150 33 SF 6 \$33	
Lavatory In room 150 1 EA 6 \$320	
Lighting - Lay-in	
Walls - Concrete Block In room 150 193 SF 6 \$566	
Water Closet	
Accessories In room 160B 33 SF 6 \$304	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroc	m						
	Ceiling - Plaster/Drywall	In room 160B	33	SF	6	\$114	
	Doors - Wood Doors inclu hw	In room 160B	1	EA	6	\$301	
	Floor - Tile/Sheet	In room 160B	33	SF	6	\$33	
	Lavatory	In room 160B	1	EA	6	\$320	
	Lighting - Lay-in	In room 160B	1	EA	6	\$119	
	Walls - Concrete Block	In room 160B	193	SF	6	\$566	
	Water Closet	In room 160B	1	EA	6	\$336	
	Accessories	Inside West gym office	37	SF	6	\$341	
	Ceiling - Plaster/Drywall	Inside West gym office	37	SF	6	\$128	
	Doors - Steel Doors incl hw	Inside West gym office	1	EA	6	\$301	
	Floor Drain	Inside West gym office	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Inside West gym office	37	SF	6	\$78	
	Lavatory	Inside West gym office	1	EA	6	\$320	
	Lighting - Lay-in	Inside West gym office	1	EA	7	\$0	
	Walls - Concrete Block	Inside West gym office	260	SF	6	\$762	
	Water Closet	Inside West gym office	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$1,421,939

Building: Linked Addition-Athletic Building B

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	or						
	Ceiling - Lay-in	1st Floor	48	SF	5	\$428	
	Ceiling - Lay-in	1st Floor	988	SF	6	\$2,967	
	Ceiling - Plaster/Drywall	1st Floor	2,059	SF	6	\$12,749	
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Drinking Fountains - Single Water Cooler	1st Floor	8	EA	6	\$2,534	
	Floor - Terrazzo	1st Floor	3,105	SF	6	\$26,064	
	Lighting - Lay-in	1st Floor	2	EA	6	\$238	
	Lighting - Lay-in	1st Floor	100	EΑ	7	\$0	
	Walls - Masonry	1st Floor	3,853	SF	6	\$12,122	
	Walls - Metal Panel	1st Floor	240	SF	5	\$7,341	
	Ceiling - Lay-in	2nd Floor passage btwn Main & Athletic building / 2nd Floor	1,152	SF	6	\$3,459	
	Doors - Side-lite	2nd Floor passage btwn Main & Athletic building / 2nd Floor	930	EA	6	\$15,547	

211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	or						
	Doors - Steel Doors incl hw	2nd Floor passage btwn Main & Athletic building / 2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor passage btwn Main & Athletic building / 2nd Floor	1,152	SF	6	\$626	
	Lighting - Lay-in	2nd Floor passage btwn Main & Athletic building / 2nd Floor	36	EA	7	\$0	
	Walls - Masonry	2nd Floor passage btwn Main & Athletic building / 2nd Floor	230	SF	6	\$724	
	Ceiling - Exposed	2nd Floor	1,146	SF	6	\$1,704	
	Ceiling - Plaster/Drywall	2nd Floor	2,659	SF	6	\$16,464	
	Doors - Steel Doors incl hw	2nd Floor	5	EA	6	\$1,505	
	Drinking Fountains - Single Fountain	2nd Floor	4	EA	6	\$1,103	
	Floor - Tile/Sheet	2nd Floor	3,105	SF	6	\$1,687	
	Lighting - Lay-in	2nd Floor	21	EA	7	\$0	
	Lighting - Metal Halide/ High Pressure Sodium	2nd Floor	15	EA	7	\$0	
	Walls - Concrete Block	2nd Floor	2,696	SF	6	\$7,903	
	Walls - Masonry	2nd Floor	1,340	SF	6	\$4,216	
	Ceiling - Lay-in	Basement	1,423	SF	6	\$4,273	
	Ceiling - Lay-in	Basement	36	SF	4	\$562	old & stainedand water damaged
	Drinking Fountains - Single Fountain	Basement	1	EA	6	\$276	
	Floor - Tile/Sheet	Basement	1,373	SF	6	\$746	
	Floor - Tile/Sheet	Basement	50	SF	4	\$741	missing/damaged tiles
	Lighting - Lay-in	Basement	4	EA	6	\$476	missing covers
	Lighting - Lay-in	Basement	12	EA	7	\$0	
	Walls - Concrete Block	Basement	2,627	SF	6	\$7,701	
Safety							
	Security Cameras	Entire Building	12	EA	7	\$0	
Stairs							
	Floor - Terrazzo	Entire building stairwells	2,698	SF	6	\$22,647	
	Floor - Tile/Sheet	Entire building stairwells	100	SF	6	\$54	
	Handrails	Entire building stairwells	612	LF	6	\$5,303	
	Stairs - Terrazzo	Entire building stairwells	290	LF	6	\$2,691	
	Walls - Masonry	Entire building stairwells	6,355	SF	6	\$19,993	Brick walls
Vertica	I Conveyance						
	Elevator - Hydraulic Elevator	Entire Building	1	EA	6	\$19,238	



211 S Laflin St Chicago, IL 60607

Building: Linked Addition-Athletic Building B

Category: Building Interior

Group Item - Type Location Quantity Unit Rank Cost Comments

Building Interior Subtotal: \$206,490

Total Building Cost \$3,481,033

Building: Main - Building A Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entranc	e						
	Entrance Control - Audio and Video	#1 W	1	EA	5	\$1,567	Do not work
	Exterior Doors - Exterior FRP Door	#1 W	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#2 W	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#3 S	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#4 S	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#5_Exit S	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#6 E	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#7_Exit E	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#8 N	2	EA	6	\$1,263	
	Exterior Doors - Exterior FRP Door	#9_Exit N	2	EA	6	\$1,263	
	Exterior Doors - Exterior Steel Door	#10_LL N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#12 Roof	2	EA	6	\$961	
	Exterior Doors - Overhead Rolling/ Garage Door	#11_LL N	1	EA	6	\$1,433	Service Drive/ Deliveries
	Exterior Doors - Side lite	#1 W	2	EA	6	\$627	
	Exterior Doors - Side lite	#2 W	2	EA	6	\$627	
	Exterior Doors - Side lite	#3 S	2	EA	6	\$627	
	Exterior Doors - Side lite	#4 S	2	EA	6	\$627	
	Exterior Doors - Side lite	#5_Exit S	2	EA	6	\$627	
	Exterior Doors - Side lite	#6 E	2	EA	6	\$627	
	Exterior Doors - Side lite	#7_Exit E	2	EA	6	\$627	
	Exterior Doors - Side lite	#8 N	2	EA	6	\$627	
	Exterior Doors - Side lite	#9_Exit N	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#1 W	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#2 W	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#3 S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#4 S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#5_Exit S	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#6 E	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#7_Exit E	2	EA	6	\$627	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrand	ce						
	Exterior Doors - Transom Lite	#8 N	2	EA	6	\$627	
	Exterior Doors - Transom Lite	#9_Exit N	2	EA	6	\$627	
	Exterior Stairs - Concrete	#10_LL N	3	LF	6	\$245	
	Power Door Operator and Controls	#1 W	1	EA	6	\$0	
Founda	ation						
	Foundation - Concrete	Entire Building	8	LF	5	\$4,415	Seepage in dock area
	Foundation - Concrete	Entire Building	1,060	LF	7	\$0	
	Superstructure - Steel	Entire Building	251,542	SF	7	\$0	
Lightin	g						
	Exterior Lighting - Wall Mounted	Entire Building	108	EA	6	\$31,185	
Roof Sy	ystem						
	Chimney - Metal Flue	Entire Building	610	LF	6	\$96,468	
	Coping - Metal	Entire Building	1,070	LF	6	\$34,366	
	Downspouts - Interior Downspouts	Entire Building	1,125	LF	6	\$37,387	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	71,420	SF	7	\$0	
	Roof - PVC Membrane	Entire Building	71,420	SF	6	\$590,315	
Walls							
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	18,607	SF	6	\$105,634	
Windov	ws						
	Curtain wall - Glazed Single Pane	Entire Building	31,983	SF	5	\$1,424,667	Sealant/Gasket Issue
	Windows - Casement Aluminum	Entire Building	1,820	SF	5	\$65,351	Sealant/Weather Stripping

Building Exterior Subtotal:

\$2,417,120

Building: Main - Building A Category: Electrical System

Group Item - Type		Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
Automatic Transfer Switch		Electrical Room	3	EA	6	\$1,224	
Emergency A/C Power - Corridors	s and Stairs	Entire Building	36,599	SF	6	\$10,991	
Emergency A/C Power - Lunchroo	oms	Entire Building / 1st Floor	3,450	SF	6	\$1,283	
Emergency A/C Power - Lunchroo	oms	Entire Building / 2nd Floor	1,550	SF	6	\$576	
Emergency A/C Power - Lunchroom	oms	Entire Building / 3rd Floor	1,550	SF	6	\$576	
Emergency A/C Power - Students	s Toilets	Entire Building	2,350	SF	6	\$874	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emerge	ency System						
	Emergency Battery Packs - Corridors and Stairs	Entire Building / Basement	3	EA	6	\$608	
	Emergency Battery Packs - Students Toilets	Entire Building / Basement	2	EA	6	\$405	
	Emergency Generator- Indoor- Natural Gas - 201 - 250 KW	Loading dock area / Loading Dock	1	EA	6	\$17,264	serves main and gym building
	Exit Signs - Corridors and Stairs	Entire Building	54	EA	6	\$8,086	
	Exit Signs - Corridors and Stairs	Entire Building	2	EA	6	\$299	
	Exit Signs - Lunchroom	Entire Building	9	EA	6	\$1,348	
	Security System - CCTV	Entire Building	251,542	SF	6	\$75,538	
	Security System - Intrusion Detection	Entire Building	251,542	SF	6	\$64,747	
	UPS - Less than 30 KW	Electrical Room	2	EA	6	\$15,772	1000W, Alpha
Main S	ervice						
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	2	EA	6	\$21,734	
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	2	EA	6	\$23,110	
	PA System	Entire Building	251,542	SF	6	\$82,732	connected to other buildings
Power	Distribution						
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	3	EA	6	\$897	
	Lighting and Power Panels - Above 100 A	Entire Building	25	EA	6	\$12,426	
	Lighting and Power Panels - Above 100 A	Entire Building	15	EA	6	\$7,455	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	4	EA	6	\$2,111	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	7	EA	6	\$5,111	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	2	EA	6	\$1,460	
	Main Distribution Panels - Less than 400 amp	Entire Building	5	EA	6	\$2,516	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	2	EA	6	\$2,530	
	Transformers - 277/480 - 120/208	Entire Building / Electrical Room	1	EA	6	\$1,265	
	deal Cretem Cribtetal					* 205 050	

Electrical System Subtotal:

\$365,859

Building: Main - Building A Category: Safty System

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm						
Fire Alarm Panel	Entire Building / Electrical Room	1	EA	6	\$6,406	
Fire Alarm Strobe Lights	Entire Building	251,542	SF	6	\$89,926	
Fire Alarm_System	Entire Building / Mechanical Room	251,542	SF	6	\$122,300	
Fire Pump Controller	Entire Building / Mechanical Room	1	EΑ	6	\$1,823	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Safty System

•							
Group	Item - Type	Location	Quantity	Unit	Rank	Cost C	Comments
Pump Ro	om Assembly						
	Fire Pump - 25-50 hp	Mechanical Room	1	EA	6	\$1,558	
	Jockey Pump	Mechanical Room	1	EA	6	\$758	
Sprinkle	System						
	Combination Wet and Dry Sprinkler System	Entire Building / Loading Dock	251,542	SF	6	\$64,747	
	Sprinkler Heads	Entire Building	251,542	SF	7	\$0	
	Sprinkler Piping	Entire Building	251,542	SF	6	\$46,762	

Safty System Subtotal: \$334,279

Building: Main - Building A

Category: Mechanical System

	bry. Wechanical System	Lagation	Our entitle	L los ? 4	Dank	0==1	Comments
•	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ir Con	ditioning						
	Condensing Unit- Ground Mounted - Less than 5 tons	Electrical Room	1	EA	6	\$3,334	water cooled condensor portion, for MDF room.
ir Han	dling Systems						
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves 300W, 300
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves 212
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves 309
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves100 main
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves 320B
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves chem lab
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves dining area
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves dining
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 21 - 30 tons	Roof	1	EA	6	\$2,792	serves lab 124
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves dining room
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves chem lab
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves office 4A

211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Han	dling Systems						
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves 312
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves oiffice 3B
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves 317
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves storage 316
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves 331
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves 203
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves 308
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves dining
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	5	\$32,040	serves kitchen, lockers
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 31 - 45 tons	Roof	1	EA	6	\$2,792	serves biology
	Roof Top Unit-Multi Zone-Roof Mounted- Gas Heating and DX Cooling w/ Self Contained Compressor - 46 - 60 tons	Roof	1	EA	6	\$2,792	serves 104
Heating	Devices						
	Cabinet Heaters - With Electric Coil	Entire Building / 1st Floor	2	EA	4	\$6,720	
	Cabinet Heaters - With Electric Coil	Entire Building	6	EA	6	\$2,140	
	Fin Tube - Electric	Entire Building	1,800	LF	6	\$16,988	
	Wall Heater - Electric	Receiving Dock / Basement	2	EA	6	\$278	
Temper	ature Control						
	DDC System	Entire Building	251,542	SF	6	\$143,882	
	Thermostats - DDC	Entire Building	170	EA	6	\$0	
	Thermostats - DDC	Entire Building	4	EA	4	\$3,277	
Ventilat	ion						
	Exhaust Fans- Indoor - Less than 500 CFM	Entire Building / 1st Floor	2	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	17	EA	6	\$10,071	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	3	EA	6	\$1,777	
	Exhaust Fans- Roof Mounted - Greater than 8000 CFM	Entire Building / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	3	EA	6	\$889	
	Lab Exhaust Hood	Entire Building	6	EA	6	\$7,486	
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	4	EA	6	\$4,991	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Mechanical System

Group Item - Type	Location	Quantity Uni	Rank	Cost C	Comments
Ventilation					
Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1 EA	2	\$28,265	
Type II Exhaust Hood- Warming Kitchen	Entire Building	3 EA	6	\$2,760	
	-				

Mechanical System Subtotal:

\$327,497

Building: Main - Building A Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Wa	ter						
	Gas Heater - 300001 - 600000 BTU/HR	Mechanical Room	2	EA	6	\$620	
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	Mechanical Room	1	EA	6	\$678	
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	251,542	SF	6	\$50,359	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	251,542	SF	6	\$61,150	
	Domestic Piping-Cold Water Risers	Entire Building	251,542	SF	6	\$46,762	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	251,542	SF	6	\$39,568	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	251,542	SF	6	\$46,762	
	Domestic Piping-Hot Water Return Lines	Entire Building	251,542	SF	6	\$35,971	
	Domestic Piping-Hot Water Return Risers	Entire Building	251,542	SF	6	\$35,971	
	Sanitary Piping	Entire Building	251,542	SF	6	\$230,211	
	Storm Piping	Entire Building	251,542	SF	6	\$219,420	
	Vent Piping	Entire Building	251,542	SF	6	\$169,061	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Entire Building / Mechanical Room	1	EA	6	\$1,977	
	Pumps - Ejector-Simplex	Entire Building / Loading Dock	1	EA	6	\$745	
	Pumps - Sump-Simplex	Entire Building / 1st Floor	3	EA	6	\$2,235	
	Pumps - Sump-Simplex	Entire Building / Electrical Room	1	EA	6	\$745	
	Pumps - Sump-Simplex	Entire Building / Mechanical Room	1	EA	6	\$745	

Plumbing System Subtotal:

\$942,979

Building: Main - Building A

Category: Classrooms

Group Item - Type Location Quantity Unit Rank Cost Comments

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
_	oom #105 (Regular Classroom)	200411011	quantity	01	rtaint	000.	
Glador	Ceiling - Lay-in	1st Floor	811	SF	6	\$2,435	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile/Sheet	1st Floor	811	SF	6	\$812	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	6	\$214	
	Walls - Concrete Block	1st Floor	292	SF	6	\$856	
	Walls - Metal Panel	1st Floor	584	SF	6	\$4,359	
Classro	oom #106 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	811	SF	6	\$2,435	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile/Sheet	1st Floor	811	SF	6	\$812	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	10	LF	6	\$214	
	Walls - Concrete Block	1st Floor	292	SF	6	\$856	
	Walls - Metal Panel	1st Floor	584	SF	6	\$4,359	
Classro	oom #107 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	811	SF	6	\$2,435	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile/Sheet	1st Floor	811	SF	6	\$812	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Concrete Block	1st Floor	292	SF	6	\$856	
	Walls - Metal Panel	1st Floor	584	SF	6	\$4,359	
Classro	oom #109 (Computer Lab)						
	Ceiling - Lay-in	1st Floor	2,438	SF	6	\$7,321	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
	Floor - Concrete Epoxy/ Painted	1st Floor	2,438	SF	6	\$1,290	
	Lighting - Lay-in	1st Floor	1	EA	6	\$119	cover missing
	Lighting - Lay-in	1st Floor	45	EA	7	\$0	
	Marker Board	1st Floor	6	LF	7	\$0	
	Storage/ Closet	1st Floor	754	SF	6	\$5,467	109 A/B/C/D
	Walls - Concrete Block	1st Floor	497	SF	6	\$1,457	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	om #109 (Computer Lab)						
	Walls - Metal Panel	1st Floor	1,492	SF	6	\$11,137	
	Wireless System	1st Floor	1	EA	6	\$372	
	Work Sink	1st Floor	3	EA	6	\$1,137	
lacero	om #110 (Regular Classroom)					, ,	
1055100	Ceiling - Lay-in	1st Floor	10	SF	4	\$1 <i>1</i> 1	water damaged
	Ceiling - Lay-in	1st Floor	1,168	SF	6		water damaged
	Chalk Board	1st Floor		LF		\$3,508 \$1,377	
			15		4		
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	1,178	SF	6	\$2,577	
	Lighting - Lay-in	1st Floor	32	EA	7	\$0	
	Marker Board	1st Floor	18	LF	7	\$0	
	Walls - Concrete Block	1st Floor	345	SF	6	\$1,011	
	Walls - Metal Panel	1st Floor	1,035	SF	6	\$7,726	
lassro	om #113 (Special Education)						
	Ceiling - Lay-in	1st Floor	420	SF	6	\$1,261	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile	1st Floor	420	SF	6	\$919	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Metal Panel	1st Floor	870	SF	6	\$6,494	
lassro	om #114 (Special Education)						
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	860	SF	6	\$2,583	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile	1st Floor	10	SF	5	\$45	damaged
	Floor - Tile Ceramic/ Porcelain	1st Floor	850	SF	6	\$1,799	· ·
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Concrete Block	1st Floor	292	SF	6	\$856	
	Walls - Metal Panel	1st Floor	584	SF	6	\$4,359	
	Work Sink	1st Floor	1	EA	6	\$379	



Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #115 (Regular Classroom)						
	Casework	1st Floor	14	LF	6	\$354	
	Ceiling - Lay-in	1st Floor	860	SF	6	\$2,583	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile/Sheet	1st Floor	20	SF	5	\$115	missing tiles
	Floor - Tile/Sheet	1st Floor	840	SF	6	\$841	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	18	LF	7	\$0	
	Walls - Concrete Block	1st Floor	292	SF	6	\$856	
	Walls - Metal Panel	1st Floor	584	SF	6	\$4,359	
	Work Sink	1st Floor	1	EA	6	\$379	
Classro	oom #116 (Regular Classroom)						
	Casework	1st Floor	18	LF	6	\$455	
	Ceiling - Lay-in	1st Floor	860	SF	6	\$2,583	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile/Sheet	1st Floor	860	SF	6	\$861	
	Lighting - Lay-in	1st Floor	14	EΑ	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	292	SF	6	\$856	
	Walls - Metal Panel	1st Floor	584	SF	6	\$4,359	
	Work Sink	1st Floor	2	EA	6	\$758	
Classro	oom #117 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	1,026	SF	6	\$3,081	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile	1st Floor	1,026	SF	6	\$2,245	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	16	LF	7	\$0	
	Storage/ Closet	1st Floor	110	SF	6	\$798	storage for book store
	Walls - Metal Panel	1st Floor	1,285	SF	6	\$9,592	
Classro	oom #119 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	735	SF	6	\$2,207	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Transom Window	1st Floor	22	SF	6	\$372	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #119 (Regular Classroom)						
	Floor - Tile	1st Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	1st Floor	15	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Metal Panel	1st Floor	1,085	SF	6	\$8,099	
Classro	oom #122 (Computer Lab)						
	Ceiling - Lay-in	1st Floor	1,037	SF	6	\$3,114	
	Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
	Doors - Transom Window	1st Floor	22	SF	6	\$372	
	Floor - Tile	1st Floor	1,037	SF	6	\$2,269	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Metal Panel	1st Floor	1,292	SF	6	\$9,644	
	Wireless System	1st Floor	1	EA	6	\$372	
Classro	oom #126 (Special Education)						
	Casework	1st Floor	4	LF	6	\$101	
	Ceiling - Lay-in	1st Floor	1,037	SF	6	\$3,114	
	Doors - Side-lite	1st Floor	40	SF	6	\$669	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
	Doors - Transom Window	1st Floor	33	SF	6	\$559	
	Floor - Tile	1st Floor	1,037	SF	6	\$2,269	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Marker Board	1st Floor	8	LF	7	\$0	
	Walls - Concrete Block	1st Floor	779	SF	6	\$2,284	
	Walls - Metal Panel	1st Floor	779	SF	6	\$5,815	
	Work Sink	1st Floor	1	EA	6	\$379	
Classro	oom #127 (Regular Classroom)						
	Ceiling - Lay-in	1st Floor	689	SF	6	\$2,069	
	Doors - Side-lite	1st Floor	10	SF	6	\$167	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Doors - Transom Window	1st Floor	11	SF	6	\$186	
	Floor - Tile	1st Floor	689	SF	6	\$1,507	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Metal Panel	1st Floor	1,060	SF	6	\$7,912	
			•			•	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Caling - Lay-in	Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Doors - Side-lite	Classro	om #129 (Regular Classroom)						
Doors - Steel Doors incl hw		Ceiling - Lay-in	1st Floor	738	SF	6	\$2,216	
Doors - Transom Window		Doors - Side-lite	1st Floor	20	SF	6	\$334	
Floor - Tile		Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
Lighting - Lay-in Marker Board 1st Floor 15 EA 7 \$0 Walls - Metal Panel 1st Floor 1,09 SF 6 \$8,136 Classroom #131 (Special Education) Casework 1st Floor 6 LF 6 \$152 Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 30 SF 6 \$502 Doors - Steel Doors incl hw 1st Floor 3 EA 6 \$903 Doors - Transom Window 1st Floor 33 SF 6 \$559 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 4 LF 7 \$0 Walls - Concrete Block 1st Floor 222 SF 6 \$451 Walls - Matel Panel 1st Floor 421 SF 6 \$451 Ceiling - Lay-in 1st Floor 421 SF 6		Doors - Transom Window	1st Floor	22	SF	6	\$372	
Marker Board Walls - Metal Panel 1st Floor 1st Floor 12 LF 7 \$ \$0 Classroom #131 (Special Education) Casework 1st Floor 6 \$152 Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 0 1st Floor 30 SF 6 \$502 Doors - Steel Doors incl hw 1st Floor 33 SF 6 \$903 Doors - Transom Window 1st Floor 33 SF 6 \$903 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 4 LF 7 \$0 Walls - Concrete Block 1st Floor 222 SF 6 \$651 Walls - Metal Panel 1st Floor 421 SF 6 \$44,971 Classroom #132 (Special Education) Celling - Lay-in 1st Floor 41 SF 6 \$1,264 Doors - Side-lite 1st Floor 421 SF 6 \$651 \$6502 Doors - Transom Window 1st Floor 421 SF 6 \$651 \$6602 Doors - Transom Window 1st Floor 2 EA 6 \$602 \$602 Doors - Transom Window 1st Floor 2 EA		Floor - Tile	1st Floor	738	SF	6	\$1,615	
Malls - Metal Panel		Lighting - Lay-in	1st Floor	15	EA	7	\$0	
Casework		Marker Board	1st Floor	12	LF	7	\$0	
Casework 1st Floor 6 LF 6 \$152 Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 30 SF 6 \$502 Doors - Steel Doors incl hw 1st Floor 3 EA 6 \$903 Doors - Transom Window 1st Floor 33 SF 6 \$559 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Marker Board 1st Floor 4 LF 7 \$0 Walls - Concrete Block 1st Floor 222 SF 6 \$551 Walls - Metal Panel 1st Floor 666 SF 6 \$4,971 Classroom #132 (Special Education) Ceiling - Lay-in 1st Floor 421 SF 6 \$167 Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Side Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 421 SF 6 \$421		Walls - Metal Panel	1st Floor	1,090	SF	6	\$8,136	
Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 30 SF 6 \$502 Doors - Steel Doors incl hw 1st Floor 3 EA 6 \$903 Doors - Transom Window 1st Floor 33 SF 6 \$559 Floor - Tile/Sheet 1st Floor 421 SF 6 \$559 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 4 LF 7 \$0 Marker Board 1st Floor 222 SF 6 \$651 Walls - Metal Panel 1st Floor 222 SF 6 \$4,971 Classroom #132 (Special Education) Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 2 EA 6 \$6	Classro	om #131 (Special Education)						
Doors - Side-lite		Casework	1st Floor	6	LF	6	\$152	
Doors - Steel Doors incl hw		Ceiling - Lay-in	1st Floor	421	SF	6	\$1,264	
Doors - Transom Window		Doors - Side-lite	1st Floor	30	SF	6	\$502	
Floor - Tile/Sheet		Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
Lighting - Lay-in 1st Floor 9 EA 7 \$0 Marker Board 1st Floor 4 LF 7 \$0 Walls - Concrete Block 1st Floor 222 SF 6 \$651 Walls - Metal Panel 1st Floor 666 SF 6 \$4,971 Celling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Doors - Transom Window	1st Floor	33	SF	6	\$559	
Marker Board 1st Floor 4 LF 7 \$0 Walls - Concrete Block 1st Floor 222 SF 6 \$651 Walls - Metal Panel 1st Floor 666 SF 6 \$4,971 Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Floor - Tile/Sheet	1st Floor	421	SF	6	\$421	
Walls - Concrete Block Walls - Metal Panel 1st Floor 222 SF 6 \$6 \$4,971 Classroom #132 (Special Education) Ceiling - Lay-in		Lighting - Lay-in	1st Floor	9	EA	7	\$0	
Walls - Metal Panel 1st Floor 666 SF 6 \$4,971 Classroom #132 (Special Education) Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Marker Board	1st Floor	4	LF	7	\$0	
Classroom #132 (Special Education) Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Walls - Concrete Block	1st Floor	222	SF	6	\$651	
Ceiling - Lay-in 1st Floor 421 SF 6 \$1,264 Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Walls - Metal Panel	1st Floor	666	SF	6	\$4,971	
Doors - Side-lite 1st Floor 10 SF 6 \$167 Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494	Classro	om #132 (Special Education)						
Doors - Steel Doors incl hw 1st Floor 2 EA 6 \$602 Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Ceiling - Lay-in	1st Floor	421	SF	6	\$1,264	
Doors - Transom Window 1st Floor 22 SF 6 \$372 Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Doors - Side-lite	1st Floor	10	SF	6	\$167	
Floor - Tile/Sheet 1st Floor 421 SF 6 \$421 Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Doors - Steel Doors incl hw	1st Floor	2	EA	6	\$602	
Lighting - Lay-in 1st Floor 9 EA 7 \$0 Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Doors - Transom Window	1st Floor	22	SF	6	\$372	
Walls - Metal Panel 1st Floor 870 SF 6 \$6,494		Floor - Tile/Sheet	1st Floor	421	SF	6	\$421	
		Lighting - Lay-in	1st Floor	9	EA	7	\$0	
Oleana and MACO (Parantary Oleana and		Walls - Metal Panel	1st Floor	870	SF	6	\$6,494	
Classroom #136 (Regular Classroom)	Classro	om #136 (Regular Classroom)						
Ceiling - Lay-in 1st Floor 1,020 SF 6 \$3,063		Ceiling - Lay-in	1st Floor	1,020	SF	6	\$3,063	
Doors - Steel Doors incl hw 1st Floor 1 EA 6 \$301		Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
Doors - Transom Window 1st Floor 11 SF 6 \$186		Doors - Transom Window	1st Floor	11	SF	6	\$186	
Floor - Tile 1st Floor 1,020 SF 6 \$2,232		Floor - Tile	1st Floor	1,020	SF	6	\$2,232	
Lighting - Lay-in 1st Floor 21 EA 7 \$0		Lighting - Lay-in	1st Floor	21	EA	7	\$0	
Marker Board 1st Floor 12 LF 7 \$0		Marker Board	1st Floor	12	LF	7	\$0	
Storage/ Closet 1st Floor 404 SF 6 \$2,929		Storage/ Closet	1st Floor	404	SF	6	\$2,929	
Walls - Metal Panel 1st Floor 1,020 SF 6 \$7,614		Walls - Metal Panel	1st Floor	1,020	SF	6	\$7,614	



211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Location	Quantity	Unit	Rank	Cost	Comments
Location	Quantity	Oint	raint	0031	Comments
1st Floor	15	LF	6		
1st Floor	667	SF	6		
1st Floor	1	EA	6	\$301	
1st Floor	11	SF	6	\$186	
1st Floor	667	SF	6	\$1,459	
1st Floor	13	EA	7	\$0	
1st Floor	1,190	SF	6	\$8,883	
2nd Floor	600	SF	6	\$1,802	
2nd Floor	2	EA	6	\$602	
2nd Floor	600	SF	6	\$4,230	
2nd Floor	10	EA	7	\$0	Exposed wires at voice outlet
2nd Floor	983	SF	6	\$7,338	
2nd Floor	735	SF	6	\$2,207	
2nd Floor	1	EA	7	\$0	
2nd Floor	735	SF	6	\$1,608	
2nd Floor	14	EA	7	\$0	
2nd Floor	8	LF	7	\$0	
2nd Floor	545	SF	6	\$4,068	
2nd Floor	16	SF	5	\$128	
2nd Floor	719	SF	6	\$2,159	
2nd Floor	8	LF	4	\$734	Remove/replace with marker board
2nd Floor	1	EA	6	\$301	
2nd Floor	735	SF	6	\$1,608	
2nd Floor	15	EA	7	\$0	
2nd Floor	792	SF	6	\$5,912	
2nd Floor	16	SF	5	\$128	
2nd Floor	719	SF	6	\$2,159	
2nd Floor	1	EA	6	\$301	
2nd Floor	735	SF	6	\$1,608	
2nd Floor	15	EA	7	\$0	
	1st Floor 2nd Floor	1st Floor 667 1st Floor 1 1st Floor 667 1st Floor 13 1st Floor 13 1st Floor 1,190 2nd Floor 600 2nd Floor 2 2nd Floor 600 2nd Floor 983 2nd Floor 983 2nd Floor 735 2nd Floor 1 2nd Floor 735 2nd Floor 1 2nd Floor 545 2nd Floor 1 2nd Floor 735 2nd Floor 735 2nd Floor 735 2nd Floor 1 2nd Floor 799	1st Floor 15 LF 1st Floor 1 EA 1st Floor 11 SF 1st Floor 667 SF 1st Floor 13 EA 1st Floor 1,190 SF 2nd Floor 600 SF 2nd Floor 2 EA 2nd Floor 600 SF 2nd Floor 10 EA 2nd Floor 983 SF 2nd Floor 1 EA 2nd Floor 1 EA 2nd Floor 1 EA 2nd Floor 14 EA 2nd Floor 14 EA 2nd Floor 16 SF 2nd Floor 16 SF 2nd Floor 1 EA 2nd Floor 1 EA 2nd Floor 15 EA 2nd Floor 15 EA 2nd Floor 15 EA 2nd Floor 15 EA 2nd Floor 792 SF 2nd F	1st Floor 15 LF 6 1st Floor 1 EA 6 1st Floor 1 EA 6 1st Floor 11 SF 6 1st Floor 13 EA 7 1st Floor 13 EA 7 1st Floor 1,190 SF 6 2nd Floor 2 EA 6 2nd Floor 2 EA 6 2nd Floor 2 EA 6 2nd Floor 10 EA 7 2nd Floor 983 SF 6 2nd Floor 1 EA 7 2nd Floor 1 EA 7 2nd Floor 1 EA 7 2nd Floor 3 LF 7 2nd Floor 3 LF 7 2nd Floor 4 EA 7 2nd Floor 5 5 6 2nd Floor 1 EA 6 2nd Floor 1 EA 6	1st Floor 15 LF 6 \$379 1st Floor 667 SF 6 \$2,003 1st Floor 1 EA 6 \$301 1st Floor 11 SF 6 \$186 1st Floor 13 EA 7 \$0 1st Floor 13 EA 7 \$0 1st Floor 600 SF 6 \$1,802 2nd Floor 600 SF 6 \$8,883 2nd Floor 600 SF 6 \$4,230 2nd Floor 983 SF 6 \$4,230 2nd Floor 10 EA 7 \$0 2nd Floor 735 SF 6 \$2,207 2nd Floor 74 EA 7 \$0

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #202 (Regular Classroom)						
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	792	SF	6	\$5,912	
Classro	oom #203 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	520	SF	6	\$1,562	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	520	SF	6	\$1,138	
	Lighting - Lay-in	2nd Floor	3	EA	6	\$357	Relamp
	Lighting - Lay-in	2nd Floor	8	EΑ	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Walls - Masonry	2nd Floor	256	SF	6	\$805	
	Walls - Metal Panel	2nd Floor	649	SF	6	\$4,845	
Classro	oom #204 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	900	SF	6	\$2,703	
	Doors - Steel Doors incl hw	2nd Floor	4	EΑ	6	\$1,204	
	Floor - Tile	2nd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	2nd Floor	16	EΑ	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Storage/ Closet	2nd Floor	32	SF	6	\$232	
	Walls - Metal Panel	2nd Floor	808	SF	6	\$6,031	
Classro	oom #205 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	2nd Floor	892	SF	6	\$2,679	
	Chalk Board	2nd Floor	8	LF	4	\$734	Remove/replace with marker board
	Doors - Steel Doors incl hw	2nd Floor	1	EΑ	7	\$0	
	Floor - Tile	2nd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	2nd Floor	3	EΑ	6	\$357	Relamp
	Lighting - Lay-in	2nd Floor	15	EΑ	7	\$0	
	Walls - Metal Panel	2nd Floor	795	SF	6	\$5,934	
Classro	oom #206 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	32	SF	5	\$255	
	Ceiling - Lay-in	2nd Floor	868	SF	6	\$2,607	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	2nd Floor	4	EA	6	\$476	Relamp
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	om #206 (Regular Classroom)		•				
	Marker Board	2nd Floor	10	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	795	SF	6	\$5,934	
Noor-	om #207 (Bogulor Classes						
iassro	om #207 (Regular Classroom)	O. J. Flance		05		#00	
	Ceiling - Lay-in	2nd Floor	4	SF	5	\$32	
	Ceiling - Lay-in	2nd Floor	896	SF	6	\$2,691	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	900	SF	6	\$1,969	
	Lighting - Lay-in	2nd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	2nd Floor	17	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	795	SF	6	\$5,934	
lassro	om #208 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	2nd Floor	727	SF	6	\$2,183	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	2nd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	•
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	792	SF	6	\$5,912	
lassro	om #209 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	16	SF	5	\$128	
	Ceiling - Lay-in	2nd Floor	719	SF	6	\$2,159	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	792	SF	6	\$5,912	
:lassro	om #210 (Regular Classroom)					,	
	Ceiling - Lay-in	2nd Floor	32	SF	5	\$255	
	Ceiling - Lay-in	2nd Floor	703	SF	6	\$2,111	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	2nd Floor	733	EA	6		Relamp
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	πειαιτιρ
	Eighting - Lay-III	ZHUTIOOI	14	LA	,	φυ	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #210 (Regular Classroom)						
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	545	SF	6	\$4,068	
Classro	oom #212 (Office)						
	Ceiling - Lay-in	2nd Floor	492	SF	6	\$1,477	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	492	SF	6	\$1,076	
	Lighting - Lay-in	2nd Floor	4	EA	6	\$476	Relamp
	Lighting - Lay-in	2nd Floor	8	EA	7	\$0	
	Walls - Metal Panel	2nd Floor	716	SF	6	\$5,345	Baseboard pulling apart
Classro	oom #213 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	492	SF	6	\$1,477	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	492	SF	6	\$1,076	
	Lighting - Lay-in	2nd Floor	2	EA	6	\$238	Relamp
	Lighting - Lay-in	2nd Floor	10	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	6	SF	5	\$240	
	Walls - Metal Panel	2nd Floor	710	SF	6	\$5,300	
Classro	oom #214 (Other Instructional Use)						
	Ceiling - Lay-in	2nd Floor	475	SF	6	\$1,426	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Wood	2nd Floor	475	SF	6	\$3,349	
	Lighting - Lay-in	2nd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	2nd Floor	11	EA	7	\$0	
	Walls - Metal Panel	2nd Floor	865	SF	6	\$6,457	
Classro	oom #215 (Regular Classroom)						
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	2nd Floor	484	SF	6	\$1,453	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	492	SF	6	\$1,076	
	Lighting - Lay-in	2nd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	2nd Floor	9	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Walls - Metal Panel	2nd Floor	716	SF	6	\$5,345	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	nom #218 (Regular Classroom)		y			0000	
	Ceiling - Lay-in	2nd Floor	96	SF	5	\$766	
	Ceiling - Lay-in	2nd Floor	1,388	SF	6	\$4,168	
	Doors - Steel Doors incl hw	2nd Floor	2	EA	7	\$0	
	Floor - Tile	2nd Floor	1,484	SF	6	\$3,247	
	Lighting - Lay-in	2nd Floor	3	EA	6	\$357	Relamp
	Lighting - Lay-in	2nd Floor	26	EA	7	\$0	
	Walls - Masonry	2nd Floor	242	SF	6	\$761	
	Walls - Metal Panel	2nd Floor	578	SF	6	\$4,315	
	Walls - Plaster/Drywall	2nd Floor	15	SF	4	\$151	Drywall damage at pier
Classro	oom #220 (Special Program)						
	Ceiling - Lay-in	2nd Floor	32	SF	5	\$255	
	Ceiling - Lay-in	2nd Floor	928	SF	6	\$2,787	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	960	SF	6	\$2,100	
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	1	EA	6	\$119	Relamp
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Masonry	2nd Floor	393	SF	6	\$1,236	
	Walls - Metal Panel	2nd Floor	865	SF	6	\$6,457	
Classro	oom #222B (Computer Lab)						
	Ceiling - Lay-in	2nd Floor	20	SF	5	\$160	
	Ceiling - Lay-in	2nd Floor	265	SF	6	\$796	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0	
	Floor - Carpet	2nd Floor	285	SF	6	\$607	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Walls - Metal Panel	2nd Floor	521	SF	6	\$3,889	
	Walls - Plaster/Drywall	2nd Floor	148	SF	6	\$408	
	Wireless System	2nd Floor	1	EA	7	\$0	
Classro	oom #222C (Computer Lab)						
	Ceiling - Lay-in	2nd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	2nd Floor	292	SF	6	\$877	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Carpet	2nd Floor	300	SF	6	\$639	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Walls - Metal Panel	2nd Floor	688	SF	6	\$5,136	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Caling - Layin	Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Caling - Lay-in Dark Dar	Classro	oom #228 (Computer Lab)						
Doors - Sheel Doors incl hw		Ceiling - Lay-in	2nd Floor	2,086	SF	6	\$6,264	
Floor - Tile		Ceiling - Lay-in	2nd Floor	88	SF	5	\$702	
Lightling - Lay-in		Doors - Steel Doors incl hw	2nd Floor	2	EA	7	\$0	
Lighting - Lay-in 2nd Floor 148 EA 6 \$5,830 Storage Closet 2nd Floor 160 170 180 180 180 Walls - Concrete Block 2nd Floor 160 180 187 6 1824 Walls - Masonny 2nd Floor 408 187 6 1828 Walls - Masonny 2nd Floor 408 187 6 1828 Wireless System 2nd Floor 187 187 7 180 Wireless System 2nd Floor 180 180 180 180 Wireless System 2nd Floor 180 180 180 180 Celling - Lay-in 2nd Floor 1,350 187 180 Lighting - Lay-in 2nd Floor 1,350 187 180 Lighting - Lay-in 2nd Floor 1,350 187 180 Lighting - Lay-in 2nd Floor 1,350 187 180 Storage Closet 2nd Floor 1,350 187 180 Lighting - Lay-in 2nd Floor 1,350 187 180 Storage Closet 2nd Floor 1,350 187 180 Walls - Masonny 2nd Floor 10 180 187 180 Walls - Masonny 2nd Floor 270 280 287 180 Walls - Meat Panel 2nd Floor 218 187 180 Wireless System 2nd Floor 218 187 180 Celling - Lay-in 3rd Floor 40 187 180 Celling - Lay-in 3rd Floor 180 180 180 Walls - Meat Panel 3rd Floor 180 180 180 Walls - Meat Panel 3rd Floor 180 180 180 Celling - Lay-in 3rd Floor 180 180 180 Celling - Lay-in 3rd Floor 180 180 180 Celling - Lay-in 3rd Floor 180 Celling - La		Floor - Tile	2nd Floor	2,174	SF	6	\$4,756	
Storage/ Closet 2nd Floor 126 5F 6 \$9.14		Lighting - Lay-in	2nd Floor	3	EA	6	\$357	Relamp
Walls - Concrete Block 2nd Floor 496 SF 6 \$5.75 Walls - Mesonry 2nd Floor 496 SF 6 \$1.28 Walls - Metail Panel 2nd Floor 437 SF 6 \$3.262 Wireless System 2nd Floor 437 SF 6 \$3.262 Celling - Lay-in 2nd Floor 1.350 SF 5 \$8.031 water stain/damage throughout Celling - Lay-in 2nd Floor 1.250 SF 5 \$8.031 water stain/damage throughout Poor - Carpet 2nd Floor 1.250 SF 6 \$8.031 water stain/damage throughout Lighting - Lay-in 2nd Floor 1.250 SF 6 \$8.031 water stain/damage throughout Walls - Masonny 2nd Floor 1.26 4 7 \$0 Walls - Masonny 2nd Floor 737 SF 6 \$2.319 Walls - Masonny 2nd Floor 73 SF 6 \$2.02 Celi		Lighting - Lay-in	2nd Floor	49	EA	6	\$5,830	
Walls - Masonry 2nd Floor 438 8F 6 \$1,284 Walls - Metal Panel 2nd Floor 437 8F 6 \$3,262 Walls - Metal Panel 2nd Floor 1 85 7 8 8 Celling - Lay-in 2nd Floor 1,350 8F 5 \$3,031 Core - Steel Doors ind hw 2nd Floor 1,350 8F 5 \$3,031 Gard Floor 2 8A 7 \$5 Floor - Carpet 2nd Floor 1,350 8F 6 \$2,2876 Lighting - Lay-in 2nd Floor 1,350 8F 6 \$2,2876 Lighting - Lay-in 2nd Floor 1,350 8F 6 \$2,2876 Lighting - Lay-in 2nd Floor 1,350 8F 6 \$2,207 Lighting - Lay-in 2nd Floor 737 8F 6 \$2,202 Walls - Masonry 2nd Floor 737 8F 6 \$2,202 Walls - Matal Panel 2nd Floor 298 8F 6 \$2,202 Wireless System 3rd Floor 40 8F 5 \$3,319 Celling - Lay-in 3rd Floor 40 8F 5 \$3,319 Celling - Lay-in 3rd Floor 40 8F 5 \$3,319 Celling - Lay-in 3rd Floor 40 8F 5 \$3,08 Celling - Lay-in 3rd Floor 40 8F 5 \$3,08 Celling - Lay-in 3rd Floor 40 8F 6 \$1,608 Floor - Tile 3rd Floor 47 8F 6 \$1,608 Marker Board 3rd Floor 47 8F 6 \$1,608 Celling - Lay-in 3rd Floor 48 8F 6 \$1,608 Walls - Matal Panel 3rd Floor 48 8F 6 \$1,608 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Marker Board 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Floor 48 8F 6 \$2,007 Celling - Lay-in 3rd Fl		Storage/ Closet	2nd Floor	126	SF	6	\$914	
Malls - Metal Panel 2nd Floor 437 5F 6 \$3.262 Wireless System 2nd Floor 1,500 5F 5 \$8.031 Celling - Lay-in 2nd Floor 2nd Floor 26 5F 7 \$00 Classroom#230 (Regular Classroom 2nd Floor 2n		Walls - Concrete Block	2nd Floor	196	SF	6	\$575	
Mireless System		Walls - Masonry	2nd Floor	408	SF	6	\$1,284	
Celling - Lay-in 2nd Floor 1,350 SF 5 \$8,031 water stain/damage throughout		Walls - Metal Panel	2nd Floor	437	SF	6		
Ceiling - Lay-in 2nd Floor 1,350 SF 5 \$8,031 water stain/damage throughout Doors - Steel Doors incl hw 2nd Floor 2 EA 7 \$0 Floor - Carpet 2nd Floor 1,350 SF 6 \$2,876 Lighting - Lay-in 2nd Floor 26 EA 7 \$0 Lighting - Lay-in 2nd Floor 266 SF 6 \$1,190 Relamp Storage/ Closet 2nd Floor 266 SF 6 \$1,290 Relamp Walls - Masonry 2nd Floor 295 SF 6 \$2,219 Walls - Metal Panel 2nd Floor 295 SF 6 \$2,202 Wireless System 2nd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 735 SF 6 \$1,6		Wireless System	2nd Floor	1	EA	7	\$0	
Ceiling - Lay-in 2nd Floor 1,350 SF 5 \$8,031 water stain/damage throughout Doors - Steel Doors incl hw 2nd Floor 2 EA 7 \$0 Floor - Carpet 2nd Floor 1,350 SF 6 \$2,876 Lighting - Lay-in 2nd Floor 26 EA 7 \$0 Lighting - Lay-in 2nd Floor 266 SF 6 \$1,190 Relamp Storage/ Closet 2nd Floor 266 SF 6 \$1,290 Relamp Walls - Masonry 2nd Floor 295 SF 6 \$2,219 Walls - Metal Panel 2nd Floor 295 SF 6 \$2,202 Wireless System 2nd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 735 SF 6 \$1,6	Classro	oom #230 (Computer Lab)						
Doors - Steel Doors incl hw			2nd Floor	1,350	SF	5	\$8,031	water stain/damage throughout
Floor - Carpet			2nd Floor		EA			
Lighting - Lay-in 2nd Floor 10 EA 6 \$1,190 Relamp Storaged Closet 2nd Floor 266 SF 6 \$1,929 Walls - Masonry 2nd Floor 295 SF 6 \$2,319 Walls - Metal Panel 2nd Floor 295 SF 6 \$2,202 Wireless System 2nd Floor 1 EA 7 \$0 Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 695 SF 6 \$2,087 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 3rd Floor 54 SF 6 \$1,608 Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Cei		Floor - Carpet	2nd Floor	1,350	SF	6		
Lighting - Lay-in 2nd Floor 10 EA 6 \$1,190 Relamp Storage/ Closet 2nd Floor 266 SF 6 \$1,929 Walls - Masonry 2nd Floor 737 SF 6 \$2,319 Walls - Metal Panel 2nd Floor 295 SF 6 \$2,202 Wireless System 2nd Floor 1 EA 7 \$0 Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 695 SF 6 \$2,087 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 545 SF 6 \$1,608 Valles - Metal Panel 3rd Floor 735 SF 6 \$2,207 Ceiling - Lay-in		Lighting - Lay-in	2nd Floor	26	EA	7	\$0	
Walls - Masonry 2nd Floor 737 SF 6 \$2,319 Walls - Metal Panel 2nd Floor 295 SF 6 \$2,202 Wireless System 2nd Floor 1 EA 7 \$0 Caling - Lay-in 3rd Floor 40 SF 5 \$319 Celling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 15 EA 7 \$0 Lighting - Lay-in 3rd Floor 10 LF 7 \$0 Walls - Metal Panel 3rd Floor 545 SF 6 \$4,068 Classroom #301 (Regular Classroom) Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 735 SF 6 \$2,207 Clighting - Lay-in 3rd Floor 1 EA 7			2nd Floor	10	EΑ	6	\$1,190	Relamp
Walls - Metal Panel 2nd Floor 295 SF 6 \$2,202 Wireless System 2nd Floor 1 EA 7 \$0 Calsarsoom/300 (Regular Classroom) Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 15 EA 7 \$0 Walls - Metal Panel 3rd Floor 10 LF 7 \$0 Caling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 735 SF 6 \$2,207 Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 735 SF 6 \$1,6		Storage/ Closet	2nd Floor	266	SF	6	\$1,929	
Vireless System 2nd Floor 1 EA 7 \$0		Walls - Masonry	2nd Floor	737	SF	6	\$2,319	
Classroom #300 (Regular Classroom) Celling - Lay-in 3rd Floor 40 SF 5 \$319 Celling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 10 LF 7 \$0 Valls - Metal Panel 3rd Floor 545 SF 6 \$4,068 Classroom #301 (Regular Classroom) Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor <td< td=""><td></td><td>Walls - Metal Panel</td><td>2nd Floor</td><td>295</td><td>SF</td><td>6</td><td>\$2,202</td><td></td></td<>		Walls - Metal Panel	2nd Floor	295	SF	6	\$2,202	
Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 15 EA 7 \$0 Lighting - Lay-in 3rd Floor 10 LF 7 \$0 Marker Board 3rd Floor 545 SF 6 \$4,068 Classroom #301 (Regular Classroom) Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 735 SF 6 \$2,207 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 735 SF 6 \$1,608 Marker Board 3rd Floor 8 LF 7 \$0		Wireless System	2nd Floor	1	EA	7	\$0	
Ceiling - Lay-in 3rd Floor 40 SF 5 \$319 Ceiling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 15 EA 7 \$0 Lighting - Lay-in 3rd Floor 10 LF 7 \$0 Marker Board 3rd Floor 545 SF 6 \$4,068 Classroom #301 (Regular Classroom) Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 735 SF 6 \$2,207 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 735 SF 6 \$1,608 Marker Board 3rd Floor 8 LF 7 \$0	Classro	oom #300 (Regular Classroom)						
Ceiling - Lay-in 3rd Floor 695 SF 6 \$2,087 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 10 LF 7 \$0 Walls - Metal Panel 3rd Floor 545 SF 6 \$4,068 Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 18 LF 7 \$0		· · ·	3rd Floor	40	SF	5	\$319	
Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 10 LF 7 \$0 Walls - Metal Panel 3rd Floor 545 SF 6 \$4,068 Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 14 EA 7 \$0			3rd Floor	695	SF	6	\$2,087	
Lighting - Lay-in 3rd Floor 15 EA 7 \$0 Marker Board 3rd Floor 10 LF 7 \$0 Walls - Metal Panel 3rd Floor 545 SF 6 \$4,068 Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 8 LF 7 \$0			3rd Floor	1	EA	7	\$0	
Marker Board Walls - Metal Panel 3rd Floor 10 545 LF 8F 7 6 \$0 84,068 Classroom #301 (Regular Classroom) Ceiling - Lay-in Doors - Steel Doors incl hw 3rd Floor 3rd Floor 735 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		Floor - Tile	3rd Floor	735	SF	6	\$1,608	
Walls - Metal Panel 3rd Floor 545 SF 6 \$4,068 Classroom #301 (Regular Classroom) Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 8 LF 7 \$0		Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
Classroom #301 (Regular Classroom) Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 8 LF 7 \$0		Marker Board	3rd Floor	10	LF	7	\$0	
Ceiling - Lay-in 3rd Floor 735 SF 6 \$2,207 Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 8 LF 7 \$0		Walls - Metal Panel	3rd Floor	545	SF	6	\$4,068	
Doors - Steel Doors incl hw 3rd Floor 1 EA 7 \$0 Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 8 LF 7 \$0	Classro	oom #301 (Regular Classroom)						
Floor - Tile 3rd Floor 735 SF 6 \$1,608 Lighting - Lay-in 3rd Floor 14 EA 7 \$0 Marker Board 3rd Floor 8 LF 7 \$0		Ceiling - Lay-in	3rd Floor	735	SF	6	\$2,207	
Lighting - Lay-in3rd Floor14 EA 7\$0Marker Board3rd Floor8 LF 7\$0		Doors - Steel Doors incl hw	3rd Floor	1	EΑ	7	\$0	
Marker Board 3rd Floor 8 LF 7 \$0		Floor - Tile	3rd Floor	735	SF	6	\$1,608	
Marker Board 3rd Floor 8 LF 7 \$0		Lighting - Lay-in	3rd Floor	14	EA	7		
			3rd Floor	8	LF	7		
		Walls - Metal Panel	3rd Floor	792	SF	6	\$5,912	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #301 (Regular Classroom)						
Classroom #302 (Regular Classroom)						
Ceiling - Lay-in	3rd Floor	735	SF	6	\$2,207	
Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
Floor - Tile	3rd Floor	735	SF	6	\$1,608	
Lighting - Lay-in	3rd Floor	2	EA	6	\$238	Relamp
Lighting - Lay-in	3rd Floor	13	EA	7	\$0	
Marker Board	3rd Floor	8	LF	7	\$0	
Walls - Metal Panel	3rd Floor	792	SF	6	\$5,912	
Classroom #304 (Regular Classroom)						
Ceiling - Lay-in	3rd Floor	899	SF	6	\$2,700	
Doors - Steel Doors incl hw	3rd Floor	4	EA	7	\$0	
Floor - Tile	3rd Floor	899	SF	6	\$1,967	
Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
Marker Board	3rd Floor	12	LF	7	\$0	
Storage/ Closet	3rd Floor	40	SF	6	\$290	
Walls - Metal Panel	3rd Floor	792	SF	6	\$5,912	
Classroom #305 (Computer Lab)						
Ceiling - Lay-in	3rd Floor	810	SF	6	\$2,432	
Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
Floor - Tile	3rd Floor	810	SF	6	\$1,772	
Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
Marker Board	3rd Floor	12	LF	7	\$0	
Walls - Metal Panel	3rd Floor	768	SF	6	\$5,733	
Wireless System	3rd Floor	1	EA	7	\$0	
Classroom #306 (Computer Lab)						
Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	
Ceiling - Lay-in	3rd Floor	802	SF	6	\$2,408	
Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
Floor - Tile	3rd Floor	810	SF	6	\$1,772	
Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
Marker Board	3rd Floor	12	LF	7	\$0	
Walls - Metal Panel	3rd Floor	768	SF	6	\$5,733	
Wireless System	3rd Floor	1	EA	7	\$0	
Classroom #307 (Regular Classroom)						
Ceiling - Lay-in	3rd Floor	810	SF	6	\$2,432	
VOLING HS	Dogo FO	of 102				Accessment Date: 0/14/15

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #307 (Regular Classroom)						
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	810	SF	6	\$1,772	
	Lighting - Lay-in	3rd Floor	2	EA	6	\$238	Relamp
	Lighting - Lay-in	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	10	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	768	SF	6	\$5,733	
Classro	oom #308 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	3rd Floor	727	SF	6	\$2,183	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	3rd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	5	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	792	SF	6	\$5,912	
Classro	oom #309 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	735	SF	6	\$2,207	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	3rd Floor	15	EA	6	\$1,785	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	792	SF	6	\$5,912	
Classro	oom #310 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	4	SF	5	\$32	
	Ceiling - Lay-in	3rd Floor	731	SF	6	\$2,195	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	735	SF	6	\$1,608	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	509	SF	6	\$3,799	
	Walls - Plaster/Drywall	3rd Floor	35	SF	6	\$97	Piers
	Walls - Plaster/Drywall	3rd Floor	1	SF	5	\$5	Drywall damage at corner pier; Two windows will not close
Classro	oom #312 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	40	SF	5	\$319	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classr	oom #312 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	455	SF	6	\$1,366	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile/Sheet	3rd Floor	495	SF	6	\$495	
	Lighting - Lay-in	3rd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	3rd Floor	11	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	716	SF	6	\$5,345	
Classr	oom #313 (Special Education)						
	Ceiling - Lay-in	3rd Floor	56	SF	5	\$388	
	Ceiling - Lay-in	3rd Floor	439	SF	6	\$1,318	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	495	SF	6	\$1,083	
	Lighting - Lay-in	3rd Floor	2	EA	6	\$238	Relamp
	Lighting - Lay-in	3rd Floor	7	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	716	SF	6	\$5,345	
Classr	oom #314 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	495	SF	6	\$1,486	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	495	SF	6	\$1,083	
	Lighting - Lay-in	3rd Floor	5	EA	6	\$595	Relamp
	Lighting - Lay-in	3rd Floor	8	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	716	SF	6	\$5,345	
Classr	oom #315 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	16	SF	5	\$128	
	Ceiling - Lay-in	3rd Floor	479	SF	6	\$1,438	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	495	SF	6	\$1,083	
	Lighting - Lay-in	3rd Floor	4	EA	6	\$476	Relamp
	Lighting - Lay-in	3rd Floor	8	EA	7	\$0	
	Marker Board	3rd Floor	18	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	716	SF	6	\$5,345	
Classr	oom #316 (Science Lab Level 3)						
	Ceiling - Lay-in	3rd Floor	1,124	SF	6	\$3,375	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #316 (Science Lab Level 3)						
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile	3rd Floor	5	SF	4	\$65	damaged tile
	Floor - Tile	3rd Floor	1,121	SF	6	\$2,453	
	Gas Line	3rd Floor	24	EA	6	\$12,219	
	Lighting - Lay-in	3rd Floor	2	EA	6	\$238	Relamp
	Lighting - Lay-in	3rd Floor	46	EA	7	\$0	
	Marker Board	3rd Floor	6	LF	7	\$0	
	Science Lab Elements	3rd Floor	1,124	SF	6	\$7,619	
	Storage/ Closet	3rd Floor	650	SF	6	\$4,713	
	Walls - Concrete Block	3rd Floor	289	SF	6	\$847	
	Walls - Masonry	3rd Floor	529	SF	6	\$1,664	
	Walls - Metal Panel	3rd Floor	289	SF	6	\$2,157	
	Walls - Plaster/Drywall	3rd Floor	41	SF	6	\$113	Piers
	Work Sink	3rd Floor	7	EA	6	\$2,653	
Classro	oom #318 (Science Lab Level 1)						
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	16	SF	5	\$128	
	Ceiling - Lay-in	3rd Floor	1,156	SF	6	\$3,471	
	Doors - Side-lite	3rd Floor	640	SF	6	\$10,699	Window wall
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Doors - Transom Window	3rd Floor	6	SF	7	\$0	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	12	SF	5	\$54	
	Floor - Tile/Sheet	3rd Floor	1,160	SF	6	\$1,161	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	22	EA	6	\$11,201	
	Lighting - Lay-in	3rd Floor	46	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Science Lab Elements	3rd Floor	1,172	SF	6	\$7,944	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Masonry	3rd Floor	413	SF	6	\$1,299	
	Walls - Metal Panel	3rd Floor	310	SF	6	\$2,314	
	Walls - Plaster/Drywall	3rd Floor	3	SF	5	\$15	Drywall damage @ pier
	Walls - Plaster/Drywall	3rd Floor	80	SF	6	\$221	Piers
	Work Sink	3rd Floor	10	EA	5	\$15,078	Not secure - wiggle; leak and blow fuses

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

			0	Rank	CUSI	Comments
m #319 (Science Lab Level 1)						
Ceiling - Lay-in	3rd Floor	576	SF	6	\$1,730	
Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
Floor - Tile	3rd Floor	576	SF	6	\$1,260	
Gas Line	3rd Floor	4	EA	6	\$2,036	
Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
Marker Board	3rd Floor	20	LF	7	\$0	
Science Lab Elements	3rd Floor	576	SF	6	\$3,904	
Walls - Concrete Block	3rd Floor	362	SF	6	\$1,061	
Walls - Metal Panel	3rd Floor	671	SF	6	\$5,009	
Work Sink	3rd Floor	1	EA	6	\$379	
m #320 (Science Lab Level 1)						
Casework	3rd Floor	22	LF	6	\$556	
Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	
Ceiling - Lay-in	3rd Floor	1,188	SF	6	\$3,568	
Doors - Side-lite	3rd Floor	125	SF	6	\$2,090	
Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
Doors - Transom Window	3rd Floor	12	SF	7	\$0	
Eye Wash Station	3rd Floor	1	EA	6	\$336	
Floor - Tile	3rd Floor	8	SF	4	\$104	missing
Floor - Tile	3rd Floor	1,188	SF	6	\$2,599	
Fume Hood	3rd Floor	1	EA	6	\$816	
Gas Line	3rd Floor	30	EA	6	\$15,274	
Lighting - Lay-in	3rd Floor	1	EA	6	\$119	Relamp
Lighting - Lay-in	3rd Floor	43	EA	7	\$0	
Marker Board	3rd Floor	8	LF	7	\$0	
Science Lab Elements	3rd Floor	1,196	SF	6	\$8,107	
Science Lab Shower	3rd Floor	1	EA	6	\$379	
Walls - Metal Panel	3rd Floor	703	SF	6	\$5,248	
Walls - Plaster/Drywall	3rd Floor	352	SF	6	\$971	
Work Sink	3rd Floor	12	EA	6	\$4,548	
m #321 (Regular Classroom)						
Ceiling - Lay-in	3rd Floor	576	SF	6	\$1,730	
Doors - Steel Doors incl hw	3rd Floor	2	EA	7	\$0	
Floor - Tile	3rd Floor	576	SF	6	\$1,260	
Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
Marker Board	3rd Floor	20	LF	7	\$0	
	Doors - Steel Doors incl hw Floor - Tile Gas Line Lighting - Lay-in Marker Board Science Lab Elements Walls - Concrete Block Walls - Metal Panel Work Sink m #320 (Science Lab Level 1) Casework Ceiling - Lay-in Ceiling - Lay-in Doors - Side-lite Doors - Steel Doors incl hw Doors - Transom Window Eye Wash Station Floor - Tile Floor - Tile Fume Hood Gas Line Lighting - Lay-in Marker Board Science Lab Elements Science Lab Shower Walls - Metal Panel Walls - Plaster/Drywall Work Sink m #321 (Regular Classroom) Ceiling - Lay-in Doors - Steel Doors incl hw Floor - Tile	Doors - Steel Doors incl hw 3rd Floor Floor - Tile 3rd Floor Gas Line 3rd Floor Lighting - Lay-in 3rd Floor Marker Board 3rd Floor Science Lab Elements 3rd Floor Walls - Concrete Block 3rd Floor Walls - Metal Panel 3rd Floor Work Sink 3rd Floor m#320 (Science Lab Level 1) Casework 3rd Floor Ceiling - Lay-in 3rd Floor Coors - Side-lite 3rd Floor Doors - Steel Doors incl hw 3rd Floor Doors - Steel Doors incl hw 3rd Floor Doors - Transom Window 3rd Floor Eye Wash Station 3rd Floor Floor - Tile 3rd Floor Floor - Tile 3rd Floor Floor - Tile 3rd Floor Furne Hood 3rd Floor Gas Line 3rd Floor Lighting - Lay-in 3rd Floor Marker Board 3rd Floor Science Lab Elements 3rd Floor Science Lab Shower	Doors - Steel Doors incl hw 3rd Floor 1 Floor - Tile 3rd Floor 576 Gas Line 3rd Floor 12 Marker Board 3rd Floor 20 Science Lab Elements 3rd Floor 576 Walls - Concrete Block 3rd Floor 362 Walls - Metal Panel 3rd Floor 671 Work Sink 3rd Floor 1 w #320 (Science Lab Level 1) 22 Celling - Lay-in 3rd Floor 22 Celling - Lay-in 3rd Floor 18 Celling - Lay-in 3rd Floor 125 Doors - Side-lite 3rd Floor 125 Doors - Steel Doors incl hw 3rd Floor 12 Doors - Steel Doors incl hw 3rd Floor 1 Doors - Transom Window 3rd Floor 1 Eye Wash Station 3rd Floor 1 Floor - Tile 3rd Floor 1 Floor - Tile 3rd Floor 1 Gas Line 3rd Floor 1 Lighting - Lay-in	Doors - Steel Doors incl hw 3rd Floor 1 EA Floor - Tille 3rd Floor 576 SF Gas Line 3rd Floor 12 EA Lighting - Lay-in 3rd Floor 12 EA Marker Board 3rd Floor 576 SF Science Lab Elements 3rd Floor 362 SF Walls - Oncrete Block 3rd Floor 362 SF Walls - Metal Panel 3rd Floor 671 SF Work Sink 3rd Floor 671 SF Work Sink 3rd Floor 2 LF Ceiling - Lay-in 3rd Floor 2 LF Ceiling - Lay-in 3rd Floor 12 SF Ceiling - Lay-in 3rd Floor 125 SF Doors - Side-lite 3rd Floor 12 SF Doors - Steel Doors incl hw 3rd Floor 12 SF Eye Wash Station 3rd Floor 1 EA Eloor - Tile 3rd Floor 1 EA	Doors - Steel Doors inch hw 3rd Floor 1 EA 7 Floor - Tille 3rd Floor 576 576 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 12 EA 7 7 A 6 6 6 6 6 12 EA 7 7 Marker Board 3rd Floor 3rd Floor 20 LF 7 5 6 6 12 EA 7 7 Marker Board 3rd Floor 3rd Floor 20 LF 7 5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	Doors - Steel Doors incl hw 3rd Floor 1

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classr	oom #321 (Regular Classroom)						
	Walls - Concrete Block	3rd Floor	168	SF	6	\$492	
	Walls - Masonry	3rd Floor	142	SF	6	\$447	
	Walls - Metal Panel	3rd Floor	310	SF	6	\$2,314	
Classr	oom #322 (Science Lab Level 1)						
	Casework	3rd Floor	126	LF	6	\$3,182	
	Ceiling - Lay-in	3rd Floor	1,116	SF	6	\$3,351	
	Doors - Steel Doors incl hw	3rd Floor	2	EA	7	\$0	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,116	SF	6	\$1,117	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	41	EA	6	\$20,874	
	Lighting - Lay-in	3rd Floor	22	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Science Lab Elements	3rd Floor	1,116	SF	6	\$7,564	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Plaster/Drywall	3rd Floor	1,033	SF	6	\$2,851	
	Work Sink	3rd Floor	11	EA	6	\$4,169	
Classr	oom #326 (Science Lab Level 1)						
	Casework	3rd Floor	120	LF	6	\$3,030	
	Ceiling - Lay-in	3rd Floor	1,196	SF	6	\$3,592	
	Doors - Steel Doors incl hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	3rd Floor	1,196	SF	6	\$1,197	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	32	EA	6	\$16,292	
	Lighting - Lay-in	3rd Floor	3	EA	6		Relamp
	Lighting - Lay-in	3rd Floor	42	EA	7	\$0	·
	Marker Board	3rd Floor	16	LF	7	\$0	
	Science Lab Elements	3rd Floor	1,196	SF	6	\$8,107	
	Science Lab Shower	3rd Floor	1	EA	6	\$379	
	Walls - Metal Panel	3rd Floor	703	SF	6	\$5,248	
	Walls - Plaster/Drywall	3rd Floor	352	SF	6	\$971	
	Work Sink	3rd Floor	12	EA	6	\$4,548	
Classr	oom #327 (Science Lab Level 3)						
	Ceiling - Lay-in	3rd Floor	576	SF	6	\$1,730	
	Chalk Board	3rd Floor	15	LF	4	\$1,377	Remove/replace with marker board
VOLINI	0.110	Dogo 64 of	100				Accomment Date: 0/14/14

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comment
_	oom #327 (Science Lab Level 3)						
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	576	SF	6	\$1,260	
	Gas Line	3rd Floor	4	EA	6	\$2,036	
	Lighting - Lay-in	3rd Floor	1	EA	6		Relamp
	Lighting - Lay-in	3rd Floor	11	EA	7	\$0	•
	Science Lab Elements	3rd Floor	576	SF	6	\$3,904	
	Walls - Concrete Block	3rd Floor	310	SF	6	\$909	
	Walls - Metal Panel	3rd Floor	517	SF	6	\$3,859	
	Work Sink	3rd Floor	1	EA	6	\$379	
assr	oom #328 (Science Lab Level 1)						
	Ceiling - Lay-in	3rd Floor	1,172	SF	6	\$3,520	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,172	SF	6	\$2,564	
	Fume Hood	3rd Floor	1	EΑ	6	\$816	
	Gas Line	3rd Floor	20	EΑ	6	\$10,182	
	Lighting - Lay-in	3rd Floor	38	EΑ	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Science Lab Elements	3rd Floor	1,172	SF	6	\$7,944	
	Science Lab Shower	3rd Floor	1	EΑ	6	\$379	
	Walls - Masonry	3rd Floor	250	SF	6	\$787	
	Walls - Metal Panel	3rd Floor	470	SF	6	\$3,508	
	Work Sink	3rd Floor	11	EA	6	\$4,169	
assr	oom #330 (Science Lab Level 1)						
	Casework	3rd Floor	25	LF	6	\$631	
	Ceiling - Lay-in	3rd Floor	1,458	SF	7	\$0	
	Doors - Side-lite	3rd Floor	20	SF	7	\$0	
	Doors - Steel Doors incl hw	3rd Floor	4	EA	6	\$1,204	
	Doors - Transom Window	3rd Floor	18	SF	7	\$0	
	Eye Wash Station	3rd Floor	1	EA	6	\$336	
	Floor - Tile	3rd Floor	1,458	SF	6	\$3,190	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	22	EA	6	\$11,201	
	Lighting - Lay-in	3rd Floor	46	EA	7	\$0	
	Science Lab Elements	3rd Floor	1,131	SF	6	\$7,666	
	Science Lab Shower	3rd Floor	1	EΑ	6	\$379	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classro	oom #330 (Science Lab Level 1)						
	Storage/ Closet	3rd Floor	327	SF	6	\$2,371	330C/D
	Walls - Concrete Block	3rd Floor	290	SF	6	\$850	
	Walls - Masonry	3rd Floor	490	SF	6	\$1,542	
	Walls - Metal Panel	3rd Floor	190	SF	6	\$1,418	
	Work Sink	3rd Floor	10	EA	6	\$3,790	
Classro	oom #341 (Science Lab Level 3)						
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	3rd Floor	568	SF	6	\$1,706	
	Doors - Steel Doors incl hw	3rd Floor	1	EΑ	7	\$0	
	Floor - Tile	3rd Floor	576	SF	6	\$1,260	
	Gas Line	3rd Floor	1	EΑ	6	\$509	Valve - needs new door
	Lighting - Lay-in	3rd Floor	2	EΑ	6	\$238	Relamp
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Marker Board	3rd Floor	24	LF	7	\$0	
	Science Lab Elements	3rd Floor	576	SF	6	\$3,904	
	Walls - Concrete Block	3rd Floor	517	SF	6	\$1,516	
	Walls - Metal Panel	3rd Floor	517	SF	6	\$3,859	
Classro	oom #342 (Science Lab Level 3)						
	Ceiling - Lay-in	3rd Floor	20	SF	5	\$160	
	Ceiling - Lay-in	3rd Floor	845	SF	6	\$2,538	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	865	SF	6	\$1,893	
	Gas Line	3rd Floor	12	EA	6	\$6,109	
	Lighting - Lay-in	3rd Floor	5	EA	6	\$595	Relamp
	Lighting - Lay-in	3rd Floor	30	EΑ	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	2	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Science Lab Elements	3rd Floor	865	SF	6	\$5,863	
	Storage/ Closet	3rd Floor	150	SF	6	\$1,088	
	Walls - Concrete Block	3rd Floor	300	SF	6	\$879	
	Walls - Masonry	3rd Floor	403	SF	6	\$1,268	Brick and mortar
	Walls - Metal Panel	3rd Floor	702	SF	6	\$5,240	
	Work Sink	3rd Floor	5	EA	6	\$1,895	
Classro	oom #344 (Science Classroom)						
	Ceiling - Lay-in	3rd Floor	859	SF	6	\$2,580	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
VOLING	2.110	Dogo 66 of	400				Accomment Date: 0/14/1

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
•	om #344 (Science Classroom)						
	Floor - Tile	3rd Floor	20	SF	5	\$115	
	Floor - Tile	3rd Floor	839	SF	6	\$1,836	
	Lighting - Lay-in	3rd Floor	2	EA	6	\$238	Relamp
	Lighting - Lay-in	3rd Floor	34	EA	7	\$0	
	Marker Board	3rd Floor	6	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	300	SF	6	\$879	
	Walls - Masonry	3rd Floor	310	SF	6	\$975	
	Walls - Metal Panel	3rd Floor	610	SF	6	\$4,553	
assro	om #345 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	3rd Floor	568	SF	6	\$1,706	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	576	SF	6	\$1,260	
	Lighting - Lay-in	3rd Floor	2	EA	6	\$238	Relamp
	Lighting - Lay-in	3rd Floor	10	EA	7	\$0	
	Marker Board	3rd Floor	14	LF	7	\$0	
	Walls - Concrete Block	3rd Floor	207	SF	6	\$607	
	Walls - Metal Panel	3rd Floor	516	SF	6	\$3,852	
	Walls - Plaster/Drywall	3rd Floor	310	SF	6	\$856	
assro	om #347 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	723	SF	6	\$2,171	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	723	SF	6	\$724	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	845	SF	6	\$6,308	
ssro	om #348 (Regular Classroom)						
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	
	Ceiling - Lay-in	3rd Floor	715	SF	6	\$2,147	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	723	SF	6	\$724	
	Lighting - Lay-in	3rd Floor	1	EA	6	\$119	Relamp
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Metal Panel	3rd Floor	845	SF	6	\$6,308	



211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Category: Classrooms

Group Item - Type Location Quantity Unit Rank Cost Comments

Classrooms Subtotal: \$1,040,415

Building: Main - Building A

Group Item	- Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrativ	e Suites/Offices						
Ceilir	ng - Lay-in	1A	100	SF	6	\$300	
Doors	s - Steel Doors incl hw	1A	1	EA	6	\$301	
Floor	· - Tile	1A	2	SF	5	\$12	
Floor	- Tile	1A	98	SF	6	\$214	
Lighti	ing - Lay-in	1A	4	EA	7	\$0	
Powe	er Distribution	1A	6	EA	7	\$0	
Walls	s - Metal Panel	1A	413	SF	6	\$3,083	
Ceilir	ng - Lay-in	1B	100	SF	6	\$300	
Doors	s - Steel Doors incl hw	1B	1	EA	6	\$301	
Floor	- Tile	1B	100	SF	6	\$219	
Lighti	ing - Lay-in	1B	3	EA	6	\$357	Relamp
Lighti	ing - Lay-in	1B	1	EA	7	\$0	
Powe	er Distribution	1B	6	EA	7	\$0	
Walls	s - Metal Panel	1B	413	SF	6	\$3,083	
Ceilir	ng - Lay-in	1D/2D	200	SF	6	\$601	
Doors	s - Steel Doors incl hw	1D/2D	2	EA	6	\$602	
Floor	· - Tile	1D/2D	200	SF	6	\$438	
Lighti	ing - Lay-in	1D/2D	8	EA	7	\$0	
Powe	er Distribution	1D/2D	8	EA	7	\$0	
Walls	s - Metal Panel	1D/2D	620	SF	6	\$4,628	
Ceilir	ng - Lay-in	224C - Library office	480	SF	6	\$1,441	
Doors	s - Steel Doors incl hw	224C - Library office	1	EA	6	\$301	
Floor	- Carpet	224C - Library office	480	SF	6	\$1,023	
Lighti	ing - Lay-in	224C - Library office	10	EA	7	\$0	
Powe	er Distribution	224C - Library office	20	EA	7	\$0	
Walls	s - Masonry	224C - Library office	197	SF	6	\$620	
Walls	s - Metal Panel	224C - Library office	669	SF	6	\$4,994	
Ceilir	ng - Lay-in	224D - Library office	104	SF	5	\$721	
Ceilir	ng - Lay-in	224D - Library office	621	SF	6	\$1,865	
Doors	s - Steel Doors incl hw	224D - Library office	2	EA	6	\$602	
Floor	- Carpet	224D - Library office	725	SF	6	\$1,545	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Lighting - Lay-in	224D - Library office	15	EA	7	\$0	
	Power Distribution	224D - Library office	16	EA	7	\$0	
	Walls - Masonry	224D - Library office	68	SF	6	\$214	
	Walls - Metal Panel	224D - Library office	747	SF	6	\$5,576	
	Work Slnk	224D - Library office	1	EA	5	\$1,508	Replace hardware
	Ceiling - Lay-in	224E - Media Center/Director's office	24	SF	5	\$192	
	Ceiling - Lay-in	224E - Media Center/Director's office	851	SF	6	\$2,556	
	Doors - Steel Doors incl hw	224E - Media Center/Director's office	1	EA	6	\$301	
	Floor - Wood	224E - Media Center/Director's office	875	SF	6	\$6,169	
	Lighting - Lay-in	224E - Media Center/Director's office	17	EA	7	\$0	
	Power Distribution	224E - Media Center/Director's office	4	EA	7	\$0	
	Walls - Metal Panel	224E - Media Center/Director's office	806	SF	6	\$6,016	
	Ceiling - Lay-in	2A	100	SF	6	\$300	
	Doors - Steel Doors incl hw	2A	1	EA	6	\$301	
	Floor - Tile	2A	100	SF	6	\$219	
	Lighting - Lay-in	2A	4	EA	7	\$0	
	Power Distribution	2A	6	EA	7	\$0	
	Walls - Metal Panel	2A	413	SF	6	\$3,083	
	Ceiling - Lay-in	2B	200	SF	6	\$601	
	Doors - Steel Doors incl hw	2B	1	EA	6	\$301	
	Floor - Tile	2B	200	SF	6	\$438	
	Lighting - Lay-in	2B	2	EA	6	\$238	Relamp
	Lighting - Lay-in	2B	4	EA	7	\$0	
	Power Distribution	2B	8	EA	7	\$0	
	Walls - Metal Panel	2B	620	SF	6	\$4,628	
	Ceiling - Lay-in	2E/2F	290	SF	6	\$871	
	Doors - Steel Doors incl hw	2E/2F	2	EA	6	\$602	
	Floor - Tile	2E/2F	290	SF	6	\$634	
	Lighting - Lay-in	2E/2F	1	EA	6	\$119	Relamp
	Lighting - Lay-in	2E/2F	9	EA	7	\$0	
	Power Distribution	2E/2F	6	EA	7	\$0	
	Walls - Metal Panel	2E/2F	787	SF	6	\$5,875	
	Ceiling - Lay-in	323-325 Science offices	8	SF	5	\$64	
	Ceiling - Lay-in	323-325 Science offices	1,092	SF	6	\$3,279	
	Doors - Steel Doors incl hw	323-325 Science offices	3	EA	7	\$0	
	Doors - Transom Window	323-325 Science offices	12	SF	7	\$0	
	Floor - Carpet	323-325 Science offices	4	SF	5	\$26	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group Iter	m - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrat	tive Suites/Offices						
Flo	oor - Carpet	323-325 Science offices	796	SF	6	\$1,696	
Lig	ghting - Lay-in	323-325 Science offices	3	EA	6	\$357	Relamp
Lig	ghting - Lay-in	323-325 Science offices	17	EA	7	\$0	
Pov	ower Distribution	323-325 Science offices	30	EA	7	\$0	
Sto	orage/ Closet	323-325 Science offices	300	SF	6	\$2,175	
Wa	alls - Concrete Block	323-325 Science offices	165	SF	6	\$484	
Wa	alls - Masonry	323-325 Science offices	248	SF	6	\$780	
Wa	alls - Metal Panel	323-325 Science offices	826	SF	6	\$6,166	
Wo	ork SInk	323-325 Science offices	1	EA	6	\$508	
Cei	eiling - Lay-in	3A	90	SF	6	\$270	
Do	pors - Steel Doors incl hw	3A	1	EA	6	\$301	
Flo	oor - Tile	3A	90	SF	6	\$197	
Lig	ghting - Lay-in	3A	4	EA	7	\$0	
Pov	ower Distribution	3A	6	EA	7	\$0	
Wa	alls - Metal Panel	3A	393	SF	6	\$2,934	
Cei	eiling - Lay-in	3B	90	SF	6	\$270	
Do	pors - Steel Doors incl hw	3B	1	EA	6	\$301	
Flo	oor - Carpet	3B	90	SF	6	\$192	
Lig	ghting - Lay-in	3B	4	EA	7	\$0	
Pov	ower Distribution	3B	6	EA	7	\$0	
Wa	alls - Metal Panel	3B	393	SF	6	\$2,934	
Cei	eiling - Lay-in	3C/4C	200	SF	6	\$601	
Do	oors - Steel Doors incl hw	3C/4C	2	EA	7	\$0	
Flo	oor - Tile	3C/4C	200	SF	6	\$438	
Lig	ghting - Lay-in	3C/4C	8	EA	7	\$0	
Pov	ower Distribution	3C/4C	8	EA	7	\$0	
Wa	alls - Metal Panel	3C/4C	620	SF	6	\$4,628	
Cei	eiling - Lay-in	3D/4D	200	SF	6	\$601	
Do	oors - Steel Doors incl hw	3D/4D	2	EA	6	\$602	
Flo	oor - Tile	3D/4D	200	SF	6	\$438	
Lig	ghting - Lay-in	3D/4D	8	EA	7	\$0	
Pov	ower Distribution	3D/4D	8	EA	7	\$0	
Wa	alls - Metal Panel	3D/4D	620	SF	6	\$4,628	
Cei	eiling - Lay-in	3E	200	SF	6	\$601	
Do	pors - Steel Doors incl hw	3E	1	EA	6	\$301	
Flo	oor - Carpet	3E	200	SF	6	\$426	
Lig	ghting - Lay-in	3E	6	EA	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Adminis	strative Suites/Offices						
	Power Distribution	3E	6	EA	7	\$0	
	Walls - Metal Panel	3E	620	SF	6	\$4,628	
	Ceiling - Lay-in	3F	100	SF	6	\$300	
	Doors - Steel Doors incl hw	3F	1	EA	6	\$301	
	Floor - Carpet	3F	100	SF	6	\$213	
	Lighting - Lay-in	3F	4	EA	7	\$0	
	Power Distribution	3F	6	EA	7	\$0	
	Walls - Metal Panel	3F	413	SF	6	\$3,083	
	Ceiling - Lay-in	4A	90	SF	6	\$270	
	Doors - Steel Doors incl hw	4A	1	EA	6	\$301	
	Floor - Tile	4A	90	SF	6	\$197	
	Lighting - Lay-in	4A	2	EA	6	\$238	Relamp
	Lighting - Lay-in	4A	2	EA	7	\$0	
	Power Distribution	4A	6	EA	7	\$0	
	Walls - Metal Panel	4A	393	SF	6	\$2,934	
	Ceiling - Lay-in	4B	100	SF	6	\$300	
	Doors - Steel Doors incl hw	4B	1	EA	6	\$301	
	Floor - Carpet	4B	100	SF	6	\$213	
	Lighting - Lay-in	4B	4	EA	7	\$0	
	Power Distribution	4B	6	EA	7	\$0	
	Walls - Metal Panel	4B	413	SF	6	\$3,083	
	Ceiling - Lay-in	4E	81	SF	6	\$243	
	Doors - Steel Doors incl hw	4E	1	EA	6	\$301	
	Floor - Carpet	4E	81	SF	6	\$173	
	Lighting - Lay-in	4E	4	EA	7	\$0	Relamp
	Power Distribution	4E	6	EA	7	\$0	
	Walls - Metal Panel	4E	372	SF	6	\$2,777	
	Ceiling - Lay-in	4F	90	SF	6	\$270	
	Doors - Steel Doors incl hw	4F	1	EA	6	\$301	
	Floor - Carpet	4F	90	SF	6	\$192	
	Lighting - Lay-in	4F	2	EA	7	\$0	
	Lighting - Lay-in	4F	2	EA	6	\$238	Relamp
	Power Distribution	4F	6	EA	7	\$0	
	Walls - Metal Panel	4F	393	SF	6	\$2,934	
	Ceiling - Plaster/Drywall	Basement- Engineer's Suite (work rm/break rm/& office)	888	SF	6	\$3,073	
	Doors - Steel Doors incl hw	Basement- Engineer's Suite (work rm/break rm/& office)	2	EA	6	\$602	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Floor - Carpet	Basement- Engineer's Suite (work rm/break rm/& office)	269	SF	6	\$573	
	Floor - Tile	Basement- Engineer's Suite (work rm/break rm/& office)	619	SF	6	\$1,354	
	Lighting - Pendent/Surface	Basement- Engineer's Suite (work rm/break rm/& office)	28	EA	7	\$0	
	Power Distribution	Basement- Engineer's Suite (work rm/break rm/& office)	28	EA	6	\$59,497	
	Storage/ Closet	Basement- Engineer's Suite (work rm/break rm/& office)	19	SF	6	\$138	
	Walls - Concrete Block	Basement- Engineer's Suite (work rm/break rm/& office)	1,852	SF	6	\$5,429	
	Ceiling - Plaster/Drywall	Rm 013- Kitchen's managers office	145	SF	6	\$502	
	Doors - Side-lite	Rm 013- Kitchen's managers office	51	SF	6	\$853	
	Doors - Steel Doors incl hw	Rm 013- Kitchen's managers office	1	EA	6	\$301	
	Doors - Transom Window	Rm 013- Kitchen's managers office	5	SF	6	\$85	
	Floor - Tile	Rm 013- Kitchen's managers office	4	SF	5	\$23	
	Floor - Tile	Rm 013- Kitchen's managers office	141	SF	6	\$308	
	Lighting - Pendent/Surface	Rm 013- Kitchen's managers office	4	EA	7	\$0	
	Power Distribution	Rm 013- Kitchen's managers office	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 013- Kitchen's managers office	437	SF	6	\$1,281	
	Ceiling - Lay-in	Rm 100- Main Office	873	SF	6	\$2,622	
	Doors - Side-lite	Rm 100- Main Office	506	SF	6	\$8,459	
	Doors - Steel Doors incl hw	Rm 100- Main Office	4	EΑ	6	\$1,204	
	Doors - Transom Window	Rm 100- Main Office	22	SF	6	\$372	
	Floor - Carpet	Rm 100- Main Office	637	SF	6	\$1,357	by desks
	Floor - Tile	Rm 100- Main Office	209	SF	6	\$457	in break area of office
	Floor - Tile Ceramic/ Porcelain	Rm 100- Main Office	549	SF	6	\$1,162	in reception area
	Lighting - Lay-in	Rm 100- Main Office	24	EA	7	\$0	
	Power Distribution	Rm 100- Main Office	16	EΑ	6	\$33,998	
	Storage/ Closet	Rm 100- Main Office	190	SF	6	\$1,378	100D & vault
	Walls - Concrete Block	Rm 100- Main Office	1,180	SF	6	\$3,459	
	Walls - Metal Panel	Rm 100- Main Office	1,180	SF	6	\$8,808	
	Work SInk	Rm 100- Main Office	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 100A - Principal's Suite (office & conference space)	656	SF	6	\$1,970	
	Doors - Side-lite	Rm 100A - Principal's Suite (office & conference space)	20	SF	6	\$334	
	Doors - Steel Doors incl hw	Rm 100A - Principal's Suite (office & conference space)	3	EA	6	\$903	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Doors - Transom Window	Rm 100A - Principal's Suite (office & conference space)	11	SF	6	\$186	
	Floor - Carpet	Rm 100A - Principal's Suite (office & conference space)	292	SF	6	\$622	
	Floor - Tile	Rm 100A - Principal's Suite (office & conference space)	364	SF	6	\$796	
	Lighting - Lay-in	Rm 100A - Principal's Suite (office & conference space)	14	EA	7	\$0	
	Power Distribution	Rm 100A - Principal's Suite (office & conference space)	14	EA	6	\$29,748	
	Storage/ Closet	Rm 100A - Principal's Suite (office & conference space)	14	SF	6	\$102	
	Walls - Concrete Block	Rm 100A - Principal's Suite (office & conference space)	785	SF	6	\$2,301	
	Walls - Metal Panel	Rm 100A - Principal's Suite (office & conference space)	690	SF	6	\$5,151	
	Ceiling - Lay-in	Rm 100B- Asst principal's office (in Main Office)	124	SF	6	\$372	
	Doors - Side-lite	Rm 100B- Asst principal's office (in Main Office)	90	SF	6	\$1,505	
	Doors - Steel Doors incl hw	Rm 100B- Asst principal's office (in Main Office)	1	EA	6	\$301	
	Doors - Transom Window	Rm 100B- Asst principal's office (in Main Office)	11	SF	6	\$186	
	Floor - Tile Ceramic/ Porcelain	Rm 100B- Asst principal's office (in Main Office)	124	SF	6	\$262	
	Lighting - Lay-in	Rm 100B- Asst principal's office (in Main Office)	3	EA	7	\$0	
	Power Distribution	Rm 100B- Asst principal's office (in Main Office)	16	EA	6	\$33,998	
	Walls - Concrete Block	Rm 100B- Asst principal's office (in Main Office)	363	SF	6	\$1,064	
	Ceiling - Lay-in	Rm 100E- Payroll office (in main office)	234	SF	6	\$703	
	Doors - Side-lite	Rm 100E- Payroll office (in main office)	10	SF	6	\$167	
	Doors - Steel Doors incl hw	Rm 100E- Payroll office (in main office)	1	EΑ	6	\$301	
	Doors - Transom Window	Rm 100E- Payroll office (in main office)	11	SF	6	\$186	
	Floor - Carpet	Rm 100E- Payroll office (in main office)	234	SF	6	\$499	
	Lighting - Lay-in	Rm 100E- Payroll office (in main office)	5	EA	7	\$0	
	Power Distribution	Rm 100E- Payroll office (in main office)	18	EA	6	\$38,248	
	Storage/ Closet	Rm 100E- Payroll office (in main office)	180	SF	6	\$1,305	shared storage for the main office
	Walls - Metal Panel	Rm 100E- Payroll office (in main office)	686	SF	6	\$5,121	
	Ceiling - Lay-in	Rm 101- Book Store	361	SF	6	\$1,084	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Administrative Suites/Offices Rm 101- Book Store 69 SF 6 \$1,153	Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Doors - Transom Window	Admini	strative Suites/Offices						
Doors - Transom Window		Doors - Side-lite	Rm 101- Book Store	69	SF	6	\$1,153	
Floor - Tile		Doors - Steel Doors incl hw	Rm 101- Book Store	2	EA	6	\$602	
Floor - Tile		Doors - Transom Window	Rm 101- Book Store	22	SF	6	\$372	
Lighting - Lay-in Rm 101- Book Store 8		Floor - Tile	Rm 101- Book Store	356	SF	6	\$779	
Power Distribution		Floor - Tile	Rm 101- Book Store	5	SF	5	\$29	worn
Walls - Concrete Block Rm 101- Book Store 523 SF 6 \$1,533 Walls - Metal Panel Rm 101- Book Store 261 SF 6 \$1,948 Calling - Lay-in Rm 102- Waiting room of Admin suite 16 \$5 6 \$3,01 Doors - Steel Doors incl hw Rm 102- Waiting room of Admin suite 11 \$5 6 \$301 Doors - Transom Window Rm 102- Waiting room of Admin suite 16 \$5 6 \$308 Floor - Tile Rm 102- Waiting room of Admin suite 367 \$F 6 \$803 Lighting - Lay-in Rm 102- Waiting room of Admin suite 10 \$6 6 \$803 Power Distribution Rm 102- Waiting room of Admin suite 10 \$6 6 \$52,240 Celling - Lay-in Rm 102- Waiting room of Admin suite 702 \$F 6 \$52,40 Celling - Lay-in Rm 102- Asst principal's office 288 \$F 6 \$865 Celling - Lay-in Rm 102- Asst principal's office 288 \$F 6 \$865 Doors - Side-lite Rm 102- Asst principal's office 30 \$F 6 \$502		Lighting - Lay-in	Rm 101- Book Store	8	EA	7	\$0	
Walls - Metal Panel Rm 101- Book Store 261 SF 6 \$1,948 Ceiling - Lay-in Rm 102- Waiting room of Admin suite 1 EA 6 \$301 Doors - Stele Doors Inch W Rm 102- Waiting room of Admin suite 1 EA 6 \$301 Doors - Transom Window Rm 102- Waiting room of Admin suite 11 SF 6 \$186 Floor - Tile Rm 102- Waiting room of Admin suite 8 EA 7 \$0 Power Distribution Rm 102- Waiting room of Admin suite 8 EA 7 \$0 Power Distribution Rm 102- Waiting room of Admin suite 10 EA 6 \$21,249 Walls - Metal Panel Rm 102- Waiting room of Admin suite 702 SF 6 \$5,240 Ceiling - Lay-in Rm 102-A sast principal's office 28 SF 6 \$865 Colling - Lay-in Rm 102-A sast principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102-A sast principal's office 30 SF 6 \$502		Power Distribution	Rm 101- Book Store	6	EA	6	\$12,749	
Ceiling - Lay-in Rm 102- Waiting room of Admin suite 367 SF 6 \$1,102 Doors - Steel Doors incl hw Rm 102- Waiting room of Admin suite 11 SF 6 \$301 Doors - Transom Window Rm 102- Waiting room of Admin suite 11 SF 6 \$186 Floor - Tile Rm 102- Waiting room of Admin suite 367 SF 6 \$803 Lighting - Lay-in Rm 102- Waiting room of Admin suite 10 EA 6 \$21,249 Walls - Metal Panel Rm 102- Waiting room of Admin suite 702 SF 6 \$5,240 Ceiling - Lay-in Rm 102- Asst principal's office 288 SF 6 \$865 Ceiling - Lay-in Rm 102-A Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102-A Asst principal's office 288 SF 6 \$806 Doors - Side-lite Rm 102-A Asst principal's office 30 SF 6 \$502 Doors - Steel Doors incl hw Rm 102-A Asst principal's office 3 EA		Walls - Concrete Block	Rm 101- Book Store	523	SF	6	\$1,533	
Doors - Steel Doors incl hw		Walls - Metal Panel	Rm 101- Book Store	261	SF	6	\$1,948	
Doors - Transom Window		Ceiling - Lay-in	Rm 102- Waiting room of Admin suite	367	SF	6	\$1,102	
Floor - Tile		Doors - Steel Doors incl hw	Rm 102- Waiting room of Admin suite	1	EA	6	\$301	
Lighting - Lay-in Rm 102- Waiting room of Admin suite 8 EA 7 \$0 Power Distribution Rm 102- Waiting room of Admin suite 10 EA 6 \$21,249 Walls - Metal Panel Rm 102- Waiting room of Admin suite 70 SF 6 \$5,240 Ceiling - Lay-in Rm 102A- Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102A- Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A- Asst principal's office 3 SF 6 \$903 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630<		Doors - Transom Window	Rm 102- Waiting room of Admin suite	11	SF	6	\$186	
Power Distribution Rm 102- Waiting room of Admin suite 10 EA 6 \$21,249 Walls - Metal Panel Rm 102- Waiting room of Admin suite 702 SF 6 \$5,240 Ceiling - Lay-in Rm 102A - Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102A - Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A - Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A - Asst principal's office 3 SF 6 \$502 Doors - Steel Doors incl hw Rm 102A - Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A - Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A - Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A - Asst principal's office 288 SF 6 \$630 Eljohing - Lay-in Rm 102A - Asst principal's office 7 EA 7		Floor - Tile	Rm 102- Waiting room of Admin suite	367	SF	6	\$803	
Walls - Metal Panel Rm 102- Waiting room of Admin suite 702 SF 6 \$5,240 Ceiling - Lay-in Rm 102A - Asst principal's office 288 SF 6 \$865 Ceiling - Lay-in Rm 102A - Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102A - Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A - Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A - Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A - Asst principal's office 30 SF 6 \$502 Doors - Steel Doors incl hw Rm 102A - Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A - Asst principal's office 33 SF 6 \$559 Doors - Trile Rm 102A - Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A - Asst principal's office 7 EA 7 \$0 <td></td> <td>Lighting - Lay-in</td> <td>Rm 102- Waiting room of Admin suite</td> <td>8</td> <td>EΑ</td> <td>7</td> <td>\$0</td> <td></td>		Lighting - Lay-in	Rm 102- Waiting room of Admin suite	8	EΑ	7	\$0	
Ceiling - Lay-in Rm 102A- Asst principal's office 288 SF 6 \$865 Ceiling - Lay-in Rm 102A- Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A- Asst principal's office 3 SF 6 \$502 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A- Asst principal's office 3 SF 6 \$559 Ploor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 <		Power Distribution	Rm 102- Waiting room of Admin suite	10	EΑ	6	\$21,249	
Ceiling - Lay-in Rm 102A- Asst principal's office 288 SF 6 \$865 Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 SF 6 \$903 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Doors - Tile Rm 102A- Asst principal's office 33 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 <td></td> <td>Walls - Metal Panel</td> <td>Rm 102- Waiting room of Admin suite</td> <td>702</td> <td>SF</td> <td>6</td> <td>\$5,240</td> <td></td>		Walls - Metal Panel	Rm 102- Waiting room of Admin suite	702	SF	6	\$5,240	
Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 33 SF 6 \$903 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,048		Ceiling - Lay-in	Rm 102A- Asst principal's office	288	SF	6	\$865	
Doors - Side-lite Rm 102A- Asst principal's office 30 SF 6 \$502 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$36,		Ceiling - Lay-in	Rm 102A- Asst principal's office	288	SF	6	\$865	
Doors - Steel Doors incl hw Rm 102A - Asst principal's office 3 EA 6 \$903 Doors - Steel Doors incl hw Rm 102A - Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A - Asst principal's office 33 SF 6 \$559 Doors - Transom Window Rm 102A - Asst principal's office 288 SF 6 \$559 Floor - Tile Rm 102A - Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A - Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A - Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A - Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A - Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A - Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A - Asst principal's office 816 SF 6 \$6,09		Doors - Side-lite	Rm 102A- Asst principal's office	30	SF	6	\$502	
Doors - Steel Doors incl hw Rm 102A- Asst principal's office 3 EA 6 \$903 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102B - Admin conference room 429 SF 6 \$6,091 <td></td> <td>Doors - Side-lite</td> <td>Rm 102A- Asst principal's office</td> <td>30</td> <td>SF</td> <td>6</td> <td>\$502</td> <td></td>		Doors - Side-lite	Rm 102A- Asst principal's office	30	SF	6	\$502	
Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102B - Admin conference room 429 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 10 SF 6 \$1,1288 <		Doors - Steel Doors incl hw	Rm 102A- Asst principal's office	3	EA	6	\$903	
Doors - Transom Window Rm 102A- Asst principal's office 33 SF 6 \$559 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 1 EA 6 \$301 <		Doors - Steel Doors incl hw	Rm 102A- Asst principal's office	3	EA	6	\$903	
Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 10 SF 6 \$167 Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$301 <		Doors - Transom Window	Rm 102A- Asst principal's office	33	SF	6	\$559	
Floor - Tile Rm 102A- Asst principal's office 288 SF 6 \$630 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102B - Admin conference room 1 EA 6 \$301 Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$186		Doors - Transom Window	Rm 102A- Asst principal's office	33	SF	6	\$559	
Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Lighting - Lay-in Rm 102A- Asst principal's office 7 EA 7 \$0 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102B - Admin conference room 1 EA 6 \$301 Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$186		Floor - Tile	Rm 102A- Asst principal's office	288	SF	6	\$630	
Lighting - Lay-inRm 102A- Asst principal's office7EA7\$0Power DistributionRm 102A- Asst principal's office18EA6\$38,248Power DistributionRm 102A- Asst principal's office18EA6\$38,248Walls - Metal PanelRm 102A- Asst principal's office816SF6\$6,091Walls - Metal PanelRm 102A- Asst principal's office816SF6\$6,091Ceiling - Lay-inRm 102B - Admin conference room429SF6\$1,288Doors - Side-liteRm 102B - Admin conference room10SF6\$167Doors - Steel Doors incl hwRm 102B - Admin conference room1EA6\$301Doors - Transom WindowRm 102B - Admin conference room11SF6\$186		Floor - Tile	Rm 102A- Asst principal's office	288	SF	6	\$630	
Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Power Distribution Rm 102A- Asst principal's office 18 EA 6 \$38,248 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102B - Admin conference room 1 EA 6 \$301 Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$186		Lighting - Lay-in	Rm 102A- Asst principal's office	7	EA	7	\$0	
Power DistributionRm 102A- Asst principal's office18EA6\$38,248Walls - Metal PanelRm 102A- Asst principal's office816SF6\$6,091Walls - Metal PanelRm 102A- Asst principal's office816SF6\$6,091Ceiling - Lay-inRm 102B - Admin conference room429SF6\$1,288Doors - Side-liteRm 102B - Admin conference room10SF6\$167Doors - Steel Doors incl hwRm 102B - Admin conference room1EA6\$301Doors - Transom WindowRm 102B - Admin conference room11SF6\$186		Lighting - Lay-in	Rm 102A- Asst principal's office	7	EA	7	\$0	
Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102B - Admin conference room 1 EA 6 \$301 Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$186		Power Distribution	Rm 102A- Asst principal's office	18	EA	6	\$38,248	
Walls - Metal Panel Rm 102A- Asst principal's office 816 SF 6 \$6,091 Ceiling - Lay-in Rm 102B - Admin conference room 429 SF 6 \$1,288 Doors - Side-lite Rm 102B - Admin conference room 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102B - Admin conference room 1 EA 6 \$301 Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$186		Power Distribution	Rm 102A- Asst principal's office	18	EA	6	\$38,248	
Ceiling - Lay-inRm 102B - Admin conference room429SF6\$1,288Doors - Side-liteRm 102B - Admin conference room10SF6\$167Doors - Steel Doors incl hwRm 102B - Admin conference room1EA6\$301Doors - Transom WindowRm 102B - Admin conference room11SF6\$186		Walls - Metal Panel	Rm 102A- Asst principal's office	816	SF	6	\$6,091	
Doors - Side-liteRm 102B - Admin conference room10SF6\$167Doors - Steel Doors incl hwRm 102B - Admin conference room1EA6\$301Doors - Transom WindowRm 102B - Admin conference room11SF6\$186		Walls - Metal Panel	Rm 102A- Asst principal's office	816	SF	6	\$6,091	
Doors - Steel Doors incl hwRm 102B - Admin conference room1EA6\$301Doors - Transom WindowRm 102B - Admin conference room11SF6\$186		Ceiling - Lay-in	Rm 102B - Admin conference room	429	SF	6	\$1,288	
Doors - Transom Window Rm 102B - Admin conference room 11 SF 6 \$186		Doors - Side-lite	Rm 102B - Admin conference room	10	SF	6	\$167	
		Doors - Steel Doors incl hw	Rm 102B - Admin conference room	1	EA	6	\$301	
Floor - Tile/Sheet Rm 102B - Admin conference room 429 SF 6 \$429		Doors - Transom Window	Rm 102B - Admin conference room	11	SF	6	\$186	
		Floor - Tile/Sheet	Rm 102B - Admin conference room	429	SF	6	\$429	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Administrative Suites/Offices Lighting - Lay-in Rm 102B - Admin conference room 12 EA 7 \$0 Power Distribution Rm 102B - Admin conference room 20 EA 6 \$42,498 Walls - Concrete Block Rm 102B - Admin conference room 195 SF 6 \$572 Walls - Metal Panel Rm 102B - Admin conference room 587 SF 6 \$4,382 Ceiling - Lay-in Rm 102C - Admin Office 127 SF 6 \$381 Doors - Side-lite Rm 102C - Admin Office 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102C - Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C - Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C - Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C - Admin Office 8 EA 6 \$16,999 Power Distribution Rm 102C - Admin Office 8 EA 6 \$16,999	
Power Distribution Rm 102B - Admin conference room 20 EA 6 \$42,498 Walls - Concrete Block Rm 102B - Admin conference room 195 SF 6 \$572 Walls - Metal Panel Rm 102B - Admin conference room 587 SF 6 \$4,382 Ceiling - Lay-in Rm 102C - Admin Office 127 SF 6 \$381 Doors - Side-lite Rm 102C - Admin Office 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102C - Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C - Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C - Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C - Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C - Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C - Admin Office 206 SF 6 \$435 Doors - Side-lite	
Walls - Concrete Block Rm 102B - Admin conference room 195 SF 6 \$572 Walls - Metal Panel Rm 102B - Admin conference room 587 SF 6 \$4,382 Ceiling - Lay-in Rm 102C - Admin Office 127 SF 6 \$381 Doors - Side-lite Rm 102C - Admin Office 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102C - Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C - Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C - Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C - Admin Office 6 EA 7 \$0 Power Distribution Rm 102C - Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C - Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C - Admin Office 206 SF 6 \$435 Doors - Side-lite Rm 102D - Admissions Director 145 SF 6 \$1,839	
Walls - Metal Panel Rm 102B - Admin conference room 587 SF 6 \$4,382 Ceiling - Lay-in Rm 102C - Admin Office 127 SF 6 \$381 Doors - Side-lite Rm 102C - Admin Office 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102C - Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C - Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C - Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C - Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C - Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C - Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D - Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D - Admissions Director 11 EA 6 \$1,839 Doors - Steel Doors incl hw	
Ceiling - Lay-in Rm 102C- Admin Office 127 SF 6 \$381 Doors - Side-lite Rm 102C- Admin Office 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102C- Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C- Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C- Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C- Admin Office 6 EA 7 \$0 Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 1 EA 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Doors - Side-lite Rm 102C- Admin Office 10 SF 6 \$167 Doors - Steel Doors incl hw Rm 102C- Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C- Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C- Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C- Admin Office 6 EA 7 \$0 Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$1,839 Doors - Side-lite Rm 102D- Admissions Director 1 EA 6 \$301	
Doors - Steel Doors incl hw Rm 102C- Admin Office 1 EA 6 \$301 Doors - Transom Window Rm 102C- Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C- Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C- Admin Office 6 EA 7 \$0 Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Doors - Transom Window Rm 102C- Admin Office 11 SF 6 \$186 Floor - Tile/Sheet Rm 102C- Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C- Admin Office 6 EA 7 \$0 Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Floor - Tile/Sheet Rm 102C- Admin Office 127 SF 6 \$127 Lighting - Lay-in Rm 102C- Admin Office 6 EA 7 \$0 Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Lighting - Lay-in Rm 102C- Admin Office 6 EA 7 \$0 Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Power Distribution Rm 102C- Admin Office 8 EA 6 \$16,999 Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Walls - Concrete Block Rm 102C- Admin Office 206 SF 6 \$604 Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Walls - Plaster/Drywall Rm 102C- Admin Office 206 SF 6 \$569 Ceiling - Lay-in Rm 102D- Admissions Director 145 SF 6 \$435 Doors - Side-lite Rm 102D- Admissions Director 110 SF 6 \$1,839 Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Ceiling - Lay-inRm 102D- Admissions Director145SF6\$435Doors - Side-liteRm 102D- Admissions Director110SF6\$1,839Doors - Steel Doors incl hwRm 102D- Admissions Director1EA6\$301	
Doors - Side-liteRm 102D- Admissions Director110SF6\$1,839Doors - Steel Doors incl hwRm 102D- Admissions Director1EA6\$301	
Doors - Steel Doors incl hw Rm 102D- Admissions Director 1 EA 6 \$301	
Day 400D Adminstone Director 44 CF C 0400	
Doors - Transom Window Rm 102D- Admissions Director 11 SF 6 \$186	
Floor - Tile/Sheet Rm 102D- Admissions Director 145 SF 6 \$145	
Lighting - Lay-in Rm 102D- Admissions Director 6 EA 7 \$0	
Power Distribution Rm 102D- Admissions Director 8 EA 6 \$16,999	
Walls - Metal Panel Rm 102D- Admissions Director 432 SF 6 \$3,225	
Ceiling - Lay-in Rm 103B- Nurses' office 239 SF 6 \$718	
Doors - Steel Doors incl hw Rm 103B- Nurses' office 1 EA 6 \$301	
Floor - Tile Rm 103B- Nurses' office 239 SF 6 \$523	
Lighting - Lay-in Rm 103B- Nurses' office 6 EA 6 \$714	
Power Distribution Rm 103B- Nurses' office 10 EA 6 \$21,249	
Walls - Metal Panel Rm 103B- Nurses' office 553 SF 6 \$4,128	
Ceiling - Lay-in Rm 111- Copy Rm 144 SF 6 \$432	
Doors - Side-lite Rm 111- Copy Rm 10 SF 6 \$167	
Doors - Steel Doors incl hw Rm 111- Copy Rm 1 EA 6 \$301	
Doors - Transom Window Rm 111- Copy Rm 11 SF 6 \$186	
Floor - Tile Rm 111- Copy Rm 144 SF 6 \$315	
Lighting - Lay-in Rm 111- Copy Rm 3 EA 7 \$0	
Power Distribution Rm 111- Copy Rm 8 EA 6 \$16,999	
Walls - Metal Panel Rm 111- Copy Rm 400 SF 6 \$2,986	
Ceiling - Lay-in Rm 112- Meeting Rm 285 SF 6 \$856	
Doors - Side-lite Rm 112- Meeting Rm 20 SF 6 \$334	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Doors - Steel Doors incl hw	Rm 112- Meeting Rm	2	EA	6	\$602	
	Doors - Transom Window	Rm 112- Meeting Rm	22	SF	6	\$372	
	Floor - Tile	Rm 112- Meeting Rm	285	SF	6	\$624	
	Lighting - Lay-in	Rm 112- Meeting Rm	6	EA	7	\$0	
	Power Distribution	Rm 112- Meeting Rm	14	EA	6	\$29,748	
	Walls - Metal Panel	Rm 112- Meeting Rm	680	SF	6	\$5,076	
	Ceiling - Lay-in	Rm 117B- History Teacher Closet Office	211	SF	6	\$634	
	Doors - Wood Doors inclu hw	Rm 117B- History Teacher Closet Office	1	EA	6	\$301	
	Floor - Tile	Rm 117B- History Teacher Closet Office	211	SF	6	\$462	
	Lighting - Lay-in	Rm 117B- History Teacher Closet Office	1	EA	6	\$119	cover missing
	Lighting - Lay-in	Rm 117B- History Teacher Closet Office	3	EA	7	\$0	
	Power Distribution	Rm 117B- History Teacher Closet Office	4	EA	6	\$8,500	
	Walls - Metal Panel	Rm 117B- History Teacher Closet Office	426	SF	6	\$3,180	
	Ceiling - Lay-in	Rm 118- Teacher Resource Center	285	SF	6	\$856	
	Doors - Side-lite	Rm 118- Teacher Resource Center	10	SF	6	\$167	
	Doors - Steel Doors incl hw	Rm 118- Teacher Resource Center	1	EA	6	\$301	
	Doors - Transom Window	Rm 118- Teacher Resource Center	11	SF	6	\$186	
	Floor - Tile	Rm 118- Teacher Resource Center	285	SF	6	\$624	
	Lighting - Lay-in	Rm 118- Teacher Resource Center	6	EA	7	\$0	
	Power Distribution	Rm 118- Teacher Resource Center	10	EA	6	\$21,249	
	Walls - Metal Panel	Rm 118- Teacher Resource Center	680	SF	6	\$5,076	
	Ceiling - Lay-in	Rm 118-Scheduler's Office	10	SF	5	\$80	water stains
	Ceiling - Lay-in	Rm 118-Scheduler's Office	502	SF	6	\$1,508	
	Doors - Steel Doors incl hw	Rm 118-Scheduler's Office	3	EA	6	\$903	
	Doors - Transom Window	Rm 118-Scheduler's Office	11	SF	6	\$186	
	Floor - Tile	Rm 118-Scheduler's Office	512	SF	6	\$1,120	
	Lighting - Lay-in	Rm 118-Scheduler's Office	15	EA	7	\$0	
	Power Distribution	Rm 118-Scheduler's Office	10	EA	6	\$21,249	
	Walls - Concrete Block	Rm 118-Scheduler's Office	994	SF	6	\$2,914	
	Ceiling - Lay-in	Rm 120 (A-L) -Counselors' Suite	2,000	SF	6	\$6,006	
	Doors - Side-lite	Rm 120 (A-L) -Counselors' Suite	10	SF	6	\$167	
	Doors - Store Front	Rm 120 (A-L) -Counselors' Suite	11	EA	6	\$13,290	
	Doors - Transom Window	Rm 120 (A-L) -Counselors' Suite	22	SF	6	\$372	
	Floor - Tile	Rm 120 (A-L) -Counselors' Suite	2,000	SF	6	\$4,376	
	Lighting - Lay-in	Rm 120 (A-L) -Counselors' Suite	34	EA	7	\$0	
	Power Distribution	Rm 120 (A-L) -Counselors' Suite	20	EA	6	\$42,498	
	Storage/ Closet	Rm 120 (A-L) -Counselors' Suite	96	SF	6		Rm 120H

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-	strative Suites/Offices						
	Walls - Metal Panel	Rm 120 (A-L) -Counselors' Suite	1,250	SF	6	\$9,331	
	Walls - Plaster/Drywall	Rm 120 (A-L) -Counselors' Suite	2,037	SF	6	\$5,622	Seven offices@ 291 sf each
	Ceiling - Lay-in	Rm 120A- Counselors Office Suite Reception	367	SF	6	\$1,102	
	Doors - Side-lite	Rm 120A- Counselors Office Suite Reception	395	SF	6	\$6,603	
	Doors - Steel Doors incl hw	Rm 120A- Counselors Office Suite Reception	3	EA	6	\$903	
	Doors - Transom Window	Rm 120A- Counselors Office Suite Reception	11	SF	6	\$186	
	Floor - Carpet	Rm 120A- Counselors Office Suite Reception	367	SF	6	\$782	
	Lighting - Lay-in	Rm 120A- Counselors Office Suite Reception	9	EA	6	\$1,071	
	Power Distribution	Rm 120A- Counselors Office Suite Reception	6	EA	6	\$12,749	
	Walls - Concrete Block	Rm 120A- Counselors Office Suite Reception	395	SF	6	\$1,158	
	Ceiling - Lay-in	Rm 120B2 - Gifted Program Office	196	SF	6	\$589	
	Doors - Steel Doors incl hw	Rm 120B2 - Gifted Program Office	2	EA	6	\$602	
	Floor - Terrazzo	Rm 120B2 - Gifted Program Office	196	SF	6	\$429	
	Lighting - Lay-in	Rm 120B2 - Gifted Program Office	2	EA	7	\$0	
	Power Distribution	Rm 120B2 - Gifted Program Office	8	EA	6	\$16,999	
	Storage/ Closet	Rm 120B2 - Gifted Program Office	916	SF	6	\$6,641	storage hall
	Walls - Metal Panel	Rm 120B2 - Gifted Program Office	590	SF	6	\$4,404	
	Ceiling - Lay-in	Rm 124- PE Coach Office	219	SF	6	\$658	
	Doors - Wood Doors inclu hw	Rm 124- PE Coach Office	2	EA	6	\$602	
	Floor - Tile	Rm 124- PE Coach Office	219	SF	5	\$983	particle board
	Lighting - Lay-in	Rm 124- PE Coach Office	4	EA	7	\$0	
	Power Distribution	Rm 124- PE Coach Office	6	EA	6	\$12,749	
	Walls - Plaster/Drywall	Rm 124- PE Coach Office	476	SF	6	\$1,314	
	Ceiling - Lay-in	Rm 125- Office	170	SF	6	\$511	
	Doors - Wood Doors inclu hw	Rm 125- Office	1	EA	6	\$301	
	Floor - Carpet	Rm 125- Office	170	SF	5	\$873	carpet is just rolled down, not even attached
	Lighting - Lay-in	Rm 125- Office	4	EA	7	\$0	
	Power Distribution	Rm 125- Office	8	EA	6	\$16,999	
	Walls - Plaster/Drywall	Rm 125- Office	520	SF	6	\$1,435	1
	Ceiling - Lay-in	Rm 128- Attendance Office	273	SF	6	\$820	
	Doors - Side-lite	Rm 128- Attendance Office	10	SF	6	\$167	
	Doors - Steel Doors incl hw	Rm 128- Attendance Office	1	EA	6	\$301	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

up Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ninistrative Suites/Offices						
Doors - Transom Window	Rm 128- Attendance Office	11	SF	6	\$186	
Floor - Tile	Rm 128- Attendance Office	273	SF	6	\$597	
Lighting - Lay-in	Rm 128- Attendance Office	5	EA	7	\$0	
Power Distribution	Rm 128- Attendance Office	10	EA	6	\$21,249	
Walls - Metal Panel	Rm 128- Attendance Office	476	SF	6	\$3,553	
Ceiling - Lay-in	Rm 128B- Attendance Coordinator	211	SF	6	\$634	
Doors - Steel Doors incl hw	Rm 128B- Attendance Coordinator	1	EA	6	\$301	
Doors - Transom Window	Rm 128B- Attendance Coordinator	11	SF	6	\$186	
Floor - Tile	Rm 128B- Attendance Coordinator	211	SF	6	\$462	
Lighting - Lay-in	Rm 128B- Attendance Coordinator	6	EA	7	\$0	
Power Distribution	Rm 128B- Attendance Coordinator	6	EA	6	\$12,749	
Walls - Metal Panel	Rm 128B- Attendance Coordinator	426	SF	6	\$3,180	
Ceiling - Lay-in	Rm 129A- Security Office	144	SF	6	\$432	
Doors - Steel Doors incl hw	Rm 129A- Security Office	1	EΑ	6	\$301	
Doors - Transom Window	Rm 129A- Security Office	11	SF	6	\$186	
Floor - Carpet	Rm 129A- Security Office	144	SF	6	\$307	
Lighting - Lay-in	Rm 129A- Security Office	3	EΑ	7	\$0	
Power Distribution	Rm 129A- Security Office	6	EA	6	\$12,749	
Walls - Metal Panel	Rm 129A- Security Office	400	SF	6	\$2,986	
Ceiling - Lay-in	Rm 129B- Office	218	SF	6	\$655	
Doors - Steel Doors incl hw	Rm 129B- Office	1	EA	6	\$301	
Doors - Transom Window	Rm 129B- Office	11	SF	6	\$186	
Floor - Carpet	Rm 129B- Office	218	SF	6	\$464	
Lighting - Lay-in	Rm 129B- Office	5	EA	7	\$0	
Power Distribution	Rm 129B- Office	8	EΑ	6	\$16,999	
Walls - Metal Panel	Rm 129B- Office	590	SF	6	\$4,404	
Ceiling - Lay-in	Rm 140- Social Services Office	219	SF	6	\$658	
Doors - Side-lite	Rm 140- Social Services Office	10	SF	6	\$167	
Doors - Steel Doors incl hw	Rm 140- Social Services Office	1	EA	6	\$301	
Doors - Transom Window	Rm 140- Social Services Office	11	SF	6	\$186	
Floor - Tile/Sheet	Rm 140- Social Services Office	219	SF	6	\$219	
Lighting - Lay-in	Rm 140- Social Services Office	5	EA	7	\$0	
Power Distribution	Rm 140- Social Services Office	10	EA	6	\$21,249	
Walls - Metal Panel	Rm 140- Social Services Office	476	SF	6	\$3,553	
Ceiling - Lay-in	Rm 141- Social Services Office	219	SF	6	\$658	
Doors - Side-lite	Rm 141- Social Services Office	10	SF	6	\$167	
Doors - Steel Doors incl hw	Rm 141- Social Services Office	1	EA	6	\$301	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Admini	strative Suites/Offices						
	Doors - Transom Window	Rm 141- Social Services Office	11	SF	6	\$186	
	Floor - Tile/Sheet	Rm 141- Social Services Office	219	SF	6	\$219	
	Lighting - Lay-in	Rm 141- Social Services Office	5	EA	7	\$0	
	Power Distribution	Rm 141- Social Services Office	8	EA	6	\$16,999	
	Walls - Metal Panel	Rm 141- Social Services Office	476	SF	6	\$3,553	
	Ceiling - Lay-in	Rm 142- Social Services Office	438	SF	7	\$0	
	Doors - Steel Doors incl hw	Rm 142- Social Services Office	1	EA	6	\$301	
	Doors - Transom Window	Rm 142- Social Services Office	11	SF	6	\$186	
	Floor - Tile/Sheet	Rm 142- Social Services Office	438	SF	6	\$438	
	Lighting - Lay-in	Rm 142- Social Services Office	9	EA	7	\$0	
	Power Distribution	Rm 142- Social Services Office	10	EA	6	\$21,249	
	Walls - Metal Panel	Rm 142- Social Services Office	633	SF	6	\$4,725	
	Ceiling - Lay-in	Rm 143- Office	219	SF	6	\$658	
	Doors - Wood Doors inclu hw	Rm 143- Office	1	EA	6	\$301	
	Floor - Carpet	Rm 143- Office	219	SF	6	\$467	
	Lighting - Lay-in	Rm 143- Office	5	EA	7	\$0	
	Power Distribution	Rm 143- Office	4	EΑ	6	\$8,500	
	Walls - Plaster/Drywall	Rm 143- Office	238	SF	6	\$657	
	Ceiling - Lay-in	Rm 145- Social Services Office	219	SF	6	\$658	
	Doors - Steel Doors incl hw	Rm 145- Social Services Office	1	EA	6	\$301	
	Doors - Transom Window	Rm 145- Social Services Office	11	SF	6	\$186	
	Floor - Tile/Sheet	Rm 145- Social Services Office	219	SF	6	\$219	
	Lighting - Lay-in	Rm 145- Social Services Office	4	EA	7	\$0	
	Power Distribution	Rm 145- Social Services Office	6	EΑ	6	\$12,749	
	Walls - Concrete Block	Rm 145- Social Services Office	238	SF	6	\$698	
	Walls - Metal Panel	Rm 145- Social Services Office	238	SF	6	\$1,777	
	Ceiling - Lay-in	Rm 146- Social Services Office	219	SF	6	\$658	
	Doors - Steel Doors incl hw	Rm 146- Social Services Office	1	EA	6	\$301	
	Doors - Transom Window	Rm 146- Social Services Office	11	SF	6	\$186	
	Floor - Tile/Sheet	Rm 146- Social Services Office	219	SF	6	\$219	
	Lighting - Lay-in	Rm 146- Social Services Office	6	EA	7	\$0	
	Power Distribution	Rm 146- Social Services Office	10	EA	6	\$21,249	
	Walls - Concrete Block	Rm 146- Social Services Office	238	SF	6	\$698	
	Walls - Metal Panel	Rm 146- Social Services Office	238	SF	6	\$1,777	
	Ceiling - Lay-in	Rm 147- Social Services Office	141	SF	6	\$423	
	Doors - Side-lite	Rm 147- Social Services Office	10	SF	6	\$167	
	Doors - Steel Doors incl hw	Rm 147- Social Services Office	1	EA	6	\$301	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
	strative Suites/Offices						
	Doors - Transom Window	Rm 147- Social Services Office	11	SF	6	\$186	
	Floor - Tile	Rm 147- Social Services Office	141	SF	6	\$308	
	Lighting - Lay-in	Rm 147- Social Services Office	3	EA	7	\$0	
	Power Distribution	Rm 147- Social Services Office	4	EA	6	\$8,500	
	Walls - Metal Panel	Rm 147- Social Services Office	238	SF	6	\$1,777	1
	Ceiling - Lay-in	Rm 147A - Social Services Office	141	SF	6	\$423	
	Doors - Side-lite	Rm 147A - Social Services Office	10	SF	6	\$167	
	Doors - Steel Doors incl hw	Rm 147A - Social Services Office	1	EA	6	\$301	
	Doors - Transom Window	Rm 147A - Social Services Office	11	SF	6	\$186	
	Floor - Tile	Rm 147A - Social Services Office	141	SF	6	\$308	
	Lighting - Lay-in	Rm 147A - Social Services Office	3	EΑ	7	\$0	
	Power Distribution	Rm 147A - Social Services Office	8	EA	6	\$16,999	
	Walls - Metal Panel	Rm 147A - Social Services Office	238	SF	6	\$1,777	1
	Ceiling - Lay-in	Rm 148 - Social Services Office	140	SF	6	\$420	
	Doors - Steel Doors incl hw	Rm 148 - Social Services Office	1	EA	6	\$301	
	Floor - Tile	Rm 148 - Social Services Office	140	SF	6	\$306	
	Lighting - Lay-in	Rm 148 - Social Services Office	3	EA	7	\$0	
	Power Distribution	Rm 148 - Social Services Office	10	EA	6	\$21,249	
	Walls - Metal Panel	Rm 148 - Social Services Office	238	SF	6	\$1,777	
	Traile motal rails.			٥.	· ·	Ψ.,	
nic							
	Ceiling - Lay-in	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	763	SF	6	\$2,291	
	Doors - Side-lite	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	70	SF	6	\$1,170	
	Doors - Steel Doors incl hw	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	4	EA	6	\$1,204	
	Doors - Transom Window	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	44	SF	6	\$745	
	Floor - Tile/Sheet	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	763	SF	6	\$764	
	Lighting - Lay-in	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	18	EA	7	\$0	
	Walls - Metal Panel	Rm 103- Nurses' Suite (Lobby, 103E, 103D, 103C)	2,161	SF	6	\$16,131	
	Ceiling - Lay-in	Rm 139- Audiology	524	SF	6	\$1,574	
	Doors - Steel Doors incl hw	Rm 139- Audiology	2	EA	6	\$602	
	Doors - Transom Window	Rm 139- Audiology	11	SF	6	\$186	
	Floor - Carpet	Rm 139- Audiology	524	SF	6	\$1,116	
	Lighting - Lay-in	Rm 139- Audiology	12	EA	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Clinic	Valls - Metal Panel						
V	Mollo Motal Danal						
	valis - ivietai Fariei	Rm 139- Audiology	950	SF	6	\$7,091	
Kitchen							
	Ceiling - Plaster/Drywall	Basement	2,279	SF	6	\$7,887	
	Doors - Side-lite	Basement	20	SF	6	\$334	
D	Doors - Steel Doors incl hw	Basement	4	EA	6	\$1,204	
F	Floor - Tile Ceramic/ Porcelain	Basement	2,279	SF	6	\$4,823	
Li	ighting - Pendent/Surface	Basement	75	EA	7	\$0	
S	Storage/ Closet	Basement	1,496	SF	6	\$10,846	Dry & Cold Storage
V	Valls - Concrete Block	Basement	3,996	SF	6	\$11,714	
Library							
C	Ceiling - Lay-in	224	7,817	SF	6	\$23,474	Clean
D	Doors - Steel Doors incl hw	224	4	EA	7	\$0	
F	Floor - Carpet	224	7,817	SF	6	\$16,656	
Li	ighting - Lay-in	224	4	EA	6	\$476	Relamp
Li	ighting - Lay-in	224	155	EA	7	\$0	
V	Valls - Masonry	224	1,835	SF	6	\$5,773	
V	Valls - Metal Panel	224	1,835	SF	6	\$13,698	
Locker/Sh	nower Room						
Α	Accessories	Basement janitors, woman	285	SF	6	\$1,117	
C	Ceiling - Plaster/ Drywall	Basement janitors, woman	285	SF	6	\$986	
D	Doors - Steel Doors incl hw	Basement janitors, woman	1	EA	6	\$301	
F	Floor Drain	Basement janitors, woman	1	EA	6	\$1,059	
F	Floor - Tile Ceramic/ Porcelain	Basement janitors, woman	190	SF	6	\$402	
F	Floor - Tile/Sheet	Basement janitors, woman	95	SF	6	\$95	
Н	Hand Dryer	Basement janitors, woman	1	EA	6	\$230	
L	Lavatory	Basement janitors, woman	1	EA	6	\$320	
Li	ighting - Pendent/Surface	Basement janitors, woman	6	EA	6	\$743	missing covers
Р	Partitions	Basement janitors, woman	1	EA	5	\$751	rusting
S	Student Lockers - One Tier	Basement janitors, woman	12	EA	6	\$1,114	
V	Valls - Concrete Block	Basement janitors, woman	930	SF	6	\$2,726	
V	Vater Closet	Basement janitors, woman	1	EA	6	\$336	
Α	Accessories	Basement Janitors	560	SF	6	\$2,194	
C	Ceiling - Plaster/ Drywall	Basement Janitors	560	SF	6	\$1,938	
D	Doors - Steel Doors incl hw	Basement Janitors	1	EA	6	\$301	
F	Floor Drain	Basement Janitors	3	EA	6	\$3,177	
F	Floor - Tile Ceramic/ Porcelain	Basement Janitors	1	SF	5	\$21	hole

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

s, unsure if showers work

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments			
Locker	Locker/Shower Room									
	Water Closet	Basement Kitchen Staff	1	EA	6	\$336				
	Water Closet	Basement Kitchen staff	2	EA	6	\$672				
Lunch	nch & Multipurpose Room									
	Ceiling - Lay-in	2nd floor east side	32	SF	5	\$255				
	Ceiling - Lay-in	2nd floor east side	6,089	SF	6	\$18,285				
	Floor - Tile/Sheet	2nd floor east side	6,121	SF	6	\$6,127				
	Lighting - Lay-in	2nd floor east side	4	EA	6	\$476	Relamp			
	Lighting - Lay-in	2nd floor east side	123	EA	7	\$0				
	Serving Line	2nd floor east side	35	LF	6	\$2,083				
	Walls - Masonry	2nd floor east side	2,225	SF	6	\$7,000				
	Ceiling - Splined	2nd floor serving areas	449	SF	5	\$3,198	Clean			
	Doors - Steel Doors incl hw	2nd floor serving areas	10	EA	6	\$3,010				
	Floor - Tile Ceramic/ Porcelain	2nd floor serving areas	449	SF	6	\$950				
	Lighting - Lay-in	2nd floor serving areas	14	EA	7	\$0				
	Serving Line	2nd floor serving areas	39	LF	6	\$2,321				
	Storage/ Closet	2nd floor serving areas	180	SF	6	\$1,305				
	Walls - Masonry	2nd floor serving areas	814	SF	6	\$2,561				
	Ceiling - Lay-in	2nd floor west side	176	SF	5	\$1,404				
	Ceiling - Lay-in	2nd floor west side	5,945	SF	6	\$17,853				
	Floor - Tile/Sheet	2nd floor west side	6,121	SF	6	\$6,127				
	Lighting - Lay-in	2nd floor west side	6	EA	6	\$714	Relamp			
	Lighting - Lay-in	2nd floor west side	102	EA	7	\$0				
	Serving Line	2nd floor west side	35	LF	6	\$2,083				
	Walls - Masonry	2nd floor west side	2,225	SF	6	\$7,000				
	Ceiling - Lay-in	2nd Floor	480	SF	6	\$1,441				
	Doors - Steel Doors incl hw	2nd Floor	1	EA	7	\$0				
	Floor - Wood	2nd Floor	480	SF	6	\$3,384				
	Lighting - Lay-in	2nd Floor	10	EA	7	\$0				
	Lighting - Pendent/Surface	2nd Floor	23	EA	7	\$0				
	Walls - Metal Panel	2nd Floor	629	SF	6	\$4,695				
	Walls - Plaster/Drywall	2nd Floor	236	SF	6	\$651				
	Ceiling - Lay-in	3rd floor east side	24	SF	5	\$192				
	Ceiling - Lay-in	3rd floor east side	6,097	SF	6	\$18,309				
	Floor - Tile/Sheet	3rd floor east side	6,121	SF	6	\$6,127				
	Lighting - Lay-in	3rd floor east side	12	EA	6	\$1,428	Relamp			
	Lighting - Lay-in	3rd floor east side	115	EA	7	\$0				
	Serving Line	3rd floor east side	35	LF	6	\$2,083				

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

•	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
ch &	Multipurpose Room						
	Walls - Concrete Block	3rd floor east side	2,225	SF	6	\$6,523	Brick walls
	Ceiling - Splined	3rd floor serving areas	449	SF	6	\$366	
	Doors - Steel Doors incl hw	3rd floor serving areas	10	EA	6	\$3,010	
	Floor - Tile Ceramic/ Porcelain	3rd floor serving areas	449	SF	6	\$950	
	Lighting - Lay-in	3rd floor serving areas	1	EA	6	\$119	Relamp
	Lighting - Lay-in	3rd floor serving areas	12	EA	7	\$0	
	Serving Line	3rd floor serving areas	39	LF	6	\$2,321	
	Storage/ Closet	3rd floor serving areas	180	SF	6	\$1,305	
	Walls - Masonry	3rd floor serving areas	814	SF	6	\$2,561	Brick and mortar
	Ceiling - Lay-in	3rd floor west side	6,121	SF	6	\$18,381	
	Floor - Tile/Sheet	3rd floor west side	6,121	SF	6	\$6,127	
	Lighting - Lay-in	3rd floor west side	9	EA	6	\$1,071	Relamp
	Lighting - Lay-in	3rd floor west side	118	EA	7	\$0	
	Serving Line	3rd floor west side	35	LF	6	\$2,083	
	Walls - Concrete Block	3rd floor west side	2,225	SF	6	\$6,523	Brick walls
	Ceiling - Lay-in	Rm 104- Community Rm	724	SF	6	\$2,174	
	Ceiling - Lay-in	Rm 104- Community Rm	5	SF	5	\$40	water damaged ceiling
	Doors - Steel Doors incl hw	Rm 104- Community Rm	2	EA	6	\$602	
	Doors - Transom Window	Rm 104- Community Rm	11	SF	6	\$186	
	Floor - Tile Ceramic/ Porcelain	Rm 104- Community Rm	729	SF	6	\$1,543	
	Lighting - Lay-in	Rm 104- Community Rm	14	EA	7	\$0	
	Walls - Concrete Block	Rm 104- Community Rm	542	SF	6	\$1,589	
	Walls - Metal Panel	Rm 104- Community Rm	271	SF	6	\$2,023	
_IDF	F						
	Doors - Steel Doors incl hw	203A	1	EA	7	\$0	
	Finishes	203A	983	SF	6	\$7,014	
	Ventilation and Cooling	203A	1	EA	6	\$1,855	
hani	ical/ Service Rooms						
	Janitor's Closet	1st Floor	32	SF	6	\$229	
	Janitor's Closet	1st Floor	16	SF	5	\$258	crack in wall - JC located inside Boy's 1st Flr RR next to Principal
	Mechanical/ Service Rooms	1st Floor	290	SF	6	\$2,078	Elec closets
	Storage Room	1st Floor	3	SF	5		3 sqft of water damage on ceiling in 127D
	Storage Room	1st Floor	597	SF	6	\$4,277	
	Janitor's Closet	2nd Floor	60	SF	6	\$430	
	Mechanical/ Service Rooms	2nd Floor	76	SF	6	\$544	
	Storage Room	2nd Floor	80	SF	6	\$573	



211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechan	ical/ Service Rooms						
	Janitor's Closet	Basement	71	SF	6	\$509	
	Loading Docks	Basement	448	SF	6	\$3,210	
	Mechanical/ Service Rooms	Basement	1,655	SF	6	\$11,857	
	Mechanical/ Service Rooms	Basement	866	SF	5	\$13,969	Water is coming into Switch Gear room. there is standing water on floor, as well as rust visible on electric panels, which contains High Voltage Electricity
	Storage Room	Basement	7,460	SF	6	\$53,446	
Prep Ro	oom						
	Ceiling - Lay-in	320A/B	750	SF	6	\$2,252	
	Doors - Side-lite	320A/B	362	SF	6	\$6,051	Window wall
	Doors - Transom Window	320A/B	24	SF	7	\$0	
	Floor - Tile	320A/B	750	SF	6	\$1,641	
	Lighting - Lay-in	320A/B	4	EΑ	6	\$476	Relamp
	Lighting - Lay-in	320A/B	26	EA	7	\$0	
	Walls - Metal Panel	320A/B	1,601	SF	6	\$11,951	
	Work Sink	320A/B	1	EA	6	\$379	
	Ceiling - Lay-in	326A/B	750	SF	6	\$2,252	
	Doors - Side-lite	326A/B	362	SF	6	\$6,051	
	Doors - Transom Window	326A/B	24	SF	7	\$0	
	Floor - Tile	326A/B	750	SF	6	\$1,641	
	Lighting - Lay-in	326A/B	5	EA	6	\$595	Relamp
	Lighting - Lay-in	326A/B	25	EA	7	\$0	
	Walls - Metal Panel	326A/B	1,601	SF	6	\$11,951	
	Work Sink	326A/B	1	EA	6	\$379	
	Ceiling - Lay-in	328B	12	SF	5	\$96	
	Ceiling - Lay-in	328B	176	SF	6	\$529	
	Doors - Steel Doors incl hw	328B	4	EA	6	\$1,204	
	Floor - Tile	328B	32	SF	5	\$157	
	Floor - Tile	328B	156	SF	6	\$341	
	Lighting - Lay-in	328B	6	EA	6	\$714	Relamp
	Lighting - Lay-in	328B	7	EA	7	\$0	
	Walls - Masonry	328B	200	SF	6	\$629	
	Walls - Metal Panel	328B	380	SF	6	\$2,837	
	Work Sink	328B	2	EA	6	\$758	
	Ceiling - Plaster/Drywall	Rm 126A- Dark Rm	150	SF	6	\$519	
	Doors - Steel Doors incl hw	Rm 126A- Dark Rm	1	EA	6	\$301	
	Floor - Tile	Rm 126A- Dark Rm	150	SF	6	\$328	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Ighting Lay-in Rm 126A- Dark Rm 3 EA 7 \$ \$ 0 Virtuals - Concrete Block Rm 126A- Dark Rm 1 EA 6 \$ \$379 Photo bath Virtuals - Concrete Block Rm 126A- Dark Rm 1 EA 6 \$ \$379 Photo bath Rm 126A- Dark Rm 1 EA 6 \$ \$379 Photo bath Rm 126C- Web Casting Room 150 SF 6 \$ \$450	р	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Valles - Concrete Block	Ro	om						
Vork Sink		Lighting - Lay-in	Rm 126A- Dark Rm	3	EA	7	\$0	
Rm 129C - Web Casting Room		Walls - Concrete Block	Rm 126A- Dark Rm	300	SF	6	\$879	
Nors Side-lile Rm 129C- Web Casting Room 10 SF 6 \$167		Work Sink	Rm 126A- Dark Rm	1	EΑ	6	\$379	Photo bath
Rm 129C- Web Casting Room		Ceiling - Lay-in	Rm 129C- Web Casting Room	150	SF	6	\$450	
Nors - Transom Window Rm 129C - Web Casting Room 11		Doors - Side-lite	Rm 129C- Web Casting Room	10	SF	6	\$167	
Idea		Doors - Steel Doors incl hw	Rm 129C- Web Casting Room	1	EA	6	\$301	
Septing - Lay-in Rm 129C- Web Casting Room 3 EA 7		Doors - Transom Window	Rm 129C- Web Casting Room	11	SF	6	\$186	
Valls - Metal Panel Rm 129C- Web Casting Room 300 SF 6 \$2,239		Floor - Tile	Rm 129C- Web Casting Room	150	SF	6	\$328	
Relling - Lay-in Rm 129D- Web Casting Room 150 SF 6 \$450 cors - Side-lite Rm 129D- Web Casting Room 10 SF 6 \$167 cors - Side-lite Rm 129D- Web Casting Room 10 SF 6 \$167 cors - Steel Doors incl hw Rm 129D- Web Casting Room 11 EA 6 \$301 cors - Transom Window Rm 129D- Web Casting Room 11 SF 6 \$186 cors - Title Rm 129D- Web Casting Room 150 SF 6 \$328 cors - Steel Doors - Title Rm 129D- Web Casting Room 150 SF 6 \$328 cors - Steel Doors - Title Rm 129D- Web Casting Room 150 SF 6 \$328 cors - Steel Doors incl hw 129D- Web Casting Room 300 SF 6 \$2,239 core sories 1st Fir- In the principal's suite 20 SF 6 \$69 cors - Steel Doors incl hw 1st Fir- In the principal's suite 20 SF 6 \$69 cors - Steel Doors incl hw 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 1st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$42 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$320 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$320 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$320 cord and Dryer 2st Fir- In the principal's suite 20 SF 6 \$320 cord and Dryer 2st Fir- In the principal's suite 2st Fir- In The Fir- In The Principal's suite 2st Fir- In		Lighting - Lay-in	Rm 129C- Web Casting Room	3	EA	7	\$0	
		Walls - Metal Panel	Rm 129C- Web Casting Room	300	SF	6	\$2,239	
Rm 129D- Web Casting Room		Ceiling - Lay-in	Rm 129D- Web Casting Room	150	SF	6	\$450	
Rm 129D- Web Casting Room 11		Doors - Side-lite	Rm 129D- Web Casting Room	10	SF	6	\$167	
Nor - Tile		Doors - Steel Doors incl hw	Rm 129D- Web Casting Room	1	EΑ	6	\$301	
Rm 129D- Web Casting Room 3 EA 7 \$0		Doors - Transom Window	Rm 129D- Web Casting Room	11	SF	6	\$186	
Rm 129D- Web Casting Room 3 EA 7 \$0		Floor - Tile	Rm 129D- Web Casting Room	150	SF	6	\$328	
1st Fir- In the principal's suite 20 SF 6 \$184		Lighting - Lay-in		3	EΑ	7		
Seliling - Plaster/Drywall 1st Fir- In the principal's suite 20 SF 6 \$69		Walls - Metal Panel	Rm 129D- Web Casting Room	300	SF	6	\$2,239	
Seliling - Plaster/Drywall 1st Fir- In the principal's suite 20 SF 6 \$69	00	m						
Seliling - Plaster/Drywall 1st Fir- In the principal's suite 20 SF 6 \$69	00		1 at Fire In the principally quite	20	CE	6	¢404	
Steel Doors incl hw 1st Fir- In the principal's suite 1			· ·					
SF 6 \$42 SF 6 \$42 SF 6 \$42 SF 6 \$42 SF SF SF SF SF SF SF S		,						
Star								
1st FIr- In the principal's suite 1 EA 6 \$320 sighting - Wall Mounted 1st FIr- In the principal's suite 1 EA 6 \$124 sighting - Wall Mounted 1st FIr- In the principal's suite 127 SF 6 \$372 sider Closet 1st FIr- In the principal's suite 127 SF 6 \$336 sider Closet 1st FIr- In the principal's suite 1 EA 6 \$336 sider Closet 1st FIr- Men's in Rm 120 36 SF 6 \$332 sider Closes FIr- Men's in Rm 120 36 SF 6 \$332 sider Closes FIr- Men's in Rm 120 36 SF 6 \$332 sider Closes FIr- Men's in Rm 120 36 SF 6 \$332 sider Closes FIr- Men's in Rm 120 36 SF 6 \$330 sider FIr- Men's in Rm 120 36 SF 6 \$301 sider FIr- Men's in Rm 120 36 SF 6 \$301 sider FIr- Men's in Rm 120 36 SF 6 \$301 sider FIr- Men's in Rm 120 36 SF 6 \$301 sider FIr- Men's in Rm 120 36 SF 6 \$302 sider FIr- Men's in Rm 120 36 SF 6 \$320 sider FIr- Men's in Rm 120 37 SF 6 \$320 sider FIr- Men's in Rm 120 37 SF 6 \$320 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIr- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 37 SF 6 \$332 sider FIR- Men's in Rm 120 \$320 sider FIR-			· ·		_			
sighting - Wall Mounted 1st Fir- In the principal's suite 1 EA 6 \$124 Valls - Concrete Block 1st Fir- In the principal's suite 127 SF 6 \$372 Vater Closet 1st Fir- In the principal's suite 1 EA 6 \$336 ccessories 1st Fir- Men's in Rm 120 36 SF 6 \$332 seiling - Plaster/Drywall 1st Fir- Men's in Rm 120 36 SF 6 \$125 poors - Steel Doors incl hw 1st Fir- Men's in Rm 120 1 EA 6 \$301 poors - Tile Ceramic/ Porcelain 1st Fir- Men's in Rm 120 36 SF 6 \$76 avatory 1st Fir- Men's in Rm 120 1 EA 6 \$320 sighting - Wall Mounted 1st Fir- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st Fir- Men's in Rm 120 1 EA 6 \$336 Vater Closet 1st Fir- Men's in Rm 120 1 EA 6 \$336 Ccessories 1st fir Men's - Next to 120A 16 SF 6 \$148 <		•						
Valls - Concrete Block 1st FIr- In the principal's suite 127 SF 6 \$372 Vater Closet 1st FIr- In the principal's suite 1 EA 6 \$336 ccessories 1st FIr- Men's in Rm 120 36 SF 6 \$332 ceiling - Plaster/Drywall 1st FIr- Men's in Rm 120 36 SF 6 \$125 coors - Steel Doors incl hw 1st FIr- Men's in Rm 120 1 EA 6 \$301 cloor - Tile Ceramic/ Porcelain 1st FIr- Men's in Rm 120 36 SF 6 \$76 avatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 righting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 1 EA 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 ccessories 1st flr Men's - Next to 120A 16 SF 6 \$148			· ·	-				
Vater Closet 1st FIr- In the principal's suite 1 EA 6 \$336 Accessories 1st FIr- Men's in Rm 120 36 SF 6 \$332 Seiling - Plaster/Drywall 1st FIr- Men's in Rm 120 36 SF 6 \$125 Boors - Steel Doors incl hw 1st FIr- Men's in Rm 120 1 EA 6 \$301 Bloor - Tile Ceramic/ Porcelain 1st FIr- Men's in Rm 120 36 SF 6 \$76 Bavatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 Bighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 Vacessories 1st flr Men's -Next to 120A 16 SF 6 \$148				•				
cccessories 1st FIr- Men's in Rm 120 36 SF 6 \$332 ceiling - Plaster/Drywall 1st FIr- Men's in Rm 120 36 SF 6 \$125 coors - Steel Doors incl hw 1st FIr- Men's in Rm 120 1 EA 6 \$301 cloor - Tile Ceramic/ Porcelain 1st FIr- Men's in Rm 120 36 SF 6 \$76 avatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 ighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 ccessories 1st flr Men's - Next to 120A 16 SF 6 \$148			• •					
Seiling - Plaster/Drywall 1st FIr- Men's in Rm 120 36 SF 6 \$125 Ploors - Steel Doors incl hw 1st FIr- Men's in Rm 120 1 EA 6 \$301 Ploor - Tile Ceramic/ Porcelain 1st FIr- Men's in Rm 120 36 SF 6 \$76 Pavatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 Eighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 Accessories 1st fIr Men's - Next to 120A 16 SF 6 \$148			· ·					
Poors - Steel Doors incl hw 1st FIr- Men's in Rm 120 1 EA 6 \$301 Bloor - Tile Ceramic/ Porcelain 1st FIr- Men's in Rm 120 36 SF 6 \$76 avatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 ighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 Accessories 1st flr Men's - Next to 120A 16 SF 6 \$148					_			
Iloor - Tile Ceramic/ Porcelain 1st FIr- Men's in Rm 120 36 SF 6 \$76 avatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 ighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 Accessories 1st fIr Men's -Next to 120A 16 SF 6 \$148								
avatory 1st FIr- Men's in Rm 120 1 EA 6 \$320 ighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 Accessories 1st fIr Men's -Next to 120A 16 SF 6 \$148				-				
ighting - Wall Mounted 1st FIr- Men's in Rm 120 1 EA 7 \$0 Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 Accessories 1st fIr Men's -Next to 120A 16 SF 6 \$148		Lavatory			_			
Valls - Concrete Block 1st FIr- Men's in Rm 120 120 SF 6 \$352 Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 .ccessories 1st fIr Men's -Next to 120A 16 SF 6 \$148		•						
Vater Closet 1st FIr- Men's in Rm 120 1 EA 6 \$336 accessories 1st fIr Men's -Next to 120A 16 SF 6 \$148		Walls - Concrete Block		-				
ccessories 1st flr Men's -Next to 120A 16 SF 6 \$148		Water Closet						
		Accessories						
		Ceiling - Plaster/Drywall	1st flr Men's -Next to 120A	16	SF	6	\$55	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stroo	m						
	Doors - Steel Doors incl hw	1st flr Men's -Next to 120A	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st flr Men's -Next to 120A	16	SF	6	\$34	
	Lavatory	1st flr Men's -Next to 120A	1	EA	6	\$320	
	Lighting - Wall Mounted	1st flr Men's -Next to 120A	1	EA	7	\$0	
	Walls - Concrete Block	1st flr Men's -Next to 120A	102	SF	6	\$299	
	Water Closet	1st flr Men's -Next to 120A	1	EA	6	\$336	
	Accessories	1st flr Men's -Next to Principal	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	1st flr Men's -Next to Principal	16	SF	6	\$55	
	Doors - Steel Doors incl hw	1st flr Men's -Next to Principal	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st flr Men's -Next to Principal	16	SF	6	\$34	
	Lavatory	1st flr Men's -Next to Principal	1	EA	6	\$320	
	Lighting - Wall Mounted	1st flr Men's -Next to Principal	1	EA	7	\$0	
	Walls - Concrete Block	1st flr Men's -Next to Principal	102	SF	6	\$299	
	Water Closet	1st flr Men's -Next to Principal	1	EA	6	\$336	
	Accessories	1st flr- Next to 104	245	SF	6	\$2,260	
	Ceiling - Plaster/Drywall	1st flr- Next to 104	245	SF	6	\$848	
	Floor Drain	1st flr- Next to 104	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr- Next to 104	245	SF	6	\$519	
	Hand Dryer	1st flr- Next to 104	2	EA	6	\$460	
	Lavatory	1st flr- Next to 104	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st flr- Next to 104	10	EA	7	\$0	
	Partitions	1st flr- Next to 104	6	EA	6	\$1,782	
	Walls - Concrete Block	1st flr- Next to 104	605	SF	6	\$1,774	
	Walls - Concrete Block	1st flr- Next to 104	3	SF	5	\$42	needs paint
	Water Closet	1st flr- Next to 104	6	EA	6	\$2,016	
	Accessories	1st flr- Next to 120A	349	SF	6	\$3,219	
	Ceiling - Plaster/Drywall	1st flr- Next to 120A	349	SF	6	\$1,208	
	Floor Drain	1st flr- Next to 120A	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr- Next to 120A	245	SF	6	\$519	
	Hand Dryer	1st flr- Next to 120A	2	EA	6	\$460	
	Lavatory	1st flr- Next to 120A	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st flr- Next to 120A	10	EA	7	\$0	
	Partitions	1st flr- Next to 120A	2	EA	6	\$594	
	Urinals	1st flr- Next to 120A	5	EA	6	\$1,680	
	Walls - Concrete Block	1st flr- Next to 120A	608	SF	6	\$1,782	
	Water Closet	1st flr- Next to 120A	1	EA	6	\$336	
	Accessories	1st flr- Next to 128	245	SF	6	\$2,260	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Ceiling - Plaster/Drywall	1st flr- Next to 128	245	SF	6	\$848	
	Floor Drain	1st flr- Next to 128	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr- Next to 128	245	SF	6	\$519	
	Hand Dryer	1st flr- Next to 128	2	EA	6	\$460	
	Lavatory	1st flr- Next to 128	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st flr- Next to 128	1	EA	6	\$124	missing cover
	Lighting - Pendent/Surface	1st flr- Next to 128	9	EA	7	\$0	
	Partitions	1st flr- Next to 128	6	EA	6	\$1,782	
	Walls - Concrete Block	1st flr- Next to 128	608	SF	6	\$1,782	
	Water Closet	1st flr- Next to 128	6	EA	6	\$2,016	
	Accessories	1st flr- Next to Principal	349	SF	6	\$3,219	
	Ceiling - Plaster/Drywall	1st flr- Next to Principal	349	SF	6	\$1,208	
	Floor Drain	1st flr- Next to Principal	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr- Next to Principal	245	SF	6	\$519	
	Hand Dryer	1st flr- Next to Principal	2	EA	6	\$460	
	Lavatory	1st flr- Next to Principal	2	EA	6	\$639	
	Lavatory	1st flr- Next to Principal	1	EA	5	\$1,590	cracked porcelain
	Lighting - Pendent/Surface	1st flr- Next to Principal	10	EA	7	\$0	
	Partitions	1st flr- Next to Principal	2	EA	6	\$594	
	Urinals	1st flr- Next to Principal	5	EA	6	\$1,680	
	Walls - Concrete Block	1st flr- Next to Principal	608	SF	6	\$1,782	
	Water Closet	1st flr- Next to Principal	1	EA	6	\$336	
	Accessories	1st Flr- Unisex inside Rm103C	26	SF	6	\$240	
	Ceiling - Plaster/Drywall	1st FIr- Unisex inside Rm103C	26	SF	6	\$90	
	Doors - Steel Doors incl hw	1st Flr- Unisex inside Rm103C	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st FIr- Unisex inside Rm103C	26	SF	6	\$55	
	Lavatory	1st FIr- Unisex inside Rm103C	1	EA	6	\$320	
	Lighting - Wall Mounted	1st FIr- Unisex inside Rm103C	1	EA	7	\$0	
	Walls - Concrete Block	1st FIr- Unisex inside Rm103C	133	SF	6	\$390	
	Water Closet	1st Flr- Unisex inside Rm103C	1	EA	6	\$336	
	Accessories	1st FIr- Unisex inside Rm103D	26	SF	6	\$240	
	Ceiling - Plaster/Drywall	1st Flr- Unisex inside Rm103D	26	SF	6	\$90	
	Doors - Steel Doors incl hw	1st Flr- Unisex inside Rm103D	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Flr- Unisex inside Rm103D	26	SF	6	\$55	
	Lavatory	1st Flr- Unisex inside Rm103D	1	EA	6	\$320	
	Lighting - Wall Mounted	1st FIr- Unisex inside Rm103D	1	EA	7	\$0	
	Walls - Concrete Block	1st FIr- Unisex inside Rm103D	133	SF	6	\$390	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
stro	om						
	Water Closet	1st Flr- Unisex inside Rm103D	1	EA	6	\$336	
	Accessories	1st Flr- Women's in Rm 120	36	SF	6	\$332	
	Ceiling - Plaster/Drywall	1st Flr- Women's in Rm 120	36	SF	6	\$125	
	Doors - Steel Doors incl hw	1st Flr- Women's in Rm 120	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Flr- Women's in Rm 120	36	SF	6	\$76	
	Lavatory	1st Flr- Women's in Rm 120	1	EA	6	\$320	
	Lighting - Wall Mounted	1st Flr- Women's in Rm 120	1	EA	7	\$0	
	Walls - Concrete Block	1st Flr- Women's in Rm 120	120	SF	6	\$352	
	Water Closet	1st Flr- Women's in Rm 120	1	EA	6	\$336	
	Accessories	1st flr Women's -Next to 104	18	SF	6	\$166	
	Ceiling - Plaster/Drywall	1st flr Women's -Next to 104	18	SF	6	\$62	
	Doors - Steel Doors incl hw	1st flr Women's -Next to 104	1	EΑ	6	\$301	
	Floor Drain	1st flr Women's -Next to 104	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr Women's -Next to 104	18	SF	6	\$38	
	Lavatory	1st flr Women's -Next to 104	1	EΑ	6	\$320	
	Lighting - Wall Mounted	1st flr Women's -Next to 104	1	EΑ	7	\$0	
	Walls - Concrete Block	1st flr Women's -Next to 104	139	SF	6	\$407	
	Water Closet	1st flr Women's -Next to 104	1	EΑ	6	\$336	
	Accessories	1st flr Women's -Next to 128	18	SF	6	\$166	
	Ceiling - Plaster/Drywall	1st flr Women's -Next to 128	18	SF	6	\$62	
	Doors - Steel Doors incl hw	1st flr Women's -Next to 128	1	EΑ	6	\$301	
	Floor Drain	1st flr Women's -Next to 128	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr Women's -Next to 128	18	SF	6	\$38	
	Lavatory	1st flr Women's -Next to 128	1	EA	6	\$320	
	Lighting - Wall Mounted	1st flr Women's -Next to 128	1	EΑ	7	\$0	
	Walls - Concrete Block	1st flr Women's -Next to 128	139	SF	6	\$407	
	Water Closet	1st flr Women's -Next to 128	1	EA	6	\$336	
	Accessories	2nd floor Men's NE	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	2nd floor Men's NE	16	SF	6	\$55	
	Doors - Steel Doors incl hw	2nd floor Men's NE	1	EA	6	\$301	
	Floor Drain	2nd floor Men's NE	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor Men's NE	16	SF	6	\$34	
	Lavatory	2nd floor Men's NE	1	EA	6	\$320	
	Lighting - Wall Mounted	2nd floor Men's NE	1	EA	7	\$0	
	Walls - Concrete Block	2nd floor Men's NE	102	SF	6	\$299	
	Water Closet	2nd floor Men's NE	1	EA	6	\$336	
	Accessories	2nd floor Men's SW	20	SF	6	\$184	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

roup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
estro	om						
	Ceiling - Plaster/Drywall	2nd floor Men's SW	20	SF	6	\$69	
	Doors - Steel Doors incl hw	2nd floor Men's SW	1	EΑ	6	\$301	
	Floor Drain	2nd floor Men's SW	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor Men's SW	20	SF	6	\$42	
	Lavatory	2nd floor Men's SW	1	EΑ	6	\$320	
	Lighting - Wall Mounted	2nd floor Men's SW	1	EΑ	7	\$0	
	Walls - Concrete Block	2nd floor Men's SW	177	SF	6	\$519	
	Water Closet	2nd floor Men's SW	1	EΑ	6	\$336	
	Accessories	2nd floor NE Women's	245	SF	6	\$2,260	
	Ceiling - Plaster/Drywall	2nd floor NE Women's	245	SF	6	\$848	
	Floor Drain	2nd floor NE Women's	1	EΑ	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor NE Women's	245	SF	5	\$3,913	
	Hand Dryer	2nd floor NE Women's	2	EA	6	\$460	
	Lavatory	2nd floor NE Women's	3	EA	6	\$959	
	Lighting - Lay-in	2nd floor NE Women's	4	EA	7	\$0	
	Partitions	2nd floor NE Women's	5	EΑ	6	\$1,485	
	Walls - Concrete Block	2nd floor NE Women's	558	SF	6	\$1,636	
	Water Closet	2nd floor NE Women's	6	EA	6	\$2,016	
	Accessories	2nd floor NW Men's	284	SF	6	\$2,619	
	Ceiling - Plaster/Drywall	2nd floor NW Men's	284	SF	6	\$983	
	Floor Drain	2nd floor NW Men's	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor NW Men's	284	SF	5	\$4,536	
	Hand Dryer	2nd floor NW Men's	2	EA	6	\$460	
	Lavatory	2nd floor NW Men's	3	EA	6	\$959	
	Lighting - Lay-in	2nd floor NW Men's	4	EA	7	\$0	
	Partitions	2nd floor NW Men's	5	EA	6	\$1,485	
	Urinals	2nd floor NW Men's	5	EA	6	\$1,680	
	Walls - Concrete Block	2nd floor NW Men's	542	SF	6	\$1,589	
	Water Closet	2nd floor NW Men's	1	EA	6	\$336	
	Accessories	2nd floor SE Men's	284	SF	6	\$2,619	
	Ceiling - Plaster/Drywall	2nd floor SE Men's	284	SF	6	\$983	
	Floor Drain	2nd floor SE Men's	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor SE Men's	284	SF	6	\$601	
	Hand Dryer	2nd floor SE Men's	2	EA	6	\$460	
	Lavatory	2nd floor SE Men's	4	EA	6	\$1,278	
	Lighting - Lay-in	2nd floor SE Men's	4	EA	7	\$0	
	Partitions	2nd floor SE Men's	5	EΑ	6	\$1,485	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom						
Urinals	2nd floor SE Men's	7	EA	6	\$2,352	
Walls - Concrete Block	2nd floor SE Men's	542	SF	6	\$1,589	
Water Closet	2nd floor SE Men's	1	EA	6	\$336	
Accessories	2nd Floor SW Women's	284	SF	6	\$2,619	
Ceiling - Plaster/Drywall	2nd Floor SW Women's	284	SF	6	\$983	
Floor Drain	2nd Floor SW Women's	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	2nd Floor SW Women's	284	SF	6	\$601	
Hand Dryer	2nd Floor SW Women's	2	EA	6	\$460	
Lavatory	2nd Floor SW Women's	4	EA	6	\$1,278	
Lighting - Lay-in	2nd Floor SW Women's	6	EA	7	\$0	
Partitions	2nd Floor SW Women's	9	EA	6	\$2,672	
Walls - Concrete Block	2nd Floor SW Women's	542	SF	7	\$0	
Water Closet	2nd Floor SW Women's	10	EA	6	\$3,360	
Accessories	2nd Floor Women's NE	16	SF	6	\$148	
Ceiling - Plaster/Drywall	2nd Floor Women's NE	16	SF	6	\$55	
Doors - Steel Doors incl hw	2nd Floor Women's NE	1	EA	6	\$301	
Floor Drain	2nd Floor Women's NE	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	2nd Floor Women's NE	16	SF	6	\$34	
Lavatory	2nd Floor Women's NE	1	EA	6	\$320	
Lighting - Wall Mounted	2nd Floor Women's NE	1	EA	7	\$0	
Walls - Concrete Block	2nd Floor Women's NE	102	SF	6	\$299	
Water Closet	2nd Floor Women's NE	1	EA	6	\$336	
Accessories	2nd Floor Women's SW	48	SF	6	\$443	
Ceiling - Plaster/Drywall	2nd Floor Women's SW	48	SF	6	\$166	
Doors - Steel Doors incl hw	2nd Floor Women's SW	1	EA	6	\$301	
Floor Drain	2nd Floor Women's SW	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	2nd Floor Women's SW	48	SF	5	\$767	
Lavatory	2nd Floor Women's SW	1	EA	6	\$320	
Lighting - Wall Mounted	2nd Floor Women's SW	1	EA	7	\$0	
Walls - Concrete Block	2nd Floor Women's SW	275	SF	6	\$806	
Water Closet	2nd Floor Women's SW	1	EA	6	\$336	
Accessories	3rd floor Men's NE	16	SF	6	\$148	
Ceiling - Plaster/Drywall	3rd floor Men's NE	16	SF	6	\$55	
Doors - Steel Doors incl hw	3rd floor Men's NE	1	EA	6	\$301	
Floor Drain	3rd floor Men's NE	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	3rd floor Men's NE	16	SF	6	\$34	
Lavatory	3rd floor Men's NE	1	EA	6	\$320	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	m						
	Lighting - Wall Mounted	3rd floor Men's NE	1	EA	7	\$0	
	Walls - Concrete Block	3rd floor Men's NE	102	SF	6	\$299	
	Water Closet	3rd floor Men's NE	1	EA	6	\$336	
	Accessories	3rd floor Men's SW	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	3rd floor Men's SW	16	SF	6	\$55	
	Doors - Steel Doors incl hw	3rd floor Men's SW	1	EA	6	\$301	
	Floor Drain	3rd floor Men's SW	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd floor Men's SW	16	SF	6	\$34	
	Lavatory	3rd floor Men's SW	1	EA	6	\$320	
	Lighting - Wall Mounted	3rd floor Men's SW	1	EA	7	\$0	
	Walls - Concrete Block	3rd floor Men's SW	102	SF	6	\$299	
	Water Closet	3rd floor Men's SW	1	EA	6	\$336	
	Accessories	3rd floor NE Men's	284	SF	6	\$2,619	
	Accessories	3rd floor NE Men's	284	SF	6	\$2,619	
	Ceiling - Plaster/Drywall	3rd floor NE Men's	284	SF	6	\$983	
	Ceiling - Plaster/Drywall	3rd floor NE Men's	284	SF	6	\$983	
	Floor Drain	3rd floor NE Men's	1	EA	6	\$1,059	clogged/back up
	Floor Drain	3rd floor NE Men's	1	EA	6	\$1,059	clogged/back up
	Floor - Tile Ceramic/ Porcelain	3rd floor NE Men's	284	SF	6	\$601	
	Floor - Tile Ceramic/ Porcelain	3rd floor NE Men's	284	SF	6	\$601	
	Hand Dryer	3rd floor NE Men's	2	EA	6	\$460	
	Hand Dryer	3rd floor NE Men's	2	EA	6	\$460	
	Lavatory	3rd floor NE Men's	3	EA	6	\$959	
	Lavatory	3rd floor NE Men's	3	EA	6	\$959	
	Lighting - Lay-in	3rd floor NE Men's	4	EA	7	\$0	
	Lighting - Lay-in	3rd floor NE Men's	4	EA	7	\$0	
	Partitions	3rd floor NE Men's	5	EA	6	\$1,485	
	Partitions	3rd floor NE Men's	5	EA	6	\$1,485	
	Urinals	3rd floor NE Men's	5	EA	6	\$1,680	
	Urinals	3rd floor NE Men's	5	EA	6	\$1,680	
	Walls - Concrete Block	3rd floor NE Men's	542	SF	6	\$1,589	
	Walls - Concrete Block	3rd floor NE Men's	542	SF	6	\$1,589	
	Water Closet	3rd floor NE Men's	1	EA	6	\$336	
	Water Closet	3rd floor NE Men's	1	EA	6	\$336	
	Accessories	3rd Floor NW Women's	284	SF	6	\$2,619	
	Ceiling - Plaster/Drywall	3rd Floor NW Women's	284	SF	6	\$983	
	Floor Drain	3rd Floor NW Women's	1	EA	6	\$1,059	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Group Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom						
Floor - Tile Ceramic/ Porcelain	3rd Floor NW Women's	284	SF	5	\$4,536	
Hand Dryer	3rd Floor NW Women's	2	EA	6	\$460	
Lavatory	3rd Floor NW Women's	3	EA	6	\$959	
Lighting - Lay-in	3rd Floor NW Women's	4	EA	7	\$0	
Partitions	3rd Floor NW Women's	5	EA	6	\$1,485	
Walls - Concrete Block	3rd Floor NW Women's	542	SF	6	\$1,589	
Water Closet	3rd Floor NW Women's	6	EA	6	\$2,016	
Accessories	3rd floor SE Women's	245	SF	6	\$2,260	
Ceiling - Plaster/Drywall	3rd floor SE Women's	245	SF	6	\$848	
Floor Drain	3rd floor SE Women's	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	3rd floor SE Women's	245	SF	6	\$519	
Hand Dryer	3rd floor SE Women's	2	EA	6	\$460	
Lavatory	3rd floor SE Women's	3	EA	6	\$959	
Lighting - Lay-in	3rd floor SE Women's	4	EA	7	\$0	
Partitions	3rd floor SE Women's	5	EA	6	\$1,485	
Walls - Concrete Block	3rd floor SE Women's	558	SF	6	\$1,636	
Water Closet	3rd floor SE Women's	7	EA	6	\$2,352	
Accessories	3rd floor SW Men's	284	SF	6	\$2,619	
Ceiling - Plaster/Drywall	3rd floor SW Men's	284	SF	6	\$983	
Floor Drain	3rd floor SW Men's	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	3rd floor SW Men's	284	SF	5	\$4,536	
Hand Dryer	3rd floor SW Men's	2	EA	6	\$460	
Lavatory	3rd floor SW Men's	3	EA	6	\$959	
Lighting - Lay-in	3rd floor SW Men's	4	EA	7	\$0	
Partitions	3rd floor SW Men's	5	EA	6	\$1,485	
Urinals	3rd floor SW Men's	4	EA	6	\$1,344	
Walls - Concrete Block	3rd floor SW Men's	542	SF	6	\$1,589	
Water Closet	3rd floor SW Men's	2	EA	6	\$672	
Accessories	3rd Floor Women's NW	16	SF	6	\$148	
Ceiling - Plaster/Drywall	3rd Floor Women's NW	16	SF	6	\$55	
Doors - Steel Doors incl hw	3rd Floor Women's NW	1	EA	6	\$301	
Floor Drain	3rd Floor Women's NW	1	EA	6	\$1,059	
Floor - Tile Ceramic/ Porcelain	3rd Floor Women's NW	16	SF	6	\$34	
Lavatory	3rd Floor Women's NW	1	EA	6	\$320	
Lighting - Wall Mounted	3rd Floor Women's NW	1	EA	7	\$0	
Walls - Concrete Block	3rd Floor Women's NW	102	SF	6	\$299	
Water Closet	3rd Floor Women's NW	1	EA	6	\$336	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restro	om						
	Accessories	3rd Floor Women's SE	16	SF	6	\$148	
	Ceiling - Plaster/Drywall	3rd Floor Women's SE	16	SF	6	\$55	
	Doors - Steel Doors incl hw	3rd Floor Women's SE	1	EA	6	\$301	
	Floor Drain	3rd Floor Women's SE	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd Floor Women's SE	16	SF	6	\$34	
	Lavatory	3rd Floor Women's SE	1	EΑ	6	\$320	
	Lighting - Wall Mounted	3rd Floor Women's SE	1	EA	7	\$0	
	Walls - Concrete Block	3rd Floor Women's SE	102	SF	6	\$299	
	Water Closet	3rd Floor Women's SE	1	EΑ	6	\$336	
	Accessories	Basement- Inside Engineer's office	40	SF	6	\$369	
	Ceiling - Plaster/Drywall	Basement- Inside Engineer's office	40	SF	6	\$138	
	Doors - Steel Doors incl hw	Basement- Inside Engineer's office	1	EΑ	6	\$301	
	Floor Drain	Basement- Inside Engineer's office	2	EΑ	6	\$2,118	
	Floor - Tile Ceramic/ Porcelain	Basement- Inside Engineer's office	40	SF	6	\$85	
	Lavatory	Basement- Inside Engineer's office	1	EΑ	6	\$320	
	Lighting - Pendent/Surface	Basement- Inside Engineer's office	1	EA	7	\$0	
	Showers	Basement- Inside Engineer's office	1	EA	6	\$311	
	Walls - Concrete Block	Basement- Inside Engineer's office	208	SF	6	\$610	
	Water Closet	Basement- Inside Engineer's office	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$1,974,420

Building: Main - Building A Category: Building Interior

Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
or						
Ceiling - Lay-in	1st Floor	14	SF	5	\$125	water stained tiles
Ceiling - Lay-in	1st Floor	14,104	SF	6	\$42,354	
Doors - Side-lite	1st Floor	440	EA	6	\$7,355	
Doors - Steel Doors incl hw	1st Floor	22	EA	6	\$6,622	
Doors - Transom Window	1st Floor	368	EA	6	\$6,231	
Drinking Fountains - Single Fountain	1st Floor	3	EA	6	\$827	
Drinking Fountains - Single Water Cooler	1st Floor	1	EA	6	\$317	
Floor - Terrazzo	1st Floor	3,060	SF	6	\$25,686	
Floor - Tile/Sheet	1st Floor	4	SF	4	\$59	missing/damaged tiles
Floor - Tile/Sheet	1st Floor	11,054	SF	6	\$6,007	
Lighting - Lay-in	1st Floor	424	EΑ	7	\$0	

211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	or						
	Student Lockers	1st Floor	288	EA	6	\$0	
	Walls - Concrete Block	1st Floor	6,059	SF	6	\$17,762	
	Walls - Masonry	1st Floor	2,450	SF	6	\$7,708	
	Walls - Metal Panel	1st Floor	6	SF	5	\$240	by door 1
	Walls - Metal Panel	1st Floor	7,053	SF	6	\$52,648	
	Ceiling - Lay-in	2nd Floor	144	SF	5	\$1,285	
	Ceiling - Lay-in	2nd Floor	42,580	SF	6	\$127,868	
	Doors - Steel Doors incl hw	2nd Floor	16	EA	6	\$4,816	
	Drinking Fountains - Single Water Cooler	2nd Floor	4	EA	6	\$1,267	
	Floor - Tile/Sheet	2nd Floor	42,724	SF	6	\$23,216	
	Lighting - Lay-in	2nd Floor	6	EA	6	\$714	
	Lighting - Lay-in	2nd Floor	381	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	772	EΑ	6	\$71,669	
	Walls - Masonry	2nd Floor	13,735	SF	6	\$43,210	
	Walls - Metal Panel	2nd Floor	13,735	SF	6	\$102,526	
	Ceiling - Lay-in	3rd Floor	176	SF	5	\$1,570	
	Ceiling - Lay-in	3rd Floor	13,942	SF	6	\$41,868	
	Doors - Steel Doors incl hw	3rd Floor	8	EΑ	6	\$2,408	
	Drinking Fountains - Single Water Cooler	3rd Floor	4	EA	6	\$1,267	
	Floor - Tile/Sheet	3rd Floor	14,118	SF	6	\$7,672	
	Lighting - Lay-in	3rd Floor	6	EA	6	\$714	
	Lighting - Lay-in	3rd Floor	433	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	625	EA	6	\$58,022	
	Walls - Masonry	3rd Floor	9,230	SF	6	\$29,038	
	Walls - Metal Panel	3rd Floor	9,230	SF	6	\$68,898	
	Ceiling - Lay-in	Basement	540	SF	6	\$1,622	
	Ceiling - Plaster/Drywall	Basement	9,211	SF	6	\$57,034	
	Doors - Steel Doors incl hw	Basement	7	EA	6	\$2,107	at each stairwell & 4 fire doors at Athletic building
	Floor - Concrete	Basement	40	SF	5	\$69	vestibule of Switch Gear room, there is seepage
	Floor - Tile/Sheet	Basement	200	SF	4	\$2,963	missing/damaged tiles
	Floor - Tile/Sheet	Basement	9,511	SF	6	\$5,168	
	Lighting - Lay-in	Basement	11	EA	7	\$0	
	Lighting - Pendent/Surface	Basement	3	EΑ	6	\$372	no cover
	Lighting - Pendent/Surface	Basement	43	EΑ	7	\$0	
	Lighting - Wall Mounted	Basement	10	EA	7	\$0	
	Stairs - Concrete Stairs	Basement	5	LF	6	\$41	Steps down to switch gear room
	Walls - Concrete Block	Basement	160	SF	6	\$760	



211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Building Interior

	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corrido	••					- 5551	
3540	Walls - Concrete Block	Basement	12,700	SF	6	\$37,230	
	Walls - Masonry	Basement	735	SF	6		by stairs
	Walls - Plaster/Drywall	Basement	295	SF	6	\$1,308	2, 55
	Walls - Plaster/Drywall	Basement	5	SF	5		water damaged wall at transition from Main to
	•						Athletic
Safety							
	Camera Viewing Station		1	EA	6	\$683	Main office
	Metal Dedector		2	EA	6	\$1,761	at Door 2
	Security Cameras		3	EA	6	\$582	
Stairs							
	Ceiling - Plaster/Drywall	North East (by Rm 116)	10	SF	5	\$205	water damaged
	Ceiling - Plaster/Drywall	North East (by Rm 116)	358	SF	6	\$2,621	-
	Floor - Terrazzo	North East (by Rm 116)	704	SF	6	\$5,909	
	Handrails	North East (by Rm 116)	300	LF	6	\$2,600	
	Lighting - Lay-in	North East (by Rm 116)	23	EA	7	\$0	
	Stairs - Terrazzo	North East (by Rm 116)	75	LF	6	\$696	
	Walls - Masonry	North East (by Rm 116)	2,850	SF	6	\$8,966	
	Ceiling - Plaster/Drywall	NorthWest (by Main Office)	368	SF	6	\$2,694	
	Floor - Terrazzo	NorthWest (by Main Office)	704	SF	6	\$5,909	
	Handrails	NorthWest (by Main Office)	300	LF	6	\$2,600	
	Lighting - Lay-in	NorthWest (by Main Office)	23	EA	7	\$0	
	Stairs - Terrazzo	NorthWest (by Main Office)	75	LF	6	\$696	
	Walls - Masonry	NorthWest (by Main Office)	2,850	SF	6	\$8,966	
	Ceiling - Plaster/Drywall	South East (by Rm 120A)	368	SF	6	\$2,694	
	Floor - Terrazzo	South East (by Rm 120A)	528	SF	6	\$4,432	
	Handrails	South East (by Rm 120A)	104	LF	6	\$901	
	Lighting - Lay-in	South East (by Rm 120A)	20	EA	7	\$0	
	Stairs - Terrazzo	South East (by Rm 120A)	51	LF	6	\$473	
	Walls - Masonry	South East (by Rm 120A)	2,275	SF	6	\$7,157	
	Ceiling - Plaster/Drywall	South West (by Rm 104)	368	SF	6	\$2,694	
	Floor - Terrazzo	South West (by Rm 104)	704	SF	6	\$5,909	
	Handrails	South West (by Rm 104)	300	LF	6	\$2,600	
	Lighting - Lay-in	South West (by Rm 104)	23	EA	7	\$0	
	Stairs - Terrazzo	South West (by Rm 104)	1	LF	5	\$54	edge damaged
	Stairs - Terrazzo	South West (by Rm 104)	74	LF	6	\$687	
	Walls - Masonry	South West (by Rm 104)	2,850	SF	6	\$8,966	



211 S Laflin St Chicago, IL 60607

Building: Main - Building A Category: Building Interior

Group Item - Type	Location	Quantity U	Jnit	Rank	Cost	Comments		
Vertical Conveyance								
Elevator - Hydraulic Elevator		3 E	EΑ	6	\$57,714			
Building Interior Subtotal:				\$1	,012,174		 	

\$8,414,742

Total Building Cost

SITE

Category: Site

oup	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
nletic							
	Lighting	North	5	EA	6	\$18,021	
	Metal Bleachers	North	75	LF	6	\$3,346	
	Surface - Asphalt	North	26,400	SF	5	\$120,429	Cracks throughout
	Surface - Natural	North	67,934	SF	6	\$56,344	
	Surface - Natural	North	67,094	SF	6	\$55,648	
/il/Dra	ainage						
	Civil/ Drainage - Catch Basin	Entire Site	36	EA	7	\$0	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	5	\$1,379	Unstable cover flips up if walked, or drove over (Bottom of Service Ramp)
	Civil/ Drainage - Site Manhole	Entire Site	24	EA	7	\$0	
	Civil/ Drainage - Site Manhole	Entire Site / North	1	EA	4	\$5,941	Major Sinking (Located north of Bldg A) - Tripping hazard
ncing	ı						
	Fencing - Chain Link	Entire Site	2,189	LF	6	\$41,100	
	Fencing - New Standard Ornamental	Entire Site / Site North	300	LF	6	\$9,571	
	Fencing - New Standard Ornamental	Entire Site / Site North	10	LF	5	\$1,424	Bent/ Damaged
	Fencing - New Standard Ornamental	Entire Site / Site South	150	LF	6	\$4,785	
	Fencing - Old Standard Ornamental	Entire Site / Site North	10	LF	5	\$1,670	Bent/ Damaged
	Fencing - Old Standard Ornamental	Entire Site / Site North	300	LF	6	\$15,530	Rusting (Need to be Scraped/porimed/painted)
	Fencing - Old Standard Ornamental	Entire Site / Site South	10	LF	5	\$1,670	Bent/ Damaged
	Fencing - Old Standard Ornamental	Entire Site / Site South	1,428	LF	6	\$73,922	Rusting (Need to be Scraped/porimed/painted)
ndsca	аре						
	Benches	Entire Site	1	EA	5	\$887	Damaged (South of Bldg C)
	Benches	Entire Site	14	EA	6	\$6,021	
	Irrigation	Entire Site	215,315	SF	5	\$578,853	

211 S Laflin St Chicago, IL 60607

SITE

Category: Site

р	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
sca	аре						
	Landscape - Grass	Entire Site	80,287	SF	6	\$66,590	
	Landscape - Hardscape- Concrete	Entire Site	49,479	SF	6	\$255,425	Sinkage on East and South sides of Bldg A
	Landscape - Hardscape- Concrete	Entire Site / North	1,000	SF	5	\$12,756	Major sinking (North of Building A)
	Lighting - Pole Mounted	Entire Site	11	EA	6	\$11,921	
	Parkway trees	Entire Site	116	EA	6	\$76,565	
	Planting Beds/ Area	Entire Site	13,943	SF	6	\$22,929	
	Retaining Wall - Concrete	Entire Site	1,068	SF	6	\$29,552	
	Retaining Wall - Concrete	Entire Site / Loading Dock Ramp	1,932	SF	6	\$45,282	
	Trash Receptacles	Entire Site	16	EA	6	\$4,997	
ing	Lot						
	Concrete Curbs	Entire Site	3,262	LF	6	\$41,889	
	Interior Plantings	Entire Site	528	LF	6	\$22,462	
	Lighting - Pole Mounted	Entire Site	64	EΑ	6	\$92,959	
	Surface - Asphalt	Entire Site	100,248	SF	6	\$242,269	
	Surface - Asphalt	Entire Site / Parking Lot- South	2,000	SF	5	\$11,812	
	Surface - Concrete	Entire Site	13,616	SF	6	\$32,906	
	Trash Compactor	Entire Site / Loading Dock	1	EΑ	6	\$0	
	Trash Enclosure - Chain Links	Entire Site	422	SF	6	\$7,404	
	Vehicular Screening	Entire Site	870	LF	6	\$68,500	
wal	ks						
	Sidewalks - Internal Walks	Entire Site	3,351	LF	6	\$40,252	
	Sidewalks - Internal Walks	Site South	400	LF	5	\$19,934	Spalling/ Cracks/ Sinkage
	Sidewalks - Perimeter Sidewalks	Entire Site	100,430	SF	6	\$199,625	
	Sidewalks - Perimeter Sidewalks	Site South	208	SF	5	\$1,987	Spalling/ Cracks/ Sinkage
age	•						
	Flag Pole - Flag Pole	Entire Site	1	EA	6	\$1,657	
	Marquee - Free Standing Back Lighted	Entire Site	1	EA	6	\$0	Located Loomis & Jackson
	Marquee - Free Standing Back Lighted	Entire Site / Main Entrance	1	EA	6	\$0	
	Monument - Building Mounted Cut Letter Sign	Entire Site / South Façade	1	EA	6	\$0	Located at Bldg C
	Monument - Sign	Entire Site	1	EA	6	\$0	Located at Bldg B
	Monument - Sign	Entire Site	2	EA	6	\$0	Located at Bldg C
	Monument - Sign-Lighted	Entire Site	2	EA	6	\$0	Located at Bldg A
	Monument - Sign-Lighted	Entire Site	2	EΑ	6	\$0	Located Laflin & Jackson

Site Subtotal: \$2,306,215



211 S Laflin St Chicago, IL 60607

Total Site Cost \$2,306,215

Campus Total ^{2 3} \$18,089,417

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- Quantity means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- Cost means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.
- Campus Total also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.



211 S Laflin St Chicago, IL 60607

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Linked Addition-Ar	ts Building C	-												1
Art Room	Art Room	1st Floor	175	NA	856	1	8	20	170	0	40	N	Υ	N
Art Room	Art Room	1st Floor	177	NA	1,322	1	12	24	90	0	40	N	Υ	N
Art Room	Art Room	1st Floor	179	NA	1,300	1	12	24	135		40	N	Υ	N
Art Room	Art Room	1st Floor	181	NA	1,420	1	12	24	90	0	40	N	Υ	N
Band Room	Band Room	1st Floor	198	NA	2,441	1	8	20	150	0	40	N	Υ	N
Choral Room	Choral Room	1st Floor	196	NA	1,109	1	8	20	117	0	40	N	Υ	Υ
Computer Lab	Art Room	1st Floor	178	NA	1,466	1	25	74	90	0	40	N	Υ	N
Computer Lab	Computer Lab	2nd Floor	277	NA	1,032	1	30	60	348	26	40	N	Υ	Υ
Computer Lab	Computer Lab	2nd Floor	279	NA	1,167	1	30	60	398	39	40	N	Υ	N
Dance Room	Regular Classroom	1st Floor	184	NA	2,170	1	12	24	249	0	40	N	Υ	N
Music Room	Music Room	1st Floor	188	NA	1,073	1	2	12	0	0	40	N	Υ	N
Music Room	Art Room	1st Floor	190	NA	1,498	1	1	20	190	0	40	N	N	N
Music Room	Music Room	1st Floor	191	NA	689	1	1	10	90	0	40	N	Υ	Υ
Music Room	Music Room	1st Floor	197	NA	682	1	8	20	72	0	40	N	Υ	Υ
Other Instructional Use	Computer Lab	2nd Floor	278	NA	1,335	1	30	60	448	39	40	N	Υ	N
Physical Education Room	Regular Classroom	2nd Floor	290	NA	2,186	1	16	32	935	78	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	275	NA	879	1	8	20	594	52	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	282	NA	879	1	8	20	594	52	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	291	NA	1,388	1	10	20	298	26	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	292	NA	879	1	8	20	299	26	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	293	NA	569	1	8	20	198	26	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	294	NA	1,218	1	8	20	245	26	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	295	NA	1,436	1	8	20	293	26	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	297	NA	733	1	6	12	544	52	40	N	Υ	Υ
Regular Classroom	Regular Classroom	2nd Floor	298	NA	604	1	6	12	245	26	40	N	Υ	Υ
Store Room	Regular Classroom	2nd Floor	281	NA	879	1	8	20	299	26	40	N	Υ	Υ
Linked Addition-At	hletic Building B													
Regular Classroom	Regular Classroom	1st Floor	154	NA	664	1	6	12	0	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	156	NA	664	1	6	12	0	0	40	N	N	N
Main - Building A														
Computer Lab	Laboratory/Shop	1st Floor	109	NA	2,438	2	16	44	0	0	40	N	Υ	N
Computer Lab	Computer Lab	1st Floor	122	NA	1,037	2	32	64	0	0	40	N	Y	Y
Computer Lab	Computer Lab	2nd Floor	222B	NA	285	1	20	22	0	0	40	N	N	N
Computer Lab	Computer Lab	2nd Floor	222C	NA	300	1	18	20	0	0	40	N	N	N
Computer Lab	Other Instructional Use	2nd Floor	228	NA	2,174	1	22	30	944	144	40	N	N	N
1			_		,		1			I	1 -			1



211 S Laflin St Chicago, IL 60607

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main - Building A														
Computer Lab	Computer Lab	2nd Floor	230	NA	1,350	1	48	60	354	54	40	N	N	N
Computer Lab	Computer Lab	3rd Floor	305	NA	810	2	30	60	300	26	40	N	N	N
Computer Lab	Computer Lab	3rd Floor	306	NA	810	2	30	60	300	26	40	N	N	N
Office	Regular Classroom	2nd Floor	212	NA	492	1	6	10	0	0	40	N	N	N
Other Instructional Use	Office	2nd Floor	1F	NA	600	2	12	16	0	0	40	N	N	N
Other Instructional Use	Regular Classroom	2nd Floor	214	NA	475	1	16	20	0	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	105	105	811	1	2	18	294	0	40	N	N	Υ
Regular Classroom	Regular Classroom	1st Floor	106	106	811	1	2	16	294	0	40	N	N	Υ
Regular Classroom	Regular Classroom	1st Floor	107	107	811	1	2	16	294	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	110	NA	1,178	2	8	22	0	0	40	N	Υ	Y
Regular Classroom	Science Lab Level 3	1st Floor	115	NA	860	2	8	16	294	0	40	N	Υ	Υ
Regular Classroom	Regular Classroom	1st Floor	116	NA	860	2	8	16	294	0	40	N	Υ	Υ
Regular Classroom	Regular Classroom	1st Floor	117	117	1,026	1	2	10	0	0	40	N	N	N
Regular Classroom		1st Floor	119	119	735	1	2	10	0	0	40	N	N	Y
Regular Classroom		1st Floor	127	127	689	1	2	10	0	0	40	N	N	Υ
Regular Classroom	Regular Classroom	1st Floor	129	129	738	1	6	20	0	0	40	N	N	Υ
Regular Classroom		1st Floor	136	136	1,020	1	2	14	0	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	200	NA	735	2	8	16	545	52	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	201	NA	735	2	8	16	247	26	40	N	N	Υ
Regular Classroom	Regular Classroom	2nd Floor	202	NA	735	2	8	16	247	26	40	N	N	Υ
Regular Classroom	Regular Classroom	2nd Floor	203	NA	520	1	10	12	0	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	204	NA	900	2	8	16	300	26	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	205	NA	900	2	8	16	300	26	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	206	NA	900	2	8	16	300	26	40	N	N	Υ
Regular Classroom	Regular Classroom	2nd Floor	207	NA	900	2	8	16	300	26	40	N	Υ	N
Regular Classroom	Regular Classroom	2nd Floor	208	NA	735	2	8	16	247	26	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	209	NA	735	2	8	16	247	26	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	210	NA	735	2	8	16	545	52	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	213	NA	492	1	18	34	0	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	215	NA	492	1	18	34	0	0	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	218	NA	1,484	2	8	50	835	65	40	N	N	Υ
Regular Classroom	Regular Classroom	3rd Floor	300	NA	735	2	8	16	545	52	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	301	NA	735	2	8	16	247	26	40	N	N	Υ
Regular Classroom	Regular Classroom	3rd Floor	302	NA	735	2	8	16	247	26	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	304	NA	899	2	8	16	300	26	40	N	N	Υ
Regular Classroom	Regular Classroom	3rd Floor	307	NA	810	2	8	16	300	26	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	308	NA	735	2	8	16	247	26	40	N	N	Υ



211 S Laflin St Chicago, IL 60607

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart- Board
Main - Building A	·	•	*		*	•				•	•			
Regular Classroom	Regular Classroom	3rd Floor	309	NA	735	2	8	16	247	26	40	N	N	Υ
Regular Classroom	Regular Classroom	3rd Floor	310	NA	735	2	8	16	545	52	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	312	NA	495	1	2	6	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	314	NA	495	1	2	6	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	NA	495	1	2	6	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	321	NA	576	1	5	18	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	345	NA	576	1	5	18	0	0	40	N	N	Υ
Regular Classroom	Regular Classroom	3rd Floor	347	NA	723	1	4	10	0	0	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	348	NA	723	1	4	10	0	0	40	N	N	Υ
Science Classroom	Science Classroom	3rd Floor	344	NA	859	1	4	18	0	0	0	N	N	Υ
Science Lab Level 1	Science Lab Level 1	3rd Floor	318	NA	1,172	2	12	26	690	84	40	N	N	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	319	NA	576	1	5	18	0	0	40	N	N	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	320	NA	1,196	2	12	26	351	48	40	N	N	Υ
Science Lab Level 1	Science Lab Level 1	3rd Floor	322	NA	1,116	2	12	26	351	48	40	N	N	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	326	NA	1,196	2	12	26	351	48	40	N	N	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	328	NA	1,499	2	12	26	690	84	40	N	N	N
Science Lab Level 1	Science Lab Level 1	3rd Floor	330	NA	1,458	1	6	12	320	48	40	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	316	NA	1,124	1	5	18	356	48	40	N	N	Υ
Science Lab Level 3	Science Lab Level 3	3rd Floor	327	NA	576	1	5	18	0	0	40	N	N	Υ
Science Lab Level 3	Science Lab Level 3	3rd Floor	341	NA	576	1	5	18	0	0	40	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	342	NA	865	1	4	24	0	0	40	N	N	N
Special Education	Office	1st Floor	113	NA	420	1	2	10	0	0	40	N	N	Υ
Special Education	Regular Classroom	1st Floor	114	NA	860	2	8	16	294	0	40	N	Υ	Υ
Special Education	Regular Classroom	1st Floor	126	NA	1,121	2	8	16	0	0	40	N	Υ	Υ
Special Education	Regular Classroom	1st Floor	131	NA	421	2	8	16	0	0	40	N	Υ	Υ
Special Education	Office	1st Floor	132	133	421	1	1	10	0	0	40	N	N	Υ
Special Education		1st Floor	138	135	667	2	4	24	0	0	40	N	N	Υ
Special Education	Regular Classroom	3rd Floor	313	NA	495	1	2	6	0	0	40	N	N	N
Special Program	Regular Classroom	2nd Floor	220	NA	960	1	2	4	0	0	40	N	N	N