

Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1893	3	48,585	\$1,489,535
Addition 1	1923	3	59,963	\$1,921,124
Addition 2	1953	3	38,561	\$1,292,928
SITE				\$380,560
Campus Total			147,109	\$5,084,147

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Main Entrance 1-North / Ariel	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	Entrance 10-South	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 11-SW	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	Entrance 12-SW	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 13-North	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 9-SE / Boiler Room	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Main Entrance 1-North / Ariel	3	EA	6	\$1,442	
	Exterior Doors - Side lite	Entrance 12-SW	2	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 10-South	1	EA	6	\$313	Chipped and peeling
	Exterior Doors - Transom Lite	Entrance 12-SW	1	EA	7	\$0	
	Exterior Doors - Transom Lite	Main Entrance 1-North / Ariel	3	EA	7	\$0	
	Exterior Stairs - Concrete	Entrance 13-North	15	LF	7	\$0	
	Exterior Stairs - Concrete	Main Entrance 1-North / Ariel	35	LF	6	\$2,862	
	Exterior Stairs - Stone	Entrance 9-SE / Boiler Room	6	LF	6	\$678	
	Stair Handrail - Steel_Stair Handrail	Main Entrance 1-North / Ariel	25	LF	6	\$217	
Foundation							
	Foundation - Masonry	Entire Building	14,290	LF	7	\$0	
	Superstructure - Heavy Timber	Entire Building	48,585	SF	7	\$0	

Building: Main

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Foundation							
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	15	EA	6	\$4,331	
Roof System							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 1	51	LF	6	\$48,689	
	Coping - Metal	Roof 1	730	LF	6	\$23,446	
	Coping - Stone	Roof 1	27	LF	6	\$867	
	Downspouts - Exterior Downspouts	Roof 1	372	LF	6	\$12,363	
	Downspouts - Interior Downspouts	Roof 1	319	LF	6	\$10,601	
	Roof Structure - Heavy Timber	Roof 1	19,483	SF	7	\$0	
	Roof - Asphalt Shingle	Roof 1	18,910	SF	6	\$86,803	
	Roof - Metal	Roof 1	883	SF	6	\$11,831	
Walls							
	Exterior Walls - Brick	Entire Building	20,695	SF	6	\$139,091	
	Exterior Walls - Stone-Cast	Entire Building	2,630	SF	6	\$17,676	
Windows							
	Guard - Guards perforated	Entire Building / 1st Floor	513	SF	6	\$6,551	
	Lintels - Brick	Entire Building	248	LF	7	\$0	
	Lintels - Steel	Entire Building	47	LF	7	\$0	
	Lintels - Stone	Entire Building	296	LF	7	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	5,202	SF	6	\$38,831	
Building Exterior Subtotal:						\$411,618	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	7,363	SF	6	\$2,211	
	Emergency A/C Power - Students Toilets	Entire Building	406	SF	6	\$151	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	58	EA	6	\$11,745	
	Emergency Generator- Indoor- Natural Gas - Below 60 KW	Electrical Room / Mechanical Room	1	EA	6	\$6,086	Serves main and both additions.
	Exit Signs - Corridors and Stairs	Entire Building	30	EA	7	\$0	
	Security System - Intrusion Detection	Electrical Room / Entire Building	48,585	SF	6	\$12,506	

Building: Main

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
Main Service							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	7	\$0	Emergency Feed from ComEd
	Main Electrical Service - 2000 A 277/480/3PH	Electrical Room	1	EA	6	\$8,662	also serves the Additions
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	Electrical Room	1	EA	6	\$11,555	also serves the Additions
	PA System	Entire Building	48,585	SF	6	\$15,980	Served from Addition 2
Power Distribution							
	Lighting and Power Panels - 100 A	Electrical Room	1	EA	6	\$299	Emergency fuse type
	Lighting and Power Panels - Above 100 A	Electrical Room	5	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	5	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	3	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	4	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Less than 400 amp	Electrical Room	1	EA	7	\$0	Emergency
	Transformers - 277/480 - 120/208	Electrical Room	1	EA	6	\$1,265	Serves Emergency power
	Transformers - 277/480 - 120/208	Electrical Room	2	EA	6	\$2,530	
	Transformers - 277/480 - 120/208	Electrical Room	1	EA	6	\$1,265	
Electrical System Subtotal:						\$75,070	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Panel	Electrical Room	1	EA	6	\$6,406	Serves entire site (Main,ADD1,ADD2)
	Fire Alarm Strobe Lights	Electrical Room / Entire Building	48,585	SF	6	\$17,369	
	Fire Alarm_System	Electrical Room / Entire Building	48,585	SF	6	\$23,622	
	Fire Pump Controller	Electrical Room / Mechanical Room	1	EA	6	\$1,823	
Pump Room Assembly							
	Fire Pump - 25-50 hp	Mechanical Room	1	EA	6	\$1,558	Serves the Main and Addition 1 and 2
	Jockey Pump	Mechanical Room	1	EA	6	\$758	Serves the Main and Addition 1 and 2
Sprinkler System							
	Combination Wet and Dry Sprinkler System	Entire Building	48,585	SF	7	\$0	
	Sprinkler Heads	Entire Building	48,585	SF	7	\$0	
	Sprinkler Piping	Entire Building	48,585	SF	7	\$0	

Building: Main

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Sprinkler System							

Safty System Subtotal: \$51,536

Building: Main

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							

	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 20001-30000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves Building
	Air Intake	Mechanical Room / Roof	1	EA	6	\$5,765	
	Fan Coil Unit- Floor Mounted - Dual Temperature Coil	Entire Building	40	EA	6	\$71,716	

Heating Devices

	Cabinet Heaters - With Hot Water Coil	Entire Building	2	EA	6	\$709	
	Fin Tube - Hot Water	Entire Building	80	LF	6	\$755	
	Unit Heater - Electric	Entire Building	2	EA	6	\$556	

Mechanical Plumbing

	Hydronic Supply and Return - Copper	Entire Building	200	LF	6	\$10,493	
	Hydronic Supply and Return - Steel	Entire Building	100	LF	6	\$7,678	

Temperature Control

	DDC System	Entire Building	48,585	SF	5	\$79,898	DDC and computer need update not all areas have Temperature control
	Electric Thermostat	Entire Building	42	EA	6	\$0	Serves Fan Coil Units
	Thermostats - DDC	Entire Building	1	EA	6	\$0	Serves AH -4

Ventilation

	Exhaust Fans- Indoor - Less than 500 CFM	Roof / Entire Building	2	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	3	EA	6	\$1,777	Lack of Safe access to equipment
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof	4	EA	6	\$1,185	Lack of Safe access to equipment

Mechanical System Subtotal: \$184,473

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							

	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	48,585	SF	6	\$9,727	
--	--	-----------------	--------	----	---	---------	--

Building: Main

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	48,585	SF	6	\$11,811	
	Domestic Piping-Cold Water Risers	Entire Building	48,585	SF	6	\$9,032	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	48,585	SF	6	\$7,642	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	48,585	SF	6	\$9,032	
	Domestic Piping-Hot Water Return Lines	Entire Building	48,585	SF	6	\$6,948	
	Domestic Piping-Hot Water Return Risers	Entire Building	48,585	SF	6	\$6,948	
	Sanitary Piping	Entire Building	48,585	SF	6	\$44,465	
	Storm Piping	Entire Building	48,585	SF	6	\$42,381	
	Vent Piping	Entire Building	48,585	SF	6	\$32,654	
Pumps							
	Pumps - Domestic Booster Pump-Duplex	Mechanical Room	1	EA	6	\$1,977	Serves main and additions.

Plumbing System Subtotal: \$182,616

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #A1 (Special Program)							
	Casework	Basement	8	LF	6	\$202	
	Ceiling - Lay-in	Basement	350	SF	6	\$1,051	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Floor - Carpet	Basement	350	SF	6	\$746	
	Lighting - Lay-in	Basement	4	EA	6	\$476	
	Marker Board	Basement	8	LF	6	\$171	
	Walls - Plaster/Drywall	Basement	665	SF	6	\$1,835	
Classroom #A101 (Kindergarten)							
	Casework	1st Floor	30	LF	6	\$758	
	Ceiling - Plaster/Drywall	1st Floor	875	SF	6	\$3,028	
	Chalk Board	1st Floor	18	LF	4	\$1,653	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	875	SF	6	\$876	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	1st Floor	1,392	SF	6	\$3,842	
	Work Sink	1st Floor	2	EA	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #A102 (Pre School)							
	Casework	1st Floor	60	LF	6	\$1,515	
	Ceiling - Plaster/Drywall	1st Floor	846	SF	6	\$2,928	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	846	SF	6	\$847	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	1st Floor	1,376	SF	6	\$3,798	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #A103 (Pre School)							
	Casework	1st Floor	60	LF	6	\$1,515	
	Ceiling - Plaster/Drywall	1st Floor	903	SF	6	\$3,125	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	903	SF	6	\$904	
	Lighting - Pendent/Surface	1st Floor	18	EA	6	\$2,230	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	1st Floor	1,444	SF	6	\$3,985	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #A104 (Regular Classroom)							
	Casework	1st Floor	53	LF	6	\$1,338	
	Ceiling - Plaster/Drywall	1st Floor	903	SF	6	\$3,125	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Carpet	1st Floor	903	SF	6	\$1,924	
	Lighting - Pendent/Surface	1st Floor	18	EA	6	\$2,230	
	Marker Board	1st Floor	8	LF	6	\$171	
	Storage/ Closet	1st Floor	160	SF	6	\$1,160	Wardrobe
	Walls - Plaster/Drywall	1st Floor	1,420	SF	6	\$3,919	
Classroom #A105 (Regular Classroom)							
	Casework	1st Floor	24	LF	6	\$606	
	Ceiling - Plaster/Drywall	1st Floor	986	SF	6	\$3,412	
	Chalk Board	1st Floor	8	LF	4	\$734	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	986	SF	6	\$987	
	Lighting - Pendent/Surface	1st Floor	18	EA	6	\$2,230	
	Walls - Plaster/Drywall	1st Floor	2,457	SF	6	\$6,781	
	Work Sink	1st Floor	2	EA	6	\$758	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #A105 (Regular Classroom)							
Classroom #A107 (Regular Classroom)							
	Casework	1st Floor	26	LF	6	\$657	
	Ceiling - Plaster/Drywall	1st Floor	883	SF	6	\$3,056	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	883	SF	6	\$884	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	10	LF	6	\$214	
	Storage/ Closet	1st Floor	80	SF	6	\$580	Wardrobe
	Walls - Plaster/Drywall	1st Floor	1,377	SF	6	\$3,800	
Classroom #A108 (Regular Classroom)							
	Casework	1st Floor	17	LF	6	\$429	
	Ceiling - Plaster/Drywall	1st Floor	1,017	SF	6	\$3,519	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,017	SF	6	\$1,018	
	Lighting - Pendent/Surface	1st Floor	16	EA	6	\$1,982	
	Marker Board	1st Floor	8	LF	6	\$171	
	Storage/ Closet	1st Floor	120	SF	6	\$870	Wardrobe
	Walls - Plaster/Drywall	1st Floor	2,278	SF	6	\$6,287	
Classroom #A2 (Special Education)							
	Ceiling - Lay-in	Basement	120	SF	6	\$360	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Floor - Carpet	Basement	120	SF	6	\$256	
	Lighting - Lay-in	Basement	2	EA	6	\$238	
	Walls - Plaster/Drywall	Basement	228	SF	6	\$629	
Classroom #A201 (Regular Classroom)							
	Casework	2nd Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	2nd Floor	866	SF	6	\$2,997	
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	866	SF	6	\$867	
	Lighting - Pendent/Surface	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	7	\$0	
	Storage/ Closet	2nd Floor	150	SF	6	\$1,088	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #A201 (Regular Classroom)							
	Walls - Plaster/Drywall	2nd Floor	1,356	SF	6	\$3,742	
Classroom #A202 (Regular Classroom)							
	Casework	2nd Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	2nd Floor	947	SF	6	\$3,277	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	947	SF	6	\$948	
	Lighting - Pendent/Surface	2nd Floor	18	EA	6	\$2,230	
	Storage/ Closet	2nd Floor	150	SF	6	\$1,088	
	Walls - Plaster/Drywall	2nd Floor	1,356	SF	6	\$3,742	
Classroom #A203 (Regular Classroom)							
	Casework	2nd Floor	36	LF	6	\$909	
	Ceiling - Plaster/Drywall	2nd Floor	875	SF	6	\$3,028	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	875	SF	6	\$876	
	Lighting - Pendent/Surface	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	20	LF	7	\$0	
	Storage/ Closet	2nd Floor	92	SF	6	\$667	
	Walls - Plaster/Drywall	2nd Floor	1,356	SF	6	\$3,742	
Classroom #A204 (Regular Classroom)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Plaster/Drywall	2nd Floor	866	SF	6	\$2,997	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	866	SF	6	\$867	
	Lighting - Pendent/Surface	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	6	LF	7	\$0	
	Storage/ Closet	2nd Floor	135	SF	6	\$979	
	Walls - Plaster/Drywall	2nd Floor	1,356	SF	6	\$3,742	
Classroom #A205 (Regular Classroom)							
	Casework	2nd Floor	24	LF	6	\$606	
	Ceiling - Plaster/Drywall	2nd Floor	851	SF	6	\$2,945	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	2nd Floor	851	SF	6	\$852	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #A205 (Regular Classroom)							
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	6	LF	7	\$0	
	Storage/ Closet	2nd Floor	68	SF	6	\$493	
	Walls - Plaster/Drywall	2nd Floor	1,385	SF	6	\$3,822	
Classroom #A207 (Regular Classroom)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Plaster/Drywall	2nd Floor	853	SF	6	\$2,952	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	853	SF	6	\$854	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	8	LF	6	\$171	
	Storage/ Closet	2nd Floor	90	SF	6	\$653	
	Walls - Plaster/Drywall	2nd Floor	1,356	SF	6	\$3,742	
Classroom #A208 (Regular Classroom)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Plaster/Drywall	2nd Floor	853	SF	6	\$2,952	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	853	SF	6	\$854	
	Lighting - Pendent/Surface	2nd Floor	16	EA	7	\$0	
	Marker Board	2nd Floor	28	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,356	SF	6	\$3,742	
Classroom #A4 (Music Room)							
	Casework	Basement	32	LF	6	\$808	
	Ceiling - Lay-in	Basement	824	SF	6	\$2,474	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Floor - Tile/Sheet	Basement	824	SF	6	\$825	
	Lighting - Lay-in	Basement	15	EA	6	\$1,785	
	Marker Board	Basement	8	LF	6	\$171	
	Storage/ Closet	Basement	130	SF	6	\$943	
	Walls - Plaster/Drywall	Basement	847	SF	6	\$2,338	
	Work Sink	Basement	2	EA	6	\$758	
Classroom #A9 (Art Room)							
	Ceiling - Lay-in	Basement	883	SF	6	\$2,652	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	

Building: Main

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #A9 (Art Room)							
	Floor - Tile/Sheet	Basement	883	SF	6	\$884	
	Lighting - Lay-in	Basement	16	EA	6	\$1,904	
	Storage/ Closet	Basement	150	SF	6	\$1,088	
	Walls - Plaster/Drywall	Basement	1,377	SF	6	\$3,800	

Classrooms Subtotal:

\$199,232

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Exposed	A303 library office	118	SF	6	\$175	
	Doors - Steel Doors incl hw	A303 library office	1	EA	6	\$301	
	Floor - Carpet	A303 library office	118	SF	6	\$251	
	Lighting - Pendent/Surface	A303 library office	4	EA	6	\$496	
	Power Distribution	A303 library office	8	EA	7	\$0	
	Storage/ Closet	A303 library office	110	SF	6	\$798	A303
	Walls - Plaster/Drywall	A303 library office	656	SF	6	\$1,810	
	Ceiling - Plaster/Drywall	A7 Staff Lounge	548	SF	6	\$1,896	
	Doors - Store Front	A7 Staff Lounge	1	EA	6	\$1,208	
	Floor - Wood	A7 Staff Lounge	548	SF	6	\$3,863	
	Lighting - Chandelier, Incandescent	A7 Staff Lounge	18	EA	6	\$8,596	
	Lighting - Pendent/Surface	A7 Staff Lounge	10	EA	6	\$1,239	
	Power Distribution	A7 Staff Lounge	8	EA	7	\$0	
	Walls - Concrete Block	A7 Staff Lounge	420	SF	6	\$1,231	
	Walls - Plaster/Drywall	A7 Staff Lounge	420	SF	6	\$1,159	
	Work Slnk	A7 Staff Lounge	1	EA	6	\$508	
	Ceiling - Lay-in	Assistant Principals Office	180	SF	6	\$541	
	Doors - Steel Doors incl hw	Assistant Principals Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Assistant Principals Office	180	SF	6	\$180	
	Lighting - Chandelier, Incandescent	Assistant Principals Office	18	EA	6	\$8,596	
	Lighting - Lay-in	Assistant Principals Office	4	EA	6	\$476	
	Power Distribution	Assistant Principals Office	8	EA	7	\$0	
	Walls - Plaster/Drywall	Assistant Principals Office	350	SF	6	\$966	
	Ceiling - Lay-in	B1 Exploratorium	175	SF	6	\$526	
	Doors - Steel Doors incl hw	B1 Exploratorium	1	EA	6	\$301	
	Floor - Tile/Sheet	B1 Exploratorium	175	SF	6	\$175	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Lighting - Lay-in	B1 Exploratorium	4	EA	7	\$0	
	Power Distribution	B1 Exploratorium	12	EA	7	\$0	
	Walls - Plaster/Drywall	B1 Exploratorium	558	SF	6	\$1,540	
	Ceiling - Lay-in	B101 Teachers room	175	SF	6	\$526	
	Doors - Steel Doors incl hw	B101 Teachers room	1	EA	6	\$301	
	Floor - Tile/Sheet	B101 Teachers room	175	SF	6	\$175	
	Lighting - Lay-in	B101 Teachers room	4	EA	7	\$0	
	Power Distribution	B101 Teachers room	12	EA	7	\$0	
	Walls - Plaster/Drywall	B101 Teachers room	558	SF	6	\$1,540	
	Ceiling - Lay-in	B201 teachers room	175	SF	6	\$526	
	Doors - Steel Doors incl hw	B201 teachers room	1	EA	6	\$301	
	Floor - Tile/Sheet	B201 teachers room	175	SF	6	\$175	
	Lighting - Lay-in	B201 teachers room	4	EA	7	\$0	
	Power Distribution	B201 teachers room	12	EA	7	\$0	
	Walls - Plaster/Drywall	B201 teachers room	558	SF	6	\$1,540	
	Ceiling - Lay-in	Basement East End	788	SF	6	\$2,366	
	Doors - Steel Doors incl hw	Basement East End	1	EA	6	\$301	
	Floor - Tile/Sheet	Basement East End	788	SF	6	\$789	
	Lighting - Lay-in	Basement East End	16	EA	6	\$1,904	
	Walls - Plaster/Drywall	Basement East End	894	SF	5	\$6,776	
	Ceiling - Lay-in	Basement next to Staff Lounge	788	SF	6	\$2,366	
	Doors - Steel Doors incl hw	Basement next to Staff Lounge	1	EA	6	\$301	
	Floor - Tile/Sheet	Basement next to Staff Lounge	788	SF	6	\$789	
	Lighting - Lay-in	Basement next to Staff Lounge	16	EA	6	\$1,904	
	Walls - Plaster/Drywall	Basement next to Staff Lounge	894	SF	6	\$2,467	
	Ceiling - Lay-in	Basement South of Room w/plan #23	729	SF	6	\$2,189	
	Doors - Steel Doors incl hw	Basement South of Room w/plan #23	1	EA	6	\$301	
	Floor - Tile/Sheet	Basement South of Room w/plan #23	729	SF	6	\$730	
	Lighting - Lay-in	Basement South of Room w/plan #23	12	EA	6	\$1,428	
	Walls - Plaster/Drywall	Basement South of Room w/plan #23	972	SF	6	\$2,683	
	Ceiling - Lay-in	Engineer Office	180	SF	6	\$541	
	Doors - Steel Doors incl hw	Engineer Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Engineer Office	180	SF	6	\$180	
	Lighting - Pendent/Surface	Engineer Office	2	EA	6	\$248	
	Power Distribution	Engineer Office	8	EA	7	\$0	
	Walls - Masonry	Engineer Office	350	SF	6	\$1,101	
	Walls - Plaster/Drywall	Engineer Office	350	SF	6	\$966	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	Main Office	228	SF	6	\$685	
	Doors - Steel Doors incl hw	Main Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Main Office	228	SF	6	\$228	
	Lighting - Chandelier, Incandescent	Main Office	18	EA	6	\$8,596	
	Lighting - Lay-in	Main Office	4	EA	6	\$476	
	Power Distribution	Main Office	8	EA	7	\$0	
	Storage/ Closet	Main Office	90	SF	6	\$653	
	Walls - Plaster/Drywall	Main Office	420	SF	6	\$1,159	
	Ceiling - Lay-in	Principals Office	350	SF	6	\$1,051	
	Doors - Steel Doors incl hw	Principals Office	1	EA	6	\$301	
	Floor - Tile/Sheet	Principals Office	350	SF	6	\$350	
	Lighting - Chandelier, Incandescent	Principals Office	18	EA	6	\$8,596	
	Lighting - Lay-in	Principals Office	6	EA	6	\$714	
	Power Distribution	Principals Office	8	EA	7	\$0	
	Walls - Plaster/Drywall	Principals Office	420	SF	6	\$1,159	
	Ceiling - Plaster/Drywall	Room in class room A202	150	SF	6	\$519	
	Doors - Steel Doors incl hw	Room in class room A202	1	EA	6	\$301	
	Floor - Tile/Sheet	Room in class room A202	150	SF	6	\$150	
	Lighting - Pendent/Surface	Room in class room A202	2	EA	7	\$0	
	Power Distribution	Room in class room A202	4	EA	7	\$0	
	Walls - Plaster/Drywall	Room in class room A202	675	SF	6	\$1,863	
Library							
	Casework	3rd Floor	73	LF	6	\$1,844	
	Ceiling - Exposed	3rd Floor	6,129	SF	6	\$9,115	
	Doors - Steel Doors incl hw	3rd Floor	2	EA	6	\$602	
	Floor - Carpet	3rd Floor	6,129	SF	6	\$13,059	
	Lighting - Pendent/Surface	3rd Floor	75	EA	7	\$0	
	Storage/ Closet	3rd Floor	23	SF	6	\$167	
	Walls - Plaster/Drywall	3rd Floor	4,765	SF	6	\$13,151	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	60	SF	6	\$430	All janitor closet are combined together
	Mechanical/ Service Rooms	1st Floor	250	SF	6	\$1,791	
	Storage Room	1st Floor	150	SF	6	\$1,075	All storage room combined together
	Mechanical/ Service Rooms	2nd Floor	72	SF	6	\$516	A206 electrical closet
	Storage Room	2nd Floor	138	SF	6	\$989	Next to A208
	Mechanical/ Service Rooms	3rd Floor	60	SF	6	\$430	A304 electrical closet

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical/ Service Rooms							
	Janitor's Closet	Basement	100	SF	6	\$716	All janitor closet are combined together
	Mechanical/ Service Rooms	Basement	1,350	SF	6	\$9,672	
	Storage Room	Basement	350	SF	6	\$2,508	All storage room are combined together
Restroom							
	Accessories	A101	43	SF	6	\$397	
	Ceiling - Plaster/Drywall	A101	43	SF	6	\$149	
	Doors - Steel Doors incl hw	A101	1	EA	6	\$301	
	Floor Drain	A101	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	A101	43	SF	6	\$91	
	Lighting - Pendent/Surface	A101	1	EA	6	\$124	
	Walls - Plaster/Drywall	A101	243	SF	6	\$671	
	Walls - Tile Ceramic/ Porcelain	A101	104	SF	6	\$235	
	Water Closet	A101	1	EA	6	\$336	
	Accessories	A102	43	SF	6	\$397	
	Ceiling - Plaster/Drywall	A102	43	SF	6	\$149	
	Doors - Steel Doors incl hw	A102	1	EA	6	\$301	
	Floor Drain	A102	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	A102	43	SF	6	\$91	
	Lighting - Pendent/Surface	A102	1	EA	6	\$124	
	Walls - Plaster/Drywall	A102	243	SF	6	\$671	
	Walls - Tile Ceramic/ Porcelain	A102	104	SF	6	\$235	
	Water Closet	A102	1	EA	6	\$336	
	Accessories	A103	43	SF	6	\$397	
	Ceiling - Plaster/Drywall	A103	43	SF	6	\$149	
	Doors - Steel Doors incl hw	A103	1	EA	6	\$301	
	Floor Drain	A103	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	A103	43	SF	6	\$91	
	Lighting - Pendent/Surface	A103	1	EA	6	\$124	
	Walls - Plaster/Drywall	A103	243	SF	6	\$671	
	Walls - Tile Ceramic/ Porcelain	A103	104	SF	6	\$235	
	Water Closet	A103	1	EA	6	\$336	
	Accessories	A105	43	SF	6	\$397	
	Ceiling - Plaster/Drywall	A105	43	SF	6	\$149	
	Doors - Steel Doors incl hw	A105	1	EA	6	\$301	
	Floor Drain	A105	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	A105	43	SF	6	\$91	
	Lighting - Pendent/Surface	A105	1	EA	6	\$124	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	A105	243	SF	6	\$671	
	Walls - Tile Ceramic/ Porcelain	A105	104	SF	6	\$235	
	Water Closet	A105	1	EA	6	\$336	
	Accessories	Girls restroom 3rd floor	406	SF	6	\$3,745	
	Ceiling - Lay-in	Girls restroom 3rd floor	406	SF	6	\$1,219	
	Doors - Steel Doors incl hw	Girls restroom 3rd floor	1	EA	6	\$301	
	Floor Drain	Girls restroom 3rd floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Girls restroom 3rd floor	406	SF	6	\$859	
	Lavatory	Girls restroom 3rd floor	2	EA	6	\$639	
	Lighting - Lay-in	Girls restroom 3rd floor	6	EA	7	\$0	
	Partitions	Girls restroom 3rd floor	5	EA	6	\$1,485	
	Walls - Plaster/Drywall	Girls restroom 3rd floor	245	SF	6	\$676	
	Walls - Structural Glazed Tile	Girls restroom 3rd floor	550	SF	6	\$1,730	
	Water Closet	Girls restroom 3rd floor	1	EA	6	\$336	
	Accessories	men's staff restroom in B201	34	SF	6	\$314	
	Ceiling - Lay-in	men's staff restroom in B201	34	SF	6	\$102	
	Doors - Steel Doors incl hw	men's staff restroom in B201	1	EA	6	\$301	
	Floor Drain	men's staff restroom in B201	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	men's staff restroom in B201	34	SF	6	\$72	
	Lavatory	men's staff restroom in B201	1	EA	6	\$320	
	Lighting - Lay-in	men's staff restroom in B201	1	EA	7	\$0	
	Walls - Plaster/Drywall	men's staff restroom in B201	101	SF	6	\$279	
	Walls - Tile Ceramic/ Porcelain	men's staff restroom in B201	134	SF	6	\$303	
	Water Closet	men's staff restroom in B201	1	EA	6	\$336	
	Accessories	Men's Toilet In Room B101	34	SF	6	\$314	
	Ceiling - Lay-in	Men's Toilet In Room B101	34	SF	6	\$102	
	Doors - Steel Doors incl hw	Men's Toilet In Room B101	1	EA	6	\$301	
	Floor Drain	Men's Toilet In Room B101	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's Toilet In Room B101	34	SF	6	\$72	
	Lavatory	Men's Toilet In Room B101	1	EA	6	\$320	
	Lighting - Lay-in	Men's Toilet In Room B101	1	EA	6	\$119	
	Walls - Plaster/Drywall	Men's Toilet In Room B101	101	SF	6	\$279	
	Walls - Tile Ceramic/ Porcelain	Men's Toilet In Room B101	134	SF	6	\$303	
	Water Closet	Men's Toilet In Room B101	1	EA	6	\$336	
	Accessories	Unisex Toilet in Room B1	34	SF	6	\$314	
	Ceiling - Lay-in	Unisex Toilet in Room B1	34	SF	6	\$102	
	Doors - Steel Doors incl hw	Unisex Toilet in Room B1	1	EA	6	\$301	

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	Unisex Toilet in Room B1	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Unisex Toilet in Room B1	34	SF	6	\$72	
	Lavatory	Unisex Toilet in Room B1	1	EA	6	\$320	
	Lighting - Lay-in	Unisex Toilet in Room B1	1	EA	6	\$119	
	Walls - Plaster/Drywall	Unisex Toilet in Room B1	101	SF	6	\$279	
	Walls - Tile Ceramic/ Porcelain	Unisex Toilet in Room B1	134	SF	6	\$303	
	Water Closet	Unisex Toilet in Room B1	1	EA	6	\$336	
	Accessories	Women's Toilet In Room B101	34	SF	6	\$314	
	Ceiling - Lay-in	Women's Toilet In Room B101	34	SF	6	\$102	
	Doors - Steel Doors incl hw	Women's Toilet In Room B101	1	EA	6	\$301	
	Floor Drain	Women's Toilet In Room B101	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's Toilet In Room B101	34	SF	6	\$72	
	Lavatory	Women's Toilet In Room B101	1	EA	6	\$320	
	Lighting - Lay-in	Women's Toilet In Room B101	1	EA	6	\$119	
	Walls - Plaster/Drywall	Women's Toilet In Room B101	101	SF	6	\$279	
	Walls - Tile Ceramic/ Porcelain	Women's Toilet In Room B101	134	SF	6	\$303	
	Water Closet	Women's Toilet In Room B101	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal:

\$194,207

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Plaster/Drywall	1st Floor	2,530	SF	6	\$15,666	
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	1st Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	1st Floor	2,530	SF	6	\$1,375	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	
	Student Lockers - One Tier	1st Floor	110	EA	6	\$10,212	
	Walls - Plaster/Drywall	1st Floor	4,807	SF	6	\$21,309	
	Ceiling - Plaster/Drywall	2nd Floor	1,919	SF	6	\$11,882	
	Doors - Steel Doors incl hw	2nd Floor	6	EA	6	\$1,806	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	2nd Floor	1,919	SF	6	\$1,043	
	Lighting - Pendent/Surface	2nd Floor	14	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	4,949	SF	6	\$21,939	

Building: Main

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	3rd Floor	262	SF	6	\$787	
	Ceiling - Plaster/Drywall	3rd Floor	509	SF	6	\$3,152	
	Doors - Steel Doors incl hw	3rd Floor	4	EA	6	\$1,204	
	Floor - Terrazzo	3rd Floor	153	SF	6	\$1,284	
	Floor - Tile/Sheet	3rd Floor	624	SF	6	\$339	
	Lighting - Lay-in	3rd Floor	3	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	5	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	2,067	SF	6	\$9,163	
	Ceiling - Lay-in	Basement	2,530	SF	6	\$7,598	
	Doors - Steel Doors incl hw	Basement	6	EA	6	\$1,806	
	Drinking Fountains - Double Water Cooler	Basement	1	EA	6	\$377	
	Floor - Tile/Sheet	Basement	2,530	SF	6	\$1,375	
	Lighting - Lay-in	Basement	20	EA	6	\$2,380	
	Stairs - Concrete Stairs	Basement	4	LF	6	\$33	
	Student Lockers - One Tier	Basement	110	EA	6	\$10,212	
	Walls - Plaster/Drywall	Basement	4,807	SF	6	\$21,309	
Stairs							
	Ceiling - Plaster/Drywall	Stairwell #1	392	SF	6	\$2,870	
	Floor - Asphalt	Stairwell #1	180	SF	6	\$1,395	
	Floor - Tile/Sheet	Stairwell #1	160	SF	6	\$87	
	Handrails	Stairwell #1	160	LF	6	\$1,387	
	Lighting - Pendent/Surface	Stairwell #1	3	EA	7	\$0	
	Stairs - Asphalt	Stairwell #1	66	LF	6	\$613	
	Walls - Plaster/Drywall	Stairwell #1	2,460	SF	6	\$6,789	
	Ceiling - Plaster/Drywall	Stairwell #2	369	SF	6	\$2,702	
	Floor - Asphalt	Stairwell #2	140	SF	6	\$1,085	
	Handrails	Stairwell #2	150	LF	6	\$1,300	
	Lighting - Pendent/Surface	Stairwell #2	3	EA	6	\$372	
	Stairs - Asphalt	Stairwell #2	74	LF	6	\$687	
	Walls - Plaster/Drywall	Stairwell #2	304	SF	6	\$839	
Vertical Conveyance							
	Elevator - Hydraulic Elevator	1st Floor	1	EA	6	\$19,238	

Building Interior Subtotal:

\$190,783

Total Building Cost

\$1,489,535

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Entrance 2-North / NKO main entrance	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	Entrance 2-North / NKO main entrance	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	Entrance 3-NE / Auditorium vestibule	6	EA	6	\$2,883	
	Exterior Doors - Exterior Steel Door	Entrance 4-East	2	EA	6	\$961	
	Exterior Doors - Transom Lite	Entrance 2-North / NKO main entrance	3	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 3-NE / Auditorium vestibule	3	EA	7	\$0	
	Exterior Doors - Transom Lite	Entrance 4-East	1	EA	7	\$0	
	Exterior Stairs - Concrete	Entrance 2-North / NKO main entrance	100	LF	6	\$8,177	
	Exterior Stairs - Concrete	Entrance 3-NE / Auditorium vestibule	100	LF	7	\$0	
	Exterior Stairs - Concrete	Entrance 4-East	6	LF	6	\$491	
	Power Door Operator and Controls	Entrance 2-North / NKO main entrance	35	EA	7	\$0	
	Ramp Handrail - Steel_Ramp Handrail	Entrance 3-NE / Auditorium vestibule	45	LF	7	\$0	
	Ramps - Concrete	Entrance 3-NE / Auditorium vestibule	20	LF	7	\$0	
	Stair Handrail - Steel_Stair Handrail	Entrance 2-North / NKO main entrance	20	LF	7	\$0	
Foundation							
	Foundation - Concrete	Entire Building	499	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	59,963	SF	7	\$0	
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	11	EA	6	\$3,176	
Roof System							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Roof 2, 3	51	LF	6	\$48,689	
	Chimney - Metal Flue	Roof 2, 3	30	LF	6	\$4,744	Lower roof 3
	Coping - Stone	Roof 2, 3	803	LF	6	\$25,791	
	Downspouts - Interior Downspouts	Roof 2, 3	319	LF	6	\$10,601	
	Parapet - 16" - 30" Height	Roof 2, 3	240	LF	6	\$9,589	
	Parapet - Parapet < 16" Height	Roof 2, 3	50	LF	6	\$1,065	
	Parapet - Parapet > 30"	Roof 2, 3	513	LF	6	\$32,791	
	Roof Structure - Steel with Clay Tile Arch	Roof 2, 3	18,450	SF	7	\$0	
	Roof - Modified Bitumen	Roof 2, 3	18,450	SF	6	\$173,603	
Walls							
	Cornice - Cast Stone	Entire Building	352	LF	6	\$12,206	
	Exterior Walls - Brick	Entire Building	26,146	SF	6	\$175,727	
	Exterior Walls - Stone-Cast	Entire Building	2,417	SF	6	\$16,245	

Building: Addition 1

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Walls							
Windows							
	Guard - Guards perforated	Entire Building	848	SF	6	\$10,829	
	Lintels - Steel	Entire Building	628	LF	7	\$0	
	Lintels - Stone	Entire Building	14	LF	6	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	5,421	SF	6	\$40,466	

Building Exterior Subtotal: \$580,179

Building: Addition 1

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	4,825	SF	6	\$2,553	The Lower Level Aisle Lights are inoperative, and the balcony is not provided with Aisle Lighting
	Emergency A/C Power - Corridors and Stairs	Entire Building	9,223	SF	6	\$2,770	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	2,992	SF	6	\$1,112	
	Emergency A/C Power - Students Toilets	Entire Building	2,538	SF	6	\$944	
	Emergency Battery Packs - Auditorium and Aisle Lighting	Entire Building / 1st Floor	14	EA	6	\$2,835	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	28	EA	6	\$5,670	
	Emergency Battery Packs - Lunchrooms	Entire Building / 1st Floor	4	EA	6	\$810	
	Exit Signs - Auditorium	Entire Building / 1st Floor	12	EA	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	9	EA	7	\$0	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	1	EA	7	\$0	
	Security System - Intrusion Detection	Entire Building	59,963	SF	6	\$15,434	
Main Service							
	PA System	Entire Building	59,963	SF	6	\$19,722	Served from Addition 2
Power Distribution							
	Lighting and Power Panels - Above 100 A	Electrical Room	2	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	6	EA	7	\$0	

Electrical System Subtotal: \$51,850

Building: Addition 1

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Addition 1

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	59,963	SF	6	\$21,437	
	Fire Alarm_System	Entire Building	59,963	SF	6	\$29,154	
Sprinkler System							
	Sprinkler Heads	Entire Building	59,963	SF	7	\$0	
	Sprinkler Piping	Entire Building	59,963	SF	7	\$0	
	Wet Sprinkler System	Entire Building	59,963	SF	7	\$0	Served from Main
Safty System Subtotal:						\$50,591	

Building: Addition 1

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Conditioning							
	Chemical Pot Feeder	Site South / Mechanical Room	1	EA	6	\$606	
	Chiller-Air Cooled-Screw Type-Ground Mounted - 201 - 300 tons	Site South	2	EA	7	\$0	
	Condensing Unit- Ground Mounted - Less than 5 tons	Site South / South Façade	1	EA	7	\$0	
	Glycol Feed	Site South / Mechanical Room	1	EA	7	\$0	
	Pipes - Chilled Water Pipe- Copper	Site South / Mechanical Room	200	LF	7	\$0	
	Pipes - Chilled Water Pipe- Steel	Site South / Mechanical Room	150	LF	7	\$0	
Air Handling Systems							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves Commo area
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 8001-12000 cfm	Mechanical Room	1	EA	6	\$3,350	Coils have been Repaired minor leaks, Serves Auditorium
	Air Intake	Mechanical Room / South Courtyard Façades	1	EA	7	\$0	
	Air Intake	Mechanical Room / South Courtyard Façades	2	EA	7	\$0	
	Fan Coil Unit- Floor Mounted - Dual Temperature Coil	Entire Building	20	EA	6	\$35,858	
	Make Up Air Unit- Indoor Mounted- Hot Water Coils - Less than 6000 cfm	Kitchen / 1st Floor	1	EA	6	\$3,350	
Boiler Systems							
	Boiler Auxiliary- Non Condensing Hot Water - Greater than 4000 MBH	Boiler Room	2	EA	6	\$4,093	
	Chemical Pot Feeder	Boiler Room / Mechanical Room	1	EA	6	\$725	
	Combustion Dampers	Boiler Room	3	EA	5	\$7,656	See Air Intakes - Fans were inoperative as well. Dampers are aluminum fan back draft dampers.
	Glycol Feed System	Boiler Room / Mechanical Room	1	EA	6	\$539	

Building: Addition 1

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Boiler Systems							
	Non Condensing- Water Tube- Flexible Tube- Force Draft- Hot Water Boiler - Greater than 4000 MBH	Boiler Room	2	EA	6	\$1,996	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building	5	EA	6	\$1,772	
	Fin Tube - Hot Water	Entire Building	60	LF	6	\$566	
	Unit Heater - Electric	Mechanical Room	7	EA	6	\$1,945	
Mechanical Plumbing							
	Chilled Water Pump - 10 - 20 HP	Mechanical Room	2	EA	6	\$2,485	
	Daul Temperature Pump - 21 - 50 HP	Mechanical Room	2	EA	6	\$2,485	
	Hot Water Pump - 10 - 20 HP	Boiler Room	2	EA	6	\$2,485	
	Hot Water Pump - Less than 10	Boiler Room	2	EA	6	\$2,222	
	Hydronic Supply and Return - Copper	Entire Building	500	LF	6	\$26,233	
	Hydronic Supply and Return - Steel	Entire Building	100	LF	6	\$7,678	
Temperature Control							
	DDC System	Entire Building	59,963	SF	5	\$98,609	Controls need to be updated served from Main
	Electric Thermostat	Entire Building	20	EA	6	\$0	Serves Fan Coils
	Thermostats - DDC	Entire Building	2	EA	6	\$0	Serves AH's
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Roof / Lower Roof	2	EA	6	\$592	
	Type I Exhaust Hood- Kitchen	Roof / 1st Floor	1	EA	2	\$28,265	Equipment doesn't fit under the hood.
	Type II Exhaust Hood- Warming Kitchen	Roof / 1st Floor	1	EA	6	\$920	Cleaning and service required

Mechanical System Subtotal:

\$238,963

Building: Addition 1

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Hot Water							
	Electric Heater - Less than 20 KW	Kitchen / 1st Floor	1	EA	4	\$7,667	Not used since 2010
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	1	EA	6	\$310	Serves also the Main Building and Addition 2
	Gas Heater - 150000 - 300000 BTU/HR	Mechanical Room	1	EA	6	\$310	Serves also the Main Building and Addition 2
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	59,963	SF	6	\$12,005	

Building: Addition 1

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	59,963	SF	6	\$14,577	
	Domestic Piping-Cold Water Risers	Entire Building	59,963	SF	6	\$11,147	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	59,963	SF	6	\$9,432	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	59,963	SF	6	\$11,147	
	Domestic Piping-Hot Water Return Lines	Entire Building	59,963	SF	6	\$8,575	
	Domestic Piping-Hot Water Return Risers	Entire Building	59,963	SF	6	\$8,575	
	Sanitary Piping	Entire Building	59,963	SF	6	\$54,878	
	Storm Piping	Entire Building	59,963	SF	6	\$52,306	
	Vent Piping	Entire Building	59,963	SF	6	\$40,301	

Plumbing System Subtotal:

\$231,229

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #B102 (Special Education)							
	Casework	1st Floor	30	LF	6	\$758	
	Ceiling - Lay-in	1st Floor	919	SF	6	\$2,760	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	919	SF	6	\$920	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	1st Floor	1,082	SF	6	\$2,986	

Classroom #B103 (Other Instructional Use)

	Casework	1st Floor	30	LF	6	\$758	
	Ceiling - Lay-in	1st Floor	927	SF	6	\$2,784	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	927	SF	6	\$928	
	Lighting - Lay-in	1st Floor	18	EA	6	\$2,142	
	Marker Board	1st Floor	12	LF	6	\$257	
	Storage/ Closet	1st Floor	90	SF	6	\$653	
	Walls - Plaster/Drywall	1st Floor	1,125	SF	6	\$3,105	

Classroom #B104 (Other Instructional Use)

	Ceiling - Lay-in	1st Floor	927	SF	6	\$2,784	
	Chalk Board	1st Floor	12	LF	4	\$1,102	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #B104 (Other Instructional Use)							
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	927	SF	6	\$928	
	Lighting - Lay-in	1st Floor	18	EA	6	\$2,142	
	Marker Board	1st Floor	8	LF	6	\$171	
	Storage/ Closet	1st Floor	120	SF	6	\$870	
	Walls - Plaster/Drywall	1st Floor	1,125	SF	6	\$3,105	
Classroom #B105 (Regular Classroom)							
	Ceiling - Lay-in	1st Floor	927	SF	6	\$2,784	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	927	SF	6	\$928	
	Lighting - Lay-in	1st Floor	12	EA	6	\$1,428	
	Marker Board	1st Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	1st Floor	1,125	SF	6	\$3,105	
Classroom #B202 (Science Lab Level 3)							
	Casework	2nd Floor	33	LF	6	\$833	
	Ceiling - Lay-in	2nd Floor	1,059	SF	6	\$3,180	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,059	SF	6	\$1,060	
	Gas Line	2nd Floor	1	EA	6	\$509	
	Lighting - Lay-in	2nd Floor	18	EA	6	\$2,142	
	Marker Board	2nd Floor	26	LF	6	\$557	
	Science Lab Elements	2nd Floor	1,059	SF	6	\$7,178	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Storage/ Closet	2nd Floor	30	SF	6	\$218	
	Walls - Plaster/Drywall	2nd Floor	1,165	SF	6	\$3,215	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroom #B203 (Regular Classroom)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Lay-in	2nd Floor	874	SF	6	\$2,625	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	5	\$1,174	Loose/broken hinges
	Floor - Tile/Sheet	2nd Floor	874	SF	6	\$875	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,063	SF	6	\$2,934	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #B203 (Regular Classroom)							
Classroom #B204 (Science Lab Level 3)							
	Casework	2nd Floor	53	LF	6	\$1,338	
	Ceiling - Lay-in	2nd Floor	1,127	SF	6	\$3,384	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	2nd Floor	1,127	SF	6	\$1,128	
	Gas Line	2nd Floor	1	EA	6	\$509	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	18	LF	6	\$386	
	Science Lab Elements	2nd Floor	1,127	SF	6	\$7,639	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Storage/ Closet	2nd Floor	160	SF	6	\$1,160	
	Walls - Plaster/Drywall	2nd Floor	1,087	SF	6	\$3,000	
	Work Sink	2nd Floor	4	EA	6	\$1,516	
Classroom #B205 (Regular Classroom)							
	Casework	2nd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	2nd Floor	887	SF	6	\$2,664	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	887	SF	6	\$888	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	867	SF	6	\$2,393	
Classroom #B206 (Regular Classroom)							
	Casework	2nd Floor	32	LF	6	\$808	
	Ceiling - Lay-in	2nd Floor	890	SF	6	\$2,673	
	Chalk Board	2nd Floor	12	LF	6	\$268	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	890	SF	6	\$891	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	867	SF	6	\$2,393	
Classroom #B301 (Regular Classroom)							
	Casework	3rd Floor	31	LF	6	\$783	
	Ceiling - Lay-in	3rd Floor	894	SF	6	\$2,685	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #B301 (Regular Classroom)							
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	Water damaged tile
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	902	SF	6	\$903	
	Lighting - Lay-in	3rd Floor	15	EA	6	\$1,785	
	Walls - Plaster/Drywall	3rd Floor	1,066	SF	6	\$2,942	
Classroom #B302 (Regular Classroom)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	3rd Floor	902	SF	6	\$2,709	
	Chalk Board	3rd Floor	14	LF	4	\$1,285	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	902	SF	6	\$903	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,017	SF	6	\$2,807	
Classroom #B303 (Regular Classroom)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	3rd Floor	902	SF	6	\$2,709	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	902	SF	6	\$903	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,017	SF	6	\$2,807	
Classroom #B304 (Regular Classroom)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	3rd Floor	902	SF	6	\$2,709	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	902	SF	6	\$903	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,017	SF	6	\$2,807	
Classroom #B305 (Regular Classroom)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	3rd Floor	902	SF	6	\$2,709	

Building: Addition 1

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #B305 (Regular Classroom)							
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	902	SF	6	\$903	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,017	SF	6	\$2,807	
Classroom #B306 (Regular Classroom)							
	Casework	3rd Floor	28	LF	6	\$707	
	Ceiling - Lay-in	3rd Floor	902	SF	6	\$2,709	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	902	SF	6	\$903	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,017	SF	6	\$2,807	
Classroom #Special Educati (Special Education)							
	Casework		30	LF	6	\$758	
	Doors - Steel Doors incl hw		1	EA	6	\$301	
	Floor - Tile/Sheet		816	SF	6	\$817	
	Lighting - Lay-in		12	EA	7	\$0	
	Marker Board		8	LF	7	\$0	
	Walls - Plaster/Drywall		1,030	SF	6	\$2,843	
Classrooms Subtotal:						\$164,374	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st Fl Health Office Rm B106	437	SF	6	\$1,312	
	Doors - Steel Doors incl hw	1st Fl Health Office Rm B106	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Fl Health Office Rm B106	437	SF	6	\$925	
	Lighting - Lay-in	1st Fl Health Office Rm B106	6	EA	6	\$714	
	Power Distribution	1st Fl Health Office Rm B106	6	EA	7	\$0	
	Walls - Plaster/Drywall	1st Fl Health Office Rm B106	856	SF	6	\$2,362	
	Ceiling - Lay-in	Basement West end	285	SF	6	\$856	
	Doors - Steel Doors incl hw	Basement West end	1	EA	6	\$301	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Floor - Tile Ceramic/ Porcelain	Basement West end	285	SF	6	\$603	
	Lighting - Lay-in	Basement West end	6	EA	6	\$714	
	Walls - Concrete Block	Basement West end	147	SF	6	\$431	
	Walls - Plaster/Drywall	Basement West end	440	SF	6	\$1,214	
	Ceiling - Lay-in	Cafeteria Office	60	SF	6	\$180	
	Doors - Steel Doors incl hw	Cafeteria Office	1	EA	6	\$301	
	Floor - Epoxy/ Painted	Cafeteria Office	60	SF	6	\$32	
	Lighting - Lay-in	Cafeteria Office	1	EA	6	\$119	
	Walls - Plaster/Drywall	Cafeteria Office	120	SF	6	\$331	
Auditorium & Theater							
	Balcony Seating	1st Floor	297	EA	6	\$51,653	
	Ceiling - Lay-in	1st Floor	2,412	SF	6	\$7,243	
	Ceiling - Plaster/Drywall	1st Floor	4,825	SF	6	\$40,226	
	Doors - Steel Doors incl hw	1st Floor	3	EA	6	\$903	
	Floor - Concrete	1st Floor	2,412	SF	6	\$1,276	
	Floor - Tile/Sheet	1st Floor	2,412	SF	6	\$2,414	
	Lighting - Lay-in	1st Floor	44	EA	6	\$5,235	
	Lighting - Wall Mounted	1st Floor	12	EA	6	\$1,487	
	Main Floor Seating	1st Floor	408	EA	6	\$70,958	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	875	SF	6	\$5,055	
	Stage Curtain	1st Floor	2	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor	4	LF	6	\$47	
	Stairs - Terrazzo	1st Floor	20	LF	6	\$153	
	Walls - Plaster/Drywall	1st Floor	5,720	SF	6	\$27,238	
Kitchen							
	Ceiling - Lay-in	B2 Kitchen	1,119	SF	6	\$3,360	
	Doors - Steel Doors incl hw	B2 Kitchen	3	EA	6	\$903	
	Floor - Tile/Sheet	B2 Kitchen	1,119	SF	6	\$1,120	
	Lighting - Lay-in	B2 Kitchen	12	EA	6	\$1,428	
	Serving Line	B2 Kitchen	20	LF	6	\$1,190	
	Walls - Plaster/Drywall	B2 Kitchen	1,135	SF	6	\$3,132	
Lunch & Multipurpose Room							
	Ceiling - Lay-in	B4 Cafeteria Room	2,150	SF	6	\$6,456	
	Doors - Steel Doors incl hw	B4 Cafeteria Room	2	EA	6	\$602	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lunch & Multipurpose Room							
	Floor - Tile/Sheet	B4 Cafeteria Room	2,150	SF	6	\$2,152	
	Lighting - Lay-in	B4 Cafeteria Room	30	EA	6	\$3,569	
	Serving Line	B4 Cafeteria Room	6	LF	6	\$357	
	Storage/ Closet	B4 Cafeteria Room	120	SF	6	\$870	
	Walls - Plaster/Drywall	B4 Cafeteria Room	1,733	SF	6	\$4,783	
MDF_IDF							
	AC Unit	MDF_IDF in Room B104	1	EA	6	\$496	
	Doors - Steel Doors incl hw	MDF_IDF in Room B104	1	EA	6	\$301	
	Finishes	MDF_IDF in Room B104	110	SF	6	\$785	
	Ventilation and Cooling	MDF_IDF in Room B104	1	EA	6	\$1,855	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	80	SF	6	\$573	All janitor closet combined together
	Storage Room	1st Floor	350	SF	6	\$2,508	All storage room combined together
	Janitor's Closet	2nd Floor	11	SF	6	\$79	across from B206
	Boiler Room	Basement	1,250	SF	6	\$8,955	
	Interior Stairs	Basement	4	LF	6	\$36	
	Janitor's Closet	Basement	60	SF	6	\$430	All janitor closet combined together
	Mechanical/ Service Rooms	Basement	1,150	SF	6	\$8,239	
	Storage Room	Basement	110	SF	6	\$788	All storage room combined together
Restroom							
	Accessories	1st Fl Boys	359	SF	6	\$3,311	
	Ceiling - Lay-in	1st Fl Boys	359	SF	6	\$1,078	
	Doors - Steel Doors incl hw	1st Fl Boys	1	EA	6	\$301	
	Floor Drain	1st Fl Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl Boys	359	SF	6	\$760	
	Hand Dryer	1st Fl Boys	1	EA	6	\$230	
	Lavatory	1st Fl Boys	2	EA	6	\$639	
	Lighting - Lay-in	1st Fl Boys	6	EA	7	\$0	
	Partitions	1st Fl Boys	2	EA	6	\$594	
	Urinals	1st Fl Boys	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	1st Fl Boys	326	SF	6	\$900	
	Walls - Tile Ceramic/ Porcelain	1st Fl Boys	526	SF	6	\$1,188	
	Water Closet	1st Fl Boys	2	EA	6	\$672	
	Accessories	1st Fl East Mens Staff	48	SF	6	\$443	
	Ceiling - Lay-in	1st Fl East Mens Staff	48	SF	6	\$144	
	Doors - Steel Doors incl hw	1st Fl East Mens Staff	1	EA	6	\$301	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Floor Drain	1st Fl East Mens Staff	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl East Mens Staff	48	SF	6	\$102	
	Lavatory	1st Fl East Mens Staff	1	EA	6	\$320	
	Lighting - Lay-in	1st Fl East Mens Staff	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st Fl East Mens Staff	158	SF	6	\$436	
	Walls - Tile Ceramic/ Porcelain	1st Fl East Mens Staff	116	SF	6	\$262	
	Water Closet	1st Fl East Mens Staff	1	EA	6	\$336	
	Accessories	1st Fl East Womens Staff	48	SF	6	\$443	
	Ceiling - Lay-in	1st Fl East Womens Staff	48	SF	6	\$144	
	Doors - Steel Doors incl hw	1st Fl East Womens Staff	1	EA	6	\$301	
	Floor Drain	1st Fl East Womens Staff	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl East Womens Staff	48	SF	6	\$102	
	Lavatory	1st Fl East Womens Staff	1	EA	6	\$320	
	Lighting - Lay-in	1st Fl East Womens Staff	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st Fl East Womens Staff	158	SF	6	\$436	
	Walls - Tile Ceramic/ Porcelain	1st Fl East Womens Staff	116	SF	6	\$262	
	Water Closet	1st Fl East Womens Staff	1	EA	6	\$336	
	Accessories	1st Fl Girls	365	SF	6	\$3,367	
	Ceiling - Lay-in	1st Fl Girls	365	SF	6	\$1,096	
	Doors - Steel Doors incl hw	1st Fl Girls	1	EA	6	\$301	
	Floor Drain	1st Fl Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl Girls	365	SF	6	\$772	
	Lavatory	1st Fl Girls	2	EA	6	\$639	
	Lighting - Lay-in	1st Fl Girls	6	EA	6	\$714	
	Partitions	1st Fl Girls	4	EA	6	\$1,188	
	Walls - Tile Ceramic/ Porcelain	1st Fl Girls	526	SF	6	\$1,188	
	Walls - Tile Ceramic/ Porcelain	1st Fl Girls	290	SF	6	\$1,945	
	Water Closet	1st Fl Girls	4	EA	6	\$1,344	
	Accessories	1st Fl Health Office	146	SF	6	\$1,347	
	Ceiling - Lay-in	1st Fl Health Office	146	SF	6	\$438	
	Doors - Steel Doors incl hw	1st Fl Health Office	1	EA	6	\$301	
	Floor Drain	1st Fl Health Office	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl Health Office	146	SF	6	\$309	
	Lavatory	1st Fl Health Office	1	EA	6	\$320	
	Lighting - Lay-in	1st Fl Health Office	2	EA	6	\$238	
	Walls - Plaster/Drywall	1st Fl Health Office	282	SF	6	\$778	
	Walls - Tile Ceramic/ Porcelain	1st Fl Health Office	208	SF	6	\$470	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	1st FI Health Office	1	EA	6	\$336	
	Accessories	1st FI West Mens Staff	33	SF	6	\$304	
	Ceiling - Lay-in	1st FI West Mens Staff	33	SF	6	\$99	
	Doors - Steel Doors incl hw	1st FI West Mens Staff	1	EA	6	\$301	
	Floor Drain	1st FI West Mens Staff	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FI West Mens Staff	33	SF	6	\$70	
	Lavatory	1st FI West Mens Staff	1	EA	6	\$320	
	Lighting - Lay-in	1st FI West Mens Staff	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st FI West Mens Staff	134	SF	6	\$370	
	Walls - Tile Ceramic/ Porcelain	1st FI West Mens Staff	98	SF	6	\$221	
	Water Closet	1st FI West Mens Staff	1	EA	6	\$336	
	Accessories	1st FI West Womens Staff	33	SF	6	\$304	
	Ceiling - Lay-in	1st FI West Womens Staff	33	SF	6	\$99	
	Doors - Steel Doors incl hw	1st FI West Womens Staff	1	EA	6	\$301	
	Floor Drain	1st FI West Womens Staff	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FI West Womens Staff	33	SF	6	\$70	
	Lavatory	1st FI West Womens Staff	1	EA	6	\$320	
	Lighting - Lay-in	1st FI West Womens Staff	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st FI West Womens Staff	134	SF	6	\$370	
	Walls - Tile Ceramic/ Porcelain	1st FI West Womens Staff	98	SF	6	\$221	
	Water Closet	1st FI West Womens Staff	1	EA	6	\$336	
	Accessories	2nd FI Boys Restroom	359	SF	6	\$3,311	
	Doors - Steel Doors incl hw	2nd FI Boys Restroom	1	EA	6	\$301	
	Floor Drain	2nd FI Boys Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd FI Boys Restroom	359	SF	6	\$760	
	Lavatory	2nd FI Boys Restroom	2	EA	6	\$639	
	Lighting - Lay-in	2nd FI Boys Restroom	6	EA	7	\$0	
	Partitions	2nd FI Boys Restroom	6	EA	6	\$1,782	
	Urinals	2nd FI Boys Restroom	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	2nd FI Boys Restroom	326	SF	6	\$900	
	Walls - Tile Ceramic/ Porcelain	2nd FI Boys Restroom	526	SF	6	\$1,188	
	Water Closet	2nd FI Boys Restroom	2	EA	6	\$672	
	Accessories	2nd FI Girls Restroom	365	SF	6	\$3,367	
	Ceiling - Lay-in	2nd FI Girls Restroom	365	SF	6	\$1,096	
	Doors - Steel Doors incl hw	2nd FI Girls Restroom	1	EA	6	\$301	
	Floor Drain	2nd FI Girls Restroom	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	2nd FI Girls Restroom	365	SF	6	\$772	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lavatory	2nd FI Girls Restroom	2	EA	6	\$639	
	Lighting - Lay-in	2nd FI Girls Restroom	6	EA	7	\$0	
	Partitions	2nd FI Girls Restroom	5	EA	6	\$1,485	
	Walls - Tile Ceramic/ Porcelain	2nd FI Girls Restroom	290	SF	6	\$1,945	
	Walls - Tile Ceramic/ Porcelain	2nd FI Girls Restroom	526	SF	6	\$1,188	
	Water Closet	2nd FI Girls Restroom	4	EA	6	\$1,344	
	Accessories	3rd FI Boys Restroom	404	SF	6	\$3,726	
	Ceiling - Lay-in	3rd FI Boys Restroom	404	SF	6	\$1,213	
	Doors - Steel Doors incl hw	3rd FI Boys Restroom	1	EA	6	\$301	
	Floor Drain	3rd FI Boys Restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd FI Boys Restroom	404	SF	6	\$855	
	Lavatory	3rd FI Boys Restroom	2	EA	6	\$639	
	Lighting - Lay-in	3rd FI Boys Restroom	6	EA	7	\$0	
	Partitions	3rd FI Boys Restroom	6	EA	6	\$1,782	
	Urinals	3rd FI Boys Restroom	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	3rd FI Boys Restroom	290	SF	6	\$800	
	Walls - Tile Ceramic/ Porcelain	3rd FI Boys Restroom	580	SF	6	\$1,310	
	Water Closet	3rd FI Boys Restroom	1	EA	6	\$336	
	Water Closet	3rd FI Boys Restroom	1	EA	5	\$1,344	Not working, covered with plastic
	Accessories	Basement Boys	343	SF	6	\$3,164	
	Ceiling - Lay-in	Basement Boys	343	SF	6	\$1,030	
	Doors - Steel Doors incl hw	Basement Boys	1	EA	6	\$301	
	Floor Drain	Basement Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement Boys	343	SF	6	\$726	
	Lavatory	Basement Boys	2	EA	6	\$639	
	Lighting - Lay-in	Basement Boys	6	EA	6	\$714	
	Partitions	Basement Boys	2	EA	6	\$594	
	Urinals	Basement Boys	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	Basement Boys	163	SF	6	\$450	
	Walls - Tile Ceramic/ Porcelain	Basement Boys	488	SF	6	\$1,103	
	Water Closet	Basement Boys	2	EA	6	\$672	
	Accessories	Basement Girls	343	SF	6	\$3,164	
	Ceiling - Lay-in	Basement Girls	343	SF	6	\$1,030	
	Doors - Steel Doors incl hw	Basement Girls	1	EA	6	\$301	
	Floor Drain	Basement Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement Girls	343	SF	6	\$726	
	Lavatory	Basement Girls	2	EA	6	\$639	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Lighting - Lay-in	Basement Girls	6	EA	6	\$714	
	Partitions	Basement Girls	4	EA	6	\$1,188	
	Walls - Plaster/Drywall	Basement Girls	163	SF	6	\$450	
	Walls - Tile Ceramic/ Porcelain	Basement Girls	488	SF	6	\$1,103	
	Water Closet	Basement Girls	4	EA	6	\$1,344	
	Accessories	Basement Mens between Lunch Room & Auditorium	50	SF	6	\$461	
	Ceiling - Lay-in	Basement Mens between Lunch Room & Auditorium	50	SF	6	\$150	
	Doors - Steel Doors incl hw	Basement Mens between Lunch Room & Auditorium	1	EA	6	\$301	
	Floor Drain	Basement Mens between Lunch Room & Auditorium	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement Mens between Lunch Room & Auditorium	50	SF	6	\$106	
	Lavatory	Basement Mens between Lunch Room & Auditorium	1	EA	6	\$320	
	Lighting - Lay-in	Basement Mens between Lunch Room & Auditorium	1	EA	6	\$119	
	Walls - Plaster/Drywall	Basement Mens between Lunch Room & Auditorium	109	SF	6	\$301	
	Walls - Tile Ceramic/ Porcelain	Basement Mens between Lunch Room & Auditorium	109	SF	6	\$246	
	Water Closet	Basement Mens between Lunch Room & Auditorium	1	EA	6	\$336	
	Accessories	Basement Womens between Lunch Room & Auditorium	50	SF	6	\$461	
	Ceiling - Lay-in	Basement Womens between Lunch Room & Auditorium	50	SF	6	\$150	
	Doors - Steel Doors incl hw	Basement Womens between Lunch Room & Auditorium	1	EA	6	\$301	
	Floor Drain	Basement Womens between Lunch Room & Auditorium	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement Womens between Lunch Room & Auditorium	50	SF	6	\$106	
	Lavatory	Basement Womens between Lunch Room & Auditorium	1	EA	6	\$320	
	Lighting - Lay-in	Basement Womens between Lunch Room & Auditorium	1	EA	6	\$119	
	Walls - Plaster/Drywall	Basement Womens between Lunch Room & Auditorium	109	SF	6	\$301	
	Walls - Tile Ceramic/ Porcelain	Basement Womens between Lunch Room & Auditorium	109	SF	6	\$246	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Water Closet	Basement Womens between Lunch Room & Auditorium	1	EA	6	\$336	
	Accessories	Men's staff restroom across from room B206	48	SF	6	\$443	
	Ceiling - Lay-in	Men's staff restroom across from room B206	48	SF	6	\$144	
	Doors - Steel Doors incl hw	Men's staff restroom across from room B206	1	EA	6	\$301	
	Floor Drain	Men's staff restroom across from room B206	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Men's staff restroom across from room B206	48	SF	6	\$102	
	Lavatory	Men's staff restroom across from room B206	1	EA	6	\$320	
	Lighting - Lay-in	Men's staff restroom across from room B206	1	EA	7	\$0	
	Walls - Plaster/Drywall	Men's staff restroom across from room B206	158	SF	6	\$436	
	Walls - Tile Ceramic/ Porcelain	Men's staff restroom across from room B206	116	SF	6	\$262	
	Water Closet	Men's staff restroom across from room B206	1	EA	6	\$336	
	Accessories	Women's staff restroom across from B206	48	SF	6	\$443	
	Ceiling - Lay-in	Women's staff restroom across from B206	48	SF	6	\$144	
	Doors - Steel Doors incl hw	Women's staff restroom across from B206	1	EA	6	\$301	
	Floor Drain	Women's staff restroom across from B206	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Women's staff restroom across from B206	48	SF	6	\$102	
	Lavatory	Women's staff restroom across from B206	1	EA	5	\$1,590	Not working, covered in plastic
	Lighting - Lay-in	Women's staff restroom across from B206	1	EA	7	\$0	
	Walls - Plaster/Drywall	Women's staff restroom across from B206	158	SF	6	\$436	
	Walls - Tile Ceramic/ Porcelain	Women's staff restroom across from B206	116	SF	6	\$262	
	Water Closet	Women's staff restroom across from B206	1	EA	6	\$336	

Building: Addition 1

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Rooms (Other Than Classrooms) Subtotal:						\$418,922	

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Plaster/Drywall	1st Floor	2,150	SF	6	\$13,313	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	1st Floor	1	EA	6	\$336	
	Floor - Tile/Sheet	1st Floor	2,150	SF	6	\$1,168	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	
	Student Lockers - One Tier	1st Floor	110	EA	6	\$10,212	
	Walls - Plaster/Drywall	1st Floor	2,795	SF	6	\$12,390	
	Ceiling - Lay-in	2nd Floor	1,646	SF	6	\$4,943	
	Doors - Steel Doors incl hw	2nd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Terrazzo	2nd Floor	823	SF	6	\$6,908	
	Floor - Tile/Sheet	2nd Floor	823	SF	6	\$447	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	2	EA	7	\$0	
	Student Lockers - One Tier	2nd Floor	106	EA	6	\$9,841	
	Walls - Plaster/Drywall	2nd Floor	3,200	SF	6	\$14,186	
	Walls - Plaster/Drywall	2nd Floor	15	SF	5	\$151	Hole in drywall
	Ceiling - Lay-in	3rd Floor	1,646	SF	6	\$4,943	
	Doors - Steel Doors incl hw	3rd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	3rd Floor	2	EA	6	\$551	
	Floor - Terrazzo	3rd Floor	823	SF	6	\$6,908	
	Floor - Tile/Sheet	3rd Floor	823	SF	6	\$447	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	2	EA	6	\$248	
	Student Lockers - One Tier	3rd Floor	104	EA	6	\$9,655	
	Walls - Plaster/Drywall	3rd Floor	3,215	SF	6	\$14,252	
	Ceiling - Lay-in	Basement	2,150	SF	6	\$6,456	
	Doors - Steel Doors incl hw	Basement	4	EA	6	\$1,204	
	Drinking Fountains - Double Fountain	Basement	1	EA	6	\$336	
	Floor - Tile/Sheet	Basement	2,150	SF	6	\$1,168	
	Lighting - Lay-in	Basement	20	EA	6	\$2,380	

Building: Addition 1

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Stairs - Concrete Stairs	Basement	4	LF	6	\$33	
	Walls - Plaster/Drywall	Basement	2,795	SF	6	\$12,390	
Stairs							
	Ceiling - Plaster/Drywall	Stairwell #1	879	SF	6	\$6,436	
	Floor - Terrazzo	Stairwell #1	685	SF	6	\$5,750	
	Handrails	Stairwell #1	170	LF	6	\$1,473	
	Lighting - Pendent/Surface	Stairwell #1	10	EA	7	\$0	
	Stairs - Asphalt	Stairwell #1	74	LF	6	\$687	
	Walls - Plaster/Drywall	Stairwell #1	3,372	SF	6	\$9,306	
	Ceiling - Lay-in	Stairwell #2	879	SF	6	\$2,640	
	Floor - Terrazzo	Stairwell #2	685	SF	6	\$5,750	
	Handrails	Stairwell #2	170	LF	6	\$1,473	
	Lighting - Pendent/Surface	Stairwell #2	10	EA	7	\$0	
	Stairs - Asphalt	Stairwell #2	74	LF	6	\$687	
	Walls - Plaster/Drywall	Stairwell #2	3,372	SF	6	\$9,306	

Building Interior Subtotal:

\$185,016

Total Building Cost

\$1,921,124

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio and Video	Entrance 6-SW	1	EA	6	\$702	
	Entrance Control - Audio and Video	Entrance 8-West	1	EA	6	\$702	
	Exterior Doors - Exterior FRP Door	Entrance 8-West	2	EA	6	\$1,263	
	Exterior Doors - Exterior Steel Door	Entrance 5-South	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Entrance 6-SW	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	Exit 7-West / Gym	1	EA	6	\$481	
	Exterior Stairs - Concrete	Exit 7-West / Gym	6	LF	6	\$491	
	Exterior Stairs - Stone	Entrance 5-South	6	LF	6	\$678	
Foundation							
	Foundation - Concrete	Entire Building	446	LF	7	\$0	
	Superstructure - Concrete	Entire Building	38,561	SF	7	\$0	

Building: Addition 2

Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Lighting							
	Exterior Lighting - Wall Mounted	Entire Building	9	EA	6	\$2,599	
Roof System							
	Coping - Stone	Roof 4,5	497	LF	6	\$15,963	
	Downspouts - Interior Downspouts	Roof 4,5	173	LF	6	\$5,749	
	Parapet - Parapet < 16" Height	Roof 4,5	497	LF	6	\$10,590	
	Roof Structure - Steel with Clay Tile Arch	Roof 4,5	15,637	SF	7	\$0	
	Roof - Modified Bitumen	Roof 4,5	15,637	SF	6	\$147,135	
Walls							
	Exterior Walls - Brick	Entire Building	20,273	SF	6	\$136,255	
	Exterior Walls - Stone-Cast	Entire Building	1,100	SF	6	\$7,393	
Windows							
	Guard - Guards perforated	Entire Building / 1st Floor	1,810	SF	6	\$23,114	
	Guard - Guards wire guard	Entire Building	621	SF	6	\$7,930	Interior
	Lintels - Steel	Entire Building	667	LF	7	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	5,319	SF	6	\$39,704	
Building Exterior Subtotal:						\$402,668	

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Emergency System							
	Emergency A/C Power - Corridors and Stairs	Entire Building	6,487	SF	6	\$1,948	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	2,400	SF	6	\$892	
	Emergency A/C Power - Students Toilets	Entire Building	1,118	SF	6	\$416	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	33	EA	6	\$6,683	
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	3	EA	6	\$608	
	Emergency Battery Packs - Students Toilets	Entire Building	6	EA	6	\$1,215	
	Exit Signs - Corridors and Stairs	Entire Building	13	EA	7	\$0	
	Exit Signs - Gym	Entire Building / 1st Floor	2	EA	7	\$0	
	Security System - Intrusion Detection	Entire Building	38,561	SF	6	\$9,926	
Main Service							
	PA System	Entire Building	38,561	SF	6	\$12,683	Also Serves Main, Addition 1

Building: Addition 2

Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Power Distribution							
	Lighting and Power Panels - 100 A	Electrical Room	1	EA	6	\$299	Emergency Fuse type
	Lighting and Power Panels - 100 A	Electrical Room	1	EA	7	\$0	Emergency Breaker type
	Lighting and Power Panels - Above 100 A	Electrical Room	9	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Electrical Room	3	EA	7	\$0	
	Main Distribution Panels - 400 - 600 amp	Electrical Room	1	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	Electrical Room	1	EA	7	\$0	

Electrical System Subtotal: \$34,669

Building: Addition 2

Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Fire Alarm							
	Fire Alarm Strobe Lights	Entire Building	38,561	SF	6	\$13,786	
	Fire Alarm_System	Entire Building	38,561	SF	6	\$18,748	
Sprinkler System							
	Sprinkler Heads	Entire Building	38,561	SF	7	\$0	
	Sprinkler Piping	Entire Building	38,561	SF	7	\$0	
	Wet Sprinkler System	Entire Building	38,561	SF	7	\$0	Served From Main

Safty System Subtotal: \$32,534

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Air Handling Systems							
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 4000-8000 cfm	Mechanical Room	1	EA	6	\$3,350	Serves Gym
	Air Intake	Mechanical Room / Façade- SE	1	EA	7	\$0	
	Fan Coil Unit- Floor Mounted - Dual Temperature Coil	Entire Building	31	EA	6	\$55,580	
Heating Devices							
	Cabinet Heaters - With Hot Water Coil	Entire Building	3	EA	6	\$1,063	
	Fin Tube - Hot Water	Entire Building	80	LF	6	\$755	
	Unit Heater - Electric	Mechanical Room	1	EA	6	\$278	
	Unit Heater - Hot Water	Mechanical Room / 1st Floor	2	EA	6	\$558	louvers are broken

Building: Addition 2

Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Mechanical Plumbing							
	Hydronic Supply and Return - Copper	Entire Building	250	LF	6	\$13,117	
	Hydronic Supply and Return - Steel	Entire Building	50	LF	6	\$3,839	
Temperature Control							
	DDC System	Entire Building	38,561	SF	5	\$63,414	Served from Main
	Electric Thermostat	Entire Building	31	EA	6	\$0	Controls Fan Coil units
	Thermostats - DDC	Entire Building	1	EA	6	\$0	Serves Gym
Ventilation							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	2	EA	4	\$12,784	Serves Gym
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	3	EA	6	\$1,777	
Mechanical System Subtotal:						\$156,514	

Building: Addition 2

Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Piping							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	38,561	SF	6	\$7,720	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	38,561	SF	6	\$9,374	
	Domestic Piping-Cold Water Risers	Entire Building	38,561	SF	6	\$7,168	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	38,561	SF	6	\$6,066	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	38,561	SF	6	\$7,168	
	Domestic Piping-Hot Water Return Lines	Entire Building	38,561	SF	6	\$5,514	
	Domestic Piping-Hot Water Return Risers	Entire Building	38,561	SF	6	\$5,514	
	Sanitary Piping	Entire Building	38,561	SF	6	\$35,291	
	Storm Piping	Entire Building	38,561	SF	6	\$33,637	
	Vent Piping	Entire Building	38,561	SF	6	\$25,917	
Pumps							
	Pumps - Sump-Simplex	Mechanical Room	1	EA	6	\$745	
Plumbing System Subtotal:						\$144,115	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #C-10 (Regular Classroom)							
	Casework	1st Floor	16	LF	6	\$404	
	Ceiling - Lay-in	1st Floor	700	SF	6	\$2,102	
	Chalk Board	1st Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	700	SF	6	\$701	
	Lighting - Lay-in	1st Floor	15	EA	6	\$1,785	
	Marker Board	1st Floor	12	LF	6	\$257	
	Walls - Plaster/Drywall	1st Floor	921	SF	6	\$2,542	
Classroom #C104 (Regular Classroom)							
	Casework	2nd Floor	35	LF	6	\$884	
	Ceiling - Lay-in	2nd Floor	695	SF	6	\$2,087	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	695	SF	6	\$696	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	942	SF	6	\$2,600	
	Work Sink	2nd Floor	2	EA	6	\$758	
Classroom #C105 (Regular Classroom)							
	Casework	2nd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	2nd Floor	1,068	SF	6	\$3,207	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,068	SF	6	\$1,069	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,224	SF	6	\$3,378	
Classroom #C106 (Regular Classroom)							
	Casework	2nd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	2nd Floor	1,105	SF	6	\$3,318	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,105	SF	6	\$1,106	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,226	SF	6	\$3,384	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #C106 (Regular Classroom)							
Classroom #C109 (Regular Classroom)							
	Casework	2nd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	2nd Floor	1,068	SF	6	\$3,207	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	1,068	SF	6	\$1,069	
	Lighting - Lay-in	2nd Floor	18	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	1,224	SF	6	\$3,378	
Classroom #C110 (Regular Classroom)							
	Casework	2nd Floor	29	LF	6	\$732	
	Ceiling - Lay-in	2nd Floor	738	SF	6	\$2,216	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	738	SF	6	\$739	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	995	SF	6	\$2,746	
Classroom #C202 (Regular Classroom)							
	Casework	3rd Floor	38	LF	6	\$960	
	Ceiling - Lay-in	3rd Floor	694	SF	6	\$2,084	
	Ceiling - Lay-in	3rd Floor	8	SF	5	\$64	Water damage
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	702	SF	6	\$703	
	Lighting - Lay-in	3rd Floor	12	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	973	SF	6	\$2,685	
Classroom #c-203 (Regular Classroom)							
	Casework	3rd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	3rd Floor	1,069	SF	6	\$3,210	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	1,069	SF	6	\$1,070	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #c-203 (Regular Classroom)							
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,087	SF	6	\$3,000	
	Work Sink	3rd Floor	1	EA	6	\$379	
Classroom #c-204 (Regular Classroom)							
	Casework	3rd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	3rd Floor	1,076	SF	6	\$3,231	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Carpet	3rd Floor	1,076	SF	6	\$2,293	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,237	SF	6	\$3,414	
Classroom #c-206 (Regular Classroom)							
	Casework	3rd Floor	42	LF	6	\$1,061	
	Ceiling - Lay-in	3rd Floor	981	SF	6	\$2,946	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Carpet	3rd Floor	981	SF	6	\$2,090	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Storage/ Closet	3rd Floor	8	SF	6	\$58	
	Walls - Plaster/Drywall	3rd Floor	1,160	SF	6	\$3,201	
Classroom #C-207 (Regular Classroom)							
	Casework	3rd Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	3rd Floor	1,069	SF	6	\$3,210	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	1,069	SF	6	\$1,070	
	Lighting - Lay-in	3rd Floor	18	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,087	SF	6	\$3,000	
Classroom #c-208 (Special Education)							
	Casework	3rd Floor	38	LF	6	\$960	
	Ceiling - Lay-in	3rd Floor	719	SF	6	\$2,159	
	Chalk Board	3rd Floor	12	LF	4	\$1,102	

Building: Addition 2

Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Classroom #c-208 (Special Education)							
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	3rd Floor	719	SF	6	\$720	
	Lighting - Lay-in	3rd Floor	15	EA	7	\$0	
	Marker Board	3rd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,087	SF	6	\$3,000	
Classroom #C-5 (Pre School)							
	Casework	1st Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	1st Floor	1,070	SF	6	\$3,213	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,070	SF	6	\$1,071	
	Lighting - Lay-in	1st Floor	18	EA	6	\$2,142	
	Marker Board	1st Floor	20	LF	6	\$428	
	Walls - Plaster/Drywall	1st Floor	1,114	SF	6	\$3,075	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #C-7 (Kindergarten)							
	Casework	1st Floor	49	LF	6	\$1,237	
	Ceiling - Lay-in	1st Floor	1,070	SF	6	\$3,213	
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Steel Doors incl hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	1,070	SF	6	\$1,071	
	Lighting - Lay-in	1st Floor	18	EA	6	\$2,142	
	Walls - Plaster/Drywall	1st Floor	1,114	SF	6	\$3,075	
	Work Sink	1st Floor	2	EA	6	\$758	
Classroom #C-8 & C-9 (Regular Classroom)							
	Casework	1st Floor	64	LF	6	\$1,616	
	Ceiling - Lay-in	1st Floor	1,070	SF	6	\$3,213	
	Chalk Board	1st Floor	14	LF	4	\$1,285	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Tile/Sheet	1st Floor	1,428	SF	6	\$1,429	
	Lighting - Lay-in	1st Floor	24	EA	6	\$2,855	
	Marker Board	1st Floor	8	LF	6	\$171	
	Walls - Plaster/Drywall	1st Floor	1,443	SF	6	\$3,983	

Classrooms Subtotal:

\$158,039

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Ceiling - Lay-in	1st Fl Rm 105	365	SF	6	\$1,096	
	Doors - Wood Doors inclu hw	1st Fl Rm 105	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Fl Rm 105	365	SF	6	\$365	
	Lighting - Lay-in	1st Fl Rm 105	6	EA	6	\$714	
	Walls - Plaster/Drywall	1st Fl Rm 105	784	SF	6	\$2,164	
	Ceiling - Lay-in	1st Flr Nurse Office	350	SF	6	\$1,051	
	Doors - Steel Doors incl hw	1st Flr Nurse Office	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Flr Nurse Office	350	SF	6	\$350	
	Lighting - Lay-in	1st Flr Nurse Office	2	EA	6	\$238	
	Power Distribution	1st Flr Nurse Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	1st Flr Nurse Office	642	SF	6	\$1,772	
	Ceiling - Lay-in	A Director Office in room C3	350	SF	6	\$1,051	
	Doors - Steel Doors incl hw	A Director Office in room C3	1	EA	6	\$301	
	Floor - Tile/Sheet	A Director Office in room C3	350	SF	6	\$350	
	Lighting - Lay-in	A Director Office in room C3	2	EA	6	\$238	
	Power Distribution	A Director Office in room C3	6	EA	7	\$0	
	Walls - Plaster/Drywall	A Director Office in room C3	642	SF	6	\$1,772	
	Ceiling - Lay-in	B Director Office in room C3	350	SF	6	\$1,051	
	Doors - Steel Doors incl hw	B Director Office in room C3	1	EA	6	\$301	
	Floor - Tile/Sheet	B Director Office in room C3	350	SF	6	\$350	
	Lighting - Lay-in	B Director Office in room C3	2	EA	6	\$238	
	Power Distribution	B Director Office in room C3	6	EA	7	\$0	
	Walls - Plaster/Drywall	B Director Office in room C3	642	SF	6	\$1,772	
	Ceiling - Lay-in	C107 office	8	SF	5	\$64	Water damage
	Ceiling - Lay-in	C107 office	322	SF	6	\$967	
	Doors - Steel Doors incl hw	C107 office	1	EA	6	\$301	
	Floor - Tile/Sheet	C107 office	330	SF	6	\$330	
	Lighting - Lay-in	C107 office	6	EA	7	\$0	
	Power Distribution	C107 office	12	EA	7	\$0	
	Walls - Plaster/Drywall	C107 office	750	SF	6	\$2,070	
	Ceiling - Lay-in	C108 office	483	SF	6	\$1,450	
	Doors - Steel Doors incl hw	C108 office	1	EA	6	\$301	
	Floor - Tile/Sheet	C108 office	483	SF	6	\$483	
	Lighting - Lay-in	C108 office	10	EA	6	\$1,190	
	Power Distribution	C108 office	12	EA	7	\$0	
	Walls - Plaster/Drywall	C108 office	898	SF	6	\$2,478	
	Ceiling - Lay-in	C205 office	365	SF	6	\$1,096	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Administrative Suites/Offices							
	Doors - Steel Doors incl hw	C205 office	1	EA	6	\$301	
	Floor - Tile/Sheet	C205 office	365	SF	6	\$365	
	Lighting - Lay-in	C205 office	6	EA	7	\$0	
	Power Distribution	C205 office	12	EA	7	\$0	
	Walls - Plaster/Drywall	C205 office	784	SF	6	\$2,164	
	Ceiling - Lay-in	C3 Main Office	705	SF	6	\$2,117	
	Doors - Steel Doors incl hw	C3 Main Office	1	EA	6	\$301	
	Floor - Tile/Sheet	C3 Main Office	705	SF	6	\$706	
	Lighting - Lay-in	C3 Main Office	9	EA	6	\$1,071	
	Power Distribution	C3 Main Office	16	EA	7	\$0	
	Walls - Plaster/Drywall	C3 Main Office	864	SF	6	\$2,385	
	Ceiling - Lay-in	C6 Teacher Lounge	450	SF	6	\$1,351	
	Doors - Steel Doors incl hw	C6 Teacher Lounge	1	EA	6	\$301	
	Floor - Tile/Sheet	C6 Teacher Lounge	450	SF	6	\$450	
	Lighting - Lay-in	C6 Teacher Lounge	6	EA	6	\$714	
	Power Distribution	C6 Teacher Lounge	10	EA	7	\$0	
	Walls - Masonry	C6 Teacher Lounge	213	SF	6	\$670	
	Walls - Plaster/Drywall	C6 Teacher Lounge	642	SF	6	\$1,772	
	Ceiling - Lay-in	Student support across from C105 2nd flr	174	SF	6	\$523	
	Ceiling - Lay-in	Student support across from C105 2nd flr	32	SF	5	\$222	Water damaged tiles
	Doors - Steel Doors incl hw	Student support across from C105 2nd flr	1	EA	6	\$301	
	Floor - Tile/Sheet	Student support across from C105 2nd flr	206	SF	6	\$206	
	Lighting - Lay-in	Student support across from C105 2nd flr	2	EA	7	\$0	
	Power Distribution	Student support across from C105 2nd flr	8	EA	7	\$0	
	Storage/ Closet	Student support across from C105 2nd flr	48	SF	6	\$348	
	Walls - Plaster/Drywall	Student support across from C105 2nd flr	671	SF	6	\$1,852	
Gymnasia							
	Ceiling - Exposed	1st Floor	2,400	SF	6	\$3,569	
	Doors - Steel Doors incl hw	1st Floor	4	EA	6	\$1,204	
	Floor - Epoxy/ Painted	1st Floor	2,400	SF	6	\$1,270	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Gymnasia							
	Sound System	1st Floor	1	EA	6	\$41,654	
	Walls - Concrete Block	1st Floor	2,780	SF	6	\$8,150	
	Walls - Structural Glazed Tile	1st Floor	1,853	SF	6	\$5,830	
Mechanical/ Service Rooms							
	Janitor's Closet	1st Floor	30	SF	6	\$215	
	Mechanical/ Service Rooms	1st Floor	354	SF	6	\$2,536	
	Storage Room	1st Floor	250	SF	6	\$1,791	
	Janitor's Closet	2nd Floor	86	SF	6	\$616	
	Mechanical/ Service Rooms	2nd Floor	44	SF	6	\$315	C103 electrical closet
	Storage Room	2nd Floor	252	SF	6	\$1,805	Across from C107
	Janitor's Closet	3rd Floor	83	SF	6	\$595	
	Mechanical/ Service Rooms	3rd Floor	128	SF	6	\$917	C201 electrical closet/janitors office
Restroom							
	Accessories	1st Fl inside Room C5	26	SF	6	\$240	
	Ceiling - Lay-in	1st Fl inside Room C5	26	SF	6	\$78	
	Doors - Steel Doors incl hw	1st Fl inside Room C5	1	EA	6	\$301	
	Floor Drain	1st Fl inside Room C5	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl inside Room C5	26	SF	6	\$55	
	Lighting - Lay-in	1st Fl inside Room C5	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st Fl inside Room C5	102	SF	6	\$282	
	Walls - Tile Ceramic/ Porcelain	1st Fl inside Room C5	102	SF	6	\$230	
	Water Closet	1st Fl inside Room C5	1	EA	6	\$336	
	Accessories	1st Fl inside Room C7	26	SF	6	\$240	
	Ceiling - Lay-in	1st Fl inside Room C7	26	SF	6	\$78	
	Doors - Steel Doors incl hw	1st Fl inside Room C7	1	EA	6	\$301	
	Floor Drain	1st Fl inside Room C7	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Fl inside Room C7	26	SF	6	\$55	
	Lighting - Lay-in	1st Fl inside Room C7	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st Fl inside Room C7	102	SF	6	\$282	
	Walls - Tile Ceramic/ Porcelain	1st Fl inside Room C7	102	SF	6	\$230	
	Water Closet	1st Fl inside Room C7	1	EA	6	\$336	
	Accessories	1st FLR Boys Toilet	223	SF	6	\$2,057	
	Ceiling - Lay-in	1st FLR Boys Toilet	223	SF	6	\$670	
	Doors - Steel Doors incl hw	1st FLR Boys Toilet	1	EA	6	\$301	
	Floor Drain	1st FLR Boys Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FLR Boys Toilet	223	SF	6	\$472	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Hand Dryer	1st FLR Boys Toilet	1	EA	6	\$230	
	Lavatory	1st FLR Boys Toilet	2	EA	6	\$639	
	Lighting - Lay-in	1st FLR Boys Toilet	5	EA	7	\$0	
	Partitions	1st FLR Boys Toilet	4	EA	6	\$1,188	
	Urinals	1st FLR Boys Toilet	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	1st FLR Boys Toilet	210	SF	6	\$580	
	Walls - Tile Ceramic/ Porcelain	1st FLR Boys Toilet	426	SF	6	\$963	
	Water Closet	1st FLR Boys Toilet	1	EA	6	\$336	
	Accessories	1st FLR Girls Toilet	224	SF	6	\$2,066	
	Ceiling - Lay-in	1st FLR Girls Toilet	224	SF	6	\$673	
	Doors - Steel Doors incl hw	1st FLR Girls Toilet	1	EA	6	\$301	
	Floor Drain	1st FLR Girls Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st FLR Girls Toilet	224	SF	6	\$474	
	Hand Dryer	1st FLR Girls Toilet	1	EA	6	\$230	
	Lavatory	1st FLR Girls Toilet	2	EA	6	\$639	
	Lighting - Lay-in	1st FLR Girls Toilet	5	EA	7	\$0	
	Partitions	1st FLR Girls Toilet	3	EA	6	\$891	
	Walls - Plaster/Drywall	1st FLR Girls Toilet	260	SF	6	\$718	
	Walls - Tile Ceramic/ Porcelain	1st FLR Girls Toilet	416	SF	6	\$940	
	Water Closet	1st FLR Girls Toilet	3	EA	6	\$1,008	
	Accessories	1st Flr Nurse Toilet	38	SF	6	\$350	
	Ceiling - Lay-in	1st Flr Nurse Toilet	38	SF	6	\$114	
	Doors - Steel Doors incl hw	1st Flr Nurse Toilet	1	EA	6	\$301	
	Floor Drain	1st Flr Nurse Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Flr Nurse Toilet	38	SF	6	\$80	
	Lavatory	1st Flr Nurse Toilet	1	EA	6	\$320	
	Lighting - Lay-in	1st Flr Nurse Toilet	1	EA	6	\$119	
	Walls - Plaster/Drywall	1st Flr Nurse Toilet	116	SF	6	\$320	
	Walls - Tile Ceramic/ Porcelain	1st Flr Nurse Toilet	106	SF	6	\$239	
	Water Closet	1st Flr Nurse Toilet	1	EA	6	\$336	
	Accessories	1st Flr Staff Toilet	38	SF	6	\$350	
	Ceiling - Lay-in	1st Flr Staff Toilet	38	SF	6	\$114	
	Doors - Steel Doors incl hw	1st Flr Staff Toilet	1	EA	6	\$301	
	Floor Drain	1st Flr Staff Toilet	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Flr Staff Toilet	38	SF	6	\$80	
	Lavatory	1st Flr Staff Toilet	1	EA	6	\$320	
	Lighting - Lay-in	1st Flr Staff Toilet	1	EA	6	\$119	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	1st Flr Staff Toilet	116	SF	6	\$320	
	Walls - Tile Ceramic/ Porcelain	1st Flr Staff Toilet	106	SF	6	\$239	
	Water Closet	1st Flr Staff Toilet	1	EA	6	\$336	
	Accessories	2nd Floor - Boys	224	SF	6	\$2,066	
	Ceiling - Lay-in	2nd Floor - Boys	224	SF	6	\$673	
	Doors - Steel Doors incl hw	2nd Floor - Boys	1	EA	6	\$301	
	Floor Drain	2nd Floor - Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor - Boys	224	SF	6	\$474	
	Hand Dryer	2nd Floor - Boys	1	EA	6	\$230	
	Lavatory	2nd Floor - Boys	2	EA	6	\$639	
	Lighting - Lay-in	2nd Floor - Boys	5	EA	7	\$0	
	Partitions	2nd Floor - Boys	4	EA	6	\$1,188	
	Urinals	2nd Floor - Boys	3	EA	6	\$1,008	
	Walls - Plaster/Drywall	2nd Floor - Boys	260	SF	6	\$718	
	Water Closet	2nd Floor - Boys	1	EA	6	\$336	
	Accessories	2nd floor girls restroom	224	SF	6	\$2,066	
	Ceiling - Lay-in	2nd floor girls restroom	224	SF	6	\$673	
	Doors - Steel Doors incl hw	2nd floor girls restroom	1	EA	6	\$301	
	Floor Drain	2nd floor girls restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd floor girls restroom	224	SF	6	\$474	
	Hand Dryer	2nd floor girls restroom	1	EA	6	\$230	
	Lavatory	2nd floor girls restroom	2	EA	6	\$639	
	Lighting - Lay-in	2nd floor girls restroom	5	EA	7	\$0	
	Partitions	2nd floor girls restroom	3	EA	6	\$891	
	Walls - Plaster/Drywall	2nd floor girls restroom	260	SF	6	\$718	
	Walls - Tile Ceramic/ Porcelain	2nd floor girls restroom	416	SF	6	\$940	
	Water Closet	2nd floor girls restroom	3	EA	6	\$1,008	
	Accessories	3rd floor girls restroom	224	SF	6	\$2,066	
	Ceiling - Lay-in	3rd floor girls restroom	16	SF	5	\$128	Water damage
	Ceiling - Lay-in	3rd floor girls restroom	224	SF	6	\$673	
	Doors - Steel Doors incl hw	3rd floor girls restroom	1	EA	6	\$301	
	Floor Drain	3rd floor girls restroom	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	3rd floor girls restroom	208	SF	6	\$440	
	Hand Dryer	3rd floor girls restroom	1	EA	6	\$230	
	Lavatory	3rd floor girls restroom	2	EA	6	\$639	
	Lighting - Lay-in	3rd floor girls restroom	5	EA	7	\$0	
	Partitions	3rd floor girls restroom	3	EA	6	\$891	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Walls - Plaster/Drywall	3rd floor girls restroom	260	SF	6	\$718	
	Walls - Tile Ceramic/ Porcelain	3rd floor girls restroom	416	SF	6	\$940	
	Water Closet	3rd floor girls restroom	3	EA	6	\$1,008	
	Accessories	Basement - Boys	224	SF	6	\$2,066	
	Ceiling - Lay-in	Basement - Boys	224	SF	6	\$673	
	Doors - Steel Doors incl hw	Basement - Boys	1	EA	6	\$301	
	Floor Drain	Basement - Boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement - Boys	224	SF	6	\$474	
	Lavatory	Basement - Boys	2	EA	6	\$639	
	Lighting - Lay-in	Basement - Boys	5	EA	7	\$0	
	Partitions	Basement - Boys	4	EA	6	\$1,188	
	Urinals	Basement - Boys	3	EA	6	\$1,008	
	Walls	Basement - Boys	260		6	\$0	
	Water Closet	Basement - Boys	1	EA	6	\$336	
	Accessories	Basement - Girls	224	SF	6	\$2,066	
	Ceiling - Lay-in	Basement - Girls	224	SF	6	\$673	
	Doors - Steel Doors incl hw	Basement - Girls	1	EA	6	\$301	
	Floor Drain	Basement - Girls	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Basement - Girls	224	SF	6	\$474	
	Hand Dryer	Basement - Girls	1	EA	6	\$230	
	Lavatory	Basement - Girls	2	EA	6	\$639	
	Lighting - Lay-in	Basement - Girls	5	EA	7	\$0	
	Partitions	Basement - Girls	3	EA	6	\$891	
	Walls	Basement - Girls	260		6	\$0	
	Water Closet	Basement - Girls	3	EA	6	\$1,008	
	Accessories	Staff restroom unisex 2nd floor	38	SF	6	\$350	
	Ceiling - Lay-in	Staff restroom unisex 2nd floor	38	SF	6	\$114	
	Doors - Steel Doors incl hw	Staff restroom unisex 2nd floor	1	EA	6	\$301	
	Floor Drain	Staff restroom unisex 2nd floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Staff restroom unisex 2nd floor	38	SF	6	\$80	
	Lavatory	Staff restroom unisex 2nd floor	1	EA	6	\$320	
	Lighting - Lay-in	Staff restroom unisex 2nd floor	1	EA	7	\$0	
	Walls - Plaster/Drywall	Staff restroom unisex 2nd floor	116	SF	6	\$320	
	Walls - Tile Ceramic/ Porcelain	Staff restroom unisex 2nd floor	106	SF	6	\$239	
	Water Closet	Staff restroom unisex 2nd floor	1	EA	6	\$336	
	Accessories	Staff restroom unisex 3rd floor	38	SF	6	\$350	
	Ceiling - Lay-in	Staff restroom unisex 3rd floor	38	SF	6	\$114	

Building: Addition 2

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Restroom							
	Doors - Steel Doors incl hw	Staff restroom unisex 3rd floor	1	EA	6	\$301	
	Floor Drain	Staff restroom unisex 3rd floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Staff restroom unisex 3rd floor	38	SF	6	\$80	
	Lavatory	Staff restroom unisex 3rd floor	1	EA	6	\$320	
	Lighting - Lay-in	Staff restroom unisex 3rd floor	1	EA	7	\$0	
	Walls - Plaster/Drywall	Staff restroom unisex 3rd floor	116	SF	6	\$320	
	Walls - Tile Ceramic/ Porcelain	Staff restroom unisex 3rd floor	106	SF	6	\$239	
	Water Closet	Staff restroom unisex 3rd floor	1	EA	6	\$336	

Rooms (Other Than Classrooms) Subtotal: \$196,058

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Ceiling - Lay-in	1st Floor	2,100	SF	6	\$6,306	
	Doors - Steel Doors incl hw	1st Floor	6	EA	6	\$1,806	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	1st Floor	2,100	SF	6	\$1,141	
	Lighting - Lay-in	1st Floor	13	EA	6	\$1,547	
	Student Lockers - One Tier	1st Floor	90	EA	6	\$8,355	
	Walls - Plaster/Drywall	1st Floor	3,990	SF	6	\$17,688	
	Ceiling - Lay-in	2nd Floor	1,944	SF	6	\$5,838	
	Ceiling - Plaster/Drywall	2nd Floor	193	SF	6	\$1,195	
	Doors - Steel Doors incl hw	2nd Floor	3	EA	6	\$903	
	Drinking Fountains - Single Fountain	2nd Floor	2	EA	6	\$551	
	Floor - Tile/Sheet	2nd Floor	2,137	SF	6	\$1,161	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Lighting - Pendent/Surface	2nd Floor	3	EA	6	\$372	
	Student Lockers - One Tier	2nd Floor	127	EA	6	\$11,790	
	Walls - Plaster/Drywall	2nd Floor	4,190	SF	6	\$18,574	
	Ceiling - Lay-in	3rd Floor	1,944	SF	6	\$5,838	
	Ceiling - Plaster/Drywall	3rd Floor	193	SF	6	\$1,195	
	Doors - Steel Doors incl hw	3rd Floor	6	EA	6	\$1,806	
	Drinking Fountains - Double Fountain	3rd Floor	2	EA	6	\$672	
	Floor - Tile/Sheet	3rd Floor	2,137	SF	6	\$1,161	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	

Building: Addition 2

Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Corridor							
	Lighting - Pendant/Surface	3rd Floor	3	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	139	EA	6	\$12,904	
	Walls - Plaster/Drywall	3rd Floor	4,190	SF	6	\$18,574	
Stairs							
	Ceiling - Plaster/Drywall	Stairwell #1	304	SF	6	\$2,226	
	Floor - Terrazzo	Stairwell #1	258	SF	6	\$2,166	
	Handrails	Stairwell #1	120	LF	6	\$1,040	
	Lighting - Pendant/Surface	Stairwell #1	3	EA	7	\$0	
	Stairs - Asphalt	Stairwell #1	42	LF	6	\$390	
	Walls - Plaster/Drywall	Stairwell #1	1,743	SF	6	\$4,811	
	Ceiling - Plaster/Drywall	Stairwell #2	304	SF	6	\$2,226	
	Floor - Terrazzo	Stairwell #2	258	SF	6	\$2,166	
	Handrails	Stairwell #2	120	LF	6	\$1,040	
	Lighting - Pendant/Surface	Stairwell #2	3	EA	7	\$0	
	Stairs - Asphalt	Stairwell #2	120	LF	6	\$1,114	
	Walls - Plaster/Drywall	Stairwell #2	1,743	SF	6	\$4,811	
	Ceiling - Plaster/Drywall	Stairwell #3	212	SF	6	\$1,552	
	Floor - Terrazzo	Stairwell #3	91	SF	6	\$764	
	Handrails	Stairwell #3	100	LF	6	\$867	
	Lighting - Pendant/Surface	Stairwell #3	1	EA	6	\$124	
	Stairs - Asphalt	Stairwell #3	42	LF	6	\$390	
	Walls - Plaster/Drywall	Stairwell #3	1,261	SF	6	\$3,480	
Vertical Conveyance							
	Elevator - Hydraulic Elevator	1st Floor	1	EA	6	\$19,238	

Building Interior Subtotal:

\$168,331

Total Building Cost

\$1,292,928

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Catch Basin	Entire Site	6	EA	6	\$6,563	
	Civil/ Drainage - Site Drain	Entire Site	1	EA	6	\$310	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Civil/Drainage							
	Civil/ Drainage - Site Manhole	Entire Site	17	EA	6	\$25,377	
Fencing							
	Fencing - Chain Link	Entire Site	796	LF	6	\$14,946	
	Fencing - Chain Link	Entire Site	100	LF	5	\$6,099	South parking lot - Damaged, bent, leaning, falling down due to not supported properly
	Fencing - New Standard Ornamental	Entire Site	50	LF	6	\$1,595	
	Fencing - Old Standard Ornamental	Entire Site	425	LF	6	\$22,001	
	Fencing - Old Standard Ornamental	Entire Site	20	LF	5	\$3,340	Sections bent, gate to playground not working properly
Landscape							
	Benches	Entire Site	2	EA	6	\$860	
	Landscape - Grass	Entire Site	17,770	SF	6	\$14,738	
	Landscape - Hardscape- Concrete	Entire Site	17,099	SF	6	\$88,270	Stamped concrete
	Parkway trees	Entire Site	18	EA	6	\$11,881	
	Planting Beds/ Area	Entire Site	3,020	SF	6	\$4,966	
	Play Area - Asphalt/ Hardscape	Entire Site	3,460	SF	6	\$8,362	
	Play Area - Synthetic Turf Play Field	Entire Site	2,190	SF	7	\$0	
	Retaining Wall - Masonry	Entire Site	408	SF	6	\$5,957	
	Trash Receptacles	Entire Site	1	EA	6	\$312	
Parking Lot							
	Concrete Curbs	South	553	LF	6	\$7,101	
	Interior Plantings	South	40	LF	6	\$1,702	
	Lighting - Pole Mounted	South	2	EA	6	\$2,905	
	Surface - Asphalt	NE	1,149	SF	6	\$2,777	
	Surface - Asphalt	South	23,280	SF	6	\$56,261	Main south lot
	Surface - Asphalt	South	1,000	SF	5	\$5,906	Several areas around catch basin covers cracked, sinking
	Surface - Concrete	South	2,008	SF	6	\$4,853	Main south lot - Chiller pad
	Trash Compactor	South	1	EA	6	\$0	
	Vehicular Screening	South	426	LF	6	\$33,541	
Playground							
	Equipment - Combo 3-12	South	1	EA	6	\$7,092	
	Surface - Poured Surface	South	2,571	SF	6	\$18,824	
Sidewalks							
	Sidewalks - Internal Walks	Entire Site	288	LF	6	\$3,459	

SITE

Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Sidewalks							
	Sidewalks - Perimeter Sidewalks	Entire Site	10,345	SF	6	\$20,563	
Signage							
	Flag Pole - Flag Pole	Northwest / North West	1	EA	7	\$0	
	Marquee - Free Standing Back Lighted	Northwest / North West	1	EA	6	\$0	

Site Subtotal: **\$380,560**

Total Site Cost **\$380,560**

Campus Total ^{2 3} **\$5,084,147**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Music Room	Basement	A9	N/A	883	1	2	8	0	0	40	N	Y	N
Kindergarten	Regular Classroom	1st Floor	A101	127	875	1	8	18	178	85	40	Y	Y	Y
Music Room	Regular Classroom	Basement	A4	23	824	2	4	10	80	40	40	Y	Y	N
Pre School	Regular Classroom	1st Floor	A102	125	846	0	3	14	178	85	40	Y	Y	N
Pre School	Regular Classroom	1st Floor	A103	123	903	0	5	14	178	85	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	A104	122	840	1	5	16	119	57	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	A105	121	986	1	9	22	149	71	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	A107	118	883	1	11	22	116	58	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	A108	120	1,017	0	11	26	178	85	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A201	A201	866	2	10	20	150	75	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A202	A202	947	2	10	20	150	75	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A203	A203	875	2	10	20	195	98	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A204	A204	866	2	10	20	130	65	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A205	A205	851	1	9	20	130	65	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A207	A207	853	2	10	20	130	65	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	A208	A208	853	2	10	20	150	75	40	Y	Y	Y
Special Education	Play Room	Basement	A2	N/A	120	0	2	8	0	0	40	N	Y	N
Special Program	Play Room	Basement	A1	N/A	350	0	4	110	60	8	40	N	Y	N
Addition 1														
Other Instructional Use	Computer Lab	1st Floor	B103	N/A	927	0	3	18	116	58	40	Y	Y	Y
Other Instructional Use	Computer Lab	1st Floor	B104	N/A	927	0	3	18	116	58	40	Y	Y	Y
Regular Classroom	Multi Purpose Room	1st Floor	B105	N/A	927	1	3	18	116	58	40	Y	Y	N
Regular Classroom	Regular Classroom	2nd Floor	B203	B203	874	1	9	28	132	67	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	B205	B205	887	1	9	28	132	67	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	B206	B206	890	3	6	28	132	67	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	B301	B301	902	2	8	16	144	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	B302	B302	902	2	8	16	144	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	B303	B303	902	2	8	16	144	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	B304	B304	902	2	8	16	144	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	B305	B305	902	2	8	16	144	72	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	B306	B306	902	2	8	16	144	72	40	Y	Y	Y
Science Lab Level 3	Regular Classroom	2nd Floor	B202	B202	1,059	1	9	26	154	78	40	Y	Y	Y
Science Lab Level 3	Science Lab Level 3	2nd Floor	B204	B204	1,127	1	9	26	176	89	40	Y	Y	Y
Special Education	Regular Classroom	1st Floor	B102	N/A	919	1	6	22	142	71	40	Y	Y	Y
Special Education	Regular Classroom		Special Educati	N/A	816	0	2	14	142	71	40	Y	Y	Y

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Addition 2														
Kindergarten	Kindergarten	1st Floor	C-7	105	1,070	1	7	28	180	90	40	Y	Y	Y
Pre School	Pre School	1st Floor	C-5	107	1,070	1	7	28	180	90	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	C-10	N/A	700	1	6	16	100	50	40	Y	Y	Y
Regular Classroom	Art Room	2nd Floor	C104	C104	695	1	9	20	116	58	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	C105	C105	1,068	1	8	24	173	88	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	C106	C106	1,105	1	7	28	173	88	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	C109	C109	1,068	1	10	32	173	88	40	Y	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	C110	C110	738	4	5	14	93	39	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	C202	C202	702	2	10	22	107	55	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	c-203	C203	1,069	1	9	36	161	82	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	c-204	C204	1,076	1	9	36	161	82	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	c-206	C206	981	1	8	34	161	82	40	Y	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	C-207	C207	1,069	1	9	36	161	82	40	Y	Y	Y
Regular Classroom	Regular Classroom	1st Floor	C-8 & C-9	101 & 103	1,428	1	12	36	240	120	40	Y	Y	Y
Special Education	Regular Classroom	3rd Floor	c-208	C208	719	2	6	20	107	55	40	Y	Y	N