

**Facility Assessment Report**

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1902	3	62,100	\$3,649,822
Gymnasium/auditorium	1913	2	7,750	\$533,876
SITE				\$304,519
<b>Campus Total</b>			<b>69,850</b>	<b>\$4,488,216</b>

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio and Video	1	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	1	3	EA	6	\$1,442	
	Exterior Doors - Exterior Steel Door	10	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	2	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	3	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	6	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	7	1	EA	5	\$1,341	
	Exterior Doors - Exterior Steel Door	8	2	EA	6	\$961	
	Exterior Doors - Side lite	1	6	EA	6	\$1,880	
	Exterior Doors - Store Front	5	4	EA	7	\$0	
	Exterior Doors - Transom Lite	1	9	EA	6	\$2,820	
	Exterior Doors - Transom Lite	2	2	EA	6	\$627	
	Exterior Doors - Transom Lite	3	2	EA	6	\$627	
	Exterior Doors - Transom Lite	7	1	EA	5	\$822	
	Exterior Stairs - Concrete	1	30	LF	7	\$0	
	Exterior Stairs - Concrete	10	3	LF	7	\$0	
	Exterior Stairs - Concrete	2	12	LF	7	\$0	
	Exterior Stairs - Concrete	3	6	LF	7	\$0	

**Building: Main**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Escape</b>							
	Fire Escape	West Façade	80	LF	5	\$84,002	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	948	LF	7	\$0	
	Superstructure - Heavy Timber	Entire Building	62,100	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	13	EA	6	\$3,754	
<b>Roof System</b>							
	Chimney	C	70	LF	6	\$0	
	Chimney	C	5	LF	4	\$0	vertical cracking
	Coping - Clay Tile	A	207	LF	6	\$6,648	
	Coping - Clay Tile	C	386	LF	6	\$12,397	
	Coping - Stone	B	56	LF	6	\$1,799	
	Coping - Terra Cotta	A	382	LF	6	\$12,269	
	Downspouts - Exterior Downspouts	A	60	LF	6	\$1,994	
	Downspouts - Exterior Downspouts	B	8	LF	6	\$266	
	Downspouts - Exterior Downspouts	C	60	LF	6	\$1,994	
	Downspouts - Interior Downspouts	A	180	LF	6	\$5,982	
	Downspouts - Interior Downspouts	B	60	LF	6	\$1,994	
	Parapet - 16" - 30" Height	A	489	LF	6	\$19,538	
	Parapet - 16" - 30" Height	B	56	LF	6	\$2,237	
	Parapet - 16" - 30" Height	C	386	LF	6	\$15,422	
	Parapet - Parapet > 30"	A	100	LF	6	\$6,392	
	Roof Structure - Concrete	C	4,688	SF	7	\$0	
	Roof Structure - Heavy Timber	A	14,033	SF	7	\$0	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	B	368	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	A	2,500	SF	4	\$70,070	leaks throughout per building engineer
	Roof - Asphalt Gravel Ballast	A	6,533	SF	6	\$66,423	
	Roof - Asphalt Gravel Ballast	A	5,000	SF	5	\$118,047	
	Roof - Modified Bitumen	B	368	SF	6	\$3,463	
	Roof - Modified Bitumen	C	2,088	SF	6	\$19,647	
	Roof - Modified Bitumen	C	2,500	SF	5	\$52,588	
	Roof - Modified Bitumen	C	100	SF	4	\$5,144	leaks throughout per building engineer
<b>Walls</b>							
	Cornice - Metal Projecting	Entire Building	373	LF	5	\$56,118	
	Exterior Walls - Brick	Entire Building	10,000	SF	6	\$78,221	

## Building: Main

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	9,245	SF	5	\$195,397	
	Exterior Walls - Brick	Entire Building / South East	2,323	SF	6	\$18,171	
	Exterior Walls - Stone-Cast	Entire Building	1,520	SF	6	\$10,216	
	Exterior Walls - Stone-Cut	Entire Building	400	SF	5	\$5,377	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building	1,303	SF	5	\$19,974	
	Guard - Guards perforated	Entire Building	250	SF	6	\$3,192	
	Lintels - Steel	Entire Building	290	LF	6	\$8,418	
	Lintels - Stone	Entire Building	325	LF	6	\$0	
	Windows - Louver	Entire Building	24	SF	5	\$2,055	
	Windows - Sash Aluminum Double-pane	Entire Building	5,387	SF	5	\$290,187	

### Building Exterior Subtotal:

**\$1,213,980**

## Building: Main

### Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Automatic Transfer Switch	Electrical Room	1	EA	7	\$0	
	Emergency A/C Power - Corridors and Stairs	Entire Building	10,766	SF	7	\$0	
	Emergency A/C Power - Lunchrooms	Entire Building	2,732	SF	7	\$0	
	Emergency A/C Power - Students Toilets	Entire Building	1,190	SF	7	\$0	
	Exit Signs - Corridors and Stairs	Entire Building	16	EA	6	\$2,396	
	Exit Signs - Lunchroom	Entire Building	4	EA	6	\$599	
	Security System - Intrusion Detection	Entire Building	62,100	SF	6	\$15,985	Serves main and addition
	UPS - Less than 30 KW	Electrical Room	1	EA	6	\$7,886	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 1200 A 120/208/3PH	Electrical Room	1	EA	7	\$0	Serves main and addition
	PA System	Entire Building	62,100	SF	6	\$20,425	Serves main and addition
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / Basement	1	EA	4	\$4,849	Live front fused panel
	Lighting and Power Panels - 100 A	Entire Building	9	EA	7	\$0	

**Building: Main**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building	7	EA	6	\$2,094	
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	3	EA	6	\$897	
	Lighting and Power Panels - 100 A	Entire Building / Mechanical Room	2	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	Entire Building / Mechanical Room	1	EA	4	\$6,578	Live front fused panel
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	7	\$0	
	Transformers - 120/240 - 120/208	Entire Building / Electrical Room	1	EA	6	\$3,021	

**Electrical System Subtotal: \$70,979**

**Building: Main**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Entire Building / Electrical Room	1	EA	4	\$49,477	Regularly trips on a ground fault (Serves main and addition)
	Fire Alarm Strobe Lights	Entire Building	62,100	SF	7	\$0	
	Fire Alarm_System	Entire Building	62,100	SF	6	\$30,193	Serves main and addition
	Fire Pump Controller	Entire Building	1	EA	6	\$1,823	
<b>Pump Room Assembly</b>							
	Fire Pump - 25-50 hp	Pump Room	1	EA	5	\$8,163	
<b>Sprinkler System</b>							
	Dry Sprinkler System	Entire Building	62,100	SF	6	\$15,985	Serves main and addition
	Sprinkler Heads	Entire Building	62,100	SF	6	\$0	
	Sprinkler Piping	Entire Building	62,100	SF	6	\$11,544	

**Safty System Subtotal: \$117,184**

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up-Multi Zone-Double Delivery- Steam Coils - 15000 - 30000 cfm	Mechanical Room	1	EA	5	\$112,299	Low corrosion but needs repairs
	Air Intake	Mechanical Room / East Façade	1	EA	4	\$17,616	At grade, next to parked cars and traffic
	Auxiliaries - 15000 - 30000 cfm	Mechanical Room	1	EA	3	\$36,420	Single blade bypass dampers, no filters installed, controls not functional

## Building: Main

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Return Duct Work	Mechanical Room	100	LF	4	\$0	
	Zone Dampers	Mechanical Room	23	EA	5	\$44,011	Repairable, but currently inoperable and propped open.
<b>Boiler Systems</b>							
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 151 - 200 HP	Boiler Room	2	EA	5	\$34,033	Needs new insulation
	Chemical Feed System	Boiler Room	1	EA	7	\$0	
	Combustion Dampers	Boiler Room	3	EA	4	\$19,660	Actuators do not work
	Condensate Pump	Boiler Room	1	EA	5	\$18,196	
	Condensate Pump	Boiler Room / Mechanical Room	1	EA	3	\$44,329	Leaks and appears inoperable
	Feed Water Pumps and Tank	Boiler Room	1	EA	5	\$36,450	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler	Boiler Room	2	EA	5	\$0	Engineer stated despite age, boilers work very well
	Piping - Condensate Pipe- Steel	Boiler Room	150	LF	4	\$27,179	Original to building
	Piping - Steam Pipe- Steel	Boiler Room	150	LF	5	\$2,113	
	Steam Traps	Boiler Room	10	EA	5	\$13,149	
<b>Heating Devices</b>							
	Unit Heater - Steam	Basement restroom	1	EA	5	\$909	
	Unit Heater - Steam	Boiler Room	1	EA	5	\$909	
	Wall Heater - Electric	Entire Building	6	EA	5	\$3,220	
	Wall Heater - Electric	Entire Building	1	EA	6	\$139	
<b>Temperature Control</b>							
	Pneumatic System	Entire Building	62,100	SF	3	\$323,243	Majority of controls do not work and are not cost effective to repair.
	Thermostats	Entire Building	32	EA	4	\$0	Thermostats need replacement with controls replacement
<b>Ventilation</b>							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / Electrical Room	1	EA	3	\$4,245	Closet doors propped open with portable fan blowing towards UPS because exhaust fan is not functional.
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building	1	EA	4	\$6,392	Fan greater than 25 years of age and in need of replacement
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building	1	EA	3	\$6,392	Fan very old, and no longer functional
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building	1	EA	7	\$0	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building	4	EA	3	\$7,768	Fan very old, and no longer functional
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building	4	EA	4	\$7,768	Fans greater than 25 years of age and in need of replacement
	Type I Exhaust Hood- Kitchen	Entire Building	1	EA	6	\$1,248	

**Building: Main**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Ventilation</b>							
	Type II Exhaust Hood- Warming Kitchen	Entire Building	1	EA	6	\$920	

**Mechanical System Subtotal:**

**\$768,608**

**Building: Main**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 300001 - 600000 BTU/HR	Boiler Room	1	EA	4	\$34,950	Leaks and corrosion, but still functional.
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	62,100	SF	4	\$44,402	Piping original to building. Many clamps installed.
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	62,100	SF	4	\$89,691	Piping original to building. Many clamps installed.
	Domestic Piping-Cold Water Risers	Entire Building	62,100	SF	4	\$49,730	Piping original to building. Many clamps installed.
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	62,100	SF	4	\$33,745	Piping original to building. Many clamps installed.
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	62,100	SF	4	\$79,923	Piping original to building. Many clamps installed.
	Domestic Piping-Hot Water Return Lines	Entire Building	62,100	SF	4	\$53,282	Piping original to building. Many clamps installed.
	Domestic Piping-Hot Water Return Risers	Entire Building	62,100	SF	4	\$30,193	Piping original to building. Many clamps installed.
	Sanitary Piping	Entire Building	62,100	SF	5	\$0	
	Storm Piping	Entire Building	62,100	SF	5	\$0	
	Vent Piping	Entire Building	62,100	SF	5	\$0	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Simplex	Tank Room	1	EA	5	\$8,937	
	Pumps - Ejector-Duplex	Tank Room	1	EA	6	\$1,387	
	Pumps - Sump-Simplex	Tank Room	1	EA	6	\$745	

**Plumbing System Subtotal:**

**\$426,983**

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #100 (Pre School)</b>							
	Casework	Basement	12	LF	6	\$303	
	Ceiling - Lay-in	Basement	887	SF	6	\$2,664	
	Doors - Transom Window	Basement	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #100 (Pre School)</b>							
	Floor - Tile/Sheet	Basement	887	SF	6	\$888	
	Lighting - Pendent/Surface	Basement	16	EA	6	\$1,982	
	Walls - Plaster/Drywall	Basement	1,560	SF	6	\$4,305	
<b>Classroom #101 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,030	SF	6	\$3,093	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,030	SF	6	\$7,261	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		26	LF	6	\$557	
	Storage/ Closet		172	SF	6	\$1,247	
	Walls - Plaster/Drywall		1,534	SF	6	\$4,234	
<b>Classroom #102 (Kindergarten)</b>							
	Casework		33	LF	6	\$833	
	Ceiling		948		6	\$0	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Wood		948	SF	6	\$6,683	
	Marker Board		10	LF	6	\$214	
	Walls - Plaster/Drywall		1,416	SF	6	\$3,908	
<b>Classroom #104 (Office)</b>							
	Casework		8	LF	6	\$202	
	Chalk Board		10	LF	4	\$918	
	Doors - Transom Window		25	SF	6	\$423	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Wood		950	SF	6	\$6,697	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Storage/ Closet		92	SF	6	\$667	
	Walls - Plaster/Drywall		1,612	SF	6	\$4,449	
<b>Classroom #105 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #105 (Regular Classroom)</b>							
	Floor - Wood		1,107	SF	6	\$7,804	
	Lighting - Lay-in		15	EA	6	\$1,785	
	Marker Board		12	LF	7	\$0	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,140	SF	6	\$5,906	
<b>Classroom #106 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,030	SF	6	\$3,093	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,030	SF	6	\$7,261	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		24	LF	6	\$514	
	Storage/ Closet		172	SF	6	\$1,247	
	Walls - Plaster/Drywall		1,534	SF	6	\$4,234	
<b>Classroom #108 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,045	SF	6	\$3,138	
	Chalk Board		28	LF	4	\$2,571	
	Doors - Transom Window		9	SF	6	\$152	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,045	SF	6	\$7,367	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		20	LF	7	\$0	
	Storage/ Closet		167	SF	6	\$1,211	
	Walls - Plaster/Drywall		1,534	SF	6	\$4,234	
<b>Classroom #200 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Casework		8	LF	6	\$202	
	Ceiling - Lay-in		887	SF	6	\$2,664	
	Chalk Board		18	LF	4	\$1,653	
	Doors - Transom Window		9	SF	6	\$152	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		887	SF	6	\$6,253	
	Lighting - Pendent/Surface		14	EA	6	\$1,735	
	Marker Board		10	LF	7	\$0	



**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #200 (Regular Classroom)</b>							
	Walls - Plaster/Drywall		1,560	SF	6	\$4,305	
<b>Classroom #201 (Computer Lab)</b>							
	AC Units		2	EA	6	\$991	
	Ceiling - Lay-in		858	SF	6	\$2,577	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		858	SF	6	\$6,049	
	Lighting - Pendent/Surface		14	EA	6	\$1,735	
	Marker Board		20	LF	6	\$428	
	Walls - Plaster/Drywall		1,534	SF	6	\$4,234	
	Wireless System		1	EA	6	\$372	
<b>Classroom #203 (Regular Classroom)</b>							
	Casework		14	LF	6	\$354	
	Ceiling - Plaster/Drywall		945	SF	6	\$3,270	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Transom Window		25	SF	6	\$423	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		945	SF	6	\$6,662	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		8	LF	7	\$0	
	Walls - Plaster/Drywall		1,612	SF	6	\$4,449	
<b>Classroom #204 (Science Classroom)</b>							
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		32	LF	7	\$0	
	Storage/ Closet		10	SF	6	\$73	
	Walls - Plaster/Drywall		2,200	SF	6	\$6,072	
<b>Classroom #205 (Regular Classroom)</b>							
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Doors - Transom Window		34	SF	6	\$576	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Wood		1,107	SF	6	\$7,804	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #205 (Regular Classroom)</b>							
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		24	LF	7	\$0	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #206 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Casework		8	LF	6	\$202	
	Ceiling		1,107		6	\$0	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		3	EA	6	\$903	
	Floor - Tile/Sheet		1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		20	LF	7	\$0	
	Storage/ Closet		10	SF	6	\$73	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #208 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,000	SF	6	\$3,003	
	Doors - Transom Window		9	SF	6	\$152	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,000	SF	6	\$1,001	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		6	LF	7	\$0	
	Storage/ Closet		107	SF	6	\$776	
	Walls - Plaster/Drywall		2,480	SF	6	\$6,845	
	Work Sink		1	EA	6	\$379	
<b>Classroom #300 (Science Classroom)</b>							
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Chalk Board		18	LF	4	\$1,653	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,107	SF	6	\$7,804	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		30	LF	7	\$0	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #301 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,107	SF	6	\$7,804	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		12	LF	7	\$0	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #302 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		1,107	SF	6	\$1,108	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		12	LF	6	\$257	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #303 (Regular Classroom)</b>							
	Casework		12	LF	6	\$303	
	Ceiling - Lay-in		1,452	SF	6	\$4,360	
	Chalk Board		28	LF	4	\$2,571	
	Doors - Transom Window		28	SF	6	\$474	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,452	SF	6	\$10,236	
	Lighting - Pendent/Surface		18	EA	6	\$2,230	
	Marker Board		12	LF	7	\$0	
	Walls - Plaster/Drywall		2,223	SF	6	\$6,135	
<b>Classroom #304 (Store Room)</b>							
	Casework		20	LF	6	\$505	
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Chalk Board		24	LF	6	\$535	
	Doors - Transom Window		41	SF	6	\$694	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Wood		1,107	SF	6	\$7,804	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #304 (Store Room)</b>							
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #305 (Regular Classroom)</b>							
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Chalk Board		20	LF	4	\$1,836	
	Doors - Transom Window		34	SF	6	\$576	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Wood		1,107	SF	6	\$7,804	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		20	LF	6	\$428	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #306 (Regular Classroom)</b>							
	Ceiling - Lay-in		1,107	SF	6	\$3,324	
	Chalk Board		24	LF	4	\$2,203	
	Doors - Transom Window		414	SF	6	\$7,010	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,107	SF	6	\$7,804	
	Lighting - Pendent/Surface		16	EA	6	\$1,982	
	Marker Board		16	LF	6	\$343	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls - Plaster/Drywall		2,740	SF	6	\$7,562	
<b>Classroom #308 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling		1,107		6	\$0	
	Chalk Board		24	LF	4	\$2,203	
	Doors		1		6	\$0	
	Doors - Transom Window		9	SF	6	\$152	
	Floor		1,107		6	\$0	
	Lighting		16		6	\$0	
	Marker Board		24	LF	7	\$0	
	Storage/ Closet		216	SF	6	\$1,566	
	Walls		2,740		6	\$0	

**Building: Main**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classrooms Subtotal:</b>						<b>\$425,186</b>	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	202	468	SF	6	\$1,405	
	Doors - Wood Doors inclu hw	202	1	EA	6	\$301	
	Floor - Tile/Sheet	202	408	SF	6	\$408	
	Lighting - Lay-in	202	15	EA	6	\$1,785	
	Power Distribution	202	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	202	1,100	SF	6	\$3,036	
	Ceiling - Lay-in	basement 009	280	SF	6	\$841	
	Doors - Transom Window	basement 009	1	SF	6	\$17	
	Floor - Carpet	basement 009	280	SF	6	\$597	
	Lighting - Lay-in	basement 009	5	EA	6	\$595	
	Power Distribution	basement 009	12	EA	6	\$25,499	
	Walls - Plaster/Drywall	basement 009	608	SF	6	\$1,678	
	Ceiling - Lay-in	basement next to boys bathroom	440	SF	6	\$1,321	
	Doors - Wood Doors inclu hw	basement next to boys bathroom	1	EA	6	\$301	
	Floor - Concrete	basement next to boys bathroom	440	SF	6	\$233	
	Lighting - Pendent/Surface	basement next to boys bathroom	3	EA	6	\$372	
	Walls - Concrete Block	basement next to boys bathroom	420	SF	6	\$1,231	
	Walls - Masonry	basement next to boys bathroom	420	SF	6	\$1,321	
	Ceiling - Exposed	councilor office basement 003	520	SF	6	\$773	
	Doors - Wood Doors inclu hw	councilor office basement 003	5	EA	6	\$1,505	
	Floor - Wood	councilor office basement 003	520	SF	6	\$3,666	
	Lighting - Pendent/Surface	councilor office basement 003	10	EA	6	\$1,239	
	Power Distribution	councilor office basement 003	10	EA	6	\$21,249	
	Storage/ Closet	councilor office basement 003	12	SF	6	\$87	
	Walls - Plaster/Drywall	councilor office basement 003	920	SF	6	\$2,539	
	Ceiling - Exposed	Engineers office - basement	143	SF	6	\$213	
	Doors - Transom Window	Engineers office - basement	16	SF	6	\$271	
	Doors - Wood Doors inclu hw	Engineers office - basement	1	EA	6	\$301	
	Floor - Concrete	Engineers office - basement	143	SF	6	\$76	asphalt
	Lighting - Pendent/Surface	Engineers office - basement	3	EA	6	\$372	
	Power Distribution	Engineers office - basement	2	EA	6	\$4,250	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Masonry	Engineers office - basement	320	SF	6	\$1,007	
	Walls - Plaster/Drywall	Engineers office - basement	320	SF	6	\$883	
	Ceiling - Plaster/Drywall	gym office	306	SF	6	\$1,059	
	Doors - Side-lite	gym office	64	SF	6	\$1,070	
	Doors - Wood Doors inclu hw	gym office	1	EA	6	\$301	
	Floor - Wood	gym office	306	SF	6	\$2,157	
	Lighting - Pendent/Surface	gym office	5	EA	6	\$619	
	Power Distribution	gym office	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	gym office	360	SF	6	\$994	
	Ceiling - Exposed	in old girls playroom basement 006	242	SF	6	\$360	
	Doors - Wood Doors inclu hw	in old girls playroom basement 006	1	EA	6	\$301	
	Floor - Wood	in old girls playroom basement 006	242	SF	6	\$1,706	
	Lighting - Pendent/Surface	in old girls playroom basement 006	3	EA	6	\$372	
	Power Distribution	in old girls playroom basement 006	2	EA	6	\$4,250	
	Walls - Masonry	in old girls playroom basement 006	320	SF	6	\$1,007	
	Walls - Plaster/Drywall	in old girls playroom basement 006	320	SF	6	\$883	
	Ceiling - Plaster/Drywall	kitchen	70	SF	6	\$242	
	Doors - Wood Doors inclu hw	kitchen	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	kitchen	70	SF	6	\$148	
	Lighting - Pendent/Surface	kitchen	1	EA	6	\$124	
	Power Distribution	kitchen	2	EA	6	\$4,250	
	Walls - Concrete Block	kitchen	100	SF	6	\$336	poured concrete
	Walls - Concrete Block	kitchen	240	SF	6	\$704	
	AC Unit	main office	1	EA	6	\$496	
	Ceiling - Plaster/Drywall	main office	323	SF	6	\$1,118	
	Doors - Side-lite	main office	81	SF	6	\$1,354	
	Doors - Wood Doors inclu hw	main office	2	EA	5	\$2,348	
	Floor - Tile/Sheet	main office	323	SF	6	\$323	
	Lighting - Pendent/Surface	main office	8	EA	6	\$991	
	Power Distribution	main office	18	EA	6	\$38,248	
	Walls - Plaster/Drywall	main office	648	SF	6	\$1,788	
	Ceiling - Plaster/Drywall	Principal office	272	SF	6	\$941	
	Doors - Side-lite	Principal office	42	SF	6	\$702	
	Doors - Wood Doors inclu hw	Principal office	2	EA	6	\$602	
	Floor - Carpet	Principal office	272	SF	6	\$580	
	Lighting - Pendent/Surface	Principal office	8	EA	6	\$991	
	Power Distribution	Principal office	13	EA	6	\$27,623	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Walls - Plaster/Drywall	Principal office	594	SF	6	\$1,639	
	Ceiling - Plaster/Drywall	work room -main office	96	SF	6	\$332	
	Floor - Tile/Sheet	work room -main office	96	SF	6	\$96	
	Lighting - Pendent/Surface	work room -main office	2	EA	6	\$248	
	Power Distribution	work room -main office	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	work room -main office	360	SF	6	\$994	
<b>Kitchen</b>							
	Ceiling	Basement	872		6	\$0	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Basement	3	EA	6	\$903	
	Floor - Tile Ceramic/ Porcelain	Basement	872	SF	6	\$1,846	
	Lighting - Pendent/Surface	Basement	19	EA	6	\$2,354	
	Storage/ Closet	Basement	72	SF	6	\$522	
	Walls - Concrete Block	Basement	1,030	SF	6	\$3,019	
	Walls - Masonry	Basement	320	SF	6	\$1,007	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Lay-in	Basement faculty lunch room 004	927	SF	6	\$2,784	
	Doors - Wood Doors inclu hw	Basement faculty lunch room 004	2	EA	6	\$602	
	Floor - Wood	Basement faculty lunch room 004	927	SF	6	\$6,535	
	Lighting - Pendent/Surface	Basement faculty lunch room 004	11	EA	6	\$1,363	
	Walls - Masonry	Basement faculty lunch room 004	1,408	SF	6	\$4,430	
	Walls - Plaster/Drywall	Basement faculty lunch room 004	253	SF	6	\$698	
	Ceiling - Lay-in	Basement	1,250	SF	6	\$3,754	
	Floor - Concrete	Basement	1,250	SF	6	\$661	ashalt
	Lighting - Lay-in	Basement	20	EA	6	\$2,380	
	Walls - Plaster/Drywall	Basement	800	SF	6	\$2,208	
	Ceiling - Lay-in	serving room - basement	555	SF	6	\$1,667	
	Floor - Concrete	serving room - basement	555	SF	6	\$294	asphalt
	Lighting - Lay-in	serving room - basement	16	EA	6	\$1,904	
	Serving Line	serving room - basement	20	LF	6	\$1,190	
	Walls - Plaster/Drywall	serving room - basement	558	SF	6	\$1,540	FRP
<b>MDF_IDF</b>							
	AC Unit	201A	1	EA	6	\$496	
	Doors - Wood Doors inclu hw	201A	7	EA	6	\$2,107	
	Finishes	201A	216	SF	6	\$1,541	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Mechanical/ Service Rooms</b>							
	Air Intake Plenums	basement, 1st, 2ed and 3ed floor	1,684	SF	6	\$10,427	
	Boiler Room	basement, 1st, 2ed and 3ed floor	1,215	SF	6	\$8,705	
	Coal Room	basement, 1st, 2ed and 3ed floor	540	SF	6	\$3,869	
	Janitor's Closet	basement, 1st, 2ed and 3ed floor	60	SF	6	\$430	
	Mechanical/ Service Rooms	basement, 1st, 2ed and 3ed floor	462	SF	6	\$3,310	
	Storage Room	basement, 1st, 2ed and 3ed floor	615	SF	6	\$4,406	
<b>Restroom</b>							
	Accessories	009A	30	SF	6	\$277	
	Ceiling - Lay-in	009A	30	SF	6	\$90	
	Doors - Wood Doors inclu hw	009A	1	EA	6	\$301	
	Floor - Terrazzo	009A	30	SF	6	\$66	
	Lavatory	009A	1	EA	7	\$0	
	Lighting - Pendent/Surface	009A	1	EA	4	\$541	incandescent
	Walls - Plaster/Drywall	009A	88	SF	6	\$243	
	Water Closet	009A	1	EA	6	\$336	
	Accessories	100A	56	SF	6	\$517	
	Ceiling - Lay-in	100A	56	SF	6	\$168	
	Doors - Wood Doors inclu hw	100A	1	EA	6	\$301	
	Floor - Tile/Sheet	100A	56	SF	6	\$56	
	Lavatory	100A	1	EA	6	\$320	
	Lighting - Pendent/Surface	100A	1	EA	6	\$124	
	Walls - Plaster/Drywall	100A	390	SF	6	\$1,076	
	Water Closet	100A	1	EA	6	\$336	
	Accessories	102A	30	SF	6	\$277	
	Ceiling - Lay-in	102A	30	SF	6	\$90	
	Doors - Wood Doors inclu hw	102A	1	EA	6	\$301	
	Floor - Tile/Sheet	102A	30	SF	6	\$30	
	Lavatory	102A	1	EA	6	\$320	
	Lighting - Wall Mounted	102A	1	EA	4	\$393	incandescent
	Walls - Plaster/Drywall	102A	264	SF	6	\$729	
	Water Closet	102A	1	EA	6	\$336	
	Accessories	2nd Floor	208	SF	7	\$0	
	Accessories	2nd Floor	312	SF	6	\$2,878	
	Ceiling - Plaster/Drywall	2nd Floor	312	SF	6	\$1,080	
	Ceiling - Plaster/Drywall	2nd Floor	208	SF	6	\$720	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	



**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor Drain	2nd Floor	1	EA	7	\$0	
	Floor Drain	2nd Floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	208	SF	7	\$0	
	Floor - Tile Ceramic/ Porcelain	2nd Floor	312	SF	6	\$660	
	Hand Dryer	2nd Floor	1	EA	6	\$230	
	Hand Dryer	2nd Floor	1	EA	7	\$0	
	Lavatory	2nd Floor	2	EA	6	\$639	
	Lavatory	2nd Floor	2	EA	7	\$0	
	Lighting	2nd Floor	5		7	\$0	
	Lighting - Pendent/Surface	2nd Floor	5	EA	6	\$619	
	Partitions	2nd Floor	2	EA	7	\$0	
	Partitions	2nd Floor	7	EA	6	\$2,078	
	Urinals	2nd Floor	6	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	826	SF	6	\$2,280	FRP
	Walls - Plaster/Drywall	2nd Floor	564	SF	7	\$0	FRP
	Walls - Tile Ceramic/ Porcelain	2nd Floor	256	SF	7	\$0	
	Walls - Tile Ceramic/ Porcelain	2nd Floor	114	SF	6	\$258	
	Water Closet	2nd Floor	2	EA	7	\$0	
	Water Closet	2nd Floor	7	EA	6	\$2,352	
	Accessories	Basement	292	SF	6	\$2,693	
	Accessories	Basement	292	SF	6	\$2,693	
	Ceiling - Plaster/Drywall	Basement	292	SF	6	\$1,010	
	Ceiling - Plaster/Drywall	Basement	292	SF	6	\$1,010	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Basement	1	EA	6	\$301	
	Floor Drain	Basement	1	EA	6	\$1,059	
	Floor Drain	Basement	1	EA	6	\$1,059	
	Floor - Concrete	Basement	292	SF	6	\$154	
	Floor - Tile Ceramic/ Porcelain	Basement	292	SF	6	\$618	
	Hand Dryer	Basement	1	EA	6	\$230	
	Hand Dryer	Basement	1	EA	6	\$230	
	Lavatory	Basement	2	EA	6	\$639	
	Lavatory	Basement	2	EA	6	\$639	
	Lighting - Pendent/Surface	Basement	5	EA	6	\$619	
	Lighting - Pendent/Surface	Basement	9	EA	6	\$1,115	
	Partitions	Basement	3	EA	6	\$891	
	Partitions	Basement	8	EA	6	\$2,375	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Urinals	Basement	6	EA	6	\$2,016	
	Walls - Concrete Block	Basement	320	SF	6	\$938	
	Walls - Concrete Block	Basement	1,132	SF	6	\$3,318	
	Walls - Plaster/Drywall	Basement	350	SF	6	\$966	
	Water Closet	Basement	3	EA	6	\$1,008	
	Water Closet	Basement	8	EA	6	\$2,688	
	Accessories	engineers toilet	40	SF	6	\$369	
	Ceiling - Exposed	engineers toilet	40	SF	6	\$59	
	Doors - Wood Doors inclu hw	engineers toilet	1	EA	6	\$301	
	Floor - Concrete	engineers toilet	40	SF	6	\$21	
	Lavatory	engineers toilet	1	EA	6	\$320	
	Lighting - Wall Mounted	engineers toilet	1	EA	4	\$393	incandescent
	Walls - Concrete Block	engineers toilet	280	SF	6	\$821	
	Water Closet	engineers toilet	1	EA	6	\$336	
	Accessories	Kitchen toilet	70	SF	6	\$646	
	Ceiling	Kitchen toilet	70		6	\$0	
	Doors	Kitchen toilet	2		6	\$0	
	Floor - Concrete	Kitchen toilet	70	SF	6	\$37	
	Lavatory	Kitchen toilet	1	EA	6	\$320	
	Lighting - Pendent/Surface	Kitchen toilet	1	EA	6	\$124	
	Walls - Concrete Block	Kitchen toilet	192	SF	6	\$563	
	Walls - Plaster/Drywall	Kitchen toilet	56	SF	6	\$155	
	Water Closet	Kitchen toilet	1	EA	6	\$336	
	Accessories	main office 1st floor	98	SF	6	\$904	
	Ceiling - Plaster/Drywall	main office 1st floor	98	SF	6	\$339	
	Doors - Wood Doors inclu hw	main office 1st floor	1	EA	6	\$301	
	Floor - Terrazzo	main office 1st floor	98	SF	6	\$214	
	Lavatory	main office 1st floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	main office 1st floor	2	EA	6	\$248	
	Partitions	main office 1st floor	1	EA	6	\$297	
	Walls	main office 1st floor	420		6	\$0	
	Water Closet	main office 1st floor	1	EA	6	\$336	
	Accessories	men's 2nd floor	208	SF	6	\$1,918	
	Ceiling - Plaster/Drywall	men's 2nd floor	208	SF	6	\$720	
	Doors - Wood Doors inclu hw	men's 2nd floor	2	EA	6	\$602	
	Floor - Terrazzo	men's 2nd floor	208	SF	6	\$455	
	Lavatory	men's 2nd floor	1	EA	6	\$320	

**Building: Main**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Pendent/Surface	men's 2nd floor	2	EA	6	\$248	
	Lighting - Pendent/Surface	men's 2nd floor	1	EA	4	\$541	incandescent
	Partitions	men's 2nd floor	2	EA	6	\$594	
	Walls - Plaster/Drywall	men's 2nd floor	840	SF	6	\$2,318	
	Water Closet	men's 2nd floor	2	EA	6	\$672	
	Accessories	toilet in boiler room	32	SF	6	\$295	
	Ceiling - Exposed	toilet in boiler room	32	SF	6	\$48	
	Doors - Transom Window	toilet in boiler room	1	SF	6	\$17	
	Floor - Concrete	toilet in boiler room	32	SF	6	\$17	
	Lavatory	toilet in boiler room	1	EA	6	\$320	
	Lighting - Pendent/Surface	toilet in boiler room	1	EA	6	\$124	
	Walls - Concrete Block	toilet in boiler room	240	SF	6	\$704	
	Water Closet	toilet in boiler room	1	EA	6	\$336	
	Accessories	unisex across form 105	182	SF	6	\$1,679	
	Ceiling - Lay-in	unisex across form 105	182	SF	6	\$547	
	Doors - Wood Doors inclu hw	unisex across form 105	2	EA	6	\$602	
	Floor - Terrazzo	unisex across form 105	182	SF	6	\$398	
	Lavatory	unisex across form 105	1	EA	6	\$320	
	Lighting - Pendent/Surface	unisex across form 105	6	EA	6	\$743	
	Walls - Plaster/Drywall	unisex across form 105	1,040	SF	6	\$2,870	
	Water Closet	unisex across form 105	1	EA	6	\$336	
	Accessories	women's second floor	208	SF	6	\$1,918	
	Benches	women's second floor	6	LF	6	\$87	
	Ceiling - Lay-in	women's second floor	208	SF	6	\$625	
	Doors - Transom Window	women's second floor	1	SF	6	\$17	
	Floor - Terrazzo	women's second floor	208	SF	6	\$455	
	Lavatory	women's second floor	1	EA	6	\$320	
	Lighting - Pendent/Surface	women's second floor	6	EA	6	\$743	
	Partitions	women's second floor	2	EA	6	\$594	
	Walls - Plaster/Drywall	women's second floor	826	SF	6	\$2,280	
	Water Closet	women's second floor	2	EA	6	\$672	

**Rooms (Other Than Classrooms) Subtotal:**

**\$356,132**

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	2,385	SF	6	\$7,162	
	Ceiling - Plaster/Drywall	1st Floor	240	SF	6	\$1,486	
	Drinking Fountains - Single Fountain	1st Floor	4	EA	6	\$1,103	
	Drinking Fountains - Single Water Cooler	1st Floor	2	EA	6	\$633	
	Floor - Asphalt Floor	1st Floor	2,628	SF	6	\$3,984	
	Lighting - Pendent/Surface	1st Floor	24	EA	6	\$2,973	
	Walls - Plaster/Drywall	1st Floor	4,126	SF	6	\$18,291	
	Ceiling - Plaster/Drywall	2nd Floor	240	SF	6	\$2,090	
	Ceiling - Plaster/Drywall	2nd Floor	2,625	SF	6	\$16,254	
	Drinking Fountains - Single Fountain	2nd Floor	4	EA	6	\$1,103	
	Drinking Fountains - Single Water Cooler	2nd Floor	2	EA	6	\$633	
	Floor - Asphalt Floor	2nd Floor	2,385	SF	6	\$3,615	
	Floor - Tile/Sheet	2nd Floor	240	SF	6	\$130	
	Lighting - Pendent/Surface	2nd Floor	24	EA	6	\$2,973	
	Student Lockers - One Tier	2nd Floor	94	EA	6	\$8,727	
	Walls - Plaster/Drywall	2nd Floor	4,170	SF	6	\$18,486	
	Ceiling - Lay-in	3rd Floor	2,625	SF	6	\$7,883	
	Ceiling - Plaster/Drywall	3rd Floor	240	SF	6	\$1,486	
	Drinking Fountains - Single Fountain	3rd Floor	3	EA	6	\$827	
	Drinking Fountains - Single Water Cooler	3rd Floor	2	EA	6	\$633	
	Floor - Asphalt Floor	3rd Floor	2,385	SF	6	\$3,615	
	Floor - Tile/Sheet	3rd Floor	240	SF	6	\$130	
	Lighting - Pendent/Surface	3rd Floor	24	EA	6	\$2,973	
	Student Lockers - One Tier	3rd Floor	34	EA	6	\$3,156	
	Walls - Plaster/Drywall	3rd Floor	4,170	SF	6	\$18,486	
	Ceiling - Exposed	Basement	1,544	SF	6	\$2,296	
	Ceiling - Plaster/Drywall	Basement	498	SF	6	\$3,084	
	Doors - Wood Doors include hw	Basement	3	EA	6	\$903	
	Drinking Fountains - Single Water Cooler	Basement	2	EA	6	\$633	
	Floor - Asphalt Floor	Basement	2,042	SF	6	\$3,095	
	Lighting - Pendent/Surface	Basement	30	EA	6	\$3,717	
	Walls - Masonry	Basement	1,880	SF	6	\$5,914	
	Walls - Plaster/Drywall	Basement	1,720	SF	6	\$7,625	
	Ceiling - Plaster/Drywall	vestibules	666	SF	6	\$4,124	
	Doors - Side-lite	vestibules	128	EA	6	\$2,140	
	Doors - Store Front	vestibules	2	EA	6	\$2,416	
	Doors - Transom Window	vestibules	178	EA	6	\$3,014	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Doors - Wood Doors include hw	vestibules	14	EA	6	\$4,214	
	Floor - Asphalt Floor	vestibules	180	SF	6	\$273	
	Floor - Terrazzo	vestibules	162	SF	6	\$1,360	
	Floor - Tile/Sheet	vestibules	324	SF	6	\$176	
	Lighting - Pendent/Surface	vestibules	14	EA	6	\$1,735	
	Walls - Masonry	vestibules	642	SF	6	\$2,020	
	Walls - Plaster/Drywall	vestibules	628	SF	6	\$2,784	
<b>Stairs</b>							
	Ceiling - Plaster/Drywall	at basement boys toilet	200	SF	6	\$1,464	
	Floor - Asphalt	at basement boys toilet	200	SF	6	\$1,550	
	Handrails	at basement boys toilet	12	LF	6	\$104	
	Lighting - Pendent/Surface	at basement boys toilet	2	EA	6	\$248	
	Stairs - Asphalt	at basement boys toilet	60	LF	6	\$557	
	Walls - Masonry	at basement boys toilet	600	SF	6	\$1,888	
	Ceiling - Plaster/Drywall	basement at girls toilet	200	SF	6	\$1,464	
	Floor - Asphalt	basement at girls toilet	200	SF	6	\$1,550	
	Handrails	basement at girls toilet	12	LF	6	\$104	
	Lighting - Pendent/Surface	basement at girls toilet	2	EA	6	\$248	
	Stairs - Asphalt	basement at girls toilet	60	LF	6	\$557	
	Walls - Masonry	basement at girls toilet	600	SF	6	\$1,888	
	Ceiling - Plaster/Drywall	Basement	270	SF	6	\$1,977	
	Floor - Asphalt	Basement	180	SF	6	\$1,395	
	Handrails	Basement	30	LF	6	\$260	
	Lighting - Pendent/Surface	Basement	3	EA	6	\$372	
	Stairs - Asphalt	Basement	42	LF	6	\$390	
	Walls - Concrete Block	Basement	108	SF	6	\$317	
	Walls - Masonry	Basement	336	SF	6	\$1,057	
	Ceiling - Plaster/Drywall	middle	648	SF	6	\$4,744	
	Floor - Asphalt	middle	341	SF	6	\$2,643	
	Handrails	middle	138	LF	6	\$1,196	
	Lighting - Pendent/Surface	middle	5	EA	6	\$619	
	Stairs - Asphalt	middle	394	LF	6	\$3,657	
	Walls - Plaster/Drywall	middle	1,440	SF	6	\$3,974	
	Ceiling - Exposed	North	448	SF	6	\$666	
	Ceiling - Lay-in	North	450	SF	6	\$1,351	
	Ceiling - Plaster/Drywall	North	325	SF	6	\$2,380	
	Floor - Asphalt	North	375	SF	6	\$2,906	

**Building: Main**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Handrails	North	154	LF	6	\$1,335	
	Lighting - Pendent/Surface	North	6	EA	6	\$743	
	Stairs - Asphalt	North	490	LF	6	\$4,548	
	Walls - Plaster/Drywall	North	4,250	SF	6	\$11,730	
	Ceiling - Lay-in	South	2,625	SF	6	\$7,883	
	Ceiling - Plaster/Drywall	South	240	SF	6	\$1,757	
	Floor - Asphalt	South	375	SF	6	\$2,906	
	Handrails	South	142	LF	6	\$1,231	
	Lighting - Pendent/Surface	South	7	EA	6	\$867	
	Stairs - Asphalt	South	448	LF	6	\$4,158	
	Walls - Plaster/Drywall	South	4,250	SF	6	\$11,730	

**Vertical Conveyance**

	Wheelchair Lift - Platform Lift	Basement	1	EA	7	\$0	
	Elevator - Hydraulic Elevator	South	1	EA	7	\$0	

**Building Interior Subtotal:**

**\$270,768**

**Total Building Cost**

**\$3,649,822**

**Building: Gymnasium/auditorium**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	4	4	EA	6	\$1,922	
	Exterior Doors - Exterior Steel Door	9	2	EA	6	\$961	
	Exterior Doors - Transom Lite	4	4	EA	6	\$1,253	
	Exterior Stairs - Concrete	4	32	LF	6	\$2,617	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	396	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	7,750	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Parapet or Roof Mounted	Main Roof	5	EA	6	\$2,683	
<b>Roof System</b>							
	Coping - Clay Tile	D	275	LF	6	\$8,832	

**Building: Gymnasium/auditorium**

**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Roof System</b>							
	Coping - Clay Tile	E	31	LF	6	\$996	
	Downspouts - Exterior Downspouts	D	16	LF	6	\$532	
	Downspouts - Exterior Downspouts	E	12	LF	6	\$399	
	Downspouts - Interior Downspouts	D	140	LF	6	\$4,653	
	Parapet - 16" - 30" Height	D	275	LF	6	\$10,987	
	Parapet - Parapet < 16" Height	E	31	LF	6	\$661	
	Roof Structure - Steel with Clay Tile Arch	D	7,540	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	E	210	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	D	7,540	SF	6	\$76,661	
	Roof - Asphalt Gravel Ballast	E	210	SF	6	\$2,135	
<b>Walls</b>							
	Cheek-Wall - Stone	Entire Building / East Façade	12	SF	6	\$123	
	Cornice - Metal Projecting	Entire Building	140	LF	5	\$21,063	
	Exterior Walls - Brick	Entire Building	3,852	SF	6	\$25,889	
	Exterior Walls - Brick	Entire Building	3,250	SF	5	\$68,690	
	Exterior Walls - Brick	Entire Building / South West	20	SF	4	\$3,293	step crack
	Exterior Walls - Stone-Cut	Entire Building	75	SF	5	\$1,197	
	Exterior Walls - Stone-Cut	Entire Building	233	SF	6	\$1,566	
<b>Windows</b>							
	Guard - Guards perforated	Entire Building	200	SF	6	\$2,554	
	Lintels - Steel	Entire Building	35	LF	6	\$1,016	
	Windows - Sash Aluminum Double-pane	Entire Building	200	SF	5	\$10,774	

**Building Exterior Subtotal: \$251,456**

**Building: Gymnasium/auditorium**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Exit Signs - Auditorium	Entire Building	7	EA	6	\$1,048	
	Exit Signs - Corridors and Stairs	Entire Building	3	EA	6	\$449	
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building	2	EA	6	\$598	

**Building: Gymnasium/auditorium**

**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Electrical System Subtotal:</b>						<b>\$2,096</b>	

**Building: Gymnasium/auditorium**

**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Strobe Lights		7,750	SF	7	\$0	
	Fire Alarm_System		7,750	SF	6	\$3,768	
<b>Sprinkler System</b>							
	Dry Sprinkler System	Entire Building	7,750	SF	6	\$1,995	
	Sprinkler Heads	Entire Building	7,750	SF	6	\$0	
	Sprinkler Piping	Entire Building	7,750	SF	6	\$1,441	
<b>Safty System Subtotal:</b>						<b>\$7,204</b>	

**Building: Gymnasium/auditorium**

**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up- Single Zone- Steam Coils - 15001 - 25000 cfm	Mechanical Room	1	EA	5	\$44,262	
	Air Intake	Mechanical Room / Roof	1	EA	3	\$17,616	Blocked closed
	Auxiliaries - 15001 - 25000 cfm	Mechanical Room	1	EA	4	\$36,420	Controls not functional, no filters installed
	Return Duct Work	Mechanical Room	100	LF	4	\$0	
<b>Mechanical System Subtotal:</b>						<b>\$98,298</b>	

**Building: Gymnasium/auditorium**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Piping</b>							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	7,750	SF	4	\$11,193	Piping original to the building. Many clamps installed.
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	7,750	SF	4	\$9,974	Piping original to the building. Many clamps installed.
	Domestic Piping-Hot Water Return Lines	Entire Building	7,750	SF	4	\$6,650	Piping original to the building. Many clamps installed.



**Building: Gymnasium/auditorium**

**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Piping</b>							
	Sanitary Piping	Entire Building	7,750	SF	5	\$0	
	Storm Piping	Entire Building	7,750	SF	5	\$0	
	Vent Piping	Entire Building	7,750	SF	5	\$0	

**Plumbing System Subtotal:**

**\$27,817**

**Building: Gymnasium/auditorium**

**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #109 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Ceiling - Lay-in		1,008	SF	6	\$3,027	
	Chalk Board		10	LF	4	\$918	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Tile/Sheet		1,008	SF	6	\$1,009	
	Lighting - Pendent/Surface		14	EA	6	\$1,735	
	Marker Board		18	LF	6	\$386	
	Storage/ Closet		150	SF	6	\$1,088	
	Walls - Plaster/Drywall		1,534	SF	6	\$4,234	

**Classrooms Subtotal:**

**\$13,493**

**Building: Gymnasium/auditorium**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Gymnasia</b>							
	Bleacher Seating	1st Floor	572	EA	6	\$16,556	seating; item line unavailable to capture 256 wood steps in balcony
	Ceiling - Plaster/Drywall	1st Floor	7,488	SF	6	\$41,332	
	Doors - Wood Doors inclu hw	1st Floor	9	EA	6	\$2,709	
	Floor - Tile/Sheet	1st Floor	2,394	SF	6	\$2,396	
	Floor - Wood	1st Floor	3,712	SF	6	\$26,169	
	Lighting - Pendent/Surface	1st Floor	50	EA	6	\$6,195	
	Sound System	1st Floor	1	EA	7	\$0	
	Stage	1st Floor	1,280	SF	6	\$7,395	
	Stage Curtain	1st Floor	2	EA	6	\$0	
	Stage Lighting System	1st Floor	1	EA	7	\$0	

**Building: Gymnasium/auditorium**

**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Gymnasia</b>							
	Stage-Stairs - Wood	1st Floor	30	LF	6	\$352	
	Storage/ Closet	1st Floor	30	SF	6	\$218	
	Walls - Plaster/Drywall	1st Floor	7,085	SF	6	\$19,554	

**Rooms (Other Than Classrooms) Subtotal:**

**\$122,875**

**Building: Gymnasium/auditorium**

**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Plaster/Drywall	auditorium vestibule	84	SF	6	\$520	
	Floor - Concrete	auditorium vestibule	84	SF	6	\$44	
	Lighting - Pendent/Surface	auditorium vestibule	2	EA	6	\$248	
	Walls - Concrete Block	auditorium vestibule	378	SF	6	\$1,108	
	Walls - Plaster/Drywall	auditorium vestibule	162	SF	6	\$718	
	Ceiling - Plaster/Drywall	gym vestibule	160	SF	6	\$991	
	Doors - Wood Doors include hw	gym vestibule	4	EA	6	\$1,204	
	Floor - Tile/Sheet	gym vestibule	160	SF	6	\$87	
	Lighting - Pendent/Surface	gym vestibule	2	EA	6	\$248	
	Walls - Plaster/Drywall	gym vestibule	520	SF	6	\$2,305	

**Stairs**

	Ceiling - Plaster/Drywall	at gym balcony	104	SF	6	\$761	
	Floor - Asphalt	at gym balcony	16	SF	6	\$124	
	Handrails	at gym balcony	61	LF	6	\$529	
	Stairs - Asphalt	at gym balcony	88	LF	6	\$817	
	Walls - Plaster/Drywall	at gym balcony	338	SF	6	\$933	

**Building Interior Subtotal:**

**\$10,637**

**Total Building Cost**

**\$533,876**

**SITE**

**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**SITE**

**Category: Site**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site / Site North	1	EA	6	\$1,094	
	Civil/ Drainage - Site Manhole	Entire Site	5	EA	6	\$7,464	
<b>Fencing</b>							
	Fencing - Chain Link	Entire Site / South West	20	LF	5	\$1,220	
	Fencing - Guard Rail	Entire Site / Site North	279	LF	6	\$3,224	
	Fencing - New Standard Ornamental	Entire Site	1,057	LF	5	\$150,516	
<b>Landscape</b>							
	Benches	Entire Site / Site South	3	EA	6	\$1,290	
	Landscape - Grass	Entire Site / Site North	11,640	SF	6	\$9,654	
	Parkway trees	Entire Site	25	EA	6	\$16,501	
	Play Area - Asphalt/ Hardscape	Entire Site	10,704	SF	6	\$25,868	
<b>Parking Lot</b>							
	Surface - Asphalt	North	16,110	SF	6	\$38,933	
<b>Playground</b>							
	Equipment - School Age 5-12	South	1	EA	6	\$3,546	
	Equipment - School Age 5-12	South	1	EA	6	\$3,546	
	Equipment - Swingset	South	1	EA	5	\$0	No swings installed
	Surface - Square Rubber Mats	South	2,244	SF	5	\$22,655	
	Surface - Square Rubber Mats	South	1,330	SF	5	\$13,427	
	Surface - Square Rubber Mats	South	496	SF	5	\$5,008	
<b>Sidewalks</b>							
	Sidewalks - Perimeter Sidewalks	Entire Site	60	SF	5	\$573	
	Sidewalks - Perimeter Sidewalks	Entire Site	10,907	SF	7	\$0	
<b>Signage</b>							
	Flag Pole - Building Mounted Flag Pole	East / East Façade	1	EA	7	\$0	at main entry
	Marquee - Free Standing Back lighted w/ LED	East / East Façade	1	EA	6	\$0	at main entry

**Site Subtotal:** **\$304,519**

**Total Site Cost** **\$304,519**

**Campus Total <sup>2 3</sup>** **\$4,488,216**

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

---

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
  - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
  - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Computer Lab	Regular Classroom		201	201	858	0	0	70	85	34	50	N	Y	N
Kindergarten	Pre School		102	102	948	0	4	10	1,460	16	50	N	Y	Y
Office	Regular Classroom		104	104	950	0	0	8	123	12	51	N	Y	Y
Pre School	Pre School	Basement	100	100	887	0	5	25	160	16	50	N	Y	N
Regular Classroom	Regular Classroom		101	101	1,030	0	0	10	123	70	51	N	Y	Y
Regular Classroom	Regular Classroom		105	105	1,107	0	0	13	123	51	50	N	Y	Y
Regular Classroom	Regular Classroom		106	106	1,030	0	0	11	123	51	50	N	Y	Y
Regular Classroom	Regular Classroom		108	108	1,045	0	0	11	140	12	50	N	Y	N
Regular Classroom	Regular Classroom		200	200	887	0	5	25	160	16	50	Y	Y	N
Regular Classroom	Regular Classroom		203	203	945	0	0	20	140	67	50	N	Y	N
Regular Classroom	Regular Classroom		205	205	1,107	0	0	13	147	67	50	N	Y	Y
Regular Classroom	Regular Classroom		206	206	1,107	0	0	11	123	51	50	N	Y	Y
Regular Classroom	Regular Classroom		208	208	1,000	0	0	16	190	84	40	N	Y	Y
Regular Classroom	Regular Classroom		301	301	1,107	0	0	25	123	51	50	N	Y	N
Regular Classroom	Library		302	302	1,107	0	5	25	105	9	50	N	Y	N
Regular Classroom	Regular Classroom		303	303	1,452	0	15	40	172	85	50	N	Y	N
Regular Classroom	Regular Classroom		305	305	1,107	0	40	50	142	68	50	N	Y	Y
Regular Classroom	Regular Classroom		306	306	1,107	0	0	26	142	68	50	N	Y	Y
Regular Classroom	Regular Classroom		308	308	1,107	0	5	25	190	84	50	N	Y	N
Science Classroom	Regular Classroom		204	204	1,107	0	0	18	123	12	51	N	Y	N
Science Classroom	Regular Classroom		300	300	1,107	0	5	25	142	68	50	N	Y	N
Store Room	Regular Classroom		304	304	1,107	0	13	26	142	68	50	N	Y	N

## Gymnasium/auditorium

Regular Classroom	Regular Classroom		109	109	1,008	0	0	12	193	81	40	N	Y	Y
-------------------	-------------------	--	-----	-----	-------	---	---	----	-----	----	----	---	---	---