

## Facility Assessment Report

This report contains the detailed findings of a facility assessment completed on the date noted in the document footer below. Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition<sup>1</sup>. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at [http://www.cps.edu/About\\_CPS/Policies\\_and\\_guidelines/Pages/facilitystandards.aspx](http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx). Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1908	5	158,545	\$6,232,728
Addition 1	1939	3	40,692	\$3,423,970
Addition 2	1953	1	4,238	\$165,792
Addition 3	1968	2	10,816	\$711,867
Addition 4	1968	2	82,150	\$3,505,428
SITE				\$952,956
<b>Campus Total</b>			<b>296,441</b>	<b>\$14,992,741</b>

### Building: Main

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Entrance Control - Audio	#2 S	1	EA	6	\$497	
	Entrance Control - Audio	#9 E	1	EA	6	\$497	
	Exterior Doors - Exterior Steel Door	#14.1 N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#14.2_Exit N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#14_Exit N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#19_Fire Escape E	2	EA	6	\$961	3rd Floor
	Exterior Doors - Exterior Steel Door	#20_Fire Escape E	2	EA	6	\$961	2nd Floor
	Exterior Doors - Exterior Steel Door	#21_Fire Escape Center E	2	EA	6	\$961	5th Floor
	Exterior Doors - Exterior Steel Door	#22_Fire Escape Center E	2	EA	6	\$961	4th Floor
	Exterior Doors - Exterior Steel Door	#23_Fire Escape Center E	2	EA	6	\$961	3rd Floor
	Exterior Doors - Exterior Steel Door	#24_Fire Escape Center W	2	EA	6	\$961	5th Floor
	Exterior Doors - Exterior Steel Door	#25_Fire Escape Center W	2	EA	6	\$961	4th Floor
	Exterior Doors - Exterior Steel Door	#26_Fire Escape Center W	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#9 E	4	EA	6	\$1,922	
	Exterior Doors - Exterior Wood Door	#2 S	4	EA	6	\$1,922	
	Exterior Doors - Exterior Wood Door	#3 W	4	EA	6	\$1,922	

## Building: Main

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Entrance							
	Exterior Doors - Transom Lite	#14.2_Exit N	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#19_Fire Escape E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#2 S	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#20_Fire Escape E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#21_Fire Escape Center E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#22_Fire Escape Center E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#23_Fire Escape Center E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#24_Fire Escape Center W	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#25_Fire Escape Center W	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#26_Fire Escape Center W	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#9 E	4	EA	6	\$1,253	
	Exterior Stairs - Concrete	#14.1 N	3	LF	6	\$245	
	Exterior Stairs - Concrete	#14_Exit N	18	LF	5	\$1,972	Stairs are leaning forward; should be replaced
	Exterior Stairs - Concrete	#3 W	24	LF	6	\$1,962	
	Exterior Stairs - Stone	#14.2_Exit N	3	LF	6	\$339	
	Power Door Operator and Controls	#2 S	2	EA	6	\$0	
	Ramp Handrail - Steel_Ramp Handrail	#9 E	40	LF	6	\$347	
	Ramps - Concrete	#9 E	20	LF	6	\$3,005	
Fire Escape							
	Fire Escape	East Courtyard	50	LF	6	\$31,588	Operable stair is warped
	Fire Escape	North Façade	427	LF	6	\$269,761	
Foundation							
	Foundation - Masonry	Entire Building	1,003	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	158,545	SF	7	\$0	
Lighting							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	6	EA	6	\$3,219	
	Exterior Lighting - Wall Mounted	Entire Building	23	EA	6	\$6,641	
Roof System							
	Coping - Metal	Roof #1	725	LF	6	\$23,285	
	Coping - Stone	Roof #2	45	LF	6	\$1,445	
	Coping - Terra Cotta	Roof #2	290	LF	6	\$9,314	Clean debris from around cover
	Coping - Terra Cotta	Roof #3	287	LF	6	\$9,218	
	Coping - Terra Cotta	Roof #4	187	LF	6	\$6,006	
	Downspouts - Exterior Downspouts	Roof #1	480	LF	6	\$15,952	
	Downspouts - Exterior Downspouts	Roof #2	95	LF	6	\$3,157	Should install down spout at NE corner

## Building: Main

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
Roof System							
	Downspouts - Exterior Downspouts	Roof #3	30	LF	6	\$997	With 13 LF of Metal Gutter.
	Downspouts - Exterior Downspouts	Roof #4	90	LF	6	\$2,991	
	Downspouts - Interior Downspouts	Roof #3	60	LF	6	\$1,994	
	Parapet - 16" - 30" Height	Roof #2	315	LF	6	\$12,586	
	Parapet - 16" - 30" Height	Roof #4	187	LF	6	\$7,471	
	Parapet - Parapet < 16" Height	Roof #2	20	LF	6	\$426	
	Parapet - Parapet < 16" Height	Roof #3	214	LF	6	\$4,560	
	Parapet - Parapet > 30"	Roof #3	35	LF	6	\$2,237	
	Roof Structure - Steel with Clay Tile Arch	Roof #1	21,364	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #2	8,045	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #3	14,658	SF	7	\$0	
	Roof Structure - Steel with Clay Tile Arch	Roof #4	3,890	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Roof #2	8,045	SF	6	\$81,796	
	Roof - Asphalt Gravel Ballast	Roof #3	14,209	SF	5	\$335,465	
	Roof - Asphalt Gravel Ballast	Roof #4	200	SF	5	\$4,722	Vegetation Growth/ Active leak
	Roof - Asphalt Shingle	Roof #1	21,364	SF	6	\$98,067	
	Roof - Metal	Roof #3	450	SF	6	\$6,030	
	Roof - Metal	Roof #4	2,750	SF	6	\$36,848	
	Roof - Modified Bitumen	Roof #4	325	SF	6	\$3,058	
Walls							
	Exterior Walls - Brick	Entire Building	80,933	SF	6	\$543,951	Efflorecence/ Moss at North Facade & Auditorium
	Exterior Walls - Prefabricated Metal Panel Wall	Entire Building	432	SF	6	\$2,453	
	Exterior Walls - Terra Cotta	Entire Building	3,009	SF	6	\$20,223	
Windows							
	Guard - Guards perforated	Entire Building	5,360	SF	6	\$68,447	
	Lintels - Brick	Entire Building	60	LF	6	\$0	
	Lintels - Steel	Entire Building	10	LF	6	\$290	
	Lintels - Terra Cotta	Entire Building	1,826	LF	6	\$0	
	Skylite - Glass Double-Pane	Entire Building	1,316	SF	6	\$31,446	
	Windows - Decorative	Entire Building	400	SF	6	\$2,986	
	Windows - Sash Aluminum Double-pane	Entire Building	14,764	SF	6	\$110,207	
	Windows - Sash Aluminum Double-pane	Entire Building	1,476	SF	5	\$79,509	10% Broken Balances

**Building Exterior Subtotal:**

**\$1,867,121**

## Building: Main

## Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	2	EA	6	\$816	
	Emergency A/C Power - Auditorium and Aisle Lighting	Entire Building / 1st Floor	5,900	SF	6	\$3,122	
	Emergency A/C Power - Corridors and Stairs	Entire Building	31,550	SF	6	\$9,474	
	Emergency A/C Power - Lunchrooms	Entire Building / 1st Floor	3,260	SF	6	\$1,212	
	Emergency A/C Power - Students Toilets	Entire Building	2,299	SF	6	\$855	
	Emergency Battery Packs - Auditorium and Aisle Lighting	Entire Building / 1st Floor	2	EA	6	\$405	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	12	EA	6	\$2,430	school also has a diesel AC generator
	Exit Signs - Auditorium	Entire Building / 1st Floor	5	EA	6	\$749	
	Exit Signs - Corridors and Stairs	Entire Building	48	EA	6	\$7,188	
	Exit Signs - Corridors and Stairs	Entire Building	2	EA	4	\$1,091	
	Exit Signs - Lunchroom	Entire Building / 2nd Floor	4	EA	6	\$599	
	Security System - CCTV	Entire Building	158,545	SF	6	\$47,611	
	Security System - Intrusion Detection	Entire Building	158,545	SF	6	\$40,809	
	UPS - Less than 30 KW	Electrical Room / 1st Floor	2	EA	6	\$15,772	1000W
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	serves additions
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	1	EA	6	\$8,232	
	PA System	Entire Building	158,545	SF	5	\$108,825	serves all buildings, can connect to building 4.
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	6	\$497	
	Lighting and Power Panels - Above 100 A	Entire Building	8	EA	6	\$3,976	
	Lighting and Power Panels - Above 100 A	Entire Building	5	EA	6	\$2,485	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	2	EA	6	\$1,055	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	

**Electrical System Subtotal:**
**\$260,952**

## Building: Main

## Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Strobe Lights	Entire Building	158,545	SF	6	\$56,680	
	Fire Alarm_System	Entire Building	158,545	SF	6	\$77,085	served by fire alarm panel in addition 1

**Safty System Subtotal:**
**\$133,764**

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Condensing Unit- Roof Mounted - Less than 5 tons	Roof	3	EA	6	\$10,001	21000 Btu/hr, 2011
	Heat Pump- Floor Mounted- Electric Heating & DX Cooling- Remote Mounted Compressor - Less than 3 tons	Roof	1	EA	6	\$1,405	serves MDF room, evaporator in MDF room
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$95,595	
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$95,595	
	Air Intake	Mechanical Room / Roof	1	EA	5	\$7,471	
	Air Intake	Mechanical Room / Roof	1	EA	5	\$7,471	
	Auxiliaries - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$18,883	
	Auxiliaries - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$18,883	
	Indoor Return Fans- Centrifugal Inline - Less than 5000 CFM	4th Floor	1	EA	6	\$1,282	
	Make Up Air Unit- Indoor Mounted- Gas Heating Coils - Less than 6000 cfm	Attic	1	EA	6	\$3,350	
	Make Up Air Unit- Roof Mounted- Gas Heating - Less than 6000 cfm	Lower Roof	1	EA	5	\$22,527	located on roof between addition 4 and main building
	Outdoor Return Fans- Air Handling Unit Type - Less than 5000 CFM	Roof	2	EA	6	\$2,564	serve RTU-1, RTU-2, fourth floor.
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	5	\$96,198	5 is not a selectable option
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	100	LF	5	\$96,198	5 is not a selectable option
	Roof Top Unit-Multi Zone-Roof Mounted- Electric and DX Cooling w/ Self Contained Compressor - 10 - 20 tons	Roof	2	EA	6	\$5,583	services 4'th floor, east and west, 2 rooms per unit, long ducts
	Zone Dampers	Mechanical Room	5	EA	5	\$9,568	
	Zone Dampers	Mechanical Room	30	EA	5	\$57,406	
	Zone Dampers	Mechanical Room	30	EA	5	\$57,406	
<b>Boiler Systems</b>							
	Condensate Pump	Entire Building / Mechanical Room	2	EA	5	\$36,392	near AHU-1 & AHU-2 steam traps
	Piping - Condensate Pipe- Steel	Entire Building	500	LF	6	\$944	
	Piping - Steam Pipe- Steel	Entire Building	500	LF	6	\$944	fed by boiler in addition 1 building
	Steam Traps	Entire Building	48	EA	5	\$63,115	
<b>Heating Devices</b>							
	Radiators - Steam	Entire Building	25	EA	5	\$41,883	
	Unit Heater - Steam	Boiler Room / Mechanical Room	2	EA	6	\$556	
<b>Temperature Control</b>							
	Pneumatic System	Entire Building	158,545	SF	4	\$825,258	no BAS
	Thermostats - Pneumatic	Entire Building	75	EA	6	\$0	
	Thermostats - Pneumatic	Entire Building	15	EA	4	\$11,059	

**Building: Main**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Temperature Control</b>							
<b>Ventilation</b>							
	Exhaust Fans- Indoor - 500 - 1500 CFM	Entire Building / Attic	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Entire Building / Roof	1	EA	6	\$592	corroded
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	1	EA	4	\$4,245	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	6	\$592	
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	6	\$592	
	Lab Exhaust Hood	Entire Building	6	EA	6	\$7,486	
	Roof Mounted Duct Work	Entire Building / Roof	80	LF	6	\$30,322	
	Type II Exhaust Hood- Warming Kitchen	Entire Building / 1st Floor	1	EA	6	\$920	above serving line

**Mechanical System Subtotal:**
**\$1,634,653**
**Building: Main**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	158,545	SF	6	\$31,741	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	158,545	SF	6	\$38,542	
	Domestic Piping-Cold Water Risers	Entire Building	158,545	SF	6	\$29,474	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	158,545	SF	6	\$24,939	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	158,545	SF	6	\$29,474	
	Domestic Piping-Hot Water Return Lines	Entire Building	158,545	SF	6	\$22,672	
	Domestic Piping-Hot Water Return Risers	Entire Building	158,545	SF	6	\$22,672	
	Sanitary Piping	Entire Building	158,545	SF	6	\$145,100	
	Storm Piping	Entire Building	158,545	SF	6	\$138,299	
	Vent Piping	Entire Building	158,545	SF	6	\$106,558	
<b>Pumps</b>							
	Pumps - Ejector-Simplex	Entire Building / Mechanical Room	1	EA	4	\$11,443	
	Pumps - Sump-Simplex	Entire Building / 1st Floor	1	EA	6	\$745	

**Plumbing System Subtotal:**
**\$601,659**
**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #100 (Art Room)</b>							
	AC Units		1	EA	7	\$0	
	Casework		70	LF	6	\$1,768	
	Ceiling - Exposed		1,215	SF	6	\$1,807	
	Doors - Wood Doors inclu hw		3	EA	6	\$903	
	Floor - Concrete		1,215	SF	6	\$643	
	Lighting - Pendent/Surface		31	EA	6	\$3,841	
	Walls - Masonry		2,430	SF	6	\$7,645	
	Walls - Plaster/Drywall		640	SF	6	\$1,766	
	Work Sink		1	EA	6	\$379	
<b>Classroom #101 (Other Instructional Use)</b>							
	Casework		40	LF	6	\$1,010	
	Ceiling - Exposed		1,330	SF	6	\$1,978	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Concrete		1,330	SF	6	\$704	
	Lighting - Lay-in		24	EA	6	\$2,855	
	Marker Board		16	LF	7	\$0	
	Storage/ Closet		186	SF	6	\$1,349	
	Walls - Masonry		2,160	SF	6	\$6,795	
	Walls - Plaster/Drywall		380	SF	6	\$1,049	
	Work Sink		1	EA	6	\$379	
<b>Classroom #102 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		4	LF	7	\$0	
	Ceiling - Lay-in		848	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile		848	SF	6	\$1,855	
	Lighting - Lay-in		1	EA	6	\$119	
	Lighting - Lay-in		13	EA	7	\$0	
	Marker Board		12	LF	7	\$0	
	Walls - Plaster/Drywall		60	SF	5	\$306	Water damage
	Walls - Plaster/Drywall		868	SF	7	\$0	
<b>Classroom #106 (Physical Education Room)</b>							
	Ceiling - Plaster/Drywall		1,465	SF	6	\$5,070	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting		1,465	SF	6	\$7,668	
	Lighting - Lay-in		22	EA	6	\$2,617	
	Walls - Masonry		2,905	SF	6	\$9,139	
	Walls - Plaster/Drywall		215	SF	6	\$593	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #107 (Physical Education Room)</b>							
	AC Units		1	EA	7	\$0	
	Ceiling - Exposed		385	SF	6	\$573	
	Ceiling - Splined		1,565	SF	6	\$1,276	
	Doors - Wood Doors inclu hw		4	EA	6	\$1,204	
	Floor - Weight/ Fitness Room Floor Matting		1,950	SF	6	\$10,206	
	Lighting - Pendent/Surface		20	EA	6	\$2,478	
	Walls - Plaster/Drywall		2,550	SF	6	\$7,038	
<b>Classroom #201 (Computer Lab)</b>							
	AC Units		1	EA	7	\$0	
	Ceiling - Lay-in		895	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile		895	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		1,106	SF	7	\$0	
	Wireless System		1	EA	7	\$0	
<b>Classroom #201A (Computer Lab)</b>							
	AC Units		2	EA	7	\$0	
	Casework		12	LF	7	\$0	
	Ceiling - Lay-in		895	SF	7	\$0	
	Charging Station		3	EA	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		895	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		1,106	SF	7	\$0	
	Wireless System		1	EA	7	\$0	likely to be more data and electrical outlets
<b>Classroom #202 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	32	LF	7	\$0	
	Ceiling - Lay-in	2nd Floor	895	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	7	\$0	
	Floor - Tile	2nd Floor	895	SF	6	\$1,958	
	Lighting - Lay-in	2nd Floor	2	EA	6	\$238	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	100	LF	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #202 (Regular Classroom)</b>							
	Walls - Plaster/Drywall	2nd Floor	1,106	SF	7	\$0	
<b>Classroom #204 (Regular Classroom)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Casework	2nd Floor	10	LF	6	\$253	
	Ceiling - Lay-in	2nd Floor	848	SF	7	\$0	
	Chalk Board	2nd Floor	4	LF	4	\$367	Remove/replace with marker board
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	848	SF	6	\$1,855	
	Lighting - Lay-in	2nd Floor	14	EA	7	\$0	
	Marker Board	2nd Floor	12	LF	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	6	SF	6	\$23	
	Walls - Plaster/Drywall	2nd Floor	922	SF	7	\$0	
<b>Classroom #205 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		50	LF	7	\$0	
	Ceiling - Lay-in		24	SF	5	\$192	Water damage
	Ceiling - Lay-in		809	SF	7	\$0	
	Ceiling - Plaster/Drywall		21	SF	7	\$0	
	Ceiling - Plaster/Drywall		3	SF	5	\$32	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile		857	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		20	LF	7	\$0	
	Walls - Plaster/Drywall		1,200	SF	7	\$0	
	Work Sink		1	EA	7	\$0	
<b>Classroom #205A (Science Lab Level 3)</b>							
	AC Units		1	EA	7	\$0	
	Casework		20	LF	7	\$0	
	Ceiling - Lay-in		857	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		857	SF	7	\$0	
	Gas Line		1	EA	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Science Lab Elements		15	SF	7	\$0	
	Walls - Plaster/Drywall		12	SF	6	\$46	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #205A (Science Lab Level 3)</b>							
	Walls - Plaster/Drywall		1,124	SF	7	\$0	
	Work Sink		1	EA	6	\$379	Missing lever
<b>Classroom #206 (Science Lab Level 1)</b>							
	AC Units		1	EA	6	\$496	
	Casework		40	LF	7	\$0	
	Ceiling - Lay-in		1,015	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Eye Wash Station		1	EA	7	\$0	
	Floor - Tile/Sheet		1,015	SF	7	\$0	
	Fume Hood		1	EA	7	\$0	
	Gas Line		20	EA	7	\$0	
	Lighting - Lay-in		15	EA	7	\$0	
	Marker Board		8	LF	7	\$0	
	Science Lab Elements		155	SF	7	\$0	
	Science Lab Shower		1	EA	7	\$0	
	Walls - Plaster/Drywall		4	SF	6	\$15	
	Walls - Plaster/Drywall		1,294	SF	7	\$0	
	Work Sink		10	EA	7	\$0	
<b>Classroom #207 (Library)</b>							
	Ceiling - Lay-in		2,670	SF	7	\$0	
	Doors - Wood Doors inclu hw		2	EA	7	\$0	
	Floor - Carpet		2,670	SF	7	\$0	
	Lighting - Pendent/Surface		27	EA	7	\$0	
	Walls - Plaster/Drywall		2,860	SF	7	\$0	
<b>Classroom #210 (Computer Lab)</b>							
	AC Units		2	EA	7	\$0	
	Casework		8	LF	7	\$0	
	Ceiling - Lay-in		892	SF	7	\$0	
	Chalk Board		5	LF	4	\$459	Remove/replace with marker board
	Charging Station		1	EA	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile		892	SF	7	\$0	
	Lighting - Lay-in		12	EA	7	\$0	
	Marker Board		95	LF	7	\$0	
	Walls - Plaster/Drywall		30	SF	5	\$153	Water damage
	Walls - Plaster/Drywall		1,076	SF	7	\$0	

**Building: Main**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #210 (Computer Lab)</b>							
	Wireless System		1	EA	7	\$0	
<b>Classroom #211 (Science Lab Level 3)</b>							
	AC Units		1	EA	7	\$0	
	Casework		90	LF	7	\$0	
	Ceiling - Lay-in		8	SF	5	\$64	1 missing tile
	Ceiling - Lay-in		32	SF	6	\$133	
	Ceiling - Lay-in		975	SF	7	\$0	
	Doors - Steel Doors incl hw		1	EA	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		1,015	SF	7	\$0	
	Lighting - Lay-in		21	EA	7	\$0	3 lights located in storage room
	Marker Board		12	LF	7	\$0	
	Science Lab Elements		20	SF	7	\$0	
	Storage/ Closet		205	SF	7	\$0	
	Walls - Plaster/Drywall		1,298	SF	7	\$0	
	Work Sink		4	EA	7	\$0	One sink located in storage room
<b>Classroom #212 (Computer Lab)</b>							
	AC Units		1	EA	7	\$0	
	Casework		12	LF	7	\$0	
	Ceiling - Lay-in		868	SF	7	\$0	
	Ceiling - Plaster/Drywall		16	SF	7	\$0	
	Ceiling - Plaster/Drywall		8	SF	6	\$33	Water damage
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile		892	SF	6	\$1,952	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		100	LF	7	\$0	
	Walls - Plaster/Drywall		60	SF	6	\$232	Water damage
	Walls - Plaster/Drywall		1,078	SF	7	\$0	
	Wireless System		1	EA	7	\$0	
<b>Classroom #213 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		8	LF	5	\$1,673	
	Ceiling - Lay-in		848	SF	7	\$0	
	Doors - Steel Doors incl hw		1	EA	7	\$0	
	Floor - Wood		848	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #213 (Regular Classroom)</b>							
	Marker Board		15	LF	7	\$0	
	Walls - Plaster/Drywall		10	SF	6	\$39	
	Walls - Plaster/Drywall		918	SF	7	\$0	
	Work Sink		1	EA	6	\$379	
<b>Classroom #214 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		5	LF	6	\$126	
	Ceiling - Lay-in		24	SF	5	\$143	
	Ceiling - Plaster/Drywall		551	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		575	SF	6	\$4,054	
	Lighting - Lay-in		8	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		910	SF	7	\$0	
<b>Classroom #215 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	7	\$0	
	Ceiling - Lay-in		32	SF	5	\$255	
	Ceiling - Lay-in		813	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		845	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		1,240	SF	7	\$0	
<b>Classroom #216 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		845	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		845	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		12	SF	6	\$46	
	Walls - Plaster/Drywall		1,228	SF	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #217 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		845	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		845	SF	7	\$0	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		1,240	SF	7	\$0	
<b>Classroom #285A (Office)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Ceiling - Lay-in	2nd Floor	496	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	496	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	4	EA	6	\$476	
	Walls - Plaster/Drywall	2nd Floor	708	SF	7	\$0	
<b>Classroom #285B (Office)</b>							
	AC Units	2nd Floor	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	2nd Floor	308	SF	7	\$0	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Floor - Tile	2nd Floor	308	SF	7	\$0	
	Lighting - Lay-in	2nd Floor	2	EA	7	\$0	
	Walls - Plaster/Drywall	2nd Floor	886	SF	7	\$0	
	Work Sink	2nd Floor	1	EA	6	\$379	
<b>Classroom #300A (Multi Purpose Room)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		960	SF	6	\$2,883	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile		960	SF	6	\$2,100	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Marker Board		20	LF	7	\$0	
	Walls - Plaster/Drywall		1,270	SF	6	\$3,505	
	Work Sink		1	EA	6	\$379	
<b>Classroom #300G (Multi Purpose Room)</b>							
	AC Units		1	EA	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #300G (Multi Purpose Room)</b>							
	Ceiling - Plaster/Drywall		415	SF	6	\$1,436	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Carpet		415	SF	6	\$884	
	Lighting - Pendent/Surface		2	EA	7	\$0	
	Storage/ Closet		15	SF	6	\$109	
	Walls - Plaster/Drywall		1,100	SF	6	\$3,036	
<b>Classroom #301 (Regular Classroom)</b>							
	AC Units		1	EA	6	\$496	
	Casework		30	LF	6	\$758	
	Ceiling - Lay-in		800	SF	6	\$2,402	
	Chalk Board		4	LF	4	\$367	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		800	SF	6	\$5,640	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Marker Board		20	LF	7	\$0	
	Walls - Plaster/Drywall		1,206	SF	6	\$3,328	
	Work Sink		1	EA	6	\$379	
<b>Classroom #302 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		25	LF	6	\$631	
	Ceiling - Lay-in		800	SF	6	\$2,402	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		800	SF	6	\$5,640	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Marker Board		40	LF	7	\$0	
	Storage/ Closet		75	SF	6	\$544	
	Walls - Plaster/Drywall		12	SF	5	\$61	
	Walls - Plaster/Drywall		1,996	SF	6	\$5,509	
	Work Sink		1	EA	6	\$379	
<b>Classroom #302A (Store Room)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Ceiling - Lay-in	3rd Floor	336	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	7	\$0	
	Floor - Wood	3rd Floor	336	SF	6	\$2,369	
	Lighting - Lay-in	3rd Floor	4	EA	6	\$476	
	Storage/ Closet	3rd Floor	15	SF	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #302A (Store Room)</b>							
	Walls - Plaster/Drywall	3rd Floor	694	SF	6	\$1,915	
<b>Classroom #303 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		892	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		892	SF	6	\$6,289	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		50	LF	7	\$0	
	Walls - Plaster/Drywall		1,206	SF	6	\$3,328	
<b>Classroom #304 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	6	LF	6	\$152	
	Ceiling - Lay-in	3rd Floor	848	SF	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	7	\$0	
	Floor - Wood	3rd Floor	848	SF	6	\$5,978	
	Lighting - Lay-in	3rd Floor	14	EA	7	\$0	
	Marker Board	3rd Floor	8	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	928	SF	7	\$0	
<b>Classroom #305 (Regular Classroom)</b>							
	Casework		2	LF	6	\$51	
	Ceiling - Lay-in		892	SF	7	\$0	
	Chalk Board		60	LF	4	\$5,508	Remove/replace with marker board
	Doors - Steel Doors incl hw		1	EA	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		892	SF	6	\$6,289	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		60	LF	7	\$0	
	Walls - Plaster/Drywall		1,138	SF	7	\$0	
<b>Classroom #306 (Science Lab Level 1)</b>							
	AC Units		1	EA	7	\$0	
	Casework		115	LF	7	\$0	
	Ceiling - Lay-in		1,440	SF	7	\$0	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Eye Wash Station		1	EA	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #306 (Science Lab Level 1)</b>							
	Floor - Tile/Sheet		1,440	SF	7	\$0	
	Fume Hood		1	EA	6	\$816	
	Gas Line		30	EA	7	\$0	
	Lighting - Lay-in		18	EA	7	\$0	
	Marker Board		6	LF	7	\$0	
	Science Lab Elements		170	SF	7	\$0	
	Science Lab Shower		1	EA	7	\$0	
	Walls - Plaster/Drywall		1,598	SF	7	\$0	
	Work Sink		10	EA	7	\$0	
<b>Classroom #307 (Science Lab Level 3)</b>							
	AC Units		1	EA	7	\$0	
	Casework		80	LF	6	\$2,020	
	Ceiling - Lay-in		1,128	SF	6	\$3,387	
	Doors - Steel Doors incl hw		1	EA	7	\$0	307A
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile/Sheet		1,128	SF	7	\$0	
	Fume Hood		1	EA	6	\$816	
	Gas Line		1	EA	7	\$0	
	Lighting - Lay-in		24	EA	6	\$2,855	
	Marker Board		12	LF	7	\$0	
	Science Lab Elements		80	SF	7	\$0	
	Storage/ Closet		113	SF	6	\$819	307A
	Walls - Plaster/Drywall		1,346	SF	6	\$3,715	
	Work Sink		2	EA	6	\$758	
<b>Classroom #308 (Science Lab Level 3)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	100	LF	6	\$2,525	
	Ceiling - Lay-in	3rd Floor	1,159	SF	6	\$3,480	
	Chalk Board	3rd Floor	18	LF	4	\$1,653	Remove/replace with marker board
	Doors - Steel Doors incl hw	3rd Floor	2	EA	7	\$0	
	Eye Wash Station	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	1,159	SF	6	\$2,536	
	Fume Hood	3rd Floor	1	EA	7	\$0	
	Gas Line	3rd Floor	1	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	24	EA	6	\$2,855	
	Marker Board	3rd Floor	18	LF	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #308 (Science Lab Level 3)</b>							
	Science Lab Elements	3rd Floor	15	SF	7	\$0	
	Science Lab Shower	3rd Floor	1	EA	7	\$0	
	Storage/ Closet	3rd Floor	84	SF	7	\$0	308A
	Walls - Plaster/Drywall	3rd Floor	1,350	SF	6	\$3,726	
	Work Sink	3rd Floor	3	EA	6	\$1,137	
<b>Classroom #309 (Regular Classroom)</b>							
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		892	SF	6	\$2,679	
	Doors - Steel Doors incl hw		1	EA	7	\$0	
	Floor - Wood		892	SF	6	\$6,289	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		50	LF	7	\$0	
	Walls - Plaster/Drywall		9	SF	5	\$46	
	Walls - Plaster/Drywall		1,129	SF	6	\$3,116	
<b>Classroom #310 (Science Lab Level 1)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	15	LF	6	\$379	
	Ceiling - Lay-in	3rd Floor	1,015	SF	6	\$3,048	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	7	\$0	
	Doors - Wood Doors inclu hw	3rd Floor	2	EA	6	\$602	
	Eye Wash Station	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	1,015	SF	6	\$2,221	
	Fume Hood	3rd Floor	1	EA	6	\$816	
	Gas Line	3rd Floor	10	EA	7	\$0	
	Lighting - Lay-in	3rd Floor	16	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Science Lab Elements	3rd Floor	60	SF	6	\$407	
	Science Lab Shower	3rd Floor	1	EA	7	\$0	
	Storage/ Closet	3rd Floor	267	SF	6	\$1,936	310B
	Walls - Plaster/Drywall	3rd Floor	1,598	SF	6	\$4,410	
	Work Sink	3rd Floor	10	EA	6	\$3,790	
<b>Classroom #311 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		872	SF	6	\$2,619	
	Ceiling - Plaster/Drywall		10	SF	5	\$108	Water damage

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #311 (Regular Classroom)</b>							
	Ceiling - Plaster/Drywall		22	SF	6	\$76	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile		892	SF	6	\$1,952	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Marker Board		50	LF	7	\$0	
	Walls - Plaster/Drywall		40	SF	5	\$204	
	Walls - Plaster/Drywall		1,108	SF	6	\$3,058	
<b>Classroom #313 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		8	LF	6	\$202	
	Ceiling - Plaster/Drywall		895	SF	6	\$3,097	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		895	SF	6	\$6,310	
	Lighting - Pendent/Surface		14	EA	6	\$1,735	
	Marker Board		20	LF	7	\$0	
	Walls - Plaster/Drywall		1,190	SF	6	\$3,284	
<b>Classroom #314 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		15	LF	6	\$379	
	Ceiling - Plaster/Drywall		575	SF	6	\$1,990	
	Chalk Board		20	LF	4	\$1,836	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile		575	SF	6	\$1,258	
	Lighting - Lay-in		8	EA	7	\$0	
	Marker Board		8	LF	7	\$0	
	Walls - Plaster/Drywall		910	SF	6	\$2,512	20 SF cracks
<b>Classroom #315 (Store Room)</b>							
	AC Units		1	EA	7	\$0	
	Casework		15	LF	6	\$379	
	Ceiling - Lay-in		845	SF	6	\$2,538	
	Chalk Board		20	LF	4	\$1,836	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Tile		845	SF	6	\$1,849	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Lighting - Wall Mounted		1	EA	6	\$124	above work sink
	Marker Board		10	LF	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #315 (Store Room)</b>							
	Walls - Plaster/Drywall		16	SF	5	\$82	
	Walls - Plaster/Drywall		1,224	SF	6	\$3,378	
	Work Sink		1	EA	6	\$379	
<b>Classroom #316 (Regular Classroom)</b>							
	AC Units	3rd Floor	1	EA	7	\$0	
	Casework	3rd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	3rd Floor	845	SF	6	\$2,538	
	Chalk Board	3rd Floor	3	LF	4	\$275	Remove/replace with marker board
	Doors - Wood Doors inclu hw	3rd Floor	1	EA	7	\$0	
	Floor - Tile	3rd Floor	845	SF	6	\$1,849	
	Lighting - Lay-in	3rd Floor	14	EA	6	\$1,666	
	Marker Board	3rd Floor	40	LF	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,240	SF	6	\$3,422	
	Work Sink	3rd Floor	1	EA	6	\$379	
<b>Classroom #317 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		20	LF	6	\$505	
	Ceiling - Lay-in		845	SF	6	\$2,538	
	Doors - Wood Doors inclu hw		1	EA	7	\$0	
	Floor - Wood		845	SF	6	\$5,957	
	Lighting - Lay-in		14	EA	6	\$1,666	
	Marker Board		30	LF	7	\$0	
	Walls - Plaster/Drywall		8	SF	5	\$41	
	Walls - Plaster/Drywall		1,232	SF	6	\$3,400	
<b>Classroom #384A (Laboratory/Shop)</b>							
	Casework		20	LF	6	\$505	
	Ceiling - Plaster/Drywall		263	SF	6	\$910	
	Chalk Board		5	LF	4	\$459	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile		263	SF	6	\$575	
	Lighting - Pendent/Surface		3	EA	6	\$372	
	Walls - Plaster/Drywall		630	SF	6	\$1,739	
<b>Classroom #384B (Office)</b>							
	Casework		30	LF	6	\$758	
	Ceiling - Plaster/Drywall		263	SF	6	\$910	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #384B (Office)</b>							
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		263	SF	6	\$1,854	
	Lighting - Pendent/Surface		2	EA	7	\$0	
	Walls - Plaster/Drywall		630	SF	6	\$1,739	
<b>Classroom #400 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		892	SF	6	\$2,679	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		892	SF	6	\$6,289	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		50	LF	7	\$0	
	Walls - Plaster/Drywall		25	SF	6	\$97	Paint
	Walls - Plaster/Drywall		1,181	SF	7	\$0	
<b>Classroom #401 (Regular Classroom)</b>							
	Casework		44	LF	6	\$1,111	
	Ceiling - Plaster/Drywall		50	SF	5	\$625	
	Ceiling - Plaster/Drywall		845	SF	6	\$2,924	
	Chalk Board		4	LF	4	\$367	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		895	SF	6	\$6,310	
	Lighting - Pendent/Surface		21	EA	7	\$0	
	Marker Board		8	LF	7	\$0	
	Walls - Plaster/Drywall		1,190	SF	6	\$3,284	
	Work Sink		1	EA	5	\$1,508	
<b>Classroom #402 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		15	LF	6	\$379	
	Ceiling - Lay-in		50	SF	5	\$399	
	Ceiling - Lay-in		842	SF	6	\$2,529	
	Chalk Board		4	LF	4	\$367	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		892	SF	6	\$6,289	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		50	LF	7	\$0	
	Walls - Plaster/Drywall		1,138	SF	6	\$3,141	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #402 (Regular Classroom)</b>							
<b>Classroom #403 (Other Instructional Use)</b>							
	Casework		33	LF	6	\$833	
	Ceiling - Plaster/Drywall		100	SF	5	\$1,075	Water damage
	Ceiling - Plaster/Drywall		795	SF	6	\$2,751	
	Doors - Wood Doors inclu hw		2	EA	6	\$602	
	Floor - Wood		895	SF	6	\$6,310	
	Lighting - Pendent/Surface		21	EA	7	\$0	
	Marker Board		6	LF	7	\$0	
	Walls - Plaster/Drywall		1,190	SF	6	\$3,284	
	Work Sink		1	EA	7	\$0	
<b>Classroom #404 (Other Instructional Use)</b>							
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		595	SF	6	\$1,787	
	Chalk Board		4	LF	4	\$367	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		595	SF	6	\$4,195	
	Lighting - Lay-in		12	EA	7	\$0	
	Marker Board		10	LF	7	\$0	
	Walls - Plaster/Drywall		930	SF	6	\$2,567	
	Work Sink		1	EA	5	\$1,508	
<b>Classroom #405 (Art Room)</b>							
	AC Units		1	EA	7	\$0	
	Casework		40	LF	6	\$1,010	
	Ceiling - Lay-in		895	SF	6	\$2,688	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		895	SF	6	\$6,310	
	Lighting - Lay-in		21	EA	7	\$0	
	Marker Board		30	LF	7	\$0	
	Walls - Plaster/Drywall		1,190	SF	6	\$3,284	
	Work Sink		1	EA	6	\$379	
<b>Classroom #406 (Regular Classroom)</b>							
	AC Units		2	EA	7	\$0	
	Casework		26	LF	6	\$657	
	Ceiling - Lay-in		25	SF	5	\$199	
	Ceiling - Lay-in		1,370	SF	6	\$4,114	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #406 (Regular Classroom)</b>							
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		1,395	SF	6	\$9,835	
	Lighting - Lay-in		27	EA	6	\$3,212	
	Marker Board		30	LF	7	\$0	
	Walls - Plaster/Drywall		150	SF	5	\$766	
	Walls - Plaster/Drywall		1,470	SF	6	\$4,057	
<b>Classroom #407 (Regular Classroom)</b>							
	Casework		44	LF	6	\$1,111	
	Ceiling - Plaster/Drywall		100	SF	5	\$1,075	
	Ceiling - Plaster/Drywall		795	SF	6	\$2,751	The ceiling contains approximaltety 700 sf of sky light which is "6"
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		895	SF	6	\$6,310	
	Lighting - Pendent/Surface		21	EA	6	\$2,602	
	Marker Board		40	LF	7	\$0	
	Walls - Plaster/Drywall		1,190	SF	6	\$3,284	
<b>Classroom #408 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		15	LF	6	\$379	
	Ceiling - Lay-in		842	SF	6	\$2,529	
	Ceiling - Plaster/Drywall		50	SF	6	\$173	
	Chalk Board		16	LF	4	\$1,469	Remove/replace with marker board
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		892	SF	6	\$6,289	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		34	LF	7	\$0	
	Walls - Plaster/Drywall		5	SF	6	\$19	
	Walls - Plaster/Drywall		1,133	SF	7	\$0	
<b>Classroom #409 (Regular Classroom)</b>							
	Casework		44	LF	6	\$1,111	
	Ceiling - Plaster/Drywall		80	SF	5	\$1,000	
	Ceiling - Plaster/Drywall		815	SF	6	\$2,820	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Wood		895	SF	6	\$6,310	
	Lighting - Pendent/Surface		21	EA	6	\$2,602	
	Marker Board		12	LF	7	\$0	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #409 (Regular Classroom)</b>							
	Walls - Plaster/Drywall		1,190	SF	6	\$3,284	
	Work Sink		1	EA	6	\$379	
<b>Classroom #410 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		10	LF	6	\$253	
	Ceiling - Lay-in		842	SF	6	\$2,529	
	Ceiling - Plaster/Drywall		5	SF	5	\$62	Water damage
	Ceiling - Plaster/Drywall		45	SF	6	\$156	
	Doors - Wood Doors inclu hw		1	EA	6	\$301	
	Floor - Tile/Sheet		3	SF	4	\$44	3 tiles missing
	Floor - Tile/Sheet		889	SF	6	\$890	
	Lighting - Lay-in		14	EA	7	\$0	
	Marker Board		100	LF	7	\$0	
	Walls - Plaster/Drywall		20	SF	5	\$102	Water damage
	Walls - Plaster/Drywall		1,118	SF	6	\$3,086	
<b>Classroom #440 (Regular Classroom)</b>							
	AC Units		1	EA	7	\$0	
	Casework		30	LF	6	\$758	
	Ceiling - Lay-in		677	SF	6	\$2,033	
	Doors - Wood Doors inclu hw		1	EA	5	\$1,174	Cracked glass
	Floor - Wood		677	SF	6	\$4,773	
	Lighting - Lay-in		18	EA	7	\$0	
	Marker Board		16	LF	7	\$0	
	Walls - Plaster/Drywall		898	SF	6	\$2,478	
<b>Classroom #500 (Fitness Room)</b>							
	Ceiling - Plaster/Drywall	5th Floor	4,935	SF	6	\$17,078	
	Chalk Board	5th Floor	20	LF	4	\$1,836	Remove & Replace with marker board
	Doors - Wood Doors inclu hw	5th Floor	2	EA	6	\$602	
	Doors - Wood Doors inclu hw	5th Floor	2	EA	5	\$2,348	Inoperable hardware at stair 3
	Floor - Weight/ Fitness Room Floor Matting	5th Floor	1,625	SF	6	\$8,505	
	Floor - Wood	5th Floor	3,315	SF	6	\$23,370	
	Lighting - Pendent/Surface	5th Floor	36	EA	7	\$0	
	Storage/ Closet	5th Floor	715	SF	5	\$11,533	Accessed from stair 4
	Walls - Plaster/Drywall	5th Floor	3,360	SF	6	\$9,273	

## Building: Main

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classrooms Subtotal:</b>						<b>\$571,903</b>	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	103B	240	SF	7	\$0	
	Doors - Wood Doors inclu hw	103B	1	EA	7	\$0	
	Floor - Tile/Sheet	103B	240	SF	6	\$240	
	Lighting - Lay-in	103B	4	EA	7	\$0	
	Walls - Plaster/Drywall	103B	618	SF	7	\$0	
	AC Unit	104 Program Office/Main Office	1	EA	7	\$0	
	Ceiling - Lay-in	104 Program Office/Main Office	368	SF	7	\$0	
	Doors - Wood Doors inclu hw	104 Program Office/Main Office	1	EA	7	\$0	
	Floor - Tile	104 Program Office/Main Office	368	SF	7	\$0	
	Lighting - Lay-in	104 Program Office/Main Office	7	EA	7	\$0	
	Power Distribution	104 Program Office/Main Office	16	EA	7	\$0	
	Walls - Plaster/Drywall	104 Program Office/Main Office	672	SF	7	\$0	
	Ceiling - Lay-in	105A Counselor Reception	98	SF	7	\$0	
	Doors - Wood Doors inclu hw	105A Counselor Reception	1	EA	7	\$0	
	Floor - Tile	105A Counselor Reception	98	SF	7	\$0	
	Lighting - Lay-in	105A Counselor Reception	4	EA	7	\$0	
	Walls - Plaster/Drywall	105A Counselor Reception	329	SF	7	\$0	
	Ceiling - Lay-in	105B Dean Office	102	SF	7	\$0	
	Doors - Wood Doors inclu hw	105B Dean Office	1	EA	6	\$301	closet
	Doors - Wood Doors inclu hw	105B Dean Office	1	EA	7	\$0	
	Floor - Tile/Sheet	105B Dean Office	102	SF	7	\$0	
	Lighting - Lay-in	105B Dean Office	2	EA	7	\$0	
	Power Distribution	105B Dean Office	4	EA	7	\$0	
	Storage/ Closet	105B Dean Office	4	SF	7	\$0	
	Walls - Plaster/Drywall	105B Dean Office	324	SF	7	\$0	
	Ceiling - Lay-in	105C Counselor Office	102	SF	7	\$0	
	Doors - Wood Doors inclu hw	105C Counselor Office	1	EA	6	\$301	closet
	Doors - Wood Doors inclu hw	105C Counselor Office	1	EA	7	\$0	
	Floor - Tile	105C Counselor Office	102	SF	7	\$0	
	Lighting - Lay-in	105C Counselor Office	2	EA	7	\$0	
	Power Distribution	105C Counselor Office	4	EA	7	\$0	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Storage/ Closet	105C Counselor Office	6	SF	6	\$44	
	Walls - Plaster/Drywall	105C Counselor Office	324	SF	7	\$0	
	Ceiling - Lay-in	105	30	SF	7	\$0	
	Ceiling - Lay-in	105D Counselor Office	102	SF	7	\$0	
	Doors - Wood Doors inclu hw	105D Counselor Office	1	EA	7	\$0	
	Floor - Tile	105D Counselor Office	102	SF	7	\$0	
	Lighting - Lay-in	105D Counselor Office	2	EA	7	\$0	
	Power Distribution	105D Counselor Office	4	EA	7	\$0	
	Walls - Plaster/Drywall	105D Counselor Office	10	SF	4	\$147	water damage and cracking
	Walls - Plaster/Drywall	105D Counselor Office	314	SF	7	\$0	
	Doors - Wood Doors inclu hw	105	1	EA	7	\$0	
	Doors - Wood Doors inclu hw	105	1	EA	6	\$301	
	Ceiling - Lay-in	105E Counselor Office	102	SF	6	\$306	Ceiling is a 7; Window trim is held by duck tape
	Doors - Wood Doors inclu hw	105E Counselor Office	1	EA	6	\$301	closet
	Doors - Wood Doors inclu hw	105E Counselor Office	1	EA	7	\$0	
	Floor - Tile	105E Counselor Office	102	SF	7	\$0	
	Lighting - Lay-in	105E Counselor Office	2	EA	7	\$0	
	Power Distribution	105E Counselor Office	4	EA	7	\$0	
	Storage/ Closet	105E Counselor Office	6	SF	7	\$0	
	Walls - Plaster/Drywall	105E Counselor Office	5	SF	5	\$26	water damage
	Walls - Plaster/Drywall	105E Counselor Office	319	SF	7	\$0	
	Ceiling - Lay-in	105F Counselor Office	80	SF	7	\$0	
	Doors - Wood Doors inclu hw	105F Counselor Office	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	105F Counselor Office	1	EA	7	\$0	
	Floor - Tile	105F Counselor Office	80	SF	7	\$0	
	Lighting - Lay-in	105F Counselor Office	2	EA	7	\$0	
	Storage/ Closet	105F Counselor Office	6	SF	6	\$44	
	Walls - Plaster/Drywall	105F Counselor Office	326	SF	7	\$0	
	Floor - Tile	105	30	SF	7	\$0	
	Ceiling - Lay-in	105G Office	25	SF	7	\$0	
	Doors - Wood Doors inclu hw	105G Office	1	EA	7	\$0	
	Floor - Tile	105G Office	25	SF	7	\$0	
	Lighting - Lay-in	105G Office	1	EA	7	\$0	
	Walls - Plaster/Drywall	105G Office	196	SF	7	\$0	
	Ceiling - Lay-in	105H Office	25	SF	7	\$0	
	Doors - Wood Doors inclu hw	105H Office	1	EA	7	\$0	
	Floor - Tile	105H Office	25	SF	7	\$0	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Lighting - Lay-in	105H Office	1	EA	7	\$0	
	Walls - Plaster/Drywall	105H Office	196	SF	7	\$0	
	Lighting - Lay-in	105	2	EA	7	\$0	
	Power Distribution	105	2	EA	7	\$0	
	Walls - Plaster/Drywall	105	202	SF	7	\$0	
	Ceiling - Plaster/Drywall	111 "Principal Office" now conference room	2	SF	6	\$10	
	Ceiling - Plaster/Drywall	111 "Principal Office" now conference room	546	SF	7	\$0	
	Doors - Wood Doors inclu hw	111 "Principal Office" now conference room	3	EA	6	\$903	
	Floor - Tile	111 "Principal Office" now conference room	548	SF	6	\$1,199	
	Lighting - Lay-in	111 "Principal Office" now conference room	4	EA	7	\$0	
	Power Distribution	111 "Principal Office" now conference room	4	EA	7	\$0	
	Storage/ Closet	111 "Principal Office" now conference room	3	SF	7	\$0	
	Walls - Plaster/Drywall	111 "Principal Office" now conference room	30	SF	4	\$441	water damage
	Walls - Plaster/Drywall	111 "Principal Office" now conference room	954	SF	7	\$0	
	Ceiling - Lay-in	111A Community Room	1,088	SF	6	\$3,267	
	Doors - Wood Doors inclu hw	111A Community Room	4	EA	6	\$1,204	
	Floor - Carpet	111A Community Room	1,088	SF	6	\$2,318	
	Lighting - Lay-in	111A Community Room	19	EA	6	\$2,261	
	Power Distribution	111A Community Room	14	EA	6	\$29,748	
	Storage/ Closet	111A Community Room	200	SF	6	\$1,450	
	Walls - Plaster/Drywall	111A Community Room	1,094	SF	6	\$3,019	
	Ceiling - Lay-in	183A office suite	718	SF	7	\$0	
	Ceiling - Lay-in	183A office suite	8	SF	6	\$33	
	Doors - Wood Doors inclu hw	183A office suite	1	EA	7	\$0	
	Floor - Tile	183A office suite	726	SF	7	\$0	
	Lighting - Lay-in	183A office suite	14	EA	7	\$0	
	Power Distribution	183A office suite	1	EA	7	\$0	
	Walls - Plaster/Drywall	183A office suite	972	SF	7	\$0	
	AC Unit	183B	1	EA	7	\$0	
	Ceiling - Lay-in	183B	96	SF	7	\$0	
	Doors - Wood Doors inclu hw	183B	2	EA	6	\$602	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Floor - Tile	183B	96	SF	7	\$0	
	Lighting - Lay-in	183B	2	EA	7	\$0	
	Power Distribution	183B	6	EA	7	\$0	
	Storage/ Closet	183B	6	SF	7	\$0	
	Walls - Plaster/Drywall	183B	364	SF	7	\$0	
	Ceiling - Lay-in	183C Office	108	SF	7	\$0	
	Doors - Wood Doors inclu hw	183C Office	1	EA	6	\$301	closet
	Doors - Wood Doors inclu hw	183C Office	1	EA	7	\$0	
	Floor - Tile	183C Office	108	SF	7	\$0	
	Lighting - Lay-in	183C Office	2	EA	7	\$0	
	Power Distribution	183C Office	10	EA	7	\$0	
	Storage/ Closet	183C Office	6	SF	7	\$0	
	Walls - Plaster/Drywall	183C Office	366	SF	7	\$0	
	Walls - Plaster/Drywall	183C Office	20	SF	4	\$294	water damage
	Ceiling - Plaster/Drywall	183D Vault	144	SF	7	\$0	
	Doors - Steel Doors incl hw	183D Vault	1	EA	7	\$0	
	Floor - Tile	183D Vault	142	SF	7	\$0	
	Floor - Tile	183D Vault	2	SF	5	\$12	
	Lighting - Lay-in	183D Vault	2	EA	7	\$0	
	Walls - Plaster/Drywall	183D Vault	468	SF	7	\$0	
	AC Unit	206A Police Room	1	EA	7	\$0	
	Ceiling - Lay-in	206A Police Room	16	SF	5	\$128	
	Ceiling - Lay-in	206A Police Room	328	SF	7	\$0	
	Doors - Wood Doors inclu hw	206A Police Room	1	EA	6	\$301	
	Floor - Tile	206A Police Room	42	SF	5	\$207	
	Floor - Tile	206A Police Room	302	SF	7	\$0	
	Lighting - Lay-in	206A Police Room	4	EA	7	\$0	
	Power Distribution	206A Police Room	14	EA	7	\$0	
	Walls - Plaster/Drywall	206A Police Room	628	SF	7	\$0	
	Ceiling - Lay-in	207A Library Office	240	SF	7	\$0	
	Doors - Wood Doors inclu hw	207A Library Office	2	EA	7	\$0	
	Floor - Carpet	207A Library Office	240	SF	7	\$0	
	Lighting - Pendant/Surface	207A Library Office	2	EA	7	\$0	
	Power Distribution	207A Library Office	6	EA	7	\$0	
	Walls - Plaster/Drywall	207A Library Office	684	SF	7	\$0	
	Ceiling - Exposed	487/ former 400D	637	SF	5	\$1,749	peeling paint
	Doors - Wood Doors inclu hw	487/ former 400D	1	EA	6	\$301	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Floor - Tile/Sheet	487/ former 400D	637	SF	6	\$638	
	Lighting - Pendant/Surface	487/ former 400D	12	EA	6	\$1,487	
	Walls - Masonry	487/ former 400D	1,200	SF	5	\$49,592	peeling paint
	Ceiling - Plaster/Drywall	490	555	SF	6	\$1,921	
	Doors - Wood Doors inclu hw	490	1	EA	6	\$301	
	Floor - Tile/Sheet	490	555	SF	6	\$556	
	Lighting - Pendant/Surface	490	3	EA	7	\$0	
	Power Distribution	490	6	EA	7	\$0	
	Walls - Plaster/Drywall	490	1,281	SF	6	\$3,535	
	Ceiling - Lay-in	Asst principal's office - access through 104	252	SF	7	\$0	
	Doors - Wood Doors inclu hw	Asst principal's office - access through 104	1	EA	7	\$0	
	Floor - Tile	Asst principal's office - access through 104	252	SF	7	\$0	
	Lighting - Lay-in	Asst principal's office - access through 104	2	EA	7	\$0	
	Power Distribution	Asst principal's office - access through 104	8	EA	7	\$0	
	Walls - Plaster/Drywall	Asst principal's office - access through 104	510	SF	7	\$0	
	AC Unit	Business Office - accessed through 104	1	EA	7	\$0	
	Ceiling - Lay-in	Business Office - accessed through 104	252	SF	7	\$0	
	Ceiling - Lay-in	Business Office - accessed through 104	4	SF	5	\$32	
	Doors - Wood Doors inclu hw	Business Office - accessed through 104	1	EA	7	\$0	
	Floor - Tile	Business Office - accessed through 104	252	SF	7	\$0	
	Lighting - Lay-in	Business Office - accessed through 104	2	EA	7	\$0	
	Power Distribution	Business Office - accessed through 104	12	EA	7	\$0	
	Walls - Plaster/Drywall	Business Office - accessed through 104	510	SF	7	\$0	
	Ceiling - Lay-in	Lunch room manager's office	83	SF	6	\$249	
	Doors - Wood Doors inclu hw	Lunch room manager's office	2	EA	6	\$602	
	Floor - Concrete	Lunch room manager's office	83	SF	6	\$44	
	Lighting - Lay-in	Lunch room manager's office	1	EA	6	\$119	
	Power Distribution	Lunch room manager's office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Lunch room manager's office	291	SF	6	\$803	
	Ceiling - Lay-in	Principal's Office - accessed through 104, terminus of hallway	222	SF	7	\$0	
	Ceiling - Lay-in	Principal's Office - accessed through 104, terminus of hallway	32	SF	5	\$222	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Doors - Wood Doors inclu hw	Principal's Office - accessed through 104, terminus of hallway	1	EA	7	\$0	
	Floor - Tile	Principal's Office - accessed through 104, terminus of hallway	252	SF	7	\$0	
	Lighting - Lay-in	Principal's Office - accessed through 104, terminus of hallway	4	EA	7	\$0	
	Power Distribution	Principal's Office - accessed through 104, terminus of hallway	10	EA	7	\$0	
	Walls - Plaster/Drywall	Principal's Office - accessed through 104, terminus of hallway	510	SF	7	\$0	
<b>Auditorium &amp; Theater</b>							
	Balcony Seating	1st Floor	160	EA	6	\$27,827	
	Ceiling - Plaster/Drywall	1st Floor	5,938	SF	5	\$137,560	peeling throughout
	Doors - Wood Doors inclu hw	1st Floor	13	EA	6	\$3,913	
	Floor - Carpet	1st Floor	1,935	SF	6	\$4,123	
	Floor - Concrete Epoxy/ Painted	1st Floor	1,935	SF	6	\$1,024	
	Floor - Wood	1st Floor	1,023	SF	6	\$7,212	balcony floor
	Lighting - Metal Halide/Sodium Vapor	1st Floor	8	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	4	EA	7	\$0	2 are can lights
	Main Floor Seating	1st Floor	568	EA	6	\$98,785	
	Sound System	1st Floor	1	EA	6	\$10,721	
	Stage	1st Floor	1,207	SF	6	\$6,973	Wood Floor
	Stage Curtain	1st Floor	6	EA	6	\$0	
	Stage Lift	1st Floor	1	EA	6	\$6,510	
	Stage Lighting System	1st Floor	1	EA	6	\$8,077	
	Stage-Stairs - Wood	1st Floor	8	LF	6	\$94	
	Walls - Plaster/Drywall	1st Floor	10	SF	5	\$113	peeling
	Walls - Plaster/Drywall	1st Floor	5,958	SF	6	\$28,371	
	Walls - Structural Glazed Tile	1st Floor	5,968	SF	6	\$18,775	
<b>Kitchen</b>							
	Ceiling - Plaster/Drywall	1st Floor	850	SF	6	\$2,942	
	Doors - Wood Doors inclu hw	1st Floor	3	EA	6	\$903	
	Floor - Concrete	1st Floor	850	SF	6	\$450	
	Lighting - Pendent/Surface	1st Floor	20	EA	6	\$2,478	
	Serving Line	1st Floor	84	LF	6	\$4,999	
	Storage/ Closet	1st Floor	180	SF	6	\$1,305	
	Walls - Plaster/Drywall	1st Floor	1,222	SF	6	\$3,373	

## Building: Main

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Lay-in	Faculty lunchroom 1st floor	834	SF	5	\$4,961	
	Doors - Wood Doors inclu hw	Faculty lunchroom 1st floor	1	EA	6	\$301	
	Floor - Tile/Sheet	Faculty lunchroom 1st floor	834	SF	6	\$835	
	Lighting - Pendent/Surface	Faculty lunchroom 1st floor	12	EA	6	\$1,487	
	Walls - Plaster/Drywall	Faculty lunchroom 1st floor	932	SF	6	\$2,572	
	Ceiling - Lay-in	Lunch room #1 1st floor	4,066	SF	6	\$12,210	
	Doors - Wood Doors inclu hw	Lunch room #1 1st floor	4	EA	6	\$1,204	
	Floor - Tile	Lunch room #1 1st floor	4,066	SF	6	\$8,896	
	Lighting - Lay-in	Lunch room #1 1st floor	36	EA	6	\$4,283	
	Serving Line	Lunch room #1 1st floor	84	LF	6	\$4,999	
	Storage/ Closet	Lunch room #1 1st floor	300	SF	6	\$2,175	
	Walls - Plaster/Drywall	Lunch room #1 1st floor	2,794	SF	6	\$7,711	
	Walls - Structural Glazed Tile	Lunch room #1 1st floor	2,794	SF	6	\$8,790	
<b>MDF_IDF</b>							
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	7	\$0	
	Finishes	2nd Floor	1,458	SF	7	\$0	Room 201C
	Ventilation and Cooling	2nd Floor	1	EA	7	\$0	
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	1st Floor	15	SF	6	\$107	100E
	Mechanical/ Service Rooms	1st Floor	90	SF	6	\$645	Elec Rm 100B (behind stage in Aud.)
	Storage Room	1st Floor	324	SF	6	\$2,321	Rm 100K (behind stage in Aud.)
	Storage Room	1st Floor	688	SF	6	\$4,929	167A
	Janitor's Closet	2nd Floor	15	SF	6	\$107	
	Janitor's Closet	3rd Floor	15	SF	6	\$107	
	Janitor's Closet	4th Floor	220	SF	6	\$1,576	
	Storage Room	4th Floor	1,440	SF	6	\$10,317	Peeling paint RM 412
	Storage Room	5th Floor Storage	713	SF	6	\$5,108	
<b>Prep Room</b>							
	Casework	206B	45	LF	7	\$0	
	Ceiling - Lay-in	206B	32	SF	5	\$222	
	Ceiling - Lay-in	206B	168	SF	7	\$0	
	Doors - Wood Doors inclu hw	206B	1	EA	7	\$0	
	Floor - Tile	206B	205	SF	7	\$0	
	Lighting - Lay-in	206B	6	EA	7	\$0	
	Walls - Plaster/Drywall	206B	368	SF	7	\$0	
	Work Sink	206B	1	EA	6	\$379	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Prep Room</b>							
	Casework	211A	50	LF	7	\$0	
	Ceiling - Plaster/Drywall	211A	205	SF	7	\$0	
	Doors - Wood Doors inclu hw	211A	2	EA	7	\$0	
	Floor - Tile/Sheet	211A	205	SF	7	\$0	
	Lighting - Lay-in	211A	4	EA	7	\$0	
	Walls - Plaster/Drywall	211A	365	SF	7	\$0	
	Work Sink	211A	1	EA	7	\$0	
	Casework	306A	40	LF	7	\$0	
	Ceiling - Lay-in	306A	290	SF	6	\$871	
	Doors - Steel Doors incl hw	306A	1	EA	7	\$0	
	Floor - Tile/Sheet	306A	290	SF	7	\$0	
	Lighting - Lay-in	306A	3	EA	6	\$357	
	Walls - Plaster/Drywall	306A	648	SF	7	\$0	
	Casework	310A	30	LF	6	\$758	
	Ceiling - Lay-in	310A	120	SF	6	\$360	
	Doors - Wood Doors inclu hw	310A	1	EA	6	\$301	
	Floor - Tile	310A	120	SF	6	\$263	
	Lighting - Lay-in	310A	5	EA	6	\$595	
	Walls - Plaster/Drywall	310A	498	SF	6	\$1,374	
<b>Restroom</b>							
	Accessories	100F - Boy's	355	SF	6	\$3,274	
	Ceiling - Plaster/Drywall	100F - Boy's	355	SF	7	\$0	
	Doors - Wood Doors inclu hw	100F - Boy's	1	EA	6	\$301	
	Floor Drain	100F - Boy's	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	100F - Boy's	355	SF	6	\$751	
	Hand Dryer	100F - Boy's	2	EA	7	\$0	
	Lavatory	100F - Boy's	2	EA	7	\$0	
	Lighting - Pendant/Surface	100F - Boy's	6	EA	7	\$0	
	Partitions	100F - Boy's	1	EA	7	\$0	
	Urinals	100F - Boy's	6	EA	7	\$0	
	Walls - Concrete Block	100F - Boy's	5	SF	6	\$24	
	Walls - Concrete Block	100F - Boy's	385	SF	7	\$0	
	Walls - Plaster/Drywall	100F - Boy's	64	SF	6	\$177	
	Walls - Tile Ceramic/ Porcelain	100F - Boy's	140	SF	6	\$316	
	Water Closet	100F - Boy's	1	EA	7	\$0	
	Accessories	100N - Girl's	224	SF	6	\$2,066	
	Ceiling - Plaster/Drywall	100N - Girl's	224	SF	7	\$0	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Doors - Steel Doors incl hw	100N - Girl's	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	100N - Girl's	1	EA	7	\$0	
	Floor Drain	100N - Girl's	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	100N - Girl's	224	SF	6	\$474	
	Hand Dryer	100N - Girl's	2	EA	7	\$0	
	Lavatory	100N - Girl's	3	EA	7	\$0	
	Lighting - Lay-in	100N - Girl's	4	EA	7	\$0	
	Partitions	100N - Girl's	5	EA	7	\$0	
	Walls - Concrete Block	100N - Girl's	342	SF	7	\$0	
	Walls - Plaster/Drywall	100N - Girl's	8	SF	6	\$31	
	Walls - Plaster/Drywall	100N - Girl's	162	SF	7	\$0	
	Water Closet	100N - Girl's	6	EA	7	\$0	
	Accessories	200A	224	SF	7	\$0	
	Ceiling - Plaster/Drywall	200A	224	SF	7	\$0	
	Doors - Wood Doors inclu hw	200A	2	EA	7	\$0	
	Floor Drain	200A	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	200A	224	SF	6	\$474	
	Hand Dryer	200A	2	EA	7	\$0	
	Lavatory	200A	3	EA	7	\$0	
	Lighting - Lay-in	200A	5	EA	7	\$0	
	Partitions	200A	5	EA	7	\$0	
	Walls - Concrete Block	200A	512	SF	7	\$0	
	Water Closet	200A	6	EA	7	\$0	
	Accessories	285C	71	SF	6	\$655	
	Ceiling - Plaster/Drywall	285C	71	SF	7	\$0	
	Doors - Wood Doors inclu hw	285C	1	EA	7	\$0	
	Floor - Tile	285C	36	SF	6	\$79	
	Floor - Tile Ceramic/ Porcelain	285C	35	SF	6	\$74	
	Lavatory	285C	1	EA	7	\$0	
	Lighting - Lay-in	285C	2	EA	7	\$0	
	Partitions	285C	1	EA	7	\$0	
	Walls - Plaster/Drywall	285C	437	SF	7	\$0	
	Water Closet	285C	2	EA	7	\$0	
	Accessories	290 - Boy's	355	SF	6	\$3,274	
	Ceiling - Plaster/Drywall	290 - Boy's	355	SF	7	\$0	
	Doors - Wood Doors inclu hw	290 - Boy's	1	EA	7	\$0	
	Floor Drain	290 - Boy's	1	EA	5	\$2,094	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor - Tile Ceramic/ Porcelain	290 - Boy's	355	SF	6	\$751	
	Hand Dryer	290 - Boy's	1	EA	5	\$590	
	Hand Dryer	290 - Boy's	1	EA	7	\$0	
	Lavatory	290 - Boy's	3	EA	6	\$959	
	Lighting - Pendent/Surface	290 - Boy's	6	EA	7	\$0	
	Partitions	290 - Boy's	3	EA	6	\$891	
	Urinals	290 - Boy's	5	EA	7	\$0	
	Walls - Concrete Block	290 - Boy's	309	SF	7	\$0	
	Walls - Plaster/Drywall	290 - Boy's	25	SF	6	\$97	
	Walls - Plaster/Drywall	290 - Boy's	260	SF	7	\$0	
	Water Closet	290 - Boy's	2	EA	7	\$0	
	Accessories	300C	160	SF	6	\$1,476	
	Ceiling - Plaster/Drywall	300C	160	SF	6	\$554	
	Doors - Wood Doors inclu hw	300C	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	300C	160	SF	6	\$339	
	Lavatory	300C	1	EA	6	\$320	
	Lighting - Pendent/Surface	300C	2	EA	7	\$0	
	Partitions	300C	1	EA	7	\$0	
	Walls - Plaster/Drywall	300C	524	SF	6	\$1,446	
	Water Closet	300C	1	EA	6	\$336	
	Accessories	300E/girl's room	224	SF	6	\$2,066	
	Ceiling - Plaster/Drywall	300E/girl's room	224	SF	7	\$0	
	Doors - Wood Doors inclu hw	300E/girl's room	1	EA	7	\$0	
	Floor - Tile Ceramic/ Porcelain	300E/girl's room	224	SF	5	\$3,578	"Baseboard" tiles
	Hand Dryer	300E/girl's room	2	EA	6	\$460	
	Lavatory	300E/girl's room	3	EA	7	\$0	
	Lighting - Lay-in	300E/girl's room	4	EA	7	\$0	
	Partitions	300E/girl's room	5	EA	6	\$1,485	
	Walls - Concrete Block	300E/girl's room	512	SF	6	\$1,501	
	Water Closet	300E/girl's room	6	EA	6	\$2,016	
	Accessories	300F	31	SF	7	\$0	
	Ceiling - Lay-in	300F	31	SF	7	\$0	
	Doors - Wood Doors inclu hw	300F	1	EA	7	\$0	
	Floor - Tile/Sheet	300F	31	SF	7	\$0	
	Hand Dryer	300F	1	EA	7	\$0	
	Hand Dryer	300F	1	EA	7	\$0	
	Lavatory	300F	1	EA	7	\$0	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lighting - Lay-in	300F	1	EA	7	\$0	
	Walls - Plaster/Drywall	300F	181	SF	7	\$0	
	Water Closet	300F	1	EA	7	\$0	
	Ceiling - Plaster/Drywall	390/3rd boys	355	SF	7	\$0	
	Doors - Wood Doors inclu hw	390/3rd boys	1	EA	6	\$301	
	Floor Drain	390/3rd boys	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	390/3rd boys	355	SF	6	\$751	
	Lavatory	390/3rd boys	3	EA	6	\$959	
	Lighting - Pendent/Surface	390/3rd boys	6	EA	6	\$743	
	Partitions	390/3rd boys	3	EA	6	\$891	Paint
	Urinals	390/3rd boys	5	EA	6	\$1,680	
	Walls - Concrete Block	390/3rd boys	594	SF	6	\$1,741	
	Water Closet	390/3rd boys	2	EA	6	\$672	
	Accessories	Girl's room 4th floor	562	SF	6	\$5,184	
	Ceiling - Plaster/Drywall	Girl's room 4th floor	562	SF	6	\$1,945	
	Doors - Wood Doors inclu hw	Girl's room 4th floor	2	EA	6	\$602	
	Floor Drain	Girl's room 4th floor	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Girl's room 4th floor	562	SF	6	\$1,189	
	Hand Dryer	Girl's room 4th floor	2	EA	7	\$0	
	Lavatory	Girl's room 4th floor	4	EA	6	\$1,278	
	Lighting - Lay-in	Girl's room 4th floor	12	EA	7	\$0	
	Partitions	Girl's room 4th floor	6	EA	6	\$1,782	
	Walls - Plaster/Drywall	Girl's room 4th floor	1,297	SF	6	\$3,580	
	Water Closet	Girl's room 4th floor	6	EA	6	\$2,016	
	Accessories	In 111	60	SF	6	\$553	
	Ceiling - Plaster/Drywall	In 111	60	SF	7	\$0	
	Doors - Wood Doors inclu hw	In 111	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	In 111	60	SF	7	\$0	
	Lavatory	In 111	1	EA	7	\$0	
	Lighting - Lay-in	In 111	1	EA	7	\$0	
	Partitions	In 111	2	EA	7	\$0	
	Walls - Plaster/Drywall	In 111	40	SF	5	\$177	
	Walls - Plaster/Drywall	In 111	248	SF	7	\$0	
	Water Closet	In 111	1	EA	7	\$0	
	Accessories	In 300G	20	SF	6	\$184	Unknown user - may be student, staff, or guest
	Ceiling - Plaster/Drywall	In 300G	20	SF	6	\$69	
	Doors - Wood Doors inclu hw	In 300G	1	EA	6	\$301	

**Building: Main**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor - Tile Ceramic/ Porcelain	In 300G	10	SF	6	\$21	
	Lavatory	In 300G	1	EA	6	\$320	
	Lighting - Chandelier, Incandescent	In 300G	1	EA	6	\$478	
	Showers	In 300G	1	EA	6	\$311	Tub only
	Walls - Tile Ceramic/ Porcelain	In 300G	130	SF	6	\$294	
	Water Closet	In 300G	1	EA	6	\$336	
	Accessories	In the teacher's lounge room 490	31	SF	6	\$286	
	Ceiling - Lay-in	In the teacher's lounge room 490	31	SF	6	\$93	
	Doors - Wood Doors inclu hw	In the teacher's lounge room 490	1	EA	6	\$301	
	Floor - Tile/Sheet	In the teacher's lounge room 490	31	SF	5	\$139	
	Lavatory	In the teacher's lounge room 490	1	EA	6	\$320	
	Lighting - Lay-in	In the teacher's lounge room 490	1	EA	6	\$119	
	Walls - Plaster/Drywall	In the teacher's lounge room 490	12	SF	5	\$61	
	Walls - Plaster/Drywall	In the teacher's lounge room 490	169	SF	6	\$466	
	Water Closet	In the teacher's lounge room 490	1	EA	6	\$336	
	Accessories	Within 103A Storage	77	SF	6	\$710	
	Ceiling - Plaster/Drywall	Within 103A Storage	77	SF	7	\$0	
	Doors - Wood Doors inclu hw	Within 103A Storage	1	EA	6	\$301	
	Floor - Tile	Within 103A Storage	77	SF	6	\$168	
	Lavatory	Within 103A Storage	1	EA	7	\$0	
	Lighting - Lay-in	Within 103A Storage	2	EA	7	\$0	
	Walls - Plaster/Drywall	Within 103A Storage	324	SF	7	\$0	
	Water Closet	Within 103A Storage	1	EA	7	\$0	

**Rooms (Other Than Classrooms) Subtotal:**
**\$656,974**
**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	200	SF	5	\$1,785	Water damage - leak scheduled to be fixed week after inspection
	Ceiling - Lay-in	1st Floor	9,545	SF	6	\$28,664	
	Ceiling - Plaster/Drywall	1st Floor	500	SF	6	\$3,096	Paint in vestibule 1050
	Doors - Wood Doors include hw	1st Floor	6	EA	6	\$1,806	
	Drinking Fountains - Single Fountain	1st Floor	6	EA	7	\$0	
	Floor - Terrazzo	1st Floor	1,564	SF	6	\$13,128	

## Building: Main

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Floor - Tile Ceramic/ Porcelain	1st Floor	40	SF	6	\$112	
	Floor - Tile Quarry	1st Floor	500	SF	6	\$1,394	
	Floor - Tile/Sheet	1st Floor	8,321	SF	5	\$37,363	Main corridor is bowed
	Lighting - Pendent/Surface	1st Floor	236	EA	7	\$0	
	Stairs - Concrete Stairs	1st Floor	6	LF	5	\$595	
	Stairs - Terrazzo	1st Floor	3	LF	5	\$163	
	Student Lockers - One Tier	1st Floor	197	EA	6	\$18,289	
	Walls - Plaster/Drywall	1st Floor	30	SF	5	\$301	
	Walls - Plaster/Drywall	1st Floor	15,894	SF	6	\$70,458	
	Ceiling - Lay-in	2nd Floor	8,943	SF	7	\$0	
	Doors - Wood Doors include hw	2nd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	2nd Floor	4	EA	7	\$0	
	Floor - Tile/Sheet	2nd Floor	8,551	SF	6	\$4,647	
	Lighting - Lay-in	2nd Floor	236	EA	7	\$0	
	Stairs - Terrazzo	2nd Floor	7	LF	6	\$65	
	Student Lockers - One Tier	2nd Floor	239	EA	6	\$22,188	
	Walls - Plaster/Drywall	2nd Floor	13,787	SF	5	\$101,732	
	Ceiling - Lay-in	3rd Floor	8,943	SF	7	\$0	
	Doors - Wood Doors include hw	3rd Floor	4	EA	6	\$1,204	
	Drinking Fountains - Single Fountain	3rd Floor	4	EA	7	\$0	
	Floor - Tile/Sheet	3rd Floor	8,551	SF	6	\$4,647	
	Lighting - Lay-in	3rd Floor	233	EA	7	\$0	
	Student Lockers - One Tier	3rd Floor	289	EA	6	\$26,829	
	Walls - Plaster/Drywall	3rd Floor	13,787	SF	6	\$61,118	
	Ceiling - Lay-in	4th Floor	3,728	SF	7	\$0	
	Drinking Fountains - Single Fountain	4th Floor	4	EA	7	\$0	
	Floor - Tile/Sheet	4th Floor	3,728	SF	6	\$2,026	Typically baseboards need maintenance
	Lighting - Lay-in	4th Floor	208	EA	7	\$0	
	Student Lockers - One Tier	4th Floor	287	EA	6	\$26,644	
	Walls - Plaster/Drywall	4th Floor	9,178	SF	7	\$0	
<b>Safety</b>							
	Camera Viewing Station		2	EA	6	\$1,365	hallway security desk & principal
	Metal Dedector		2	EA	6	\$1,761	
	Security Cameras		15	EA	6	\$2,911	
	Security Cameras		2	EA	6	\$388	

**Building: Main**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Ceiling - Plaster/Drywall	Central East Stair: 1-5	601	SF	6	\$4,400	
	Floor - Concrete	Central East Stair: 1-5	608	SF	6	\$322	
	Floor - Terrazzo	Central East Stair: 1-5	136	SF	6	\$1,142	
	Handrails	Central East Stair: 1-5	218	LF	6	\$1,889	
	Lighting - Pendent/Surface	Central East Stair: 1-5	10	EA	6	\$1,239	
	Stairs - Rubber	Central East Stair: 1-5	140	LF	6	\$1,506	
	Walls - Plaster/Drywall	Central East Stair: 1-5	898	SF	6	\$2,478	
	Ceiling - Plaster/Drywall	Central West Stair: 1-5	601	SF	6	\$4,400	
	Floor - Concrete	Central West Stair: 1-5	608	SF	6	\$322	
	Floor - Terrazzo	Central West Stair: 1-5	136	SF	6	\$1,142	
	Handrails	Central West Stair: 1-5	218	LF	6	\$1,889	
	Lighting - Pendent/Surface	Central West Stair: 1-5	6	EA	6	\$743	
	Stairs - Rubber	Central West Stair: 1-5	140	LF	6	\$1,506	
	Walls - Plaster/Drywall	Central West Stair: 1-5	898	SF	6	\$2,478	
	Ceiling - Plaster/Drywall	East Stair: 1-4	493	SF	6	\$3,610	
	Floor - Concrete	East Stair: 1-4	258	SF	6	\$137	
	Floor - Terrazzo	East Stair: 1-4	126	SF	6	\$1,058	
	Handrails	East Stair: 1-4	206	LF	6	\$1,785	
	Lighting - Pendent/Surface	East Stair: 1-4	8	EA	6	\$991	
	Lighting - Wall Mounted	East Stair: 1-4	2	EA	6	\$248	
	Stairs - Terrazzo	East Stair: 1-4	52	LF	6	\$483	
	Stairs - Tile	East Stair: 1-4	57	LF	6	\$529	
	Ceiling - Lay-in	West Stair: 1-4	493	SF	6	\$1,480	
	Floor - Concrete	West Stair: 1-4	258	SF	6	\$137	
	Floor - Terrazzo	West Stair: 1-4	126	SF	6	\$1,058	
	Handrails	West Stair: 1-4	192	LF	6	\$1,664	
	Lighting - Lay-in	West Stair: 1-4	3	EA	7	\$0	
	Lighting - Wall Mounted	West Stair: 1-4	2	EA	7	\$0	
	Stairs - Rubber	West Stair: 1-4	57	LF	6	\$613	
	Stairs - Terrazzo	West Stair: 1-4	52	LF	5	\$2,820	
	Walls - Plaster/Drywall	West Stair: 1-4	663	SF	6	\$1,830	
<b>Vertical Conveyance</b>							
	Elevator - Hydraulic Elevator		1	EA	6	\$19,238	
	Wheelchair Lift - Platform Lift		1	EA	6	\$6,690	In auditorium

**Building Interior Subtotal:**
**\$505,703**

## Total Building Cost

**\$6,232,728**

### Building: Addition 1

#### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#8 E	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	#4 W	3	EA	6	\$1,442	
	Exterior Doors - Overhead Rolling/ Garage Door	#7 E	1	EA	6	\$1,433	
	Exterior Doors - Transom Lite	#4 W	3	EA	6	\$940	
	Exterior Stairs - Concrete	#8 E	6	LF	6	\$491	
	Exterior Stairs - Stone	#4 W	10	LF	6	\$1,130	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	418	LF	7	\$0	
	Superstructure - Steel with Clay Tile Arch	Entire Building	40,692	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	5	EA	4	\$25,476	Engineer states lights are not operational.
<b>Roof System</b>							
	Chimney - Brick Chimney- Concrete/ Mortar Liner	Entire Building	70	LF	6	\$66,828	
	Coping - Clay Tile	Entire Building	620	LF	6	\$19,913	
	Downspouts - Interior Downspouts	Entire Building	180	LF	6	\$5,982	
	Parapet - 16" - 30" Height	Entire Building	520	LF	6	\$20,776	
	Parapet - Parapet < 16" Height	Entire Building	100	LF	6	\$2,131	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	19,925	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Entire Building	19,925	SF	5	\$470,415	
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	18,778	SF	6	\$126,207	
	Exterior Walls - Terra Cotta	Entire Building	2,090	SF	6	\$14,047	Painted
<b>Windows</b>							
	Guard - Guards perforated	Entire Building / 1st Floor	280	SF	6	\$3,576	
	Lintels - Terra Cotta	Entire Building	234	LF	6	\$0	
	Windows - Sash Aluminum Double-pane	Entire Building	2,080	SF	6	\$15,526	

### Building Exterior Subtotal:

**\$776,792**

### Building: Addition 1

#### Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Addition 1**
**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Emergency A/C Power - Corridors and Stairs	Entire Building	2,850	SF	6	\$856	
	Emergency A/C Power - Gym	Entire Building / 2nd Floor	8,240	SF	6	\$3,064	
	Emergency A/C Power - Students Toilets	Entire Building	550	SF	6	\$204	
	Emergency Generator- Outdoor- Diesel - 101 - 150 KW	Site - East	1	EA	6	\$11,529	serves main, and additions 1,2,3
	Exit Signs - Corridors and Stairs	Entire Building	6	EA	6	\$898	
	Exit Signs - Gym	Entire Building / 2nd Floor	7	EA	6	\$1,102	
	Security System - CCTV	Entire Building	40,692	SF	6	\$12,220	
	Security System - Intrusion Detection	Entire Building	40,692	SF	6	\$10,474	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	school as ATS
	Main Electrical Service - 2000 A 120/208/3PH	Electrical Room	1	EA	6	\$8,232	
	PA System	Entire Building	40,692	SF	6	\$13,384	connected to main building
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building	2	EA	6	\$994	
	Lighting and Power Panels - Above 100 A	Entire Building	3	EA	6	\$1,491	
	Main Distribution Panels - 400 - 600 amp	Entire Building / Electrical Room	1	EA	6	\$528	

**Electrical System Subtotal: \$68,195**
**Building: Addition 1**
**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Entire Building / Boiler Room	1	EA	6	\$6,406	also serves main, addition 2 and addition 3
	Fire Alarm Strobe Lights	Entire Building	40,692	SF	6	\$14,547	
	Fire Alarm_System	Entire Building	40,692	SF	6	\$19,784	

**Safty System Subtotal: \$40,738**
**Building: Addition 1**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Addition 1**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$95,595	
	Air Intake	Mechanical Room / Main Roof	1	EA	6	\$5,765	
	Auxiliaries - Greater than 35000 cfm	Mechanical Room	1	EA	5	\$18,883	
	Fan Coil Unit- Ceiling Mounted - Steam	ROTC room / Basement	1	EA	5	\$6,068	rusted ducts, located in lower basement area
	Return Duct Work - Indoor- Vertical Shaft and Ducts	Mechanical Room / Entire Building	200	LF	5	\$192,395	5 is not a selectable option
	Roof Top Unit-Single Zone-Roof Mounted- DX Cooling Only with Self Contained Compressor - 5 - 10 tons	Roof	1	EA	7	\$0	serves music/band room
	Zone Dampers	Mechanical Room	10	EA	5	\$19,135	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 201 - 300 HP	Boiler Room	2	EA	5	\$55,593	
	Chemical Feed System	Boiler Room	1	EA	6	\$1,078	
	Combustion Dampers	Boiler Room	3	EA	6	\$1,227	1 extra damper, not presently used
	Condensate Pump	Boiler Room / Mechanical Room	1	EA	6	\$2,021	
	Feed Water Pumps and Tank	Boiler Room	1	EA	6	\$2,545	
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 201 - 300 HP	Boiler Room	2	EA	5	\$55,593	
	Piping - Condensate Pipe- Steel	Boiler Room / Entire Building	300	LF	6	\$566	
	Piping - Steam Pipe- Steel	Boiler Room / Entire Building	300	LF	6	\$566	
	Steam Traps	Boiler Room / Entire Building	25	EA	5	\$32,872	
<b>Heating Devices</b>							
	Radiators - Steam	Entire Building	10	EA	5	\$16,753	
<b>Temperature Control</b>							
	Pneumatic System	Entire Building	40,692	SF	4	\$211,810	No BAS
	Thermostats - Pneumatic	Entire Building	2	EA	6	\$0	
	Thermostats - Pneumatic	Entire Building	6	EA	4	\$4,423	
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - Less than 500 CFM	Entire Building / Roof	2	EA	6	\$592	
	Type I Exhaust Hood- Kitchen	Entire Building / 1st Floor	1	EA	2	\$28,265	
<b>Mechanical System Subtotal:</b>						<b>\$751,748</b>	

**Building: Addition 1**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Addition 1**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - 150000 - 300000 BTU/HR	Entire Building / 1st Floor	1	EA	6	\$310	serves kiitchen
	Gas Heater - 300001 - 600000 BTU/HR	Entire Building / Boiler Room	2	EA	6	\$620	2'd heater for kitchen is in the main building, not in addition 1
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	40,692	SF	6	\$8,147	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	40,692	SF	6	\$9,892	
	Domestic Piping-Cold Water Risers	Entire Building	40,692	SF	6	\$7,565	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	40,692	SF	6	\$6,401	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	40,692	SF	6	\$7,565	
	Domestic Piping-Hot Water Return Lines	Entire Building	40,692	SF	6	\$5,819	
	Domestic Piping-Hot Water Return Risers	Entire Building	40,692	SF	6	\$5,819	
	Sanitary Piping	Entire Building	40,692	SF	6	\$37,241	
	Storm Piping	Entire Building	40,692	SF	6	\$35,496	
	Vent Piping	Entire Building	40,692	SF	6	\$27,349	
<b>Pool Systems</b>							
	Pool Drain Piping	1st Floor / Basement	150	LF	4	\$15,193	pool is closed for a few years because of major repair issues, quotes being reviewed
	Pool Filtration System including Pump	1st Floor / Basement	1	EA	4	\$162,839	pool is closed for a few years because of major repair issues, quotes being reviewed
	Pool Hot Water Heater - Steam Heat Exchanger	1st Floor / Basement	1	EA	4	\$39,560	pool is closed, not used for a few yers
	Pool Supply and Return Piping	1st Floor / Basement	150	LF	4	\$24,906	
<b>Pumps</b>							
	Pumps - Domestic Booster Pump-Duplex	Basement / Mechanical Room	1	EA	6	\$1,977	
	Pumps - Ejector-Simplex	Basement	1	EA	6	\$745	
	Pumps - Sump-Duplex	Basement / Mechanical Room	1	EA	5	\$7,535	
<b>Plumbing System Subtotal:</b>						<b>\$404,977</b>	

**Building: Addition 1**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #009 (Vacant)</b>							
	Ceiling - Exposed	Basement	1,205	SF	6	\$1,792	
	Doors - Steel Doors incl hw	Basement	1	EA	6	\$301	
	Floor - Concrete	Basement	1,205	SF	6	\$638	

## Building: Addition 1

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #009 (Vacant)</b>							
	Lighting - Pendent/Surface	Basement	4	EA	6	\$496	they did not turn on, so I'm not sure if circuit is tripped, or bulbs need replacing
	Walls - Concrete Block	Basement	1,775	SF	6	\$5,203	
<b>Classroom #114 (Vacant)</b>							
	Ceiling - Exposed	Basement	2,342	SF	5	\$6,430	peeling paint
	Doors - Wood Doors inclu hw	Basement	2	EA	6	\$602	at top of stairwells
	Floor - Concrete	Basement	2,342	SF	5	\$4,019	floor drains back up & flood area
	Lighting - Pendent/Surface	Basement	34	EA	7	\$0	
	Walls - Concrete Block	Basement	2,477	SF	5	\$25,432	peeling paint/cracks
<b>Classroom #319 (Music Room)</b>							
	Casework	3rd Floor	52	LF	6	\$1,313	
	Ceiling - Lay-in	3rd Floor	2,176	SF	6	\$6,535	
	Chalk Board	3rd Floor	24	LF	4	\$2,203	
	Doors - Steel Doors incl hw	3rd Floor	1	EA	6	\$301	
	Doors - Transom Window	3rd Floor	28	SF	6	\$474	
	Doors - Wood Doors inclu hw	3rd Floor	4	EA	6	\$1,204	
	Floor - Terrazzo	3rd Floor	21	SF	6	\$46	
	Floor - Wood	3rd Floor	2,155	SF	6	\$15,193	
	Lighting - Lay-in	3rd Floor	32	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	2	EA	7	\$0	
	Marker Board	3rd Floor	20	LF	7	\$0	
	Storage/ Closet	3rd Floor	72	SF	6	\$522	
	Student Lockers - One Tier	3rd Floor	4	EA	6	\$371	
	Student Lockers - Three Tiers	3rd Floor	43	EA	6	\$1,331	Five Tier
	Student Lockers - Two Tiers	3rd Floor	4	EA	6	\$186	
	Walls - Plaster/Drywall	3rd Floor	2,430	SF	6	\$6,707	

### Classrooms Subtotal:

**\$81,298**

## Building: Addition 1

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Exposed	Rm 108- ROTC Office	293	SF	5	\$804	peeling paint
	Doors - Side-lite	Rm 108- ROTC Office	33	SF	6	\$552	
	Doors - Wood Doors inclu hw	Rm 108- ROTC Office	1	EA	6	\$301	

## Building: Addition 1

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Floor - Concrete	Rm 108- ROTC Office	293	SF	6	\$155	
	Lighting - Pendent/Surface	Rm 108- ROTC Office	2	EA	7	\$0	
	Power Distribution	Rm 108- ROTC Office	4	EA	6	\$8,500	
	Storage/ Closet	Rm 108- ROTC Office	200	SF	5	\$3,226	mold & peeling paint
	Walls - Concrete Block	Rm 108- ROTC Office	763	SF	5	\$7,834	mildew & peeling paint
	Ceiling - Lay-in	Rm 180A- Eng. Office	172	SF	6	\$517	
	Doors - Wood Doors inclu hw	Rm 180A- Eng. Office	1	EA	6	\$301	
	Floor - Tile	Rm 180A- Eng. Office	172	SF	5	\$772	very old
	Lighting - Lay-in	Rm 180A- Eng. Office	2	EA	7	\$0	
	Power Distribution	Rm 180A- Eng. Office	4	EA	6	\$8,500	
	Storage/ Closet	Rm 180A- Eng. Office	21	SF	6	\$152	
	Walls - Plaster/Drywall	Rm 180A- Eng. Office	546	SF	6	\$1,507	
	Ceiling - Plaster/Drywall	Rm 218B- Girl's gym office	144	SF	6	\$498	
	Doors - Wood Doors inclu hw	Rm 218B- Girl's gym office	1	EA	6	\$301	
	Floor - Wood	Rm 218B- Girl's gym office	144	SF	4	\$4,168	buckeled
	Lighting - Pendent/Surface	Rm 218B- Girl's gym office	1	EA	4	\$541	T12
	Power Distribution	Rm 218B- Girl's gym office	2	EA	6	\$4,250	
	Walls - Structural Glazed Tile	Rm 218B- Girl's gym office	324	SF	6	\$1,019	
	Work Sink	Rm 218B- Girl's gym office	1	EA	6	\$508	
	Ceiling - Plaster/Drywall	Rm 219C- Boys Gym Office	135	SF	6	\$467	
	Doors - Side-lite	Rm 219C- Boys Gym Office	12	SF	6	\$201	
	Doors - Wood Doors inclu hw	Rm 219C- Boys Gym Office	1	EA	5	\$1,174	delaminating & missing hardware
	Floor - Wood	Rm 219C- Boys Gym Office	135	SF	6	\$952	
	Lighting - Pendent/Surface	Rm 219C- Boys Gym Office	1	EA	7	\$0	
	Power Distribution	Rm 219C- Boys Gym Office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Rm 219C- Boys Gym Office	376	SF	6	\$1,038	
	Walls - Plaster/Drywall	Rm 219C- Boys Gym Office	14	SF	5	\$71	damaged & peeling paint
	Ceiling - Plaster/Drywall	Rm 319C- Practice Room	20,083	SF	6	\$69,499	
	Ceiling - Plaster/Drywall	Rm 319C- Practice Room	1	SF	5	\$12	peeling
	Ceiling - Plaster/Drywall	Rm 319C- Practice Room	83	SF	6	\$287	
	Doors - Wood Doors inclu hw	Rm 319C- Practice Room	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Rm 319C- Practice Room	1	EA	6	\$301	
	Floor - Wood	Rm 319C- Practice Room	201	SF	6	\$1,417	
	Floor - Wood	Rm 319C- Practice Room	6	SF	5	\$118	rotted
	Floor - Wood	Rm 319C- Practice Room	77	SF	6	\$543	
	Lighting - Pendent/Surface	Rm 319C- Practice Room	2	EA	7	\$0	
	Lighting - Pendent/Surface	Rm 319C- Practice Room	1	EA	7	\$0	

**Building: Addition 1**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Power Distribution	Rm 319C- Practice Room	4	EA	6	\$8,500	
	Power Distribution	Rm 319C- Practice Room	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Rm 319C- Practice Room	3	SF	5	\$15	peeling
	Walls - Plaster/Drywall	Rm 319C- Practice Room	464	SF	6	\$1,281	
	Walls - Plaster/Drywall	Rm 319C- Practice Room	322	SF	6	\$889	
	Ceiling - Plaster/Drywall	Rm 319E- Practice Room	152	SF	6	\$526	
	Doors - Steel Doors incl hw	Rm 319E- Practice Room	1	EA	6	\$301	Vault door
	Floor - Wood	Rm 319E- Practice Room	152	SF	5	\$2,224	needs refinishing
	Lighting - Pendent/Surface	Rm 319E- Practice Room	2	EA	7	\$0	
	Power Distribution	Rm 319E- Practice Room	4	EA	6	\$8,500	
	Storage/ Closet	Rm 319E- Practice Room	8	SF	6	\$58	
	Walls - Plaster/Drywall	Rm 319E- Practice Room	416	SF	6	\$1,148	
	Ceiling - Plaster/Drywall	Rm 322- Boy's gym office	10	SF	5	\$125	water damaged
	Ceiling - Plaster/Drywall	Rm 322- Boy's gym office	438	SF	6	\$1,516	
	Doors - Steel Doors incl hw	Rm 322- Boy's gym office	1	EA	6	\$301	
	Doors - Transom Window	Rm 322- Boy's gym office	9	SF	6	\$152	
	Floor - Wood	Rm 322- Boy's gym office	448	SF	6	\$3,158	
	Lighting - Pendent/Surface	Rm 322- Boy's gym office	3	EA	7	\$0	
	Power Distribution	Rm 322- Boy's gym office	4	EA	6	\$8,500	
	Walls - Plaster/Drywall	Rm 322- Boy's gym office	10	SF	5	\$51	water damaged
	Walls - Plaster/Drywall	Rm 322- Boy's gym office	893	SF	6	\$2,465	
	Work Sink	Rm 322- Boy's gym office	1	EA	6	\$508	lavatory
<b>Gymnasias</b>							
	Ceiling - Plaster/Drywall	Rm 218- Girls Gym 2nd floor	15	SF	5	\$301	peeling paint
	Ceiling - Plaster/Drywall	Rm 218- Girls Gym 2nd floor	3,092	SF	6	\$17,067	
	Doors - Steel Doors incl hw	Rm 218- Girls Gym 2nd floor	1	EA	6	\$301	
	Doors - Wood Doors inclu hw	Rm 218- Girls Gym 2nd floor	4	EA	6	\$1,204	
	Floor - Wood	Rm 218- Girls Gym 2nd floor	113	SF	4	\$3,271	buckled
	Floor - Wood	Rm 218- Girls Gym 2nd floor	3	SF	6	\$29	
	Lighting - Metal Halide/Sodium Vapor	Rm 218- Girls Gym 2nd floor	12	EA	7	\$0	
	Storage/ Closet	Rm 218- Girls Gym 2nd floor	232	SF	6	\$1,682	
	Walls - Structural Glazed Tile	Rm 218- Girls Gym 2nd floor	4,805	SF	6	\$15,117	
	Balcony Seating	Rm 219- Boy's gym 2nd floor	42	EA	6	\$7,304	
	Ceiling - Plaster/Drywall	Rm 219- Boy's gym 2nd floor	25	SF	5	\$501	water damaged
	Ceiling - Plaster/Drywall	Rm 219- Boy's gym 2nd floor	5,636	SF	6	\$31,110	
	Doors - Steel Doors incl hw	Rm 219- Boy's gym 2nd floor	2	EA	6	\$602	
	Doors - Transom Window	Rm 219- Boy's gym 2nd floor	30	SF	6	\$508	

## Building: Addition 1

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Gymnasia</b>							
	Doors - Wood Doors inclu hw	Rm 219- Boy's gym 2nd floor	4	EA	5	\$4,696	Doors to balcony- really old
	Doors - Wood Doors inclu hw	Rm 219- Boy's gym 2nd floor	6	EA	6	\$1,806	
	Floor - Wood	Rm 219- Boy's gym 2nd floor	7,213	SF	6	\$50,851	
	Lighting - Metal Halide/Sodium Vapor	Rm 219- Boy's gym 2nd floor	31	EA	7	\$0	
	Lighting - Pendant/Surface	Rm 219- Boy's gym 2nd floor	1	EA	7	\$0	
	Scoreboards	Rm 219- Boy's gym 2nd floor	1	EA	6	\$2,244	
	Sound System	Rm 219- Boy's gym 2nd floor	1	EA	6	\$41,654	
	Stage-Stairs - Terrazzo	Rm 219- Boy's gym 2nd floor	19	LF	6	\$145	stairs up to balcony
	Storage/ Closet	Rm 219- Boy's gym 2nd floor	944	SF	5	\$15,227	Total of Seven T12 fixtures inside 3 closets & inside of 1 closet has damage around door frame
	Walls - Structural Glazed Tile	Rm 219- Boy's gym 2nd floor	6,785	SF	6	\$21,346	
<b>Locker/Shower Room</b>							
	Accessories	Rm 168- Girl's locker room	3,592	SF	6	\$14,074	
	Benches, ped mounted	Rm 168- Girl's locker room	96	LF	6	\$10,452	
	Ceiling - Plaster/ Drywall	Rm 168- Girl's locker room	150	SF	5	\$1,958	peeling
	Ceiling - Plaster/ Drywall	Rm 168- Girl's locker room	3,442	SF	6	\$11,911	
	Doors - Steel Doors incl hw	Rm 168- Girl's locker room	5	EA	6	\$1,505	
	Doors - Transom Window	Rm 168- Girl's locker room	32	SF	6	\$542	
	Floor Drain	Rm 168- Girl's locker room	15	EA	6	\$15,887	
	Floor - Concrete	Rm 168- Girl's locker room	3,192	SF	6	\$1,689	
	Floor - Tile Ceramic/ Porcelain	Rm 168- Girl's locker room	400	SF	6	\$847	
	Hand Dryer	Rm 168- Girl's locker room	11	EA	6	\$2,530	
	Lavatory	Rm 168- Girl's locker room	2	EA	6	\$639	
	Lighting - Pendant/Surface	Rm 168- Girl's locker room	67	EA	7	\$0	
	Partitions	Rm 168- Girl's locker room	28	EA	6	\$8,314	
	Showers	Rm 168- Girl's locker room	26	EA	6	\$8,097	
	Storage/ Closet	Rm 168- Girl's locker room	135	SF	6	\$979	168B- old restroom- fixtures removed & capped, now storage
	Storage/ Closet	Rm 168- Girl's locker room	51	SF	5	\$823	T12 fixture inside
	Student Lockers - Two Tier	Rm 168- Girl's locker room	768	EA	6	\$35,649	
	Walls - Plaster/Drywall	Rm 168- Girl's locker room	40	SF	5	\$204	peeling
	Walls - Plaster/Drywall	Rm 168- Girl's locker room	744	SF	6	\$2,053	
	Walls - Structural Glazed Tile	Rm 168- Girl's locker room	2,351	SF	6	\$7,396	
	Walls - Tile Ceramic/ Porcelain	Rm 168- Girl's locker room	1,000	SF	6	\$2,259	
	Water Closet	Rm 168- Girl's locker room	2	EA	6	\$672	
	Accessories	Rm 170- Boy's locker room	3,088	SF	6	\$12,099	
	Benches, ped mounted	Rm 170- Boy's locker room	50	LF	6	\$5,444	

**Building: Addition 1**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Locker/Shower Room</b>							
	Ceiling - Plaster/ Drywall	Rm 170- Boy's locker room	3,088	SF	6	\$10,686	
	Doors - Steel Doors incl hw	Rm 170- Boy's locker room	2	EA	6	\$602	
	Floor Drain	Rm 170- Boy's locker room	6	EA	6	\$6,355	
	Floor - Concrete	Rm 170- Boy's locker room	3,088	SF	6	\$1,634	
	Hand Dryer	Rm 170- Boy's locker room	1	EA	6	\$230	
	Lavatory	Rm 170- Boy's locker room	1	EA	6	\$320	
	Lighting - Pendent/Surface	Rm 170- Boy's locker room	30	EA	7	\$0	
	Partitions	Rm 170- Boy's locker room	12	EA	6	\$3,563	
	Showers	Rm 170- Boy's locker room	12	EA	6	\$3,737	
	Storage/ Closet	Rm 170- Boy's locker room	100	SF	6	\$725	Locked storage room inside locked weight area cage: Room size & condition is assumed based on surrounding conditions
	Student Lockers - Two Tier	Rm 170- Boy's locker room	163	EA	6	\$7,566	
	Urinals	Rm 170- Boy's locker room	2	EA	6	\$672	
	Walls - Plaster/Drywall	Rm 170- Boy's locker room	1,200	SF	6	\$3,312	
	Walls - Structural Glazed Tile	Rm 170- Boy's locker room	4,225	SF	6	\$13,292	
	Water Closet	Rm 170- Boy's locker room	1	EA	6	\$336	
	AC Unit	Rm 219D- Asst Engineer's office/ locker room	1	EA	3	\$6,086	Not on own circuit
	Accessories	Rm 219D- Asst Engineer's office/ locker room	219	SF	6	\$858	
	Ceiling - Plaster/ Drywall	Rm 219D- Asst Engineer's office/ locker room	219	SF	6	\$758	
	Doors - Wood Doors inclu hw	Rm 219D- Asst Engineer's office/ locker room	1	EA	6	\$301	
	Floor Drain	Rm 219D- Asst Engineer's office/ locker room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Rm 219D- Asst Engineer's office/ locker room	217	SF	6	\$459	
	Floor - Tile Ceramic/ Porcelain	Rm 219D- Asst Engineer's office/ locker room	2	SF	5	\$42	missing tiles
	Lavatory	Rm 219D- Asst Engineer's office/ locker room	1	EA	6	\$320	
	Lighting - Pendent/Surface	Rm 219D- Asst Engineer's office/ locker room	2	EA	4	\$1,081	T12
	Partitions	Rm 219D- Asst Engineer's office/ locker room	1	EA	6	\$297	
	Showers	Rm 219D- Asst Engineer's office/ locker room	1	EA	6	\$311	
	Student Lockers - One Tier	Rm 219D- Asst Engineer's office/ locker room	3	EA	6	\$279	

**Building: Addition 1**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Locker/Shower Room</b>							
	Student Lockers - Two Tier	Rm 219D- Asst Engineer's office/ locker room	4	EA	6	\$186	
	Walls - Plaster/Drywall	Rm 219D- Asst Engineer's office/ locker room	708	SF	6	\$1,954	
	Water Closet	Rm 219D- Asst Engineer's office/ locker room	1	EA	5	\$3,894	Out of order
	Accessories	Rm 219E- Engineer's locker room	168	SF	6	\$658	
	Ceiling - Plaster/ Drywall	Rm 219E- Engineer's locker room	168	SF	6	\$581	
	Doors - Wood Doors inclu hw	Rm 219E- Engineer's locker room	1	EA	6	\$301	
	Floor Drain	Rm 219E- Engineer's locker room	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Rm 219E- Engineer's locker room	168	SF	6	\$356	
	Lavatory	Rm 219E- Engineer's locker room	1	EA	6	\$320	
	Lighting - Pendent/Surface	Rm 219E- Engineer's locker room	2	EA	4	\$1,081	T12
	Partitions	Rm 219E- Engineer's locker room	2	EA	6	\$594	
	Showers	Rm 219E- Engineer's locker room	1	EA	6	\$311	
	Student Lockers - Two Tier	Rm 219E- Engineer's locker room	8	EA	6	\$371	
	Walls - Plaster/Drywall	Rm 219E- Engineer's locker room	624	SF	6	\$1,722	
	Water Closet	Rm 219E- Engineer's locker room	1	EA	4	\$7,669	missing
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Lay-in	Rm 116-C	1,549	SF	6	\$4,652	
	Doors - Wood Doors inclu hw	Rm 116-C	1	EA	6	\$301	
	Floor - Tile	Rm 116-C	1,549	SF	6	\$3,389	
	Lighting - Lay-in	Rm 116-C	28	EA	7	\$0	
	Storage/ Closet	Rm 116-C	206	SF	6	\$1,494	116D
	Walls - Concrete Block	Rm 116-C	827	SF	6	\$2,424	
	Walls - Metal Panel	Rm 116-C	827	SF	6	\$6,173	FRP
<b>MDF_IDF</b>							
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Finishes	2nd Floor	47	SF	6	\$335	
	Ventilation and Cooling	2nd Floor	1	EA	6	\$1,855	
<b>Mechanical/ Service Rooms</b>							
	Boiler Room	1st Floor	1,571	SF	6	\$11,255	
	Mechanical/ Service Rooms	1st Floor	232	SF	5	\$3,742	Rm116E- small amount of peeling paint, or efflorescence
	Mechanical/ Service Rooms	1st Floor	911	SF	6	\$6,527	pump room & sump pump room
	Storage Room	1st Floor	239	SF	6	\$1,712	off boiler room
	Storage Room	2nd Floor	317	SF	6	\$2,271	

## Building: Addition 1

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Mechanical/ Service Rooms</b>							
	Storage Room	2nd Floor	214	SF	5	\$3,452	Storage Rm220A- plaster damaged
	Air Tunnel	Basement	1,742	SF	6	\$10,786	
	Mechanical/ Service Rooms	Basement	2,157	SF	6	\$15,453	RM 010- Filter Room
<b>Pool &amp; Natatorium</b>							
	Ceiling - Lay-In	1st Floor	3,035	SF	6	\$9,114	
	Ceiling - Plaster/ Drywall	1st Floor	55	SF	5	\$819	peeling
	Doors - Transom Window	1st Floor	32	SF	6	\$542	
	Doors - Wood Doors inclu hw	1st Floor	4	EA	6	\$1,204	
	Lighting - Lay-in	1st Floor	22	EA	7	\$0	
	Pool Basin	1st Floor	1,465	SF	4	\$373,299	needs a new liner, leaks & is no longer in use
	Pool Deck	1st Floor	1,595	SF	6	\$15,145	
	Pool Deck	1st Floor	30	SF	5	\$758	minor cracks in tile
	Pool Deck Drains	1st Floor	8	EA	6	\$3,377	
	Storage/ Closet	1st Floor	43	SF	5	\$694	T12 & peeling walls
	Walls - Structural Glazed Tile	1st Floor	2,702	SF	6	\$8,500	
<b>Prep Room</b>							
	Ceiling - Exposed	Rm 171- Laundry room	366	SF	6	\$544	
	Doors - Wood Doors inclu hw	Rm 171- Laundry room	1	EA	6	\$301	
	Floor - Concrete Epoxy/ Painted	Rm 171- Laundry room	366	SF	6	\$194	
	Lighting - Pendant/Surface	Rm 171- Laundry room	3	EA	7	\$0	
	Walls - Masonry	Rm 171- Laundry room	1,050	SF	6	\$3,303	
<b>Restroom</b>							
	Accessories	1st Flr Girls next to Cafeteria	139	SF	6	\$1,282	
	Ceiling - Plaster/Drywall	1st Flr Girls next to Cafeteria	139	SF	6	\$481	
	Doors - Steel Doors incl hw	1st Flr Girls next to Cafeteria	1	EA	6	\$301	
	Doors - Transom Window	1st Flr Girls next to Cafeteria	8	SF	6	\$135	
	Floor - Tile Ceramic/ Porcelain	1st Flr Girls next to Cafeteria	139	SF	6	\$294	
	Lavatory	1st Flr Girls next to Cafeteria	1	EA	6	\$320	
	Lighting - Pendant/Surface	1st Flr Girls next to Cafeteria	2	EA	7	\$0	
	Partitions	1st Flr Girls next to Cafeteria	3	EA	6	\$891	
	Walls - Plaster/Drywall	1st Flr Girls next to Cafeteria	515	SF	6	\$1,421	
	Water Closet	1st Flr Girls next to Cafeteria	3	EA	6	\$1,008	
	Accessories	1st Flr- Inside Eng. Office 180A	33	SF	6	\$304	
	Ceiling - Splined	1st Flr- Inside Eng. Office 180A	33	SF	6	\$27	
	Doors - Wood Doors inclu hw	1st Flr- Inside Eng. Office 180A	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	1st Flr- Inside Eng. Office 180A	33	SF	6	\$70	

**Building: Addition 1**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Lavatory	1st Flr- Inside Eng. Office 180A	1	EA	5	\$1,590	cracked
	Lighting - Pendent/Surface	1st Flr- Inside Eng. Office 180A	1	EA	7	\$0	
	Lighting - Wall Mounted	1st Flr- Inside Eng. Office 180A	2	EA	7	\$0	
	Walls - Plaster/Drywall	1st Flr- Inside Eng. Office 180A	241	SF	6	\$665	
	Water Closet	1st Flr- Inside Eng. Office 180A	1	EA	6	\$336	
	Ceiling - Plaster/Drywall	Inside Office 219C	3	SF	5	\$37	damaged
	Ceiling - Plaster/Drywall	Inside Office 219C	39	SF	6	\$135	
	Doors - Wood Doors inclu hw	Inside Office 219C	1	EA	6	\$301	
	Floor Drain	Inside Office 219C	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Inside Office 219C	42	SF	6	\$89	
	Lighting - Pendent/Surface	Inside Office 219C	1	EA	4	\$541	T12
	Partitions	Inside Office 219C	1	EA	6	\$297	
	Showers	Inside Office 219C	1	EA	5	\$1,172	capped off
	Walls - Plaster/Drywall	Inside Office 219C	204	SF	6	\$563	
	Water Closet	Inside Office 219C	1	EA	6	\$336	
	Ceiling - Plaster/Drywall	Inside Office 322	42	SF	6	\$145	
	Doors - Wood Doors inclu hw	Inside Office 322	1	EA	6	\$301	
	Floor Drain	Inside Office 322	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Inside Office 322	42	SF	6	\$89	
	Lighting - Pendent/Surface	Inside Office 322	1	EA	7	\$0	
	Partitions	Inside Office 322	1	EA	6	\$297	
	Showers	Inside Office 322	1	EA	5	\$1,172	capped off
	Walls - Plaster/Drywall	Inside Office 322	204	SF	6	\$563	
	Water Closet	Inside Office 322	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal:**
**\$1,138,766**
**Building: Addition 1**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	2,597	SF	6	\$7,799	
	Ceiling - Plaster/Drywall	1st Floor	869	SF	6	\$5,381	
	Doors - Steel Doors incl hw	1st Floor	7	EA	6	\$2,107	
	Doors - Transom Window	1st Floor	18	EA	6	\$305	
	Doors - Wood Doors include hw	1st Floor	9	EA	6	\$2,709	
	Floor - Terrazzo	1st Floor	345	SF	6	\$2,896	

## Building: Addition 1

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Floor - Tile Ceramic/ Porcelain	1st Floor	222	SF	6	\$619	
	Floor - Tile/Sheet	1st Floor	2,899	SF	6	\$1,575	
	Lighting - Lay-in	1st Floor	21	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	28	EA	7	\$0	
	Stairs - Terrazzo	1st Floor	59	LF	6	\$548	
	Walls - Masonry	1st Floor	774	SF	6	\$2,435	
	Walls - Plaster/Drywall	1st Floor	10	SF	5	\$100	damaged by Door #8
	Walls - Plaster/Drywall	1st Floor	5,544	SF	6	\$24,577	
	Walls - Structural Glazed Tile	1st Floor	222	SF	6	\$698	
	Ceiling - Lay-in	2nd Floor	2,899	SF	6	\$8,706	
	Doors - Side-lite	2nd Floor	18	EA	6	\$301	
	Doors - Transom Window	2nd Floor	60	EA	6	\$1,016	
	Floor - Tile/Sheet	2nd Floor	2,899	SF	6	\$1,575	
	Lighting - Lay-in	2nd Floor	15	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	3	EA	6	\$357	2 cracked & 1 missing cover
	Student Lockers - One Tier	2nd Floor	30	EA	6	\$2,785	
	Walls - Plaster/Drywall	2nd Floor	5,544	SF	6	\$24,577	
	Ceiling - Lay-in	3rd Floor	439	SF	6	\$1,318	
	Ceiling - Plaster/Drywall	3rd Floor	439	SF	6	\$2,718	
	Doors - Transom Window	3rd Floor	12	EA	6	\$203	
	Floor - Terrazzo	3rd Floor	439	SF	6	\$3,685	
	Floor - Tile/Sheet	3rd Floor	439	SF	5	\$1,971	
	Lighting - Lay-in	3rd Floor	5	EA	7	\$0	
	Lighting - Pendent/Surface	3rd Floor	5	EA	7	\$0	
	Walls - Plaster/Drywall	3rd Floor	1,168	SF	6	\$5,178	
<b>Safety</b>							
	Security Cameras		4	EA	6	\$776	
	Security Cameras		1	EA	6	\$194	
<b>Stairs</b>							
	Ceiling - Exposed	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	308	SF	6	\$458	
	Floor - Concrete	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	30	SF	6	\$16	
	Handrails	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	76	LF	6	\$659	
	Lighting - Wall Mounted	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	4	EA	7	\$0	

## Building: Addition 1

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Stairs - Concrete	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	1	LF	5	\$99	crack
	Stairs - Concrete	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	37	LF	6	\$307	
	Walls - Concrete Block	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	260	SF	6	\$874	
	Walls - Concrete Block	ROTC Basement Stairs 11 & 12 (up to 1st floor only)	260	SF	5	\$3,138	peeling
	Ceiling - Plaster/Drywall	Stairwell # 10 (NE)	293	SF	5	\$4,307	peeling
	Floor - Terrazzo	Stairwell # 10 (NE)	478	SF	6	\$4,012	
	Handrails	Stairwell # 10 (NE)	94	LF	6	\$815	
	Lighting - Pendent/Surface	Stairwell # 10 (NE)	12	EA	4	\$6,488	T12
	Stairs - Terrazzo	Stairwell # 10 (NE)	47	LF	6	\$436	
	Walls - Plaster/Drywall	Stairwell # 10 (NE)	2,079	SF	6	\$5,738	
	Ceiling - Plaster/Drywall	Stairwell #8 (NW)	354	SF	6	\$2,592	
	Floor - Terrazzo	Stairwell #8 (NW)	504	SF	6	\$4,231	
	Handrails	Stairwell #8 (NW)	106	LF	6	\$919	
	Lighting - Pendent/Surface	Stairwell #8 (NW)	6	EA	7	\$0	
	Stairs - Terrazzo	Stairwell #8 (NW)	53	LF	6	\$492	
	Walls - Plaster/Drywall	Stairwell #8 (NW)	2,079	SF	6	\$5,738	
	Ceiling - Plaster/Drywall	Stairwell #9 (S)	347	SF	6	\$2,541	
	Floor - Terrazzo	Stairwell #9 (S)	267	SF	6	\$2,241	
	Handrails	Stairwell #9 (S)	88	LF	6	\$763	
	Lighting - Pendent/Surface	Stairwell #9 (S)	5	EA	6	\$619	
	Stairs - Terrazzo	Stairwell #9 (S)	44	LF	6	\$408	
	Walls - Plaster/Drywall	Stairwell #9 (S)	2,340	SF	6	\$6,458	
<b>Vertical Conveyance</b>							
	Wheelchair Lift		1	EA	6	\$0	for band room 319

**Building Interior Subtotal:**
**\$161,456**
**Total Building Cost**
**\$3,423,970**

## Building: Addition 2

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Addition 2**
**Category: Building Exterior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#5 N	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#6 S	1	EA	6	\$481	
	Exterior Doors - Overhead Rolling/ Garage Door	#6.1 S	1	EA	6	\$1,433	
	Exterior Doors - Transom Lite	#5 N	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#6 S	1	EA	6	\$313	
	Exterior Stairs - Concrete	#5 N	8	LF	6	\$654	
<b>Foundation</b>							
	Foundation - Masonry	Entire Building	273	LF	7	\$0	
	Superstructure - Concrete	Entire Building	4,095	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	3	EA	6	\$866	
<b>Roof System</b>							
	Coping - Stone	Entire Building	182	LF	6	\$5,845	
	Downspouts - Exterior Downspouts	Entire Building	70	LF	6	\$2,326	
	Downspouts - Interior Downspouts	Entire Building	34	LF	6	\$1,130	
	Parapet - 16" - 30" Height	Entire Building	182	LF	6	\$7,272	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	4,066	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Entire Building	4,066	SF	6	\$41,340	
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	3,094	SF	6	\$20,795	Efflorescence at South wall
<b>Windows</b>							
	Guard - Guards perforated	Entire Building	702	SF	6	\$8,964	
	Lintels - Steel	Entire Building	114	LF	6	\$3,309	
	Windows - Sash Aluminum Double-pane	Entire Building	702	SF	6	\$5,240	

**Building Exterior Subtotal: \$100,764**

**Building: Addition 2**
**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Emergency A/C Power - Corridors and Stairs	1st Floor	4,238	SF	6	\$1,273	served from addition 1
	Exit Signs - Corridors and Stairs	1st Floor	2	EA	6	\$299	corridor, open area
	Security System - CCTV	1st Floor / Entire Building	4,238	SF	6	\$1,273	

## Building: Addition 2

### Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Security System - Intrusion Detection	1st Floor / Entire Building	4,238	SF	6	\$1,091	
<b>Main Service</b>							
	PA System	1st Floor	4,238	SF	6	\$1,394	connected to main building
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	1st Floor	1	EA	7	\$0	
	Lighting and Power Panels - Above 100 A	1st Floor	1	EA	7	\$0	
	Main Distribution Panels - Greater than 600 amp	1st Floor	1	EA	7	\$0	addition 2 is being remodeled, served from addition 1

**Electrical System Subtotal: \$5,330**

## Building: Addition 2

### Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Strobe Lights	1st Floor	4,238	SF	6	\$1,515	
	Fire Alarm_System	1st Floor	4,238	SF	6	\$2,061	

**Safty System Subtotal: \$3,576**

## Building: Addition 2

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 8001-12000 cfm	Mezzanine	1	EA	7	\$0	2015 installation, addition 2 area is being remodeled
	Air Intake	Mezzanine / Façade- NE	1	EA	7	\$0	
<b>Heating Devices</b>							
	Unit Heater - Hot Water	1st Floor	8	EA	6	\$2,233	to be replaced by air handler, which is being installed
<b>Mechanical Plumbing</b>							
	Hydronic Supply and Return - Galvanized	1st Floor	100	LF	6	\$7,732	to be removed, serve 8 hot water unit heater, which are being replaced by an air handler
<b>Temperature Control</b>							
	Pneumatic System	1st Floor	4,238	SF	5	\$14,605	being updated, addition is being remodeled

## Building: Addition 2

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Temperature Control</b>							
	Thermostats - Pneumatic	1st Floor	2	EA	4	\$1,474	
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Roof	1	EA	4	\$4,245	ventilation to be upgraded with ongoing remodeling

**Mechanical System Subtotal:** **\$30,290**

## Building: Addition 2

### Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Piping</b>							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	4,238	SF	6	\$1,030	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	4,238	SF	6	\$788	
	Domestic Piping-Hot Water Return Lines	Entire Building	4,238	SF	6	\$606	
	Sanitary Piping	Entire Building	4,238	SF	6	\$3,879	
	Storm Piping	Entire Building	4,238	SF	6	\$3,697	
	Vent Piping	Entire Building	4,238	SF	6	\$2,848	

**Plumbing System Subtotal:** **\$12,848**

## Building: Addition 2

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #174 (Autoshop)</b>							
	Ceiling - Exposed	1st Floor	3,061	SF	6	\$4,552	
	Doors - Steel Doors incl hw	1st Floor	1	EA	7	\$0	
	Floor - Concrete Epoxy/ Painted	1st Floor	3,061	SF	7	\$0	
	Lighting - Pendent/Surface	1st Floor	44	EA	7	\$0	
	Storage/ Closet	1st Floor	196	SF	7	\$0	
	Walls - Concrete Block	1st Floor	1,617	SF	7	\$0	
	Walls - Masonry	1st Floor	1,597	SF	6	\$5,024	
	Walls - Masonry	1st Floor	20	SF	5	\$1,144	efflorescence
<b>Classroom #174A (Regular Classroom)</b>							
	AC Units	1st Floor	1	EA	7	\$0	
	Ceiling - Lay-in	1st Floor	863	SF	7	\$0	
	Doors - Steel Doors incl hw	1st Floor	1	EA	7	\$0	

## Building: Addition 2

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #174A (Regular Classroom)</b>							
	Floor - Tile	1st Floor	863	SF	7	\$0	
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Marker Board	1st Floor	12	LF	7	\$0	
	Walls - Concrete Block	1st Floor	720	SF	7	\$0	
	Walls - Masonry	1st Floor	720	SF	6	\$2,265	
<b>Classrooms Subtotal:</b>						<b>\$12,985</b>	

## Total Building Cost

**\$165,792**

## Building: Addition 3

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Exterior Steel Door	#10_Exit S	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#11_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#12_Exit N	2	EA	6	\$961	
	Exterior Doors - Exterior Wood Door	#13 E	6	EA	6	\$2,883	
	Exterior Stairs - Concrete	#10_Exit S	18	LF	6	\$1,472	
	Exterior Stairs - Concrete	#11_Exit N	18	LF	6	\$1,472	
	Exterior Stairs - Concrete	#12_Exit N	18	LF	6	\$1,472	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	399	LF	7	\$0	
	Superstructure - Steel	Entire Building	10,816	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Wall Mounted	Entire Building	4	EA	6	\$1,155	
<b>Roof System</b>							
	Coping - Metal	Entire Building	399	LF	6	\$12,815	
	Downspouts - Interior Downspouts	Entire Building	110	LF	6	\$3,656	Clean debris from drain covers
	Parapet - Parapet > 30"	Entire Building	399	LF	6	\$25,504	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	9,762	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Entire Building	9,762	SF	5	\$230,474	
	Roof - Metal	Entire Building	1,995	SF	6	\$26,731	

## Building: Addition 3

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	8,493	SF	6	\$57,081	1951 SF of Efflorescence at East Facade
<b>Windows</b>							
	Lintels - Steel	Entire Building	19	LF	6	\$552	
	Windows - Louver	Entire Building	100	SF	6	\$746	

### Building Exterior Subtotal:

**\$368,897**

## Building: Addition 3

### Category: Electrical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Emergency A/C Power - Corridors and Stairs	Entire Building / 1st Floor	450	SF	6	\$135	
	Emergency A/C Power - Gym	Entire Building / 1st Floor	8,250	SF	6	\$3,067	
	Emergency Battery Packs - Gym	Entire Building / 1st Floor	2	EA	6	\$405	
	Exit Signs - Corridors and Stairs	Entire Building / 1st Floor	1	EA	6	\$150	
	Exit Signs - Gym	Entire Building / 1st Floor	4	EA	6	\$630	
	Security System - CCTV	Electrical Room / Entire Building	10,816	SF	6	\$3,248	
	Security System - Intrusion Detection	Electrical Room / Entire Building	10,816	SF	6	\$2,784	
<b>Main Service</b>							
	PA System	Entire Building	10,816	SF	6	\$3,557	
<b>Power Distribution</b>							
	Lighting and Power Panels - Above 100 A	1st Floor	2	EA	6	\$994	gym electrical panels served from 1'st addition

### Electrical System Subtotal:

**\$14,970**

## Building: Addition 3

### Category: Safty System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Strobe Lights	Entire Building	10,816	SF	6	\$3,867	
	Fire Alarm_System	Entire Building	10,816	SF	6	\$5,259	served from 1'st addition panel

### Safty System Subtotal:

**\$9,125**

**Building: Addition 3**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Handling Systems</b>							
	Air Handling Unit- Package Single Zone- Indoor- Steam Coils - 12001-20000 cfm	Mezzanine / Mechanical Room	2	EA	5	\$83,029	both serve gym
	Air Intake	Mezzanine / Roof	2	EA	6	\$11,529	
	Indoor Return Fans- Centrifugal Squirrel Cage - 10001 - 20000 CFM	Mezzanine / 1st Floor	2	EA	6	\$3,714	15,000 cfm
<b>Boiler Systems</b>							
	Piping - Condensate Pipe- Steel	first addition / 1st Floor	100	LF	6	\$189	
	Piping - Steam Pipe- Steel	first addition / 1st Floor	100	LF	6	\$189	
	Steam Traps	first addition / 1st Floor	2	EA	5	\$2,630	steam reheat coils for gym
<b>Heating Devices</b>							
	Duct Heater - Hot Water	1st Floor	2		6	\$965	actually with steam coils
<b>Temperature Control</b>							
	Electric Thermostat	Entire Building / 1st Floor	2	EA	6	\$0	for 2 single zone air handlers
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	Roof	1	EA	6	\$592	
<b>Mechanical System Subtotal:</b>						<b>\$102,838</b>	

**Building: Addition 3**
**Category: Plumbing System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Piping</b>							
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	10,816	SF	6	\$2,629	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	10,816	SF	6	\$2,011	
	Domestic Piping-Hot Water Return Lines	Entire Building	10,816	SF	6	\$1,547	
	Sanitary Piping	Entire Building	10,816	SF	6	\$9,899	
	Storm Piping	Entire Building	10,816	SF	6	\$9,435	
	Vent Piping	Entire Building	10,816	SF	6	\$7,269	
<b>Plumbing System Subtotal:</b>						<b>\$32,790</b>	

**Building: Addition 3**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
-------	-------------	----------	----------	------	------	------	----------

**Building: Addition 3**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Plaster/Drywall	Rm 175- Coach's office	246	SF	6	\$851	
	Doors - Wood Doors inclu hw	Rm 175- Coach's office	1	EA	6	\$301	
	Floor - Tile/Sheet	Rm 175- Coach's office	246	SF	6	\$246	
	Lighting - Pendent/Surface	Rm 175- Coach's office	2	EA	7	\$0	
	Power Distribution	Rm 175- Coach's office	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 175- Coach's office	448	SF	6	\$1,313	
<b>Gymnasias</b>							
	Bleacher Seating	Rm 178- 1st floor	400	EA	6	\$11,577	
	Ceiling - Exposed	Rm 178- 1st floor	8,021	SF	6	\$11,929	
	Doors - Wood Doors inclu hw	Rm 178- 1st floor	4	EA	6	\$1,204	
	Floor - Wood	Rm 178- 1st floor	8,021	SF	6	\$56,547	
	Lighting - Metal Halide/Sodium Vapor	Rm 178- 1st floor	48	EA	7	\$0	possibly LED or even Halogen lights
	Scoreboards	Rm 178- 1st floor	1	EA	6	\$2,244	
	Sound System	Rm 178- 1st floor	1	EA	6	\$41,654	
	Storage/ Closet	Rm 178- 1st floor	458	SF	6	\$3,321	1 storage door is damaged
	Walls - Concrete Block	Rm 178- 1st floor	8,303	SF	6	\$24,340	
<b>Restroom</b>							
	Accessories	Unisex- Next to 175	125	SF	6	\$1,153	
	Ceiling - Plaster/Drywall	Unisex- Next to 175	40	SF	5	\$430	mildew & water damaged
	Ceiling - Plaster/Drywall	Unisex- Next to 175	125	SF	6	\$433	
	Doors - Wood Doors inclu hw	Unisex- Next to 175	1	EA	6	\$301	
	Floor Drain	Unisex- Next to 175	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	Unisex- Next to 175	125	SF	6	\$265	
	Hand Dryer	Unisex- Next to 175	1	EA	6	\$230	
	Lavatory	Unisex- Next to 175	1	EA	6	\$320	
	Lighting - Pendent/Surface	Unisex- Next to 175	1	EA	7	\$0	
	Walls - Concrete Block	Unisex- Next to 175	310	SF	6	\$909	
	Water Closet	Unisex- Next to 175	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal:**
**\$169,462**
**Building: Addition 3**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	120	SF	6	\$360	

## Building: Addition 3

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Plaster/Drywall	1st Floor	30	SF	5	\$523	water damaged by door 13
	Ceiling - Plaster/Drywall	1st Floor	919	SF	6	\$5,690	
	Floor - Tile/Sheet	1st Floor	8	SF	5	\$46	damaged at transition from addition 3 to 1
	Floor - Tile/Sheet	1st Floor	1,069	SF	6	\$581	
	Lighting - Lay-in	1st Floor	2	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	16	EA	7	\$0	
	Stairs - Terrazzo	1st Floor	3	LF	6	\$28	
	Walls - Concrete Block	1st Floor	428	SF	6	\$1,255	
	Walls - Masonry	1st Floor	2	SF	5	\$114	cap on knee wall is broken off
	Walls - Masonry	1st Floor	1,402	SF	6	\$4,411	
<b>Safety</b>							
	Security Cameras		2	EA	6	\$388	
	Security Cameras		2	EA	6	\$388	

**Building Interior Subtotal:** **\$13,785**

**Total Building Cost** **\$711,867**

## Building: Addition 4

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Entrance Control - Audio and Video	#15 N	1	EA	6	\$702	
	Exterior Doors - Exterior Steel Door	#16 N	2	EA	6	\$961	
	Exterior Doors - Exterior Steel Door	#17 N	4	EA	6	\$1,922	
	Exterior Doors - Exterior Steel Door	#17.1_Exit E	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#17.2_Exit E	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#17.3 E	1	EA	6	\$481	
	Exterior Doors - Exterior Steel Door	#17.4_Exit E	1	EA	6	\$481	
	Exterior Doors - Exterior Wood Door	#1 S	6	EA	6	\$2,883	
	Exterior Doors - Exterior Wood Door	#15 N	6	EA	6	\$2,883	
	Exterior Doors - Side lite	#17.1_Exit E	3	EA	6	\$940	
	Exterior Doors - Side lite	#17.2_Exit E	3	EA	6	\$940	
	Exterior Doors - Side lite	#17.4_Exit E	3	EA	6	\$940	
	Exterior Doors - Transom Lite	#1 S	6	EA	6	\$1,880	
	Exterior Doors - Transom Lite	#15 N	6	EA	6	\$1,880	

## Building: Addition 4

### Category: Building Exterior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Entrance</b>							
	Exterior Doors - Transom Lite	#17 N	4	EA	6	\$1,253	Metal Panels
	Exterior Doors - Transom Lite	#17.1_Exit E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#17.2_Exit E	1	EA	6	\$313	
	Exterior Doors - Transom Lite	#17.4_Exit E	1	EA	6	\$313	
	Exterior Stairs - Concrete	#1 S	52	LF	6	\$4,252	
	Exterior Stairs - Concrete	#15 N	140	LF	6	\$11,447	
	Exterior Stairs - Concrete	#16 N	30	LF	6	\$2,453	
	Exterior Stairs - Concrete	#17 N	40	LF	6	\$3,271	
	Power Door Operator and Controls	#15 N	1	EA	6	\$0	
	Ramp Handrail - Steel_Ramp Handrail	#16 N	14	LF	6	\$121	
	Ramps - Concrete	#16 N	12	LF	6	\$1,803	
<b>Foundation</b>							
	Foundation - Concrete	Entire Building	893	LF	7	\$0	
	Superstructure - Steel	Entire Building	82,150	SF	7	\$0	
<b>Lighting</b>							
	Exterior Lighting - Parapet or Roof Mounted	Entire Building	3	EA	6	\$1,610	
	Exterior Lighting - Wall Mounted	Entire Building	52	EA	6	\$15,015	
<b>Roof System</b>							
	Chimney - Metal Flue	Entire Building	26	LF	6	\$4,112	At Roof
	Chimney - Metal Flue	Entire Building	27	LF	6	\$4,270	At Elevation
	Coping - Metal	Entire Building	913	LF	6	\$29,324	
	Downspouts - Interior Downspouts	Entire Building	207	LF	6	\$6,879	
	Roof Structure - Steel / Metal Deck/ Concrete Topping	Entire Building	45,640	SF	7	\$0	
	Roof - Asphalt Gravel Ballast	Entire Building	45,640	SF	6	\$464,036	
<b>Walls</b>							
	Exterior Walls - Brick	Entire Building	13,134	SF	6	\$88,274	
<b>Windows</b>							
	Curtain wall - Glazed Single Pane	Entire Building	5,632	SF	6	\$63,141	Cloudy
	Curtain wall - Insulated Panel	Entire Building	2,920	SF	5	\$109,359	Rust/Dents/Holes
	Curtain wall - Louver	Entire Building	896	SF	6	\$10,045	
	Skylite - Lexan	Entire Building / Roof	4,649	SF	6	\$111,089	
<b>Building Exterior Subtotal:</b>						<b>\$950,547</b>	

**Building: Addition 4**
**Category: Electrical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Emergency System</b>							
	Automatic Transfer Switch	Electrical Room	1	EA	6	\$408	
	Emergency A/C Power - Corridors and Stairs	Entire Building	17,550	SF	6	\$5,270	
	Emergency Battery Packs - Corridors and Stairs	Entire Building	7	EA	6	\$1,418	
	Exit Signs - Corridors and Stairs	Entire Building	30	EA	2	\$16,365	
	Exit Signs - Lunchroom	Entire Building / 1st Floor	2	EA	6	\$299	
	Security System - CCTV	Entire Building	82,150	SF	6	\$24,670	
	Security System - Intrusion Detection	Entire Building	82,150	SF	6	\$21,145	
<b>Main Service</b>							
	Independent Electrical Service for emergency power	Electrical Room	1	EA	6	\$2,921	
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	Electrical Room	1	EA	6	\$10,867	
	PA System	Entire Building	82,150	SF	6	\$27,019	also connected to main building
<b>Power Distribution</b>							
	Lighting and Power Panels - 100 A	Entire Building / 1st Floor	1	EA	6	\$299	
	Lighting and Power Panels - 100 A	Entire Building / Electrical Room	1	EA	6	\$299	
	Lighting and Power Panels - Above 100 A	Entire Building / Electrical Room	1	EA	4	\$6,578	no cover, exposed wires and contacts
	Lighting and Power Panels - Above 100 A	Entire Building	7	EA	6	\$3,479	
	Lighting and Power Panels - Above 100 A	Entire Building	5	EA	6	\$2,485	
	Main Distribution Panels - 400 - 600 amp	Entire Building / 1st Floor	2	EA	6	\$1,055	
	Main Distribution Panels - Greater than 600 amp	Entire Building / Electrical Room	1	EA	6	\$730	
	Main Distribution Panels - Less than 400 amp	Entire Building / 2nd Floor	1	EA	6	\$503	
<b>Electrical System Subtotal:</b>						<b>\$125,811</b>	

**Building: Addition 4**
**Category: Safty System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Fire Alarm</b>							
	Fire Alarm Panel	Entire Building / 1st Floor	1	EA	6	\$6,406	alarm panel in room 147A,
	Fire Alarm Strobe Lights	Entire Building	82,150	SF	6	\$29,369	
	Fire Alarm_System	Entire Building	82,150	SF	6	\$39,941	
<b>Safty System Subtotal:</b>						<b>\$75,716</b>	

**Building: Addition 4**
**Category: Mechanical System**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Air Conditioning</b>							
	Chemical Pot Feeder	Site North / Mechanical Room	1	EA	6	\$606	
	Chiller-Air Cooled- Recipricating-Ground Mounted - 101 - 200 tons	Site North / East Courtyard	1	EA	6	\$4,314	6 compressors
	Condensing Unit- Roof Mounted - 5-10 tons	Roof	3	EA	5	\$28,771	
	Glycol Feed	Site North / Mechanical Room	1	EA	6	\$490	
	Pipes - Chilled Water Pipe- Steel	Site North / Entire Building	400	LF	6	\$755	400 LF
	Pressure Fill System	Site North / Mechanical Room	1	EA	6	\$1,405	
<b>Air Handling Systems</b>							
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 15001-20000 cfm	Mechanical Room	1	EA	5	\$64,830	
	Air Handling Unit- Package Multi Zone- Indoor- Hot Water and Chilled Water Coils - 15001-20000 cfm	Mechanical Room	1	EA	5	\$64,830	serves corridors and central area
	Air Intake	Mechanical Room / Façade- NE	1	EA	6	\$5,765	
	Air Intake	Mechanical Room / Façade- NE	1	EA	6	\$5,765	
	Indoor Return Fans- Centrifugal Squirrel Cage - 10001 - 20000 CFM	Mechanical Room	2	EA	6	\$3,714	15000 cfm
	Make Up Air Unit- Roof Mounted- Gas Heating - 6000 - 10,000 cfm	Roof	1	EA	6	\$3,350	
	Zone Dampers	Mechanical Room	10	EA	6	\$8,330	
	Zone Dampers	Mechanical Room	8	EA	6	\$6,664	
<b>Boiler Systems</b>							
	Boiler Auxiliary- Scotch Marine- Hot Water Boiler - 4001 - 6000 MBH	Boiler Room	1	EA	5	\$11,428	
	Chemical Pot Feeder	Boiler Room / Mechanical Room	1	EA	6	\$725	
	Combustion Dampers	Boiler Room / Mechanical Room	1	EA	6	\$409	
	Dual Temperature Pump	Boiler Room / Mechanical Room	1	EA	6	\$374	
	Glycol Feed System	Boiler Room / Mechanical Room	1	EA	6	\$539	
	Non Condensing- Scotch Marine- Hot Water Boiler - 4001 - 6000 MBH	Boiler Room / Mechanical Room	1	EA	5	\$81,651	only 1 boiler
	Piping - Dual Temperature Pipes- Steel	Boiler Room / Entire Building	600	LF	6	\$1,133	
	Water Fill System	Boiler Room / Mechanical Room	1	EA	6	\$1,168	
<b>Heating Devices</b>							
	Fin Tube - Hot Water	Entire Building	200	LF	6	\$1,888	
	Radiators - Hot Water	Entire Building	8	EA	5	\$12,977	in vestibules
<b>Mechanical Plumbing</b>							
	Chilled Water Pump - Less than 10	Mechanical Room	2	EA	6	\$2,222	
	Daul Temperature Pump - Less than 10	Mechanical Room	2	EA	6	\$2,222	
	Hot Water Pump - Less than 10	Boiler Room	1	EA	6	\$1,111	
<b>Temperature Control</b>							
	Pneumatic System	Entire Building	82,150	SF	4	\$427,607	
	Thermostats - Pneumatic	Entire Building	16	EA	6	\$0	internal building rooms

## Building: Addition 4

### Category: Mechanical System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Unit Ventilation</b>							
	Unit Ventilators- Floor Mounted- Hot Water & Chilled Water Coils	Entire Building	28	EA	6	\$34,936	
	Unit Ventilators- Floor Mounted- Hot Water & Chilled Water Coils	Entire Building	3	EA	5	\$32,526	
<b>Ventilation</b>							
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	1	EA	6	\$592	
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	Entire Building / Roof	2	EA	6	\$1,185	
<b>Mechanical System Subtotal:</b>						<b>\$814,282</b>	

## Building: Addition 4

### Category: Plumbing System

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Hot Water</b>							
	Gas Heater - Less than 150000 BTU/HR	Boiler Room	1	EA	6	\$310	
	Hot Water Storage Tank_Gas - 201 - 500 Gallons	Boiler Room	1	EA	6	\$678	
<b>Piping</b>							
	Domestic Piping-Cold Water from Risers to Fixtures	Entire Building	82,150	SF	6	\$16,446	
	Domestic Piping-Cold Water Horizontal Lines	Entire Building	82,150	SF	6	\$19,971	
	Domestic Piping-Cold Water Risers	Entire Building	82,150	SF	6	\$15,272	
	Domestic Piping-Hot Water from Risers to Fixtures	Entire Building	82,150	SF	6	\$12,922	
	Domestic Piping-Hot Water Horizontal Lines	Entire Building	82,150	SF	6	\$15,272	
	Domestic Piping-Hot Water Return Lines	Entire Building	82,150	SF	6	\$11,747	
	Domestic Piping-Hot Water Return Risers	Entire Building	82,150	SF	6	\$11,747	
	Sanitary Piping	Entire Building	82,150	SF	6	\$75,184	
	Storm Piping	Entire Building	82,150	SF	6	\$71,659	
	Vent Piping	Entire Building	82,150	SF	6	\$55,213	
<b>Plumbing System Subtotal:</b>						<b>\$306,422</b>	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #122 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	789	SF	6	\$2,369	
	Ceiling - Lay-in	1st Floor	6	SF	5	\$48	water stains

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #122 (Regular Classroom)</b>							
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	795	SF	6	\$796	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	36	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #123 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	775	SF	6	\$2,327	
	Ceiling - Lay-in	1st Floor	20	SF	5	\$160	water stains
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	36	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #124 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	795	SF	6	\$796	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #125 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	795	SF	6	\$796	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #125 (Regular Classroom)</b>							
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	28	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #126 (Store Room)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	785	SF	6	\$2,357	
	Ceiling - Lay-in	1st Floor	10	SF	5	\$80	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	20	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #127 (Store Room)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	790	SF	6	\$2,372	
	Ceiling - Lay-in	1st Floor	5	SF	5	\$40	water damage
	Chalk Board	1st Floor	20	LF	4	\$1,836	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	795	SF	5	\$3,570	very old
	Lighting - Lay-in	1st Floor	11	EA	7	\$0	
	Lighting - Lay-in	1st Floor	1	EA	6	\$119	missing cover
	Marker Board	1st Floor	28	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #133 (Office)</b>							
	Casework	1st Floor	12	LF	6	\$303	
	Ceiling - Lay-in	1st Floor	576	SF	6	\$1,730	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #133 (Office)</b>							
	Floor - Tile	1st Floor	576	SF	6	\$1,260	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Storage/ Closet	1st Floor	197	SF	6	\$1,428	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #133-B (Unsafe/Unusable Condition)</b>							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	840	SF	6	\$2,523	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	566	SF	5	\$2,541	old
	Floor - Tile/Sheet	1st Floor	274	SF	5	\$1,230	old
	Lighting - Lay-in	1st Floor	14	EA	7	\$0	
	Storage/ Closet	1st Floor	19	SF	6	\$138	missing closet doors
	Walls - Concrete Block	1st Floor	374	SF	5	\$3,840	need painting
	Walls - Masonry	1st Floor	192	SF	5	\$7,935	appears that ext wall may be leaking, sand on floor along the wall
	Walls - Plaster/Drywall	1st Floor	374	SF	5	\$2,835	need painting
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #133-D (Unsafe/Unusable Condition)</b>							
	Casework	1st Floor	9	LF	4	\$4,178	mostly missing
	Ceiling - Lay-in	1st Floor	904	SF	4	\$9,191	mostly missing & damaged tiles (possible leak)
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	904	SF	5	\$1,551	needs a finish material
	Lighting - Lay-in	1st Floor	15	EA	7	\$0	
	Storage/ Closet	1st Floor	19	SF	6	\$138	missing closet doors
	Walls - Concrete Block	1st Floor	482	SF	5	\$4,949	needs paint
	Walls - Masonry	1st Floor	482	SF	6	\$1,516	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #133-E (Unsafe/Unusable Condition)</b>							
	Casework	1st Floor	9	LF	6	\$227	
	Ceiling - Lay-in	1st Floor	892	SF	6	\$2,679	
	Ceiling - Lay-in	1st Floor	5	SF	5	\$40	water stains
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Concrete	1st Floor	897	SF	5	\$1,539	needs a finish material
	Lighting - Lay-in	1st Floor	16	EA	7	\$0	
	Marker Board	1st Floor	12	LF	6	\$257	

**Building: Addition 4**
**Category: Classrooms**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #133-E (Unsafe/Unusable Condition)</b>							
	Storage/ Closet	1st Floor	19	SF	6	\$138	missing closet doors
	Walls - Concrete Block	1st Floor	720	SF	5	\$7,393	needs paint
	Walls - Masonry	1st Floor	240	SF	6	\$755	
	Work Sink	1st Floor	2	EA	6	\$758	
<b>Classroom #134 (Office)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	794	SF	6	\$1,737	
	Floor - Tile	1st Floor	1	SF	5	\$6	missing
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	32	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #135 (Faculty Lounge)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	775	SF	6	\$2,327	
	Ceiling - Lay-in	1st Floor	20	SF	5	\$160	water damage
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	795	SF	6	\$796	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	48	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #136 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	775	SF	6	\$2,327	
	Ceiling - Lay-in	1st Floor	20	SF	5	\$160	water damaged
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	795	SF	6	\$796	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #136 (Regular Classroom)</b>							
	Marker Board	1st Floor	40	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #137 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	785	SF	6	\$2,357	
	Ceiling - Lay-in	1st Floor	10	SF	5	\$80	water stains
	Doors - Side-lite	1st Floor	3	SF	6	\$50	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	795	SF	6	\$796	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	48	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #138 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	48	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #139 (Regular Classroom)</b>							
	Casework	1st Floor	20	LF	6	\$505	
	Ceiling - Lay-in	1st Floor	795	SF	6	\$2,387	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile	1st Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	1st Floor	12	EA	7	\$0	
	Marker Board	1st Floor	48	LF	7	\$0	
	Storage/ Closet	1st Floor	3	SF	6	\$22	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #139 (Regular Classroom)</b>							
	Walls - Concrete Block	1st Floor	815	SF	6	\$2,389	
	Walls - Masonry	1st Floor	60	SF	6	\$189	
<b>Classroom #140J (Other Instructional Use)</b>							
	Ceiling - Lay-in	1st Floor	887	SF	6	\$2,664	
	Doors - Side-lite	1st Floor	8	SF	6	\$134	
	Doors - Transom Window	1st Floor	3	SF	6	\$51	
	Doors - Wood Doors inclu hw	1st Floor	2	EA	6	\$602	
	Floor - Carpet	1st Floor	887	SF	6	\$1,890	
	Lighting - Lay-in	1st Floor	9	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Walls - Concrete Block	1st Floor	726	SF	6	\$2,128	
	Walls - Masonry	1st Floor	242	SF	6	\$761	
<b>Classroom #144 (Other Instructional Use)</b>							
	Ceiling - Lay-in	1st Floor	2,039	SF	6	\$6,123	
	Ceiling - Lay-in	1st Floor	2	SF	5	\$16	water stain
	Doors - Side-lite	1st Floor	60	SF	6	\$1,003	
	Doors - Transom Window	1st Floor	9	SF	6	\$152	
	Doors - Wood Doors inclu hw	1st Floor	3	EA	6	\$903	
	Floor - Carpet	1st Floor	2,041	SF	6	\$4,349	
	Lighting - Lay-in	1st Floor	35	EA	7	\$0	
	Marker Board	1st Floor	24	LF	7	\$0	
	Walls - Concrete Block	1st Floor	1,005	SF	6	\$2,946	
	Walls - Plaster/Drywall	1st Floor	335	SF	6	\$925	
<b>Classroom #222 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	785	SF	6	\$2,357	
	Ceiling - Lay-in	2nd Floor	10	SF	5	\$80	water damage
	Chalk Board	2nd Floor	8	LF	4	\$734	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	32	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #223 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	34	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #224 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	794	SF	6	\$2,384	
	Ceiling - Lay-in	2nd Floor	1	SF	5	\$8	water damaged
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	5	\$1,174	will not shut
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	34	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #225 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Chalk Board	2nd Floor	12	LF	4	\$1,102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	2nd Floor	10	EA	7	\$0	
	Lighting - Lay-in	2nd Floor	2	EA	6	\$238	covers missing
	Marker Board	2nd Floor	22	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #226 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #226 (Regular Classroom)</b>							
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	30	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #227 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	34	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	5	\$8,368	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #228 (Regular Classroom)</b>							
	Casework	2nd Floor	15	LF	6	\$379	
	Ceiling - Lay-in	2nd Floor	945	SF	6	\$2,838	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Tile	2nd Floor	945	SF	6	\$2,068	
	Lighting - Lay-in	2nd Floor	6	EA	7	\$0	
	Marker Board	2nd Floor	22	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	380	SF	6	\$1,114	
	Walls - Plaster/Drywall	2nd Floor	780	SF	6	\$2,153	
<b>Classroom #229 (Science Lab Level 1)</b>							
	Casework	2nd Floor	60	LF	6	\$1,515	
	Ceiling - Lay-in	2nd Floor	1,127	SF	6	\$3,384	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	5	\$1,174	split at lock
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #229 (Science Lab Level 1)</b>							
	Floor - Tile/Sheet	2nd Floor	1,127	SF	6	\$1,128	
	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Lay-in	2nd Floor	19	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	1,340	SF	6	\$3,928	
	Work Sink	2nd Floor	8	EA	6	\$3,032	
<b>Classroom #231 (Physical Education Room)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	1,418	SF	6	\$4,258	
	Doors - Side-lite	2nd Floor	40	SF	6	\$669	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Weight/ Fitness Room Floor Matting	2nd Floor	1,418	SF	6	\$7,422	
	Lighting - Lay-in	2nd Floor	22	EA	7	\$0	
	Storage/ Closet	2nd Floor	6	SF	6	\$44	
	Walls - Concrete Block	2nd Floor	1,630	SF	6	\$4,778	
	Walls - Masonry	2nd Floor	120	SF	6	\$378	
<b>Classroom #232 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	5	\$4,182	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	623	SF	6	\$1,363	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	4	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	4	\$84	solid transom panel above closet is loose & could fall injuring someone
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #233 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #233 (Regular Classroom)</b>							
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	34	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
	Work Sink	2nd Floor	2	EA	6	\$758	
<b>Classroom #235 (Science Lab Level 1)</b>							
	Casework	2nd Floor	66	LF	6	\$1,667	
	Ceiling - Lay-in	2nd Floor	1,211	SF	6	\$3,637	
	Doors - Side-lite	2nd Floor	40	SF	6	\$669	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile	2nd Floor	1,211	SF	6	\$2,650	
	Fume Hood	2nd Floor	1	EA	6	\$816	
	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Lay-in	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	16	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	1,476	SF	6	\$4,327	
	Work Sink	2nd Floor	8	EA	6	\$3,032	
<b>Classroom #236 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	795	SF	6	\$1,739	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	32	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #237 (Regular Classroom)</b>							
	Casework	1st Floor	10	LF	6	\$253	inside the closet now
	Ceiling - Lay-in	1st Floor	640	SF	6	\$1,922	
	Doors - Side-lite	1st Floor	20	SF	6	\$334	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #237 (Regular Classroom)</b>							
	Doors - Wood Doors inclu hw	1st Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	1st Floor	640	SF	6	\$641	
	Lighting - Lay-in	1st Floor	10	EA	7	\$0	
	Lighting - Pendent/Surface	1st Floor	3	EA	6	\$372	can lights
	Marker Board	1st Floor	34	LF	7	\$0	
	Storage/ Closet	1st Floor	117	SF	6	\$848	
	Walls - Concrete Block	1st Floor	720	SF	6	\$2,111	
	Walls - Masonry	1st Floor	80	SF	6	\$252	
<b>Classroom #238 (Regular Classroom)</b>							
	Ceiling - Lay-in	2nd Floor	794	SF	6	\$2,384	
	Ceiling - Lay-in	2nd Floor	1	SF	5	\$8	water stain
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile	2nd Floor	791	SF	6	\$1,731	
	Floor - Tile	2nd Floor	4	SF	5	\$23	damaged
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	30	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	54	SF	6	\$170	
	Walls - Masonry	2nd Floor	6	SF	5	\$343	efflorescence
<b>Classroom #239 (Regular Classroom)</b>							
	Casework	2nd Floor	20	LF	6	\$505	
	Ceiling - Lay-in	2nd Floor	795	SF	6	\$2,387	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Wood Doors inclu hw	2nd Floor	1	EA	6	\$301	
	Floor - Tile/Sheet	2nd Floor	795	SF	6	\$796	
	Lighting - Lay-in	2nd Floor	12	EA	7	\$0	
	Marker Board	2nd Floor	34	LF	7	\$0	
	Storage/ Closet	2nd Floor	3	SF	6	\$22	
	Walls - Concrete Block	2nd Floor	815	SF	6	\$2,389	
	Walls - Masonry	2nd Floor	60	SF	6	\$189	
<b>Classroom #240 (Computer Lab)</b>							
	Ceiling - Lay-in	2nd Floor	1,299	SF	6	\$3,901	
	Doors - Side-lite	2nd Floor	40	SF	6	\$669	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classroom #240 (Computer Lab)</b>							
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Floor - Carpet	2nd Floor	1,299	SF	6	\$2,768	
	Lighting - Lay-in	2nd Floor	24	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Walls - Concrete Block	2nd Floor	1,340	SF	6	\$3,928	
	Wireless System	2nd Floor	1	EA	6	\$372	
<b>Classroom #241 (Science Lab Level 1)</b>							
	Casework	2nd Floor	80	LF	6	\$2,020	
	Ceiling - Lay-in	2nd Floor	1,407	SF	6	\$4,225	
	Doors - Side-lite	2nd Floor	40	SF	6	\$669	
	Doors - Transom Window	2nd Floor	12	SF	6	\$203	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile	2nd Floor	1,407	SF	6	\$3,078	
	Gas Line	2nd Floor	9	EA	6	\$4,582	
	Lighting - Lay-in	2nd Floor	22	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	1,340	SF	6	\$3,928	
	Work Sink	2nd Floor	9	EA	6	\$3,411	
<b>Classroom #242 (Science Lab Level 1)</b>							
	Casework	2nd Floor	80	LF	6	\$2,020	
	Ceiling - Lay-in	2nd Floor	1,131	SF	6	\$3,396	
	Doors - Side-lite	2nd Floor	20	SF	6	\$334	
	Doors - Transom Window	2nd Floor	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	2nd Floor	2	EA	6	\$602	
	Eye Wash Station	2nd Floor	1	EA	6	\$336	
	Floor - Tile	2nd Floor	1,131	SF	6	\$2,475	
	Gas Line	2nd Floor	8	EA	6	\$4,073	
	Lighting - Lay-in	2nd Floor	20	EA	7	\$0	
	Marker Board	2nd Floor	24	LF	7	\$0	
	Science Lab Shower	2nd Floor	1	EA	6	\$379	
	Walls - Concrete Block	2nd Floor	1,340	SF	6	\$3,928	
	Work Sink	2nd Floor	8	EA	6	\$3,032	

## Building: Addition 4

### Category: Classrooms

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Classrooms Subtotal:</b>						<b>\$411,166</b>	

## Building: Addition 4

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Ceiling - Lay-in	Rm 128B- Library Work Rm	265	SF	6	\$796	
	Doors - Wood Doors inclu hw	Rm 128B- Library Work Rm	2	EA	6	\$602	
	Floor - Carpet	Rm 128B- Library Work Rm	265	SF	6	\$565	
	Lighting - Lay-in	Rm 128B- Library Work Rm	3	EA	7	\$0	
	Power Distribution	Rm 128B- Library Work Rm	14	EA	6	\$29,748	
	Walls - Concrete Block	Rm 128B- Library Work Rm	425	SF	6	\$1,246	
	Ceiling - Lay-in	Rm 128C- Social Work Office	358	SF	6	\$1,075	
	Doors - Wood Doors inclu hw	Rm 128C- Social Work Office	1	EA	6	\$301	
	Floor - Carpet	Rm 128C- Social Work Office	358	SF	6	\$763	
	Lighting - Lay-in	Rm 128C- Social Work Office	6	EA	7	\$0	
	Power Distribution	Rm 128C- Social Work Office	8	EA	6	\$16,999	
	Walls - Concrete Block	Rm 128C- Social Work Office	425	SF	6	\$1,246	
	Walls - Plaster/Drywall	Rm 128C- Social Work Office	223	SF	6	\$615	
	Ceiling - Lay-in	Rm 129- Conference Rm/Security Suite	367	SF	6	\$1,102	
	Doors - Side-lite	Rm 129- Conference Rm/Security Suite	14	SF	6	\$234	
	Doors - Transom Window	Rm 129- Conference Rm/Security Suite	3	SF	6	\$51	
	Doors - Wood Doors inclu hw	Rm 129- Conference Rm/Security Suite	1	EA	6	\$301	
	Floor - Carpet	Rm 129- Conference Rm/Security Suite	367	SF	6	\$782	
	Lighting - Lay-in	Rm 129- Conference Rm/Security Suite	6	EA	7	\$0	
	Power Distribution	Rm 129- Conference Rm/Security Suite	8	EA	6	\$16,999	
	Walls - Concrete Block	Rm 129- Conference Rm/Security Suite	154	SF	6	\$451	
	Walls - Plaster/Drywall	Rm 129- Conference Rm/Security Suite	462	SF	6	\$1,275	
	Ceiling - Lay-in	Rm 140- Administrators Office	528	SF	6	\$1,586	
	Doors - Side-lite	Rm 140- Administrators Office	140	SF	6	\$2,340	
	Doors - Transom Window	Rm 140- Administrators Office	3	SF	6	\$51	
	Doors - Wood Doors inclu hw	Rm 140- Administrators Office	1	EA	6	\$301	
	Floor - Carpet	Rm 140- Administrators Office	528	SF	6	\$1,125	
	Lighting - Lay-in	Rm 140- Administrators Office	6	EA	7	\$0	
	Power Distribution	Rm 140- Administrators Office	16	EA	6	\$33,998	
	Walls - Concrete Block	Rm 140- Administrators Office	736	SF	6	\$2,158	
	Ceiling - Lay-in	Rm 140A- Principals Office	395	SF	6	\$1,186	

**Building: Addition 4**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Doors - Side-lite	Rm 140A- Principals Office	8	SF	6	\$134	
	Doors - Wood Doors inclu hw	Rm 140A- Principals Office	2	EA	6	\$602	
	Floor - Carpet	Rm 140A- Principals Office	395	SF	6	\$842	
	Lighting - Lay-in	Rm 140A- Principals Office	6	EA	7	\$0	
	Power Distribution	Rm 140A- Principals Office	14	EA	6	\$29,748	
	Walls - Concrete Block	Rm 140A- Principals Office	652	SF	6	\$1,911	
	Ceiling - Lay-in	Rm 140C- Admin Office	91	SF	6	\$273	
	Doors - Side-lite	Rm 140C- Admin Office	40	SF	6	\$669	
	Doors - Wood Doors inclu hw	Rm 140C- Admin Office	1	EA	6	\$301	
	Floor - Carpet	Rm 140C- Admin Office	91	SF	6	\$194	
	Lighting - Lay-in	Rm 140C- Admin Office	2	EA	7	\$0	
	Power Distribution	Rm 140C- Admin Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 140C- Admin Office	312	SF	6	\$915	
	Ceiling - Lay-in	Rm 140G- Deans Office	395	SF	6	\$1,186	
	Doors - Side-lite	Rm 140G- Deans Office	40	SF	6	\$669	
	Doors - Wood Doors inclu hw	Rm 140G- Deans Office	1	EA	6	\$301	
	Floor - Carpet	Rm 140G- Deans Office	395	SF	6	\$842	
	Lighting - Lay-in	Rm 140G- Deans Office	2	EA	7	\$0	
	Power Distribution	Rm 140G- Deans Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 140G- Deans Office	444	SF	6	\$1,302	
	Ceiling - Lay-in	Rm 140H-Asst Principals Office	395	SF	6	\$1,186	
	Doors - Side-lite	Rm 140H-Asst Principals Office	40	SF	6	\$669	
	Doors - Wood Doors inclu hw	Rm 140H-Asst Principals Office	1	EA	6	\$301	
	Floor - Carpet	Rm 140H-Asst Principals Office	395	SF	6	\$842	
	Lighting - Lay-in	Rm 140H-Asst Principals Office	2	EA	7	\$0	
	Power Distribution	Rm 140H-Asst Principals Office	6	EA	6	\$12,749	
	Walls - Concrete Block	Rm 140H-Asst Principals Office	444	SF	6	\$1,302	
	Ceiling - Lay-in	Rm 141B- Laundry Rm	26	SF	6	\$78	
	Doors - Wood Doors inclu hw	Rm 141B- Laundry Rm	1	EA	6	\$301	
	Floor - Tile	Rm 141B- Laundry Rm	26	SF	6	\$57	
	Lighting - Lay-in	Rm 141B- Laundry Rm	1	EA	7	\$0	
	Power Distribution	Rm 141B- Laundry Rm	2	EA	6	\$4,250	
	Walls - Plaster/Drywall	Rm 141B- Laundry Rm	164	SF	6	\$453	
	Work Sink	Rm 141B- Laundry Rm	1	EA	6	\$508	
	Ceiling - Lay-in	Rm 141C- Sports Equipment Rm	304	SF	6	\$913	
	Doors - Wood Doors inclu hw	Rm 141C- Sports Equipment Rm	1	EA	6	\$301	
	Floor - Tile	Rm 141C- Sports Equipment Rm	304	SF	6	\$665	

## Building: Addition 4

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Administrative Suites/Offices</b>							
	Lighting - Lay-in	Rm 141C- Sports Equipment Rm	5	EA	7	\$0	
	Power Distribution	Rm 141C- Sports Equipment Rm	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 141C- Sports Equipment Rm	321	SF	6	\$941	
	Walls - Plaster/Drywall	Rm 141C- Sports Equipment Rm	321	SF	6	\$886	
	Ceiling - Lay-in	Rm 145 (in 129)-Security Office	199	SF	6	\$598	
	Doors - Side-lite	Rm 145 (in 129)-Security Office	20	SF	6	\$334	
	Doors - Transom Window	Rm 145 (in 129)-Security Office	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	Rm 145 (in 129)-Security Office	1	EA	6	\$301	
	Floor - Carpet	Rm 145 (in 129)-Security Office	199	SF	6	\$424	
	Lighting - Lay-in	Rm 145 (in 129)-Security Office	3	EA	7	\$0	
	Power Distribution	Rm 145 (in 129)-Security Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 145 (in 129)-Security Office	236	SF	6	\$692	
	Walls - Plaster/Drywall	Rm 145 (in 129)-Security Office	236	SF	6	\$651	
	Ceiling - Lay-in	Rm 146 (in 129)- Conference Rm	199	SF	6	\$598	
	Doors - Side-lite	Rm 146 (in 129)- Conference Rm	20	SF	6	\$334	
	Doors - Transom Window	Rm 146 (in 129)- Conference Rm	6	SF	6	\$102	
	Doors - Wood Doors inclu hw	Rm 146 (in 129)- Conference Rm	1	EA	6	\$301	
	Floor - Carpet	Rm 146 (in 129)- Conference Rm	199	SF	6	\$424	
	Lighting - Lay-in	Rm 146 (in 129)- Conference Rm	3	EA	7	\$0	
	Power Distribution	Rm 146 (in 129)- Conference Rm	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 146 (in 129)- Conference Rm	236	SF	6	\$692	
	Walls - Plaster/Drywall	Rm 146 (in 129)- Conference Rm	236	SF	6	\$651	
	Ceiling - Lay-in	Rm 228A- Special Ed Teacher's Office	767	SF	6	\$2,303	
	Doors - Wood Doors inclu hw	Rm 228A- Special Ed Teacher's Office	2	EA	6	\$602	
	Floor - Tile	Rm 228A- Special Ed Teacher's Office	767	SF	6	\$1,678	
	Lighting - Lay-in	Rm 228A- Special Ed Teacher's Office	9	EA	7	\$0	
	Power Distribution	Rm 228A- Special Ed Teacher's Office	12	EA	6	\$25,499	
	Walls - Concrete Block	Rm 228A- Special Ed Teacher's Office	506	SF	6	\$1,483	
	Walls - Plaster/Drywall	Rm 228A- Special Ed Teacher's Office	506	SF	6	\$1,397	
	Work Slnk	Rm 228A- Special Ed Teacher's Office	2	EA	6	\$1,016	
	Ceiling - Lay-in	Rm 244- Social Work Office	331	SF	6	\$994	
	Doors - Side-lite	Rm 244- Social Work Office	10	SF	6	\$167	
	Doors - Wood Doors inclu hw	Rm 244- Social Work Office	1	EA	6	\$301	
	Floor - Carpet	Rm 244- Social Work Office	331	SF	6	\$705	
	Lighting - Lay-in	Rm 244- Social Work Office	6	EA	7	\$0	
	Power Distribution	Rm 244- Social Work Office	4	EA	6	\$8,500	
	Walls - Concrete Block	Rm 244- Social Work Office	596	SF	6	\$1,747	

## Building: Addition 4

### Category: Rooms (Other Than Classrooms)

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Library</b>							
	Casework	Room 128	60	LF	6	\$1,515	
	Ceiling - Lay-in	Room 128	4,052	SF	6	\$12,168	
	Doors - Side-lite	Room 128	42	SF	6	\$702	
	Doors - Wood Doors inclu hw	Room 128	4	EA	6	\$1,204	
	Floor - Tile/Sheet	Room 128	4,052	SF	6	\$4,056	
	Lighting - Lay-in	Room 128	60	EA	7	\$0	
	Walls - Concrete Block	Room 128	1,350	SF	6	\$3,958	
	Walls - Masonry	Room 128	830	SF	6	\$2,611	
<b>Locker/Shower Room</b>							
	Accessories	2nd flr Boys- By 232	453	SF	6	\$1,775	
	Benches, ped mounted	2nd flr Boys- By 232	10	LF	6	\$1,089	
	Ceiling - Plaster/ Drywall	2nd flr Boys- By 232	453	SF	6	\$1,568	
	Doors - Wood Doors inclu hw	2nd flr Boys- By 232	2	EA	6	\$602	
	Floor Drain	2nd flr Boys- By 232	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd flr Boys- By 232	453	SF	6	\$959	
	Hand Dryer	2nd flr Boys- By 232	1	EA	6	\$230	
	Lavatory	2nd flr Boys- By 232	2	EA	6	\$639	
	Lavatory	2nd flr Boys- By 232	1	EA	5	\$3,763	out of order
	Lighting - Pendent/Surface	2nd flr Boys- By 232	8	EA	7	\$0	
	Partitions	2nd flr Boys- By 232	1	EA	6	\$297	
	Student Lockers - One Tier	2nd flr Boys- By 232	2	EA	6	\$186	
	Student Lockers - Two Tier	2nd flr Boys- By 232	28	EA	6	\$1,300	
	Urinals	2nd flr Boys- By 232	5	EA	6	\$1,680	
	Walls - Concrete Block	2nd flr Boys- By 232	555	SF	6	\$1,627	
	Walls - Plaster/Drywall	2nd flr Boys- By 232	277	SF	6	\$764	
	Water Closet	2nd flr Boys- By 232	1	EA	6	\$336	
	Accessories	2nd flr Girls- By 231	453	SF	6	\$1,775	
	Benches, ped mounted	2nd flr Girls- By 231	10	LF	6	\$1,089	
	Ceiling - Plaster/ Drywall	2nd flr Girls- By 231	453	SF	6	\$1,568	
	Doors - Wood Doors inclu hw	2nd flr Girls- By 231	2	EA	6	\$602	
	Floor Drain	2nd flr Girls- By 231	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd flr Girls- By 231	453	SF	6	\$959	
	Hand Dryer	2nd flr Girls- By 231	1	EA	6	\$230	
	Lavatory	2nd flr Girls- By 231	2	EA	6	\$639	
	Lavatory	2nd flr Girls- By 231	1	EA	5	\$3,763	out of order
	Lighting - Pendent/Surface	2nd flr Girls- By 231	8	EA	7	\$0	
	Partitions	2nd flr Girls- By 231	5	EA	6	\$1,485	

**Building: Addition 4**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Locker/Shower Room</b>							
	Walls - Concrete Block	2nd flr Girls- By 231	555	SF	6	\$1,627	
	Walls - Plaster/Drywall	2nd flr Girls- By 231	274	SF	6	\$756	
	Water Closet	2nd flr Girls- By 231	5	EA	6	\$1,680	
<b>Lunch &amp; Multipurpose Room</b>							
	Ceiling - Lay-in	Rm 140E- Staff Lounge	826	SF	6	\$2,480	
	Doors - Side-lite	Rm 140E- Staff Lounge	16	SF	6	\$267	
	Doors - Transom Window	Rm 140E- Staff Lounge	3	SF	6	\$51	
	Doors - Wood Doors inclu hw	Rm 140E- Staff Lounge	2	EA	6	\$602	
	Floor - Carpet	Rm 140E- Staff Lounge	826	SF	6	\$1,760	
	Lighting - Lay-in	Rm 140E- Staff Lounge	13	EA	7	\$0	
	Walls - Concrete Block	Rm 140E- Staff Lounge	1,008	SF	6	\$2,955	
	Ceiling - Lay-in	Rm 200N- Faculty Lounge	347	SF	6	\$1,042	
	Doors - Wood Doors inclu hw	Rm 200N- Faculty Lounge	1	EA	6	\$301	
	Floor - Carpet	Rm 200N- Faculty Lounge	347	SF	6	\$739	
	Lighting - Lay-in	Rm 200N- Faculty Lounge	6	EA	7	\$0	
	Market Board	Rm 200N- Faculty Lounge	8	LF	7	\$0	
	Walls - Concrete Block	Rm 200N- Faculty Lounge	604	SF	6	\$1,771	
	Ceiling - Lay-in	Rm- 230 2nd floor	3,424	SF	6	\$10,282	
	Doors - Side-lite	Rm- 230 2nd floor	60	SF	6	\$1,003	
	Doors - Transom Window	Rm- 230 2nd floor	18	SF	6	\$305	
	Doors - Wood Doors inclu hw	Rm- 230 2nd floor	3	EA	6	\$903	
	Floor - Tile	Rm- 230 2nd floor	3,424	SF	6	\$7,491	
	Lighting - Lay-in	Rm- 230 2nd floor	45	EA	7	\$0	
	Serving Line	Rm- 230 2nd floor	21	LF	6	\$1,250	
	Walls - Concrete Block	Rm- 230 2nd floor	964	SF	6	\$2,826	
	Walls - Metal Panel	Rm- 230 2nd floor	482	SF	6	\$3,598	FRP
	Walls - Plaster/Drywall	Rm- 230 2nd floor	482	SF	6	\$1,330	
<b>Mechanical/ Service Rooms</b>							
	Janitor's Closet	1st Floor	64	SF	6	\$459	
	Mechanical/ Service Rooms	1st Floor	1,027	SF	6	\$7,358	Rm 100U & 147B
	Storage Room	1st Floor	269	SF	6	\$1,927	Rm 147A
	Janitor's Closet	2nd Floor	45	SF	6	\$322	
	Janitor's Closet	2nd Floor	65	SF	5	\$1,048	T12 fixture inside (near Rm 241)
	Mechanical/ Service Rooms	2nd Floor	50	SF	5	\$807	part of 200-J has water damage
	Mechanical/ Service Rooms	2nd Floor	1,158	SF	6	\$8,296	Electrical Closet & 200-J

**Building: Addition 4**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Prep Room</b>							
	Casework	Rm 229A- Science Prep Room	16	LF	6	\$404	
	Ceiling - Lay-in	Rm 229A- Science Prep Room	395	SF	6	\$1,186	
	Doors - Wood Doors inclu hw	Rm 229A- Science Prep Room	1	EA	6	\$301	
	Floor - Tile	Rm 229A- Science Prep Room	395	SF	6	\$864	
	Lighting - Lay-in	Rm 229A- Science Prep Room	4	EA	7	\$0	
	Walls - Concrete Block	Rm 229A- Science Prep Room	680	SF	6	\$1,993	
	Work Sink	Rm 229A- Science Prep Room	1	EA	6	\$379	
	Casework	Rm 235A- Science Prep Room	16	LF	6	\$404	
	Ceiling - Lay-in	Rm 235A- Science Prep Room	229	SF	6	\$688	
	Doors - Wood Doors inclu hw	Rm 235A- Science Prep Room	1	EA	6	\$301	
	Floor - Tile	Rm 235A- Science Prep Room	229	SF	6	\$501	
	Lighting - Lay-in	Rm 235A- Science Prep Room	3	EA	7	\$0	
	Walls - Concrete Block	Rm 235A- Science Prep Room	600	SF	6	\$1,759	
	Work Sink	Rm 235A- Science Prep Room	1	EA	6	\$379	
	Casework	Rm 241A- Science Prep Room	16	LF	6	\$404	
	Ceiling - Lay-in	Rm 241A- Science Prep Room	267	SF	6	\$802	
	Doors - Wood Doors inclu hw	Rm 241A- Science Prep Room	1	EA	6	\$301	
	Floor - Tile	Rm 241A- Science Prep Room	267	SF	6	\$584	
	Lighting - Lay-in	Rm 241A- Science Prep Room	3	EA	7	\$0	
	Walls - Concrete Block	Rm 241A- Science Prep Room	600	SF	6	\$1,759	
	Work Sink	Rm 241A- Science Prep Room	1	EA	6	\$379	
<b>Restroom</b>							
	Accessories	1st flr Boy's- by 139	286	SF	6	\$2,638	
	Ceiling - Plaster/Drywall	1st flr Boy's- by 139	286	SF	6	\$990	
	Doors - Wood Doors inclu hw	1st flr Boy's- by 139	2	EA	6	\$602	
	Floor Drain	1st flr Boy's- by 139	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr Boy's- by 139	286	SF	6	\$605	
	Hand Dryer	1st flr Boy's- by 139	1	EA	6	\$230	
	Lavatory	1st flr Boy's- by 139	3	EA	6	\$959	
	Lighting - Pendent/Surface	1st flr Boy's- by 139	6	EA	7	\$0	
	Partitions	1st flr Boy's- by 139	1	EA	6	\$297	
	Urinals	1st flr Boy's- by 139	5	EA	6	\$1,680	
	Walls - Concrete Block	1st flr Boy's- by 139	569	SF	6	\$1,668	
	Water Closet	1st flr Boy's- by 139	1	EA	6	\$336	
	Accessories	1st flr Girls- by 139	275	SF	6	\$2,536	
	Ceiling - Plaster/Drywall	1st flr Girls- by 139	275	SF	6	\$952	
	Doors - Wood Doors inclu hw	1st flr Girls- by 139	2	EA	6	\$602	

**Building: Addition 4**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor Drain	1st flr Girls- by 139	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st flr Girls- by 139	275	SF	6	\$582	
	Hand Dryer	1st flr Girls- by 139	1	EA	6	\$230	
	Lavatory	1st flr Girls- by 139	3	EA	6	\$959	
	Lighting - Pendant/Surface	1st flr Girls- by 139	6	EA	7	\$0	
	Partitions	1st flr Girls- by 139	5	EA	6	\$1,485	
	Walls - Concrete Block	1st flr Girls- by 139	553	SF	6	\$1,621	
	Water Closet	1st flr Girls- by 139	5	EA	6	\$1,680	
	Accessories	1st Flr- Unisex across from 144	113	SF	6	\$1,042	
	Ceiling - Plaster/Drywall	1st Flr- Unisex across from 144	113	SF	6	\$391	
	Doors - Wood Doors inclu hw	1st Flr- Unisex across from 144	1	EA	6	\$301	
	Floor Drain	1st Flr- Unisex across from 144	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	1st Flr- Unisex across from 144	113	SF	6	\$239	
	Hand Dryer	1st Flr- Unisex across from 144	1	EA	6	\$230	
	Lavatory	1st Flr- Unisex across from 144	1	EA	6	\$320	
	Lighting - Pendant/Surface	1st Flr- Unisex across from 144	2	EA	7	\$0	
	Showers	1st Flr- Unisex across from 144	1	EA	6	\$311	
	Student Lockers - One Tier	1st Flr- Unisex across from 144	2	EA	6	\$186	
	Walls - Plaster/Drywall	1st Flr- Unisex across from 144	258	SF	6	\$712	
	Walls - Tile Ceramic/ Porcelain	1st Flr- Unisex across from 144	86	SF	6	\$194	
	Water Closet	1st Flr- Unisex across from 144	1	EA	6	\$336	
	Accessories	2nd flr Boy's- by 239	286	SF	6	\$2,638	
	Ceiling - Plaster/Drywall	2nd flr Boy's- by 239	286	SF	6	\$990	
	Doors - Wood Doors inclu hw	2nd flr Boy's- by 239	2	EA	6	\$602	
	Floor Drain	2nd flr Boy's- by 239	1	EA	6	\$1,059	
	Floor - Tile Ceramic/ Porcelain	2nd flr Boy's- by 239	286	SF	6	\$605	
	Hand Dryer	2nd flr Boy's- by 239	1	EA	6	\$230	
	Lavatory	2nd flr Boy's- by 239	3	EA	6	\$959	
	Lighting - Pendant/Surface	2nd flr Boy's- by 239	6	EA	7	\$0	
	Partitions	2nd flr Boy's- by 239	1	EA	6	\$297	
	Urinals	2nd flr Boy's- by 239	5	EA	6	\$1,680	
	Walls - Concrete Block	2nd flr Boy's- by 239	569	SF	6	\$1,668	
	Water Closet	2nd flr Boy's- by 239	1	EA	6	\$336	
	Accessories	2nd flr Girls- across from 241	275	SF	6	\$2,536	
	Ceiling - Plaster/Drywall	2nd flr Girls- across from 241	275	SF	6	\$952	
	Doors - Wood Doors inclu hw	2nd flr Girls- across from 241	2	EA	6	\$602	
	Floor Drain	2nd flr Girls- across from 241	1	EA	6	\$1,059	

**Building: Addition 4**
**Category: Rooms (Other Than Classrooms)**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Restroom</b>							
	Floor - Tile Ceramic/ Porcelain	2nd flr Girls- across from 241	275	SF	6	\$582	
	Hand Dryer	2nd flr Girls- across from 241	1	EA	6	\$230	
	Lavatory	2nd flr Girls- across from 241	3	EA	6	\$959	
	Lighting - Pendent/Surface	2nd flr Girls- across from 241	6	EA	7	\$0	
	Partitions	2nd flr Girls- across from 241	5	EA	6	\$1,485	
	Walls - Concrete Block	2nd flr Girls- across from 241	553	SF	6	\$1,621	
	Water Closet	2nd flr Girls- across from 241	5	EA	6	\$1,680	
	Accessories	2nd flr Unisex- by 233	61	SF	6	\$563	
	Ceiling - Plaster/Drywall	2nd flr Unisex- by 233	61	SF	6	\$211	
	Doors - Wood Doors inclu hw	2nd flr Unisex- by 233	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd flr Unisex- by 233	61	SF	6	\$129	
	Hand Dryer	2nd flr Unisex- by 233	1	EA	6	\$230	
	Lavatory	2nd flr Unisex- by 233	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd flr Unisex- by 233	2	EA	7	\$0	
	Walls - Concrete Block	2nd flr Unisex- by 233	240	SF	6	\$704	
	Water Closet	2nd flr Unisex- by 233	1	EA	6	\$336	
	Accessories	2nd flr Unisex- by 244	61	SF	6	\$563	
	Ceiling - Plaster/Drywall	2nd flr Unisex- by 244	61	SF	6	\$211	
	Doors - Wood Doors inclu hw	2nd flr Unisex- by 244	1	EA	6	\$301	
	Floor - Tile Ceramic/ Porcelain	2nd flr Unisex- by 244	61	SF	6	\$129	
	Hand Dryer	2nd flr Unisex- by 244	1	EA	6	\$230	
	Lavatory	2nd flr Unisex- by 244	1	EA	6	\$320	
	Lighting - Pendent/Surface	2nd flr Unisex- by 244	2	EA	7	\$0	
	Walls - Concrete Block	2nd flr Unisex- by 244	240	SF	6	\$704	
	Water Closet	2nd flr Unisex- by 244	1	EA	6	\$336	

**Rooms (Other Than Classrooms) Subtotal: \$471,605**
**Building: Addition 4**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Ceiling - Lay-in	1st Floor	53	SF	5	\$473	water stains/damage
	Ceiling - Lay-in	1st Floor	8,912	SF	6	\$26,763	
	Doors - Steel Doors incl hw	1st Floor	16	EA	5	\$22,062	
	Doors - Transom Window	1st Floor	20	EA	6	\$339	
	Drinking Fountains - Single Fountain	1st Floor	2	EA	6	\$551	

**Building: Addition 4**
**Category: Building Interior**

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Corridor</b>							
	Drinking Fountains - Single Water Cooler	1st Floor	4	EA	5	\$12,029	
	Floor - Tile/Sheet	1st Floor	8,965	SF	6	\$4,872	
	Lighting - Lay-in	1st Floor	90	EA	7	\$0	
	Student Lockers - One Tier	1st Floor	385	EA	6	\$35,742	
	Walls - Concrete Block	1st Floor	10,153	SF	5	\$104,245	
	Walls - Masonry	1st Floor	1,749	SF	6	\$5,502	
	Walls - Plaster/Drywall	1st Floor	1,403	SF	6	\$6,219	
	Ceiling - Lay-in	2nd Floor	16	SF	5	\$143	water stains
	Ceiling - Lay-in	2nd Floor	8,325	SF	6	\$25,000	
	Doors - Steel Doors incl hw	2nd Floor	8	EA	6	\$2,408	
	Doors - Transom Window	2nd Floor	20	EA	6	\$339	
	Drinking Fountains - Single Fountain	2nd Floor	4	EA	6	\$1,103	
	Floor - Tile/Sheet	2nd Floor	8,341	SF	6	\$4,532	
	Lighting - Lay-in	2nd Floor	14	EA	6	\$1,666	
	Lighting - Pendent/Surface	2nd Floor	78	EA	7	\$0	
	Stairs - Terrazzo	2nd Floor	3	LF	6	\$28	
	Student Lockers - One Tier	2nd Floor	363	EA	6	\$33,699	
	Walls - Concrete Block	2nd Floor	10,153	SF	6	\$29,764	
	Walls - Masonry	2nd Floor	597	SF	6	\$1,878	
	Walls - Plaster/Drywall	2nd Floor	1,403	SF	6	\$6,219	
<b>Safety</b>							
	Camera Viewing Station		2	EA	6	\$1,365	Principal & Security Office
	Security Cameras		32	EA	6	\$6,209	20 were added in 2015
	Security Cameras		1	EA	6	\$194	
<b>Stairs</b>							
	Ceiling - Lay-in	North East Stairwell	332	SF	6	\$997	
	Floor - Tile	North East Stairwell	148	SF	6	\$80	
	Handrails	North East Stairwell	54	LF	6	\$468	
	Lighting - Lay-in	North East Stairwell	4	EA	7	\$0	
	Stairs - Tile	North East Stairwell	24	LF	6	\$223	
	Walls - Masonry	North East Stairwell	1,190	SF	6	\$3,744	
	Ceiling - Lay-in	South East Stairwell	332	SF	6	\$997	
	Floor - Tile	South East Stairwell	148	SF	6	\$80	
	Handrails	South East Stairwell	54	LF	6	\$468	
	Lighting - Lay-in	South East Stairwell	4	EA	7	\$0	
	Stairs - Tile	South East Stairwell	24	LF	6	\$223	

## Building: Addition 4

### Category: Building Interior

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Stairs</b>							
	Walls - Masonry	South East Stairwell	1,190	SF	6	\$3,744	
	Ceiling - Lay-in	South West Stairwell	332	SF	6	\$997	
	Floor - Tile	South West Stairwell	148	SF	6	\$80	
	Handrails	South West Stairwell	54	LF	6	\$468	
	Lighting - Lay-in	South West Stairwell	4	EA	7	\$0	
	Stairs - Tile	South West Stairwell	24	LF	6	\$223	
	Walls - Masonry	South West Stairwell	1,190	SF	6	\$3,744	

**Building Interior Subtotal: \$349,879**

**Total Building Cost \$3,505,428**

## SITE

### Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Civil/Drainage</b>							
	Civil/ Drainage - Catch Basin	Entire Site	13	EA	6	\$14,220	
	Civil/ Drainage - Catch Basin	Entire Site / East	1	EA	5	\$2,570	Sinking in a sink hole at East Parking Lot
	Civil/ Drainage - Site Manhole	Entire Site	24	EA	6	\$35,826	

### Fencing

	Fencing - Chain Link	Entire Site	224	LF	6	\$4,206	
	Fencing - New Standard Ornamental	Entire Site	1,463	LF	6	\$46,675	

### Landscape

	Benches	Entire Site	11	EA	6	\$4,730	
	Landscape - Grass	Entire Site	87,601	SF	6	\$72,656	
	Parkway trees	Entire Site	55	EA	6	\$36,302	
	Planting Beds/ Area	Entire Site	23,501	SF	6	\$38,647	
	Retaining Wall - Concrete	Entire Site	48	SF	6	\$1,125	
	Retaining Wall - Masonry	Entire Site	150	SF	6	\$2,190	
	Trash Receptacles	Entire Site	5	EA	6	\$1,561	

### Parking Lot

	Concrete Curbs	Entire Site	1,254	LF	6	\$16,103	
	Interior Plantings	Entire Site	340	LF	6	\$14,464	
	Lighting - Lighting	Entire Site	2	EA	6	\$931	
	Surface - Asphalt	Entire Site	97,613	SF	5	\$445,281	

## SITE

### Category: Site

Group	Item - Type	Location	Quantity	Unit	Rank	Cost	Comments
<b>Parking Lot</b>							
	Surface - Asphalt	Entire Site	10,000	SF	4	\$105,963	Major sink hole in the East lot; Potholes, cracking throughout
	Trash Compactor	Entire Site	1	EA	6	\$0	
	Trash Enclosure - Masonry	Entire Site	385	SF	6	\$15,190	
<b>Playground</b>							
	Equipment - Pre K 3-5	Entire Site	4	EA	6	\$14,183	
	Surface	Entire Site	1,115		6	\$0	Grass
	Surface - Poured Surface	Entire Site	404	SF	6	\$2,958	
<b>Sidewalks</b>							
	Sidewalks - Internal Walks	Entire Site	1,202	LF	6	\$14,438	Cracks
	Sidewalks - Perimeter Sidewalks	Entire Site	30,728	SF	6	\$61,078	Cracks/ Uneven
<b>Signage</b>							
	Flag Pole - Flag Pole	Entire Site / South West	1	EA	6	\$1,657	
	Marquee - Free Standing Back lighted w/ LED	Entire Site / South East	1	EA	6	\$0	
	Monument - Building Mounted Cut Letter Sign	Entire Site	4	EA	6	\$0	
<b>Site Subtotal:</b>						<b>\$952,956</b>	
<b>Total Site Cost</b>						<b>\$952,956</b>	
<b>Campus Total <sup>2 3</sup></b>						<b>\$14,992,741</b>	

<sup>1</sup> It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

<sup>2</sup> As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

<sup>3</sup> The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

## Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").

- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
  - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
  - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Art Room	Laboratory/Shop		100	100	1,215	1	2	14	340	170	50	N	Y	N
Art Room	Art Room		405	405	895	1	4	20	192	96	50	N	N	N
Computer Lab	Regular Classroom		201	201B	895	1	15	30	160	80	40	N	Y	N
Computer Lab	Computer Lab		201A	201A	895	1	6	6	160	80	40	N	Y	N
Computer Lab	Regular Classroom		210	210	892	1	20	50	160	80	40	N	N	N
Computer Lab	Regular Classroom		212	212	892	1	22	60	128	64	40	N	N	N
Fitness Room	Other Instructional Use	5th Floor	500	NA	4,935	1	4	30	192	96	40	N	N	N
Laboratory/Shop	Laboratory/Shop		384A	305A	263	0	0	6	0	0	40	N	Y	N
Library	Music Room		207	207+209	2,670	1	2	10	160	80	50	N	N	N
Multi Purpose Room	Regular Classroom		300A	300	960	1	2	10	160	80	40	N	Y	N
Multi Purpose Room	Regular Classroom		300G	300G	415	0	0	4	64	32	40	N	Y	N
Office	Special Education	2nd Floor	285A	285A	496				36	18		N	N	N
Office	Office	2nd Floor	285B	285B	308				18	9		N	Y	N
Office	Laboratory/Shop		384B	303-2	263	0	0	6	0	0	40	N	N	N
Other Instructional Use	Laboratory/Shop		101	101	1,330	2	12	10	272	136	50	N	Y	N
Other Instructional Use	Regular Classroom		403	403	895	1	4	10	0	0	50	N	N	N
Other Instructional Use	Regular Classroom		404	404	595	0	2	4	66	33	40	N	Y	N
Physical Education Room	Laboratory/Shop		106	100J	1,465	0	0	20	0	0	50	N	N	N
Physical Education Room	Other Instructional Use		107	107	1,950	0	2	4	238	119	50	N	N	N
Regular Classroom	Regular Classroom		102	102	848	1	8	22	384	192	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	895	1	18	16	160	80	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	204	204	848	1	1	22	384	192	40	N	Y	N
Regular Classroom	Science Lab Level 3		205	205	857	1	18	26	64	32	40	N	N	N
Regular Classroom	Regular Classroom		213	213	848	1	8	22	384	192	50	N	N	Y
Regular Classroom	Regular Classroom		214	214	575	1	8	20	96	48	40	N	N	Y
Regular Classroom	Regular Classroom		215	215	845	1	12	20	160	80	40	N	N	N
Regular Classroom	Regular Classroom		216	216	845	1	18	20	160	80	40	N	N	N
Regular Classroom	Regular Classroom		217	217	845	1	18	30	160	80	40	N	N	N
Regular Classroom	Regular Classroom		301	301	800	1	10	18	160	80	40	N	N	N
Regular Classroom	Regular Classroom		302	302	800	1	2	18	160	80	40	N	N	N
Regular Classroom	Regular Classroom		303	303	892	1	2	14	64	32	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	304	304	848	4	3	14	384	192	50	N	Y	N
Regular Classroom	Regular Classroom		305	305	892	1	10	14	128	64	40	N	Y	N
Regular Classroom	Regular Classroom		309	309	892	1	4	14	128	64	40	N	Y	N
Regular Classroom	Regular Classroom		311	311	892	1	4	14	128	64	40	N	Y	N
Regular Classroom	Regular Classroom		313	313	895	1	4	20	384	192	50	N	N	Y
Regular Classroom	Regular Classroom		314	314	575	1	4	10	96	48	40	N	Y	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Main</b>														
Regular Classroom	Regular Classroom	3rd Floor	316	316	845	1	2	14	160	80	40	N	N	N
Regular Classroom	Regular Classroom		317	317	845	1	2	14	160	80	40	N	N	N
Regular Classroom	Regular Classroom		400	400	892	1	6	14	64	32	40	N	Y	Y
Regular Classroom	Regular Classroom		401	401	895	1	4	24	0	0	50	N	N	Y
Regular Classroom	Regular Classroom		402	402	892	1	8	14	128	64	40	N	Y	N
Regular Classroom	Regular Classroom		406	406	1,395	1	10	60	224	112	50	N	Y	N
Regular Classroom	Regular Classroom		407	407	895	1	6	20	0	0	50	N	Y	N
Regular Classroom	Regular Classroom		408	408	892	1	4	14	128	69	40	N	Y	N
Regular Classroom	Regular Classroom		409	409	895	1	4	24	0	0	50	N	Y	N
Regular Classroom	Regular Classroom		410	410	892	1	8	14	128	69	40	N	Y	N
Regular Classroom	Regular Classroom		440	440	677	1	6	4	128	64	40	N	Y	Y
Science Lab Level 1	Science Lab Level 3		206	206	1,015	1	16	50	224	112	50	N	N	N
Science Lab Level 1	Science Lab Level 3		306	306	1,440	1	18	40	256	128	50	N	Y	N
Science Lab Level 1	Science Lab Level 3	3rd Floor	310	310	1,015	1	18	40	192	96	50	N	N	Y
Science Lab Level 3	Science Lab Level 3		205A	205A	857	1	20	26	128	64	40	N	N	N
Science Lab Level 3	Science Lab Level 3		211	211	1,015	1	16	40	224	112	50	N	N	N
Science Lab Level 3	Science Lab Level 3		307	307	1,128	1	4	28	160	80	50	N	N	N
Science Lab Level 3	Science Lab Level 3	3rd Floor	308	308	1,159	1	3	26	192	96	50	N	Y	N
Store Room	Office	3rd Floor	302A	302A	336	0	4	12	36	18		N	N	N
Store Room	Regular Classroom		315	315	845	1	2	14	160	80	40	N	N	N

### Addition 1

Music Room	Music Room	3rd Floor	319	319	2,176	1	4	10	128	64	50	N	N	N
Vacant	Other Instructional Use	Basement	009	114B	1,205	1	0	4	0	0	40	N	N	N
Vacant	Special Program	Basement	114	114	2,342	1	0	6	0	0	40	N	N	N

### Addition 2

Autoshop	Autoshop	1st Floor	174	174	3,061	1	2	12	684	0	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	174A		863	1	10	16	228	114	40	N	N	N

### Addition 4

Computer Lab	Computer Lab	2nd Floor	240	240	1,299	1	20	50	0	0	50	N	Y	Y
Faculty Lounge	Regular Classroom	1st Floor	135	135	795	1	3	10	152	0	50	N	Y	N
Office	Regular Classroom	1st Floor	133	133	576	1	3	28	152	0	50	N	Y	N
Office	Regular Classroom	1st Floor	134	134	795	1	3	10	152	0	50	N	Y	N
Other Instructional Use	Other Instructional Use	1st Floor	140J	140I&J/128C	887	1	3	10	0	0	40	N	N	Y
Other Instructional Use	Other Instructional Use	1st Floor	144	144/129	2,041	1	48	68	0	0	50	N	N	N

## Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
<b>Addition 4</b>														
Physical Education Room	Regular Classroom	2nd Floor	231	231	1,418	1	3	24	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	122	122	795	1	20	50	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	123	123	795	1	20	50	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	124	124	795	1	10	30	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	125	125	795	1	10	30	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	136	136	795	1	3	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	137	137	795	1	3	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	138	138	795	1	3	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	139	139	795	1	3	10	152	0	50	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	222	222	795	1	2	30	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	223	223	795	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	224	224	795	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	225	225	795	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	226	226	795	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	227	227	795	1	2	44	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	228	228	945	1	2	10	0	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	232	232	623	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	233	233	795	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	236	236	795	1	2	10	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	237	237	640	1	4	10	150	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	238	238	795	1	2	40	152	0	50	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	239	239	795	1	2	10	152	0	50	N	Y	N
Science Lab Level 1	Regular Classroom	2nd Floor	229	229	1,127	1	20	50	0	0	50	N	Y	Y
Science Lab Level 1	Regular Classroom	2nd Floor	235	235	1,211	1	2	38	152	0	50	N	Y	N
Science Lab Level 1	Regular Classroom	2nd Floor	241	241	1,407	1	30	70	0	0	50	N	Y	N
Science Lab Level 1	Regular Classroom	2nd Floor	242	242	1,131	1	20	50	0	0	50	N	Y	Y
Store Room	Regular Classroom	1st Floor	126	126	795	1	10	30	152	0	50	N	N	Y
Store Room	Regular Classroom	1st Floor	127	127	795	1	10	30	152	0	50	N	N	N
Unsafe/Unusable Conditio	Regular Classroom	1st Floor	133-B	133-B	840	1	0	8	168	0	40	N	N	N
Unsafe/Unusable Conditio	Regular Classroom	1st Floor	133-D	133-D	904	1	0	8	168	0	40	N	N	N
Unsafe/Unusable Conditio	Regular Classroom	1st Floor	133-E	133-E	897	1	0	6	168	0	40	N	N	N