

Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1905	3	328,514	\$27,138,737
SITE				\$143,924
Campus Total			328,514	\$27,282,661

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Entrance Control - Audio	1	EA	6	\$497
	Entrance Control - Audio and Video	1	EA	6	\$702
	Exterior Doors	3	EA	7	\$0
	Exterior Doors - Exterior FRP Door	3	EA	5	\$5,509
	Exterior Doors - Exterior FRP Door	36	EA	6	\$22,730
	Exterior Doors - Exterior Steel Door	5	EA	6	\$2,403
	Exterior Doors - Overhead Rolling/ Garage Door	3	EA	6	\$4,300
	Exterior Doors - Side lite	12	EA	6	\$3,760
	Exterior Doors - Side lite	4	EA	7	\$0
	Exterior Doors - Transom Lite	22	EA	6	\$6,893
	Exterior Doors - Transom Lite	25	EA	7	\$0
	Exterior Stairs - Concrete	31	LF	4	\$5,071
	Exterior Stairs - Concrete	18	LF	5	\$1,972
	Exterior Stairs - Concrete	247	LF	6	\$20,197
	Ramp Handrail - Steel_Ramp Handrail	30	LF	6	\$260
	Ramps - Concrete	10	LF	6	\$1,502
Fire Escape					
	Fire Escape	120	LF	6	\$75,811

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Foundation					
	Foundation - Masonry	1,870	LF	7	\$0
	Superstructure - Steel with Clay Tile Arch	20	SF	5	\$0
	Superstructure - Steel with Clay Tile Arch	328,494	SF	7	\$0
Lighting					
	Exterior Lighting - Parapet or Roof Mounted	2	EA	5	\$4,360
	Exterior Lighting - Parapet or Roof Mounted	12	EA	6	\$6,438
	Exterior Lighting - Wall Mounted	1	EA	5	\$427
	Exterior Lighting - Wall Mounted	7	EA	6	\$2,021
Roof System					
	Cell Tower	1	EA	7	\$0
	Chimney - Brick Chimney- Concrete/ Mortar Liner	5	LF	5	\$14,258
	Chimney - Brick Chimney- Concrete/ Mortar Liner	65	LF	6	\$62,054
	Chimney - Brick Chimney- Concrete/ Mortar Liner	120	LF	7	\$0
	Chimney - Metal Flue	70	LF	7	\$0
	Coping - Clay Tile	1,700	LF	5	\$100,546
	Coping - Clay Tile	33	LF	7	\$0
	Coping - Metal	65	LF	5	\$2,748
	Coping - Stone	1,375	LF	5	\$150,575
	Coping - Stone	293	LF	7	\$0
	Downspouts - Exterior Downspouts	140	LF	6	\$4,653
	Downspouts - Interior Downspouts	1,960	LF	6	\$65,137
	Parapet - 16" - 30" Height	210	LF	4	\$147,834
	Parapet - 16" - 30" Height	1,170	LF	5	\$202,428
	Parapet - 16" - 30" Height	155	LF	7	\$0
	Parapet - Parapet < 16" Height	180	LF	4	\$100,040
	Parapet - Parapet < 16" Height	670	LF	5	\$61,979
	Parapet - Parapet > 30"	138	LF	4	\$160,236
	Parapet - Parapet > 30"	735	LF	5	\$181,338
	Parapet - Parapet > 30"	104	LF	7	\$0
	Roof - Asphalt Gravel Ballast	600	SF	3	\$21,175
	Roof - Asphalt Gravel Ballast	9,830	SF	5	\$251,170
	Roof - Asphalt Gravel Ballast	82,017	SF	6	\$841,142
	Roof - Metal	575	SF	6	\$7,704
	Roof - Modified Bitumen	5	SF	3	\$257
	Roof - Modified Bitumen	1,645	SF	6	\$15,478
	Roof Structure - Concrete	1,300	SF	7	\$0

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Roof System					
	Roof Structure - Steel with Clay Tile Arch	92,922	SF	7	\$0
Walls					
	Cornice - Masonry Projecting Limestone	1,760	LF	6	\$61,032
	Exterior Walls - Brick	83,960	SF	4	\$6,775,144
	Exterior Walls - Prefabricated Metal Panel Wall	115	SF	5	\$747
	Exterior Walls - Stone-Cast	21,415	SF	4	\$3,011,204
Windows					
	Guard - Guards wire guard	3,530	SF	5	\$54,113
	Lintels - Brick	55	LF	7	\$0
	Lintels - Steel	2,205	LF	6	\$64,009
	Lintels - Stone	1,600	LF	4	\$417,491
	Windows - Decorative	100	SF	5	\$12,255
	Windows - Decorative	635	SF	6	\$4,740
	Windows - Louver	140	SF	7	\$0
	Windows - Sash Lexan	27,780	SF	4	\$3,646,394
	Windows - Sash Lexan	6,945	SF	6	\$51,842

Building Exterior Subtotal:

\$16,654,579

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
	Automatic Transfer Switch	1	EA	4	\$8,200
	Emergency A/C Power - Auditorium and Aisle Lighting	9,705	SF	6	\$5,135
	Emergency A/C Power - Corridors and Stairs	59,354	SF	6	\$17,824
	Emergency A/C Power - Lunchrooms	33,192	SF	6	\$12,341
	Emergency A/C Power - Students Toilets	4,272	SF	6	\$1,588
	Emergency Battery Packs - Gym	2	EA	6	\$405
	Emergency Battery Packs - Lunchrooms	8	EA	6	\$1,620
	Exit Signs - Auditorium	30	EA	4	\$16,365
	Exit Signs - Corridors and Stairs	50	EA	4	\$27,274
	Exit Signs - Gym	4	EA	4	\$2,313
	Exit Signs - Lunchroom	6	EA	4	\$3,273
	Security System - CCTV	328,529	SF	6	\$98,657
	Security System - Intrusion Detection	328,529	SF	6	\$84,563

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
Main Service					
	Independent Electrical Service for emergency power	1	EA	4	\$18,799
	Main Electrical Service - 1200 A 120/208/3PH	1	EA	6	\$5,078
	Main Electrical Service - 2001 to 3000 A 120/208/3PH	2	EA	6	\$21,734
	Main Electrical Service - 2001 to 3000 A 277/480/3PH	1	EA	6	\$11,555
	Main Electrical Service - Greater than 3000 A 120/208/3PH	1	EA	6	\$16,381
	PA System	328,529	SF	5	\$225,502
Power Distribution					
	Lighting and Power Panels - 100 A	9	EA	4	\$43,644
	Lighting and Power Panels - 100 A	42	EA	6	\$12,563
	Lighting and Power Panels - Above 100 A	33	EA	4	\$217,066
	Lighting and Power Panels - Above 100 A	54	EA	6	\$26,839
	Main Distribution Panels - 400 - 600 amp	2	EA	4	\$27,388
	Main Distribution Panels - 400 - 600 amp	4	EA	6	\$2,111
	Main Distribution Panels - Greater than 600 amp	3	EA	6	\$2,191
	Transformers - 120/240 - 120/208	3	EA	6	\$9,064
	Transformers - 277/480 - 120/208	6	EA	6	\$7,590

Electrical System Subtotal:

\$927,064

Building: Main

Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Alarm Panel	1	EA	4	\$49,477
	Fire Alarm_System	56,976	SF	4	\$113,251

Safty System Subtotal:

\$162,728

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Conditioning					
	Condensing Unit- Roof Mounted - 5-10 tons	1	EA	6	\$3,334

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Handling Systems					
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - 20001-30000 cfm	4	EA	6	\$13,400
	Air Handling Unit- Package Multi Zone- Indoor- Steam Coils - Greater than 30,000 cfm	1	EA	6	\$3,350
	Air Intake	5	EA	7	\$0
	Auxiliaries - 20001-30000 cfm	1	EA	6	\$0
	Make Up Air Unit- Roof Mounted- Gas Heating - 10,001 - 20,000 cfm	1	EA	6	\$3,350
	Make Up Air Unit- Roof Mounted- Gas Heating - 6000 - 10,000 cfm	1	EA	6	\$3,350
	Roof Top Unit-Single Zone-Roof Mounted- Gas Heating & DX Cooling w/ Remote Mounted Compressor - Less than 5 tons	1	EA	6	\$1,265
	Zone Dampers	165	EA	6	\$137,450
Boiler Systems					
	Boiler Auxiliary- Scotch Marine- Steam High Pressure Boiler - 150 - 300 HP	3	EA	6	\$2,994
	Chemical Feeder	1	EA	7	\$0
	Combustion Dampers	3	EA	7	\$0
	Condensate Pump	3	EA	6	\$6,063
	Feed Water Pumps and Tank	3	EA	6	\$7,636
	Non Condensing- Fire Tube- Scotch Marine- Steam- High Pressure Boiler - 150 - 300 HP	3	EA	6	\$2,994
	Piping - Condensate Pipe- Steel	1,000	LF	6	\$1,888
	Piping - Steam Pipe- Steel	1,000	LF	6	\$1,888
	Steam Traps	82	EA	5	\$107,822
	Vacuum Pump	1	EA	6	\$2,471
Gas Booster					
	Gas Booster	3	EA	6	\$1,497
Heating Devices					
	Cabinet Heaters - With Steam Coil	1	EA	6	\$357
	Fin Tube - Steam	50	LF	6	\$472
	Radiators - Steam	43	EA	5	\$72,039
	Unit Heater - Electric	2	EA	4	\$4,002
	Unit Heater - Electric	5	EA	6	\$1,389
	Unit Heater - Hot Water	3	EA	6	\$837
	Wall Heater - Electric	4	EA	4	\$4,330
	Wall Heater - Electric	16	EA	6	\$2,223
Temperature Control					
	Pneumatic System	328,529	SF	5	\$1,132,209
	Thermostats - Pneumatic	10	EA	4	\$7,372
	Thermostats - Pneumatic	165	EA	6	\$0

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Ventilation					
	Exhaust Fans- Indoor - 1501 - 8000 CFM	6	EA	6	\$3,554
	Exhaust Fans- Indoor - 500 - 1500 CFM	6	EA	6	\$3,554
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	2	EA	4	\$12,784
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	6	EA	6	\$3,554
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	5	EA	6	\$2,962
	Exhaust Fans- Roof Mounted - Less than 500 CFM	1	EA	6	\$296
	Lab Exhaust Hood	1	EA	5	\$2,950
	Lab Exhaust Hood	1	EA	6	\$1,248
	Roof Mounted Duct Work	120	LF	6	\$45,483
	Roof Mounted Duct Work	10	LF	7	\$0
	Type I Exhaust Hood- Kitchen	2	EA	6	\$2,495
	Type II Exhaust Hood- Warming Kitchen	3	EA	5	\$7,819

Mechanical System Subtotal:

\$1,612,680

Building: Main

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Hot Water					
	Electric Heater - Less than 20 KW	2	EA	6	\$1,364
	Gas Heater - 300001 - 600000 BTU/HR	2	EA	6	\$620
	Gas Heater - Less than 150000 BTU/HR	1	EA	6	\$310
Piping					
	Domestic Piping-Cold Water from Risers to Fixtures	328,529	SF	6	\$65,772
	Domestic Piping-Cold Water Horizontal Lines	328,529	SF	6	\$79,865
	Domestic Piping-Cold Water Risers	328,529	SF	6	\$61,074
	Domestic Piping-Hot Water from Risers to Fixtures	328,529	SF	6	\$51,678
	Domestic Piping-Hot Water Horizontal Lines	328,529	SF	6	\$61,074
	Domestic Piping-Hot Water Return Lines	328,529	SF	6	\$46,980
	Domestic Piping-Hot Water Return Risers	328,529	SF	6	\$46,980
	Sanitary Piping	328,529	SF	6	\$300,670
	Storm Piping	328,529	SF	6	\$286,576
	Vent Piping	328,529	SF	6	\$220,804
Pumps					
	Pumps - Domestic Booster Pump-Duplex	1	EA	6	\$1,977
	Pumps - Sump-Duplex	6	EA	5	\$45,209

Building: Main

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Pumps					

Plumbing System Subtotal:

\$1,270,951

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Art Room (2 rooms)					
	Ceiling - Lay-in	1,015	SF	6	\$3,048
	Ceiling - Plaster/Drywall	215	SF	6	\$744
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Concrete	215	SF	6	\$114
	Floor - Tile	1,015	SF	6	\$2,221
	Lighting - Lay-in	29	EA	7	\$0
	Lighting - Pendent/Surface	2	EA	4	\$1,081
	Lighting - Pendent/Surface	3	EA	6	\$372
	Marker Board	5	LF	7	\$0
	Storage/ Closet	508	SF	6	\$3,683
	Walls - Masonry	1,056	SF	6	\$3,322
	Walls - Plaster/Drywall	1,140	SF	6	\$3,146
	Work Sink	1	EA	6	\$379
Auditorium (1 room)					
	AC Units	3	EA	6	\$1,487
	Ceiling - Lay-in	1,802	SF	6	\$5,411
	Ceiling - Plaster/Drywall	843	SF	6	\$2,917
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile/Sheet	2,632	SF	6	\$2,635
	Lighting - Lay-in	30	EA	6	\$3,569
	Lighting - Pendent/Surface	12	EA	6	\$1,487
	Storage/ Closet	230	SF	6	\$1,668
	Walls - Plaster/Drywall	3,029	SF	6	\$8,360
Autoshop (1 room)					
	Auto Repair Lifts	3	EA	6	\$2,805
	Casework	60	LF	6	\$1,515
	Ceiling - Exposed	2,925	SF	6	\$4,350
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Concrete	2,925	SF	6	\$1,548

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Autoshop (1 room)					
	Lighting - Pendent/Surface	40	EA	7	\$0
	Student Lockers - One Tier	5	EA	6	\$464
	Walls - Masonry	3,590	SF	6	\$11,294
	Work Sink	1	EA	6	\$379
Band Room (1 room)					
	Casework	12	LF	6	\$303
	Ceiling - Lay-in	2,798	SF	6	\$8,402
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile/Sheet	2,798	SF	6	\$2,801
	Lighting - Lay-in	21	EA	6	\$2,498
	Marker Board	14	LF	6	\$300
	Storage/ Closet	20	SF	6	\$145
	Walls - Plaster/Drywall	2,798	SF	6	\$7,722
Carpentry (1 room)					
	Ceiling - Plaster/Drywall	2,761	SF	6	\$9,555
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Concrete	2,761	SF	6	\$1,461
	Lighting - Pendent/Surface	54	EA	6	\$6,690
	Student Lockers - Three Tiers	108	EA	6	\$3,342
	Walls - Masonry	3,964	SF	6	\$12,471
	Wood Shop Equipment	9	EA	6	\$36,246
	Work Sink	1	EA	6	\$379
Computer Lab (10 rooms)					
	AC Units	3	EA	4	\$18,259
	AC Units	7	EA	5	\$12,781
	AC Units	2	EA	7	\$0
	Casework	125	LF	6	\$3,157
	Ceiling - Lay-in	10,761	SF	6	\$32,315
	Ceiling - Plaster/Drywall	657	SF	6	\$2,274
	Chalk Board	59	LF	4	\$5,417
	Doors - Wood Doors inclu hw	15	EA	6	\$4,515
	Floor - Carpet	2,799	SF	6	\$5,964
	Floor - Concrete	657	SF	6	\$348
	Floor - Tile	2,553	SF	6	\$5,586
	Floor - Tile/Sheet	3,533	SF	6	\$3,537
	Floor - Wood	1,876	SF	6	\$13,226

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Computer Lab (10 rooms)					
	Lighting - Lay-in	115	EA	6	\$13,682
	Lighting - Lay-in	55	EA	7	\$0
	Lighting - Pendent/Surface	9	EA	6	\$1,115
	Marker Board	160	LF	6	\$3,427
	Marker Board	120	LF	7	\$0
	Storage/ Closet	60	SF	6	\$435
	Walls - Concrete Block	573	SF	6	\$1,680
	Walls - Masonry	240	SF	6	\$755
	Walls - Plaster/Drywall	10,810	SF	6	\$29,835
	Wireless System	1	EA	6	\$372
	Work Sink	3	EA	6	\$1,137
Laboratory/Shop (1 room)					
	Ceiling - Plaster/Drywall	857	SF	6	\$2,966
	Chalk Board	8	LF	4	\$734
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Floor - Tile/Sheet	857	SF	6	\$858
	Lighting - Pendent/Surface	18	EA	6	\$2,230
	Marker Board	18	LF	6	\$386
	Walls - Plaster/Drywall	1,323	SF	6	\$3,651
Music Room (1 room)					
	Casework	70	LF	6	\$1,768
	Ceiling - Lay-in	2,259	SF	6	\$6,784
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile/Sheet	2,259	SF	6	\$2,261
	Lighting - Lay-in	36	EA	6	\$4,283
	Walls - Plaster/Drywall	3,094	SF	6	\$8,539
Office (3 rooms)					
	Casework	12	LF	6	\$303
	Ceiling - Lay-in	1,779	SF	6	\$5,342
	Doors - Transom Window	19	SF	6	\$322
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile	571	SF	6	\$1,249
	Floor - Tile/Sheet	1,208	SF	6	\$1,209
	Lighting - Lay-in	20	EA	6	\$2,380
	Lighting - Lay-in	10	EA	7	\$0
	Marker Board	21	LF	6	\$450

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Office (3 rooms)					
	Risers	16	LF	6	\$360
	Storage/ Closet	4	SF	6	\$29
	Walls - Plaster/Drywall	3,169	SF	6	\$8,746
Other Instructional Use (2 rooms)					
	AC Units	4	EA	5	\$7,303
	Casework	23	LF	6	\$581
	Ceiling - Lay-in	20	SF	5	\$160
	Ceiling - Lay-in	2,462	SF	6	\$7,393
	Chalk Board	24	LF	4	\$2,203
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Carpet	1,618	SF	6	\$3,447
	Floor - Tile	834	SF	6	\$1,825
	Lighting - Lay-in	48	EA	7	\$0
	Lighting - Pendent/Surface	1	EA	4	\$541
	Marker Board	88	LF	7	\$0
	Storage/ Closet	58	SF	6	\$421
	Walls - Plaster/Drywall	3,326	SF	6	\$9,179
Regular Classroom (53 rooms)					
	AC Units	1	EA	4	\$6,086
	AC Units	8	EA	5	\$14,607
	AC Units	1	EA	6	\$496
	AC Units	2	EA	7	\$0
	Casework	451	LF	6	\$11,389
	Ceiling - Lay-in	16	SF	5	\$128
	Ceiling - Lay-in	34,586	SF	6	\$103,862
	Ceiling - Plaster/Drywall	2,451	SF	5	\$22,467
	Ceiling - Plaster/Drywall	4,540	SF	6	\$15,711
	Chalk Board	130	LF	4	\$11,935
	Chalk Board	8	LF	6	\$178
	Doors - Side-lite	14	SF	6	\$234
	Doors - Steel Doors incl hw	7	EA	6	\$2,107
	Doors - Transom Window	140	SF	6	\$2,370
	Doors - Wood Doors inclu hw	52	EA	6	\$15,651
	Floor - Carpet	1,546	SF	6	\$3,294
	Floor - Concrete	583	SF	6	\$308
	Floor - Tile	3,130	SF	5	\$14,084

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Regular Classroom (53 rooms)					
	Floor - Tile	8,886	SF	6	\$19,442
	Floor - Tile/Sheet	20	SF	5	\$115
	Floor - Tile/Sheet	25,322	SF	6	\$25,347
	Floor - Wood	2,106	SF	6	\$14,847
	Lighting - Lay-in	471	EA	6	\$56,038
	Lighting - Lay-in	178	EA	7	\$0
	Lighting - Pendent/Surface	54	EA	4	\$29,195
	Lighting - Pendent/Surface	63	EA	6	\$7,805
	Lighting - Pendent/Surface	4	EA	7	\$0
	Marker Board	1,884	LF	6	\$40,358
	Marker Board	266	LF	7	\$0
	Storage/ Closet	228	SF	6	\$1,653
	Walls - Masonry	2,805	SF	6	\$8,825
	Walls - Plaster/Drywall	130	SF	5	\$574
	Walls - Plaster/Drywall	63,460	SF	6	\$175,143
	Walls - Vinyl Coated Gypsum Panel	1,330	SF	6	\$3,671
	Work Sink	7	EA	6	\$2,653
Science (7 rooms)					
	AC Units	1	EA	6	\$496
	Casework	652	LF	6	\$16,465
	Ceiling - Lay-in	7,160	SF	6	\$21,501
	Chalk Board	64	LF	4	\$5,876
	Doors - Wood Doors inclu hw	12	EA	6	\$3,612
	Eye Wash Station	2	EA	6	\$672
	Floor - Tile/Sheet	7,160	SF	6	\$7,167
	Fume Hood	1	EA	6	\$816
	Gas Line	28	EA	6	\$14,255
	Lighting - Lay-in	130	EA	6	\$15,467
	Lighting - Pendent/Surface	48	EA	6	\$5,947
	Marker Board	174	LF	6	\$3,727
	Science Lab Shower	2	EA	6	\$758
	Storage/ Closet	30	SF	6	\$218
	Walls - Plaster/Drywall	8,031	SF	6	\$22,165
	Work Sink	24	EA	6	\$9,097
Special Program (1 room)					
	Casework	24	LF	6	\$606

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Special Program (1 room)					
	Ceiling - Lay-in	1,445	SF	6	\$4,339
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,445	SF	6	\$3,162
	Lighting - Lay-in	33	EA	7	\$0
	Marker Board	30	LF	7	\$0
	Walls - Plaster/Drywall	1,434	SF	6	\$3,958
	Work Sink	2	EA	6	\$758
Store Room (5 rooms)					
	Casework	104	LF	6	\$2,626
	Ceiling - Lay-in	1,467	SF	6	\$4,405
	Ceiling - Plaster/Drywall	4,871	SF	6	\$16,857
	Chalk Board	65	LF	4	\$5,967
	Chalk Board	20	LF	6	\$446
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Transom Window	20	SF	6	\$339
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Floor - Concrete	2,963	SF	6	\$1,568
	Floor - Tile	1,880	SF	6	\$4,113
	Floor - Tile/Sheet	686	SF	6	\$687
	Floor - Wood	781	SF	6	\$5,506
	Lighting - Lay-in	31	EA	6	\$3,688
	Lighting - Pendent/Surface	107	EA	4	\$57,848
	Lighting - Pendent/Surface	33	EA	7	\$0
	Marker Board	34	LF	6	\$728
	Marker Board	13	LF	7	\$0
	Storage/ Closet	829	SF	6	\$6,010
	Walls - Concrete Block	624	SF	6	\$1,829
	Walls - Masonry	6,016	SF	6	\$19,011
	Walls - Plaster/Drywall	2,177	SF	6	\$6,008
	Work Sink	2	EA	6	\$758
Weight (1 room)					
	Ceiling - Plaster/Drywall	1,449	SF	6	\$5,014
	Chalk Board	8	LF	4	\$734
	Doors - Steel Doors incl hw	3	EA	6	\$903
	Floor - Concrete	1,449	SF	6	\$767

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Weight (1 room)					
	Lighting - Pendent/Surface	10	EA	6	\$1,239
	Walls - Concrete Block	301	SF	6	\$882
	Walls - Structural Glazed Tile	1,840	SF	6	\$5,789

Classrooms Subtotal:

\$1,325,099

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	AC Unit	1	EA	4	\$6,086
	AC Unit	12	EA	5	\$21,910
	AC Unit	6	EA	6	\$2,973
	Ceiling - Lay-in	12	SF	5	\$96
	Ceiling - Lay-in	12,291	SF	6	\$36,910
	Ceiling - Plaster/Drywall	579	SF	5	\$5,307
	Ceiling - Plaster/Drywall	2,261	SF	6	\$7,824
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Wood Doors inclu hw	49	EA	6	\$14,748
	Floor - Concrete	614	SF	6	\$325
	Floor - Terrazzo	679	SF	6	\$1,486
	Floor - Tile	392	SF	5	\$1,768
	Floor - Tile	3,509	SF	6	\$7,677
	Floor - Tile/Sheet	254,743	SF	6	\$254,998
	Floor - Wood	4,008	SF	6	\$28,256
	Lighting - Lay-in	8	EA	4	\$2,687
	Lighting - Lay-in	127	EA	6	\$15,110
	Lighting - Lay-in	106	EA	7	\$0
	Lighting - Pendent/Surface	4	EA	4	\$2,163
	Lighting - Pendent/Surface	44	EA	6	\$5,451
	Lighting - Pendent/Surface	5	EA	7	\$0
	Power Distribution	345	EA	6	\$733,084
	Storage/ Closet	518	SF	6	\$3,756
	Walls - Concrete Block	257	SF	6	\$753
	Walls - Masonry	60	SF	5	\$3,431
	Walls - Masonry	1,321	SF	6	\$4,156
	Walls - Plaster/Drywall	10	SF	4	\$147

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Walls - Plaster/Drywall	975	SF	5	\$7,315
	Walls - Plaster/Drywall	29,955	SF	6	\$82,909
	Walls - Structural Glazed Tile	75	SF	6	\$236
	Work Slnk	3	EA	6	\$1,524
Auditorium & Theater					
	Balcony Seating	662	EA	6	\$115,133
	Ceiling - Plaster/Drywall	9,705	SF	6	\$80,910
	Doors - Steel Doors incl hw	22	EA	6	\$6,622
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Carpet	1,951	SF	6	\$4,157
	Floor - Concrete	5,833	SF	6	\$3,086
	Floor - Terrazzo	440	SF	6	\$963
	Lighting - Chandelier, Incandescent	17	EA	6	\$8,119
	Lighting - Pendent/Surface	3	EA	6	\$372
	Lighting - Wall Mounted	32	EA	6	\$3,965
	Main Floor Seating	902	EA	6	\$156,873
	Sound System	1	EA	6	\$10,721
	Stage	2,034	SF	6	\$11,751
	Stage Curtain	3	EA	6	\$0
	Stage Lighting System	1	EA	6	\$8,077
	Stage-Stairs - Terrazzo	10	LF	6	\$77
	Stage-Stairs - Wood	16	LF	6	\$188
	Stairs - Asphalt	180	LF	6	\$1,671
	Stairs - Terrazzo	10	LF	6	\$77
	Walls - Plaster/Drywall	175	SF	5	\$1,974
	Walls - Plaster/Drywall	13,134	SF	6	\$62,543
Gymnasia					
	Balcony Seating	440	EA	6	\$76,523
	Ceiling - Plaster/Drywall	12,897	SF	5	\$188,161
	Ceiling - Plaster/Drywall	7,740	SF	6	\$42,723
	Doors - Steel Doors incl hw	10	EA	6	\$3,010
	Floor - Wood	17,832	SF	6	\$125,714
	Lighting - Metal Halide/Sodium Vapor	36	EA	6	\$4,814
	Lighting - Pendent/Surface	36	EA	4	\$19,463
	Lighting - Pendent/Surface	36	EA	7	\$0
	Scoreboards	3	EA	6	\$6,733

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Gymnasia					
	Sound System	2	EA	6	\$83,308
	Storage/ Closet	104	SF	5	\$1,678
	Storage/ Closet	34	SF	6	\$247
	Walls - Plaster/Drywall	5,788	SF	5	\$43,372
	Walls - Plaster/Drywall	13,232	SF	6	\$36,519
	Walls - Structural Glazed Tile	3,000	SF	6	\$9,438
Kitchen					
	AC Unit	2	EA	6	\$991
	Ceiling - Lay-in	1,700	SF	6	\$5,105
	Ceiling - Plaster/Drywall	678	SF	6	\$2,346
	Ceiling - Splined	1,903	SF	6	\$1,551
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Floor - Concrete	1,903	SF	6	\$1,007
	Floor - Tile	1,700	SF	6	\$3,719
	Floor - Tile/Sheet	678	SF	6	\$679
	Lighting - Lay-in	35	EA	7	\$0
	Lighting - Pendent/Surface	42	EA	6	\$5,204
	Storage/ Closet	261	SF	6	\$1,892
	Walls - Plaster/Drywall	5,237	SF	6	\$14,454
Library					
	AC Unit	2	EA	5	\$3,652
	AC Unit	2	EA	7	\$0
	Casework	256	LF	6	\$6,465
	Ceiling - Plaster/Drywall	4,269	SF	6	\$14,773
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	4,269	SF	6	\$9,096
	Floor - Wood	533	SF	6	\$3,758
	Lighting - Pendent/Surface	27	EA	6	\$3,345
	Walls - Plaster/Drywall	2,342	SF	6	\$6,464
Locker/Shower Room					
	Accessories	7,000	SF	5	\$61,161
	Accessories	3,082	SF	6	\$12,076
	Benches, ped mounted	70	LF	5	\$19,232
	Ceiling - Exposed	2,789	SF	6	\$4,148
	Ceiling - Plaster/ Drywall	7,293	SF	6	\$25,238
	Doors - Transom Window	25	SF	6	\$423

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Locker/Shower Room					
	Doors - Wood Doors inclu hw	11	EA	6	\$3,311
	Floor - Concrete	8,288	SF	6	\$4,385
	Floor - Terrazzo	224	SF	6	\$490
	Floor - Tile Ceramic/ Porcelain	370	SF	6	\$783
	Floor - Tile/Sheet	1,092	SF	6	\$1,093
	Floor Drain	10	EA	6	\$10,592
	Hand Dryer	25	EA	6	\$5,751
	Lavatory	1	EA	5	\$3,763
	Lavatory	6	EA	6	\$1,918
	Lighting - Pendent/Surface	22	EA	4	\$11,894
	Lighting - Pendent/Surface	100	EA	6	\$12,390
	Partitions	2	EA	6	\$594
	Showers	44	EA	6	\$13,702
	Student Lockers - Two Tier	948	EA	6	\$44,004
	Urinals	3	EA	6	\$1,008
	Walls - Concrete Block	410	SF	6	\$1,202
	Walls - Masonry	4,448	SF	6	\$13,993
	Walls - Plaster/Drywall	3,826	SF	6	\$10,559
	Walls - Structural Glazed Tile	3,605	SF	6	\$11,341
	Walls - Tile Ceramic/ Porcelain	1,024	SF	6	\$2,314
	Water Closet	9	EA	6	\$3,024
Lunch & Multipurpose Room					
	AC Unit	13	EA	6	\$6,443
	Ceiling - Lay-in	15,427	SF	6	\$46,327
	Doors - Wood Doors inclu hw	9	EA	6	\$2,709
	Floor - Tile/Sheet	16,278	SF	6	\$16,294
	Lighting - Lay-in	138	EA	6	\$16,419
	Lighting - Pendent/Surface	12	EA	6	\$1,487
	Serving Line	192	LF	6	\$11,427
	Stage	790	SF	6	\$4,564
	Walls - Plaster/Drywall	10,625	SF	6	\$29,324
MDF_IDF					
	AC Unit	1	EA	4	\$6,086
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Finishes	588	SF	6	\$4,196

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Mechanical/ Service Rooms					
	Air Intake Plenums	1,958	SF	6	\$12,124
	Air Tunnel	236	SF	5	\$3,142
	Air Tunnel	891	SF	6	\$5,517
	Boiler Room	2,067	SF	5	\$33,342
	Crawl Space - Unfinished	1,887	SF	6	\$11,684
	Janitor's Closet	180	SF	6	\$1,290
	Mechanical/ Service Rooms	2,400	SF	5	\$38,713
	Mechanical/ Service Rooms	2,281	SF	6	\$16,342
	Storage Room	81	SF	3	\$2,258
	Storage Room	1,856	SF	5	\$29,938
	Storage Room	9,324	SF	6	\$66,585
Pool & Natatorium					
	Accessories	3,409	SF	6	\$2,340
	Bleachers Seating/Plank Seating	7	EA	6	\$203
	Ceiling - Lay-In	3,409	SF	6	\$10,237
	Doors - Steel Doors incl hw	3	EA	6	\$903
	Floor - Concrete	1,466	SF	6	\$776
	Lighting - Lay-in	51	EA	6	\$6,068
	Pool Basin	2,482	SF	6	\$83,975
	Pool Deck	1,466	SF	6	\$13,920
	Pool Deck Drains	1	EA	6	\$422
	Walls - Masonry	5,131	SF	6	\$16,142
Prep Room					
	Casework	100	LF	6	\$2,525
	Ceiling - Plaster/Drywall	621	SF	6	\$2,149
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile/Sheet	621	SF	6	\$622
	Lighting - Pendent/Surface	10	EA	6	\$1,239
	Walls - Plaster/Drywall	2,253	SF	6	\$6,218
	Work Sink	5	EA	6	\$1,895
Restroom					
	Accessories	130	SF	5	\$2,573
	Accessories	6,025	SF	6	\$55,572
	Ceiling - Lay-in	570	SF	6	\$1,773
	Ceiling - Plaster/Drywall	137	SF	5	\$1,256
	Ceiling - Plaster/Drywall	5,527	SF	6	\$19,127

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Restroom					
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Transom Window	14	SF	6	\$237
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Doors - Wood Doors inclu hw	21	EA	6	\$6,321
	Floor - Concrete	216	SF	6	\$114
	Floor - Terrazzo	5,752	SF	6	\$12,585
	Floor - Tile	225	SF	6	\$492
	Floor Drain	19	EA	6	\$20,124
	Hand Dryer	3	EA	4	\$3,236
	Hand Dryer	25	EA	6	\$5,751
	Lavatory	41	EA	6	\$13,104
	Lighting - Chandelier, Incandescent	1	EA	4	\$1,057
	Lighting - Lay-in	1	EA	4	\$336
	Lighting - Lay-in	6	EA	6	\$714
	Lighting - Lay-in	1	EA	7	\$0
	Lighting - Pendent/Surface	5	EA	4	\$2,703
	Lighting - Pendent/Surface	49	EA	6	\$6,071
	Lighting - Pendent/Surface	18	EA	7	\$0
	Partitions	64	EA	6	\$19,003
	Showers	1	EA	5	\$1,172
	Showers	2	EA	6	\$623
	Student Lockers - One Tier	13	EA	6	\$1,207
	Urinals	4	EA	5	\$5,376
	Urinals	35	EA	6	\$11,759
	Walls - Masonry	1,517	SF	6	\$5,118
	Walls - Plaster/Drywall	1,492	SF	5	\$11,135
	Walls - Plaster/Drywall	8,647	SF	6	\$23,878
	Walls - Structural Glazed Tile	443	SF	6	\$1,394
	Walls - Tile Ceramic/ Porcelain	5,543	SF	6	\$12,524
	Water Closet	2	EA	5	\$2,688
	Water Closet	58	EA	6	\$19,487

Rooms (Other Than Classrooms) Subtotal: \$3,530,000

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
-------	-------------	----------	------	------	------

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					
	Ceiling - Lay-in	46,740	SF	6	\$140,360
	Ceiling - Plaster/Drywall	16,749	SF	6	\$103,708
	Doors - Steel Doors incl hw	13	EA	6	\$3,913
	Doors - Wood Doors include hw	1	EA	5	\$1,174
	Doors - Wood Doors include hw	1	EA	6	\$301
	Drinking Fountains - Double Fountain	14	EA	6	\$4,704
	Drinking Fountains - Single Fountain	1	EA	6	\$276
	Floor - Terrazzo	56,011	SF	6	\$470,162
	Floor - Tile/Sheet	8,352	SF	6	\$4,538
	Floor - Wood	126	SF	6	\$888
	Lighting - Chandelier, Incandescent	2	EA	4	\$2,113
	Lighting - Lay-in	240	EA	6	\$28,554
	Lighting - Pendent/Surface	6	EA	4	\$3,244
	Lighting - Pendent/Surface	90	EA	6	\$11,151
	Student Lockers - One Tier	1,021	EA	6	\$94,785
	Walls - Plaster/Drywall	162,306	SF	6	\$719,502
Safety					
	Camera Viewing Station	4	EA	6	\$2,730
	Security Cameras	2	EA	5	\$1,375
	Security Cameras	38	EA	6	\$7,373
Stairs					
	Ceiling - Plaster/Drywall	404	SF	6	\$2,958
	Floor - Concrete	226	SF	6	\$120
	Floor - Terrazzo	20	SF	6	\$168
	Handrails	192	LF	6	\$1,664
	Lighting - Lay-in	2	EA	7	\$0
	Lighting - Pendent/Surface	6	EA	4	\$3,244
	Stairs - Concrete	95	LF	6	\$788
	Walls - Plaster/Drywall	2,669	SF	6	\$7,366
Vertical Conveyance					
	Elevator - Freight Elevator	1	EA	6	\$19,238
	Elevator - Hydraulic Elevator	1	EA	6	\$19,238

Building Interior Subtotal:

\$1,655,636

Total Building Cost

\$27,138,737

SITE

Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Civil/Drainage					
	Civil/ Drainage - Catch Basin	4	EA	6	\$4,375
	Civil/ Drainage - Site Manhole	28	EA	6	\$41,797
Fencing					
	Fencing - New Standard Ornamental	25	LF	5	\$3,560
	Fencing - New Standard Ornamental	1,100	LF	7	\$0
Landscape					
	Benches	2	EA	6	\$860
	Landscape - Grass	10,790	SF	7	\$0
	Landscape - Hardscape- Concrete	3,020	SF	5	\$33,124
	Landscape - Hardscape- Concrete	4,025	SF	7	\$0
	Parkway trees	46	EA	6	\$30,362
	Retaining Wall - Concrete	95	SF	5	\$5,081
	Retaining Wall - Concrete	16	SF	7	\$0
Parking Lot					
	Surface - Asphalt	1,000	SF	5	\$5,906
	Surface - Asphalt	32,180	SF	7	\$0
Sidewalks					
	Sidewalks - Internal Walks	85	LF	5	\$4,911
	Sidewalks - Internal Walks	830	LF	7	\$0
	Sidewalks - Perimeter Sidewalks	1,200	SF	5	\$11,463
	Sidewalks - Perimeter Sidewalks	14,365	SF	7	\$0
Signage					
	Flag Pole - Building Mounted Flag Pole	1	EA	6	\$828
	Flag Pole - Flag Pole	1	EA	6	\$1,657
	Marquee - Free Standing Back Lighted	1	EA	6	\$0
	Monument - Building Mounted Cut Letter Sign	2	EA	6	\$0

Site Subtotal:

\$143,924

Total Site Cost

\$143,924

Campus Total ^{2 3}**\$27,282,661**

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
- **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
- **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
- **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
- **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Art Room	1st Floor	112B	B12B	215	0	0	0	40	20	40	N	N	N
Art Room	Art Room	3rd Floor	333	233	1,015	0	1	12	228	60	40	Y	N	N
Auditorium	Auditorium	3rd Floor	306	206	2,632	0	0	10	480	240	40	N	N	N
Autoshop	Autoshop	1st Floor	109	B11	2,925	0	0	34	310	68	40	Y	Y	N
Band Room	Band Room	4th Floor	424	324	2,798	0	0	8	114	30	40	N	Y	N
Carpentry	Carpentry	1st Floor	112	B12	2,761	0	0	50	136	78	40	N	N	N
Computer Lab	Computer Lab	1st Floor	112C	B12C	657	0	23	46	136	78	40	N	N	N
Computer Lab	Regular Classroom	2nd Floor	214	114	761	0	32	130	132	40	40	Y	N	N
Computer Lab	Regular Classroom	3rd Floor	314	214	980	1	10	30	228	60	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	316	216	980	1	10	30	228	60	40	N	Y	N
Computer Lab	Regular Classroom	3rd Floor	318	218	980	1	10	30	228	60	40	N	Y	N
Computer Lab	Computer Lab	3rd Floor	320	220	2,799	1	30	120	520	260	40	N	N	N
Computer Lab	Computer Lab	4th Floor	408	308	1,573	8	27	70	228	60	40	N	N	Y
Computer Lab	Regular Classroom	4th Floor	436	336	896	2	10	27	266	70	40	Y	Y	N
Computer Lab	Regular Classroom	4th Floor	438	338	896	2	10	27	266	70	40	Y	Y	N
Computer Lab	Regular Classroom	4th Floor	440	340	896	2	10	27	266	70	40	Y	Y	N
Laboratory/Shop	Laboratory/Shop	1st Floor	113	B13	857	0	1	8	48	15	40	N	N	N
Music Room	Music Room	4th Floor	425	325	2,259	0	0	12	432	90	40	N	Y	N
Office	Choral Room	1st Floor	103	B03	571	0	6	13	81	18	40	Y	Y	N
Office	Regular Classroom	2nd Floor	222	122	445	0	5	15	81	24	40	N	N	N
Office	Regular Classroom	2nd Floor	230	130	763	1	1	8	54	18	40	N	Y	N
Other Instructional Use	Regular Classroom	2nd Floor	231	131	1,618	3	16	43	260	60	40	Y	Y	Y
Other Instructional Use	Regular Classroom	2nd Floor	235	135	854	3	0	13	81	24	40	Y	Y	N
Regular Classroom	Regular Classroom	1st Floor	101	B01	2,239	0	0	24	392	126	40	Y	Y	N
Regular Classroom	Carpentry	1st Floor	112A	B12A	583	0	1	8	136	78	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	115	B15	857	1	1	8	48	15	40	N	N	N
Regular Classroom	Regular Classroom	1st Floor	117	B17	594	0	1	8	48	15	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	119	B19	547	0	0	8	48	15	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	121	224	475	1	6	8	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	203	103	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	205	105	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	207	107	680	0	6	12	160	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	209	109	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	211	111	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	213	113	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	215	115	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	217	117	686	1	5	20	135	40	40	N	N	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	2nd Floor	218	118	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	219	119	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	220	120	686	0	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	221	121	686	1	5	20	135	40	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	224	124	498	0	4	20	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	225	125	515	0	7	18	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	226	126	441	0	4	20	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	227	127	515	0	7	18	81	24	40	N	N	N
Regular Classroom	Regular Classroom	2nd Floor	228	128	532	1	4	20	81	24	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	304	204	916	6	7	26	64	16	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	207	913	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	309	209	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	311	211	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	313	213	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	215	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	317	217	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	319	219	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	321	221	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	323	223	1,546	1	12	38	380	100	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	325	225	906	0	0	8	228	60	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	327	227	868	1	1	12	138	35	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	329	229	868	1	1	12	138	35	40	Y	N	N
Regular Classroom	Regular Classroom	3rd Floor	330	230	913	0	0	14	81	21	40	Y	Y	N
Regular Classroom	Regular Classroom	3rd Floor	332	232	1,462	0	0	18	228	60	40	Y	N	Y
Regular Classroom	Multi Purpose Room	3rd Floor	334	234	1,206	0	0	14	304	80	40	Y	N	N
Regular Classroom	Science	4th Floor	401	301	474	0	0	5	114	30	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	411	310	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	413	313	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	415	315	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	416	316	1,053	0	1	10	280	140	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	417	317	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	418	318	980	0	0	10	228	60	40	N	Y	Y
Regular Classroom	Regular Classroom	4th Floor	419	319	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	420	320	980	0	1	10	228	60	40	N	Y	N
Regular Classroom	Regular Classroom	4th Floor	421	321	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	423	323	702	1	2	20	152	40	40	N	N	N
Regular Classroom	Regular Classroom	4th Floor	429	337	906	0	0	8	228	60	40	Y	Y	N

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Regular Classroom	Regular Classroom	4th Floor	431	331	868	1	1	12	138	35	40	Y	Y	N
Regular Classroom	Regular Classroom	4th Floor	433	333	868	1	1	12	138	35	40	Y	Y	N
Science	Science	3rd Floor	301	201	1,155	0	0	72	266	70	40	N	N	N
Science	Science	3rd Floor	303	205	1,155	0	0	72	266	70	40	N	N	N
Science	Regular Classroom	3rd Floor	305	205	1,142	1	1	26	266	70	40	N	N	N
Science	Science	4th Floor	403	303	988	1	16	36	228	60	40	N	Y	N
Science	Science	4th Floor	405	305	988	1	6	66	228	60	40	N	Y	N
Science	Science	4th Floor	407	307	879	0	0	12	190	50	40	N	N	N
Science	Science	4th Floor	409	309	879	0	0	12	190	50	40	N	N	N
Special Program	Art Room	3rd Floor	331	233	1,445	0	0	14	266	70	40	Y	N	N
Store Room	Art Room	1st Floor	102	B02	1,908	0	0	28	270	40	40	Y	N	N
Store Room	Laboratory/Shop	1st Floor	105	B05	1,706	0	4	24	316	96	40	Y	N	N
Store Room	Regular Classroom	1st Floor	107		1,257	0	16	48	221	67	40	Y	N	N
Store Room	Regular Classroom	2nd Floor	223	123	686	0	0	16	107	32	40	N	N	N
Store Room	Regular Classroom	4th Floor	410	310	781	0	0	10	152	40	40	N	N	N
Weight	Multi Purpose Room	1st Floor	120	228	1,449	1	0	15	0	0	40	N	N	N