

Facility Assessment Report

This report contains a summary of the results from the facility assessment completed on the date noted in the document footer below. This report will roll-up each assessed item with identical rank and total the quantity into a single line, regardless of item location (for location data, see the detailed report) . Assessors rate each facility item by visual observation only; they do not test the operation of equipment or perform destructive testing of walls, ceilings or floors. Each facility item is ranked on a 7-point scale: rank 7 means the item is in new or in good condition and no work is required while rank 1 means the item has failed and has lead to an immediate life safety condition¹. The remaining ranks choices generally mean that the item requires regular maintenance (rank 5 or 6) or full replacement (rank 2, 3 or 4). For additional detail and definition on rank values as they relate to each assessed item, please visit the "CPS Guide to Biennial Facility Assessments" found on the Facilities Standards webpage under CPS Policies and Guidelines at http://www.cps.edu/About_CPS/Policies_and_guidelines/Pages/facilitystandards.aspx. Definitions for Quantity, Unit, Cost and Campus Total can be found at the end of this report.

Campus Summary				
Building Name	Year Constructed	Number of Floors	Building Area (Sq Ft)	Assessed Need
Main	1896	4	94,016	\$6,286,488
Linked Addition	1995	3	36,097	\$1,671,567
SITE				\$632,123
Campus Total			130,113	\$8,590,179

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Exterior Doors - Exterior Steel Door	6	EA	6	\$2,883
	Exterior Doors - Exterior Wood Door	9	EA	5	\$12,072
	Exterior Doors - Exterior Wood Door	7	EA	6	\$3,364
	Exterior Doors - Side lite	2	EA	6	\$627
	Exterior Doors - Transom Lite	17	EA	6	\$5,326
	Exterior Stairs - Concrete	56	LF	6	\$4,579
	Exterior Stairs - Steel or Aluminum	180	LF	6	\$692
	Stair Handrail - Steel_Stair Handrail	84	LF	6	\$728
Fire Escape					
	Fire Escape	87	LF	6	\$54,963
Foundation					
	Foundation - Concrete	945	LF	7	\$0
	Superstructure - Steel with Clay Tile Arch	94,016	SF	7	\$0
Lighting					
	Exterior Lighting - Parapet or Roof Mounted	14	EA	6	\$7,512
	Exterior Lighting - Wall Mounted	12	EA	6	\$3,465

Building: Main

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Roof System					
	Chimney - Brick Chimney- Concrete/ Mortar Liner	35	LF	5	\$99,805
	Chimney - Brick Chimney- Concrete/ Mortar Liner	42	LF	6	\$40,097
	Coping - Clay Tile	216	LF	6	\$6,937
	Coping - Stone	146	LF	6	\$4,689
	Coping - Terra Cotta	1,210	LF	6	\$38,863
	Downspouts - Exterior Downspouts	430	LF	6	\$14,290
	Downspouts - Interior Downspouts	115	LF	6	\$3,822
	Parapet - 16" - 30" Height	1,258	LF	6	\$50,262
	Parapet - Parapet < 16" Height	228	LF	6	\$4,858
	Parapet - Parapet > 30"	40	LF	6	\$2,557
	Roof - Asphalt Gravel Ballast	28,260	SF	6	\$287,328
	Roof - Asphalt Shingle	1,576	SF	6	\$7,234
	Roof - Metal	424	SF	6	\$5,681
	Roof Structure - Steel with Clay Tile Arch	28,260	SF	7	\$0
Walls					
	Cornice - Metal Projecting	12	LF	4	\$14,473
	Cornice - Metal Projecting	415	LF	5	\$62,437
	Exterior Walls - Brick	24	SF	4	\$3,952
	Exterior Walls - Brick	17,550	SF	5	\$370,926
	Exterior Walls - Brick	17,550	SF	6	\$137,278
	Exterior Walls - Concrete Block	684	SF	6	\$4,597
	Exterior Walls - Stone-Cast	6,385	SF	5	\$85,827
Windows					
	Guard - Guards wire guard	3,358	SF	6	\$42,881
	Lintels - Brick	356	LF	6	\$0
	Lintels - Steel	395	LF	6	\$11,466
	Lintels - Stone	568	LF	6	\$0
	Skylite - Glass Single-Pane	324	SF	6	\$7,742
	Windows - Sash Aluminum Double-pane	11,610	SF	5	\$625,409
	Windows - Sash Aluminum Double-pane	1,290	SF	6	\$9,629

Building Exterior Subtotal: \$2,039,252

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
-------	-------------	----------	------	------	------

Building: Main

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Auditorium and Aisle Lighting	4,420	SF	6	\$2,339
	Emergency A/C Power - Corridors and Stairs	18,637	SF	6	\$5,597
	Emergency A/C Power - Gym	5,970	SF	6	\$2,220
	Emergency A/C Power - Students Toilets	1,750	SF	6	\$651
	Emergency Battery Packs - Auditorium and Aisle Lighting	4	EA	6	\$810
	Emergency Battery Packs - Corridors and Stairs	6	EA	6	\$1,215
	Emergency Battery Packs - Lunchrooms	2	EA	6	\$405
	Exit Signs - Auditorium	7	EA	6	\$1,048
	Exit Signs - Corridors and Stairs	24	EA	6	\$3,594
	Exit Signs - Gym	1	EA	4	\$578
	Exit Signs - Gym	1	EA	6	\$157
	Exit Signs - Lunchroom	2	EA	6	\$299
	Security System - CCTV	94,016	SF	6	\$28,233
	Security System - Intrusion Detection	94,016	SF	6	\$24,200
Main Service					
	Independent Electrical Service for emergency power	1	EA	6	\$2,921
	Main Electrical Service - 1200 A 120/240/3PH	1	EA	5	\$0
	PA System	94,016	SF	6	\$30,922
Power Distribution					
	Lighting and Power Panels - 100 A	3	EA	6	\$897
	Lighting and Power Panels - Above 100 A	1	EA	4	\$6,578
	Lighting and Power Panels - Above 100 A	6	EA	5	\$0
	Lighting and Power Panels - Above 100 A	4	EA	6	\$1,988
	Main Distribution Panels - 400 - 600 amp	2	EA	4	\$27,388
	Transformers - 277/480 - 120/240	1	EA	6	\$1,019
Electrical System Subtotal:					\$143,467

Building: Main

Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Alarm Panel	1	EA	4	\$49,477
	Fire Alarm Strobe Lights	94,016	SF	4	\$127,721
	Fire Alarm_System	94,016	SF	4	\$186,876

Building: Main

Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Pump Controller	1	EA	4	\$23,389
Pump Room Assembly					
	Fire Pump - Less than 25hp	1	EA	5	\$5,674
Sprinkler System					
	Dry Sprinkler System	94,016	SF	5	\$33,611
	Sprinkler Heads	94,016	SF	7	\$0
	Sprinkler Piping	94,016	SF	6	\$17,478

Safty System Subtotal: \$444,224

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Conditioning					
	Condensing Unit- Ground Mounted - Less than 5 tons	4	EA	6	\$13,335
Air Handling Systems					
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 15001 - 25000 cfm	1	EA	5	\$66,438
	Air Handling Unit- Built Up-Multi Zone- Steam Coils - 8001 - 15000 cfm	1	EA	5	\$50,003
	Air Handling Unit- Built Up-Multi Zone-Double Delivery- Steam Coils - 30001 - 45000 cfm	1	EA	5	\$184,422
	Air Intake	1	EA	5	\$7,471
	Air Intake	2	EA	6	\$11,529
	Auxiliaries - 15001 - 25000 cfm	1	EA	6	\$5,788
	Auxiliaries - 30001 - 45000 cfm	1	EA	6	\$8,716
	Auxiliaries - 8001 - 15000 cfm	1	EA	6	\$4,341
	Return Duct Work - Indoor- Vertical Shaft and Ducts	400	LF	5	\$384,790
	Zone Dampers	41	EA	4	\$196,500
Boiler Systems					
	Boiler Auxiliary- Scotch Marine- Steam Low Pressure Boiler - 101 - 150 HP	2	EA	5	\$24,345
	Chemical Feed System	1	EA	5	\$3,075
	Combustion Dampers	2	EA	5	\$5,104
	Condensate Pump	4	EA	5	\$72,784
	Feed Water Pumps and Tank	1	EA	6	\$2,545
	Non Condensing- Fire Tube- Scotch Marine- Steam- Low Pressure Boiler - 101 - 150 HP	2	EA	4	\$106,661
	Piping - Condensate Pipe- Steel	500	LF	6	\$944
	Piping - Steam Pipe- Steel	500	LF	6	\$944

Building: Main

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Boiler Systems					
	Steam Traps	60	EA	5	\$78,894
Heating Devices					
	Radiators - Steam	2	EA	5	\$3,351
	Unit Heater - Electric	1	EA	4	\$2,001
	Unit Heater - Steam	1	EA	5	\$909
	Wall Heater - Electric	2	EA	4	\$2,165
	Wall Heater - Electric	12	EA	5	\$6,439
Temperature Control					
	Pneumatic System	94,016	SF	4	\$489,372
	Thermostats - Pneumatic	46	EA	4	\$33,913
Ventilation					
	Exhaust Fans- Indoor - Less than 500 CFM	2	EA	4	\$2,556
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	2	EA	4	\$12,784
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	2	EA	4	\$8,489

Mechanical System Subtotal:

\$1,790,608

Building: Main

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Hot Water					
	Gas Heater - 150000 - 300000 BTU/HR	1	EA	5	\$2,249
Piping					
	Domestic Piping-Cold Water from Risers to Fixtures	94,016	SF	6	\$18,822
	Domestic Piping-Cold Water Horizontal Lines	94,016	SF	6	\$22,855
	Domestic Piping-Cold Water Risers	94,016	SF	6	\$17,478
	Domestic Piping-Hot Water from Risers to Fixtures	94,016	SF	6	\$14,789
	Domestic Piping-Hot Water Horizontal Lines	94,016	SF	6	\$17,478
	Domestic Piping-Hot Water Return Lines	94,016	SF	6	\$13,444
	Domestic Piping-Hot Water Return Risers	94,016	SF	6	\$13,444
	Sanitary Piping	94,016	SF	6	\$86,043
	Storm Piping	94,016	SF	6	\$82,010
	Vent Piping	94,016	SF	6	\$63,188

Building: Main

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Pumps					
	Pumps - Domestic Booster Pump-Simplex	1	EA	5	\$8,937
	Pumps - Sump-Simplex	1	EA	5	\$5,627

Plumbing System Subtotal:

\$366,364

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Art Room (1 room)					
	Casework	34	LF	6	\$859
	Ceiling - Plaster/Drywall	810	SF	6	\$2,803
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	810	SF	6	\$5,710
	Lighting - Pendent/Surface	15	EA	7	\$0
	Storage/ Closet	220	SF	6	\$1,595
	Walls - Plaster/Drywall	969	SF	6	\$2,674
Computer Lab (1 room)					
	Ceiling - Plaster/Drywall	880	SF	6	\$3,045
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Floor - Wood	880	SF	6	\$6,204
	Lighting - Pendent/Surface	14	EA	7	\$0
	Marker Board	25	LF	6	\$536
	Storage/ Closet	200	SF	5	\$3,226
	Walls - Plaster/Drywall	1,312	SF	6	\$3,621
Kindergarten (1 room)					
	Casework	6	LF	6	\$152
	Ceiling - Plaster/Drywall	810	SF	6	\$2,803
	Chalk Board	24	LF	4	\$2,203
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	810	SF	6	\$5,710
	Lighting - Pendent/Surface	14	EA	7	\$0
	Marker Board	18	LF	6	\$386
	Storage/ Closet	48	SF	6	\$348

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Kindergarten (1 room)					
	Walls - Plaster/Drywall	969	SF	6	\$2,674
Office (1 room)					
	AC Units	1	EA	6	\$496
	Ceiling - Plaster/Drywall	810	SF	5	\$7,425
	Doors - Transom Window	9	SF	6	\$152
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Wood	810	SF	6	\$5,710
	Lighting - Pendent/Surface	14	EA	7	\$0
	Storage/ Closet	218	SF	5	\$3,516
	Walls - Plaster/Drywall	1,242	SF	5	\$9,413
Other Instructional Use (1 room)					
	Ceiling - Plaster/Drywall	685	SF	6	\$2,371
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	685	SF	6	\$1,499
	Lighting - Pendent/Surface	15	EA	7	\$0
	Marker Board	16	LF	6	\$343
	Walls - Masonry	1,130	SF	6	\$3,555
Play Room (1 room)					
	Ceiling - Plaster/Drywall	840	SF	5	\$7,700
	Chalk Board	44	LF	4	\$4,039
	Doors - Wood Doors inclu hw	1	EA	5	\$1,174
	Floor - Tile	840	SF	6	\$1,838
	Lighting - Pendent/Surface	14	EA	6	\$1,735
	Storage/ Closet	84	SF	6	\$609
	Walls - Structural Glazed Tile	1,392	SF	6	\$4,379
Regular Classroom (27 rooms)					
	AC Units	13	EA	6	\$6,443
	Casework	36	LF	6	\$909
	Ceiling - Plaster/Drywall	10,439	SF	5	\$95,687
	Ceiling - Plaster/Drywall	11,817	SF	6	\$40,894
	Chalk Board	165	LF	4	\$15,148
	Doors - Transom Window	207	SF	6	\$3,505
	Doors - Wood Doors inclu hw	3	EA	5	\$3,522
	Doors - Wood Doors inclu hw	28	EA	6	\$8,428
	Floor - Tile	1,120	SF	5	\$5,029

Building: Main

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Regular Classroom (27 rooms)					
	Floor - Tile	3,500	SF	6	\$7,658
	Floor - Wood	1,620	SF	5	\$23,699
	Floor - Wood	16,016	SF	6	\$112,911
	Lighting - Pendent/Surface	1	EA	4	\$541
	Lighting - Pendent/Surface	14	EA	5	\$2,556
	Lighting - Pendent/Surface	13	EA	6	\$1,611
	Lighting - Pendent/Surface	341	EA	7	\$0
	Marker Board	511	LF	6	\$10,946
	Storage/ Closet	150	SF	4	\$4,181
	Storage/ Closet	708	SF	5	\$11,420
	Storage/ Closet	2,123	SF	6	\$15,392
	Walls - Masonry	450	SF	5	\$18,597
	Walls - Plaster/Drywall	15,100	SF	5	\$114,443
	Walls - Plaster/Drywall	14,975	SF	6	\$41,330
Store Room (1 room)					
	Ceiling - Plaster/Drywall	820	SF	6	\$2,838
	Chalk Board	20	LF	4	\$1,836
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Wood	820	SF	6	\$5,781
	Lighting - Pendent/Surface	10	EA	7	\$0
	Walls - Masonry	1,292	SF	6	\$4,065

Classrooms Subtotal:

\$663,909

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	AC Unit	1	EA	6	\$496
	Ceiling - Exposed	168	SF	6	\$250
	Ceiling - Plaster/Drywall	708	SF	5	\$6,490
	Ceiling - Plaster/Drywall	1,199	SF	6	\$4,149
	Doors - Side-lite	27	SF	6	\$451
	Doors - Transom Window	36	SF	6	\$610
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Floor - Tile	708	SF	5	\$3,179

Building: Main
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Floor - Tile	1,367	SF	6	\$2,991
	Lighting - Pendent/Surface	18	EA	7	\$0
	Power Distribution	26	EA	6	\$55,247
	Storage/ Closet	47	SF	6	\$341
	Walls - Masonry	97	SF	6	\$305
	Walls - Plaster/Drywall	814	SF	5	\$6,169
	Walls - Plaster/Drywall	1,476	SF	6	\$4,096
	Work Slnk	1	EA	6	\$508
Auditorium & Theater					
	Balcony Seating	85	EA	6	\$14,783
	Ceiling - Plaster/Drywall	2,928	SF	6	\$24,410
	Doors - Wood Doors inclu hw	6	EA	6	\$1,806
	Floor - Wood	2,928	SF	6	\$20,642
	Lighting - Chandelier, Incandescent	18	EA	6	\$8,596
	Lighting - Wall Mounted	6	EA	6	\$743
	Main Floor Seating	426	EA	6	\$74,088
	Sound System	1	EA	6	\$10,721
	Stage	517	SF	6	\$2,987
	Stage Curtain	2	EA	4	\$95,567
	Stage Lighting System	1	EA	6	\$8,077
	Stage-Stairs - Wood	10	LF	6	\$117
	Walls - Plaster/Drywall	3,367	SF	6	\$16,033
Gymnasia					
	Ceiling - Exposed	3,660	SF	6	\$5,443
	Doors - Transom Window	18	SF	6	\$305
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Tile	3,660	SF	5	\$16,434
	Lighting - Metal Halide/ High Pressure Sodium	12	EA	6	\$1,605
	Scoreboards	1	EA	6	\$2,244
	Walls - Plaster/Drywall	4,209	SF	5	\$31,900
Kitchen					
	Ceiling - Plaster/Drywall	334	SF	6	\$1,156
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	334	SF	6	\$731
	Lighting - Pendent/Surface	5	EA	7	\$0
	Walls - Masonry	192	SF	6	\$604

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Kitchen					
	Walls - Plaster/Drywall	192	SF	6	\$530
Lunch & Multipurpose Room					
	Ceiling - Exposed	2,829	SF	6	\$4,207
	Floor - Tile	2,829	SF	6	\$6,190
	Lighting - Pendent/Surface	12	EA	7	\$0
	Serving Line	16	LF	6	\$952
	Storage/ Closet	272	SF	6	\$1,972
	Walls - Masonry	3,253	SF	5	\$134,437
Mechanical/ Service Rooms					
	Air Intake Plenums	545	SF	6	\$3,375
	Boiler Room	1,818	SF	6	\$13,025
	Coal Room	564	SF	6	\$4,041
	Mechanical/ Service Rooms	1,214	SF	6	\$8,697
	Storage Room	94	SF	6	\$673
Restroom					
	Accessories	1,216	SF	6	\$11,216
	Ceiling - Plaster/Drywall	814	SF	5	\$7,461
	Ceiling - Plaster/Drywall	422	SF	6	\$1,460
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Doors - Wood Doors inclu hw	4	EA	6	\$1,204
	Floor - Concrete	20	SF	6	\$11
	Floor - Tile	276	SF	6	\$604
	Floor - Tile Ceramic/ Porcelain	940	SF	6	\$1,989
	Floor Drain	2	EA	6	\$2,118
	Hand Dryer	2	EA	6	\$460
	Lavatory	7	EA	6	\$2,237
	Lighting - Pendent/Surface	16	EA	7	\$0
	Lighting - Wall Mounted	1	EA	6	\$124
	Partitions	19	EA	6	\$5,642
	Urinals	7	EA	6	\$2,352
	Walls - Concrete Block	373	SF	6	\$1,093
	Walls - Masonry	354	SF	5	\$14,630
	Walls - Masonry	33	SF	6	\$104
	Walls - Plaster/Drywall	318	SF	6	\$907
	Walls - Structural Glazed Tile	354	SF	6	\$1,114
	Water Closet	21	EA	6	\$7,056

Building: Main

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Restroom					

Rooms (Other Than Classrooms) Subtotal:

\$667,766

Building: Main

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					
	Ceiling - Plaster/Drywall	11,379	SF	6	\$70,458
	Doors - Transom Window	40	EA	6	\$677
	Doors - Wood Doors include hw	20	EA	6	\$6,020
	Drinking Fountains - Single Fountain	10	EA	6	\$2,757
	Floor - Epoxy/ Painted	11,379	SF	6	\$6,021
	Lighting - Pendent/Surface	18	EA	6	\$2,230
	Lighting - Pendent/Surface	52	EA	7	\$0
	Walls - Plaster/Drywall	13,084	SF	6	\$58,001
Safety					
	Camera Viewing Station	1	EA	6	\$683
	Security Cameras	2	EA	6	\$388
Stairs					
	Ceiling - Plaster/Drywall	1,674	SF	6	\$12,256
	Floor - Epoxy/ Painted	1,674	SF	6	\$886
	Handrails	408	LF	6	\$3,536
	Lighting - Pendent/Surface	12	EA	7	\$0
	Stairs - Asphalt	180	LF	6	\$1,671
	Walls - Plaster/Drywall	1,926	SF	6	\$5,316

Building Interior Subtotal:

\$170,899

Total Building Cost

\$6,286,488

Building: Linked Addition

Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Exterior Doors - Exterior FRP Door	2	EA	6	\$1,263

Building: Linked Addition
Category: Building Exterior

Group	Item - Type	Quantity	Unit	Rank	Cost
Entrance					
	Exterior Doors - Exterior Steel Door	2	EA	5	\$2,683
	Exterior Doors - Exterior Steel Door	3	EA	6	\$1,442
	Exterior Doors - Side lite	12	EA	6	\$3,760
	Exterior Doors - Store Front	4	EA	6	\$2,184
	Exterior Doors - Transom Lite	7	EA	6	\$2,193
Foundation					
	Foundation - Concrete	595	LF	7	\$0
	Superstructure - Steel	36,097	SF	7	\$0
Lighting					
	Exterior Lighting - Wall Mounted	9	EA	6	\$2,599
Roof System					
	Coping - Stone	615	LF	6	\$19,752
	Downspouts - Interior Downspouts	234	LF	6	\$7,777
	Parapet - 16" - 30" Height	536	LF	6	\$21,415
	Roof - Modified Bitumen	12,560	SF	6	\$118,182
	Roof Structure - Steel / Metal Deck/ Concrete Topping	12,560	SF	7	\$0
Walls					
	Exterior Walls - Brick	18,650	SF	6	\$125,347
Windows					
	Guard - Guards perforated	1,186	SF	6	\$15,145
	Lintels - Steel	652	LF	6	\$18,927
	Storefront Windows	296	SF	6	\$3,319
	Windows - Casement Aluminum Double-pane	3,474	SF	5	\$187,138
	Windows - Casement Aluminum Double-pane	386	SF	6	\$2,881
Building Exterior Subtotal:					\$536,006

Building: Linked Addition
Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
	Automatic Transfer Switch	1	EA	6	\$408
	Emergency A/C Power - Corridors and Stairs	6,422	SF	6	\$1,929
	Emergency A/C Power - Gym	1,834	SF	6	\$682

Building: Linked Addition

Category: Electrical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Emergency System					
	Emergency A/C Power - Lunchrooms	2,952	SF	6	\$1,098
	Emergency A/C Power - Students Toilets	920	SF	6	\$342
	Emergency Battery Packs - Corridors and Stairs	6	EA	6	\$1,215
	Exit Signs - Corridors and Stairs	17	EA	6	\$2,546
	Security System - CCTV	36,097	SF	6	\$10,840
	Security System - Intrusion Detection	36,097	SF	6	\$9,291
Main Service					
	Independent Electrical Service for emergency power	1	EA	6	\$2,921
	Main Electrical Service - 1600 A 120/208/3PH	1	EA	6	\$5,641
	Main Electrical Service - 2000 A 120/208/3PH	1	EA	6	\$8,232
	PA System	36,097	SF	6	\$11,872
Power Distribution					
	Lighting and Power Panels - 100 A	1	EA	6	\$299
	Lighting and Power Panels - Above 100 A	6	EA	6	\$2,982
	Main Distribution Panels - 400 - 600 amp	1	EA	6	\$528
	Main Distribution Panels - Greater than 600 amp	2	EA	6	\$1,460
Electrical System Subtotal:					\$62,285

Building: Linked Addition

Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Fire Alarm					
	Fire Alarm Panel	1	EA	6	\$6,406
	Fire Alarm Strobe Lights	36,097	SF	6	\$12,905
	Fire Alarm_System	36,097	SF	6	\$17,550
	Fire Pump Controller	1	EA	6	\$1,823
Pump Room Assembly					
	Fire Pump - 51-75hp	1	EA	6	\$1,558
	Jockey Pump	1	EA	6	\$758
Sprinkler System					
	Sprinkler Heads	36,097	SF	7	\$0
	Sprinkler Piping	36,097	SF	6	\$6,710
	Wet Sprinkler System	36,097	SF	6	\$9,291

Building: Linked Addition

Category: Safty System

Group	Item - Type	Quantity	Unit	Rank	Cost
Safty System Subtotal:					\$57,001

Building: Linked Addition

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Air Conditioning					
	Chemical Pot Feeder	1	EA	6	\$725
	Chiller-Air Cooled-Scroll Type-Roof Mounted - 101 - 150 tons	1	EA	5	\$41,796
	Pipes - Dual Temperature Pipe- Galvanized	1,000	LF	6	\$1,888
	Pressure Fill System	1	EA	6	\$1,405
Air Handling Systems					
	Air Handling Unit-Package Single Zone- Indoor- Hot Water and Chilled Water Coils - 12001-20000 cfm	3	EA	5	\$145,776
	Air Intake	3	EA	6	\$17,294
	Auxiliaries - 12001-20000 cfm	2	EA	6	\$0
	Indoor Return Fans- Centrifugal Inline - 10001 - 20000 CFM	2	EA	6	\$3,714
	Indoor Return Fans- Centrifugal Inline - 5000 - 10000 CFM	1	EA	6	\$1,857
	VAV Box	19	EA	6	\$5,304
	Zone Dampers	19	EA	6	\$15,828
Boiler Systems					
	Boiler Auxiliary- Non Condensing Hot Water - 1001 - 2000 MBH	2	EA	6	\$4,093
	Chemical Pot Feeder	1	EA	6	\$725
	Combustion Dampers	2	EA	6	\$818
	Glycol Feed System	1	EA	6	\$539
	Non Condensing- Flexible Tube- Atmospheric- Hot Water Boiler - 1001 - 2000 MBH	2	EA	5	\$93,399
	Piping - Dual Temperature Pipes- Galvanized	1,000	LF	6	\$1,888
	Water Fill System	1	EA	6	\$1,168
Heating Devices					
	Cabinet Heaters - With Hot Water Coil	8	EA	6	\$2,835
	Fin Tube - Hot Water	48	LF	6	\$453
	Unit Heater - Electric	3	EA	6	\$833
	Unit Heater - Hot Water	1	EA	6	\$279
Mechanical Plumbing					
	Chilled Water Pump - 10 - 20 HP	2	EA	6	\$2,485
	Hot Water Pump - Less than 10	2	EA	6	\$2,222

Building: Linked Addition

Category: Mechanical System

Group	Item - Type	Quantity	Unit	Rank	Cost
Temperature Control					
	DDC System	36,097	SF	6	\$20,647
	Thermostats - DDC	19	EA	6	\$0
Ventilation					
	Exhaust Fans- Indoor - Less than 500 CFM	2	EA	6	\$592
	Exhaust Fans- Roof Mounted - 1501 - 8000 CFM	2	EA	6	\$1,185
	Exhaust Fans- Roof Mounted - 500 - 1500 CFM	2	EA	6	\$1,185

Mechanical System Subtotal:

\$370,933

Building: Linked Addition

Category: Plumbing System

Group	Item - Type	Quantity	Unit	Rank	Cost
Hot Water					
	Gas Heater - Less than 150000 BTU/HR	2	EA	6	\$620
Piping					
	Domestic Piping-Cold Water from Risers to Fixtures	36,097	SF	6	\$7,227
	Domestic Piping-Cold Water Horizontal Lines	36,097	SF	6	\$8,775
	Domestic Piping-Cold Water Risers	36,097	SF	6	\$6,710
	Domestic Piping-Hot Water from Risers to Fixtures	36,097	SF	6	\$5,678
	Domestic Piping-Hot Water Horizontal Lines	36,097	SF	6	\$6,710
	Domestic Piping-Hot Water Return Lines	36,097	SF	6	\$5,162
	Domestic Piping-Hot Water Return Risers	36,097	SF	6	\$5,162
	Sanitary Piping	36,097	SF	6	\$33,036
	Storm Piping	36,097	SF	6	\$31,487
	Vent Piping	36,097	SF	6	\$24,261

Pumps

	Pumps - Domestic Booster Pump-Duplex	1	EA	6	\$1,977
	Pumps - Sump-Simplex	1	EA	6	\$745

Plumbing System Subtotal:

\$137,550

Building: Linked Addition

Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
-------	-------------	----------	------	------	------

Building: Linked Addition
Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Kindergarten (4 rooms)					
	Ceiling - Lay-in	2,144	SF	5	\$12,754
	Ceiling - Splined	1,072	SF	5	\$7,634
	Ceiling - Splined	1,072	SF	6	\$874
	Chalk Board	77	LF	4	\$7,069
	Doors - Side-lite	48	SF	6	\$802
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Floor - Tile	4,288	SF	6	\$9,382
	Lighting - Lay-in	1	EA	5	\$162
	Lighting - Lay-in	14	EA	6	\$1,666
	Lighting - Lay-in	45	EA	7	\$0
	Storage/ Closet	80	SF	6	\$580
	Walls - Concrete Block	5,720	SF	6	\$16,768
	Walls - Plaster/Drywall	400	SF	6	\$1,104
	Work Sink	6	EA	6	\$2,274
Pre School (2 rooms)					
	Ceiling - Splined	1,027	SF	5	\$7,314
	Ceiling - Splined	1,027	SF	6	\$837
	Chalk Board	20	LF	4	\$1,836
	Doors - Side-lite	36	SF	6	\$602
	Doors - Steel Doors incl hw	2	EA	6	\$602
	Doors - Wood Doors inclu hw	3	EA	6	\$903
	Floor - Tile	2,054	SF	6	\$4,494
	Lighting - Lay-in	27	EA	7	\$0
	Marker Board	20	LF	6	\$428
	Storage/ Closet	44	SF	6	\$319
	Walls - Concrete Block	1,670	SF	6	\$4,896
	Walls - Plaster/Drywall	900	SF	6	\$2,484
	Work Sink	4	EA	6	\$1,516
Regular Classroom (6 rooms)					
	Ceiling - Lay-in	3,144	SF	5	\$18,703
	Ceiling - Lay-in	2,973	SF	6	\$8,928
	Chalk Board	50	LF	4	\$4,590
	Doors - Side-lite	48	SF	6	\$802
	Doors - Transom Window	12	SF	6	\$203
	Doors - Wood Doors inclu hw	9	EA	6	\$2,709

Building: Linked Addition
Category: Classrooms

Group	Item - Type	Quantity	Unit	Rank	Cost
Regular Classroom (6 rooms)					
	Floor - Carpet	784	SF	6	\$1,670
	Floor - Tile	5,333	SF	6	\$11,668
	Lighting - Lay-in	16	EA	6	\$1,904
	Lighting - Lay-in	72	EA	7	\$0
	Marker Board	56	LF	6	\$1,200
	Storage/ Closet	172	SF	6	\$1,247
	Walls - Concrete Block	4,088	SF	6	\$11,984
	Walls - Plaster/Drywall	4,754	SF	6	\$13,121
	Walls - Tile	784	SF	6	\$1,715
	Work Sink	4	EA	6	\$1,516
Special Education (1 room)					
	Ceiling - Lay-in	476	SF	6	\$1,429
	Chalk Board	12	LF	4	\$1,102
	Doors - Side-lite	12	SF	6	\$201
	Doors - Wood Doors inclu hw	1	EA	6	\$301
	Floor - Tile	476	SF	6	\$1,041
	Lighting - Lay-in	8	EA	7	\$0
	Marker Board	12	LF	6	\$257
	Storage/ Closet	120	SF	6	\$870
	Walls - Structural Glazed Tile	852	SF	6	\$2,680
Classrooms Subtotal:					\$179,851

Building: Linked Addition
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Ceiling - Exposed	103	SF	6	\$153
	Ceiling - Lay-in	2,618	SF	6	\$7,862
	Doors - Side-lite	15	SF	6	\$251
	Doors - Wood Doors inclu hw	7	EA	6	\$2,107
	Floor - Carpet	2,218	SF	6	\$4,726
	Floor - Tile	615	SF	6	\$1,346
	Lighting - Lay-in	28	EA	7	\$0
	Lighting - Pendent/Surface	2	EA	7	\$0
	Power Distribution	50	EA	6	\$106,244

Building: Linked Addition
Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Administrative Suites/Offices					
	Walls - Concrete Block	209	SF	6	\$613
	Walls - Plaster/Drywall	1,326	SF	5	\$10,050
	Walls - Plaster/Drywall	1,594	SF	6	\$4,399
Gymnasia					
	Ceiling - Exposed	1,834	SF	6	\$2,728
	Doors - Steel Doors incl hw	4	EA	6	\$1,204
	Floor - Tile	1,834	SF	6	\$4,013
	Lighting - Pendent/Surface	28	EA	7	\$0
	Storage/ Closet	118	SF	6	\$856
	Walls - Concrete Block	2,109	SF	6	\$6,183
Kitchen					
	Ceiling - Plaster/Drywall	563	SF	6	\$1,948
	Doors - Steel Doors incl hw	1	EA	6	\$301
	Floor - Epoxy/ Painted	563	SF	6	\$298
	Lighting - Lay-in	9	EA	7	\$0
	Walls - Concrete Block	647	SF	6	\$1,897
Library					
	Ceiling - Lay-in	1,790	SF	6	\$5,375
	Doors - Side-lite	24	SF	6	\$401
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Carpet	1,780	SF	6	\$3,793
	Lighting - Lay-in	20	EA	7	\$0
	Walls - Concrete Block	2,047	SF	6	\$6,001
Lunch & Multipurpose Room					
	Ceiling - Lay-in	1,068	SF	6	\$3,207
	Doors - Side-lite	12	SF	6	\$201
	Doors - Wood Doors inclu hw	2	EA	6	\$602
	Floor - Tile	1,068	SF	6	\$2,337
	Lighting - Lay-in	16	EA	7	\$0
	Serving Line	12	LF	6	\$714
	Walls - Concrete Block	1,228	SF	6	\$3,600
Mechanical/ Service Rooms					
	Boiler Room	1,949	SF	6	\$13,963
	Janitor's Closet	75	SF	6	\$537
	Mechanical/ Service Rooms	377	SF	6	\$2,701

Building: Linked Addition

Category: Rooms (Other Than Classrooms)

Group	Item - Type	Quantity	Unit	Rank	Cost
Mechanical/ Service Rooms					
	Vaults	150	SF	6	\$1,075
Restroom					
	Accessories	1,233	SF	6	\$11,373
	Ceiling - Plaster/Drywall	1,233	SF	6	\$4,267
	Doors - Wood Doors inclu hw	8	EA	6	\$2,408
	Floor - Epoxy/ Painted	44	SF	6	\$23
	Floor - Tile Ceramic/ Porcelain	1,189	SF	6	\$2,516
	Floor Drain	5	EA	6	\$5,296
	Lavatory	14	EA	6	\$4,474
	Lighting - Lay-in	20	EA	7	\$0
	Partitions	18	EA	6	\$5,345
	Student Lockers - Two Tiers	6	EA	6	\$279
	Urinals	6	EA	6	\$2,016
	Walls - Concrete Block	52	SF	6	\$152
	Walls - Structural Glazed Tile	1,376	SF	6	\$4,329
	Water Closet	20	EA	6	\$6,720

Rooms (Other Than Classrooms) Subtotal:

\$251,482

Building: Linked Addition

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Corridor					
	Ceiling - Lay-in	5,139	SF	6	\$15,432
	Doors - Store Front	2	EA	6	\$2,416
	Doors - Wood Doors include hw	7	EA	6	\$2,107
	Drinking Fountains - Single Fountain	6	EA	6	\$1,654
	Floor - Tile/Sheet	5,139	SF	6	\$2,793
	Lighting - Lay-in	45	EA	7	\$0
	Walls - Masonry	5,910	SF	6	\$18,593
Safety					
	Camera Viewing Station	1	EA	6	\$683
	Security Cameras	1	EA	5	\$688
	Security Cameras	7	EA	6	\$1,358

Building: Linked Addition

Category: Building Interior

Group	Item - Type	Quantity	Unit	Rank	Cost
Stairs					
	Ceiling - Lay-in	3,123	SF	6	\$9,378
	Floor - Tile	1,041	SF	6	\$566
	Floor - Tile/Sheet	2,082	SF	6	\$1,131
	Handrails	630	LF	6	\$5,459
	Lighting - Lay-in	9	EA	7	\$0
	Lighting - Wall Mounted	9	EA	7	\$0
	Stairs - Rubber	270	LF	6	\$2,903
	Walls - Masonry	3,591	SF	6	\$11,297
Vertical Conveyance					
	Elevator - Elevator- Roped Holeless Hydraulic	1	EA	7	\$0

Building Interior Subtotal: \$76,460

Total Building Cost \$1,671,567

SITE

Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Civil/Drainage					
	Civil/ Drainage - Catch Basin	10	EA	6	\$10,938
	Civil/ Drainage - Site Drain	1	EA	6	\$310
	Civil/ Drainage - Site Manhole	18	EA	6	\$26,869
Fencing					
	Fencing - Chain Link	515	LF	6	\$9,670
	Fencing - Guard Rail	72	LF	6	\$832
	Fencing - Iron and Concrete Post	6	LF	5	\$731
	Fencing - Iron and Concrete Post	626	LF	6	\$22,961
	Fencing - New Standard Ornamental	1,015	LF	6	\$32,382
Landscape					
	Benches	4	EA	6	\$1,720
	Landscape - Grass	16,355	SF	6	\$13,565
	Landscape - Hardscape- Concrete	20,084	SF	6	\$103,680
	Landscape - Hardscape- Pavers	855	SF	6	\$4,842
	Parkway trees	49	EA	6	\$32,342
	Planting Beds/ Area	5,685	SF	6	\$9,349

SITE

Category: Site

Group	Item - Type	Quantity	Unit	Rank	Cost
Landscape					
	Play Area - Asphalt/ Hardscape	43,625	SF	6	\$105,429
	Retaining Wall - Concrete	355	SF	6	\$8,320
	Trash Receptacles	2	EA	6	\$625
Parking Lot					
	Concrete Curbs	731	LF	6	\$9,387
	Interior Plantings	120	LF	6	\$5,105
	Lighting - Pole Mounted	3	EA	6	\$4,357
	Surface - Asphalt	25,675	SF	6	\$62,049
	Trash Compactor	1	EA	6	\$0
	Trash Enclosure - Masonry	2,808	SF	6	\$110,786
Playground					
	Equipment - Combo 3-12	1	EA	6	\$7,092
	Surface - Wood Chips	3,328	SF	6	\$6,710
Sidewalks					
	Sidewalks - Internal Walks	45	LF	5	\$2,243
	Sidewalks - Internal Walks	195	LF	6	\$2,342
	Sidewalks - Perimeter Sidewalks	18,026	SF	6	\$35,830
Signage					
	Flag Pole - Flag Pole	1	EA	6	\$1,657
	Marquee - Free Standing Back Lighted	1	EA	6	\$0
Site Subtotal:					\$632,123
Total Site Cost					\$632,123
Campus Total ^{2 3}					\$8,590,179

¹ It is very rare for assessors to find a feature in this condition. If assessors do, they are required to report it immediately to CPS, and CPS addresses it immediately. Thus, no features will be ranked "1" in this report; by the time the report is compiled, they have been resolved.

² As stated above, Total Assessed Campus Need does not include the addition of features not already in a particular facility, such as programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration or construction to alleviate overcrowding; these items are treated as separate capital needs. The Total Assessed Campus Need includes current deficiencies and is based on current unit cost estimates; it does not reflect a complete project cost.

³ The overall condition of different items can change after an assessment date due to many variables, including newly occurring deficiencies, renovation or repairs and cost changes. These dollar figures in this report are estimates only and are based solely on the data that was collected as of the assessment date in the footer below.

Definitions

- **Quantity** means, for each item, the total number (or amount) of that item that exists and was evaluated.
 - **Unit** means the generally accepted standard unit of measure for each item. Some items, like doors, are measured individually and use the unit of measurement "EA" for "each." Other items, like chimneys, are measured in terms of linear feet ("LF"). Still other items, like flooring, are generally measured in square feet ("SF").
 - **Cost** means a basic estimate for each item needing some level of repair or replacement. Cost does not include all expenses that would be necessary to complete a repair or replacement project. This is because, depending on the item and on the overall scope of a construction project, repair/replacement projects can include additional costs such as destructive testing, environmental needs, discovered conditions, and additional work triggered by building codes.
 - **For the same reason, the Total Campus Need listed at the end of this report reflects only a portion of what it would actually cost to repair/replace all of the listed features.**
 - **Campus Total** also does not reflect features that do not yet exist at a particular facility, such as: programmatic improvements, school-wide ADA compliance, air conditioning, space reconfiguration, or construction to alleviate overcrowding; these are viewed as separate capital needs.
-

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Main														
Art Room	Regular Classroom	2nd Floor	207	205	810	1	2	10	96	48	40	N	Y	Y
Computer Lab	Regular Classroom	2nd Floor	206	206	880	3	24	56	112	52	40	N	Y	N
Kindergarten	Kindergarten	1st Floor	141	101	810	1	2	10	96	48	40	N	Y	N
Office	Regular Classroom	1st Floor	104	104	810			10	92	26	40	N	Y	N
Other Instructional Use	Lunch Room	Basement	005		685		1	44	60	30	40	N	Y	N
Play Room	Play Room	Basement	011		840	1		8	72	36	40	N	Y	N
Regular Classroom	Unknown	Basement	002		840	1	2	8	105	53	40	N	Y	N
Regular Classroom	Other	Basement	008		410	1	2	8	30	15	40	N	Y	N
Regular Classroom	Unknown	Basement	013		750	1		8	99	50	40	N	Y	N
Regular Classroom	Unknown	Basement	014		690	1		8	87	44	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	102	102	810			10	128	60	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	103	103	810	1	2	10	96	48	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	106	106	810	1		10	112	52	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	108	108	810	1		10	98	39	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	109	108	810	1		10	98	48	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	110	109	810	1		10	98	39	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	111	110	810	1		10	138	48	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	112	112	907	1	2	10	138	48	40	N	Y	N
Regular Classroom	Regular Classroom	1st Floor	113	111	810	1		10	144	64	40	N	Y	Y
Regular Classroom	Regular Classroom	1st Floor	114	113	810			10	138	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	201	201	810			10	90	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	202	202	900			10	114	47	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	203	203	810	1	2	10	96	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	204	204	832			10	84	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	209	208	810	1	2	10	98	48	40	N	Y	Y
Regular Classroom	Regular Classroom	2nd Floor	210	209	840	1		10	92	36	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	211	210	810	1		10	138	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	212	212	810	1	2	10	138	48	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	213	211	810	1	2	10	144	64	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	214	213	907			10	138	48	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	306	306	955	1		10	108	48	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	307	305	1,120	1		10	150	40	40	N	Y	Y
Regular Classroom	Regular Classroom	3rd Floor	308	307	955	1		10	108	48	40	N	Y	N
Store Room	Regular Classroom	Basement	012		820	1		8	87	44	40	N	Y	N

Linked Addition

Kindergarten	Kindergarten	1st Floor	119	119	1,072	1		10	214	12	40	N	Y	N
--------------	--------------	-----------	-----	-----	-------	---	--	----	-----	----	----	---	---	---

Classroom Summary

Current Usage	Intended Usage	Room Location	Room Number	Floor Plan Room Number	Area (SF)	Voice Outlets	Data Outlets	Elect. Outlets	Glazed Window Area	Operable Window Area	Noise Level	Window Stop	Power Strip	Smart-Board
Linked Addition														
Kindergarten	Kindergarten	1st Floor	122	122	1,072	1		10	214	12	40	N	Y	N
Kindergarten	Kindergarten	2nd Floor	215	217	1,072	1		14	32	16	40	N	Y	N
Kindergarten	Kindergarten	2nd Floor	217	216	1,072	1		14	32	16	40	N	Y	N
Pre School	Pre School	1st Floor	115/116	124	1,027	1		10	32	12	40	N	Y	N
Pre School	Pre School	1st Floor	117/ 118	122	1,027	1		10	214	12	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	219	215	1,072	1		14	32	16	40	N	Y	N
Regular Classroom	Regular Classroom	2nd Floor	221	212	1,117	1		14	32	16	40	N	N	N
Regular Classroom	Regular Classroom	3rd Floor	315	315	784	1	0	10	32	16	40	N	N	Y
Regular Classroom	Regular Classroom	3rd Floor	316	300	955	1		10	200	16	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	319	309	1,072	1		14	200	16	40	N	Y	N
Regular Classroom	Regular Classroom	3rd Floor	321	308	1,117	1		14	200	16	40	N	N	N
Special Education	Regular Classroom	3rd Floor	318	318	476	1		16	50	4	40	N	N	N